

ESSENTIAL MATHEMATICS

FOR THE AUSTRALIAN CURRICULUM

SECOND EDITION

DAVID GREENWOOD | SARA WOOLLEY
JENNY GOODMAN | JENNIFER VAUGHAN
STUART PALMER

CAMBRIDGE UNIVERSITY PRESS

Essential Mathematics for the Australian Curriculum Year 9 2ed

ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Cambridge University Press

CAMBRIDGE
UNIVERSITY PRESS

477 Williamstown Road, Port Melbourne, VIC 3207, Australia

Cambridge University Press is part of the University of Cambridge.

It furthers the University's mission by disseminating knowledge in the pursuit of education, learning and research at the highest international levels of excellence.

www.cambridge.edu.au
Information on this title: www.cambridge.org/9781107570078

David Greenwood, Sara Woolley, Jennifer Vaughan, Jenny Goodman 2015

This publication is in copyright. Subject to statutory exception and to the provisions of relevant collective licensing agreements, no reproduction of any part may take place without the written permission of Cambridge University Press.

First published 2011
Reprinted 2012, 2013, 2014, 2015
Second edition published 2015

Cover designed by Sardine Design
Typeset by Diacritech
Printed in China by C & C Offset Printing Co. Ltd.

A Cataloguing-in-Publication entry is available from the catalogue of the National Library of Australia at www.nla.gov.au

ISBN 978-1-107-57007-8 Paperback

Additional resources for this publication at www.cambridge.edu.au/GO

Reproduction and communication for educational purposes
The Australian *Copyright Act 1968* (the Act) allows a maximum of one chapter or 10% of the pages of this publication, whichever is the greater, to be reproduced and/or communicated by any educational institution for its educational purposes provided that the educational institution (or the body that administers it) has given a remuneration notice to Copyright Agency Limited (CAL) under the Act.

For details of the CAL licence for educational institutions contact:

Copyright Agency Limited
Level 15, 233 Castlereagh Street
Sydney NSW 2000
Telephone: (02) 9394 7600
Facsimile: (02) 9394 7601
Email: info@copyright.com.au

Reproduction and communication for other purposes
Except as permitted under the Act (for example a fair dealing for the purposes of study, research, criticism or review) no part of this publication may be reproduced, stored in a retrieval system, communicated or transmitted in any form or by any means without prior written permission. All inquiries should be made to the publisher at the address above.

Cambridge University Press has no responsibility for the persistence or accuracy of URLS for external or third-party internet websites referred to in this publication, and does not guarantee that any content on such websites is, or will remain, accurate or appropriate. Information regarding prices, travel timetables and other factual information given in this work is correct at the time of first printing but Cambridge University Press does not guarantee the accuracy of such information thereafter.

Disclaimer
All material identified by AC is material subject to copyright under the Copyright Act 1968 (Cth) and is owned by the Australia Curriculum, Assessment and Reporting Authority 2015.

Table of contents

About the authors *ix*
Introduction and how to use this series *x*
Working with unfamiliar problems *xiv*

1 Reviewing number and financial mathematics **2**

Number and Algebra

Money and financial mathematics

1A Integer operations CONSOLIDATING 4
1B Decimals and significant figures 9
1C Rational numbers CONSOLIDATING 14
1D Operations with fractions CONSOLIDATING 20
1E Ratios, rates and best buys CONSOLIDATING 26
1F Percentages and money CONSOLIDATING 33
1G Percentage increase and decrease CONSOLIDATING 38
1H Profits and discounts 43
Progress quiz 48
1I Income and taxation 50
1J Simple interest 58
1K Compound interest EXTENDING 63
Investigation 68
Problems and challenges 70
Chapter summary 71
Review: Multiple-choice questions 72
Short-answer questions 73
Extended-response questions 75

Using a CAS calculator 1J: Number and interest problems (website)

2 Linear and simultaneous equations **76**

Number and Algebra

Patterns and algebra

2A Algebraic expressions CONSOLIDATING 78
2B Simplifying algebraic expressions CONSOLIDATING 84
2C Expanding algebraic expressions 89

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2D	Solving linear equations	94
2E	Equations with brackets and pronumerals on both sides	99
2F	Solving word problems	103
	Progress quiz	108
2G	Inequalities	109
2H	Using formulas	114
2I	Simultaneous equations: substitution EXTENDING	120
2J	Simultaneous equations: elimination EXTENDING	124
2K	Applications of simultaneous equations EXTENDING	130
	Investigation	134
	Problems and challenges	136
	Chapter summary	137
	Review: Multiple-choice questions	138
	Short-answer questions	139
	Extended-response questions	141

Using a CAS calculator 2E: Solving equations (website)

Using a CAS calculator 2I: Solving simultaneous equations (website)

3 Pythagoras' theorem and trigonometry 142

Measurement and Geometry

Pythagoras and trigonometry

3A	Pythagoras' theorem	144
3B	Finding the shorter sides	151
3C	Applying Pythagoras' theorem	156
3D	Pythagoras in three dimensions EXTENDING	161
3E	Trigonometric ratios	166
3F	Finding side lengths	173
3G	Solving for the denominator	179
	Progress quiz	183
3H	Finding an angle	185
3I	Applying trigonometry EXTENDING	190
3J	Bearings EXTENDING	197
	Investigation	204
	Problems and challenges	206
	Chapter summary	207
	Review: Multiple-choice questions	208
	Short-answer questions	209
	Extended-response questions	211

Using a CAS calculator 3G: Trigonometry (website)

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 Linear relations 212

Number and Algebra

Real numbers

Linear and non-linear relationships

4A	Introduction to linear relations CONSOLIDATING	214
4B	Graphing straight lines using intercepts	221
4C	Lines with one intercept	226
4D	Gradient	233
4E	Gradient and direct proportion	241
4F	Gradient–intercept form	246
4G	Finding the equation of a line	252
	Progress quiz	258
4H	Midpoint and length of a line segment	260
4I	Perpendicular and parallel lines EXTENDING	264
4J	Linear modelling	268
4K	Graphical solutions to simultaneous equations	273
	Investigation	279
	Problems and challenges	281
	Chapter summary	282
	Review: Multiple-choice questions	283
	Short-answer questions	285
	Extended-response questions	287

Using a CAS calculator 4B: Sketching straight lines (website)

Using a CAS calculator 4K: Finding intersection points (website)

5 Measurement 288

Measurement and Geometry

Using units of measurements

5A	Length and perimeter CONSOLIDATING	290
5B	Circumference and perimeter of a sector	296
5C	Area	302
5D	Composite shapes	310
5E	Surface area of prisms and pyramids	316
5F	Surface area of a cylinder	321
	Progress quiz	326
5G	Volume of prisms	328
5H	Volume of a cylinder	335
	Investigation	340
	Problems and challenges	342
	Chapter summary	343
	Review: Multiple-choice questions	344
	Short-answer questions	345
	Extended-response questions	347

Using a CAS calculator 5C: Measurement formulas (website)

Semester review 1 348

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 Indices and surds 356

Number and Algebra

Real numbers

Patterns and algebra

Measurement and Geometry

Using units of measurements

6A	Index notation CONSOLIDATING	358
6B	Index laws 1 and 2	364
6C	Index law 3 and the zero power	370
6D	Index laws 4 and 5	376
6E	Negative indices	381
	Progress quiz	386
6F	Scientific notation	387
6G	Scientific notation using significant figures	394
6H	Fractional indices and surds EXTENDING	399
6I	Simple operations with surds EXTENDING	404
	Investigation	408
	Problems and challenges	410
	Chapter summary	411
	Review: Multiple-choice questions	412
	Short-answer questions	413
	Extended-response questions	414

7 Geometry 416

Measurement and Geometry

Geometric reasoning

7A	Angles and triangles CONSOLIDATING	418
7B	Parallel lines CONSOLIDATING	427
7C	Quadrilaterals and other polygons	435
7D	Congruent triangles	442
7E	Using congruence in proof EXTENDING	449
	Progress quiz	454
7F	Enlargement and similar figures	456
7G	Similar triangles	464
7H	Proving and applying similar triangles	472
	Investigation	477
	Problems and challenges	479
	Chapter summary	480
	Review: Multiple-choice questions	481
	Short-answer questions	482
	Extended-response questions	485

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 Algebraic techniques 486

Number and Algebra

Patterns and algebra

8A	Expanding binomial products	488
8B	Perfect squares and difference of perfect squares	492
8C	Factorising algebraic expressions	498
8D	Factorising the difference of two squares	503
8E	Factorisation by grouping	507
8F	Factorising quadratic trinomials EXTENDING	510
8G	Factorising trinomials of the form $ax^2 + bx + c$ EXTENDING	514
	Progress quiz	518
8H	Simplifying algebraic fractions: multiplication and division	519
8I	Simplifying algebraic fractions: addition and subtraction	524
8J	Further simplification of algebraic fractions EXTENDING	528
8K	Equations with algebraic fractions EXTENDING	532
	Investigation	537
	Problems and challenges	539
	Chapter summary	540
	Review: Multiple-choice questions	541
	Short-answer questions	542
	Extended-response questions	543

Using a CAS calculator 8E: Expanding and factorising (website)

9 Probability and statistics 544

Statistics and Probability

Chance

Data representation and interpretation

9A	Probability review CONSOLIDATING	546
9B	Venn diagrams and two-way tables	552
9C	Using set notation	559
9D	Using arrays for two-step experiments	564
9E	Tree diagrams	570
9F	Experimental probability	576

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9G	Summarising data: measures of centre	581
	Progress quiz	586
9H	Stem-and-leaf plots	588
9I	Grouped data	595
9J	Measures of spread	602
9K	Box plots EXTENDING	608
	Investigation	615
	Problems and challenges	617
	Chapter summary	618
	Review: Multiple-choice questions	619
	Short-answer questions	620
	Extended-response questions	622

Using a CAS calculator 9G: Finding measures of centre (website)

Using a CAS calculator 9I: Graphing grouped data (website)

Using a CAS calculator 9K: Finding measures of spread and drawing box plots (website)

10 Introduction to quadratic equations and graphs 624

Number and Algebra

Linear and non-linear relationship

10A	Quadratic equations EXTENDING	626
10B	Solving $ax^2 + bx = 0$ and $x^2 = d$ EXTENDING	632
10C	Solving $x^2 + bx + c = 0$ EXTENDING	636
10D	Applications of quadratic equations EXTENDING	640
	Progress quiz	644
10E	The parabola	645
10F	Sketching $y = ax^2$ with dilations and reflections	654
10G	Sketching $y = x^2$ with translations	662
10H	Sketching parabolas using intercept form EXTENDING	671
	Investigation	678
	Problems and challenges	680
	Chapter summary	681
	Review: Multiple-choice questions	682
	Short-answer questions	683
	Extended-response questions	685

Using a CAS calculator 10B: Solving quadratic equations (website)

Using a CAS calculator 10E: Sketching parabolas (website)

Semester review 2 686

Answers 694

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

About the authors

David Greenwood is the Head of Mathematics at Trinity Grammar School in Melbourne and has 21 years' experience teaching mathematics from Years 7 to 12. He has run numerous workshops within Australia and overseas regarding the implementation of the Australian Curriculum and the use of technology for the teaching of mathematics. He has written more than 20 mathematics titles and has a particular interest in the sequencing of curriculum content and working with the Australian Curriculum proficiency strands.

Sara Woolley was born and educated in Tasmania. She completed an Honours degree in Mathematics at the University of Tasmania before completing her education training at the University of Melbourne. She has taught mathematics in Victoria from Years 7 to 12 since 2006, has written more than 10 mathematics titles and specialises in lesson design and differentiation.

Jennifer Vaughan has taught secondary mathematics for over 30 years in New South Wales, Western Australia, Queensland and New Zealand and has tutored and lectured in mathematics at Queensland University of Technology. She is passionate about providing students of all ability levels with opportunities to understand and to have success in using mathematics. She has taught special needs students and has had extensive experience in developing resources that make mathematical concepts more accessible; hence, facilitating student confidence, achievement and an enjoyment of maths.

Jenny Goodman has worked for 20 years in comprehensive state and selective high schools in New South Wales and has a keen interest in teaching students of differing ability levels. She was awarded the Jones Medal for education at Sydney University and the Bourke prize for Mathematics. She has written for Cambridge NSW and was involved in the Spectrum and Spectrum Gold series.

Stuart Palmer has been a head of department in two schools and is now an educational consultant who conducts professional development workshops for teachers all over New South Wales and beyond. He is a Project Officer with the Mathematical Association of New South Wales, and also works with pre-service teachers at The University of Sydney and The University of Western Sydney.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Introduction

This second edition of *Essential Mathematics for the Australian Curriculum* has been developed into a complete resources pack comprising a revised and updated print textbook, a new interactive textbook with a host of cutting-edge features, and an online teaching suite.

The successful elements of the first edition have been retained and improved upon. These include:

- logical sequencing of chapters and development of topics
- careful structuring of exercises according to the four Australian Curriculum proficiency strands plus enrichment
- graduated difficulty of exercise questions within the overall exercise and within proficiency groups
- *Let's Start* and *Key Ideas* to help introduce concepts and key skills.

Additions and revisions to the text include:

- New topics reflecting updates to the Australian Curriculum and state syllabuses
- Revision and extension topics are marked as 'Consolidating' or 'Extending' to help customise the course to each classroom's needs
- The working programs have been subtly embedded in each exercise to differentiate three student pathways: Foundation, Standard and Advanced
- A 'Progress quiz' has been added about two-thirds of the way into each chapter, allowing students to check and consolidate their learning – in time to address misunderstandings or weaknesses prior to completing the chapter
- Pre-tests have been revised and moved to the interactive textbook.

Features of the all-new interactive textbook:

- Seamlessly blended with Cambridge HOTmaths, allowing enhanced learning opportunities in blended classrooms, revision of previous years' work, and access to *Scorcher*
- Every worked example in the book is linked to a high-quality video demonstration, supporting both in-class learning and the 'flipped classroom'
- A searchable dictionary of mathematical terms and pop-up definitions in the text
- Hundreds of interactive widgets, walkthroughs and games
- Automatically-marked quizzes and assessment tests, with saved scores
- Printable worksheets (HOTsheets) suitable for homework or class group work.

Features of the Online Teaching Suite, also powered by Cambridge HOTmaths:

- A test generator, with ready-made tests
- Printable worked solutions for all questions
- A powerful learning management system with task-setting, progress-tracking and reporting functions.

The chart on the next pages shows how the components of this resource are integrated.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Guide to the working programs in the exercises

The working programs that were previously available in separate supporting documents have been updated, refined and embedded in the exercises for this second edition of *Essential Mathematics for the Australian Curriculum*. The suggested working programs provide three pathways through the course to allow differentiation for Foundation, Standard and Advanced students.

As with the first edition, each exercise is structured in subsections that match the four Australian Curriculum proficiency strands (Understanding, Fluency, Problem-solving and Reasoning) as well as Enrichment (Challenge). The questions suggested for each pathway are listed in three columns at the top of each subsection:

- The left column (lightest shaded colour) is the Foundation pathway
- The middle column (medium shaded colour) is the Standard pathway
- The right column (darkest shaded colour) is the Advanced pathway.



The working program for Exercise 3A in Year 7 (see pages 106-108)

Gradients within exercises and proficiency strands

The working programs make use of the gradients that have been seamlessly integrated into the exercises. A gradient runs through the overall structure of each exercise – where there is an increasing level of mathematical sophistication required from Understanding through to Reasoning and Enrichment – but also within each proficiency strand; the first few questions in Fluency, for example, are easier than the last few, and the last Problem-solving question is more challenging than the first Problem-solving question.

The right mix of questions

Questions in the working programs are selected to give the most appropriate mix of *types* of questions for each learning pathway. Students going through the Foundation pathway will likely need more practice at Understanding and Fluency, but should also attempt the easier Problem-solving and Reasoning questions. An Advanced student will likely be able to skip the Understanding questions, proceed through the Fluency questions (often half of each question), focus on the Problem-solving and Reasoning questions, and attempt the Enrichment question. A Standard student would do a mix of everything.

Choosing a pathway

There are a variety of ways of determining the appropriate pathway for students through the course. Schools and individual teachers should follow the method that works for them.
If required, the chapter pre-tests (now found online) can also be used as a diagnostic tool. The following are recommended guidelines:

- A student who gets 40% or lower in the pre-test should complete the Foundation questions
- A student who gets between 40% and 85% in the pre-test should complete the Standard questions
- A student who gets 85% or higher in the pre-test should complete the Advanced questions.

For schools that have classes grouped according to ability, teachers may wish to set one of the Foundation, Standard or Advanced pathways as their default setting for their entire class and then make individual alterations depending on student need. For schools that have mixed-ability classes, teachers may wish to set a number of pathways within the one class, depending on previous performance and other factors.

* The nomenclature used to list questions is as follows:

- 3, 4: complete all parts of questions 3 and 4
- 1-4: complete all parts of questions 1, 2, 3 and 4
- 10(½): complete half of the parts from question 10 (a, c, e, ... or b, d, f, ...)
- 2-4(½): complete half of the parts of questions 2, 3 and 4
- 4(½), 5: complete half of the parts of question 4 and all parts of question 5
- — : do not complete any of the questions in this section.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

An overview of the *Essential Mathematics for the Australian Curriculum* complete learning suite

For more detail, see the guide in the online Interactive Textbook

All non-core topics are marked Consolidating or Extending to assist with course planning

Examples with fully worked solutions and explanations show the thinking behind each step



PRINT TEXTBOOK

- Investigations
- Problems and challenges
- Chapter summaries
- Chapter reviews
- Answers
- 'Working with unfamiliar problems' poster

Each topic in the print book comes with interactive *HOTmaths* widgets, walkthroughs and HOTsheets in the interactive textbook

Key ideas summarise key knowledge and skills for each lesson

Let's start activities get students thinking critically and creatively about the topic

Working programs subtly embedded in each Proficiency Strand to provide three learning pathways through the book



Downloadable

Included with print textbook and interactive textbook

Note-taking

Search functions

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Easy navigation within sections without scrolling

Walkthroughs, Scorcher and levelled question sets in every section

Interactive navigation and searching

Tasks sent by teacher

Access to interactive resources at any time without leaving the page

Hundreds of interactive widgets



INTERACTIVE TEXTBOOK POWERED BY *HOTmaths*

Online tests sent by teacher

Video demonstration for every worked example

Student reporting

Class reporting

Access to all *HOTmaths* Australian Curriculum courses



ONLINE TEACHING SUITE POWERED BY *HOTmaths*

Teacher's copy of interactive textbook

Test generator and ready-made tests

Student results

Printable chapter tests and worksheets

Plus:
- worked solutions
- teaching program
- curriculum grids

and more

Essential Mathematics for the Australian Curriculum Year 9 2ed

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Working with unfamiliar problems: Part 1

The questions on the next four pages are designed to provide practice in solving unfamiliar problems. Use the 'Working with unfamiliar problems' poster at the back of this book to help you if you get stuck.

In Part 1, apply the suggested strategy to solve these problems, which are in no particular order. Clearly communicate your solution and final answer.

1 Determine the exact answer for the following calculations:
a $999\,999\,999^2$ **b** $10^{2x} - 10^x + 1$ when $x = 10$



2 In a school of 999 students all the lockers are closed but unlocked. The first student opens all the lockers, then each next student changes the 'state' (i.e. open to shut or shut to open) of some lockers: student 2 changes every second locker; student 3 changes every third locker, etc. Imagine that this continues until all the 999 students have had a turn with the 999 lockers. At the end, how many lockers are open and which locker numbers are they?

3 What is the smallest number that, when divided by 11, has a remainder of 6 and when divided by 6 has a remainder of 1?



4 When 9 is added to certain two digit numbers the digits are reversed; that is, $AB + 9 = BA$. Find all the two digit numbers for which this is true.

5 A new east–west highway is 12 km north of Adina and 39 km north of Birubi. Town residents want the shortest possible road that will connect both towns to the same highway entry point. The east–west distance between the towns is 68 km. Determine the total length of the new road and the length and true bearing from each town along the new road to the highway. Round bearings to two decimal places.



6 A rectangle has coordinates $(0, 0)$, $(0, 4)$, $(6, 4)$ and $(6, 0)$. If a point (x, y) is randomly chosen in this rectangle, determine the probability that $y \geq x$.

7 Future travel to Mars could be with rockets powered by nuclear fusion. Estimate how many days a one way Earth–Mars trip would take if a fusion powered rocket travels at 321 800 km/h and the journey distance is 563 800 000 km.



8 Estimate the average time that a year 9 student takes to walk between classes at your school.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 A plane flight between two cities takes t hours. If the plane increases its speed by 25% by what percentage will the flight time decrease?

10 Find the value of x in this diagram. The diagram is not necessarily to scale.



11 Three numbers have a median of 14 and a mean that is 9 more than the smallest number and 11 less than the largest number. Find the sum of the three numbers.

12 An even integer is tripled and added to double the next consecutive even integer. If the result is 364, determine the value of the first even integer.

13 A school has two rooms that are square. The larger room has sides 5 m longer than the sides of the smaller room. If the total floor area of these rooms is 157 m^2, find the side length of each room.

14 **a** A diagonal line is ruled on a rectangular sheet of paper. In your own words, describe the 3-dimensional object that this line forms when the sheet of paper is rolled up to make a cylinder.

b Calculate the length of handrail required for a spiral staircase with steps of length 80 cm attached to a central pole of radius 10 cm and height 2.5 m. Round to two decimal places.



c An amusement park has a spiral track for a section of the roller coaster ride. The track has 2 revolutions and is designed around a virtual cylinder with diameter 12 m and height 8 m. Find the length of this spiral track correct to two decimal places.

15 If 27 dots are used to form a cube, with 9 dots on each of its faces and one dot in the middle of the cube, how many lines containing exactly three dots can be drawn?

16 Given that $a^{2q} = 5$, find the value of $2a^{6q} + 4$.

17 What is the value of $\dfrac{x - \dfrac{1}{y}}{y - \dfrac{1}{x}}$?



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Working with unfamiliar problems: Part 2

For the questions in Part 2, again use the 'Working with unfamiliar problems' poster at the back of this book, but this time choose your own strategy (or strategies) to solve each problem. Clearly communicate your solution and final answer.

1 The number $\frac{79}{21}$ can be written in the form $3 + \cfrac{1}{x + \cfrac{1}{y + \frac{1}{5}}}$. Find the values of x and y.

2 How many solids can you name that have eight vertices?

3 Increasing a number by 25% then decreasing the result by $x\%$ gives the original number again. What is the value of x in this case?

4 Prove that the sum of two odd numbers is an even number.

5 $x + y + xy = 34$ and x and y are both positive integers. What is the value of xy?

6 Find the value of the angle marked x in this diagram.



7 If n is a perfect square then write an expression, in terms of n, for the next largest perfect square.

8 A square of side length 8 cm has the midpoints of its sides joined to form a smaller square inside it. The midpoints of that square are joined to form an even smaller square. This method is repeated to create more squares.



a Find the area of the first five squares. Write these area values as a sequence of powers of a prime number.

b Continue your sequence from part b to find the areas of the 7^{th} square and the 10^{th} square.

c Write a rule for the area of the n^{th} square. Use this rule to find the area of the 15^{th} square.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 If the exterior angles of a triangle are in the ratio 4 : 5 : 6, then what is the ratio of the interior angles of the same triangle?

10 An operation exists where A # B = $A^B + B^A$. If A # 6 = 100 then A has what value?

11 Six years ago Sam was five times Noah's age. In ten years' time Sam will be two more than twice Noah's age. How old are they now?

12 Find the area of this triangle.



13 Simplify these expressions.

a $3^{x-2} + 3^{x-2} + 3^{x-2}$

b $(-1)^1 + (-1)^2 + (-1)^3 + \ldots + (-1)^{345} + (-1)^{346}$

14 **a** What is the volume of the rectangular prism shown?



b Find the exact area of the shaded triangle, given each grid square is 1 unit^2.



15 When a certain number is added to 18 and the same number is subtracted from 21 the product is 350. Find two possible values of this number.

16 On a training ride Holly cycled at an average speed of 20 km/h, stopped for a 15 minute break and then completed her trip at an average speed of 24 km/h. If the total distance was 68 km and the total time 3.5 hours (including the stop), determine the time taken for each stage of the ride.

17 A triangle has vertices $A(-7, -3)$, $B(8, 7)$ and $C(6, -3)$. *A* point *D* is on line *AB* so that *CD* is perpendicular to *AB*. Determine the exact ratio of the area of triangle *ABC* to the area of triangle *DBC*.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 1

Reviewing number and financial mathematics

What you will learn

1A Integer operations (Consolidating)
1B Decimals and significant figures
1C Rational numbers (Consolidating)
1D Operations with fractions (Consolidating)
1E Ratios, rates and best buys (Consolidating)
1F Percentages and money (Consolidating)
1G Percentage increase and decrease (Consolidating)
1H Profits and discounts
1I Income and taxation
1J Simple interest
1K Compound interest (Extending)

Australian curriculum

NUMBER AND ALGEBRA

Money and financial mathematics

Solve problems involving simple interest AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Global financial crisis

The global financial crisis of 2008 and 2009 was one of the most serious financial situations since the Great Depression in the 1930s. Prior to the crisis, US interest rates were lowered to about 1%, which created access to easy credit and 'sub-prime' lending. House prices in the US rose about 125% in the 10 years prior to the crisis. When the housing bubble burst, house prices began to fall and lenders began foreclosing on mortgages if borrowers could not keep up with their repayments. At the beginning of the crisis, US household debt as a percentage of personal income was about 130%. As house prices collapsed, financial institutions struggled to survive due to the increased number of bad debts. The crisis expanded to cause negative growth in the US general economy and in other countries. In Australia, our sharemarket All Ordinaries Index collapsed by 55% from 6874 in November 2007 to 3112 in March 2009.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

1A Integer operations CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Throughout history, mathematicians have developed number systems to investigate and explain the world in which they live. The Egyptians used hieroglyphics to record whole numbers as well as fractions, the Babylonians use a place-value system based on the number 60 and the ancient Chinese and Indians developed systems using negative numbers. Our current base 10 decimal system (the Hindu–Arabic system) has expanded to include positive and negative numbers, fractions (rational numbers) and also numbers that cannot be written as a fraction (irrational numbers), for example, π and $\sqrt{2}$. All the numbers in our number system, not including imaginary numbers, are called real numbers.

Markets used number systems in ancient times to enable trade through setting prices, counting stock and measuring produce.

Let's start: Special sets of numbers

Here are some special groups of numbers. Can you describe what special property each group has? Try to use the correct vocabulary, for example, factors of 12.

- 7, 14, 21, 28, . . .
- 1, 4, 9, 16, 25, . . .
- 1, 2, 3, 4, 6, 9, 12, 18, 36.
- 1, 8, 27, 64, 125, . . .
- 0, 1, 1, 2, 3, 5, 8, 13, . . .
- 2, 3, 5, 7, 11, 13, 17, 19, . . .

Key ideas

- The **integers** include . . . , –3, –2, –1, 0, 1, 2, 3, . . .
- For numbers a and b:
  - $a + (-b) = a - b$ For example: $5 + (-2) = 5 - 2 = 3$
  - $a - (-b) = a + b$ For example: $5 - (-2) = 5 + 2 = 7$
  - $a \times (-b) = -ab$ For example: $3 \times (-2) = -6$
  - $-a \times (-b) = ab$ For example: $-4 \times (-3) = 12$
  - $a \div (-b) = -\frac{a}{b}$ For example: $8 \div (-4) = -2$
  - $-a \div (-b) = \frac{a}{b}$ For example: $-8 \div (-4) = 2$
- **Squares and cubes**
  - $a^2 = a \times a$ and $\sqrt{a^2} = a$ (if $a \geq 0$). For example: $6^2 = 36$ and $\sqrt{36} = 6$
  - $a^3 = a \times a \times a$ and $\sqrt[3]{a^3} = a$. For example: $4^3 = 64$ and $\sqrt[3]{64} = 4$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **LCM, HCF and primes**
  - The **Lowest Common Multiple** (LCM) of two numbers is the smallest multiple shared by both numbers. For example: the LCM of 6 and 9 is 18.
  - The **Highest Common Factor** (HCF) of two numbers is the largest factor shared by both numbers. For example: the HCF of 24 and 30 is 6.
  - **Prime numbers** have only two factors, 1 and the number itself. The number 1 is not a prime number.
  - **Composite numbers** have more than two factors.
- **Order of operations**
  - Deal with brackets first.
  - Do multiplication and division next from left to right.
  - Do addition and subtraction last from left to right.

Example 1 Operating with integers

Evaluate the following.

a $-2-(-3\times 13)+(-10)$ **b** $(-20\div(-4)+(-3))\times 2$ **c** $\sqrt[3]{8}-(-1)^2+3^3$

SOLUTION	EXPLANATION
a $-2-(-3\times 13)+(-10)=-2-(-39)+(-10)$	Deal with the operations in brackets first.
$=-2+39+(-10)$	$-a-(-b)=-a+b$
$=37-10$	$a+(-b)=a-b$
$=27$	
b $(-20\div(-4)+(-3))\times 2=(5+(-3))\times 2$	$-a\div(-b)=\frac{a}{b}$
$=2\times 2$	Deal with the operations inside brackets before doing the multiplication. $5+(-3)=5-3$.
$=4$	
c $\sqrt[3]{8}-(-1)^2+3^3=2-1+27$	Evaluate powers first.
$=28$	$\sqrt[3]{8}=2$ since $2^3=8$
	$(-1)^2=-1\times(-1)=1$
	$3^3=3\times 3\times 3=27$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 1A

1, 2, 3(½) | 3(½) | —

UNDERSTANDING

1 Write down these sets of numbers.

- **a** The factors of 16
- **b** The factors of 56
- **c** The HCF (Highest Common Factor) of 16 and 56
- **d** The first 7 multiples of 3
- **e** The first 6 multiples of 5
- **f** The LCM (Lowest Common Multiple) of 3 and 5
- **g** The first 10 prime numbers starting from 2
- **h** All the prime numbers between 80 and 110

2 Evaluate the following.

a 11^2	**b** 15^2	**c** $\sqrt{144}$	**d** $\sqrt{400}$
e 3^3	**f** 5^3	**g** $\sqrt[3]{8}$	**h** $\sqrt[3]{64}$

3 Evaluate the following.

a $5 - 10$	**b** $-6 - 2$	**c** $-3 + 2$	**d** $-9 + 18$
e $2 + (-3)$	**f** $-6 + (-10)$	**g** $11 - (-4)$	**h** $-21 - (-30)$
i $2 \times (-3)$	**j** -21×4	**k** $-11 \times (-2)$	**l** $-3 \times (-14)$
m $18 \div (-2)$	**n** $-36 \div 6$	**o** $-100 \div (-10)$	**p** $-950 \div (-50)$

4(½), 5–7 | 4(½), 5, 6, 7–8(½) | 4–8(½)

FLUENCY

Example 1a

Example 1b

4 Evaluate the following showing your steps.

a $-4 - 3 \times (-2)$	**b** $-3 \times (-2) + (-4)$
c $-2 \times (3 - 8)$	**d** $2 - 7 \times (-2)$
e $2 - 3 \times 2 + (-5)$	**f** $4 + 8 \div (-2) - 3$
g $(-24 \div (-8) + (-5)) \times 2$	**h** $-7 - (-4 \times 8) - 15$
i $-3 - 12 \div (-6) \times (-4)$	**j** $4 \times (-3) \div (-2 \times 3)$
k $(-6 - 9 \times (-2)) \div (-4)$	**l** $10 \times (-2) \div (-7 - (-2))$
m $6 \times (-5) - 14 \div (-2)$	**n** $(-3 + 7) - 2 \times (-3)$
o $-2 + (-4) \div (-3 + 1)$	**p** $-18 \div ((-2 - (-4)) \times (-3))$
q $-2 \times 6 \div (-4) \times (-3)$	**r** $(7 - 14 \div (-2)) \div 2$
s $2 - (1 - 2 \times (-1))$	**t** $20 \div (6 \times (-4 \times 2) \div (-12) - (-1))$

5 Find the LCM of these pairs of numbers.

a 4, 7	**b** 8, 12	**c** 11, 17	**d** 15, 10

6 Find the HCF of these pairs of numbers.

a 20, 8	**b** 100, 65	**c** 37, 17	**d** 23, 46

Example 1c

7 Evaluate the following.

a $2^3 - \sqrt{16}$	**b** $5^2 - \sqrt[3]{8}$	**c** $(-1)^2 \times (-3)$
d $(-2)^3 \div (-4)$	**e** $\sqrt{9} - \sqrt[3]{125}$	**f** $1^3 + 2^3 - 3^3$
g $\sqrt[3]{27} - \sqrt{81}$	**h** $\sqrt[3]{27} - \sqrt{9} - \sqrt[3]{1}$	**i** $(-1)^{101} \times (-1)^{1000} \times \sqrt[3]{-1}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1A

FLUENCY

8 Evaluate these expressions by substituting $a = -2$, $b = 6$ and $c = -3$.

a $a^2 - b$ **b** $a - b^2$ **c** $2c + a$ **d** $b^2 - c^2$

e $a^3 + c^2$ **f** $3b + ac$ **g** $c - 2ab$ **h** $abc - (ac)^2$

9, 10 | 9–11 | 11–13

PROBLEM-SOLVING

9 Insert brackets into these statements to make them true.

a $-2 \times 11 + (-2) = -18$ **b** $-6 + (-4) \div 2 = -5$ **c** $2 - 5 \times (-2) = 6$

d $-10 \div 3 + (-5) = 5$ **e** $3 - (-2) + 4 \times 3 = -3$ **f** $(-2)^2 + 4 \div (-2) = -2^2$

10 How many different answers are possible if any number of pairs of brackets is allowed to be inserted into this expression?

$-6 \times 4 - (-7) + (-1)$

11 Margaret and Mildred meet on a Eurostar train travelling from London to Paris. Margaret visits her daughter in Paris every 28 days. Mildred visits her son in Paris every 36 days. When will Margaret and Mildred have a chance to meet again on the train?

12 **a** The sum of two numbers is 5 and their difference is 9. What are the two numbers?

b The sum of two numbers is –3 and their product is –10. What are the two numbers?

13 Two opposing football teams have squad sizes of 24 and 32. For a training exercise, each squad is to divide into smaller groups of equal size. What is the largest number of players in a group if the group size for both squads is the same?

14 | 14, 15 | 14, 15

REASONING

14 **a** Evaluate:

i 4^2 **ii** $(-4)^2$

b If $a^2 = 16$, write down the possible values of a.

c If $a^3 = 27$, write down the value of a.

d Explain why there are two values of a for which $a^2 = 16$ but only one value of a for which $a^3 = 27$.

e Find $\sqrt[3]{-27}$.

f Explain why $\sqrt{-16}$ cannot exist (using real numbers).

g -2^2 is the same as -1×2^2. Now evaluate:

i -2^2 **ii** -5^3 **iii** $-(-3)^2$ **iv** $-(-4)^2$

h Decide if $(-2)^2$ and -2^2 are equal.

i Decide if $(-2)^3$ and -2^3 are equal.

j Explain why the HCF of two distinct prime numbers is 1.

k Explain why the LCM of two distinct prime numbers a and b is $a \times b$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1A

REASONING

15 If a and b are both positive numbers and $a > b$, decide if the following are true or false.

a $a - b < 0$ **b** $-a \times b > 0$ **c** $-a \div (-b) > 0$

d $(-a)^2 - a^2 = 0$ **e** $-b + a < 0$ **f** $2a - 2b > 0$

Special numbers — — 16

ENRICHMENT

16 a Perfect numbers are positive integers which are equal to the sum of all their factors, excluding the number itself.

i Show that 6 is a perfect number.

ii There is one perfect number between 20 and 30. Find the number.

iii The next perfect number is 496. Show that 496 is a perfect number.

b Triangular numbers are the number of dots required to form triangles as shown in this table.

i Complete this table.

Number of rows	1	2	3	4	5	6
Diagram	•	• • •	• • • • • •			
Number of dots (triangular number)	1	3				

ii Find the 7th and 8th triangular numbers.

c Fibonacci numbers are a sequence of numbers where each number is the sum of the two preceding numbers. The first two numbers in the sequence are 0 and 1.

i Write down the first ten Fibonacci numbers.

ii If the Fibonacci numbers were to be extended in the negative direction, what would the first four negative Fibonacci numbers be?



Fibonacci numbers have many applications in nature, such as in the structure of an uncurling fern frond.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1B Decimals and significant figures

Numbers with and without decimal places can be rounded depending on the level of accuracy required. When using numbers with decimal places it is common to round off the number to leave only a certain number of decimal places. The time for a 100 m sprint race, for example, might be 9.94 seconds.

For road construction purposes, the volume of sand in these piles would only need to be known to two or three significant figures.

Due to the experimental nature of science and engineering, not all the digits in all numbers are considered important or 'significant'. In such cases we are able to round numbers to within a certain number of significant figures (sometimes abbreviated to sig. fig.). The number of cubic metres of gravel required for a road, for example, might be calculated as 3485 but is rounded to 3500. This number is written using two significant figures.

Let's start: Plausible but incorrect

Johny says that the number 2.748 when rounded to one decimal place is 2.8 because:

- the 8 rounds the 4 to a 5
- then the new 5 rounds the 7 to an 8.

What is wrong with Johny's theory?

Key ideas

- To round a number to a required number of **decimal places**:
  - Locate the digit in the required decimal place.
  - Round down (leave as is) if the next digit (**critical digit**) is 4 or less.
  - Round up (increase by 1) if the next digit is 5 or more.

  For example:
  - To two decimal places, 1.543 rounds to 1.54 and 32.9283 rounds to 32.93.
  - To one decimal place, 0.248 rounds to 0.2 and 0.253 rounds to 0.3.
- To round a number to a required number of **significant figures**:
  - Locate the first non-zero digit counting from left to right.
  - From this first significant digit, count out the number of significant digits including zeros.
  - Stop at the required number of significant digits and round this last digit.
  - Replace any non-significant digit to the left of a decimal point with a zero.

  For example, these numbers are all rounded to 3 significant figures:
  $2.5391 \approx 2.54$, $0.002713 \approx 0.00271$, $568\,810 \approx 569\,000$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 2 Rounding to a number of decimal places

Round each of these to two decimal places.

a 256.1793 **b** 0.04459 **c** 4.8972

SOLUTION	EXPLANATION
a 256.1793 ≈ 256.18	The number after the second decimal place is 9, so round up (increase the 7 by 1).
b 0.04459 ≈ 0.04	The number after the second decimal place is 4, so round down. 4459 is closer to 4000 than 5000.
c 4.8972 ≈ 4.90	The number after the second decimal place is 7, so round up. Increasing by 1 means 0.89 becomes 0.90.

Example 3 Rounding to a number of significant figures

Round each of these numbers to two significant figures.

a 2567 **b** 23 067.453 **c** 0.04059

SOLUTION	EXPLANATION
a 2567 ≈ 2600	The first two digits are the first two significant figures. The third digit is 6, so round up. Replace the last two non-significant digits with zeros.
b 23 067.453 ≈ 23 000	The first two digits are the first two significant figures. The third digit is 0, so round down.
c 0.04059 ≈ 0.041	Locate the first non-zero digit, i.e. 4. So 4 and 0 are the first two significant figures. The next digit is 5, so round up.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4 Estimating using significant figures

Estimate the answer to the following by rounding each number in the problem to one significant figure and use your calculator to check how reasonable your answer is.
$27 + 1329.5 \times 0.0064$

SOLUTION	EXPLANATION
$27 + 1329.5 \times 0.0064$ $\approx 30 + 1000 \times 0.006$ $= 30 + 6$ $= 36$	Round each number to one significant figure and evaluate. Recall multiplication occurs before the addition.
The estimated answer is reasonable.	By calculator (to one decimal place): $27 + 1329.5 \times 0.0064 = 35.5$

Exercise 1B

1–3 | 2 | —

UNDERSTANDING

1 Choose the number to answer each question.
- **a** Is 44 closer to 40 or 50?
- **b** Is 266 closer to 260 or 270?
- **c** Is 7.89 closer to 7.8 or 7.9?
- **d** Is 0.043 closer to 0.04 or 0.05?

2 Choose the correct answer if the first given number is rounded to three significant figures.
- **a** 32 124 is rounded to 321, 3210 or 32 100
- **b** 431.92 is rounded to 431, 432 or 430
- **c** 5.8871 is rounded to 5.887, 5.88 or 5.89
- **d** 0.44322 is rounded to 0.44, 0.443 or 0.44302
- **e** 0.0019671 is rounded to 0.002, 0.00197 or 0.00196

3 Using one significant figure rounding, 324 rounds to 300, 1.7 rounds to 2 and 9.6 rounds to 10.
- **a** Calculate $300 \times 2 \div 10$.
- **b** Use a calculator to calculate $324 \times 1.7 \div 9.6$.
- **c** What is the difference between the answer in part **a** and the exact answer in part **b**?

4(½), 5–8, 9(½) | 4(½), 5, 6, 7(½), 8, 9(½) | 4–9(½)

FLUENCY

Example 2

4 Round each of the following numbers to two decimal places.

a 17.962	**b** 11.082	**c** 72.986	**d** 47.859
e 63.925	**f** 23.807	**g** 804.5272	**h** 500.5749
i 821.2749	**j** 5810.2539	**k** 1004.9981	**l** 2649.9974

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1B

FLUENCY

5 Round these numbers to the nearest integer.

a 6.814 **b** 73.148 **c** 129.94 **d** 36200.49

6 Use division to write these fractions as decimals rounded to three decimal places.

a $\frac{1}{3}$ **b** $\frac{2}{7}$ **c** $\frac{13}{11}$ **d** $\frac{400}{29}$

Example 3

7 Round each of these numbers to two significant figures.

a 2436 **b** 35057.4 **c** 0.06049 **d** 34.024

e 107 892 **f** 0.00245 **g** 2.0745 **h** 0.7070

8 Round these numbers to one significant figure.

a 32 000 **b** 194.2 **c** 0.0492 **d** 0.0006413

Example 4

9 Estimate the answers to the following by rounding each number in the problem to one significant figure. Check how reasonable your answer is with a calculator.

a $567 + 3126$ **b** $795 - 35.6$ **c** 97.8×42.2

d $965.98 + 5321 - 2763.2$ **e** $4.23 - 1.92 \times 1.827$ **f** $17.43 - 2.047 \times 8.165$

g $0.0704 + 0.0482$ **h** 0.023×0.98 **i** $0.027 \div 0.0032$

j 41.034^2 **k** 0.078×0.9803^2 **l** $1.8494^2 + 0.972 \times 7.032$

10, 11 10–12 11–13

PROBLEM-SOLVING

10 An electronic timer records the time for a running relay between two teams A and B. Team A's time is 54.283 seconds and team B's time is 53.791 seconds. What would be the difference in the times for teams A and B if the times were written down using:

a 1 decimal place

b 4 significant figures

c 2 significant figures

d 1 significant figure

11 $28.4 \times 2.94 \times 11.31$ is calculated by first rounding each of the three numbers. Describe the type of rounding that has taken place if the answer is:

a 900 **b** 893.2 **c** 924

12 150 m of fencing and 18 posts are used to create an area in the shape of an equilateral triangle. Posts are used in the corners and are evenly spaced along the sides. Find the distance between each post. Write your answer in metres rounded to the nearest centimetre.

13 A tonne (1000 kg) of soil is to be equally divided between 7 garden beds. How much soil does each garden bed get? Write your answer in tonnes rounded to the nearest kilogram.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

REASONING

14 Should 2.14999 be rounded down or up if it is to be rounded to one decimal place? Give reasons.

15 A scientific experiment uses very small amounts of magnesium (0.0025 g) and potassium (0.0062 g). Why does it make sense to use two significant figures instead of two decimal places when recording numbers in a situation like this?

16 Consider the two numbers 24 and 26.

- **a** Calculate:
  - **i** $24 + 26$
  - **ii** 24×26
- **b** Find the sum (+) of the numbers after rounding each number using one significant figure.
- **c** Find the product ($\times$) of the numbers after rounding each number using one significant figure.
- **d** What do you notice about the answers for parts **b** and **c** as compared to part **a**? Give an explanation.

Minute amounts of reagents are commonly used in chemistry laboratories.

nth decimal place | — | — | 17

ENRICHMENT

17 **a** Use division to express $\frac{2}{11}$ as a decimal correct to 8 decimal places.

- **b** Using the decimal pattern from part **a**, find the digit in the:
  - **i** 20th decimal place
  - **ii** 45th decimal place
  - **iii** 1000th decimal place.
- **c** Express $\frac{1}{7}$ as a decimal correct to 13 decimal places.
- **d** Using the decimal pattern from part **c** find the digit in the:
  - **i** 20th decimal place
  - **ii** 45th decimal place
  - **iii** 1000th decimal place.
- **e** Can you find any fraction whose decimal representation is non-terminating and has no pattern? Use a calculator to help.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1C Rational numbers CONSOLIDATING

Under the guidance of Pythagoras around 500 BCE, it was discovered that some numbers could not be expressed as a fraction. These special numbers, called irrational numbers, when written as a decimal continue forever and do not show any pattern. So to write these numbers exactly, you need to use special symbols such as $\sqrt{\ }$ and π. If, however, the decimal places in a number terminate or if a pattern exists, the number can be expressed as a fraction. These numbers are called rational numbers.

This is $\sqrt{2}$ to 100 decimal places:

1.41421356237309504880168872420969807856967187537694
80731766797379907324784621070388503875343276415727

Let's start: Approximating π

To simplify calculations, the ancient and modern civilisations have used fractions to approximate π. To 10 decimal places, $\pi = 3.1415926536$.

- Using single digit numbers, what fraction best approximates π? $\left(\text{For example: } \frac{5}{2}\right)$.
- Using single and/or double digit numbers, find a fraction that is a good approximation of π. Compare with other students to see who has the best approximation. $\left(\text{For example: } \frac{35}{11}\right)$.

Key ideas

- An **infinite** decimal is one where the decimal places continue indefinitely.

Real numbers

- **Rational number (fractions)** (e.g. $\frac{48}{6}, \frac{1}{3}, \frac{7}{1}$)
  - **Terminating decimals** (e.g. 8, 1.2, –6.123)
  - **Recurring decimals** (e.g. $0.5\dot{}$, $-1.\dot{4}$, $2.\overline{345}$)
- **Irrational numbers** (e.g. $\sqrt{2}$, pi (π), phi (φ) – the golden ratio)
  - **Infinite non-recurring decimals** (e.g. $\pi = 3.14159...$, $\varphi = 1.618033...$, $\sqrt{2} = 1.414213...$)

- **Equivalent fractions** have the same value.
  For example: $\frac{2}{3} = \frac{6}{9}$
- A fraction can be simplified by dividing the **numerator** and **denominator** by their highest common factor.
- If $\frac{a}{b}$ is a **proper fraction** then $a < b$.
  For example: $\frac{2}{7}$
- If $\frac{a}{b}$ is an **improper fraction** then $a > b$.
  For example: $\frac{10}{3}$
- A **mixed number** is written as a whole number plus a proper fraction.
  For example: $2\frac{3}{5}$
- Recall that $\frac{a}{b}$ means $a \div b$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Fractions can be compared using a **common denominator**. This should be the lowest common multiple of both denominators.
- A dot or bar is used to show a pattern in a recurring decimal number.
  For example: $\frac{1}{6} = 0.16666\ldots = 0.1\dot{6}$ or $\frac{3}{11} = 0.272727\ldots = 0.\overline{27}$

Example 5 Writing fractions as decimals

Write these fractions as decimals.

a $3\frac{3}{8}$ b $\frac{5}{13}$

SOLUTION	EXPLANATION
a $8\overline{)3.^{3}0^{6}0^{4}0}$ (0. 3 7 5)	Find a decimal for $\frac{3}{8}$ by dividing 8 into 3 using the short division algoritm.
$3\frac{3}{8} = 3.375$	
b $13\overline{)5.^{5}0^{11}0^{6}0^{8}0^{2}0^{7}0^{5}0}$ (0. 3 8 4 6 1 5 3)	Divide 13 into 5 and continue until the pattern repeats.
$\frac{5}{13} = 0.\overline{384615}$	Add a bar over the repeating pattern.
	Writing $0.\dot{3}84615\dot{}$ is an alternative.

Example 6 Writing decimals as fractions

Write these decimals as fractions.

a 0.24 b 2.385

SOLUTION	EXPLANATION
a $0.24 = \frac{24}{100}$	Write as a fraction using the smallest place value (hundredths) then simplify using the HCF of 4.
$= \frac{6}{25}$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $2.385 = 2\frac{385}{1000}$ $= 2\frac{77}{200}$

OR $\frac{2385}{1000} = \frac{477}{200} = 2\frac{77}{200}$

The smallest place value is thousandths.

Simplify to an improper fraction or a mixed number.

Example 7 Comparing fractions

Decide which is the larger fraction of the following.

$\frac{7}{12}$ or $\frac{8}{15}$

SOLUTION

LCM of 12 and 15 is 60.

$\frac{7}{12} = \frac{35}{60}$ and $\frac{8}{15} = \frac{32}{60}$

$\therefore \frac{7}{12} > \frac{8}{15}$

EXPLANATION

Find the lowest common multiple of the two denominators (lowest common denominator).

Write each fraction as an equivalent fraction using the common denominator. Then compare numerators (i.e. 35 > 32) to determine the larger fraction.

Exercise 1C

1–4 | 3–4(½) | —

UNDERSTANDING

1 Write these numbers as mixed numbers.

a $\frac{7}{5}$ **b** $\frac{13}{3}$ **c** $\frac{48}{11}$ **d** $\frac{326}{53}$

2 Write these numbers as improper fractions.

a $1\frac{4}{7}$ **b** $5\frac{1}{3}$ **c** $9\frac{1}{2}$ **d** $18\frac{4}{13}$

3 Simplify by cancelling.

a $\frac{4}{10}$ **b** $\frac{8}{58}$ **c** $4\frac{20}{120}$ **d** $-72\frac{125}{1000}$

4 Write down the missing number.

a $\frac{3}{5} = \frac{\square}{15}$ **b** $\frac{5}{6} = \frac{20}{\square}$ **c** $\frac{3}{7} = \frac{9}{\square}$ **d** $\frac{5}{11} = \frac{\square}{77}$

e $\frac{\square}{4} = \frac{21}{28}$ **f** $\frac{\square}{9} = \frac{42}{54}$ **g** $\frac{3}{\square} = \frac{15}{50}$ **h** $\frac{11}{\square} = \frac{121}{66}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5, 6(½), 7, 8(½), 10 | 5–8(½), 9, 10 | 5–8(½), 9, 10(½)

1C

FLUENCY

Example 5a

5 Write these fractions as decimals.

a $\frac{11}{4}$ **b** $\frac{7}{20}$ **c** $3\frac{2}{5}$ **d** $\frac{15}{8}$

e $2\frac{5}{8}$ **f** $3\frac{4}{5}$ **g** $\frac{37}{16}$ **h** $\frac{7}{32}$

Example 5b

6 Write these fractions as recurring decimals.

a $\frac{3}{11}$ **b** $\frac{7}{9}$ **c** $\frac{9}{7}$ **d** $\frac{5}{12}$

e $\frac{10}{9}$ **f** $3\frac{5}{6}$ **g** $7\frac{4}{15}$ **h** $\frac{29}{11}$

Example 6

7 Write these decimals as fractions.

a 0.35 **b** 0.06 **c** 3.7 **d** 0.56

e 1.07 **f** 0.075 **g** 3.32 **h** 7.375

i 2.005 **j** 10.044 **k** 6.45 **l** 2.101

Example 7

8 Decide which is the larger fraction in the following pairs.

a $\frac{3}{4}$ or $\frac{5}{6}$ **b** $\frac{13}{20}$ or $\frac{3}{5}$ **c** $\frac{7}{10}$ or $\frac{8}{15}$ **d** $\frac{5}{12}$ or $\frac{7}{18}$

e $\frac{7}{16}$ or $\frac{5}{12}$ **f** $\frac{26}{35}$ or $\frac{11}{14}$ **g** $\frac{7}{12}$ or $\frac{19}{30}$ **h** $\frac{7}{18}$ or $\frac{11}{27}$

9 Place these fractions in descending order.

a $\frac{3}{8}, \frac{5}{12}, \frac{7}{18}$

b $\frac{1}{6}, \frac{5}{24}, \frac{3}{16}$

c $\frac{8}{15}, \frac{23}{40}, \frac{7}{12}$

10 Express the following quantities as simplified fractions.

a \$45 out of \$100

b 12 kg out of 80 kg

c 64 baskets out of 90 shots in basketball

d 115 mL out of 375 mL

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1C

11, 12 | 11(½), 12, 13 | 12–14

PROBLEM-SOLVING

11 These sets of fractions form a pattern. Find the next two fractions in the pattern.

a $\frac{1}{3}, \frac{5}{6}, \frac{4}{3}, \frac{\square}{\square}, \frac{\square}{\square}$

b $\frac{6}{5}, \frac{14}{15}, \frac{2}{3}, \frac{\square}{\square}, \frac{\square}{\square}$

c $\frac{2}{3}, \frac{3}{4}, \frac{5}{6}, \frac{\square}{\square}, \frac{\square}{\square}$

d $\frac{1}{2}, \frac{4}{7}, \frac{9}{14}, \frac{\square}{\square}, \frac{\square}{\square}$

12 The 'Weather forecast' website says there is a 0.45 chance that it will rain tomorrow. The 'Climate control' website says that the chance of rain is $\frac{14}{30}$. Which website gives the least chance that it will rain?

The chance of rain could be expressed as a decimal, a fraction or a percentage.

13 A jug has 400 mL of half-strength orange juice. The following amounts of full strength juice are added to the mix. Find a fraction to describe the strength of the orange drink after the full strength juice is added.

a 100 mL **b** 50 mL **c** 120 mL **d** 375 mL

14 If x is an integer, determine what values x can take in the following.

a The fraction $\frac{x}{3}$ is a number between (and not including) 10 and 11.

b The fraction $\frac{x}{7}$ is a number between (and not including) 5 and 8.

c The fraction $\frac{34}{x}$ is a number between 6 and 10.

d The fraction $\frac{23}{x}$ is a number between 7 and 12.

e The fraction $\frac{x}{14}$ is a number between (and not including) 3 and 4.

f The fraction $\frac{58}{x}$ is a number between 9 and 15.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

15 15, 16 15, 16 **1C**

REASONING

15 $a\frac{b}{c}$ is a mixed number with unknown digits a, b and c. Write it as an improper fraction.

16 If $\frac{a}{b}$ is a fraction, answer the given questions with reasons.

a Is it possible to find a fraction that can be simplified by cancelling if one of a or b is prime?

b Is it possible to find a fraction that can be simplified by cancelling if both a and b are prime? Assume $a \neq b$.

c If $\frac{a}{b}$ is a fraction in simplest form, can a and b both be even?

d If $\frac{a}{b}$ is a fraction in simplest form, can a and b both be odd?

Converting recurring decimals to fractions

— — 17

ENRICHMENT

17 Here are two examples of how to convert recurring decimals to fractions.

$0.\dot{6} = 0.6666\ldots.$

Let $x = 0.6666\ldots.$ (1)

$10x = 6.6666\ldots.$ (2)

(2) – (1) $9x = 6$

$x = \frac{6}{9} = \frac{2}{3}$

$\therefore 0.\dot{6} = \frac{2}{3}$

$1.\overline{27} = 1.272727\ldots.$

Let $x = 1.272727\ldots.$ (1)

$100x = 127.2727\ldots.$ (2)

(2) – (1) $99x = 126$

$x = \frac{126}{99}$

$\therefore 1.\overline{27} = \frac{126}{99} = 1\frac{27}{99} = 1\frac{3}{11}$

Convert these recurring decimals to fractions using the above method.

a $0.\dot{8}$ **b** $1.\dot{2}$ **c** $0.\overline{81}$ **d** $3.\overline{43}$

e $9.\overline{75}$ **f** $0.\overline{132}$ **g** $2.9\overline{17}$ **h** $13.\overline{8125}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1D Operations with fractions

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Operations with integers can be extended to include rational and irrational numbers. The operations include: addition, subtraction, multiplication and division. Addition and subtraction of fractions is generally more complex than multiplication and division because there is the added step of finding common denominators.

Fractions are all around you and part of everyday life.

Let's start: The common errors

Here are incorrect solutions to four problems involving fractions.

- $\frac{2}{3} \times \frac{5}{3} = \frac{2 \times 5}{3} = \frac{10}{3}$
- $\frac{2}{3} + \frac{1}{2} = \frac{2+1}{3+2} = \frac{3}{5}$
- $\frac{7}{6} \div \frac{7}{3} = \frac{7}{6} \div \frac{14}{6} = \frac{\frac{1}{2}}{6} = \frac{1}{12}$
- $1\frac{1}{2} - \frac{2}{3} = 1\frac{3}{6} - \frac{4}{6} = -1\frac{1}{6}$

In each case describe what is wrong and give the correct solution.

Key ideas

- To add or subtract fractions, first convert each fraction to **equivalent fractions** that have the same **denominator**.
  - Choose the lowest common denominator.
  - Add or subtract the numerators and retain the denominator.
- To multiply fractions, multiply the numerators and multiply the denominators.
  - Cancel the highest common factor between any numerator and any denominator before multiplication.
  - Convert mixed numbers to improper fractions before multiplying.
  - The word 'of' usually means 'multiply'.

    For example: $\frac{1}{3}$ of $24 = \frac{1}{3} \times 24$.
- The **reciprocal** of a number multiplied by the number itself is equal to 1.
  - For example: the reciprocal of 2 is $\frac{1}{2}$ since $2 \times \frac{1}{2} = 1$.

    the reciprocal of $\frac{3}{5} = \frac{5}{3}$ since $\frac{3}{5} \times \frac{5}{3} = 1$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- To divide a number by a fraction, multiply by its reciprocal.
  For example: $\frac{2}{3} \div \frac{5}{6}$ becomes $\frac{2}{3} \times \frac{6}{5}$
- Whole numbers can be written using a denominator of 1.
  For example: $3 = \frac{3}{1}$

Example 8 Adding and subtracting fractions

Evaluate the following.

a $\frac{1}{2} + \frac{3}{5}$ **b** $1\frac{2}{3} + 4\frac{5}{6}$ **c** $3\frac{2}{5} - 2\frac{3}{4}$

SOLUTION	EXPLANATION
a $\frac{1}{2} + \frac{3}{5} = \frac{5}{10} + \frac{6}{10}$	The lowest common denominator of 2 and 5 is 10. Rewrite as equivalent fractions using a denominator of 10 and add the numerators.
$= \frac{11}{10}$ or $1\frac{1}{10}$	
b $1\frac{2}{3} + 4\frac{5}{6} = \frac{5}{3} + \frac{29}{6}$	Change each mixed number to an improper fraction.
$= \frac{10}{6} + \frac{29}{6}$	Remember the lowest common denominator of 3 and 6 is 6. Change $\frac{5}{3}$ to an equivalent fraction with denominator 6 then add the numerators and simplify by cancelling HCF of 3.
$= \frac{39}{6}$	
$= \frac{13}{2}$ or $6\frac{1}{2}$	
Alternatively: $1\frac{2}{3} + 4\frac{5}{6} = 1\frac{4}{6} + 4\frac{5}{6}$	**Alternative method**: add whole numbers and fractions separately, obtaining a common denominator for the fractions $\left(\frac{2}{3} = \frac{4}{6}\right)$.
$= 5\frac{9}{6}$	$\frac{9}{6} = 1\frac{3}{6}$
$= 6\frac{3}{6}$	
$= 6\frac{1}{2}$	
c $3\frac{2}{5} - 2\frac{3}{4} = \frac{17}{5} - \frac{11}{4}$	Convert to improper fractions then rewrite as equivalent fractions with the same denominator.
$= \frac{68}{20} - \frac{55}{20}$	Subtract the numerators.
$= \frac{13}{20}$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Multiplying fractions

Evaluate the following.

a $\frac{2}{3} \times \frac{5}{7}$ **b** $1\frac{2}{3} \times 2\frac{1}{10}$

SOLUTION **EXPLANATION**

a $\frac{2}{3} \times \frac{5}{7} = \frac{2 \times 5}{3 \times 7}$

$= \frac{10}{21}$

No cancelling is possible as there are no common factors between numerators and denominators.

Multiply the numerators and the denominators.

b $1\frac{2}{3} \times 2\frac{1}{10} = \frac{{}^{1}\cancel{5}}{\cancel{3}_{1}} \times \frac{\cancel{21}^{7}}{\cancel{10}_{2}}$

$= \frac{7}{2}$ or $3\frac{1}{2}$

Rewrite as improper fractions.

Cancel common factors between numerators and denominators and then multiply remaining numerators and denominators.

Example 10 Dividing fractions

Evaluate the following.

a $\frac{4}{15} \div \frac{12}{25}$ **b** $1\frac{17}{18} \div 1\frac{1}{27}$

SOLUTION **EXPLANATION**

a $\frac{4}{15} \div \frac{12}{25} = \frac{4}{15} \times \frac{25}{12}$

$= \frac{{}^{1}\cancel{4}}{\cancel{15}_{3}} \times \frac{\cancel{25}^{5}}{\cancel{12}_{3}}$

$= \frac{5}{9}$

To divide by $\frac{12}{25}$ we multiply by its reciprocal $\frac{25}{12}$.

Cancel common factors between numerators and denominators then multiply fractions.

b $1\frac{17}{18} \div 1\frac{1}{27} = \frac{35}{18} \div \frac{28}{27}$

$= \frac{{}^{5}\cancel{35}}{\cancel{18}_{2}} \times \frac{\cancel{27}^{3}}{\cancel{28}_{4}}$

$= \frac{15}{8}$ or $1\frac{7}{8}$

Rewrite mixed numbers as improper fractions.

Multiply by the reciprocal of the second fraction.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 1D

1(½), 2, 3 | 3 | —

UNDERSTANDING

1 Find the lowest common denominator for these pairs of fractions.

a $\frac{1}{2}, \frac{1}{3}$ **b** $\frac{3}{7}, \frac{5}{9}$ **c** $\frac{2}{5}, \frac{1}{13}$ **d** $\frac{3}{10}, \frac{8}{15}$

e $\frac{1}{2}, \frac{1}{4}$ **f** $\frac{9}{11}, \frac{4}{33}$ **g** $\frac{5}{12}, \frac{7}{30}$ **h** $\frac{13}{29}, \frac{2}{3}$

2 Convert these mixed numbers to improper fractions.

a $2\frac{1}{3}$ **b** $7\frac{4}{5}$ **c** $10\frac{1}{4}$ **d** $22\frac{5}{6}$

3 Copy and complete the given working.

a $\frac{3}{2}+\frac{4}{3}=\frac{\square}{6}+\frac{\square}{6}$
$=\frac{\square}{6}$

b $1\frac{1}{3}-\frac{2}{5}=\frac{\square}{3}-\frac{2}{5}$
$=\frac{\square}{15}-\frac{\square}{15}$
$=\frac{14}{\square}$

c $\frac{5}{3}\div\frac{2}{7}=\frac{5}{3}\times\frac{\square}{\square}$
$=\frac{\square}{6}$

4–10(½) | 4–10(½) | 4–10(½)

FLUENCY

Example 8a

4 Evaluate the following.

a $\frac{2}{5}+\frac{1}{5}$ **b** $\frac{3}{9}+\frac{1}{9}$ **c** $\frac{5}{7}+\frac{4}{7}$ **d** $\frac{3}{4}+\frac{1}{5}$

e $\frac{1}{3}+\frac{4}{7}$ **f** $\frac{3}{8}+\frac{4}{5}$ **g** $\frac{2}{5}+\frac{3}{10}$ **h** $\frac{4}{9}+\frac{5}{27}$

Example 8b

5 Evaluate the following.

a $3\frac{1}{4}+1\frac{3}{4}$ **b** $2\frac{3}{5}+\frac{4}{5}$ **c** $1\frac{3}{7}+3\frac{5}{7}$

d $2\frac{1}{3}+4\frac{2}{5}$ **e** $2\frac{5}{7}+4\frac{5}{9}$ **f** $10\frac{5}{8}+7\frac{3}{16}$

6 Evaluate the following.

a $\frac{4}{5}-\frac{2}{5}$ **b** $\frac{4}{5}-\frac{7}{9}$ **c** $\frac{3}{4}-\frac{1}{5}$ **d** $\frac{2}{5}-\frac{3}{10}$

e $\frac{8}{9}-\frac{5}{6}$ **f** $\frac{3}{8}-\frac{1}{4}$ **g** $\frac{5}{9}-\frac{3}{8}$ **h** $\frac{5}{12}-\frac{5}{16}$

Example 8c

7 Evaluate the following.

a $2\frac{3}{4}-1\frac{1}{4}$ **b** $3\frac{5}{8}-2\frac{7}{8}$ **c** $3\frac{1}{4}-2\frac{3}{5}$

d $3\frac{5}{8}-2\frac{9}{10}$ **e** $2\frac{2}{3}-1\frac{5}{6}$ **f** $3\frac{7}{11}-2\frac{3}{7}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

1D

FLUENCY

Example 9

8 Evaluate the following (recall $6 = \frac{6}{1}$).

a $\frac{2}{5} \times \frac{3}{7}$ **b** $\frac{3}{5} \times \frac{5}{6}$ **c** $\frac{2}{15} \times \frac{5}{8}$ **d** $\frac{6}{21} \times 1\frac{5}{9}$

e $6 \times \frac{3}{4}$ **f** $8 \times \frac{2}{3}$ **g** $\frac{5}{6} \times 9$ **h** $1\frac{1}{4} \times 4$

i $2\frac{1}{2} \times 6$ **j** $1\frac{5}{8} \times 16$ **k** $\frac{10}{21} \times 1\frac{2}{5}$ **l** $\frac{25}{44} \times 1\frac{7}{15}$

m $1\frac{1}{2} \times 1\frac{1}{2}$ **n** $1\frac{1}{2} \times 2\frac{1}{3}$ **o** $2\frac{2}{3} \times 2\frac{1}{4}$ **p** $1\frac{1}{5} \times 1\frac{1}{9}$

9 Write down the reciprocal of these numbers.

a 3 **b** $\frac{5}{7}$ **c** $\frac{1}{8}$ **d** $\frac{13}{9}$

Example 10

10 Evaluate the following (recall the reciprocal of 8 is $\frac{1}{8}$).

a $\frac{4}{7} \div \frac{3}{5}$ **b** $\frac{3}{4} \div \frac{2}{3}$ **c** $\frac{5}{8} \div \frac{7}{9}$ **d** $\frac{3}{7} \div \frac{4}{9}$

e $\frac{3}{4} \div \frac{9}{16}$ **f** $\frac{4}{5} \div \frac{8}{15}$ **g** $\frac{8}{9} \div \frac{4}{27}$ **h** $\frac{15}{42} \div \frac{20}{49}$

i $15 \div \frac{5}{6}$ **j** $6 \div \frac{2}{3}$ **k** $12 \div \frac{3}{4}$ **l** $24 \div \frac{3}{8}$

m $\frac{4}{5} \div 8$ **n** $\frac{3}{4} \div 9$ **o** $\frac{8}{9} \div 6$ **p** $14 \div 4\frac{1}{5}$

q $6 \div 1\frac{1}{2}$ **r** $1\frac{1}{3} \div 8$ **s** $2\frac{1}{4} \div 1\frac{1}{2}$ **t** $4\frac{2}{3} \div 5\frac{1}{3}$

PROBLEM-SOLVING

12–14 | 11(½), 12, 14, 15 | 11(½), 14–16

11 Evaluate these mixed-operation problems.

a $\frac{2}{3} \times \frac{1}{3} \div \frac{7}{9}$ **b** $\frac{4}{5} \times \frac{3}{5} \div \frac{9}{10}$ **c** $\frac{4}{9} \times \frac{6}{25} \div \frac{1}{150}$

d $2\frac{1}{5} \times \frac{3}{7} \div 1\frac{3}{14}$ **e** $5\frac{1}{3} \times \frac{13}{24} \div 1\frac{1}{6}$ **f** $2\frac{4}{13} \times \frac{3}{8} \div 3\frac{3}{4}$

12 To remove impurities a mining company filters $3\frac{1}{2}$ tonnes of raw material. If $2\frac{5}{8}$ tonnes are removed, what quantity of material remains?

13 When a certain raw material is processed it produces $3\frac{1}{7}$ tonnes of mineral and $2\frac{3}{8}$ tonnes of waste. How many tonnes of raw material were processed?

The concentration (proportion) of the desired mineral within an ore body is vital information in the minerals industry.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1D

PROBLEM-SOLVING

14 In a $2\frac{1}{2}$ hour maths exam, $\frac{1}{6}$ of that time is allocated as reading time. How long is the reading time?

15 A road is to be constructed with $15\frac{1}{2}$ m^3 of crushed rock. If a small truck can carry $2\frac{1}{3}$ m^3 of crushed rock, how many truckloads will be needed?

16 Regan worked for $7\frac{1}{2}$ hours in a sandwich shop. Three-fifths of her time was spent cleaning up and the rest serving customers. How much time did she spend serving customers?

17 | 17, 18 | 18, 19

REASONING

17 Here is an example involving the subtraction of fractions where improper fractions are not used. $2\frac{1}{2}-1\frac{1}{3}=2\frac{3}{6}-1\frac{2}{6}=1\frac{1}{6}$
Try this technique on the following problem and explain the difficulty that you encounter.

$$2\frac{1}{3}-1\frac{1}{2}$$

18 **a** A fraction is given by $\frac{a}{b}$. Write down its reciprocal.

b A mixed number is given by $a\frac{b}{c}$. Write an expression for its reciprocal.

19 If a, b and c are integers simplify the following.

a $\frac{b}{a}\times\frac{a}{b}$ **b** $\frac{a}{b}\div\frac{b}{a}$ **c** $\frac{a}{b}\div\frac{a}{b}$

d $\frac{a}{b}\times\frac{c}{a}\div\frac{a}{b}$ **e** $\frac{abc}{a}\div\frac{bc}{a}$ **f** $\frac{a}{b}\div\frac{b}{c}\times\frac{b}{a}$

Fraction operation challenge — | — | 20

ENRICHMENT

20 Evaluate the following. Express your answers using improper fractions.

a $2\frac{1}{3}-1\frac{2}{5}\times2\frac{1}{7}$ **b** $1\frac{1}{4}\times1\frac{1}{5}-2\frac{1}{2}\div10$

c $1\frac{4}{5}\times4\frac{1}{6}+\frac{2}{3}\times1\frac{1}{5}$ **d** $\left(1\frac{2}{3}+1\frac{3}{4}\right)\div3\frac{5}{12}$

e $4\frac{1}{6}\div\left(1\frac{1}{3}+1\frac{1}{4}\right)$ **f** $\left(1\frac{1}{5}-\frac{3}{4}\right)\times\left(1\frac{1}{5}-\frac{3}{4}\right)$

g $\left(2\frac{1}{4}-1\frac{2}{3}\right)\times\left(2\frac{1}{4}+1\frac{2}{3}\right)$ **h** $\left(3\frac{1}{2}+1\frac{3}{5}\right)\times\left(3\frac{1}{2}-1\frac{3}{5}\right)$

i $\left(2\frac{2}{3}-1\frac{3}{4}\right)\times\left(2\frac{2}{3}+1\frac{3}{4}\right)$ **j** $\left(4\frac{1}{2}-3\frac{2}{3}\right)\div\left(1\frac{1}{3}+\frac{1}{2}\right)$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1E Ratios, rates and best buys

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Fractions, ratios and rates are used to compare quantities. A lawn mower, for example, might require $\frac{1}{6}$ of a litre of oil to make a petrol mix of 2 parts oil to 25 parts petrol, which is an oil to petrol ratio of 2 to 25 or 2 : 25. The mower's blades might then spin at a rate of 1000 revolutions per minute (1000 revs/min).

Two-stroke lawnmowers run on petrol and oil mixed in a certain ratio.

Let's start: The lottery win

$100 000 is to be divided up for three lucky people into a ratio of 2 to 3 to 5 (2 : 3 : 5). Work out how the money is to be divided.

- Clearly write down your method and answer. There may be many different ways to solve this problem.
- Write down and discuss the alternative methods suggested by other students in the class.

Key ideas

- **Ratios** are used to compare quantities with the same units.
  - The ratio of a to b is written $a : b$.
  - Ratios in simplest form use whole numbers that have no common factor.
- The **unitary method** involves finding the value of one part of a total.
  - Once the value of one part is found then the value of several parts can easily be determined.
- A **rate** compares related quantities with different units.
  - The rate is usually written with one quantity compared to a single unit of the other quantity. For example: 50 km per 1 hour or 50 km/h.
- Ratios and rates can be used to determine **best buys** when purchasing products.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Simplifying ratios

Simplify these ratios.

a $38 : 24$ **b** $2\frac{1}{2} : 1\frac{1}{3}$ **c** $0.2 : 0.14$

SOLUTION	EXPLANATION
a $38 : 24 = 19 : 12$	The HCF of 38 and 24 is 2 so divide both sides by 2.
b $2\frac{1}{2} : 1\frac{1}{3} = \frac{5}{2} : \frac{4}{3}$ $= \frac{15}{6} : \frac{8}{6}$ $= 15 : 8$	Write as improper fractions using the same denominator. Then multiply both sides by 6 to write as whole numbers.
c $0.2 : 0.14 = 20 : 14$ $= 10 : 7$	Multiply by 100 to remove all the decimal places and simplify.

Example 12 Dividing into a given ratio

$300 is to be divided into the ratio 2 : 3.
Find the value of the larger portion using the unitary method.

SOLUTION	EXPLANATION
Total number of parts is $2 + 3 = 5$	Use the ratio 2 : 3 to get the total number of parts.
5 parts = $300	
1 part = $\frac{1}{5}$ of $300 = $60	Calculate the value of each part, $300 \div 5$.
Larger portion = 3×60 = $180	Calculate the value of 3 parts.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Simplifying rates

Write these rates in simplest form.

a 120 km every 3 hours **b** 5000 revolutions in $2\frac{1}{2}$ minutes

SOLUTION	EXPLANATION
a 120 km per 3 hours $= \frac{120}{3}$ km/h	Divide by 3 to write the rate compared to 1 hour.
$= 40$ km/h	
b 5000 revolutions per $2\frac{1}{2}$ minutes	
$= 10\,000$ revolutions per 5 minutes	First multiply by 2 to remove the fraction.
$= \frac{10\,000}{5}$ revs/min	Then divide by 5 to write the rate using 1 minute.
$= 2000$ revs/min	

Example 14 Finding best buys

a Which is better value?
5 kg of potatoes for \$3.80 or 3 kg for \$2.20

b Find the cost of 100 mL of each product then decide which is the best buy. Assume the products are of similar quality. 400 mL of shampoo A at \$3.20 or 320 mL of shampoo B at \$2.85

SOLUTION	EXPLANATION
a **Method A.** Price per kg.	
5 kg bag.	
1 kg costs \$3.80 ÷ 5 = \$0.76	Divide each price by the number of kilograms to find the price per kilogram.
3 kg bag.	
1 kg costs \$2.20 ÷ 3 = \$0.73	
∴ the 3 kg bag is better value	Then compare.
Method B. Amount per \$1.	
5 kg bag.	
\$1 buys 5 ÷ 3.8 = 1.32 kg	Divide each amount in kilograms by the cost to find the weight per \$1 spent.
3 kg bag.	
\$1 buys 3 ÷ 2.2 = 1.36 kg	
∴ the 3 kg bag is better value	Then compare.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b Shampoo A.
100 mL costs $3.20 ÷ 4 = $0.80
Alternatively, divide by 400 to find the cost of 1 mL then multiply by 100.
Shampoo B.
100 mL costs $2.85 ÷ 3.2 = $0.89
Alternatively, divide by 320 to find the cost of 1 mL then multiply by 100.
∴ shampoo A is the best buy

Exercise 1E

1–4 | 3 | —

UNDERSTANDING

1 Write down the missing number.

a 2 : 5 = ☐ : 10 **b** 3 : 7 = ☐ : 28 **c** 5 : 8 = 15 : ☐ **d** 7 : 12 = 42 : ☐

e ☐ : 12 = 1 : 4 **f** 4 : ☐ = 16 : 36 **g** 8 : ☐ = 640 : 880 **h** ☐ : 4 = 7.5 : 10

2 Consider the ratio of boys to girls of 4 : 5.

a What is the total number of parts?

b What fraction of the total are boys?

c What fraction of the total are girls?

d If there were 18 students in total, how many of them are boys?

e If there were 18 students in total, how many of them are girls?

3 A car is travelling at a rate (speed) of 80 km/h.

a How far would it travel in:

i 3 hours?

ii $\frac{1}{2}$ hour?

iii $6\frac{1}{2}$ hours?

b How long would it take to travel:

i 400 km?

ii 360 km?

iii 20 km?



Odometers in cars record the distance travelled.

4 Find the cost of 1 kg if:

a 2 kg costs $8 **b** 5 kg costs $15 **c** 4 kg costs $10

5–6(½), 7, 8, 10–12 | 5–6(½), 7–13 | 9–12(½), 13

FLUENCY

Example 11

5 Simplify these ratios.

a 6 : 30 **b** 8 : 20 **c** 42 : 28 **d** 52 : 39

e $1\frac{1}{2} : 3\frac{1}{3}$ **f** $2\frac{1}{4} : 1\frac{2}{5}$ **g** $\frac{3}{8} : 1\frac{3}{4}$ **h** $1\frac{5}{6} : 3\frac{1}{4}$

i 0.3 : 0.9 **j** 0.7 : 3.5 **k** 1.6 : 0.56 **l** 0.4 : 0.12

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1E

6 Write each of the following as a ratio in simplest form. *Hint*: convert to the same units first.

a 80c : $8 **b** 90c : $4.50 **c** 80 cm : 1.2 m
d 0.7 kg : 800 g **e** 2.5 kg : 400 g **f** 30 min : 2 hours
g 45 min : 3 hours **h** 4 hours : 50 min **i** 40 cm : 2 m : 50 cm
j 80 cm : 600 mm : 2 m **k** 2.5 hours : 1.5 days **l** 0.09 km : 300 m : 1.2 km

Example 12

7 Divide $500 into these given ratios using the unitary method.

a 2 : 3 **b** 3 : 7 **c** 1 : 1 **d** 7 : 13

8 420 g of flour is to be divided into a ratio of 7 : 3 for two different recipes. Find the smaller amount.

The correct ratio of ingredients in a recipe has to be maintained when the amount of product to be made is changed.

9 Divide $70 into these ratios.

a 1 : 2 : 4 **b** 2 : 7 : 1 **c** 8 : 5 : 1

Example 13

10 Write these rates in simplest form.

a 150 km in 10 hours
b 3000 revolutions in $1\frac{1}{2}$ minutes
c 15 swimming strokes in $\frac{1}{3}$ of a minute
d 56 metres in 4 seconds
e 180 mL in 22.5 hours
f 207 heart beats in $2\frac{1}{4}$ minutes

11 Hamish rides his bike at an average speed of 22 km/h. How far does he ride in:

a $2\frac{1}{2}$ hours? **b** $\frac{3}{4}$ hours? **c** 15 minutes?

Example 14a

12 Determine the best buy (cheaper deal) in each of the following.

a 2 kg of washing powder for $11.70 or 3 kg for $16.20
b 1.5 kg of red delicious apples for $4.80 or 2.2 kg of royal gala apples for $7.92
c 2.4 litres of orange juice for $4.20 or 3 litres of orange juice for $5.40
d 0.7 GB of internet usage for $14 or 1.5 GB for $30.90 with different service providers

Example 14b

13 Find the cost of 100 g of each product below then decide which is the best buy (cheaper deal).

a 300 g of coffee A at $10.80 or 220 g of coffee B at $8.58
b 600 g of pasta A for $7.50 or 250 g of pasta B for $2.35
c 1.2 kg of cereal A for $4.44 or 825 g of cereal B for $3.30

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1E

14, 15 | 15–18 | 17–21

PROBLEM-SOLVING

14 Kirsty manages a restaurant. Each day she buys watermelons and mangoes in the ratio of 3 : 2. How many watermelons did she buy if, on one day, the total number of watermelons and mangoes was 200?

15 If a prize of $6000 was divided among Georgia, Leanne and Maya in the ratio of 5 : 2 : 3, how much did each girl get?

16 When a crate of twenty 375 mL soft drink cans is purchased it works out to be $1.68 per litre. If a crate of 30 of the same cans is advertised as being a saving of 10 cents per can compared with the 20-can crate, calculate how much the 30-can crate costs.

17 The dilution ratio for a particular chemical with water is 2 : 3 (chemical to water). If you have 72 litres of chemical, how much water is needed to dilute the chemical?

18 Amy, Belinda, Candice and Diane invested money in the ratio of 2 : 3 : 1 : 4 in a publishing company. If the profit was shared according to their investment, and Amy's profit was $2400, find the profit each investor made.

Concentrations of substances in water or solvents are ratios.

19 Julie is looking through the supermarket catalogue for her favourite cookies and cream ice cream. She can buy 2 L of triple chocolate ice cream for $6.30 while the cookies and cream ice cream is usually $5.40 for 1.2 L. What saving does there need to be on the price of the 1.2 L container of cookies and cream ice cream for it to be of equal value to the 2 L triple chocolate container?

20 The ratio of the side lengths of one square to another is 1 : 2. Find the ratio of the areas of the two squares.

21 A quadrilateral (with angle sum 360°) has interior angles in the ratio 1 : 2 : 3 : 4. Find the size of each angle.

22 | 22, 23 | 23, 24

REASONING

22 2.5 kg of cereal A costs $4.80 and 1.5 kg of cereal B costs $2.95. Write down at least two different methods to find which cereal is a better buy (cheaper deal).

23 If $a : b$ is in simplest form, state whether the following are true or false.

a a and b must both be odd.

b a and b must both be prime.

c At least one of a or b is odd.

d The HCF of a and b is 1.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1E

REASONING

24 A ratio is $a : b$ with $a < b$ and a and b are positive integers. Write an expression for:

- **a** the total number of parts
- **b** the fraction of the smaller quantity out of the total
- **c** the fraction of the larger quantity out of the total.

ENRICHMENT

Mixing drinks — — 25

25 Four jugs of cordial have a cordial to water ratio as shown and a given total volume.

Jug	Cordial to water ratio	Total volume
1	1 : 5	600 mL
2	2 : 7	900 mL
3	3 : 5	400 mL
4	2 : 9	330 mL

- **a** How much cordial is in:
  - **i** Jug 1? **ii** Jug 2?
- **b** How much water is in:
  - **i** Jug 3? **ii** Jug 4?
- **c** If Jugs 1 and 2 were mixed together to give 1500 mL of drink:
  - **i** how much cordial is in the drink?
  - **ii** find the ratio of cordial to water in the drink.
- **d** Find the ratio of cordial to water if the following jugs are mixed.
  - **i** Jugs 1 and 3
  - **ii** Jugs 2 and 3
  - **iii** Jugs 2 and 4
  - **iv** Jugs 3 and 4
- **e** Which combination of two jugs gives the strongest cordial to water ratio?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1F Percentages and money

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

We use percentages for many different things in our daily lives. Some examples are loan rates, the interest given on term deposits and discounts on goods.

We know from our previous studies that a percentage is a number expressed out of 100. 'Per cent' comes from the Latin term *per centum* and means 'out of 100'.

Let's start: Which is the largest piece?

Four people receive the following portions of a cake:

- Milly 25.5%
- Tom $\frac{1}{4}$
- Adam 0.26
- Mai The left over

a Which person gets the most cake and why?

b How much cake does Mai get? What is her portion written as a percentage, decimal and fraction?

Key ideas

- To express a number as **percentage**, *multiply* by 100.
- To express a percentage as a **fraction** or **decimal**, *divide* by 100.
- A percentage of a number can be found using multiplication.
  For example: 25% of \$26 = $0.25 \times \$26$
  $= \$6.50$
- To find an original amount, use the **unitary method** or use division.
  For example: if 3% of an amount is \$36:
  - Using the unitary method: 1% of the amount is $\$36 \div 3 = \$12$
    $\therefore$ 100% of the amount is $\$12 \times 100 = \$1200$
  - Using division: 3% of the amount is \$36
    $0.03 \times \text{amount} = \$36$
    $\text{amount} = \$36 \div 0.03$
    $= \$1200$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 15 Converting between percentages, decimals and fractions

a Express 0.45 as a percentage.

b Express 25% as a decimal.

c Express $3\frac{1}{4}\%$ as a fraction.

SOLUTION	EXPLANATION
a $0.45 \times 100 = 45$ $\therefore\ 0.45 = 45\%$	Multiply by 100. This moves the decimal point 2 places to the right.
b $25\% = 25 \div 100 = 0.25$	Divide by 100. This moves the decimal point 2 places to the left.
c $3\frac{1}{4}\% = 3\frac{1}{4} \div 100$ $= \frac{13}{4} \times \frac{1}{100}$ $= \frac{13}{400}$	Divide by 100. Write the mixed number as an improper fraction and multiply by the reciprocal of 100 (i.e. $\frac{1}{100}$).

Example 16 Expressing a quantity as a percentage

Express 50c out of $2.50 as a percentage.

SOLUTION	EXPLANATION
50c out of \$2.50 $= \frac{{}^{1}\cancel{50}}{{}_{5}\cancel{250}} \times 100$ $= 20\%$	Convert to the same units (\$2.50 = 250c) and write as a fraction. Multiply by 100, cancelling first.

Example 17 Finding a percentage of a quantity

Find 15% of $35.

SOLUTION	EXPLANATION
15% of \$35 $= \frac{{}^{3}\cancel{15}}{{}_{20}\cancel{100}} \times \$35$ $= \$5.25$	Write the percentage as a fraction out of 100 and multiply by \$35. Note: 'of' means to 'multiply'.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 18 Finding the original amount

Determine the original amount if 5% of the amount is $45.

SOLUTION	EXPLANATION
Method 1: Unitary	
5% of the amount = $45 1% of the amount = $9 100% of the amount = $900 So the original amount is $900	To use the unitary method, find the value of 1 part or 1% then multiply by 100 to find 100%.
Method 2: Division	
5% of the amount = $45 0.05 × amount = $45 amount = $45 ÷ 0.05 = $900	Write 5% as a decimal then divide both sides by this number to find the original amount.

Exercise 1F

1–3 | 3 | —

UNDERSTANDING

1 Divide these percentages by 100 to express them as fractions. For example, $9\% = \frac{9}{100}$. Simplify where possible.

a 3% **b** 11% **c** 35% **d** 8%

2 Divide these percentages by 100 to express them as decimals. For example, 9% = 0.09.

a 4% **b** 23% **c** 86% **d** 46.3%

3 Express these simple decimals and fractions as percentages.

a 0.5 **b** 0.6 **c** 0.25 **d** 0.9

e $\frac{3}{4}$ **f** $\frac{1}{2}$ **g** $\frac{1}{5}$ **h** $\frac{1}{8}$

4–6(½), 7, 8–10(½) | 4–6(½), 7, 8–10(½) | 4–6(½), 7, 8–11(½)

FLUENCY

Example 15a **4** Express each of the following as a percentage.

a 0.34 **b** 0.4 **c** 0.06 **d** 0.7

e 1 **f** 1.32 **g** 1.09 **h** 3.1

Example 15b **5** Express each of the following as decimals.

a 67% **b** 30% **c** 250% **d** 8%

e $4\frac{3}{4}\%$ **f** $10\frac{5}{8}\%$ **g** $30\frac{2}{5}\%$ **h** $44\frac{1}{4}\%$

Example 15c **6** Express each part of Question **5** as a simplified fraction.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

1F

FLUENCY

7 Copy and complete this table. Use the simplest form for fractions.

Percentage	Fraction	Decimal
10%		
	$\frac{1}{2}$	
5%		
		0.25
		0.2
	$\frac{1}{8}$	
1%		
	$\frac{1}{9}$	
		$0.\dot{2}$

Percentage	Fraction	Decimal
	$\frac{3}{4}$	
15%		
		0.9
37.5%		
$33\frac{1}{3}\%$	$\frac{1}{3}$	
$66\frac{2}{3}\%$		
		0.625
	$\frac{1}{6}$	

Example 16

8 Convert each of the following to a percentage.

a \$3 out of \$12 **b** \$6 out of \$18 **c** \$0.40 out of \$2.50
d \$44 out of \$22 **e** \$140 out of \$5 **f** 45c out of \$1.80

Example 17

9 Find:

a 10% of \$360 **b** 50% of \$420 **c** 75% of 64 kg
d 12.5% of 240 km **e** 37.5% of 40 apples **f** 87.5% of 400 m
g $33\frac{1}{3}\%$ of 750 people **h** $66\frac{2}{3}\%$ of 300 cars **i** $8\frac{3}{4}\%$ of \$560

Example 18

10 Determine the original amount if:

a 10% of the amount is \$12 **b** 6% of the amount is \$42
c 3% of the amount is \$9 **d** 40% of the amount is \$2.80
e 90% of the amount is \$0.18 **f** 35% of the amount is \$140

11 Determine the value of x in the following if:

a 10% of x is \$54 **b** 15% of x is \$90 **c** 25% of x is \$127
d 18% of x is \$225 **e** 105% of x is \$126 **f** 110% of x is \$44

PROBLEM-SOLVING

12, 13 13–15 15–17

12 Bad weather stopped a cricket game for 35 minutes of a scheduled $3\frac{1}{2}$ hour match. What percentage of the scheduled time was lost?

13 Joe lost 4 kg and now weighs 60 kg. What percentage of his original weight did he lose?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

PROBLEM-SOLVING

14 About 80% of the mass of the human body is water. If Clare weighs 60 kg, how many kilograms of water make up her body weight?

15 In a class of 25 students, 40% have been to England. How many students have not been to England?

16 20% of the cross country runners in a school team weigh between 60 and 70 kg. If 4% of the school of 1125 students are in the cross country team, how many students in the team weigh between 60 and 70 kg?

17 One week Grace spent 16% of her weekly wage on a new bookshelf that cost $184. What is her weekly wage?

REASONING

18	18	18, 19

18 Consider the equation $P\%$ of $a = b$ (like 20% of 40 = 8 or 150% of 22 = 33).

a For what value of P is $P\%$ of $a = a$?

b For what values of P is $P\%$ of $a < a$?

c For what values of P is $P\%$ of $a > a$?

19 What can be said about the numbers x and y if:

a 10% of x = 20% of y?

b 10% of x = 50% of y?

c 5% of x = 3% of y?

d 14% of x = 5% of y?

ENRICHMENT

More than 100%

—	—	20

20 **a** Find 120% of 60.

b Determine the value of x if 165% of x = 1.5.

c Write 2.80 as a percentage.

d Write 325% as a fraction.

e $2000 in a bank account increases to $5000 over a period of time. By how much has the amount increased as a percentage?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1G Percentage increase and decrease

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Percentages are often used to describe by how much a quantity has increased or decreased. The price of a car in the new year might be increased by 5%. On a $70 000 car, this equates to a $3500 increase. The price of a shirt might be marked down by 30% and if the shirt originally cost $60, this provides an $18 discount. It is important to note that the increase or decrease is calculated on the original amount.

Let's start: The quicker method

Two students, Nicky and Mila, consider the question: $250 is increased by 15%. What is the final amount?

Nicky puts his solution on the board with two steps.

Step 1. 15% of $250 = $0.15 \times \$250$

$= \$37.50$

Step 2. Final amount = $250 + $37.50

$= \$287.50$

Mila says that the same problem can be solved with only one step using the number 1.15.

- Can you explain Mila's method? Write it down.
- What if the question was altered so that $250 is decreased by 15%. How would Nicky and Mila's methods work in this case?
- Which of the two methods do you prefer and why?

Key ideas

- To increase an amount by a given percentage, multiply by the sum of 100% and the given percentage.
  For example: to increase by 30%, multiply by 100% + 30% = 130% = 1.3
- To decrease an amount by a given percentage, multiply by 100% minus the given percentage.
  For example: to decrease by 25%, multiply by 100% – 25% = 75% = 0.75
- To find a **percentage change** or **absolute percentage difference** use

$$\text{Percentage change} = \frac{\text{change}}{\text{original amount}} \times 100\%$$

  - **Percentage error** is calculated in the same way.

$$\%\ \text{Error} = \frac{\text{difference between measured value and theoretical value}}{\text{theoretical value}} \times 100\%$$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 19 Increasing by a percentage

Increase $70 by 15%.

SOLUTION	EXPLANATION
$100\% + 15\% = 115\%$ $= 1.15$	First add 15% to 100%
$\$70 \times 1.15 = \$80.50$	Multiply by 1.15 to give $70 plus the increase in one step.

Example 20 Decreasing by a percentage

Decrease $5.20 by 40%.

SOLUTION	EXPLANATION
$100\% - 40\% = 60\%$ $= 0.6$	First subtract the 40% from 100% to find the percentage remaining.
$\$5.20 \times 0.6 = \$3.12$	Multiply by 60% = 0.6 to get the result.

Example 21 Finding a percentage change

a The price of a mobile phone increased from $250 to $280. Find the percentage increase.

b The population of a town decreases from 3220 to 2985. Find the percentage decrease and round to one decimal place.

SOLUTION	EXPLANATION
a Increase $= \$280 - \$250$ $= \$30$	First find the actual increase.
Percentage increase $= \frac{30}{250} \times \frac{100}{1}\%$ $= 12\%$	Divide the increase by the original amount and multiply by 100%.
b Decrease $= 3220 - 2985$ $= 235$	First find the actual decrease.
Percentage decrease $= \frac{235}{3220} \times \frac{100}{1}\%$ $= 7.3\%$ (to 1 d.p.)	Divide the decrease by the original population. Round as indicated.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 22 Finding the original amount

After rain, the volume of water in a tank increased by 24% to 2200 L. How much water was in the tank before it rained? Round to the nearest litre.

SOLUTION	EXPLANATION
$100\% + 24\% = 124\%$ $= 1.24$	Write the total percentage as a decimal.
Original volume $\times 1.24 = 2200$ $\therefore$ original volume $= 2200 \div 1.24$ $= 1774$ litres	The original volume is increased by 24% to give 2200 litres. Divide to find the original volume. Round as indicated.

Exercise 1G

1–3 | 3 | —

UNDERSTANDING

1 Write the missing number.

- **a** To increase a number by 40% multiply by _____
- **b** To increase a number by 26% multiply by _____
- **c** To increase a number by _____ multiply by 1.6
- **d** To increase a number by _____ multiply by 1.21
- **e** To decrease a number by 20% multiply by _____
- **f** To decrease a number by 73% multiply by _____
- **g** To decrease a number by _____ multiply by 0.94
- **h** To decrease a number by _____ multiply by 0.31

2 The price of a watch increases from $120 to $150.

- **a** What is the price increase?
- **b** Write this increase as a percentage of the original price.

3 A person's weight decreases from 108 kg to 96 kg.

- **a** What is the weight decrease?
- **b** Write this decrease as a percentage of the original weight. Round to one decimal place.

4–5(½), 6–9 | 4–5(½), 6–10 | 4–5(½), 6–9, 10(½)

FLUENCY

Example 19

4 Increase the given amounts by the percentage given in the brackets.

- **a** $50 (5%)
- **b** 35 min (8%)
- **c** 250 mL (50%)
- **d** 1.6 m (15%)
- **e** 24.5 kg (12%)
- **f** 25 watts (44%)
- **g** $13 000 (4.5%)
- **h** $1200 (10.2%)

Example 20

5 Decrease the given amounts by the percentage given in the brackets.

- **a** 24 cm (20%)
- **b** 35 cm (30%)
- **c** 42 kg (7%)
- **d** 55 mins (12%)
- **e** $90 (12.8%)
- **f** 220 mL (8%)
- **g** 25°C (28%)
- **h** $420 (4.2%)

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1G

FLUENCY

Example 21a

6 The length of a bike sprint race is increased from 800 m to 1200 m. Find the percentage increase.

7 From the age of 10 to 17, Nick's height increased from 125 cm to 180 cm. Find the percentage increase.

Example 21b

8 The temperature at night decreased from 25°C to 18°C. Find the percentage decrease.

9 Brett, a rising sprint star, lowered his 100 m time from 13 seconds flat to 12.48 seconds. Find the percentage decrease.

10 Find the percentage change in these situations rounding to one decimal place in each case.

- **a** 22 g increases to 27 g
- **b** 86°C increases to 109°C
- **c** 136 km decreases to 94 km
- **d** \$85.90 decreases to \$52.90

PROBLEM-SOLVING

11–13 | 11–14 | 11, 13–16

Example 22

11 After a price increase of 20% the cost of entry to a museum rose to \$25.80. Find the original price.

12 Average attendance at a sporting match rose by 8% in the past year to 32 473. Find the average in the previous year to the nearest integer.

13 A car when resold had decreased in value by 38% to \$9235. What was the original price of the car to the nearest dollar?

14 Calculate the % error for these experimental measures and theoretical measures.

	Experimental	Theoretical
a	22 cm	20 cm
b	4.5 L	4 L
c	1.05 sec	1.25 sec
d	58 m^2	64 m^2

15 The total price of an item including GST (at 10%) is \$120. How much GST is paid to the nearest cent?

16 A consultant charges a school a fee of \$300 per hour including GST (at 10%). The school hires the consultant for 2 hours but can claim back the GST from the government. Find the net cost of the consultant for the school to the nearest cent.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1G

17 | 17, 18 | 17–20

REASONING

17 An investor starts with $1000.

- **a** After a bad day the initial investment is reduced by 10%. Find the balance at the end of the day.
- **b** The next day is better and the balance is increased by 10%. Find the balance at the end of the second day.
- **c** The initial amount decreased by 10% on the first day and increased by 10% on the second day. Explain why the balance on the second day didn't return to $1000.

18 During a sale in a bookstore all travel guides are reduced from $30 by 20%. What percentage increase is required to take the price back to $30?

19 The cost of an item is reduced by 50%. What percentage increase is required to return to its original price?

20 The cost of an item is increased by 75%. What percentage decrease is required to return to its original price? Round to two decimal places.

Repeated increase and decrease

— | — | 21, 22

ENRICHMENT

21 If the cost of a pair of shoes was increased three times by 10%, 15% and 8% from an original price of $80, then the final price would be

$$\$80 \times 1.10 \times 1.15 \times 1.08 = \$109.30$$

Use a similar technique to find the final price of these items. Round to the nearest cent.

- **a** Skis starting at $450 and increasing by 20%, 10% and 7%
- **b** A computer starting at $2750 and increasing by 6%, 11% and 4%
- **c** A DVD player starting at $280 and decreasing by 10%, 25% and 20%
- **d** A circular saw starting at $119 and increasing by 18%, 37% and 11%

22 If an amount is increased by the same percentage each time, powers can be used.
For example 50 kg increased by 12% three times would increase to

$$50 \text{ kg} \times 1.12 \times 1.12 \times 1.12$$
$$= 50 \text{ kg} \times (1.12)^3$$
$$= 70.25 \text{ kg (to 2 d.p.)}$$

Use a similar technique to find the final value in these situations. Round to two decimal places.

- **a** The mass of a rat initially at 60 grams grows at a rate of 10% every month for 3 months.
- **b** The cost of a new lawnmower initially at $80 000 increases by 5% every year for 4 years.
- **c** The value of a house initially at $380 000 decreases by 4% per year for 3 years.
- **d** The length of a pencil initially at 16 cm decreases through being sharpened by 15% every week for 5 weeks.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1H Profits and discounts

Interactive

Widgets

HOTsheets

Walkthroughs

Percentages are widely used in the world of finance. Profits, losses, commissions, discounts and taxation are often expressed and calculated using percentages.

Percentages are used by retailers to advertise discounts on items.

Let's start: The best discount

Two adjacent shops are selling the same jacket at a discounted price. The recommended retail price for the jacket is the same for both shops. Each shop has a sign near the jacket with the given details:

- Shop A. Discounted by 25%
- Shop B. Reduced by 20% then take a further 10% off that.

Which shop offers the bigger discount and is the difference equal to 5% of the retail price?

Key ideas

- **Profit** is the amount of money made on a sale. If the profit is negative we say that a loss has been made.
  - Profit = selling price – cost price
- **Mark-up** is the amount added to the cost price to produce the selling price.
  - Selling price = cost price + mark-up
- The **percentage profit** or loss can be found by dividing the profit or loss by the cost price and multiplying by 100.
  - $\%\ \text{Profit or Loss} = \frac{\text{profit or loss}}{\text{cost price}} \times 100\%$
- **Discount** is the amount by which an item is marked down.
  - New price = original price – discount
  - Discount = % discount × original price

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 23 Determining profit

A manufacturer produces an item for $400 and sells it for $540.

a Determine the profit made.

b Express this profit as a percentage of the cost price.

SOLUTION

a Profit = $540 – $400
= $140

b % profit = $\frac{140}{400} \times 100\%$
= 35%

EXPLANATION

Profit = selling price – cost price

% profit = $\frac{\text{profit}}{\text{cost price}} \times 100\%$

Example 24 Calculating selling price from mark-up

An electrical store marks up all entertainment systems by 30%.
If the cost price of one entertainment system is $8000, what will be its selling price?

SOLUTION

Selling price = 130% of cost price
= 1.3 × $8000
= $10 400

EXPLANATION

Since there is a 30% mark-up added to the cost price (100%), it follows that the selling price is 130% of the cost price.

Alternate method

Mark-up = 30% of $8000
= 0.3 × $8000
= $2400

Change percentage to a decimal and evaluate.

∴ selling price = $8000 + $2400
= $10 400

Selling price = cost price + mark-up

Example 25 Finding the discount amount

Harvey Norman advertises a 15% discount on all equipment as a Christmas special. Find the sale price on a projection system that has a marked price of $18 000.

SOLUTION

New price = 85% of $18 000
= 0.85 × $18 000
= $15 300

EXPLANATION

Discounting by 15% means the new price is 85%, i.e. (100 – 15)% of the original price.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Alternate method

Discount = 15% of \$18 000	Change the percentage to a decimal and evaluate.
$= 0.15 \times \$18\,000$	
= \$2700	
∴ The new price = \$18 000 – \$2700	New price is original price minus discount.
= \$15 300	

Example 26 Calculating sale saving

Toys 'R' Us discounts a toy by 10%, due to a sale. If the sale price was \$10.80, what was the original price?

SOLUTION	EXPLANATION
Let \$$x$ be the original price.	The discount factor = 100% – 10% = 90% = 0.9. Thus \$10.80 is 90% of the original price. Write an equation representing this and solve.
$0.9 \times x = 10.8$	
$x = 10.8 \div 0.9$	
$x = 12$	
The original price was \$12.	Write the answer in words.

Exercise 1H

1, 2 | 2 | —

UNDERSTANDING

1 Write the missing numbers in these tables.

a

Cost price (\$)	7	18	24.80		460.95	3250
Selling price (\$)	10	15.50	26.20	11.80	395	
Profit/Loss (\$)				4.50 profit		1180 loss

b

Cost price (\$)		99.95	199.95			18 000
Mark up (\$)	10			700	16 700	
Selling price (\$)	40.95	179.95	595.90	1499.95	35 499	26 995

c

Original price (\$)	100	49.95	29.95			2215
New price (\$)	72	40.90		176	299.95	
Discount (\$)			7.25	23	45.55	178

2 The following percentage discounts are given on the price of various products. State the percentage of the original price that each product is selling for.

a 10%
b 20%
c 15%
d 8%

Percentage discounts in a sale tell us how much the price is reduced by.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

1H

3–8, 11–13 | 3(½), 4–9, 11–14 | 3(½), 5–7, 10–14

FLUENCY

Example 23

3 A manufacturer produces and sells items for the prices shown.

i Determine the profit made.

ii Express this profit as a percentage of the cost price.

a Cost price $10, selling price $12

b Cost price $20, selling price $25

c Cost price $120, selling price $136.80

d Cost price $1400, selling price $3850

4 Dom runs a pizza business. Last year he took in $88 000 and it cost him $33 000 to run. What is his percentage profit for the year? Round to two decimal places.

5 It used to take 20 hours to fly to Los Angeles. It now takes 12 hours. What is the percentage decrease in travel time?

6 Rob goes to the races with $600 in his pocket. He leaves at the end of the day with $45. What is his percentage loss?

Example 24

7 Helen owns a handicrafts store that has a policy of marking up all of its items by 25%. If the cost price of one article is $30, what will be its selling price?

8 Lenny marks up all computers in his store by 12.5%. If a computer cost him $890, what will be the selling price of the computer, to the nearest dollar?

9 A dining room table sells for $448. If its cost price was $350 determine the percentage mark-up on the table.

10 A used-car dealer purchases a vehicle for $13 000 and sells it for $18 500. Determine the percentage mark-up on the vehicle to one decimal place.

Example 25

11 A store is offering a 15% discount for customers who pay with cash. Rada wants a microwave oven marked at $175. How much will she pay if she is paying with cash?

12 A camera store displays a camera marked at $595 and a lens marked at $380. Sam is offered a discount of 22% if he buys both items. How much will he pay for the camera and lens?

Example 26

13 A refrigerator is discounted by 25%. If Paula pays $460 for it what was the original price? Round to the nearest cent.

14 Maria put a $50 000 deposit on a house. What is the cost of the house if the deposit is 15% of the total price? Round to the nearest dollar.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1H

PROBLEM-SOLVING

15 | 15, 16 | 16, 17

15 A store marks up a $550 widescreen television by 30%. During a sale it is discounted by 20%. What is the percentage change in the original price of the television?

16 An armchair was purchased for a cost price of $380 and marked up to a retail price. It was then discounted by 10% to a sale price of $427.50. What is the percentage mark-up from the cost price to the sale price?

17 Pairs of shoes are manufactured for $24. They are sold to a warehouse with a mark-up of 15%. The warehouse sells the shoes to a distributor after charging a holding fee of $10 per pair. The distributor sells them to 'Fine Shoes' for a percentage profit of 12%. The store then marks them up by 30%.

a Determine the price of a pair of shoes if you buy it from one of the 'Fine Shoes' stores (round to the nearest 5 cents).

b What is the overall percentage mark-up of a pair of shoes to the nearest whole per cent?

REASONING

18 | 18, 19 | 19, 20

18 An item before being sold includes a percentage mark-up as well as a sale discount. Does it make a difference in which order the mark up and discount occur? Explain your answer.

19 Depreciation relates to a reduction in value. A computer depreciates in value by 30% in its first year. If its original value is $3000, find its value after one year.

20 John buys a car for $75 000. The value of the car depreciates at 15% per year. After 1 year the car is worth 85% of its original value, i.e. 85% of $75 000 = $0.85 \times 75\,000$ = $63 750.

a What is the value of the car, to the nearest cent, after:

i 2 years? **ii** 5 years?

b After how many years will the car first be worth less than $15 000?

ENRICHMENT

Deposits and discounts — | — | 21

21 A car company offers a special discount deal. After the cash deposit is paid, the amount that remains to be paid is discounted by a percentage that is one tenth of the deposit percentage.

For example, a deposit of $8000 on a $40 000 car represents 20% of the cost. The remaining $32 000 will be discounted by 2%.

Find the amount paid for each car given the following car price and deposit. Round to two decimal places where necessary.

a Price = $35 000, deposit = $7000

b Price = $45 000, deposit = $15 000

c Price = $28 000, deposit = $3500

d Price = $33 400, deposit = $5344

e Price = $62 500, deposit = $5000

f Price = $72 500, deposit = $10 150

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

1A **1** Evaluate the following.

a $-45 + (-3 \times 6 + 9)$ **b** $-4 \times 8 \div (-2) - 2^3$

1B **2** Round each of these numbers as indicated in the brackets.

a 3.45678 (2 decimal places) **b** 45.89985 (1 decimal place)

c 0.007856473 (2 significant figures) **d** 46 789 000 (3 significant figures)

1C **3** Write these fractions as decimals.

a $\frac{3}{4}$ **b** $\frac{4}{5}$ **c** $\frac{7}{20}$ **d** $\frac{1}{3}$

1C **4** Write these decimals as fractions.

a 0.9 **b** 0.85 **c** 0.125

1D **5** Evaluate the following.

a $\frac{1}{2} + \frac{5}{6}$ **b** $\frac{6}{7} - \frac{2}{3}$ **c** $1\frac{1}{2} \times \frac{4}{5}$ **d** $\frac{5}{8} \div \frac{3}{10}$

1E **6** Simplify these ratios.

a \$24 to 80 cents **b** 45 : 81 **c** 2.4 : 0.36 **d** $\frac{3}{4} : 8$

1E **7** Divide:

a \$400 in the ratio of 5 : 3 **b** 6 kg in the ratio of 3 : 7

c 1000 cm in the ratio of 4 : 5 : 6

1E **8** Write these rates in simplest form.

a \$350 in 5 hours **b** 200 km in 2.5 hours

1E **9** Which is the best buy (cheaper deal)?

Product A, which costs \$3.45 for 500 grams, or Product B, which costs \$4.38 for 680 grams.

1F **10** Write the following as percentages.

a $\frac{4}{5}$ **b** 0.96 **c** $3\frac{3}{4}$ **d** 40 cents out of \$5

1F **11** Find 34% of 6000 cm.

1F **12** Determine the original amount if 8% of the amount is \$32.

1G **13** **a** Increase \$450 by 12%.

b Decrease 500 kg by 5%.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1H **14** **a** The price of a first edition book increased from $400 to $480. Find the percentage increase.

b The price of a share in a company fell from $20 to $14. Find the percentage decrease.

1H **15** Find the selling price if a:

a $7500 TV was discounted by 15% in a sale

b $560 bike was marked up by 45%.

1F/G/H **16** A store displays a jacket with a recommended retail price of $159.

a If the jacket is on sale for 30% off, what is the selling price of the jacket?

b If the jacket sold for $124.02, what was the discounted amount as a percentage of the retail price?

c If Lemona bought the jacket on sale for 30% off then used her staff discount of 20%, what was the final cost of the jacket and what was the overall percentage saved on this purchase by Lemona?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1I Income and taxation

Most people's income is made up largely of the money they receive from their paid work – their job. Depending on the job, this payment can be made using a number of different methods. Many professional workers will receive an annual fixed *salary* which may be paid monthly or fortnightly. Casual workers, including those working in the retail area or restaurants, may receive a *wage* where they are paid a rate per hour worked – this rate may be higher out of regular working hours such as weekends or public holidays. Many sales people, including some real estate agents, may receive a weekly fee (a *retainer*) but may also receive a set percentage of the amount of sales they make (a *commission*). From their income, people have to pay living costs such as electricity, rent, groceries and other items. In addition, they have to pay tax to the government, which funds many of the nation's infrastructure projects and welfare. The method in which this tax is paid from their income may also vary.

Let's start: Which job pays better?

Ben and Nick are both looking for part-time jobs and they spot the following advertisements.

Kitchen hand
$9.40 per hour, $14.10 per hour on weekends.

Office assistant
Receive $516 per month for 12 hours work per week.

- Nick chooses to work as the kitchen hand. If in his first week he works 4 hours during the week and 8 hours at the weekend, how much will he earn?
- Ben works as the office assistant. How much does he earn per week if he works 4 weeks in a month? What does his hourly rate turn out to be?
- If Nick continues to work 12 hours in a week, does he earn more than Ben if he only works on week days? How many weekday hours must Nick work to match Ben's pay?
- Out of the 12 hours, what is the minimum number of hours Nick must work at the weekend to earn at least as much as Ben?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Workers who earn a **wage** (for example, a casual waiter) are paid a fixed rate per hour. Hours outside the normal working hours (public holidays etc.) are paid at a higher rate called **overtime**. This can occur in a couple of common ways:
  - **Time and a half**: pay is 1.5 times the usual hourly rate
  - **Double time**: pay is twice the usual hourly rate
- Workers who earn a **salary** (for example, an engineer) are paid a fixed amount per year, say $95 000. This is often paid monthly or fortnightly.
  - 12 months in a year and approximately 52 weeks in a year = 26 fortnights
- **Commission** is a proportion of the overall sales amount. Salespeople may receive a commission of their sales as well as a set weekly or monthly fee called a **retainer**.
  - Commission = % commission × total sales
- A person's **gross income** is the total income that they earn. The **net income** is what is left after deductions, such as tax, are taken out.
  - Net income = gross income – deductions
- **Taxation** is paid to the government once a person's taxable income passes a set amount. The amount paid depends on the person's taxable income.

Example 27 Comparing wages and salaries

Ken earns an annual salary of $59 735 and works a 38 hour week. His wife Brooke works part time in retail and earns $21.80 per hour.

a Calculate how much Ken earns per week.

b Determine who has the higher hourly rate of pay.

c If Brooke works on average 18 hours per week, what is her yearly income?

SOLUTION	EXPLANATION
a Weekly rate = $59735 ÷ 52	$59 735 pay in a year.
= $1148.75	There are approximately 52 weeks in a year.
∴ Ken earns $1148.75 per week	
b Brooke: $21.80/h	Ken works 38 hours in week.
Ken: $1148.75 ÷ 38	Hourly rate = weekly rate ÷ number of hours.
= $30.23/h	Round to the nearest cent.
∴ Ken is paid more per hour.	Compare hourly rates.
c In one week: $21.80 × 18	Weekly income = hourly rate × number of hours.
= $392.40	
Yearly income = $392.4 × 52	Multiply by 52 weeks to get yearly income.
= $20 404.80	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 28 Calculating overtime

Georgie works some weekends and late nights in addition to normal working hours and has overtime pay arrangements with her employer.

a Calculate how much Georgie earns in one week if she works 16 hours during the week at the normal hourly rate of $18.50 and 6 hours on the weekend at time and a half.

b Georgie's normal hourly rate is changed. In a week she works 9 hours at the normal rate, 4 hours at time and a half and 5 hours at double time. If she earns $507.50, what is her normal hourly rate?

SOLUTION	EXPLANATION
a Earnings at normal rate	
$= 16 \times \$18.50$	16 hours at standard rate
$= \$296$	
Earnings at time and a half	
$= 6 \times 1.5 \times \$18.50$	Time and a half is 1.5 times the normal rate.
$= \$166.50$	
$\therefore$ total earnings $= \$296 + \$166.50$	Combine earnings.
$= \$462.50$	
b Equivalent hours worked in week	Calculate the number of equivalent hours worked. 4 hours at time and a half is the same pay as for working 6 hours (4×1.5). 5 hours at double time is the same as working 10 hours (5×2).
$= 9 + (4 \times 1.5) + (5 \times 2)$	
$= 9 + 6 + 10$	
$= 25$ hours	
Normal hourly rate $= \$507.50 \div 25$	Divide weekly earnings by the 25 equivalent hours worked.
$= \$20.30$	
$\therefore$ earns $20.30 per hour	

Example 29 Calculating commission

A saleswoman is paid a retainer of $1500 per month. She also receives a commission of 1.25% on the value of goods she sells. If she sells goods worth $5600 during the month, calculate her earnings for that month.

SOLUTION	EXPLANATION
Commission = 1.25% of $5600	Calculate the commission on sales. Change the percentage to a decimal and evaluate.
$= 0.0125 \times \$5600$	
$= \$70$	
Earnings $= \$1500 + \$70$	Earnings = retainer + commission
$= \$1570$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 30 Calculating tax to find net income

Liam has an annual salary of $52 800. His payslip each month shows deductions for taxation of $968.

a Calculate Liam's net income each month.

b What percentage of Liam's monthly pay is being paid to the government by his employer for taxation?

c If the taxation rate for Liam's salary changes to 24% with the first $6000 now tax free, calculate Liam's net income for the year.

SOLUTION	EXPLANATION
a Monthly pay $= \$52\,800 \div 12$	Calculate gross income per month.
$= \$4400$	
$\therefore$ net monthly income $= \$4400 - \$968$	Net income = gross income – taxation
$= \$3432$	
b $\%\ \text{tax} = \frac{968}{4400} \times 100\%$	Calculate what fraction $968 is of the monthly income $4400. Multiply by 100% to convert to a percentage.
$= 22\%$	
c Salary for tax purposes $= \$52\,800 - \$6000$	First $6000 is not taxed.
$= \$46\,800$	
Tax amount = 24% of $46 800	Calculate tax amount on $46 800. Convert percentage to a decimal and evaluate.
$= 0.24 \times \$46\,800$	
$= \$11\,232$	
$\therefore$ net income $= \$52\,800 - \$11\,232$	Net income = gross income – tax amount.
$= \$41\,568$	

Exercise 1I

1–4 | 3 | —

UNDERSTANDING

1 An employee has an annual salary of $47 424 and works 38 hour weeks. Find the average earnings:

a per month **b** per week **c** per hour

2 A shop assistant is paid $11.40 per hour. Calculate the assistant's earnings from the following hours worked:

a 7 hours

b 5.5 hours

c 4 hours at twice the hourly rate (double time)

d 6 hours at 1.5 times the hourly rate (time and a half)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11

UNDERSTANDING

3 Find the commission earned on the given sales figures if the percentage commission is 20%.
- a $1000
- b $280
- c $4500
- d $725.50

4 Find the net annual income given the following:
- a Gross annual income = $56 300, tax paid = $10 134
- b Gross annual income = $28 700, tax paid = $5453

5, 6, 8, 10, 12 | 5, 6, 7(½), 8–13 | 7, 8–10, 12–13(½)

FLUENCY

Example 27

5 a Calculate the hourly rate of pay for a 38-hour working week with an annual salary of:
- i $38 532
- ii $53 352
- iii 83 980

b Calculate the yearly income for someone who earns $24.20 per hour and in a week works, on average:
- i 24 hours
- ii 35 hours
- iii 16 hours

Example 28a

6 A job has a normal working hours pay rate of $9.20 per hour. Calculate the pay including overtime from the following hours worked:
- a 3 hours and 4 hours at time and a half
- b 4 hours and 6 hours at time and a half
- c 14 hours and 3 hours at double time
- d 20 hours and 5 hours at double time
- e 10 hours and 8 hours at time and a half and 3 hours double time
- f 34 hours and 4 hours at time and a half and 2 hours double time

7 Calculate how many hours at the standard hourly rate the following working hours are equivalent to:
- a 3 hours and 2 hours at double time
- b 6 hours and 8 hours at time and a half
- c 15 hours and 12 hours at time and a half
- d 10 hours time and a half and 5 hours at double time
- e 20 hours and 6 hours at time and a half and 4 hours at double time
- f 32 hours and 4 hours at time and a half and 1 hour at double time

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 28b

8 Jim, a part-time gardener, earned $261 in a week. If he worked 12 hours during normal working hours and 4 hours overtime at time and a half, what was his hourly rate of pay?

9 Sally earned $329.40 in a week. If she worked 10 hours during the week and 6 hours on Saturday at time and a half and 4 hours on Sunday at double time, what was her hourly rate of pay?

Example 29

10 Amy works at Best Bookshop. During one week she sells books valued at $800. If she earns $450 per week plus 5% commission, how much does she earn in this week?

11 Jason works for a caravan company. If he sells $84 000 worth of caravans in a month, and he earns $650 per month plus 4% commission on sales, how much does he earn that month?

Example 30a

Example 30b

12 For each of the following, find:

i the annual net income

ii the percentage of gross income paid as tax. Round to one decimal place where necessary.

a Gross annual income = $48 241, tax withdrawn = $8206

b Gross annual income = $67 487, tax withdrawn = $13581.20

c Gross monthly income = $4041, tax withdrawn = $606.15

d Gross monthly income = $3219, tax withdrawn = $714.62

Example 30c

13 Calculate the amount of tax to be paid using the following annual salaries and tax rates if the first $6000 is tax free.

a salary = $18 200, tax rate = 15%

b salary = $44 300, tax rate = 21%

c salary = $57 500, tax rate = 24.5%

d salary = $84 200, tax rate = 30.4%

ISBN 978-1-107-57007-8
© Greenwood et al. 2016

Photocopying is restricted under law and this material must not be transferred to another party.

11

14, 15 | 15–17 | 16–18

PROBLEM-SOLVING

14 Arrange the following workers in order of most to least earnt in a week of work.
- Adam has an annual salary of $33 384.
- Bill works for 26 hours at a rate of $22.70 per hour.
- Cate earns $2964 per month. (Assume 52 weeks in a year.)
- Diana does shift work 4 days of the week between 10 pm and 4 am. She earns $19.90 per hour before midnight and $27.50 per hour after midnight.
- Ed works 18 hours at the normal rate of $18.20 per hour, 6 hours at time and a half and 4 hours at double time in a week.

15 Stephen earns an hourly rate of $17.30 for the first 38 hours he works, time and a half for the next 3 hours and double time for each extra hour above that. Calculate his earnings if he works 44 hours in a week.

16 Jessica works for Woods Real Estate and earns $800 per week plus 0.05% commission. If this week she sold three houses valued at $334 000, $210 000 and $335 500 respectively, how much will she have earned?

17 A door-to-door salesman sells 10 security systems in one week at $1200 each. For the week, he earns a total of $850 including a retainer of $300 and a commission. Find his percentage commission correct to two decimal places.

18 Mel has a net annual income of $53 246 after 21% of her income is withdrawn for tax purposes. What was her gross income?

19 | 19, 20 | 20, 21

REASONING

19 Karl is saving and wants to earn $90 from a casual job paying $7.50 per hour.
- **a** How many hours must he work to earn the $90?
- **b** Karl can also work some hours where he is paid time and a half. He decides to work x hours at the normal rate and y hours at time and a half to earn the $90. If x and y are both positive integers, find the possible combinations for x and y.

20 A car salesman earns 2% commission on sales up to $60 000 and 2.5% on sales above that.
- **a** Determine the amount earned on sales worth:
  - **i** $46 000
  - **ii** $72 000
- **b** Write a rule for the amount, A dollars, earned on sales of $\$x$ if:
  - **i** $x \leq 60\,000$
  - **ii** $x > 60\,000$

21 Kim has a job selling jewellery. She is about to enter into one of two new payment plans below.
Plan A: $220 per week plus 5% of sales Plan B: 9% of sales and no set weekly retainer
- **a** What value of sales gives the same return from each plan?
- **b** Explain how you would choose between Plan A and Plan B.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

22 Many countries use a progressive taxation system where the percentage of tax paid is increased for higher incomes. An example is shown in this table.

Income	Tax rate	Tax payable
$0–$10 000	0%	$0
$10 001–$30 000	20%	$0 + 20% of each dollar over $10 000
$30 001–$100 000	30%	$4000 + 30% of (income – $30 000)
$100 001–	40%	$25 000 + 40% of (income – $100 000)

a Using the above example, find the tax payable on the following incomes.

i $20 000 **ii** $55 000 **iii** $125 000

b Copy and complete the details in this progressive tax system.

Income	Tax rate	Tax payable
$0–$15 000	0%	$0
$15 001–$40 000	15%	$0 + 15% of each dollar over $15 000
$40 001–$90 000	25%	- -
$90 001–	33%	- -

c A different system on 'Taxation Island' looks like this.

Income	Tax rate	Tax payable
$0–$20 000	10%	10% of total income
$20 001–$80 000	30%	30% of total income
$80 001–	50%	50% of total income

Find the tax payable on an income of:

i $20 000 **ii** $21 000

iii $80 000 **iv** $80 001

d By referring to your answers in part **c**, describe the problems associated with the taxation system on Taxation Island.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1J Simple interest

When paying back the amount borrowed from a bank or other financial institution, the borrower pays interest to the lender. It's like rent paid on the money borrowed. A financial institution might be the lender, giving you a loan, or a borrower, when you invest your savings with them (effectively when you lend them your money). In either case, interest is calculated as a percentage of the amount borrowed. With simple interest, the percentage is calculated on the amount originally borrowed or invested and is paid at agreed times, such as once a year.

Let's start: Developing the rule

$5000 is invested in a bank and 5% simple interest is paid every year. In the table at right, the amount of interest paid is shown for Year 1, the amount of accumulated total interest is shown for Years 1 and 2.

Year	Interest paid that year	Accumulated total interest
1	$\frac{5}{100} \times \$5000 = \$250$	$1 \times \$250 = \$250$
2		$2 \times \$250 = \$500$
3		
4		
t		

- Complete the table, writing an expression in the last cell for the accumulated total interest after t years.
- Now write a rule using $\$P$ for the initial amount, t for the number of years and r for the interest rate to find the total interest earned, $\$I$.

Key ideas

- To compute **simple interest**, we apply the formula:

$$I = P \times \frac{r}{100} \times t \quad \text{or} \quad I = \frac{Prt}{100}$$

  where
  - I is the amount of **simple interest** (in $)
  - P is the **principal** amount; the money borrowed or loaned (in $)
  - $r\%$ is the rate per unit time; usually **per annum** (p.a.) which means per year
  - t is the period of **time**, expressed in the stated units, usually years.
- When using simple interest, the principal amount is constant and remains unchanged from one period to the next.
- The total amount ($\$A$) equals the principal plus interest

$$A = P + I$$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 31 Using the simple interest formula

Calculate the simple interest earned if the principal is \$1000, the rate is 5% p.a. and the time is 3 years.

SOLUTION	EXPLANATION
$P = 1000, r = 5, t = 3$	List the information given.
$I = P \times \frac{r}{100} \times t$ $= 1000 \times 0.05 \times 3$ $= 150$	Write the formula and substitute the given values. $\frac{5}{100} = 0.05$ Alternatively, use $I = \frac{Prt}{100}$
Interest = \$150	Answer the question.

Example 32 Calculating the final balance

Allan and Rachel plan to invest some money for their child Kaylan. They invest \$4000 for 30 months in a bank that pays 4.5% p.a. Calculate the simple interest and the amount available at the end of the 30 months.

SOLUTION	EXPLANATION
$P = 4000, r = 4.5, t = \frac{30}{12} = 2.5$	t is written in years since interest rate is per annum.
$I = P \times \frac{r}{100} \times t$ $= 4000 \times 0.045 \times 2.5$ $= 450$ Interest = \$450	Write the formula, substitute and evaluate. Alternatively, use $I = \frac{Prt}{100}$
Total amount = \$4000 + \$450 = \$4450	Total amount = principal + interest

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 33 Determining the investment period

Remy invests $2500 at 8% p.a. simple interest, for a period of time, to produce $50 interest. For how long did she invest the money?

SOLUTION	EXPLANATION
$I = 50, P = 2500, r = 8$	List the information.
$I = P \times \frac{r}{100} \times t$	Write the formula, substitute the known information and simplify.
$50 = 2500 \times 0.08 \times t$	
$50 = 200t$	Solve the remaining equation for t.
$t = \frac{50}{200}$	
$= 0.25$	
Time $= 0.25$ years	Convert decimal time to months where appropriate.
$= 0.25 \times 12$ months	
$= 3$ months	

Exercise 1J

1, 2 | 2(½) | —

UNDERSTANDING

1 $12 000 is invested at 6% p.a. for 42 months.
- a What is the principal amount?
- b What is the interest rate?
- c What is the time period in years?
- d How much interest is earned each year?
- e How much interest is earned after 2 years?
- f How much interest is earned after 42 months?

Example 31

2 Use the rule $I = P \times \frac{r}{100} \times t$ to find the simple interest earnt in these financial situations.
- a Principal $10 000, rate 10% p.a., time 3 years
- b Principal $6000, rate 12% p.a., time 5 years
- c Principal $5200, rate 4% p.a., time 24 months
- d Principal $3500, rate 6% p.a., time 18 months

3–6 | 3, 5–7 | 3, 5, 6, 8

FLUENCY

Example 32

3 Wally invests $15 000 at a rate of 6% p.a. for 3 years. Calculate the simple interest and the amount available at the end of 3 years.

4 Annie invests $22 000 at a rate of 4% p.a. for 27 months. Calculate the simple interest and the amount available at the end of 27 months.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1J

FLUENCY

5 A finance company charges 14% p.a. simple interest. If Lyn borrows $2000 to be repaid over 2 years, calculate her total repayment.

Example 33

6 Zac invests $3500 at 8% p.a. simple interest, for a period of time, to produce $210 interest. For how long did he invest the money?

7 If $4500 earns $120 simple interest at a flat rate of 2% p.a. calculate the duration of the investment.

8 Calculate the principal amount which earns $500 simple interest over 3 years at a rate of 8% p.a. Round to the nearest cent.

PROBLEM-SOLVING

9–11 | 10–12 | 11, 12

9 Wendy wins $5000 during a chess tournament. She wishes to invest her winnings, and has the two choices given below. Which one gives her the greater total at the end of the time?
Choice 1: 8.5% p.a. simple interest for 4 years
Choice 2: 8% p.a. simple interest for 54 months

10 Charlotte borrows $9000 to buy a second-hand car. The loan must be repaid over 5 years at 12% p.a. simple interest. Calculate:
- **a** the total amount to be repaid
- **b** the monthly repayment amount if the repayments are spread equally over the 5 years.

11 If $5000 earns $6000 simple interest in 12 years, find the interest rate.

12 An investor invests $\$P$ and wants to double this amount of money.
- **a** How much interest must be earned to double this initial amount?
- **b** What simple interest rate is required to double the initial amount in 8 years?
- **c** If the simple interest rate is 5% p.a.:
  - **i** how many years will it take to double the investment?
  - **ii** how many years will it take to triple the investment amount?
  - **iii** how do the investment periods in parts **i** and **ii** compare?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1J

13 | 13, 14 | 13, 14

REASONING

13 To find the total amount $\$T$ including simple interest, the rule is $T = P\left(1 + \frac{rt}{100}\right)$.

- **a** Use this rule to find the total amount after 10 years if \$30 000 is invested at 7% p.a.
- **b** Use the rule to find the time that it takes for an investment to grow from \$18 000 to \$22 320 invested at 6% p.a. simple interest.

14 Rearrange the rule $I = P \times \frac{r}{100} \times t$ to find a rule for:

- **a** P in terms of I, r and t
- **b** t in terms of I, P and r
- **c** r in terms of I, P and t

Property investing

— | — | 15

ENRICHMENT

15 Many investors use interest only loans to buy shares or property. This is where the principal stays constant and only the interest is paid back each month.

Sasha buys an investment property for \$300 000 and borrows the full amount at 7% p.a. simple interest. She rents out the property at \$1500 per month and it costs \$3000 per year in rates and other costs to keep the property.

- **a** Find the amount of interest Sasha needs to pay back every month.
- **b** Find Sasha's yearly income from rent.
- **c** By considering the other costs in keeping the property, what will Sasha's overall loss be in a year.
- **d** Sasha hopes that the property's value will increase enough to cover any loss she is making. By what percentage of the original price will the property need to increase in value per year?

Using a CAS calculator 1J: Number and interest problems

The activity is in the interactive textbook in the form of a printable PDF.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1K Compound interest EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

When interest is added onto an investment total before the next amount of interest is calculated, we say that the interest is compounded. Interest on a $1000 investment at 8% p.a. gives $80 in the first year and if compounded, the interest calculated in the second year is 8% of $1080. This is repeated until the end of the investment period. Other forms of growth and decay work in a similar manner.

In compound interest, the balance grows faster as time passes.

Let's start: Power play

$10 000 is invested at 5% compounded annually. Complete this table showing the interest paid and the balance (original investment plus interest) at the end of each year.

Year	Interest paid that year	Balance
1	$0.05 \times \$10\,000 = \$$_____	$\$10\,000 \times 1.05 = \$$_____
2	$0.05 \times \$$_____ $= \$$_____	$\$10\,000 \times 1.05 \times 1.05$ $= \$10\,000 \times 1.05^2$ $= \$$_____
3	$0.05 \times \$$_____ $= \$$_____	$\$10\,000 \times$_____ $= \$10\,000 \times 1.05^{\square}$ $= \$$_____

- What patterns can you see developing in the table?
- How can you use the *power* button on your calculator to help find the balance at the end of each year?
- How would you find the balance at the end of 10 years without creating a large table of values?

Key ideas

- A repeated product can be written and calculated using a power.
  - For example: $1.06 \times 1.06 \times 1.06 \times 1.06 = (1.06)^4$

    $0.85 \times 0.85 \times 0.85 = (0.85)^3$
- **Compound interest** is interest which is added to the investment amount before the next amount of interest is calculated.
  - For example: $5000 invested at 6% compounded annually for 3 years gives $\$5000 \times 1.06 \times 1.06 \times 1.06 = 5000 \times (1.06)^3$.
  - 6% compounded annually can be written as 6% p.a.
  - p.a. means 'per annum' or 'per year'.
  - The initial investment or loan is called the **principal**.
  - The total interest earned = final amount – principal.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 34 Calculating a balance using compound interest

Find the total value of the investment if $8000 is invested at 5% compounded annually for 4 years.

SOLUTION	EXPLANATION
$100\% + 5\% = 105\%$ $= 1.05$	Add 5% to 100% to find the multiplying factor.
Investment total $= \$8000 \times (1.05)^4$ $= \$9724.05$	Multiplying by $(1.05)^4$ is the same as multiplying by $1.05 \times 1.05 \times 1.05 \times 1.05$.

Example 35 Finding the initial amount

After 6 years a loan grows to $62 150. If the interest was compounded annually at a rate of 9%, find the size of the initial loan to the nearest dollar.

SOLUTION	EXPLANATION
$100\% + 9\% = 109\%$ $= 1.09$	Add 9% to 100% to find the multiplying factor.
Initial amount $\times (1.09)^6 = \$62\,150$	Write the equation including the final total.
Initial amount $= \$62\,150 \div (1.09)^6$ $= \$37\,058$	Divide by $(1.09)^6$ to find the initial amount and round as required.

Exercise 1K

1–3 | 3 | —

UNDERSTANDING

1 $2000 is invested at 10% compounded annually for 3 years.

- **a** Find the interest earned in the first year.
- **b** Find the total balance at the end of the first year.
- **c** Find the interest earned in the second year.
- **d** Find the total balance at the end of the second year.
- **e** Find the interest earned in the third year.
- **f** Find the total balance at the end of the third year.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1K

UNDERSTANDING

2 Find the value of the following correct to two decimal places.

a $2500 \times 1.03 \times 1.03 \times 1.03$ **b** $420 \times 1.22 \times 1.22 \times 1.22 \times 1.22$

c $2500 \times (1.03)^3$ **d** $420 \times (1.22)^4$

3 Fill in the missing numbers to describe each situation.

a \$4000 is invested at 20% compounded annually for 3 years.

$\$4000 \times (_____)^3$

b \$15 000 is invested at 7% compounded annually for 6 years.

$\$_____ \times (1.07)^{\square}$

c \$825 is invested at 11% compounded annually for 4 years.

$\$825 \times (_____)^{\square}$

FLUENCY

4–7 | 4(½), 5, 6(½), 7, 8(½) | 4(½), 5, 6(½), 7, 8(½)

Example 34

4 Find the total balance of these investments with the given interest rates and time period. Assume interest is compounded annually in each case. Round to the nearest cent.

a \$4000, 5%, 10 years **b** \$6500, 8%, 6 years

c \$25 000, 11%, 36 months **d** \$4000, 7%, 60 months

5 Barry borrows \$200 000 from a bank for 5 years and does not pay any money back until the end of the period. The compound interest rate is 8% p.a. How much does he need to pay back at the end of the 5 years? Round to the nearest cent.

6 Find the total percentage increase in the value of these amounts, compounded annually at the given rates. Round to one decimal place.

a \$1000, 4% p.a., 5 years **b** \$20 000, 6% p.a., 3 years

c \$125 000, 9% p.a., 10 years **d** \$500 000, 7.5% p.a., 4 years

Example 35

7 After 5 years a loan grows to \$45 200. If the interest was compounded annually at a rate of 6% p.a., find the size of the initial loan to the nearest dollar.

8 Find the initial investment amount to the nearest dollar given these final balances, annual interest rates and time periods. Assume interest is compounded annually in each case.

a \$26 500, 4%, 3 years **b** \$42 000, 6%, 4 years

c \$35 500, 3.5%, 6 years **d** \$28 200, 4.7%, 2 years

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1K

9, 10 | 10–12 | 11–13

PROBLEM-SOLVING

9 Average house prices in Hobart are expected to grow by 8% per year for the next 5 years. What is the expected average value of a house in Hobart in 5 years time, to the nearest dollar, if it is currently valued at $370 000?

The future value of any asset that grows by the same percentage every year (which can happen with a house) can also be calculated with the compound interest formula.

10 The population of a country town is expected to fall by 15% per year for the next 8 years due to the downsizing of the iron ore mine. If the population is currently 22 540 people, what is the expected population in 8 years time? Round to the nearest whole number.

11 It is proposed that the mass of a piece of limestone lying out in the weather has decreased by 4.5% per year for the last 15 years. Its current mass is 3.28 kg. Find its approximate mass 15 years ago. Round to two decimal places.

12 Charlene wants to invest $10 000 long enough for it to grow to at least $20 000. The compound interest rate is 6% p.a. How many whole number of years does she need to invest the money for so that it grows to her $20 000 target?

13 A forgetful person lets a personal loan balance grow from $800 to $1440 with a compound interest rate of 12.5% p.a. Approximately how many years did the person forget about the loan?

14 | 14 | 14, 15

REASONING

14 $400 is invested for 5 years under the following conditions.

i Simple interest at 7% p.a.

ii Compound interest at 7% p.a.

a Find the percentage increase in the total value of the investment using condition **i**.

b Find the percentage increase in the total value of the investment using condition **ii**. Round to two decimal places.

c Explain why the total for condition **i** is less than the total for condition **ii**.

15 Find the total percentage increase in these compound interest situations to two decimal places.

a 5% p.a. for 3 years **b** 12% p.a. for 2 years **c** 4.4% p.a. for 5 years

d 7.2% p.a. for 9 years **e** r % for t years

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Comparing simple and compound interest — — 16–18

1K

ENRICHMENT

16 $16 000 is invested for 5 years at 8% compounded annually.

a Find the total interest earned over the 5 years to the nearest cent.

b Find the simple interest rate that would deliver the same overall interest at the end of the 5 years. Round to two decimal places.

17 $100 000 is invested for 10 years at 5.5% compounded annually.

a Find the total percentage increase in the investment to two decimal places.

b Find the simple interest rate that would deliver the same overall interest at the end of the 10 years. Round to two decimal places.

18 Find the simple interest rate which is equivalent to these annual compound interest rates for the given periods. Round to two decimal places.

a 5% p.a. for 4 years

b 10.5% p.a. for 12 years



This graph shows the effect of the same rate of compound and simple interest on the increase in value of an investment or loan, compared over time. Simple interest is calculated only on the principal, so yields a balance that increases by the same amount every year, forming a straight-line graph. After the first year, compound interest is calculated on the principal and what has been added by the previous years' interest, so the balance increases by a greater amount each year. This forms an exponential graph.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Compounding investments

Banks offer many types of investments paying compound interest. Recall that for compound interest you gain interest on the money you have invested over a given time period. This increases your investment amount and therefore the amount of interest you gain in the next period.

Calculating yearly interest

Mary invests \$1000 at 6% per annum. This means Mary earns 6% of the principal every year in interest. That is, after 1 year the interest earned is

$$6\% \text{ of } \$1000 = \frac{6}{100} \times \$1000 = \$60$$

Mary now has \$1060 after one year.

a The interest earned is added to the principal at the end of the year, and the total becomes the principal for the second year.

- **i** Assuming the same rate of interest how much interest will she earn at the end of the second year?
- **ii** Calculate the interest earned for the third year?
- **iii** What total amount will Mary have at the end of the third year?
- **iv** How much interest will her money earn altogether over the 3 years?

b Write down a rule that calculates the total value of Mary's investment after t years. Use an initial investment amount of \$1000 and an annual interest rate of 6% p.a.

c Use your rule from part **b** to calculate:

- **i** the value of Mary's investment after 5 years
- **ii** the value of Mary's investment after 10 years
- **iii** the time it takes for Mary's investment to grow to \$1500
- **iv** the time it takes for Mary's investment to grow to \$2000.

Using a spreadsheet

This spreadsheet will calculate the compound interest for you if you place the principal in cell B3 and the rate in cell D3.

In Mary's case put 1000 in B3 and $\frac{6}{100}$ in D3.

	A	B	C	D
1	COMPOUND	INTEREST	SIMULATOR	
2				
3	PRINCIPAL	. . .	RATE OF PERIOD	. . .
4				
5	PERIOD	OPENING BALANCE	INTEREST EARNED	NEW BALANCE
6	1	=B3	=B6*D3	=B6 + C6
7	2	=D6	=B7*D3	=B7 + C7
8	3	=D7	=B8*D3	=B8 + C8
9	4	=D8	=B9*D3	=B9 + C9

a Copy the spreadsheet shown using 'fill down' at cells B7, C6 and D6.

b Determine how much money Mary would have after 4 years.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigating compound interest

a What will be Mary's balance after 10 years? Extend your spreadsheet to find out.

b Draw a graph of Investment value versus time as shown. Plot points using the results from your spreadsheet and join them with a smooth curve. Discuss the shape of the curve.



c How long does it take for Mary's investment to grow to $2000? Show on your spreadsheet.

d Now try altering the interest rate.

- **i** What would Mary's investment grow to in 10 years if the interest rate was 10%?
- **ii** What would Mary's investment grow to in 10 years if the interest rate was 12%?

e What interest rate makes Mary's investment grow to $2000 in 8 years? Use trial and error to get an answer correct to two decimal places. Record your investigation results using a table.

f Investigate how changing the principal changes the overall investment amount. Record your investigations in a table, showing the principal amounts and investment balance for a given interest rate and period.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 By only using the four operations +, –, × and ÷ as well as brackets and square root $(\sqrt{\ })$, the number 4 can be used exactly 4 times to give the answer 9 in the following way: $4 \times \sqrt{4} + 4 \div 4$. Use the number 4 exactly 4 times (and no other numbers) and any of the operations (as many times as you like) to give the answer 0 or 1 or 2 or 3 or … or 10.

2 What is the value of n if n is the largest of 5 consecutive numbers that multiply to give 95 040?

3 Evaluate.

a $\dfrac{1}{1+\dfrac{1}{1+\dfrac{1}{3}}}$ **b** $\dfrac{2}{1+\dfrac{2}{1+\dfrac{2}{5}}}$

4 A jug has 1 litre of 10% strength cordial. How much pure cordial needs to be added to make the strength 20%? (The answer is not 100 mL.)

5 An old table in a furniture store is marked down by 10% from its previous price on five separate occasions. What is the total percentage reduction in price correct to two decimal places?

6 What simple interest rate is equivalent to a compound interest rate of 6% p.a. over 10 years correct to two decimal places?

7 Brendon has a rectangular paved area in his yard.

a If he increases both the length and width by 20%, what is the percentage increase in area?

b If the length and width were increased by the same percentage and the area increases by 21%, what is the percentage increase of the length and width?

8 A rectangular sandpit is shown on a map which has a scale of 1 : 100. On the map the sandpit has an area of 20 cm^2. What is its actual area?

9 Arrange the numbers 1 to 15 in a row so that each adjacent pair of numbers sum to a square number.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Reviewing number and financial mathematics

Review of numbers

$2 + (-3) = -1$
$-4 - (-2) = -2$
$15 \div (-5) = -3$
$-7 \times (-3) = 21$
$(-2)^2 = 4$
$4^3 = 64$

For 8 and 12
HCF is 4
LCM is 24

$\sqrt{36} = 6$
$\sqrt[3]{27} = 3$

Operations with fractions

$$1\frac{5}{6} - \frac{7}{12} = \frac{11}{6} - \frac{7}{12}$$
$$= \frac{22}{12} - \frac{7}{12}$$
$$= \frac{15}{12}$$
$$= 1\frac{1}{4}$$

$$1\frac{1}{2} \div \frac{7}{2} = \frac{3}{\cancel{2}_1} \times \frac{\cancel{2}^1}{7}$$
$$= \frac{3}{7}$$

Rounding

1.284 to 1 d.p. is 1.3
2 sig. fig. is 1.3
472.543 to 1 d.p. is 472.5
1 sig. fig. is 500
0.0624 to 2 d.p. is 0.06
2 sig. fig. is 0.062

Rates, ratios and best buy

Rate: 180 km per 3 hrs = 60 km/h

Ratio: $\frac{3}{7} : \frac{1}{2} = \frac{6}{14} : \frac{7}{14} = 6 : 7$

$200 divided into 7 : 3
10 parts is $200
1 part is $20
3 parts is $60
7 parts is $140

Best buy: 3 kg of carrots for $6.45
5 kg for $10.20
3 kg bag: $6.45 \div 3 = $2.15/kg
5 kg bag: $10.20 \div 5 = $2.04/kg
$\therefore$ 5 kg is best buy

Rational numbers (fractions)

$1\frac{3}{8} = \frac{11}{8} = 1.375$
mixed number — improper fraction — terminating decimal

$\frac{1}{6} = 0.166... = 0.1\dot{6}$
proper fraction — recurring decimal

$\frac{2}{3}$ and $\frac{4}{6}$ are equivalent fractions

Irrational numbers cannot be expressed as a fraction

Compound interest (Ext)

$3000 at 5% for 3 years
Amount $= \$3000 \times (1.05)^3$
$= \$3472.88$

Percentages

$\frac{3}{4} = \frac{3}{4} \times 100\% = 75\%$

$25\frac{1}{2}\% = 25.5 \div 100\% = 0.255$

20% of 60 $= 0.2 \times 60 = 12$

5% of amount $= 32$
$\therefore$ amount $= 32 \div 0.05$
$= 640$

Simple interest

$2000 at 5% for 4 years

$I = P \times \frac{r}{100} \times t = \$2000 \times \frac{5}{100} \times 4$
$= \$400$

Income and tax

Employees can be paid:
wage: hourly rate with overtime at time and a half = 1.5 or double time
salary: annual amount
commission: % of sales
net income = gross income – tax

Applications of percentages

Percentage profit or loss
$= \frac{\text{Profit or loss}}{\text{Cost price}} \times 100\%$
Mark-up and discount
Commission/tax

Percentage increase and decrease

Increase	Decrease
20 by 6%	20 by 5%
$20 \times 1.06 = 21.2$	$20 \times 0.95 = 19$

Percentage change $= \frac{\text{change}}{\text{original}} \times 100\%$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

1B **1** $\frac{2}{7}$ written as a decimal is:

A 0.29 **B** 0.286 **C** $0.28\dot{5}$ **D** $0.\overline{285714}$ **E** $0.285714\dot{}$

1B **2** 3.0456 written to three significant figures is:

A 3.04 **B** 3.05 **C** 3.045 **D** 3.046 **E** 3.45

1C **3** 2.25 written as a fraction in simplest form is:

A $2\frac{1}{2}$ **B** $\frac{5}{4}$ **C** $\frac{9}{4}$ **D** $9\frac{1}{4}$ **E** $\frac{225}{100}$

1D **4** $1\frac{1}{2} - \frac{5}{6}$ is equal to:

A $\frac{2}{3}$ **B** $\frac{5}{6}$ **C** $-\frac{1}{2}$ **D** $\frac{2}{6}$ **E** $\frac{1}{2}$

1D **5** $\frac{2}{7} \times \frac{3}{4}$ is equivalent to:

A $\frac{8}{11}$ **B** $\frac{3}{7}$ **C** $\frac{5}{11}$ **D** $\frac{8}{12}$ **E** $\frac{3}{14}$

1D **6** $\frac{3}{4} \div \frac{5}{6}$ is equivalent to:

A $\frac{5}{8}$ **B** 1 **C** 21 **D** $\frac{4}{5}$ **E** $\frac{9}{10}$

1E **7** Simplifying the ratio 50 cm : 4 m gives:

A 50 : 4 **B** 8 : 1 **C** 25 : 2 **D** 1 : 8 **E** 5 : 40

1F **8** 28% as a fraction in its simplest form is:

A 0.28 **B** $\frac{28}{100}$ **C** $\frac{0.28}{100}$ **D** $\frac{2.8}{100}$ **E** $\frac{7}{25}$

1F **9** 15% of \$1600 is equal to:

A 24 **B** 150 **C** \$240 **D** \$24 **E** 240

1I **10** Jane is paid a wage of \$7.80 per hour. If she works 12 hours at this rate during a week plus 4 hours on a public holiday in the week where she gets paid at time and a half, her earnings in the week are:

A \$140.40 **B** \$124.80 **C** \$109.20 **D** \$156 **E** \$62.40

1I **11** Simon earns a weekly retainer of \$370 and 12% commission of any sales he makes. If he makes \$2700 worth of sales in a particular week, he will earn:

A \$595 **B** \$652 **C** \$694 **D** \$738.40 **E** \$649.60

1K **12** \$1200 is increased by 10% for two years with compound interest. The total balance at the end of the two years is:

A \$252 **B** \$1452 **C** \$1450 **D** \$240 **E** \$1440

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1A **1** Evaluate the following.

a $-4 \times (2 - (-3)) + 4$ **b** $-3 - 4 \times (-2) + (-3)$ **c** $(-8 \div 8 - (-1)) \times (-2)$

d $\sqrt{25} \times \sqrt[3]{8}$ **e** $(-2)^2 - 3^3$ **f** $\sqrt[3]{1000} - (-3)^2$

1B **2** Round these numbers to three significant figures.

a 21.483 **b** 29 130 **c** 0.15271 **d** 0.002414

1B **3** Estimate the answer by firstly rounding each number to one significant figure.

a $294 - 112$ **b** 21.48×2.94 **c** $1.032 \div 0.493$

1C **4** Write these fractions as decimals.

a $2\frac{1}{8}$ **b** $\frac{5}{6}$ **c** $\frac{13}{7}$

1C **5** Write these decimals as fractions.

a 0.75 **b** 1.6 **c** 2.55

1D **6** Simplify the following.

a $\frac{5}{6} - \frac{1}{3}$ **b** $1\frac{1}{2} + \frac{2}{3}$ **c** $\frac{13}{8} - \frac{4}{3}$ **d** $3\frac{1}{2} \times \frac{4}{7}$ **e** $5 \div \frac{4}{3}$ **f** $3\frac{3}{4} \div 1\frac{2}{5}$

1E **7** Simplify these ratios.

a 30 : 12 **b** 1.6 : 0.9 **c** $7\frac{1}{2} : 1\frac{2}{5}$

1E **8** Divide 80 into the given ratio.

a 5 : 3 **b** 5 : 11 **c** 1 : 2 : 5

1E **9** Dry dog food can be bought from store A for $18 for 8 kg or from store B for $14.19 for 5.5 kg.

a Determine the cost per kilogram at each store and state which is the best buy (cheaper deal).

b Determine to the nearest integer how many grams of each brand you get per dollar.

1F **10** Copy and complete the table at right.

Decimal	Fraction	Percentage
0.6		
	$\frac{1}{3}$	
		$3\frac{1}{4}\%$
	$\frac{3}{4}$	
1.2		
		200%

1F **11** Find:

a 25% of $310

b 110% of 1.5

1G **12** Determine the original amount if:

a 20% of the amount is 30

b 72% of the amount is 18

1G **13** **a** Increase 45 by 60%.

b Decrease 1.8 by 35%.

c Find the percentage change if $150 is reduced by $30.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

1G

14 The mass of a cat increased by 12% to 14 kg over a 12 month period. What was its previous mass?

1H

15 Determine the discount given on a $15 000 car if it is discounted by 12%.

1H

16 The cost price of an article is $150. If it is sold for $175:

- **a** determine the profit made
- **b** express the profit as a percentage of the cost price.

1I

17 Determine the hourly rate of pay for each of the following cases:

- **a** a person with an annual salary of $36 062 working a 38 hour week
- **b** a person who earns $429 working 18 hours at the hourly rate and 8 hours at time and a half.

1I

18 Jo's monthly income is $5270; however, 20% of this is paid straight to the government in taxes. What is Jo's net yearly income?

1J

19 Find the simple interest earned on $1500 at 7% p.a. for 5 years.

1J

20 Rob invests $10 000 at 8% p.a. simple interest to produce $3600. How long was the money invested for?

1K Ext

21 Find the total value of an investment if $50 000 is invested at 4% compounded annually for 6 years. Round to the nearest cent.

1K Ext

22 After 8 years a loan grows to $75 210. If the interest was compounded annually at a rate of 8.5%, find the size of the initial loan to the nearest dollar.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 Pauline buys a formal dress at cost price from her friend Tila. Pauline paid $420 for the dress, which is normally marked up by 55%.

a How much did she save?

b What is the normal selling price of the dress?

c If Tila gets a commission of 15%:

i how much commission did she get in dollars?

ii how much commission did Tila lose by selling the dress at cost price rather than the normal selling price?

Ext 2 Matilda has two bank accounts with the given details.

A Investment. Principal $25 000, interest rate 6.5% compounded annually

B Loan. 11.5% compounded annually

a Find Matilda's investment account balance after:

i 1 year

ii 10 years (to the nearest cent)

b Find the total percentage increase in Matilda's investment account after 10 years correct to two decimal places.

c After 3 years Matilda's loan account has increased to $114 250. Find the initial loan amount to the nearest dollar.

d Matilda reduces her $114 250 loan by $30 000. What is this reduction as a percentage to two decimal places?

e For Matilda's investment loan, what simple interest rate is equivalent to 5 years of the compounded interest rate of 6.5%? Round to one decimal place.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 2

Linear and simultaneous equations

What you will learn

2A Algebraic expressions (Consolidating)
2B Simplifying algebraic expressions (Consolidating)
2C Expanding algebraic expressions
2D Solving linear equations
2E Equations with brackets and pronumerals on both sides
2F Solving word problems
2G Inequalities
2H Using formulas
2I Simultaneous equations: substitution (Extending)
2J Simultaneous equations: elimination (Extending)
2K Applications of simultaneous equations (Extending)

Australian curriculum

NUMBER AND ALGEBRA

Patterns and algebra

Apply the distributive law to the expansion of algebraic expressions, including binomials, and collect like terms where appropriate AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

On a collision course

Linear equations with two variables, such as $2x + 3y = 12$, have an infinite number of solutions. If we plot them on a number plane we get a line. Each point on the line represents a possible solution.

These equations can model many different situations or systems in real life. For instance the two variables might be *total cost* and *quantity* of an item, or the *distance* of an object from its starting point over *time*, when it moves at uniform speed in a straight line.

Although there is no single solution to such a *distance-time* equation for one object, there is only one solution that satisfies both equations for two objects moving at constant speed in the same plane (provided they are not moving on parallel tracks). In this situation the two equations are called simultaneous equations. The one solution that satisfies the simultaneous equations can be found using algebra, and this solution represents the position and time at which they meet or collide.

Solving simultaneous equations can be applied to problems such as working out when and where one ship will intercept another, but navigation is only one of many areas where this aspect of algebra has applications.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

2A Algebraic expressions CONSOLIDATING

Algebra is central to the study of mathematics and is commonly used to solve problems in a vast array of theoretical and practical problems. Algebra involves the represention and manipulation of unknown or varying quantities in a mathematical context. Pronumerals (or variables) are used to represent these unknown quantities.

Variables representing unknown quantities are used in a wide range of jobs and occupations.

Let's start: Remembering the vocabulary

State the parts of the expression $5x - 2xy + (4a)^2 - 2$ that match these words.

- pronumeral (or variable)
- term
- coefficient
- constant term
- squared term

Key ideas

- In algebra, letters are used to represent numbers. These letters are called **pronumerals** or **variables**.
- An **expression** is a combination of numbers and pronumerals connected by the four operations +, –, × and ÷. Brackets can also be used.
  For example: $5x^2 + 4y - 1$ and $3(x + 2) - \frac{y}{5}$
- A **term** is a combination of numbers and variables connected with only multiplication and division. Terms are separated with the operations + and –.
  For example: $5x + 7y$ is a two-term expression.
- **Coefficients** are the numbers being multiplied by pronumerals.
  For example: the 3 in $3x$ and $\frac{1}{2}$ in $\frac{x^2}{2}$ are coefficients.
- **Constant terms** consist of a number only.
  For example: –2 in $x^2 + 4x - 2$ (The sign must be included.)
- Expressions can be **evaluated** by substituting a number for a pronumeral.
  For example: if $a = -2$ then $a + 6 = -2 + 6 = 4$
- **Order of operations** should be followed when evaluating expressions:
  1. Brackets
  2. Powers
  3. Multiplication and division
  4. Addition and subtraction

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Writing algebraic expressions for word problems

Write an algebraic expression for the following:

a the number of tickets needed for 3 boys and r girls

b the cost of P pies at \$3 each

c the number of grams of peanuts for one child if 300 g of peanuts is shared equally among C children.

SOLUTION	EXPLANATION
a $3 + r$	3 tickets plus the number of girls
b $3P$	3 multiplied by the number of pies
c $\frac{300}{C}$	300 g divided into C parts

Example 2 Converting words to expressions

Write an algebraic expression for the following:

a five less than x

b three more than twice x

c the sum of a and b is divided by 4

d the square of the sum of x and y

SOLUTION	EXPLANATION
a $x - 5$	5 subtracted from x
b $2x + 3$	Twice x plus 3
c $\frac{a+b}{4}$	The sum of a and b is done first $(a + b)$ and the result divided by 4.
d $(x + y)^2$	The sum of x and y is done first and then the result is squared.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Substituting values into expressions

Evaluate these expressions if $a = 5$, $b = -2$ and $c = 3$.

a $7a - 2(a - c)$ **b** $b^2 - ac$

SOLUTION	EXPLANATION
a $7a - 2(a - c) = 7 \times 5 - 2(5 - 3)$ $= 35 - 2 \times 2$ $= 35 - 4$ $= 31$	Substitute the values for a and c. When using order of operations, evaluate brackets before moving to multiplication and division then addition and subtraction.
b $b^2 - ac = (-2)^2 - 5 \times 3$ $= 4 - 15$ $= -11$	Evaluate powers before the other operations. $(-2)^2 = -2 \times (-2) = 4$.

Exercise 2A

1–3 | 3 | —

UNDERSTANDING

1 State the number of terms in these expressions.

a $5x + 2y$ **b** $1 + 2a^2$ **c** $b^2 + ca - 1$ **d** $\frac{x^2}{2}$

2 Match an item in the left column with an item in the right column.

A Product	**a** Division
B Sum	**b** Subtraction
C Difference	**c** Multiplication
D Quotient	**d** Addition
E x^2	**e** the reciprocal of a
F $\frac{1}{a}$	**f** the square of x

3 State the coefficient in these terms.

a $5xy$ **b** $-2a^2$ **c** $\frac{x}{3}$ **d** $-\frac{2a}{5}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2A

FLUENCY

4, 5–6(½) | 4, 5–6(½), 7 | 4, 5–6(½), 7

Example 1

4 Write an algebraic expression for the following.

a The number of tickets required for:

i 4 boys and r girls

ii t boys and 2 girls

iii b boys and g girls

iv x boys, y girls and z adults

b The cost of:

i P pies at \$6 each

ii 10 pies at \$$n$ each

iii D drinks at \$2 each

iv P pies at \$5 and D drinks at \$2

c The number of grams of lollies for one child if 500 g of lollies is shared equally among C children.

Example 2

5 Write an algebraic expression for each of the following.

a The sum of 2 and x

b The sum of ab and y

c 5 less than x

d The product of x and 3

e The difference between $3x$ and $2y$

f Three times the value of p

g Four more than twice x

h The sum of x and y is divided by 5

i 10 less than the product of 4 and x

j The square of the sum of m and n

k The sum of the squares of m and n

l The square root of the sum of x and y

m The sum of a and its reciprocal

n The cube of the square root of x

Example 3

6 Evaluate these expressions if $a = 4$, $b = -3$ and $c = 7$.

a $b - ac$

b $bc - a$

c $a^2 - c^2$

d $b^2 - ac$

e $\frac{a+b}{2}$

f $\frac{b^2+c}{a}$

g $\frac{1}{c} \times (a - b)$

h $a^3 - bc$

7 Evaluate these expressions if $x = -2$, $y = -\frac{1}{2}$ and $z = \frac{1}{6}$.

a $xy + z$

b $y^2 + x^2$

c xyz

d $\frac{xz+1}{y}$

PROBLEM-SOLVING

8, 9 | 8, 9 | 9, 10

8 A rectangular garden bed is 12 m long and 5 m wide.

a Find the area of the garden bed.

b The length is increased by x cm and the width is decreased by y cm. Find the new length and width of the garden.

c Write an expression for the area of the new garden bed.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2A

PROBLEM-SOLVING

9 The expression for the area of a trapezium is $\frac{1}{2}(a+b)h$ where a and b are the lengths of the two parallel sides and h is the distance between the two parallel sides.

- **a** Find the area of the trapezium with $a = 5, b = 7$ and $h = 3$.
- **b** A trapezium has $h = 4$ and area 12. If a and b are positive integers, what possible values can the variable a have?

10 The cost of 10 identical puzzles is $\$P$.

- **a** Write an expression for the cost of one puzzle.
- **b** Write an expression for the cost of n puzzles.

11 | 11, 12 | 12, 13

REASONING

11 For each of these shapes, write an expression for:

i the perimeter **ii** the area

a



b



c



12 Decide if the following statements refer to the same or different expressions. If they are different, write an expression for each statement.

- **a** **A** Twice the sum of x and y
  B The sum of $2x$ and y
- **b** **A** The difference between half of x and half of y
  B Half of the difference between x and y

13 For a right-angled triangle with hypotenuse c and shorter sides a and b, Pythagoras' theorem states that $c^2 = a^2 + b^2$.

- **a** Which of these two descriptions also describes Pythagoras' theorem?
  A The square of the hypotenuse is equal to the square of the sum of the two shorter sides.
  B The square of the hypotenuse is equal to the sum of the squares of the two shorter sides.



- **b** For the incorrect description, write an equation to match.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

14 The rule for the sum of the first n positive integers is given by:

The product of n and one more than n all divided by 2.

a Write an expression for the above description.

b Test the expression to find these sums

i $1 + 2 + 3 + 4$ $(n = 4)$

ii $1 + 2 + 3 + \cdots + 10$ $(n = 10)$

c Another way to describe the same expression is:

The sum of half of the square of n and half of n.

Write the expression for this description.

d Check that your expressions in parts **a** and **c** are equivalent (the same) by testing $n = 4$ and $n = 10$.

e $\frac{1}{2}(n^2 + n)$ is also equivalent to the above two expressions. Write this expression in words.



A diagram representing the sum of the first five positive integers arranged according to the expression in Question 14.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2B Simplifying algebraic expressions

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Just as $2+2+2+2=4\times2$, so $x+x+x+x=4\times x$ or $4x$. We say that the expression $x+x+x+x$ is simplified to $4x$. Similarly, $3x+5x=8x$ and $8x-3x=5x$.

All these expressions have like terms and can be simplified to an expression with a smaller number of terms.

A single term such as $2\times5\times x\div10$ can also be simplified using multiplication and division, so $2\times5\times x\div10=\frac{10x}{10}=x$.

Let's start: Are they equivalent?

All these expressions can be separated into two groups. Group them so that the expressions in each group are equivalent.

$2x$	$2x-y$	$4x-x-x$	$10x-y-8x$
$\frac{24x}{12}$	$y+x-y+x$	$2\times x-1\times y$	$-y+2x$
$0+\frac{1}{2}\times4x$	$\frac{x}{\left(\frac{1}{2}\right)}+0y$	$\frac{6x^2}{3x}$	$-1\times y+\frac{x^2}{\frac{1}{2}x}$

Key ideas

- The symbols for multiplication ($\times$) and division ($\div$) are usually not shown in simplified algebraic terms.
  For example: $5\times a\times b=5ab$ and $-7\times x\div y^2=-\frac{7x}{y^2}$
- When dividing algebraic expressions common factors can be cancelled.
  For example: $\frac{7x}{14}=\frac{x}{2}$, $\frac{a^2b}{a}=\frac{a^1\times a\times b}{a^1}=ab$
  $\frac{7xy}{14y}=\frac{x}{2}$ and $\frac{15a^2b}{10a}=\frac{3\times5\times a\times a\times b}{2\times5\times a}=\frac{3ab}{2}$
- **Like terms** have the same pronumeral factors.
  - For example: $5x$ and $7x$ are like terms and $3a^2b$ and $-2a^2b$ are like terms.
  - Since $a\times b=b\times a$ then ab and ba are also like terms.
- The pronumeral part of a term is often written in alphabetical order.
- **Like terms** can be collected (added and subtracted) to form a single term.
  For example: $5ab+8ab=13ab$
  $4x^2y-2yx^2=2x^2y$
- **Unlike terms** do not have the same pronumeral factors.
  For example: $5x$, x^2, xy and $\frac{4xyz}{5}$ are all unlike terms.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 4 Multiplying algebraic terms

Simplify the following.

a $3 \times 2b$ **b** $-2a \times 3ab$

SOLUTION | **EXPLANATION**

a $3 \times 2b = 3 \times 2 \times b$
$= 6b$

Multiply the coefficients.

b $-2a \times 3ab = -2 \times 3 \times a \times a \times b$
$= -6a^2b$

Multiply the coefficients and simplify.

Example 5 Dividing algebraic terms

Simplify the following.

a $\frac{6ab}{18b}$ **b** $12a^2b \div (3ab)$

SOLUTION | **EXPLANATION**

a $\frac{{}^{1}\cancel{6}ab^{\cancel{1}}}{{}_{3}\cancel{18}\,b_{\cancel{1}}} = \frac{a}{3}$

Deal with numerals and promumerals separately, cancelling where possible.

b $12a^2b \div (3ab) = \frac{{}^{4}\cancel{12}\,a^{2\,1}\cancel{b}^{\cancel{1}}}{{}_{1}\cancel{3}\,a_{\cancel{1}}\,b_{\cancel{1}}}$
$= 4a$

Write as a fraction first.

Cancel where possible, recall $a^2 = a \times a$.

Example 6 Collecting like terms

Simplify the following by collecting like terms.

a $3x + 4 - 2x$ **b** $3x + 2y + 4x + 7y$

c $8ab^2 - 9ab - ab^2 + 3ba$

SOLUTION | **EXPLANATION**

a $3x + 4 - 2x = 3x - 2x + 4$
$= x + 4$

Collect like terms ($3x$ and $-2x$). The sign belongs to the term that follows. Combine their coefficients $3 - 2 = 1$.

b $3x + 2y + 4x + 7y = 3x + 4x + 2y + 7y$
$= 7x + 9y$

Collect like terms and combine their coefficients.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

c $8ab^2 - 9ab - ab^2 + 3ba$
$= 8ab^2 - ab^2 - 9ab + 3ab$
$= 7ab^2 - 6ab$

Collect like terms. Remember $ab = ba$ and $ab^2 = 1ab^2$.

$8 - 1 = 7$ and $-9 + 3 = -6$

Exercise 2B

1, 2–3(½) | 3(½) | —

UNDERSTANDING

1 Write the missing word or expression.
- **a** Like terms have the same _____ factors.
- **b** $3x + 2x$ simplifies to _____.
- **c** $3a^2b$ and $2a$ are _____ terms.

2 Simplify these fractions.

a $\frac{4}{6}$ **b** $\frac{20}{8}$ **c** $\frac{30}{10}$ **d** $\frac{8}{40}$

e $-\frac{4}{14}$ **f** $-\frac{5}{100}$ **g** $-\frac{22}{106}$ **h** $-\frac{408}{24}$

3 Decide if the following pairs of terms are like terms.

a $4ab$ and $3ab$ **b** $2x$ and $7xy$ **c** 5 and $4m$
d $3t$ and $-6tw$ **e** $7yz$ and yz **f** $2mn$ and $9nm$
g $5a$ and a **h** $3x^2y$ and $7xy^2$ **i** $4ab^2$ and $-3b^2a$

4–7(½), 9–11(½) | 4–11(½) | 4–11(½)

FLUENCY

Example 4a

4 Simplify the following.

a $5 \times 2m$ **b** $2 \times 6b$ **c** $3 \times 5p$ **d** $3x \times 2y$
e $3p \times 6r$ **f** $4m \times 4n$ **g** $-2x \times 7y$ **h** $5m \times (-3n)$
i $-4c \times 3d$ **j** $2a \times 3b \times 5$ **k** $-4r \times 3 \times 2s$ **l** $5j \times (-4) \times 2k$

Example 4b

5 Simplify the following.

a $4n \times 6n$ **b** $-3q \times q$ **c** $5s \times 2s$
d $7a \times 3ab$ **e** $5mn \times (-3n)$ **f** $-3gh \times (-6h)$
g $3xy \times 4xy$ **h** $-4ab \times (-2ab)$ **i** $-2mn \times 3mn$

Example 5a

6 Simplify the following by cancelling.

a $\frac{8b}{2}$ **b** $-\frac{2a}{6}$ **c** $\frac{4ab}{6}$ **d** $\frac{3mn}{6n}$
e $-\frac{5xy}{20y}$ **f** $\frac{10st}{6t}$ **g** $\frac{u^2v}{u}$ **h** $\frac{5r^2s^2}{8rs}$
i $\frac{5ab^2}{9b}$ **j** $\frac{7y}{y^2}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2B

FLUENCY

Example 5b

7 Simplify the following by first writing in fraction form.

a $2x \div 5$ **b** $-4 \div (-3a)$ **c** $11mn \div 3$

d $12ab \div 2$ **e** $-10 \div (2gh)$ **f** $8x \div x$

g $-3xy \div (yx)$ **h** $7mn \div (3m)$ **i** $-27pq \div (6p)$

j $24ab^2 \div (8ab)$ **k** $25x^2y \div (-5xy)$ **l** $9m^2n \div (18mn)$

8 Simplify the following.

a $x \times 4 \div y$ **b** $5 \times p \div 2$ **c** $6 \times (-a) \times b$

d $a \times (-3) \div (2b)$ **e** $-7 \div (5m) \times n$ **f** $5s \div (2t) \times 4$

g $6 \times 4mn \div (3m)$ **h** $8x \times 3y \div (8x)$ **i** $3ab \times 12bc \div (9abc)$

j $4x \times 3xy \div (2x)$ **k** $10m \times 4mn \div (8mn)$ **l** $3pq \times pq \div p$

Example 6a

9 Simplify the following by collecting like terms.

a $3a + 7a$ **b** $4n + 3n$ **c** $12y - 4y$

d $5x + 2x + 4x$ **e** $6ab - 2ab - ba$ **f** $7mn + 2mn - 2mn$

g $4y - 3y + 8$ **h** $7x + 5 - 4x$ **i** $6xy + xy + 4y$

j $5ab + 3 + 7ba$ **k** $2 - 5m - m$ **l** $4 - 2x + x$

Example 6b

10 Simplify the following by collecting like terms.

a $2a + 4b + 3a + 5b$ **b** $4x + 3y + 2x + 2y$

c $6t + 5 - 2t + 1$ **d** $5x + 1 + 6x + 3$

e $xy + 8x + 4xy - 4x$ **f** $3mn - 4 + 4nm - 5$

g $4ab + 2a + ab - 3a$ **h** $3st - 8ts + 2st + 3ts$

Example 6c

11 Simplify the following by collecting like terms.

a $5xy^2 - 4xy^2$ **b** $3a^2b + 4ba^2$

c $8m^2n - 6nm^2 + m^2n$ **d** $7p^2q^2 - 2p^2q^2 - 4p^2q^2$

e $2x^2y - 4xy^2 + 5yx^2$ **f** $10rs^2 + 3rs^2 - 6r^2s$

g $x^2 - 7x - 3x^2$ **h** $a^2b - 4ab^2 + 3a^2b + b^2a$

i $10pq^2 - 2qp - 3pq^2 - 6pq$ **j** $12m^2n^2 - 2mn^2 - 4m^2n^2 + mn^2$

12, 13 | 12–14 | 13–15

PROBLEM-SOLVING

12 A farmer has x pigs and y chickens.

a Write an expression for the total number of heads.

b Write an expression for the total number of legs.

13 A rectangle's length is three times its width x metres. Write an expression for:

a the rectangle's perimeter

b the rectangle's area.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2B

PROBLEM-SOLVING

14 A right-angled triangle has side lengths $5x$ cm, $12x$ cm and $13x$ cm. Write an expression for:

a the triangle's perimeter

b the triangle's area.

15 The average (mean) mark on a test for 20 students is x. Another student who scores 75 in the test is added to the list. Write an expression for the new average (mean).

REASONING

16 | 16 | 16, 17

16 Decide if the following are always true for all real numbers.

a $a \times b = b \times a$ **b** $a \div b = b \div a$ **c** $a + b = b + a$

d $a - b = b - a$ **e** $a^2b = b^2a$ **f** $1 \div \frac{1}{a} = a \ (a \neq 0)$

17 The diagram shows the route taken by a salesperson who travels from A to D via B and C.



a If the salesperson then returns directly to A, write an expression (in simplest form) for the total distance travelled.

b If $y = x + 1$, write an expression for the total distance the salesperson travels in terms of x only. Simplify your expression.

c When $y = x + 1$, how much would the distance have been reduced by (in terms of x) if the salesperson had travelled directly from A to D and straight back to A?

ENRICHMENT

Higher powers — | — | 18

18 For this question, note this example: $\frac{2a^3}{4a} = \frac{2_1 \times a \times a \times \cancel{a}^1}{\cancel{2}^2 \times \cancel{a}^1}$

$= \frac{a^2}{2}$

Simplify these expressions with higher powers.

a $\frac{a^4}{a}$ **b** $\frac{3b^3}{9b}$ **c** $\frac{4ab^3}{12ab}$ **d** $\frac{6a^4b^2}{16a^3b}$ **e** $-\frac{2a^5}{3a^2}$ **f** $-\frac{8a^5}{20a^7}$

g $\frac{4a^3}{10a^8}$ **h** $\frac{3a^3b}{12ab^4}$ **i** $\frac{15a^4b^2}{5ab}$ **j** $\frac{28a^3b^5}{7a^4b^2}$ **k** $\frac{2a^5b^2}{6a^2b^3}$ **l** $-\frac{5a^3b^7}{10a^2b^{10}}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2C Expanding algebraic expressions

Interactive

Widgets

HOTsheets

Walkthroughs

A mental technique to find the product of 5 and 23 might be to find 5×20 and add 5×3 to give 115. This technique uses the distributive law over addition.

So $5 \times 23 = 5 \times (20 + 3)$

$= 5 \times 20 + 5 \times 3$

Since variables (or pronumerals) represent numbers, the same law applies for algebraic expressions.

Let's start: Rectangular distributions

This diagram shows two joined rectangles with the given dimensions.



- Find two different ways to write expressions for the combined area of the two rectangles.
- Compare your two expressions. Are they equivalent?

This diagram shows a rectangle of length x reduced by a length of 3.



- Find two different ways to write expressions for the remaining area (shaded).
- Compare your two expressions. Are they equivalent?

Examples of the distributive law can often be found in everyday tasks.

Key ideas

- The **distributive law** is used to expand and remove brackets.
  - A term on the outside of the brackets is multiplied by each term inside the brackets.

    $a(b+c) = ab + ac$ or $a(b-c) = ab - ac$

    $-a(b+c) = -ab - ac$ or $-a(b-c) = -ab + ac$
  - If the number in front of the bracket is negative, the sign of each of the terms inside the brackets will change when expanded.

    For example: $-2(x-3) = -2x + 6$ since $-2 \times x = -2x$ and $-2 \times (-3) = 6$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 7 Expanding simple expressions with brackets

Expand the following.

a $3(x+4)$ **b** $5(x-11)$ **c** $-2(x-5)$

SOLUTION	EXPLANATION
a $3(x+4) = 3x+12$	$3\times x = 3x$ and $3\times 4 = 12$
b $5(x-11) = 5x-55$	$5\times x = 5x$ and $5\times(-11) = -55$
c $-2(x-5) = -2x+10$	$-2\times x = -2x$ and $-2\times(-5) = +10$

Example 8 Expanding brackets and simplifying

Expand the following.

a $4(x+3y)$ **b** $-2x(4x-3)$

SOLUTION	EXPLANATION
a $4(x+3y) = 4\times x + 4\times 3y$ $= 4x+12y$	Multiply each term inside the brackets by 4. $4\times x = 4x$ and $4\times 3\times y = 12y$.
b $-2x(4x-3) = -2x\times 4x + (-2x)\times(-3)$ $= -8x^2+6x$	Each term inside the brackets is multiplied by $-2x$. $-2\times 4 = -8$, $x\times x = x^2$ and $-2\times(-3) = 6$

Example 9 Simplifying by removing brackets

Expand the following and collect like terms.

a $2-3(x-4)$ **b** $3(x+2y)-(3x+y)$

SOLUTION	EXPLANATION
a $2-3(x-4) = 2-(3x-12)$ $= 2-3x+12$ $= 14-3x$	$3(x-4) = 3x-12$. $-(3x-12) = -1(3x-12)$, so multiplying by negative 1 changes the sign of each term inside the brackets.
b $3(x+2y)-(3x+y)$ $= 3x+6y-3x-y$ $= 3x-3x+6y-y$ $= 5y$	$-(3x+y) = -1(3x+y) = -3x-y$. Collect like terms and simplify.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 2C

1–2 | 2(½) | —

UNDERSTANDING

1 This diagram shows two joined rectangles with the given dimensions.



- **a** Write an expression for the area of:
  - **i** the larger rectangle (x by 5)
  - **ii** the smaller rectangle (2 by 5)
- **b** Use your answers from part **a** to find the combined area of both rectangles.
- **c** Write an expression for the total side length of the side involving x.
- **d** Use your answer from part **c** to find the combined area of both rectangles.
- **e** Complete this statement: $5(x + 2) =$ _____ + _____

2 **a** Substitute the value $x = 5$ into these expressions.

i $-2(x + 3)$ **ii** $-2x + 6$

- **b** Do your answers from part **a** suggest that $-2(x + 3) = -2x + 6$? When expanded what should $-2(x + 3)$ equal?
- **c** Substitute the value $x = 10$ into these expressions.

i $-3(x - 1)$ **ii** $-3x - 3$

- **d** Do your answers from part **c** suggest that $-3(x - 1) = -3x - 3$? When expanded what should $-3(x - 1)$ equal?

3–6(½) | 3–7(½) | 3–7(½)

FLUENCY

Example 7a, Example 7b

3 Expand the following.

a $2(x + 3)$	**b** $5(x + 12)$	**c** $2(x - 7)$	**d** $7(x - 9)$
e $3(2 + x)$	**f** $7(3 - x)$	**g** $4(7 - x)$	**h** $2(x - 6)$

Example 7c

4 Expand the following.

a $-3(x + 2)$	**b** $-2(x + 11)$	**c** $-5(x - 3)$	**d** $-6(x - 6)$
e $-4(2 - x)$	**f** $-13(5 + x)$	**g** $-20(9 + x)$	**h** $-300(1 - x)$

Example 8

5 Expand the following.

a $2(a + b)$	**b** $5(a - 2)$	**c** $3(m - 4)$	**d** $-8(2x + 5)$
e $-3(4x + 5)$	**f** $-4x(x - 2y)$	**g** $-9t(2y - 3)$	**h** $a(3a + 4)$
i $d(2d - 5)$	**j** $-2b(3b - 5)$	**k** $2x(4x + 1)$	**l** $5y(1 - 3y)$

Example 9a

6 Expand the following and collect like terms.

a $3 + 2(x + 4)$	**b** $4 + 6(x - 3)$	**c** $2 + 5(3x - 1)$	**d** $5 + (3x - 4)$
e $3 + 4(x - 2)$	**f** $7 + 2(x - 3)$	**g** $2 - 3(x + 2)$	**h** $1 - 5(x + 4)$
i $5 - (x - 6)$	**j** $9 - (x - 3)$	**k** $5 - (3 + 2x)$	**l** $4 - (3x - 2)$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2C

Example 9b

FLUENCY

7 Expand the following and collect like terms.

a $2(x+3)+3(x+2)$ **b** $2(x-3)+2(x-1)$ **c** $3(2x+1)+5(x-1)$

d $4(3x+2)+5(x-3)$ **e** $-3(2x+1)+(2x-3)$ **f** $-2(x+2)+3(x-1)$

g $2(4x-3)-2(3x-1)$ **h** $-3(4x+3)-5(3x-1)$ **i** $-(x+3)-3(x+5)$

j $-2(2x-4)-3(3x+5)$ **k** $3(3x-1)-2(2-x)$ **l** $-4(5-x)-(2x-5)$

PROBLEM-SOLVING

8, 9 | 8–10 | 9–11

8 A rectangle's length is 4 more than its width, x. Find an expanded expression for its area.

9 Find the area of these basic shapes in expanded form. All angles at vertices are 90°.

a



b



c



d



e



f



10 Gary gets a bonus \$20 for every computer he sells over and above his quota of 10 per week. If he sells n computers in a week and $n > 10$, write an expression for Gary's bonus in that week (in expanded form).

11 Jill pays tax at 20c in the dollar for every dollar earned over \$10 000. If Jill earns \$$x$ and $x > 10\,000$, write an expression for Jill's tax in expanded form.

REASONING

12 | 12, 13 | 12, 13

12 Identify the errors in these expressions then write out the correct expansion.

a $2(x+6) = 2x+6$

b $x(x-4) = 2x-4x$

c $-3(x+4) = -3x+12$

d $-7(x-7) = -7x-49$

e $5-2(x-7) = 5-2x-14$
$= -9-2x$

f $4(x-2)-3(x+2) = 4x-8-3x+6$
$= x-2$

13 In Year 7 and 8 we explored how to use the distributive law to find products mentally.

For example: $7\times104 = 7\times(100+4)$
$= 7\times100+7\times4$
$= 728$

and

$4\times298 = 4\times(300-2)$
$= 4\times300-4\times2$
$= 1192$

Use the distributive law to evaluate these products mentally.

a 6×52 **b** 9×102 **c** 5×91 **d** 4×326

e 3×99 **f** 7×395 **g** 9×990 **h** 6×879

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

ENRICHMENT

14 A progressive income tax system increases the tax rate for higher incomes. Here is an example.

Income	Tax
0 – $20 000	$0
$20 001 – $50 000	$0 + 20% of income above $20 000
$50 001 – $100 000	a + 30% of income above $50 000
$100 000 –	b + 50% of income above $100 000

a Find the values of a and b in the above table.

b Find the tax payable for these incomes.

i $35 000

ii $72 000

iii $160 000

c Find an expression for the tax payable for an income of $\$x$ if:

i $0 \leq x \leq 20\,000$

ii $20\,000 < x \leq 50\,000$

iii $50\,000 < x \leq 100\,000$

iv $x > 100\,000$

d Check that you have fully expanded and simplified your expressions for part **c**. Add steps if required.

e Use your expressions from parts **c** and **d** to check your answers to part **b** by choosing a particular income amount and checking against the table above.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2D Solving linear equations

Interactive

Widgets

HOTsheets

Walkthroughs

A mathematical statement containing an equals sign, a left-hand side and a right-hand side is called an equation. $5 = 10 \div 2$, $3x = 9$, $x^2 + 1 = 10$ and $\frac{1}{x} = \frac{x}{5}$ are examples of equations. Linear equations can be written in the form $ax + b = c$ where the power of x is 1. $4x - 1 = 6$, $3 = 2(x + 1)$ and $\frac{5x}{3} = \frac{2x + 1}{4}$ are all linear equations. Equations are solved by finding the value of the variable (or pronumeral) that makes the equation true. This can be done by inspection for very simple linear equations (for example, if $3x = 15$ then $x = 5$ since $3 \times 5 = 15$). More complex linear equations can be solved through a series of steps where each step produces an equivalent equation.

Let's start: Why are they equivalent?

The following list of equations can be categorised into two groups. The equations in each group should be equivalent.

$5x = 20$	$2x - 1 = -3$	$x = 4$	$1 - x = -3$
$7x = -7$	$3 - 5x = -17$	$\frac{8x}{5} - \frac{3x}{5} = -1$	$x = -1$

- Discuss how you divided the equations into the two groups.
- How can you check to see if the equations in each group are equivalent?

Key ideas

- **Equivalent equations** are created by:
  - adding a number to or subtracting a number from both sides of the equation
  - multiplying or dividing both sides of the equation by the same number (not including 0).
- Solve a linear equation by creating equivalent equations using **inverse operations** (sometimes referred to as **backtracking**).
- The solution to an equation can be checked by substituting the solution into the original equation and checking that both sides are equal.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Solving simple linear equations

Solve each of the following equations.

a $2x + 3 = 4$ **b** $\frac{x}{4} - 3 = 7$ **c** $5 - 2x = 12$

d $\frac{2x}{3} + 5 = 7$ **e** $\frac{2x + 4}{9} = 2$

SOLUTION	EXPLANATION
a $2x + 3 = 4$	
$2x = 1$	Subtract 3 from both sides.
$x = \frac{1}{2}$	Divide both sides by 2.
Check: $2 \times \left(\frac{1}{2}\right) + 3 = 4$	Check the answer by substituting $x = \frac{1}{2}$ into the original equation.
b $\frac{x}{4} - 3 = 7$	
$\frac{x}{4} = 10$	Add 3 to both sides.
$x = 40$	Multiply both sides by 4.
Check: $\frac{(40)}{4} - 3 = 10 - 3 = 7$	Check the answer by substituting $x = 40$ into $\frac{x}{4} - 3$. Since this equals 7, $x = 40$ is the solution.
c $5 - 2x = 12$	
$-2x = 7$	Subtract 5 from both sides.
$x = -\frac{7}{2}$	Divide both sides by –2.
Check: $5 - 2 \times \left(-\frac{7}{2}\right) = 5 + 7 = 12$	Check the answer.
d $\frac{2x}{3} + 5 = 7$	
$\frac{2x}{3} = 2$	Subtract 5 from both sides first then multiply both sides by 3.
$2x = 6$	
$x = 3$	Divide both sides by 2.
Check: $\frac{2 \times (3)}{3} + 5 = 2 + 5 = 7$	Check the answer.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

e $\frac{2x+4}{9} = 2$

$2x + 4 = 18$ — Multiply both sides by 9 first to eliminate the fraction. Solve the remaining equation by subtracting 4 from both sides and then dividing both sides by 2.

$2x = 14$

$x = 7$

Check: $\frac{2\times(7)+4}{9} = \frac{18}{9} = 2$ — Check the answer.

Exercise 2D

1–2(½), 3 | 3 | —

UNDERSTANDING

1 Write down the value of x that is the solution to these equations. No written working is required.

a $3x = 9$ **b** $\frac{x}{4} = 10$ **c** $x + 7 = 12$ **d** $x - 7 = -1$

2 Use a 'guess and check' (trial and error) method to solve these equations. No written working is required.

a $2x + 1 = 7$ **b** $11x - 1 = 21$ **c** $4 - x = 2$ **d** $\frac{x}{3} + 1 = 5$

e $2 + \frac{x}{3} = 6$ **f** $3x - 1 = -16$ **g** $\frac{x+1}{7} = 1$ **h** $\frac{3x+2}{5} = 1$

3 Which of the following equations are equivalent to $3x = 12$?

a $3x + 1 = 13$ **b** $3x - 1 = 12$ **c** $12x = 12$ **d** $-3x = -12$

e $\frac{3x}{4} = 3$ **f** $x = 4$ **g** $\frac{3x}{5} = 10$ **h** $3x - x = 12 - x$

4–8(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 10a

4 Solve each of the following equations. Check your answers.

a $2x + 5 = 9$ **b** $5a + 6 = 11$ **c** $3m - 4 = 8$

d $2x - 4 = -6$ **e** $2n + 13 = 7$ **f** $2x + 5 = -7$

g $2b + 15 = 7$ **h** $3y - 2 = -13$ **i** $3a + 2 = 7$

j $4b + 7 = 25$ **k** $24x - 2 = 10$ **l** $6x - 5 = 3$

m $7y - 3 = -8$ **n** $2a + \frac{1}{2} = \frac{1}{4}$ **o** $5n - \frac{1}{4} = -1$

Example 10b

5 Solve each of the following equations.

a $\frac{x}{4} + 3 = 5$ **b** $\frac{x}{2} + 4 = 5$ **c** $\frac{b}{3} + 5 = 9$ **d** $\frac{t}{2} + 5 = 2$

e $\frac{a}{3} + 4 = 2$ **f** $\frac{y}{5} - 4 = 2$ **g** $\frac{x}{3} - 7 = -12$ **h** $\frac{s}{2} - 3 = -7$

i $\frac{x}{4} - 5 = -2$ **j** $\frac{m}{4} - 2 = 3$ **k** $1 - \frac{y}{5} = 2$ **l** $2 - \frac{x}{5} = 4$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2D

FLUENCY

Example 10c

6 Solve each of the following equations.

a $12 - 2x = 18$ **b** $2 - 7x = 9$ **c** $15 - 5x = 5$ **d** $3 - 2x = -13$

e $2 - 5x = 9$ **f** $4 - 7x = 23$ **g** $5 - 8x = 2$ **h** $-3 - 4x = -10$

Example 10d

7 Solve these equations.

a $\frac{2b}{3} = 6$ **b** $\frac{3x}{2} = 9$ **c** $\frac{4x}{3} = -9$ **d** $\frac{2x}{5} = -3$

e $\frac{3x}{4} = \frac{1}{2}$ **f** $\frac{5n}{4} = -\frac{1}{5}$ **g** $\frac{2x}{3} - 1 = 7$ **h** $\frac{3x}{4} - 2 = 7$

i $3 + \frac{2x}{3} = -3$ **j** $5 + \frac{3d}{2} = -7$ **k** $11 - \frac{3f}{2} = 2$ **l** $3 - \frac{4z}{3} = 5$

Example 10e

8 Solve each of the following equations. Check your answers.

a $\frac{x+1}{3} = 4$ **b** $\frac{x+4}{2} = 5$ **c** $\frac{4+y}{3} = -2$ **d** $\frac{6+b}{2} = -3$

e $\frac{1-a}{2} = 3$ **f** $\frac{5-x}{3} = 2$ **g** $\frac{3m-1}{5} = 4$ **h** $\frac{2x+2}{3} = 4$

i $\frac{7x-3}{3} = 9$ **j** $\frac{3b-6}{2} = 5$ **k** $\frac{4-2y}{6} = 3$ **l** $\frac{9-5t}{3} = -2$

PROBLEM-SOLVING

9 9 9(½)

9 For each of the following, write an equation and solve it to find the unknown value. Use x as the unknown value.

a If 8 is added to a certain number, the result is 34.

b Seven less than a certain number is 21.

c I think of a number, double it and add 4. The result is 10.

d I think of a number, halve it and subtract 4. The result is 10.

e Four less than three times a number is 20.

f A number is multiplied by 7 and the product is divided by 3. The final result is 8.

g Five Easter eggs are added to my initial collection of Easter eggs. I share them between myself and 2 friends and each person gets exactly four. How many were there initially?

h My weekly pay is increased by $200 per week. Half of my pay now goes to pay the rent and $100 to buy groceries. If this leaves me with $450, what was my original weekly pay?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2D

10 | 10 | 10, 11

REASONING

10 Describe the error made in each of these incorrect solutions.

a
$2x - 1 = 4$
$x - 1 = 2$
$x = 3$

b
$\frac{5x + 2}{3} = 7$
$\frac{5x}{3} = 5$
$5x = 15$
$x = 3$

c
$5 - x = 12$
$x = 7$

d
$\frac{x}{3} - 4 = 2$
$x - 4 = 6$
$x = 10$

11 An equation like $2(x + 3) = 8$ can be solved without expanding the brackets. The first step is to divide both sides by 2.

a Use this approach to solve these equations.

i $3(x - 1) = 12$ **ii** $4(x + 2) = -4$ **iii** $7(5x + 1) = 14$

iv $5(1 - x) = -10$ **v** $-2(3x + 1) = 3$ **vi** $-5(1 - 4x) = 1$

b By considering your solutions to the equations in part **a**, when do you think this method is most appropriate?

Changing the subject

— | — | 12

ENRICHMENT

12 Make a the subject of each of the following equations.

a $a - b = c$ **b** $2a + b = c$ **c** $c - ab = 2d$ **d** $b = \frac{a}{c} - d$

e $\frac{ab}{c} = -d$ **f** $\frac{2a}{b} = \frac{1}{c}$ **g** $\frac{2ab}{c} - 3 = -d$ **h** $b - \frac{ac}{2d} = 3$

i $\frac{a + b}{c} = d$ **j** $\frac{b - a}{c} = -d$ **k** $\frac{ad - 6c}{2b} = e$ **l** $\frac{d - 4ac}{e} = 3f$

$$a = \frac{c - d}{4b + 1}$$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2E Equations with brackets and pronumerals on both sides

Interactive

Widgets

HOTsheets

Walkthroughs

More complex linear equations may have pronumerals on both sides of the equation and/or brackets. Examples are $3x = 5x - 1$ or $4(x + 2) = 5x$. Brackets can be removed by expanding and equations with pronumerals on both sides can be solved by collecting like terms using addition and subtraction.

Solving problems in algebra (like many other procedures and puzzles) requires steps to be done in the right order.

Let's start: Steps in the wrong order

The steps to solve $3(2 - x) = -2(2x - 1)$ are listed here in the incorrect order.

$$3(2 - x) = -2(2x - 1)$$
$$x = -4$$
$$6 + x = 2$$
$$6 - 3x = -4x + 2$$

- Arrange them in the correct order working from top to bottom.
- By considering all the steps in the correct order, explain what has happened in each step.

Key ideas

- Equations with brackets can be solved by firstly expanding the brackets.
  For example: $3(x + 1) = 2$ becomes $3x + 3 = 2$.
- If an equation has pronumerals on both sides, collect to one side by adding or subtracting one of the terms.
  For example: $3x + 4 = 2x - 3$ becomes $x + 4 = -3$ by subtracting $2x$ from both sides.

Example 11 Solving equations with brackets and pronumerals on both sides

Solve each of the following equations.

a $2(3x - 4) = 11$
b $2(x + 3) - 4x = 8$
c $5x - 2 = 3x - 4$
d $3(2x + 4) = 8(x + 1)$

SOLUTION	EXPLANATION
a $2(3x - 4) = 11$	
$6x - 8 = 11$	Expand the brackets, $2(3x - 4) = 2 \times 3x + 2 \times (-4)$.
$6x = 19$	Add 8 to both sides then divide both sides by 6, leaving your answer in fraction form.
$x = \frac{19}{6}$ or $3\frac{1}{6}$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

b $2(x + 3) - 4x = 8$

$2x + 6 - 4x = 8$ — Expand the brackets and collect any like terms, i.e. $2x - 4x = -2x$.

$-2x + 6 = 8$

$-2x = 2$ — Subtract 6 from both sides.

$x = -1$ — Divide by -2.

c $5x - 2 = 3x - 4$

$2x - 2 = -4$ — Collect x terms on one side by subtracting $3x$ from both sides.

$2x = -2$

$x = -1$ — Add 2 to both sides and then divide both sides by 2.

d $3(2x + 4) = 8(x + 1)$

$6x + 12 = 8x + 8$ — Expand the brackets on each side.

$12 = 2x + 8$ — Subtract $6x$ from both sides, alternatively subtract $8x$ to end up with $-2x + 12 = 8$. (Subtracting $6x$ keeps the x-coefficient positive.)

$4 = 2x$

$2 = x$

$\therefore x = 2$ — Solve the equation and make x the subject.

Exercise 2E

1, 2 | 2 | —

UNDERSTANDING

1 Expand these expressions and simplify.

a $3(x - 4) + x$ **b** $2(1 - x) + 2x$ **c** $3(x - 1) + 2(x - 3)$

d $5(1 - 2x) - 2 + x$ **e** $2 - 3(3 - x)$ **f** $7(2 - x) - 5(x - 2)$

2 Show the next step only for the given equations and instructions.

a $2(x + 3) = 5$ (expand the brackets)

b $5 + 2(x - 1) = 7$ (expand the brackets)

c $3x + 1 = x - 6$ (subtract x from both sides)

d $4x - 3 = 2x + 1$ (subtract $2x$ from both sides)

3–5(½) | 3–6(½) | 3–6(½)

FLUENCY

Example 11a

3 Solve each of the following equations by first expanding the brackets.

a $2(x + 3) = 11$ **b** $5(a + 3) = 8$ **c** $3(m + 4) = 31$

d $5(y - 7) = -12$ **e** $4(p - 5) = -35$ **f** $2(k - 5) = 9$

g $4(5 - b) = 18$ **h** $2(1 - m) = 13$ **i** $5(3 - x) = 19$

j $7(2a + 1) = 8$ **k** $4(3x - 2) = 30$ **l** $3(3n - 2) = 0$

m $5(3 - 2x) = 6$ **n** $6(1 - 2y) = -8$ **o** $4(3 - 2a) = 13$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2E

FLUENCY

Example 11b

4 Expand and simplify then solve each of the following equations.

a $2(x + 4) + x = 14$
b $2(x - 3) - 3x = 4$
c $4(x - 1) + x - 1 = 0$
d $3(2x + 3) - 1 - 4x = 4$
e $3(x - 4) + 2(x + 1) = 15$
f $2(x + 1) - 3(x - 2) = 8$
g $6(x + 3) + 2x = 26$
h $3(x + 2) + 5x = 46$
i $3(2x - 3) + x = 12$
j $(3x + 1) + 3x = 19$

Example 11c

5 Solve each of the following equations.

a $5b = 4b + 1$
b $8a = 7a - 4$
c $4t = 10 - t$
d $3m - 8 = 2m$
e $5x - 3 = 4x + 5$
f $9a + 3 = 8a + 6$
g $12x - 3 = 10x + 5$
h $3y + 6 = 2 - y$
i $5m - 4 = 1 - 6m$

Example 11d

6 Solve each of the following equations.

a $5(x - 2) = 2x - 13$
b $3(a + 1) = a + 10$
c $3(y + 4) = y - 6$
d $2(x + 5) = x - 4$
e $5b - 4 = 6(b + 2)$
f $2(4m - 5) = 4m + 2$
g $3(2a - 3) = 5(a + 2)$
h $4(x - 3) = 3(3x + 1)$
i $3(x - 2) = 5(x + 4)$
j $3(n - 2) = 4(n + 5)$
k $2(a + 5) = -2(2a + 3)$
l $-4(x + 2) = 3(2x + 1)$

PROBLEM-SOLVING

7, 8 | 7, 8 | 8, 9

7 Using x for the unknown number, write down an equation then solve it to find the number.

a The product of 2 and 3 more than a number is 7.
b The product of 3 and 4 less than a number is -4.
c When 2 less than 3 lots of a number is doubled the result is 5.
d When 5 more than 2 lots of a number is tripled the result is 10.
e 2 more than 3 lots of a number is equivalent to 8 lots of the number.
f 2 more than 3 times the number is equivalent to 1 less than 5 times the number.
g 1 less than a doubled number is equivalent to 5 more than 3 lots of the number.

8 Since Tara started work her original hourly wage has been tripled, then decreased by $6. It is now to be doubled so that she gets $18 an hour. Write an equation and solve it to find Tara's original hourly wage.

9 At the start of lunch Jimmy and Jake each brought out a new bag of x marbles to play with their friends. By the end of lunch they were surprised to see they still had the same number as each other even though overall Jimmy had gained 5 marbles and Jake had ended up with two lots of 3 less than his original amount. How many marbles were originally in the bags?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

2E

10, 11 | 10, 11 | 10–12

REASONING

10 Consider the equation $3(x-2)=9$.
- **a** Solve the equation by firstly dividing both sides by 3.
- **b** Solve the equation by firstly expanding the brackets.
- **c** Which of the above two methods is preferable and why?

11 Consider the equation $3(x-2)=7$.
- **a** Solve the equation by firstly dividing both sides by 3.
- **b** Solve the equation by firstly expanding the brackets.
- **c** Which of the above two methods is preferable and why?

12 Consider the equation $3x+1=5x-7$.
- **a** Solve the equation by firstly subtracting $3x$ from both sides.
- **b** Solve the equation by firstly subtracting $5x$ from both sides.
- **c** Which method above do you prefer and why? Describe the differences.

Literal solutions with factorisation

— | — | 13

ENRICHMENT

13 Literal equations contain a variable (such as x) and other variables (or pronumerals) such as a, b and c. To solve such an equation for x, factorisation can be used as shown here.

$ax = bx + c$

$ax - bx = c$ Subtract bx from both sides

$x(a-b) = c$ Factorise by taking out x

$x = \frac{c}{a-b}$ Divide both sides by $(a-b)$

Note: $a \neq b$

Solve each of the following for x in terms of the other pronumerals by using factorisation.

- **a** $ax = bx + d$
- **b** $ax + 1 = bx + 3$
- **c** $5ax = bx + c$
- **d** $3ax + 1 = 4bx - 5$
- **e** $ax - bc = xb - ac$
- **f** $a(x-b) = x - b$
- **g** $ax - bx - c = d + bd$
- **h** $a(x+b) = b(x-c) - x$

Using a CAS calculator 2E: Solving equations

This activity is in the interactive textbook in the form of a printable PDF.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F Solving word problems

Interactive

Many types of problems can be solved by writing and solving linear equations. Often problems are expressed only in words. Reading and understanding the problem, defining a variable and writing an equation become important steps in solving the problem.

Widgets

HOTsheets

Walkthroughs

Let's start: Too much television?

Three friends, Rick, Kate and Sue compare how much television they watch in a week at home. Kate watches 3 times the amount of television of Rick and Sue watches 4 hours less television than Kate. In total they watch 45 hours of television. Find the number of hours of television watched by Rick.

- Let x hours be the number of hours of television watched by Rick.
- Write expressions for the number of hours of television watched by Kate and by Sue.
- Write an equation to represent the information above.
- Solve the equation.
- Answer the question in the original problem.

Key ideas

- To solve a **word problem** using algebra:
  - Read the problem and find out what the question is asking for.
  - Define a variable and write a statement such as: 'Let x be the number of ……' The variable is often what you have been asked to find.
  - Write an equation using your defined variable to show the relationship between the facts in the question.
  - Solve the equation.
  - Answer the question in words.

Example 12 Turning a word problem into an equation

Five less than a certain number is 9 less than three times the number. Write an equation and solve it to find the number.

SOLUTION	EXPLANATION
Let x be the number.	Define the unknown as a pronumeral.
$x - 5 = 3x - 9$	5 less than x is $x - 5$ and this equals 9 less than three times x, i.e. $3x - 9$.
$-5 = 2x - 9$	Subtract x from both sides and solve the equation.
$4 = 2x$	
$x = 2$	
The number is 2.	Write the answer in words.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Solving word problems

David and Mitch made 254 runs between them in a cricket match. If Mitch made 68 more runs than David, how many runs did each of them make?

SOLUTION	EXPLANATION
Let the number of runs for David be r.	Define the unknown value as a pronumeral.
Number of runs Mitch made is $r + 68$.	Write all other unknown values in terms of r.
$r + (r + 68) = 254$	Write an equation: number of runs for David + number of runs for Mitch = 254.
$2r + 68 = 254$	
$2r = 186$	Subtract 68 from both sides and then divide both sides by 2.
$r = 93$	
David made 93 runs and Mitch made $93 + 68 = 161$ runs.	Express the answer in words.

Exercise 2F

1 | 1(½) | —

UNDERSTANDING

Example 12

1 For each of the following examples, make x the unknown number and write an equation.

- **a** Three less than a certain number is 9 less than four times the number.
- **b** Seven is added to a number and the result is then multiplied by 3. The result is 9.
- **c** I think of a number, take away 9, then multiply the result by 4. This gives an answer of 12.
- **d** A number when doubled results in a number that is 5 more than the number itself.
- **e** Eight less than a certain number is 2 more than three times the number.

2–6 | 2–7 | 2, 4, 5, 7–9

FLUENCY

Example 13

2 Leonie and Emma scored 28 goals between them in a netball match. Leonie scored 8 more goals than Emma.

- **a** Define a variable for the number of goals scored by Emma.
- **b** Write the number of goals scored by Leonie in terms of the variable in part **a**.
- **c** Write an equation in terms of your variable to represent the problem.
- **d** Solve the equation in part **c** to find the unknown value.
- **e** How many goals did each of them score?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F

FLUENCY

3 A rectangle is four times as long as it is wide and its perimeter is 560 cm.
- **a** Define a variable for the unknown width.
- **b** Write an expression for the length in terms of your variable in part **a**.
- **c** Write an equation involving your variable to represent the problem. Draw and label a rectangle to help you.
- **d** Solve the equation in part **c**.
- **e** What is the length and width of the rectangle?

4 Toby rented a car for a total cost of $290. If the rental company charged $40 per day, plus a hiring fee of $50, for how many days did Toby rent the car?

5 Andrew walked a certain distance, and then ran twice as far as he walked. He then caught a bus for the last 2 km. If he travelled a total of 32 km, find how far Andrew walked and ran.

6 A prize of $1000 is divided between Adele and Benita so that Adele receives $280 more than Benita. How much did each person receive?

7 Kate is three times as old as her son. If Kate is 30 years older than her son, what are their ages?

8 A train station is between the towns Antville and Bugville. The station is four times as far from Bugville as it is from Antville. If the distance from Antville to Bugville is 95 km, how far is it from Antville to the station? *Hint:* draw a diagram to help you picture the problem.

9 Andrew, Brenda and Cammi all work part-time at a supermarket. Cammi earns $20 more than Andrew and Brenda earns $30 less than twice Andrew's wage. If their total combined wage is $400, find how much each of these workers earns.

10, 11, 13 | 10, 12, 13 | 10, 12–15

PROBLEM-SOLVING

10 Macy bought a total of 12 fiction and non-fiction books. The fiction books cost $12 each and the non-fiction books cost $25 each. If she paid $248 altogether, how many of each kind of book did she purchase? Define the number of non-fiction books bought in terms of the number of fiction books bought.

11 If I multiply my age in six years' time by three, the resulting age is my mother's age now. If my mother is currently 48 years old, how old am I?

12 Twelve years ago Eric's father was seven times as old as Eric was. If Eric's father is now 54 years old, how old is Eric now?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F

PROBLEM-SOLVING

13 In a yacht race the second leg was half the length of the first leg, the third leg was two-thirds of the length of the second leg, and the last leg was twice the length of the second leg. If the total distance was 153 km, find the length of each leg.

14 The Ace Bicycle Shop charges a flat fee of $4, plus $1 per hour, for the hire of a bicycle. The Best Bicycle Shop charges a flat fee of $8, plus 50 cents per hour. Connie and her friends hire three bicycles from Ace, and David and his brother hire two bicycles from Best. After how many hours will their hire costs be the same?

15 Car A left Melbourne for Adelaide at 11:00 am and travelled at an average speed of 70 km per hour.
Car B left Melbourne for Adelaide at 1:00 pm on the same day and travelled at an average speed of 90 km per hour. At what time will Car B catch Car A?

REASONING

16 | 16, 17 | 17, 18

16 Two paddocks in the shapes shown below are to be fenced with wire. If the same total amount of wire is used for each paddock, what are the dimensions of each paddock in metres?



17 Consecutive integers can be represented algebraically as x, $x + 1$, $x + 2$ etc.

a Find three consecutive numbers that add to 84.

b **i** Write three consecutive even numbers starting with x.

ii Find three consecutive even numbers that add to 18.

c **i** Write three consecutive odd numbers starting with x.

ii Find three consecutive odd numbers that add to 51.

d **i** Write three consecutive multiples of 3 starting with x.

ii Find three consecutive multiples of 3 that add to 81.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F

REASONING

18 Tedco produces a teddy bear which sells for $24. Each teddy bear costs the company $8 to manufacture and there is an initial start-up cost of $7200.

- **a** Write a rule for the total cost, $T, of producing x teddy bears.
- **b** If the cost of a particular production run was $9600, how many teddy bears were manufactured in that run?
- **c** If x teddy bears are sold, write a rule for the revenue, $R, received by the company.
- **d** How many teddy bears were sold if the revenue was $8400?
- **e** If they want to make an annual profit of $54 000, how many teddy bears do they need to sell?

Worded challenges	—	—	19–21

ENRICHMENT

19 An art curator was investigating the price trends of two art works that had the same initial value. The first painting, 'Green poles', doubled in value in the first year then lost $8000 in the second year. In the third year its value was three-quarters of the previous year.

The second painting, 'Orchids', added $10 000 to its value in the first year then the second year its value was only a third of the previous year. In the third year its value improved to double that of the previous year.

If the value of the paintings was the same in the third year, write an equation and solve it to find the initial value of each painting.



20 Julia drove to her holiday destination over a period of five days. On the first day she travels a certain distance, on the second day she travels half that distance, on the third day a third of that distance, on the fourth day one-quarter of the distance and on the fifth day one-fifth of the distance. If her destination was 1000 km away write an equation and solve it to find how far she travelled on the first day, to the nearest kilometre.

21 Anna King is x years old. Her brother Henry is two-thirds of her age and her sister Chloe is three times Henry's age. The twins who live next door are 5 years older than Anna. If the sum of the ages of the King children is equal to the sum of the ages of the twins, find the ages of all the children.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

2A **1** Write an algebraic expression for each of the following.

- **a** The number of tickets required for 5 boys, x girls and y adults
- **b** 15 less than the product of 4 and y
- **c** The sum of the squares of k and p
- **d** The square of the difference between m and n
- **e** The square root of 16 more than x

2A **2** Evaluate these expressions if $x = 4$ and $y = -2$.

a $x^2 - y^2$ **b** $5y - 3(x - y)$ **c** $\frac{x + y}{x}$ **d** $\frac{3xy}{2}$

2B **3** Simplify the following.

a $2a \times 7b$ **b** $5pq \times (-8p)$ **c** $\frac{12k^2}{3km}$ **d** $30xy^3 \div (-5xy)$

2B **4** Simplify the following by collecting like terms.

a $6xy + 7 - 4xy$ **b** $7 - 3mk + 4km + 4$

c $8xy - 3x - 3yx + 2y$ **d** $a^2b + ba + b^2a - ab + b$

2C **5** Expand the following.

a $4(a + 7)$ **b** $-3x(2x - 5)$

2C **6** Expand the following and collect like terms.

a $10 - 3(a - 2)$ **b** $4(2x + y) - 3(x + 2y)$

2D **7** Solve each of the following equations.

a $3x - 7 = 5$ **b** $\frac{a}{3} - 5 = 2$ **c** $9 - 2p = 16$ **d** $5 - \frac{x}{3} = 7$

e $\frac{3t}{5} - 4 = 8$ **f** $2k - \frac{2}{3} = \frac{1}{6}$ **g** $8 - \frac{2x}{3} = 14$ **h** $\frac{3k - 6}{3} = 5$

2E **8** Solve each of the following equations.

a $3(x - 4) = 7$ **b** $4(3a + 1) - 3a = 31$

c $7m - 4 = 3m - 12$ **d** $3(2y + 1) = 8(y - 2)$

2F **9** For each of the following examples, make x the unknown number and write an equation.

- **a** Five is added to a number and the result is then multiplied by 2. The result is 14.
- **b** Nine less than a certain number is 6 more than four times the number.

2F **10** If I multiply my age in five years' time by four, the resulting age is my grandfather's age now. If my grandfather is currently 88 years old, set up and solve an equation to determine how old I am now.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2G Inequalities

Interactive

Widgets

HOTsheets

Walkthroughs

An inequality (or inequation) is a mathematical statement which uses a $<$, $\leq$, $>$ or $\geq$ sign. Some examples of inequalities include:

$$2 < 6, \qquad 5 \geq -1, \qquad 3x + 1 \leq 7 \quad \text{and} \quad 2x + \frac{1}{3} > \frac{x}{4}.$$

Inequalities can represent an infinite set of numbers. For example, the inequality $2x < 6$ means that $x < 3$ and this is the infinite set of all real numbers less than 3.

Let's start: Infinite solutions

Greg, Kevin and Greta think that they all have a correct solution to the equation

$$4x - 1 \geq x + 6$$

Greg says $x = 4$ is a solution.

Kevin says $x = 10$ is a solution.

Greta says $x = 100$ is a solution.

- Use substitution to show that they are all correct.
- Can you find the smallest whole number which is a solution to the inequality?
- Can you find the smallest number (including fractions) which satisfies the inequality? What method leads you to your answer?

Key ideas

- **Inequalities** can be illustrated using a number line because a line represents an infinite number of points.
  - Use an **open circle** when showing $>$ (greater than) or $<$ (less than).

    For example: $x > 1$

    

    $x < 1$

    

  - Use a **closed circle** when showing $\geq$ (greater than or equal to) or $\leq$ (less than or equal to).

    For example: $x \geq 1$

    

    $x \leq 1$

    

- A **set** of numbers may have both an upper and lower bound.

  For example: $-2 < x \leq 3$

  

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Linear inequalities can be solved in a similar way to linear equations.
  - All the numbers that satisfy an inequality are called a **solution set**.
  - If we multiply or divide both sides of an inequality by a negative number, the inequality sign is reversed.
    For example: $5 < 8$ but $-5 > -8$ so if $-x > 1$ then $x < -1$.
  - If we swap the sides of an inequality, then the inequality sign is reversed.
    For example: $3 < 7$ but $7 > 3$ so if $2 > x$ then $x < 2$.

Example 14 Representing inequalities on a number line

Show each of the following examples on a number line:

a x is less than 6 ($x < 6$)

b x is greater than or equal to 2 ($x \geq 2$)

c x is greater than -2 but less than or equal to 3 ($-2 < x \leq 3$).

SOLUTION	EXPLANATION
a 	An open circle is used to indicate that 6 is not included.
b 	A closed circle is used to indicate that 2 is included.
c 	An open circle is used to indicate that -2 is not included and a closed circle is used to indicate that 3 is included.

Example 15 Solving inequalities

Find the solution set for each of the following inequalities.

a $x - 3 < 7$ **b** $5 - 2x > 3$ **c** $\frac{d}{11} - 3 \geq -11$ **d** $2a + 7 \leq 6a + 3$

SOLUTION	EXPLANATION
a $x - 3 < 7$	
$x < 10$	Add 3 to both sides

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $5 - 2x > 3$

$-2x > -2$ Subtract 5 from both sides.

$x < 1$ Divide both sides by –2, and reverse the inequality sign.

c $\frac{d}{4} - 3 \geq -11$

$\frac{d}{4} \geq -8$ Add 3 to both sides.

$d \geq -32$ Multiply both sides by 4; the inequality sign does not change.

d $2a + 7 \leq 6a + 3$

$7 \leq 4a + 3$ Gather pronumerals on one side by subtracting $2a$ from both sides.

$4 \leq 4a$

$1 \leq a$ Subtract 3 from both sides and then divide both sides by 4.

$a \geq 1$ Place the variable a on the left and reverse the inequality.

Exercise 2G

1, 2(½) | 2(½) | —

UNDERSTANDING

1 Insert the symbol < or > to make each statement true.

a 3 ___ 2 **b** –1 __ 4 **c** –7 __ –3 **d** 5 __ –50

Example 14

2 Show each of the following inequalities on a number line.

a $x > 2$ **b** $x \geq 1$ **c** $x \leq 4$ **d** $x < -2$

e $x \geq -1$ **f** $x < -8$ **g** $-1 < x < 1$ **h** $-2 \leq x \leq 2$

i $0 \leq x \leq 3$ **j** $2 \leq x \leq 5$ **k** $-3 < x \leq 4$ **l** $-6 \leq x < -2$

3–6(½) | 3–7(½) | 3–7(½)

FLUENCY

Example 15a

3 Find the solution set for each of the following inequalities.

a $x + 5 < 8$ **b** $b - 2 > 3$ **c** $y - 8 > -2$ **d** $-12 + m < -7$

e $5x \geq 15$ **f** $4t > -20$ **g** $\frac{x}{3} \geq 4$ **h** $y + 10 \geq 0$

i $3m - 7 < 11$ **j** $4a + 6 \geq 12$ **k** $7x - 5 < 2$ **l** $2x - 7 > 9$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2G

FLUENCY

Example 15b

4 Find the solution set for each of the following inequalities.

a $4 - 3x > -8$ **b** $2 - 4n \geq 6$ **c** $4 - 5x \leq 1$

d $7 - a \leq 3$ **e** $5 - x \leq 11$ **f** $7 - x \leq -3$

g $-2x - 3 > 9$ **h** $-4t + 2 \geq 10$ **i** $-6m - 14 < 15$

Example 15c

5 Find the solution set for each of the following inequalities.

a $\frac{x}{2} - 5 \leq 3$ **b** $3 - \frac{x}{9} \geq 4$ **c** $\frac{2x}{5} \leq 8$

d $\frac{2x + 6}{7} < 4$ **e** $\frac{3x - 4}{2} > -6$ **f** $\frac{1 - 7x}{5} \leq 3$

6 Solve each of the following inequalities.

a $4(x + 2) < 12$ **b** $-3(a + 5) > 9$ **c** $5(3 - x) \geq 25$

d $2(3 - x) > 1$ **e** $5(y + 2) < -6$ **f** $-7(1 - x) < -11$

Example 15d

7 Find the solution set for each of the following inequalities.

a $2x + 9 \leq 6x - 1$ **b** $6t + 2 > t - 1$ **c** $7y + 4 \leq 7 - y$

d $3a - 2 < 4 - 2a$ **e** $1 - 3m \geq 7 - 4m$ **f** $7 - 5b > -4 - 3b$

PROBLEM-SOLVING

8–10 9–11 10–12

8 Wendy is x years old and Jay is 6 years younger. The sum of their ages is less than 30. Write an inequality involving x and solve it. What can you say about Wendy's age?

9 The perimeter of a particular rectangle needs to be less than 50 cm. If the length of the rectangle is 12 cm and the width is w cm, write an inequality involving w and solve it. What width does the rectangle need to be?



10 How many integers satisfy both of the given equations?

a $2x + 1 \leq 5$ and $5 - 2x \leq 5$ **b** $7 - 3x > 10$ and $5x + 13 > -5$

c $\frac{x + 1}{3} \geq -2$ and $2 - \frac{x}{3} > 3$ **d** $\frac{5x + 1}{6} < 2$ and $\frac{x}{3} < 2x - 7$

11 The width of a rectangular area is 10 m and its height is $(2x - 4)$ m. If the area is less than 80 m^2, what are the possible integer values for x?

12 Two car rental companies have the following payment plans:
Carz: \$90 per week and 15c per kilometre
Renta: \$110 per week and 10c per kilometre
What is the maximum whole number of kilometres that can be travelled in one week with Carz if it is to cost less than it would with Renta?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

13 13, 14 14, 15 **2G**

REASONING

13 **a** Consider the inequality $2 > x$.

i List 5 values of x between -1 and 2 which make the inequality true.

ii What must be true about all the values of x if the inequality is true?

b Consider the inequality $-x < 5$.

i List 5 values of x which make the inequality true.

ii What must be true about all the values of x if the inequality is true.

c Complete these statements.

i If $a > x$ then x __ __

ii If $-x < a$ then x __ __

14 Consider the equation $9 - 2x > 3$.

a Solve the equation by firstly adding $2x$ to both sides then solve for x.

b Solve the equation by firstly subtracting 9 from both sides.

c What did you have to remember to do in part **b** to ensure that the answer is the same as in part **a**?

15 Combine all your knowledge from this chapter so far to solve these inequalities.

a $\frac{2(x+1)}{3} > x + 5$

b $2x + 3 \geq \frac{x-6}{3}$

c $\frac{2-3x}{2} < 2x - 1$

d $\frac{4(2x-1)}{3} \leq x + 3$

e $1 - x > \frac{7(2-3x)}{4}$

f $2(3 - 2x) \leq 4x$

Literal inequalities

— — 16

ENRICHMENT

16 Given a, b, c and d are positive numbers (such that $1 < a < b$), solve each of the following for x.

a $ax - b > -c$

b $b - x \leq a$

c $\frac{x}{a} - b \leq c$

d $\frac{bx}{c} \leq a$

e $\frac{ax+b}{c} < d$

f $\frac{b-2x}{c} \leq d$

g $a(x + b) < c$

h $\frac{ax-b}{c} > -d$

i $a(b - x) > c$

j $ax + b \leq x - c$

k $ax + b > bx - 1$

l $b - ax \leq c - bx$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2H Using formulas

A formula (or rule) is an equation that relates two or more variables. You can find the value of one of the variables if you are given the value of all others. Some common formulas contain squares, square roots, cubes and cube roots. The following are some examples of formulas.

- $A = \pi r^2$ is the formula for finding the area, A, of a circle given its radius, r.
- $F = \frac{9}{5}C + 32$ is the formula for converting degrees Celsius, C, to degrees Fahrenheit, F.
- $d = vt$ is the formula for finding the distance, d, given the velocity, v, and time, t.

A, F and d are said to be the subjects of the formulas given above.

Let's start: Common formulas

As a class group, try to list at least 10 formulas that you know.

- Write down the formulas and describe what each variable represents.
- Which variable is the subject of each formula?

Key ideas

- The **subject** of a **formula** is a variable that usually sits on its own on the left-hand side. For example, the C in $C = 2\pi r$ is the subject of the formula.
- A variable in a formula can be evaluated by substituting numbers for all other variables.
- A formula can be **transposed** (rearranged) to make another variable the subject.
  $C = 2\pi r$ can be transposed to give $r = \frac{C}{2\pi}$
  - To transpose a formula use similar steps as you would for solving an equation, since variables represent numbers.
- Note that $\sqrt{a^2} = a$ if $a \geq 0$ and $\sqrt{a^2 + b^2} \neq a + b$ provided a or b is not zero.

Example 16 Substituting values into formulas

Substitute the given values into the formula to evaluate the subject.

a $S = \frac{a}{1-r}$, when $a = 3$ and $r = 0.4$ **b** $E = \frac{1}{2}mv^2$, when $m = 4$ and $v = 5$

SOLUTION	EXPLANATION
a $S = \frac{a}{1-r}$	
$S = \frac{3}{1-0.4}$	Substitute $a = 3$ and $r = 0.4$ and evaluate.
$= \frac{3}{0.6}$	
$= 5$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $E = \frac{1}{2}mv^2$

$E = \frac{1}{2} \times 4 \times 5^2$

$= \frac{1}{2} \times 4 \times 25$

$= 50$

Substitute $m = 4$ and $v = 5$ and evaluate.
Note: square the value of v before multiplying by the value of m.

Example 17 Finding the unknown value in a formula

The area of a trapezium is given by $A = \frac{1}{2}(a + b)h$. Substitute $A = 12$, $a = 5$ and $h = 4$ then find the value of b.

SOLUTION

$A = \frac{1}{2}(a + b)h$

$12 = \frac{1}{2} \times (5 + b) \times 4$

$12 = 2(5 + b)$

$6 = 5 + b$

$b = 1$

EXPLANATION

Write the formula and substitute the given values of A, a and h. Then solve for b.
$\frac{1}{2} \times 4 = 2$ and divide both sides by 2 since 2 is a factor of 12. Alternatively, you can expand the brackets.

Example 18 Transposing formulas

Transpose each of the following to make b the subject.

a $c = a(x + b)$ **b** $c = \sqrt{a^2 + b^2}$ $(b > 0)$

SOLUTION

a $c = a(x + b)$

$\frac{c}{a} = x + b$

$\frac{c}{a} - x = b$

$b = \frac{c}{a} - x \quad \left(\text{or } b = \frac{c - ax}{a}\right)$

EXPLANATION

Divide both sides by a.

Subtract x from both sides.

Make b the subject on the left side. An alternative answer has a common denominator, which will also be the answer format if you expand the brackets first.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $c = \sqrt{a^2 + b^2}$ $(b > 0)$

$c^2 = a^2 + b^2$	Square both sides to remove the square root.
$c^2 - a^2 = b^2$	Subtract a^2 from both sides.
$b^2 = c^2 - a^2$	Make b^2 the subject.
$b = \sqrt{c^2 - a^2}$	Take the square root of both sides, $b = \sqrt{c^2 - a^2}$ as b is positive.

Exercise 2H

1, 2(½) | 2(½) | —

UNDERSTANDING

1 State the letter which is the subject of these formulas.

a $A = \frac{1}{2}bh$ **b** $D = b^2 - 4ac$

c $M = \frac{a+b}{2}$ **d** $A = \pi r^2$

Example 16

2 Substitute the given values into each of the following formulas to evaluate the subject. Round to two decimal places where appropriate.

a $A = bh$, when $b = 3$ and $h = 7$ **b** $F = ma$, when $m = 4$ and $a = 6$

c $m = \frac{a+b}{4}$, when $a = 14$ and $b = -6$ **d** $t = \frac{d}{v}$, when $d = 18$ and $v = 3$

e $A = \pi r^2$, when $\pi = 3.14$ and $r = 12$ **f** $V = \frac{4}{3}\pi r^3$, when $\pi = 3.14$ and $r = 2$

g $c = \sqrt{a^2 + b^2}$, when $a = 12$ and $b = 22$ **h** $Q = \sqrt{2gh}$, when $g = 9.8$ and $h = 11.4$

i $I = \frac{MR^2}{2}$, when $M = 12.2$ and $R = 6.4$ **j** $x = ut + \frac{1}{2}at^2$, when $u = 0$, $t = 4$ and $a = 10$

3–4(½) | 3–4(½) | 3–4(½)

FLUENCY

Example 17

3 Substitute the given values into each of the following formulas then solve the equations to determine the value of the unknown pronumeral each time. Round to two decimal places where appropriate.

a $m = \frac{F}{a}$, when $m = 12$ and $a = 3$

b $A = lw$, when $A = 30$ and $l = 6$

c $A = \frac{1}{2}(a + b)h$, when $A = 64$, $b = 12$ and $h = 4$

d $C = 2\pi r$, when $C = 26$ and $\pi = 3.14$

e $S = 2\pi r^2$, when $S = 72$ and $\pi = 3.14$

f $v^2 = u^2 + 2as$, when $v = 22$, $u = 6$ and $a = 12$

g $m = \sqrt{\frac{x}{y}}$, when $m = 8$ and $x = 4$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2H

FLUENCY

Example 18

4 Transpose each of the following formulas to make the pronumeral shown in brackets the subject.

a $A = 2\pi rh$ $[r]$

b $I = \dfrac{Prt}{100}$ $[r]$

c $p = m(x + n)$ $[n]$

d $d = \dfrac{a + bx}{c}$ $[x]$

e $V = \pi r^2 h \quad (r > 0)$ $[r]$

f $P = \dfrac{v^2}{R} \quad (v > 0)$ $[v]$

g $S = 2\pi rh + 2\pi r^2$ $[h]$

h $A = (p + q)^2$ $[p]$

i $T = 2\pi\sqrt{\dfrac{l}{g}}$ $[g]$

j $\sqrt{A} + B = 4C$ $[A]$

5, 6 | 5–7 | 6–8

PROBLEM-SOLVING

5 The formula $s = \dfrac{d}{t}$ gives the speed s km/h of a car which has travelled a distance of d km in t hours.

a Find the speed of a car which has travelled 400 km in 4.5 hours. Round to two decimal places.

b **i** Transpose the formula $s = \dfrac{d}{t}$ to make d the subject.

ii Find the distance covered if a car travels at 75 km/h for 3.8 hours.

6 The formula $F = \dfrac{9}{5}C + 32$ converts degrees Celsius, C, to degrees Fahrenheit, F.

a Find what each of the following temperatures is in degrees Fahrenheit.

i 100°C **ii** 38°C

b Transpose the formula to make C the subject.

c Calculate what each of the following temperatures is in degrees Celsius. Round to one decimal place where necessary.

i 14°F **ii** 98°F

7 The velocity, v m/s, of an object is described by the rule $v = u + at$, where u is the initial velocity in m/s, a is the acceleration in m/s^2 and t is the time in seconds.

a Find the velocity after 3 seconds if the initial velocity is 5 m/s and the acceleration is 10 m/s^2.

b Find the time taken for a body to reach a velocity of 20 m/s if its acceleration is 4 m/s^2 and its initial velocity is 12 m/s.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2H

PROBLEM-SOLVING

8 The volume of water (V litres) in a tank is given by $V = 4000 - 0.1t$ where t is the time in seconds after a tap is turned on.

a Over time, does the water volume increase or decrease according to the formula?

b Find the volume after 2 minutes.

c Find the time it takes for the volume to reach 1500 litres. Round to the nearest minute.

d How long, to the nearest minute, does it take to completely empty the tank?

9	9, 10	9(½), 10

REASONING

9 Write a formula for the following situations. Make the first listed variable the subject.

a $\$D$ given c cents

b d cm given e metres

c The discounted price $\$D$ which is 30% off the marked price $\$M$.

d The value of an investment $\$V$ which is 15% more than the initial amount $\$P$.

e The cost $\$C$ of hiring a car at \$50 upfront plus \$18 per hour for t hours.

f The distance d km remaining in a 42 km marathon after t hours if the running speed is 14 km/h.

g The cost $\$C$ of a bottle of soft drink if b bottles cost $\$c$.

10 Write a formula for the value of a in these diagrams.

a



Perimeter P

b



c



d



e



Note: $a^2 + b^2 = c^2$

f



$Area = A$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Basketball formulas — — 11

2H

ENRICHMENT

11 The formula $T = 3x + 2y + f$ can be used to calculate the total number of points made in a basketball game where:

x = number of three-point goals
y = number of two-point goals
f = number of free throws made
T = total number of points

a Find the total number of points for a game where 12 three-point goals, 15 two-point goals and 7 free throws were made.

b Find the number of three-point goals made if the total number of points was 36 with 5 two-point goals made and 5 free throws made.

c The formula $V = \left(p + \frac{3r}{2} + 2a + \frac{3s}{2} + 2b\right) - \frac{1.5t + 2f + m - o}{g}$ can be used to calculate the value, V, of a basketball player where:

p = points earned
r = number of rebounds
a = number of assists
s = number of steals
b = number of blocks
t = number of turnovers
f = number of personal fouls
m = number of missed shots
o = number of offensive rebounds
g = number of games played

Calculate the value of a player with 350 points earned, 2 rebounds, 14 assists, 25 steals, 32 blocks, 28 turnovers, 14 personal fouls, 24 missed shots, 32 offensive rebounds and 10 games.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

21 Simultaneous equations: substitution EXTENDING

A linear equation with one unknown has one unique solution. For example, $x = 2$ is the only value of x that makes the equation $2x + 3 = 7$ true.

The linear equation $2x + 3y = 12$ has two unknowns and it has an infinite number of solutions. Each solution is a pair of x and y values that makes the equation true, for example $x = 0$ and $y = 4$ or $x = 3$ and $y = 2$ or $x = 4\frac{1}{2}$ and $y = 1$.

However, if we are told that $2x + 3y = 12$ and also that $y = 2x - 1$, we can find a single solution that satisfies both equations. Equations like this are called simultaneous linear equations, because we can find a pair of x and y values that satisfy both equations at the same time (simultaneously).

A share trader examining computer models of financial data, which can involve finding values that satisfy two equations simultaneously.

Let's start: Multiple solutions

There is more than one pair of numbers x and y which satisfy the equation $x - 2y = 5$.

- Write down at least 5 pairs (x, y) which make the equation true.

A second equation is $y = x - 8$.

- Do any of your pairs that make the first equation true, also make the second equation true? If not, can you find the special pair of numbers that satisfies both equations simultaneously?

Key ideas

- An algebraic method called **substitution** can be used to solve **simultaneous equations**. It is used when at least one of the equations has a single variable as the subject. For example, y is the subject in the equation $y = 3x + 1$.
- To solve simultaneous equations using substitution:
  1. Substitute one equation into the other, using brackets.
  2. Solve for the remaining variable.
  3. Substitute to find the value of the second variable.

$2x + 3y = 8$ and $y = x + 1$

$2x + 3(x + 1) = 8$

$2x + 3x + 3 = 8$

$5x + 3 = 8$

$5x = 5$

$x = 1$

$\therefore\ y = (1) + 1 = 2$

Example 19 Solving simultaneous equations using substitution

Solve each of the following pairs of simultaneous equations by using substitution.

a $x + y = 10$
$y = 4x$

b $4x - y = 6$
$y = 2x - 4$

c $3x + 2y = 19$
$y = 2x - 8$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
a $x + y = 10$ (1)	Number the equations for reference.
$y = 4x$ (2)	
$x + (4x) = 10$	Substitute $y = 4x$ into (1).
$5x = 10$	Combine like terms and solve for x.
$x = 2$	
From (2) $y = 4x$	
$= 4 \times (2)$	Substitute $x = 2$ into (2) to find the value of y.
$= 8$	
$\therefore x = 2, y = 8$	
Check: $2 + 8 = 10$ and $8 = 4 \times 2$	Check answer by substituting $x = 2$ and $y = 8$ into (1) and (2).
b $4x - y = 6$ (1)	
$y = 2x - 4$ (2)	
$4x - (2x - 4) = 6$	Substitute $y = 2x - 4$ into (1) using brackets.
$4x - 2x + 4 = 6$	Use the distributive law and solve for x.
$2x + 4 = 6$	$-(2x - 4) = -1(2x - 4)$
$2x = 2$	$= -1 \times 2x - 1 \times (-4)$
$x = 1$	$= -2x + 4$
From (2) $y = 2x - 4$	
$= 2 \times (1) - 4$	Substitute $x = 1$ into (2) to find the value of y.
$= -2$	
$\therefore x = 1, y = -2$	
Check: $4 + 2 = 6$ and $-2 = 2 \times 1 - 4$	Check: substitute $x = 1$ and $y = -2$ into (1) and (2).
c $3x + 2y = 19$ (1)	
$y = 2x - 8$ (2)	
$3x + 2(2x - 8) = 19$	Substitute $y = 2x - 8$ into (1).
$3x + 4x - 16 = 19$	Use the distributive law and solve for x.
$7x - 16 = 19$	
$7x = 35$	
$x = 5$	
From (2) $y = 2x - 8$	
$= 2 \times (5) - 8$	Substitute $x = 5$ into (2) to find the value of y.
$= 2$	
$\therefore x = 5, y = 2$	
Check: $3 \times 5 + 2 \times 2 = 19$ and $2 = 2 \times 5 - 8$	Check: substitute $x = 5$ and $y = 2$ into (1) and (2).

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 2I

1–3 | 2, 3(½) | —

UNDERSTANDING

1 Find the value of x or y by substituting the known value.

a $y = 2x - 3 \quad (x = 4)$ **b** $x = 5 - 2y \quad (y = 4)$ **c** $2x + 4y = 8 \quad (y = -3)$

2 Choose the correct option.

a When substituting $y = 2x - 1$ into $3x + 2y = 5$ the second equation becomes

A $3x + 2(2x - 1) = 5$ **B** $3(2x - 1) + 2y = 5$ **C** $3x + 2y = 2x - 1$

b When substituting $x = 1 - 3y$ into $5x - y = 6$ the second equation becomes

A $1 - 3x - y = 6$ **B** $5(1 - 3y) = 6$ **C** $5(1 - 3y) - y = 6$

3 Check whether $x = -2$ and $y = 2$ is a solution to each of the following pairs of simultaneous equations.

a $x + y = 0$ and $x - y = -4$ **b** $x - 2y = -6$ and $2x + y = 0$

c $3x + 4y = -2$ and $x = -3y - 4$ **d** $2x + y = -2$ and $x = 4y - 10$

4–5(½) | 4–5(½), 6 | 4–6(½)

FLUENCY

Example 19a

4 Solve each of the following pairs of simultaneous equations by using substitution.

a $x + y = 3$, $y = 2x$ **b** $x + y = 6$, $x = 5y$ **c** $x + 5y = 8$, $y = 3x$

d $x - 5y = 3$, $x = 2y$ **e** $3x + 2y = 18$, $y = 3x$ **f** $x + 2y = 15$, $y = -3x$

Example 19b

5 Solve each of the following pairs of simultaneous equations by using substitution.

a $x + y = 12$, $y = x + 6$ **b** $2x + y = 1$, $y = x + 4$ **c** $5x + y = 5$, $y = 1 - x$

d $3x - y = 7$, $y = x + 5$ **e** $3x - y = 9$, $y = x - 1$ **f** $x + 2y = 6$, $x = 9 - y$

g $y - x = 14$, $x = 4y - 2$ **h** $3x + y = 4$, $y = 2 - 4x$ **i** $4x - y = 12$, $y = 8 - 6x$

Example 19c

6 Solve each of the following pairs of simultaneous equations by using substitution.

a $3x + 2y = 8$, $y = 4x - 7$ **b** $2x + 3y = 11$, $y = 2x + 1$ **c** $4x + y = 4$, $x = 2y - 8$

d $2x + 5y = -4$, $y = x - 5$ **e** $2x - 3y = 5$, $x = 5 - y$ **f** $3x + 2y = 5$, $y = 3 - x$

7, 8 | 7, 8 | 8, 9

PROBLEM-SOLVING

7 The sum of two numbers is 48 and the larger number is 14 more than the smaller number. Write two equations and solve them to find the two numbers.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

PROBLEM-SOLVING

8 The combined mass of two trucks is 29 tonnes. The heavier truck is 1 tonne less than twice the mass of the smaller truck. Write two equations and solve them to find the mass of each truck.

9 The perimeter of a rectangle is 11 cm and the length is 3 cm more than half the width. Find the dimensions of the rectangle.

10	10	10, 11

REASONING

10 One of the common errors when applying the method of substitution is made in this working. Find the error and describe how to avoid it.

Solve $y = 3x - 1$ and $x - y = 7$.

$x - 3x - 1 = 7$ substituting $y = 3x - 1$ into $x - y = 7$

$-2x - 1 = 7$

$-2x = 8$

$x = -4$

11 If both equations have the same variable as the subject, substitution is still possible. For example, solve $y = 3x - 1$ . . . (1) and $y = 2 - x$ . . . (2)

Substitute (1) into (2)

$3x - 1 = 2 - x$

$4x = 3$

$x = \frac{3}{4}$ and $y = \frac{5}{4}$

Use this method to solve these simultaneous equations.

a $y = 4x + 1$
$y = 3 - 2x$

b $y = 3 - 4x$
$y = 2x + 8$

c $y = \frac{1}{2}x + 4$
$y = \frac{x + 1}{3}$

ENRICHMENT

Literally challenging | — | — | 12

12 Use substitution to solve each of the following pairs of simultaneous equations for x and y in terms of a and b.

a $ax + y = b$
$y = bx$

b $ax + by = b$
$x = by$

c $x + y = a$
$x = y - b$

d $ax - by = a$
$y = x - a$

e $ax - y = a$
$y = bx + a$

f $ax - by = 2a$
$x = y - b$

Using a CAS calculator 2I: Solving simultaneous equations
This activity is in the interactive textbook in the form of a printable PDF.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

2J Simultaneous equations: elimination EXTENDING

Interactive

Another method used to solve simultaneous linear equations is called elimination. This involves the addition or subtraction of the two equations to eliminate one of the variables. We can then solve for the remaining variable and substitute to find the value of the second variable.

Widgets

HOTsheets

Walkthroughs

Let's start: To add or subtract?

To use the method of elimination you need to decide if using addition or using subtraction will eliminate one of the variables.

Decide if the terms in these pairs should be added or subtracted to give the result of 0.

- $3x$ and $3x$
- $-x$ and x
- $2y$ and $-2y$
- $-7y$ and $-7y$

Describe under what circumstances addition or subtraction should be used to eliminate a pair of terms.

Key ideas

- **Elimination** involves the addition or subtraction of two equations to remove one variable.
- Elimination is often used when both equations are of the form $ax + by = d$ or $ax + by + c = 0$.
- Add equations to eliminate terms of opposite sign:

$$\begin{array}{rl} & 3x - y = 4 \\ + & 5x + y = 4 \\ \hline & 8x \quad\; = 8 \end{array}$$

- Subtract equations to eliminate terms of the same sign:

$$\begin{array}{rl} & 2x + 3y = 6 \\ - & 2x - 5y = 7 \\ \hline & \quad 8y = -1 \end{array}$$

- If terms cannot be eliminated just by using addition or subtraction, first multiply one or both equations to form a matching pair.
  For example:

matching pair

1 $3x - 2y = 1$
$2x + y = 3$ $-$ $3x - 2y = 1$, $4x + 2y = 6$ (Multiply both sides by 2)

matching pair

2 $7x - 2y = 3$
$4x - 5y = -6$ $-$ $28x - 8y = 12$, $28x - 35y = -42$ (Multiply both sides by 4), (Multiply both sides by 7)

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 20 Solving simultaneous equations using elimination

Solve the following pairs of simultaneous equations by using elimination.

a $x - 2y = 1$
$-x + 5y = 2$

b $3x - 2y = 5$
$5x - 2y = 11$

c $5x + 2y = -7$
$x + 7y = 25$

d $4x + 3y = 18$
$3x - 2y = 5$

SOLUTION | **EXPLANATION**

a

$x - 2y = 1$ (1)
$-x + 5y = 2$ (2)

(1) + (2) $3y = 3$

Add the two equations to eliminate x since $x + (-x) = 0$. Then solve for y.

$y = 1$

From (1) $x - 2y = 1$

Substitute $y = 1$ into equation (1) to find x.

$x - 2 \times (1) = 1$
$x - 2 = 1$
$x = 3$

$\therefore x = 3, y = 1$

Substitute $x = 3$ and $y = 1$ into the original equations to check.

b

$3x - 2y = 5$ (1)
$5x - 2y = 11$ (2)

Subtract the two equations to eliminate y since they are the same sign, i.e. $-2y - (-2y) = -2y + 2y = 0$. Alternatively, could do (1) – (2) but (2) – (1) avoids negative coefficients. Solve for x.

(2) – (1) $2x = 6$
$x = 3$

From (1) $3x - 2y = 5$

Substitute $x = 3$ into equation (1) to find y.

$3 \times (3) - 2y = 5$
$9 - 2y = 5$
$-2y = -4$
$y = 2$

$\therefore x = 3, y = 2$

Substitute $x = 3$ and $y = 2$ into the original equations to check.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c

$5x + 2y = -7$ (1)

$x + 7y = 25$ (2)

$5 \times (2)$ $5x + 35y = 125$ (3)

$5x + 2y = -7$ (1)

$(3) - (1)$ $33y = 132$

$y = 4$

There are different numbers of x and y in each equation so multiply equation (2) by 5 to make the coefficient of x equal in size to (1).

Subtract the equations to eliminate x.

From (2) $x + 7y = 25$

$x + 7 \times (4) = 25$

$x + 28 = 25$

$x = -3$

Substitute $y = 4$ in equation (2) to find x.

$\therefore x = -3, y = 4$

Substitute $x = -3$ and $y = 4$ into the original equations to check.

d

$4x + 3y = 18$ (1)

$3x - 2y = 5$ (2)

$2 \times (1)$ $8x + 6y = 36$ (3)

$3 \times (2)$ $9x - 6y = 15$ (4)

$(3) + (4)$ $17x = 51$

$x = 3$

Multiply equation (1) by 2 and equation (2) by 3 to make the coefficients of y equal in size but opposite in sign.

Add the equations to eliminate y.

From (1) $4x + 3y = 18$

$4 \times (3) + 3y = 18$

$12 + 3y = 18$

$3y = 6$

$y = 2$

Substitute $x = 3$ into equation (1) to find y.

$\therefore x = 3, y = 2$

Substitute $x = 3$ and $y = 2$ into the original equations to check.

Exercise 2J

1, 2 | 2 | —

UNDERSTANDING

1 Insert a '+' or '–' sign inside each statement to make them true.

a $3x$ ___ $3x = 0$ **b** $-2y$ ___ $2y = 0$ **c** $11y$ ___ $(-11y) = 0$ **d** $-4x$ ___ $(-4x) = 0$

2 **a** Decide if addition or subtraction should be chosen to eliminate the variable x in these simultaneous equations.

i $x + 2y = 3$
$x - 5y = -4$

ii $-2x - y = -9$
$2x + 3y = 11$

iii $y - x = 0$
$3y - x = 8$

b Decide if addition or subtraction will eliminate the variable y in these simultaneous equations.

i $4x - y = 6$
$x + y = 4$

ii $7x - 2y = 5$
$-3x - 2y = -5$

iii $10y + x = 14$
$-10y - 3x = -24$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2J

FLUENCY

3–5, 6(½) | 3–5, 6–7(½) | 3–7(½)

Example 20a

3 Solve these simultaneous equations by firstly adding the equations.

a $x + 2y = 3$
$-x + 3y = 2$

b $x - 4y = 2$
$-x + 6y = 2$

c $-2x + y = 1$
$2x - 3y = -7$

d $3x - y = 2$
$2x + y = 3$

e $2x - 3y = -2$
$-5x + 3y = -4$

f $4x + 3y = 5$
$-4x - 5y = -3$

4 Solve these simultaneous equations by firstly subtracting the equations.

a $3x + y = 10$
$x + y = 6$

b $2x + 7y = 9$
$2x + 5y = 11$

c $2x + 3y = 14$
$2x - y = -10$

Example 20b

5 Solve these simultaneous equations by firstly subtracting the equations.

a $5x - y = -2$
$3x - y = 4$

b $-5x + 3y = -1$
$-5x + 4y = 2$

c $9x - 2y = 3$
$-3x - 2y = -9$

Example 20c

6 Solve the following pairs of simultaneous linear equations by using elimination.

a $4x + y = -8$
$3x - 2y = -17$

b $2x - y = 3$
$5x + 2y = 12$

c $-x + 4y = 2$
$3x - 8y = -2$

d $3x + 2y = 0$
$4x + y = -5$

e $4x + 3y = 13$
$x + 2y = -3$

f $3x - 4y = -1$
$6x - 5y = 10$

g $-4x - 3y = -5$
$7x - y = 40$

h $3x - 4y = -1$
$-5x - 2y = 19$

i $5x - 4y = 7$
$-3x - 2y = 9$

Example 20d

7 Solve the following pairs of simultaneous linear equations by using elimination.

a $3x + 2y = -1$
$4x + 3y = -3$

b $7x + 2y = 8$
$3x - 5y = 21$

c $6x - 5y = -8$
$-5x + 2y = -2$

d $2x - 3y = 3$
$3x - 2y = 7$

e $7x + 2y = 1$
$4x + 3y = 8$

f $5x + 7y = 1$
$3x + 5y = -1$

g $5x + 3y = 16$
$4x + 5y = 5$

h $3x - 7y = 8$
$4x - 3y = -2$

i $2x - 3y = 1$
$3x + 2y = 8$

j $2x - 7y = 11$
$5x + 4y = -37$

k $3x + 5y = 36$
$7x + 2y = -3$

l $2x - 4y = 6$
$5x + 3y = -11$

PROBLEM-SOLVING

8, 9 | 8–10 | 9–11

8 The sum of two numbers is 30 and their difference is 12.
Write two equations and find the numbers.

9 Two supplementary angles differ by 24°.
Write two equations and find the two angles.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2J

PROBLEM-SOLVING

10 The perimeter of a rectangular city block is 800 metres and the difference between the length and width is 123 metres. What are the dimensions of the city block?

11 A teacher collects a total of 17 mobile phones and iPads before a group of students heads off on a bushwalk. From a second group of students, 40 phones and iPads are collected. The second group had twice the number of phones and 3 times the number of iPads than the first group. How many phones and iPads did the first group have?

12 | 12, 13 | 13, 14

REASONING

12 Consider the pair of simultaneous equations:

$$2x + y = 5 \ldots \quad (1)$$
$$5x + y = 11 \ldots \quad (2)$$

a Solve the equations by firstly subtracting equation (2) from equation (1), i.e. (1) – (2).
b Now solve the equations by firstly subtracting equation (1) from equation (2), i.e. (2) – (1).
c Which method **a** or **b** is preferable and why?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2J

REASONING

13 To solve any of the pairs of simultaneous equations in this section using the method of substitution, what would need to be done first before the substitution is made?

Try these using substitution.

a $x + y = 5$
$2x - y = 7$

b $3x - y = -2$
$x - 4y = 3$

14 Find the solution to these pairs of simultaneous equations. What do you notice?

a $2x + 3y = 3$ and $2x + 3y = 1$

b $7x - 14y = 2$ and $y = \frac{1}{2}x + 1$

Literal elimination — — 15

ENRICHMENT

15 Use elimination to solve the following pairs of simultaneous equations to find the value of x and y in terms of the other pronumerals.

a $x + y = a$
$x - y = b$

b $ax + y = 0$
$ax - y = b$

c $x - by = a$
$-x - by = 2a$

d $2ax + y = b$
$x + y = b$

e $bx + 5ay = 2b$
$bx + 2ay = b$

f $ax + 3y = 14$
$ax - y = -10$

g $2ax + y = b$
$3ax - 2y = b$

h $2ax - y = b$
$3ax + 2y = b$

i $-x + ay = b$
$3x - ay = -b$

j $ax + 2y = c$
$2ax + y = -c$

k $ax - 4y = 1$
$x - by = 1$

l $ax + by = a$
$x + y = 1$

m $ax + by = c$
$-ax + y = d$

n $ax - by = a$
$-x + y = 2$

o $ax + by = b$
$3x - y = 2$

p $ax - by = b$
$cx - y = 2$

q $ax + by = c$
$dx - by = f$

r $ax + by = c$
$dx + by = f$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2K Applications of simultaneous equations EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Many problems can be described mathematically using a pair of simultaneous linear equations from which a solution can be obtained algebraically.

Let's start: The tyre store

In one particular week a total of 83 cars and motorcycles check into a garage to have their tyres changed. All the motorcycles change 2 tyres each and all the cars change 4 tyres each. The total number of tyres sold in the week is 284.

If you had to find the number of motorcycles and the number of cars that have their tyres changed in the week:

- What two variables should you define?
- What two equations can you write?
- Which method (substitution or elimination) would you use to solve the equations?
- What is the solution to the simultaneous equations?
- How would you answer the question in words?

Key ideas

- To solve worded problems with simultaneous equations complete these steps.
  - Define two variables by writing down what they represent.
    For example: Let $\$C$ be the cost of …
    Let x be the number of …
  - Write a pair of simultaneous equations from the given information using your two variables.
  - Solve the equations simultaneously using substitution or elimination.
  - Check the solution by substituting into the original equations.
  - Express the answer in words.

Example 21 Solving word problems with simultaneous equations

Andrea bought two containers of ice cream and three bottles of maple syrup for a total of $22.
At the same shop, Bettina bought one container of ice cream and two bottles of maple syrup for $13.
How much does each container of ice cream and each bottle of maple syrup cost?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
Let: $\$x$ be the cost of a container of ice cream $\$y$ be the cost of a bottle of maple syrup	Define the unknowns. Ask yourself what you are being asked to find.
$2x + 3y = 22$ (1) $x + 2y = 13$ (2)	2 containers of ice cream and 3 bottles of maple syrup for a total of \$22 1 container of ice cream and 2 bottles of maple syrup for \$13.
$2 \times (2)$ $2x + 4y = 26$ (3) $2x + 3y = 22$ (1) $(3) - (1)$ $y = 4$	Choose the method of elimination to solve. Multiply (2) by 2 to obtain a matching pair. Subtract equation (1) from (3).
From (2) $x + 2y = 13$ $x + 2 \times (4) = 13$ $x + 8 = 13$ $x = 5$	Substitute $y = 4$ into (2). Solve for x. Substitute $y = 4$ and $x = 5$ into original equations to check.
The cost of one container of ice cream is \$5 and the cost of one bottle of maple syrup is \$4.	Answer the question in a sentence.

Exercise 2K

1, 3 | 2 | —

UNDERSTANDING

1 The sum of two numbers is 42 and their difference is 6. Find the two numbers x and y by completing the following steps.
- **a** Write a pair of simultaneous equations relating x and y.
- **b** Solve the pair of equations using substitution or elimination.
- **c** Write your answer in words.

2 The length l cm of a rectangle is 5 cm longer than its width w cm. If the perimeter is 84 cm, find the dimensions of the rectangle by completing the following steps.
- **a** Write a pair of simultaneous equations relating l and w.
- **b** Solve the pair of equations using substitution or elimination.
- **c** Write your answer in words.

3 A rectangular block of land has a perimeter of 120 metres and the length l m of the block is three times the width w m. Find the dimensions of the block of land by completing the following steps.
- **a** Write a pair of simultaneous equations relating l and w.
- **b** Solve the pair of equations using substitution or elimination.
- **c** Write your answer in words.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2K

Example 21

FLUENCY

4–7 | 4–8 | 4, 6, 8, 9

4 Mal bought 3 bottles of milk and 4 bags of chips for a total of $17. At the same shop, Barbara bought 1 bottle of milk and 5 bags of chips for $13. Find how much each bottle of milk and each bag of chips cost by completing the following steps.

- **a** Define two variables to represent the problem.
- **b** Write a pair of simultaneous equations relating the two variables.
- **c** Solve the pair of equations using substitution or elimination.
- **d** Write your answer in words.

5 Leonie bought seven lip glosses and two eye shadows for a total of $69 and Chrissie bought four lip glosses and three eye shadows for a total of $45. Find how much each lip gloss and each eye shadow costs by completing the following steps.

- **a** Define two variables to represent the problem.
- **b** Write a pair of simultaneous equations relating the two variables.
- **c** Solve the pair of equations using substitution or elimination.
- **d** Write your answer in words.

6 Steve bought five cricket balls and fourteen tennis balls for $130. Ben bought eight cricket balls and nine tennis balls for $141. Find the cost of a cricket ball and the cost of a tennis ball.

7 At a birthday party for 20 people each person could order a hot dog or a bucket of chips. If there were four times as many hot dogs as buckets of chips calculate how many hot dogs and how many buckets of chips were bought.

8 The entry fee for a fun run is $10 for adults and $3 for children. A total of $3360 was collected from the 420 competitors. Find the number of adults running and the number of children running.

9 Mila plants 820 hectares of potatoes and corn. To maximise his profit he plants 140 hectares more of potatoes than of corn. How many hectares of each does he plant?

PROBLEM-SOLVING

10, 11 | 10–12 | 11–13

10 Carrie has 27 coins in her purse. All the coins are 5 cent or 20 cent coins. If the total value of the coins is $3.75, how many of each type does she have?

11 Michael is 30 years older than his daughter. In five years' time Michael will be 4 times as old as his daughter. How old is Michael now?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

PROBLEM-SOLVING

12 Jenny has twice as much money as Kristy. If I give Kristy $250, she will have three times as much as Jenny. How much did each of them have originally?

13 At a particular cinema the cost of an adult movie ticket is $15 and the cost of a child's ticket is $10. The seating capacity of the cinema is 240. For one movie session all seats are sold and $3200 is collected from the sale of tickets. How many adult and how many children's tickets were sold?

Solve simultaneous equations to find the number of tickets sold to children and the number sold to adults.

REASONING

14	14, 15	15, 16

14 Wilfred and Wendy have a long distance bike race. Wilfred rides at 20 km/h and has a 2 hour head start. Wendy travels at 28 km/h. How long does it take for Wendy to catch up to Wilfred? Use distance = speed × time.

15 Andrew travelled a distance of 39 km by jogging for 4 hours and cycling for 3 hours. He could have travelled the same distance by jogging for 7 hours and cycling for 2 hours. Find the speed at which he was jogging and the speed at which he was cycling.

16 Malcolm's mother is 27 years older than he is and their ages are both two digit numbers. If Malcolm swaps the digits in his age he gets his mother's age.

- **a** How old is Malcolm if the sum of the digits in his age is 5?
- **b** What is the relationship between the digits in Malcolm's age if the sum of the digits is unknown.
- **c** If the sum of the digits in Malcolm's two-digit age is unknown, how many possible ages could he be? What are these ages?

ENRICHMENT

Digit swap

—	—	17, 18

17 The digits of a two digit number sum to 10. If the digits swap places the number is 36 more than the original number. What is the original number? Can you show an algebraic solution?

18 The difference between the two digits of a two-digit number is 2. If the digits swap places the number is 18 less than the original number. What is the original number? Can you show an algebraic solution?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016

Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Fire danger

In many countries fire indices have been developed to help predict the likelihood of fire occurring. One of the simplest fire-danger rating systems devised is the Swedish Angstrom Index. This index only considers the relationship between relative humidity, temperature and the likelihood of fire danger.

The index, I, is given by: $I = \frac{H}{20} + \frac{27 - T}{10}$

where H is the percentage of relative humidity and T is the temperature in degrees Celsius. The table below shows the likelihood of a fire occurring for different index values.

Index	Likelihood of fire occurring
$I > 4.0$	Unlikely
$2.5 < I < 4.0$	Medium
$2.0 < I < 2.5$	High
$I < 2.0$	Very likely

Constant humidity

a If the humidity is 35% ($H = 35$), how hot would it have to be for the occurrence of fire to be
i very likely? **ii** unlikely?
Discuss your findings with regard to the range of summer temperatures for your capital city or nearest town.

b Repeat part **a** for a humidity of 40%.

c Describe how the 5% change in humidity affects the temperature at which fires become
i very likely **ii** unlikely

Constant temperature

a If the temperature was 30°C, investigate what humidity would make fire occurrence
i very likely **ii** unlikely

b Repeat part **a** for a temperature of 40°C.

c Determine how the ten-degree change in temperature affects the relative humidity at which fire occurrence becomes
i very likely **ii** unlikely

Reflection

Is this fire index more sensitive to temperature or to humidity? Explain your answer.

Investigate

Use the internet to investigate fire indices used in Australia. You can type in key words, such as Australia, fire danger and fire index.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Families of equations

If a set of equations has something in common then it may be possible to solve all the equations in the family at once using literal equations. Literal equations use pronumerals in place of numbers.

Family of linear equations

a Solve these linear equations for x.

i $2x + 3 = 5$ **ii** $2x + 1 = 5$ **iii** $2x - 1 = 5$

b Now solve the literal equation $2x + a = 5$ for x. Your answer will be in terms of a.

c For part **a i**, the value of a is 3. Substitute $a = 3$ into your rule for x in part **b** to check the result.

Literal equations

a Solve these literal equations for x in terms of the other pronumerals.

i $ax + b = 10$ **ii** $\frac{x-a}{b} = c$ **iii** $\frac{ax}{b} + c = d$

b Use your results from part **a** to solve these equations.

i $-3x + 2 = 10$ **ii** $\frac{x-5}{7} = -4$ **iii** $-\frac{3x}{4} + 1 = 2$

Factorising to solve for x

To solve for x in an equation like $ax + 1 = bx + 2$ you can use factorisation as shown here.

$$ax + 1 = bx + 2$$
$$ax - bx = 2 - 1$$
$$x(a - b) = 1$$
$$x = \frac{1}{a-b}$$

a Use the above idea to solve these literal equations.

i $ax + 5 = 1 - bx$ **ii** $a(x + 2) = b(x - 1)$

iii $\frac{ax}{2} + bx = 1$ **iv** $\frac{b(x-1)}{a} = x - 2$

b Solve these literal simultaneous equations for x and y.

i $ax + y = 1$
$bx - y = -11$

ii $y = ax + b$
$2x + y = 2b$

iii $ax + by = c$
$x - y = 0$

iv $ax + by = 1$
$bx + ay = 1$

c Check your solutions to parts **a** and **b** above by choosing an equation or a pair of simultaneous equations and solving in the normal way. Choose your equations so that they belong to the family described by the literal equation.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Transpose each of the following formulas to make the pronumeral shown in brackets the subject.

a $wx - 4 = ax + k \quad [x]$ **b** $\frac{a}{K} - y = \frac{b}{K} \quad [K]$ **c** $\sqrt{\frac{a-w}{ak}} = m \quad [a]$

2 Five consecutive integers add to 195. Find the middle integer.

3 A group of office workers had some prize money to distribute amongst themselves. When all but one took \$9 each, the last person only received \$5. When they all took \$8 each there was \$12 left over. How much had they won?

4 The sides of an equilateral triangle have lengths $3y - x$, $5x + 3$ and $2 + 2y$. Find the length of the sides.



5 **a** If $a > b > 0$ and $c < 0$, insert an inequality sign to make a true statement.

i $a + c ___ b + c$ **ii** $ac ___ bc$

iii $a - b ___ 0$ **iv** $\frac{1}{a} ___ \frac{1}{b}$

b Place a, b, c and d in order from smallest to largest given

$$a > b$$
$$a + b = c + d$$
$$b - a > c - d$$

6 Find the values of x, y and z if

$$x - 3y + 2z = 17$$
$$x - y + z = 8$$
$$y + z = 3$$

7 Solve these equations for x.

a $\frac{1}{x} + \frac{1}{a} = \frac{1}{b}$ **b** $\frac{1}{2x} + \frac{1}{3x} = \frac{1}{4}$

c $\frac{x-1}{3} - \frac{x+1}{4} = x$ **d** $\frac{2x-3}{4} - \frac{1-x}{5} = \frac{x+1}{2}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Linear and simultaneous equations

Substitution
The process of replacing a pronumeral with a given value
e.g. if $x = 3$, $2x + 4 = 2 \times 3 + 4$
$= 6 + 4$
$= 10$
e.g. if $x = 2$, $y = -4$, $xy = 2 \times (-4)$
$= -8$

Expanding brackets
e.g. $2(x + 3) = 2 \times x + 2 \times 3$
$= 2x + 6$
$-3(4 - 2x) = -12 + 6x$

Expressions
e.g. $2x - 3y + 5$
term, constant, coefficient
e.g. 2 more than 3 lots of m is $3m + 2$

Addition/subtraction
Only like terms can be combined under addition or subtraction.
Like terms, e.g. $3a$ and $7a$
$2ab$ and $5ab$
not $4a$ and $7ab$
e.g. $3x + 2y - x + 4y + 7$
$= 3x - x + 2y + 4y + 7$
$= 2x + 6y + 7$

Solving linear equations
Finding the value that makes an equation true
e.g. $2x + 5 = 9$
$2x = 4$ (subtract 5)
$x = 2$ (divide by 2)
e.g. $5(x - 1) = 2x + 7$
$5x - 5 = 2x + 7$ (expand)
$3x - 5 = 7$ (subtract $2x$)
$3x = 12$ (add 5)
$x = 4$ (divide by 3)

Inequalities
These can be represented using $>$, $<$, $\geq$, $\leq$ rather than $=$.
e.g. $x > 2$



Solving inequalities uses the same steps as solving equations except when multiplying or dividing by a negative number. In this case, the inequality sign must be reversed.
e.g. $4 - 2x < 10$ (-4)
$-2x < 6$ $(\div -2)$
$x > -3$ reverse sign

Solving word problems
1 Define variable(s)
2 Set up equation(s)
3 Solve equation(s)
4 Check each answer and write in words

Simultaneous equations (Ext)
Use substitution or elimination to find the solution that satisfies 2 equations.

Substitution
e.g. $2x + y = 12$ (1)
$y = x + 3$ (2)
In (1) replace y with (2)
$2x + (x + 3) = 12$
$3x + 3 = 12$
$x = 3$
Substitute $x = 3$ to find y
In (2) $y = (3) + 3 = 6$

Elimination
Ensure both equations have a matching pair.
Add 2 equations if matching pair has different sign; subtract if same sign.

e.g. $x + 2y = 2$ (1)
$2x + 3y = 5$ (2)
(1) $\times 2$ $2x + 4y = 4$ (3)
(3) $-$ (2) $y = -1$
In (1) $x + 2(-1) = 2$
$x - 2 = 2$
$\therefore x = 4$

Formulas
Some common formulas
e.g. $A = \pi r^2$, $C = 2\pi r$
An unknown value can be found by substituting values for the other variables.
A formula can be transposed to make a different variable the subject.
e.g. make r the subject in $A = \pi r^2$
$A = \pi r^2$
$\frac{A}{\pi} = r^2$
$\sqrt{\frac{A}{\pi}} = r$
$\therefore r = \sqrt{\frac{A}{\pi}}$ where $r > 0$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter review

Multiple-choice questions

2A **1** The algebraic expression that represents 2 less than 3 lots of n is

A $3(n-2)$ **B** $2-3n$ **C** $3n-2$ **D** $3+n-2$ **E** n

2B **2** The simplified form of $6ab + 14a \div 2 - 2ab$ is:

A $8ab$ **B** $8ab + 7a$ **C** $ab + 7a$ **D** $4ab + 7a$ **E** $4ab + \frac{7a}{2}$

2D **3** The solution to $\frac{x}{3} - 1 = 4$ is:

A $x = 13$ **B** $x = 7$ **C** $x = 9$ **D** $x = 15$ **E** $x = \frac{5}{3}$

2D **4** The result when a number is tripled and increased by 21 is 96. The original number is:

A 22 **B** 32 **C** 25 **D** 30 **E** 27

2E **5** The solution to the equation $3(x-1) = 5x + 7$ is:

A $x = -4$ **B** $x = -5$ **C** $x = 5$ **D** $x = 3$ **E** $x = 1$

2F **6** \$$x$ is raised from a sausage sizzle. Once the \$50 running cost is taken out, the money is shared equally amongst three charities so that they each get \$120. An equation to represent this is:

A $\frac{x-50}{3} = 120$ **B** $\frac{x}{3} - 50 = 120$ **C** $\frac{x}{50} = 360$

D $\frac{x}{3} = 310$ **E** $3x + 50 = 120$

2H **7** If $A = 2\pi rh$ with $A = 310$ and $r = 4$ then the value of h is closest to:

A 12.3 **B** 121.7 **C** 24.7 **D** 38.8 **E** 10.4

2H **8** The formula $d = \sqrt{\frac{a}{b}}$ transposed to make a the subject is:

A $a = \sqrt{bd}$ **B** $a = d\sqrt{b}$ **C** $a = \frac{d^2}{b^2}$ **D** $a = \sqrt{\frac{d}{b}}$ **E** $a = bd^2$

2G **9** The inequality representing the x values on the number line below is:



A $x < -1$ **B** $x > -1$ **C** $x \leq -1$ **D** $x \geq -1$ **E** $-1 < x < 3$

2G **10** The solution to the inequality $1 - 2x > 9$ is:

A $x < -4$ **B** $x < 4$ **C** $x < -5$ **D** $x > -4$ **E** $x > 5$

2I Ext **11** The solution to the simultaneous equations $x + 2y = 16$ and $y = x - 4$ is:

A $x = 4, y = 0$ **B** $x = 8, y = 4$ **C** $x = 6, y = 2$ **D** $x = 12, y = 8$ **E** $x = 5, y = 1$

2J Ext **12** The solution to the simultaneous equations $2x + y = 2$ and $2x + 3y = 10$ is:

A $x = 0, y = 2$ **B** $x = 2, y = 2$ **C** $x = 2, y = -2$

D $x = -1, y = 4$ **E** $x = -2, y = 6$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

2A **1** Write algebraic expressions to represent the following.

a The product of m and 7

b Twice the sum of x and y

c The cost of 3 movie tickets at m dollars each

d n divided by 4 less 3

2A **2** Evaluate the following if $x = 2$, $y = -1$ and $z = 5$.

a $yz - x$ **b** $\frac{2z - 4y}{x}$ **c** $\frac{2z^2}{x} + y$ **d** $x(y + z)$

2B **3** Simplify.

a $2m \times 4n$ **b** $\frac{4x^2y}{12x}$ **c** $3ab \times 4b \div (2a)$

d $4 - 5b + 2b$ **e** $3mn + 2m - 1 - nm$ **f** $4p + 3q - 2p + q$

2C **4** Expand and simplify the following.

a $2(x + 7)$ **b** $-3(2x + 5)$ **c** $2x(3x - 4)$

d $-2a(5 - 4a)$ **e** $5 - 4(x - 2)$ **f** $4(3x - 1) - 3(2 - 5x)$

2D **5** Solve the following linear equations for x.

a $5x + 6 = 51$ **b** $\frac{x + 2}{4} = 7$ **c** $\frac{2x}{5} - 3 = 3$ **d** $\frac{2x - 5}{3} = -1$

e $7x - 4 = 10$ **f** $3 - 2x = 21$ **g** $1 - \frac{4x}{5} = 9$ **h** $2 - 7x = -3$

2D **6** Write an equation to represent each of the following and then solve it for the pronumeral.

a A number n is doubled and increased by 3 to give 21.

b A number of lollies l is decreased by 5 and then shared equally among three friends so that they each get 7.

c 5 less than the result of Toni's age x divided by 4 is 0.

2E **7** Solve the following linear equations.

a $2(x + 4) = 18$ **b** $3(2x - 3) = 2$ **c** $8x = 2x + 24$

d $5(2x + 4) = 7x + 5$ **e** $3 - 4x = 7x - 8$ **f** $1 - 2(2 - x) = 5(x - 3)$

2F **8** Nick makes an initial bid of $\$x$ in an auction for a signed cricket bat. By the end of the auction he has paid \$550, \$30 more than twice his initial bid. Set up and solve an equation to determine Nick's initial bid.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

2G **9** Represent each of the following on a number line.

a $x > 1$ **b** $x \leq 7$ **c** $x \geq -4$

d $x < -2$ **e** $2 < x \leq 8$ **f** $-1 < x < 3$

2G **10** Solve the following inequalities.

a $x + 8 < 20$ **b** $2m - 4 > -6$ **c** $3 - 2y \leq 15$

d $\frac{7 - 2x}{3} > -9$ **e** $3a + 9 < 7(a - 1)$ **f** $-4x + 2 \leq 5x - 16$

2G **11** A car salesman earns $800 per month plus a 10% commission on the amount of sales for the month. If he is aiming to earn a minimum of $3200 a month, what is the possible sales amount that will enable this?

2H **12** Find the value of the unknown in each of the following formulas.

a $E = \sqrt{PR}$ when $P = 90$ and $R = 40$

b $v = u + at$ when $v = 20$, $u = 10$, $t = 2$

c $V = \frac{1}{3}Ah$ when $V = 20$, $A = 6$

2H **13** Rearrange the following formulas to make the variable in brackets the subject.

a $v^2 = u^2 + 2ax$ $[x]$ **b** $A = \frac{1}{2}r^2\theta$ $[\theta]$

c $P = RI^2, I > 0$ $[I]$ **d** $S = \frac{n}{2}(a + l)$ $[a]$

2I/J Ext **14** Solve the following simultaneous equations using the substitution method for parts **a**–**c** and the elimination method for **d**–**f**.

a $x + 2y = 12$
$x = 4y$

b $2x + 3y = -6$
$y = x - 1$

c $7x - 2y = 6$
$y = 2x + 3$

d $x + y = 15$
$x - y = 7$

e $3x + 2y = -19$
$4x - y = -7$

f $3x - 5y = 7$
$5x + 2y = 22$

2K Ext **15** Billy went to the Show and spent $78 on a combined total of 9 items including rides and showbags. If each showbag cost $12 and each ride cost $7, how many of each did Billy buy?

How many rides did Billy buy?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 The area of a trapezium is given by $A = \frac{1}{2}(a + b)h$. A new backyard deck in the shape of the trapezium shown is being designed.
Currently the dimensions are set such that $a = 12$ m and $h = 10$ m.



- **a** What range of b values is required for an area of at most 110 m^2?
- **b** Rearrange the area formula to make b the subject.
- **c** Use your answer to part **b** to find the length b m required to give an area of 100 m^2.
- **d** Rearrange the area formula to make h the subject.
- **e** If b is set as 8 m, what does the width of the deck (h m) need to be reduced to for an area of 80 m^2?

2 Members of the Hayes and Thompson families attend the local Regatta by the Bay.

- **a** The entry fee for an adult is $18 and the entry fee for a student is $8. The father and son from the Thompson family notice that after paying the entry fees and after 5 rides for the son and 3 for the adult, they have each spent the same amount. If the cost of a ride is the same for an adult and a student, write an equation and solve it to determine the cost of a ride.

Ext

- **b** For lunch each family purchases some buckets of hot chips and some drinks.
The Hayes family buys 2 drinks and 1 bucket of chips for $11 and the Thompson family buys 3 drinks and 2 buckets of chips for $19. To determine how much each bucket of chips and each drink costs, complete the following steps.
  - **i** Define two variables to represent the problem.
  - **ii** Set up two equations relating the variables.
  - **iii** Solve your equations in part **b ii** simultaneously.
  - **iv** What is the cost of a bucket of chips and the cost of a drink?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 3

Pythagoras' theorem and trigonometry

What you will learn

3A Pythagoras' theorem
3B Finding the shorter sides
3C Applying Pythagoras' theorem
3D Pythagoras in three dimensions (Extending)
3E Trigonometric ratios
3F Finding side lengths
3G Solving for the denominator
3H Finding an angle
3I Applying trigonometry (Extending)
3J Bearings (Extending)

Australian curriculum

MEASUREMENT AND GEOMETRY

Pythagoras and Trigonometry

Investigate Pythagoras' theorem and its application to solving simple problems involving right-angled triangles

Use similarity to investigate the constancy of the sine, cosine and tangent ratios for a given angle in right-angled triangles

Apply trigonometry to solve right-angled triangle problems

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Satellites

Satellite navigation systems work by determining where you are and calculating how far it is to where you want to go. Distances are worked out using the mathematics of trigonometry. The position of the satellite, your position and your destination are three points which form a triangle. This triangle can be divided into two right-angled triangles and, using two known angles and one side length, the distance between where you are and your destination can be found using sine, cosine and tangent functions. Similar techniques are used to navigate the seas, study the stars and map our planet, Earth.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3A Pythagoras' theorem

Interactive

Widgets

HOTsheets

Walkthroughs

Pythagoras was born on the Greek island of Samos in the 6th century BCE. He received a privileged education and travelled to Egypt and Persia where he developed his ideas in mathematics and philosophy. He settled in Crotone Italy where he founded a school. His many students and followers were called the Pythagoreans and under the guidance of Pythagoras, lived a very structured life with strict rules. They aimed to be pure, self-sufficient and wise, where men and women were treated equally and all property was considered communal. They strove to perfect their physical and mental form and made many advances in their understanding of the world through mathematics.

The Pythagorean brotherhood in ancient Greece

The Pythagoreans discovered the famous theorem, which is named after Pythagoras, and the existence of irrational numbers such as $\sqrt{2}$, which cannot be written down as a fraction or terminating decimal. Such numbers cannot be measured exactly with a ruler with fractional parts and were thought to be unnatural. The Pythagoreans called these numbers 'unutterable' numbers and it is believed that any member of the brotherhood who mentioned these numbers in public would be put to death.

Let's start: Matching the areas of squares

Look at this right-angled triangle and the squares drawn on each side. Each square is divided into smaller sections.

- Can you see how the parts of the two smaller squares would fit into the larger square?
- What is the area of each square if the side lengths of the right-angled triangle are a, b and c as marked?
- What do the answers to the above two questions suggest about the relationship between a, b and c?



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- The longest side of a right-angled triangle is called the **hypotenuse** and is opposite the right angle.
- The **theorem of Pythagoras** says that the square of the length of the hypotenuse is equal to the sum of the squares of the lengths of the other two sides.
  For the triangle shown, it is:



$$c^2 = a^2 + b^2$$

square of the hypotenuse; squares of the two shorter sides

  - The theorem can be illustrated in a diagram like the one on the right. The sum of the areas of the two smaller squares ($a^2 + b^2$) is the same as the area of the largest square (c^2).



- Lengths can be expressed with **exact values** using **surds**. $\sqrt{2}, \sqrt{28}$ and $2\sqrt{3}$ are examples of surds.
  - When expressed as a decimal, a surd is an infinite non-recurring decimal with no pattern.
    For example: $\sqrt{2} = 1.4142135623\ldots$

Example 1 Finding the length of the hypotenuse

Find the length of the hypotenuse in these right-angled triangles. Round to two decimal places in part **b**.

a



b



SOLUTION

a $c^2 = a^2 + b^2$
$= 5^2 + 12^2$
$= 169$
$\therefore\ c = \sqrt{169}$
$= 13$

EXPLANATION

Write the rule and substitute the lengths of the two shorter sides.

If $c^2 = 169$ then $c = \sqrt{169} = 13$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

b $c^2 = a^2 + b^2$
$= 7^2 + 9.5^2$
$= 139.25$
$\therefore\ c = \sqrt{139.25}$
$= 11.80$ (to 2 d.p.)

The order for a and b does not matter since $7^2 + 9.5^2 = 9.5^2 + 7^2$.

Round as required.

Example 2 Finding the length of the hypotenuse using exact values

Find the length of the hypotenuse in this right-angled triangle, leaving your answer as an exact value.



SOLUTION | **EXPLANATION**

$c^2 = a^2 + b^2$
$= 5^2 + 2^2$
$= 29$
$\therefore\ c = \sqrt{29}$

Apply Pythagoras' theorem to find the value of c.

Express the answer exactly using a surd.

Exercise 3A

1–3 | 3(½) | —

UNDERSTANDING

1 State the length of the hypotenuse (c units) in these right-angled triangles.

a


b


c


2 Write down Pythagoras' theorem using the given pronumerals for these right-angled triangles.
For example: $z^2 = x^2 + y^2$.

a


b


c


3 Evaluate the following, rounding to two decimal places in parts **g** and **h**.

a 9^2 **b** 3.2^2 **c** $3^2 + 2^2$ **d** $9^2 + 5^2$
e $\sqrt{36}$ **f** $\sqrt{64 + 36}$ **g** $\sqrt{24}$ **h** $\sqrt{3^2 + 2^2}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

4–7(½) 4–8(½) 4–8(½) 3A

FLUENCY

Example 1a

4 Find the length of the hypotenuse in each of the following right-angled triangles.

a 

b 

c 

d 

e 

f 

g 

h 

i 

Example 1b

5 Find the length of the hypotenuse in each of these right-angled triangles, correct to two decimal places.

a 

b 

c 

d 

e 

f 

Example 2

6 Find the length of the hypotenuse in these triangles, leaving your answer as an exact value.

a 

b 

c 

d 

e 

f 

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3A

FLUENCY

7 Find the length of the hypotenuse in each of these right-angled triangles, rounding to two decimal places where necessary. Convert to the units indicated in red.

a



b



c



d



e



f



8 For each of these triangles, first calculate the length of the hypotenuse then find the perimeter, correct to two decimal places.

a



b



c



d



e



f



9–11 | 9–11, 13 | 11–14

PROBLEM-SOLVING

9 Find the perimeter of this triangle. (*Hint*: you will need to find *AB* and *BC* first.)



10 Find the length of the diagonal steel brace required to support a wall of length 3.5 m and height 2.6 m. Give your answer correct to one decimal place.



11 A helicopter hovers at a height of 150 m above the ground and is a horizontal distance of 200 m from a beacon on the ground. Find the direct distance of the helicopter from the beacon.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3A

PROBLEM-SOLVING

12 A miniature rocket blasts off at an angle of 45° and travels in a straight line. After a few seconds, it reaches a height of 350 m above the ground. At this point it has also covered a horizontal distance of 350 m. How far has the rocket travelled to the nearest metre?



13 Find the length of the longest rod that will fit inside a cylinder of height 2.1 m and with circular end surface of 1.2 m diameter. Give your answer correct to one decimal place.



14 For the shape on the right, find the value of:

a x

b y (as a fraction)



15 | 15, 16 | 16, 17

REASONING

15 One way to check whether a four-sided figure is a rectangle is to ensure that both its diagonals are the same length. What should the length of the diagonals be if a rectangle has side lengths 3 m and 5 m? Answer to two decimal places.

16 We know that if the triangle has a right angle, then $c^2 = a^2 + b^2$. The converse of this is that if $c^2 = a^2 + b^2$ then the triangle must have a right angle. Test if $c^2 = a^2 + b^2$ to see if these triangles must have a right angle. They may not be drawn to scale.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3A

REASONING

17 Triangle ABC is a right-angled isosceles triangle, and BD is perpendicular to AC. If $DC = 4$ cm and $BD = 4$ cm:

- **a** find the length of BC correct to two decimal places
- **b** state the length of AB correct to two decimal places
- **c** use Pythagoras' theorem and ΔABC to check that the length of AC is twice the length of DC.



ENRICHMENT

Kennels and kites — — 18, 19

18 A dog kennel has the dimensions shown in the diagram on the right. Give your answers to each of the following correct to two decimal places.

- **a** What is the width, in cm, of the kennel?
- **b** What is the total height, h m, of the kennel?
- **c** If the sloping height of the roof was to be reduced from 55 cm to 50 cm, what difference would this make to the total height of the kennel? (Assume that the width is the same as in part **a**.)
- **d** What is the length of the sloping height of the roof of a new kennel if it is to have a total height of 1.2 m? (The height of the kennel without the roof is still 1 m and its width is unchanged.)



19 The frame of a kite is constructed with six pieces of timber dowel. The four pieces around the outer edge are two 30 cm pieces and two 50 cm pieces. The top end of the kite is to form a right angle. Find the length of each of the diagonal pieces required to complete the construction. Answer to two decimal places.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3B Finding the shorter sides

Interactive

Widgets

HOTsheets

Walkthroughs

Throughout history, mathematicians have utilised known theorems to explore new ideas, discover new theorems and solve a wider range of problems. Similarly, Pythagoras knew that his right-angled triangle theorem could be manipulated so that the length of one of the shorter sides of a triangle can be found if the length of the other two sides are known.

We know that the sum $7 = 3 + 4$ can be written as a difference $3 = 7 - 4$. Likewise, if $c^2 = a^2 + b^2$ then $a^2 = c^2 - b^2$ or $b^2 = c^2 - a^2$.

Applying this to a right-angled triangle means that we can now find the length of one of the shorter sides if the other two sides are known.

If we know the length of the crane jib and the horizontal distance it extends, Pythagoras' theorem enables us to calculate its vertical height.

Let's start: True or false

Below are some mathematical statements relating to a right-angled triangle with hypotenuse c and the two shorter sides a and b.



Some of these mathematical statements are true and some are false. Can you sort them into true and false groups?

$a^2 + b^2 = c^2$	$a = \sqrt{c^2 - b^2}$	$c^2 - a^2 = b^2$	$a^2 - c^2 = b^2$
$c = \sqrt{a^2 + b^2}$	$b = \sqrt{a^2 - c^2}$	$c = \sqrt{a^2 - b^2}$	$c^2 - b^2 = a^2$

Key ideas

- When finding the length of a side:
  - substitute known values into Pythagoras' rule
  - solve this equation to find the unknown value.

  For example:
  - If $a^2 + 16 = 30$ then subtract 16 from both sides.
  - If $a^2 = 14$ then take the square root of both sides.
    - $a = \sqrt{14}$ is an **exact** answer (a surd).
    - $a = 3.74$ is a rounded decimal answer.

$$c^2 = a^2 + b^2$$
$$25^2 = a^2 + 15^2$$
$$625 = a^2 + 225$$
$$400 = a^2$$
$$a = 20$$



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Finding the length of a shorter side

In each of the following, find the value of the pronumeral. Round your answer in part **b** to two decimal places and give an exact answer to part **c**.

a



b



c



SOLUTION	EXPLANATION
a $a^2 + 15^2 = 17^2$	Write the rule and substitute the known sides.
$a^2 + 225 = 289$	Square 15 and 17.
$a^2 = 64$	Subtract 225 from both sides.
$\therefore a = \sqrt{64}$	Take the square root of both sides.
$a = 8$	
b $x^2 + 7.6^2 = 10^2$	Write the rule.
$x^2 + 57.76 = 100$	
$x^2 = 42.24$	Subtract 57.76 from both sides.
$\therefore x = \sqrt{42.24}$	Take the square root of both sides.
$x = 6.50$ (to 2 d.p.)	Round to two decimal places.
c $x^2 + x^2 = 3^2$	Two sides are of length x.
$2x^2 = 9$	Add like terms and then divide both sides by 2.
$x^2 = \frac{9}{2}$	Take the square root of both sides. To express as an exact answer, do not round.
$\therefore x = \sqrt{\frac{9}{2}} \left(= \frac{3}{\sqrt{2}} = \frac{3\sqrt{2}}{2}\right)$	Different forms are possible.

Exercise 3B

1(½), 2 | 2 | —

UNDERSTANDING

1 Find the value of a or b in these equations. (Both a and b are positive numbers.)

a $a = \sqrt{196}$ **b** $a = \sqrt{121}$ **c** $a^2 = 144$ **d** $a^2 = 400$

e $b^2 + 9 = 25$ **f** $b^2 + 49 = 625$ **g** $36 + b^2 = 100$ **h** $15^2 + b^2 = 289$

2 If $a^2 + 64 = 100$, decide if the following are true or false.

a $a^2 = 100 - 64$ **b** $64 = 100 + a^2$ **c** $100 = \sqrt{a^2 + 64}$

d $a = \sqrt{100 - 64}$ **e** $a = 6$ **f** $a = 10$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3a

3 In each of the following find the value of the pronumeral.

a



b



c



d



e



f



Example 3b

4 In each of the following, find the value of the pronumeral. Express your answers correct to two decimal places.

a



b



c



d



e



f



5 Find the length of the unknown side of each of these triangles, correct to two decimal places where necessary. Convert to the units shown in red.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3B

Example 3c

6 In each of the following, find the value of x as an exact answer.

a



b



c



FLUENCY

7–9 | 7, 8, 10 | 9–11

PROBLEM-SOLVING

7 For each of the following diagrams, find the value of x. Give an exact answer each time.

a



b



c



8 A 32 m communication tower is supported by 35 m cables stretching from the top of the tower to a position at ground level. Find the distance from the base of the tower to the point where the cable reaches the ground, correct to one decimal place.



9 The base of a ladder leaning against a vertical wall is 1.5 m from the base of the wall. If the ladder is 5.5 m long, find how high the top of the ladder is above the ground, correct to one decimal place.



10 If a television has a screen size of 63 cm it means that the diagonal length of the screen is 63 cm. If the vertical height of a 63 cm screen is 39 cm, find how wide the screen is to the nearest centimetre.

11 A 1.3 m vertical fence post is supported by a 2.27 m bar, as shown in the diagram on the right. Find the distance (d metres) from the base of the post to where the support enters the ground. Give your answer correct to two decimal places.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Photocopying is restricted under law and this material must not be transferred to another party.

12 | 12 | 12, 13

3B

REASONING

12 For these questions note that $(2x)^2 = 4x^2$ and $(3x)^2 = 9x^2$.
In each of the following find the value of x as an exact answer.

a



b



c



13 A right-angled triangle has a hypotenuse measuring 5 m. Find the lengths of the other sides if their lengths are in the given ratio. Give an exact answer.
Hint: you can draw a triangle like the one shown for part **a**.



a 1 to 3 **b** 2 to 3 **c** 5 to 7

The power of exact values

— | — | 14, 15

ENRICHMENT

14 Consider this diagram and the unknown length x.



a Explain what needs to be found first before x can be calculated.
b Now try calculating the value x as an exact value.
c Was it necessary to calculate the value of c or was c^2 enough?
d What problems might be encountered if the value of c was calculated and rounded before the value of x is found?

15 In the diagram below, $OD = 3$ and $AB = BC = CD = 1$.

a Using exact values find the length of:
i OC **ii** OB **iii** OA

b Round your answer in part **a iii** to one decimal place and use that length to recalculate the lengths of OB, OC and OD (correct to two decimal places) starting with ΔOAB.

c Explain the difference between the given length $OD = 3$ and your answer for OD in part **b**.

d Investigate how changing the side length AB affects your answers to parts **a** to **c** above.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3C Applying Pythagoras' theorem

Interactive
Widgets
HOTsheets
Walkthroughs

Initially it may not be obvious that Pythagoras' theorem can be used to help solve a particular problem. With further investigation, however, it may be possible to identify and draw in a right-angled triangle which can help solve the problem. As long as two sides of the right-angled triangle are known, the length of the third side can be found.

The length of each cable on the Anzac Bridge, Sydney can be calculated using Pythagoras' theorem.

Let's start: The biggest square

Imagine trying to cut the largest square from a circle of a certain size and calculating the side length of the square. Drawing a simple diagram as shown does not initially reveal a right-angled triangle.



- If the circle has a diameter of 2 cm, can you find a good position to draw the diameter that also helps to form a right-angled triangle?
- Can you determine the side length of the largest square?
- What percentage of the area of a circle does the largest square occupy?

Key ideas

- When applying Pythagoras' theorem, follow these steps.
  - Identify and draw right-angled triangles which may help to solve the problem.
  - Label the sides with their lengths or with a letter (pronumeral) if the length is unknown.
  - Use Pythagoras' theorem to solve for the unknown.
  - Solve the problem by making any further calculations and answering in words.

Example 4 Applying Pythagoras' theorem

Two skyscrapers are located 25 m apart and a cable links the tops of the two buildings. Find the length of the cable if the buildings are 50 m and 80 m in height. Give your answer correct to two decimal places.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
Let x m be the length of the cable.	Draw a right-angled triangle and label the measurements and pronumerals.





$c^2 = a^2 + b^2$

$x^2 = 25^2 + 30^2$

$x^2 = 625 + 900$

$= 1525$

$\therefore x = \sqrt{1525}$

$= 39.05$ (to 2 d.p.)

Set up an equation using Pythagoras' theorem and solve for x.

$\therefore$ The cable is 39.05 m long.

Answer the question in words.

Exercise 3C

1 | 1 | —

UNDERSTANDING

1 Match each problem (**a**, **b** or **c**) with both a diagram (**A**, **B** or **C**) and its solution (**I**, **II**, **III**).

a Two trees stand 20 m apart and they are 32 m and 47 m tall. What is the distance between the tops of the two trees?

A



b A man walks due north for 2 km then north-east for 3 km. How far north is he from his starting point?

B



c A kite is flying with a kite string of length 35 m. Its horizontal distance from its anchor point is 17 m. How high is the kite flying?

C



I The kite is flying at a height of 30.59 m.

II The distance between the top of the two trees is 25 m.

III The man has walked a total of 2 + 2.12 = 4.12 km north from his starting point.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

3C

2–5 | 2, 4, 6 | 2, 4, 6(½)

FLUENCY

Example 4

2 Two skyscrapers are located 25 m apart and a cable of length 62.3 m links the tops of the two buildings. If the taller building is 200 metres tall, what is the height of the shorter building? Give your answer correct to one decimal place.

3 Two poles are located 2 m apart. A wire links the tops of the two poles. Find the length of the wire if the poles are 2.8 m and 5 m in height. Give your answer correct to one decimal place.



4 A garage is to be built with a skillion roof (a roof with a single slope). The measurements are given in the diagram. Calculate the pitch line length, to the nearest millimetre. Allow 500 mm for each of the eaves.



5 Two bushwalkers are standing on different mountain sides. According to their maps, one of them is at a height of 2120 m and the other is at a height of 1650 m. If the horizontal distance between them is 950 m, find the direct distance between the two bushwalkers. Give your answer correct to the nearest metre.

6 Find the direct distance between the points A and B in each of the following, correct to one decimal place.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7, 8 | 8, 9 | 8–10

3C

PROBLEM-SOLVING

7 A 100 m radio mast is supported by six cables in two sets of three cables. They are anchored to the ground at an equal distance from the mast. The top set of three cables is attached at a point 20 m below the top of the mast. Each cable in the lower set of three cables is 60 m long and is attached at a height of 30 m above the ground. If all the cables have to be replaced, find the total length of cable required. Give your answer correct to two decimal places.

8 In a particular circle of radius 2 cm, AB is a diameter and C is a point on the circumference. Angle ACB is a right angle. The chord AC is 1 cm in length.



a Draw the triangle ABC as described, and mark in all the important information.

b Find the length of BC correct to one decimal place.

9 A suspension bridge is built with two vertical pylons and two straight beams of equal length that are positioned to extend from the top of the pylons to meet at a point C above the centre of the bridge, as shown in the diagram on the right.



a Calculate the vertical height of the point C above the tops of the pylons.

b Calculate the distance between the pylons, that is, the length of the span of the bridge correct to one decimal place.

10 Two circles of radii 10 cm and 15 cm respectively are placed inside a square. Find the perimeter of the square to the nearest centimetre. *Hint*: first find the diagonal length of the square using the diagram on the right.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3C

11 | 11 | 11, 12

REASONING

11 It is possible to find the length of the shorter sides of a right-angled isosceles triangle if only the hypotenuse length is known.

a Find the exact value of x in this right-angled isosceles triangle.



b Now find the exact value of a in this diagram.



c Finally, use your results from above to find the length of AB in this diagram correct to one decimal place.



12 Use the method outlined in Question **11** for this problem.

In an army navigation exercise, a group of soldiers hiked due south from base camp for 2.5 km to a water hole. From there, they turned 45° to the left, to head south-east for 1.6 km to a resting point. When the soldiers were at the resting point, how far (correct to one decimal place):

a east were they from the water hole?

b south were they from the water hole?

c were they in a straight line from base camp?

Folding paper

— | — | 13

ENRICHMENT

13 A square piece of paper, $ABCD$, of side length 20 cm is folded to form a right-angled triangle ABC. The paper is folded a second time to form a right-angled triangle ABE as shown in the diagram below.



a Find the length of AC correct to two decimal places.

b Find the perimeter of each of the following, correct to one decimal place where necessary:

i square $ABCD$ **ii** triangle ABC **iii** triangle ABE

c Use Pythagoras' theorem and your answer for part **a** to confirm that $AE = BE$ in triangle ABE.

d Investigate how changing the initial side length changes the answers to the above.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3D Pythagoras in three dimensions

EXTENDING

If you cut a solid to form a cross-section a two-dimensional shape is revealed. From that cross-section it may be possible to identify a right-angled triangle that can be used to find unknown lengths. These lengths can then tell us information about the three-dimensional solid.

You can visualise right-angled triangles in all sorts of different solids.



The glass pyramid at the Palais du Louvre, Paris, is made up of a total of 70 triangular and 603 rhombus-shaped glass segments together forming many right-angled triangles.

Let's start: How many triangles in a pyramid?

Here is a drawing of a square-based pyramid. By drawing lines from any vertex to the centre of the base and another point, how many different right-angled triangles can you visualise and draw? The triangles could be inside or on the outside surface of the pyramid.



- Right-angled triangles can be identified in many three-dimensional solids.
- It is important to try to draw any identified right-angled triangle using a separate diagram.



Key ideas

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 5 Using Pythagoras in 3D

The length of the diagonal on the base of a rectangular prism is 8.3 m and the rectangular prism's height is 3.9 m. Find the distance from one corner of the rectangular prism to the opposite corner. Give your answer correct to two decimal places.



SOLUTION

Let d m be the distance required.



$d^2 = 3.9^2 + 8.3^2$

$= 84.1$

$\therefore d = 9.17$ (to 2 d.p.)

The distance from one corner of the rectangular prism to the opposite corner is approximately 9.17 m.

EXPLANATION

Draw a right-angled triangle and label all the measurements and pronumerals.

Use Pythagoras' theorem.
Round $\sqrt{84.1}$ to two decimal places.

Write your answer in words.

Exercise 3D

1 | 1 | —

UNDERSTANDING

1 Decide if the following shaded regions would form right-angled triangles.

a



Right cylinder

b



Right cone

c



Cone

d



Cube

e



Cube

f



Rectangular prism

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

g



Triangular prism

h



Tetrahedron (regular triangular-based pyramid)

i



Right square-based pyramid (apex above centre of base)

Example 5

2 Find the distance, d units, from one corner to the opposite corner in each of the following rectangular prisms. Give your answers correct to two decimal places.

a



b



c



3 Find the slant height, s units, of each of the following cones. Give your answers correct to one decimal place.

a



b



c



4 Find the length to the nearest millimetre of the longest rod that will fit inside a cylinder of the following dimensions.

a Diameter 10 cm and height 15 cm

b Radius 2.8 mm and height 4.2 mm

c Diameter 0.034 m and height 0.015 m



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3D

FLUENCY

5 The cube in the diagram on the right has 1 cm sides.

a Find the length of AC as an exact value.

b Hence, find the length of AD correct to one decimal place.



6 Consider the shape shown.

a Find the length of AC as an exact value.

b Hence, find the length of AD correct to one decimal place.



PROBLEM-SOLVING

7 | 7, 8 | 8, 9

7 A miner makes claim to a circular piece of land with a radius of 40 m from a given point, and is entitled to dig to a depth of 25 m. If the miner can dig tunnels at any angle, find the length of the longest straight tunnel that he can dig, to the nearest metre.

8 A bowl is in the shape of a hemisphere (half sphere) with radius 10 cm. The surface of the water in the container has a radius of 7 cm. How deep is the water? Give your answer to two decimal places.

9 A cube of side length l sits inside a sphere of radius r so that the vertices of the cube sit on the sphere. Find the ratio $r : l$.

REASONING

10 | 10 | 10, 11

10 There are different ways to approach finding the height of a pyramid depending on what information is given. For each of the following square-based pyramids, find:

i the exact length (using a surd) of the diagonal on the base

ii the height of the pyramid correct to two decimal places.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 For this rectangular prism answer these questions.



- **a** Find the exact length AB.
- **b** Find AB correct to two decimal places.
- **c** Find the length AC using your result from part **a** and then round to two decimal places.
- **d** Find the length AC using your result from part **b** and then round to two decimal places.
- **e** How can you explain the difference between your results from parts **c** and **d** above?

Spider crawl — — 12

12 A spider crawls from one corner, A, of the ceiling of a room to the opposite corner, G, on the floor. The room is a rectangular prism with dimensions as given in the diagram on the right.



- **a** Assuming the spider crawls in a direct line between points, find how far (correct to two decimal places) the spider crawls if it crawls from A to G via:
  i B **ii** C **iii** D **iv** F
- **b** Investigate other paths to determine the shortest distance that the spider could crawl in order to travel from point A to point G. (*Hint*: consider drawing a net for the solid.)

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3E Trigonometric ratios

Interactive

Widgets

HOTsheets

Walkthroughs

The branch of mathematics called trigonometry deals with the relationship between the side lengths and angles in triangles. Trigonometry dates back to the ancient Egyptian and Babylonian civilisations where a basic form of trigonometry was used in the building of pyramids and in the study of astronomy. The first table of values including chord and arc lengths on a circle for a given angle was created by Hipparchus in the 2nd century BCE in Greece. These tables of values helped to calculate the position of the planets. About three centuries later, Claudius Ptolemy advanced the study of trigonometry writing 13 books called the *Almagest*. Ptolemy also developed tables of values linking the sides and angles of a triangle and produced many theorems which use the sine, cosine and tangent functions.

A basic form of trigonometry was used in the building of pyramids in ancient Egypt.

Let's start: Constancy of sine, cosine and tangent

In geometry we would say that similar triangles have the same shape but are of different size. Here are three similar right-angled triangles. The angle θ (theta) is the same for all three triangles.



We will now calculate three special ratios: sine, cosine and tangent for the angle θ in the above triangles. We use the sides labelled Hypotenuse (H), Opposite (O) and Adjacent (A) as shown at right.



- Complete this table simplifying all fractions.
- What do you notice about the value of:
  - **a** $\sin\theta$ $\left(\text{i.e. } \frac{\text{O}}{\text{H}}\right)$ for all three triangles?
  - **b** $\cos\theta$ $\left(\text{i.e. } \frac{\text{A}}{\text{H}}\right)$ for all three triangles?
  - **c** $\tan\theta$ $\left(\text{i.e. } \frac{\text{O}}{\text{A}}\right)$ for all three triangles?
- Why are the three ratios ($\sin\theta$, $\cos\theta$ and $\tan\theta$) the same for all three triangles? Discuss.

Triangle	$\frac{\text{O}}{\text{H}}$ ($\sin\theta$)	$\frac{\text{A}}{\text{H}}$ ($\cos\theta$)	$\frac{\text{O}}{\text{A}}$ ($\tan\theta$)
A	$\frac{5}{13}$		
B		$\frac{24}{26} = \frac{12}{13}$	
C			$\frac{15}{36} = \frac{5}{12}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- For a right-angled triangle with another angle named θ:
  - The **hypotenuse** is the longest side, opposite the 90° angle
  - The **opposite** side is opposite θ
  - The **adjacent** side is next to θ but not the hypotenuse.





- For a right-angled triangle with a given angle θ, the three ratios **sine (sin)**, **cosine (cos)** and **tangent (tan)** are given by:
  - sine of angle θ (or $\sin\theta$) $= \dfrac{\text{length of the opposite side}}{\text{length of the hypotenuse}}$
  - cosine of angle θ (or $\cos\theta$) $= \dfrac{\text{length of the adjacent side}}{\text{length of the hypotenuse}}$
  - tangent of angle θ (or $\tan\theta$) $= \dfrac{\text{length of the opposite side}}{\text{length of the adjacent side}}$
- For any right-angled triangle with the same angles, these ratios are always the same.
- The term **SOHCAHTOA** is useful when trying to remember the three ratios.

SOH CAH TOA

$\sin\theta = \dfrac{\text{Opposite}}{\text{Hypotenuse}}$ $\cos\theta = \dfrac{\text{Adjacent}}{\text{Hypotenuse}}$ $\tan\theta = \dfrac{\text{Opposite}}{\text{Adjacent}}$



Example 6 Labelling the sides of triangles

Copy this triangle and label the sides as opposite to θ (O), adjacent to θ (A) or hypotenuse (H).



SOLUTION



EXPLANATION

Draw the triangle and label the side opposite the right angle as hypotenuse (H), the side opposite the angle θ as opposite (O) and the remaining side next to the angle θ as adjacent (A).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 7 Writing trigonometric ratios

Write a trigonometric ratio (in fraction form) for each of the following triangles.

a



b



c



SOLUTION **EXPLANATION**

a $\cos\theta = \frac{A}{H}$

$= \frac{5}{7}$



Side length 7 is opposite the right angle so it is the hypotenuse (H). Side length 5 is adjacent to angle θ so it is the adjacent (A).

b $\sin\theta = \frac{O}{H}$

$= \frac{4}{9}$



Side length 9 is opposite the right angle so it is the hypotenuse (H). Side length 4 is opposite angle θ so it is the opposite (O).

c $\tan\theta = \frac{O}{A}$

$= \frac{3}{5}$



Side length 5 is the adjacent side to angle θ so it is the adjacent (A). Side length 3 is opposite angle θ so it is the opposite (O).

Exercise 3E

1, 2(½), 3 | 3 | —

UNDERSTANDING

1 Write the missing word in these sentences.

a H stands for the word _____.

b O stands for the word _____.

c A stands for the word _____.

d sin θ = _____ ÷ Hypotenuse.

e cos θ = Adjacent ÷ _____.

f tan θ = Opposite ÷ _____.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3E

UNDERSTANDING

Example 6

2 Copy each of these triangles and label the sides as opposite to θ (O), adjacent to θ (A) or hypotenuse (H).

a



b



c



d



e



f



g



h



3 For the triangle shown, state the length of the side which corresponds to:

a the hypotenuse
b the side opposite angle θ
c the side opposite angle α
d the side adjacent to angle θ
e the side adjacent to angle α.



4–6 | 4(½), 5–7 | 4(½), 5, 6(½), 7

FLUENCY

Example 7

4 Write a trigonometric ratio (in fraction form) for each of the following triangles and simplify where possible.

a



b



c



d



e



f



g



h



i



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3E

FLUENCY

5 Here are two similar triangles A and B.



a i Write the ratio sin θ (as a fraction) for triangle A.
ii Write the ratio sin θ (as a fraction) for triangle B.
iii What do you notice about your two answers from parts **a i** and **a ii** above?

b i Write the ratio cos θ (as a fraction) for triangle A.
ii Write the ratio cos θ (as a fraction) for triangle B.
iii What do you notice about your two answers from parts **b i** and **b ii** above?

c i Write the ratio tan θ (as a fraction) for triangle A.
ii Write the ratio tan θ (as a fraction) for triangle B.
iii What do you notice about your two answers from parts **c i** and **c ii** above?

6 For each of these triangles, write a ratio (in simplified fraction form) for sin θ, cos θ and tan θ.

a



b



c



7 For the triangle shown on the right, write a ratio (in fraction form) for:

a sin θ **b** sin α **c** cos θ
d tan α **e** cos α **f** tan θ



8, 9 | 9, 10 | 10, 11

PROBLEM-SOLVING

8 A vertical flag pole casts a shadow 20 m long. If the pole is 15 m high, find the ratio for tan θ.



We can use trigonometry to calculate the angle of the shadow that the pole casts.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3E

PROBLEM-SOLVING

9 The facade of a Roman temple has the given measurements below. Write down the ratio for:

- **a** $\sin\theta$
- **b** $\cos\theta$
- **c** $\tan\theta$

The Pantheon, a Roman temple that was built in 126 CE.

10 For each of the following:

- **i** use Pythagoras' theorem to find the unknown side.
- **ii** find the ratios for $\sin\theta$, $\cos\theta$ and $\tan\theta$.

a



b



c



d



11 **a** Draw a right-angled triangle and mark one of the angles as θ. Mark in the length of the opposite side as 15 units and the length of the hypotenuse as 17 units.

- **b** Using Pythagoras' theorem, find the length of the adjacent side.
- **c** Determine the ratios for $\sin\theta$, $\cos\theta$ and $\tan\theta$.

12 | 12, 13 | 12–14

REASONING

12 This triangle has angles 90°, 60° and 30° and side lengths 1, 2 and $\sqrt{3}$.



- **a** Write a ratio for:
  - **i** $\sin 30°$ **ii** $\cos 30°$ **iii** $\tan 30°$
  - **iv** $\sin 60°$ **v** $\cos 60°$ **vi** $\tan 60°$
- **b** What do you notice about the following pairs of ratios?
  - **i** $\cos 30°$ and $\sin 60°$
  - **ii** $\sin 30°$ and $\cos 60°$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3E

REASONING

13 **a** Measure all the side lengths of this triangle to the nearest millimetre.



b Use your measurements from part **a** to find an approximate ratio for:

i cos 40° **ii** sin 40° **iii** tan 40°

iv sin 50° **v** tan 50° **vi** cos 50°

c Do you notice anything about the trigonometric ratios for 40° and 50°?

14 Decide if it is possible to draw a right-angled triangle with the given properties. Explain.

a $\tan\theta = 1$ **b** $\sin\theta = 1$

c $\cos\theta = 0$ **d** $\sin\theta > 1$ or $\cos\theta > 1$

ENRICHMENT

Pythagorean extensions — — 15

15 **a** Given that θ is acute and $\cos\theta = \frac{4}{5}$, find $\sin\theta$ and $\tan\theta$.

Hint: use Pythagoras' theorem.



b For each of the following, draw a right-angled triangle then use it to find the other two trigonometric ratios.

i $\sin\theta = \frac{1}{2}$ **ii** $\cos\theta = \frac{1}{2}$ **iii** $\tan\theta = 1$

c Use your results from part **a** to calculate $(\cos\theta)^2 + (\sin\theta)^2$. What do you notice?

d Evaluate $(\cos\theta)^2 + (\sin\theta)^2$ for other combinations of $\cos\theta$ and $\sin\theta$. Research and describe what you have found.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F Finding side lengths

Interactive

Widgets

HOTsheets

Walkthroughs

For similar triangles we know that the ratio of corresponding sides is always the same. This implies that the three trigonometric ratios for similar right-angled triangles are also constant if the internal angles are equal. Since ancient times, mathematicians have attempted to tabulate these ratios for varying angles. Here are the ratios for some angles in a right-angled triangle, correct to three decimal places.

Angle (θ)	sin θ	cos θ	tan θ
0°	0	1	0
15°	0.259	0.966	0.268
30°	0.5	0.866	0.577
45°	0.707	0.707	1
60°	0.866	0.5	1.732
75°	0.966	0.259	3.732
90°	1	0	undefined



Trigonometric tables in a 400-year old European book.

In modern times these values can be evaluated using calculators to a high degree of accuracy and can be used to help solve problems involving triangles with unknown side lengths.

Let's start: Calculator start-up

All scientific or CAS calculators can produce accurate values of sin θ, cos θ and tan θ.

- Ensure that your calculator is in degree mode.
- Check the values in the above table to ensure that you are using the calculator correctly.
- Use trial and error to find (to the nearest degree) an angle θ which satisfies these conditions:

a sin $\theta = 0.454$ **b** cos $\theta = 0.588$ **c** tan $\theta = 9.514$

Key ideas

- If θ is in degrees, the ratios for sin θ, cos θ and tan θ can accurately be found using a calculator in **degree mode**.
- If the angles and one side length of a right-angled triangle are known then the other side lengths can be found using the sin θ, cos θ or tan θ ratios.



$\sin 30^\circ = \frac{x}{3}$

$\therefore x = 3 \times \sin 30^\circ$



$\cos 42^\circ = \frac{x}{7.2}$

$\therefore x = 7.2 \times \cos 42^\circ$



$\tan 71^\circ = \frac{x}{4}$

$\therefore x = 4 \times \tan 71^\circ$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 8 Using a calculator

Use a calculator to evaluate the following, correct to two decimal places.

a $\sin 50°$ **b** $\cos 16°$ **c** $\tan 77°$

SOLUTION	EXPLANATION
a $\sin 50° = 0.77$ (to 2 d.p.)	$\sin 50° = 0.766044...$ the 3rd decimal place is greater than 4 so round up.
b $\cos 16° = 0.96$ (to 2 d.p.)	$\cos 16° = 0.961261...$ the 3rd decimal place is less than 5 so round down.
c $\tan 77° = 4.33$ (to 2 d.p.)	$\tan 77° = 4.331475...$ the 3rd decimal place is less than 5 so round down.

Example 9 Solving for x in the numerator of a trigonometric ratio

Find the value of x in the equation $\cos 20° = \frac{x}{3}$, correct to two decimal places.

SOLUTION	EXPLANATION
$\cos 20° = \frac{x}{3}$	
$x = 3 \times \cos 20°$ $= 2.82$ (to 2 d.p.)	Multiply both sides of the equation by 3 and round as required.

Example 10 Finding side lengths

For each triangle, find the value of x correct to two decimal places.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION	
a $\sin 38^\circ = \frac{O}{H}$ $\sin 38^\circ = \frac{x}{7}$ $x = 7 \sin 38^\circ$ $= 4.31$ (to 2 d.p.)	Since the opposite side (O) and the hypotenuse (H) are involved, the sin θ ratio must be used. Multiply both sides by 7 and evaluate using a calculator.	
b $\tan 42^\circ = \frac{O}{A}$ $\tan 42^\circ = \frac{x}{4}$ $x = 4 \tan 42^\circ$ $= 3.60$ (to 2 d.p.)	Since the opposite side (O) and the adjacent side (A) are involved, the tan θ ratio must be used. Multiply both sides by 4 and evaluate.	
c $\cos 24^\circ = \frac{A}{H}$ $\cos 24^\circ = \frac{x}{10}$ $x = 10 \cos 24^\circ$ $= 9.14$ (to 2 d.p.)	Since the adjacent side (A) and the hypotenuse (H) are involved, the cos θ ratio must be used. Multiply both sides by 10.	

Exercise 3F

1–3 | 3(½) | —

UNDERSTANDING

1 For the marked angle θ, decide if x represents the length of the opposite (O), adjacent (A) or hypotenuse (H) side.

a



b



c



2 Decide if you would use $\sin \theta = \frac{O}{H}$, $\cos \theta = \frac{A}{H}$ or $\tan \theta = \frac{O}{A}$ to help find the value of x in these triangles. Do not find the value of x, just state which ratio would be used.

a



b



c



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

3F

UNDERSTANDING

Example 8

3 Use a calculator to evaluate the following correct to two decimal places.

a $\sin 20°$ **b** $\cos 37°$ **c** $\tan 64°$ **d** $\sin 47°$

e $\cos 84°$ **f** $\tan 14.1°$ **g** $\sin 27.4°$ **h** $\cos 76.2°$

4–5(½) 4–5(½) 4–5(½)

FLUENCY

Example 9

4 In each of the following, find the value of x correct to two decimal places.

a $\sin 50° = \frac{x}{4}$ **b** $\tan 81° = \frac{x}{3}$ **c** $\cos 33° = \frac{x}{6}$

d $\cos 75° = \frac{x}{3.5}$ **e** $\sin 24° = \frac{x}{4.2}$ **f** $\tan 42° = \frac{x}{10}$

g $\frac{x}{7.1} = \tan 18.4°$ **h** $\frac{x}{5.3} = \sin 64.7°$ **i** $\frac{x}{12.6} = \cos 52.9°$

Example 10

5 For the triangles given below, find the value of x correct to two decimal places.

a



b



c



d



e



f



g



h



i



j



k



l



m



n



o



p



6, 7 6–8 7–9

PROBLEM-SOLVING

6 Amy walks 5.4 m up a ramp which is inclined at 12° to the horizontal. How high (correct to two decimal places) is she above her starting point?



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F

PROBLEM-SOLVING

7 Kane wanted to measure the width of a river. He placed two markers, A and B, 72 m apart along the bank. C is a point directly opposite marker B. Kane measured angle CAB to be 32°. Find the width of the river correct to two decimal places.



8 One end of a 12.2 m rope is tied to a boat. The other end is tied to an anchor, which is holding the boat steady in the water. If the anchor is making an angle of 34° with the vertical, how deep is the water? Give your answer correct to two decimal places.



9 Find the length AB in these diagrams. Round to two decimal places where necessary.

a



b



10 | 10 | 10, 11

REASONING

10 Consider the right-angled triangle shown.



a Find the size of $\angle C$.

b Calculate the value of x correct to three decimal places using the sine ratio.

c Calculate the value of x correct to three decimal places but instead use the cosine ratio.

d Comment on your answers to parts **b** and **c**.

11 Complementary angles sum to 90°.

a Find the complementary angles to these angles.

i 10° **ii** 28° **iii** 54° **iv** 81°

b Evaluate:

i sin 10° and cos 80° **ii** sin 28° and cos 62°

iii cos 54° and sin 36° **iv** cos 81° and sin 9°

c What do you notice in part **b**?

d Complete the following.

i sin 20° = cos _____ **ii** sin 59° = cos _____

iii cos 36° = sin _____ **iv** cos 73° = sin _____

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F Exact values — — 12

ENRICHMENT

12 $\sqrt{2}, \sqrt{3}$ and $\frac{1}{\sqrt{2}}$ are examples of exact values.



a For the triangle shown (right), use Pythagoras' theorem to find the exact length BC.

b Use your result from part **a** to write down the exact values of:

i $\sin 45°$ **ii** $\cos 45°$ **iii** $\tan 45°$

c For this triangle (right) use Pythagoras' theorem to find the exact length BC.



d Use your result from part **c** to write down the exact values of:

i $\sin 30°$ **ii** $\cos 30°$ **iii** $\tan 30°$

iv $\sin 60°$ **v** $\cos 60°$ **vi** $\tan 60°$



This diagram by the third century AD Chinese mathematician Liu Hui shows how to measure the height of a mountain on a sea island using right-angled triangles. This method of surveying became known as triangulation.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G Solving for the denominator

So far we have constructed trigonometric ratios using a pronumeral which has always appeared in the numerator.

For example: $\frac{x}{5} = \sin 40°$.

This makes it easy to solve for x where both sides of the equation can be multiplied by 5.

If, however, the pronumeral appears in the denominator there are a number of algebraic steps that can be taken to find the solution.

Let's start: Solution steps

Three students attempt to solve $\sin 40° = \frac{5}{x}$ for x.

Nick says $x = 5 \times \sin 40°$

Sharee says $x = \frac{5}{\sin 40°}$

Dori says $x = \frac{1}{5} \times \sin 40°$

- Which student has the correct solution?
- Can you show the algebraic steps that support the correct answer?

Key ideas

- If the unknown value of a trigonometric ratio is in the **denominator**, you need to rearrange the equation to make the pronumeral the subject.

For example: For the triangle shown, $\cos 30° = \frac{5}{x}$

Multiplying both sides by x $\quad x \times \cos 30° = 5$

Dividing both sides by $\cos 30°$ $\quad x = \frac{5}{\cos 30°}$



Example 11 Solving for x in the denominator

Solve for x in the equation $\cos 35° = \frac{2}{x}$, correct to two decimal places.

SOLUTION	EXPLANATION
$\cos 35° = \frac{2}{x}$	
$x \cos 35° = 2$	Multiply both sides of the equation by x.
$x = \frac{2}{\cos 35°}$	Divide both sides of the equation by $\cos 35°$.
$= 2.44$ (to 2 d.p.)	Evaluate and round to two decimal places.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Finding side lengths

Find the values of the pronumerals correct to two decimal places.

a



b



SOLUTION

a

$$\sin 35° = \frac{O}{H}$$

$$\sin 35° = \frac{5}{x}$$

$$x \sin 35° = 5$$

$$x = \frac{5}{\sin 35°}$$

$$= 8.72 \text{ (to 2 d.p.)}$$

b

$$\tan 28° = \frac{O}{A}$$

$$\tan 28° = \frac{19}{x}$$

$$x \tan 28° = 19$$

$$x = \frac{19}{\tan 28°}$$

$$= 35.73 \text{ (to 2 d.p.)}$$

$$y^2 = x^2 + 19^2$$

$$= 1637.904\ldots$$

$$y = \sqrt{1637.904\ldots}$$

$$\therefore y = 40.47 \text{ (to 2 d.p.)}$$

EXPLANATION

Since the opposite side (O) is given and we require the hypotenuse (H), use $\sin \theta$.



Multiply both sides of the equation by x then divide both sides of the equation by $\sin 35°$.

Evaluate on a calculator and round to two decimal places.

Since the opposite side (O) is given and the adjacent (A) is required, use $\tan \theta$.



Multiply both sides of the equation by x.

Divide both sides of the equation by $\tan 28°$ and round the answer to two decimal places.

Find y by using Pythagoras' theorem and substitute the exact value of x, i.e. $\frac{19}{\tan 28°}$

Alternatively, y can be found by using $\sin \theta$.



Exercise 3G

1–2(½) | 2(½) | —

UNDERSTANDING

1 Solve these simple equations for x.

a $\frac{4}{x} = 2$ **b** $\frac{20}{x} = 4$ **c** $\frac{15}{x} = 5$ **d** $25 = \frac{100}{x}$

e $5 = \frac{35}{x}$ **f** $\frac{10}{x} = 2.5$ **g** $\frac{2.5}{x} = 5$ **h** $12 = \frac{2.4}{x}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

3G

UNDERSTANDING

Example 11

2 For each of the following equations, find the value of x correct to two decimal places.

a $\cos 43° = \frac{3}{x}$ **b** $\sin 36° = \frac{4}{x}$ **c** $\tan 9° = \frac{6}{x}$

d $\tan 64° = \frac{2}{x}$ **e** $\cos 67° = \frac{5}{x}$ **f** $\sin 12° = \frac{3}{x}$

g $\sin 38.3° = \frac{5.9}{x}$ **h** $\frac{45}{x} = \tan 21.4°$ **i** $\frac{18.7}{x} = \cos 32°$

3–4(½) 3–4(½) 3–4(½)

FLUENCY

Example 12a

3 Find the value of x correct to two decimal places using the sine, cosine or tangent ratios.

a 

b 

c 

d 

e 

f 

g 

h 

i 

j 

k 

l 

Example 12b

4 Find the value of each pronumeral correct to one decimal place.

a 

b 

c 

d 

e 

f 

g 

h 

5, 6 5, 6, 7a 6, 7

PROBLEM-SOLVING

5 A kite is flying at a height of 27 m above the anchor point. If the string is inclined at 42° to the horizontal, find the length of the string, correct to the nearest metre.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G

PROBLEM-SOLVING

6 A paraglider flying at a height of 800 m descends at an angle of 12° to the horizontal. How far (to the nearest metre) has it travelled in descending to the ground?



7 Find the perimeter of these triangles, correct to one decimal place.

a



b



REASONING

8	8	8

8 In calculating the value of x for this triangle, correct to two decimal places, two students come up with these answers.



A $x = \dfrac{5}{\sin 31°} = \dfrac{5}{0.52} = 9.62$ **B** $x = \dfrac{5}{\sin 31°} = 9.71$

a Which of the above two answers is more correct and why?

b What advice would you give to the student whose answer is not accurate?

c Find the difference in the answers if the different methods (A and B) are used to calculate the value of x correct to two decimal places in these triangles.

i



ii



ENRICHMENT

Linking tan θ to sin θ and cos θ

—	—	9

9 a For this triangle find, correct to three decimal places:

i AB **ii** BC



b Calculate these ratios to two decimal places.

i $\sin 20°$ **ii** $\cos 20°$ **iii** $\tan 20°$

c Evaluate $\dfrac{\sin 20°}{\cos 20°}$ using your results from part **b**. What do you notice?

d For this triangle with side lengths a, b and c, find an expression for:



i $\sin\theta$ **ii** $\cos\theta$ **iii** $\tan\theta$ **iv** $\dfrac{\sin\theta}{\cos\theta}$

e Simplify your expression for part **d iv**. What do you notice?

Using a CAS calculator 3G: Trigonometry

This activity is in the interactive textbook in the form of a printable PDF.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Progress quiz

3A/B **1** Find the length of the missing side in these right-angled triangles. Round to two decimal places.

a



b



3A/B **2** Find the exact value of x in these right-angled triangles.

a



b



3C **3** A ladder 230 cm long is placed 50 cm from the edge of a building, how far up the side of the building will this ladder reach? Round to one decimal place.

3D **4** Find the length of the diagonals of these prisms, correct to one decimal place.

a



b



3E **5** Consider the triangle ABC.



a Name the hypotenuse.

b Name the side adjacent to angle ACB.

c Write the ratio for $\cos\ \theta$.

d Write the ratio for $\tan\ \theta$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F/G **6** Solve for x, correct to two decimal places.

a $x = 12.7 \cos 54°$

b $\tan 30° = \frac{x}{12}$

c $\sin 56° = \frac{58.4}{x}$

3F/G **7** Find the values of the pronumerals, correct to two decimal places.

a



b



c



3G **8** Find the perimeter of this triangle, correct to two decimal places.



3A–G **9** Triangle ABC is equilateral with a perimeter of 12 cm.



Find:

a the height AD using any suitable method, correct to three decimal places

b the area of the triangle ABC, correct to one decimal place.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3H Finding an angle

Interactive

Widgets

HOTsheets

Walkthroughs

Logically, if you can use trigonometry to find a side length of a right-angled triangle given one angle and one side, you should be able to find an angle if you are given two sides.



We know that $\sin 30° = \frac{1}{2}$ so if we were to determine θ if $\sin\ \theta = \frac{1}{2}$, the answer would be $\theta = 30°$.

We write this as $\theta = \sin^{-1}\left(\frac{1}{2}\right) = 30°$ and we say that the inverse sine of $\frac{1}{2}$ is 30°.

Calculators can be used to help solve problems using inverse sine ($\sin^{-1}$), inverse cosine ($\cos^{-1}$) and inverse tangent ($\tan^{-1}$). For angles in degrees, ensure your calculator is in degree mode.

Let's start: Trial and error can be slow

We know that for this triangle, $\sin\ \theta = \frac{1}{3}$.



- Guess the angle θ.
- For your guess use a calculator to see if $\sin\ \theta = \frac{1}{3} = 0.333\ldots$
- Update your guess and use your calculator to check once again.
- Repeat this trial-and-error process until you think you have the angle θ correct to three decimal places.
- Now evaluate $\sin^{-1}\left(\frac{1}{3}\right)$ and check your guess.

Key ideas

- **Inverse sine** ($\sin^{-1}$), **inverse cosine** ($\cos^{-1}$) and **inverse tangent** ($\tan^{-1}$) can be used to find angles in right-angled triangles.
  - $\sin\ \theta = \frac{a}{c}$ means $\theta = \sin^{-1}\left(\frac{a}{c}\right)$
  - $\cos\ \theta = \frac{b}{c}$ means $\theta = \cos^{-1}\left(\frac{b}{c}\right)$
  - $\tan\ \theta = \frac{a}{b}$ means $\theta = \tan^{-1}\left(\frac{a}{b}\right)$
- Note that $\sin^{-1} x$ does *not* mean $\frac{1}{\sin x}$.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Using inverse trigonometric ratios

Find the value of θ to the level of accuracy indicated.

a $\sin\theta = 0.3907$ (nearest degree)

b $\tan\theta = \frac{1}{2}$ (one decimal place)

SOLUTION

a $\sin\theta = 0.3907$

$\theta = \sin^{-1}(0.3907)$

$= 23°$ (to nearest degree)

EXPLANATION

Use the $\sin^{-1}$ key on your calculator.

Round to the nearest whole number.

b $\tan\theta = \frac{1}{2}$

$\theta = \tan^{-1}\left(\frac{1}{2}\right)$

$= 26.6°$ (to 1 d.p.)

Use the $\tan^{-1}$ key on your calculator and round the answer to one decimal place.

Example 14 Finding an angle

Find the value of θ to the nearest degree.



SOLUTION

$\sin\theta = \frac{O}{H}$

$= \frac{6}{10}$

$\theta = \sin^{-1}\left(\frac{6}{10}\right)$

$= 37°$ (to the nearest degree)

EXPLANATION

Since the opposite side (O) and the hypotenuse (H) are given, use $\sin\theta$.



Use the $\sin^{-1}$ key on your calculator and round as required.

Exercise 3H

1, 2, 3(½), 4 | 4 | —

UNDERSTANDING

1 Use a calculator to evaluate the following rounding to two decimal places.

a $\sin^{-1}(0.2)$ **b** $\sin^{-1}(0.9)$ **c** $\cos^{-1}(0.75)$

d $\cos^{-1}(0.43)$ **e** $\tan^{-1}(0.5)$ **f** $\tan^{-1}(2.5)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3H

UNDERSTANDING

2 Write the missing number.

a If $\sin 30° = \frac{1}{2}$ then $30° = \sin^{-1}(_____)$.

b If $\cos 50° = 0.64$ then $_____ = \cos^{-1}(0.64)$.

c If $\tan 45° = 1$ then $_____ = \tan^{-1}(_____)$.

3 Evaluate each of the following to the nearest degree.

a $\sin^{-1}(0.7324)$ **b** $\cos^{-1}(0.9763)$ **c** $\tan^{-1}(0.3321)$

d $\tan^{-1}(1.235)$ **e** $\sin^{-1}(0.4126)$ **f** $\cos^{-1}(0.7462)$

g $\cos^{-1}(0.1971)$ **h** $\sin^{-1}(0.2247)$ **i** $\tan^{-1}(0.0541)$

4 Which trigonometric ratio should be used to solve for θ?

a



b



c



d



5–6(½), 7 | 5–7(½) | 5–7(½)

FLUENCY

Example 13a

5 Find the value of θ to the nearest degree.

a $\sin\theta = 0.5$ **b** $\cos\theta = 0.5$ **c** $\tan\theta = 1$

d $\cos\theta = 0.8660$ **e** $\sin\theta = 0.7071$ **f** $\tan\theta = 0.5774$

g $\sin\theta = 1$ **h** $\tan\theta = 1.192$ **i** $\cos\theta = 0$

j $\cos\theta = 0.5736$ **k** $\cos\theta = 1$ **l** $\sin\theta = 0.9397$

Example 13b

6 Find the angle θ correct to two decimal places.

a $\sin\theta = \frac{4}{7}$ **b** $\sin\theta = \frac{1}{3}$ **c** $\sin\theta = \frac{9}{10}$

d $\cos\theta = \frac{1}{4}$ **e** $\cos\theta = \frac{4}{5}$ **f** $\cos\theta = \frac{7}{9}$

g $\tan\theta = \frac{3}{5}$ **h** $\tan\theta = \frac{8}{5}$ **i** $\tan\theta = 12$

Example 14

7 Find the value of θ to the nearest degree.

a



b



c



d



e



f



g



h



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3H

8–10 | 9–11 | 10–12

PROBLEM-SOLVING

8 A road rises at a grade of 3 in 10. Find the angle (to the nearest degree) the road makes with the horizontal.



9 When a 2.8 m long seesaw is at its maximum height it is 1.1 m off the ground. What angle (correct to two decimal places) does the seesaw make with the ground?

10 Adam, who is 1.8 m tall, holds up a plank of wood 4.2 m long. Find the angle that the plank makes with the ground, correct to one decimal place.



11 A children's slide has a length of 5.8 m. The vertical ladder is 2.6 m above the ground. Find the angle the slide makes with the ground, correct to one decimal place.



12 Find the value of θ in these diagrams, correct to one decimal place.

a



b



c



13 | 13, 14 | 14, 15

REASONING

13 Find all the angles to the nearest degree in right-angled triangles with these side lengths.

a 3, 4, 5 **b** 5, 12, 13 **c** 7, 24, 25

14 For what value of θ is $\sin\theta = \cos\theta$?

15 If M is the midpoint of AB, decide if $\angle ACM$ is exactly half of angle $\angle ACB$. Investigate and explain.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Viewing angle — — 16

3H

ENRICHMENT

16 Jo has forgotten her glasses and is trying to view a painting in a gallery. Her eye level is at the same level as the base of the painting and the painting is 1 metre tall.
Answer the following to the nearest degree for angles and to two decimal places for lengths.



a If $x = 3$, find the viewing angle θ.
b If $x = 2$, find the viewing angle θ.
c If Jo can stand no closer than 1 metre to the painting, what is Jo's largest viewing angle?
d When the viewing angle is 10°, Jo has trouble seeing the painting. How far is she from the painting at this viewing angle?
e Theoretically, what would be the largest viewing angle if Jo could go as close as she would like to the painting?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3I Applying trigonometry EXTENDING

In many situations, angles are measured up or down from the horizontal. These are called angles of elevation and depression. Combined with the mathematics of trigonometry, these angles can be used to solve problems, provided right-angled triangles can be identified. The line of sight to a helicopter 100 m above the ground, for example, creates an angle of elevation inside a right-angled triangle.

Let's start: Illustrate the situation

For the situation below, draw a detailed diagram showing these features:

- an angle of elevation
- an angle of depression
- any given lengths
- a right-angled triangle that will help to solve the problem

A cat and a bird eye each other from their respective positions. The bird is 20 m up a tree and the cat is on the ground 30 m from the base of the tree. Find the angle their line of sight makes with the horizontal.

Compare your diagram with others in your class. Is there more than one triangle that could be drawn and used to solve the problem?

Key ideas

- To solve application problems involving trigonometry follow these steps.
  1. Draw a diagram and label the key information.
  2. Identify and draw the appropriate right-angled triangles separately.
  3. Solve using trigonometry to find the missing measurements.
  4. Express your answer in words.
- The **angle of elevation** or **depression** of a point, Q, from another point, P, is given by the angle the line PQ makes with the horizontal.





- Angles of elevation or depression are always measured from the horizontal.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- In this diagram the angle of elevation of B from A is equal to the angle of depression of A from B. They are equal alternate angles in parallel lines.



Example 15 Using angles of elevation

The angle of elevation of the top of a tower from a point on the ground 30 m away from the base of the tower is 28°. Find the height of the tower to the nearest metre.



Angle of elevation

SOLUTION

Let the height of the tower be h m.

$$\tan 28^\circ = \frac{\text{O}}{\text{A}}$$

$$= \frac{h}{30}$$

$$h = 30 \tan 28^\circ$$

$$= 15.951\ldots$$

The height is 16 m, to the nearest metre.

EXPLANATION

Since the opposite side (O) is required and the adjacent (A) is given, use $\tan\ \theta$.



Multiply both sides by 30 and evaluate. Round to the nearest metre and write the answer in words.

Example 16 Finding an angle of depression

From the top of a vertical cliff Andrea spots a boat out at sea. If the top of the cliff is 42 m above sea level and the boat is 90 m away from the base of the cliff, find Andrea's angle of depression to the boat to the nearest degree.

SOLUTION



EXPLANATION

Draw a diagram and label all the given measurements.

Use alternate angles in parallel lines to mark θ inside the triangle.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

$\tan\theta = \frac{O}{A}$

$= \frac{42}{90}$

$\theta = \tan^{-1}\left(\frac{42}{90}\right)$

$\theta = 25.0168\ldots°$

The angle of depression is 25°, to the nearest degree.

Since the opposite (O) and adjacent sides (A) are given, use $\tan\theta$.

Use the $\tan^{-1}$ key on your calculator. Round to the nearest degree and express the answer in words.

Example 17 Applying trigonometry

A plane flying at an altitude of 1500 m starts to climb at an angle of 15° to the horizontal when the pilot sees a mountain peak 2120 m high, 2400 m away from him horizontally. Will the pilot clear the mountain?



SOLUTION



EXPLANATION

Draw a diagram, identifying and labelling the right-angled triangle to help solve the problem. The plane will clear the mountain if the opposite (O) is greater than

(2120 – 1500) m = 620 m.

$\tan 15° = \frac{x}{2400}$

Set up the trigonometric ratio using tan.

$x = 2400\tan 15°$

$= 643.078\ldots$

Multiply by 2400 and evaluate.

x needs to be greater than
2120 – 1500 = 620

Since $x > 620$ the plane will clear the mountain peak.

Answer the question in words.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 3I

1–3 | 3 | —

UNDERSTANDING

1 Find the values of the pronumerals in this diagram.



2 For this diagram:

a what is the angle of elevation of B from A?

b what is the angle of depression of A from B?



3 Draw this diagram and complete these tasks.

a Mark in the following:

i the angle of elevation (θ) of B from A

ii the angle of depression (α) of A from B.

b Is $\theta = \alpha$ in your diagram? Why?



4–9 | 4–6, 8–10 | 4, 6, 8–11

FLUENCY

Example 15

4 The angle of elevation of the top of a tower from a point on the ground 40 m from the base of the tower is 36°. Find the height of the tower to the nearest metre.



5 The angle of elevation of the top of a castle wall from a point on the ground 25 m from the base of the castle wall is 32°. Find the height of the castle wall to the nearest metre.

6 From a point on the ground, Emma measures the angle of elevation of an 80 m tower to be 27°. Find how far Emma is from the base of the tower, correct to the nearest metre.

7 From a pedestrian overpass, Chris spots a landmark at an angle of depression of 32°. How far away (to the nearest metre) is the landmark from the base of the 24 m high overpass?



8 From a lookout tower, David spots a bushfire at an angle of depression of 25°. If the lookout tower is 42 m high, how far away (to the nearest metre) is the bushfire from the base of the tower?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

3I

FLUENCY

Example 16

9 From the top of a vertical cliff, Josh spots a swimmer out at sea. If the top of the cliff is 38 m above sea level and the swimmer is 50 m away from the base of the cliff, find the angle of depression from Josh to the swimmer, to the nearest degree.

10 From a ship, a person is spotted floating in the sea 200 m away. If the viewing position on the ship is 20 m above sea level, find the angle of depression from the ship to person in the sea. Give your answer to the nearest degree.

11 A power line is stretched from a pole to the top of a house. The house is 4.1 m high and the power pole is 6.2 m high. The horizontal distance between the house and the power pole is 12 m. Find the angle of elevation of the top of the power pole from the top of the house, to the nearest degree.

12, 13 | 12–14 | 12, 15, 16

PROBLEM-SOLVING

Example 17

12 A plane flying at 1850 m starts to climb at an angle of 18° to the horizontal when the pilot sees a mountain peak 2450 m high, 2600 m away from him in a horizontal direction. Will the pilot clear the mountain?



13 A road has a steady gradient of 1 in 10.

a What angle does the road make with the horizontal? Give your answer to the nearest degree.

b A car starts from the bottom of the inclined road and drives 2 km along the road. How high vertically has the car climbed? Use your rounded answer from part **a** and give your answer correct to the nearest metre.

14 A house is to be built using the design shown on the right. The eaves are 600 mm and the house is 7200 mm wide, excluding the eaves. Calculate the length (to the nearest mm) of a sloping edge of the roof, which is pitched at 25° to the horizontal.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

15 A garage is to be built with measurements as shown in the diagram on the right. Calculate the sloping length and pitch (angle) of the roof if the eaves extend 500 mm on each side. Give your answers correct to the nearest unit.



16 The chains on a swing are 3.2 m long and the seat is 0.5 m off the ground when it is in the vertical position. When the swing is pulled as far back as possible, the chains make an angle of 40° with the vertical. How high off the ground, to the nearest cm, is the seat when it is at this extreme position?

17 | 17 | 17, 18

17 A person views a vertical monument x metres away as shown.



a If $h = 1.5$, $x = 20$ and $\theta = 15°$ find the height of the monument to two decimal places.

b If $h = 1.5$, $x = 20$ and $y = 10$ find θ correct to one decimal place.

c Let the height of the monument be m metres. Write expressions for the following:

- **i** m using (in terms of) y and h.
- **ii** y using x and θ.
- **iii** m using (in terms of) x, θ and h.

18 Find an expression for the area of this triangle using a and θ.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

3I Plane trigonometry — — 19–21

ENRICHMENT

19 An aeroplane takes off and climbs at an angle of 20° to the horizontal, at 190 km/h along its flight path for 15 minutes.

- **a** Find:
  - **i** the distance the aeroplane travels in 15 minutes
  - **ii** the height the aeroplane reaches after 15 minutes correct to two decimal places.
- **b** If the angle at which the plane climbs is twice the original angle but its speed is halved will it reach a greater height after 15 minutes? Explain.
- **c** If the plane's speed is doubled and its climbing angle is halved, will the plane reach a greater height after 15 minutes? Explain.

20 The residents of Skeville live 12 km from an airport. They maintain that any plane flying lower than 4 km disturbs their peace. Each Sunday they have an outdoor concert from 12:00 noon till 2:00 pm.

- **a** Will a plane taking off from the airport at an angle of 15° over Skeville disturb the residents?
- **b** When the plane in part **a** is directly above Skeville, how far (to the nearest metre) has it flown?
- **c** If the plane leaves the airport at 11:50 am on Sunday and travels at an average speed of 180 km/h, will it disturb the start of the concert?
- **d** Investigate what average speed (correct to the nearest km/h) the plane can travel at so that it does not disturb the concert. Assume it leaves at 11:50 am.

21 Peter observes a plane flying directly overhead at a height of 820 m. Twenty seconds later, the angle of elevation of the plane from Peter is 32°. Assume the plane flies horizontally.

- **a** How far (to the nearest metre) did the plane fly in 20 seconds?
- **b** What is the plane's speed in km/h, correct to the nearest km/h?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3J Bearings EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Bearings are used to indicate direction and therefore are commonly used to navigate the sea or air in ships or planes. Bushwalkers use bearings with a compass to help follow a map and navigate a forest. The most common type of bearing is the True bearing measured clockwise from north.

A compass can determine direction using Earth's magnetic field.

Let's start: Opposite directions

Marg at point A and Jim at point B start walking toward each other. Marg knows that she has to face 50° south of due east.



- Measured clockwise from north, can you help Marg determine her True compass bearing that she should walk on?
- Can you find what bearing Jim should walk on?
- Draw a detailed diagram which supports your answers above.

Key ideas

- A **True bearing** is an angle measured clockwise from north.
  - It is written using three digits.
    For example: 008° T, 032° T or 144° T.



- To describe the true bearing of an object positioned at A from an object positioned at O, we need to start at O, face north then turn clockwise through the required angle to face the object at A.



- When solving problems with bearings, draw a diagram including four point compass directions (N, E, S, W) at each point.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 18 Stating true bearings

For the diagram shown give:

a the true bearing of A from O

b the true bearing of O from A.



SOLUTION	EXPLANATION
a The bearing of A from O is 120° T.	Start at O, face north and turn clockwise until you are facing A.
b 	Start at A, face north and turn clockwise until you are facing O. Mark in a compass at A and use alternate angles in parallel lines to mark a 60° angle.
The bearing of O from A is: $(360 - 60)°$ T = 300° T	True bearing is then 60° short of 360°.

Example 19 Using bearings with trigonometry

A bushwalker walks 3 km on a true bearing of 060° from point A to point B. Find how far east (correct to one decimal place) point B is from point A.



SOLUTION	EXPLANATION
Let the distance travelled towards the east be d km. 	Define the distance required and draw and label the right-angled triangle. Since the adjacent (A) is required and the hypotenuse (H) is given, use $\cos\ \theta$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

$\cos 30° = \frac{d}{3}$

$d = 3 \cos 30°$

$= 2.6$ (to 1 d.p.)

Multiply both sides of the equation by 3 and evaluate, rounding to one decimal place.

$\therefore$ The distance east is 2.6 km.

Express the answer in words.

Example 20 Calculating a bearing

A fishing boat starts from point O and sails 75 km on a bearing of 160° T to point B.

a How far east (to the nearest kilometre) of its starting point is the boat?

b What is the bearing of O from B?



SOLUTION

a Let the distance travelled towards the east be d km.



$\sin 20° = \frac{d}{75}$

$d = 75 \sin 20°$

$= 25.651 \ldots$

The boat has travelled 26 km to the east of its starting point, to the nearest kilometre.

b The bearing of O from B is $(360 - 20)°$ T = 340° T

EXPLANATION

Draw a diagram and label all the given measurements. Mark in a compass at B and use alternate angles to label extra angles.

Set up a trigonometric ratio using sine and solve for d.

Alternate angle = 20°



Round to the nearest kilometre and write the answer in words.

Start at B, face north then turn clockwise to face O.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 3J

1, 2 | 2 | —

UNDERSTANDING

1 Give the true bearings for these common directions.

a North (N)
b North-east (NE)
c East (E)
d South-east (SE)
e South (S)
f South-west (SW)
g West (W)
h North-west (NW)



2 Write down the true bearings shown in these diagrams. Use three digits, for example, 045° T.

a



b



c



d



3(½), 4–6 | 3(½), 4–7 | 3(½), 4, 6, 7

FLUENCY

Example 18

3 For each diagram shown, write:

i the true bearing of A from O **ii** the true bearing of O from A.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

d



e



f



g



h



i



Example 19

4 A bushwalker walks 4 km on a true bearing of 055° from point *A* to point *B*. Find how far east point *B* is from point *A*, correct to two decimal places.



5 A speed boat travels 80 km on a true bearing of 048°. Find how far east of its starting point the speed boat is, correct to two decimal places.



6 After walking due east, then turning and walking due south, a hiker is 4 km 148° T from her starting point. Find how far she walked in a southerly direction, correct to one decimal place.



7 A four-wheel drive vehicle travels for 32 km on a true bearing of 200°. How far west (to the nearest kilometre) of its starting point is it?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

3J

8–10 | 8–11 | 9–12

PROBLEM-SOLVING

Example 20

8 A fishing boat starts from point O and sails 60 km on a true bearing of 140° to point B.



a How far east of its starting point is the boat, to the nearest kilometre?

b What is the bearing of O from B?

9 Two towns, A and B, are 12 km apart. The true bearing of B from A is 250°.



a How far west of A is B, correct to one decimal place?

b Find the bearing of A from B.

10 A helicopter flies on a true bearing of 140° for 210 km then flies due east for 175 km. How far east (to the nearest kilometre) has the helicopter travelled from its starting point?

11 Christopher walks 5 km south then walks on a true bearing of 036° until he is due east of his starting point. How far is he from his starting point, to one decimal place?

12 Two cyclists leave from the same starting point. One cyclist travels due west while the other travels on a true bearing of 202°. After travelling for 18 km, the second cyclist is due south of the first cyclist. How far (to the nearest metre) has the first cyclist travelled?

13 | 13 | 13, 14

REASONING

13 A true bearing is $a°$. Write an expression for the true bearing of the opposite direction of $a°$ if

a a is between 0 and 180 **b** a is between 180 and 360.

14 A hiker walks on a triangular pathway starting at point A, walking to point B then C, then A again as shown.



a Find the bearing from B to A.

b Find the bearing from B to C.

c Find the bearing from C to B.

d If the initial bearing was instead 133° and $\angle ABC$ is still 75°, find the bearing from B to C.

e If $\angle ABC$ was 42°, with the initial bearing of 140°, find the bearing from B to C.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Speed trigonometry — — 15, 16

3J

ENRICHMENT

15 A plane flies on a true bearing of 168° for two hours at an average speed of 310 km/h. How far (to the nearest kilometre):

- **a** has the plane travelled?
- **b** south of its starting point is the plane?
- **c** east of its starting point is the plane?

16 A pilot intends to fly directly to Anderly, which is 240 km due north of his starting point. The trip usually takes 50 minutes. Due to a storm, the pilot changes course and flies to Boxleigh on a true bearing of 320° for 150 km, at an average speed of 180 km/h.

- **a** Find (to the nearest kilometre) how far:
  - **i** north the plane has travelled from its starting point
  - **ii** west the plane has travelled from its starting point.
- **b** How many kilometres is the plane from Anderly?
- **c** From Boxleigh the pilot flies directly to Anderly at 240 km/h.
  - **i** Compared to the usual route, how many extra kilometres (to the nearest kilometre) has the pilot travelled in reaching Anderly?
  - **ii** Compared to the usual trip, how many extra minutes (correct to one decimal place) did the trip to Anderly take?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Illustrating Pythagoras

It is possible to use a computer geometry package ('Cabri Geometry' or 'Geometers Sketchpad') to build this construction, which will illustrate Pythagoras' theorem.



Construct

a Start by constructing the line segment AB.

b Construct the right-angled triangle ABC by using the 'Perpendicular Line' tool.

c Construct a square on each side of the triangle. Circles may help to ensure your construction is exact.

Calculate

a Measure the areas of the squares representing AB^2, AC^2 and BC^2.

b Calculate the sum of the areas of the two smaller squares by using the 'Calculate' tool.

c i Drag point A or point B and observe the changes in the areas of the squares.

ii Investigate how the areas of the squares change as you drag point A or point B. Explain how this illustrates Pythagoras' theorem.

Constructing triangles to solve problems

Illustrations for some problems may not initially look as if they include right-angled triangles. A common mathematical problem-solving technique is to construct right-angled triangles so that trigonometry can be used.

Car gap

Two cars are observed in the same lane from an overpass bridge 10 m above the road. The angles of depression to the cars are 20° and 35°.



a Find the horizontal distance from car A to the overpass. Show your diagrams and working.

b Find the horizontal distance from car B to the overpass.

c Find the distance between the fronts of the two cars.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Cinema screen

A 5 m vertical cinema screen sits 3 m above the floor of the hall and Wally sits 20 m back from the screen. His eye level is 1 m above the floor.

a Find the angle of elevation from Wally's eye level to the base of the screen. Illustrate your method using a diagram.

b Find the angle of elevation as in part **a** but from his eye level to the top of the screen.



c Use your results from parts **a** and **b** to find Wally's viewing angle θ.

Problem solving without all the help

Solve these similar types of problems. You will need to draw detailed diagrams and split the problem into parts. Refer to the above two problems if you need help.

a An observer is 50 m horizontally from a hot air balloon. The angle of elevation to the top of the balloon is 60° and to the bottom of the balloon's basket is 40°. Find the total height of the balloon (to the nearest metre) from the base of the basket to the top of the balloon.

b A ship (at A) is 24 km due east of a lighthouse (L). The captain takes bearings from two landmarks, M and Q, which are due north and due south of the lighthouse respectively. The true bearings of M and Q from the ship are 322° and 244° respectively. How far apart are the two landmarks?



c From the top of a 90 m cliff the angles of depression of two boats in the water, both directly east of the light house, are 25° and 38° respectively. What is the distance between the two boats to the nearest metre?



d A person on a boat 200 m out to sea views a 40 m high castle wall on top of a 32 m high cliff. Find the viewing angle between the base and top of the castle wall from the person on the boat.

Design your own problem

Design a problem similar to the ones above that involve a combination of triangles.

a Clearly write the problem.

b See if a friend can understand and solve your problem.

c Show a complete solution including all diagrams.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



1 A right-angled isosceles triangle has area of 4 square units. Determine the exact perimeter of the triangle.

2 Find the area of this triangle using trigonometry.
Hint: insert a line showing the height of the triangle.



3 A rectangle $ABCD$ has sides $AB = CD = 34$ cm. E is a point on CD such that $CE = 9$ cm and $ED = 25$ cm. AE is perpendicular to EB. What is the length of BC?

4 Find the bearing from B to C in this diagram.



5 Which is a better fit? A square peg in a round hole or a round peg in a square hole. Use area calculations and percentages to investigate.

6 Boat A is 20 km from port on a true bearing of 025° and boat B is 25 km from port on a true bearing of 070°. Boat B is in distress. What bearing (to the nearest degree) should boat A travel on to reach boat B?

7 For positive integers m and n such that $n < m$, the Pythagorean triples (like 3, 4, 5) can be generated using $a = m^2 - n^2$ and $b = 2mn$, where a and b are the two shorter sides of the right-angled triangle.

a Using the above formulas and Pythagoras' theorem to calculate the third side, generate the Pythagorean triples for:

i $m = 2, n = 1$ **ii** $m = 3, n = 2$

b Using the expressions for a and b and Pythagoras' theorem, find a rule for c (the hypotenuse) in terms of n and m.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Pythagoras' theorem and trigonometry

Finding the hypotenuse

$c^2 = 2^2 + 1^2$
$= 5$
$c = \sqrt{5}$
$= 2.24$ (to 2 decimal places)



Shorter sides

$a^2 + 5^2 = 7^2$
$a^2 = 7^2 - 5^2$
$= 24$
$\therefore a = \sqrt{24}$



Applications



SOHCAHTOA

$\sin\theta = \frac{O}{H} = \frac{4}{5}$

$\cos\theta = \frac{A}{H} = \frac{3}{5}$

$\tan\theta = \frac{O}{A} = \frac{4}{3}$



Pythagoras' theorem



$c^2 = a^2 + b^2$

Bearings (Ext)

True bearings are measured clockwise from North.





Finding side lengths



$\cos 22° = \frac{x}{7}$
$x = 7 \cos 22°$
$= 6.49$ (to 2 d. p.)



$\tan 36° = \frac{5}{x}$
$x \times \tan 36° = 5$
$x = \frac{5}{\tan 36°}$
$= 6.88$ (to 2 d. p.)

Elevation and depression



Finding angles



$\sin\theta = \frac{6}{7.5}$

$\theta = \sin^{-1}\left(\frac{6}{7.5}\right)$

$= 53.13°$ (to 2 d. p.)

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter review

Multiple-choice questions

3A **1** For the right-angled triangle shown, the length of the hypotenuse can be found from the equation:



A $c^2 = 5^2 + 12^2$ **B** $c^2 = 5^2 - 12^2$
C $c^2 = 12^2 - 5^2$ **D** $c^2 = 5^2 \times 12^2$
E $(5 + 12)^2$

3B **2** For the right-angled triangle shown, the value of b is given by:



A $\sqrt{0.7^2 + 0.4^2}$ **B** $\sqrt{0.7^2 - 0.4^2}$
C $\sqrt{0.4^2 - 0.7^2}$ **D** $\sqrt{0.7^2 \times 0.4^2}$
E $\sqrt{(0.7 - 0.4^2)^2}$

3B **3** For the right-angled triangle shown:



A $x^2 = \frac{49}{2}$ **B** $7x^2 = 2$ **C** $x^2 = \frac{7}{2}$
D $x^2 + 7^2 = x^2$ **E** $x^2 = \frac{2}{7}$

3E **4** For the triangle shown:



A $\sin\theta = \frac{a}{b}$ **B** $\sin\theta = \frac{c}{a}$ **C** $\sin\theta = \frac{a}{c}$
D $\sin\theta = \frac{b}{c}$ **E** $\sin\theta = \frac{c}{b}$

3F **5** The value of $\cos 46°$ correct to four decimal places is:
A 0.7193 **B** 0.6947 **C** 0.594 **D** 0.6532 **E** 1.0355

3F **6** In the diagram the value of x, correct to two decimal places, is:



A 40 **B** 13.61 **C** 4.70
D 9.89 **E** 6.47

3G **7** The length of x in the triangle is given by:



A $8\sin 46°$ **B** $8\cos 46°$ **C** $\frac{8}{\cos 46°}$
D $\frac{8}{\sin 46°}$ **E** $\frac{\cos 46°}{8}$

3J Ext **8** The true bearing of A from O is 130°. The true bearing of O from A is:



A 050° **B** 220° **C** 310°
D 280° **E** 170°

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G **9** A ladder is inclined at an angle of 28° to the horizontal. If the ladder reaches 8.9 m up the wall, the length of the ladder correct to the nearest metre is:

A 19 m **B** 4 m **C** 2 m
D 10 m **E** 24 m

3H **10** The value of θ in the diagram, correct to two decimal places, is:



A 0.73° **B** 41.81° **C** 48.19°
D 33.69° **E** 4.181°

Short-answer questions

3A/B **1** Find the unknown length in these triangles. Give an exact answer.

a



b



c



3B **2** A steel support beam of length 6.5 m is connected to a wall at a height of 4.7 m from the ground. Find the distance (to the nearest centimetre) between the base of the building and the point where the beam is joined to the ground.



3A **3** For this double triangle, find:

a AC

b CD (correct to two decimal places).



3C **4** Two different cafés on opposite sides of an atrium in a shopping centre are respectively 10 m and 15 m above the ground floor. If the cafés are linked by a 20 m escalator, find the horizontal distance (to the nearest metre) across the atrium, between the two cafés.

3D Ext **5** Find the values of the pronumerals in the three-dimensional objects shown below, correct to two decimal places.

a



b



3F **6** Find the value of each of the following, correct to two decimal places.

a sin 40° **b** tan 66° **c** cos 44°

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

3F/G/H

7 Find the value of each pronumeral, correct to two decimal places.

a



b



c



3I Ext

8 The angle of elevation of the top of a lighthouse from a point on the ground 40 m from its base is 35°. Find the height of the lighthouse to two decimal places.



3I Ext

9 A train travels up a slope, making an angle of 7° with the horizontal. When the train is at a height of 3 m above its starting point, find the distance it has travelled up the slope, to the nearest metre.



3J Ext

10 A yacht sails 80 km on a true bearing of 048°.

a How far east of its starting point is the yacht, correct to two decimal places?

b How far north of its starting point is the yacht, correct to two decimal places?



3I Ext

11 From a point on the ground, Geoff measures the angle of elevation of a 120 m tower to be 34°. How far from the base of the tower is Geoff, correct to two decimal places?

3J Ext

12 A ship leaves Coffs Harbour and sails 320 km east. It then changes direction and sails 240 km due north to its destination. What will the ship's true bearing be from Coffs Harbour when it reaches its destination, correct to two decimal places?

3I Ext

13 From the roof of a skyscraper, Aisha spots a car at an angle of depression of 51° from the roof of the skyscraper. If the skyscraper is 78 m high, how far away is the car from the base of the skyscraper, correct to one decimal place?

3F

14 Penny wants to measure the width of a river. She places two markers, A and B, 10 m apart along one bank. C is a point directly opposite marker B. Penny measures angle BAC to be 28°. Find the width of the river to one decimal place.

3I Ext

15 An aeroplane takes off and climbs at an angle of 15° to the horizontal, at 210 km/h along its flight path for 15 minutes. Find:

a the distance the aeroplane travels

b the height the aeroplane reaches, correct to two decimal places.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions



1 An extension ladder is initially placed so that it reaches 2 m up a wall. The foot of the ladder is 80 cm from the base of the wall.

- **a** Find the length of the ladder, to the nearest centimetre, in its original position.
- **b** Without moving the foot of the ladder, it is extended so that it reaches 1 m further up the wall. How far (to the nearest centimetre) has the ladder been extended?
- **c** The ladder is placed so that its foot is now 20 cm closer to the base of the wall.
  - **i** How far up the wall can the ladder length found in part **b** reach? Round to two decimal places.
  - **ii** Is this further than the distance in part **a**?

Ext **2** From the top of a 100 m cliff, Skevi sees a boat out at sea at an angle of depression of 12°.

- **a** Draw a diagram for this situation.
- **b** Find how far out to sea the boat is to the nearest metre.
- **c** A swimmer is 2 km away from the base of the cliff and in line with the boat. What is the angle of depression to the swimmer, to the nearest degree?
- **d** How far away is the boat from the swimmer, to the nearest metre?

Ext **3** A pilot takes off from Amber Island and flies for 150 km at 040° T to Barter Island where she unloads her first cargo. She intends to fly to Dream Island but a bad thunderstorm between Barter and Dream islands forces her to fly off-course for 60 km to Crater Atoll on a bearing of 060° T. She then turns on a bearing of 140° T and flies for 100 km until she reaches Dream Island where she unloads her second cargo. She then takes off and flies 180 km on a bearing of 055° T to Emerald Island.

- **a** How many extra kilometres did she fly trying to avoid the storm? Round to the nearest kilometre.
- **b** From Emerald Island she flies directly back to Amber Island. How many kilometres did she travel on her return trip? Round to the nearest kilometre.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 4

Linear relations

What you will learn

4A Introduction to linear relations (Consolidating)
4B Graphing straight lines using intercepts
4C Lines with one intercept
4D Gradient
4E Gradient and direct proportion
4F Gradient–intercept form
4G Finding the equation of a line
4H Midpoint and length of a line segment
4I Perpendicular and parallel lines (Extending)
4J Linear modelling
4K Graphical solutions to simultaneous equations

Australian curriculum

NUMBER AND ALGEBRA

Real numbers

Solve problems involving direct proportion

Explore the relationship between graphs and equations corresponding to simple rate problems

Linear and non-linear relationships

Find the distance between two points located on a Cartesian plane using a range of strategies, including graphing software

Find the midpoint and gradient of a line segment (interval) on the Cartesian plane using a range of strategies, including graphing software

Sketch linear graphs using the coordinates of two points AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Computer-generated imagery (CGI)

Movies and computer games include many scenes and characters that are generated by computer, such as *Elsa* in *Frozen* or Nemo in *Finding Nemo*. Another classic example is the character Gollum in *The Lord of the Rings* film trilogy, one of the first and most successful CGI characters to interact with live actors in a movie blockbuster. CGI characters are added after filming the other real-life characters.

The fundamentals of CGI and computer graphics are more generally based on computer programming, including linear algebra, which is the focus of this chapter. Straight lines described by linear relations can form polygons and with the use of linear algebra can be transformed to create moving three-dimensional images in a two-dimensional plane.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4A Introduction to linear relations

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

If two variables are related in some way we can use mathematical rules to more precisely describe this relationship. The most simple kind of mathematical relationship is one that can be illustrated with a straight line graph. These are called linear relations. The volume of petrol in your car at a service bowser, for example, might initially be 10 L then be increasing by 1.2 L per second after that. This is an example of a linear relationship between *volume* and *time* because the volume is increasing at a constant rate of 1.2 L/sec.

Let's start: Is it linear?

Here are three rules linking x and y.

1 $y_1 = \frac{2}{x} + 1$

2 $y_2 = x^2 - 1$

3 $y_3 = 3x - 4$

First complete this simple table and graph.

x	1	2	3
y_1			
y_2			
y_3			



- Which of the three rules do you think is linear?
- How do you decide it's linear?

Key ideas

- **Coordinate geometry** provides a link between geometry and algebra.
- The **Cartesian plane** (or number plane) consists of two axes which divide the number plane into four **quadrants**.
  - The horizontal x-axis and vertical y-axis intersect at the **origin** (0, 0) at right angles titled O.
  - A point is precisely positioned on a Cartesian plane using the **coordinate pair** (x, y) where x describes the horizontal position and y describes the vertical position of the point from the origin.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- A **linear relation** is a set of ordered pairs (x, y) that when graphed give a straight line.
- The x-intercept is the x-coordinate at the point where the graph cuts the x-axis.
- The y-intercept is the y-coordinate at the point where the graph cuts the y-axis.

x-intercept

x	–2	–1	0	1	2	3
y	8	6	4	2	0	–2

y-intercept



Example 1 Plotting points to graph straight lines

Using $-3 \le x \le 3$, construct a table of values and plot a graph for these linear relations.

a $y = x + 2$ **b** $y = -2x + 2$

SOLUTION

a

x	–3	–2	–1	0	1	2	3
y	–1	0	1	2	3	4	5



b

x	–3	–2	–1	0	1	2	3
y	8	6	4	2	0	–2	–4



EXPLANATION

Use $-3 \le x \le 3$ as instructed and substitute each value of x into the rule $y = x + 2$.

The coordinates of the points are read from the table, i.e. $(-3, -1)$, $(-2, 0)$, etc.

Plot each point and join to form a straight line. Extend the line to show it continues in either direction.

Use $-3 \le x \le 3$ as instructed and substitute each value of x into the rule $y = -2x + 2$.

For example,

$x = -3, y = -2 \times (-3) + 2$

$= 6 + 2$

$= 8$

Plot each point and join to form a straight line. Extend the line beyond the plotted points.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 2 Reading off the *x*-intercept and *y*-intercept

Write down the *x*-intercept and *y*-intercept from this table and graph.

a

x	–2	–1	0	1	2	3
y	6	4	2	0	–2	–4

b



SOLUTION

EXPLANATION

a The *x*-intercept is 1.

The *x*-intercept is at the point where $y = 0$ (on the *x*-axis).

The *y*-intercept is 2.

The *y*-intercept is at the point where $x = 0$ (on the *y*-axis).

b The *x*-intercept is –4.

The *x*-intercept is at the point where $y = 0$ (on the *x*-axis).

The *y*-intercept is 6.

The *y*-intercept is at the point where $x = 0$ (on the *y*-axis).

Example 3 Deciding if a point is on a line

Decide if the point (–2, 4) is on the line with the given rules.

a $y = 2x + 10$ **b** $y = -x + 2$

SOLUTION

EXPLANATION

a $y = 2x + 10$

Substitute $x = -2$

$y = 2(-2) + 10$

$= 6$

$\therefore$ the point (–2, 4) is not on the line

Find the value of *y* on the graph of the rule for $x = -2$.

The *y* value is not 4 so (–2, 4) is not on the line.

b $y = -x + 2$

Substitute $x = -2$

$y = -(-2) + 2$

$= 4$

$\therefore$ the point (–2, 4) is on the line.

By substituting $x = -2$ into the rule for the line, *y* is 4.

So (–2, 4) is on the line.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4A

1–3 | 3 | —

UNDERSTANDING

1 Refer to the Cartesian plane shown.

a Give the coordinates of all the points A–L.

b Which points lie on:

i the x-axis

ii the y-axis.

c Which points lie inside the:

i 2nd quadrant

ii 4th quadrant.



2 For the rule $y = 3x - 4$, find the value of y for these x values.

a $x = 2$ **b** $x = 1$ **c** $x = 0$ **d** $x = -1$

3 For the rule $y = -2x + 1$, find the value of y for these x values.

a $x = 0$ **b** $x = 3$ **c** $x = -1$ **d** $x = -10$

4–7(½) | 4–7(½) | 4–7(½)

FLUENCY

Example 1

4 Using $-3 \leq x \leq 3$, construct a table of values and plot a graph for these linear relations.

a $y = x - 1$ **b** $y = x + 3$ **c** $y = -2x - 1$

d $y = 2x - 3$ **e** $y = -x + 4$ **f** $y = -3x$

Example 2

5 Write down the x- and y-intercepts from these tables and the graphs on the next page.

a

x	−3	−2	−1	0	1	2	3
y	4	3	2	1	0	1	2

b

x	−3	−2	−1	0	1	2	3
y	−1	0	1	2	3	4	5

c

x	−1	0	1	2	3	4
y	10	8	6	4	2	0

d

x	−5	−4	−3	−2	−1	0
y	0	2	4	6	8	10

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4A

FLUENCY

e



f



g



h



Example 3

6 Decide if the point (1, 2) is on the line with the given rule.

a $y = x + 1$ **b** $y = 2x - 1$ **c** $y = -x + 3$

d $y = -2x + 4$ **e** $y = -x + 5$ **f** $y = -\frac{1}{2}x + \frac{1}{2}$

7 Decide if the point (–3, 4) is on the line with the given rule.

a $y = 2x + 8$ **b** $y = x + 7$ **c** $y = -x - 1$

d $y = \frac{1}{3}x + 6$ **e** $y = -\frac{1}{3}x + 3$ **f** $y = \frac{5}{6}x + \frac{11}{2}$

PROBLEM-SOLVING

8 | 8, 10 | 9, 10

8 Find a rule in the form $y = mx + c$ (e.g. $y = 2x - 1$) that matches these tables of values.

a

x	0	1	2	3	4
y	2	3	4	5	6

b

x	–1	0	1	2	3
y	–2	0	2	4	6

c

x	–2	–1	0	1	2	3
y	–3	–1	1	3	5	7

d

x	–3	–2	–1	0	1	2
y	5	4	3	2	1	0

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9 Rearrange these equations into the form $y = mx + c$.

a $2x + 3y = 6$

b $3x + 4y = -3$

c $x - y = 4$

d $2x - y = -7$

e $x - 3y = 1$

f $4x - 7y = 10$

The slope of this mountain railway could be expressed in the form $y = mx + c$.

10 Match these rules **A**, **B**, **C** and **D** to the graphs **a**, **b**, **c** and **d**.

A $y = 2x + 1$

B $y = -x - 1$

C $y = -2x + 3$

D $x + y = 2$

a



b



c



d



11 | 11, 12 | 12, 13

11 Decide if the following equations are true or false.

a $\frac{2x+4}{2} = x + 4$

b $\frac{3x-6}{3} = x - 2$

c $\frac{1}{2}(x-1) = \frac{1}{2}x - \frac{1}{2}$

d $\frac{2}{3}(x-6) = \frac{2}{3}x - 12$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4A

REASONING

12 Give reasons why the x-intercept on these graphs is $\frac{3}{2}$.

a



b



13 Decide if the following rules are equivalent.

a $y = 1 - x$ and $y = -x + 1$

b $y = 1 - 3x$ and $y = 3x - 1$

c $y = -2x + 1$ and $y = -1 - 2x$

d $y = -3x + 1$ and $y = 1 - 3x$

ENRICHMENT

Tough rule finding — — 14

14 Find the linear rule linking x and y in these tables.

a

x	−1	0	1	2	3
y	5	7	9	11	13

b

x	−2	−1	0	1	2
y	22	21	20	19	18

c

x	0	2	4	6	8
y	−10	−16	−22	−28	−34

d

x	−5	−4	−3	−2	−1
y	29	24	19	14	9

e

x	1	3	5	7	9
y	1	2	3	4	5

f

x	−14	−13	−12	−11	−10
y	$5\frac{1}{2}$	5	$4\frac{1}{2}$	4	$3\frac{1}{2}$

The lines in this structure can be modelled by linear relations.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

4B Graphing straight lines using intercepts

Interactive

Widgets

HOTsheets

Walkthroughs

When linear rules are graphed, all the points lie in a straight line, so it is therefore possible to graph a straight line using only two points. Two critical points that help draw these graphs are the x-intercept and y-intercept introduced in the previous section.

Let's start: Two key points

Consider the relation $y = \frac{1}{2}x + 1$ and complete this table and graph.

x	−4	−3	−2	−1	0	1	2
y							



- What are the coordinates of the point where the line crosses the y-axis? That is, state the coordinates of the y-intercept.
- What are the coordinates of the point where the line crosses the x-axis? That is, state the coordinates of the x-intercept.
- Discuss how you might find the coordinates of the x- and y-intercepts without drawing a table and plotting points. Explain your method.

Key ideas

- The ***y*-intercept** is the y value at the point on the y-axis where $x = 0$.
  - Substitute $x = 0$ to find the y-intercept.
- The ***x*-intercept** is the x value at the point on the x-axis where $y = 0$.
  - Substitute $y = 0$ to find the x-intercept.

Example: $2x + 3y = 6$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4 Sketching with intercepts

Sketch the graph of the following, showing the x- and y-intercepts.

a $2x + 3y = 6$ **b** $y = 2x - 6$

SOLUTION	EXPLANATION
a $2x + 3y = 6$	
y-intercept (let $x = 0$):	Only two points are required to generate a straight line. For the y-intercept, substitute $x = 0$ into the rule and solve for y by dividing each side by 3.
$2(0) + 3y = 6$	
$3y = 6$	
$y = 2$	
$\therefore$ the y-intercept is 2	State the y-intercept. The coordinates are (0, 2).
x-intercept (let $y = 0$):	Similarly to find the x-intercept, substitute $y = 0$ into the rule and solve for x.
$2x + 3(0) = 6$	
$2x = 6$	
$x = 3$	
$\therefore$ the x-intercept is 3	State the x-intercept. The coordinates are (3, 0).
	Mark and label the intercepts on the axes and sketch the graph by joining the two intercepts.
b $y = 2x - 6$	
y-intercept (let $x = 0$):	
$y = 2(0) - 6$	Substitute $x = 0$ for the y-intercept.
$y = -6$	Simplify to find the y-coordinate.
$\therefore$ the y-intercept is -6	The coordinates are $(0, -6)$.
x-intercept (let $y = 0$):	
$0 = 2x - 6$	Substitute $y = 0$ for the x-intercept. Solve the remaining equation for x by adding 6 to both sides and then dividing both sides by 2.
$6 = 2x$	
$x = 3$	
$\therefore$ the x-intercept is 3	The coordinates are (3, 0).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Mark in the two intercepts and join to sketch the graph.

Exercise 4B

1, 2(½), 3, 4 | 3–4(½) | —

UNDERSTANDING

1 For each of the given rules, complete a table like the one shown and plot points to draw a graph. Clearly label the x- and y-intercepts.

x	–3	–2	–1	0	1	2	3
y							

a $y = x + 2$ **b** $y = \frac{1}{2}x - 1$ **c** $y = 3x$ **d** $y = -x + 3$

2 **a** Find the value of y in these equations.

i $2y = 6$ **ii** $y = 3 \times 0 + 4$ **iii** $y = -2 \times 0 - 3$

iv $y = \frac{1}{2} \times 0 - 1$ **v** $-2y = 12$ **vi** $-6y = -24$

b Find the value of x in these equations.

i $3x = 18$ **ii** $-4x = -40$ **iii** $0 = 2x - 2$

iv $3x - 6 = 0$ **v** $\frac{1}{2}x = 3$ **vi** $\frac{1}{3}x = -1$

3 For these equations find the y-intercept by letting $x = 0$.

a $x + y = 4$ **b** $x - y = 5$ **c** $2x + 3y = 9$ **d** $y = 2x - 4$

4 For these equations find the x-intercept by letting $y = 0$.

a $x + 2y = 5$ **b** $2x - y = -4$ **c** $4x - 3y = 12$ **d** $y = 3x - 6$

5–6(½) | 5–7(½) | 5–7(½)

FLUENCY

Example 4a

5 Sketch the graph of the following relations, by finding the x- and y-intercepts.

a $x + y = 2$ **b** $x + y = 5$ **c** $x - y = 3$

d $x - y = -2$ **e** $2x + y = 4$ **f** $3x - y = 9$

g $4x - 2y = 8$ **h** $3x + 2y = 6$ **i** $3x - 2y = 6$

j $y - 3x = 12$ **k** $-5y + 2x = -10$ **l** $-x + 7y = 21$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4B

Example 4b

FLUENCY

6 Sketch the graph of the following relations, showing the x- and y-intercepts.

a $y = 3x + 3$ **b** $y = 2x + 2$ **c** $y = x - 5$

d $y = -x - 6$ **e** $y = -2x - 2$ **f** $y = -3x - 6$

g $y = -2x + 4$ **h** $y = 2x - 3$ **i** $y = -x + 1$

7 Sketch the graph of each of the following mixed linear relations.

a $x + 2y = 8$ **b** $3x - 5y = 15$ **c** $3x + 4y = 12$

d $y = 3x - 6$ **e** $3y - 4x = 12$ **f** $5y - x = 10$

g $2x - y - 4 = 0$ **h** $2x - y + 5 = 0$ **i** $x - 4y + 2 = 0$

8, 9 8, 9 9, 10

PROBLEM-SOLVING

8 The distance d metres of a vehicle from an observation point after t seconds is given by the rule $d = 8 - 2t$.

a Find the distance from the observation point initially (at $t = 0$).

b Find after what time t the distance d is equal to 0 (substitute $d = 0$).

c Sketch a graph of d versus t between the d and t intercepts.

9 The height h, in metres, of a lift above ground after t seconds is given by $h = 100 - 8t$.

a How high is the lift initially (at $t = 0$)?

b How long does it take for the lift to reach the ground ($h = 0$)?

10 Find the x- and y-axis intercepts of the graphs with the given rules. Write answers using fractions.

a $3x - 2y = 5$

b $x + 5y = -7$

c $y - 2x = -13$

d $y = -2x - 1$

e $2y = x - 3$

f $-7y = 1 - 3x$

Using a linear graph, we can model the time it takes a lift to reach the ground.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4B

11 | 11, 12 | 12, 13

REASONING

11 Use your algebra and fraction skills to help sketch graphs for these relations by finding x- and y-intercepts.

a $\frac{x}{2}+\frac{y}{3}=1$ **b** $y=\frac{8-x}{4}$ **c** $\frac{y}{2}=\frac{2-4x}{8}$

12 Explain why the graph of the equation $ax + by = 0$ must pass through the origin for any values of the constants a and b.

13 Write down the rule for the graph with these axes intercepts. Write the rule in the form $ax + by = d$.

a (0, 4) and (4, 0) **b** (0, 2) and (2, 0) **c** (0, –3) and (3, 0)

d (0, 1) and (–1, 0) **e** (0, k) and (k, 0) **f** (0, –k) and (–k, 0)

ENRICHMENT

Intercept families — | — | 14

14 Find the x- and y-intercepts in terms of the constants a, b and c for these relations.

a $ax + by = c$ **b** $y=\frac{a}{b}x+c$ **c** $\frac{ax-by}{c}=1$

d $ay - bx = c$ **e** $ay = bx + c$ **f** $a(x + y) = bc$

Using a CAS calculator 4B: Sketching straight lines

This activity is in the interactive textbook in the form of a printable PDF.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4C Lines with one intercept

Interactive

Widgets

HOTsheets

Walkthroughs

Lines with one intercept include vertical lines, horizontal lines and other lines that pass through the origin.

Let's start: What rule satisfies all points?

Here is one vertical and one horizontal line.



- For the vertical line shown, write down the coordinates of all the points shown as dots.
- What is always true for each coordinate pair?
- What simple equation describes every point on the line?
- For the horizontal line shown write down the coordinates of all the points shown as dots.
- What is always true for each coordinate pair?
- What simple equation describes every point on the line?
- Where do the two lines intersect?

Key ideas

- Vertical line: $x = b$
  - Parallel to the y-axis
  - Equation of the form $x = b$, where b is a constant
  - x-intercept is b



- Horizontal line: $y = c$
  - Parallel to the x-axis
  - Equation of the form $y = c$, where c is a constant
  - y-intercept is c



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

■ Lines through the origin (0, 0): $y = mx$



- y-intercept is 0
- x-intercept is 0
- Substitute $x = 1$ or any other value of x to find a second point

Example 5 Graphing vertical and horizontal lines

Sketch the graph of the following vertical and horizontal lines.

a $y = 3$ **b** $x = -4$

SOLUTION	EXPLANATION
a 	y-intercept is 3. Sketch a horizontal line through all points where $y = 3$.
b 	x-intercept is -4. Sketch a vertical line through all points where $x = -4$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 6 Sketching lines which pass through the origin

Sketch the graph of $y = 3x$.

SOLUTION

The x- and y-intercept is 0.

Another point (let $x = 1$):

$$y = 3 \times (1)$$

$$y = 3$$

Another point is at (1, 3).



EXPLANATION

The equation is of the form $y = mx$.

Since two points are required to generate the straight line, find another point by substituting $x = 1$.

Other x values could also be shown.

Plot and label both points and sketch the graph by joining the points in a straight line.

Exercise 4C

1–3 | 3(½) | —

UNDERSTANDING

1 Write down the x-intercept for these graphs.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4C

UNDERSTANDING

2 Write down the y-intercept for these graphs.

a



b



c



d



3 Find the value of y if $x = 1$ using these rules.

a $y = 5x$ **b** $y = \frac{1}{3}x$

c $y = -4x$ **d** $y = -0.1x$

4–6(½), 7 | 4–6(½), 7 | 4–7(½)

FLUENCY

Example 5

4 Sketch the graph of the following vertical and horizontal lines.

a $x = 2$ **b** $x = 5$ **c** $y = 4$ **d** $y = 1$

e $x = -3$ **f** $x = -2$ **g** $y = -1$ **h** $y = -3$

Example 6

5 Sketch the graph of the following linear relations which pass through the origin.

a $y = 2x$ **b** $y = 5x$ **c** $y = 4x$ **d** $y = x$

e $y = -4x$ **f** $y = -3x$ **g** $y = -2x$ **h** $y = -x$

6 Sketch the graphs of these special lines all on the same set of axes and label with their equations.

a $x = -2$ **b** $y = -3$ **c** $y = 2$ **d** $x = 4$

e $y = 3x$ **f** $y = -\frac{1}{2}x$ **g** $y = -1.5x$ **h** $x = 0.5$

i $x = 0$ **j** $y = 0$ **k** $y = 2x$ **l** $y = 1.5x$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

4C

FLUENCY

7 What is the equation of each of the following graphs?

a



b



c



d



e



f



8, 9 | 9, 10(½), 11 | 10(½), 11, 12

PROBLEM-SOLVING

8 Find the equation of the straight line which is:

a parallel to the x-axis and passes through the point (1, 3)

b parallel to the y-axis and passes through the point (5, 4)

c parallel to the y-axis and passes through the point (–2, 4)

d parallel to the x-axis and passes through the point (0, 0).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 If in a picture, the surface of the sea is represented by the x-axis, state the equation of the following paths.

a A plane flies horizontally at 250 m above sea level. One unit is 1 metre.

b A submarine travels horizontally 45 m below sea level. One unit is 1 metre.

10 The graphs of these pairs of equations intersect at a point. Find the coordinates of the point.

a $x = 1, y = 2$ **b** $x = -3, y = 5$ **c** $x = 0, y = -4$

d $x = 4, y = 0$ **e** $y = -6x, x = 0$ **f** $y = 3x, x = 1$

g $y = -9x, x = 3$ **h** $y = 8x, y = 40$ **i** $y = 5x, y = 15$

11 Find the area of the rectangle contained within the following four lines.

a $x = 1, x = -2, y = -3, y = 2$ **b** $x = 0, x = 17, y = -5, y = -1$

12 The lines $x = -1$, $x = 3$ and $y = -2$ form three sides of a rectangle. Find the possible equation of the fourth line if:

a the area of the rectangle is:

i 12 square units **ii** 8 square units **iii** 22 square units

b the perimeter of the rectangle is:

i 14 units **ii** 26 units **iii** 31 units

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4C

13 | 13–14(½) | 13–15(½)

REASONING

13 The rules of the following graphs are of the form $y = mx$. Use the points marked with a dot to find m and hence state the equation.

a



b



c



d



14 Find the equation of the line which passes through the origin and the given point.

a (1, 3) **b** (1, 4) **c** (1, –5) **d** (1, –2)

15 Sketch the graph of each of the following by first making y or x the subject.

a $y - 8 = 0$ **b** $x + 5 = 0$ **c** $x + \frac{1}{2} = 0$ **d** $y - 0.6 = 0$

e $y + 3x = 0$ **f** $y - 5x = 0$ **g** $2y - 8x = 0$ **h** $5y + 7x = 0$

ENRICHMENT

Trisection — | — | 16–18

16 A vertical line, horizontal line and another line that passes through the origin all intersect at (–1, –5). What are the equations of the three lines?

17 If $y = c$, $x = b$ and $y = mx$ all intersect at one point:

a state the coordinates of the intersection point

b find m in terms of c and b.

18 The area of a triangle formed by $x = 4$, $y = -2$ and $y = mx$ is 16 square units. Find the value of m given $m > 0$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4D Gradient

The gradient of a line is a measure of its slope. It is a number which describes the steepness of a line and is calculated by considering how far a line rises or falls between two points within a given horizontal distance. The horizontal distance between two points is called the *run* and the vertical distance is called the *rise*.



Gradients are used to describe the steepness of this rollercoaster track.

Let's start: Which line is the steepest?

The three lines below right connect the points *A*–*H*.

- Calculate the rise and run (working from left to right) and also the fraction $\frac{\text{rise}}{\text{run}}$ for these segments.

  i *AB* **ii** *BC* **iii** *BD*
  iv *EF* **v** *GH*

- What do you notice about the fractions $\left(\frac{\text{rise}}{\text{run}}\right)$ for parts **i**, **ii** and **iii**?
- How does the $\frac{\text{rise}}{\text{run}}$ for *EF* compare with the $\frac{\text{rise}}{\text{run}}$ for parts **i**, **ii** and **iii**? Which of the two lines is the steepest?
- Your $\frac{\text{rise}}{\text{run}}$ for *GH* should be negative. Why is this the case?
- Discuss whether or not *GH* is steeper than *AD*.



Use computer software (dynamic geometry) to produce a set of axes and grid.

- Construct a line segment with endpoints on the grid. Show the coordinates of the endpoints.
- Calculate the rise (vertical distance between the endpoints) and the run (horizontal distance between the endpoints).
- Calculate the gradient as the *rise* divided by the *run*.
- Now drag the endpoints and explore the effect on the gradient.
- Can you drag the endpoints but retain the same gradient value? Explain why this is possible.
- Can you drag the endpoints so that the gradient is zero or undefined? Describe how this can be achieved.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Gradient (m)** $= \dfrac{\text{rise}}{\text{run}}$





- We work from left to right, so the run is always positive.
- The gradient can be positive, negative, zero or undefined.
- A vertical line has an undefined gradient.



Example 7 Finding the gradient of a line

For each graph, state whether the gradient is positive, negative, zero or undefined, then find the gradient where possible.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION | **EXPLANATION**

a The gradient is positive.



$$\text{Gradient} = \frac{\text{rise}}{\text{run}}$$
$$= \frac{4}{2}$$
$$= 2$$

By inspection, the gradient will be positive since the graph rises from left to right. Select any two points and create a right-angled triangle to determine the rise and run.

Substitute rise = 4 and run = 2.

b The gradient is negative.



$$\text{Gradient} = \frac{\text{rise}}{\text{run}}$$
$$= \frac{-3}{2}$$
$$= -\frac{3}{2}$$

By inspection, the gradient will be negative since y values decrease from left to right.

Rise = –3 and run = 2.

c The gradient is 0.

The line is horizontal.

d The gradient is undefined.

The line is vertical.

Example 8 Finding the gradient between two points

Find the gradient (m) of the line joining the given points.

a $A(3, 4)$ and $B(5, 6)$ **b** $A(-3, 6)$ and $B(1, -3)$

SOLUTION | **EXPLANATION**

a
$$m = \frac{\text{rise}}{\text{run}}$$
$$= \frac{6-4}{5-3}$$
$$= \frac{2}{2}$$
$$= 1$$



b
$$m = \frac{\text{rise}}{\text{run}}$$
$$= \frac{-9}{4} \text{ or } -\frac{9}{4} \text{ or } -2.25$$



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4D

1, 2 | 2 | —

UNDERSTANDING

1 Calculate the gradient using $\frac{\text{rise}}{\text{run}}$ for these lines. Remember to give a negative answer if the line is sloping downward from left to right.

a



b



c



d



e



f



2 Use the words: positive, negative, zero or undefined to complete each sentence.

a The gradient of a horizontal line is _____.

b The gradient of the line joining (0, 3) with (5, 0) is _____.

c The gradient of the line joining (–6, 0) with (1, 1) is _____.

d The gradient of a vertical line is _____.

3–4(½) | 3–4(½), 5 | 3–4(½), 5

FLUENCY

Example 7

3 For each graph state whether the gradient is positive, negative, zero or undefined, then find the gradient where possible.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

e



f



g



h



i



j



k



l



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4D

Example 8

FLUENCY

4 Find the gradient of the lines joining the following pairs of points.

a $A(2, 3)$ and $B(3, 5)$
b $C(-2, 6)$ and $D(0, 8)$
c $E(-4, 1)$ and $F(4, -1)$
d $G(2, 1)$ and $H(5, 5)$
e $A(1, 5)$ and $B(2, 7)$
f $C(-2, 4)$ and $D(1, -2)$
g $E(-3, 4)$ and $F(2, -1)$
h $G(-1, 5)$ and $H(1, 6)$
i $A(-2, 1)$ and $B(-4, -2)$
j $C(3, -4)$ and $D(1, 1)$
k $E(3, 2)$ and $F(0, 1)$
l $G(-1, 1)$ and $H(-3, -4)$

5 Find the gradient of each line A–F on this graph and grid.



6, 7 | 6–8 | 7–9

PROBLEM-SOLVING

6 Find the gradient corresponding to the following slopes.

a A road falls 10 m for every 200 horizontal metres.
b A cliff rises 35 metres for every 2 metres horizontally.
c A plane descends 2 km for every 10 horizontal kilometres.
d A submarine ascends 150 m for every 20 horizontal metres.

Gradients can be used to find the measure of slope of these cliff faces.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 Find the missing number.

- **a** The gradient joining the points (0, 2) and (1, ?) is 4.
- **b** The gradient joining the points (?, 5) and (1, 9) is 2.
- **c** The gradient joining the points (–3, ?) and (0, 1) is –1.
- **d** The gradient joining the points (– 4, –2) and (?, –12) is – 4.

8 A train climbs a slope with gradient 0.05. How far horizontally has the train travelled after rising 15 metres?

9 Complete this table showing the gradient, x-intercept and y-intercept for straight lines.

	A	B	C	D	E	F
Gradient	3	–1	$\frac{1}{2}$	$-\frac{2}{3}$	0.4	–1.25
***x*-intercept**	–3			6	1	
***y*-intercept**		– 4	$\frac{1}{2}$			3

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4D

10 | 10, 11 | 10, 11

REASONING

10 Give a reason why a line with gradient $\frac{7}{11}$ is steeper than a line with gradient $\frac{3}{5}$.

11 The two points A and B shown here have coordinates (x_1, y_1) and (x_2, y_2).



- **a** Write a rule for the run using x_1 and x_2.
- **b** Write a rule for the rise using y_1 and y_2.
- **c** Write a rule for the gradient m using x_1, x_2, y_1 and y_2.
- **d** Use your rule to find the gradient between these pairs of points.
  - **i** $(1, 1)$ and $(3, 4)$
  - **ii** $(0, 2)$ and $(4, 7)$
  - **iii** $(-1, 2)$ and $(2, -3)$
  - **iv** $(-4, -6)$ and $(-1, -2)$
- **e** Does your rule work for points which include negative coordinates? Explain why.

Where does it hit?

— | — | 12

ENRICHMENT

12 The line here has gradient $-\frac{2}{3}$ which means that it falls 2 units for every 3 across.

The y-intercept is 3.



- **a** Use the gradient to find the y-coordinate on the line where:
  - **i** $x = 6$
  - **ii** $x = 9$
- **b** What will be the x-intercept?
- **c** What would be the x-intercept if the gradient was changed to:
  - **i** $-\frac{1}{2}$?
  - **ii** $-\frac{5}{4}$?
  - **iii** $-\frac{7}{3}$?
  - **iv** $-\frac{2}{5}$?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4E Gradient and direct proportion

Interactive

Widgets

HOTsheets

Walkthroughs

The connection between gradient, rate problems and direct proportion can be illustrated through the use of linear rules and graphs. If two variables are directly related then the rate of change of one variable with respect to the other is constant. This implies that the rule linking the two variables is linear and can be represented as a straight line graph passing through the origin. The amount of water squirting from a hose, for example, is directly proportional to the time since it was turned on. The gradient of the graph of *water volume* versus *time* will equal the rate at which water is squirting from the hose.

The volume of water squirting from a hose is directly proportional to the time.

Let's start: Average speed

Over 5 hours, Sandy travels 420 km.

- What is Sandy's average speed for the trip?
- Is speed a rate? Discuss.
- Draw a graph of distance versus time, assuming a constant speed.
- Where does your graph intersect the axes and why?
- Find the gradient of your graph. What do you notice?
- Find a rule linking distance (d) and time (t).



Key ideas

- If two variables are **directly proportional**:
  - the rate of change of one variable with respect to the other is constant
  - the graph is a straight line passing through the origin
  - the rule is of the form $y = mx$
  - the gradient (m) of the graph equals the rate of change of y with respect to x.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Exploring direct proportion

Water is poured into an empty tank at a constant rate. It takes 3 hours to fill the tank with 6000 litres.

a What is the rate at which water is poured into the tank?

b Draw a graph of volume (V litres) vs time (t hours) using $0 \leq t \leq 3$.

c Find:

- **i** the gradient of your graph
- **ii** the rule for V.

d Use your rule to find:

- **i** the volume after 1.5 hours
- **ii** the time to fill 5000 litres.

SOLUTION	EXPLANATION
a 6000 L in 3 hours = 2000 L/hour	6000 L per 3 hours = 2000 L per 1 hour
b 	Plot the two end points (0, 0) and (3, 6000) then join with a straight line.
c i gradient $= \frac{6000}{3} = 2000$	The gradient is the same as the rate.
ii $V = 2000t$	2000 L are filled for each hour.
d i $V = 2000t$ $= 2000 \times (1.5)$ $= 3000$ litres	Substitute $t = 1.5$ into your rule.
ii $V = 2000t$ $5000 = 2000t$ $2.5 = t$ $\therefore$ it takes $2\frac{1}{2}$ hours	Substitute $V = 5000$ into the rule and solve for t.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4E

1, 2 | 2 | —

UNDERSTANDING

1 This graph shows how far a bike travels over 4 hours.



- **a** State how far the bike has travelled after:
  - **i** 1 hour
  - **ii** 2 hours
  - **iii** 3 hours.
- **b** Write down the speed of the bike (rate of change of distance over time).
- **c** Find the gradient of the graph.
- **d** What do you notice about your answers from parts **b** and **c**.

2 The rule linking the height of a plant over time is given by $h = 5t$ where h is in millimetres and t is in days.

- **a** Find the height of the plant after 3 days.
- **b** Find the time for the plant to reach:
  - **i** 30 mm **ii** 10 cm.
- **c** Complete this table.

t	0	1	2	3	4
h					

- **d** Complete this graph.



- **e** Find the gradient of the graph.

3–5 | 3–6 | 3–6

FLUENCY

Example 9

3 A 300 litre fish tank takes 3 hours to fill from a hose.

- **a** What is the rate at which water is poured into the tank?
- **b** Draw a graph of volume (V litres) vs time (t hours) using $0 \leq t \leq 3$.
- **c** Find:
  - **i** the gradient of your graph
  - **ii** the rule for V.
- **d** Use your rule to find:
  - **i** the volume after 1.5 hours
  - **ii** the time to fill 200 litres.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4E

4 A solar powered car travels 100 km in 4 hours.

a What is the rate of change of distance over time (i.e. speed)?

b Draw a graph of distance (d km) versus time (t hours) using $0 \leq t \leq 4$.

c Find:

i the gradient of your graph

ii the rule for d.

d Use your rule to find:

i the distance after 2.5 hours

ii the time to travel 40 km.

5 Write down a rule linking the given variables.

a I travel 600 km in 12 hours. Use d for distance in km and t for time in hours.

b A calf grows 12 cm in 6 months. Use g for growth height in cm and t for time in months.

c The cost of petrol is \$100 for 80 litres. Use \$$C$ for cost and n for the number of litres.

d The profit is \$10 000 for 500 tonnes. Use \$$P$ for profit and t for the number of tonnes.

6 Use the gradient to find the rate of change of distance over time (speed) for these graphs. Use the units given on each graph.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4E

7, 8 | 7–9 | 9, 10

PROBLEM-SOLVING

7 A car's trip computer says that the fuel economy for a trip is 8.5 L per 100 km.

- **a** How many litres would be used for 120 km?
- **b** How many litres would be used for 850 km?
- **c** How many kilometres could be travelled if the car's petrol tank capacity was 68 L?

8 Who is travelling the fastest?

- Mick runs 120 m in 20 seconds.
- Sally rides 700 m in 1 minute.
- Udhav jogs 2000 m in 5 minutes.

9 Which animal is travelling the slowest?

- A leopard runs 200 m in 15 seconds.
- A jaguar runs 2.5 km in 3 minutes.
- A panther runs 60 km in 1.2 hours.

10 An investment fund starts at \$0 and grows at a rate of \$100 per month. Another fund starts at \$4000 and reduces by \$720 per year. After how long will the funds have the same amount of money?

By using direct proportion, we can determine the slowest wild cat.

11 | 11, 12 | 12–14

REASONING

11 The circumference of a circle (given by $C = 2\pi r$) is directly proportional to its radius.

- **a** Find the circumference for a circle with the given radius. Give an exact answer like 6π.
  - **i** $r = 0$ **ii** $r = 2$ **iii** $r = 6$
- **b** Draw a graph of C against r for $0 \leq r \leq 6$. Use exact values for C.
- **c** Find the gradient of your graph. What do you notice?

12 Is the area of a circle directly proportional to its radius? Give a reason.

13 The base length of a triangle is 4 cm but its height h cm is variable.

- **a** Write a rule for the area of this triangle.
- **b** What is the rate at which the area changes with respect to height h?

14 Over a given time interval, is an object's speed directly proportional to the distance travelled? Give a rule for speed (s) in terms of distance (d) if the time taken is 5 hours.

Rate challenge | — | — | 15, 16

ENRICHMENT

15 Hose A can fill a bucket in 2 minutes and hose B can fill the same bucket in 3 minutes. How long would it take to fill the bucket if both hoses were used at the same time?

16 A river is flowing downstream at a rate of 2 km/h. Murray can swim at a rate of 3 km/h. Murray jumps in and swims downstream for a certain distance then turns around and swims upstream back to the start. In total it takes 30 minutes. How far did Murray swim downstream?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4F Gradient–intercept form

Interactive

Widgets

HOTsheets

Walkthroughs

Shown here is the graph of the rule $y = 2x - 1$. It shows a gradient of 2 and a y-intercept of -1. The fact that these two numbers correspond to numbers in the rule is no coincidence. This is why rules written in this form are called gradient–intercept form. Other examples of rules in this form include:

$$y = -5x + 2,\ y = \frac{1}{2}x - 0.5 \text{ and } y = \frac{x}{5} + 20.$$



Let's start: Family traits

The graph of a linear relation can be sketched easily if you know the gradient and the y-intercept. If one of these is kept constant, we create a family of graphs.

Different y-intercepts and same gradient



Different gradients and same y-intercept



- For the first family, discuss the relationship between the y-intercept and the given rule for each graph.
- For the second family, discuss the relationship between the gradient and the given rule for each graph.

Key ideas

- m = gradient y-intercept = c

  $y = mx + c$ (or $y = mx + b$ depending on preference) is the **gradient–intercept form** of a straight line equation.
- If the y-intercept is zero, the equation becomes $y = mx$ and these graphs will therefore pass through the origin.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- To sketch a graph using the **gradient–intercept method**, locate the y-intercept and use the gradient to find a second point.
  For example, if $m = \frac{2}{5}$, move 5 across and 2 up.



Example 10 Stating the gradient and y-intercept

State the gradient and the y-intercept for the graphs of the following relations.

a $y = 2x + 1$ b $y = -3x$

SOLUTION | **EXPLANATION**

a $y = 2x + 1$ — The rule is given in gradient-intercept form.

The gradient = 2 — The gradient is the coefficient of x.

y-intercept = 1 — The constant term is the y-intercept.

b $y = -3x$

The gradient = -3 — The gradient is the coefficient of x including the negative sign.

y-intercept = 0 — The constant term is not present so the y-intercept = 0.

Example 11 Rearranging linear equations

Rearrange these linear equations into the form shown in the brackets.

a $4x + 2y = 10$ $(y = mx + c)$ b $y = 4x - 7$ $(ax + by = d)$

SOLUTION | **EXPLANATION**

a $4x + 2y = 10$ — Subtract $4x$ from both sides. Here $10 - 4x$ is better written as $-4x + 10$.

$2y = -4x + 10$

$y = -2x + 5$ — Divide both sides by 2.

b $y = 4x - 7$

$y - 4x = -7$ — Subtract $4x$ from both sides.

or $-4x + y = -7$

or $4x - y = 7$ — Multiply both sides by -1 to convert between forms.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Sketching linear graphs using the gradient and y-intercept

Find the value of the gradient and y-intercept for these relations and sketch their graphs.

a $y = 2x - 1$ **b** $x + 2y = 6$

SOLUTION	EXPLANATION
a $y = 2x - 1$	The rule is in gradient–intercept form so we can read off the gradient and the y-intercept.
y intercept $= -1$	
gradient $= 2 = \frac{2}{1}$	
	Label the y-intercept at $(0, -1)$. From the gradient $\frac{2}{1}$, for every 1 across, move 2 up. From $(0, -1)$ this gives a second point at $(1, 1)$. Mark and join the points to form a line.
b $x + 2y = 6$	Rewrite in the form $y = mx + c$ to read off the gradient and y-intercept. Make y the subject by subtracting x from both sides and then dividing both sides by 2.
$2y = -x + 6$	
$y = \frac{-x + 6}{2}$	$\frac{-x}{2}$ is the same as $-\frac{1}{2}x$ and $6 \div 2 = 3$.
$= -\frac{1}{2}x + 3$	
so the y-intercept is 3	
$m = -\frac{1}{2} = \frac{-1}{2}$	Link the negative sign to the rise (-1) so the run is positive $(+2)$.
	Mark the y-intercept at $(0, 3)$ then from this point move 2 right and 1 down to give a second point at $(2, 2)$. Note that the x-intercept will be 6. If the gradient is $\frac{-1}{2}$ then a run of 6 gives a fall of 3.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4F

1–3 | 3 | —

UNDERSTANDING

1 Write a rule (in gradient–intercept form) for a straight line with the given properties.

a gradient = 2, y-intercept = 5
b gradient = 3, y-intercept = –1
c gradient = –2, y-intercept = 3
d gradient = –1, y-intercept = –2
e gradient = $-\frac{1}{2}$, y-intercept = –10
f gradient = $-\frac{2}{3}$, y-intercept = $\frac{5}{2}$

2 Substitute $x = -3$ to find the value of y for these rules.

a $y = x + 4$
b $y = x - 2$
c $y = 2x + 1$
d $y = 3x - 2$
e $y = -2x + 3$
f $y = -x - 1$

3 Rearrange to make y the subject.

a $y - x = 7$
b $x + y = 3$
c $2y - 4x = 10$

4–7(½) | 4–7(½) | 4–7(½)

FLUENCY

Example 10

4 State the gradient and y-intercept for the graphs of the following relations.

a $y = 3x - 4$
b $y = -5x - 2$
c $y = -2x + 3$
d $y = \frac{1}{3}x + 4$
e $y = -4x$
f $y = 2x$
g $y = x$
h $y = -0.7x$

Example 11

5 Rearrange these linear equations into the form shown in the brackets.

a $2x + y = 3$ $(y = mx + c)$
b $-3x + y = -1$ $(y = mx + c)$
c $6x + 2y = 4$ $(y = mx + c)$
d $-3x + 3y = 6$ $(y = mx + c)$
e $y = 2x - 1$ $(ax + by = d)$
f $y = -3x + 4$ $(ax + by = d)$
g $3y = x - 1$ $(ax + by = d)$
h $7y - 2 = 2x$ $(ax + by = d)$

Example 12a

6 Find the gradient and y-intercept for these relations and sketch their graphs.

a $y = x - 2$
b $y = 2x - 1$
c $y = \frac{1}{2}x + 1$
d $y = -\frac{1}{2}x + 2$
e $y = -3x + 3$
f $y = \frac{3}{2}x + 1$
g $y = -\frac{4}{3}x$
h $y = \frac{5}{3}x - \frac{1}{3}$

Example 12b

7 Find the gradient and y-intercept for these relations and sketch their graphs.
Rearrange each equation first.

a $x + y = 4$
b $x - y = 6$
c $x + 2y = 6$
d $x - 2y = 8$
e $2x - 3y = 6$
f $4x + 3y = 12$
g $x - 3y = -4$
h $2x + 3y = 6$
i $3x - 4y = 12$
j $x + 4y = 0$
k $x - 5y = 0$
l $x - 2y = 0$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4F

8 | 8, 9–11(½) | 9–11(½)

PROBLEM-SOLVING

8 Match the following equations to the straight lines shown.

i $y = 3$ **ii** $y = -2x - 1$ **iii** $y = -2x - 4$

iv $y = x + 3$ **v** $x = 2$ **vi** $y = x + 2$

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4F

PROBLEM-SOLVING

9 Sketch the graph of each of the following linear relations, by finding the gradient and y-intercept.

a $5x - 2y = 10$ **b** $y = 6$ **c** $x + y = 0$ **d** $y = 5 - x$

e $y = \frac{x}{2} - 1$ **f** $4y - 3x = 0$ **g** $4x + y - 8 = 0$ **h** $2x + 3y - 6 = 0$

10 Decide if the following points are on the line with rule $3x - y = 7$.

a $(1, -2)$ **b** $(-1, 4)$ **c** $(5, 8)$ **d** $(-2, -10)$

11 Which of these linear relations have a gradient of 2 and y-intercept of -3?

a $y = 2(x - 3)$ **b** $y = 3 - 2x$ **c** $y = \frac{3 - 2x}{-1}$ **d** $y = 2(x - 1.5)$

e $y = \frac{2x - 6}{2}$ **f** $y = \frac{4x - 6}{2}$ **g** $2y = 4x - 3$ **h** $-2y = 6 - 4x$

12 | 12, 13 | 13, 14

REASONING

12 Jeremy says that the graph of the rule $y = 2(x + 1)$ has gradient 2 and y-intercept 1.

a Explain his error.

b What can be done to the rule to help show the y-intercept?

13 A horizontal line has gradient 0 and y-intercept at $(0, k)$. Using gradient–intercept form, write the rule for the line.

14 Write the rule $ax + by = d$ in gradient–intercept form. Then state the gradient m and the y-intercept.

ENRICHMENT

The missing y-intercept — | — | 15

15 This graph shows two points $(-1, 3)$ and $(1, 4)$ with a gradient of $\frac{1}{2}$. By considering the gradient, the y-intercept can be calculated to be 3.5 (or $\frac{7}{2}$) so $y = \frac{1}{2}x + \frac{7}{2}$.



Use this approach to find the rule of the line passing through these points.

a $(-1, 1)$ and $(1, 5)$ **b** $(-2, 4)$ and $(2, 0)$

c $(-1, -1)$ and $(2, 4)$ **d** $(-3, 1)$ and $(2, -1)$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4G Finding the equation of a line

Interactive

Widgets

HOTsheets

Walkthroughs

Using gradient–intercept form, the rule (or equation) of a line can be found by calculating the value of the gradient and the y-intercept. Given a graph, the gradient can be calculated using two points. If the y-intercept is known then the value of the constant in the rule is obvious, but if not, another point can be used to help find its value.

Let's start: But we don't know the y-intercept!

A line with the rule $y = mx + c$ passes through two points $(-1, 3)$ and $(1, -2)$.

- Using the information given is it possible to find the value of m? If so, calculate its value.
- The y-intercept is not given on the graph. Discuss what information could be used to find the value of the constant c in the rule. Is there more than one way you can find the y-intercept?
- Write the rule for the line.



Key ideas

- To find the equation of a line in gradient–intercept form $y = mx + c$, you need to find:
  - the value of the gradient (m) using $m = \frac{\text{rise}}{\text{run}}$
  - the value of the constant (c), by observing the y-intercept or by substituting another point.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Finding the equation of a line given the y-intercept and another point

Determine the equation of the straight line shown here.



SOLUTION

$y = mx + c$

$m = \frac{\text{rise}}{\text{run}}$

$= \frac{-4}{2}$

$= -2$

y-intercept $= -4$.

$\therefore y = -2x - 4$

EXPLANATION

Write down the general straight line equation.



The y-intercept is -4.

Substitute $m = -2$ and the y-intercept into the general equation.

Example 14 Finding the equation of a line given the gradient and a point

Find the equation of the line which has a gradient m of $\frac{1}{3}$ and passes through the point $(9, 2)$.

SOLUTION

$y = mx + c$

$y = \frac{1}{3}x + c$

$2 = \frac{1}{3}(9) + c$

$2 = 3 + c$

$-1 = c$

$\therefore y = \frac{1}{3}x - 1$

EXPLANATION

Substitute $m = \frac{1}{3}$ into $y = mx + c$.

Since $(9, 2)$ is on the line, it must satisfy the equation $y = \frac{1}{3}x + c$, hence substitute the point $(9, 2)$ where $x = 9$ and $y = 2$ to find c. Simplify and solve for c.

Write the equation in the form $y = mx + c$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4G

1, 2 | 2(½) | —

UNDERSTANDING

1 Substitute the given values of m and c into $y = mx + c$ to write the rule.

a $m = 2, c = 5$

b $m = 4, c = -1$

c $m = -2, c = 5$

d $m = -1, c = -\frac{1}{2}$

2 Substitute the point into the given rule and solve to find the value of c. For example, using (3, 4), substitute $x = 3$ and $y = 4$ into the rule.

a $(3, 4), y = x + c$

b $(1, 5), y = 2x + c$

c $(-2, 3), y = 3x + c$

d $(-1, 6), y = 4x + c$

e $(3, -1), y = -2x + c$

f $(-2, 4), y = -x + c$

3–4(½) | 3–5(½) | 3–5(½)

FLUENCY

Example 13

3 Determine the equation of the following straight lines.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 Find the equation of these straight lines, which have fractional gradients.

a



b



c



d



e



f



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4G

Example 14

FLUENCY

5 Find the equation of the line which:

a has a gradient of 3 and passes through the point (1, 8)
b has a gradient of –2 and passes through the point (2, –5)
c has a gradient of –3 and passes through the point (2, 2)
d has a gradient of 1 and passes through the point (1, –2)
e has a gradient of –3 and passes through the point (–1, 6)
f has a gradient of 5 and passes through the point (2, 9)
g has a gradient of –1 and passes through the point (4, 4)
h has a gradient of –3 and passes through the point (3, –3)
i has a gradient of –2 and passes through the point (–1, 4)
j has a gradient of – 4 and passes through the point (–2, –1).

PROBLEM-SOLVING

6–8 | 6(½), 7–9 | 8–10

6 For the line connecting the following pairs of points:

i find the gradient **ii** find the equation

a (2, 6) and (4, 10) **b** (–3, 6) and (5, –2)
c (1, 7) and (3, –1) **d** (– 4, –8) and (1, –3)

7 A line has gradient –2 and y-intercept 5. Find its x-intercept.

8 A line passes through the points (–1, –2) and (3, 3). Find its x- and y-intercepts.

9 The tap on a tank has been left on and water is running out. The volume of water in the tank after 1 hour is 100 L and after 5 hours the volume is 20 L. Assuming the relationship is linear, find a rule and then state the initial volume of water in the tank.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4G

PROBLEM-SOLVING

10 The coordinates (0, 0) mark the take-off point for a rocket constructed as part of a science class. The positive x direction from (0, 0) is considered to be east.

a Find the equation of the rocket's path if it rises at a rate of 5 m vertically for every 1 m in an easterly direction.

b A second rocket is fired 2 m vertically above from where the first rocket was launched. It rises at a rate of 13 m for every 2 m in an easterly direction. Find the equation describing its path.

	11	11, 12	12, 13

REASONING

11 A line has equation $y = mx - 2$. Find the value of m if the line passes through:

a (2, 0) **b** (1, 6) **c** (–1, 4) **d** (–2, –7)

12 A line with rule $y = 2x + c$ passes through (1, 5) and (2, 7).

a Find the value of c using the point (1, 5).

b Find the value of c using the point (2, 7).

c Does it matter which point you use? Explain.

13 A line passes through the origin and the point (a, b). Write its equation in terms of a and b.

The general rule	—	—	14

ENRICHMENT

14 To find the equation of a line between two points (x_1, y_1) and (x_2, y_2) some people prefer to use the rule:

$$y - y_1 = m(x - x_1) \text{ where } m = \frac{y_2 - y_1}{x_2 - x_1}$$

Use this rule to find the equation of the line passing through these pairs of points. Write your answer in the form $y = mx + c$.

a (1, 2) and (3, 6) **b** (0, 4) and (2, 0)

c (–1, 3) and (1, 7) **d** (–4, 8) and (2, –1)

e (–3, –2) and (4, 3) **f** (–2, 5) and (1, –8)

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

4A **1** Read off the x- and y-intercepts from this table and graph.

a

x	–2	–1	0	1	2	3
y	–8	–6	–4	–2	0	2

b



4A **2** Decide if the point $(-1, 3)$ is on the line with the given rules.

a $y = 2x - 1$ **b** $y = 2x + 5$

4B **3** Sketch the graph of the following relations, by finding the x- and y-intercepts.

a $3x + 2y = 6$ **b** $y = \frac{3x}{4} + 3$

4C **4** Sketch the graphs of these special lines all on the same set of axes and label with their equations.

a $y = 2$ **b** $x = 4$ **c** $y = 2x$

4D **5** For each graph state whether the gradient is positive, negative, zero or undefined, then find the gradient where possible.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c



d



4D **6** Find the gradient (m) of the line joining the given points.

a $P(2, 5)$ and $Q(4, 9)$ **b** $A(-3, 2)$ and $B(1, -10)$

4E **7** An empty tank on a water truck is being filled. It takes 4 hours to fill the tank with 6000 litres.

a What is the rate at which water is poured into the tank?

b Draw a graph of volume (V litres) vs time (t hours) using $0 \leq t \leq 4$.

c Find:

i the gradient of your graph **ii** the rule for V.

d Use your rule to find:

i the volume after 3 hours **ii** the time to fill 5250 litres.

4F **8** Rearrange these linear equations into the form shown in the brackets.

a $5x + y = 8$ $(y = mx + c)$ **b** $y = 3x - 5$ $(ax + by = d)$

4F **9** Find the value of the gradient and y-intercept for these relations and sketch their graphs.

a $y = 3x - 2$ **b** $2x + 3y = 9$

4G **10** Determine the equation of the following straight lines.

a A line which has a gradient of 5 and passes through the point (0, 8)

b A line which has a gradient of –3 and passes through the point (–2, 1)

c



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4H Midpoint and length of a line segment

A line segment (or line interval) has a defined length and therefore must have a midpoint. Both the midpoint and length can be found by using the coordinates of the endpoints.

Let's start: Choosing a method

This graph shows a line segment between the points at (–2, –1) and (2, 3).



- What is the horizontal distance between the two points?
- What is the vertical distance between the two points?
- What is the x-coordinate of the point halfway along the line segment?
- What is the y-coordinate of the point halfway along the line segment?
- Discuss and explain a method for finding the midpoint of a line segment.
- Discuss and explain a method for finding the length of a line segment.

Using graphing software or dynamic geometry software, produce a line segment like the one shown above. Label the coordinates of the endpoints and the midpoint. Also find the length of the line segment. Now drag one or both of the endpoints to a new position.

- Describe how the coordinates of the midpoint relate to the coordinates of the endpoints. Is this true for all positions of the endpoints that you choose?
- Now use your software to calculate the vertical distance and the horizontal distance between the two endpoints. Then square these lengths. Describe these squared lengths compared to the square of the length of the line segment. Is this true for all positions of the endpoints that you choose?

Key ideas

- The **midpoint** (M) of a line segment is the halfway point between the two endpoints.
  - The x-coordinate is the average (mean) of the x-coordinates of the two endpoints.
  - The y-coordinate is the average (mean) of the y-coordinates of the two end points.
  - $M = \left(\frac{x_1 + x_2}{2}, \frac{y_1 + y_2}{2}\right)$



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- The **length of a line segment** (or line interval) is found using Pythagoras' theorem. This gives the distance between any two points.
  - The line segment is the hypotenuse (longest side) of a right-angled triangle.
  - Find the horizontal distance by subtracting the lower x-coordinate from the upper x-coordinate.
  - Find the vertical distance by subtracting the lower y-coordinate from the upper y-coordinate.



$$\text{horizontal distance} = -1 - (-3)$$
$$= 2$$
$$\text{vertical distance} = 5 - 2$$
$$= 3$$

$$c^2 = 2^2 + 3^2$$
$$= 13$$
$$\therefore\ c = \sqrt{13}$$

Example 15 Finding a midpoint

Find the midpoint $M(x, y)$ of the line segment joining these pairs of points.

a (1, 0) and (4, 4)

b (−3, −2) and (5, 3)

SOLUTION

EXPLANATION

a $x = \dfrac{1+4}{2} = 2.5$

$y = \dfrac{0+4}{2} = 2$

$\therefore M = (2.5, 2)$

Find the average (mean) of the x-coordinates and y-coordinates for both points.

b $x = \dfrac{-3+5}{2} = 1$

$y = \dfrac{-2+3}{2} = 0.5$

$\therefore M = (1, 0.5)$



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 16 Finding the length of a segment

Find the length of the segment joining $(-2, 2)$ and $(4, -1)$, correct to two decimal places.

SOLUTION

$$\text{Horizontal length} = 4 - (-2)$$
$$= 6$$
$$\text{Vertical length} = 2 - (-1)$$
$$= 3$$

$$c^2 = 6^2 + 3^2$$
$$= 45$$
$$\therefore c = \sqrt{45}$$
$$\therefore \text{length} = 6.71 \text{ units (to 2 d.p.)}$$

EXPLANATION



Apply Pythagoras' theorem $c^2 = a^2 + b^2$.

Round as required.

Exercise 4H

1–3 | 3 | —

UNDERSTANDING

1 Find the number which is halfway between these pairs of numbers.

a 1, 7 **b** 5, 11 **c** –2, 4 **d** –6, 0

2 Find the average (mean) of these pairs of numbers.

a 4, 7 **b** 0, 5 **c** –3, 0 **d** –4, –1

3 Evaluate c in the following correct to two decimal places.

a $c^2 = 1^2 + 2^2$ **b** $c^2 = 5^2 + 7^2$ **c** $c^2 = 10^2 + 2^2$

4–5(½) | 4–5(½) | 4–5(½)

FLUENCY

Example 15

4 Find the midpoint $M(x, y)$ of the segment joining these pairs of points.

a (0, 0) and (6, 6) **b** (0, 0) and (4, 4)
c (0, 2) and (2, 8) **d** (3, 0) and (5, 2)
e (–2, 0) and (0, 6) **f** (–4, –2) and (2, 0)
g (1, 3) and (2, 0) **h** (–1, 5) and (6, –1)
i (–3, 7) and (4, –1) **j** (–2, –4) and (–1, –1)
k (–7, –16) and (1, –1) **l** (–4, –3) and (5, –2)

Example 16

5 Find the length of the segment joining these pairs of points correct to two decimal places.

a (1, 1) and (2, 6) **b** (1, 2) and (3, 4) **c** (0, 2) and (5, 0)
d (–2, 0) and (0, –4) **e** (–1, 3) and (2, 1) **f** (–2, –2) and (0, 0)
g (–1, 7) and (3, –1) **h** (–4, –1) and (2, 3) **i** (–3, –4) and (3, –1)

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4H

6, 7 | 6, 8 | 7–9

PROBLEM-SOLVING

6 Find the missing coordinates in this table if M is the midpoint of points A and B.

A	B	M
(4, 2)		(6, 1)
	(0, –1)	(–3, 2)
	(4, 4)	(–1, 6.5)

7 A circle has centre (2, 1). Find the coordinates of the endpoint of a diameter if the other endpoint has these coordinates.

a (7, 1) **b** (3, 6) **c** (–4, –0.5)

8 Find the perimeter of these shapes correct to one decimal place.

a A triangle with vertices (–2, 0), (–2, 5) and (1, 3).

b A trapezium with vertices (–6, –2), (1, –2), (0, 4) and (–5, 4).

9 Find the coordinates of the four points which have integer coordinates and are a distance of $\sqrt{5}$ from the point (1, 2). *Hint*: $5 = 1^2 + 2^2$.

10 | 10, 11 | 10, 11

REASONING

10 A line segment has two endpoints (x_1, y_1) and (x_2, y_2) and a midpoint $M(x, y)$.

a Write a rule for x, the x-coordinate of the midpoint.

b Write a rule for y, the y-coordinate of the midpoint.

c Test your rule to find the coordinates of M if $x_1 = -3$, $y_1 = 2$, $x_2 = 5$ and $y_2 = -3$.

11 A line segment has two endpoints (x_1, y_1) and (x_2, y_2). Assume $x_2 > x_1$ and $y_2 > y_1$.

a Write a rule for:

i the horizontal distance between the endpoints

ii the vertical distance between the endpoints

iii the length of the segment.

b Use your rule to show that the length of the segment joining (–2, 3) with (1, –3) is $\sqrt{45}$.

Division by ratio | — | — | 12

ENRICHMENT

12 Looking from left to right, this line segment shows the point $P(-1, 0)$ which divides the segment in the ratio 1 : 2.



a What fraction of the horizontal distance between the endpoints is P from A?

b What fraction of the vertical distance between the endpoints is P from A?

c Find the coordinates of point P on the segment AB if it divides the segment in these ratios.

i 2 : 1 **ii** 1 : 5 **iii** 5 : 1

d Find the coordinates of point P which divides the segments with the given endpoints in the ratio 2 : 3.

i $A(-3, -1)$ and $B(2, 4)$ **ii** $A(-4, 9)$ and $B(1, -1)$

iii $A(-2, -3)$ and $B(4, 0)$ **iv** $A(-6, -1)$ and $B(3, 8)$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4I Perpendicular and parallel lines

EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Perpendicular and parallel lines are commonplace in mathematics and in the world around us. Using parallel lines in buildings, for example, ensures that beams or posts point in the same direction. Perpendicular beams help to construct rectangular shapes, which are central in the building of modern structures.

Perpendicular and parallel lines are central to construction.

Let's start: How are they related?

This graph shows a pair of parallel lines and a line perpendicular to the other two. Find the equation of all three lines.



- What do you notice about the equation for the pair of parallel lines?
- What do you notice about the gradient of the line that is perpendicular to the other two lines?
- Write down the equations of three other lines that are parallel to $y = -2x$.
- Write down the equations of three other lines that are perpendicular to $y = -2x$.

Key ideas

- If two lines are **parallel** then they have the same gradient.
- If two **perpendicular** lines (at right angles) have gradients m_1 and m_2 then

$$m_1 \times m_2 = -1 \text{ or } m_2 = -\frac{1}{m_1}$$



- The **negative reciprocal** of m_1 gives m_2

For example: If $m_1 = 4$ then $m_2 = -\frac{1}{4}$

If $m_1 = -\frac{2}{3}$ then $m_2 = \frac{-1}{\left(-\frac{2}{3}\right)} = -1 \times \left(-\frac{3}{2}\right) = \frac{3}{2}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 17 Finding the equation of a parallel line

Find the equation of a line which is parallel to $y = 3x - 1$ and passes through $(0, 4)$.

SOLUTION	EXPLANATION
$y = mx + c$	Since it's parallel to $y = 3x - 1$, the gradient is the same so $m = 3$.
$m = 3$	
$c = 4$	The y-intercept is given in the question so $c = 4$.
$\therefore y = 3x + 4$	

Example 18 Finding the equation of a perpendicular line

Find the equation of a line which is perpendicular to the line $y = 2x - 3$ and passes through $(0, -1)$.

SOLUTION	EXPLANATION
$y = mx + c$	Since it is perpendicular to $y = 2x - 3$,
$m = -\frac{1}{2}$	$m_2 = -\frac{1}{m_1} = -\frac{1}{2}$
$c = -1$	The y-intercept is given.
$y = -\frac{1}{2}x - 1$	

Exercise 4I

1–3 | 2, 3 | —

UNDERSTANDING

1 Decide if the pairs of lines with these equations are parallel (have the same gradient).

a $y = 3x - 1$ and $y = 3x + 4$

b $y = 2x - 1$ and $y = 2x - 3$

c $y = 7x - 2$ and $y = 2x - 7$

d $y = x + 4$ and $y = x - 3$

e $y = \frac{1}{2}x - 1$ and $y = -\frac{1}{2}x + 2$

f $y = -\frac{3}{4}x + 4$ and $y = -\frac{3}{4}x - 6$

2 Two perpendicular lines with gradients m_1 and m_2 are such that $m_2 = -\frac{1}{m_1}$. Find m_2 for the given values of m_1.

a $m_1 = 5$

b $m_1 = 10$

c $m_1 = -3$

d $m_1 = -6$

3 Decide if the pairs of lines with these equations are perpendicular.

a $y = 4x - 2$ and $y = -\frac{1}{4}x + 3$

b $y = 2x - 3$ and $y = \frac{1}{2}x + 4$

c $y = -\frac{1}{2}x + 6$ and $y = -\frac{1}{2}x - 2$

d $y = -\frac{1}{5}x + 1$ and $y = 5x + 2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4I

4–5(½) | 4–6(½) | 4–6(½)

FLUENCY

Example 17

4 Find the equation of the line which is:

a parallel to the line with equation $y = 2x + 3$ and passes through $(0, 1)$

b parallel to the line with equation $y = 4x + 2$ and passes through $(0, 8)$

c parallel to the line with equation $y = -x + 3$ and passes through $(0, 5)$

d parallel to the line with equation $y = -2x - 3$ and passes through $(0, -7)$

e parallel to the line with equation $y = \frac{2}{3}x + 6$ and passes through $(0, -5)$

f parallel to the line with equation $y = -\frac{4}{5}x - 3$ and passes through $(0, \frac{1}{2})$.

Example 18

5 Find the equation of the line which is:

a perpendicular to the line with equation $y = 3x - 2$ and passes through $(0, 3)$

b perpendicular to the line with equation $y = 5x - 4$ and passes through $(0, 7)$

c perpendicular to the line with equation $y = -2x + 3$ and passes through $(0, -4)$

d perpendicular to the line with equation $y = -x + 7$ and passes through $(0, 4)$

e perpendicular to the line with equation $y = -7x + 2$ and passes through $(0, -\frac{1}{2})$

f perpendicular to the line with equation $y = x - \frac{3}{2}$ and passes through $(0, \frac{5}{4})$.

6 **a** Write the equation of the line parallel to $y = 4$ which passes through:

i $(0, 1)$ **ii** $(0, -3)$

iii $(1, 6)$ **iv** $(-3, -2)$.

b Write the equation of the line parallel to $x = -2$ which passes through:

i $(3, 0)$ **ii** $(-4, 0)$

iii $(1, 5)$ **iv** $(-3, -3)$.

c Write the equation of the line perpendicular to $y = -3$ which passes through:

i $(2, 0)$ **ii** $(-1, 0)$

iii $(0, 0)$ **iv** $(3, 5)$.

d Write the equation of the line perpendicular to $x = 6$ which passes through:

i $(0, 7)$ **ii** $(0, -\frac{1}{2})$ **iii** $(1, 3)$ **iv** $(-2, \frac{1}{2})$

7 | 7, 8 | 7–9

PROBLEM-SOLVING

7 Find the equation of the line which is:

a parallel to the line with equation $y = -3x - 7$ and passes through $(3, 0)$; remember to substitute the point $(3, 0)$ to find the value of the y-intercept

b parallel to the line with equation $y = \frac{1}{2}x + 2$ and passes through $(1, 3)$

c perpendicular to the line with equation $y = 5x - 4$ and passes through $(1, 6)$

d perpendicular to the line with equation $y = -x - \frac{1}{2}$ and passes through $(-2, 3)$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4I

PROBLEM-SOLVING

8 A right-angled isosceles triangle has vertices at (0, 3), (3, 0) and (–3, 0). Find the equation of each of the three sides.



9 A parallelogram has two side lengths of 5 units. Three of its sides have equations $y = 0$, $y = 2$, $y = 2x$. Find the equation of the fourth side.

	10	10, 11	10, 11

REASONING

10 a Using $m_2 = -\frac{1}{m_1}$, find the gradient of a line perpendicular to the line with the given gradient.

i $m_1 = \frac{2}{3}$ **ii** $m_1 = \frac{1}{5}$ **iii** $m_1 = -\frac{1}{7}$ **iv** $m_1 = -\frac{3}{11}$

b If $m_1 = \frac{a}{b}$, find m_2 given $m_1 \times m_2 = -1$.

11 a Find the gradient of a line that is parallel to:

i $2x + 4y = 9$ **ii** $3x - y = 8$

b Find the gradient of a line which is perpendicular to

i $5x + 5y = 2$ **ii** $7x - y = -1$

Perpendicular bisectors	—	—	12

ENRICHMENT

12 If a line segment AB is cut by another line PQ at right angles at the midpoint (M) of AB then PQ is called the perpendicular bisector.

By firstly finding the midpoint of AB, find the equation of the perpendicular bisector of the segment connecting these points.



a $A(1, 1), B(3, 5)$
b $A(0, 6), B(4, 0)$
c $A(–2, 3), B(6, –1)$
d $A(–6, –1), B(0, 2)$
e $A(–1, 3), B(2, –4)$
f $A(–6, –5), B(4, 7)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4J Linear modelling

If a relationship between two variables is linear, the graph will be a straight line and the equation linking the two variables can be written in gradient–intercept form. The process of describing and using such line graphs and rules for the relationship between two variables is called linear modelling. A test car, for example, increasing its speed from 100 km/h to 200 km/h in 10 seconds with constant acceleration could be modelled by the rule $S = 10t + 100$. This rule could then be used to calculate the speed at different times in the test run.



Let's start: The test car

The graph shown above describes the speed of a racing car over a 10 second period.

- Explain why the rule is $S = 10t + 100$.
- Why might negative values of t not be considered for the graph?
- How could you accurately calculate the speed after 6.5 seconds?
- If the car continued to accelerate at the same rate, how could you accurately predict the car's speed after 13.2 seconds?

Key ideas

- Many situations can often be **modelled** by using a linear rule or graph. The key elements of linear modelling include:
  - finding the rule linking the two variables
  - sketching a graph
  - using the graph or rule to predict or estimate the value of one variable given the other
  - finding the rate of change of one variable with respect to the other variable – this is equivalent to finding the gradient.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 19 Applying linear relations

The deal offered by Netshare, an internet provider, to its new customers is a fixed charge of $20 per month plus $5 per hour of use.

a Write a rule for the total monthly cost, $\$C$, of using Netshare for t hours per month.

b Sketch the graph of C versus t using $0 \leq t \leq 10$.

c What is the total cost in a month when Netshare is used for 4 hours?

d If the monthly cost was $50, for how many hours was Netshare used during the month?

SOLUTION	EXPLANATION
a $C = 20 + 5t$	A fixed amount of $20 plus $5 for each hour.
b C-intercept is 20 At $t = 10$, $C = 20 + 5(10)$ $= 70$ $\therefore$ endpoint is (10, 70)  	Let $t = 0$ to find the C-intercept. Letting $t = 10$ gives $C = 70$ and this gives the other endpoint. Sketch the graph using the points (0, 20) and (10, 70).
c $C = 20 + 5t$ $= 20 + 5(4)$ $= 40$ The cost is $40.	Substitute $t = 4$ into the rule. Answer the question using the correct units.
d $C = 20 + 5t$ $50 = 20 + 5t$ $30 = 5t$ $t = 6$ Netshare was used for 6 hours.	Write the rule and substitute $C = 50$. Solve the resulting equation for t by subtracting 20 from both sides then dividing both sides by 5. Answer the question in words.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4J

1–3	3(½)	—

UNDERSTANDING

1 A person gets paid \$50 plus \$20 per hour. Decide which rule describes the relationship between the pay \$$P$ and number of hours n.

A $P = 50 + n$ **B** $P = 50 + 20n$ **C** $P = 50n + 20$ **D** $P = 20 + 50$

2 The amount of money in a bank account is \$1000 and is increasing by \$100 per month.

a Find the amount of money in the account after:

i 2 months **ii** 5 months **iii** 12 months

b Write a rule for the amount of money A dollars after n months.

3 If $d = 5t - 4$, find:

a d if $t = 10$ **b** d if $t = 1.5$ **c** t if $d = 6$ **d** t if $d = 11$

4–6	4–6	4, 5, 7

FLUENCY

Example 19

4 A sales representative earns \$400 a week plus \$20 for each sale she makes.

a Write a rule which gives the total weekly wage, \$$W$, if the sales representative makes x sales.

b Draw a graph of W versus x using $0 \leq x \leq 40$.

c How much does the sales representative earn if, in a particular week, she makes 12 sales?

d If, in a particular week, the sales representative earns \$1000, how many sales did she make?

5 A plumber charges a \$40 fee up-front and \$50 for each hour he works.

a Find a linear equation for the total charge, \$$C$, for n hours of work.

b What will a 4 hour job cost?

c If the plumber works on a job for two days and averages 6 hours per day, what will the total cost be?

6 A catering company charges \$500 for the hire of a marquee, plus \$25 per guest.

a Write a rule for the cost, \$$C$, of hiring a marquee and catering for n guests.

b Draw a graph of C versus n for $0 \leq n \leq 100$.

c How much would a party catering for 40 guests cost?

d If a party cost \$2250, how many guests were catered for?

7 The cost, \$$C$, of recording a music CD is \$300, plus \$120 per hour of studio time.

a Write a rule for the cost, \$$C$, of recording a CD requiring t hours of studio time.

b Draw a graph of C versus t for $0 \leq t \leq 10$.

c How much does a recording requiring 6 hours of studio time cost?

d If a recording cost \$660 to make, for how long was the studio used?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4J

8, 9 | 8, 9 | 9, 10

PROBLEM-SOLVING

8 A petrol tank holds 66 litres of fuel. If it contains 12 litres of petrol initially and the petrol pump fills it at 3 litres every 10 seconds, find:

- **a** a linear equation for the amount of fuel (F litres) in the tank after t minutes
- **b** how long it will take to fill the tank
- **c** how long it will take to add 45 litres into the petrol tank.

9 A tank is initially full with 4000 L of water and water is being used at a rate of 20 L per minute.

- **a** Write a rule for the volume, V litres, of water after t minutes.
- **b** Calculate the volume after 1.5 hours.
- **c** How long will it take for the tank to be emptied?
- **d** How long will it take for the tank to have only 500 L?

10 A spa pool contains 1500 litres of water. It is draining at the rate of 50 litres per minute.

- **a** Draw a graph of the volume of water, V litres, remaining after t minutes.
- **b** Write a rule for the volume of water at time t minutes.
- **c** What does the gradient represent?
- **d** What is the volume of water remaining after 5 minutes?
- **e** After how many minutes is the pool half empty?

11 | 11 | 11, 12

REASONING

11 The rule for distance travelled d km over a given time t hours for a moving vehicle is given by $d = 50 + 80t$.

- **a** What is the speed of the vehicle?
- **b** If the speed was actually 70 km per hour, how would this change the rule? Give the new rule.

12 The altitude, h metres, of a helicopter t seconds after it begins its descent is given by $h = 350 - 20t$.

- **a** At what rate is the helicopter altitude decreasing?
- **b** At what rate is the helicopter altitude increasing?
- **c** What is the helicopter's initial height?
- **d** How long will it take for the helicopter to reach the ground?
- **e** If instead the rule was $h = 350 + 20t$, describe what the helicopter would be doing.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4J Sausages and cars

— — 13, 14

ENRICHMENT

13 Joanne organised a sausage sizzle to raise money for her science club. The hire of the barbecue cost Joanne $20, and the sausages cost 40c each.

a **i** Write a rule for the total cost, $\$C$, if Joanne buys and cooks n sausages.

ii If the total cost was $84, how many sausages did Joanne buy?

b **i** If Joanne sells each sausage for $1.20, write a rule to find her profit, $\$P$, after buying and selling n sausages.

ii How many sausages must she sell to 'break even'?

iii If Joanne's profit was $76, how many sausages did she buy and sell?

14 The directors of a car manufacturing company believe that, in order to make a new component, they would need to spend $6700 on set-up costs, and each component would cost $10 to make. They make x components.

a Write a rule for the total cost, $\$C$, of producing x components.

b Find the cost of producing 200 components.

c How many components could be produced for $13 000?

d Find the cost of producing 500 components.

e If each component is able to be sold for $20, how many must they sell to 'break even'?

f Write a rule for the profit, $\$P$, in terms of x.

g Write a rule for the profit, $\$T$, per component in terms of x.

h Find x, the number of components, if the profit per component is to be $5.

Linear modelling is used in manufacturing and service industries to calculate cost and profit for different rates of production.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4K Graphical solutions to simultaneous equations

To find a point that satisfies more than one equation involves finding the solution to simultaneous equations. An algebraic approach was considered in Chapter 2. Graphically, this involves finding an intersection point.

This road intersection in Perth is an example of an intersection of two linear features.

Let's start: Accuracy counts

Two graphs have the rules $y = x$ and $y = 2 - 4x$.

Accurately sketch the graphs of both rules on a large set of axes like the one shown.



- State the x value of the point at the intersection of your two graphs.
- State the y value of the point at the intersection of your two graphs.
- Discuss how you could use the rules to check if your point is correct.
- If your point does not satisfy both rules, check the accuracy of your graphs and try again.

Key ideas

- When we consider two or more equations at the same time, they are called **simultaneous equations**.
- To determine the **point of intersection** of two lines we can use an accurate graph and determine its coordinates (x, y). Two situations can arise.
  - The two graphs intersect at one point only and there is one solution (x, y).
  - The point of intersection is simultaneously on both lines and is the **solution** to the simultaneous equations.



  - The two lines are parallel and there is no intersection.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 20 Checking an intersection point

Decide if the given point is at the intersection of the two lines with the given equations.

a $y = 2x + 3$ and $y = -x$ with point $(-1, 1)$

b $y = -2x$ and $3x + 2y = 4$ with point $(2, -4)$

SOLUTION	EXPLANATION
a Substitute $x = -1$	
$y = 2x + 3$	Substitute $x = -1$ into $y = 2x + 3$ to see if $y = 1$.
$= 2 \times (-1) + 3$	If so, then $(-1, 1)$ is on the line.
$= -2 + 3$	
$= 1$	
So $(-1, 1)$ satisfies $y = 2x + 3$.	
$y = -x$	Repeat for $y = -x$.
$= -(-1)$	
$= 1$	
So $(-1, 1)$ satisfies $y = -x$	
$\therefore$ $(-1, 1)$ is the intersection point.	If $(-1, 1)$ is on both lines then it must be the intersection point.
b Substitute $x = 2$	Substitute $x = 2$ into $y = -2x$ to see if $y = -4$.
$y = -2x$	
$= -2 \times (2)$	
$= -4$	
So $(2, -4)$ satisfies $y = -2x$.	If so, then $(2, -4)$ is on the line.
$3x + 2y = 4$	Substitute $x = 2$ and $y = -4$ to see if $3x + 2y = 4$ is true.
$3 \times (2) + 2 \times (-4) = 4$	
$6 + (-8) = 4$	
$-2 = 4$ (false)	Clearly, the equation is not satisfied.
So $(2, -4)$ is not on the line.	
$\therefore$ $(2, -4)$ is not the intersection point.	Since the point is not on both lines, it cannot be the intersection point.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 21 Solving simultaneous equations graphically

Solve the simultaneous equations $y = 2x - 2$ and $x + y = 4$ graphically.

SOLUTION

$y = 2x - 2$

y-intercept (let $x = 0$):

$y = 2 \times (0) - 2$

$y = -2$

x-intercept (let $y = 0$):

$0 = 2x - 2$

$2 = 2x$

$x = 1$

$x + y = 4$

y-intercept (let $x = 0$):

$(0) + y = 4$

$y = 4$

x-intercept (let $y = 0$):

$x + (0) = 4$

$x = 4$



The intersection point is (2, 2).

EXPLANATION

Sketch each linear graph by first finding the y-intercept (substitute $x = 0$) and the x-intercept (substitute $y = 0$ and solve the resulting equation).

Repeat the process for the second equation.

Sketch both graphs on the same set of axes by marking in intercepts and joining in a straight line.

Ensure that the axes are scaled accurately.

Locate the intersection point and read off the coordinates.

The point (2, 2) simultaneously belongs to both lines.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4K

1–3 | 3 | —

UNDERSTANDING

1 Give the coordinates of the point of intersection for these pairs of lines.

a



b



c



2 Decide if the point (1, 3) satisfies these equations. (*Hint:* substitute (1, 3) into each equation to see if the equation is true.)

a $y = 2x + 1$ **b** $y = -x + 5$

c $y = -2x - 1$ **d** $y = 4x - 1$

3 Consider the two lines with the rules $y = 5x$ and $y = 3x + 2$ and the point (1, 5).

a Substitute (1, 5) into $y = 5x$. Does (1, 5) sit on the line with equation $y = 5x$?

b Substitute (1, 5) into $y = 3x + 2$. Does (1, 5) sit on the line with equation $y = 3x + 2$?

c Is (1, 5) the intersection point of the lines with the given equations?

4–5(½) | 4–5(½) | 4–5(½)

FLUENCY

Example 20

4 Decide if the given point is at the intersection of the two lines with the given equations.

a $y = x + 2$ and $y = 3x$ with point (1, 3).

b $y = 3x - 4$ and $y = 2x - 2$ with point (2, 2).

c $y = -x + 3$ and $y = -x$ with point (2, 1).

d $y = -4x + 1$ and $y = -x - 1$ with point $(1, -3)$.

e $x + 2y = 6$ and $3x - 4y = -2$ with point (2, 2).

f $x - y = 10$ and $2x + y = 8$ with point $(6, -4)$.

g $2x + y = 0$ and $y = 3x + 4$ with point $(-1, 2)$.

h $x - 3y = 13$ and $y = -x - 1$ with point $(4, -3)$.



These planes need to make sure that their paths do not intersect at the same point in time.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4K

FLUENCY

Example 21

5 Solve these pairs of simultaneous equations graphically by finding the coordinates of the intersection point.

a $2x + y = 6$
$x + y = 4$

b $3x - y = 7$
$y = 2x - 4$

c $y = x - 6$
$y = -2x$

d $y = 2x - 4$
$x + y = 5$

e $2x - y = 3$
$3x + y = 7$

f $y = 2x + 1$
$y = 3x - 2$

g $x + y = 3$
$3x + 2y = 7$

h $y = x + 2$
$y = 3x - 2$

i $y = x - 3$
$y = 2x - 7$

j $y = 3$
$x + y = 2$

k $y = 2x - 3$
$x = -1$

l $y = 4x - 1$
$y = 3$

6, 7 | 6, 7 | 7, 8

PROBLEM-SOLVING

6 A company manufactures electrical components. The cost, $\$C$ (including rent, materials and labour), is given by the rule $C = n + 3000$, and its revenue, $\$R$, is given by the rule $R = 5n$, where n is the number of components produced.

a Sketch the graphs of C and R on the same set of axes and determine the point of intersection.

b State the number of components n where the costs $\$C$ are equal to the revenue $\$R$.

7 Dvdcom and Associates manufacture DVDs. Its costs, $\$C$, are given by the rule $C = 4n + 2400$, and its revenue, $\$R$, is given by the rule $R = 6n$, where n is the number of DVDs produced. Sketch the graphs of C and R on the same set of axes and determine the number of DVDs to be produced if the costs are equal to the revenue.

8 Two asteroids are 1000 km apart and are heading straight for each other. One asteroid is travelling at 59 km per second and the other at 41 km per second. How long does it take for them to collide?

9 | 9, 10 | 9–11

REASONING

9 Explain why the graphs of the rules $y = 3x - 7$ and $y = 3x + 4$ have no intersection point.

10 For the following families of graphs, determine their points of intersection (if any).

a $y = x, y = 2x, y = 3x$

b $y = x, y = -2x, y = 3x$

c $y = x + 1, y = x + 2, y = x + 3$

d $y = -x + 1, y = -x + 2, y = -x + 3$

e $y = 2x + 1, y = 3x + 1, y = 4x + 1$

f $y = 2x + 3, y = 3x + 3, y = 4x + 3$

11 **a** If two lines have the equations $y = 3x + 1$ and $y = 2x + c$, find the value of c if the intersection point is at $x = 1$.

b If two lines have the equations $y = mx - 4$ and $y = -2x - 3$, find the value of m if the intersection point is at $x = -1$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4K Intersecting to find triangular areas — — 12, 13

ENRICHMENT

12 The three lines with equations $y = 0$, $y = x + 2$ and $y = -2x + 5$ are illustrated here.



- **a** State the coordinates of the intersection point of $y = x + 2$ and $y = -2x + 5$.
- **b** Use $A = \frac{1}{2}bh$ to find the area of the enclosed triangle ABC.

13 Use the method outlined in Question **12** to find the area enclosed by these sets of three lines.

- **a** $y = 0$, $y = x + 3$ and $y = -2x + 9$
- **b** $y = 0$, $y = \frac{1}{2}x + 1$ and $y = -x + 10$
- **c** $y = 2$, $x - y = 5$ and $x + y = 1$
- **d** $y = -5$, $2x + y = 3$ and $y = x$
- **e** $x = -3$, $y = -3x$ and $x - 2y = -7$

Using a CAS calculator 4K: Finding intersection points

This activity is in the interactive textbook in the form of a printable PDF.



The calculation of intersection points of lines has many applications in science and technology.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Coming and going

The distance between two towns, Palton and Verton, is 100 km. Two cyclists travel in opposite directions between the towns, starting their journeys at the same time. Cyclist A travels from Palton to Verton at a speed of 20 km/h while cyclist B travels from Verton to Palton at a speed of 25 km/h.



Measuring the distance from Palton

a Using d_A km as the distance cyclist A is from Palton after t hours explain why the rule connecting d_A and t is $d_A = 20t$.

b Using d_B km as the distance cyclist B is from Palton after t hours explain why the rule connecting d_B and t is $d_B = 100 - 25t$.

Technology – spreadsheet (alternatively use a graphics or CAS calculator – see parts e and f below)

c Instructions:

- Enter the time in hours into column A starting at 0 hours.
- Enter the formulae for the distances d_A and d_B into columns B and C.
- Use the **Fill down** function to fill in the columns. Fill down until the distances show that both cyclists have completed their journey.

	A	B	C
1	0	= 20* A1	= 100 – 25* A1
2	= A1 + 1		
3			

d **i** Determine how long it takes for cyclist A to reach Verton.

ii Determine how long it takes for cyclist B to reach Palton.

iii After which hour are the cyclists the closest?

Alternative technology – graphics or CAS calculator

e Instructions:

- Enter or define the formulae for the distances d_A and d_B.
- Go to the table and scroll down to view the distance for each cyclist at hourly intervals. You may need to change the settings so that t increases by 1 each time.

f **i** Determine how long it takes for cyclist A to reach Verton.

ii Determine how long it takes for cyclist B to reach Palton.

iii After which hour are the cyclists the closest?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Investigating the intersection

a Change the time increment to a smaller unit for your chosen technology.

- Spreadsheet: Try 0.5 hours using '= A1 + 0.5' or 0.1 hours using '= A1 + 0.1' in column A.
- Graphics or CAS calculator: Try changing the t increment to 0.5 or 0.1.

b Fill or scroll down to ensure that the distances show that both cyclists have completed their journey.

c Determine the time at which the cyclists are the closest.

d Continue altering the time increment until you are satisfied that you have found the time of intersection of the cyclists correct to one decimal place.

e **Extension** Complete part **d** above but find an answer correct to three decimal places.

The graph

a Sketch a graph of d_A and d_B on the same set of axes. Scale your axes carefully to ensure that the full journey for both cyclists is represented.

b Determine the intersection point as accurately as possible on your graph and hence estimate the time when the cyclists meet.

c Use technology (graphing calculator) to confirm the point of intersection and hence determine the time at which the cyclists meet correct to three decimal places.

Algebra and proof

a At the point of intersection it could be said that $d_A = d_B$.
This means that $20t = 100 - 25t$.
Solve this equation for t.

b Find the exact distance from Palton at the point where the cyclists meet.

Reflection

Write a paragraph describing the journey of the two cyclists. Comment on the following:

- the speeds of the cyclists
- their meeting point
- the difference in computer and algebraic approaches in finding the time of the intersection point.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 A tank with 520 L of water begins to leak at a rate of 2 L per day. At the same time, a second tank is being filled at a rate of 1 L per hour starting at 0 L. How long does it take for the tanks to have the same volume?

2 Two cars travel towards each other on a 400 km stretch of road. One car travels at 90 km/h and the other at 70 km/h. How long does it take before they pass each other?

3 The points $(-1, 4)$, $(4, 6)$, $(2, 7)$ and $(-3, 5)$ are the vertices of a parallelogram. Find the midpoints of its diagonals. What do you notice?

4 A trapezium is enclosed by the straight lines $y = 0, y = 3, y = 7 - x$ and $x = k$, where k is a constant. Find the possible values of k if the trapezium has an area of 24 units^2.

5 Prove that the triangle with vertices at the points $A(-1, 3)$, $B(0, -1)$ and $C(3, 2)$ is isosceles.

6 Find the perimeter (to the nearest whole number) and area of the triangle enclosed by the lines with equations $x = -4$, $y = x$ and $y = -2x - 3$.

7 $ABCD$ is a parallelogram. A, B and C have coordinates $(5, 8)$, $(2, 5)$ and $(3, 4)$ respectively. Find the coordinates of D.

8 A kite is formed by joining the points $A(a, b)$, $B(-1, 3)$, $C(x, y)$ and $D(3, -5)$.

- **a** Determine the equations of the diagonals BD and AC of this kite.
- **b** Given $a = -5$ and $y = 4$, find the values of b and x.
- **c** Find the area of the kite (without the use of a calculator).

9 A trapezium is enclosed by the straight lines $y = 0, y = 6, y = 8 - 2x$ and $y = x + k$, where k is a constant. Find the possible values of k if the trapezium has an area of 66 units^2.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter summary

Linear relations

Direct proportion

If two variables are directly proportional, their rule is of the form $y = mx$. The gradient of the graph represents the rate of change of y with respect to x, e.g. for a car travelling at 60 km/h for t hours, distance $= 60t$.

Gradient

This measures the slope of a line



Gradient $m = \frac{\text{rise}}{\text{run}}$

$m = \frac{4}{2} = 2$

e.g.



Parallel and perpendicular lines (Ext)

Parallel lines have the same gradient
e.g. $y = 2x + 3$, $y = 2x - 1$ and $y = 2x$

Perpendicular lines are at right angles
Their gradients m_1 and m_2 are such that $m_1 m_2 = -1$, i.e. $m_2 = -\frac{1}{m_1}$

A line perpendicular to $y = 2x + 3$ has gradient $-\frac{1}{2}$

Linear graphs

Sketch with two points. Often we find the x-intercept ($y = 0$) and y-intercept ($x = 0$).

e.g. $y = 2x - 4$

y-int: $x = 0$, $y = 2(0) - 4$
$= -4$

x-int: $y = 0$, $0 = 2x - 4$
$2x = 4$
$x = 2$



Graphical solutions of simultaneous equations

Graph each line and read off the point of intersection.



Parallel lines have no intersection point



Straight line

$y = mx + c$

gradient, y-intercept

In the form $ax + by = d$, rearrange to $y = mx + c$ form to read off gradient and y-intercept

A linear relation is made up of points (x, y) that form a straight line when plotted

Linear modelling

Define variables to represent the problem and write a rule relating the two variables. The rate of change of one variable with respect to the other is the gradient.

Finding the equation of a line

Gradient–intercept form ($y = mx + c$)
Require gradient and y-intercept or any other point to substitute e.g.
line with gradient 3 passes through point (2, 1)
$\therefore y = 3x + c$
substitute $x = 2$, $y = 1$
$1 = 3(2) + c$
$1 = 6 + c$
$\therefore c = -5$
$y = 3x - 5$

Midpoint and length of a line segment

Midpoint is halfway between segment endpoints, e.g. midpoint of segment joining (−1, 2) and (3, 6)

$M = \left(\frac{x_1 + x_2}{2}, \frac{y_1 + y_2}{2}\right)$

$x = \frac{-1 + 3}{2} = 1$

$y = \frac{2 + 6}{2} = 4$, i.e. (1, 4)

Length of segment



$c^2 = 4^2 + 4^2$
$c = \sqrt{32}$
$c = 5.7$ (to 1 d.p.)

Special lines

Horizontal line $y = c$
e.g. $y = 3$



Vertical line $x = b$
e.g. $x = 2$



$y = mx$ passes through the origin, substitute $x = 1$ to find another point e.g. $y = 3x$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

4A **1** The x- and y-intercepts of the graph of $2x + 4y = 12$ are respectively:

A 4, 2 **B** 3, 2
C 6, 3 **D** 2, 12
E 8, 6

4B **2** The graph of $y = 3x - 6$ is represented by:

A



B



C



D



E



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

4D **3** The gradient of the line joining the points $(1, -2)$ and $(5, 6)$ is:

A 2 **B** 1 **C** 3

D -1 **E** $\frac{1}{3}$

4A **4** The point that is not on the straight line $y = -2x + 3$ is:

A $(1, 1)$ **B** $(0, 3)$ **C** $(2, 0)$

D $(-2, 7)$ **E** $(3, -3)$

4F **5** The linear graph that *does not* have a gradient of 3 is:

A $y = 3x + 7$ **B** $\frac{y}{3} = x + 2$ **C** $2y - 6x = 1$

D $y - 3x = 4$ **E** $3x + y = -1$

4G **6** A straight line has a gradient of -2 and passes through the point $(0, 5)$, its equation is:

A $2y = -2x + 10$ **B** $y = -2x + 5$ **C** $y = 5x - 2$

D $y - 2x = 5$ **E** $y = -2(x - 5)$

4G **7** The equation of the graph shown is:

A $y = x + 1$

B $y = \frac{1}{2}x + 4$

C $y = 2x + 1$

D $y = -2x - 1$

E $y = \frac{1}{2}x + 2$



4H **8** The length of the line segment joining the points $A(1, 2)$ and $B(4, 6)$ is:

A 5 **B** $\frac{4}{3}$ **C** 7

D $\sqrt{5}$ **E** $\sqrt{2}$

4I **9** The gradient of a line perpendicular to $y = 4x - 7$ would be:

Ext

A $\frac{1}{4}$ **B** 4 **C** -4

D $-\frac{1}{4}$ **E** -7

4K **10** The point of intersection of $y = 2x$ and $y = 6 - x$ is:

A $(6, 2)$ **B** $(-1, -2)$ **C** $(6, 12)$

D $(2, 4)$ **E** $(3, 6)$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

4A **1** Read off the x- and y-intercepts from the table and graph.

a

x	–2	–1	0	1	2
y	0	2	4	6	8

b



4B **2** Sketch the following linear graphs labelling x- and y-intercepts.

a $y = 2x - 4$ **b** $y = 3x + 9$ **c** $y = -2x + 5$ **d** $y = -x + 4$

e $2x + 4y = 8$ **f** $4x - 2y = 10$ **g** $2x - y = 7$ **h** $-3x + 6y = 12$

4B **3** Holly leaves her beach house by car and drives back to her home. Her distance d kilometres from her home after t hours is given by $d = 175 - 70t$.

a How far is her beach house from her home?

b How long does it take to reach her home?

c Sketch a graph of her journey between the beach house and her home.

4C **4** Sketch the following lines.

a $y = 3$ **b** $y = -2$ **c** $x = -4$ **d** $x = 5$ **e** $y = 3x$ **f** $y = -2x$

4D **5** By first plotting the given points, find the gradient of the line passing through the points.

a (3, 1) and (5, 5) **b** (2, 5) and (4, 3) **c** (1, 6) and (3, 1)

d (–1, 2) and (2, 6) **e** (–3, –2) and (1, 6) **f** (–2, 6) and (1, –4)

4E **6** An inflatable backyard swimming pool is being filled with water by a hose. It takes 4 hours to fill 8000 L.

a What is the rate at which water is poured into the pool?

b Draw a graph of volume (V litres) versus time (t hours) for $0 \leq t \leq 4$.

c By finding the gradient of your graph, give the rule for V in terms of t.

d Use your rule to find the time to fill 5000 L.

4F **7** For each of the following linear relations, state the value of the gradient and the y-intercept and then sketch using the gradient–intercept method.

a $y = 2x + 3$ **b** $y = -3x + 7$ **c** $2x + 3y = 9$ **d** $2y - 3x - 8 = 0$

4G **8** Give the equation of the straight line that:

a has gradient 3 and passes through the point (0, 2)

b has gradient –2 and passes through the point (3, 0)

c has gradient $\frac{4}{3}$ and passes through the point (6, 3).

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

4G **9** Find the equations of the linear graphs below.

a



b



c



d



4H **10** For the line segment joining the following pairs of points, find:

i the midpoint **ii** the length (to two decimal places where applicable)

a (2, 4) and (6, 8) **b** (5, 2) and (10, 7)

c (–2, 1) and (2, 7) **d** (–5, 7) and (–1, –2)

4H **11** Find the missing coordinate, n, if:

a the line joining $(-1, 3)$ and $(2, n)$ has gradient 2

b the line segment joining $(-2, 2)$ and $(4, n)$ has length 10, $n > 0$

c the midpoint of the segment joining $(n, 1)$ and $(1, -3)$ is $(3.5, -1)$.

4I Ext **12** Determine the linear equation that is:

a parallel to the line $y = 2x - 1$ and passes through the point (0, 4)

b parallel to the line $y = -x + 4$ and passes through the point $(0, -3)$

c perpendicular to the line $y = 2x + 3$ and passes through the point $(0, -1)$

d perpendicular to the line $y = -\frac{1}{3}x - 2$ and passes through the point (0, 4)

e parallel to the line $y = 3x - 2$ and passes through the point (1, 4)

f parallel to the line $3x + 2y = 10$ and passes through the point $(-2, 7)$.

4K **13** Determine if the point (2, 5) is the intersection point of the graphs of the following pairs of equations.

a $y = 4x - 3$ and $y = -2x + 6$

b $3x - 2y = -4$ and $2x + y = 9$

4K **14** Find the point of intersection of the following straight lines.

a $y = 2x - 4$ and $y = 6 - 3x$

b $2x + 3y = 8$ and $y = -x + 2$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 Joe requires an electrician to come to his house to do some work. He is trying to choose between two electricians he has been recommended.

a The first electrician's cost, $\$C$, is given by $C = 80 + 40n$ where n is the number of hours the job takes.

- **i** State the hourly rate this electrician charges and his initial fee for coming to the house.
- **ii** Sketch a graph of C versus n for $0 \leq n \leq 8$.
- **iii** What is the cost of a job that takes 2.5 hours?
- **iv** If the job costs \$280, how many hours did it take?

b The second electrician charges a callout fee of \$65 to visit the house and then \$45 per hour thereafter.

- **i** Give the equation for the cost, C, of a job that takes n hours.
- **ii** Sketch the graph of part **b i** for $0 \leq n \leq 8$ on the same axes as the graph in part **a**.

c Determine the point of intersection of the two graphs.

d After how many hours does the first electrician become the cheaper option?

2 Abby has set up a small business making clay vases. She is trying to determine the selling price of these vases to ensure that she makes a weekly profit.

Abby has determined that the cost of producing 7 vases in a week was \$146 and the cost of producing 12 vases in a week was \$186.

a Find a linear rule relating the production cost, $\$C$, to the number of vases produced, v.

b Use your rule to state:

- **i** the initial cost of materials each week
- **ii** the ongoing cost of production per vase.

At a selling price of \$12 per vase Abby determines her weekly profit to be given by $P = 4v - 90$.

c How many vases must she sell in order to make a profit?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 5 Measurement

What you will learn

5A Length and perimeter (Consolidating)
5B Circumference and perimeter of a sector
5C Area
5D Composite shapes
5E Surface area of prisms and pyramids
5F Surface area of a cylinder
5G Volume of prisms
5H Volume of a cylinder

Australian curriculum

NUMBER AND ALGEBRA

Using units of measurement

Calculate the areas of composite shapes

Calculate the surface area and volume of cylinders and solve related problems

Solve problems involving the surface area and volume of right prisms

Essential Mathematics for the Australian Curriculum Year 9 2ed

ISBN 978-1-107-57007-8

© Greenwood et al. 2016

Cambridge University Press

Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

The Millau Viaduct

The Millau Viaduct in France opened in 2005 and is the tallest bridge structure in the world. Some of the measurements for the construction of the bridge include:

- maximum pylon height 343 m above ground
- length 2.46 km
- concrete volume 80 000 m^3
- steel cables 1500 tonnes
- road/deck area 70 000 m^2

Many of these measurements are calculated by considering basic shapes that make up the bridge's structure. These include circles (cross-section for the main piers) and trapeziums (cross-section for the bridge deck). Lengths, areas and volumes were measured using metric units like kilometres (km) for length, square metres (m^2) for area and cubic metres (m^3) for volume. You can imagine how important accurate measurements are to the planning, financing and building of such a bridge structure.

ISBN 978-1-107-57007-6
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5A Length and perimeter CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Length is at the foundation of measurement from which the concepts of perimeter, circumference, area and volume are developed. From the use of the royal cubit (distance from tip of middle finger to the elbow) used by the ancient Egyptians to the calculation of pi (π) by modern computers, units of length have helped to create the world in which we live.



Units of length are essential in measuring distance, area and volume.

Let's start: Not enough information?

All the angles at each vertex in this shape are 90° and the two given lengths are 10 cm and 13 cm.

- The simple question is: Is there enough information to find the perimeter of the shape?
- If there is enough information, find the perimeter and discuss your method. If not then say what information needs to be provided.



Key ideas

■ To convert between **metric units** of length multiply or divide by the appropriate power of 10.



■ **Perimeter** is the distance around a closed shape.
- Sides with the same markings are of equal length



$P = 2 \times 5 + 3$
$= 13$ cm

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Finding perimeters of simple shapes

Find the perimeter of each of the following shapes.

a



b



SOLUTION

a Perimeter $= 2 \times 12 + 2 \times 18$

$= 24 + 36$

$= 60$ m

b Perimeter $= (2 \times 5) + 6 + 3 + 2 + 1$

$= 22$ cm

Alternatively:

Perimeter $= 2 \times 6 + 2 \times 5$

$= 22$ cm

EXPLANATION

Two lengths of 12 m and two lengths of 18 m.

Missing sides are:

5 cm – 3 cm = 2 cm

6 cm – 5 cm = 1 cm



2 opposite sides each of combined length 6 cm

2 opposite sides each of combined length 5 cm

Example 2 Finding missing sides given a perimeter

Find the unknown side length in this shape with the given perimeter.



Perimeter = 16 m

SOLUTION

$2 \times 5 + 4 + x = 16$

$14 + x = 16$

$x = 2$

$\therefore$ the missing length is 2 m

EXPLANATION

Add all the lengths and set equal to the given perimeter.

Solve for the unknown.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 5A

1–4 | 4(½) | —

UNDERSTANDING

1 Convert the following length measurements into the units given in the brackets.

a 5 cm (mm) **b** 2.8 m (cm) **c** 521 mm (cm)

d 83.7 cm (m) **e** 4.6 km (m) **f** 2170 m (km)

2 A steel beam is 8.25 m long and 22.5 mm wide. Write down the length and the width of the beam in centimetres.

3 Write down the values of the pronumerals in these shapes. All angles at vertices are 90°.

a



b



c



Example 1a

4 Find the perimeter of each of the following shapes.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5–7 | 5(½), 6, 7–8(½) | 5–8(½)

5A

FLUENCY

Example 1b

5 Find the perimeter of each of the following composite shapes.

a



b



c



d



e



f



6 Find the perimeter of each of these shapes. You will need to convert the measurements to the same units. Give your answers in the units given in red.

a



b



c



7 Convert the following measurements into the units given in the brackets.

a 8 m (mm)
b 110 000 mm (m)
c 0.00001 km (cm)
d 0.02 m (mm)
e 28 400 cm (km)
f 62 743 000 mm (km)

Example 2

8 Find the unknown side length in these shapes with the given perimeters.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5A

9, 10 | 9–11 | 10–12

PROBLEM-SOLVING

9 A lion enclosure is made up of five straight fence sections. Three sections are 20 m in length and the other two sections are 15.5 m and 32.5 m. Find the perimeter of the enclosure.

10 Find the perimeter of these shapes. Assume all angles are right angles.

a



b



c



11 Find the value of x in these shapes with the given perimeter.

a



b



c



12 A photo 12 cm wide and 20 cm long is surrounded with a picture frame 3 cm wide. Find the outside perimeter of the framed picture.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

13 | 13, 14 | 14, 15 — 5A

REASONING

13 Give the rule for the perimeter of these shapes using the given pronumerals, e.g. $P = 3a + 2b$.

a



b



c



d



e



f



14 Explain why you do not need any more information to find the perimeter of this shape assuming all angles are right angles.



15 A piece of string 1 m long is divided into parts according to the given ratios. Find the length of each part.

a 1 : 3 **b** 2 : 3 **c** 5 : 3 **d** 1 : 2 : 3 : 4

Picture framing

— | — | 16

ENRICHMENT

16 A square picture of side length 20 cm is surrounded by a frame of width x cm.



a Find the perimeter of the framed picture if:

i $x = 2$ **ii** $x = 3$ **iii** $x = 5$

b Write a rule for the perimeter P of the framed picture in terms of x.

c Use your rule to find the perimeter if:

i $x = 3.7$ **ii** $x = 7.05$

d Use your rule to find the value of x if:

i the perimeter is 90 cm

ii the perimeter is 102 cm.

e Is there a value of x for which the perimeter is 75 cm? Explain.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5B Circumference and perimeter of a sector

A portion of a circle enclosed by two radii and an arc is called a sector. The perimeter of a sector is made up of three components: two radii and the circular arc. Given an angle θ it is possible to find the length of the arc using the rule for the circumference of a circle $C = 2\pi r$ or $C = \pi d$.



Let's start: Perimeter of a sector

A sector is formed by dividing a circle with two radius cuts. The angle between the two radii determines the size of the sector. The perimeter will therefore depend on both the radius length and the angle between them.

- Complete this table to see if you can determine a rule for the perimeter of a sector. Remember that the circumference C of a circle is given by $C = 2\pi r$ where r is the radius length.

Shape	Fraction of full circle	Working
	$\frac{90}{360} = \frac{1}{4}$	$P = 2 \times 3 + \frac{1}{4} \times 2\pi \times 3 \approx 10.71$
	$\frac{270}{360} =$	$P =$
		$P =$
		$P =$
		$P =$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Circumference** of a circle $C = 2\pi r$ or $C = \pi d$.
  - Use $\frac{22}{7}$ or 3.14 to approximate π or use technology for more precise calculations.



- A **sector** is a portion of a circle enclosed by two radii and an arc.
  Special sectors include:
  - a half circle, called a **semicircle**
  - a quarter circle, called a **quadrant**.
- The perimeter of a sector is given by $P = 2r + \frac{\theta}{360} \times 2\pi r$.



- The symbol for pi (π) can be used to write an answer exactly.
  For example, $C = 2\pi r$
  $= 2\pi \times 3$
  $= 6\pi$



Example 3 Finding the circumference of a circle and perimeter of a sector

Find the circumference of this circle and perimeter of this sector correct to two decimal places.

a



b



SOLUTION	EXPLANATION
a $C = 2\pi r$ $= 2 \times \pi \times 3$ $= 6\pi$ $= 18.85$ cm (to 2 d.p.)	Use the formula $C = 2\pi r$ or $C = \pi d$ and substitute $r = 3$ (or $d = 6$). 6π would be the exact answer and 18.85 is the rounded answer. Give units.
b $P = 2r + \frac{\theta}{360} \times 2\pi r$ $= 2 \times 7 + \frac{100}{360} \times 2 \times \pi \times 7$ $= 14 + \frac{35\pi}{9}$ $= 26.22$ m (to 2 d.p.)	Write the formula. The fraction of the circle is $\frac{100}{360}$ (or $\frac{5}{18}$). $14 + \frac{35\pi}{9}$ is the exact answer. Use a calculator and round the two decimal places.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 4 Using exact values

Give the exact circumference/perimeter of these shapes.

a 

b 

SOLUTION	EXPLANATION
a $C = 2\pi r$	Write the formula with $r = 4$
$= 2 \times \pi \times 4$	$2 \times \pi \times 4 = 2 \times 4 \times \pi$
$= 8\pi$	Write the answer exactly in terms of π.
b $P = 2 \times r + \frac{\theta}{360} \times 2\pi r$	Use the perimeter of a sector formula.
$= 2 \times 2 + \frac{270}{360} \times 2\pi \times 2$	The angle inside the sector is 270° so the fraction is $\frac{270}{360} = \frac{3}{4}$.
$= 4 + \frac{3}{4} \times 4\pi$	
$= 4 + 3\pi$	$4 + 3\pi$ cannot be simplified further.

Exercise 5B

1–4 | 2(½), 4 | —

UNDERSTANDING

1 a What is the radius of a circle if its diameter is 5.6 cm?
b What is the diameter of a circle if its radius is 48 mm?

2 Simplify these numbers to give an exact answer. Do not evaluate with a calculator or round off. The first one is done for you.

a $2 \times 3 \times \pi = 6\pi$ b $6 \times 2\pi$ c $7 \times 2.5 \times \pi$

d $3 + \frac{1}{2} \times 4\pi$ e $2 \times 6 + \frac{1}{4} \times 12\pi$ f $2 \times 5 + \frac{2}{5} \times 2 \times \pi \times 5$

g $2 \times 4 + \frac{90}{360} \times 2 \times \pi \times 4$ h $3 + \frac{270}{360} \times \pi$ i $7 + \frac{30}{360} \times \pi$

3 Determine the fraction of a circle shown in these sectors. Write the fraction in simplest form.

a 

b 

c 

d 

e 

f 

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5B

UNDERSTANDING

Example 3a

4 Find the circumference of these circles, correct to two decimal places. Use a calculator for the value of π.

a



b



c



d



5–7(½) 5–8(½) 5–8(½)

FLUENCY

Example 3b

5 Find the perimeter of these sectors, correct to two decimal places.

a



b



c



d (Quadrant)



e (Semicircle)



f



6 Find the circumference of these circles without a calculator using the given approximation of π.

a



$\pi = 3.14$

b



$\pi = 3.14$

c



$\pi = \frac{22}{7}$

d



$\pi = \frac{22}{7}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5B

FLUENCY

Example 4a

7 Give the exact circumference of these circles.

a



b



c



d



e



f



Example 4b

8 Give the exact perimeter of these sectors.

a



b



c



d



e



f



PROBLEM-SOLVING

9, 10 | 9–11 | 10–12

9 Find the distance around the outside of a circular pool of radius 4.5 m, correct to two decimal places.

10 Find the length of string required to surround the circular trunk of a tree that has a diameter of 1.3 m, correct to one decimal place.

11 The end of a cylinder has a radius of 5 cm. Find the circumference of the end of the cylinder, correct to two decimal places.

12 A wheel of radius 30 cm is rolled in a straight line.

a Find the circumference of the wheel correct to two decimal places.

b How far, correct to two decimal places, has the wheel rolled after completing:

i 2 rotations? **ii** 10.5 rotations?



c Can you find how many rotations would be required to cover at least 1 km in length? Round to the nearest whole number.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5B

13 | 13 | 13(½), 14

REASONING

13 Give exact answers for the perimeter of these shapes. Express answers using fractions.

a



b



c



d



e



f



14 We know that the rule for the circumference of a circle is $C = 2\pi r$.

a Find a rule for r in terms of C.

b Find the radius of a circle to one decimal place if its circumference is:

i 10 cm **ii** 25 m

c Give the rule for the diameter of a circle in terms of its circumference C.

d After 1000 rotations a wheel has travelled 2.12 km. Find its diameter to the nearest centimetre.

The ferris wheel

— | — | 15

ENRICHMENT

15 A large ferris wheel has a radius of 21 m. Round to two decimal places for these questions.

a Find the distance a person will travel on one rotation of the wheel.

b A ride includes 6 rotations of the wheel. What distance is travelled in one ride?

c How many rotations would be required to ride a distance of:

i 500 m? **ii** 2 km?

d A ferris wheel has a sign which reads, 'One ride of 10 rotations will cover 2 km'. What must be the diameter of the wheel?

We can find the distance travelled from one rotation by calculating its circumference.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5C Area

The number of square centimetres in this rectangle is 6; therefore the area is 6 cm^2.



A quicker way to find the number of squares is to note that there are two rows of three squares and hence the area is $2 \times 3 = 6$ cm^2. This leads to the formula $A = l \times w$ for the area of a rectangle.

For many common shapes, such as the parallelogram and trapezium, the rules for their area can be developed through consideration of simple rectangles and triangles. Shapes that involve circles or sectors rely on calculations involving pi (π).

How many tiles cover this area?

Let's start: Formula for the area of a sector

We know that the area of a circle with radius r is given by the rule $A = \pi r^2$.

Complete this table of values to develop the rule for the area of a sector.

Shape	Fraction of full circle	Working and answers
	1	$A = \pi \times 2^2 \approx 12.57$ units^2
	$\frac{180}{360} =$	$A = \frac{1}{2} \times$
		$A =$
		$A =$
		$A =$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

■ Conversion of area units



$10^2 = 10 \times 10 = 100$

$100^2 = 100 \times 100 = 10\,000$

$1000^2 = 1000 \times 1000 = 1\,000\,000$

■ The area of a two-dimensional shape is a measure of the space enclosed within its boundaries.

Square



Area $= l^2$

Rectangle



Area $= l \times w$

Triangle



Area $= \frac{1}{2}\ b \times h$

Parallelogram



Area $= b \times h$

Trapezium



Area $= \frac{1}{2}(a + b)h$

Rhombus



Area $= \frac{1}{2}xy$

Kite



$A = \frac{1}{2}xy$

Circle

$A = \pi r^2$

Sector



$A = \frac{\theta}{360} \times \pi r^2$

Example 5 Converting units of area

Convert the following area measurements into the units given in the brackets.

a 859 mm² (cm²)

b 2.37 m² (cm²)

SOLUTION

a $859\ \text{mm}^2 = 859 \div 10^2\ \text{cm}^2$
$= 8.59\ \text{cm}^2$

b $2.37\ \text{m}^2 = 2.37 \times 100^2\ \text{cm}^2$
$= 23\,700\ \text{cm}^2$

EXPLANATION

cm² ← mm² ÷10² = 100 : 859.

m² → cm² ×100² = 10 000 : 2.3700

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 6 Finding areas of rectangles, triangles and parallelograms

Find the area of each of the following plane figures.

a



b



c



SOLUTION	EXPLANATION
a Area $= l \times w$	Use the area formula for a rectangle.
$= 7 \times 3$	Substitute $l = 7$ and $w = 3$.
$= 21 \text{ m}^2$	Include the correct units.
b Area $= \frac{1}{2} \times b \times h$	Use the area formula for a triangle.
$= \frac{1}{2} \times 11 \times 5$	Substitute $b = 11$ and $h = 5$.
$= 27.5 \text{ km}^2$	Include the correct units.
c Area $= b \times h$	Use the area formula for a parallelogram.
$= 3 \times 1.5$	Multiply the base length by the perpendicular height.
$= 4.5 \text{ cm}^2$	

Example 7 Finding areas of rhombuses and trapeziums

Find the area of each of the following plane figures.

a



b



SOLUTION	EXPLANATION
a Area $= \frac{1}{2} \times x \times y$	Use the area formula for a rhombus.
$= \frac{1}{2} \times 10 \times 9$	Substitute $x = 10$ and $y = 9$.
$= 45 \text{ mm}^2$	Include the correct units.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b Area $= \frac{1}{2}(a+b)h$

$= \frac{1}{2}(4+6)\times 3$

$= 15 \text{ m}^2$

Use the area formula for a trapezium.

Substitute $a = 4$, $b = 6$ and $h = 3$.

$\frac{1}{2}\times(4+6)\times 3 = 5\times 3$

Example 8 Finding areas of circles and sectors

Find the area of this circle and sector correct to two decimal places.

a



b



SOLUTION

EXPLANATION

a $A = \pi r^2$

$= \pi\times(5.1)^2$

$= 81.71 \text{ cm}^2$ (to 2 d.p.)

Write the rule and substitute $r = 5.1$.

81.7128 . . . rounds to 81.71 since the third decimal place is 2.

b $A = \frac{\theta}{360}\times\pi r^2$

$= \frac{260}{360}\times\pi\times 4^2$

$= \frac{13}{18}\times\pi\times 16$

$= 36.30 \text{ m}^2$ (to 2 d.p.)

Use the sector formula.

The fraction of the full circle is $\frac{260}{360} = \frac{13}{18}$,

so multiply this by πr^2 to get the sector area.

Exercise 5C

1–3 | 2 | —

UNDERSTANDING

1 Count the number of squares to find the area of these shapes. Each square in each shape represents one square unit.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5C

UNDERSTANDING

d



e



f



2 Name the shape that has the given area formula.

a $A = lw$ **b** $A = \pi r^2$ **c** $A = \frac{1}{2}xy$ (2 shapes)

d $A = \frac{\theta}{360} \times \pi r^2$ **e** $A = \frac{1}{2}bh$ **f** $A = \frac{1}{2}(a+b)h$

g $A = bh$ **h** $A = l^2$ **i** $A = \frac{1}{2}\pi r^2$

3 What fraction of a full circle is shown by these sectors? Simplify your fraction.

a

b



c



d



e



f



4–9(½) 4–9(½) 4–9(½)

FLUENCY

Example 5

4 Convert the following area measurements into the units given in the brackets.

a 2 cm^2 (mm^2) **b** 500 mm^2 (cm^2) **c** 2.1 m^2 (cm^2)

d 210 000 cm^2 (m^2) **e** 0.001 km^2 (m^2) **f** 3 200 000 m^2 (km^2)

Example 6

5 Find the area of each of the following plane figures.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d



e



f



Example 7

6 Find the area of each of the following plane figures.

a



b



c



d



e



f



7 Find the area of each of the following mixed plane figures.

a



b



c



d



e



f



Example 8a

8 Find the area of these circles using the given value for pi (π). Round to two decimal places.

a $\pi = 3.14$

b $\pi = \frac{22}{7}$

c π (from calculator)



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

5C

Example 8b

FLUENCY

9 Find the area of these sectors rounding to two decimal places.

a



b



c



d



e



f



10–12 | 10, 11, 13, 14 | 10, 13–15

PROBLEM-SOLVING

10 Convert the following measurements into the units given in the brackets.

a 1.5 km^2 (cm^2) **b** 0.000005 m^2 (mm^2) **c** 75 000 mm^2 (m^2)

11 A valuer tells you that your piece of land has an area of one-half a square kilometre (0.5 km^2). How many square metres (m^2) do you own?

12 A rectangular park covers an area of 175 000 m^2. Give the area of the park in km^2.

13 An old picture frame that was once square now leans to one side to form a rhombus. If the distances between pairs of opposite corners are 85 cm and 1.2 m, find the area enclosed within the frame in m^2.

14 A pizza shop is considering increasing the diameter of its family pizza tray from 32 cm to 34 cm. Find the percentage increase in area, correct to two decimal places, from the 32 cm tray to the 34 cm tray.

15 A tennis court area is illuminated by 4 corner lights. The illumination of the sector area close to each light is considered to be good (G) while the remaining area is considered to be lit satisfactorily (S).
What percentage of the area is considered 'good'? Round to the nearest per cent.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5C

16 | 16 | 16, 17

REASONING

16 The rule for the area of a circle is given by $A = \pi r^2$.

a Rearrange this rule to find a rule for r in terms of A.

b Find the radius of a circle with the given areas. Round to one decimal place.

i 5 cm^2 **ii** 6.9 m^2 **iii** 20 km^2

17 A sector has a radius of 3 m.



a Find the angle θ, correct to the nearest degree, if its area is:

i 5 m^2 **ii** 25 m^2

b Explain why the area of the sector could not be 30 m^2.

Windows | — | — | 18, 19

ENRICHMENT

18 Six square windows of side length 2 m are to be placed into a 12 m wide by 8.5 m high wall as shown. The windows are to be positioned so that the vertical spacing between the windows and the wall edges are equal. Similarly, the horizontal spacings are also equal.



a **i** Find the horizontal distance between the windows.

ii Find the vertical distance between the windows.

b Find the area of the wall not including the window spaces.

c If the wall included 3 rows of 4 windows (instead of 2 rows of 3) investigate if it would be possible to space all the windows so that the horizontal and vertical spacings are uniform (although not necessarily equal to each other).

19 A rectangular window is wiped by a wiper blade forming the given sector shape. What percentage area is cleaned by the wiper blade? Round to one decimal place.



Using a CAS calculator 5C: Measurement formulas

This activity is in the interactive textbook in the form of a printable PDF.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5D Composite shapes

Interactive

Widgets

HOTsheets

Walkthroughs

Composite shapes can be thought of as a combination of more simplistic shapes such as triangles and rectangles. Finding perimeters and areas of such shapes is a matter of identifying the more basic shapes they consist of and combining any calculations in an organised fashion.

The area of glass in this window can be calculated using the area of trapeziums, triangles and rectangles.

Let's start: Incorrect layout

Three students write their solution to finding the area of this shape on the board.



Chris	Matt	Moira
$A = l \times w$ $= 50 + \frac{1}{2}\pi r^2$ $= \frac{1}{2}\pi \times 5^2$ $= 39.27 + 50$ $= 89.27 \text{ cm}^2$	$A = \frac{1}{2}\pi \times 5^2$ $= 39.27 + 10 \times 5$ $= 89.27 \text{ cm}^2$	$A = l \times w + \frac{1}{2}\pi r^2$ $= 10 \times 5 + \frac{1}{2}\pi \times 5^2$ $= 89.27 \text{ cm}^2$

- All three students have the correct answer but only one student receives full marks. Who is it?
- Explain what is wrong with the layout of the other two solutions.

Key ideas

- **Composite shapes** are made up of more than one basic shape.
- Addition and/or subtraction can be used to find areas and perimeters of composite shapes.
- The layout of the relevant mathematical working needs to make sense so that the reader of your work understands each step.

Example 9 Finding perimeters and areas of composite shapes

Find the perimeter and area of this composite shape, rounding answers to two decimal places.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
$P = 2 \times l + w + \frac{1}{2} \times 2\pi r$	3 straight sides ⊐ + semicircle arc ◠
$= 2 \times 17 + 14 + \frac{1}{2} \times 2\pi \times 7$	Substitute $l = 17$, $w = 14$ and $r = 7$.
$= 34 + 14 + \pi \times 7$	Simplify.
$= 69.99$ cm (to 2 d.p.)	Calculate and round to two decimal places.
$A = l \times w + \frac{1}{2}\pi r^2$	Area of rectangle ▭ + area of semicircle ◡
$= 17 \times 14 + \frac{1}{2} \times \pi \times 7^2$	Substitute $l = 17$, $w = 14$ and $r = 7$.
$= 238 + \frac{1}{2} \times \pi \times 49$	Simplify.
$= 314.97$ cm^2 (to 2 d.p.)	Calculate and round to two decimal places.

Exercise 5D

1, 2 | 2 | —

UNDERSTANDING

1 Name the two different shapes that make up these composite shapes, e.g. square and semicircle.

a

b



c



2 Copy and complete the working to find the perimeter and area of these composite shapes. Round to one decimal place in part **a**.

a



$P = 2 \times ____ + 3 + \frac{1}{2} \times 2\pi r$

$= ____ + 3 + ____$

$= _____$

$= ____$ m

$A = bh + \frac{1}{2} ____$

$= 5 \times ____ + \frac{1}{2} \times ____$

$= ____ + ____$

$= ____$ m^2

b



$P = 20 + 12 + ____ + ____ + ____$

$= ____$ cm

$A = lw - \frac{1}{2}bh$

$= 12 \times ____ - \frac{1}{2} \times 8 \times ____$

$= ____ - ____$

$= ____$ cm^2

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5D

3–6(½) 3–7(½) 3–7(½)

FLUENCY

Example 9

3 Find the perimeter and the area of each of these simple composite shapes, rounding answers to two decimal places where necessary.

a



b



c



d



e



f



4 Find the area of each of the following composite shapes.

a



b



c



d



e



f



5 Find the area of each of these composite shapes. *Hint*: use subtraction.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

6 Find the perimeter and the area of each of the following composite shapes, correct to two decimal places where necessary.

a



b



c



d



e



f



7 Find the area of the shaded region of each of the following shapes by subtracting the area of the clear shape from the total area. Round to one decimal place where necessary.

a



b



c



d



e



f



g



h



i



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5D

8, 9 | 9, 10 | 10, 11

PROBLEM-SOLVING

8 An area of lawn is made up of a rectangle measuring 10 m by 15 m and a semicircle of radius 5 m. Find the total area of lawn, correct to two decimal places.

9 Twenty circular pieces of pastry, each of diameter 4 cm, are cut from a rectangular layer of pastry 20 cm long and 16 cm wide. What is the area, correct to two decimal places, of pastry remaining after the twenty pieces are removed?

10 These shapes include sectors. Find their area, correct to one decimal place.

a



b



c



11 A new car manufacturer is designing a logo. It is in the shape of a diamond inside a rectangle. The diamond is to have a horizontal width of 3 cm and an area equal to one-sixth of the area of the rectangle. Find the required height of the diamond.



12 | 12, 13 | 12(½), 13, 14

REASONING

12 Using exact values (e.g. $10 + 4\pi$), find the area of the shapes given in Question **6**.

13 A circle of radius 10 cm has a hole cut out of its centre to form a ring. Find the radius of the hole if the remaining area is 50% of the original area. Round to one decimal place.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5D

REASONING

14 Use Pythagoras' theorem (illustrated in this diagram) to help explain why these composite shapes include incorrect information.



a



b



c



ENRICHMENT

Construction cut-outs — — 15, 16

15 The front of a grandfather clock consists of a timber board with dimensions as shown. A circle of radius 20 cm is cut from the board to form the clock face. Find the remaining area of the timber board correct to one decimal place.



16 The number 10 is cut from a rectangular piece of paper. The dimensions of the design are shown below.



a Find the length and width of the rectangular piece of paper shown.

b Find the sum of the areas of the two cut-out digits, 1 and 0, correct to one decimal place.

c Find the area of paper remaining after the digits have been removed (include the centre of the '0' in your answer) and round to one decimal place.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5E Surface area of prisms and pyramids

Interactive

Widgets

HOTsheets

Walkthroughs

Three-dimensional objects or solids have outside surfaces which together form the total surface area. Nets are very helpful for determining the number and shape of the surfaces of a three-dimensional object.

For this section we will deal with right prisms and pyramids. A right prism has a uniform cross-section with two identical ends and the remaining sides are rectangles. A right pyramid has its apex sitting above the centre of its base.



Right triangular prism



Right square-based pyramid

Let's start: Drawing prisms and pyramids

Prisms are named by the shape of their cross-section and pyramids by the shape of their base.

- Try to draw as many different right prisms and pyramids as you can.
- Describe the different kinds of shapes that make up the surface of your solids.
- Which solids are the most difficult to draw and why?

Key ideas

- The **total surface area** (TSA) of a solid is the sum of the areas of all the surfaces.
- A **net** is a two-dimensional illustration of all the surfaces of a solid.
- A right **prism** is a solid with a uniform cross-section and remaining sides are rectangles.
  - They are named by the shape of their cross-section.
- The nets for a **rectangular prism** (**cuboid**) and square-based **pyramid** are shown here.

Solid	Net	TSA
Rectangular prism 		$TSA = 2(lw) + 2(lh) + 2(hw)$
Square-based pyramid 		$TSA = b^2 + 4\left(\frac{1}{2}bh\right)$ $= b^2 + 2bh$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 10 Finding a total surface area

Find the total surface area of this right rectangular prism and this right square-based pyramid.

a



b



SOLUTION

EXPLANATION

a $\text{TSA} = 2\times(5\times3) + 2\times(5\times2) + 2\times(2\times3)$

$= 30 + 20 + 12$

$= 62 \text{ cm}^2$



b $\text{TSA} = 2\times2 + 4\times\frac{1}{2}\times2\times3$

$= 4 + 12$

$= 16 \text{ m}^2$

Square base + 4 identical triangles



Exercise 5E

1(½), 2 | 2 | —

UNDERSTANDING

1 Draw a suitable net for these prisms and pyramids and name each solid.

a



b



c



d



e



f



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

5E

UNDERSTANDING

2 Copy and complete the working to find the surface area of these solids.

a



TSA = $2 \times 8 \times 7 + 2 \times 8 \times$ ___

$+ 2 \times$ ___ $\times$ ___

= ___ + ___ + ___

= ___ m^2

b



TSA = $2 \times \frac{1}{2} \times 4 \times$ ___ $+ 5 \times 7$

$+ 4 \times$ ___ + ___ $\times$ ___

= ___ + ___ + ___ + ___

= ___ cm^2

3–5(½) | 3–5(½), 6 | 3–5(½), 6

FLUENCY

Example 10a

3 Find the surface area of the following right rectangular prisms. Draw a net of the solid to help you.

a



b



c



d



e



f



Example 10b

4 Find the surface area of each of these right square-based pyramids. Draw a net to help you.

a



b



c



5 Find the surface area of each of the following solid objects.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5E

FLUENCY

c



d



e



f



6 Find the total surface area of a cube of side length 1 metre.

7, 8 | 8, 9 | 9, 10

PROBLEM-SOLVING

7 A rectangular box is to be covered in material. How much is required to cover the entire box if it has the dimensions 1.3 m, 1.5 m and 1.9 m?

8 Two wooden boxes, both with dimensions 80 cm, 1 m and 25 cm, are placed on the ground, one on top of the other as shown. The entire outside surface is then painted. Find the area of the painted surface.



9 The outside four walls and roof of a barn (shown) are to be painted.

a Find the surface area of the barn, not including the floor.

b If 1 litre of paint covers 10 m^2, find how many litres are required to complete the job.



10 An open top rectangular box 20 cm wide, 25 cm long and 10 cm high is made from wood 1 cm thick. Find the surface area:

a outside the box (do not include the top edge)

b inside the box (do not include the top edge).



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5E

11 | 11 | 11, 12

REASONING

11 Draw the stack of 1 cm cube blocks that gives the minimum outside surface area and state this surface area if there are:

a 2 blocks **b** 4 blocks **c** 8 blocks

12 Cubes of side length one unit are stacked as shown.



1 cube 2 cubes 3 cubes etc.

a Complete this table.

Number of cubes (n)	1	2	3	4	5	6	7	8	9
Surface area (S)									

b Can you find the rule for the surface area (S) for n cubes stacked in this way? Write down the rule for S in terms of n.

c Investigate other ways of stacking cubes and look for rules for surface area in terms of n, the number of cubes.

Pythagoras required

— | — | 13

ENRICHMENT

13 For prisms and pyramids involving triangles, Pythagoras' theorem ($c^2 = a^2 + b^2$) can be used. Apply the theorem to help find the surface area of these solids. Round to one decimal place.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5F Surface area of a cylinder

Interactive

Widgets

HOTsheets

Walkthroughs

The net of a cylinder includes two circles and one rectangle. The length of the rectangle is equal to the circumference of the circle.

These pipes are hollow cylinders, like the rolled-up paper sheets.



Let's start: Curved area

- Roll a piece of paper to form the curved surface of a cylinder.
- Do not stick the ends together so you can allow the paper to return to a flat surface.
- What shape is the paper when lying flat on a table?
- When curved to form the cylinder, what do the sides of the rectangle represent on the cylinder? How does this help to find the surface area of a cylinder?

Key ideas

- Surface area of a **cylinder** = 2 circles + 1 rectangle

$$= 2 \times \pi r^2 + 2\pi r \times h$$

$$\therefore \text{TSA} = 2\pi r^2 + 2\pi rh$$

2 circular ends; curved area



- $\text{TSA} = 2\pi r^2 + 2\pi rh = 2\pi r(r + h)$

- In problem-solving questions, you will need to decide which parts of the surface of the cylinder should be included.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 11 Finding the surface area of a cylinder

Find the surface area of this cylinder, rounding to two decimal places.



SOLUTION

$$\begin{aligned}\text{TSA} &= 2\pi r^2 + 2\pi rh \\ &= 2\times\pi\times 5^2 + 2\pi\times 5\times 25 \\ &= 50\times\pi + 250\times\pi \\ &= 50\pi + 250\pi \\ &= 300\pi \\ &= 942.48 \text{ m}^2 \text{ (to 2 d.p.)}\end{aligned}$$

EXPLANATION



Example 12 Finding surface areas of cylindrical portions

Find the total surface area of this half-cylinder, rounding to two decimal places.



SOLUTION

$$\begin{aligned}\text{TSA} &= 2\left(\frac{1}{2}\pi r^2\right) + \frac{1}{2}(2\pi r)\times 8 + 4\times 8 \\ &= 2\times\frac{1}{2}\pi\times 2^2 + \frac{1}{2}\times 2\times\pi\times 2\times 8 + 32 \\ &= 20\pi + 32 \\ &= 94.83 \text{ cm}^2 \text{ (to 2 d.p.)}\end{aligned}$$

EXPLANATION

As well as half the cylinder formula, include the rectangular base.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 5F

1, 2 | 2 | —

UNDERSTANDING

1 Draw a net suited to these cylinders. Label the sides using the given measurements. C represents the circumference.

a



b



2 The curved surface of these cylinders is allowed to flatten out to form a rectangle. What would be the length and width of this rectangle? Round to two decimal places where necessary.

a



b



c



3–5 | 3–6 | 3, 4(½), 5, 6(½)

FLUENCY

Example 11

3 Find the surface area of these cylinders, rounding to two decimal places. Use a net to help.

a



b



c



4 Find the surface area of these cylinders, rounding to one decimal place. Remember that the radius of a circle is half the diameter.

a



b



c



5 Find the surface area of a cylindrical plastic container of height 18 cm and with a circle of radius 3 cm at each end, correct to two decimal places.

6 Find the area of the curved surface only for these cylinders, correct to two decimal places.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5F

7, 8 | 7(½), 8, 9 | 7(½), 9, 10

PROBLEM-SOLVING

Example 12

7 Find the total surface area of these solids, rounding to two decimal places.

a



b



c



d



e



f



g



h



i



8 A water trough is in the shape of a half-cylinder. Its semicircular ends have diameter 40 cm and the trough length is 1 m. Find the outside surface area in cm^2 of the curved surface plus the two semicircular ends, correct to two decimal places.

9 A log with diameter 60 cm is 3 m in length. Its hollow centre is 20 cm in diameter.
Find the surface area of the log in cm^2, including the ends and the inside, correct to one decimal place.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

5F

PROBLEM-SOLVING

10 A cylindrical roller is used to press crushed rock in preparation for a tennis court. The rectangular tennis court area is 30 m long and 15 m wide. The roller has a width of 1 m and diameter 60 cm.

a Find the surface area of the curved part of the roller in cm^2 correct to three decimal places.



b Find the area, in m^2 to two decimal places, of crushed rock that can be pressed after:

i 1 revolution **ii** 20 revolutions.

c Find the minimum number of complete revolutions required to press the entire tennis court area.

11	11, 12	11, 12

REASONING

11 It is more precise to give exact values for calculations involving π, e.g. 24π. Give the exact answers to the surface area of the cylinders in Question **3**.

12 A cylinder cut in half gives half the volume but not half the surface area. Explain why.

Solid sectors	—	—	13

ENRICHMENT

13 The sector area rule $A = \frac{\theta}{360} \times \pi r^2$ can be applied to find the surface areas of solids which have ends that are sectors. Find the exact total surface area of these solids.

a



b



c



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

5A/B **1** Find the perimeter of each of the following shapes. Round to one decimal place in part **b**.

a



b



5B/C **2** Find, correct to one decimal place, the circumference and area of:

a



b



5C **3** Find the exact area of the following.

a



b



c



5C **4** Convert 85 000 mm^2 into cm^2.

5D **5** Find the perimeter and area of these composite shapes, rounding answers to two decimal places in part **a**. *Hint*: use Pythagoras' theorem in part **b**.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5D **6** Find, correct to two decimal places, the area of the shaded region.



5E **7** Find the total surface area of each of the following solids. Round to one decimal place in part **b**.

a



b



c



5F **8** Find the surface area of this cylinder and half cylinder, rounding to two decimal places.

a



b



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5G Volume of prisms

Interactive

Widgets

HOTsheets

Walkthroughs

Volume is the number of cubic units contained within a three-dimensional object.

To find the volume for this solid we can count 24 cubic centimetres (24 cm^3) *or* multiply $3 \times 4 \times 2 = 24$ cm^3.



We can see that the area of the base ($3 \times 4 = 12$ cm^2) also gives the volume of the base layer 1 cm high. The number of layers equals the height, hence, multiplying the area of the base by the height will give the volume.

This idea can be applied to all right prisms provided a uniform cross-section can be identified. In such solids, the height length used to calculate the volume is the length of the edge running perpendicular to the base or cross-section.

Let's start: Cubic units

Consider this 1 cm cube divided into cubic millimetres.



- How many cubic mm sit on one edge of the 1 cm cube?
- How many cubic mm sit on one layer of the 1 cm cube?
- How many cubic mm are there in total in the 1 cm cube?
- Complete this statement 1 cm^3 = _____ mm^3
- Explain how you can find how many:
  a cm^3 in 1 m^3 **b** m^3 in 1 km^3

Key ideas

- Common metric units for **volume** include **cubic kilometres** (km^3), **cubic metres** (m^3), **cubic centimetres** (cm^3) and **cubic millimetres** (mm^3).

$km^3 \xrightarrow{\times 1000^3} m^3 \xrightarrow{\times 100^3} cm^3 \xrightarrow{\times 10^3} mm^3$

$km^3 \xleftarrow{\div 1000^3} m^3 \xleftarrow{\div 100^3} cm^3 \xleftarrow{\div 10^3} mm^3$

$1000^3 = 1\,000\,000\,000$
$100^3 = 1\,000\,000$
$10^3 = 1000$

- For **capacity** common units include:
  - **megalitres** (ML) 1 ML = 1000 kL
  - **kilolitres** (kL) 1 kL = 1000 L
  - **litres** (L) 1 L = 1000 mL
  - **millilitres** (mL)

Also 1 cm^3 = 1 mL so 1 L = 1000 cm^3 and 1 m^3 = 1000 L

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Volume of solids with a uniform **cross-section** is equal to area of cross-section (A) × height (h).
  $V = A \times h$



- The 'height' is the length of the edge that runs perpendicular to the cross-section.

Some common formulas for volume include:

Rectangular prism (cuboid)	Triangular prism
 $V = A \times h$ $= l \times w \times h$ $= lwh$	 $V = A \times h$ $= (\frac{1}{2} \times b \times h_1) \times h_2$ $= (\frac{1}{2} b h_1) \times h_2$

Example 13 Converting units of volume

Convert the following volume measurements into the units given in the brackets.

a 2.5 m^3 (cm^3) **b** 458 mm^3 (cm^3)

SOLUTION

a $2.5\ m^3 = 2.5 \times 100^3\ cm^3$
$= 2\,500\,000\ cm^3$

b $458\ mm^3 = 458 \div 10^3\ cm^3$
$= 0.458\ cm^3$

EXPLANATION

$\times 100^3 = 1\,000\,000$ 2.500000
m^3 cm^3

cm^3 mm^3
$\div 10^3 = 1000$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 14 Finding volumes of prisms and other solids

Find the volume of each of these three-dimensional objects.

a 

b 

c 

SOLUTION

a Volume $= l \times w \times h$
$= 1 \times 1 \times 3$
$= 3 \text{ cm}^3$

b Volume = area of cross-section × height
$= 10 \times 5$
$= 50 \text{ cm}^3$

c Volume = area of cross-section × height
$= \left(\frac{1}{2} \times b \times h_1\right) \times h_2$
$= \left(\frac{1}{2} \times 4 \times 3\right) \times 6$
$= 36 \text{ cm}^3$

EXPLANATION

The solid is a rectangular prism.

Length = 1 cm, width = 1 cm and height = 3 cm

Substitute cross-sectional area = 10 and height = 5.

The cross-section is a triangle.



Exercise 5G

1, 2 | 2 | —

UNDERSTANDING

1 Draw the cross-sectional shape for these prisms and state the 'height' (perpendicular to the cross-section).

a 

b 

c 

d 

e 

f 

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5G

UNDERSTANDING

2 What is the name given to the shape of the shaded cross-section of each of the following solids?

a



b



c



d



e



f



3(½), 4, 5(½), 6, 7 | 3(½), 4, 5(½), 6–8 | 3(½), 5(½), 6–8

FLUENCY

Example 13

3 Convert the following volume measurements into the units given in the brackets.

a 3 cm^3 (mm^3)
b 2000 mm^3 (cm^3)
c 8.7 m^3 (cm^3)
d 5900 cm^3 (m^3)
e 0.00001 km^3(m^3)
f 21 700 m^3 (km^3)
g 3 L (mL)
h 0.2 kL (L)
i 3500 mL (L)
j 0.021 L (mL)
k 37 000 L (kL)
l 42 900 kL (ML)

Example 14a

4 Find the volume of these three-dimensional rectangular prisms.

a



b



c



Example 14b

5 Find the volume of each of these three-dimensional objects. The cross-sectional area has been given.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5G

d



e



f



g



h



i



Example 14c

6 Find the volume of these prisms.

a



b



c



7 Find the volume of each of these rectangular prisms (cuboids).

a



b



c



8 Find the volume of these solids converting your answer to litres. Recall 1 cm^3 = 1 mL.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9, 10 | 10–12 | 11–14

5G

PROBLEM-SOLVING

9 A brick is 10 cm wide, 20 cm long and 8 cm high. How much space would five of these bricks occupy?

10 How much air space is contained inside a rectangular cardboard box that has the dimensions 85 cm by 62 cm by 36 cm. Answer using cubic metres (m^3), correct to two decimal places.

11 25 L of water is poured into a rectangular fish tank which is 50 cm long, 20 cm wide and 20 cm high. Will it overflow?

12 Find the volume of each of the following solids, rounding to one decimal place where necessary.

a



b



c



d



e



f



13 Use units for capacity to find the volume of these solids in litres.

a



b



c



14 The given diagram is a sketch of a new 25 m swimming pool to be installed in a school sports complex.

a Find the area of one side of the pool (shaded).

b Find the volume of the pool in litres.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5G

15 | 15 | 15, 16

REASONING

15 **a** What single number do you multiply by to convert from:

- **i** L to cm^3?
- **ii** L to m^3?
- **iii** mL to mm^3?

b What single number do you divide by to convert from:

- **i** mm^3 to L?
- **ii** m^3 to ML?
- **iii** cm^3 to kL?

16 Write rules for the volume of these solids using the given pronumerals.

a A rectangular prism with length = width = x and height h.

b A cube with side length s.

c A rectangular prism with a square base (with side length t) and height 6 times the side length of the base.

Volume of a pyramid

— | — | 17

ENRICHMENT

17 Earlier we looked at finding the total surface area of a right pyramid like the one shown here.



Imagine the pyramid sitting inside a prism with the same base.

a Make an educated guess as to what fraction of the prism's volume is the pyramid's volume.

b Use the internet to find the actual answer to part **a**.

c Draw some pyramids and find their volume using the results from part **b**.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5H Volume of a cylinder

Technically, a cylinder is not a right prism because its sides are not rectangles. It does, however, have a uniform cross-section (a circle) and so a cylinder's volume can be calculated in a similar way to that of a right prism. Cylindrical objects are commonly used to store gases and liquids and so working out the volume of a cylinder is an important measurement calculation.

The volume of liquid in this tanker can be calculated using the volume formula for a cylinder.

Let's start: Writing the rule

Previously we used the formula $V = A \times h$ to find the volume of solids with a uniform cross-section.

- Discuss any similarities between the two given solids.
- How can the rule $V = A \times h$ be developed further to find the rule for the volume of a cylinder?



Key ideas

- The volume of a cylinder is given by
  $V = \pi r^2 \times h$ or $V = \pi r^2 h$
  - r is the radius of the circular ends
  - h is the length or distance between the circular ends



Example 15 Finding the volume of a cylinder

Find the volume of these cylinders correct to two decimal places.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $V = \pi r^2 h$	
$= \pi \times (3)^2 \times 10$	Substitute $r = 3$ and $h = 10$ into the rule.
$= 90\pi$	90π cm^3 would be the exact answer.
$= 282.74$ cm^3 (to 2 d.p.)	Include volume units.
b $V = \pi r^2 h$	The diameter is 1.8 m so $r = 0.9$.
$= \pi \times (0.9)^2 \times 0.3$	
$= 0.76$ m^3 (to 2 d.p.)	

Example 16 Finding the capacity of a cylinder

Find the capacity in litres of a cylinder with radius 30 cm and height 90 cm. Round to the nearest litre.

SOLUTION	EXPLANATION
$V = \pi r^2 h$	Substitute $r = 30$ and $h = 90$.
$= \pi \times (30)^2 \times 90$	There are 1000 cm^3 in 1 L so divide by 1000 to convert to litres. 254.469 to nearest litre is 254 L.
$= 254\,469$ cm^3	
$= 254$ L (to the nearest litre)	

Exercise 5H

1(½), 2, 3 | 3 | —

UNDERSTANDING

1 State the radius and the height of these cylinders.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5H

UNDERSTANDING

2 Find the area of these circles correct to two decimal places.

a



b



c



d



3 Convert the following into the units given in the brackets. Remember, 1 L = 1000 cm^3 and 1 m^3 = 1000 L.

a 2000 cm^3 (L)
b 4.3 cm^3 (mL)
c 3.7 L (cm^3)
d 1 m^3 (L)
e 38 000 L (m^3)
f 0.0002 m^3 (mL)

4–5(½) 4–5(½) 4–5(½)

FLUENCY

Example 15

4 Find the volume of these cylinders correct to two decimal places.

a



b



c



d



e



f



Example 16

5 Find the capacity in litres of these cylinders. Round to the nearest litre.
Remember 1 L = 1000 cm^3 and 1 m^3 = 1000 L.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5H

6, 7 | 7–9 | 8, 9

PROBLEM-SOLVING

6 A cylindrical water tank has a radius of 2 m and a height of 2 m.

a Find its capacity in m^3 rounded to three decimal places.

b Find its capacity in L rounded to the nearest litre.

7 How many litres of gas can a tanker carry if its tank is cylindrical with a 2 m diameter and is 12 m in length? Round to the nearest litre.

8 Of the following, which has a bigger volume and what is the difference in volume to two decimal places? A cube with side length 1 m or a cylinder with radius 1 m and height 0.5 m.

9 Find the volume of these cylindrical portions correct to two decimal places.

a



b



c



d



e



f



10 | 10, 11(½) | 10, 11(½), 12

REASONING

10 The rule for the volume of a cylinder is $V = \pi r^2 h$. Show how you could use this rule to find, correct to three decimal places:

a h if $V = 20$ and $r = 3$

b r if $V = 100$ and $h = 5$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5H

REASONING

11 Using exact values (e.g. 20π) find the volume of these solids.

a



b



c



d



e



f



12 Draw a cylinder with its circumference equal to its height. Try to draw it to scale.

Solid sectors — — 13

ENRICHMENT

13 You will recall that the area of a sector is given by $A = \frac{\theta}{360} \times \pi r^2$.

Use this fact to help find the volume of these solids, correct to two decimal places.



a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Capacity and depth

Finding capacity

Find the capacity in litres of these containers (i.e. find the total volume of fluid they can hold).

a



b



Remember: 1 millilitre (mL) of fluid occupies 1 cm^3 of space therefore 1 litre (L) occupies 1000 cm^3 as there are 1000 mL in 1 litre.

Designing containers

Design a container with the given shape which has a 10 litre capacity. You will need to state the dimensions – length, width, height, radius, etc. – and calculate its capacity.

a rectangular prism

b cylinder

Finding depth

The depth of water in a prism can be found if the base (cross-sectional) area and volume of water are given.

Consider a cuboid, as shown, with 2.4 litres of water.



To find the depth of water:

- Convert the volume to cm^3: $2.4\text{ L} = 2.4 \times 1000$
  $= 2400\text{ cm}^3$
- Find the depth: Volume = area of base $\times d$
  $2400 = 20 \times 20 \times d$
  $2400 = 400 \times d$
  $\therefore d = 6$
  $\therefore$ depth is 6 cm

Use the above method to find the depth of water in these prisms.

a



Volume = 96 L

b



Volume = 8 L

c



Volume = 500 L

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Volumes of odd-shaped objects

Some solids may be peculiar in shape and their volume may be difficult to measure.

a A rare piece of rock is placed into a cylindrical jug of water and the water depth rises from 10 cm to 11 cm. The radius of the jug is 5 cm.

- **i** Find the area of the circular base of the cylinder.
- **ii** Find the volume of water in the jug before the rock is placed in the jug.
- **iii** Find the volume of water in the jug including the rock.
- **iv** Hence find the volume of the rock.

b Use the procedure outlined in part **a i–iv** above to find the volume of an object of your choice. Explain and show your working and compare your results with other students in your class if they are measuring the volume of the same object.



Measuring cylinders are used in laboratories to measure the volume of liquids. They can also measure the volume of irregular solids by the rise in the liquid level when the solid is dropped into it.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 A 100 m^2 factory flat roof feeds all the water collected to a rainwater tank. If there is 1 mm of rainfall, how many litres of water go into the tank?

2 What is the relationship between the shaded and non-shaded regions in this circular diagram?



3 A goat is tethered to the centre of one side of a shed with a 10 m length of rope. What area of grass can the goat graze?



4 A rain gauge is in the shape of a triangular prism with dimensions as shown. What is the depth of water when it is half full?



5 A rectangular fish tank has base area 0.3 m^2 and height 30 cm and is filled with 80 L of water. Ten large fish, each with volume 50 cm^3, are placed into the tank. By how much does the water rise?

6 If it takes 4 people 8 days to knit 2 rugs, how many days will it take for 1 person to knit 1 rug?

7 Find the rule for the volume of a cylinder in terms of r only if the height is equal to its circumference.

8 The surface area of a cylinder is 2π square units. Find a rule for h in terms of r.

9 Give the dimensions of a cylinder that can hold one litre of milk. What considerations are needed when designing containers for use by consumers?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Measurement

Length and perimeter

Units

$\times 1000^3$ $\times 100^3$ $\times 10^3$

km^3 m^3 cm^3 mm^3

$\div 1000^3$ $\div 100^3$ $\div 10^3$

$1\text{L} = 1000\text{ mL} = 1000\text{ cm}^3$

Circle circumference

$C = 2\pi r$ or πd

Units

$\times 1000$ $\times 100$ $\times 10$

km m cm mm

$\div 1000$ $\div 100$ $\div 10$

Sector

$P = 2r + \frac{\theta}{360} \times 2\pi r$

$= 2 \times 3 + \frac{90}{360} \times 2\pi \times 3$

$= 6 + 1.5\pi$ (exact)

$= 10.71$ cm (to 2 d.p.)



Volume

Prism or cylinders

$V = Ah$

A = area of cross-section

h = height

$V = lwh$

$= 11 \times 6 \times 5$

$= 330\text{ m}^3$



$V = \pi r^2 h$

$= \pi(2)^2 7$

$= 28\pi$

$= 87.96\text{ cm}^3$

Area

Triangle

$A = \frac{1}{2}bh$

Quadrilaterals

Square $A = l^2$

Rectangle $A = lw$

Parallelogram $A = bh$

Trapezium $A = \frac{1}{2}(a + b)h$

Rhombus or kite $A = \frac{1}{2}xy$ 

Units

$\times 1000^2$ $\times 100^2$ $\times 10^2$

km^2 m^2 cm^2 mm^2

$\div 1000^2$ $\div 100^2$ $\div 10^2$

Composite shapes



$A = lw - \frac{1}{2}\pi r^2$

$= 10 \times 8 - \frac{1}{2}\pi \times 4^2$

$= 80 - 8\pi$

$= 54.87\text{ m}^2$

$P = 2 \times 10 + 8 + \frac{1}{2}2\pi(4)$

$= 28 + 4\pi$

$= 40.57$ m

Surface area

Prism or pyramid

Use a net to help find the sum of all surface areas.



$\text{TSA} = b^2 + 4\left(\frac{1}{2}bh\right)$

$= 3^2 + 4 \times \frac{1}{2} \times 3 \times 5$

$= 39\text{ m}^2$

Cylinder

$\text{TSA} = 2\pi r^2 + 2\pi rh$

$= 2\pi(3)^2 + 2\pi(3)(4)$

$= 18\pi + 24\pi$

$= 42\pi$

$= 131.95\text{ cm}^2$

Circle

$A = \pi r^2$

sector $A = \frac{\theta}{360} \times \pi r^2$

$= \frac{120}{360} \times \pi \times 5^2$

$= \frac{1}{3} \times \pi \times 25$

$= 26.18\text{ m}^2$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

5A/C **1** If the area of a square field is 25 km^2, its perimeter is:
A 10 km **B** 20 km **C** 5 km **D** 50 km **E** 25 km

5C **2** 2.7 m^2 is the same as:
A 270 cm^2 **B** 0.0027 km^2 **C** 27 000 cm^2 **D** 2700 mm^2 **E** 27 cm^2

5A **3** The perimeter of this shape is:
A 21 cm **B** 14 cm **C** 24 cm
D 20 cm **E** 22 cm



5C **4** A parallelogram has area 10 m^2 and base 5 m. Its perpendicular height is:
A 50 m **B** 2 m **C** 50 m^2 **D** 2 m^2 **E** 0.5 m

5D **5** This composite shape could be considered as a rectangle with an area in the shape of a trapezium removed. The shape's area is:
A 16 km^2 **B** 12 km^2 **C** 20 km^2
D 24 km^2 **E** 6 km^2



5B **6** A semicircular goal area has diameter 20 m. Its perimeter correct to the nearest metre is:
A 41 m **B** 36 m **C** 83 m **D** 51 m **E** 52 m

5E **7** The surface area of the pyramid shown is:
A 185 cm^2 **B** 105 cm^2 **C** 65 cm^2 **D** 100 cm^2 **E** 125 cm^2



5F **8** The area of the curved surface only of a half-cylinder with radius 5 mm and height 12 mm is closest to:
A 942.5 mm^2 **B** 94.2 mm^2 **C** 377 mm^2 **D** 471.2 mm^2 **E** 188.5 mm^2



5G **9** A prism's cross-sectional area is 100 m^2. If its volume is 6500 m^3, the prism's total height would be:
A 0.65 m **B** 650 000 m **C** 65 m **D** 6.5 m **E** 650 m

5H **10** The exact volume of a cylinder with radius 3 cm and height 10 cm is:
A 60π cm^2 **B** 80π cm **C** 45π cm^3 **D** 30π cm^3 **E** 90π cm^3

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

5A/C/G **1** Convert the following measurements into the units given in brackets.

a 3.8 m (cm) **b** 1.27 km (m) **c** 273 mm^2 (cm^2)
d 5.2 m^2 (cm^2) **e** 0.01 m^3 (cm^3) **f** 53 100 mm^3 (cm^3)
g 3100 mL (L) **h** 0.043 L (mL) **i** 2.83 kL (L)

5A **2** Find the perimeter of each of the following shapes.

a



b



c



5C **3** Find the area of each of the following plane figures.

a



b



c



d



e



f



5D **4** Inside a rectangular lawn area of length 10.5 m and width 3.8 m, a new garden bed is to be constructed. The garden bed is to be the shape of a triangle with base 2 m and height 2.5 m. With the aid of a diagram, find:

a the area of the garden bed
b the area of the lawn remaining around the garden bed.

5B/C **5** Find the area and circumference/perimeter of each of the following shapes correct to two decimal places.

a



b



5D **6** Find the perimeter and area of these sectors. Round to two decimal places.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

5D

7 Find the perimeter and area of each of the following composite shapes, correct to two decimal places.

a



b



5E

8 Find the total surface area of each of the following solid objects.

a



b



5F

9 Find the total surface area of each of the following solid objects, correct to two decimal places.

a



b



half-cylinder

5G/H

10 Find the volume of each of these solid objects, rounding to two decimal places where necessary.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 An office receives five new desks with a bench shape made up of a rectangle and quarter-circle as shown.
The edge of the bench is lined with a rubber strip at a cost of $2.50 per metre.



a Find the length of the rubber edging strip in centimetres for one desk correct to two decimal places.

b By converting your answer in part **a** to metres, find the total cost of the rubber strip for the five desks. Round to the nearest dollar.

The manufacturer claims that the desk top area space is more than 1.5 m^2.

c Find the area of the desk top in cm^2 correct to two decimal places.

d Convert your answer to m^2 and determine whether or not the manufacturer's claim is correct.

2 Circular steel railing of diameter 6 cm is to be used to fence the side of a bridge. The railing is hollow and the radius of the hollow circular space is 2 cm.



a By adding the given information to this diagram of the cross-section of the railing, determine the thickness of the steel.

b Determine, correct to two decimal places, the area of steel in the cross-section.

Eight lengths of railing at 10 m each are required for the bridge.

c Using your result from part **b**, find the volume of steel required for the bridge in cm^3.

d Convert your answer in part **c** to m^3.

The curved outside surface of the steel railings is to be painted to help protect the steel from the weather.

e Find the outer circumference of the cross-section of the railing correct to two decimal places.

f Find the total surface area in m^2 of the eight lengths of railing that are to be painted. Round to the nearest m^2.

The cost of the railing paint is $80 per m^2.

g Using your answer from part **f**, find the cost of painting the bridge rails to the nearest dollar.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Semester review 1

Reviewing number and financial mathematics

Multiple-choice questions

1 $-3 + (4 + (-10)) \times (-2)$ is equal to:

A 21 **B** 9 **C** 18 **D** –15 **E** –6

2 The estimate of $221.7 \div 43.4 - 0.0492$ using one significant figure rounding is:

A 4.9 **B** 5.06 **C** 5.5 **D** 5 **E** 4.95

3 \$450 is divided in the ratio 4 : 5. The value of the smaller portion is:

A \$210 **B** \$250 **C** \$90 **D** \$200 **E** \$220

4 A book that costs \$27 is discounted by 15%. The new price is:

A \$20.25 **B** \$31.05 **C** \$4.05 **D** \$22.95 **E** \$25.20

5 Anna is paid a normal rate of \$12.10 per hour. If in a week she works 6 hours at the normal rate, 2 hours at time and a half and 3 hours at double time, how much does she earn?

A \$181.50 **B** \$145.20 **C** \$193.60 **D** \$175.45 **E** \$163.35

Short-answer questions

1 Evaluate the following.

a $\frac{3}{7} + \frac{1}{4}$ **b** $2\frac{1}{3} - 1\frac{5}{9}$ **c** $\frac{9}{10} \times \frac{5}{12}$ **d** $3\frac{3}{4} \div 2\frac{1}{12}$

2 Convert each of the following to a percentage.

a 0.6 **b** $\frac{5}{16}$ **c** 2 kg out of 20 kg **d** 75c out of \$3

3 Write these rates and ratios in simplest form.

a Prize money is shared between two people in the ratio 60 : 36.

b Jodie travels 165 km in three hours.

c 3 mL of rain falls in $1\frac{1}{4}$ hours.

4 Jeff earns a weekly retainer of \$400 plus 6% of the sales he makes. If he sells \$8200 worth of goods, how much will he earn for the week?

Extended-response question

Husband and wife Jim and Jill are trialling new banking arrangements.

a Jill plans to trial a simple interest plan. Before investing her money she increases the amount in her account by 20% to \$21 000.

i What was the original amount in her account?

ii She invests the \$21 000 for 4 years at an interest rate of 3% p.a. How much does she have in her account at the end of the four years?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

iii She continues with this same plan and after a certain number of years has obtained $5670 interest. For how many years has she had the money invested?

iv What percentage increase does this interest represent on her initial investment?

b Jim is investing his $21 000 in an account that compounds annually at 3% p.a. How much does he have after 4 years to the nearest cent?

c i Who had the most money after 4 years and by how much? Round to the nearest dollar.

ii Who will have the most money after 10 years and by how much? Round to the nearest dollar.

Linear and simultaneous equations

Multiple-choice questions

1 The simplified form of $5ab + 6a \div 2 + a \times 2b - a$ is:

A $10ab$ **B** $10ab + 3a$ **C** $13ab - a$ **D** $5ab + 3a + 2b$ **E** $7ab + 2a$

2 The expanded form of $-2(3m - 4)$ is:

A $-6m + 8$ **B** $-6m + 4$ **C** $-6m - 8$ **D** $-5m - 6$ **E** $5m + 8$

3 The solution to $\frac{d}{4} - 7 = 2$ is:

A $d = -20$ **B** $d = 15$ **C** $d = 36$ **D** $d = 1$ **E** $d = 30$

4 The solution to $1 - 3x < 10$ represented on a number line is:

A


B


C


D


E


5 The formula $m = \sqrt{\frac{b-1}{a}}$ with b as the subject is:

A $b = a\sqrt{m} + 1$ **B** $b = \frac{m^2}{a} + 1$ **C** $b = a^2m^2 + 1$

D $b = am^2 + 1$ **E** $b = m^2\sqrt{a} + 1$

Short-answer questions

1 Solve the following equations and inequalities.

a $3x + 7 = 25$ **b** $\frac{2x-1}{4} > 2$

c $4(2m + 3) = 15$ **d** $-3(2y + 4) - 2y = -4$

e $3(a + 1) \leq 4 - 8a$ **f** $3(2x - 1) = -2(4x + 3)$

2 Noah receives m dollars pocket money per week. His younger brother Jake gets half of three dollars less than Noah's amount. If Jake receives $6:

a write an equation to represent the problem

b solve the equation in part **a** to determine how much Noah receives each week.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 The formula $S = \frac{n}{2}(a + l)$ gives the sum S of a sequence of n numbers with first term a and last term l.

- **a** Find the sum of the sequence of 10 terms $2, 5, 8, \ldots, 29$.
- **b** Rearrange the formula to make l the subject.
- **c** If a sequence of 8 terms has a sum of 88 and a first term equal to 4, use your answer to part **b** to find the last term of this sequence.

4 Solve the following equations simultaneously.

a $x + 4y = 18$, $x = 2y$ **b** $7x - 2y = 3$, $y = 2x - 3$ **c** $2x + 3y = 4$, $x + y = 3$ **d** $3x + 4y = 7$, $5x + 2y = -7$

Extended-response question

a Chris referees junior basketball games on a Sunday. He is paid \$20 plus \$12 per game he referees. He is trying to earn more than \$74 one Sunday. Let x be the number of games he referees.

- **i** Write an inequality to represent the problem.
- **ii** Solve the inequality to find the minimum number of games he must referee.

b Two parents support the game by buying raffle tickets and badges. One buys 5 raffle tickets and 2 badges for \$11.50 while the other buys 4 raffle tickets and 3 badges for \$12. Determine the cost of a raffle ticket and the cost of a badge by:

- **i** defining two variables
- **ii** setting up two equations to represent the problem
- **iii** solving your equations simultaneously.

Pythagoras' theorem and trigonometry

Multiple-choice questions

1 The exact value of x in the triangle shown is:



A 3.9 **B** $\sqrt{113}$ **C** $\sqrt{57}$ **D** $\sqrt{15}$ **E** 2.7

2 The correct expression for the triangle shown is:



A $x = \frac{6}{\sin 42^\circ}$ **B** $x = 6 \tan 42^\circ$ **C** $x = 6 \sin 42^\circ$

D $x = \frac{6}{\cos 42^\circ}$ **E** $x = \frac{\sin 42^\circ}{6}$

3 The correct expression for the angle θ is:



A $\theta = \tan^{-1}\left(\frac{x}{z}\right)$ **B** $\theta = \sin^{-1}\left(\frac{x}{z}\right)$ **C** $\theta = \tan^{-1}\left(\frac{y}{x}\right)$

D $\theta = \cos^{-1}\left(\frac{z}{x}\right)$ **E** $\theta = \cos^{-1}\left(\frac{x}{y}\right)$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 A 5-metre plank of wood is leaning up against a side of a building as shown. If the wood touches the ground 3 m from the base of the building, the angle the wood makes with the building is closest to:



A 36.9° **B** 59° **C** 53.1° **D** 31° **E** 41.4°

5 The true bearing of A from O is:

A 025° **B** 125° **C** 155°
D 065° **E** 115°



Short-answer questions

1 Find the value of each pronumeral, correct to one decimal place.

a



b



c



d



2 Find the value of the pronumerals. Round to one decimal place where necessary.

a



b



3 A wire is to be connected from the edge of the top of a 28 m high building to the edge of the top of a 16 m high building. The buildings are 15 m apart.

a What length of wire, to the nearest centimetre, is required?

b What is the angle of depression from the top of the taller building to the top of the smaller building? Round to one decimal place.

4 A yacht sails 18 km from its start location on a bearing of 295° T.

a How far east or west is it from its start location? Answer correct to one decimal place.

b On what true bearing would it need to sail to return directly to its start location?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response question

A skateboard ramp is constructed as shown.

a Calculate the distance d metres up the ramp, correct to two decimal places.



b What is the angle of inclination (θ) between the ramp and the ground, correct to one decimal place?

c **i** If the skateboarder rides from one corner of the ramp diagonally to the other corner, what distance would be travelled? Round to one decimal place.

ii If the skateboarder travels at an average speed of 10 km/h, how many seconds does it take to ride diagonally across the ramp? Answer correct to one decimal place.

Linear relations

Multiple-choice questions

1 The coordinates of the x- and y-intercepts respectively for the graph shown are:

A $(-2, 4)$ and $(4, -2)$
B $(0, 4)$ and $(-2, 0)$
C $(-2, 0)$ and $(0, 4)$
D $(4, 0)$ and $(0, -2)$
E $(2, 0)$ and $(0, -4)$



2 The graph shown has equation:

A $y = 3x$
B $y = 3$
C $y = x + 3$
D $x = 3$
E $x + y = 3$



3 If the point $(-1, 3)$ is on the line $y = 2x + c$, the value of c is:

A 1 **B** 5 **C** –7 **D** –5 **E** –1

4 The line passing through the points $(-3, -1)$ and $(1, y)$ has gradient 2. The value of y is:

A 3 **B** 5 **C** 7 **D** 1 **E** 4

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 The midpoint and length (to one decimal place) of the line segment joining the points (–2, 1) and (4, 6) are:

A (1, 3.5) and 7.8 **B** (3, 5) and 5.4 **C** (3, 3.5) and 6.1
D (1, 3.5) and 3.3 **E** (3, 3.5) and 3.6

Short-answer questions

1 Sketch the following linear graphs labelling x- and y-intercepts.

a $y = 2x - 6$ **b** $3x + 4y = 24$ **c** $y = 4x$

2 Find the gradient of each of the following.

a The line passing through the points (–1, 2) and (2, 4)
b The line passing through the points (–2, 5) and (1, – 4)
c The line with equation $y = -2x + 5$
d The line with equation $-4x + 3y = 9$

3 Give the equation of the following lines in gradient–intercept form.

a The line with the given graph.
b The line with gradient 3 and passing through the point (2, 5).
c The line parallel to the line with equation $y = 2x - 1$ that passes through the origin.
d The line perpendicular to the line with equation $y = 3x + 4$ that passes through the point (0, 2).



4 Solve the simultaneous equations $y = 2x - 4$ and $x + y = 5$ graphically by finding the coordinates of the point of intersection.

Extended-response question

Doug works as a labourer. He is digging a trench and has 180 kg of soil to remove. He has taken 3 hours to remove 36 kg.

a What is the rate at which he is removing the soil?

b If he maintains this rate, write a rule for the amount of soil, S (kg), remaining after t hours.

c Draw a graph of your rule.

d How long will it take to remove all of the soil?

e Doug is paid $40 for the job plus $25 per hour worked.

i Write a rule for his pay P dollars for working h hours.
ii How much will he be paid to remove all the soil?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Measurement

Multiple-choice questions

1 The perimeter and area of the figure shown are:

A 20.2 m, 22.42 m^2
B 24.8 m, 22.42 m^2
C 24.8 m, 25.15 m^2
D 20.2 m, 25.15 m^2
E 21.6 m, 24.63 m^2



2 The exact perimeter in centimetres of this sector is:

A 127.2
B $\frac{81\pi}{2} + 27$
C $12\pi + 27$
D 45.8
E $6\pi + 27$



3 420 cm^2 is equivalent to:

A 4.2 m^2 **B** 0.42 m^2 **C** 42 000 m^2 **D** 0.042 m^2 **E** 0.0042 m^2

4 This square pyramid has a total surface area of:

A 525 m^2
B 300 m^2
C 750 m^2
D 450 m^2
E 825 m^2



5 The volume of the cylinder shown is closest to:

A 703.7 cm^3 **B** 351.9 cm^3 **C** 2814.9 cm^3
D 452.4 cm^3 **E** 1105.8 cm^3



Short-answer questions

1 Find the area of each of the figures below. Round to two decimal places where necessary.

a



b



2 A tin of varnish for the timber (shaded) on the deck shown covers 6.2 square metres. How many tins will be required to completely varnish the deck?



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3 Find the total surface area of these solid objects. Round to two decimal places where necessary.

a



b



4 Find the value of the pronumeral for the given volume.

a



$V = 192 \text{ cm}^3$

b



$V = 156.4 \text{ m}^3$

Extended-response question

A barn in the shape of a rectangular prism with a semicylindrical roof and with the dimensions shown is used to store hay.

a The roof and the two long side walls of the barn are to be painted. Calculate the surface area to be painted correct to two decimal places.



b A paint roller has a width of 20 cm and a radius of 3 cm.

i Find the area of the curved surface of the paint roller in m^2. Round to four decimal places.

ii Hence, state the area that the roller will cover in 100 revolutions.

c Find the minimum number of revolutions required to paint the area of the barn in part **a** with one coat.

d Find the volume of the barn correct to two decimal places.

e A rectangular bail of hay has dimensions 1 m by 40 cm by 40 cm. If there are 115 bails of hay in the barn, what volume of air space remains? Answer to two decimal places.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter 6

Indices and surds

What you will learn

- 6A Index notation (Consolidating)
- 6B Index laws 1 and 2
- 6C Index law 3 and the zero power
- 6D Index laws 4 and 5
- 6E Negative indices
- 6F Scientific notation
- 6G Scientific notation using significant figures
- 6H Fractional indices and surds (Extending)
- 6I Simple operations with surds (Extending)

Australian curriculum

NUMBER AND ALGEBRA

Real numbers

Apply index laws to numerical expressions with integer indices

Express numbers in scientific notation

Patterns and algebra

Extend and apply the index laws to variables, using positive integral indices and the zero index

MEASUREMENT AND GEOMETRY

Using units of measurement

Investigate very small and very large time scales and intervals AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Deadly bacteria

Mycobacterium tuberculosis is a deadly type of bacteria that causes the disease tuberculosis. In 1900, tuberculosis was one of the most common causes of death in developed countries and is still one of the most common causes of death today. In the developing world about 1.5 million deaths are caused by tuberculosis every year.

Bacteria, such as tuberculosis, reproduce rapidly under favourable conditions. The bacteria cells undergo binary fission where each cell divides in two within a given period of time. So after n divisions the number of cells N is given by $N = 2^n$ where n is the index in the rule. Such rules involving indices help to model population growth of bacteria and other forms of growth and decay.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6A Index notation CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

When a product includes the repeated multiplication of the same factor, indices can be used to produce a more concise expression. For example, $5 \times 5 \times 5$ can be written as 5^3 and $x \times x \times x \times x \times x$ can be written as x^5. The expression 5^3 is a power and we can say '5 to the power of 3'. The 5 is called the base and the 3 is the index, exponent or power. Numbers written with indices are common in mathematics and can be applied to many types of problems. The mass of a 100 kg limestone block, for example, might decrease by 2 per cent per year for 20 years. The mass after 20 years could be calculated by multiplying 100 by 0.98, 20 times. This is written as $100 \times (0.98)^{20}$.

Index notation is a convenient way for expressing large numbers or for carrying out calculations such as how much mass is lost over time from ancient stone monuments.

Let's start: Who has the most?

A person offers you one of two prizes.

- Which offer would you take?
- Try to calculate the final amount for prize B.
- How might you use indices to help calculate the value of prize B?
- How can a calculator help to find the amount for prize B using the power button $\boxed{\wedge}$?

Key ideas

- **Indices** (plural of **index**) can be used to represent a product of the same factor.
- The **base** is the factor in the product.
- The index (**exponent** or **power**) is the number of times the factor (base number) is written.
- Note that $a^1 = a$.
  For example: $5^1 = 5$
- **Prime factorisation** involves writing a number as a product of its prime factors.

Expanded form: $\overbrace{2 \times 2 \times 2 \times 2 \times 2}^{\text{Index form}} = 2^5 = 32$

base, index, basic numeral

$x \times x \times x \times x \times x = x^4$

base, index



$108 = 2 \times 2 \times 3 \times 3 \times 3$
$= \underbrace{2^2 \times 3^3}$
prime factor form

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Writing in expanded form

Write in expanded form:

a a^3 **b** $(xy)^4$ **c** $2a^3b^2$

SOLUTION	EXPLANATION
a $a^3 = a \times a \times a$	Factor a is written three times.
b $(xy)^4 = xy \times xy \times xy \times xy$	Factor xy is written four times.
c $2a^3b^2 = 2 \times a \times a \times a \times b \times b$	Factor a is written three times and factor b is written twice. Factor 2 only appears once.

Example 2 Expanding and evaluating

Write each of the following in expanded form and then evaluate.

a 5^3 **b** $(-2)^5$ **c** $\left(\frac{2}{5}\right)^3$

SOLUTION	EXPLANATION
a $5^3 = 5 \times 5 \times 5$ $= 125$	Write in expanded form with 5 written three times and evaluate.
b $(-2)^5 = (-2) \times (-2) \times (-2) \times (-2) \times (-2)$ $= -32$	Write in expanded form with –2 written five times and evaluate.
c $\left(\frac{2}{5}\right)^3 = \frac{2}{5} \times \frac{2}{5} \times \frac{2}{5}$ $= \frac{8}{125}$	Write in expanded form. Evaluate by multiplying numerators and denominators.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Writing in index form

Write each of the following in index form.

a $6 \times x \times x \times x \times x \times x$ **b** $\frac{3}{7} \times \frac{3}{7} \times \frac{4}{5} \times \frac{4}{5} \times \frac{4}{5}$ **c** $8 \times a \times a \times 8 \times b \times b \times a \times b$

SOLUTION	EXPLANATION
a $6 \times x \times x \times x \times x \times x = 6x^4$	Factor x is written 4 times, 6 only once.
b $\frac{3}{7} \times \frac{3}{7} \times \frac{4}{5} \times \frac{4}{5} \times \frac{4}{5} = \left(\frac{3}{7}\right)^2 \times \left(\frac{4}{5}\right)^3$	There are two groups of $\left(\frac{3}{7}\right)$ and three groups of $\left(\frac{4}{5}\right)$.
c $8 \times a \times a \times 8 \times b \times b \times a \times b$ $= 8 \times 8 \times a \times a \times a \times b \times b \times b$ $= 8^2a^3b^3$	Group the numerals and like pronumerals and write in index form.

Example 4 Finding the prime factor form

Express 48 as a product of prime factors in index form.

SOLUTION	EXPLANATION
	Choose a pair of factors of 48, for example 8 and 6. Choose a pair of factors of 8, i.e. 2 and 4. Choose a pair of factors of 6, i.e. 2 and 3. Continue this process until the factors are all prime numbers (circled numbers).
$\therefore 48 = 2 \times 2 \times 2 \times 2 \times 3$ $= 2^4 \times 3$	Write the prime factors of 48. Express in index notation.

Exercise 6A

1–4(½) | 1 | —

UNDERSTANDING

1 Evaluate:

a 5^2 **b** 2^3 **c** 3^3 **d** $(-4)^2$

2 Write the number or variable that is the base in these expressions.

a 3^7 **b** 6^4 **c** $(1.2)^5$ **d** $(-7)^3$

e $\left(\frac{2}{3}\right)^4$ **f** y^{10} **g** w^6 **h** t^2

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6A

UNDERSTANDING

3 Write the number that is the index in these expressions.

a 4^3 **b** 10^8 **c** $(-3)^7$ **d** $\left(\frac{1}{2}\right)^4$

e x^{11} **f** $(xy)^{13}$ **g** $\left(\frac{x}{2}\right)^9$ **h** $(1.3x)^2$

4 Write the prime factors of these numbers.

a 6 **b** 15 **c** 30 **d** 77

5–10(½) 5–11(½) 5–11(½)

FLUENCY

Example 1 **5** Write each of the following in expanded form.

a a^4 **b** b^3 **c** x^3 **d** $(xp)^6$

e $(5a)^4$ **f** $(3y)^3$ **g** $4x^2y^5$ **h** $(pq)^2$

i $-3s^3t^2$ **j** $6x^3y^5$ **k** $5(yz)^6$ **l** $4(ab)^3$

Example 2 **6** Write each of the following in expanded form and then evaluate.

a 6^2 **b** 2^4 **c** 3^5 **d** 12^1

e $(-2)^3$ **f** $(-1)^7$ **g** $(-3)^4$ **h** $(-5)^2$

i $\left(\frac{2}{3}\right)^3$ **j** $\left(\frac{3}{4}\right)^2$ **k** $\left(\frac{1}{6}\right)^3$ **l** $\left(\frac{5}{2}\right)^2$

m $\left(\frac{2}{-3}\right)^3$ **n** $\left(\frac{-3}{4}\right)^4$ **o** $\left(\frac{-1}{4}\right)^2$ **p** $\left(\frac{5}{-2}\right)^5$

Example 3a **7** Write each of the following in index form.

a $3\times3\times3$ **b** $8\times8\times8\times8\times8\times8$

c $y\times y$ **d** $3\times x\times x\times x$

e $4\times c\times c\times c\times c\times c$ **f** $5\times5\times5\times d\times d$

g $x\times x\times y\times y\times y$ **h** $7\times b\times7\times b\times7$

Example 3b **8** Write each of the following in index form.

a $\frac{2}{3}\times\frac{2}{3}\times\frac{2}{3}\times\frac{2}{3}$ **b** $\frac{3}{5}\times\frac{3}{5}\times\frac{3}{5}\times\frac{3}{5}\times\frac{3}{5}$

c $\frac{4}{7}\times\frac{4}{7}\times\frac{1}{5}\times\frac{1}{5}\times\frac{1}{5}\times\frac{1}{5}$ **d** $\frac{7x}{9}\times\frac{7x}{9}\times\frac{y}{4}\times\frac{y}{4}\times\frac{y}{4}$

Example 3c **9** Write each of the following in index form.

a $3\times x\times y\times x\times3\times x\times3\times y$ **b** $3x\times2y\times3x\times2y$

c $4d\times2e\times4d\times2e$ **d** $6by(6by)(6y)$

e $3pq(3pq)(3pq)(3pq)$ **f** $7mn\times7mn\times mn\times7$

Example 4 **10** Express each of the following as a product of prime factors in index form.

a 10 **b** 8 **c** 144

d 512 **e** 216 **f** 500

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6A

FLUENCY

11 If $a = 3$, $b = 2$ and $c = -3$, evaluate these expressions.

a $(ab)^2$ **b** $(bc)^3$ **c** $\left(\frac{a}{c}\right)^4$ **d** $\left(\frac{b}{c}\right)^3$

e $(abc)^1$ **f** $c^2 + ab$ **g** ab^2c **h** c^2ab^3

12, 13 | 12–14 | 13–15

PROBLEM-SOLVING

12 Find the missing number.

a $3^{\square} = 81$ **b** $2^{\square} = 256$ **c** $\square^3 = 125$ **d** $\square^5 = 32$

e $\square^3 = -64$ **f** $\square^7 = -128$ **g** $\square^3 = \frac{1}{8}$ **h** $\left(\frac{2}{3}\right)^{\square} = \frac{16}{81}$

13 Bacteria cells split in 2 every 5 minutes. New cells also continue splitting in the same way. Use a table to help.

a How long will it take for 1 cell to divide into:

i 4 cells? **ii** 16 cells?

iii 64 cells?

b A single cell is set aside to divide for two hours. How many cells will there be after this time?

14 A share broker says he can triple your money every year, so you invest $1000 with him.

a How much should your investment be worth in 5 years?

b How many years should you invest for if you were hoping for a total of at least $100 000? Give a whole number of years.

15 A fat cat that was initially 12 kg reduces its weight by 10% each month. How long does it take for the cat to be at least 6 kg lighter than its original weight? Give your answer as a whole number of months.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6A

	16, 17	16, 17	16, 17, 18(½)

REASONING

16 **a** Evaluate the following.

i 3^2 **ii** $(-3)^2$ **iii** $-(3)^2$ **iv** $-(-3)^2$

b Explain why the answers to parts **i** and **ii** are positive.

c Explain why the answers to parts **iii** and **iv** are negative.

17 **a** Evaluate the following.

i 2^3 **ii** $(-2)^3$ **iii** $-(2)^3$ **iv** $-(-2)^3$

b Explain why the answers to parts **i** and **iv** are positive.

c Explain why the answers to parts **ii** and **iii** are negative.

18 It is often easier to evaluate a decimal raised to a power by firstly converting the decimal to a fraction as shown on the right. Use this idea to evaluate these as a fraction.

$$(0.5)^4 = \left(\frac{1}{2}\right)^4$$
$$= \frac{1}{2} \times \frac{1}{2} \times \frac{1}{2} \times \frac{1}{2}$$
$$= \frac{1}{16}$$

a $(0.5)^3$ **b** $(0.25)^2$ **c** $(0.2)^3$

d $(0.5)^6$ **e** $(0.7)^2$ **f** $(1.5)^4$

g $(2.6)^2$ **h** $(11.3)^2$ **i** $(3.4)^2$

LCM and HCF from prime factorisation

	—	—	19

ENRICHMENT

19 Last year you may have used prime factorisation to find the LCM (Lowest Common Multiple) and the HCF (Highest Common Factor) of two numbers. Here are the definitions.

- The LCM of two numbers in their prime factor form is the product of all the different primes raised to their highest power.
- The HCF of two numbers in their prime factor form is the product of all the common primes raised to their smallest power.

For example: $12 = 2^2 \times 3$ and $30 = 2 \times 3 \times 5$

The prime factors 2 and 3 are common.

$\therefore$ HCF $= 2 \times 3$ $\quad \therefore$ LCM $= 2^2 \times 3 \times 5$

$= 6$ $\quad = 60$

Find the LCM and HCF of these pairs of numbers by firstly writing them in prime factor form.

a 4, 6 **b** 42, 28 **c** 24, 36 **d** 10, 15

e 40, 90 **f** 100, 30 **g** 196, 126 **h** 2178, 1188

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6B Index laws 1 and 2

Interactive

Widgets

HOTsheets

Walkthroughs

An index law (or identity) is an equation that is true for all possible values of the variables in that equation. When multiplying or dividing numbers with the same base, index laws can be used to simplify the expression.

Consider $a^m \times a^n$.

Using expanded form:

$$a^m \times a^n = \overbrace{a \times a \times a \times \ldots \times a}^{m \text{ factors of } a} \times \overbrace{a \times a \times \ldots \times a}^{n \text{ factors of } a}$$
$$= \overbrace{a \times a \times \ldots \times a}^{m+n \text{ factors of } a}$$
$$= a^{m+n}$$

So the total number of factors of a is $m + n$.

Also,

$$a^m \div a^n = \frac{\overbrace{a \times a \times \ldots \times \cancel{a} \times \cancel{a} \times \cancel{a} \times \cancel{a}}^{m \text{ factors of a}}}{\underbrace{\cancel{a} \times \ldots \times \cancel{a} \times \cancel{a}}_{n \text{ factors of } a}}$$
$$= a^{m-n}$$

So the total number of factors of a is $m - n$.

Index laws have applications in calculations involving very large (or very small) numbers.

Let's start: Discovering laws 1 and 2

Consider the two expressions $2^3 \times 2^5$ and $6^8 \div 6^6$.

Complete this working.

$$2^3 \times 2^5 = 2 \times \square \times \square \times 2 \times \square \times \square \times \square \times \square$$
$$= 2^{\square}$$
$$6^8 \div 6^6 = \frac{6 \times \square \times \square \times \square \times \square \times \square \times \square \times \square}{6 \times \square \times \square \times \square \times \square \times \square}$$
$$= \frac{6 \times 6}{1}$$
$$= 6^{\square}$$

- What do you notice about the given expression and the answer in each case? Can you express this as a rule or law in words?
- Repeat the type of working given above and test your laws on these expressions.

a $3^2 \times 3^7$ **b** $4^{11} \div 4^8$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Index law 1:** $a^m \times a^n = a^{m+n}$
  - When multiplying terms with the same base, add the powers.
- **Index law 2:** $a^m \div a^n = \frac{a^m}{a^n} = a^{m-n}$
  - When dividing terms with the same base, subtract the powers.

Example 5 Using laws 1 and 2 with numbers

Simplify, giving your answer in index form.

a $3^6 \times 3^4$ b $7^9 \div 7^5$

SOLUTION

a $3^6 \times 3^4 = 3^{6+4}$
$= 3^{10}$

b $7^9 \div 7^5 = 7^{9-5}$
$= 7^4$

EXPLANATION

$a^m \times a^n = a^{m+n}$ (add the powers)

$a^m \div a^n = a^{m-n}$ (subtract the powers)

Example 6 Using index law 1

Simplify each of the following using the first index law.

a $x^4 \times x^5$ b $x^3y^4 \times x^2y$ c $3m^4 \times 2m^5$

SOLUTION

a $x^4 \times x^5 = x^{4+5}$
$= x^9$

b $x^3y^4 \times x^2y = x^{3+2}y^{4+1}$
$= x^5y^5$

c $3m^4 \times 2m^5 = 3 \times 2 \times m^{4+5}$
$= 6m^9$

EXPLANATION

Use law 1 to add the indices.

Use law 1 to add the indices corresponding to each different base. Recall $y = y^1$.

Multiply the numbers then use law 1 to add the indices of the base m.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 7 Using index law 2

Simplify each of the following using the second index law.

a $x^{10} \div x^2$

b $\dfrac{8a^6b^3}{12a^2b^2}$

SOLUTION

a $x^{10} \div x^2 = x^{10-2}$
$= x^8$

b $\dfrac{8a^6b^3}{12a^2b^2} = \dfrac{{}^{2}\cancel{8}a^{6-2}b^{3-2}}{{}^{3}\cancel{12}}$
$= \dfrac{2a^4b}{3}$

EXPLANATION

Use law 2 to subtract the indices.

Cancel the numbers using the highest common factor (4) and use law 2 to subtract the indices for each different base.

Example 8 Combining index laws 1 and 2

Simplify each of the following using the first two index laws.

a $x^2 \times x^3 \div x^4$

b $\dfrac{2a^3b \times 8a^2b^3}{4a^4b^2}$

SOLUTION

a $x^2 \times x^3 \div x^4 = x^5 \div x^4$
$= x$

b $\dfrac{2a^3b \times 8a^2b^3}{4a^4b^2} = \dfrac{{}^{4}\cancel{16}a^5b^4}{{}^{1}\cancel{4}a^4b^2}$
$= 4ab^2$

EXPLANATION

Use law 1 to add the indices for $x^2 \times x^3$.
Use law 2 to subtract the indices for $x^5 \div x^4$.

Multiply the numbers and use law 1 to add the indices for each different base in the numerator.
Use law 2 to subtract the indices of each different base and cancel the numbers.

Exercise 6B

1–3 | 3 | —

UNDERSTANDING

1 Write the missing words.

a Index law 1 states that if you _____ two terms with the same _____ you _____ the powers.

b Index law 2 states that if you _____ two terms with the same _____ you _____ the powers.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6B

UNDERSTANDING

2 Copy and complete to give an answer in index form. Use cancelling in parts **c** and **d**.

a $3^2 \times 3^4 = 3 \times \square \times 3 \times \square \times \square \times \square$
$= 3^{\square}$

b $6^4 \times 6^3 = 6 \times \square \times \square \times \square \times 6 \times \square \times \square$
$= 6^{\square}$

c $5^5 \div 5^3 = \dfrac{5 \times \square \times \square \times \square \times \square}{5 \times \square \times \square}$
$= 5^{\square}$

d $9^4 \div 9^2 = \dfrac{9 \times \square \times \square \times \square}{9 \times \square}$
$= 9^{\square}$

3 Decide if these statements are true or false.

a $5 \times 5 \times 5 \times 5 = 5^4$
b $2^6 \times 2^2 = 2^{6+2}$
c $7^2 \times 7^4 = 7^{4-2}$
d $8^4 \div 8^2 = 8^{4+2}$
e $a \times a^2 = a^3$
f $a^5 \times a^2 = a^{5-2}$
g $x^7 \div x = x^7$
h $b^4 \div b = b^3$

4–7(½) 4–8(½) 4–8(½)

FLUENCY

Example 5

4 Simplify, giving your answers in index form.

a $2^4 \times 2^3$
b $5^6 \times 5^3$
c $7^2 \times 7^4$
d $8^9 \times 8$
e $3^4 \times 3^4$
f $6^5 \times 6^9$
g $3^7 \div 3^4$
h $6^8 \div 6^3$
i $5^4 \div 5$
j $10^6 \div 10^5$
k $9^9 \div 9^6$
l $(-2)^5 \div (-2)^3$

Example 6

5 Simplify each of the following using the first index law.

a $x^4 \times x^3$
b $a^6 \times a^3$
c $t^5 \times t^3$
d $y \times y^4$
e $d^2 \times d$
f $y^2 \times y \times y^4$
g $b \times b^5 \times b^2$
h $q^6 \times q^3 \times q^2$
i $x^3y^3 \times x^4y^2$
j $x^7y^3 \times x^2y$
k $5x^3y^5 \times xy^4$
l $xy^4z \times 4xy$
m $3m^3 \times 5m^2$
n $4e^4f^2 \times 2e^2f^2$
o $5c^4d \times 4c^3d$
p $9yz^2 \times 2yz^5$

Example 7

6 Simplify each of the following using the second index law.

a $a^6 \div a^4$
b $x^5 \div x^2$
c $\dfrac{q^{12}}{q^2}$
d $\dfrac{d^7}{d^6}$
e $\dfrac{8b^{10}}{4b^5}$
f $\dfrac{12d^{10}}{36d^5}$
g $\dfrac{4a^{14}}{2a^7}$
h $\dfrac{18y^{15}}{9y^7}$
i $9m^3 \div m^2$
j $14x^4 \div x$
k $5y^4 \div y^2$
l $6a^6 \div a^5$
m $\dfrac{3m^7}{12m^2}$
n $\dfrac{5w^2}{25w}$
o $\dfrac{4a^4}{20a^3}$
p $\dfrac{7x^5}{63x}$
q $\dfrac{16x^8y^6}{12x^2y^3}$
r $\dfrac{6s^6t^3}{14s^5t}$
s $\dfrac{8m^5n^4}{6m^4n^3}$
t $-\dfrac{5x^2y}{xy}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6B

Example 8

FLUENCY

7 Simplify each of the following using the first two index laws.

a $b^5 \times b^2 \div b$ **b** $y^5 \times y^4 \div y^3$ **c** $c^4 \div c \times c^4$ **d** $x^4 \times x^2 \div x^5$

e $\dfrac{t^4 \times t^3}{t^6}$ **f** $\dfrac{p^2 \times p^7}{p^3}$ **g** $\dfrac{d^5 \times d^3}{d^2}$ **h** $\dfrac{x^9 \times x^2}{x}$

i $\dfrac{3x^3y^4 \times 8xy}{6x^2y^2}$ **j** $\dfrac{9b^4}{2g^3} \times \dfrac{4g^4}{3b^2}$

k $\dfrac{24m^7n^5}{5m^3n} \times \dfrac{5m^2n^4}{8mn^2}$ **l** $\dfrac{p^4q^3}{p^2q} \times \dfrac{p^6q^4}{p^3q^2}$

8 Simplify each of the following.

a $\dfrac{m^4}{n^2} \times \dfrac{m}{n^3}$ **b** $\dfrac{x}{y} \times \dfrac{x^3}{y}$ **c** $\dfrac{a^4}{b^3} \times \dfrac{b^6}{a}$

d $\dfrac{12a}{3c^3} \times \dfrac{6a^4}{4c^4}$ **e** $\dfrac{3f^2 \times 8f^7}{4f^3}$ **f** $\dfrac{4x^2b \times 9x^3b^2}{3xb}$

g $\dfrac{8k^4m^5}{5km^3} \times \dfrac{15km}{4k}$ **h** $\dfrac{12x^7y^3}{5x^4y} \times \dfrac{25x^2y^3}{8xy^4}$ **i** $\dfrac{9m^5n^2 \times 4mn^3}{12mn \times m^4n^2} \times \dfrac{m^3n^2}{2m^2n}$

9(½), 10 | 9(½), 10 | 10, 11

PROBLEM-SOLVING

9 Write the missing number.

a $2^7 \times 2^{\square} = 2^{19}$ **b** $6^{\square} \times 6^3 = 6^{11}$ **c** $11^6 \div 11^{\square} = 11^3$

d $19^{\square} \div 19^2 = 19$ **e** $x^6 \times x^{\square} = x^7$ **f** $a^{\square} \times a^2 = a^{20}$

g $b^{13} \div b^{\square} = b$ **h** $y^{\square} \div y^9 = y^2$ **i** $\square \times x^2 \times 3x^4 = 12x^6$

j $15y^4 \div (\square\, y^3) = y$ **k** $\square\, a^9 \div (4a) = \dfrac{a^8}{2}$ **l** $13b^6 \div (\square\, b^5) = \dfrac{b}{3}$

10 Evaluate without using a calculator.

a $7^7 \div 7^5$ **b** $10^6 \div 10^5$ **c** $13^{11} \div 13^9$ **d** $2^{20} \div 2^{17}$

e $101^5 \div 101^4$ **f** $200^{30} \div 200^{28}$ **g** $7 \times 31^{16} \div 31^{15}$ **h** $3 \times 50^{200} \div 50^{198}$

11 If m and n are positive integers, how many combinations of m and n satisfy the following?

a $a^m \times a^n = a^8$ **b** $a^m \times a^n = a^{15}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6B

	12	12, 13	13, 14(½)

REASONING

12 The given answers are incorrect. Give the correct answer and explain the error made.

a $a^4 \times a = a^4$ **b** $x^7 \div x = x^7$ **c** $3a^5 \div (6a^3) = 2a^2$

d $5x^7 \div (10x^3) = \dfrac{1}{2x^4}$ **e** $2x^7 \times 3x^4 = 5x^{11}$ **f** $a^5 \div a^2 \times a = a^5 \div a^3 = a^2$

13 Given that $a = 2x$, $b = 4x^2$ and $c = 5x^3$, find expressions for:

a $2a$ **b** $3b$ **c** $2c$ **d** $-2a$

e abc **f** $\dfrac{c}{b}$ **g** $\dfrac{ab}{c}$ **h** $\dfrac{-2bc}{a}$

14 Simplify these expressions using the given variables.

a $2^x \times 2^y$ **b** $5^a \times 5^b$ **c** $t^x \times t^y$

d $3^x \div 3^y$ **e** $10^p \div 10^y$ **f** $2^p \times 2^q \div 2^r$

g $10^p \div 10^q \div 10^r$ **h** $2^a \times 2^{a+b} \times 2^{3a-b}$ **i** $a^{x-2}b^x \times a^{2x}b^3$

j $a^x b^y \times a^y b^x$ **k** $a^x b^y \div (a^y b^x)$ **l** $w^{x+2}b^x \div w^{2x} \times b^3$

m $\dfrac{a^x \times 3a^y}{3a^2}$ **n** $\dfrac{4p^a \times 5q^b}{20q^5}$ **o** $\dfrac{10k^x m^y}{8km^3} \div \dfrac{5k^x m^{2x}}{16k}$

Equal to *ab*	—	—	15, 16

ENRICHMENT

15 Show working to prove that these expressions simplify to ab.

a $\dfrac{5a^2b^7}{9a^3b} \times \dfrac{9a^4b^2}{5a^2b^7}$ **b** $\dfrac{3a^5bc^3}{6a^4c} \times \dfrac{4b^3}{2abc} \times \dfrac{2a^3b^2c}{2a^2b^4c^2}$

c $\dfrac{3a^4b^5}{a^5b^2} \div \dfrac{6b^3}{2a^2b}$ **d** $\dfrac{2a}{3a^2b^3} \times \dfrac{9a^4b^7}{ab^5} \div \dfrac{6a}{b^2}$

16 Make up your own expressions which simplify to ab. Test them on a friend.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6C Index law 3 and the zero power

Interactive

Widgets

HOTsheets

Walkthroughs

Sometimes we find expressions already written in index form are raised to another power, such as $(2^3)^4$ or $(a^2)^5$

Consider $(a^m)^n$.

Using expanded form $(a^m)^n = \overbrace{a^m \times a^m \times \ldots \times a^m}^{n \text{ factors of } a^m}$

$$= \overbrace{\underbrace{a \times a \times \ldots \times a}_{m \text{ factors of } a} \times \underbrace{a \times a \times \ldots \times a}_{m \text{ factors of } a} \times \ldots \times \underbrace{a \times a \times \ldots \times a}_{m \text{ factors of } a}}^{m \times n \text{ factors of } a}$$

$$= a^{m \times n}$$

So the total number of factors of a is $m \times n$.

We also know that $a^m \div a^m = \dfrac{\cancel{a} \times \cancel{a} \times \cancel{a} \times \cdots \times \cancel{a}}{\cancel{a} \times \cancel{a} \times \cancel{a} \times \cdots \times \cancel{a}}$

$$= \frac{1}{1}$$

$$= 1$$

But using index law number 2: $a^m \div a^m = a^{m-m}$

$$= a^0$$

This implies that $a^0 = 1$.



Any number raised to the power of zero is one.

Let's start: Discovering law 3 and the zero power

Use the expanded form of 5^3 to simplify $(5^3)^2$ as shown.

$$(5^3)^2 = \left(5 \times \square \times \square\right) \times \left(5 \times \square \times \square\right)$$

$$= 5^{\square}$$

- Repeat the above steps to also simplify $(3^2)^4$ and $(x^4)^2$.
- What do you notice about the given expression and answer in each case? Can you express this as a law or rule in words?

  Now complete this table.

Index form	3^5	3^4	3^3	3^2	3^1	3^0
Basic Numeral	243	81				

- What pattern do you notice in the basic numerals?
- What conclusion do you come to regarding 3^0 ?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Index law 3**: $(a^m)^n = a^{mn}$
  - When raising a term in index form to another power, retain the base and multiply the indices. For example: $(x^2)^3 = x^{2 \times 3} = x^6$.
- **The zero power**: $a^0 = 1$, where $a \neq 0$
  - Any term except 0 raised to the power of zero is 1. For example: $(2a)^0 = 1$.

Example 9 Using index law 3

Apply index law 3 to simplify each of the following.

a $(x^5)^4$ b $3(y^5)^2$

SOLUTION	EXPLANATION
a $(x^5)^4 = x^{5 \times 4}$ $= x^{20}$	Retain x as the base and multiply the indices.
b $3(y^5)^2 = 3y^{5 \times 2}$ $= 3y^{10}$	Retain y and multiply the indices. The power only applies to the bracketed term.

Example 10 Using the zero power

Apply the zero power rule to evaluate each of the following.

a $(-3)^0$ b $-(5x)^0$ c $2y^0 - (3y)^0$

SOLUTION	EXPLANATION
a $(-3)^0 = 1$	Any number raised to the power of 0 is 1.
b $-(5x)^0 = -1$	Everything in the brackets is to the power of 0 so $(5x)^0$ is 1.
c $2y^0 - (3y)^0 = 2 \times 1 - 1$ $= 2 - 1$ $= 1$	$2y^0$ has no brackets so the power applies to the y only so $2y^0 = 2 \times y^0 = 2 \times 1$ while $(3y)^0 = 1$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Combining index laws

Simplify each of the following by applying the various index laws.

a $(x^2)^3 \times (x^3)^5$ **b** $\dfrac{(m^3)^4}{m^7}$ **c** $\dfrac{4x^2 \times 3x^3}{6x^5}$

SOLUTION	EXPLANATION
a $(x^2)^3 \times (x^3)^5 = x^6 \times x^{15}$ $= x^{21}$	Use index law 3 to remove brackets first by multiplying indices. Then use index law 1 to add indices.
b $\dfrac{(m^3)^4}{m^7} = \dfrac{m^{12}}{m^7}$ $= m^5$	Remove brackets by multiplying indices then simplify using index law 2.
c $\dfrac{4x^2 \times 3x^3}{6x^5} = \dfrac{12x^5}{6x^5}$ $= 2x^0$ $= 2 \times 1$ $= 2$	Simplify the numerator first by multiplying numbers and adding indices of base x. Then cancel and subtract indices. The zero power says $x^0 = 1$.

Exercise 6C

1–3 | 3(½) | —

UNDERSTANDING

1 Write the missing words or numbers in these sentences.

a When raising a term or numbers in index form to another power, _____ the indices.

b Any number (except 0) raised to the power 0 is equal to _____.

2 Write the missing numbers in these tables.

a

Index form	2^6	2^5	2^4	2^3	2^2	2^1	2^0
Basic numeral	64	32					

b

Index form	4^5	4^4	4^3	4^2	4^1	4^0
Basic numeral	1024	256				

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6C

UNDERSTANDING

3 Copy and complete this working.

a $(4^2)^3 = (4 \times \square) \times (4 \times \square) \times (4 \times \square)$
$= 4^{\square}$

b $(12^3)^3 = (12 \times \square \times \square) \times (12 \times \square \times \square) \times (12 \times \square \times \square)$
$= 12^{\square}$

c $(x^4)^2 = (x \times \square \times \square \times \square) \times (x \times \square \times \square \times \square)$
$= x^{\square}$

d $(a^2)^5 = (a \times \square) \times (a \times \square) \times (a \times \square) \times (a \times \square) \times (a \times \square)$
$= a^{\square}$

4–7(½) 4–8(½) 4–8(½)

FLUENCY

Example 9

4 Apply index law 3 to simplify each of the following. Leave your answers in index form.

a $(y^6)^2$	**b** $(m^3)^6$	**c** $(x^2)^5$	**d** $(b^3)^4$
e $(3^2)^3$	**f** $(4^3)^5$	**g** $(3^5)^6$	**h** $(7^5)^2$
i $5(m^8)^2$	**j** $4(q^7)^4$	**k** $-3(c^2)^5$	**l** $2(f^4)^6$

Example 10

5 Evaluate each of the following.

a 5^0	**b** 9^0	**c** $(-6)^0$	**d** $(-3)^0$
e $-(4^0)$	**f** $\left(\frac{3}{4}\right)^0$	**g** $\left(-\frac{1}{7}\right)^0$	**h** $(4y)^0$
i $5m^0$	**j** $-3p^0$	**k** $6x^0 - 2x^0$	**l** $-5n^0 - (8n)^0$
m $(3x^4)^0$	**n** $1^0 + 2^0 + 3^0$	**o** $(1 + 2 + 3)^0$	**p** $100^0 - a^0$

Example 11a

6 Simplify each of the following by combining various index laws.

a $4 \times (4^3)^2$	**b** $(3^4)^2 \times 3$	**c** $x \times (x^0)^5$
d $y^5 \times (y^2)^4$	**e** $b^5 \times (b^3)^3$	**f** $(a^2)^3 \times a^4$
g $(d^3)^4 \times (d^2)^6$	**h** $(y^2)^6 \times (y)^4$	**i** $z^4 \times (z^3)^2 \times (z^5)^3$
j $a^3f \times (a^4)^2 \times (f^4)^3$	**k** $x^2y \times (x^3)^4 \times (y^2)^2$	**l** $(s^2)^3 \times 5(r^0)^3 \times rs^2$

Example 11b

7 Simplify each of the following.

a $7^8 \div (7^3)^2$	**b** $(4^2)^3 \div 4^5$	**c** $(3^6)^3 \div (3^5)^2$
d $(m^3)^6 \div (m^2)^9$	**e** $(y^5)^3 \div (y^6)^2$	**f** $(h^{11})^2 \div (h^5)^4$
g $\frac{(b^2)^5}{b^4}$	**h** $\frac{(x^4)^3}{x^7}$	**i** $\frac{(y^3)^3}{y^3}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

6C

FLUENCY

Example 11c

8 Simplify each of the following using various index laws.

a $\dfrac{3x^4 \times 6x^3}{9x^{12}}$ **b** $\dfrac{5x^5 \times 4x^2}{2x^{10}}$ **c** $\dfrac{24(x^4)^4}{8(x^4)^2}$

d $\dfrac{4(d^4)^3 \times (e^4)^2}{8(d^2)^5 \times e^7}$ **e** $\dfrac{6(m^3)^2(n^5)^3}{15(m^5)^0(n^2)^7}$ **f** $\dfrac{2(a^3)^4(b^2)^6}{16(a)^0(b^6)^2}$

PROBLEM-SOLVING

9 | 9, 10 | 10, 11

9 There are 100 rabbits on Mt Burrow at the start of the year 2000. The rule for the number of rabbits N after t years (from the start of the year 2000) is $N = 100 \times 2^t$.

a Find the number of rabbits at:

i $t = 2$ **ii** $t = 6$ **iii** $t = 0$

b Find the number of rabbits at the beginning of:

i 2003 **ii** 2007 **iii** 2010

c How many years will it take for the population to first rise to more than 500 000? Give a whole number of years.

10 If m and n are positive integers, in how many ways can $(a^m)^n = a^{16}$?

11 Evaluate these without using a calculator.

a $(2^4)^8 \div 2^{30}$ **b** $(10^3)^7 \div 10^{18}$ **c** $(x^4)^9 \div x^{36}$

d $((-1)^{11})^2 \times ((-1)^2)^{11}$ **e** $-2((-2)^3)^3 \div (-2)^8$ **f** $\dfrac{(a^2)^3}{(b^4)^7} \times \dfrac{(b^7)^4}{(a^3)^2}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6C

12 | 12, 13 | 13, 14

REASONING

12 Explain the error made in the following problems then give the correct answer.

a $(a^4)^5 = a^9$ **b** $3(x^3)^2 = 9x^6$ **c** $(2x)^0 = 2$

13 a Simplify these by firstly working with the inner brackets. Leave your answer in index form.

i $(2^3)^4)^2$ **ii** $(((-2)^2)^5)^3$ **iii** $((x^6)^2)^7$ **iv** $(((a^2)^4)^3)^2$

b Simplify these expressions.

i $((2^a)^b)^c$ **ii** $((a^m)^n)^p$ **iii** $(x^{2y})^{3z}$

14 a Show that $\frac{5a^2b}{2ab^2} \div \frac{10a^4b^7}{4a^3b^8}$ is equal to 1.

b Make up your own expression like the one above where the answer is equal to 1. Test it on a friend.

Changing the base

— | — | 15

ENRICHMENT

15 The base of a number in index form can be changed using index law number 3.

For example: $8^2 = (2^3)^2$

$= 2^6$

Change the base numbers and simplify the following using the smallest possible base integer.

a 8^4 **b** 32^3 **c** 9^3

d 81^5 **e** 25^5 **f** 243^{10}

g 256^9 **h** 2401^{20} **i** $100\,000^{10}$

A research scientist in a microbiology laboratory would use indices to express the numbers of microbes being studied.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6D Index laws 4 and 5

It is common to find expressions such as $(2x)^3$ and $\left(\frac{x}{3}\right)^4$ in mathematical problems. These differ from most of the expressions in previous sections as they contain more than one single number or variable, connected by multiplication or division, raised to a power. These expressions can also be simplified using two index laws which effectively remove the brackets.

Consider $(a \times b)^m$:

Using expanded form:

$$(a \times b)^m = \overbrace{ab \times ab \times ab \times \cdots \times ab}^{m \text{ factors of } ab}$$
$$= \overbrace{a \times a \times \cdots \times a}^{m \text{ factors of } a} \times \overbrace{b \times b \times \cdots \times b}^{m \text{ factors of } b}$$
$$= a^m \times b^m$$

So, this becomes a product of m factors of a and m factors of b.

Also,
$$\left(\frac{a}{b}\right)^m = \overbrace{\frac{a}{b} \times \frac{a}{b} \times \frac{a}{b} \times \cdots \times \frac{a}{b}}^{m \text{ factors of } \frac{a}{b}}$$
$$= \frac{\overbrace{a \times a \times a \times \cdots \times a}^{m \text{ factors of } a}}{\underbrace{b \times b \times b \times \cdots \times b}_{m \text{ factors of } b}}$$
$$= \frac{a^m}{b^m}$$

So to remove the brackets, we can raise each of a and b to the power m.

Let's start: Discovering laws 4 and 5

Use the expanded form of $(2x)^3$ and $\left(\frac{x}{3}\right)^4$ to help simplify the expressions.

$$(2x)^3 = 2x \times \square \times \square$$
$$= 2 \times 2 \times 2 \times \square \times \square \times \square$$
$$= 2^{\square} \times \square^{\square}$$

$$\left(\frac{x}{3}\right)^4 = \frac{x}{3} \times \square \times \square \times \square$$
$$= \frac{x \times \square \times \square \times \square}{3 \times \square \times \square \times \square}$$
$$= \frac{\square^{\square}}{\square^{\square}}$$

- Repeat these steps to also simplify these expressions $(3y)^4$ and $\left(\frac{x}{2}\right)^5$.
- What do you notice about the given expressions and the answer in each case? Can you express this as a rule or law in words?

Key ideas

- **Index law 4**: $(a \times b)^m = (ab)^m = a^m b^m$
  - When multiplying two or more numbers raised to the power of m, raise each number in the brackets to the power of m. For example: $(2x)^2 = 2^2 x^2 = 4x^2$.
- **Index law 5**: $\left(\frac{a}{b}\right)^m = \frac{a^m}{b^m}$ and $b \neq 0$
  - When dividing two numbers raised to the power of m, raise each number in the brackets to the power of m. For example: $\left(\frac{y}{3}\right)^3 = \frac{y^3}{3^3} = \frac{y^3}{27}$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Using index law 4

Expand each of the following using the fourth index law.

a $(5b)^3$ **b** $(-2x^3y)^4$ **c** $4(c^2d^3)^5$

SOLUTION	EXPLANATION
a $(5b)^3 = 5^3b^3$ $= 125b^3$	Raise each numeral and pronumeral in the brackets to the power of 3. Evaluate $5^3 = 5 \times 5 \times 5$.
b $(-2x^3y)^4 = (-2)^4(x^3)^4y^4$ $= 16x^{12}y^4$	Raise each value in the brackets to the power of 4. Evaluate $(-2)^4$ and simplify using law 3.
c $4(c^2d^3)^5 = 4(c^2)^5(d^3)^5$ $= 4c^{10}d^{15}$	Raise each value in the brackets to the power of 5. Note that the coefficient (4) is not raised to the power of 5. Simplify using index laws.

Example 13 Using index law 5

Apply the fifth index law to the following.

a $\left(\frac{6}{b}\right)^3$ **b** $\left(\frac{-2a^2}{3bc^3}\right)^4$ **c** $\left(\frac{x^2y^3}{c}\right)^3 \times \left(\frac{xc}{y}\right)^4$

SOLUTION	EXPLANATION
a $\left(\frac{6}{b}\right)^3 = \frac{6^3}{b^3}$ $= \frac{216}{b^3}$	Raise each value in the brackets to the power of 3 and evaluate 6^3.
b $\left(\frac{-2a^2}{3bc^3}\right)^4 = \frac{(-2)^4a^8}{3^4b^4c^{12}}$ $= \frac{16a^8}{81b^4c^{12}}$	Raise each value in the brackets to the power of 4. Recall $(a^2)^4 = a^{2\times4}$ and $(c^3)^4 = c^{3\times4}$ Evaluate $(-2)^4$ and 3^4.
c $\left(\frac{x^2y^3}{c}\right)^3 \times \left(\frac{xc}{y}\right)^4 = \frac{x^6y^9}{c^3} \times \frac{x^4c^4}{y^4}$ $= \frac{x^{10}y^9c^4}{c^3y^4}$ $= x^{10}y^5c$	Raise each value in the brackets to the power. Multiply the numerators using law 1 then divide using law 2.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 6D

1, 2 | 2(½) | —

UNDERSTANDING

1 Copy and complete index laws 4 and 5.

a $(a \times b)^m = a^m \times \square$

b $\left(\frac{a}{b}\right)^m = \frac{a^m}{\square}$

2 Copy and complete this working.

a $(5a)^3 = 5a \times \square \times \square$
$= 5 \times 5 \times 5 \times a \times \square \times \square$
$= 5^3 \times \square$

b $(ab)^4 = ab \times \square \times \square \times \square \times \square$
$= a \times \square \times \square \times \square \times b \times \square \times \square \times \square$
$= a^4 \times \square$

c $\left(\frac{x}{6}\right)^3 = \frac{x}{6} \times \square \times \square$
$= \frac{x \times \square \times \square}{6 \times \square \times \square}$
$= \frac{x^3}{\square}$

d $\left(\frac{a}{b}\right)^5 = \frac{a}{b} \times \square \times \square \times \square \times \square \times \square$
$= \frac{a \times \square \times \square \times \square \times \square \times \square}{b \times \square \times \square \times \square \times \square \times \square}$
$= \frac{a^5}{\square}$

3–5(½) | 3–6(½) | 3–6(½)

FLUENCY

Example 12

3 Expand each of the following using the fourth index law.

a $(2x)^3$ **b** $(5y)^2$ **c** $(4a^2)^3$ **d** $(-3r)^2$

e $-(3b)^4$ **f** $-(7r)^3$ **g** $(-2h^2)^4$ **h** $(5c^2d^3)^4$

i $(2x^3y^2)^5$ **j** $9(p^2q^4)^3$ **k** $2(x^3y)^2$ **l** $(8t^2u^9v^4)^0$

m $(-3w^3y)^3$ **n** $-4(p^4qr)^2$ **o** $(-5s^7t)^2$ **p** $-(-2x^4yz^3)^3$

Example 13a

Example 13b

4 Apply the fifth index law to expand the following.

a $\left(\frac{p}{q}\right)^3$ **b** $\left(\frac{x}{y}\right)^4$ **c** $\left(\frac{4}{y}\right)^3$ **d** $\left(\frac{5}{p^2}\right)^4$

e $\left(\frac{2}{r^3}\right)^2$ **f** $\left(\frac{s^3}{7}\right)^2$ **g** $\left(\frac{2m}{n}\right)^5$ **h** $\left(\frac{2a^2}{3}\right)^3$

i $\left(\frac{3n^3}{2m^4}\right)^3$ **j** $\left(\frac{-2r}{n}\right)^4$ **k** $\left(\frac{-3f}{2^3g^5}\right)^2$ **l** $\left(\frac{5x^4y}{2x^3}\right)^2$

m $\left(\frac{-3x}{2y^3g^5}\right)^2$ **n** $\left(\frac{3km^3}{4n^7}\right)^3$ **o** $-\left(\frac{-5w^4y}{2x^3}\right)^2$ **p** $\left(-\frac{3x^2y^3}{2a^5b^3}\right)^2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6D

FLUENCY

5 Simplify each of the following by applying the various index laws.

a $a(3b)^2$ **b** $a(3b^2)^3$ **c** $-3(2a^3b^4)^2a^2$

d $2(3x^2y^3)^3$ **e** $(-4b^2c^5d)^3$ **f** $a(2a)^3$

g $a(3a^2)^2$ **h** $5a^3(-2a^4b)^3$ **i** $-5(-2m^3pt^2)^5$

j $-(-7d^2f^4g)^2$ **k** $-2(-2^3x^4yz^3)^3$ **l** $-4a^2b^3(-2a^3b^2)^2$

Example 13c

6 Simplify each of the following.

a $((x^2)^3)^4$ **b** $((2x^3)^2)^4$ **c** $(a^3b^2)^3 \times (a^4b)^2$

d $(a^2b)^3 \times (ab^2)^4$ **e** $\dfrac{(2m^3n)^3}{m^4}$ **f** $\dfrac{3(2^2c^4d^5)^3}{(2cd^2)^4}$

g $\left(\dfrac{-3x^2y^0}{5a^5b^3}\right)^3$ **h** $\dfrac{-3(2^4a^4b^3)^3}{(-2^3a^2b)^4}$ **i** $\dfrac{-5(3^5m^3n^2)^2}{(-3^3m^2n)^3}$

j $\left(\dfrac{a^3b}{c}\right)^3 \times \left(\dfrac{ac^4}{b}\right)^2$ **k** $\left(\dfrac{x^2z}{y}\right)^4 \times \left(\dfrac{xy^2}{z}\right)^3$ **l** $\left(\dfrac{r^3s}{t}\right)^2 \div \left(\dfrac{s}{rt^4}\right)^3$

7 | 7, 8(½) | 7, 8

PROBLEM-SOLVING

7 The rule for the number of seeds germinating in a glass house over a two-week period is given by $N = \left(\dfrac{t}{2}\right)^3$ where N is the number of germinating seeds and t is the number of days.

a Find the number of germinating seeds after:
  i 4 days **ii** 10 days

b Use index law 5 to rewrite the rule without brackets.

c Use your rule in part **b** to find the number of seeds germinating after:
  i 6 days **ii** 4 days

d Find the number of days required to germinate:
  i 64 seeds **ii** 1 seed

8 Find the value of a that makes these equations true, given $a > 0$.

a $\left(\dfrac{a}{3}\right)^2 = \dfrac{4}{9}$ **b** $\left(\dfrac{a}{2}\right)^4 = 16$ **c** $(5a)^3 = 1000$

d $(2a)^4 = 256$ **e** $\left(\dfrac{2a}{3}\right)^2 = \dfrac{4}{9}$ **f** $\left(\dfrac{6a}{7}\right)^3 = 1728$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

6D

9 | 9, 10 | 9, 10

REASONING

9 Rather than evaluating $\frac{2^4}{4^4}$ as $\frac{16}{256} = \frac{1}{16}$, it is easier to evaluate $\frac{2^4}{4^4}$ in the following way (below).

a Explain why this method is helpful.

$$\frac{2^4}{4^4} = \left(\frac{2}{4}\right)^4$$
$$= \left(\frac{1}{2}\right)^4$$
$$= \frac{1^4}{2^4}$$
$$= \frac{1}{16}$$

b Use this idea to evaluate these without the use of a calculator.

i $\frac{6^3}{3^3}$ **ii** $\frac{10^4}{5^4}$

iii $\frac{4^4}{12^4}$ **iv** $\frac{3^3}{30^3}$

10 Decide if the following are true or false. Give reasons.

a $(-2x)^2 = -(2x)^2$ **b** $(-3x)^3 = -(3x)^3$

c $\left(\frac{-5}{x}\right)^5 = -\left(\frac{5}{x}\right)^5$ **d** $\left(\frac{-4}{x}\right)^4 = -\left(\frac{4}{x}\right)^4$

False laws

— | — | 11

ENRICHMENT

11 Consider the equation $(a + b)^2 = a^2 + b^2$.

a Using $a = 2$ and $b = 3$, evaluate $(a + b)^2$.

b Using $a = 2$ and $b = 3$, evaluate $a^2 + b^2$.

c Would you say that the equation is true for all values of a and b?

d Now decide if $(a - b)^2 = a^2 - b^2$ for all values of a and b. Give an example to support your answer.

e Decide if these equations are true or false for all values of a and b.

i $(-ab)^2 = a^2b^2$ **ii** $-(ab)^2 = a^2b^2$

iii $\left(\frac{-a}{b}\right)^3 = \frac{-a^3}{b^3}$ $(b \neq 0)$ **iv** $\left(\frac{-a}{b}\right)^4 = \frac{-a^4}{b^4}$ $(b \neq 0)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6E Negative indices

We know that $2^3 = 8$ and $2^0 = 1$ but what about 2^{-1} or 2^{-6}? Such numbers written in index form using negative indices also have meaning in mathematics.

Consider $a^2 \div a^5$.

Method 1: Using law 2

$$\frac{a^2}{a^5} = a^{2-5}$$

$$= a^{-3} \text{ (from index law 2)}$$

Method 2: By cancelling

$$\frac{a^2}{a^5} = \frac{\cancel{a^1} \times \cancel{a^1}}{a \times a \times a \times \cancel{a_1} \times \cancel{a_1}}$$

$$= \frac{1}{a^3}$$

$$\therefore a^{-3} = \frac{1}{a^3}$$

Also, using index law 1 we can write:

$$a^m \times a^{-m} = a^{m+(-m)}$$

$$= a^0$$

$$= 1$$

So dividing by a^m we have $a^{-m} = \frac{1}{a^m}$ or dividing by a^{-m} we have $a^m = \frac{1}{a^{-m}}$.

Let's start: Continuing the pattern

Explore the use of negative indices by completing this table.

Index form	2^4	2^3	2^2	2^1	2^0	2^{-1}	2^{-2}	2^{-3}
Whole number or fraction	16	8					$\frac{1}{4} = \frac{1}{2^2}$	

÷2 ÷2 ÷2

- What do you notice about the numbers with negative indices in the top row in comparison to the fractions in the second row?
- Can you describe this connection formally in words?
- What might be another way of writing 2^{-7} or 5^{-4}?

Key ideas

■ $a^{-m} = \frac{1}{a^m}$ and $a^m = \frac{1}{a^{-m}}$

a raised to the power $-m$ is equal to the reciprocal of a raised to the power m. $(a \neq 0)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 14 Writing expressions using positive indices

Express each of the following with positive indices only.

a x^{-2} **b** $3a^{-2}b^4$

SOLUTION	EXPLANATION
a $x^{-2} = \frac{1}{x^2}$	$a^{-m} = \frac{1}{a^m}$.
b $3a^{-2}b^4 = \frac{3}{1} \times \frac{1}{a^2} \times \frac{b^4}{1}$ $= \frac{3b^4}{a^2}$	Rewrite a^{-2} using a positive power and collect numerators and denominators.

Example 15 Using $\frac{1}{a^{-m}} = a^m$

Express each of the following using positive indices only.

a $\frac{1}{c^{-2}}$ **b** $\frac{x^{-3}}{y^{-5}}$ **c** $\frac{5}{x^3y^{-4}}$

SOLUTION	EXPLANATION
a $\frac{1}{c^{-2}} = c^2$	$\frac{1}{a^{-m}} = a^m$.
b $\frac{x^{-3}}{y^{-5}} = x^{-3} \times \frac{1}{y^{-5}}$ $= \frac{1}{x^3} \times \frac{y^5}{1}$ $= \frac{y^5}{x^3}$	Express x^{-3} and $\frac{1}{y^{-5}}$ with positive indices using $a^{-m} = \frac{1}{a^m}$ and $\frac{1}{a^{-m}} = a^m$.
c $\frac{5}{x^3y^{-4}} = \frac{5y^4}{x^3}$	Express $\frac{1}{y^{-4}}$ as a positive power.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 16 Evaluating without a calculator

Express using positive powers only, then evaluate without using a calculator.

a 3^{-4} **b** $\frac{-5}{3^{-2}}$ **c** $\left(\frac{2}{3}\right)^{-4}$

SOLUTION	EXPLANATION
a $3^{-4} = \frac{1}{3^4}$ $= \frac{1}{81}$	Express 3^{-4} as a positive power and evaluate 3^4.
b $\frac{-5}{3^{-2}} = -5 \times \frac{1}{3^{-2}}$ $= -5 \times 3^2$ $= -5 \times 9$ $= -45$	Express $\frac{1}{3^{-2}}$ as a positive power and simplify.
c $\left(\frac{2}{3}\right)^{-4} = \frac{2^{-4}}{3^{-4}}$ $= 2^{-4} \times \frac{1}{3^{-4}}$ $= \frac{1}{2^4} \times 3^4$ $= \frac{3^4}{2^4}$ $= \frac{81}{16}$	Apply the power to each numeral in the brackets using index law 5. Express 2^{-4} and $\frac{1}{3^{-4}}$ with positive indices and evaluate.

Exercise 6E

1, 2a | 2b | —

UNDERSTANDING

1 Write the following using positive indices. For example: $\frac{1}{8} = \frac{1}{2^3}$.

a $\frac{1}{4}$ **b** $\frac{1}{9}$ **c** $\frac{1}{125}$ **d** $\frac{1}{27}$

2 Complete the tables with the missing numbers.

a

Index form	3^4	3^3	3^2	3^1	3^0	3^{-1}	3^{-2}	3^{-3}
Whole number or fraction	81	27					$\frac{1}{9} = \frac{1}{3^2}$	

÷3 ÷3 ÷3

b

Index form	10^4	10^3	10^2	10^1	10^0	10^{-1}	10^{-2}	10^{-3}
Whole number or fraction	10 000							$\frac{1}{1000} = \frac{1}{10^3}$

÷10 ÷10

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

6E

3–5(½) | 3–6(½) | 3–6(½)

FLUENCY

Example 14

3 Express each of the following with positive indices only.

a x^{-1} **b** a^{-4} **c** b^{-6} **d** 5^{-2}

e 4^{-3} **f** 9^{-1} **g** $5x^{-2}$ **h** $4y^{-3}$

i $3m^{-5}$ **j** p^7q^{-2} **k** mn^{-4} **l** x^4y^{-4}

m $2a^{-3}b^{-1}$ **n** $7r^{-2}s^{-3}$ **o** $5^{-1}u^{-8}v^2$ **p** $9^{-1}m^{-3}n^{-5}$

Example 15a

4 Express each of the following using positive indices only.

a $\frac{1}{y^{-1}}$ **b** $\frac{1}{b^{-2}}$ **c** $\frac{1}{m^{-5}}$ **d** $\frac{1}{x^{-4}}$

e $\frac{7}{q^{-1}}$ **f** $\frac{3}{t^{-2}}$ **g** $\frac{5}{h^{-4}}$ **h** $\frac{4}{p^{-4}}$

i $\frac{a}{b^{-2}}$ **j** $\frac{e}{d^{-1}}$ **k** $\frac{2n^2}{m^{-3}}$ **l** $\frac{y^5}{3x^{-2}}$

m $\frac{-3}{7y^{-4}}$ **n** $\frac{-2}{b^{-8}}$ **o** $\frac{-3g}{4h^{-3}}$ **p** $\frac{(-3u)^2}{5t^{-2}}$

Example 15b

5 Express each of the following using positive indices only.

a $\frac{a^{-3}}{b^{-3}}$ **b** $\frac{x^{-2}}{y^{-5}}$ **c** $\frac{g^{-2}}{h^{-3}}$ **d** $\frac{m^{-1}}{n^{-1}}$

e $\frac{5^{-1}}{7^{-3}}$ **f** $\frac{3^{-2}}{4^{-3}}$ **g** $\frac{5^{-2}}{6^{-1}}$ **h** $\frac{4^{-3}}{8^{-2}}$

Example 15c

6 Express each of the following using positive indices only.

a $\frac{7}{x^{-4}y^3}$ **b** $\frac{1}{u^{-3}v^2}$ **c** $\frac{a^{-3}5^{-1}}{y^{-3}}$ **d** $\frac{2a^{-4}}{b^{-5}c^2}$

e $\frac{5a^2c^{-4}}{6b^{-2}d}$ **f** $\frac{5^{-1}h^3k^{-2}}{4^{-1}m^{-2}p}$ **g** $\frac{4t^{-1}u^{-2}}{3^{-1}v^2w^{-6}}$ **h** $\frac{4^{-1}x^2y^{-5}}{4m^{-1}n^{-4}}$

7(½) | 7(½), 8 | 7(½), 8, 9

PROBLEM-SOLVING

Example 16

7 Evaluate without the use of a calculator. *Hint:* write expressions using positive indices.

a 5^{-1} **b** 3^{-2} **c** $(-4)^{-2}$ **d** -5^{-2}

e 4×10^{-2} **f** -5×10^{-3} **g** -3×2^{-2} **h** $8\times(2^2)^{-2}$

i $6^4\times6^{-6}$ **j** $8^{-7}\times(8^2)^3$ **k** $(5^2)^{-1}\times(2^{-2})^{-1}$ **l** $(3^{-2})^2\times(7^{-1})^{-1}$

m $\frac{1}{8^{-1}}$ **n** $\frac{1}{10^{-2}}$ **o** $\frac{-2}{5^{-3}}$ **p** $\frac{2}{2^{-3}}$

q $\frac{-5}{2^{-1}}$ **r** $\frac{2^3}{2^{-3}}$ **s** $\left(\frac{3}{8}\right)^{-2}$ **t** $\left(\frac{-4}{3}\right)^{-3}$

u $\frac{(-5)^2}{2^{-2}}$ **v** $\frac{(3^{-2})^3}{3^{-5}}$ **w** $\frac{(-2^{-3})^{-3}}{(2^{-2})^{-4}}$ **x** $\left(\frac{2^{-4}}{7^{-2}}\right)^{-1}\times\left(\frac{7^{-1}}{2^{-1}}\right)^{-4}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6E

PROBLEM-SOLVING

8 The mass of a small insect is 2^{-9} kg. How many grams is this? Round to two decimal places.

9 Find the value of x in these equations.

a $2^x = \frac{1}{16}$ **b** $5^x = \frac{1}{625}$ **c** $(-3)^x = \frac{1}{81}$

d $(0.5)^x = 2$ **e** $(0.2)^x = 25$ **f** $3(2^{2x}) = 0.75$

	10	10	10, 11

REASONING

10 Describe the error made in these problems then give the correct answer.

a $2x^{-2} = \frac{1}{2x^2}$ **b** $\frac{5}{a^4} = \frac{a^{-4}}{5}$ **c** $\frac{2}{(3b)^{-2}} = \frac{2b^2}{9}$

11 Consider the number $\left(\frac{2}{3}\right)^{-1}$.

a Complete this working: $\left(\frac{2}{3}\right)^{-1} = \frac{1}{\left(\frac{2}{3}\right)} = 1 \div \square = 1 \times \square = \frac{3}{2}$

b Show similar working as in part **a** to simplify these.

i $\left(\frac{5}{4}\right)^{-1}$ **ii** $\left(\frac{2}{7}\right)^{-1}$ **iii** $\left(\frac{x}{3}\right)^{-1}$ **iv** $\left(\frac{a}{b}\right)^{-1}$

c What conclusion can you come to regarding the simplification of fractions raised to the power -1?

d Simplify these fractions.

i $\left(\frac{2}{3}\right)^{-2}$ **ii** $\left(\frac{4}{5}\right)^{-2}$ **iii** $\left(\frac{1}{2}\right)^{-5}$ **iv** $\left(\frac{7}{3}\right)^{-3}$

Exponential equations

	—	—	12

ENRICHMENT

12 To find x in $2^x = 32$ you could use trial and error; however, the following approach is more useful.

$2^x = 32$

$2^x = 2^5$ (express 32 using a matching base)

$\therefore x = 5$

Use this idea to solve for x in these equations.

a $2^x = 16$ **b** $3^x = 81$ **c** $\left(\frac{1}{2}\right)^x = \frac{1}{8}$ **d** $\left(\frac{1}{7}\right)^x = \frac{1}{49}$

e $\left(\frac{2}{3}\right)^x = \frac{16}{81}$ **f** $4^{2x} = 64$ **g** $3^{x+1} = 243$ **h** $2^{3x-1} = 64$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

6A **1** Write each of the following in expanded form and then evaluate where possible.

a a^4 **b** $5(hk)^3$ **c** 2^4 **d** $\left(\frac{-3}{4}\right)^3$

6A **2** Write each of the following in index form.

a $7 \times m \times m \times m \times m$ **b** $\frac{2}{3} \times \frac{2}{3} \times \frac{1}{5} \times \frac{1}{5} \times \frac{1}{5}$ **c** $8h \times e \times 8h \times e \times 8h \times e \times e$

6B **3** Simplify each of the following using the first or second index laws.

a $2^5 \times 2^3$ **b** $a^3 \times a^5 \times a$ **c** $3k^3m \times 4mk^4$

d $5^{10} \div 5^2$ **e** $\frac{6a^8}{3a^2}$ **f** $\frac{8a^{10}m^6}{24a^5m^2}$

6B **4** Simplify each of the following using the first two index laws.

a $x^4 \times x^5 \div x^3$ **b** $\frac{4x^3y^2 \times 6x^2y}{8x^4y^2}$

6C **5** Apply index law 3 to simplify each of the following. Leave your answers in index form.

a $(x^3)^4$ **b** $-4(q^6)^7$

6C **6** Apply the zero power rule to evaluate each of the following.

a 8^0 **b** $(2x)^0$ **c** $7m^0$ **d** $-4n^0 - (5n)^0$

6C **7** Simplify each of the following by applying the various index laws.

a $(a^3)^2 \times (a^2)^4$ **b** $\frac{(m^4)^6}{m^2}$ **c** $\frac{3x^4 \times 12x^2}{9x^6}$ **d** $\frac{8(m^2)^4 5(n^3)^2}{15(m^5)^0 2n^2}$

6D **8** Expand each of the following using the fourth and fifth index laws and simplify.

a $(2b)^3$ **b** $5(h^2j^3k)^3$ **c** $(-3x^4y^2)^3$

d $\left(\frac{4}{c}\right)^3$ **e** $\left(\frac{-2wx^3}{5y^2}\right)^3$ **f** $\left(\frac{a^2b}{c^2}\right)^4 \times \left(\frac{c^5}{b^2}\right)^2$

6E **9** Express each of the following using positive indices only.

a m^{-4} **b** $7x^{-3}y^5$ **c** $\frac{1}{a^{-5}}$

d $\frac{a^{-2}}{c^{-3}}$ **e** $\frac{-13}{m^{-5}}$ **f** $\frac{-5t^{-2}u^3}{3^{-1}v^2w^{-3}}$

6E **10** Express using positive powers only, then evaluate without using a calculator.

a 4^{-2} **b** $\frac{3}{3^{-2}}$ **c** $(-6)^{-2}$ **d** $\left(\frac{3}{2}\right)^{-3}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F Scientific notation

Interactive

Widgets

HOTsheets

Walkthroughs

It is common in the practical world to be working with very large or very small numbers. For example, the number of cubic metres of concrete used to build the Hoover Dam in the United States was 3 400 000 m^3 and the mass of a molecule of water is 0.000000000000000000000299 grams. Such numbers can be written more efficiently using powers of 10 with positive or negative indices. This is called scientific notation or standard form. The number is written using a number between 1 inclusive and 10 and this is multiplied by a power of 10. Such notation is also used to state very large and very small time intervals.

At the time of construction, the Hoover Dam was the largest concrete structure in the world.

Let's start: Building scientific notation

Use the information given to complete the table.

Decimal form	Working	Scientific notation
2 350 000	$2.35 \times 1\,000\,000$	2.35×10^6
502 170		
314 060 000		
0.000298	$2.98 \div 10\,000 = \frac{2.98}{10^4}$	2.98×10^{-4}
0.000004621		
0.003082		

- Discuss how each number using scientific notation is formed.
- When are positive indices used and when are negative indices used?
- Where does the decimal point appear to be placed when using scientific notation?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Numbers written in **scientific notation** are expressed in the form $a \times 10^m$ where $1 \leq a < 10$ or $-10 < a \leq -1$ and m is an integer.
- Large numbers will use positive powers of 10.
  For example: 38 million years = 38 000 000 years
  $= 3.8 \times 10^7$ years
- Small numbers will use negative powers of 10.
  For example: 417 nanoseconds = 0.000000417 seconds
  $= 4.17 \times 10^{-7}$ seconds
- To write numbers using scientific notation, place the decimal point after the first non-zero digit then multiply by a power of 10.
- Examples of units where very large or small numbers may be used:
  - 2178 km = 2 178 000 m = 2.178×10^6 metres
  - 4517 centuries = 451 700 years = 4.517×10^5 years
  - 12 million years = 12 000 000 years = 12×10^6 or 1.2×10^7 years
  - 2320 tonnes = 2320×10^3 kg = 2.32×10^6 kg
  - 27 microns (millionth of a metre) = 0.000027 m = 27×10^{-6} or 2.7×10^{-5} metres
  - 109 milliseconds (thousandths of a second) = 0.109 seconds = 109×10^{-3} or 1.09×10^{-1} seconds
  - 3.8 microseconds (millionth of a second) = 0.0000038 = 3.8×10^{-6} seconds
  - 54 nanoseconds (billionth of a second) = 0.000000054 = 54×10^{-9} or 5.4×10^{-8} seconds

The big bang theory deals with measurements from microscopically small to astronomically large, all expressed conveniently in scientific notation.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 17 Writing numbers using scientific notation

Write the following in scientific notation.

a 4 500 000 **b** 0.0000004

SOLUTION | **EXPLANATION**

a $4\,500\,000 = 4.5 \times 10^6$

Place the decimal point after the first non-zero digit (4) then multiply by 10^6 since the decimal place has been moved 6 places to the left.

b $0.0000004 = 4 \times 10^{-7}$

The first non-zero digit is 4. Multiply by 10^{-7} since the decimal place has been moved 7 places to the right.

Example 18 Writing numbers in decimal form

Express each of the following in decimal form.

a 9.34×10^5 **b** 4.71×10^{-5}

SOLUTION | **EXPLANATION**

a $9.34 \times 10^5 = 934\,000$

Move the decimal point 5 places to the right.

b $4.71 \times 10^{-5} = 0.0000471$

Move the decimal point 5 places to the left and insert zeros where necessary.

Exercise 6F

1–3 | 3 | —

UNDERSTANDING

1 Which of the numbers 1000, 10 000 or 100 000 completes each equation?

a $6.2 \times$ _____ $= 62\,000$ **b** $9.41 \times$ _____ $= 9410$

c $1.03 \times$ _____ $= 103\,000$ **d** $3.2 \div$ _____ $= 0.0032$

e $5.16 \div$ _____ $= 0.0000516$ **f** $1.09 \div$ _____ $= 0.000109$

2 Write the following as powers of 10.

a 100 000 **b** 100 **c** 1 000 000 000

3 If these numbers were written using scientific notation, would positive or negative indices be used?

a 2000 **b** 0.0004 **c** 19 300 **d** 0.00101431

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F

4–8(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 17a

4 Write the following in scientific notation.

a 40 000	**b** 2 300 000 000 000	**c** 16 000 000 000
d –7 200 000	**e** –3500	**f** –8 800 000
g 52 hundreds	**h** 3 million	**i** 21 thousands

Example 17b

5 Write the following in scientific notation.

a 0.000003	**b** 0.0004	**c** –0.00876
d 0.00000000073	**e** –0.00003	**f** 0.000000000125
g –0.00000000809	**h** 0.000000024	**i** 0.0000345

6 Write each of the following numbers in scientific notation.

a 6000	**b** 720 000	**c** 324.5	**d** 7869.03
e 8459.12	**f** 0.2	**g** 0.000328	**h** 0.00987
i –0.00001	**j** –460 100 000	**k** 17 467	**l** –128

Example 18a

7 Express each of the following in decimal form.

a 5.7×10^4	**b** 3.6×10^6	**c** 4.3×10^8
d 3.21×10^7	**e** 4.23×10^5	**f** 9.04×10^{10}
g 1.97×10^8	**h** 7.09×10^2	**i** 6.357×10^5

Example 18b

8 Express each of the following in decimal form.

a 1.2×10^{-4}	**b** 4.6×10^{-6}	**c** 8×10^{-10}
d 3.52×10^{-5}	**e** 3.678×10^{-1}	**f** 1.23×10^{-7}
g 9×10^{-5}	**h** 5×10^{-2}	**i** 4×10^{-1}

9–11(½) | 9–11(½), 12, 13 | 9–11(½), 13, 14

PROBLEM-SOLVING

9 Express each of the following approximate numbers using scientific notation.

a The mass of Earth is 6 000 000 000 000 000 000 000 000 kg.
b The diameter of Earth is 40 000 000 m.
c The diameter of a gold atom is 0.0000000001 m.
d The radius of Earth's orbit around the Sun is 150 000 000 km.
e The universal constant of gravitation is 0.0000000000667 Nm^2/kg^2.
f The half-life of polonium-214 is 0.00015 seconds.
g Uranium-238 has a half-life of 4 500 000 000 years.



Image of gold atoms formed by a very powerful electron microscope.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 Express each of the following in decimal form.

- **a** Neptune is approximately 4.6×10^9 km from Earth.
- **b** A population of bacteria contained 8×10^{12} organisms.
- **c** The Moon is approximately 3.84×10^5 km from Earth.
- **d** A fifty-cent coin is approximately 3.8×10^{-3} m thick.
- **e** The diameter of the nucleus of an atom is approximately 1×10^{-14} m.
- **f** The population of a city is 7.2×10^5.

Earth is about 3.84×10^5 km from the Moon.

11 Write the following using scientific notation in the units given in the brackets.
Recall:

1 second = 1000 milliseconds

1 millisecond = 1000 microseconds

1 microsecond = 1000 nanoseconds

- **a** 3 million years (months)
- **b** 0.03 million years (months)
- **c** 492 milliseconds (seconds)
- **d** 0.38 milliseconds (seconds)
- **e** 2.1 microseconds (seconds)
- **f** 0.052 microseconds (seconds)
- **g** 4 nanoseconds (seconds)
- **h** 139.2 nanoseconds (seconds)
- **i** 39.5 centuries (years)
- **j** 438 decades (years)
- **k** 2.3 hours (milliseconds)
- **l** 5 minutes (nanoseconds)

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F

PROBLEM-SOLVING

12 When Sydney was planning for the 2000 Olympic Games, the Olympic Organising Committee made the following predictions.

- The cost of staging the games would be A$1.7 billion ($1.7 \times 10^9$) (excluding infrastructure). In fact, $140 million extra was spent on staging the games.
- The cost of constructing or upgrading infrastructure would be $807 million.

Give each of the following answers in scientific notation.

a The actual total cost of staging the Olympic Games.

b The total cost of staging the games and constructing or upgrading the infrastructure.

Sydney Olympic Stadium.

13 Two planets are 2.8×10^8 km and 1.9×10^9 km from their closest sun. What is the difference between these two distances in scientific notation?

14 Two particles weigh 2.43×10^{-2} g and 3.04×10^{-3} g. Find the difference in their weight in scientific notation.

15(½) 15(½) 15–16(½)

REASONING

15 The number 47×10^4 is not written using scientific notation since 47 is not a number between 1 and 10. The following shows how to convert to scientific notation.

$$47 \times 10^4 = 4.7 \times 10 \times 10^4$$
$$= 4.7 \times 10^5$$

Write these numbers using scientific notation.

a 32×10^3	**b** 41×10^5	**c** 317×10^2	**d** 5714×10^2
e 0.13×10^5	**f** 0.092×10^3	**g** 0.003×10^8	**h** 0.00046×10^9
i 61×10^{-3}	**j** 424×10^{-2}	**k** 1013×10^{-6}	**l** $490\,000 \times 10^{-1}$
m 0.02×10^{-3}	**n** 0.0004×10^{-2}	**o** 0.00372×10^{-1}	**p** 0.04001×10^{-6}

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F

REASONING

16 Use index law 3: $(a^m)^n = a^{m \times n}$ and index law 5: $(a \times b)^m = a^m \times b^m$ to simplify these numbers. Give your answer in scientific notation.

a $(2 \times 10^2)^3$ **b** $(3 \times 10^4)^2$ **c** $(2.5 \times 10^{-2})^2$ **d** $(1.5 \times 10^{-3})^3$

e $(2 \times 10^{-3})^{-3}$ **f** $(5 \times 10^{-4})^{-2}$ **g** $\left(\frac{1}{3} \times 10^2\right)^{-2}$ **h** $\left(\frac{2}{5} \times 10^4\right)^{-1}$

Scientific notation with index laws — — 17–19

ENRICHMENT

17 Use index laws to simplify these and write using scientific notation.

a $(3 \times 10^2) \times (2 \times 10^4)$ **b** $(4 \times 10^4) \times (2 \times 10^7)$

c $(8 \times 10^6) \div (4 \times 10^2)$ **d** $(9 \times 10^{20}) \div (3 \times 10^{11})$

e $(7 \times 10^2) \times (8 \times 10^2)$ **f** $(1.5 \times 10^3) \times (8 \times 10^4)$

g $(6 \times 10^4) \div (0.5 \times 10^2)$ **h** $(1.8 \times 10^6) \div (0.2 \times 10^3)$

i $(3 \times 10^{-4}) \times (3 \times 10^{-5})$ **j** $(15 \times 10^{-2}) \div (2 \times 10^6)$

k $(4.5 \times 10^{-3}) \div (3 \times 10^2)$ **l** $(8.8 \times 10^{-1}) \div (8.8 \times 10^{-1})$

18 Determine, using index laws, how long it takes for light to travel from the Sun to Earth in seconds given that Earth is 1.5×10^8 km from the Sun and the speed of light is 3×10^5 km/s.

19 Using index laws and the fact that the speed of light is equal to 3×10^5 km/s, determine:

a how far light travels in one nanosecond (1×10^{-9} seconds). Answer in scientific notation in kilometres then convert your answer to centimetres.

b how long light takes to travel 300 kilometres. Answer in seconds.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6G Scientific notation using significant figures

Interactive

Widgets

HOTsheets

Walkthroughs

The number of digits used to record measurements depends on how accurately the measurements can be recorded. The volume of Earth, for example, has been calculated as $1\,083\,210\,000\,000\ km^3$. This appears to show six significant figures and could be written using scientific notation as 1.08321×10^{12}. A more accurate calculation may include more non-zero digits in the last seven places.

The mass of a single oxygen molecule is known to be 0.000000000000000000000000053 g. This shows two significant figures and is written using scientific notation as 5.3×10^{-26}. On many calculators you will notice that very large or very small numbers are automatically converted to scientific notation using a certain number of significant figures. Numbers can also be entered into a calculator using scientific notation.

The accuracy of a measurement of the volume of Earth is reflected in the number of significant figures shown.

Let's start: Significant discussions

Begin a discussion regarding scientific figures by referring to these questions.

- Why is the volume of Earth given as $1\,083\,210\,000\,000\ km^3$ written using seven zeros at the end of the number? Wouldn't the exact mass of Earth include some other digits in these places?
- Why is the mass of an oxygen molecule given as 5.3×10^{-26} written using only two significant digits? Wouldn't the exact mass of a water molecule include more decimal places?

Key ideas

- **Significant figures** are counted from left to right starting at the first non-zero digit. Zeros with no non-zero digit on their right are not counted. For example:
  - 38 041 has five significant figures
  - 0.0016 has two significant figures
  - 3.21×10^4 has three significant figures.
- When writing scientific notation the first significant figure sits to the left of the decimal point.
- Calculators can be used to work with scientific notation.
  - E or EE or EXP are common key names on calculators.
  - Pressing 2.37 EE 5 gives 2.37×10^5.
  - 2.37E5 means 2.37×10^5.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 19 Stating the number of significant figures

State the number of significant figures given in these numbers.

a 451 **b** 0.005012 **c** 3.2×10^7

SOLUTION	EXPLANATION
a 3 significant figures	Starting at the '4' and moving right we count three digits.
b 4 significant figures	Start counting at the first non-zero digit.
c 2 significant figures	With scientific notation the first significant figure is to the left of the decimal point.

Example 20 Writing numbers in scientific notation using significant figures

Write these numbers using scientific notation and three significant figures.

a 2 183 000 **b** 0.0019482

SOLUTION	EXPLANATION
a $2\,183\,000 = 2.18 \times 10^6$ (to 3 sig. fig.)	Put the decimal point after the first non-zero digit. The decimal point has moved 6 places so multiply by 10^6. Round the third significant figure down since the following digit is less than 5.
b $0.0019482 = 1.95 \times 10^{-3}$ (to 3 sig. fig.)	Move the decimal point 3 places to the right and multiply by 10^{-3}. Round the third significant figure up to 5 since the following digit is greater than 4.

Example 21 Using a calculator with scientific notation

Use a calculator to evaluate each of the following, leaving your answers in scientific notation correct to four significant figures.

a $3.67 \times 10^5 \times 23.6 \times 10^4$ **b** $7.6 \times 10^{-3} + \sqrt{2.4 \times 10^{-2}}$

SOLUTION	EXPLANATION
a $3.67 \times 10^5 \times 23.6 \times 10^4$ $= 8.661 \times 10^{10}$ (to 4 sig. fig.)	Use a calculator and locate the button used to enter scientific notation. Write in scientific notation with four significant figures.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $7.6 \times 10^{-3} + \sqrt{2.4 \times 10^{-2}}$
$= 0.1625$
$= 1.625 \times 10^{-1}$ (to 4 sig. fig.)

Use a calculator and locate the button used to enter scientific notation.

Write in scientific notation with a number between 1 and 10.

Exercise 6G

1, 2 | 2(½) | —

UNDERSTANDING

1 Complete the tables, rounding each number to the given number of significant figures.

a 57 263

Significant figures	Rounded number
4	
3	57 300
2	
1	

b 4 170 162

Significant figures	Rounded number
5	
4	
3	4 170 000
2	
1	

c 0.0036612

Significant figures	Rounded number
4	
3	
2	
1	0.004

d 24.8706

Significant figures	Rounded number
5	
4	
3	
2	25
1	

2 Decide if the following numbers are written using scientific notation with three significant figures. Answer as 'yes' or 'no'.

a 4.21×10^{4} **b** 32×10^{-3} **c** 1800×10^{6}
d 0.04×10^{2} **e** 1.89×10^{-10} **f** 9.04×10^{-6}
g 5.56×10^{-14} **h** 0.213×10^{2} **i** 26.1×10^{-2}

3–6(½) | 3–7(½) | 3–7(½)

FLUENCY

Example 19

3 State the number of significant figures given in these numbers.

a 202 **b** 1007 **c** 30101 **d** 19
e 0.0183 **f** 0.2 **g** 0.706 **h** 0.00109
i 4.21×10^{3} **j** 2.905×10^{-2} **k** 1.07×10^{-6} **l** 5.9×10^{5}

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6G

FLUENCY

Example 20

4 Write these numbers using scientific notation and three significant figures.

a 242 300	**b** 171 325	**c** 2829	**d** 3247000
e 0.00034276	**f** 0.006859	**g** 0.01463	**h** 0.001031
i 23.41	**j** 326.042	**k** 19.618	**l** 0.172046

5 Write each number using scientific notation rounding to the number of significant figures given in the brackets.

a 47 760 (3)	**b** 21 610 (2)	**c** 4 833 160 (4)
d 37.16 (2)	**e** 99.502 (3)	**f** 0.014427 (4)
g 0.00201 (1)	**h** 0.08516 (1)	**i** 0.0001010 (1)

Example 21a

6 Use a calculator to evaluate each of the following, leaving your answers in scientific notation correct to four significant figures.

a 4^{-6}	**b** 78^{-3}
c $(-7.3 \times 10^{-4})^{-5}$	**d** $\dfrac{3.185}{7 \times 10^4}$
e $2.13 \times 10^4 \times 9 \times 10^7$	**f** $5.671 \times 10^2 \times 3.518 \times 10^5$
g $9.419 \times 10^5 \times 4.08 \times 10^{-4}$	**h** $2.85 \times 10^{-9} \times 6 \times 10^{-3}$
i $12\,345^2$	**j** 87.14^8
k $\dfrac{1.8 \times 10^{26}}{4.5 \times 10^{22}}$	**l** $\dfrac{-4.7 \times 10^2 \times 6.1 \times 10^7}{3.2 \times 10^6}$

Example 21b

7 Use a calculator to evaluate each of the following, leaving your answers in scientific notation correct to five significant figures.

a $\sqrt{8756}$	**b** $\sqrt{634 \times 7.56 \times 10^7}$
c $8.6 \times 10^5 + \sqrt{2.8 \times 10^{-2}}$	**d** $-8.9 \times 10^{-4} + \sqrt{7.6 \times 10^{-3}}$
e $\dfrac{5.12 \times 10^{21} - 5.23 \times 10^{20}}{2 \times 10^6}$	**f** $\dfrac{8.942 \times 10^{47} - 6.713 \times 10^{44}}{2.5 \times 10^{19}}$
g $\dfrac{2 \times 10^7 + 3 \times 10^8}{5}$	**h** $\dfrac{4 \times 10^8 + 7 \times 10^9}{6}$
i $\dfrac{6.8 \times 10^{-8} + 7.5 \times 10^{27}}{4.1 \times 10^{27}}$	**j** $\dfrac{2.84 \times 10^{-6} - 2.71 \times 10^{-9}}{5.14 \times 10^{-6} + 7 \times 10^{-8}}$

PROBLEM-SOLVING

8, 9 | 9–11 | 10, 11

8 The mass of Earth is approximately 6 000 000 000 000 000 000 000 000 kg. Given that the mass of the Sun is 330 000 times the mass of Earth, find the mass of the Sun. Express your answer in scientific notation correct to three significant figures.

9 The diameter of Earth is approximately 12 756 000 m. If the Sun's diameter is 109 times that of Earth, compute its diameter in kilometres. Express your answer in scientific notation correct to three significant figures.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6G

PROBLEM-SOLVING

10 Using the formula for the volume of a sphere, $V = \frac{4\pi r^3}{3}$, and, assuming Earth to be spherical, calculate the volume of Earth in km^3. Use the data given in Question **9**. Express your answer in scientific notation correct to three significant figures.

11 Write these numbers from largest to smallest.
2.41×10^6, 24.2×10^5, 0.239×10^7, 2421×10^3, 0.02×10^8

REASONING

12 | 12, 13 | 13, 14

12 The following output is common on a number of different calculators and computers. Write down the number that you think they represent.

a 4.26E6 **b** 9.1E – 3 **c** 5.04EXP11
d 1.931EXP – 1 **e** 2.1^{06} **f** 6.14^{-11}

13 Anton writes down $352\,000 \times 250\,000 = 8.8^{10}$. Explain his error.

14 **a** Round these numbers to three significant figures. Retain the use of scientific notation.
i 2.302×10^2 **ii** 4.9045×10^{-2} **iii** 3.996×10^6

b What do you notice about the digit which is the third significant figure?

c Why do you think that it might be important to a scientist to show a significant figure at the end of a number which is a zero?

ENRICHMENT

Combining bacteria | — | — | 15

15 A flask of type A bacteria contains 5.4×10^{12} cells and a flask of type B bacteria contains 4.6×10^8 cells. The two types of bacteria are combined in the same flask.

a How many bacterial cells are there in the flask?

b If type A bacterial cells double every 8 hours and type B bacterial cells triple every 8 hours how many cells are in the flask after:
i one day?
ii a week?
iii 30 days?

Express your answers in scientific notation correct to three significant figures.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

6H Fractional indices and surds EXTENDING

So far we have considered indices including positive and negative integers and zero. Numbers can also be expressed using fractional indices. Two examples are $9^{\frac{1}{2}}$ and $5^{\frac{1}{3}}$.

Using index law 1: $9^{\frac{1}{2}} \times 9^{\frac{1}{2}} = 9^{\frac{1}{2}+\frac{1}{2}} = 9^1 = 9$

Since $\sqrt{9} \times \sqrt{9} = 9$ and $9^{\frac{1}{2}} \times 9^{\frac{1}{2}} = 9$ then $9^{\frac{1}{2}} = \sqrt{9}$.

Similarly, $5^{\frac{1}{3}} \times 5^{\frac{1}{3}} \times 5^{\frac{1}{3}} = 5^{\frac{1}{3}+\frac{1}{3}+\frac{1}{3}} = 5^1 = 5$

Since $\sqrt[3]{5} \times \sqrt[3]{5} \times \sqrt[3]{5} = 5$ and $5^{\frac{1}{3}} \times 5^{\frac{1}{3}} \times 5^{\frac{1}{3}} = 5$ then $5^{\frac{1}{3}} = \sqrt[3]{5}$.

This shows that numbers with fractional powers can be written using root signs. In the example above, $9^{\frac{1}{2}}$ is the square root of 9 ($\sqrt{9}$) and $5^{\frac{1}{3}}$ is the cube root of 5 ($\sqrt[3]{5}$).

You will have noticed that $9^{\frac{1}{2}} = \sqrt{9} = 3 = \frac{3}{1}$ and so $9^{\frac{1}{2}}$ is a rational number (a fraction) but $5^{\frac{1}{3}} = \sqrt[3]{5}$ does not appear to be able to be expressed as a fraction. In fact, $\sqrt[3]{5}$ is irrational and cannot be expressed as a fraction and is called a surd. As a decimal $\sqrt[3]{5} = 1.70997594668\ldots$, which is an infinite, non-recurring decimal with no repeated pattern. This is a characteristic of all surds.

Let's start: A surd or not?

Surds are numbers with a root sign that cannot be expressed as a fraction. As a decimal they are infinite and non-recurring (with no pattern).

Use a calculator to help complete this table then decide if you think the numbers are surds.

Index form	With root sign	Decimal	Surd (Yes or No)
$2^{\frac{1}{2}}$	$\sqrt{2}$		
$4^{\frac{1}{2}}$	$\sqrt{4}$		
$11^{\frac{1}{2}}$			
$36^{\frac{1}{2}}$			
$\left(\frac{1}{9}\right)^{\frac{1}{2}}$			
$(0.1)^{\frac{1}{2}}$			
$3^{\frac{1}{3}}$	$\sqrt[3]{3}$		
$8^{\frac{1}{3}}$	$\sqrt[3]{8}$		
$15^{\frac{1}{3}}$			
$\left(\frac{1}{27}\right)^{\frac{1}{3}}$			
$5^{\frac{1}{4}}$			
$64^{\frac{1}{6}}$			

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Numbers written with **fractional indices** can also be written using a root sign.
  - $a^{\frac{1}{m}} = \sqrt[m]{a}$
  - $\sqrt[2]{a}$ is written $\sqrt{a}$

  For example: $3^{\frac{1}{2}} = \sqrt{3}, 7^{\frac{1}{3}} = \sqrt[3]{7}, 2^{\frac{1}{5}} = \sqrt[5]{2}$
- **Surds** are irrational numbers written with a root sign.
  - Irrational numbers cannot be expressed as a fraction.
  - The decimal expansion is infinite and non-recurring with no pattern.

$\sqrt{2} = 1.41421356237\ldots$
$\sqrt[3]{10} = 2.15443469003\ldots$
$3^{\frac{1}{2}} = 1.73205080757\ldots$

Example 22 Writing numbers using a root sign

Write these numbers using a root sign.

a $6^{\frac{1}{2}}$ b $2^{\frac{1}{5}}$

SOLUTION	EXPLANATION
a $6^{\frac{1}{2}} = \sqrt{6}$	$a^{\frac{1}{m}} = \sqrt[m]{a}$ so $6^{\frac{1}{2}} = \sqrt[2]{6}$ (or $\sqrt{6}$) the square root of 6.
b $2^{\frac{1}{5}} = \sqrt[5]{2}$	$\sqrt[5]{2}$ is called the 5th root of 2.

Example 23 Evaluating numbers with fractional indices

Evaluate:

a $144^{\frac{1}{2}}$ b $27^{\frac{1}{3}}$

SOLUTION	EXPLANATION
a $144^{\frac{1}{2}} = \sqrt{144}$ $= 12$	$a^{\frac{1}{m}} = \sqrt[m]{a}$ where $m = 2$ and the square root of 144 = 12 since $12^2 = 144$.
b $27^{\frac{1}{3}} = \sqrt[3]{27}$ $= 3$	The cube root of 27 is 3 since $3^3 = 3 \times 3 \times 3 = 27$.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 24 Using index laws

Use index laws to simplify these expressions.

a $a^{\frac{1}{2}} \times a^{\frac{3}{2}}$ **b** $\dfrac{x^{\frac{1}{2}}}{x^{\frac{1}{3}}}$ **c** $(y^2)^{\frac{1}{4}}$

SOLUTION	EXPLANATION
a $a^{\frac{1}{2}} \times a^{\frac{3}{2}} = a^{\frac{1}{2}+\frac{3}{2}}$ $= a^{\frac{4}{2}}$ $= a^2$	When multiplying indices with the same base add the powers.
b $\dfrac{x^{\frac{1}{2}}}{x^{\frac{1}{3}}} = x^{\frac{1}{2}-\frac{1}{3}}$ $= x^{\frac{1}{6}}$	When dividing indices with the same base, subtract the powers. $\frac{1}{2}-\frac{1}{3}=\frac{3}{6}-\frac{2}{6}=\frac{1}{6}$.
c $(y^2)^{\frac{1}{4}} = y^{2 \times \frac{1}{4}}$ $= y^{\frac{1}{2}}$	When raising a power to a power, multiply the indices. $2 \times \frac{1}{4}=\frac{2}{4}=\frac{1}{2}$.

Exercise 6H

1–3 | 1 | —

UNDERSTANDING

1 Evaluate these numbers.

a 2^2 and $\sqrt{4}$ **b** 2^3 and $\sqrt[3]{8}$ **c** 3^2 and $\sqrt{9}$
d 3^3 and $\sqrt[3]{27}$ **e** 4^2 and $\sqrt{16}$ **f** 4^3 and $\sqrt[3]{64}$

2 State whether the following are true or false.

a Rational numbers are fractions. **b** A surd is a rational number.
c A surd in decimal form will be infinite and non recurring (with no pattern).
d $\sqrt{3} = 3^{\frac{1}{2}}$ **e** $\sqrt{8} = 8^{\frac{1}{3}}$ **f** $5^{\frac{1}{3}} = \sqrt{5}$ **g** $10^{\frac{1}{6}} = \sqrt[10]{6}$

3 Use a calculator to evaluate these surds and round to four decimal places.

a $7^{\frac{1}{2}}$ (or $\sqrt{7}$) **b** $13^{\frac{1}{2}}$ (or $\sqrt{13}$) **c** $83^{\frac{1}{2}}$ (or $\sqrt{83}$)

4–7(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 22

4 Write these numbers using a root sign.

a $3^{\frac{1}{2}}$ **b** $7^{\frac{1}{2}}$ **c** $5^{\frac{1}{3}}$ **d** $12^{\frac{1}{3}}$
e $31^{\frac{1}{5}}$ **f** $18^{\frac{1}{7}}$ **g** $9^{\frac{1}{9}}$ **h** $3^{\frac{1}{8}}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6H

FLUENCY

5 Write these numbers in index form.

a $\sqrt{8}$ **b** $\sqrt{19}$ **c** $\sqrt[3]{10}$ **d** $\sqrt[3]{31}$

e $\sqrt[4]{5}$ **f** $\sqrt[5]{9}$ **g** $\sqrt[8]{11}$ **h** $\sqrt[11]{20}$

Example 23

6 Without a calculator, evaluate these numbers with fractional indices.

a $25^{\frac{1}{2}}$ **b** $49^{\frac{1}{2}}$ **c** $81^{\frac{1}{2}}$ **d** $169^{\frac{1}{2}}$

e $8^{\frac{1}{3}}$ **f** $64^{\frac{1}{3}}$ **g** $125^{\frac{1}{3}}$ **h** $1000^{\frac{1}{3}}$

i $16^{\frac{1}{4}}$ **j** $81^{\frac{1}{4}}$ **k** $625^{\frac{1}{4}}$ **l** $32^{\frac{1}{5}}$

Example 24

7 Use index laws to simplify these expressions. Leave your answer in index form.

a $a^{\frac{1}{2}} \times a^{\frac{1}{2}}$ **b** $a^{\frac{1}{3}} \times a^{\frac{1}{3}}$ **c** $a^{\frac{2}{3}} \times a^{\frac{4}{3}}$ **d** $a^2 \times a^{\frac{1}{2}}$

e $\dfrac{x^{\frac{2}{3}}}{x^{\frac{1}{3}}}$ **f** $\dfrac{x^{\frac{3}{2}}}{x^{\frac{1}{2}}}$ **g** $\dfrac{x^{\frac{7}{6}}}{x^{\frac{2}{6}}}$ **h** $\dfrac{x^{\frac{4}{3}}}{x^{\frac{1}{3}}}$

i $(y^2)^{\frac{1}{2}}$ **j** $(y^3)^{\frac{2}{3}}$ **k** $(y^{\frac{1}{2}})^3$ **l** $(x^{\frac{1}{2}})^{\frac{1}{2}}$

m $(x^{\frac{2}{3}})^4$ **n** $(a^{\frac{2}{5}})^{\frac{1}{3}}$ **o** $(a^{\frac{3}{4}})^{\frac{1}{2}}$ **p** $(n^{\frac{2}{5}})^{\frac{10}{3}}$

8 Use index laws to simplify these expressions.

a $a \times a^{\frac{1}{3}}$ **b** $a^{\frac{1}{2}} \times a^{\frac{1}{5}}$ **c** $a^{\frac{2}{3}} \times a^{\frac{3}{7}}$ **d** $a^5 \div a^{\frac{7}{3}}$ **e** $b^{\frac{2}{3}} \div b^{\frac{1}{2}}$ **f** $x^{\frac{4}{5}} \div x^{\frac{2}{3}}$

9(½), 11(½) | 9–11(½) | 9–11(½)

PROBLEM-SOLVING

9 Evaluate the following without a calculator. *Hint*: first rewrite each question using positive indices.

a $4^{-\frac{1}{2}}$ **b** $8^{-\frac{1}{3}}$ **c** $32^{-\frac{1}{5}}$ **d** $81^{-\frac{1}{4}}$

e $25^{-\frac{1}{2}}$ **f** $27^{-\frac{1}{3}}$ **g** $1000^{-\frac{1}{3}}$ **h** $256^{-\frac{1}{4}}$

10 Note that $8^{\frac{2}{3}} = (8^{\frac{1}{3}})^2$ using index law 3

$= (\sqrt[3]{8})^2$ since $8^{\frac{1}{3}} = \sqrt[3]{8}$

$= 2^2$ $\sqrt[3]{8} = 2$ since $2^3 = 8$

$= 4$

Use the approach shown in the example above to evaluate these numbers.

a $27^{\frac{2}{3}}$ **b** $64^{\frac{2}{3}}$ **c** $9^{\frac{3}{2}}$ **d** $25^{\frac{3}{2}}$ **e** $16^{\frac{5}{4}}$ **f** $4^{\frac{5}{2}}$ **g** $81^{\frac{3}{2}}$ **h** $125^{\frac{5}{3}}$

11 Find the length of the hypotenuse (c) in these right-angled triangles. Use Pythagoras' theorem ($c^2 = a^2 + b^2$) and write your answer as a surd.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

12 | 12, 13 | 13, 14

6H

REASONING

12 Show working to prove that the answers to all these questions simplify to 1. Remember $a^0 = 1$.

a $a^{\frac{1}{2}} \times a^{-\frac{1}{2}}$ **b** $a^{\frac{2}{3}} \times a^{-\frac{2}{3}}$ **c** $a^{\frac{4}{7}} \times a^{-\frac{4}{7}}$

d $a^{\frac{5}{6}} \div a^{\frac{5}{6}}$ **e** $\left(a^{\frac{1}{2}}\right)^{\frac{1}{2}} \div a^{\frac{1}{4}}$ **f** $a^2 \div (a^3)^{\frac{2}{3}}$

13 A student tries to evaluate $9^{\frac{1}{2}}$ on a calculator and types 9^1/2 and gets 4.5. But you know that $9^{\frac{1}{2}} = \sqrt{9} = 3$. What has the student done wrong? (Note: $\wedge$ on some calculators is x^y.)

14 **a** Evaluate the following.

i $\sqrt{3^2}$ **ii** $\sqrt{5^2}$ **iii** $\sqrt{10^2}$

b Simplify $\sqrt{a^2}$ for $a \geq 0$.

c Use fractional indices to show that $\sqrt{a^2} = a$ if $a \geq 0$.

d Evaluate the following.

i $(\sqrt{4})^2$ **ii** $(\sqrt{9})^2$ **iii** $(\sqrt{36})^2$

e Simplify $(\sqrt{a})^2$.

f Use fractional indices to show that $(\sqrt{a})^2 = a$. Assume $a \geq 0$.

g Simplify:

i $\sqrt[3]{a^3}$ **ii** $\sqrt[5]{a^5}$ **iii** $(\sqrt[3]{a})^3$ **iv** $(\sqrt[6]{a})^6$

Fractions raised to fractions

— | — | 15, 16

ENRICHMENT

15 Note, for example, that $\left(\frac{4}{9}\right)^{\frac{1}{2}} = \sqrt{\frac{4}{9}} = \frac{2}{3}$ since $\frac{2}{3} \times \frac{2}{3} = \frac{4}{9}$. Now evaluate the following.

a $\left(\frac{16}{25}\right)^{\frac{1}{2}}$ **b** $\left(\frac{9}{49}\right)^{\frac{1}{2}}$ **c** $\left(\frac{4}{81}\right)^{\frac{1}{2}}$ **d** $\left(\frac{8}{27}\right)^{\frac{1}{3}}$

e $\left(\frac{64}{125}\right)^{\frac{1}{3}}$ **f** $\left(\frac{16}{81}\right)^{\frac{1}{4}}$ **g** $\left(\frac{256}{625}\right)^{\frac{1}{4}}$ **h** $\left(\frac{1000}{343}\right)^{\frac{1}{3}}$

16 Note that $\left(\frac{4}{9}\right)^{-\frac{1}{2}} = \frac{1}{\left(\frac{4}{9}\right)^{\frac{1}{2}}} = \frac{1}{\sqrt{\frac{4}{9}}} = \frac{1}{\left(\frac{2}{3}\right)} = \frac{3}{2}$. Now evaluate the following.

a $\left(\frac{9}{4}\right)^{-\frac{1}{2}}$ **b** $\left(\frac{49}{144}\right)^{-\frac{1}{2}}$ **c** $\left(\frac{8}{125}\right)^{-\frac{1}{3}}$ **d** $\left(\frac{1296}{625}\right)^{-\frac{1}{4}}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

6I Simple operations with surds EXTENDING

Since surds, such as $\sqrt{2}$ and $\sqrt{7}$, are numbers, they can be added, subtracted, multiplied or divided. Expressions with surds can also be simplified but this depends on the surds themselves and the types of operations that sit between them.

$\sqrt{2}+\sqrt{3}$ cannot be simplified since $\sqrt{2}$ and $\sqrt{3}$ are not 'like' surds. This is like trying to simplify $x+y$. However, $\sqrt{2}+5\sqrt{2}$ simplifies to $6\sqrt{2}$ and this is like simplifying $x+5x=6x$. Subtraction of surds is treated in the same manner.

Products and quotients involving surds can also be simplified as in these examples:

$\sqrt{11}\times\sqrt{2}=\sqrt{22}$ and $\sqrt{30}\div\sqrt{3}=\sqrt{10}$

Let's start: Rules for multiplication and division

Use a calculator to find a decimal approximation for each of the expressions in these pairs.

- $\sqrt{2}\times\sqrt{3}$ and $\sqrt{6}$
- $\sqrt{10}\times\sqrt{5}$ and $\sqrt{50}$

What does this suggest about the simplification of $\sqrt{a}\times\sqrt{b}$?

Repeat the above exploration for these.

- $\sqrt{6}\div\sqrt{2}$ and $\sqrt{\dfrac{6}{2}}$
- $\sqrt{80}\div\sqrt{8}$ and $\sqrt{\dfrac{80}{8}}$

What does this suggest about the simplification of $\sqrt{a}\div\sqrt{b}$?

Key ideas

- **Surds** can be simplified using addition or subtraction if they are **'like' surds**.
  - $2\sqrt{3}+3\sqrt{3}=5\sqrt{3}$
  - $11\sqrt{7}-2\sqrt{7}=9\sqrt{7}$
  - $\sqrt{3}+\sqrt{5}$ cannot be simplified.
- $(\sqrt{a})^2=a$
  For example: $(\sqrt{5})^2=5$
- $\sqrt{a}\times\sqrt{b}=\sqrt{ab}$
  For example: $\sqrt{5}\times\sqrt{3}=\sqrt{5\times3}=\sqrt{15}$
- $\sqrt{a}\div\sqrt{b}=\sqrt{\dfrac{a}{b}}$
  For example: $\sqrt{10}\div\sqrt{5}=\sqrt{\dfrac{10}{5}}=\sqrt{2}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 25 Adding and subtracting surds

Simplify:

a $2\sqrt{5} + 6\sqrt{5}$ **b** $\sqrt{3} - 5\sqrt{3}$

SOLUTION	EXPLANATION
a $2\sqrt{5} + 6\sqrt{5} = 8\sqrt{5}$	This is like simplifying $2x + 6x = 8x$. $2\sqrt{5}$ and $6\sqrt{5}$ contain like surds.
b $\sqrt{3} - 5\sqrt{3} = -4\sqrt{3}$	This is similar to $x - 5x = -4x$ in algebra.

Example 26 Multiplying and dividing surds

Simplify:

a $\sqrt{3} \times \sqrt{10}$ **b** $\sqrt{24} \div \sqrt{8}$

SOLUTION	EXPLANATION
a $\sqrt{3} \times \sqrt{10} = \sqrt{3 \times 10}$ $= \sqrt{30}$	Use $\sqrt{a} \times \sqrt{b} = \sqrt{ab}$
b $\sqrt{24} \div \sqrt{8} = \sqrt{\frac{24}{8}}$ $= \sqrt{3}$	Use $\sqrt{a} \div \sqrt{b} = \sqrt{\frac{a}{b}}$

Exercise 6I

1, 2 | 2(½) | —

UNDERSTANDING

1 Decide if the following pairs of numbers contain 'like' surds.

a $3\sqrt{2}$, $4\sqrt{2}$ **b** $5\sqrt{3}$, $2\sqrt{3}$ **c** $4\sqrt{2}$, $5\sqrt{7}$ **d** $\sqrt{3}$, $2\sqrt{5}$

e $6\sqrt{6}$, $3\sqrt{3}$ **f** $\sqrt{8}$, $3\sqrt{8}$ **g** $19\sqrt{2}$, $-\sqrt{2}$ **h** $-3\sqrt{6}$, $3\sqrt{5}$

2 **a** Use a calculator to find a decimal approximation for both $\sqrt{5} \times \sqrt{2}$ and $\sqrt{10}$. What do you notice?

b Use a calculator to find a decimal approximation for both $\sqrt{7} \times \sqrt{3}$ and $\sqrt{21}$. What do you notice?

c Use a calculator to find a decimal approximation for both $\sqrt{15} \div \sqrt{5}$ and $\sqrt{3}$. What do you notice?

d Use a calculator to find a decimal approximation for both $\sqrt{60} \div \sqrt{10}$ and $\sqrt{6}$. What do you notice?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6I

3–4(½) | 3–4(½) | 3–4(½)

FLUENCY

Example 25

3 Simplify by collecting like surds.

a $3\sqrt{7}+5\sqrt{7}$ **b** $2\sqrt{11}+6\sqrt{11}$ **c** $\sqrt{5}+8\sqrt{5}$

d $3\sqrt{6}+\sqrt{6}$ **e** $3\sqrt{3}+2\sqrt{5}+4\sqrt{3}$ **f** $5\sqrt{7}+3\sqrt{5}+4\sqrt{7}$

g $3\sqrt{5}-8\sqrt{5}$ **h** $6\sqrt{7}-10\sqrt{7}$ **i** $3\sqrt{7}-2\sqrt{7}+4\sqrt{7}$

j $5\sqrt{14}+\sqrt{14}-7\sqrt{14}$ **k** $3\sqrt{2}-\sqrt{5}+4\sqrt{2}$ **l** $6\sqrt{3}+2\sqrt{7}-3\sqrt{3}$

Example 26

4 Simplify:

a $\sqrt{5}\times\sqrt{6}$ **b** $\sqrt{3}\times\sqrt{7}$ **c** $\sqrt{10}\times\sqrt{7}$

d $\sqrt{8}\times\sqrt{2}$ **e** $\sqrt{12}\times\sqrt{3}$ **f** $\sqrt{2}\times\sqrt{11}$

g $\sqrt{3}\times\sqrt{3}$ **h** $\sqrt{12}\times\sqrt{12}$ **i** $\sqrt{36}\div\sqrt{12}$

j $\sqrt{20}\div\sqrt{2}$ **k** $\sqrt{42}\div\sqrt{6}$ **l** $\sqrt{60}\div\sqrt{20}$

m $\sqrt{45}\div\sqrt{5}$ **n** $\sqrt{32}\div\sqrt{2}$ **o** $\sqrt{49}\div\sqrt{7}$

5–6(½) | 5–6(½) | 5–7(½)

PROBLEM-SOLVING

5 Simplify:

a $2-\sqrt{3}+6-2\sqrt{3}$ **b** $\sqrt{2}-\sqrt{3}+5\sqrt{2}$ **c** $7\sqrt{5}-\sqrt{2}+1+\sqrt{2}$

d $\frac{\sqrt{2}}{3}+\frac{\sqrt{2}}{2}$ **e** $\frac{\sqrt{7}}{2}+\frac{\sqrt{7}}{5}$ **f** $\frac{2\sqrt{6}}{7}-\frac{\sqrt{6}}{2}$

g $\sqrt{10}-\frac{\sqrt{10}}{3}$ **h** $5-\frac{2\sqrt{3}}{3}+\sqrt{3}$ **i** $\frac{2\sqrt{8}}{7}-\frac{5\sqrt{8}}{8}$

6 Note, for example, that $2\sqrt{3}\times5\sqrt{2}=2\times5\times\sqrt{3}\times\sqrt{2}$

$=10\sqrt{6}$

Now simplify the following.

a $5\sqrt{2}\times3\sqrt{3}$ **b** $3\sqrt{7}\times2\sqrt{3}$

c $4\sqrt{5}\times2\sqrt{6}$ **d** $2\sqrt{6}\times5\sqrt{3}$

e $10\sqrt{6}\div5\sqrt{2}$ **f** $18\sqrt{12}\div6\sqrt{2}$

g $20\sqrt{28}\div5\sqrt{2}$ **h** $6\sqrt{14}\div12\sqrt{7}$

7 Expand and simplify.

a $2\sqrt{3}(3\sqrt{5}+1)$ **b** $\sqrt{5}(\sqrt{2}+\sqrt{3})$

c $5\sqrt{6}(\sqrt{2}+3\sqrt{5})$ **d** $7\sqrt{10}(2\sqrt{3}-\sqrt{10})$

e $\sqrt{13}(\sqrt{13}-2\sqrt{3})$ **f** $\sqrt{5}(\sqrt{7}-2\sqrt{5})$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6I

8(½) 8(½) 8–9(½)

REASONING

8 Using $\sqrt{ab} = \sqrt{a} \times \sqrt{b}$, the surd $\sqrt{18}$ can be simplified as shown.

$$\begin{aligned}\sqrt{18} &= \sqrt{9 \times 2} \\ &= \sqrt{9} \times \sqrt{2} \\ &= 3\sqrt{2}\end{aligned}$$

This simplification is possible because 18 has a factor that is a perfect square (9). Use this technique to simplify these surds.

a $\sqrt{8}$ **b** $\sqrt{12}$ **c** $\sqrt{27}$ **d** $\sqrt{45}$

e $\sqrt{75}$ **f** $\sqrt{200}$ **g** $\sqrt{60}$ **h** $\sqrt{72}$

9 Building on the idea discussed in Question **8**, expressions like $\sqrt{8} - \sqrt{2}$ can be simplified as shown:

$$\begin{aligned}\sqrt{8} - \sqrt{2} &= \sqrt{4 \times 2} - \sqrt{2} \\ &= 2\sqrt{2} - \sqrt{2} \\ &= \sqrt{2}\end{aligned}$$

Now simplify these expressions.

a $\sqrt{8} + 3\sqrt{2}$ **b** $3\sqrt{2} - \sqrt{8}$ **c** $\sqrt{18} + \sqrt{2}$ **d** $5\sqrt{3} - 2\sqrt{12}$

e $4\sqrt{8} - 2\sqrt{2}$ **f** $\sqrt{27} + 2\sqrt{3}$ **g** $3\sqrt{45} - 7\sqrt{5}$ **h** $6\sqrt{12} - 8\sqrt{3}$

Binomial products

— — 10

ENRICHMENT

10 Simplify the following by using the rule $(a + b)(c + d) = ac + ad + bc + bd$.
Note, $(a + b)^2 = (a + b)(a + b)$.

a $(\sqrt{2} + \sqrt{3})(\sqrt{2} + \sqrt{5})$ **b** $(\sqrt{3} - \sqrt{5})(\sqrt{3} + \sqrt{2})$

c $(2\sqrt{5} - 1)(3\sqrt{2} + 4)$ **d** $(1 - 3\sqrt{7})(2 + 3\sqrt{2})$

e $(2 - \sqrt{3})(2 + \sqrt{3})$ **f** $(\sqrt{5} - 1)(\sqrt{5} + 1)$

g $(3\sqrt{2} + \sqrt{3})(3\sqrt{2} - \sqrt{3})$ **h** $(8\sqrt{2} + \sqrt{5})(8\sqrt{2} - \sqrt{5})$

i $(1 + \sqrt{2})^2$ **j** $(\sqrt{6} - 3)^2$

k $(2\sqrt{3} - 1)^2$ **l** $(\sqrt{2} + 2\sqrt{5})^2$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Cell growth

Many cellular organisms reproduce by a process of subdivision. A single cell, for example, may divide into two every hour as shown at right. After another hour, the single starting cell has become four:





A cell dividing in two.

Dividing into two

A single cell divides into two every hour.

a How many cells will there be after the following number of hours? Explain how you obtained your answers.

i 1 **ii** 2 **iii** 5

b Complete the table showing the number of cells after n hours.

n hours	0	1	2	3	4	5	6
Number of cells, N	1	2	4				
N in index form	2^0	2^1	2^2				

c Write a rule for the number of cells N after n hours.

d Use your rule from part **c** to find the number of cells after:

i 8 hours **ii** 12 hours **iii** 2 days

e Find how long it takes for a single cell to divide into a total of:

i 128 cells **ii** 1024 cells **iii** 65 536 cells

Dividing into three or more

a Complete a table similar to the table in the previous section for a cell that divides into 3 every hour.

b Write a rule for N in terms of n if a cell divides into 3 every hour. Then use the rule to find the number of cells after:

i 2 hours **ii** 4 hours **iii** 8 hours

c Write a rule for N in terms of n if a single cell divides into the following number of cells every hour.

i 4 **ii** 5 **iii** 10

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Cell cycle times

a If a single cell divides into two every 20 minutes investigate how many cells there will be after 4 hours.

b If a single cell divides into three every 10 minutes investigate how many cells there will be after 2 hours.

c Use the internet to research the cell cycle time and the types of division for at least two different types of cells. Describe the cells and explain the reproductive process.

Constructing surds

Since surds are not fractions it is difficult to precisely measure a length representing a surd.

Pythagoras' theorem can however be used to construct lengths which represent surds.

Using Pythagoras' theorem

Use Pythagoras' theorem to find the length of the hypotenuse (c) in these triangles.

a



b



c



Constructing surds

Show how you can use a single triangle to construct a hypotenuse with the following length. The lengths of the shorter sides have to be whole numbers.

a $\sqrt{5}$ **b** $\sqrt{13}$ **c** $\sqrt{26}$

Combined triangles

The diagram below shows how you can construct the surd $\sqrt{3}$.



$$c^2 = 1^2 + (\sqrt{2})^2$$
$$= 1 + 2$$
$$= 3$$
$$c = \sqrt{3}$$

a Copy this diagram (right) to find the value of x.



b Show how you can add other triangles to construct a line segment with the following lengths.

i $\sqrt{5}$ **ii** $\sqrt{6}$ **iii** $\sqrt{7}$

c Using compasses, draw exact right-angles and transfer exact lengths to a number line. Mark these exact lengths on a number line.

i $\sqrt{2}$ **ii** $\sqrt{3}$ **iii** $-\sqrt{5}$ **iv** $-\sqrt{7}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Determine the last digit of each of the following without using a calculator.

a 2^{222} **b** 3^{300} **c** 6^{87}

2 Determine the smallest value of n such that:

a $24n$ is a square number

b $750n$ is a square number.

3 Simplify $\left(\frac{32}{243}\right)^{-\frac{2}{5}}$ without a calculator.

4 If $2^x = t$, express the following in terms of t:

a 2^{2x+1} **b** 2^{1-x}

5 A single cell divides in two every 5 minutes and each new cell continues to divide every 5 minutes. How long does it take for the cell population to reach at least 1 million?

6 Find the value of x if $3^{3x-1} = \frac{1}{27}$.

7 **a** Write the following in index form

i $\sqrt{2\sqrt{2}}$ **ii** $\sqrt{2\sqrt{2\sqrt{2}}}$ **iii** $\sqrt{2\sqrt{2\sqrt{2\sqrt{2}}}}$

b What value do your answers to part **a** appear to be approaching?

8 Determine the highest power of 2 that divides exactly into 2 000 000.

9 Simplify these surds.

a $5\sqrt{8} - \sqrt{18}$ **b** $\frac{1}{\sqrt{2}} + \sqrt{2}$ **c** $(\sqrt{2} + 3\sqrt{5})^2 - (\sqrt{2} - 3\sqrt{5})^2$

10 Prove that:

a $\frac{1}{\sqrt{2}} = \frac{\sqrt{2}}{2}$ **b** $\frac{3}{\sqrt{3}} = \sqrt{3}$ **c** $\frac{1}{\sqrt{2}-1} = \sqrt{2}+1$

11 Solve for x. There are two solutions for each.

a $2^{2x} - 3 \times 2^x + 2 = 0$ **b** $3^{2x} - 12 \times 3^x + 27 = 0$

12 Given that $2^4 \times 3^2 \times 5 = 720$ find the smallest whole number x so that $720x$ is a perfect cube.

13 Given that $4^y \times 9^x \times 27 = 4 \times 2^x \times 3^{2y}$ find the values of x and y.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Indices and surds

Index laws 4 and 5

Law 4: $(ab)^m = a^m b^m$

e.g. $(3x^2)^3 = 3^3(x^2)^3$
$= 27x^6$

Law 5: $\left(\frac{a}{b}\right)^m = \frac{a^m}{b^m}$

e.g. $\left(\frac{x}{2}\right)^4 = \frac{x^4}{2^4}$
$= \frac{x^4}{16}$

Zero power

$a^0 = 1$

Any number (except 0) to the power 0 equals 1.

e.g. $3x^0 = 3 \times 1$
$= 3$
$(3x)^0 = 1$

Index law 3

Law 3: $(a^m)^n = a^{mn}$

To expand brackets, multiply indices.

e.g. $(x^2)^5 = x^{2\times 5}$
$= x^{10}$

Negative indices

$a^{-m} = \frac{1}{a^m}$

e.g. $2x^{-3} = \frac{2}{1} \times \frac{1}{x^3}$
$= \frac{2}{x^3}$

$\frac{1}{a^{-m}} = a^m$

e.g. $\frac{1}{(2x)^{-2}} = (2x)^2$
$= 4x^2$

Index form

a^m ← index

base

e.g. $2^3 = 2 \times 2 \times 2$
$3^4 = 3 \times 3 \times 3 \times 3$
$a \times b \times a \times b \times b = a^2b^3$

Index laws 1 and 2

Law 1: $a^m \times a^n = a^{m+n}$

When multiplying terms with the same base, add indices.

e.g. $x^3 \times x^5 = x^{3+5}$
$= x^8$

Law 2: $a^m \div a^n = a^{m-n}$

When dividing terms with the same base, subtract indices.

e.g. $\frac{x^7}{x^4} = x^{7-4}$
$= x^3$

Scientific notation

In scientific notation, very large or very small numbers are written in the form $a \times 10^m$ where $1 \le a < 10$ or $-10 < a \le -1$

Large numbers will use positive powers of 10.

e.g. 2 350 000 kg $= 2.35 \times 10^6$ kg

Small numbers will use negative powers of 10.

e.g. 16 nanoseconds
$= 0.000000016$ s
$= 1.6 \times 10^{-8}$ seconds

Fractional indices (Ext)

$a^{\frac{1}{n}} = \sqrt[n]{a}$

e.g. $a^{\frac{1}{2}} = \sqrt{a}$

$a^{\frac{1}{3}} = \sqrt[3]{a}$

e.g. $25^{\frac{1}{2}} = \sqrt{25} = 5$
since $5^2 = 25$

$8^{\frac{1}{3}} = \sqrt[3]{8} = 2$
since $2^3 = 8$

Operations with surds (Ext)

'Like' surds can be added or subtracted.

$3\sqrt{7}$ and $5\sqrt{7}$ are 'like surds'

e.g. $3\sqrt{7} + 5\sqrt{7} = 8\sqrt{7}$

$\sqrt{a} \times \sqrt{b} = \sqrt{ab}$

e.g. $\sqrt{3} \times \sqrt{10} = \sqrt{3 \times 10} = \sqrt{30}$

$\frac{\sqrt{a}}{\sqrt{b}} = \sqrt{\frac{a}{b}}$

e.g. $\frac{\sqrt{20}}{\sqrt{5}} = \sqrt{\frac{20}{5}}$
$= \sqrt{4} = 2$

Surds (Ext)

A surd is a number written with a root sign which has a decimal expansion that is infinite and non-recurring with no pattern.

e.g. $\sqrt{2} = 1.41421356...$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

6B **1** $3x^7 \times 4x^4$ is equivalent to:

A $12x^7$ **B** $12x^{28}$ **C** $7x^{11}$ **D** $12x^{11}$ **E** $7x^3$

6C **2** $3(2y^2)^0$ simplifies to:

A 6 **B** 3 **C** $6y^2$ **D** $3y$ **E** 12

6D **3** $(2x^2)^3$ expands to:

A $2x^5$ **B** $2x^6$ **C** $6x^6$ **D** $8x^5$ **E** $8x^6$

6B **4** $2x^3y \times \dfrac{x^5y^2}{4x^2y}$ simplifies to:

A $\dfrac{x^6y^2}{2}$ **B** $2x^8y$ **C** $2x^6y^2$ **D** $\dfrac{x^4y^2}{2}$ **E** $8x^6y$

6D **5** $\left(\dfrac{-x^2y}{3z^4}\right)^3$ is equal to:

A $\dfrac{x^6y^3}{3z^{12}}$ **B** $\dfrac{-x^5y^4}{9z^7}$ **C** $\dfrac{-x^6y^3}{27z^{12}}$ **D** $\dfrac{-x^2y^3}{3z^{12}}$ **E** $\dfrac{x^6y^3}{9z^{12}}$

6E **6** $2x^{-3}y^4$ expressed with positive indices is:

A $\dfrac{y^4}{2x^3}$ **B** $\dfrac{2y^4}{x^3}$ **C** $-2x^3y^4$ **D** $\dfrac{2}{x^3y^4}$ **E** $\dfrac{y^4}{8x^3}$

6E **7** $\dfrac{3}{(2x)^{-2}}$ is equivalent to:

A $\dfrac{-3}{(2x)^2}$ **B** $6x^2$ **C** $\dfrac{3x^2}{2}$ **D** $12x^2$ **E** $\dfrac{-3x^2}{4}$

6F **8** The weight of a cargo crate is 2.32×10^4 kg. In expanded form this weight in kilograms is:

A 2 320 000 **B** 232 **C** 23 200 **D** 0.000232 **E** 2320

6G **9** 0.00032761 in scientific notation rounded to three significant figures is:

A 328×10^{-5} **B** 3.27×10^{-4} **C** 3.28×10^4 **D** 3.30×10^4 **E** 3.28×10^{-4}

6H Ext **10** $36^{\frac{1}{2}}$ is equal to:

A 18 **B** 6 **C** 1296 **D** 9 **E** 81

6I Ext **11** The simplified form of $2\sqrt{7} - 3 + 4\sqrt{7}$ is:

A $-2\sqrt{7} - 3$ **B** $3\sqrt{7}$ **C** $6\sqrt{7} - 3$ **D** $\sqrt{7}$ **E** $8\sqrt{7} - 3$

6I Ext **12** $\sqrt{3} \times \sqrt{7}$ is equivalent to:

A $\sqrt{21}$ **B** $\sqrt{10}$ **C** $2\sqrt{10}$ **D** $10\sqrt{21}$ **E** $21\sqrt{10}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

6A **1** Express each of the following in index form.

a $3 \times 3 \times 3 \times 3$ **b** $2 \times x \times x \times x \times x \times y \times y$

c $3 \times a \times a \times a \times \frac{b}{a} \times b$ **d** $\frac{3}{5} \times \frac{3}{5} \times \frac{3}{5} \times \frac{1}{7} \times \frac{1}{7}$

6A **2** Write the following as a product of prime factors in index form.

a 45 **b** 300

6B **3** Simplify using index laws 1 and 2.

a $x^3 \times x^7$ **b** $2a^3b \times 6a^2b^5c$ **c** $3m^2n \times 8m^5n^3 \times \frac{1}{2}m^{-3}$

d $a^{12} \div a^3$ **e** $x^5y^3 \div (x^2y)$ **f** $\frac{5a^6b^3}{10a^8b}$

6C/D **4** Simplify:

a $(m^2)^3$ **b** $(3a^4)^2$ **c** $(-2a^2b)^5$

d $3a^0b$ **e** $2(3m)^0$ **f** $\left(\frac{a^2}{3}\right)^3$

6E **5** Express each of the following with positive indices.

a x^{-3} **b** $4t^{-3}$ **c** $(3t)^{-2}$

d $\frac{2}{3}x^2y^{-3}$ **e** $5\left(\frac{x^2}{y^{-1}}\right)^{-3}$ **f** $\frac{5}{m^{-3}}$

6E **6** Fully simplify each of the following.

a $\frac{5x^8y^{-12}}{x^{10}} \times \frac{(x^2y^5)^2}{10}$ **b** $\left(\frac{(3x)^0}{3x^0y^2}\right)^4 \times \frac{9y^{10}}{x^{-3}}$ **c** $\frac{(4m^2n^3)^2}{2m^5n^4} \div \frac{mn^5}{(m^3n^2)^3}$

6F **7** Arrange the following numbers in ascending order:
$2.35,\ 0.007 \times 10^2,\ 0.0012,\ 3.22 \times 10^{-1},\ 0.4, 35.4 \times 10^{-3}$.

6F **8** Write the following numbers expressed in scientific notation in decimal form.

a 3.24×10^2 **b** 1.725×10^5 **c** 2.753×10^{-1} **d** 1.49×10^{-3}

6G **9** Write each of the following values in scientific notation using three significant figures.

a The population of Australia for the beginning of 2016 was projected to reach 23 783 500

b The area of the USA is 9 629 091 km^2

c The time taken for light to travel 1 metre (in a vacuum) is 0.00000000333564 seconds

d The wavelength of ultraviolet light from a fluorescent lamp is 0.000000294 m.

6F **10** Write each of the following values using scientific notation in the units given in brackets.

a 25 years (hours). Assume 1 year = 365 days.

b 12 milliseconds (seconds)

c 432 nanoseconds (seconds)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

6G

11 Use a calculator to evaluate the following, giving your answer in scientific notation correct to two significant figures.

a $m_s \times m_e$ where m_s (mass of Sun) $= 1.989 \times 10^{30}$ kg and m_e (mass of Earth) $= 5.98 \times 10^{24}$ kg.

b The speed, v, in m/s of an object of mass $m = 2 \times 10^{-3}$ kg and kinetic energy $E = 1.88 \times 10^{-12}$ joules where $v = \sqrt{\frac{2E}{m}}$.

6H Ext

12 Evaluate without using a calculator.

a $\sqrt[4]{16}$ **b** $\sqrt[3]{125}$ **c** $49^{\frac{1}{2}}$

d $81^{\frac{1}{4}}$ **e** $27^{-\frac{1}{3}}$ **f** $121^{-\frac{1}{2}}$

6H Ext

13 Simplify the following expressing all answers in positive index form.

a $(s^6)^{\frac{1}{3}}$ **b** $3x^{\frac{1}{2}} \times 5x^2$ **c** $(3m^{\frac{1}{2}}n^2)^2 \times m^{-\frac{1}{4}}$ **d** $\frac{4}{a^{\frac{1}{3}}} \times \frac{(a^{\frac{1}{2}})^4}{a}$

6I Ext

14 Simplify the following operations with surds.

a $8\sqrt{7} - \sqrt{7} + 2$ **b** $2\sqrt{3} + 5\sqrt{2} - \sqrt{3} + 4\sqrt{2}$ **c** $\sqrt{8} \times \sqrt{8}$

d $\sqrt{5} \times \sqrt{3}$ **e** $2\sqrt{7} \times \sqrt{2}$ **f** $3\sqrt{2} \times 5\sqrt{11}$

g $\sqrt{42} \div \sqrt{7}$ **h** $2\sqrt{75} \div \sqrt{3}$ **i** $\sqrt{50} \div (2\sqrt{10})$

Extended-response questions

1 Simplify each of the following, expressing answers with positive indices, using a combination of index laws.

a $\frac{(4x^2y)^3 \times x^2y}{12(xy^2)^2}$ **b** $\frac{2a^3b^4}{(5a^3)^2} \times \frac{20a}{3b^{-4}}$

c $\frac{(5m^4n^{-3})^2}{m^{-1}n^2} \div \frac{5(m^{-1}n)^{-2}}{mn^{-4}}$ Ext **d** $\frac{(8x^4)^{\frac{1}{3}}}{2(y^3)^0} \times \frac{(3x^{\frac{1}{3}})^2}{3(x^2)^{\frac{1}{2}}}$

2 The law of gravitational force is given by $F = \frac{Gm_1m_2}{d^2}$ where F is the magnitude of the gravitational force (in newtons, N) between two objects of mass m_1 and m_2 (in kilograms) a distance d (metres) apart. G is the universal gravitational constant which is approximately 6.67×10^{-11} Nm^2 kg^{-2}.

a If two objects of masses 2 kg and 4 kg are 3 m apart, calculate the gravitational force F between them. Answer in scientific notation correct to three significant figures.

b The average distance between Earth and the Sun is approximately 149 597 870 700 m.

i Write this distance in scientific notation with three significant figures.

ii Hence, if the mass of Earth is approximately 5.98×10^{24} kg and the mass of the Sun is approximately 1.99×10^{30}, calculate the gravitational force between them in scientific notation to two significant figures.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c The universal gravitational constant, G, is constant throughout the universe. However, acceleration due to gravity (a, units ms^{-2}) varies according to where you are in the solar system. Using the formula $a = \frac{Gm}{r^2}$ and the following table, work out and compare the acceleration due to gravity on Earth and on Mars. Answer to three significant figures.

Planet	Mass, m	Radius, r
Earth	5.98×10^{24} kg	6.375×10^{6} m
Mars	6.42×10^{23} kg	3.37×10^{6} m



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 7

Geometry

What you will learn

7A Angles and triangles (Consolidating)
7B Parallel lines (Consolidating)
7C Quadrilaterals and other polygons
7D Congruent triangles
7E Using congruence in proof (Extending)
7F Enlargement and similar figures
7G Similar triangles
7H Proving and applying similar triangles

Australian curriculum

MEASUREMENT AND GEOMETRY

Geometric reasoning

Use the enlargement transformation to explain similarity and develop the conditions for triangles to be similar

Solve problems using ratio and scale factors in similar figures AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Penrose stairs

Penrose stairs are an example of an impossible object. They are a two-dimensional illusion which appears to show a three-dimensional, never-ending staircase. Such an illusion was featured in the 2010 movie *Inception*. The Penrose stairs are a variation of the Penrose Triangle which shows three right angles, which have been joined in an impossible way to add up to 270 degrees.

The Dutch artist MC Escher (1898–1972) became famous for his fascinating drawings based on such impossible objects. His work has a strong geometrical component and a number of his works such as 'The Waterfall' were based on the Penrose Triangle. They can easily be found on the internet.

As you look at each part of the waterfall you cannot find any errors but when you view it as a whole you see the problem of water travelling up a flat plane yet the water is falling and spinning in the wheel. The towers appear to be the same height yet one is three stories and the other only two.

Escher has drawn a building which is impossible as it displays a different reality if looked at from above or below. You need to look at his work more than once to see the illusion. The two-dimensional representations are impossible to construct in three-dimensional space.

To draw his designs, Escher needed a clear understanding of the properties of both two- and three-dimensional geometrical shapes.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A Angles and triangles CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Geometry is all around us. The properties of the shape of a window, doorway or roofline, depend on their geometry. When lines meet, angles are formed and it is these angles which help define the shape of an object. Fundamental to geometry are the angles formed at a point and the three angles in a triangle. Lines meeting at a point and triangles have special properties and will be revised in this section.

Modern architecture using geometric shapes: the spire of the Arts Centre, Melbourne.

Let's start: Impossible triangles

Triangles are classified either by their side lengths or by their angles.

- First, write the list of three triangles which are classified by their side lengths and the three triangles that are classified by their angles.
- Now try to draw a triangle for each of these descriptions. Then decide which are possible and which are impossible.
  - Acute scalene triangle
  - Right equilateral triangle
  - Right isosceles triangle
  - Obtuse isosceles triangle
  - Obtuse scalene triangle
  - Acute equilateral triangle

Key ideas

■ When two **rays**, **lines** or **line segments** meet at a point, an **angle** is formed.

- This angle is named $\angle A$ or $\angle BAC$ or $\angle CAB$
- The size of this angle in degrees is $a°$.



■ Angle types

- **Acute** between 0° and 90°
- **Obtuse** between 90° and 180°
- **Reflex** between 180° and 360°
- **Right** 90°
- **Straight** 180°
- **Revolution** 360°

■ Angles at a point

- **Complementary** (sum to 90°)



$a + 60 = 90$

- **Supplementary** (sum to 180°)



$a + 41 = 180$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- **Revolution**
  (sum to 360°)



$a + 90 + 115 = 360$

- **Vertically opposite**
  (are equal)



Types of triangles

Acute angled (all angles < 90°)	Right-angled (includes a 90° angle)	Obtuse angled (one angle > 90°)
 Scalene (all sides and angles are different sizes)	Scalene	 Scalene
 Equilateral (all angles 60° and all sides equal)  Isosceles (two angles equal and two sides equal)	 Isosceles	Isosceles

- The sum of the angles in a triangle is 180°.



An **exterior angle** is formed by extending one side of a shape.

- **Exterior angle theorem of a triangle**. The exterior angle of a triangle is equal to the sum of the two opposite interior angles.



$a = b + c$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Finding supplementary and complementary angles

For the angle 47° determine the:

a supplementary angle **b** complementary angle

SOLUTION	EXPLANATION
a $180° - 47° = 133°$	Supplementary angles sum to 180°.
b $90° - 47° = 43°$	Complementary angles sum to 90°.

Example 2 Finding unknown angles in triangles

Name the types of triangles shown here and determine the values of the pronumerals.

a



b



c



SOLUTION	EXPLANATION
a Equilateral triangle $x = 60$	All sides are equal, therefore all angles are equal.
b Obtuse isosceles triangle $2r + 120 = 180$	One angle is more than 90° and two sides are equal.
$2r = 60$	Angles in a triangle add to 180°. Since isosceles, both base angles are $r°$.
$r = 30$	Subtract 120° from both sides and then divide both sides by 2.
c Acute scalene triangle $s + 50 + 60 = 180$	All angles are less than 90° and all sides are of different length.
$s + 110 = 180$	Angles in a triangle add to 180°. Simplify and solve for s.
$s = 70$	

Example 3 Finding exterior angles

Find the value of each pronumeral. Give reasons for your answers.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $y = 90 + 55$ $= 145$	Use the exterior angle theorem which says that the exterior angle is equal to the sum of the two opposite interior angles.
Alternate method:	
Let a be the unknown angle. $a + 90 + 55 = 180$ (Angle sum) $a = 35$ $y + 35 = 180$ $y = 145$	Angles in a triangle sum to 180°.  Angles in a straight line are supplementary (sum to 180°).
b $x + 47 + 47 = 180$ (Angle sum) $x + 94 = 180$ $x = 86$	 Note the isosceles triangle and vertically opposite angles. Angles in a triangle add to 180° and vertically opposite angles are equal. Simplify and solve for x.

Exercise 7A

1, 2, 3–4(½) | 2, 4 | —

UNDERSTANDING

1 Choose a word or number to complete each sentence.

a A 90° angle is called a _____ angle.
b A _____ angle is called a straight angle.
c A 360° angle is called a _____.
d _____ angles are between 90° and 180°.
e _____ angles are between 0° and 90°.
f Reflex angles are between _____ and 360°.
g Complementary angles sum to _____.
h _____ angles sum to 180°.
i The three angles in a triangle sum to _____.
j Vertically opposite angles are _____.

2 Name the type of triangle that has:

a a pair of equal length sides
b one obtuse angle
c all angles 60°
d one pair of equal angles
e all angles acute
f all sides of different length
g one right angle.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A

UNDERSTANDING

3 For each diagram:

i name the angle shown (e.g. $\angle ABC$)

ii state the type of angle given

iii estimate the size of the angle

iv measure the angle using a protractor.

a



b



c



d



e



f

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A

UNDERSTANDING

4 Estimate the size of each of the following angles and use your protractor to determine an accurate measurement.

a



b



c



d



e



f



FLUENCY

5–8(½) 5–9(½) 5–9(½)

Example 1

5 For each of the following angles determine:

i the supplementary angle

ii the complementary angle

a 55°	**b** 31°	**c** 74°	**d** 10°	**e** 89°
f 22°	**g** 38°	**h** 65°	**i** 47°	**j** 77°

6 State whether each of the following pairs of angles is supplementary (S), complementary (C) or neither (N).

a 30°, 60°	**b** 45°, 135°	**c** 100°, 90°	**d** 50°, 40°
e 70°, 110°	**f** 14°, 66°	**g** 137°, 43°	**h** 24°, 56°

7 Find the value of a in these diagrams.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A

FLUENCY

Example 2

8 Name the types of triangles shown here and determine the values of the pronumerals.

a



b



c



d



e



f



g



h



i



Example 3

9 Find the value of each pronumeral.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7A

10, 11 | 10(½), 11, 12(½) | 11–12(½)

PROBLEM-SOLVING

10 Calculate how many degrees the minute hand of a clock rotates in:

a 1 hour
b $\frac{1}{4}$ of an hour
c 10 minutes
d 15 minutes
e 72 minutes
f 1 minute
g 2 hours
h 1 day

11 Find the value of x in these diagrams.

a



b



c



12 Find the acute or obtuse angle between the hour and minute hands at these times. Remember to consider how the hour hand moves between each whole number.

a 3:00 pm
b 5:00 am
c 6:30 pm
d 11:30 pm
e 3:45 am
f 1:20 am
g 4:55 am
h 2:42 am
i 9:27 am

13, 14 | 13, 14 | 14–16

REASONING

13 A tangent to a circle is 90° to its radius. Explain why $x = 330$ in this diagram.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A

REASONING

14 Explain why $\angle OAB$ is 32° in this circle if O is the centre of the circle.



15 In this diagram, $\angle XYZ$ is an exterior angle. *Do not* use the exterior angle theorem in the following.



a If $a = 85$ and $b = 75$, find $\angle XYZ$.

b If $a = 105$ and $b = 60$, find $\angle XYZ$.

c Now using the pronumerals a and b, prove that $\angle XYZ = a° + b°$.

16 Prove that the three exterior angles of a triangle sum to 360°. Use the fact that the three interior angles sum to 180°.

ENRICHMENT

Algebra in geometry — — 17

17 Write an equation for each diagram and solve it to find x.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7B Parallel lines CONSOLIDATING

A line crossing two or more other lines (called a transversal) creates a number of special pairs of angles. If the transversal cuts two parallel lines then these special pairs of angles will be either equal or supplementary.

Double lines on straight roads are parallel.

Let's start: Are they parallel?

Here are three diagrams including a transversal crossing two other lines.

1



2



3



- Decide if each diagram contains a pair of parallel lines. Give reasons for your answer.
- What words do you remember regarding the name given to each pair of angles shown in the diagrams?

Key ideas

■ A **transversal** is a line crossing two or more other lines.

Pair of angles	Non-parallel lines	Parallel lines
Corresponding angles • If lines are parallel corresponding angles are equal		
Alternate angles • If lines are parallel alternate angles are equal		

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

Cointerior angles

- If lines are parallel cointerior angles are supplementary





- If a line AB is parallel to a line CD we write $AB \parallel CD$.
- A parallel line can be added to diagrams to help find other angles.



$\angle AOB = a° + b°$

Example 4 Deciding if lines are parallel

Decide if each diagram contains a pair of parallel lines. Give a reason.

a



b



c



SOLUTION	EXPLANATION
a No. The two cointerior angles are not supplementary.	$60° + 114° = 174° \neq 180°$
b No. The two corresponding angles are not equal.	$79° \neq 82°$
c Yes. The two alternate angles are equal.	If alternate angles are equal then the lines are parallel.

Example 5 Finding angles in parallel lines

Find the value of each of the pronumerals. Give reasons for your answers.

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
a $a = 110$ (vertically opposite angles)	 Vertically opposite angles are equal
$b + 110 = 180$ (cointerior angles in parallel lines) $b = 70$	 Cointerior angles add to 180° in parallel lines
b $b = 68$ (corresponding angles in parallel lines)	 Corresponding angles are equal in parallel lines
$a + 68 = 180$ (supplementary angles) $a = 112$	Supplementary angles add to 180° so $a + b = 180$.

Example 6 Adding a third parallel line

Add a third parallel line to help find $\angle ABC$ in this diagram.



SOLUTION	EXPLANATION
	Add a third parallel line through B to create two pairs of equal alternate angles.
$\angle ABC = 50° + 70°$ $= 120°$	Add 50° and 70° to give the size of $\angle ABC$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Exercise 7B

1, 2 | 2(½) | —

UNDERSTANDING

1 Use the word *equal* or *supplementary* to complete these sentences.

- **a** If two lines are parallel corresponding angles are _____.
- **b** If two lines are parallel alternate angles are _____.
- **c** If two lines are parallel cointerior angles are _____.

2 Find the values of the pronumerals. Give reasons for your answers.

a



b



c



d



e



f



g



h



i



3–4(½) | 3–4(½) | 3–4(½)

FLUENCY

Example 4

3 Decide if each diagram contains a pair of parallel lines. Give a reason.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

g



h



i



Example 5

4 Find the value of each pronumeral. Give reasons for your answers.

a



b



c



d



e



f



The parallel bars is an Olympic event for male gymnasts in Artistic Gymnastics.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

7B

5 | 5–6(½) | 5–6(½), 7

PROBLEM-SOLVING

5 Find the value of each pronumeral.

a



b



c



d



e



f



Example 6

6 Add a third parallel line to help find $\angle ABC$ in these diagrams.

a



b



c



d



e



f



7 Find the value of x.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8 Write an expression (for example, $180° - a°$) for $\angle ABC$ in these diagrams.

a



b



c



d



e



f



9 Give reasons why $AB \parallel DC$ (AB is parallel to DC) in this diagram.



10 The diagram below includes a triangle and a pair of parallel lines.

a Using the parallel lines explain why $a + b + c = 180$.

b Explain why $\angle ACB = c°$.

c Explain why this diagram helps to prove that the angle sum of a triangle is 180°.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

ENRICHMENT

11 Here is a written proof showing that $\angle ABC = a° - b°$.



$\angle BED = 180° - a°$ (Supplementary angles)

$\angle BCA = 180° - a°$ (Alternate angles and $ED \parallel AC$)

$\angle ABC = 180° - b° - (180 - a)°$ (Angle sum of a triangle)

$= 180° - b° - 180° + a°$

$= -b° + a°$

$= a° - b°$

Write proofs similar to the above for each of the following.

a $\angle ABC = a° - c°$



b $\angle ABC = a° + b°$



c $\angle ABC = a° + b°$



d $\angle ABC = 180° + b° - a°$



Sections of train tracks are parallel lines. Train tracks that cross form a range of angles.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7C Quadrilaterals and other polygons

Interactive

Widgets

HOTsheets

Walkthroughs

Closed two-dimensional shapes with straight sides are called polygons and are classified by their number of sides. Quadrilaterals have four sides and are classified further by their special properties.

Mosaics are made of numerous polygons.

Let's start: Draw that shape

Use your knowledge of polygons to draw each of the following shapes. Mark any features, including parallel sides and sides of equal length.

- convex quadrilateral
- non-convex pentagon
- regular hexagon
- square, rectangle, rhombus and parallelogram
- kite and trapezium

This is a non-convex quadrilateral.

Compare the properties of each shape to ensure you have indicated each property on your drawings.

Key ideas

- **Convex polygons** have all interior angles less than 180°. A **non-convex polygon** has at least one interior angle greater than 180°.



Convex quadrilateral



Non-convex hexagon

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **The sum of the interior angles**, $S°$, in a polygon with n sides is given by $S = 180(n-2)$.

Polygon	Number of sides (n)	Angle sum ($S°$)
Triangle	3	180°
Quadrilateral	4	360°
Pentagon	5	540°
Hexagon	6	720°
Heptagon	7	900°
Octagon	8	1080°
Nonagon	9	1260°
Decagon	10	1440°
Undecagon	11	1620°
Dodecagon	12	1800°
n-gon	n	180(n – 2)°

- **Regular polygons** have equal length sides and equal interior angles.
- The sum of all the exterior angles of every polygon is 360°.
  - This example shows a pentagon but the 360° exterior sum is true for all polygons.

$a+b+c+d+e=360$



- **Parallelograms** are **quadrilaterals** with two pairs of parallel sides. They include:
  - Parallelogram: A quadrilateral with two pairs of parallel sides.



  - Rhombus: A parallelogram with all sides equal.



  - Rectangle: A parallelogram with all angles 90°.



  - Square: A rhombus with all angles 90°.



- The kite and trapezium are also special quadrilaterals.
  - Kite



  - Trapezium



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 7 Finding angles in quadrilaterals

Find the value of the pronumeral in each of these quadrilaterals.

a



b



c



SOLUTION

EXPLANATION

a $x + 80 + 100 + 110 = 360$

$x + 290 = 360$

$x = 70$

The angles in a quadrilateral add to 360°.

Simplify and solve for x.

b $2s + 60 + 40 = 360$

$2s + 100 = 360$

$2s = 260$

$s = 130$



The angles in a quadrilateral add to 360° and the opposite angles (s°) are equal in a kite.

Simplify and solve for s.

c $y + 125 = 180$

$y = 55$

Cointerior angles inside parallel lines are supplementary.

Example 8 Finding angles in polygons

For each polygon find the angle sum using $S = 180(n - 2)$ then find the value of any pronumerals. The polygon in part **b** is regular.

a



b



SOLUTION

EXPLANATION

a $n = 6$ and $S = 180(n - 2)$

$= 180(6 - 2)$

$= 720$

The shape is a hexagon with 6 sides so $n = 6$.

$a + 90 + 115 + 100 + 135 + 40 = 720$

$a + 480 = 720$

$a = 240$

The sum of all angles is 720°. Simplify and solve for a.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $n = 8$ and $S = 180(n - 2)$
$= 180(8 - 2)$
$= 1080$
$8b = 1080$
$b = 135$
$a + 135 = 180$
$a = 45$

The regular octagon has 8 sides so use $n = 8$.



Each interior angle is equal so $8b°$ makes up the angle sum.

$a°$ is an exterior angle and $a°$ and $b°$ are supplementary.

Exercise 7C

1–4 | 3, 4 | —

UNDERSTANDING

1 How many sides do these polygons have?

a pentagon
b heptagon
c quadrilateral
d undecagon
e nonagon
f dodecagon

2 Use $S = 180(n - 2)$ to find the angle sum S of these polygons.

a hexagon **b** octagon **c** undecagon

3 Write the word to complete these sentences.

a A parallelogram has two pairs of _____ sides.
b The diagonals in a rhombus intersect at _____ angles.
c A _____ has one pair of parallel sides.
d The diagonals in a rectangle are _____ in length.

4 Name each of these shapes as convex or non convex.

a



b

c



5–7(½) | 5–7(½) | 5–7(½)

FLUENCY

Example 7a

5 Find the values of the pronumerals.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

d



e



f



Example 7b Example 7c **6** Find the value of the pronumerals.

a



b



c



d



e



f



Example 8 **7** For each polygon find the angle sum using $S = 180(n - 2)$ then find the value of any pronumerals. The polygons in parts **e–i** are regular.

a



b



c



d



e



f



g



h



i



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7C

8 | 8, 9, 10(½) | 9, 10

PROBLEM-SOLVING

8 List all the quadrilaterals which have these properties.

a 2 pairs of equal length sides
b All interior angles 90°
c Diagonals of equal length
d Diagonals intersecting at right angles

9 Calculate the number of sides if a polygon has the given angle sum. Suggestion: use the rule $S = 180(n - 2)$.

a 2520°
b 4140°
c 18 000°

10 Find the value of x in these diagrams.

a



b



c



d



e



f



11 | 11, 12 | 12, 13

REASONING

11 Explain why a rectangle, square and rhombus are all parallelograms.

12 For a regular polygon with n sides:

a write the rule for the sum of the interior angles ($S°$)
b write the rule for the size of each interior angle ($I°$)
c write the rule for the size of each exterior angle ($E°$)
d use your rule from part **c** to find the size of the exterior angle of a regular decagon.



13 Recall that a non-convex polygon has at least one reflex interior angle.

a What is the maximum number of interior reflex angles possible for these polygons?
i quadrilateral **ii** pentagon **iii** octagon

b Write an expression for the maximum number of interior reflex angles for a polygon with n sides.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Angle sum proof — — 14

14 Note that if you follow the path around this pentagon starting and finishing at point A (provided you finish by pointing in the same direction as you started) you will have turned a total of 360°.



Complete this proof of the angle sum of a pentagon (540°).

$(180 - a) + (180 - b) + (\quad) + (\quad) + (\quad) =$ _____

(Sum of exterior angles is _____)

$180 + 180 +$ ____ + ____ + ____ $- (a + b +$ ____ + ____ + ____ $) = 360$

____ $- (\quad) = 360$

$(\quad) =$ ____

Now complete a similar proof for the angle sum of these polygons.

a Hexagon **b** Heptagon

(For an additional challenge, try to complete a similar proof for a polygon with n sides.)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

7D Congruent triangles

When two shapes have the same shape and size we say they are congruent. Matching sides will be the same length and matching angles will be the same size. The area of congruent shapes will also be equal. However, not every property of a pair of shapes needs to be known in order to determine their congruence. This is highlighted in the study of congruent triangles where four tests can be used to establish congruence.

The Petronas Twin Towers in Kuala Lumpur look congruent.

Let's start: Constructing congruent triangles

To complete this task you will need a ruler, pencil and protractor. (For accurate constructions you may wish to use compasses.) Divide these constructions up equally amongst the members of the class. Each group is to construct their triangle with the given properties.

1. Triangle ABC with $AB = 8$ cm, $AC = 5$ cm and $BC = 4$ cm
2. Triangle DEF with $DE = 7$ cm, $DF = 6$ cm and $\angle EDF = 40°$
3. Triangle GHI with $GH = 6$ cm, $\angle IGH = 50°$ and $\angle IHG = 50°$
4. Triangle JKL with $\angle JKL = 90°$, $JL = 5$ cm and $KL = 4$ cm
   - Now compare all triangles with the vertices ABC. What do you notice? What does this say about two triangles that have three pairs of equal side lengths?
   - Compare all triangles with the vertices DEF. What do you notice? What does this say about two triangles that have two pairs of equal side lengths and the included angles equal?
   - Compare all triangles with the vertices GHI. What do you notice? What does this say about two triangles that have two equal corresponding angles and one corresponding equal length side?
   - Compare all triangles with the vertices JKL. What do you notice? What does this say about two triangles that have one right angle, the hypotenuse and one other corresponding equal length side?

Key ideas

- **Congruent figures** have the same shape and size.
  - If two figures are congruent, one of them can be transformed by using rotation, reflection and/or translation to match the other figure exactly.



- If triangle ABC (ΔABC) is congruent to triangle DEF (ΔDEF) we write $\Delta ABC \equiv \Delta DEF$. This is called a **congruence statement**.



Corresponding sides	Corresponding angles
$AB = DE$	$\angle A = \angle D$
$BC = EF$	$\angle B = \angle E$
$AC = DF$	$\angle C = \angle F$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Corresponding** sides are opposite equal corresponding angles.
- **Tests for triangle congruence**.
  - Side, Side, Side (SSS)
    Three pairs of corresponding sides are equal.
  - Side, Angle, Side (SAS)
    Two pairs of corresponding sides and the included angle are equal.
  - Angle, Angle, Side (AAS)
    Two angles and any pair of corresponding sides are equal.
  - Right angle, Hypotenuse, Side (RHS)
    A right angle, the hypotenuse and one other pair of corresponding sides are equal.



Example 9 Choosing a congruence test

Which congruence test (SSS, SAS, AAS or RHS) would be used to show that these pairs of triangles are congruent?

a 

b 

c 

d 

SOLUTION	EXPLANATION
a SAS	Two pairs of corresponding sides and the included angle are equal.
b RHS	A right angle, hypotenuse and one pair of corresponding sides are equal.
c AAS	Two pairs of angles and a pair of corresponding sides are equal.
d SSS	Three pairs of corresponding sides are equal.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Finding missing side lengths and angles using congruence

Find the values of the pronumerals in these pairs of congruent triangles.

a



b



SOLUTION

a $x = 5$

$y = 6$

b $a = 25$

$b = 180 - 100 - 25$

$= 55$

EXPLANATION

The side of length x and the side of length 5 are in corresponding positions (opposite the ▫).

The longest side on both triangles must be equal.

The angle marked $a°$ corresponds to the 25° angle in the other triangle.

The angle marked $b°$ corresponds to the missing angle in the first triangle.

The sum of three angles in a triangle is 180°.

Exercise 7D

1–3 | 3(½) | —

UNDERSTANDING

1 Copy and complete the sentences below.

a Congruent figures are exactly the same shape and _____.

b If triangle ABC is congruent to triangle STU then we write $\Delta ABC \equiv$ _____.

c The abbreviated names of the four congruence tests for triangles are SSS, ____, ____ and ____.

2 These two triangles are congruent.

a Name the side on ΔXYZ which corresponds to (matches):

i AB **ii** AC **iii** BC



b Name the angle in ΔABC which corresponds to (matches):

i $\angle X$ **ii** $\angle Y$ **iii** $\angle Z$

3 Write a congruence statement (e.g. $\Delta ABC \equiv \Delta DEF$) if:

a triangle ABC is congruent to triangle FGH

b triangle DEF is congruent to triangle STU

c triangle AMP is congruent to triangle CBD

d triangle BMW is congruent to triangle SLK.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 9

4 Which congruence test (SSS, SAS, AAS or RHS) would be used to show that these pairs of triangles are congruent?

a



b



c



d



e



f



g



h



Example 10

5 Find the values of the pronumerals in these pairs of congruent triangles.

a



b



c



d



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7D

FLUENCY

e



f



g



h



6, 7 6, 7 6–8

PROBLEM-SOLVING

6 For each set of three triangles choose the two which are congruent. Give a reason (SSS, SAS, AAS or RHS) and write a congruence statement (e.g. $\Delta ABC \equiv \Delta FGH$).

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

e







7 Identify all pairs of congruent triangles from those below. Angles with the same mark are equal.



8 Use Pythagoras' theorem to help find the length *BC* in these pairs of congruent triangles.

a





b





Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7D

9, 10 | 9–11 | 10–12

REASONING

9 Are all triangles with three pairs of equal corresponding angles congruent? Explain why or why not.

10 Consider this diagram including two triangles.



- **a** Explain why there are two pairs of equal matching angles.
- **b** Give the reason (SSS, SAS, AAS or RHS) why there are two congruent triangles.

11 *ABCD* is a parallelogram.



- **a** Give the reason why $\Delta ABC \equiv \Delta CDA$.
- **b** What does this say about $\angle B$ and $\angle D$?

12 Consider the diagram below right.



- **a** Explain why there are two pairs of corresponding sides of equal length for the two triangles.
- **b** Give the reason (SSS, SAS, AAS or RHS) why there are two congruent triangles.
- **c** Write a congruence statement.
- **d** Explain why *AC* is perpendicular (90°) to *DB*.

Why not *ASS?*

— | — | 13

ENRICHMENT

13 Angle, Side, Side (ASS) is not a test for congruence of triangles. Complete these tasks to see why.

- **a** Draw two line segments *AB* and *EF* both 5 cm long.
- **b** Draw two rays *AG* and *EH* so that both $\angle A$ and $\angle E$ are 40°.
- **c** Now place a point *C* on ray *AG* so that *BC* = 4 cm.
- **d** Place a point *I* on ray *EH* so that *FI* is 4 cm but place it in a different position so that ΔABC is not congruent to ΔEFI.
- **e** Show how you could use compasses to find the two different places you could put the points *C* or *I* so that *BC* and *FI* are 4 cm.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7E Using congruence in proof

EXTENDING

A mathematical proof is a sequence of correct statements that leads to a result. It should not contain any big 'leaps' and should provide reasons at each step. The proof that two triangles are congruent should list all the corresponding pairs of sides and angles. Showing that two triangles are congruent in more complex problems can then lead to the proof of other geometrical results.

Let's start: Complete the proof

Help complete the proof that $\Delta ABC \equiv \Delta EDC$ for this diagram. Give the missing reasons and congruent triangle in the final statement.



In ΔABC and ΔEDC

$\angle DCE = \angle BCA$ (_____)

$\angle ABC = \angle EDC$ (_____)

$BC = DC$ (given equal sides)

$\therefore \Delta ABC \equiv$ _____ (AAS)



A mathematical proof is like a puzzle in which each step of the solution needs a reason for being correct.

- Prove that two triangles are congruent by listing all the known corresponding equal angles and sides.
  - Give reasons at each step.
  - Conclude by writing a congruence statement and the abbreviated reason (SSS, SAS, AAS or RHS).
  - Vertex labels are usually written in matching order.
- Other geometrical results can be proved by using the properties of congruent triangles.

Key ideas

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Proving that two triangles are congruent

Prove that $\Delta ABC \equiv \Delta ADC$



SOLUTION	EXPLANATION
In ΔABC and ΔADC	
$\angle ABC = \angle ADC = 90°$ (given equal angles) (R)	Both triangles have a right angle.
AC is common (H)	AC is common to both triangles (hypotenuse).
$AB = AD$ (given equal sides) (S)	AB and AD are marked as equal.
$\therefore \Delta ABC \equiv \Delta ADC$ (RHS)	Write the congruence statement and the abbreviated reason. Write the vertex labels in matching order.

Example 12 Proving geometrical results using congruence

a Prove that $\Delta ABC \equiv \Delta EDC$

b Hence prove that $AB \parallel DE$ (AB is parallel to DE)



SOLUTION	EXPLANATION
a In ΔABC and ΔEDC	
$AC = EC$ (given equal sides) (S)	List the given pairs of equal length sides and the vertically opposite angles. The included angle is between the given sides.
$BC = DC$ (given equal sides) (S)	
$\angle ACB = \angle ECD$ (vertically opposite angles) (A)	
$\Delta ABC \equiv \Delta EDC$ (SAS)	
b $\angle BAC = \angle DEC$ (matching angles in congruent triangles)	All matching angles are equal.
$\therefore AB \parallel DE$ (Alternate angles are equal)	If alternate angles are equal then AB and DE must be parallel.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 7E

1–4 | 3, 4 | —

UNDERSTANDING

1 Name the line segment which is common to both triangles in each diagram.

a



b



c



2 Why is ΔOAB an isosceles triangle in this circle? O is the centre of the circle.



3 For this diagram name the angle which is:

a vertically opposite to $\angle ACB$

b alternate to $\angle CDE$

c alternate to $\angle BAC$.



4 For this isosceles triangle, CM is common to ΔAMC and ΔBMC.

a Which congruence test would be used to prove that $\Delta AMC \equiv \Delta BMC$?

b Which angle in ΔBMC corresponds to $\angle AMC$ in ΔAMC?



5(½) | 5(½) | 5(½)

FLUENCY

Example 11

5 Prove that each pair of triangles is congruent. List your reasons and give the abbreviated congruence test.

a



b



c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7E

FLUENCY

d



e



f



g



h



i



j



k



l



6, 7 | 6–9 | 8–11

PROBLEM-SOLVING

Example 12

6 **a** Prove $\Delta ABC \equiv \Delta EDC$.

b Hence, prove $AB \parallel DE$.



7 **a** Prove $\Delta ABE \equiv \Delta CBD$.

b Hence, prove $AE \parallel CD$.



8 **a** Prove $\Delta ABD \equiv \Delta CDB$.

b Hence, prove $AD \parallel BC$.



9 **a** Prove that $\Delta AOB \equiv \Delta DOC$. ($O$ is the centre of the circle)

b Hence, prove that $AB \parallel CD$.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7E

PROBLEM-SOLVING

10 **a** Prove that $\Delta ABD \equiv \Delta CBD$.

b Hence, prove that AC is perpendicular to BD. ($AC \perp BD$)



11 **a** Prove that $\Delta ABD \equiv \Delta CBD$.

b Hence, prove that ΔACD is isosceles.



12	12, 13	12–15

REASONING

12 Use congruence to explain why OC is perpendicular to AB in this diagram.



13 Use congruence to explain why $AD = BC$ and $AB = DC$ in this parallelogram.



14 Use ΔABE and ΔCDE to explain why $AE = CE$ and $BE = DE$ in this parallelogram.



15 Use congruence to show that the diagonals of a rectangle are equal in length.

Extended proofs	—	—	16, 17

ENRICHMENT

16 $ABCD$ is a rhombus. To prove that AC bisects BD at 90°, follow these steps.

a Prove that $\Delta ABE \equiv \Delta CDE$.

b Hence prove that AC bisects BD at 90°.



17 Use congruence to prove that the three angles in an equilateral triangle (given three equal side lengths) are all 60°.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Progress quiz

7A **1** For the angle 53° determine the:

a complementary angle

b supplementary angle.

7A **2** Find the value of x in each of these triangles.

a



b



c



d



e



f



7B **3** Decide if each diagram contains a pair of parallel lines. Give a reason.

a



b



7B/C **4** Find the value of each pronumeral. Giving reasons.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7D **5** Which congruency test could be used to prove these triangles are congruent

a



b



7E **6** Prove that triangle *ABC* is congruent to triangle *ADC*, hence prove that triangle *ABD* is isosceles.



7 Consider the diagram below.



a Prove that triangle *ABE* is congruent to triangle *DBC*.

b If $\angle EAB$ is 62°, what is the size of angle *BDC*?

c If $AE = 7$ cm, find the length of the side *CD*.

d If the area of triangle *ABE* is 21 cm^2, what is the area of triangle *DBC*?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7F Enlargement and similar figures

Interactive

Widgets

HOTsheets

Walkthroughs

Similar figures have the same shape but not necessarily the same size. If two figures are similar then one of them can be enlarged or reduced so that it is identical (congruent) to the other. If a figure is enlarged by a scale factor greater than 1 the image will be larger than the original. If the scale factor is between 0 and 1, the image will be smaller.

Photographic images that are reduced or enlarged to any given size are similar figures.

Let's start: Enlarging a kite

After drawing a kite design, Mandy cuts out a larger shape to make the actual kite. The actual kite shape is to be similar to the design drawing. The 10 cm length on the drawing matches a 25 cm length on the kite.



- How should the interior angles compare between the drawing and the actual kite?
- By how much has the drawing been enlarged i.e. what is the scale factor? Explain your method to calculate the scale factor.
- What length on the kite matches the 15 cm length on the drawing?

Key ideas

- **Enlargement** is a transformation which involves the increase or decrease in size of an object.
  - The 'shape' of the object is unchanged.
  - Enlargement uses a **centre of enlargement** and an **enlargement factor** or **scale factor**.

Centre of enlargement



Scale factor

$$\frac{OA'}{OA} = \frac{OB'}{OB} = \frac{OC'}{OC}$$

- Two figures are **similar** if one can be enlarged to be congruent to the other.
  - Corresponding angles are equal.
  - Pairs of corresponding sides are in the same proportion or ratio.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- The **scale factor** = $\frac{\text{image length}}{\text{original length}}$
  - If the scale factor is between 0 and 1, the image will be smaller than the original.
  - If the scale factor is greater than 1 then the image will be larger than the original.
  - If the scale factor is equals 1 then the image will be congruent to the original.
- The symbols ||| and ~ are used to describe similarity.
  - We can write $ABCD \,|||\, EFGH$ or $ABCD \sim EFGH$
  - The letters are usually written down in matching order.



  - Scale factor = $\frac{EF}{AB} = \frac{10}{5} = 2$ (assuming the two given shapes are similar)

Example 13 Enlarging figures

Copy the given diagram using plenty of space and use the given centre of enlargement (O) and these scale factors to enlarge ΔABC.

a Scale factor $\frac{1}{2}$

b Scale factor 3



SOLUTION

EXPLANATION

a



Connect dashed lines between O and the vertices A, B and C.

Since the scale factor is $\frac{1}{2}$, place A' so that OA' is half of OA.

Repeat for B' and C'. Join vertices A', B' and C'.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

b



Draw dashed lines from O through A, B and C. Place A' so that $OA' = 3OA$. Repeat for B' and C' and form $\Delta A'B'C'$.

Example 14 Using the scale factor

These figures are similar.

a Find a scale factor.

b Find the value of x.

c Find the value of y.



SOLUTION

a Scale factor $= \frac{6}{4} = 1.5$

b $x = 3 \times 1.5$
$= 4.5$

c $y = 7.5 \div 1.5$
$= 5$

EXPLANATION

Choose two corresponding sides and use

$$\text{scale factor} = \frac{\text{image length}}{\text{original length}}$$

Multiply the side lengths on the original by the scale factor to get the length of the corresponding side on the image.

Divide the side lengths on the image by the scale factor to get the length of the corresponding side on the original.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 7F

1–4 | 3, 4 | —

UNDERSTANDING

1 The two figures below are similar.



a Name the angle in the larger figure which corresponds to $\angle A$.
b Name the angle in the smaller figure which corresponds to $\angle I$.
c Name the side in the larger figure which corresponds to BC.
d Name the side in the smaller figure which corresponds to FJ.
e Use FG and AB to find the scale factor.

2 This diagram shows ΔABC enlarged to give the image $\Delta A'B'C'$.



a Measure the lengths OA and OA'. What do you notice?
b Measure the lengths OB and OB'. What do you notice?
c Measure the lengths OC and OC'. What do you notice?
d What is the scale factor?
e Is $A'B'$ twice the length of AB? Measure to check.

3 This diagram shows rectangle $ABCD$ enlarged (in this case reduced) to rectangle $A'B'C'D'$.



a Measure the lengths OA and OA'. What do you notice?
b Measure the lengths OD and OD'. What do you notice?
c What is the scale factor?
d Compare the lengths AD and $A'D'$. Is $A'D'$ one quarter of the length of AD?

4 A square is enlarged by a scale factor of 4.



a Are the internal angles the same for both the original and the image?
b If the side length of the original square was 2 cm, what would be the side length of the image square?
c If the side length of the image square was 100 m, what would be the side length of the original square?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7F

5–7 | 5–7 | 5, 6, 7(½)

FLUENCY

Example 13

5 Copy the given diagram leaving plenty of space around it and use the given centre of enlargement (O) and given scale factors to enlarge ΔABC.



a Scale factor $\frac{1}{3}$ **b** Scale factor 2

6 This diagram includes a square with centre O and vertices $ABCD$.

a Copy the diagram leaving plenty of space around it.



b Enlarge square $ABCD$ by these scale factors and draw the image. Use O as the centre of enlargement.

i $\frac{1}{2}$ **ii** 1.5

Example 14

7 Each of the pairs of figures shown here are similar. For each pair, find the following:

i a scale factor **ii** the value of x **iii** the value of y.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 These diagrams show a shape and its image after enlargement. For each part, find:

i the scale factor

ii the coordinates (x, y) of the centre of enlargement.

a



b



c



d



9 A person 1.8 m tall stands in front of a light that sits on the floor.
The person casts a shadow on the wall behind them.



a How tall will the shadow be if the distance between the wall and the light is:

i 4 m?

ii 10 m?

iii 3 m?

b How tall will the shadow be if the distance between the wall and the person is the following distance?

i 4 m **ii** 5 m

c Find the distance from the wall to the person if the shadow is the following height.

i 7.2 m **ii** 4.5 m

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7F

PROBLEM-SOLVING

10 This truck is 12.7 m long.

- **a** Measure the length of the truck in the photo.
- **b** Measure the height of the truck in the photo.
- **c** Estimate the actual height of the truck.

11, 12 | 11–13 | 12–14

REASONING

11 A figure is enlarged by a scale factor of a where $a > 0$.

- **a** For what values of a will the image be larger than the original figure?
- **b** For what values of a will the image be smaller than the original figure?
- **c** For what value of a will the image be congruent to the original figure?

12 Explain why:

- **a** any two squares are similar
- **b** any two equilateral triangles are similar
- **c** any two rectangles are not necessarily similar
- **d** any two isosceles triangles are not necessarily similar.

13 An object is enlarged by a factor of k. What scale factor should be used to reverse this enlargement?

14 A map has a scale ratio of 1 : 50 000.

- **a** What length on the ground is represented by 2 cm on the map?
- **b** What length on the map is represented by 12 km on the ground?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

The Sierpinski triangle — — 15

7F

ENRICHMENT

15 a Make a large copy of figures 1 to 3 then draw the next two figures in the pattern.



b If the original triangle (figure 1) had side length l, find the side length of the smallest triangle in:

i figure 2

ii figure 3

iii figure 8 (assuming figure 8 is the 8th diagram in the pattern).

c What fraction of the area is shaded in:

i figure 2? **ii** figure 3?

iii figure 6 (assuming figure 6 is the 6th diagram in the pattern)?

d The Sierpinski triangle is one where the process of enlargement and copying is continued forever. What is the area of a Sierpinski triangle?

The Sierpinski triangle shown is a mathematically generated pattern. It is created by repeatedly enlarging triangles by a factor of $\frac{1}{2}$. The steps are listed below.



1. Start with an equilateral triangle as in figure 1.
2. Enlarge the triangle by a factor $\frac{1}{2}$.
3. Arrange three copies of the image as in figure 2.
4. Continue repeating steps 2 and 3 with each triangle.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7G Similar triangles

Interactive

Widgets

HOTsheets

Walkthroughs

Many geometric problems can be solved by using similar triangles. Shadows, for example, can be used to determine the height of a tall mast where the shadows form the base of two similar triangles. To solve such problems firstly involves the identification of two triangles and an explanation as to why they are similar. As with congruence of triangles there is a set of minimum conditions to establish similarity in triangles.

Similar triangles can be used to calculate distances in the natural world.

Let's start: Are they similar?

Each point below describes two triangles. Accurately draw each pair and decide if they are similar (same shape but of different size).

- ΔABC with $AB = 2$ cm, $AC = 3$ cm and $BC = 4$ cm
  ΔDEF with $DE = 4$ cm, $DF = 6$ cm and $EF = 8$ cm
- ΔABC with $AB = 3$ cm, $AC = 4$ cm and $\angle A = 40°$
  ΔDEF with $DE = 6$ cm, $DF = 8$ cm and $\angle D = 50°$
- ΔABC with $\angle A = 30°$ and $\angle B = 70°$
  ΔDEF with $\angle D = 30°$ and $\angle F = 80°$
- ΔABC with $\angle A = 90°$, $AB = 3$ cm and $BC = 5$ cm
  ΔDEF with $\angle D = 90°$, $DE = 6$ cm and $EF = 9$ cm

Which pairs are similar and why? For the pairs that are not similar, what measurements could be changed so that they are similar?

Key ideas

- Two triangles are **similar** if:
  - corresponding angles are equal
  - corresponding sides are in proportion (the same ratio)
- The **similarity statement** for two similar triangles ΔABC and ΔDEF is:
  - $\Delta ABC \text{ III } \Delta DEF$ or
  - $\Delta ABC \sim \Delta DEF$

  Letters are usually written in matching order so AB corresponds to DE etc.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

■ **Tests for similar triangles**. (Not to be confused with the congruence tests for triangles).

- Side, Side, Side (SSS)
  All three pairs of corresponding sides are in the same ratio.

$$\frac{12}{6} = \frac{8}{4} = \frac{14}{7}$$



- Side, Angle, Side (SAS)
  Two pairs of corresponding sides are in the same ratio and the included angle is equal.

$$\frac{22}{11} = \frac{10}{5}$$



- Angle, Angle, Angle (AAA or AA)
  All three corresponding angles are equal. (If there are two equal pairs then the third pair must be equal by the angle sum of a triangle.)



- Right angle, Hypotenuse, Side (RHS)
  The hypotenuses of right-angled triangles and another corresponding pair of sides are in the same ratio.

$$\frac{15}{5} = \frac{6}{2}$$



Example 15 Choosing a similarity test for triangles

Choose the similarity test which proves that these pairs of triangles are similar.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a AAA	Three pairs of angles are equal.
b RHS	Both are right-angled triangles and the hypotenuses and another pair of sides are in the same ratio $\left(\frac{9}{3} = \frac{6}{2}\right)$.
c SAS	Two pairs of corresponding sides are in the same ratio $\left(\frac{21}{7} = \frac{18}{6}\right)$ and the included angles are equal.
d SSS	Three pairs of corresponding sides are in the same ratio $\left(\frac{15}{5} = \frac{12}{4} = \frac{6}{2}\right)$.

Example 16 Finding a missing length using similarity

For this pair of triangles:



a give a reason (SSS, SAS, AAA or RHS) why the two triangles are similar.

b find the value of x.

SOLUTION	EXPLANATION
a AAA or just AA.	$\angle EAC = \angle DBC$ since AE is parallel to BD and $\angle C$ is common to both triangles. (Also $\angle AEC = \angle BDC$ since AE is parallel to BC).
b Scale factor $= \frac{3}{2} = 1.5$.	$\frac{AE}{BD} = \frac{3}{2}$.
$\therefore x = 5 \times 1.5$	Multiply CD by the scale factor to find the length of the corresponding side CE.
$= 7.5$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 7G

1–3 | 3 | —

UNDERSTANDING

1 These two triangles are similar.



- **a** Which vertex on ΔDEF corresponds to (matches) vertex B on ΔABC?
- **b** Which vertex on ΔABC corresponds to (matches) vertex F on ΔDEF?
- **c** Which side on ΔDEF corresponds to (matches) side AC on ΔABC?
- **d** Which side on ΔABC corresponds to (matches) side EF on ΔDEF?
- **e** Which angle on ΔABC corresponds to (matches) $\angle D$ on ΔDEF?
- **f** Which angle on ΔDEF corresponds to (matches) $\angle B$ on ΔABC?

2 What is the scale factor on this pair of similar triangles which enlarges ΔABC to ΔDEF?



3 Copy and complete the following sentences.

- **a** The abbreviated tests for similar triangles are SSS, _____, _____ and _____.
- **b** Similar figures have the same _____ but are not necessarily the same _____.

4–6 | 4–5(½), 6–8 | 4–5(½), 6–9

FLUENCY

Example 15

4 Choose the similarity test which proves that these pairs of triangles are similar.

a



b



c



d



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7G

FLUENCY

e



f



g



h



5 Write similarity statements for these pairs of similar triangles. Write letters in matching order.

a



b



c



d



e



f



Example 16

6 For this pair of triangles:

a give a reason (SSS, SAS, AAA or RHS) why the two triangles are similar

b find the value of x.



7 For this pair of triangles:

a give a reason (SSS, SAS, AAA or RHS) why the two triangles are similar

b find the value of x.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7G

FLUENCY

8 Each given pair of triangles is similar. For each pair find:

i the enlargement factor (scale factor) which enlarges the smaller triangle to the larger triangle

ii the value of x.

a



b



9 For this pair of triangles:

a give a reason (SSS, SAS, AAA or RHS) why the two triangles are similar

b find the value of x.



10 | 10, 11 | 10–12

PROBLEM-SOLVING

10 For each pair of similar triangles:

i give a reason (SSS, SAS, AAA or RHS) why the two triangles are similar

ii find the value of x.

a



b



c



11 Find the value of x in these triangles.

a



b



c



12 Name the triangle which is not similar to the other two in each group of three triangles.

a







ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

7G

PROBLEM-SOLVING

b







c







d







REASONING

13 | 13, 14 | 14–16

13 Give reasons why these two triangles are similar.





14 Give reasons why the two triangles in these diagrams are not similar.





15 When two intersecting transversals join parallel lines, two triangles are formed. Explain why these two triangles are similar.



16 The four tests for similarity closely resemble the tests for congruence. Which similarity test closely matches the AAS congruence test? Explain the difference.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

17 Consider these four similar triangular prisms (not drawn to scale).



a Complete this table.

Triangle	Original	Image 1	Image 2	Image 3
Length scale factor	1	2		
Area (cross section)				
Area scale factor	1			
Volume				
Volume scale factor	1			

b What do you notice about the area scale factor compared to the length scale factor?

c What would be the area scale factor if the length scale factor is n?

d What would be the area scale factor if the length scale factor is:

i 10? **ii** 20? **iii** 100?

e What would be the area scale factor if the length scale factor is $\frac{1}{2}$?

f What do you notice about the volume scale factor compared to the length scale factor?

g What would be the volume scale factor if the length scale factor is n?

h What would be the volume scale factor if the length scale factor is:

i 5? **ii** 10? **iii** $\frac{1}{2}$?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7H Proving and applying similar triangles

Interactive

Widgets

HOTsheets

Walkthroughs

Similar triangles can be used in many mathematical and practical problems. If two triangles are proved to be similar then the properties of similar triangles can be used to find missing lengths or unknown angles. Finding the approximate height of a tall object, or the width of a projected image, for example, can be found using similar triangles.

The height of even the tallest building in the world, the Burj Khalifa in Dubai, can be verified using similar triangles.

Let's start: How far is the rock?

Ali is at the beach and decides to estimate how far an exposed rock is from seashore. He places four pegs in the sand as shown and measures the distance between them.



- Why do you think Ali has placed the four pegs in the way that is shown in the diagram?
- Why are the two triangles similar? Which test (SSS, SAS, AAA or RHS) could be used and why?
- How would Ali use the similar triangles to find the distance from the beach at peg A to the rock?

Key ideas

- To prove triangles are similar, list any pairs of corresponding equal angles or pairs of sides in a given ratio.
  - Give reasons at each step.
  - Write a similarity statement, for example, $\Delta ABC \Vert\Vert \Delta DEF$ or $\Delta ABC \sim \Delta DEF$
  - Write the triangle similarity test in abbreviated form (SSS, SAS, AAA, RHS).
- To apply similarity in practical problems, follow these steps.
  - Prove two triangles are similar.
  - Find a scale factor.
  - Find the value of any unknowns.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 17 Proving two triangles are similar

Prove that each pair of triangles is similar.

a



b



SOLUTION

a $\angle BAC = \angle DEC$
(alternate angles and $DE \parallel AB$)
$\angle ABC = \angle EDC$
(alternate angles and $DE \parallel AB$)
$\angle ACB = \angle ECD$
(vertically opposite angles)
$\therefore \Delta ABC \equiv \Delta EDC$ (AAA)

b $\frac{AC}{DC} = \frac{18}{6} = 3$

$\angle ACE = \angle DCB$ (common)

$\frac{EC}{BC} = \frac{12}{4} = 3$

$\therefore \Delta ACE \equiv \Delta DCB$ (SAS)

EXPLANATION

Parallel lines cut by a transversal will create a pair of equal alternate angles.

Vertically opposite angles are also equal. Write the similarity statement and the abbreviated reason.



Note that there is a common angle and two pairs of corresponding sides. Find the scale factor for both pairs of sides to see if they are equal. Complete the proof with a similarity statement.

Example 18 Applying similarity

Chris' shadow is 1.2 m long while a 1 m vertical stick has a shadow 0.8 m long.

a Give a reason why the two triangles are similar.

b Determine Chris' height.



SOLUTION

a All angles are the same (AAA).

b Scale factor $= \frac{1.2}{0.8} = 1.5$

$\therefore$ Chris' height $= 1 \times 1.5$
$= 1.5$ m

EXPLANATION

The sun's rays will pass over Chris and the stick and hit the ground at approximately the same angle.

First find the scale factor.

Multiply the height of the stick by the scale factor to find Chris' height.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 7H

1–3 | 3 | —

UNDERSTANDING

1 In this diagram, name the angle which is common to both ΔACE and ΔBCD.



2 In this diagram:

a name the pair of vertically opposite angles

b name the two pairs of equal alternate angles.



3 In this diagram:

a name the common angle for the two triangles

b which side corresponds to side

i DC? **ii** AE?



4(½), 5 | 4(½), 5 | 4(½), 5

FLUENCY

Example 17a

4 Prove that each pair of triangles is similar.

a



b



c



d



e



f



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7H

FLUENCY

Example 17b

5 Prove that each pair of triangles is similar.

a



b



c



6–9 6–10 8–11

PROBLEM-SOLVING

Example 18

6 A tree's shadow is 20 m long, while a 2 m vertical stick has a shadow 1 m long.

a Give a reason why the two triangles contained within the objects and their shadows are similar.

b Find the height of the tree.

7 Two cables support a steel pole at the same angle as shown. The two cables are 4 m and 10 m in length, while the shorter cable reaches 3 m up the pole.



a Give a reason why the two triangles are similar.

b Find the height of the pole.

8 John stands 6 m from a vertical lamp post and casts a 2 m shadow. The shadow from the lamp post and from John end at the same place. Determine the height of the lamp post if John is 1.5 m tall.

9 Joanne wishes to determine the width of the river shown without crossing it. She places four pegs as shown. Calculate the river's width.



10 A deep chasm has a large rock (R) sitting on one side as shown. Find the width of the chasm.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7H

PROBLEM-SOLVING

11 Find the length AB in this diagram if the two triangles are similar.



12	12	12, 13

REASONING

12 In this diagram, ΔADC is isosceles.

- **a** There are two triangles which are similar. Identify them and complete a proof. You may need to find another angle first.
- **b** Find the lengths DC and CB expressing your answers as fractions.



13 In this diagram, AC is perpendicular to BD and ΔABD is right angled.

- **a** Prove that ΔABD is similar to:
  - **i** ΔCBA
  - **ii** ΔCAD
- **b** Find the lengths:
  - **i** BD
  - **ii** AC
  - **iii** AB



Extended proofs	—	—	14

ENRICHMENT

14 a Prove $AE = 4AC$.



b Prove $BC = \frac{1}{2}CE$.



c Prove $CE = \frac{7}{5}CD$.



d Prove $AB = 3BC$.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Triangle centres with technology

Use a computer dynamic geometry package like 'Geometers Sketchpad' or 'Cabri Geometry' to construct the shapes in each of the following questions.

The circumcentre of a triangle

The point at which all perpendicular bisectors of the sides of a triangle meet is called the circumcentre.



a Draw any triangle.

b Label the vertices A, B and C.

c Draw a perpendicular bisector for each side.

d Label the intersection point of the bisectors O.

e Using O as the centre, construct a circle that touches the vertices of the triangle.

f Drag any of the vertices and describe what happens to your construction.

The incentre of a triangle

The point at which all angle bisectors of a triangle meet is called the incentre.



a Draw any triangle.

b Label the vertices A, B and C.

c Draw the three angle bisectors, through the vertices.

d Label the intersection point of the bisectors O.

e Using O as your centre, construct a circle that touches the sides of the triangle.

f Drag any of the vertices and describe what happens to your construction.

The centroid of a triangle

The point of intersection of the three medians of a triangle is called the centroid. It can also be called the centre of gravity.



a Draw a triangle and label the vertices A, B and C.

b Find the midpoint of each line and draw a line segment from each midpoint to its opposite vertex.

c Label the intersection point of these lines O. This is the centroid of the triangle.

d Show your teacher the final construction and print it. Cut out the triangle and place a sharp pencil under the centroid. The triangle should balance perfectly.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

The equilateral triangle: the special triangle

a Construct an equilateral triangle. Determine its incentre, circumcentre and centroid.

b What do you notice?

The tethered goat

A goat is tied to a post by a rope. The area over which the goat can graze will vary in shape depending on where the post is placed or the length of the rope.

Fixed distance from a fence

Assume the post is 3 m from the centre of a high fence 8 m long.

If the rope is quite short as shown in the diagram the area the goat can graze in is circular in shape. For longer lengths of the rope, the shape of the accessible area is different.



a On a sheet of paper draw a scale diagram of the location of the post and fence shown above.

b On your scale diagram use a compass (or a string and drawing pins) to help you trace out the shape of the area accessible to the goat if the length of the rope is:

i 2 m **ii** 3 m **iii** 4 m **iv** 5 m
v 6 m **vi** 9 m **vii** 11 m **viii** 13 m

Be careful! Think about what will happen when the goat reaches either end of the fence.

Fixed length of rope

For the following situations the goat is tied to a post on the fence by a 3 m length of rope. Draw a scale diagram of each one and determine the shape of the accessible area.

a



b



c



Shed problem

In this diagram the goat is tied to a post of a shed, which is 2 m long and 1 m wide by a 3 m length of rope.



a Draw a scale diagram and determine the shape of the accessible area.

b Investigate other situations where the goat is tied to other positions on the shed. Clearly show your diagrams and post position.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Use 12 matchsticks to make 6 equilateral triangles.

2 How many acute angles are there in the diagram shown on the right?

3 Find the value of a.



4 Explore (using dynamic geometry) where the points A, B and C should be on the sides of ΔDEF so that the perimeter of ΔABC is a minimum.



5 Find the size of angle UQS given the sides $PQ = PU$ and $QR = RS$. Angle PTR is 90°.



6 A circle is divided using chords (one chord is shown here). What is the maximum number of regions that can be formed if the circle is divided with 4 chords?



7 Two poles are 30 m and 40 m high. Cables connect the top of each vertical pole to the base of the other pole. How high is the intersection point of the cables above the ground?



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Geometry

Angles
Acute $0° < \theta < 90°$
Right $90°$
Obtuse $90° < \theta < 180°$
Straight $180°$
Reflex $180° < \theta < 360°$
Revolution $360°$
Complementary angles sum to $90°$
Supplementary angles sum to $180°$
Vertically opposite angles are equal.

Parallel lines
If the lines are parallel:

corresponding angles are equal

Alternate angles are equal

Cointerior angles are supplementary
$a + b = 180$

Quadrilaterals
Four-sided figures – sum of the interior angles is $360°$

parallelogram

rhombus 

rectangle 

square

kite

trapezium

Congruent triangles
These are identical in shape and size. They may need to be rotated or reflected. We write $\Delta ABC \equiv \Delta DEF$
(congruent to)
Tests for congruence:
(SSS) – three pairs of corresponding sides equal
(SAS) – two pairs of corresponding sides and included angle are equal
(AAS) – two pairs of angles pairs and any pair of corresponding sides are equal
(RHS) – a right angle, hypotenuse and one other pair of corresponding sides are equal

Polygons
The sum of the interior angles in a polygon with n sides is $S = 180(n - 2)$. Regular polygons have all sides and angles equal.

Triangles
Sum of angles is $180°$.
Exterior angle equals sum of two opposite interior angles



$a = b + c$
exterior angle

Types:
Acute angled – all angles $< 90°$
Obtuse angled – 1 angle $> 90°$
Right angled – 1 angle $90°$
Equilateral – all angles $60°$ – all sides are equal
Isosceles – 2 angles and 2 sides are equal
Scalene – all sides and angles are different sizes

Proving congruence/similarity (Ext)
List corresponding pairs of equal angles and pairs of sides that are equal/in same ratio. Give reasons for each pair. Write a congruence/similarity statement giving the abbreviated reason.
e.g.



AC (common)
$BC = DC$ (given)
$\angle ACD = \angle ACB = 90°$ (given)
$\therefore \Delta ACD \equiv \Delta ACB$ (SAS)

Similar figures
These are the same shape but different size.
Two figures are similar if one can be enlarged to be congruent to the other.
Enlargement uses a scale factor.
Scale factor $= \frac{\text{image length}}{\text{original length}}$

Similar triangles
Similar triangles have corresponding angles equal and corresponding sides are in the same ratio.
We say $\Delta ABC \,|||\, \Delta DEF$ or $\Delta ABC \sim \Delta DEF$
(similar to)
Tests for similar triangles:
(SSS) – three pairs of corresponding sides in the same ratio
(SAS) – two pairs of corresponding sides in the same ratio and included angle equal
(AAA or AA) – all three pairs of corresponding angles are equal; two pairs is enough to prove this
(RHS) – the hypotenuses of right-angled triangles and another pair of corresponding sides are in the same ratio

Applying similar triangles
In practical problems, look to identify and prove pairs of similar triangles. Find a scale factor and use this to find the value of any unknowns.
e.g. shadow cast by a tree is 10.5 m while a person 1.7 m tall has a 1.5 m shadow. How tall is the tree?
Similar (AAA)
Scale factor $= \frac{10.5}{1.5} = 7$
$\therefore h = 1.7 \times 7$
$= 11.9$ m
Tree is 11.9 m tall.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Multiple-choice questions

7A **1** The angle that is supplementary to an angle of 55° is:

A 35° **B** 55° **C** 95°
D 125° **E** 305°

7B **2** What is the value of x if AB is parallel to CD?



A 110 **B** 70 **C** 20
D 130 **E** 120

7A **3** If two angles in a triangle are complementary then the third angle is:

A acute **B** a right angle
C obtuse **D** reflex
E supplementary

7B **4** The values of x and y in the diagram are:



A $x = 35, y = 85$
B $x = 45, y = 45$
C $x = 50, y = 60$
D $x = 55, y = 65$
E $x = 65, y = 55$

7C **5** The sum of the interior angles in a hexagon is:

A 1078° **B** 360° **C** 720°
D 900° **E** 540°

7C **6** The quadrilateral with all sides equal, two pairs of opposite parallel sides and no right angles is:

A a kite **B** a trapezium **C** a parallelogram
D a rhombus **E** a square

7C **7** The values of a and b in the diagram are:



A $a = 85, b = 60$
B $a = 75, b = 80$
C $a = 80, b = 55$
D $a = 70, b = 55$
E $a = 75, b = 50$

7D **8** The abbreviated reason for congruence in the two triangles shown is:



A AA
B SAS
C SSS
D AAS
E RHS

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

7G **9** The scale factor in the two similar figures that enlarges the original figure to its image is:

A $\frac{2}{3}$
B 2
C 1.2
D 1.5
E 0.5



7G **10** The value of x in the diagram is:

A 6 **B** 9
C 10 **D** 8
E 7.5



Short-answer questions

7A **1** Name the following triangles and find the value of the pronumerals.

a



b



c



7A/B **2** Find the value of each pronumeral in the diagrams. Give reasons for your answers.

a



b



c



7B **3** By adding a third parallel line to the diagram, find $\angle ABC$.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7C **4** Find the value of each pronumeral in the following polygons. The polygon in part **d** is regular.

a



b



c



d



7D **5** Determine if each pair of triangles is congruent. If congruent, give the abbreviated reason and state the value of any pronumerals.

a



b



c



d



7E **Ext** **6** **a** Prove that $\Delta ADB \equiv \Delta ADC$. List your reasons and give the abbreviated congruence test.



b **i** Prove that $\Delta ACB \equiv \Delta ECD$. List your reasons and give the abbreviated congruence test.

ii Hence, prove that $AB \parallel DE$.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

7F **7** Copy the given diagram using plenty of space. Using the centre of enlargement (O) and a scale factor of 3, enlarge ΔABC.



7G **8** Determine if the following pairs of triangles are similar, and state the similarity test which proves this.

a



b



c



7G **9** For the following pairs of similar triangles find the value of x.

a



b



c



7H **10** A conveyor belt loading luggage onto a plane is 12.5 m long. A vertical support 1.6 m high is placed under the conveyor belt such that it is 4 m along the conveyor belt as shown.



a Prove that $\Delta BCD \,|||\, \Delta ACE$.

b Find the height (AE) of the luggage door above the ground.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 Complete the following.

a Prove that $DE \parallel CF$.



b Show, with reasons, that $a = 20$.



Ext

c Use congruence to prove that $AC = BD$ in the diagram, given $AB = CD$ and $\angle ABC = \angle DCB$.



2 A buoy (E) is floating in the sea at some unknown distance from the beach as shown. The points A, B, C and D are measured and marked out on the beach as shown.



a Name the angle which is vertically opposite to $\angle ACB$.

b Explain, with reasons, why $\Delta ABC \,|||\, \Delta EDC$.

c Find the distance from the buoy to the beach (ED) to one decimal place.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter 8

Algebraic techniques

What you will learn

8A Expanding binomial products
8B Perfect squares and difference of perfect squares
8C Factorising algebraic expressions
8D Factorising the difference of two squares
8E Factorisation by grouping
8F Factorising quadratic trinomials (Extending)
8G Factorising trinomials of the form $ax^2 + bx + c$ (Extending)
8H Simplifying algebraic fractions: multiplication and division
8I Simplifying algebraic fractions: addition and subtraction
8J Further simplification of algebraic fractions (Extending)
8K Equations with algebraic fractions (Extending)

Australian curriculum

NUMBER AND ALGEBRA

Patterns and algebra

Apply the distributive law to the expansion of algebraic expressions, including binomials, and collect like terms where appropriate AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Free falling

The distance (x units) of an object from the top of a building after it has been dropped (where air resistance is negligible) can be found using the formula $x = ut + \frac{1}{2}at^2$ where u is the initial velocity of the object, t the time since the object has been dropped and a the acceleration due to gravity, which is approximately equal to -9.8 m/s^2. When an object is dropped it has an initial velocity of 0 m/s, so the distance the object has fallen becomes $x = -4.9t^2$. Using algebra, the distance from the building after t seconds can be found or the time taken to reach ground level could be calculated. If the object is instead dropped from a hot air balloon ascending at 10 m/s, the object first travels in an upward direction. Its distance (x metres) above or below the height of the balloon from when the object is dropped can be found using $x = 10t - 4.9t^2$. Knowing the time taken for the object to reach the ground, we could again use algebra to find factors, such as the height of the balloon, the greatest height reached by the object and the time taken for the object to return to the height from which it was released.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A Expanding binomial products

Interactive

Widgets

HOTsheets

Walkthroughs

A binomial is an expression with two terms such as $x + 5$ or $x^2 + 3$. You will recall from Chapter 2 that we looked at the product of a single term with a binomial expression, e.g. $2(x - 3)$ or $x(3x - 1)$. The product of two binomial expressions can also be expanded using the distributive law. This involves multiplying every term in one expression by every term in the other expression.



Expanding the product of two binomial expressions can be applied to problems involving the expansion of rectangular areas such as a farmer's paddock.

Let's start: Rectangular expansions

If $(x + 1)$ and $(x + 2)$ are the side lengths of a rectangle as shown, the total area can be found as an expression in two different ways.



- Write an expression for the total area of the rectangle using length = $(x + 2)$ and width = $(x + 1)$.
- Now find the area of each of the four parts of the rectangle and combine to give an expression for the total area.
- Compare your two expressions above and complete this equation:

$$(x + 2)(\quad) = x^2 + \quad + \quad .$$

- Can you explain a method for expanding the left-hand side to give the right-hand side?

Key ideas

- Expanding **binomial products** uses the **distributive law**.

$$(a + b)(c + d) = a(c + d) + b(c + d)$$
$$= ac + ad + bc + bd$$

- Diagrammatically $(a + b)(c + d) = ac + ad + bc + bd$



For example: $(x + 1)(x + 5) = x^2 + 5x + x + 5$
$= x^2 + 6x + 5$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Expanding binomial products

Expand the following.

a $(x + 3)(x + 5)$ **b** $(x - 4)(x + 7)$

c $(2x - 1)(x - 6)$ **d** $(5x - 2)(3x + 7)$

SOLUTION	EXPLANATION
a $(x + 3)(x + 5) = x^2 + 5x + 3x + 15$ $= x^2 + 8x + 15$	Use the distributive law to expand the brackets and then collect the like terms $5x$ and $3x$.
b $(x - 4)(x + 7) = x^2 + 7x - 4x - 28$ $= x^2 + 3x - 28$	After expanding to get the four terms, collect the like terms $7x$ and $-4x$.
c $(2x - 1)(x - 6) = 2x^2 - 12x - x + 6$ $= 2x^2 - 13x + 6$	Remember $2x \times x = 2x^2$ and $-1 \times (-6) = 6$.
d $(5x - 2)(3x + 7) = 15x^2 + 35x - 6x - 14$ $= 15x^2 + 29x - 14$	Recall $5x \times 3x = 5 \times 3 \times x \times x = 15x^2$.

Exercise 8A

1–3 | 3(½) | —

UNDERSTANDING

1 The given diagram shows the area $(x + 2)(x + 3)$.



a Write down an expression for the area of each of the four regions inside the rectangle.

b Copy and complete:

$(x + 2)(x + 3) = ____ + 3x + ____ + 6$

$= ____ + 5x + ____$

2 The given diagram shows the area $(2x + 3)(x + 1)$.



a Write down an expression for the area of each of the four regions inside the rectangle.

b Copy and complete:

$(2x + 3)(____) = 2x^2 + ____ + 3x + ____$

$= ____ + ____ + ____$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A

UNDERSTANDING

3 Copy and complete these expansions.

a $(x+1)(x+5) = __ + 5x + __ + 5$
$= __ + 6x + __$

b $(x-3)(x+2) = __ + __ - 3x - __$
$= __ - x - __$

c $(3x-2)(7x+2) = __ + 6x - __ - __$
$= __ - __ + __$

d $(4x-1)(3x-4) = __ - __ - 3x + __$
$= __ - 19x + __$

4–5(½) | 4–6(½) | 4–6(½)

FLUENCY

Example 1a

4 Expand the following.

a $(x+2)(x+5)$ **b** $(b+3)(b+4)$ **c** $(t+8)(t+7)$
d $(p+6)(p+6)$ **e** $(x+9)(x+6)$ **f** $(d+15)(d+4)$
g $(a+1)(a+7)$ **h** $(y+10)(y+2)$ **i** $(m+4)(m+12)$

Example 1b
Example 1c
Example 1d

5 Expand the following.

a $(x+3)(x-4)$ **b** $(x+5)(x-2)$ **c** $(x+4)(x-8)$
d $(x-6)(x+2)$ **e** $(x-1)(x+10)$ **f** $(x-7)(x+9)$
g $(x-2)(x+7)$ **h** $(x-1)(x-2)$ **i** $(x-4)(x-5)$
j $(4x+3)(2x+5)$ **k** $(3x+2)(2x+1)$ **l** $(3x+1)(5x+4)$
m $(2x-3)(3x+5)$ **n** $(8x-3)(3x+4)$ **o** $(3x-2)(2x+1)$
p $(5x+2)(2x-7)$ **q** $(2x+3)(3x-2)$ **r** $(4x+1)(4x-5)$
s $(3x-2)(6x-5)$ **t** $(5x-2)(3x-1)$ **u** $(7x-3)(3x-4)$

6 Expand these binomial products.

a $(a+b)(a+c)$ **b** $(a-b)(a+c)$ **c** $(b-a)(a+c)$
d $(x-y)(y-z)$ **e** $(y-x)(z-y)$ **f** $(1-x)(1+y)$
g $(2x+y)(x-2y)$ **h** $(2a+b)(a-b)$ **i** $(3x-y)(2x+y)$
j $(2a-b)(3a+2)$ **k** $(4x-3y)(3x-4y)$ **l** $(xy-yz)(z+3x)$

7 | 7, 8 | 8, 9

PROBLEM-SOLVING

7 A room in a house with dimensions 4 m by 5 m is to be extended. Both the length and width are to be increased by x m.

a Find an expanded expression for the area of the new room.

b If $x = 3$:
i find the area of the new room
ii by how much has the area increased?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A

PROBLEM-SOLVING

8 A rectangular picture frame 5 cm wide has a length which is twice the width x cm.



- **a** Find an expression for the total area of the frame and picture.
- **b** Find an expression in expanded form for the area of the picture only.

9 The outside edge of a path around a rectangular swimming pool is 15 m long and 10 m wide. The path is x metres wide.



- **a** Find an expression for the area of the pool in expanded form.
- **b** Find the area of the pool if $x = 2$.

	10(½)	10(½), 11	10(½), 11

REASONING

10 Write the missing terms in these expansions.

- **a** $(x + 2)(x + __) = x^2 + 5x + 6$
- **b** $(x + __)(x + 5) = x^2 + 7x + 10$
- **c** $(x + 1)(x + __) = x^2 + 7x + __$
- **d** $(x + __)(x + 9) = x^2 + 11x + __$
- **e** $(x + 3)(x - __) = x^2 + x - __$
- **f** $(x - 5)(x + __) = x^2 - 2x - __$
- **g** $(x + 1)(__ + 3) = 2x^2 + __ + __$
- **h** $(__ - 4)(3x - 1) = 9x^2 - __ + __$
- **i** $(x + 2)(__ + __) = 7x^2 + __ + 6$
- **j** $(__ - __)(2x - 1) = 6x^2 - __ + 4$

11 Consider the binomial product $(x + a)(x + b)$. Find the possible integer values of a and b if:

- **a** $(x + a)(x + b) = x^2 + 5x + 6$
- **b** $(x + a)(x + b) = x^2 - 5x + 6$
- **c** $(x + a)(x + b) = x^2 + x - 6$
- **d** $(x + a)(x + b) = x^2 - x - 6$

Trinomial expansions	—	—	12, 13

ENRICHMENT

12 Using the distributive law $(a + b)(c + d + e) = ac + ad + ae + bc + bd + be$.
Use this knowledge to expand and simplify these products. Note: $x \times x^2 = x^3$.

- **a** $(x + 1)(x^2 + x + 1)$
- **b** $(x - 2)(x^2 - x + 3)$
- **c** $(2x - 1)(2x^2 - x + 4)$
- **d** $(x^2 - x + 1)(x + 3)$
- **e** $(5x^2 - x + 2)(2x - 3)$
- **f** $(2x^2 - x + 7)(4x - 7)$
- **g** $(x + a)(x^2 - ax + a)$
- **h** $(x - a)(x^2 - ax - a^2)$
- **i** $(x + a)(x^2 - ax + a^2)$
- **j** $(x - a)(x^2 + ax + a^2)$

13 Now try to expand $(x + 1)(x + 2)(x + 3)$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8B Perfect squares and difference of perfect squares

We know that $2^2 = 4$, $15^2 = 225$, x^2 and $(a + b)^2$ are all examples of perfect squares. To expand $(a + b)^2$ we multiply $(a + b)$ by $(a + b)$ and use the distributive law:

$$\begin{aligned}(a + b)^2 &= (a + b)(a + b)\\ &= a^2 + ab + ba + b^2\\ &= a^2 + 2ab + b^2\end{aligned}$$

A similar result is obtained for the square of $(a - b)$:

$$\begin{aligned}(a - b)^2 &= (a - b)(a - b)\\ &= a^2 - ab - ba + b^2\\ &= a^2 - 2ab + b^2\end{aligned}$$

Another type of expansion involves the case that deals with the product of the sum and difference of the same two terms. The result is the difference of two perfect squares:



Binomial products can be used to calculate the most efficient way to cut the shapes required for a fabrication out of a metal sheet.

$$\begin{aligned}(a + b)(a - b) &= a^2 - ab + ba - b^2\\ &= a^2 - b^2 \text{ (since } ab = ba, \text{ the two middle terms cancel each other out.)}\end{aligned}$$

Let's start: Seeing the pattern

Using $(a + b)(c + d) = ac + ad + bc + bd$, expand and simplify the binomial products in the two sets below.

Set A

$(x + 1)(x + 1) = x^2 + x + x + 1$

$=$

$(x + 3)(x + 3) =$

$=$

$(x - 5)(x - 5) =$

$=$

Set B

$(x + 1)(x - 1) = x^2 - x + x - 1$

$=$

$(x - 3)(x + 3) =$

$=$

$(x - 5)(x + 5) =$

$=$

- Describe what patterns you see in both sets of expansions above.
- Generalise your observations by completing the following expansions.

A $(a + b)(a + b) = a^2 + ____ + ____ + ____$

$= a^2 + ____ + ____$

$(a - b)(a - b) =$

$=$

B $(a + b)(a - b) = a^2 - ____ + ____ - ____$

$=$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- $3^2 = 9, a^2, (2y)^2, (x-1)^2$ and $(3-2y)^2$ are all examples of **perfect squares**.
- Expanding perfect squares
  - $(a+b)^2 = (a+b)(a+b)$
    $= a^2 + ab + ba + b^2$
    $= a^2 + 2ab + b^2$
  - $(a-b)^2 = (a-b)(a-b)$
    $= a^2 - ab - ba + b^2$
    $= a^2 - 2ab + b^2$
- **Difference of perfect squares** (DOPS)
  - $(a+b)(a-b) = a^2 - ab + ba - b^2$
    $= a^2 - b^2$
  - $(a-b)(a+b)$ also expands to $a^2 - b^2$
  - The result is a difference of two perfect squares.

Example 2 Expanding perfect squares

Expand each of the following.

a $(x-2)^2$ b $(2x+3)^2$

SOLUTION | **EXPLANATION**

a $(x-2)^2 = (x-2)(x-2)$ — Write in expanded form.

$= x^2 - 2x - 2x + 4$ — Use the distributive law.

$= x^2 - 4x + 4$ — Collect like terms.

Alternative solution:

$(x-2)^2 = x^2 - 2 \times x \times 2 + 2^2$

$= x^2 - 4x + 4$ — Expand using $(a-b)^2 = a^2 - 2ab + b^2$ where $a = x$ and $b = 2$.

b $(2x+3)^2 = (2x+3)(2x+3)$ — Write in expanded form.

$= 4x^2 + 6x + 6x + 9$ — Use the distributive law.

$= 4x^2 + 12x + 9$ — Collect like terms.

Alternative solution:

$(2x+3)^2 = (2x)^2 + 2 \times 2x \times 3 + 3^2$

$= 4x^2 + 12x + 9$ — Expand using $(a+b)^2 = a^2 + 2ab + b^2$ where $a = 2x$ and $b = 3$. Recall $(2x)^2 = 2x \times 2x = 4x^2$.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Forming a difference of perfect squares

Expand and simplify the following.

a $(x + 2)(x - 2)$ **b** $(3x - 2y)(3x + 2y)$

SOLUTION	EXPLANATION
a $(x + 2)(x - 2) = x^2 - 2x + 2x - 4$ $= x^2 - 4$	Expand using the distributive law. $-2x + 2x = 0$.
Alternative solution:	
$(x + 2)(x - 2) = (x)^2 - (2)^2$ $= x^2 - 4$	$(a + b)(a - b) = a^2 - b^2$. Here $a = x$ and $b = 2$.
b $(3x - 2y)(3x + 2y) = 9x^2 + 6xy - 6xy - 4y^2$ $= 9x^2 - 4y^2$	Expand using the distributive law. $6xy - 6xy = 0$.
Alternative solution:	
$(3x - 2y)(3x + 2y) = (3x)^2 - (2y)^2$ $= 9x^2 - 4y^2$	$(a + b)(a - b) = a^2 - b^2$ with $a = 3x$ and $b = 2y$ here.

Exercise 8B

1–3 | 1(½), 3(½) | —

UNDERSTANDING

1 Complete these expansions.

a $(x + 3)(x + 3) = x^2 + 3x + ____ + ____$
$= _____$

b $(x + 5)(x + 5) = x^2 + 5x + ____ + ____$
$= _____$

c $(x - 2)(x - 2) = x^2 - 2x - ____ + ____$
$= _____$

d $(x - 7)(x - 7) = x^2 - 7x - ____ + ____$
$= _____$

2 **a** Substitute the given value of b into $x^2 + 2bx + b^2$ and simplify.
i $b = 3$ **ii** $b = 11$ **iii** $b = 15$

b Substitute the given value of b into $x^2 - 2bx + b^2$ and simplify.
i $b = 2$ **ii** $b = 9$ **iii** $b = 30$

3 Complete these expansions.

a $(x + 4)(x - 4) = x^2 - 4x + ____ - ____$
$= _____$

b $(x - 10)(x + 10) = x^2 + 10x - ____ - ____$
$= _____$

c $(2x - 1)(2x + 1) = 4x^2 + ____ - ____ - ____$
$= _____$

d $(3x + 4)(3x - 4) = 9x^2 - ____ + ____ - ____$
$= _____$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8B

FLUENCY

4–7(½) 4–8(½) 4–8(½)

Example 2a

4 Expand each of the following perfect squares.

a $(x+1)^2$	**b** $(x+3)^2$	**c** $(x+2)^2$	**d** $(x+5)^2$
e $(x+4)^2$	**f** $(x+9)^2$	**g** $(x+7)^2$	**h** $(x+10)^2$
i $(x-2)^2$	**j** $(x-6)^2$	**k** $(x-1)^2$	**l** $(x-3)^2$
m $(x-9)^2$	**n** $(x-7)^2$	**o** $(x-4)^2$	**p** $(x-12)^2$

Example 2b

5 Expand each of the following perfect squares.

a $(2x+1)^2$	**b** $(2x+5)^2$	**c** $(3x+2)^2$
d $(3x+1)^2$	**e** $(5x+2)^2$	**f** $(4x+3)^2$
g $(7+2x)^2$	**h** $(5+3x)^2$	**i** $(2x-3)^2$
j $(3x-1)^2$	**k** $(4x-5)^2$	**l** $(2x-9)^2$
m $(3x+5y)^2$	**n** $(2x+4y)^2$	**o** $(7x+3y)^2$
p $(6x+5y)^2$	**q** $(4x-9y)^2$	**r** $(2x-7y)^2$
s $(3x-10y)^2$	**t** $(4x-6y)^2$	**u** $(9x-2y)^2$

6 Expand each of the following perfect squares.

a $(3-x)^2$	**b** $(5-x)^2$	**c** $(1-x)^2$
d $(6-x)^2$	**e** $(11-x)^2$	**f** $(4-x)^2$
g $(7-x)^2$	**h** $(12-x)^2$	**i** $(8-2x)^2$
j $(2-3x)^2$	**k** $(9-2x)^2$	**l** $(10-4x)^2$

Example 3a

7 Expand and simplify the following to form a difference of perfect squares.

a $(x+1)(x-1)$	**b** $(x+3)(x-3)$	**c** $(x+8)(x-8)$
d $(x+4)(x-4)$	**e** $(x+12)(x-12)$	**f** $(x+11)(x-11)$
g $(x-9)(x+9)$	**h** $(x-5)(x+5)$	**i** $(x-6)(x+6)$
j $(5-x)(5+x)$	**k** $(2-x)(2+x)$	**l** $(7-x)(7+x)$

Example 3b

8 Expand and simplify the following.

a $(3x-2)(3x+2)$	**b** $(5x-4)(5x+4)$	**c** $(4x-3)(4x+3)$
d $(7x-3y)(7x+3y)$	**e** $(9x-5y)(9x+5y)$	**f** $(11x-y)(11x+y)$
g $(8x+2y)(8x-2y)$	**h** $(10x-9y)(10x+9y)$	**i** $(7x-5y)(7x+5y)$
j $(6x-11y)(6x+11y)$	**k** $(8x-3y)(8x+3y)$	**l** $(9x-4y)(9x+4y)$

PROBLEM-SOLVING

9 9, 10 9, 10

9 Lara is x years old and her two best friends are $(x-2)$ and $(x+2)$ years old.

a Write an expression for:

i the square of Lara's age

ii the product of the ages of Lara's best friends (in expanded form).

b Are the answers from parts **a i** and **ii** equal? If not, by how much do they differ?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8B

PROBLEM-SOLVING

10 A square piece of tin of side length 20 cm has four squares of side length x cm removed from each corner. The sides are folded up to form a tray. The centre square forms the tray base.



- **a** Write an expression for the side length of the base of the tray.
- **b** Write an expression for the base of the tray. Expand your answer.
- **c** Find the area of the tray base if $x = 3$.
- **d** Find the volume of the tray if $x = 3$.

11 | 12, 13 | 12, 13

REASONING

11 Four tennis courts are arranged as shown with a square storage area in the centre. Each court area has the same dimensions $a \times b$.



- **a** Write an expression for the side length of the total area.
- **b** Write an expression for the total area.
- **c** Write an expression for the side length of the inside storage area.
- **d** Write an expression for the area of the inside storage area.
- **e** Subtract your answer to part **d** from your answer to part **b** to find the area of the four courts.
- **f** Find the area of one court. Does your answer confirm that your answer to part **e** is correct?

12 A square of side length x units has one side reduced by 1 unit and the other increased by 1 unit.

- **a** Find an expanded expression for the area of the resulting rectangle.
- **b** Is the area of the original square the same as the area of the resulting rectangle? Explain why/why not?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

13 A square of side length b is removed from a square of side length a.



a Using subtraction write down an expression for the remaining area.

b Write expressions for the area of the regions:

i A **ii** B **iii** C

c Add all the expressions from part **b** to see if you get your answer from part **a**.

Extended expansions — — 14

14 Expand and simplify these expressions.

a $(x+2)^2 - 4$ **b** $(2x-1)^2 - 4x^2$

c $(x+3)(x-3) + 6x$ **d** $1 - (x+1)^2$

e $x^2 - (x+1)(x-1)$ **f** $(x+1)^2 - (x-1)^2$

g $(3x-2)(3x+2) - (3x+2)^2$ **h** $(5x-1)^2 - (5x+1)(5x-1)$

i $(x+y)^2 - (x-y)^2 + (x+y)(x-y)$ **j** $(2x-3)^2 + (2x+3)^2$

k $(2-x)^2 - (2+x)^2$ **l** $(3-x)^2 + (x-3)^2$

m $2(3x-4)^2 - (3x-4)(3x+4)$ **n** $2(x+y)^2 - (x-y)^2$

The logical skills of algebra have applications in computer programming.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

8C Factorising algebraic expressions

The process of factorisation is a key step in the simplification of many algebraic expressions and in the solution of equations. It is the reverse process of expansion and involves writing an expression as a product of its factors.

$$2(x-3) = 2x-6$$

expanding: $\longrightarrow$

factorising: $\longleftarrow$

Factorising is a key mathematical skill required in many diverse occupations, such as in business, science, technology and engineering.

Let's start: Which factorised form?

The product $x(4x + 8)$ when expanded gives $4x^2 + 8x$.

- Write down three other products that when expanded give $4x^2 + 8x$. (Do not use fractions.)
- Which of your products uses the highest common factor of $4x^2$ and $8x$? What is this highest common factor?

Key ideas

- When **factorising** expressions with common factors, take out the highest common factor (HCF). The HCF could be:
  - a number
    For example: $2x + 10 = 2(x + 5)$
  - a pronumeral (or variable)
    For example: $x^2 + 5x = x(x + 5)$
  - the product of numbers and pronumerals
    For example: $2x^2 + 10x = 2x(x + 5)$
- A factorised expression can be checked by using expansion.
  For example: $2x(x + 5) = 2x^2 + 10x$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4 Finding the HCF

Determine the HCF of the following.

a $6a$ and $8ab$

b $3x^2$ and $6xy$

SOLUTION	EXPLANATION
a $2a$	HCF of 6 and 8 is 2.
	HCF of a and ab is a.
b $3x$	HCF of 3 and 6 is 3.
	HCF of x^2 and xy is x.

Example 5 Factorising expressions

Factorise the following.

a $40 - 16b$

b $-8x^2 - 12x$

SOLUTION	EXPLANATION
a $40 - 16b = 8(5 - 2b)$	The HCF of 40 and $16b$ is 8. Place 8 in front of the brackets and divide each term by 8.
b $-8x^2 - 12x = -4x(2x + 3)$	The HCF of the terms is $-4x$, including the common negative. Place the factor in front of the brackets and divide each term by $-4x$.

Example 6 Taking out a binomial factor

Factorise the following.

a $3(x + y) + x(x + y)$

b $(7 - 2x) - x(7 - 2x)$

SOLUTION	EXPLANATION
a $3(x + y) + x(x + y)$	HCF = $(x + y)$.
$= (x + y)(3 + x)$	The second pair of brackets contains what remains when $3(x + y)$ and $x(x + y)$ are divided by $(x + y)$.
b $(7 - 2x) - x(7 - 2x)$	Insert 1 in front of the first bracket.
$= 1(7 - 2x) - x(7 - 2x)$	HCF = $(7 - 2x)$.
$= (7 - 2x)(1 - x)$	The second bracket must contain $1 - x$ after dividing $(7 - 2x)$ and $x(7 - 2x)$ by $(7 - 2x)$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 8C

1–2(½), 3 | 3 | —

UNDERSTANDING

1 Write down the highest common factor (HCF) of these pairs of numbers.

a 8, 12 **b** 10, 20 **c** 5, 60 **d** 24, 30
e 3, 5 **f** 100, 75 **g** 16, 24 **h** 36, 72

2 Write down the missing factor.

a $5 \times ____ = 5x$ **b** $7 \times ____ = 7x$ **c** $2a \times ____ = 2a^2$
d $5a \times ____ = 10a^2$ **e** $____ \times 3y = -6y^2$ **f** $____ \times 12x = -36x^2$
g $-3 \times ____ = 6x$ **h** $-2x \times ____ = 20x^2$ **i** $____ \times 7xy = -14x^2y$

3 **a** Write down the missing factor in each part.

i $__(x^2 + 2x) = 6x^2 + 12x$ **ii** $__(2x + 4) = 6x^2 + 12x$
iii $__(x + 2) = 6x^2 + 12x$

b Which equation above uses the HCF of $6x^2$ and $12x$?

c By looking at the terms left in the brackets, how do you know you have taken out the HCF?

4–7(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 4

4 Determine the HCF of the following.

a $6x$ and $14xy$ **b** $12a$ and $18a$ **c** $10m$ and 4 **d** $12y$ and 8
e $15t$ and $6s$ **f** 15 and p **g** $9x$ and $24xy$ **h** $6n$ and $21mn$
i $10y$ and $2y$ **j** $8x^2$ and $14x$ **k** $4x^2y$ and $18xy$ **l** $5ab^2$ and $15a^2b$

Example 5a

5 Factorise the following.

a $7x + 7$ **b** $3x + 3$ **c** $4x - 4$ **d** $5x - 5$
e $4 + 8y$ **f** $10 + 5a$ **g** $3 - 9b$ **h** $6 - 2x$
i $12a + 3b$ **j** $6m + 6n$ **k** $10x - 8y$ **l** $4a - 20b$
m $x^2 + 2x$ **n** $a^2 - 4a$ **o** $y^2 - 7y$ **p** $x - x^2$
q $3p^2 + 3p$ **r** $8x - 8x^2$ **s** $4b^2 + 12b$ **t** $6y - 10y^2$
u $12a - 15a^2$ **v** $9m + 18m^2$ **w** $16xy - 48x^2$ **x** $7ab - 28ab^2$

Example 5b

6 Factorise the following by factoring out the negative sign as part of the HCF.

a $-8x - 4$ **b** $-4x - 2$ **c** $-10x - 5y$ **d** $-7a - 14b$
e $-9x - 12$ **f** $-6y - 8$ **g** $-10x - 15y$ **h** $-4m - 20n$
i $-3x^2 - 18x$ **j** $-8x^2 - 12x$ **k** $-16y^2 - 6y$ **l** $-5a^2 - 10a$
m $-6x - 20x^2$ **n** $-6p - 15p^2$ **o** $-16b - 8b^2$ **p** $-9x - 27x^2$

Example 6

7 Factorise the following which involve a binomial common factor.

a $4(x + 3) + x(x + 3)$ **b** $3(x + 1) + x(x + 1)$ **c** $7(m - 3) + m(m - 3)$
d $x(x - 7) + 2(x - 7)$ **e** $8(a + 4) - a(a + 4)$ **f** $5(x + 1) - x(x + 1)$
g $y(y + 3) - 2(y + 3)$ **h** $a(x + 2) - x(x + 2)$ **i** $t(2t + 5) + 3(2t + 5)$
j $m(5m - 2) + 4(5m - 2)$ **k** $y(4y - 1) - (4y - 1)$ **l** $(7 - 3x) + x(7 - 3x)$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8C

FLUENCY

8 Factorise these mixed expressions.

a $6a + 30$ **b** $5x - 15$ **c** $8b + 18$

d $x^2 - 4x$ **e** $y^2 + 9y$ **f** $a^2 - 3a$

g $x^2y - 4xy + xy^2$ **h** $6ab - 10a^2b + 8ab^2$ **i** $m(m + 5) + 2(m + 5)$

j $x(x + 3) - 2(x + 3)$ **k** $b(b - 2) + (b - 2)$ **l** $x(2x + 1) - (2x + 1)$

m $y(3 - 2y) - 5(3 - 2y)$ **n** $(x + 4)^2 + 5(x + 4)$ **o** $(y + 1)^2 - 4(y + 1)$

PROBLEM-SOLVING

9 | 9, 10 | 9(½), 10, 11

9 Write down the perimeter of these shapes in factorised form.

a



b



c



d



e



f



10 The expression for the area of a rectangle is $(4x^2 + 8x)$ square units. Find an expression for its width if the length is $(x + 2)$ units.

11 The height, in metres, of a ball thrown in the air is given by $5t - t^2$, where t is the time in seconds.

a Write an expression for the ball's height in factorised form.

b Find the ball's height at these times:

i $t = 0$

ii $t = 2$

iii $t = 4$

c How long does it take for the ball's height to return to 0 metres? Use trial and error if required.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

8C

12 | 12, 13 | 13, 14

REASONING

12 $7 \times 9 + 7 \times 3$ can be evaluated by firstly factorising to $7(9 + 3)$. This gives $7 \times 12 = 84$. Use a similar technique to evaluate the following.

a $9 \times 2 + 9 \times 5$ **b** $6 \times 3 + 6 \times 9$ **c** $-2 \times 4 - 2 \times 6$

d $-5 \times 8 - 5 \times 6$ **e** $23 \times 5 - 23 \times 2$ **f** $63 \times 11 - 63 \times 8$

13 Common factors can also be removed from expressions with more than two terms.
For example: $2x^2 + 6x + 10xy = 2x(x + 3 + 5y)$
Factorise these expressions by taking out the HCF.

a $3a^2 + 9a + 12$ **b** $5z^2 - 10z + zy$ **c** $x^2 - 2xy + x^2y$

d $4by - 2b + 6b^2$ **e** $-12xy - 8yz - 20xyz$ **f** $3ab + 4ab^2 + 6a^2b$

14 Sometimes we can choose to factor out a negative HCF or a positive HCF. Both factorisations are correct. For example:

$$-13x + 26 = -13(x - 2) \quad \text{(HCF is } -13\text{)}$$
$$\text{OR } -13x + 26 = 13(-x + 2) \quad \text{(HCF is 13)}$$
$$= 13(2 - x)$$

Factorise in two different ways: the first by factoring out a negative HCF and the second by a positive HCF.

a $-4x + 12$ **b** $-3x + 9$ **c** $-8n + 8$ **d** $-3b + 3$

e $-5m + 5m^2$ **f** $-7x + 7x^2$ **g** $-5x + 5x^2$ **h** $-4y + 22y^2$

i $-8n + 12n^2$ **j** $-8y + 20$ **k** $-15mn + 10$ **l** $-15x + 45$

ENRICHMENT

Factoring out a negative

— | — | 15

15 Using the fact that $a - b = -(b - a)$ you can factorise $x(x - 2) - 5(2 - x)$ by following these steps.

$$x(x - 2) - 5(2 - x) = x(x - 2) + 5(x - 2)$$
$$= (x - 2)(x + 5)$$

Use this idea to factorise these expressions.

a $x(x - 4) + 3(4 - x)$ **b** $x(x - 5) - 2(5 - x)$ **c** $x(x - 3) - 3(3 - x)$

d $3x(x - 4) + 5(4 - x)$ **e** $3(2x - 5) + x(5 - 2x)$ **f** $2x(x - 2) + (2 - x)$

g $-4(3 - x) - x(x - 3)$ **h** $x(x - 5) + (10 - 2x)$ **i** $x(x - 3) + (6 - 2x)$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D Factorising the difference of two squares

Interactive

Widgets

HOTsheets

Walkthroughs

Recall that a difference of two perfect squares is formed when expanding the product of the sum and difference of two terms. For example, $(x + 2)(x - 2) = x^2 - 4$. Reversing this process means that a difference of two perfect squares can be factorised into two binomial expressions of the form $(a + b)$ and $(a - b)$.

Let's start: Expanding to understand factorising

Complete the steps in these expansions then write the conclusion.

- $(x + 3)(x - 3) = x^2 - 3x + __ - __$
  $= x^2 - __$
  $\therefore x^2 - 9 = (__ + __)(__ - __)$
- $(2x - 5)(2x + 5) = 4x^2 + 10x - __ - __$
  $= _____ - _____$
  $\therefore 4x^2 - __ = (__ + __)(__ - __)$
- $(a + b)(a - b) = a^2 - ab + __ - __$
  $= _____ - _____$
  $\therefore a^2 - __ = (__ + __)(__ - __)$

Key ideas

- Factorising the difference of perfect squares (DOPS) uses the rule $a^2 - b^2 = (a + b)(a - b)$.
  - $x^2 - 16 = x^2 - 4^2$
    $= (x + 4)(x - 4)$
  - $9x^2 - 100 = (3x)^2 - 10^2$
    $= (3x + 10)(3x - 10)$
  - $25 - 4y^2 = 5^2 - (2y)^2$
    $= (5 + 2y)(5 - 2y)$
- First take out common factors where possible.
  - $2x^2 - 18 = 2(x^2 - 9)$
    $= 2(x + 3)(x - 3)$

Example 7 Factorising DOPS

Factorise each of the following.

a $x^2 - 4$
b $9a^2 - 25$
c $81x^2 - y^2$
d $2b^2 - 32$
e $(x + 1)^2 - 4$

SOLUTION	EXPLANATION
a $x^2 - 4 = x^2 - 2^2$ $= (x + 2)(x - 2)$	Write as a DOPS (4 is the same as 2^2). Write in factorised form $a^2 - b^2 = (a + b)(a - b)$. Here $a = x$ and $b = 2$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

b $9a^2 - 25 = (3a)^2 - 5^2$
$= (3a + 5)(3a - 5)$
Write as a DOPS. $9a^2$ is the same as $(3a)^2$.
Write in factorised form.

c $81x^2 - y^2 = (9x)^2 - y^2$
$= (9x + y)(9x - y)$
$81x^2 = (9x)^2$
Use $a^2 - b^2 = (a + b)(a - b)$

d $2b^2 - 32 = 2(b^2 - 16)$
$= 2(b^2 - 4^2)$
$= 2(b + 4)(b - 4)$
First, factor out the common factor of 2.
Write as a DOPS and then factorise.

e $(x + 1)^2 - 4 = (x + 1)^2 - 2^2$
$= (x + 1 + 2)(x + 1 - 2)$
$= (x + 3)(x - 1)$
Write as a DOPS. In $a^2 - b^2$ here, a is the expression $x + 1$ and $b = 2$.
Write in factorised form and simplify.

Exercise 8D

1–3(½) | 3(½) | —

UNDERSTANDING

1 Expand these binomial products to form a difference of perfect squares.

a $(x + 2)(x - 2)$ **b** $(x - 7)(x + 7)$ **c** $(2x - 1)(2x + 1)$
d $(x + y)(x - y)$ **e** $(3x - y)(3x + y)$ **f** $(a + b)(a - b)$

2 Write the missing term. Assume it is a positive number.

a $(__)^2 = 9$ **b** $(__)^2 = 121$ **c** $(__)^2 = 81$ **d** $(__)^2 = 400$
e $(__)^2 = 4x^2$ **f** $(__)^2 = 9a^2$ **g** $(__)^2 = 25b^2$ **h** $(__)^2 = 49y^2$

3 Complete these factorisations.

a $x^2 - 16 = x^2 - 4^2$
$= (x + 4)(__ - __)$

b $x^2 - 144 = x^2 - (__)^2$
$= (__ + 12)(x - __)$

c $16x^2 - 1 = (__)^2 - (__)^2$
$= (4x + __)(__ - 1)$

d $9a^2 - 4b^2 = (__)^2 - (__)^2$
$= (3a + __)(__ - 2b)$

4–6(½) | 4–7(½) | 4–7(½)

FLUENCY

Example 7a

4 Factorise each of the following.

a $x^2 - 9$ **b** $y^2 - 25$ **c** $y^2 - 1$ **d** $x^2 - 64$
e $x^2 - 16$ **f** $b^2 - 49$ **g** $a^2 - 81$ **h** $x^2 - y^2$
i $a^2 - b^2$ **j** $16 - a^2$ **k** $25 - x^2$ **l** $1 - b^2$
m $36 - y^2$ **n** $121 - b^2$ **o** $x^2 - 400$ **p** $900 - y^2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8D

FLUENCY

Example 7b
Example 7c

5 Factorise each of the following.

a $4x^2 - 25$	**b** $9x^2 - 49$	**c** $25b^2 - 4$	**d** $4m^2 - 121$
e $100y^2 - 9$	**f** $81a^2 - 4$	**g** $1 - 4x^2$	**h** $25 - 64b^2$
i $16 - 9y^2$	**j** $36x^2 - y^2$	**k** $4x^2 - 25y^2$	**l** $64a^2 - 49b^2$
m $4p^2 - 25q^2$	**n** $81m^2 - 4n^2$	**o** $25a^2 - 49b^2$	**p** $100a^2 - 9b^2$

Example 7d

6 Factorise each of the following by first taking out the common factor.

a $3x^2 - 108$	**b** $10a^2 - 10$	**c** $6x^2 - 24$
d $4y^2 - 64$	**e** $98 - 2x^2$	**f** $32 - 8m^2$
g $5x^2y^2 - 5$	**h** $3 - 3x^2y^2$	**i** $63 - 7a^2b^2$

Example 7e

7 Factorise each of the following.

a $(x + 5)^2 - 9$	**b** $(x + 3)^2 - 4$	**c** $(x + 10)^2 - 16$
d $(x - 3)^2 - 25$	**e** $(x - 7)^2 - 1$	**f** $(x - 3)^2 - 36$
g $49 - (x + 3)^2$	**h** $4 - (x + 2)^2$	**i** $81 - (x + 8)^2$

8 | 8, 9 | 8, 9

PROBLEM-SOLVING

8 The height above ground (in metres) of an object thrown off the top of a building is given by $36 - 4t^2$ where t is in seconds.

- **a** Factorise the expression for the height of the object by firstly taking out the common factor.
- **b** Find the height of the object:
  - **i** initially ($t = 0$)
  - **ii** at 2 seconds ($t = 2$).
- **c** How long does it take for the object to hit the ground? Use trial and error if you wish.

9 This 'multisize' square picture frame has side length 30 cm and can hold a square picture with any side length less than 26 cm.



- **a** If the side length of the picture is x cm, write an expression for:
  - **i** the area of the picture
  - **ii** the area of the frame (in factorised form).
- **b** Use your result from part **a ii** to find the area of the frame if:
  - **i** $x = 20$
  - **ii** the area of the picture is 225 cm^2.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D

10 | 10, 11 | 10–12

REASONING

10 Initially it may not appear that an expression such as $-4 + 9x^2$ is a difference of perfect squares. However, swapping the position of the two terms makes $-4 + 9x^2 = 9x^2 - 4$, which can be factorised to $(3x + 2)(3x - 2)$. Use this idea to factorise these difference of perfect squares.

a $-9 + x^2$ **b** $-121 + 16x^2$ **c** $-25a^2 + 4$ **d** $-y^2 + x^2$

e $-25a^2 + 4b^2$ **f** $-36a^2b^2 + c^2$ **g** $-16x^2 + y^2z^2$ **h** $-900a^2 + b^2$

11 Olivia factorises $16x^2 - 4$ to get $(4x + 2)(4x - 2)$ but the answer says $4(2x + 1)(2x - 1)$.

a What should Olivia do to get from her answer to the actual answer?

b What should Olivia have done initially to avoid this issue?

12 Find and explain the error in this working and correct it.

$$9 - (x - 1)^2 = (3 + x - 1)(3 - x - 1)$$
$$= (2 + x)(2 - x)$$

Factorising with fractions and powers of 4

— | — | 13

ENRICHMENT

13 Some expressions with fractions or powers of 4 can be factorised in a similar way. Factorise these.

a $x^2 - \frac{1}{4}$ **b** $x^2 - \frac{4}{25}$ **c** $25x^2 - \frac{9}{16}$ **d** $\frac{x^2}{9} - 1$

e $\frac{a^2}{4} - \frac{b^2}{9}$ **f** $\frac{5x^2}{9} - \frac{5}{4}$ **g** $\frac{7a^2}{25} - \frac{28b^2}{9}$ **h** $\frac{a^2}{8} - \frac{b^2}{18}$

i $x^4 - y^4$ **j** $2a^4 - 2b^4$ **k** $21a^4 - 21b^4$ **l** $\frac{x^4}{3} - \frac{y^4}{3}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8E Factorisation by grouping

Interactive

Widgets

HOTsheets

Walkthroughs

When an expression contains four terms, such as $x^2 + 2x - x - 2$, it may be possible to factorise it into a product of two binomial terms like $(x - 1)(x + 2)$. In such situations the method of grouping is often used.

Factorising by grouping is a bit like arranging scattered objects into some sort of order.

Let's start: Two methods – same result

The four-term expression $x^2 - 3x - 3 + x$ is written on the board.

Tommy chooses to rearrange the terms to give $x^2 - 3x + x - 3$ then factorises by grouping.

Sharon chooses to rearrange the terms to give $x^2 + x - 3x - 3$ then also factorises by grouping.

- Complete Tommy and Sharon's factorisation working.

Tommy

$x^2 - 3x + x - 3 = x(x - 3) + 1(_____)$

$= (x - 3)(_____)$

Sharon

$x^2 + x - 3x - 3 = x(_____) - 3(_____)$

$= (x + 1)(_____)$

- Discuss the differences in the methods. Is there any difference in their answers?
- Whose method do you prefer?

Key ideas

■ **Factorisation by grouping** is a method which is often used to factorise a four-term expression.

- Terms are grouped into pairs and factorised separately.
- The common binomial factor is then taken out to complete the factorisation.
- Terms can be rearranged to assist in the search of a common factor.

$x^2 + 3x - 2x - 6$

$= x(x + 3) - 2(x + 3)$

$= (x + 3)(x - 2)$

Example 8 Factorising by grouping

Use the method of grouping to factorise these expressions.

a $x^2 + 2x + 3x + 6$ b $x^2 + 3x - 5x - 15$

SOLUTION	EXPLANATION
a $x^2 + 2x + 3x + 6 = (x^2 + 2x) + (3x + 6)$	Group the first and second pair of terms.
$= x(x + 2) + 3(x + 2)$	Factorise each group.
$= (x + 2)(x + 3)$	Take the common factor $(x + 2)$ out of both groups.
b $x^2 + 3x - 5x - 15 = (x^2 + 3x) + (-5x - 15)$	Group the first and second pair of terms.
$= x(x + 3) - 5(x + 3)$	Factorise each group.
$= (x + 3)(x - 5)$	Take out the common factor $(x + 3)$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Rearranging an expression to factorise by grouping

Factorise $2x^2 - 9 - 18x + x$ using grouping.

SOLUTION	EXPLANATION
$2x^2 - 9 - 18x + x = 2x^2 + x - 18x - 9$	Rearrange so that each group has a common factor.
$= x(2x + 1) - 9(2x + 1)$	Factorise each group then take out $(2x + 1)$.
$= (2x + 1)(x - 9)$	
Alternatively:	Alternatively, you can group in another order where each group has a comman factor. Then factorise.
$2x^2 - 9 - 18x + x = 2x^2 - 18x + x - 9$	
$= 2x(x - 9) + 1(x - 9)$	
$= (x - 9)(2x + 1)$	The answer will be the same.

Exercise 8E

1–3(½) | 3(½) | —

UNDERSTANDING

1 Expand each expression.

a $2(x - 1)$ **b** $3(a + 4)$ **c** $-5(1 - a)$
d $-2(3 - x)$ **e** $a(a + 5)$ **f** $b(2 - b)$
g $x(x - 4)$ **h** $y(4 - y)$ **i** $x(a + 1) + 2(a + 1)$
j $a(x - 3) + 5(x - 3)$ **k** $b(x - 2) - 3(x - 2)$ **l** $c(1 - x) - 4(1 - x)$

2 Copy and then fill in the missing information.

a $2(x + 1) + x(x + 1) = (x + 1)(____)$ **b** $3(x + 3) - x(x + 3) = (x + 3)(____)$
c $5(x + 5) - x(x + 5) = (x + 5)(____)$ **d** $x(x + 7) + 4(x + 7) = (x + 7)(____)$
e $a(x - 3) + (x - 3) = (x - 3)(____)$ **f** $a(x + 4) - (x + 4) = (x + 4)(____)$
g $(x - 3) - a(x - 3) = (x - 3)(____)$ **h** $(4 - x) + 2a(4 - x) = (4 - x)(____)$

3 Take out the common binomial term to factorise each expression.

a $x(x - 3) - 2(x - 3)$ **b** $x(x + 4) + 3(x + 4)$ **c** $x(x - 7) + 4(x - 7)$
d $3(2x + 1) - x(2x + 1)$ **e** $4(3x - 2) - x(3x - 2)$ **f** $2x(2x + 3) - 3(2x + 3)$
g $3x(5 - x) + 2(5 - x)$ **h** $2(x + 1) - 3x(x + 1)$ **i** $x(x - 2) + (x - 2)$

4–5(½) | 4–6(½) | 4–6(½)

FLUENCY

Example 8

4 Use the method of grouping to factorise these expressions.

a $x^2 + 3x + 2x + 6$ **b** $x^2 + 4x + 3x + 12$ **c** $x^2 + 7x + 2x + 14$
d $x^2 - 6x + 4x - 24$ **e** $x^2 - 4x + 6x - 24$ **f** $x^2 - 3x + 10x - 30$
g $x^2 + 2x - 18x - 36$ **h** $x^2 + 3x - 14x - 42$ **i** $x^2 + 4x - 18x - 72$
j $x^2 - 2x - xa + 2a$ **k** $x^2 - 3x - 3xc + 9c$ **l** $x^2 - 5x - 3xa + 15a$

5 Use the method of grouping to factorise these expressions. The HCF for each pair includes a pronumeral.

a $3ab + 5bc + 3ad + 5cd$ **b** $4ab - 7ac + 4bd - 7cd$ **c** $2xy - 8xz + 3wy - 12wz$
d $5rs - 10r + st - 2t$ **e** $4x^2 + 12xy - 3x - 9y$ **f** $2ab - a^2 - 2bc + ac$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8E

FLUENCY

6 Factorise these expressions. Remember to use a factor of 1 where necessary, for example, $x^2 - ax + x - a = x(x - a) + 1(x - a)$.

a $x^2 - bx + x - b$ **b** $x^2 - cx + x - c$ **c** $x^2 + bx + x + b$

d $x^2 + cx - x - c$ **e** $x^2 + ax - x - a$ **f** $x^2 - bx - x + b$

7	7, 8	7, 9

PROBLEM-SOLVING

Example 9

7 Factorise these expressions by first rearranging the terms.

a $2x^2 - 7 - 14x + x$ **b** $5x + 2x + x^2 + 10$ **c** $2x^2 - 3 - x + 6x$

d $3x - 8x - 6x^2 + 4$ **e** $11x - 5a - 55 + ax$ **f** $12y + 2x - 8xy - 3$

g $6m - n + 3mn - 2$ **h** $15p - 8r - 5pr + 24$ **i** $16x - 3y - 8xy + 6$

8 What expanded expression factorises to the following?

a $(x - a)(x + 4)$ **b** $(x - c)(x - d)$ **c** $(x + y)(2 - z)$ **d** $(x - 1)(a + b)$

e $(3x - b)(c - b)$ **f** $(2x - y)(y + z)$ **g** $(3a + b)(2b + 5c)$ **h** $(m - 2x)(3y + z)$

9 Note that $x^2 + 5x + 6 = x^2 + 2x + 3x + 6$ which can be factorised by grouping. Use a similar method to factorise the following.

a $x^2 + 7x + 10$ **b** $x^2 + 8x + 15$ **c** $x^2 + 10x + 24$

d $x^2 - x - 6$ **e** $x^2 + 4x - 12$ **f** $x^2 - 11x + 18$

10	10	10, 11

REASONING

10 $xa - 21 + 7a - 3x$ could be rearranged in two different ways before factorising.

Method 1

$xa + 7a - 3x - 21 = a(x + 7) - 3(_____)$

$= _____$

Method 2

$xa - 3x + 7a - 21 = x(a - 3) + 7(_____)$

$= _____$

a Copy and complete both methods for the above expression.

b Use different arrangements of the four terms to complete the factorisation of the following in two ways. Show working using both methods.

i $xb - 6 - 3b + 2x$ **ii** $xy - 8 + 2y - 4x$ **iii** $4m^2 - 15n + 6m - 10mn$

iv $2m + 3n - mn - 6$ **v** $4a - 6b^2 + 3b - 8ab$ **vi** $3ab - 4c - b + 12ac$

11 Make up at least three of your own four-term expressions that factorise to a binomial product. Describe the method that you used to make up each four-term expression.

Grouping with more than four terms

—	—	12

ENRICHMENT

12 Factorise by grouping.

a $2(a - 3) - x(a - 3) - c(a - 3)$ **b** $b(2a + 1) + 5(2a + 1) - a(2a + 1)$

c $x(a + 1) - 4(a + 1) - ba - b$ **d** $3(a - b) - b(a - b) - 2a^2 + 2ab$

e $c(1 - a) - x + ax + 2 - 2a$ **f** $a(x - 2) + 2bx - 4b - x + 2$

g $a^2 - 3ac - 2ab + 6bc + 3abc - 9bc^2$ **h** $3x - 6xy - 5z + 10yz + y - 2y^2$

i $8z - 4y + 3x^2 + xy - 12x - 2xz$ **j** $-ab - 4cx + 3aby + 2abx + 2c - 6cy$

Using a CAS calculator 8E: Expanding and factorising

This activity is in the interactive textbook in the form of a printable PDF.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8F Factorising quadratic trinomials EXTENDING

An expression that takes the form $x^2 + bx + c$, where b and c are constants, is an example of a monic quadratic trinomial which has the coefficient of x^2 equal to 1. To factorise a quadratic expression, we need to use the distributive law in reverse. Consider the expansion shown at right:



If we examine the expansion above we can see how each term of the product is formed.





Let's start: So many choices

Mia says that since $-2 \times 3 = -6$ then $x^2 + 5x - 6$ must equal $(x - 2)(x + 3)$.

- Expand $(x - 2)(x + 3)$ to see if Mia is correct.
- What other pairs of numbers multiply to give -6?
- Which pair of numbers should Mia choose to correctly factorise $x^2 + 5x - 6$?
- What advice can you give Mia when trying to factorise these types of trinomials?

Key ideas

- To factorise a **quadratic trinomial** of the form $x^2 + bx + c$, find two numbers which:
  - multiply to give c and
  - add to give b.

  For example:
  $x^2 - 3x - 10 = (x - 5)(x + 2)$ choose -5 and $+2$
  since $-5 \times 2 = -10$ and $-5 + 2 = -3$

- Check factorisation steps by expanding.

  check: $(x - 5)(x + 2) = x^2 + 2x - 5x - 10$
  $= x^2 - 3x - 10$

- Write the factors in any order.

  write $(x - 5)(x + 2)$ or $(x + 2)(x - 5)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Factorising quadratic trinomials

Factorise each of the following quadratic expressions.

a $x^2 + 7x + 10$ **b** $x^2 + 2x - 8$ **c** $x^2 - 7x + 10$

SOLUTION	EXPLANATION
a $x^2 + 7x + 10 = (x + 5)(x + 2)$	Factors of 10 include: (10, 1) and (5, 2). The pair that adds to 7 is (5, 2).
b $x^2 + 2x - 8 = (x + 4)(x - 2)$	Factors of –8 are (–8, 1) or (8, –1) or (4, –2) or (–4, 2) and 4 + (–2) = 2 so choose (4, –2).
c $x^2 - 7x + 10 = (x - 2)(x - 5)$	Factors of 10 are: (10, 1) or (–10, –1) or (5, 2) or (–5, –2). To add to a negative (–7), both factors must then be negative: –5 + (–2) = –7 so choose (–5, –2).

Example 11 Factorising with a common factor

Factorise the quadratic expression $2x^2 - 2x - 12$.

SOLUTION	EXPLANATION
$2x^2 - 2x - 12 = 2(x^2 - x - 6)$ $= 2(x - 3)(x + 2)$	First take out common factor of 2. Factors of –6 are: (–6, 1) or (6, –1) or (–3, 2) or (3, –2). –3 + 2 = –1 so choose (–3, 2).

Exercise 8F

1–2(½) | 2(½) | —

UNDERSTANDING

1 Expand these binomial products.

a $(x + 1)(x + 3)$ **b** $(x + 2)(x + 7)$ **c** $(x - 3)(x + 11)$
d $(x - 5)(x + 6)$ **e** $(x + 12)(x - 5)$ **f** $(x + 13)(x - 4)$
g $(x - 2)(x - 6)$ **h** $(x - 20)(x - 11)$ **i** $(x - 9)(x - 1)$

2 Decide what two numbers multiply to give the first number and add to give the second number.

a 6, 5 **b** 10, 7 **c** 12, 13
d 20, 9 **e** –5, 4 **f** –7, –6
g –15, 2 **h** –30, –1 **i** 6, –5
j 18, –11 **k** 40, –13 **l** 100, –52

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8F

3–6(½) | 3–7(½) | 3–7(½)

FLUENCY

Example 10a

3 Factorise each of the following quadratic expressions.

a $x^2 + 3x + 2$	**b** $x^2 + 4x + 3$	**c** $x^2 + 8x + 12$
d $x^2 + 10x + 9$	**e** $x^2 + 8x + 7$	**f** $x^2 + 15x + 14$
g $x^2 + 6x + 8$	**h** $x^2 + 7x + 12$	**i** $x^2 + 10x + 16$
j $x^2 + 8x + 15$	**k** $x^2 + 9x + 20$	**l** $x^2 + 11x + 24$

Example 10b

4 Factorise each of the following quadratic expressions.

a $x^2 + 3x - 4$	**b** $x^2 + x - 2$	**c** $x^2 + 4x - 5$
d $x^2 + 5x - 14$	**e** $x^2 + 2x - 15$	**f** $x^2 + 8x - 20$
g $x^2 + 3x - 18$	**h** $x^2 + 7x - 18$	**i** $x^2 + x - 12$

Example 10c

5 Factorise each of the following quadratic expressions.

a $x^2 - 6x + 5$	**b** $x^2 - 2x + 1$	**c** $x^2 - 5x + 4$
d $x^2 - 9x + 8$	**e** $x^2 - 4x + 4$	**f** $x^2 - 8x + 12$
g $x^2 - 11x + 18$	**h** $x^2 - 10x + 21$	**i** $x^2 - 5x + 6$

6 Factorise each of the following quadratic expressions.

a $x^2 - 7x - 8$	**b** $x^2 - 3x - 4$	**c** $x^2 - 5x - 6$
d $x^2 - 6x - 16$	**e** $x^2 - 2x - 24$	**f** $x^2 - 2x - 15$
g $x^2 - x - 12$	**h** $x^2 - 11x - 12$	**i** $x^2 - 4x - 12$

Example 11

7 Factorise each of the following quadratic expressions by first taking out a common factor.

a $2x^2 + 10x + 8$	**b** $2x^2 + 22x + 20$	**c** $3x^2 + 18x + 24$
d $2x^2 + 14x - 60$	**e** $2x^2 - 14x - 36$	**f** $4x^2 - 8x + 4$
g $2x^2 + 2x - 12$	**h** $6x^2 - 30x - 36$	**i** $5x^2 - 30x + 40$
j $3x^2 - 33x + 90$	**k** $2x^2 - 6x - 20$	**l** $3x^2 - 3x - 36$

8 | 8(½), 9 | 8(½), 9

PROBLEM-SOLVING

8 Find the missing term in these trinomials if they are to factorise using integers. For example: the missing term in $x^2 + \square + 10$ could be $7x$ because $x^2 + 7x + 10$ factorises to $(x + 5)(x + 2)$ and 5 and 2 are integers. There may be more than one answer in each case.

a $x^2 + \square + 5$	**b** $x^2 - \square + 9$	**c** $x^2 - \square - 12$	**d** $x^2 + \square - 12$
e $x^2 + \square + 18$	**f** $x^2 - \square + 18$	**g** $x^2 - \square - 16$	**h** $x^2 + \square - 25$

9 A backyard, rectangular in area, has a length 2 metres more than its width (x metres). Inside the rectangle are three square paved areas each of area 5 m^2 as shown. The remaining area is lawn.

a Find an expression for:
- **i** the total backyard area
- **ii** the area of lawn in expanded form
- **iii** the area of lawn in factorised form.

b Find the area of lawn if:
- **i** $x = 10$
- **ii** $x = 7$.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8F

10(½) | 10(½) | 10(½), 11

REASONING

10 The expression $x^2 - 6x + 9$ factorises to $(x-3)(x-3) = (x-3)^2$, which is a perfect square. Factorise these perfect squares.

a $x^2 + 8x + 16$ **b** $x^2 + 10x + 25$ **c** $x^2 + 30x + 225$

d $x^2 - 2x + 1$ **e** $x^2 - 14x + 49$ **f** $x^2 - 26x + 169$

g $2x^2 + 4x + 2$ **h** $5x^2 - 30x + 45$ **i** $-3x^2 + 36x - 108$

11 Sometimes it is not possible to factorise quadratic trinomials using integers. Decide which of the following cannot be factorised using integers.

a $x^2 - x - 56$ **b** $x^2 + 5x - 4$ **c** $x^2 + 7x - 6$

d $x^2 + 3x - 108$ **e** $x^2 + 3x - 1$ **f** $x^2 + 12x - 53$

Completing the square

— | — | 12

ENRICHMENT

12 It is useful to be able to write a simple quadratic trinomial in the form $(x+b)^2 + c$. This involves adding (and subtracting) a special number to form the first perfect square. This procedure is called completing the square. Here is an example.

$$\left(-\frac{6}{2}\right)^2 = 9$$

$$x^2 - 6x - 8 = \underbrace{x^2 - 6x + 9}\ \underbrace{- 9 - 8}$$

$$= (x-3)(x-3) - 17$$

$$= (x-3)^2 - 17$$

Complete the square for these trinomials.

a $x^2 - 2x - 8$ **b** $x^2 + 4x - 1$ **c** $x^2 + 10x + 3$

d $x^2 - 16x - 3$ **e** $x^2 + 18x + 7$ **f** $x^2 - 32x - 11$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8G Factorising trinomials of the form $ax^2 + bx + c$ EXTENDING

So far we have factorised quadratic trinomials where the coefficient of x^2 is 1, such as $x^2 - 3x - 40$. These are called monic trinomials. We will now consider non-monic trinomials where the coefficient of x is not equal to 1 and is also not a common factor to all three terms, such as in $6x^2 + x - 15$. The method used in this section uses grouping which was discussed in section 8E.

Let's start: How the grouping method works

Consider the trinomial $2x^2 + 9x + 10$.

- First write $2x^2 + 9x + 10 = 2x^2 + 4x + 5x + 10$ then factorise by grouping.
- Note that $9x$ was split to give $4x + 5x$ and the product of $2x^2$ and 10 is $20x^2$. Describe the link between the pair of numbers $\{4, 5\}$ and the pair of numbers $\{2, 10\}$.
- Why was $9x$ split to give $4x + 5x$ and not, say, $3x + 6x$?
- Describe how the $13x$ should be split in $2x^2 + 13x + 15$ so it can be factorised by grouping.
- Now try your method for $2x^2 - 7x - 15$.

Key ideas

- To factorise a trinomial of the form $ax^2 + bx + c$ by grouping, find two numbers which sum to give b and multiply to give $a \times c$.
  For example:

$5x^2 + 13x - 6$
$= 5x^2 + 15x - 2x - 6$
$= 5x(x + 3) - 2(x + 3)$
$= (x + 3)(5x - 2)$

$a \times c = 5 \times (-6) = -30$ so the two numbers are 15 and -2 since $15 + (-2) = 13$ and $15 \times (-2) = -30$.

- Mentally check your factors by expanding your answer.

$(x + 3)(5x - 2)$: $5x^2$, -6, $15x$, $-2x$; $15x - 2x = 13x$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Factorising trinomials of the form $ax^2 + bx + c$

Factorise $2x^2 + 7x + 3$.

SOLUTION

$$\begin{aligned} 2x^2 + 7x + 3 &= 2x^2 + x + 6x + 3 \\ &= x(2x + 1) + 3(2x + 1) \\ &= (2x + 1)(x + 3) \end{aligned}$$

EXPLANATION

$a \times c = 2 \times 3 = 6$ then ask what factors of this number (6) add to 7. The answer is 1 and 6, so split $7x = x + 6x$. Then factorise by grouping.

Example 13 Factorising trinomials with negative numbers

Factorise the quadratic trinomials.

a $10x^2 + 9x - 9$ **b** $6x^2 - 17x + 12$

SOLUTION

a
$$\begin{aligned} 10x^2 + 9x - 9 &= 10x^2 + 15x - 6x - 9 \\ &= 5x(2x + 3) - 3(2x + 3) \\ &= (2x + 3)(5x - 3) \end{aligned}$$

b
$$\begin{aligned} 6x^2 - 17x + 12 &= 6x^2 - 9x - 8x + 12 \\ &= 3x(2x - 3) - 4(2x - 3) \\ &= (2x - 3)(3x - 4) \end{aligned}$$

EXPLANATION

$10 \times (-9) = -90$ so ask what factors of -90 add to give 9. Choose 15 and -6. Then complete the factorisation by grouping.

$6 \times 12 = 72$ so ask what factors of 72 add to give -17. Choose -9 and -8.

Complete a mental check.

$(2x - 3)(3x - 4)$

$-9x$, $-8x$

$-9x - 8x = -17x$

Exercise 8G

1, 2(½) | 2(½) | —

UNDERSTANDING

1 List the two numbers which satisfy each part.

a Multiply to give 6 and add to give 5
b Multiply to give 12 and add to give 8
c Multiply to give -10 and add to give 3
d Multiply to give -24 and add to give 5
e Multiply to give 18 and add to give -9
f Multiply to give 35 and add to give -12
g Multiply to give -30 and add to give -7
h Multiply to give -28 and add to give -3

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8G

UNDERSTANDING

2 Copy and complete.

a $2x^2 + 7x + 5 = 2x^2 + 2x + ____ + 5$
$= 2x(____) + 5(____)$
$= (____)(____)$

b $3x^2 + 8x + 4 = 3x^2 + 6x + ____ + 4$
$= 3x(____) + 2(____)$
$= (____)(____)$

c $2x^2 - 7x + 6 = 2x^2 - 3x - ____ + 6$
$= x(____) - 2(____)$
$= (____)(____)$

d $5x^2 + 9x - 2 = 5x^2 + 10x - ____ - 2$
$= 5x(____) - 1(____)$
$= (____)(____)$

e $4x^2 + 11x + 6 = 4x^2 + ____ + 3x + 6$
$= __(x + 2) + 3(____)$
$= (____)(____)$

f $6x^2 - 7x - 3 = 6x^2 - 9x + ____ - 3$
$= __(____) + 1(____)$
$= (____)(____)$

FLUENCY

3–4(½) | 3–4(½) | 3–4(½)

Example 12

3 Factorise these quadratic trinomials.

a $2x^2 + 9x + 4$ **b** $3x^2 + 7x + 2$ **c** $2x^2 + 7x + 6$
d $3x^2 + 8x + 4$ **e** $5x^2 + 12x + 4$ **f** $2x^2 + 11x + 12$
g $6x^2 + 13x + 5$ **h** $4x^2 + 5x + 1$ **i** $8x^2 + 14x + 5$

Example 13

4 Factorise these quadratic trinomials.

a $3x^2 + 2x - 5$ **b** $5x^2 + 6x - 8$ **c** $8x^2 + 10x - 3$
d $6x^2 - 13x - 8$ **e** $10x^2 - 3x - 4$ **f** $5x^2 - 11x - 12$
g $4x^2 - 16x + 15$ **h** $2x^2 - 15x + 18$ **i** $6x^2 - 19x + 10$
j $12x^2 - 13x - 4$ **k** $4x^2 - 12x + 9$ **l** $7x^2 + 18x - 9$
m $9x^2 + 44x - 5$ **n** $3x^2 - 14x + 16$ **o** $4x^2 - 4x - 15$

PROBLEM-SOLVING

5(½) | 5–6(½) | 5–6(½), 7

5 Factorise these quadratic trinomials.

a $10x^2 + 27x + 11$ **b** $15x^2 + 14x - 8$ **c** $20x^2 - 36x + 9$
d $18x^2 - x - 5$ **e** $25x^2 + 5x - 12$ **f** $32x^2 - 12x - 5$
g $27x^2 + 6x - 8$ **h** $33x^2 + 41x + 10$ **i** $54x^2 - 39x - 5$
j $12x^2 - 32x + 21$ **k** $75x^2 - 43x + 6$ **l** $90x^2 + 33x - 8$

6 Factorise by firstly taking out a common factor.

a $30x^2 - 14x - 4$ **b** $12x^2 + 18x - 30$ **c** $27x^2 - 54x + 15$
d $21x^2 - 77x + 42$ **e** $36x^2 + 36x - 40$ **f** $50x^2 - 35x - 60$

7 Factorise these trinomials.

a $-2x^2 + 7x - 6$ **b** $-5x^2 - 3x + 8$ **c** $-6x^2 + 13x + 8$
d $18 - 9x - 5x^2$ **e** $16x - 4x^2 - 15$ **f** $14x - 8x^2 - 5$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8G

8 | 8 | 8, 9

REASONING

8 When splitting the $3x$ in $2x^2 + 3x - 20$, you could write:

A $2x^2 + 8x - 5x - 20$ or **B** $2x^2 - 5x + 8x - 20$

a Complete the factorisation using **A**.

b Complete the factorisation using **B**.

c Does the order matter when you split the $3x$?

d Factorise these trinomials twice each. Factorise once by grouping then repeat but reverse the order of the two middle terms in the first line of working.

i $3x^2 + 5x - 12$ **ii** $5x^2 - 3x - 14$ **iii** $6x^2 + 5x - 4$

9 Make up five non-monic trinomials with the coefficient of x^2 not equal to 1 which factorise using the above method. Explain your method in finding these trinomials.

The cross method

— | — | 10

ENRICHMENT

10 The cross method is another way to factorise trinomials of the form $ax^2 + bx + c$. It involves finding factors of ax^2 and factors of c then choosing pairs of these factors that add to bx.

For example: Factorise $6x^2 - x - 15$.
Factors of $6x^2$ include $(x, 6x)$ and $(2x, 3x)$.
Factors of -15 include $(15, -1)$, $(-15, 1)$, $(5, -3)$ and $(-5, 3)$.

We arrange a chosen pair of factors vertically then cross-multiply and add to get $-1x$.

x 15
$6x$ -1
$x \times (-1) + 6x \times 15$
$= 89x \neq -1x$

x 5
$6x$ -3
$x \times (-3) + 6x \times 5$
$= 27x \neq -1x$

$2x$ 3 ← $(2x + 3)$
$3x$ -5 ← $(3x - 5)$
$2x \times (-5) + 3x \times 3$
$= -1x$

You will need to continue until a particular combination works. The third cross-product gives a sum of $-1x$ so choose the factors $(2x + 3)$ and $(3x - 5)$ so:

$$6x^2 - x - 15 = (2x + 3)(3x - 5)$$

Try this method on the trinomials from Questions **4** and **5**.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

8A **1** Expand the following.

a $(x + 4)(x + 2)$ **b** $(a - 5)(a + 8)$

c $(2x - 3)(x + 6)$ **d** $(3a - b)(a - 2b)$

8B **2** Expand each of the following.

a $(y + 4)^2$ **b** $(x - 3)^2$

c $(2a - 3)^2$ **d** $(7k + 2m)^2$

8B **3** Expand and simplify the following.

a $(x + 5)(x - 5)$ **b** $(11x - 9y)(11x + 9y)$

8C **4** Factorise the following.

a $25a - 15$ **b** $x^2 - 7x$

c $-12x^2 - 16x$ **d** $2(a + 3) + a(a + 3)$

e $7(8 + a) - a(8 + a)$ **f** $k(k - 4) - (k - 4)$

8D **5** Factorise each of the following.

a $x^2 - 81$ **b** $16a^2 - 49$

c $25x^2 - y^2$ **d** $2a^2 - 50$

e $12x^2y^2 - 12$ **f** $(h + 3)^2 - 64$

8E **6** Use the method of grouping to factorise these expressions.

a $x^2 + 7x + 2x + 14$

b $a^2 + 5a - 4a - 20$

c $x^2 - hx + x - h$

8E **7** Use grouping to factorise these expressions by first rearranging.

a $2x^2 - 9 - 6x + 3x$

b $3ap - 10 + 2p - 15a$

8F **8** Factorise each of the following quadratic expressions.

Ext

a $x^2 + 6x + 8$ **b** $a^2 + 2a - 15$

c $m^2 - 11m + 30$ **d** $2k^2 + 2k - 24$

8G **9** Factorise these quadratic trinomials.

Ext

a $2k^2 + 7k + 6$ **b** $2x^2 + 11x + 5$

c $3a^2 + 10a - 8$ **d** $10m^2 - 19m + 6$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8H Simplifying algebraic fractions: multiplication and division

With a numerical fraction such as $\frac{6}{9}$, the highest common factor of 6 and 9 is 3, which can be cancelled $\frac{6}{9} = \frac{{}^{1}\cancel{3} \times 2}{{}_{1}\cancel{3} \times 3} = \frac{2}{3}$. For algebraic fractions the process is the same. If expressions are in a factorised form, common factors can be easily identified and cancelled.

Let's start: Correct cancelling

Consider this cancelling attempt:

$$\frac{5x + \cancel{10}^{1}}{\cancel{20}_{2}} = \frac{5x + 1}{2}$$

- Substitute $x = 6$ into the left-hand side to evaluate $\frac{5x + 10}{20}$.
- Substitute $x = 6$ into the right-hand side to evaluate $\frac{5x + 1}{2}$.
- What do you notice about the two answers to the above? How can you explain this?
- Decide how you might correctly cancel the expression on the left-hand side. Show your steps and check by substituting a value for x.

Key ideas

- Simplify **algebraic fractions** by factorising and cancelling only common factors.

Incorrect

$$\frac{2x + \cancel{4}^{2}}{\cancel{2}^{1}} = 2x + 2$$

Correct

$$\frac{2x + 4}{2} = \frac{{}^{1}\cancel{2}(x + 2)}{\cancel{2}^{1}}$$
$$= x + 2$$

- To multiply algebraic fractions:
  - factorise expressions where possible
  - cancel if possible
  - multiply the numerators and the denominators.
- To divide algebraic fractions:
  - multiply by the reciprocal of the fraction following the division sign
  - follow the rules for multiplication after converting to the reciprocal
    - The reciprocal of $\frac{a}{b}$ is $\frac{b}{a}$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 14 Simplifying algebraic fractions

Simplify the following by cancelling.

a $\dfrac{3(x+2)(x-4)}{6(x-4)}$ **b** $\dfrac{20-5x}{8-2x}$ **c** $\dfrac{x^2-4}{x+2}$

SOLUTION

a $\dfrac{{}^{1}\cancel{3}(x+2)\cancel{(x-4)}^{1}}{{}^{2}\cancel{6}\cancel{(x-4)}^{1}} = \dfrac{x+2}{2}$

b $\dfrac{20-5x}{8-2x} = \dfrac{5\cancel{(4-x)}^{1}}{2\cancel{(4-x)}^{1}}$

$= \dfrac{5}{2}$

c $\dfrac{x^2-4}{x+2} = \dfrac{{}^{1}\cancel{(x+2)}(x-2)}{\cancel{(x+2)}_{1}}$

$= x-2$

EXPLANATION

Cancel the common factors $(x-4)$ and 3.

Factorise the numerator and denominator then cancel common factor of $(4-x)$.

Factorise the difference of squares in the numerator then cancel the common factor.

Example 15 Multiplying and dividing algebraic fractions

Simplify the following.

a $\dfrac{3(x-1)}{(x+2)} \times \dfrac{4(x+2)}{9(x-1)(x-7)}$ **b** $\dfrac{(x-3)(x+4)}{x(x+7)} \div \dfrac{3(x+4)}{x+7}$ **c** $\dfrac{x^2-4}{25} \times \dfrac{5x+5}{x^2-x-2}$ Ext

SOLUTION

a $\dfrac{{}^{1}\cancel{3}\cancel{(x-1)}^{1}}{\cancel{(x+2)}_{1}} \times \dfrac{4\cancel{(x+2)}^{1}}{{}_{3}\cancel{9}\cancel{(x-1)}_{1}(x-7)}$

$= \dfrac{1 \times 4}{1 \times 3(x-7)}$

$= \dfrac{4}{3(x-7)}$

b $\dfrac{(x-3)(x+4)}{x(x+7)} \div \dfrac{3(x+4)}{x+7}$

$= \dfrac{(x-3)\cancel{(x+4)}^{1}}{x\cancel{(x+7)}_{1}} \times \dfrac{\cancel{(x+7)}^{1}}{3\cancel{(x+4)}^{1}}$

$= \dfrac{x-3}{3x}$

EXPLANATION

First, cancel any factors in the numerators with a common factor in the denominators. Then multiply the numerators and the denominators.

Multiply by the reciprocal of the fraction after the division sign.

Cancel common factors and multiply remaining numerators and denominators.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c $\dfrac{x^2-4}{25} \times \dfrac{5x+5}{x^2-x-2}$

$= \dfrac{{}^{1}\cancel{(x-2)}(x+2)}{\cancel{25}^{5}} \times \dfrac{5^{1}(x+1)^{1}}{{}_{1}\cancel{(x-2)}\,\cancel{(x+1)}_{1}}$

$= \dfrac{x+2}{5}$

First factorise all the algebraic expressions. Note that $x^2 - 4$ is a difference of perfect squares. Then cancel as normal.

Exercise 8H

1–3 | 3 | —

UNDERSTANDING

1 Simplify these fractions by cancelling.

a $\dfrac{5}{15}$ **b** $\dfrac{24}{16}$ **c** $\dfrac{5x}{10}$ **d** $\dfrac{42x}{12}$

e $\dfrac{24}{8x}$ **f** $\dfrac{9}{18x}$ **g** $\dfrac{3(x+1)}{6}$ **h** $\dfrac{22(x-4)}{11}$

2 Factorise these by taking out common factors.

a $3x + 6$ **b** $20 - 40x$ **c** $x^2 - 7x$ **d** $6x^2 + 24x$

3 Copy and complete.

a $\dfrac{2x-4}{8} = \dfrac{2(\quad)}{8}$

$= \dfrac{\quad}{4}$

b $\dfrac{12-18x}{2x-3x^2} = \dfrac{6(\quad)}{x(\quad)}$

$= \dfrac{6}{x}$

c $\dfrac{x-1}{x+3} \div \dfrac{2(x-1)}{(x+3)(x+2)} = \dfrac{x-1}{x+3} \times$ _____

$= \dfrac{x+2}{2}$

4–8(½) | 4–9(½) | 5–9(½)

FLUENCY

Example 14a

4 Simplify the following by cancelling.

a $\dfrac{3(x+2)}{4(x+2)}$ **b** $\dfrac{x(x-3)}{3x(x-3)}$ **c** $\dfrac{20(x+7)}{5(x+7)}$

d $\dfrac{(x+5)(x-5)}{(x+5)}$ **e** $\dfrac{6(x-1)(x+3)}{9(x+3)}$ **f** $\dfrac{8(x-2)}{4(x-2)(x+4)}$

Example 14b

5 Simplify the following by factorising and then cancelling.

a $\dfrac{5x-5}{5}$ **b** $\dfrac{4x-12}{10}$ **c** $\dfrac{2x-4}{3x-6}$ **d** $\dfrac{12-4x}{6-2x}$

e $\dfrac{x^2-3x}{x}$ **f** $\dfrac{4x^2+10x}{5x}$ **g** $\dfrac{3x+3y}{2x+2y}$ **h** $\dfrac{4x-8y}{3x-6y}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8H

FLUENCY

Example 14c

6 Simplify the following. These expressions involve difference of perfect squares.

a $\frac{x^2 - 100}{x + 10}$ **b** $\frac{x^2 - 49}{x + 7}$ **c** $\frac{x^2 - 25}{x + 5}$

d $\frac{2(x - 20)}{x^2 - 400}$ **e** $\frac{5(x - 6)}{x^2 - 36}$ **f** $\frac{3x + 27}{x^2 - 81}$

Example 15a

7 Simplify the following by cancelling.

a $\frac{2x(x - 4)}{4(x + 1)} \times \frac{(x + 1)}{x}$ **b** $\frac{(x + 2)(x - 3)}{x - 5} \times \frac{x - 5}{x + 2}$

c $\frac{x - 3}{x + 2} \times \frac{3(x + 4)(x + 2)}{x + 4}$ **d** $\frac{2(x + 3)(x + 4)}{(x + 1)(x - 5)} \times \frac{(x + 1)}{4(x + 3)}$

Example 15b

8 Simplify the following by cancelling.

a $\frac{x(x + 1)}{x + 3} \div \frac{x + 1}{x + 3}$ **b** $\frac{x + 3}{x + 2} \div \frac{x + 3}{2(x - 2)}$

c $\frac{x - 4}{(x + 3)(x + 1)} \div \frac{x - 4}{4(x + 3)}$ **d** $\frac{4x}{x + 2} \div \frac{8x}{x - 2}$

e $\frac{3(4x - 9)(x + 2)}{2(x + 6)} \div \frac{9(x + 4)(4x - 9)}{4(x + 2)(x + 6)}$ **f** $\frac{5(2x - 3)}{(x + 7)} \div \frac{(x + 2)(2x - 3)}{x + 7}$

Ext

9 Simplify by firstly factorising.

a $\frac{x^2 - x - 6}{x - 3}$ **b** $\frac{x^2 + 8x + 16}{x + 4}$ **c** $\frac{x^2 - 7x + 12}{x - 4}$

d $\frac{x - 2}{x^2 + x - 6}$ **e** $\frac{x + 7}{x^2 + 5x - 14}$ **f** $\frac{x - 9}{x^2 - 19x + 90}$

10(½) 10 10

PROBLEM-SOLVING

Example 15c

Ext

10 These expressions involve a combination of trinomials, difference of perfect squares and simple common factors. Simplify by firstly factorising where possible.

a $\frac{x^2 + 5x + 6}{x + 5} \div \frac{x + 3}{x^2 - 25}$ **b** $\frac{x^2 + 6x + 8}{x^2 - 9} \div \frac{x + 4}{x - 3}$

c $\frac{x^2 + x - 12}{x^2 + 8x + 16} \times \frac{x^2 - 16}{x^2 - 8x + 16}$ **d** $\frac{x^2 + 12x + 35}{x^2 - 25} \times \frac{x^2 - 10x + 25}{x^2 + 9x + 14}$

e $\frac{9x^2 - 3x}{6x - 45x^2}$ **f** $\frac{x^2 - 4x}{3x - x^2}$

g $\frac{3x^2 - 21x + 36}{2x^2 - 32} \times \frac{2x + 10}{6x - 18}$ **h** $\frac{2x^2 - 18x + 40}{x^2 - x - 12} \times \frac{3x + 15}{4x^2 - 100}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8H

11(½) | 11 | 11, 12

REASONING

11 The expression $\frac{5-2x}{2x-5}$ can be written in the form $\frac{-1(-5+2x)}{2x-5} = \frac{-1(2x-5)}{2x-5}$, which can be cancelled to –1.
Use this idea to simplify these algebraic fractions.

a $\frac{7-3x}{3x-7}$ **b** $\frac{4x-1}{1-4x}$ **c** $\frac{8x+16}{-2-x}$

d $\frac{x+3}{-9-3x}$ **e** $\frac{5-3x}{18x-30}$ **f** $\frac{x^2-9}{3-x}$

12 Just like $\frac{a^2}{2a}$ can be cancelled to $\frac{a}{2}$, $\frac{(a+5)^2}{2(a+5)}$ cancels to $\frac{a+5}{2}$. Use this idea to cancel these fractions.

a $\frac{(a+1)^2}{(a+1)}$ **b** $\frac{5(a-3)^2}{(a-3)}$ **c** $\frac{7(x+7)^2}{14(x+7)}$

d $\frac{3(x-1)(x+2)^2}{18(x-1)(x+2)}$ Ext **e** $\frac{x^2+6x+9}{2x+6}$ Ext **f** $\frac{11x-22}{x^2-4x+4}$

All in together | — | — | 13

ENRICHMENT

Ext **13** Use your knowledge of factorisation and the ideas in Questions **11** and **12** above to simplify these algebraic fractions.

a $\frac{2x^2-2x-24}{16-4x}$ **b** $\frac{x^2-14x+49}{21-3x}$

c $\frac{x-16x+64}{64-x^2}$ **d** $\frac{4-x^2}{x^2+x-6} \times \frac{2x+6}{x+4x+4}$

e $\frac{2x^2-18}{x^2-6x+9} \times \frac{6-2x}{x^2+6x+9}$ **f** $\frac{x^2-2x+1}{4-4x} \div \frac{1-x^2}{3x^2+6x+3}$

g $\frac{4x^2-9}{x^2-5x} \div \frac{6-4x}{15-3x}$ **h** $\frac{x^2-4x+4}{8-4x} \times \frac{-2}{4-x^2}$

i $\frac{(x+2)^2-4}{(1-x)^2} \times \frac{x^2-2x+1}{3x+12}$ **j** $\frac{2(x-3)^2-50}{x^2-11x+24} \div \frac{x^2-4}{3-x}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8I Simplifying algebraic fractions: addition and subtraction

The process required for adding or subtracting algebraic fractions is similar to that used for fractions without pronumerals.

To simplify $\frac{2}{3}+\frac{4}{5}$, for example, you would find the lowest common multiple of the denominators (15) then express each fraction using this denominator. Adding the numerators completes the task.



Although algebraic fractions seem abstract, performing operations on them and simplifying them is essential to many calculations in real-life mathematical problems.

Let's start: Compare the working

Here is the working for the simplification of the sum of a pair of numerical fractions and the sum of a pair of algebraic fractions.

$$\frac{2}{5}+\frac{3}{4}=\frac{8}{20}+\frac{15}{20}$$
$$=\frac{23}{20}$$

$$\frac{2x}{5}+\frac{3x}{4}=\frac{8x}{20}+\frac{15x}{20}$$
$$=\frac{23x}{20}$$

- What type of steps were taken to simplify the algebraic fractions that are the same as for the numerical fractions?
- Write down the steps required to add (or subtract) algebraic fractions.

Key ideas

- To add or subtract algebraic fractions:
  - determine the lowest common denominator (LCD)
  - express each fraction using the LCD
  - add or subtract the numerators.

Example 16 Adding and subtracting with numerals in the denominators

Simplify:

a $\frac{x}{4}-\frac{2x}{5}$ b $\frac{7x}{3}+\frac{x}{6}$ c $\frac{x+3}{2}+\frac{x-2}{5}$

SOLUTION	EXPLANATION
a $\frac{x}{4}-\frac{2x}{5}=\frac{5x}{20}-\frac{8x}{20}$ $=-\frac{3x}{20}$	Determine the LCD of 4 and 5, i.e. 20. Express each fraction as an equivalent fraction with a denominator of 20. $2x\times4=8x$. Then subtract numerators.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $\frac{7x}{3} + \frac{x}{6} = \frac{14x}{6} + \frac{x}{6}$

$= \frac{15x}{6}$

$= \frac{5x}{2}$

Note the LCD of 3 and 6 is 6 not $3 \times 6 = 18$.

Simplify $\frac{15}{6}$ to $\frac{5}{2}$ in the final step.

c $\frac{x+3}{2} + \frac{x-2}{5} = \frac{5(x+3)}{10} + \frac{2(x-2)}{10}$

$= \frac{5x + 15 + 2x - 4}{10}$

$= \frac{7x + 11}{10}$

The LCD of 2 and 5 is 10, write as equivalent fractions with denominator 10.

Expand the brackets and simplify the numerator by adding and collecting like terms.

Example 17 Adding and subtracting with algebraic terms in the denominators

Simplify:

a $\frac{2}{x} - \frac{5}{2x}$ **b** $\frac{2}{x} + \frac{3}{x^2}$

SOLUTION **EXPLANATION**

a $\frac{2}{x} - \frac{5}{2x} = \frac{4}{2x} - \frac{5}{2x}$

$= -\frac{1}{2x}$

The LCD of x and $2x$ is $2x$, so rewrite the first fraction in an equivalent form with a denominator also of $2x$.

b $\frac{2}{x} + \frac{3}{x^2} = \frac{2x}{x^2} + \frac{3}{x^2}$

$= \frac{2x + 3}{x^2}$

The LCD of x and x^2 is x^2 so change the first fraction so its denominator is also x^2, then add numerators.

Exercise 8I

1–4 | 3 | —

UNDERSTANDING

1 Find the lowest common multiple of these pairs of numbers.

a (6, 8) **b** (3, 5) **c** (11, 13) **d** (12, 18)

2 Write equivalent fractions by stating the missing expression.

a $\frac{2x}{5} = \frac{\square}{10}$ **b** $\frac{7x}{3} = \frac{\square}{9}$ **c** $\frac{x+1}{4} = \frac{\square(x+1)}{12}$

d $\frac{3x+5}{11} = \frac{\square(3x+5)}{22}$ **e** $\frac{4}{x} = \frac{\square}{2x}$ **f** $\frac{30}{x+1} = \frac{\square}{3(x+1)}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8I

UNDERSTANDING

3 Copy and complete these simplifications.

a $\frac{x}{4}+\frac{2x}{3}=\frac{\square}{12}+\frac{\square}{12}=\frac{\square}{12}$

b $\frac{5x}{7}-\frac{2x}{5}=\frac{\square}{35}-\frac{\square}{35}=\frac{\square}{35}$

c $\frac{x+1}{2}+\frac{2x+3}{4}=\frac{\square(x+1)}{4}+\frac{2x+3}{4}=\frac{\square\ +2x+3}{4}=\frac{\square}{4}$

4 Write down the LCD for these pairs of fractions.

a $\frac{x}{3},\frac{2x}{5}$ **b** $\frac{3x}{7},\frac{x}{2}$ **c** $\frac{-5x}{4},\frac{x}{8}$ **d** $\frac{2x}{3},\frac{-5x}{6}$ **e** $\frac{7x}{10},\frac{-3x}{5}$

FLUENCY

5–6(½) 5–7(½) 5–7(½)

Example 16a Example 16b

5 Simplify:

a $\frac{x}{7}+\frac{x}{2}$ **b** $\frac{x}{3}+\frac{x}{15}$ **c** $\frac{x}{4}-\frac{x}{8}$ **d** $\frac{x}{9}+\frac{x}{5}$

e $\frac{y}{7}-\frac{y}{8}$ **f** $\frac{a}{2}+\frac{a}{11}$ **g** $\frac{b}{3}-\frac{b}{9}$ **h** $\frac{m}{3}-\frac{m}{6}$

i $\frac{m}{6}+\frac{3m}{4}$ **j** $\frac{a}{4}+\frac{2a}{7}$ **k** $\frac{2x}{5}+\frac{x}{10}$ **l** $\frac{p}{9}-\frac{3p}{7}$

m $\frac{b}{2}-\frac{7b}{9}$ **n** $\frac{9y}{8}+\frac{2y}{5}$ **o** $\frac{4x}{7}-\frac{x}{5}$ **p** $\frac{3x}{4}-\frac{x}{3}$

Example 16c

6 Simplify:

a $\frac{x+1}{2}+\frac{x+3}{5}$ **b** $\frac{x+3}{3}+\frac{x-4}{4}$ **c** $\frac{a-2}{7}+\frac{a-5}{8}$

d $\frac{y+4}{5}+\frac{y-3}{6}$ **e** $\frac{m-4}{8}+\frac{m+6}{5}$ **f** $\frac{x-2}{12}+\frac{x-3}{8}$

g $\frac{2b-3}{6}+\frac{b+2}{8}$ **h** $\frac{3x+8}{6}+\frac{2x-4}{3}$ **i** $\frac{2y-5}{7}+\frac{3y+2}{14}$

j $\frac{2t-1}{8}+\frac{t-2}{16}$ **k** $\frac{4-x}{3}+\frac{2-x}{7}$ **l** $\frac{2m-1}{4}+\frac{m-3}{6}$

Example 17a

7 Simplify:

a $\frac{3}{x}+\frac{5}{2x}$ **b** $\frac{7}{3x}-\frac{2}{x}$ **c** $\frac{7}{4x}-\frac{5}{2x}$ **d** $\frac{4}{3x}+\frac{2}{9x}$

e $\frac{3}{4x}-\frac{2}{5x}$ **f** $\frac{2}{3x}+\frac{1}{5x}$ **g** $\frac{-3}{4x}-\frac{7}{x}$ **h** $\frac{-5}{3x}-\frac{3}{4x}$

PROBLEM-SOLVING

8(½) 8–9(½) 8–10(½)

Example 17b

8 Simplify:

a $\frac{3}{x}+\frac{2}{x^2}$ **b** $\frac{5}{x^2}+\frac{4}{x}$ **c** $\frac{7}{x}+\frac{3}{x^2}$ **d** $\frac{4}{x}-\frac{5}{x^2}$

e $\frac{3}{x^2}-\frac{8}{x}$ **f** $-\frac{4}{x^2}+\frac{1}{x}$ **g** $\frac{3}{x}-\frac{7}{2x^2}$ **h** $-\frac{2}{3x}+\frac{3}{x^2}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8I

PROBLEM-SOLVING

9 Simplify these mixed algebraic fractions.

a $\frac{2}{x}+\frac{x}{4}$ **b** $\frac{-5}{x}+\frac{x}{2}$ **c** $\frac{-2}{x}-\frac{4x}{3}$ **d** $\frac{3}{2x}-\frac{5x}{4}$

e $\frac{3x}{4}-\frac{5}{6x}$ **f** $\frac{1}{3x}-\frac{x}{9}$ **g** $-\frac{2}{5x}+\frac{3x}{2}$ **h** $-\frac{5}{4x}-\frac{3x}{10}$

10 Find the missing algebraic fraction. The fraction should be in simplest form.

a $\frac{x}{2}+\frac{\square}{\square}=\frac{5x}{6}$ **b** $\frac{\square}{\square}+\frac{x}{4}=\frac{3x}{8}$ **c** $\frac{2x}{5}+\frac{\square}{\square}=\frac{9x}{10}$

d $\frac{2x}{3}-\frac{\square}{\square}=\frac{7x}{15}$ **e** $\frac{\square}{\square}-\frac{x}{3}=\frac{5x}{9}$ **f** $\frac{2x}{3}-\frac{\square}{\square}=\frac{5x}{12}$

11 | 11, 12 | 11, 12

REASONING

11 Find and describe the error in each set of working. Then find the correct answer.

a $\frac{4x}{5}-\frac{x}{3}=\frac{3x}{2}$

b $\frac{x+1}{5}+\frac{x}{2}=\frac{2x+1}{10}+\frac{5x}{10}$

$=\frac{7x+1}{10}$

c $\frac{5x}{3}+\frac{x-1}{2}=\frac{10x}{6}+\frac{3x-1}{6}$

$=\frac{13x-1}{6}$

d $\frac{2}{x}-\frac{3}{x^2}=\frac{2}{x^2}-\frac{3}{x^2}$

$=\frac{-1}{x^2}$

12 A student thinks that the LCD to use when simplifying $\frac{x+1}{2}+\frac{2x-1}{4}$ is 8.

a Complete the simplification using a common denominator of 8.

b Now complete the simplification using the actual LCD of 4.

c How does your working for parts **a** and **b** compare? Which method is preferable and why?

More than two fractions! — | — | 13

ENRICHMENT

13 Simplify by finding the LCD.

a $\frac{2x}{5}-\frac{3x}{2}-\frac{x}{3}$ **b** $\frac{x}{4}-\frac{2x}{3}+\frac{5x}{6}$ **c** $\frac{5x}{8}-\frac{5x}{6}+\frac{3x}{4}$

d $\frac{x+1}{4}+\frac{2x-1}{3}-\frac{x}{5}$ **e** $\frac{2x-1}{3}-\frac{2x}{7}+\frac{x-3}{6}$ **f** $\frac{1-2x}{5}-\frac{3x}{8}+\frac{3x+1}{2}$

g $\frac{2}{3x}+\frac{5}{x}-\frac{1}{x}$ **h** $-\frac{1}{2x}+\frac{2}{x}-\frac{4}{3x}$ **i** $-\frac{4}{5x}-\frac{1}{2x}+\frac{3}{4x}$

j $\frac{4}{x^2}+\frac{3}{2x}-\frac{5}{3x}$ **k** $\frac{5}{x}-\frac{3}{2x^2}-\frac{5}{7x}$ **l** $\frac{2}{x^2}-\frac{4}{9x}-\frac{5}{3x^2}$

m $\frac{2}{x}+\frac{x}{5}-\frac{x}{3}$ **n** $\frac{3x}{2}-\frac{1}{2x}+\frac{x}{3}$ **o** $-\frac{4x}{9}+\frac{2}{5x}+\frac{2x}{5}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8J Further simplification of algebraic fractions

EXTENDING

More complex addition and subtraction of algebraic fractions involves expressions like:

$$\frac{2x-1}{3}-\frac{x+4}{4} \text{ and } \frac{2}{x-3}-\frac{5}{(x-3)^2}$$

In such examples, care needs to be taken at each step in the working to avoid common errors.

Let's start: Three critical errors

The following simplification of algebraic fractions has three critical errors. Can you find them?

$$\frac{2x+1}{3}-\frac{x+2}{2}=\frac{2x+1}{6}-\frac{3(x+2)}{6}$$
$$=\frac{2x+1-3x+6}{6}$$
$$=\frac{x+7}{6}$$

The correct answer is $\frac{x-4}{6}$.

Fix the solution to produce the correct answer.

Key ideas

- When combining algebraic fractions which involve subtraction signs, recall that:
  - the product of two numbers of opposite sign is a negative number
  - the product of two negative numbers is a positive number.

  For example: $\frac{2(x-1)}{6}-\frac{3(x+2)}{6}=\frac{2x-2-3x-6}{6}$

  and $\frac{5(1-x)}{8}-\frac{2(x-1)}{8}=\frac{5-5x-2x+2}{8}$

- A common denominator can be a product of two binomial terms.

  For example: $\frac{2}{x+3}+\frac{3}{x-1}=\frac{2(x-1)}{(x+3)(x-1)}+\frac{3(x+3)}{(x+3)(x-1)}$

  $$=\frac{2x-2+3x+9}{(x+3)(x-1)}$$
  $$=\frac{5x+7}{(x+3)(x-1)}$$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 18 Simplifying with more complex numerators

Simplify:

a $\frac{x-1}{3}-\frac{x+4}{5}$

b $\frac{2x-3}{6}-\frac{3-x}{5}$

SOLUTION

EXPLANATION

a $\frac{x-1}{3}-\frac{x+4}{5}=\frac{5(x-1)}{15}-\frac{3(x+4)}{15}$

$=\frac{5x-5-3x-12}{15}$

$=\frac{2x-17}{15}$

The LCD of 3 and 5 is 15. Insert brackets around each numerator when multiplying.

Note: $-3(x+4)=-3x-12$ not $-3x+12$.

b $\frac{2x-3}{6}-\frac{3-x}{5}=\frac{5(2x-3)}{30}-\frac{6(3-x)}{30}$

$=\frac{10x-15-18+6x}{30}$

$=\frac{16x-33}{30}$

Determine the LCD and express as equivalent fractions. Insert brackets.

Expand the brackets, recall $-6\times(-x)=6x$ and then simplify the numerator.

Example 19 Simplifying with more complex denominators

Simplify:

a $\frac{4}{x+1}+\frac{3}{x-2}$

b $\frac{3}{(x-1)^2}-\frac{2}{x-1}$

SOLUTION

EXPLANATION

a $\frac{4}{x+1}+\frac{3}{x-2}$

$=\frac{4(x-2)}{(x+1)(x-2)}+\frac{3(x+1)}{(x+1)(x-2)}$

$=\frac{4x-8+3x+3}{(x+1)(x-2)}$

$=\frac{7x-5}{(x+1)(x-2)}$

The lowest common multiple of $(x+1)$ and $(x-2)$ is $(x+1)(x-2)$. Rewrite each fraction as an equivalent fraction with this denominator then add numerators.

b $\frac{3}{(x-1)^2}-\frac{2}{x-1}=\frac{3}{(x-1)^2}-\frac{2(x-1)}{(x-1)^2}$

$=\frac{3-2x+2}{(x-1)^2}$

$=\frac{5-2x}{(x-1)^2}$

Just like the LCD of 3^2 and 3 is 3^2, the LCD of $(x-1)^2$ and $x-1$ is $(x-1)^2$.

Remember that $-2(x-1)=-2x+2$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 8J

1, 2 | 2(½) | —

UNDERSTANDING

1 Expand the following.

a $-2(x+3)$ **b** $-5(x+1)$ **c** $-7(2+3x)$

d $-3(x-1)$ **e** $-10(3-2x)$ **f** $-16(1-4x)$

2 Write the LCD for these pairs of fractions.

a $\frac{1}{3}, \frac{5}{9}$ **b** $\frac{3}{16}, \frac{1}{8}$ **c** $\frac{3}{x}, \frac{5}{x^2}$ **d** $-\frac{5}{2x}, \frac{3}{2}$

e $\frac{3}{x-1}, \frac{2}{x+1}$ **f** $\frac{7}{x-2}, \frac{3}{x+3}$ **g** $\frac{4}{2x-1}, \frac{-1}{x-4}$ **h** $\frac{5}{(x+1)^2}, \frac{4}{x+1}$

3–5(½) | 3–5(½) | 3–5(½)

FLUENCY

Example 18a

3 Simplify:

a $\frac{x+3}{4} - \frac{x+2}{3}$ **b** $\frac{x-1}{3} - \frac{x+3}{5}$ **c** $\frac{x-4}{3} - \frac{x+1}{6}$

d $\frac{3-x}{5} - \frac{x+4}{2}$ **e** $\frac{5x-1}{4} - \frac{2+x}{8}$ **f** $\frac{3x+2}{14} - \frac{x+4}{4}$

g $\frac{1+3x}{4} - \frac{2x+3}{6}$ **h** $\frac{2-x}{5} - \frac{3x+1}{3}$ **i** $\frac{2x-3}{6} - \frac{4+x}{15}$

Example 18b

4 Simplify:

a $\frac{x+5}{3} - \frac{x-1}{2}$ **b** $\frac{x-4}{5} - \frac{x-6}{7}$ **c** $\frac{3x-7}{4} - \frac{x-1}{2}$

d $\frac{5x-9}{7} - \frac{2-x}{3}$ **e** $\frac{3x+2}{4} - \frac{5-x}{10}$ **f** $\frac{9-4x}{6} - \frac{2-x}{8}$

g $\frac{4x+3}{3} - \frac{5-2x}{9}$ **h** $\frac{2x-1}{4} - \frac{1-3x}{14}$ **i** $\frac{3x-2}{8} - \frac{4x-3}{7}$

Example 19a

5 Simplify:

a $\frac{3}{x-1} + \frac{4}{x+1}$ **b** $\frac{5}{x+4} + \frac{2}{x-3}$ **c** $\frac{3}{x-2} + \frac{4}{x+3}$

d $\frac{3}{x-4} + \frac{2}{x+7}$ **e** $\frac{7}{x+2} - \frac{3}{x+3}$ **f** $\frac{3}{x+4} - \frac{2}{x-6}$

g $\frac{-1}{x+5} + \frac{2}{x+1}$ **h** $\frac{-2}{x-3} - \frac{4}{x-2}$ **i** $\frac{3}{x-5} - \frac{5}{x-6}$

6(½) | 6–7(½) | 6–7(½)

PROBLEM-SOLVING

Example 19b

6 Simplify:

a $\frac{4}{(x+1)^2} - \frac{3}{x+1}$ **b** $\frac{2}{(x+3)^2} - \frac{4}{x+3}$ **c** $\frac{3}{x-2} + \frac{4}{(x-2)^2}$

d $\frac{-2}{x-5} + \frac{8}{(x-5)^2}$ **e** $\frac{-1}{x-6} + \frac{3}{(x-6)^2}$ **f** $\frac{2}{(x-4)^2} - \frac{3}{x-4}$

g $\frac{5}{(2x+1)^2} + \frac{2}{2x+1}$ **h** $\frac{9}{(3x+2)^2} - \frac{4}{3x+2}$ **i** $\frac{4}{(1-4x)^2} - \frac{5}{1-4x}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8J

PROBLEM-SOLVING

7 Simplify:

a $\frac{3x}{(x-1)^2} + \frac{2}{x-1}$ **b** $\frac{3x+2}{3x} + \frac{7}{12}$ **c** $\frac{2x-1}{4} + \frac{2-3x}{10x}$

d $\frac{2x}{x-5} - \frac{x}{x+1}$ **e** $\frac{3}{4-x} - \frac{2x}{x-1}$ **f** $\frac{5x+1}{(x-3)^2} + \frac{x}{x-3}$

g $\frac{3x-7}{(x-2)^2} - \frac{5}{x-2}$ **h** $\frac{-7x}{2x+1} + \frac{3x}{x+2}$ **i** $\frac{x}{x+1} - \frac{5x+1}{(x+1)^2}$

8	8, 9(½)	9, 10(½)

REASONING

8 One of the most common errors made when subtracting algebraic fractions is hidden in this working shown on the right.

$$\frac{7x}{2} - \frac{x-2}{5} = \frac{35x}{10} - \frac{2(x-2)}{10}$$
$$= \frac{35x - 2x - 4}{10}$$
$$= \frac{33x - 4}{10}$$

a What is the error and in which step is it made?

b By correcting the error how does the answer change?

9 Simplify:

a $\frac{1}{(x+3)(x+4)} + \frac{2}{(x+4)(x+5)}$ **b** $\frac{3}{(x+1)(x+2)} - \frac{5}{(x+1)(x+4)}$

c $\frac{4}{(x-1)(x-3)} - \frac{6}{(x-1)(2-x)}$ **d** $\frac{5x}{(x+1)(x-5)} - \frac{2}{x-5}$

e $\frac{3}{x-4} + \frac{8x}{(x-4)(3-2x)}$ **f** $\frac{3x}{(x+4)(2x-1)} - \frac{x}{(x+4)(3x+2)}$

10 Use the fact that $a - b = -1(b - a)$ to help simplify these.

a $\frac{3}{1-x} - \frac{2}{x-1}$ **b** $\frac{4x}{5-x} + \frac{3}{x-5}$ **c** $\frac{2}{7x-3} - \frac{7}{3-7x}$

d $\frac{1}{4-3x} + \frac{2x}{3x-4}$ **e** $\frac{-3x}{5-3x} - \frac{5}{3x-5}$ **f** $\frac{4}{x-6} + \frac{4}{6-x}$

Factorise first

—	—	11

ENRICHMENT

11 Factorising a denominator before further simplification is a useful step. Simplify these by firstly factorising the denominators if possible.

a $\frac{3}{x+2} + \frac{5}{2x+4}$ **b** $\frac{7}{3x-3} - \frac{2}{x-1}$

c $\frac{3}{8x-4} - \frac{5}{1-2x}$ **d** $\frac{4}{x^2-9} - \frac{3}{x+3}$

e $\frac{5}{2x+4} + \frac{2}{x^2-4}$ **f** $\frac{10}{3x-4} - \frac{7}{9x^2-16}$

g $\frac{7}{x^2+7x+12} + \frac{2}{x^2-2x-15}$ **h** $\frac{3}{(x+1)^2-4} - \frac{2}{x^2+6x+9}$

i $\frac{3}{x^2-7x+10} - \frac{2}{10-5x}$ **j** $\frac{1}{x^2+x} - \frac{1}{x^2-x}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8K Equations with algebraic fractions EXTENDING

For equations with more than one fraction it is often best to try to simplify the equation by dealing with all the denominators at once. This involves finding and multiplying both sides by the lowest common denominator.

Let's start: Why use the LCD?

For this equation follow each instruction.

$$\frac{x+1}{3}+\frac{x}{4}=1$$

- Multiply every term in the equation by 3. What effect does this have on the fractions on the left-hand side?
- Starting with the original equation, multiply every term in the equation by 4. What effect does this have on the fractions on the left-hand side?
- Starting with the original equation, multiply every term in the equation by 12 and simplify.

Which instruction above does the best job in simplifying the algebraic fractions? Why?

Key ideas

- For equations with more than one fraction multiply both sides by the **lowest common denominator (LCD)**.
  - Multiply every term on both sides, not just the fractions.
  - Simplify the fractions and solve the equation using the methods learnt earlier.
- Alternatively, express each fraction using the same denominator then simplify by adding or subtracting and solve.

Example 20 Solving equations involving algebraic fractions

Solve each of the following equations.

a $\frac{2x}{3}+\frac{x}{2}=7$

b $\frac{x-2}{5}-\frac{x-1}{3}=1$

c $\frac{5}{2x}-\frac{4}{3x}=2$

d $\frac{3}{x+1}=\frac{2}{x+4}$

SOLUTION	EXPLANATION
a $\frac{2x}{3}+\frac{x}{2}=7$	
$\frac{2x}{\cancel{3}_1}\times\cancel{6}^{2}+\frac{x}{\cancel{2}_1}\times\cancel{6}^{3}=7\times 6$	Multiply each term by the LCD (LCD of 3 and 2 is 6) and cancel.
$4x+3x=42$	
$7x=42$	Simplify and solve for x.
$x=6$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

OR $\frac{2x}{3}+\frac{x}{2}=7$

$\frac{4x}{6}+\frac{3x}{6}=7$

$\frac{7x}{6}=7$

$7x=42$

$x=6$

Alternatively, write each term on the left-hand side using the LCD = 6.
Simplify by adding the numerators and solve the remaining equation.

b $\frac{x-2}{5}-\frac{x-1}{3}=1$

$\frac{15^{3}(x-2)}{5_{1}}-\frac{15^{5}(x-1)}{3_{1}}=1\times 15$

$3(x-2)-5(x-1)=15$

$3x-6-5x+5=15$

$-2x-1=15$

$-2x=16$

$x=-8$

Multiply each term on both sides by 15 (LCD of 3 and 5 is 15) and cancel.

Expand the brackets and simplify by combining like terms. Note: $-5(x-1)=-5x+5$ not $-5x-5$.

(Alternatively, write each term using the LCD = 15 then combine the numerators and solve $\frac{3(x-2)}{15}-\frac{5(x-1)}{15}=1$).

c $\frac{5}{2x}-\frac{4}{3x}=2$

$\frac{5}{2x_{1}}\times 6x^{3}-\frac{4}{3x_{1}}\times 6x^{2}=2\times 6x$

$15-8=12x$

$7=12x$

$x=\frac{7}{12}$

LCD of $2x$ and $3x$ is $6x$.

Multiply each term by $6x$. Cancel and simplify.

Solve for x leaving the answer in fraction form.

(Alternative solution: $\frac{15}{6x}-\frac{8}{6x}=2$)

d $\frac{3}{x+1}=\frac{2}{x+4}$

$\frac{3(x+1)(x+4)}{(x+1)}=\frac{2(x+1)(x+4)}{(x+4)}$

$3(x+4)=2(x+1)$

$3x+12=2x+2$

$x+12=2$

$x=-10$

Multiply each term by the common denominator $(x+1)(x+4)$.

Expand the brackets.

Subtract $2x$ from both sides to gather x terms on one side then subtract 12 from both sides.

OR $\frac{3}{x+1}=\frac{2}{x+4}$

$3(x+4)=2(x+1)$

$3x+12=2x+2$

$x+12=2$

$x=-10$

Since each side is a single fraction you can 'cross-multiply': $\frac{3}{x+1}\times\frac{2}{x+4}$

This gives the same result as above.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 8K

1–2(½) | 2(½) | —

UNDERSTANDING

1 Write down the lowest common denominator of all the fractions in these equations.

a $\frac{x}{3}-\frac{2x}{5}=1$ **b** $\frac{x}{2}-\frac{3x}{4}=3$ **c** $\frac{x+1}{3}-\frac{x}{6}=5$

d $\frac{2x-1}{7}+\frac{5x+2}{4}=6$ **e** $\frac{x}{3}+\frac{x}{2}=\frac{1}{5}$ **f** $\frac{x-1}{4}-\frac{3x}{8}=\frac{1}{8}$

2 Simplify the fractions by cancelling.

a $\frac{12x}{3}$ **b** $\frac{21x}{7}$ **c** $\frac{4(x+3)}{2}$

d $\frac{5(2x+5)}{5}$ **e** $\frac{15x}{5x}$ **f** $\frac{-7(x+1)(x+2)}{7(x+1)}$

g $\frac{36(x-7)(x-1)}{9(x-7)}$ **h** $\frac{18(3-2x)(1-x)}{9(3-2x)}$ **i** $\frac{-8(2-3x)(2x-1)}{-8(2-3x)}$

3–5(½) | 3–7(½) | 3–7(½)

FLUENCY

Example 20a

3 Solve each of the following equations.

a $\frac{x}{2}+\frac{x}{5}=7$ **b** $\frac{x}{2}+\frac{x}{3}=10$ **c** $\frac{y}{3}+\frac{y}{4}=14$

d $\frac{x}{2}-\frac{3x}{5}=-1$ **e** $\frac{5m}{3}-\frac{m}{2}=1$ **f** $\frac{3a}{5}-\frac{a}{3}=2$

g $\frac{3x}{4}-\frac{5x}{2}=14$ **h** $\frac{8a}{3}-\frac{2a}{5}=34$ **i** $\frac{7b}{2}+\frac{b}{4}=15$

Example 20b

4 Solve each of the following equations.

a $\frac{x-1}{2}+\frac{x+2}{3}=11$ **b** $\frac{b+3}{2}+\frac{b-4}{3}=1$ **c** $\frac{n+2}{3}+\frac{n-2}{2}=1$

d $\frac{a+1}{5}-\frac{a+1}{6}=2$ **e** $\frac{x+5}{2}-\frac{x-1}{4}=3$ **f** $\frac{x+3}{2}-\frac{x+1}{3}=2$

g $\frac{m+4}{3}-\frac{m-4}{4}=3$ **h** $\frac{2a-8}{2}+\frac{a+7}{6}=1$ **i** $\frac{2y-1}{4}-\frac{y-2}{6}=-1$

5 Solve each of the following equations.

a $\frac{x+1}{2}=\frac{x}{3}$ **b** $\frac{x-2}{3}=\frac{x}{2}$ **c** $\frac{n+3}{4}=\frac{n-1}{2}$

d $\frac{a+2}{3}=\frac{a+1}{2}$ **e** $\frac{3+y}{2}=\frac{2-y}{3}$ **f** $\frac{2m+4}{4}=\frac{m+6}{3}$

Example 20c

6 Solve each of the following equations.

a $\frac{3}{4x}-\frac{1}{2x}=4$ **b** $\frac{2}{3x}-\frac{1}{2x}=2$ **c** $\frac{4}{2m}-\frac{2}{5m}=3$

d $\frac{1}{2x}-\frac{1}{4x}=9$ **e** $\frac{1}{2b}+\frac{1}{b}=2$ **f** $\frac{1}{2y}+\frac{1}{3y}=4$

g $\frac{1}{3x}+\frac{1}{2x}=2$ **h** $\frac{2}{3x}-\frac{1}{x}=2$ **i** $\frac{7}{2a}-\frac{2}{3a}=1$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8K

FLUENCY

Example 20d

7 Solve each of the following equations.

a $\frac{3}{x+1} = \frac{1}{x+2}$ **b** $\frac{2}{x+3} = \frac{3}{x+2}$ **c** $\frac{2}{x+5} = \frac{3}{x-2}$

d $\frac{1}{x-3} = \frac{1}{2x+1}$ **e** $\frac{2}{x-1} = \frac{1}{2x+1}$ **f** $\frac{1}{x-2} = \frac{2}{3x+2}$

8	8, 9(½)	9(½), 10

PROBLEM-SOLVING

8 Half of a number (x) plus one-third of twice the same number is equal to 4.

a Write an equation describing the situation.

b Solve the equation to find the number.

9 Use your combined knowledge of all the methods learnt earlier to solve these equations with algebraic fractions.

a $\frac{2x+3}{1-x} = 4$ **b** $\frac{5x+2}{x+2} = 3$ **c** $\frac{3x-2}{x-1} = 2$

d $\frac{2x}{3} + \frac{x-1}{4} = 2x-1$ **e** $\frac{3}{x^2} - \frac{2}{x} = \frac{5}{x}$ **f** $\frac{1-3x}{x^2} + \frac{3}{2x} = \frac{4}{x}$

g $\frac{x-1}{2} + \frac{3x-2}{4} = \frac{2x}{3}$ **h** $\frac{4x+1}{3} - \frac{x-3}{6} = \frac{x+5}{6}$ **i** $\frac{1}{x+2} - \frac{2}{x-3} = \frac{5}{(x+2)(x-3)}$

10 Molly and Billy each have the same number of computer games (x computer games each). Hazel takes one-third of Molly's computer games and a quarter of Billy's computer games to give her a total of 77 computer games.

a Write an equation describing the total number of computer games for Hazel.

b Solve the equation to find how many computer games Molly and Billy each had.

11, 12	11, 12	12, 13

REASONING

11 A common error when solving equations with algebraic fractions is made in this working. Find the error and explain how to avoid it.

$$\frac{3x-1}{4} + 2x = \frac{x}{3} \qquad \text{(LCD = 12)}$$

$$\frac{12(3x-1)}{4} + 2x = \frac{12x}{3}$$

$$3(3x-1) + 2x = 4x$$

$$9x - 3 + 2x = 4x$$

$$7x = 3$$

$$x = \frac{3}{7}$$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8K

REASONING

12 Another common error is made in this working. Find and explain how to avoid this error.

$$\frac{x}{2} - \frac{2x-1}{3} = 1 \qquad \text{(LCD = 6)}$$

$$\frac{6x}{2} - \frac{6(2x-1)}{3} = 6$$

$$3x - 2(2x-1) = 6$$

$$3x - 4x - 2 = 6$$

$$-x = 8$$

$$x = -8$$

13 Some equations with decimals can by solved by firstly multiplying by a power of 10. Here is an example.

$$0.8x - 1.2 = 2.5$$

$$8x - 12 = 25 \quad \text{Multiply both sides by 10 to remove all decimals.}$$

$$8x = 37$$

$$x = \frac{37}{8}$$

Solve these decimal equations using the same idea. For parts **d–f** you will need to multiply by 100.

a $0.4x + 1.4 = 3.2$ **b** $0.3x - 1.3 = 0.4$ **c** $0.5 - 0.2x = 0.2$

d $1.31x - 1.8 = 2.13$ **e** $0.24x + 0.1 = 3.7$ **f** $2 - 3.25x = 8.5$

Literal equations — — 14

ENRICHMENT

14 Solve each of the following equations for x in terms of the other pronumerals.
Hint: you may need to use factorisation.

a $\frac{x}{a} - \frac{x}{2a} = b$ **b** $\frac{ax}{b} - \frac{cx}{2} = d$ **c** $\frac{x-a}{b} = \frac{x}{c}$

d $\frac{x+a}{b} = \frac{d+e}{c}$ **e** $\frac{ax+b}{4} = \frac{x+c}{3}$ **f** $\frac{x+a}{3b} + \frac{x-a}{2b} = 1$

g $\frac{2a-b}{a} + \frac{a}{x} = a$ **h** $\frac{1}{a} - \frac{1}{x} = \frac{1}{c}$ **i** $\frac{a}{x} = \frac{b}{c}$

j $\frac{a}{x} + b = \frac{c}{x}$ **k** $\frac{ax-b}{x-b} = c$ **l** $\frac{cx+b}{x+a} = d$

m $\frac{2a+x}{a} = b$ **n** $\frac{1}{x-a} = \frac{1}{ax+b}$ **o** $\frac{a}{b} - \frac{a}{a+x} = 1$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Expanding quadratics using areas

Consider the expansion of the quadratic $(x + 3)(x + 6)$. This can be represented by finding the area of the rectangle shown.

Total area $= A_1 + A_2 + A_3 + A_4$

$= x^2 + 6x + 3x + 18$

Therefore:

$(x + 3)(x + 6) = x^2 + 9x + 18$



Expanding with positive signs

a Draw a diagram and calculate the area to determine the expansion of the following quadratics.

i $(x + 4)(x + 5)$ **ii** $(x + 7)(x + 8)$

iii $(x + 3)^2$ **iv** $(x + 5)^2$

b Using the same technique establish the rule for expanding $(a + b)^2$.

Expanding with negative signs

Consider the expansion of $(x - 4)(x - 7)$.

Area required = total area $- (A_2 + A_3 + A_4)$

$= x^2 - [(A_2 + A_4) + (A_3 + A_4) - A_4]$

$= x^2 - (7x + 4x - 28)$

$= x^2 - 11x + 28$

Therefore:

$(x - 4)(x - 7) = x^2 - 11x + 28$



This area is counted twice when we add $7x + 4x$.

a Draw a diagram and calculate the area to determine the expansion of the following quadratics.

i $(x - 3)(x - 5)$

ii $(x - 6)(x - 4)$

iii $(x - 4)^2$

iv $(x - 2)^2$

b Using the same technique, establish the rule for expanding $(a - b)^2$.

Difference of perfect squares

Using a diagram to represent $(a - b)(a + b)$, determine the appropriate area and establish a rule for the expansion of $(a - b)(a + b)$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Numerical applications of perfect squares

The expansion and factorisation of perfect squares and difference of perfect squares can be applied to the mental calculation of some numerical problems.

Evaluating a perfect square

The perfect square 32^2 can be evaluated using $(a+b)^2 = a^2 + 2ab + b^2$.

$$\begin{aligned} 32^2 &= (30+2)^2 \qquad (\text{Let } a = 30, b = 2) \\ &= 30^2 + 2(30)(2) + 2^2 \\ &= 900 + 120 + 4 \\ &= 1024 \end{aligned}$$

a Use the same technique to evaluate these perfect squares.

i 22^2 **ii** 21^2 **iii** 33^2 **iv** 51^2

v 1.2^2 **vi** 3.2^2 **vii** 6.1^2 **viii** 9.01^2

Similarly, the perfect square 29^2 can be evaluated using $(a-b)^2 = a^2 - 2ab + b^2$.

$$\begin{aligned} 29^2 &= (30-1)^2 \qquad (\text{Let } a = 30, b = 1) \\ &= 30^2 - 2(30)(1) + 1^2 \\ &= 900 - 60 + 1 \\ &= 841 \end{aligned}$$

b Use the same technique to evaluate these perfect squares.

i 19^2 **ii** 39^2 **iii** 98^2 **iv** 87^2

v 1.9^2 **vi** 4.7^2 **vii** 8.8^2 **viii** 3.96^2

Evaluating the difference of perfect squares

The difference of perfect squares $14^2 - 9^2$ can be evaluated using $a^2 - b^2 = (a+b)(a-b)$.

$$\begin{aligned} 14^2 - 9^2 &= (14+9)(14-9) \qquad (\text{Let } a = 14, b = 9) \\ &= 23 \times 5 \\ &= 115 \end{aligned}$$

a Use the same technique to evaluate these difference of perfect squares.

i $13^2 - 8^2$ **ii** $25^2 - 23^2$ **iii** $42^2 - 41^2$ **iv** $85^2 - 83^2$

v $1.4^2 - 1.3^2$ **vi** $4.9^2 - 4.7^2$ **vii** $1001^2 - 1000^2$ **viii** $2.01^2 - 1.99^2$

The expansion $(a+b)(a-b) = a^2 - b^2$ can also be used to evaluate some products. Here is an example:

$$\begin{aligned} 31 \times 29 &= (30+1)(30-1) \qquad (\text{Let } a = 30, b = 1) \\ &= 30^2 - 1^2 \\ &= 900 - 1 \\ &= 899 \end{aligned}$$

b Use the same technique to evaluate these products.

i 21×19 **ii** 32×28 **iii** 63×57 **iv** 105×95

v 2.1×1.9 **vi** 7.4×6.6 **vii** 520×480 **viii** 915×885

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



1 **a** The difference between the squares of two consecutive numbers is 97.
What are the two numbers?

b The difference between the squares of two consecutive odd numbers is 136.
What are the two numbers?

c The difference between the squares of two consecutive multiples of 3 is 81.
What are the two numbers?

2 **a** If $x^2 + y^2 = 6$ and $(x + y)^2 = 36$, find the value of xy.

b If $x + y = 10$ and $xy = 2$, find the value of $\frac{1}{x} + \frac{1}{y}$.

3 Find the values of the different digits a, b, c and d if the four digit number $abcd \times 4 = dcba$.

4 **a** Find the quadratic rule that relates the width n to the number of matches in the pattern below.



b Draw a possible pattern for these rules.

i $n^2 + 3$

ii $n(n - 1)$

5 Factorise $n^2 - 1$ and use the factorised form to explain why when n is prime and greater than 3, $n^2 - 1$ is:

i divisible by 4

ii divisible by 3

iii thus divisible by 12.

6 Prove that this expression is equal to 1.

$$\frac{2x^2 - 8}{5x^2 - 5} \div \frac{x - 2}{5x - 5} \div \frac{2x^2 - 10x - 28}{x^2 - 6x - 7}$$

7 Prove that $4x^2 - 4x + 1 \geq 0$ for all x.

8 In a race over 4 km Ryan ran at a constant speed. Sophie, however, ran the first 2 km at a speed 1 km/h more than Ryan and ran the second 2 km at a speed 1 km/h less than Ryan. Who won the race?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter summary

Algebraic techniques

Monic quadratic trinomials (Ext)

These are of the form:

$x^2 + bx + c$

Require two numbers that multiply to c and add to b

e.g. $x^2 - 7x - 18 = (x - 9)(x + 2)$

since $-9 \times 2 = -18$

and $-9 + 2 = -7$

DOPS

$a^2 - b^2 = (a - b)(a + b)$

e.g. $x^2 - 16 = x^2 - 4^2$

$= (x - 4)(x + 4)$

e.g. $4x^2 - 9 = (2x)^2 - 3^2$

$= (2x - 3)(2x + 3)$

Expansion

The process of removing brackets.

e.g. $2(x + 5) = 2x + 10$



$(x + 3)(2x - 4) = x(2x - 4) + 3(2x - 4)$

$= 2x^2 - 4x + 6x - 12$

$= 2x^2 + 2x - 12$

Special cases

DOPS (difference of perfect squares)

$(a - b)(a + b) = a^2 - b^2$

e.g. $(x - 5)(x + 5) = x^2 + 5x - 5x - 25$

$= x^2 - 25$

Perfect squares

$(a + b)^2 = a^2 + 2ab + b^2$

$(a - b)^2 = a^2 - 2ab + b^2$

e.g. $(2x + 3)^2 = (2x + 3)(2x + 3)$

$= 4x^2 + 6x + 6x + 9$

$= 4x^2 + 12x + 9$

Factorisation

The reverse process of expansion. Always remove the highest common factor first.

e.g. $2ab + 8b$ HCF $= 2b$

$= 2b(a + 4)$

e.g. $3(x + 2) + y(x + 2)$ HCF $= x + 2$

$= (x + 2)(3 + y)$

Add/subtract

Must find lowest common denominator (LCD) before applying operation.

e.g. $\frac{3x}{4} + \frac{x - 1}{3}$

$= \frac{9x}{12} + \frac{4(x - 1)}{12}$

$= \frac{9x + 4x - 4}{12}$

$= \frac{13x - 4}{12}$

Algebraic fractions

These involve algebraic expressions in the numerator and/or denominator.

e.g. $\frac{2x}{x - 7}, \frac{3}{5x}, \frac{7}{(x - 1)^2}$

Multiply/divide

To divide, multiply by the reciprocal. Factorise all expressions, cancel and then multiply.

e.g. $\frac{3}{x^2 - 9} \div \frac{15}{2x + 6}$

$= \frac{\cancel{3}^{1}}{(x - 3)\cancel{(x + 3)}^{1}} \times \frac{2\cancel{(x + 3)}^{1}}{\cancel{15}^{5}}$

$= \frac{2}{5(x - 3)}$

By grouping

If there are four terms, we may be able to group into two binomial terms.

e.g. $5x + 10 - 3x^2 - 6x$

$= 5(x + 2) - 3x(x + 2)$

$= (x + 2)(5 - 3x)$

Trinomials of the form $ax^2 + bx + c$ (Ext)

Can be factorised using grouping also

e.g. $3x^2 + 7x - 6$, $3 \times (-6) = -18$

$= 3x^2 + 9x - 2x - 6$, Use 9 and -2

$= 3x(x + 3) - 2(x + 3)$ since

$= (x + 3)(3x - 2)$ $9 \times (-2) = -18$

and $9 + (-2) = 7$

Solving equations with algebraic fractions (Ext)

Find lowest common denominator (LCD) and multiply every term by the LCD.

e.g. LCD of $2x$ and $3x$ is $6x$

LCD of $(x - 1)$ and $(x + 3)$ is $(x - 1)(x + 3)$

LCD of $2x$ and x^2 is $2x^2$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

8A **1** $(2x-1)(x+5)$ in expanded and simplified form is:

A $2x^2+9x-5$ **B** $x^2+11x-5$ **C** $4x^2-5$
D $3x^2-2x+5$ **E** $2x^2+4x-5$

8B **2** $(3a+2b)^2$ is equivalent to:

A $9a^2+6ab+4b^2$ **B** $9a^2+4b^2$ **C** $3a^2+6ab+2b^2$
D $3a^2+12ab+2b^2$ **E** $9a^2+12ab+4b^2$

8D **3** $16x^2-49$ in factorised form is:

A $(4x-7)^2$ **B** $(16x-49)(16x+49)$ **C** $(2x-7)(8x+7)$
D $(4x-7)(4x+7)$ **E** $4(4x^2-49)$

8E **4** The factorised form of $x^2+3x-2x-6$ is:

A $(x-3)(x+2)$ **B** $x-2(x+3)^2$ **C** $(x+3)(x-2)$
D $x-2(x+3)$ **E** $x(x+3)-2$

8F Ext **5** If $(x-2)$ is a factor of $x^2+5x-14$ the other factor is:

A x **B** $x+7$ **C** $x-7$ **D** $x-16$ **E** $x+5$

8G Ext **6** The factorised form of $3x^2+10x-8$ is:

A $(3x+1)(x-8)$
B $(x-4)(3x+2)$
C $(3x+2)(x+5)$
D $(3x-2)(x+4)$
E $(x+1)(3x-8)$

8H **7** The simplified form of $\frac{3x+6}{(x+5)(x+1)} \times \frac{x+5}{x+2}$ is:

A $\frac{3}{x+1}$ **B** $\frac{15}{2x^2+5}$ **C** $x+3$ **D** $\frac{5}{x+2}$ **E** $3(x+5)$

8I **8** $\frac{x+2}{5}+\frac{2x-1}{3}$ written as a single fraction is:

A $\frac{11x+1}{15}$ **B** $\frac{11x+9}{8}$ **C** $\frac{3x+1}{8}$ **D** $\frac{11x+7}{15}$ **E** $\frac{13x+1}{15}$

8J Ext **9** The LCD of $\frac{3x+1}{2x}$ and $\frac{4}{x+1}$ is:

A $8x$ **B** $2x(x+1)$ **C** $(x+1)(3x+1)$
D $8x(3x+1)$ **E** $x(x+1)$

8K Ext **10** The solution to $\frac{3}{1-x}=\frac{4}{2x+3}$ is:

A $x=-\frac{1}{2}$ **B** $x=-\frac{9}{11}$ **C** $x=\frac{1}{7}$ **D** $x=2$ **E** $x=-\frac{4}{5}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter review

Short-answer questions

8A **1** Expand the following binomial products.

a $(x-3)(x+4)$ b $(x-7)(x-2)$

c $(2x-3)(3x+2)$ d $3(x-1)(3x+4)$

8B **2** Expand the following.

a $(x+3)^2$ b $(x-4)^2$ c $(3x-2)^2$

d $(x-5)(x+5)$ e $(7-x)(7+x)$ f $(11x-4)(11x+4)$

8C **3** Write the following in fully factorised form by removing the highest common factor.

a $4a+12b$ b $6x-9x^2$ c $-5x^2y-10xy$

d $3(x-7)+x(x-7)$ e $x(2x+1)-(2x+1)$ f $(x-2)^2-4(x-2)$

8D **4** Factorise the following DOPS.

a x^2-100 b $3x^2-48$ c $25x^2-y^2$

d $49-9x^2$ e $(x-3)^2-81$ f $1-x^2$

8E **5** Factorise the following by grouping.

a $x^2-3x+6x-18$

b $4x^2+10x-2x-5$

c $3x-8b+2bx-12$

8F/G Ext **6** Factorise the following trinomials.

a $x^2+8x+15$ b $x^2-3x-18$ c x^2-7x+6 d $3x^2+15x-42$

e $2x^2+16x+32$ f $5x^2+17x+6$ g $4x^2-4x-3$ h $6x^2-17x+12$

8H **7** Simplify the following.

a $\dfrac{3x+12}{3}$ b $\dfrac{2x-16}{3x-24}$ c $\dfrac{x^2-9}{5(x+3)}$

8H **8** Simplify the following algebraic fractions by first factorising and cancelling where possible.

a $\dfrac{3}{2x}\times\dfrac{x}{6}$ b $\dfrac{x(x-4)}{8(x+1)}\times\dfrac{4(x+1)}{x}$ c $\dfrac{x^2+3x}{3x+6}\times\dfrac{x+2}{x+3}$

d $\dfrac{2x}{5x+20}\div\dfrac{x}{x+4}$ e $\dfrac{4x^2-9}{10x^2}\div\dfrac{10x-15}{x}$ Ext f $\dfrac{x^2+5x+6}{x+3}\div\dfrac{x^2-4}{4x-8}$

8I/J **9** Simplify the following by first finding the lowest common denominator.

a $\dfrac{x}{4}+\dfrac{2x}{3}$ Ext b $\dfrac{x-1}{6}-\dfrac{x+3}{8}$ c $\dfrac{3}{4x}+\dfrac{1}{2x}$

d $\dfrac{7}{x}-\dfrac{2}{x^2}$ Ext e $\dfrac{3}{x+1}+\dfrac{5}{x+2}$ Ext f $\dfrac{7}{(x-4)^2}-\dfrac{2}{x-4}$

8K Ext **10** Solve the following equations involving fractions.

a $\dfrac{x}{4}+\dfrac{2x}{5}=13$ b $\dfrac{4}{x}-\dfrac{2}{3x}=20$

c $\dfrac{x+3}{2}+\dfrac{x-4}{3}=6$ d $\dfrac{4}{1-x}=\dfrac{5}{x+4}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 A pig pen for a small farm is being redesigned. It is originally a square of side length x m.

a In the planning the length is initially kept as x m and the width altered such that the area of the pen is $(x^2 + 3x)$ square metres. What is the new width?

b Instead, it is determined that the original length will be increased by 1 metre and the original width will be decreased by 1 metre.

i What effect does this have on the perimeter of the pig pen compared with the original size?

ii Determine an expression for the new area of the pig pen in expanded form. How does this compare to the original area?

c The final set of dimensions requires an extra 8 m of fencing to go around the pen compared with the original pen. If the length of the pen has been increased by 7 m, then the width of the pen must decrease. Find:

i the change that has been made to the width of the pen

ii the new area enclosed by the pen

iii what happens when $x = 3$.

2 The security tower for a palace is on a small square piece of land 20 m by 20 m with a moat of width x metres the whole way around it as shown.

a State the area of the piece of land.



b **i** Give expressions for the length and the width of the combined moat and land.

ii Find an expression, in expanded form, for the entire area occupied by the moat and the land.

c If the tower occupies an area of $(x + 10)^2$ m^2, what fraction of the total area in part **b ii** is this?

d Use your answers to parts **a** and **b** to give an expression for the area occupied by the moat alone, in factorised form.

e Use trial and error to find the value of x such that the area of the moat alone is 500 m^2.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter 9

Probability and statistics

What you will learn

9A Probability review (Consolidating)
9B Venn diagrams and two-way tables
9C Using set notation
9D Using arrays for two-step experiments
9E Tree diagrams
9F Experimental probability
9G Summarising data: measures of centre
9H Stem-and-leaf plots
9I Grouped data
9J Measures of spread
9K Box plots (Extending)

Australian curriculum

STATISTICS AND PROBABILITY

Chance

List all outcomes for two-step chance experiments, both with and without replacement using tree diagrams or arrays

Assign probabilities to outcomes and determine probabilities for events

Calculate relative frequencies from given or collected data to estimate probabilities of events involving 'and' or 'or'

Investigate reports of surveys in digital media and elsewhere for information on how data were obtained to estimate population means and medians

Data representation and interpretation

Identify everyday questions and issues involving at least one numerical and at least one categorical variable, and collect data directly from secondary sources

Construct back-to-back stem-and-leaf plots and histograms and describe data, using terms including 'skewed', 'symmetric' and 'bimodal'

Compare data displays using mean, median and range to describe and interpret numerical data sets in terms of location (centre) and spread

Investigate techniques for collecting data, including census, sampling and observation AC

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8

© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Cambridge University Press

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Are lotteries worth it?

The probability of winning first division in a lottery such as Tattslotto (also known as Saturday Lotto and Gold Lotto), based on the choice of six numbers chosen from 45, is 1 in 8 145 060. This means that you would expect to win first division once in every eight million, one hundred and forty-five thousand and sixty attempts. This is calculated by counting the number of possible ways of winning as well as the total number of ways that six numbers can be drawn from 45.

If you played 1 game per week every week of the year, you would expect to win once every 1562 centuries. Many thousands of people take this chance every week. Looking at the statistics, adults in Australia gamble an average of about $1000 per year trying their luck in various national and state lotteries and other games of chance.

Essential Mathematics for the Australian Curriculum Year 9 2nd
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9A Probability review CONSOLIDATING

The mathematics associated with describing chance is called probability. We can precisely calculate the chance of some events occurring like rolling a sum of 12 from two dice or flipping 3 heads if a coin is tossed 5 times. To do this we need to know how many outcomes there are in total and how many of the outcomes are favourable (i.e. which match the result we are interested in). The number of favourable outcomes in comparison to the total number of outcomes will determine how likely it is that the favourable event will occur.



Using probability we can find the likelihood of rolling a particular total score with two dice.

Let's start: Choose an event

As a class group, write down and discuss at least three events which have the following chance of occurring.

- impossible chance
- very low chance
- medium to low chance
- even (50–50) chance
- medium to high chance
- very high chance
- certain chance

Key ideas

- A **random experiment** results in a list of **outcomes** which occur without interference.
- The **sample space** is the list of all possible outcomes from an experiment.
- Set brackets {…} are used to list sets of numbers or other objects.
- An **event** is a collection of outcomes resulting from an experiment.
  For example, rolling a die is a random experiment with six possible outcomes: {1, 2, 3, 4, 5, 6}. The event 'rolling a number greater than 4' includes the outcomes 5 and 6. This is an example of a **compound event** because it contains more than one element from the sample space.
- The probability of an event where all outcomes are **equally likely** is given by:

$$\Pr(\text{Event}) = \frac{\text{Number of outcomes where event occurs}}{\text{Total number of outcomes}}$$

- Probabilities are numbers between 0 and 1 inclusive, and can be written as a decimal, fraction or percentage. For example: 0.55 or $\frac{11}{20}$ or 55%
- For all events, $0 \leq \Pr(\text{Event}) \leq 1$.



- The **complement** of an event A is the event where A does not occur.

$$\Pr(\text{not A}) = 1 - \Pr(\text{A})$$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Finding probabilities of events

This spinner has five equally divided sections.

a List the sample space using the given numbers.

b Find Pr(3).

c Find Pr(not a 3).

d Find Pr(a 3 or a 7).

e Find Pr(a number which is at least a 3).



SOLUTION	EXPLANATION
a $\{1, 2, 3, 7\}$	Use set brackets and list all the possible outcomes in any order.
b $\Pr(3) = \frac{2}{5}$ or 0.4	$\Pr(3) = \frac{\text{number of sections labelled 3}}{\text{number of equal sections}}$
c $\Pr(\text{not a 3}) = 1 - \Pr(3)$ $= 1 - \frac{2}{5}$ or $1 - 0.4$ $= \frac{3}{5}$ or 0.6	'Not a 3' is the complementary event of obtaining a 3. Alternatively, count the number of sectors which are not 3.
d $\Pr(\text{a 3 or a 7}) = \frac{2}{5} + \frac{1}{5}$ $= \frac{3}{5}$	There are two 3s and one 7 in the five sections.
e $\Pr(\text{at least a 3}) = \frac{3}{5}$	Three of the sections have the numbers 3 or 7 which are 3 or more.

Example 2 Choosing letters from a word

A letter is randomly chosen from the word PROBABILITY. Find the following probabilities.

a Pr(L)

b Pr(not L)

c Pr(vowel)

d Pr(consonant)

e Pr(vowel or a B)

f Pr(vowel or consonant)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $\Pr(\text{L}) = \frac{1}{11}$	One of the 11 letters in PROBABILITY is an L.
b $\Pr(\text{not L}) = 1 - \frac{1}{11}$ $= \frac{10}{11}$	The event 'not L' is the complement of the event selecting an L. Complementary events sum to 1.
c $\Pr(\text{vowel}) = \frac{4}{11}$	There are 4 vowels: O, A and two letter Is.
d $\Pr(\text{consonant}) = 1 - \frac{4}{11}$ $= \frac{7}{11}$	The events 'vowel' and 'consonant' are complementary.
e $\Pr(\text{vowel or a B}) = \frac{6}{11}$	There are 4 vowels and 2 letter Bs.
f $\Pr(\text{vowel or consonant}) = 1$	This event includes all possible outcomes.

Exercise 9A

1–3 | 3 | —

UNDERSTANDING

1 Jim believes that there is a 1 in 4 chance that the flower on his prized rose will bloom tomorrow.

a Write the chance '1 in 4' as:

i a fraction **ii** a decimal **iii** a percentage

b Draw a number line from 0 to 1 and mark the level of chance described by Jim.

2 Copy and complete this table.

	Percentage	Decimal	Fraction	Number line
a	50%	0.5	$\frac{1}{2}$	0, 0.5, 1
b	25%			
c			$\frac{3}{4}$	
d				0, 0.2, 0.5, 1
e		0.6		
f			$\frac{17}{20}$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9A

UNDERSTANDING

3 Ten people make the following guesses of the chance that they will get a salary bonus this year.

0.7, $\frac{2}{5}$, 0.9, $\frac{1}{3}$, 2 in 3, $\frac{3}{7}$, 1 in 4, 0.28, $\frac{2}{9}$, 0.15

Can you order their chances from lowest to highest? (*Hint*: change each into a decimal.)

4, 5, 7, 8(½) | 4–6(½), 7, 8(½) | 4–6(½), 7, 8(½)

FLUENCY

Example 1

4 The spinners below have equally divided sections. Complete the following for each spinner.

i List the sample space using the given numbers.
ii Find Pr(2).
iii Find Pr(not a 2).
iv Find Pr(a 2 or a 3).
v Find Pr(a number which is at least a 2).

a



b



c



d



e



f



5 Find the probability of obtaining a blue ball if a ball is selected at random from a box which contains:

a 4 blue balls and 4 red balls
b 3 blue balls and 5 red balls
c 1 blue ball, 3 red balls and 2 white balls
d 8 blue balls, 15 black balls and 9 green balls
e 15 blue balls only
f 5 yellow balls and 2 green balls.

6 Find the probability of *not* selecting a blue ball if a ball is selected at random from a box containing the balls described in Question **5** parts **a** to **f** above.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9A

FLUENCY

7 If a swimming pool has eight lanes and each of eight swimmers has an equal chance of being placed in lane 1, find the probability that a particular swimmer:

- **a** will swim in lane 1
- **b** will not swim in lane 1.

Example 2

8 A letter is chosen at random from the word ALPHABET. Find the following probabilities.

- **a** Pr(L)
- **b** Pr(A)
- **c** Pr(A or L)
- **d** Pr(vowel)
- **e** Pr(consonant)
- **f** Pr(vowel or consonant)
- **g** Pr(Z)
- **h** Pr(A or Z)
- **i** Pr(not an A)
- **j** Pr(letter from the first half of the alphabet)

9, 10 | 10, 11 | 10–12

PROBLEM-SOLVING

9 The school captain is to be chosen at random from four candidates. Two are girls (Hayley and Alisa) and two are boys (Rocco and Stuart).

- **a** List the sample space.
- **b** Find the probability that the school captain will be:
  - **i** Hayley
  - **ii** male
  - **iii** neither Stuart nor Alisa

10 From a deck of 52 playing cards a card is drawn at random. The deck includes 13 black spades, 13 black clubs, 13 red hearts and 13 red diamonds. This includes four of each of ace, king, queen, jack, 2, 3, 4, 5, 6, 7, 8, 9 and 10. Find the probability that the card will be:

- **a** the queen of diamonds
- **b** an ace
- **c** a red king
- **d** a red card
- **e** a jack or a queen
- **f** any card except a 2
- **g** any card except a jack or a black queen
- **h** not a black ace.

11 A six-sided die is tossed and the upper-most face is observed and recorded. Find the following probabilities.

- **a** Pr(6)
- **b** Pr(3)
- **c** Pr(not a 3)
- **d** Pr(1 or 2)
- **e** Pr(a number less than 5)
- **f** Pr(even number or odd number)
- **g** Pr(square number)
- **h** Pr(not a prime number)
- **i** Pr(a number greater than 1)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9A

PROBLEM-SOLVING

12 A letter is chosen at random from the word PROBABILITY. Find the probability that the letter will be:

a a B **b** not a B **c** a vowel
d not a vowel **e** a consonant
f a letter belonging to one of the first five letters in the alphabet
g a letter from the word RABBIT **h** a letter that is not in the word RABBIT.

13, 14 | 13, 14 | 14, 15

REASONING

13 Amanda selects a letter at random from the word SOLO and writes $\Pr(S) = \frac{1}{3}$. Explain her error.

14 A six-sided die is rolled. Which of the following events have a probability equal to $\frac{1}{3}$?

a more than 4 **b** at least 4
c less than or equal to 3 **d** no more than 2
e at most 4 **f** less than 3

15 A number is selected at random from the set $\{1, 2, 3, \ldots, 25\}$. Find the probability that the number chosen is:

a a multiple of 2 **b** a factor of 24 **c** a square number
d a prime number **e** divisible by 3 **f** divisible by 3 or 2
g divisible by 3 and 2 **h** divisible by 2 or 3 or 7 **i** divisible by 13 and 7

Faulty CD player | — | — | 16

ENRICHMENT

16 A compact disc (CD) contains eight tracks. The time length for each track is as shown in the table on the right.
The CD is placed in a faulty CD player which begins playing randomly at an unknown place somewhere on the CD, not necessarily at the beginning of a track.

Track	Time (minutes)
1	3
2	4
3	4
4	5
5	4
6	3
7	4
8	4

a Find the total number of minutes of music available on the CD.
b Find the probability that the CD player will begin playing somewhere on track 1.
c Find the probability that the CD player will begin somewhere on:
i track 2 **ii** track 3
iii a track that is 4 minutes long **iv** track 4
v track 7 or 8 **vi** a track that is not 4 minutes long.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9B Venn diagrams and two-way tables

When the results of an experiment involve overlapping categories it can be very helpful to organise the information into a Venn diagram or two-way table. Probabilities can easily be calculated from these types of diagrams.

Let's start: Mac or PC

Twenty people were surveyed to find out whether or not they owned a Mac or PC computer at home. The survey revealed that 8 people owned a Mac and 15 people owned a PC. All people surveyed owned at least one type of computer.

- Do you think some people owned both a Mac and PC? Discuss.
- Use these diagrams to help organise the number of people who own Macs and PCs.

Venn diagram



Two-way table

	Mac	No Mac	Total
PC			
No PC			
Total			

- Use your diagrams to describe the proportion (fraction) of people owning Macs and/or PCs for all the different areas in the diagrams.

Key ideas

A **Venn diagram** and a **two-way table** help to organise outcomes into different categories. This example shows the type of computers owned by 100 people.

Venn diagram



Two-way table

	Mac	No Mac	Total
PC	12	50	62
No PC	31	7	38
Total	43	57	100

These diagrams show, for example:

- 12 people own both a Mac and a PC
- 62 people own a PC
- 57 people do not own a Mac
- $\Pr(\text{Mac}) = \frac{43}{100}$
- $\Pr(\text{only Mac}) = \frac{31}{100}$
- $\Pr(\text{Mac or PC}) = \frac{93}{100}$
- $\Pr(\text{Mac and PC}) = \frac{12}{100} = \frac{3}{25}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Using a Venn diagram

A survey of 30 people found that 21 like AFL and 12 like soccer. Also 7 people like both AFL and soccer and 4 like neither AFL nor soccer.

a Construct a Venn diagram for the survey results.

b How many people:

- **i** like AFL or soccer?
- **ii** do not like soccer?
- **iii** like only AFL?

c If one of the 30 people was randomly selected, find:

- **i** Pr(like AFL and soccer)
- **ii** Pr(like neither AFL nor soccer)
- **iii** Pr(like only soccer).

SOLUTION	EXPLANATION
a 	Place the appropriate number in each category ensuring that: • the total that like AFL is 21 • the total that like soccer is 12 • there are 30 in total.
b i 26	The total number of people that like AFL, soccer or both is $14 + 7 + 5 = 26$.
ii $30 - 12 = 18$	12 like soccer so 18 do not.
iii 14	21 like AFL but 7 of these also like soccer.
c i Pr(like AFL and soccer) $= \frac{7}{30}$	7 out of 30 people like AFL and soccer.
ii Pr(like neither AFL nor soccer) $= \frac{4}{30}$ $= \frac{2}{15}$	The 4 people who like neither AFL nor soccer sit outside both categories.
iii Pr(like soccer only) $= \frac{5}{30}$ $= \frac{1}{6}$	5 people like soccer but not AFL.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4 Using a two-way table

At a car yard, 24 cars are tested for fuel economy: 18 of the cars run on petrol, 8 cars run on gas and 3 cars can run on both petrol and gas.

a Illustrate the situation using a two-way table.

b How many of the cars:

i do not run on gas? **ii** run on neither petrol nor gas?

c Find the probability that a randomly selected car:

i runs on gas **ii** runs on only gas **iii** runs on gas or petrol

SOLUTION

a

	Gas	Not gas	Total
Petrol	3	15	18
Not petrol	5	1	6
Total	8	16	24

EXPLANATION

Set up a table as shown and enter the numbers (in black) from the given information.
Fill in the remaining numbers (in red) ensuring that each column and row adds to the correct total.

b **i** 16

The total at the base of the 'Not gas' column is 16.

ii 1

The number at the intersection of the 'Not gas' column and the 'Not petrol' row is 1.

c **i** $\Pr(\text{gas}) = \frac{8}{24}$

$= \frac{1}{3}$

8 cars in total run on gas out of the 24 cars.

ii $\Pr(\text{only gas}) = \frac{5}{24}$

Of the 8 cars that run on gas, 5 of them do not also run on petrol.

iii $\Pr(\text{gas or petrol}) = \frac{15 + 5 + 3}{24}$

$= \frac{23}{24}$

Of the 24 cars, some run on petrol only (15), some run on gas only (5) and some run on gas and petrol (3).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 9B

1–3 | 2, 3 | —

UNDERSTANDING

1 This Venn diagram shows the number of people who enjoy riding and running.



a How many people in total are represented by this Venn diagram?

b How many people enjoy:

i only riding? **ii** riding (in total)?

iii only running? **iv** running (in total)?

v both riding and running? **vi** neither riding nor running?

vii riding or running?

c How many people do not enjoy:

i riding? **ii** running?

2 Match the diagrams **A**, **B**, **C** or **D** with the given description.

a S **b** S only **c** S and T **d** S or T

A



B



C



D



3 Fill in the missing numbers in these two-way tables.

a

	A	Not A	Total
B	7	8	
Not B		1	
Total	10		

b

	A	Not A	Total
B	2		7
Not B		4	
Total			20

4–7 | 4–7 | 4–7

FLUENCY

Example 3

4 In a class of 30 students, 22 carried a phone and 9 carried an iPod. Three carried both a phone and an iPod and 2 students carried neither.

a Represent the information using a Venn diagram.

b How many people:

i carried a phone or an iPod (includes carrying both)?

ii do not carry an iPod?

iii carry only an iPod?

c If one of the 30 people was selected at random, find the following probabilities.

i Pr(carry a phone and an iPod)

ii Pr(carry neither a phone nor an iPod)

iii Pr(carry only a phone).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9B

FLUENCY

5 For each Venn diagram, find the following probabilities. You will need to calculate the total number in the sample first.

i Pr(A)
ii Pr(A only)
iii Pr(not B)
iv Pr(A and B)
v Pr(A or B)
vi Pr(neither A nor B)

a



b



Example 4

6 From 50 desserts served at a restaurant one evening, 25 were served with ice cream, 21 were served with cream and 5 were served with both cream and ice cream.

a Illustrate the situation using a two-way table.

b How many of the desserts:
i did not have cream?
ii had neither cream nor ice cream?

c Find the probability that a chosen dessert:
i had cream
ii had only cream
iii had cream or ice cream.

7 Find the following probabilities using each of the given tables. First fill in the missing numbers.

i Pr(A)
ii Pr(not A)
iii Pr(A and B)
iv Pr(A or B)
v Pr(B only)
vi Pr(neither A nor B)

a

	A	Not A	Total
B	3	1	
Not B	2		4
Total			

b

	A	Not A	Total
B		4	15
Not B	6		
Total			26

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 For each two-way table, fill in the missing numbers then transfer the information to a Venn diagram.

a

	A	Not A	Total
B	2		8
Not B			
Total		7	12



b

	A	Not A	Total
B		4	
Not B	9		13
Total	12		



9 In a group of 10 people, 6 rented their house, 4 rented a car and 3 did not rent either a car or their house.

- **a** Draw a Venn diagram.
- **b** How many people rented both a car and their house?
- **c** Find the probability that one of them rented only a car.

10 One hundred people were surveyed regarding their use of water for their garden. Of that group, 23 said that they use rain water, 48 said that they used tap water and 41 said that they did not water at all.

- **a** Represent this information in a two-way table.
- **b** How many people used both rain and tap water?
- **c** What is the probability that one of the people uses only tap water?
- **d** What is the probability that one of the people uses tap water or rain water?

11 All members of a ski club enjoy either skiing and/or snowboarding. Of those members, enjoy 7 only snowboarding, 16 enjoy skiing and 4 enjoy both snowboarding and skiing. How many people are in the ski club?

12 Of a group of 30 cats, 24 eat tinned or dry food, 10 like dry food and 5 like both tinned and dry food. Find the probability that a randomly selected cat likes only tinned food.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

9B

13 | 13, 14 | 14–16

REASONING

13 Complete the two-way table and transfer to a Venn diagram using the pronumerals w, x, y and z.

	A	Not A	Total
B	x	y	
Not B	z	w	
Total			

→



14 The total number of people in a survey is T. The number of males in the survey is x and the number of doctors is y. The number of doctors that are males is z. Write algebraic expressions for the following using any of the variables x, y, z and T.

- **a** The number who are neither male nor a doctor.
- **b** The number who are not males.
- **c** The number who are not doctors.
- **d** The number who are male but not a doctor.
- **e** The number who are a doctor but not male.
- **f** The number who are female and a doctor.
- **g** The number who are female or a doctor.

15 Explain what is wrong with this two-way table. Try to complete it to find out.

	A	Not A	Total
B		12	
Not B			7
Total	11		19

16 How many numbers need to be given in a two-way table so that all numbers in the table can be calculated?

Finding a rule for A and B

— | — | 17

ENRICHMENT

17 Two overlapping events, A and B, include 20 elements with 0 elements in the 'neither A nor B' region.



- **a** Draw a Venn diagram for the following situations.
  - **i** The number in A is 12 and the number in B is 10.
  - **ii** The number in A is 15 and the number in B is 11.
  - **iii** The number in A is 18 and the number in B is 6.
- **b** If the total number in A or B is now 100 (not 20), complete a Venn diagram for the following situations.
  - **i** The number in A is 50 and the number in B is 60.
  - **ii** The number in A is 38 and the number in B is 81.
  - **iii** The number in A is 83 and the number in B is 94.
- **c** Now describe a method that finds the number in the common area for A and B. Your method should work for all the above examples.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9C Using set notation

Interactive

Widgets

HOTsheets

Walkthroughs

Using symbols to describe different sets of objects can make the writing of mathematics more efficient and easier to read. For example, *the probability that a randomly chosen person likes both apples and bananas* could be written Pr(A ∩ B) provided the events A and B are clearly defined.

Let's start: English language meaning to mathematical meaning

Two events called A and B are illustrated in this Venn diagram. Use your understanding of the English language meaning of the given words to match with one of the mathematical terms and a number from the Venn diagram. They are in jumbled order.



English	Mathematical	Number in Venn diagram
a not A	A A union B	i 1
b A or B	B sample space	ii 7
c A and B	C complement of A	iii 13
d anyone	D A intersection B	iv 17

Key ideas

- The **sample space** (list of all possible outcomes) is sometimes called the universal set and is given the symbol S, Ω, U or ξ.
  For example: Ω = {1, 2, 3, 4, 5, 6, 7, 8, 9, 10}
- A is a particular **subset** (⊂) of the sample space if all the elements in A are contained in the sample space. For example, A is the set of prime numbers less than or equal to 10 which is a subset of all the integers less than 10.



- A′ is the complement of A and contains the elements not in A.
- 5 ∈ A means that 5 is **an element of** A.
- ∅ is the **null** or **empty** set and contains no elements. ∴ ∅ = { }
- n(A) is the **cardinal number** of A and means the number of elements in A. e.g. n(A) = 4
- A Venn diagram can be used to illustrate how different subsets in the sample space are grouped.
  For example: A = {2, 3, 5, 7}
  B = {1, 3, 5, 7, 9}



  - A ∩ B means A **and** B which means the **intersection** of A and B and includes the elements in common with both sets. ∴ A ∩ B = {3, 5, 7}
  - A ∪ B means A **or** B which means the **union** of A and B and includes the elements in either A or B or both. ∴ A ∪ B = {1, 2, 3, 5, 7, 9}
- A **only** is the elements in A but not in B. ∴ A only = {2}

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 5 Using set notation

A number is chosen from the set of positive integers between 1 and 8 inclusive. If A is the set of odd numbers between 1 and 8 inclusive and B is the set of prime numbers between 1 and 8 inclusive:

a list the sets:
- **i** the sample space
- **ii** A
- **iii** B

b draw a Venn diagram

c list the sets:
- **i** $A \cap B$
- **ii** $A \cup B$
- **iii** A'
- **iv** B only

d find:
- **i** $n(A)$
- **ii** $Pr(A)$
- **iii** $n(A \cap B)$
- **iv** $Pr(A \cap B)$

SOLUTION	EXPLANATION
a i $\{1, 2, 3, 4, 5, 6, 7, 8\}$	List all the numbers, using set brackets.
ii $A = \{1, 3, 5, 7\}$	A includes all the odd numbers.
iii $B = \{2, 3, 5, 7\}$	B includes all the prime numbers. 1 is not prime.
b 	Place each cardinal number into the appropriate region, i.e. there are 3 numbers common to sets A and B so 3 is placed in the overlapping region.
c i $A \cap B = \{3, 5, 7\}$	$\{3, 5, 7\}$ are common to both A and B.
ii $A \cup B = \{1, 2, 3, 5, 7\}$	$\{1, 2, 3, 5, 7\}$ are in either A or B or both.
iii $A' = \{2, 4, 6, 8\}$	A' means the elements not in A.
iv B only $= \{2\}$	B only means the elements in B but not in A.
d i $n(A) = 4$	$n(A)$ is the cardinal number of A. There are four elements in A.
ii $Pr(A) = \frac{4}{8} = \frac{1}{2}$	Pr(A) means the chance that the element will belong to A. There are 4 numbers in A compared with 8 in the sample space.
iii $n(A \cap B) = 3$	There are three elements in $A \cap B$.
iv $Pr(A \cap B) = \frac{3}{8}$	Three out of eight elements are in $A \cap B$.

Exercise 9C

1–3 | 1–3 | —

UNDERSTANDING

1 Match each of the terms in the first list with the symbols in the second list.

a complement	**A** $\cap$
b union	**B** $n(A)$
c element of	**C** A'
d intersection	**D** $\cup$
e empty or null set	**E** $\in$
f number of elements	**F** $\varnothing$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9C

UNDERSTANDING

2 Choose a diagram that matches each of these sets.

a $A \cup B$ **b** A' **c** $A \cap B$ **d** B only

A



B



C



D



3 Using the given two-way table, find the following.

a $n(A \cap B)$
b $n(B)$
c $n(A)$
d $n(A')$

	A	A'	Total
B	2	8	10
B'	5	1	6
Total	7	9	16

4, 6, 7 4–7 5–7

FLUENCY

Example 5

4 A number is chosen from the set of positive integers between 1 and 10 inclusive. If A is the set of odd numbers between 1 and 10 inclusive and B is the set of prime numbers between 1 and 10 inclusive:

a list the sets:
i the sample space **ii** A **iii** B

b draw a Venn diagram

c list the sets:
i $A \cap B$ **ii** $A \cup B$ **iii** A' **iv** B only

d find:
i $n(A)$ **ii** $\Pr(A)$ **iii** $n(A \cap B)$ **iv** $\Pr(A \cap B)$

5 A number is chosen from the set of positive integers between 1 and 20 inclusive. If A is the set of multiples of 3 that are less than 20 and B is the set of factors of 15:

a draw a Venn diagram

b list the sets:
i $A \cap B$ **ii** $A \cup B$ **iii** A' **iv** B only

c find:
i $n(B)$ **ii** $\Pr(B)$ **iii** $n(A \cap B)$
iv $\Pr(A \cap B)$ **v** $n(A \cup B)$ **vi** $\Pr(A \cup B)$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9C

FLUENCY

6 Consider the sample space $\Omega = \{1, 2, 3, 4, 5, 6\}$ and the sets $A = \{1, 4, 6\}$ and $B = \{2, 3, 5\}$.

a State whether the following are true (T) or false (F).

i $A \subset \Omega$ **ii** $B \subset \Omega$

iii $3 \in A$ **iv** $5 \in A$

v $n(B) = 3$ **vi** $n(B') = 2$

vii $A \cap B = \varnothing$ **viii** $A \cup B = \varnothing$

b Find the following probabilities.

i $\Pr(B)$ **ii** $\Pr(B')$ **iii** $\Pr(A \cap B)$

7 For each diagram, find the following probabilities.

i $\Pr(A \cap B)$ **ii** $\Pr(A \cup B)$ **iii** $\Pr(A')$

a



b



c

	A	A′	Total
B	5	2	
B′			
Total	9		15

d

	A	A′	Total
B		8	13
B′	4		
Total		12	

8–10 8–10 9, 10

PROBLEM-SOLVING

8 Four students have the names FRED, RON, RACHEL and HELEN while the sets A, B and C are defined by:

A = {students with a name including the letter R}

B = {students with a name including the letter E}

C = {students with a name including the letter Z}

a List the sets:

i A **ii** B

iii C **iv** $A \cap B$

b If a student is chosen at random from the group, find these probabilities.

i $\Pr(A)$ **ii** $\Pr(A')$ **iii** $\Pr(C)$

iv $\Pr(C')$ **v** $\Pr(A \cap B)$ **vi** $\Pr(A \cup B)$

9 Consider all the letters of the alphabet. Let A = {the set of vowels} and B = {different letters of the word MATHEMATICS}. Find:

a n(sample space) **b** $n(A)$

c $n(A \cap B)$ **d** $n(B')$

e $\Pr(A)$ **f** $\Pr(A')$

g $\Pr(A \cap B)$ **h** $\Pr(A \cup B)$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9C

PROBLEM-SOLVING

10 From 50 people all of which have at least a cat or a dog, let A be the set of all pet owners who have a dog and B be the set of all pet owners who have a cat. If $n(A) = 32$ and $n(B) = 29$, find the following.

a $n(A \cap B)$ **b** $n(A \text{ only})$

c $\Pr(A \cup B)$ **d** $\Pr(A')$

11, 13 | 11–13 | 12–15

REASONING

11 From Question **10**, A is the set of dog owners and B is the set of cat owners. Write a brief description of the following groups of people.

a $A \cap B$ **b** $A \cup B$ **c** B' **d** B only

12 **a** Is $n(A) + n(B)$ ever equal to $n(A \cup B)$? If so, show an example using a Venn diagram.

b Is $n(A) + n(B)$ ever less than $n(A \cup B)$? Explain.

13 The region A only could be thought of as the intersection of A and the complement of B so, A only = $A \cap B'$. Use set notation to describe the region 'B only'.



14 The four inner regions of a two-way table can be described using intersections. The A only region is described by $n(A \cap B')$. Describe the other three regions using intersections.

	A	A'	Total
B			$n(B)$
B'	$n(A \cap B')$		$n(B')$
Total	$n(A)$	$n(A')$	$n(\Omega)$

15 Research what it means if we say that two events A and B are **mutually exclusive**. Give a brief description.

How are $A' \cap B'$ and $(A \cup B)'$ related? | — | — | 16

ENRICHMENT

16 Consider the set of integers $\{1, 2, 3, \ldots, 20\}$. Let A = {prime numbers less than 20} and B = {factors of 12}.

a List:

i A **ii** B **iii** $A \cap B$

iv $A \cup B$ **v** $A' \cap B$ **vi** $A \cap B'$

vii $A' \cup B$ **viii** $A \cup B'$ **ix** $A' \cup B'$

b Find the following probabilities.

i $\Pr(A \cup B)$ **ii** $\Pr(A \cap B)$ **iii** $\Pr(A' \cap B)$ **iv** $\Pr(A' \cap B')$

v $\Pr(A \cup B')$ **vi** $\Pr((A \cap B)')$ **vii** $\Pr(A' \cup B')$ **viii** $\Pr((A \cup B)')$

c Draw Venn diagrams to shade the regions $A' \cap B'$ and $(A \cup B)'$. What do you notice?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9D Using arrays for two-step experiments

When an experiment consists of two steps like tossing two dice or selecting two people from a group, we can use a table to systematically list the sample space.

Let's start: Is it a 1 in 3 chance?

Billy tosses two coins on the kitchen table at home and asks what the chance is of getting two tails.

- Dad says that there are 3 outcomes: two heads, two tails or one of each, so there is a 1 in 3 chance.
- Mum says that with coins, all outcomes have a 1 in 2 chance of occurring.
- Billy's sister Betty says that there are 4 outcomes so it's a 1 in 4 chance.

Can you explain who is correct and why?

Tossing one coin gives a 1 in 2 chance of heads or tails, but what are the chances of getting two tails with two coins?

Key ideas

- An **array** or table is often used to list the sample space for experiments with two steps.
- When listing outcomes it is important to be consistent with the order for each outcome.
  For example: the outcome (heads, tails) is different from the outcome (tails, heads).
- Some experiments are conducted **without replacement**, which means some outcomes that may be possible **with replacement** are not possible.
  For example: Two letters are chosen from the word CAT.

With replacement

		1st		
		C	A	T
2nd	C	(C, C)	(A, C)	(T, C)
	A	(C, A)	(A, A)	(T, A)
	T	(C, T)	(A, T)	(T, T)

9 outcomes

Without replacement

		1st		
		C	A	T
2nd	C	×	(A, C)	(T, C)
	A	(C, A)	×	(T, A)
	T	(C, T)	(A, T)	×

6 outcomes

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 6 Finding the sample space for events with replacement

Two coins are tossed.

a Draw a table to list the sample space.

b Find the probability of obtaining (H, T).

c Find Pr(1 head).

SOLUTION

EXPLANATION

a

		Toss 1	
		H	T
Toss 2	H	(H, H)	(T, H)
	T	(H, T)	(T, T)

Sample space =
{(H, H), (H, T), (T, H), (T, T)}

Represent the results of each coin toss.

The table shows four possible outcomes.

b $\Pr(\text{H, T}) = \frac{1}{4}$

One of the four outcomes is (H, T).

c $\Pr(\text{1 head}) = \frac{2}{4} = \frac{1}{2}$

Two outcomes have one head: (H, T), (T, H).

Example 7 Finding the sample space for events without replacement

Two letters are chosen at random from the word TREE without replacement.

a List the outcomes in a table.

b Find the probability that the two letters chosen are both E.

c Find the probability that at least one of the letters is an E.

SOLUTION

EXPLANATION

a

		1st			
		T	R	E	E
2nd	T	×	(R, T)	(E, T)	(E, T)
	R	(T, R)	×	(E, R)	(E, R)
	E	(T, E)	(R, E)	×	(E, E)
	E	(T, E)	(R, E)	(E, E)	×

List all the outcomes maintaining a consistent order. Note that the same letter cannot be chosen twice.
Both Es need to be listed so that each outcome in the sample space is equally likely.

b $\Pr(\text{E, E}) = \frac{2}{12} = \frac{1}{6}$

Since there are 2 Es in the word TREE it is still possible to obtain the outcome (E, E) in two ways.

c $\Pr(\text{at least one E}) = \frac{10}{12} = \frac{5}{6}$

10 of the 12 outcomes contain at least one E.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 9D

1–3 | 2 | —

UNDERSTANDING

1 Fill in these tables to show all the outcomes then count the total number of outcomes. Parts **a** and **b** are *with replacement* and parts **c** and **d** are *without replacement*.

a

		1st		
		1	2	3
2nd	1	(1, 1)	(2, 1)	
	2			
	3			

b

		Die					
		1	2	3	4	5	6
Coin	H	(1, H)					
	T			(3, T)			

c

		1st		
		A	B	C
2nd	A	×	(B, A)	(C, A)
	B		×	
	C			×

d

		1st		
		●	○	○
2nd	●	×	(○, ●)	
	○		×	(○, ○)
	○			×

2 These two tables list the outcomes for the selection of two letters at random from the word MAT.

	Table A		
	M	A	T
M	(M, M)	(A, M)	(T, M)
A	(M, A)	(A, A)	(T, A)
T	(M, T)	(A, T)	(T, T)

	Table B		
	M	A	T
M	×	(A, M)	(T, M)
A	(M, A)	×	(T, A)
T	(M, T)	(A, T)	×

a Which table shows selection where replacement is allowed (with replacement)?

b Which table shows selection where replacement is not allowed (without replacement)?

c What is the probability of choosing the outcome (T, M) from:

i Table A? **ii** Table B?

d How many outcomes include the letter A using:

i Table A? **ii** Table B?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9D

UNDERSTANDING

3 Two dot circles are selected, one from each of the sets A and B where A = {●, ○} and B = {●, ○, ○}.

- **a** Copy and complete this table, showing all the possible outcomes.
- **b** State the total number of outcomes.
- **c** Find the probability that the outcome will:
  - **i** be (●, ○)
  - **ii** contain one black dot
  - **iii** contain two of the same dots.

		A	
		●	○
B	●	(●, ●)	(○, ●)
	○		
	○		

4–7 5–7 4, 6, 7

FLUENCY

Example 6

4 Two four-sided dice (numbered 1, 2, 3, 4) are tossed.

- **a** Complete a table like the one shown and list the sample space.
- **b** Find the probability of obtaining (2, 3).
- **c** Find Pr(double). A double is an outcome with two of the same number.

		1st			
		1	2	3	4
2nd	1	(1, 1)	(2, 1)		
	2				
	3				
	4				

5 A six-sided die is tossed twice.

- **a** Complete a table like the one shown.
- **b** What is the total number of outcomes?
- **c** Find the probability that the outcome is:
  - **i** (1, 1)
  - **ii** a double
  - **iii** (3, 1), (2, 2) or (1, 3)
  - **iv** any outcome containing a 1 or a 6.

		1st					
		1	2	3	4	5	6
2nd	1	(1, 1)	(2, 1)				
	2						
	3						
	4						
	5						
	6						

Example 7

6 Two letters are chosen at random from the word DOG *without replacement*.

- **a** Complete the given table.
- **b** Find the probability of obtaining the (G, D) outcome.
- **c** Find the probability of obtaining an outcome with an O in it.

		1st		
		D	O	G
2nd	D	×	(O, D)	(G, D)
	O		×	
	G			×

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9D

FLUENCY

7 Two digits are selected at random *without replacement* from the set $\{1, 2, 3, 4\}$.

a Draw a table to show the sample space. Remember doubles like (1, 1), (2, 2), etc. are not allowed.

b Find:

i Pr(1, 2) **ii** Pr(4, 3)

c Find the probability that:

i both numbers will be at least 3 **ii** the outcome will contain a 1 or a 4

iii the outcome will contain a 1 and a 4 **iv** the outcome will not contain a 3.

8–9 8–9 9–10

PROBLEM-SOLVING

8 The total sum is recorded from tossing two four-sided dice.

a Copy and complete this table, showing all possible totals that can be obtained.

		Toss 1			
		1	2	3	4
Toss 2	1	2	3		
	2				
	3				
	4				

b Find the probability that the total sum is:

i 2 **ii** 2 or 3

iii less than or equal to 4 **iv** more than 6 **v** at most 6.

9 Jill guesses the answers to two multiple-choice questions with options A, B, C, D or E.

a Copy and complete this table, showing all possible guesses that can be obtained.

		1st				
		A	B	C	D	E
Guess 2	A	(A, A)	(B, A)			
	B					
	C					
	D					
	E					

b Find the probability that she will guess:

i (D, A) **ii** the same letter **iii** different letters.

c Find the probability that Jill will get:

i exactly one of her answers correct **ii** both of her answers correct.

10 Many board games involve the tossing of two six-sided dice.

a Use a table to help find the probability that the sum of the two dice is:

i 12 **ii** 2 or 3

iii 11 or 12 **iv** less than or equal to 7

v less than 7 **vi** at least 10

vii at most 4 **viii** 1.

b Which total sum has the highest probability and what is the probability of tossing that sum?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11, 12 | 12–14 | 13–15

9D

REASONING

11 Two letters are chosen at random from the word MATHEMATICIAN.

a How many outcomes sit in the sample space if selections are made:

i with replacement? **ii** without replacement?

b How many of the outcomes contain the same letter if selection is made:

i with replacement? **ii** without replacement?

12 Two letters are chosen from the word WOOD without replacement. Is it possible to obtain the outcome (O, O)? Explain why.

13 In a bag are five counters each of a different colour: green (G), yellow (Y), red (R), blue (B) and purple (P).

a If one counter is drawn from the bag, replaced and then a second is selected, find the probability that a green counter then a blue counter is selected. That is, find Pr(G, B).

b If the first counter selected is not replaced before the second is selected, find the probability that a green counter then a blue counter is selected.

14 A six-sided die and a ten-sided die have been tossed simultaneously. What total sum(s) has the highest probability?

15 A spinner numbered 1 to 50 is spun twice. Find the probability that the total from the two spins is:

a 100 **b** 51 **c** 99 **d** 52 **e** 55

Two cards from the deck

— | — | 16

ENRICHMENT

16 Two cards are dealt to you from a pack of playing cards which includes four of each of {2, 3, 4, 5, 6, 7, 8, 9, 10, J, Q, K, A}. You keep both cards.

a Does this situation involve with replacement or without replacement?

b How many outcomes would there be in your sample space (all possible selections of two cards)?

c What is the probability of receiving an ace of diamonds and an ace of hearts?

d Find the probability of obtaining two cards which:

i are both twos

ii are both hearts.



Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9E Tree diagrams

Interactive

Widgets

HOTsheets

Walkthroughs

When experiments consist of two or more steps a tree diagram can be used to list the sample space. While tables are often used for two-step experiments, a tree diagram can be extended for experiments with any number of steps.

Let's start: What's the difference?

You are offered a choice of two pieces of fruit from a banana, an apple and an orange. You choose two at random. This tree diagram shows selection with replacement.

- How many outcomes will there be?
- How many of the outcomes contain two round fruits?
- How would the tree diagram change if the selection was completed without replacement? Would there be any difference in the answers to the above two questions? Discuss.



Key ideas

■ **Tree diagrams** are used to list the sample space for experiments with two or more steps.

- The outcomes for each stage of the experiment are listed vertically and each stage is connected with branches.

For example:

Tossing a coin 3 times (with replacement)



Selecting 2 letters from {A, B, C} (without replacement)



In these examples, each set of branches produce outcomes which are all equally likely.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 8 Constructing a tree diagram

An experiment involves tossing two coins.

a Complete a tree diagram to show all possible outcomes.

b What is the total number of outcomes?

c Find the probability of tossing:

i two tails **ii** one tail **iii** at least one head

SOLUTION	EXPLANATION
a Toss 1, Toss 2, Outcomes H → H: HH H → T: HT T → H: TH T → T: TT	The tree diagram shows two coin tosses one after the other resulting in $2 \times 2 = 4$ outcomes.
b The total number of outcomes is 4	There are four possibilities in the outcomes column.
c i $\Pr(TT) = \frac{1}{4}$	One out of the four outcomes is TT.
ii $\Pr(1 \text{ tail}) = \frac{2}{4} = \frac{1}{2}$	Two outcomes have one tail: {HT, TH}
iii $\Pr(\geq 1 \text{ head}) = \frac{3}{4}$	Three outcomes have at least one head: {HH, HT, TH}

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Constructing a tree diagram without replacement

Two people are selected at random without replacement from a group of three: Annabel (A), Brodie (B) and Chris (C).

a List all the possible outcomes for the selection using a tree diagram.

b Find the probability that the selection will contain:

i Annabel and Brodie **ii** Chris **iii** Chris or Brodie

SOLUTION

a



EXPLANATION

On the first choice there are three options (A, B or C) but on the second choice there are only two remaining.

b i $\Pr(\text{Annabel and Brodie}) = \frac{2}{6}$

$= \frac{1}{3}$

2 of the 6 outcomes contain Annabel and Brodie (A B) and (B A).

ii $\Pr(\text{Chris}) = \frac{4}{6}$

$= \frac{2}{3}$

4 out of the 6 outcomes contain Chris.

iii $\Pr(\text{Chris or Brodie}) = \frac{6}{6}$

$= 1$

All of the outcomes contain at least one of Chris or Brodie.

Exercise 9E

1, 2 | 1–2(½) | —

UNDERSTANDING

1 Find the total number of outcomes from these experiments *with replacement*. First, complete each tree diagram.

a Tossing a coin 3 times



b Selecting 2 letters from the word TO



Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9E

UNDERSTANDING

2 By first completing each tree diagram, find the total number of outcomes from these experiments *without replacement*.

a Selecting two letters from the word TWO



b Selecting two people from a group of three (A, B and C).



3–6 | 3, 5, 6, 7 | 4, 6, 7

FLUENCY

Example 8

3 A coin is tossed twice.



a Complete this tree diagram to show all the possible outcomes.

b What is the total number of outcomes?

c Find the probability of obtaining:

i two heads

ii one head

iii at least one head

iv at least one tail.

4 A spinner with three numbers, 1, 2 and 3, is spun twice.

a List the set of possible outcomes, using a tree diagram.

b What is the total number of possible outcomes?

c Find the probability of spinning:

i two 3s

ii at least one 3

iii no more than one 2

iv two odd numbers.

Example 9

5 Two people are selected at random without replacement from a group of three: Donna (D), Elle (E) and Fernando (F).

a List all the possible outcomes for the selection using a tree diagram.

b Find the probability that the selection will contain:

i Donna and Elle

ii Fernando

iii Fernando or Elle.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9E

FLUENCY

6 A drawer contains 2 red socks (R), 1 blue sock (B) and 1 yellow sock (Y) and two socks are selected at random without replacement.



- **a** Copy and complete this tree diagram.
- **b** Find the probability of obtaining:
  - **i** a red sock and a blue sock
  - **ii** two red socks
  - **iii** any pair of socks of the same colour
  - **iv** any pair of socks of different colour.

7 A student who has not studied for a multiple-choice test decides to guess the answers for every question. There are three questions, and three choices of answer (A, B and C) for each question. If only one of the possible choices (A, B or C) is correct for each question, find the probability that the student guesses:

a 1 correct answer **b** 2 correct answers **c** 3 correct answers **d** 0 correct answers.

8 9 9

PROBLEM-SOLVING

8 A discount supermarket shelf contains a large number of tomato tins and peach tins with no labels. There are an equal number of tins all mixed together on the same shelf. You select four tins in a hurry. Use a tree diagram to help find the probability of selecting the correct number of tins of tomatoes and/or peaches for each of these recipe requirements.

- **a** You need four tins of tomatoes for a stew.
- **b** You need four tins of peaches for a peach crumble.
- **c** You need at least three tins of tomatoes for a bolognaise.
- **d** You need at least two tins of peaches for a fruit salad.
- **e** You need at least one tin of tomatoes for a vegetable soup.

9 Michael needs to deliver parcels to three places (A, B and C in order) in the city. This diagram shows the different ways that he can travel.



- **a** Draw a tree diagram showing all the possible outcomes of transportation options.
- **b** What is the total number of possible outcomes?
- **c** If Michael randomly chooses one of these outcomes, find the probability that he will use:
  - **i** the train all three times
  - **ii** the train exactly twice
  - **iii** his bike exactly once
  - **iv** different transport each time
  - **v** a car at least once.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9E

10 | 10, 11 | 11, 12

REASONING

10 If a coin is tossed four times, use a tree diagram to find the probability that you receive:
a 0 tails **b** 1 tail **c** 2 tails **d** 3 tails **e** 4 tails

11 **a** A coin is tossed 5 times. How many outcomes will there be?
b A coin is tossed n times. Write a rule for the number of outcomes in the sample space.

12 Use a tree diagram to investigate the probability of selecting two counters from a bag of 3 black and 2 white counters if the selection is drawn:
a with replacement **b** without replacement.
Is there any difference?

Selecting matching clothes — | — | 13

ENRICHMENT

13 A man randomly selects a tie from his collection of one green and two red ties, a shirt from a collection of one red and two white shirts, and either a red or a black hat. Use a tree diagram to help find the probability that the man selects a tie, shirt and hat according to the following descriptions:
a a red tie, red shirt and black hat
b all three items red
c one item red
d two items red
e at least two items red
f a green hat
g a green tie and a black hat
h a green tie or a black hat
i not a red item
j a red tie or white shirt or black hat.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9F Experimental probability

In some situations it may not be possible to list all the outcomes in the sample space and find theoretical probabilities. If this is the case then an experiment, survey or simulation can be conducted to find experimental probabilities. Provided the experiment includes a sufficient number of trials, these probabilities can be used to estimate the chance of particular events. Experimental probability is frequently used in science experiments and for research in medicine and economics.

Let's start: Newspaper theories

A tabloid newspaper reports that of 10 people interviewed in the street 5 had a dose of the flu. At a similar time a medical student tested 100 people and found that 21 had the flu.

- What is the experimental probability of having the flu, according to the newspaper's survey?
- What is the experimental probability of having the flu, according to the medical student's results?
- Which of the two sets of results would be most reliable and why? Discuss the reasons.
- Using the results from the medical student, how many people would you expect to have the flu in a group of 1000 and why?

Key ideas

- **Experimental probability** or relative frequency is calculated using the results of an experiment or survey.

$$\text{Experimental probability} = \frac{\text{number of times the outcome occurs}}{\text{total number of trials in the experiment}} = \text{relative frequency}$$

- The **long-run proportion** is the experimental probability for a sufficiently large number of trials.
- The **expected number of occurrences** = probability × number of trials

Example 10 Finding the experimental probability

A box contains an unknown number of coloured balls and a ball is drawn from the box and then replaced. The procedure is repeated 100 times and the colour of the ball drawn is recorded each time. Twenty-five red balls were recorded.

a Find the experimental probability for selecting a red ball.

b Find the expected number of red balls if the box contained 500 balls in total.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a Pr(red ball) $= \frac{25}{100}$	Pr(red ball) $= \frac{\text{number of red balls drawn}}{\text{total number of balls drawn}}$
$= 0.25$	There are 25 red balls drawn and 100 balls in total.
b Expected number of red balls in 500	Expected number of occurrences
$= 0.25 \times 500$	= probability × number of trials
$= 125$	

Exercise 9F

1–3 | 3 | —

UNDERSTANDING

1 This table shows the results of three different surveys of how many people in Perth use public transport (PT).

Survey	Number who use PT	Survey size	Experimental probability
A	2	10	$\frac{2}{10} = 0.2$
B	5	20	_____
C	30	100	_____

a What are the two missing numbers in the experimental probability list?

b Which survey should be used to estimate the probability that a person uses public transport and why?

2 The experimental probability of Jess hitting a bullseye on a dartboard is 0.05 (or $\frac{5}{100}$). How many bullseyes would you expect Jess to get if she threw the following number of darts?

a 100 darts **b** 200 darts

c 1000 darts **d** 80 darts

3 The results of tossing a drawing pin and observing how many times the pin lands with the spike pointing up are shown in the table. Results are recorded at different stages of the experiment.

Number of throws	Frequency (spike up)	Experimental probability
1	1	1.00
5	2	0.40
10	5	0.50
20	9	0.45
50	18	0.36
100	41	0.41

Which experimental probability would you choose to best represent the probability that the pin will land spike up? Why?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9F

Example 10

4, 5 | 4–6 | 4–6

FLUENCY

4 A bag contains an unknown number of counters, and a counter is selected from the bag and then replaced. The procedure is repeated 100 times and the colour of the counter is recorded each time. Sixty of the counters drawn were blue.

- **a** Find the experimental probability for selecting a blue counter.
- **b** Find the expected number of blue counters if the bag contained:
  - **i** 100 counters **ii** 200 counters **iii** 600 counters.

5 In an experiment involving 200 people chosen at random, 175 people said that they owned a home computer.

- **a** Calculate the experimental probability of choosing a person who owns a home computer.
- **b** Find the expected number of people who own a home computer from the following group sizes.
  - **i** 400 people **ii** 5000 people **iii** 40 people

6 By calculating the experimental probability, estimate the chance that each of the following events will occur.

- **a** Nat will walk to work today, given that she walked to work five times in the last 75 working days.
- **b** Mike will win the next game of cards if, in the last 80 games, he has won 32.
- **c** Brett will hit the bullseye on the dartboard with his next attempt if, in the last 120 attempts, he was successful 22 times.

7, 8 | 8, 9 | 8–10

PROBLEM-SOLVING

7 A six-sided die is rolled 120 times. How many times would you expect the following events to occur?

- **a** a 6
- **b** a 1 or a 2
- **c** a number less than 4
- **d** a number that is at least 5

8 The colour of cars along a highway was noted over a short period of time and summarised in this frequency table.

Colour	White	Silver	Blue	Green
Frequency	7	4	5	4

- **a** How many cars had their colour recorded?
- **b** Find the experimental probability that a car's colour is:
  - **i** blue **ii** white.
- **c** If the colour of 100 cars was recorded, find the expected number of:
  - **i** blue cars
  - **ii** green cars
  - **iii** blue or green cars.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9F

PROBLEM-SOLVING

9 The letters from a three-letter word are written separately onto cards. A card is chosen at random and replaced and this is repeated 100 times. The results are shown in the table.

Letter	E	S
Frequency	64	36

a Find the experimental probability of obtaining an E.

b Based on these results what is the three-letter word likely to be?

10 A spinner is divided into three regions not necessarily of equal size. The regions are numbered 1, 2 and 3 and the spinner is spun 50 times. The table shows the results.

Number	1	2	3
Frequency	26	11	13

a Find the experimental probability of obtaining:

i a 1 **ii** at least a 2 **iii** a 1 or a 3.

b Based on these results, how many 3s would you expect if the spinner is spun 300 times?

c In fact, the spinner is divided up using simple and common fractions. Give a likely example describing how the regions might be divided.

11, 12 | 11–13 | 12–14

REASONING

11 Phil tossed a fair six-sided die 10 times and, incredibly, receives 9 sixes.

a Find the experimental probability of rolling a six.

b Is it likely that Phil will receive the same number of sixes if he tossed the die 10 more times? Explain.

12 Do you think that a coin is fair or biased given the following experimental results? Give reasons.

a 47 tails out of 100 tosses

b 23 heads out of 24 tosses

c 1 tail out of 1 toss

13 One hundred darts are randomly thrown at the given dartboards. No darts miss the dartboard entirely. How many darts do you expect to hit the blue shaded region? Give reasons.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9F

REASONING

14 Decide if the following statements are true.

- **a** The experimental probability is always equal to the theoretical probability.
- **b** The experimental probability can be greater than the theoretical probability.
- **c** If the experimental probability is zero then the theoretical probability is zero.
- **d** If the theoretical probability is zero then the experimental probability is zero.

ENRICHMENT

More than a guessing game — — 15, 16

15 A bag of 10 counters includes counters with four different colours. The results from drawing and replacing one counter at a time for 80 trials are shown in this table.
Use the given information to find out how many counters of each colour were likely to be in the bag.

Colour	Total
Blue	26
Red	17
Green	29
Yellow	8

16 A box of 12 chocolates all of which are the same size and shape include five different centres. The results from selecting and replacing one chocolate at a time for 60 trials are shown in this table.
Use the given information to find out how many chocolates of each type were likely to be in the box.

Centre	Total
Strawberry	11
Caramel	14
Coconut	9
Nut	19
Mint	7

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9G Summarising data: measures of centre

The discipline of statistics involves collecting and summarising data. It also involves drawing conclusions and making predictions, which is why many of the decisions we make today are based on statistical analysis. The type and amount of product stocked on supermarket shelves, for example, is determined by the sales statistics and other measures such as average cost and price range.

Let's start: Game purchase

Arathi purchases 7 computer games at a sale. 3 games cost $20 each, 2 games cost $30, 1 game costs $50 and the last game cost $200.

- Recall and discuss the meaning of the words mean, median and mode.
- Can you work out the mean, median or mode for the cost of Arathi's games?
- Which of the mean, median or mode gives the best 'average' for the cost of Arathi's games?
- Why is the mean greater than the median in this case?

Key ideas

- The **mean** and **median** are called **measures of centre** because they give some idea of the 'average' or middle of the data set.
- **Mean ($\bar{x}$)**

  If there are n values, $x_1, x_2, x_3, \ldots x_n$, then the mean is calculated as follows:

$$\bar{x} = \frac{\text{sum of all data values}}{\text{number of data values}}$$

$$= \frac{x_1 + x_2 + x_3 + \cdots + x_n}{n}$$

- **Median**

  The median is the middle value if the data is placed in order.
  - If there are two middle values, the median is calculated as the mean of these two values.

Odd number of values

1 3 5 (5) 6 7 10

median

Even number of values

13 17 17 20 21 27 27 28

20.5

median

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Mode**
  The mode is the most common value.
  - There can be more than one mode.
  - If there are two modes, we say that the data set is **bimodal**.
  - If each data value occurs just once, there is no mode.
- An **outlier** is a score that is much larger or smaller than the rest of the data.

Example 11 Finding measures of centre

For the given data sets, find the following.

i the mean ii the median iii the mode

a 5 2 4 10 6 1 2 9 6

b 17 13 26 15 9 10

SOLUTION

EXPLANATION

a i $\text{Mean} = \frac{5+2+4+10+6+1+2+9+6}{9}$

$= 5$

Find the sum of all the numbers and divide by the number of values.

ii 1 2 2 4 (5) 6 6 9 10

Median = 5

First, order the data.
The median is the middle value.

iii Mode = 2 and 6

The data set is bimodal since there are two numbers with the highest frequency.

b i $\text{Mean} = \frac{17+13+26+15+9+10}{6}$

$= 15$

The sum is 90 and there are 6 values.

ii 9 10 13 15 17 26

14

First, order the data.

$\text{Median} = \frac{13+15}{2}$

$= 14$

Since there are two values in the middle find the mean of them.

iii No mode

None of the values are repeated so there is no mode.

Example 12 Finding a data value for a required mean

The hours a shop assistant spends cleaning the store in eight successive weeks are:
8, 9, 12, 10, 10, 8, 5, 10.

a Calculate the mean for this set of data.

b How many hours would the shop assistant need to clean in the ninth week for the mean to equal 10?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a Mean $= \frac{8+9+12+10+10+8+5+10}{8}$	Sum of the 8 data values is 72.
$= 9$	
b Let a be the number of hours in the ninth week.	
Require $\frac{72+a}{8+1} = 10$	$72 + a$ is the total of the new data and $8 + 1$ is the new total number of data values. Set this equal to the required mean of 10.
$\frac{72+a}{9} = 10$	
$72 + a = 90$	Solve for a.
$a = 18$	
The new score would need to be 18.	Write the answer.

Exercise 9G

1, 2 | 1 | —

UNDERSTANDING

1 Write the missing word.

a The mode is the most _____ value. **b** The median is the _____ value.

c To calculate the _____, you add up all the values and divide by the number of values.

2 Find the mean, median and mode for these simple ordered data sets.

a 1 2 2 2 4 4 6 **b** 1 4 8 8 9 10 10 10 12

c 1 5 7 7 8 10 11 **d** 3 3 6 8 10 12

e 7 11 14 18 20 20 **f** 2 2 2 4 10 10 12 14

3–5(½) | 3–5(½) | 3–5(½)

FLUENCY

Example 11

3 For the given data sets, find:

i the mean **ii** the median **iii** the mode

a 7 2 3 8 5 9 8 **b** 6 13 5 4 16 10 3 5 10

c 12 9 2 5 8 7 2 3 **d** 10 17 5 16 4 14

e 3.5 2.1 4.0 8.3 2.1 **f** 0.7 3 2.9 10.4 6 7.2 1.3 8.5

g 6 0 –3 8 2 –3 9 5 **h** 3 –7 2 3 –2 –3 4

4 These data sets include an outlier. Write down the outlier then calculate the mean and the median. Include the outlier in your calculations.

a 5 7 7 8 12 33 **b** 1.3 1.1 1.0 1.7 1.5 1.6 –1.1 1.5

c –58 –60 –59 –4 –64

5 Decide if the following data sets are bimodal.

a 2 7 9 5 6 2 8 7 4 **b** 1 6 2 3 3 1 5 4 1 9

c 10 15 12 11 18 13 9 16 17 **d** 23 25 26 23 19 24 28 26 27

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9G

6–8 | 7–9 | 7–10

PROBLEM-SOLVING

6 In three races Paula recorded the times 25.1 seconds, 24.8 seconds and 24.1 seconds.

- **a** What is the mean time of the races? Round to two decimal places.
- **b** Find the median time.

Example 12

7 A netball player scored the following number of goals in her 10 most recent games:
15 14 16 14 15 12 16 17 16 15

- **a** What is her mean score?
- **b** What number of goals does she need to score in the next game for the mean of her scores to be 16?

8 Stevie obtained the following scores on her first five Maths tests:
92 89 94 82 93

- **a** What is her mean test score?
- **b** If there is one more test left to complete, and she wants to achieve an average of at least 85, what is the lowest score Stevie can obtain for her final test?

9 Seven numbers have a mean of 8. Six of the numbers are 9, 7, 6, 4, 11 and 10. Find the seventh number.

10 Write down a set of 5 numbers which has the following values:

- **a** a mean of 5, median of 6 and mode of 7
- **b** a mean of 5, median of 4 and mode of 8
- **c** a mean of 4, median of 4 and mode of 4
- **d** a mean of 4.5, median of 3 and mode of 2.5
- **e** a mean of 1, median of 0 and mode of 5
- **f** a mean of 1, median of $1\frac{1}{4}$ and mode of $1\frac{1}{4}$.

11, 12 | 11–13 | 12–14

REASONING

11 This data contains six houses prices in Darwin.
$324 000 $289 000 $431 000 $295 000 $385 000 $1 700 000

- **a** Which price would be considered the outlier?
- **b** If the outlier was removed from the data set, by how much would the median change? (First work out the median for each case.)
- **c** If the outlier was removed from the data set, by how much would the mean change, to the nearest dollar? (First work out the mean for each case.)

12 Explain why outliers significantly affect the mean but not the median.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9G

REASONING

13 This dot plot shows the frequency of households with 0, 1, 2 or 3 pets.



- **a** How many households were surveyed?
- **b** Find the mean number of pets.
- **c** Find the median number of pets.
- **d** Find the mode.
- **e** Another household with 7 pets is added to the list. Does this change the median? Explain.

14 This simple data set contains nine numbers.

1 2 2 2 2 2 3 4 5

- **a** Find the median.
- **b** How many numbers greater than 5 need to be added to the list to change the median? (Give the least number.)
- **c** How many numbers less than 1 need to be added to the list to change the median? (Give the least number.)

Formula to get an A — — 15

ENRICHMENT

15 A school awards grades in Mathematics each semester according to this table.

Average score	Grade
90–100	A+
80–	A
70–	B+
60–	B
50–	C+
0–	C

Ryan has scored the following results for four topics this semester and has one topic to go.

75 68 85 79

- **a** What is Ryan's mean score so far?
- **b** What grade will Ryan get for the semester if his fifth score is:
  - **i** 50? **ii** 68? **iii** 94?
- **c** Find the maximum average score Ryan can receive for the semester. Is it possible for him to get an A+?
- **d** Find the least score that Ryan needs in his fifth topic for him to receive an average of:
  - **i** B+ **ii** A
- **e** Write a rule for the mean score M for the semester if Ryan receives a mark of m in the fifth topic.
- **f** Write a rule for the mark m in the fifth topic if he wants an average of M for the semester.

Using a CAS calculator 9G: Finding measures of centre

The activity is in the interactive textbook in the form of a printable PDF.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

9A **1** List the sample space for:

a rolling a standard die

b the gender of a set of twins.

9A **2** Find the probability of choosing a vowel, when choosing one letter at random, from the word MATHEMATICS.

9B **3** A survey of 40 sporty people found 28 liked tennis and 25 liked squash, with 13 liking both.

a Construct a Venn diagram for these results.

b How many people like both tennis and squash?

c If one of the 40 people are chosen at random, what is the probability that they like only one sport?

9B **4** Use this two-way table to find the probability that a randomly selected car has both a sunroof and air-conditioning.

	Aircon	No aircon	Total
Sunroof		9	
No sunroof	55	6	61
Total		15	100

9C **5** A number is chosen from the set of positive integers between 10 and 20, inclusive. If A is the set of even numbers between 10 and 20, inclusive, and B is the set of numbers divisible by 3 between 10 and 20, inclusive:

a list the sets:

i the sample space

ii A

iii B

iv $A \cup B$.

b find:

i $n(A \cap B)$

ii $\Pr(A \cup B)$

iii $\Pr(A')$.

9D **6** Find the probability of:

a obtaining a head and a tail if two coins are tossed

b choosing two vowels from the word MATE if two letters are chosen at random, without replacement

c rolling a double 6 or a double 3 if two standard dice are rolled.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9E **7** Two letters are chosen, without replacement, from the letters of the word WAY.

- **a** List all the possible combinations for the selection using a tree diagram.
- **b** Find the probability that the selection will contain:
  - **i** the letter A
  - **ii** W or Y
  - **iii** not a Y
  - **iv** a W as the first letter.

9F **8** A drawer contains an unknown number of blue, black and white single socks. One sock is chosen at random from the drawer and its colour recorded, before it is returned to the drawer. The outcome of this experiment is recorded in the table below.

Colour	Blue	Black	White
Frequency	16	44	40

Find the experimental probability of choosing:

- **a** a white sock
- **b** a blue or a white sock.

9F **9** If a six sided die is rolled 420 times, how many times would you expect a 1 or a 2 to appear?

9G **10** For the data 8, 9, 4, 3, 9, 10, 9, 6, 5, find the:

- **a** mean
- **b** median
- **c** mode.

9G **11** James has a mean of 82% in 5 chapter tests so far this year. What score does James need to achieve in the next test if he hopes to increase his mean to 85%?

9G **12** The selling price for four properties in Perth were as follows: $759 000, $1.4 million, $4.15 million and $849 000.

- **a** Which selling price would be considered an outlier?
- **b** What is the mean selling price of the 4 properties?
- **c** What is the median selling price of these 4 properties?
- **d** Recalculate the mean and median if the outlier is removed. Answer to the nearest dollar.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9H Stem-and-leaf plots

Stem-and-leaf plots (or stem plots) are commonly used to display a single data set or two related data sets. They help to show how the data is distributed like a histogram but retain all the individual data elements so no detail is lost. The median and mode can be easily read from a stem-and-leaf plot because all the data sits in order.



For this data below, digits representing the stem give the tens and digits representing the leaves give the units.

Let's start: Ships vs Chops

At a school, Ms Ships' class and Mr Chops' class sit the same exam. The scores are displayed using this back-to-back stem-and-leaf plot. Discuss the following.

Ms Ships' class					Mr Chops' class						
			3	1	5	0	1	1	3	5	7
	8	8	7	5	6	2	3	5	5	7	9	9
6	4	4	2	1	7	8	9	9			
		7	4	3	8	0	3				
				6	9	1					

7 | 8 means 78

- Which class had the most students?
- What were the lowest and highest scores from each class?
- What were the median scores from each class?
- Which class could be described as symmetrical and which as skewed?
- Which class had the better results?

Key ideas

- A **stem-and-leaf plot** uses a stem number and leaf number to represent data.
  - The data is shown in two parts: a stem and a leaf.
  - The 'key' tells you how the plot is to be read.
  - The graph is similar to a histogram on its side or a bar graph with class intervals but there is no loss of detail of the original data.

Ordered stem-and-leaf plot

Stem	Leaf
1	2 6
2	2 3 4 7
3	1 2 4 7 8 9
4	2 3 4 5 8
5	7 9

2 | 4 represents 24 people

A key is added to show the place value of the stems and leaves.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Back-to-back stem-and-leaf plots** can be used to compare two sets of data. The stem is drawn in the middle with the leaves on either side.

Scores for the last 30 football games

Winning scores		Losing scores
	7	4 5 8 8 9
1	8	0 0 3 3 6 7
7 5	9	1 2 3 6
8 4 4 1	10	3 9
9 5 0	11	1
3 1	12	

81 lowest winning score

Symmetrical

Skewed

111 highest losing score

10|9 represents 109

- **Symmetrical data** will produce a graph which is symmetrical about the centre.
- **Skewed data** will produce a graph which includes data bunched to one side of the centre.

Example 13 Constructing and using a stem-and-leaf plot

Consider this set of data.

0.3 2.5 4.1 3.7 2.0 3.3 4.8 3.3 4.6 0.1 4.1 7.5 1.4 2.4
5.7 2.3 3.4 3.0 2.3 4.1 6.3 1.0 5.8 4.4 0.1 6.8 5.2 1.0

a Organise the data into an ordered stem-and-leaf plot.

b Find the median.

c Find the mode.

d Describe the data as symmetrical or skewed.

SOLUTION

a

Stem	Leaf
0	1 1 3
1	0 0 4
2	0 3 3 4 5
3	0 3 3 4 7
4	1 1 1 4 6 8
5	2 7 8
6	3 8
7	5

3 | 4 means 3.4

b $\text{Median} = \frac{3.3 + 3.4}{2}$

$= 3.35$

EXPLANATION

The minimum is 0.1 and the maximum is 7.5 so stems range from 0 to 7.

Place leaves in order from smallest to largest. Since some numbers appear more than once, e.g. 0.1, their leaf (1) appears the same number of times.

There are 28 data values. The median is the average of the two middle values (the 14th and 15th values).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c Mode is 4.1.

The most common value is 4.1.

d Data is approximately symmetrical.

The distribution of numbers is approximately symmetrical about the stem containing the median.

Statisticians work in many fields, particularly business, finance, health, government, science and technology.

Example 14 Constructing back-to-back stem-and-leaf plots

A shop owner has two jeans shops. The daily sales in each shop over a 16-day period are monitored and recorded as follows.

Shop A

3 12 12 13 14 14 15 15 21 22 24 24 24 26 27 28

Shop B

4 6 6 7 7 8 9 9 10 12 13 14 14 16 17 27

a Draw a back-to-back stem-and-leaf plot with an interval of 10.

b Compare and comment on differences between the sales made by the two shops.

SOLUTION

a

Shop A		Shop B
3	0	4 6 6 7 7 8 9 9
5 5 4 4 3 2 2	1	0 2 3 4 4 6 7
8 7 6 4 4 4 2 1	2	7

1 | 3 means 13

b Shop A has the highest number of daily sales. Its sales are generally between 12 and 28, with one day of very low sales of 3. Shop B sales are generally between 4 and 17 with only one high sale day of 27.

EXPLANATION

The data for each shop is already ordered. Stems are in intervals of 10. Record leaf digits for Shop A on the left and Shop B on the right.

Look at both sides of the plot for the similarities and differences.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 9H

1, 2 | 2 | —

UNDERSTANDING

1 This stem-and-leaf plot shows the number of minutes Alexis spoke on her phone for a number of calls.

Stem	Leaf
0	8
1	5 9
2	1 1 3 7
3	4 5

2 | 1 means 21 minutes

a How many calls are represented by the stem-and-leaf plot?

b What is the length of the:

i shortest phone call? **ii** longest phone call?

c What is the mode (the most common call time)?

d What is the median call time (middle value)?

2 This back-to-back stem-and-leaf plot shows the thickness of tyre tread on a selection of cars from the city and country.

City		Country
8 7 3 1 0 0 0	0	6 8 8 9
8 6 3 1 1 0	1	4 5 5 6 9
1	2	3 4 4

1 | 3 means 13 mm

a How many car tyres were tested altogether?

b What was the smallest tyre tread thickness in:

i the city? **ii** the country?

c What was the largest tyre tread thickness in:

i the city? **ii** the country?

d Find the median tyre tread thickness for tyres in:

i the city **ii** the country.

e Is the distribution of tread thickness for city cars more symmetrical or skewed?

f Is the distribution of tread thickness for country cars more symmetrical or skewed?

3(½), 4, 5(½), 6 | 3(½), 5(½), 6, 7 | 3(½), 5(½), 6, 7

FLUENCY

Example 13

3 For each of the following data sets:

i organise the data into an ordered stem-and-leaf plot

ii find the median **iii** find the mode

iv describe the data as symmetrical or skewed.

a 41 33 28 24 19 32 54 35 26 28 19 23 32 26 28

b 31 33 23 35 15 23 48 50 35 42 45 15 21 45
51 31 34 23 42 50 26 30 45 37 39

c 34.5 34.9 33.7 34.5 35.8 33.8 34.3 35.2 37.0 34.7
35.2 34.4 35.5 36.5 36.1 33.3 35.4 32.0 36.3 34.8

d 167 159 159 193 161 164 167 157 158 175 177 185
177 202 185 187 159 189 167 159 173 198 200

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9H

FLUENCY

4 The number of vacant rooms in a motel each week over a 20-week period is shown below.

12 8 11 10 21 12 6 11 12 16 14 22 5 15 20 6 17 8 14 9

a Draw a stem-and-leaf plot of this data.

b In how many weeks were there fewer than 12 vacant rooms?

c Find the median number of vacant rooms.

Example 14

5 For each of the following sets of data:

i draw a back-to-back stem-and-leaf plot.

ii compare and comment on the difference between the two data sets.

a

Set A: 46 32 40 43 45 47 53 54 40 54 33 48 39 43

Set B: 48 49 31 40 43 47 48 41 49 51 44 46 53 44

b

Set A: 1 43 24 26 48 50 2 2 36 11 16 37 41 3 36

6 8 9 10 17 22 10 11 17 29 30 35 4 23 23

Set B: 9 18 19 19 20 21 23 24 27 28 31 37 37 38 39 39 39

40 41 41 43 44 44 45 47 50 50 51 53 53 54 54 55 56

c

Set A: 0.7 0.8 1.4 8.8 9.1 2.6 3.2 0.3 1.7 1.9 2.5 4.1 4.3 3.3 3.4

3.6 3.9 3.9 4.7 1.6 0.4 5.3 5.7 2.1 2.3 1.9 5.2 6.1 6.2 8.3

Set B: 0.1 0.9 0.6 1.3 0.9 0.1 0.3 2.5 0.6 3.4 4.8 5.2 8.8 4.7 5.3

2.6 1.5 1.8 3.9 1.9 0.1 0.2 1.2 3.3 2.1 4.3 5.7 6.1 6.2 8.3

6 **a** Draw back-to-back stem-and-leaf plots for the final scores of St. Kilda and Collingwood in the 24 games given here.

St. Kilda:

126	68	78	90	87	118
88	125	111	117	82	82
80	66	84	138	109	113
122	80	94	83	106	68

Collingwood:

104	80	127	88	103	95
78	118	89	82	103	115
98	77	119	91	71	70
63	89	103	97	72	68



b In what percentage of games did each team score more than 100 points?

c Comment on the distribution of the scores for each team.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9H

FLUENCY

7 The data below gives the maximum temperature each day for a three-week period in spring.

18	18	15	17	19	17	21
20	15	17	15	18	19	19
20	22	19	17	19	15	17

Use a stem-and-leaf plot to determine the following:

- **a** how many days the temperature was higher than 18°C
- **b** the median temperature
- **c** the difference in the minimum and maximum temperatures.

8 | 8 | 8, 9

PROBLEM-SOLVING

8 This stem-and-leaf plot shows the time taken, in seconds, by Helena to run 100 m in her last 25 races.

Stem	Leaf
14	9
15	4 5 6 6 7 7 7 8 9
16	0 0 1 1 2 2 3 4 4 5 5 5 7 7
17	2

14 | 9 represents 14.9 seconds

- **a** Find Helena's median time.
- **b** What is the difference between the slowest and fastest time?
- **c** If in her 26th race her time was 14.8 seconds and this was added to the stem-and-leaf plot, would her median time change? If so, by how much?

9 Two brands of batteries were tested to determine their lifetime in hours. The data below shows the lifetime of 20 batteries of each brand.

Brand A:	7.3	8.2	8.4	8.5	8.7	8.8	8.9	9.0	9.1	9.2
	9.3	9.4	9.4	9.5	9.5	9.6	9.7	9.8	9.9	9.9
Brand B:	7.2	7.3	7.4	7.5	7.6	7.8	7.9	7.9	8.0	8.1
	8.3	9.0	9.1	9.2	9.3	9.4	9.5	9.6	9.8	9.8

- **a** Draw a back-to-back stem-and-leaf plot for this data.
- **b** How many batteries from each brand lasted more than 9 hours?
- **c** Compare the two sets of data and comment on any similarities or differences.

10, 11 | 10–12 | 10, 12, 13

REASONING

10 This ordered stem-and-leaf plot has some unknown digits.

0	2 3 8
1	1 5 *a* 8
c	0 *b* 6 6 2
3	2 5 9

3 | 5 means 0.35

- **a** What is the value of c?
- **b** What is the smallest number in the data set?
- **c** What values could the following pronumerals take?
  - **i** a
  - **ii** b

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9H

REASONING

11 The back-to-back stem-and-leaf plot below shows the birth weight in kilograms of babies born to mothers who do or don't smoke.

Birth weight of babies

Smoking mothers										Non-smoking mothers								
					4	3	2	2	2	4								
	9	9	8	7	6	6	5	5	2*	8	9							
4	3	2	1	1	1	0	0	0	3	0	0	1	2	2	3			
						6	5	5	3*	5	5	5	6	6	7	7	8	
								1	4									
									4*	5	5	6						

2 | 4 means 2.4

2* | 5 means 2.5

Do babies born to mothers who smoke weigh more or less than those born to mothers who don't smoke?

a What percentage of babies born to smoking mothers have a birth weight of less than 3 kg?

b What percentage of babies born to non-smoking mothers have a birth weight of less than 3 kg?

c Compare and comment on the differences between the birth weights of babies born to mothers who smoke and those born to mothers who don't smoke.

12 Explain why in a symmetrical distribution the mean is close to the median.

13 Find the median if all the data in each back-to-back stem-and-leaf plot was combined.

a

				5	3	8	9			
	9	7	7	1	4	0	2	2	3	6	8
8	6	5	2	2	5	3	3	7	9		
		7	4	0	6	1	4			

4 | 2 means 42

b

					3	16	0	3	3	6	7	9
			9	6	6	1	17	0	1	1	4	8	8
8	7	5	5	4	0	18	2	2	6	7		
					2	19	0	1				

16 | 3 means 16.3

ENRICHMENT

How skewed? — — 14

14 Skewness can be positive or negative. If the tail of the distribution is pointing up in a stem-and-leaf plot (towards the smaller numbers) then we say the data is negatively skewed. If the tail is pointing in the reverse direction then the data is positively skewed.

1	3	
2	1	4
3	0	2	7
4	1	1	3	8	9	9
5	0	4	4	5	7	

3 | 2 means 32

Negatively skewed data

a Find the mean (correct to two decimal places) and the median for the above data.

b Which of the mean or median is higher for the given data? Can you explain why?

c Which of the mean or median would be higher for a set of positively skewed data? Why?

d What type of distribution would lead to the median and mean being quite close?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9I Grouped data

Interactive

Widgets

HOTsheets

Walkthroughs

For some data, especially large sets, it makes sense to group the data and then record the frequency for each group to produce a frequency table. For numerical data, a graph generated from a frequency table gives a histogram. Like a stem-and-leaf plot, a histogram shows how the data is distributed across the full range of values. A histogram, for example, is used to display the level of exposure of the pixels in an image in digital photography. It uses many narrow columns to show how the luminance values are distributed across the scale from black to white.



A luminance value histogram used in digital photography software.

Let's start: Baggage check

This histogram shows the distribution of the weight of a number of bags checked at the airport.

- How many bags had a weight in the range 10–15 kg?
- How many bags were checked in total?
- Is it possible to determine the exact mean, median or mode of the weight of the bags by looking at the histogram? Discuss.
- Describe the distribution of checked bag weights for the given graph.



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- A **frequency table** shows the number of values within a set of categories or **class intervals**.
- Grouped numerical data can be illustrated using a **histogram**.
  - The height of a column corresponds to the frequency of values in that class interval.
  - There are usually no gaps between columns.
  - The scales are evenly spread with each bar spreading across the boundaries of the class interval.
  - A **percentage frequency histogram** shows the frequencies as percentages of the total.
- Like a stem-and-leaf plot, a histogram can show if the data is **skewed** or **symmetrical**.

Frequency table

Class interval	Frequency	Percentage frequency
60–	3	12
65–	4	16
70–	6	24
75–	8	32
80–85	4	16
Total	25	100

Frequency histogram



This gap may be used when our intervals do not start at zero.

Percentage frequency histogram



- In this frequency table, 70– includes numbers from 70 to less than 75.

Example 15 Constructing frequency tables and histograms

The data below shows the number of hamburgers sold each hour by a 24-hour fast-food store during a 50-hour period.

1	10	18	14	20	11	19	10	17	21
5	16	7	15	21	15	10	22	11	18
12	12	3	12	8	12	6	5	14	14
14	4	9	15	17	19	6	24	16	17
14	11	17	18	19	19	19	18	18	20

a Set up and complete a grouped frequency table, using class intervals 0–, 5–, 10–, etc. Include a percentage frequency column.

b Construct a frequency histogram.

c How many hours did the fast-food store sell:

i fewer than 10 hamburgers?

ii at least 15 hamburgers?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION

a

Class interval	Frequency	Percentage frequency
0–	3	6
5–	7	14
10–	15	30
15–	19	38
20–25	6	12
Total	50	100

EXPLANATION

Create class intervals of 5 from 0 up to 25, since 24 is the maximum number. Record the number of data values in each interval in the frequency column. Convert to a percentage by dividing by the total (50) and multiplying by 100.

b



Create a frequency histogram with frequency on the vertical axis and the class intervals on the horizontal axis. The height of the column shows the frequency of that interval.

c **i** 3 + 7 = 10 hours

Fewer than 10 hamburgers covers the 0–4 and 5–9 intervals.

ii 19 + 6 = 25 hours

At least 15 hamburgers covers the 15–19 and 20–24 intervals.

Exercise 9I

1–3 | 3 | —

UNDERSTANDING

1 This frequency histogram shows in how many years the number of international visitors to South Australia is within a given range for the decade from 2000 to 2009.

a How many years in the decade were there less than 330 000 international visitors?

b Which range of visitor numbers had the highest frequency?



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

91

UNDERSTANDING

2 Write down the missing numbers in these frequency tables, i.e. find the values of the pronumerals.

a

Class interval	Frequency	Percentage frequency
0–4	1	10
5–9	3	*c*
10–14	4	*d*
a–19	*b*	*e*
Total	10	*f*

b

Class interval	Frequency	Percentage frequency
40–	20	20
a–	28	*b*
60–	12	*c*
70–79	*d*	40
Total	100	*e*

3 This frequency histogram shows in how many books the number of pages is within a given interval for some textbooks selected from a school library.

a How many textbooks had between 100 and 200 pages?

b How many textbooks were selected from the library?

c What percentage of textbooks had between:

i 200 and 300 pages?

ii 200 and 400 pages?



4, 5, 7 | 4, 6, 7 | 4, 6, 7

FLUENCY

Example 15

4 The data below shows the number of ice creams sold from an ice cream van over a 50-day period.

0	5	0	35	14	15	18	21	21	36	45	2	8
2	2	3	17	3	7	28	35	7	21	3	46	47
1	1	3	9	35	22	7	18	36	3	9	2	2
11	37	37	45	11	12	14	17	22	1	2		

a Set up and complete a grouped frequency table using class intervals 0–, 10–, 20–, etc. Include a percentage frequency column.

b Construct a frequency histogram.

c How many days did the ice cream van sell:

i fewer than 20 ice creams?

ii at least 30 ice creams?

d What percentage of days were 20 or more ice creams sold?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 The data below shows the mark out of 100 on the Science exam for 60 Year 9 students.

50	67	68	89	82	81	50	50	89	52	60	82	52	60	87	89	71	73	75	83
86	50	52	71	80	95	87	87	87	74	60	60	61	63	63	65	82	86	96	88
50	94	87	64	64	72	71	72	88	86	89	69	71	80	89	92	89	89	60	83

a Set up and complete a grouped frequency table, using class intervals 50–, 60–, 70–, etc. Include a percentage frequency column rounding to two decimal places where necessary.

b Construct a frequency histogram.

c **i** How many marks were less than 70 out of 100?

ii What percentage of marks were at least 80 out of 100? Answer correct to one decimal place.

6 The number of goals kicked by a country footballer in each of his last 30 football matches is given below.

8	9	3	6	12	14	8	3	4	5	2	5	6	4	13
8	9	12	11	7	12	14	10	9	8	12	10	11	4	5

a Organise the data into a grouped frequency table using a class interval width of 3 starting at 0.

b Draw a frequency histogram for the data.

c In how many games did the player kick fewer than six goals?

d In how many games did he kick more than 11 goals?

7 Which one of these histograms illustrates a symmetrical data set and which one shows a skewed data set?

a



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

91

8, 9 | 8, 9 | 8, 10

PROBLEM-SOLVING

8 Find the unknown numbers (pronumerals) in these frequency tables.

a

Class interval	Frequency	Percentage frequency
10–	*a*	15
15–	11	*b*
20–	7	*c*
25–	*d*	10
30–34	*e*	*f*
Total	40	*g*

b

Class interval	Frequency	Percentage frequency
0–	*a*	2
3–	9	*b*
6–	*c*	16
9–	12	*d*
12–14	*e*	*f*
Total	50	*g*

9 This percentage frequency histogram shows the heights of office towers in a city.



a What percentage of office towers have the following heights?

i between 50 m and 100 m

ii less than 150 m

iii no more than 200 m

iv at least 100 m

v between 100 m and 150 m or greater than 200 m

b If the city had 100 office towers, how many have a height of:

i between 100 m and 150 m?

ii at least 150 m?

c If the city had 40 office towers, how many have a height of:

i between 0 m and 50 m?

ii no more than 150 m?

10 The data below shows the length of overseas phone calls (in minutes) made by a particular household over a six-week period.

1.5	1	1.5	1.4	8	4	4	10.1	9.5	1	3
8	5.9	6	6.4	7	3.5	3.1	3.6	3	4.2	4.3
4	12.5	10.2	10.3	4.5	4.5	3.4	3.5	3.5	5	3.5
3.6	4.5	4.5	12	11	12	14	14	12	13	10.8
12.1	2.4	3.8	4.2	5.6	10.8	11.2	9.3	9.2	8.7	8.5

What percentage of phone calls were more than 3 minutes in length? Answer to one decimal place.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 | 11, 13 | 11–13

9I

REASONING

11 Explain why you cannot work out the exact value for the mean, median and mode for a set of data presented in a histogram.

12 What can you work out from a frequency histogram that you cannot work out from a percentage frequency histogram? Completing Question **9** will provide a clue.

13 Two students show different histograms for the same set of data.



a Which histogram is more useful in helping to analyse the data?

b What would you advise student B to do differently when constructing the histogram?

ENRICHMENT

The distribution of weekly wages — | — | 14

14 The data below shows the weekly wages of 50 people in dollars.

400	500	552	455	420	424	325	204	860	894	464	379	563
940	384	370	356	345	380	720	540	654	678	628	656	670
740	750	730	766	760	700	700	768	608	576	890	920	874
450	674	725	612	605	600	548	670	230	725	860		

a What is the minimum weekly wage and the maximum weekly wage?

b **i** Organise the data into about 10 class intervals.

ii Draw a frequency histogram for the data.

c **i** Organise the data into about 5 class intervals.

ii Draw a frequency histogram for the data.

d Discuss the shapes of the two graphs. Which graph represents the data better and why?

Using a CAS calculator 9I: Graphing grouped data

The activity is in the interactive textbook in the form of a printable PDF.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9J Measures of spread

The mean, median and mode are three numbers which help define the centre of a data set; however, it is also important to describe the spread. Two teams of swimmers from different countries, for example, might have similar mean race times but the spread of race times for each team could be very different.

Let's start: Swim times

Two Olympic swimming teams are competing in the 4 × 100 m relay. The 100 m personal best times for the four members of each team are:

Team A: 48.3 s, 48.5 s, 48.9 s, 49.2 s

Team B: 47.4 s, 48.2 s, 49.0 s, 51.2 s

- Find the mean for each team.
- Which team's times are more spread out?
- What does the difference in the range of values for each team tell you about the spread?

Key ideas

- Two measures, considered here, which help to describe how data is spread are the **range** and **interquartile range**. These are called measures of spread.
- The **range** is the difference between the maximum and minimum values.
  - Range = maximum value – minimum value
- If a set of numerical data is placed in order, from smallest to largest, then:
  - the middle number of the lower half is called the **lower quartile** (Q_1)
  - the middle number of the data is called the median (Q_2)
  - the middle number of the upper half is called the **upper quartile** (Q_3)
  - the difference between the upper quartile and lower quartile is called the **interquartile range** (IQR).

$$\text{IQR} = Q_3 - Q_1$$

  - if there is an odd number of values, remove the middle value (the median) before calculating Q_1 and Q_3
- An **outlier** is a value that is not in the vicinity of the rest of the data.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 16 Finding the range and quartiles for an odd number of data values

The following data values are the results for a school Mathematics test.

67 96 62 85 73 56 79 19 76 23 68 89 81

a List the data in order, from smallest to largest.

b Find the range.

c Find:

i the median (Q_2)

ii the lower quartile (Q_1)

iii the upper quartile (Q_3)

iv the interquartile range (IQR)

SOLUTION	EXPLANATION
a 19 23 56 62 67 68 73 76 79 81 85 89 96 (Q_1 = 56 62, Q_2 = 73, Q_3 = 81 85)	Order the data.
b Range = 96 – 19 = 77	Range = maximum value – minimum value.
c i $Q_2 = 73$	The middle number is 73.
ii $Q_1 = \frac{56 + 62}{2}$ = 59	Q_1 (the middle value of the lower half) is halfway between 56 and 62. Since there is an odd number of values, exclude the number 73 before finding Q_1 and Q_3.
iii $Q_3 = \frac{81 + 85}{2}$ = 83	Q_3 (the middle value of the upper half) is halfway between 81 and 85.
iv IQR = 83 – 59 = 24	IQR = $Q_3 - Q_1$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 17 Finding quartiles for an even number of data values

Here is a set of measurements, collected by measuring the lengths, in metres, of 10 long-jump attempts.
6.7 9.2 8.3 5.1 7.9 8.4 9.0 8.2 8.8 7.1

a List the data in order, from smallest to largest.

b Find the range.

c Find:

i the median (Q_2)

ii the lower quartile (Q_1)

iii the upper quartile (Q_3)

iv the interquartile range (IQR)

d Interpret the IQR.

SOLUTION	EXPLANATION
a 5.1 6.7 7.1 7.9 8.2 8.3 8.4 8.8 9.0 9.2 Q_1 Q_2 Q_3	Order the data to locate Q_1, Q_2 and Q_3.
b Range = 9.2 – 5.1 = 4.1 m	Range = maximum value – minimum value.
c i $Q_2 = \frac{8.2 + 8.3}{2}$ = 8.25 m	Q_2 is halfway between 8.2 and 8.3.
ii Q_1 = 7.1 m	The middle value of the lower half is 7.1.
iii Q_3 = 8.8 m	The middle value of the upper half is 8.8.
iv IQR = 8.8 – 7.1 = 1.7 m	IQR is the difference between Q_1 and Q_3.
d The middle 50% of jumps differed by less than 1.7 m.	The IQR is the range of the middle 50% of the data.

Exercise 9J

1, 2 | 2 | —

UNDERSTANDING

1 This ordered data set shows the number of hours of sleep 11 people had the night before.
3 5 5 6 7 7 7 8 8 8 9

a Find the range (the difference between the maximum and minimum values).

b Find the median (Q_2, the middle number).

c Remove the middle number then find:

i the lower quartile (Q_1, the middle of the lower half)

ii the upper quartile (Q_3, the middle of the upper half).

d Find the interquartile range (IQR, the difference between the upper quartile and lower quartile).

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9J

UNDERSTANDING

2 This ordered data set shows the number of fish Daniel caught in the 12 weekends that he went fishing during the year.

1 2 3 3 4 4 6 7 7 9 11 13

a Find the range (the difference between the maximum and minimum values).

b Find the median (Q_2, the middle number).

c Split the data in half then find:

- **i** the lower quartile (Q_1, the middle of the lower half)
- **ii** the upper quartile (Q_3, the middle of the upper half).

d Find the interquartile range (IQR, the difference between the upper quartile and lower quartile).

FLUENCY

3(½), 4 | 3(½), 4 | 3(½), 4

Example 16

3 For each of the following sets of data:

- **i** list the set of data in order, from smallest to largest
- **ii** find the range
- **iii** find the median (Q_2)
- **iv** find the lower quartile (Q_1)
- **v** find the upper quartile (Q_3)
- **vi** find the interquartile range (IQR).

a 5 7 3 6 2 1 9 7 11 9 0 8 5

b 38 36 21 18 27 41 29 35 37 30 30 21 26

c 180 316 197 176 346 219 183 253 228

d 256 163 28 520 854 23 367 64 43 787 12 343 76 3 28

e 1.8 1.9 1.3 1.2 2.1 1.2 0.9 1.7 0.8

f 10 35 0.1 2.3 23 12 0.02

Example 17

4 The running time, in minutes, of 16 movies at the cinema were as follows:

123 110 98 120 102 132 112 140 120 139 42 96 152 115 119 128

a Find the range.

b Find:

- **i** the median (Q_2)
- **ii** the lower quartile (Q_1)
- **iii** the upper quartile (Q_3)
- **iv** the interquartile range (IQR).

c Interpret the IQR.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 The following set of data represents the sale price, in thousands of dollars, of 14 vintage cars.

89 46 76 41 12 52 76
97 547 59 67 76 78 30

a For the 14 vintage cars, find:
- **i** the lowest price paid
- **ii** the highest price paid
- **iii** the median price
- **iv** the lower quartile of the data
- **v** the upper quartile of the data
- **vi** the IQR.

b Interpret the IQR for the price of the vintage cars.

c If the price of the most expensive vintage car increased, what effect would this have on Q_1, Q_2 and Q_3? What effect would it have on the mean price?

6 Find the interquartile range for the data in these stem-and-leaf plots.

a

Stem	Leaf
3	4 8 9
4	1 4 8 8
5	0 3 6 9
6	2 6

5 | 2 means 52

b

Stem	Leaf
17	5 8
18	0 4 6 7
19	1 1 2 9 9
20	4 4 7 8
21	2 6 8

21 | 3 means 21.3

7 Over a period of 30 days, Lara records how many fairies she sees in the garden each day. The data is organised into this frequency table.

Number of fairies each day	0	1	2	3	4	5
Frequency	7	4	8	4	6	1

a Find the median number of fairies seen in the 30 days.

b Find the interquartile range.

c If Lara changes her mind about the day she saw 5 fairies and now says that she saw 10 fairies, would this change the IQR? Explain.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

8 | 8, 9 | 9, 10

9J

REASONING

8 Two data sets have the same range. Does this mean they have the same lowest and highest values? Explain.

9 A car yard has more than 10 cars listed for sale. One expensive car is priced at $600 000 while the remaining cars are all priced near $40 000. Later the salesperson realises that there was an error in the price for the expensive car – there was one too many zeros printed onto the price.

- **a** Does the change in price for the expensive car change the value of the range? Give reasons.
- **b** Does the change in price for the expensive car change the value of the median? Give reasons.
- **c** Does the change in price for the expensive car change the value of the IQR? Give reasons.

10
- **a** Is it possible for the range to equal the IQR? If so, give an example.
- **b** Is it possible for the IQR to equal zero? If so, give an example.

How many lollies in the jar?

— | — | 11

ENRICHMENT

11 The following two sets of data represent the number of jelly beans found in 10 jars purchased from two different confectionery stores, A and B.

Shop A: 25 26 24 24 28 26 27 25 26 28
Shop B: 22 26 21 24 29 19 25 27 31 22

- **a** Find Q_1, Q_2 and Q_3 for:
  - **i** shop A
  - **ii** shop B.
- **b** The top 25% of the data is above which value for shop A?
- **c** The lowest 25% of the data is below which value for shop B?
- **d** Find the interquartile range (IQR) for the number of jelly beans in 10 jars from:
  - **i** shop A
  - **ii** shop B.
- **e** By looking at the given sets of data, why should you expect there to be a significant difference between the IQR of shop A and the IQR of shop B?
- **f** Which shop offers greater consistency in the number of jelly beans in each jar it sells?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9K Box plots EXTENDING

A box plot is a commonly used graph for a data set showing the maximum and minimum values, the median and the upper and lower quartiles. Box plots are often used to show how a data set is distributed and how two sets compare. Box plots are used, for example, to compare a school's examination performance against the performance of all schools in a state.

Let's start: School performance

These two box plots show the performance of two schools on their English exams.

Box High School



Plot Secondary College



- Which school produced the highest mark?
- Which school produced the highest median (Q_2)?
- Which school produced the highest IQR?
- Which school produced the highest range?
- Describe the performance of Box High School against Plot Secondary College. Which school has better overall results and why?

Key ideas

- A **box plot** (also called a box-and-whisker plot) is a graph which shows:
  - maximum and minimum values
  - median (Q_2)
  - lower and upper quartiles (Q_1 and Q_3).
- A quarter (25%) of the data is spread across each of the four sections of the graph



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 18 Interpreting a box plot

This box plot summarises the price of all the books in a book shop.



a State the minimum and maximum book prices.
b Find the range of the book prices.
c State the median book price.
d Find the interquartile range.
e Fifty per cent of the books are priced below what amount?
f Twenty-five per cent of the books are priced above what amount?
g If there were 1000 books in the store, how many would be priced below $15?

SOLUTION	EXPLANATION
a Minimum book price = $5 Maximum book price = $50	
b Range = $50 – $5 = $45	Range = maximum price – minimum price
c Median book price = $20	The median is Q_2.
d Interquartile range = $35 – $15 = $20	Interquartile range = $Q_3 - Q_1$
e $20	50% of books are below Q_2.
f $35	The top 25% of books are above Q_3.
g $0.25 \times 1000 = 250$ 250 books would be below $15	25% of books are priced below $15.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 19 Constructing a box plot

Consider the following set of data representing 11 scores resulting from throwing two dice and adding their scores.

7 10 7 12 8 9 6 6 5 4 8

a Find:

i the minimum value **ii** the maximum value **iii** the median

iv the lower quartile **v** the upper quartile.

b Draw a box plot to represent the data.

SOLUTION

a

Q_1 Q_2 Q_3

4 5 6 6 7 7 8 8 9 10 12

i Min. value = 4 **ii** Max. value = 12

iii $Q_2 = 7$ **iv** $Q_1 = 6$

v $Q_3 = 9$

b Box plot: Throwing two dice



EXPLANATION

Order the data.
Determine the minimum and maximum value.
The median is the middle value.
Remove the middle value then locate the lower quartile and upper quartile.

Draw a scaled horizontal axis.

Place the box plot above the axis marking in the five key statistics from part **a**.

Exercise 9K

1–3 | 1, 3 | —

UNDERSTANDING

1 Write down the names of all the features labelled *a* to *h* on this box plot.



2 Write the missing words.

a To find the range, you subtract the _____ from the _____.

b To find the interquartile range, you subtract the _____ from the _____.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9K

UNDERSTANDING

3 Choose the correct box plot for a data set which has all these measures:

- minimum = 3
- maximum = 12
- median = 9
- lower quartile = 5
- upper quartile = 11

A



B



C



D



4, 5, 6(½) 4, 5, 6(½) 4, 5, 6(½)

FLUENCY

Example 18

4 This box plot summarises the length of babies born in a particular week in a hospital.



a State the minimum and maximum baby lengths.
b Find the range of the length of the babies.
c State the median baby length.
d Find the interquartile range.
e Fifty per cent of the baby lengths are below what amount?
f Twenty-five per cent of the babies are born longer than what amount?
g If there were 80 babies born in the week, how many would be expected to be less than 45 cm in length?



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

9K

FLUENCY

5 This box plot summarises the number of rabbits spotted per day in a paddock over a 100-day period.



a State the minimum and maximum number of rabbits spotted.
b Find the range of the number of rabbits spotted.
c State the median number of rabbits spotted.
d Find the interquartile range.
e Seventy-five per cent of the days the number of rabbits spotted is below what amount?
f Fifty per cent of the days the number of rabbits spotted is more than what amount?
g How many days was the number of spotted rabbits less than 10?

Example 19

6 For each of the sets of data below:
i state the minimum value
ii state the maximum value
iii find the median (Q_2)
iv find the lower quartile (Q_1)
v find the upper quartile (Q_3)
vi draw a box plot to represent the data.

a 2 2 3 3 4 6 7 7 7 8 8 8 8 9 11 11 13 13 13
b 43 21 65 45 34 42 40 28 56 50 10 43 70 37 61 54 88 19
c 435 353 643 244 674 364 249 933 523 255 734
d 0.5 0.7 0.1 0.2 0.9 0.5 1.0 0.6 0.3 0.4 0.8 1.1 1.2 0.8 1.3 0.4 0.5

7, 8 | 7, 8 | 8, 9

PROBLEM-SOLVING

7 The following set of data describes the number of cars parked in a street on 18 given days.
14 26 39 46 13 30 5 46 37 26 39 8 8 9 17 48 29 27

a Represent the data as a box plot.
b On what percentage of days were the number of cars parked on the street between:
i 5 and 48?
ii 13 and 39?
iii 5 and 39?
iv 39 and 48?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 The weight of a sample of adult leopards from Africa and Asia are summarised in these box plots.



a Which leopard population sample has the highest minimum weight?

b What is the difference between the ranges for both population samples?

c Is the IQR the same for both leopard samples? If so, what is it?

d What percentage of leopards have a weight less than 80 kg for:

i African leopards?

ii Asian leopards?

e A leopard has a weight of 90 kg. Is it likely to be an Asian or African leopard?

9 The time that it takes for a sample of computers to start up is summarised in these box plots.



a What type of computer has the lowest median?

b What percentage of Mac computers loaded in less than 1 minute?

c What percentage of PC computers took longer than 55 seconds to load?

d What do you notice about the range for Mac computers and the IQR for PC computers? What does this mean?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9K

10 | 10–12 | 11–13

REASONING

10 The number of points per game for two basketball players over a season is summarised in these box plots.



Box plots can be used to compare the performance of each basketballer.

a Which player has the highest maximum?
b Which player has the highest median?
c Which player has the smallest IQR?
d Which player is a more consistent basketball scorer? Give reasons.
e Which player most likely scored the greatest number of points? Give reasons.

11 Give an example of a small data set which has the following.
a maximum = upper quartile
b median = lower quartile

12 Does the median always sit exactly in the middle of a box on a box plot? Explain.

13 Could the mean of a data set be greater than Q_3? Explain.

Outliers and battery life

— | — | 14

ENRICHMENT

14 Outliers on box plots are shown as a separate point.



The life in months of a particular kind of battery used in a special type of high-powered calculator is shown in this data set.

3 3 3 4 4 5 6 6 6 7 8 8 9 17

a Use all the values to calculate Q_1, Q_2 and Q_3 for the data set.
b Do any of the values appear to be outliers?
c Not including the outlier, what is the next highest value?
d Draw a box plot for the data using a cross (×) to show the outlier.
e Can you give a logical reason for the outlier?

Using a CAS calculator 9K: Finding measures of spread and drawing box plots

The activity is in the interactive textbook in the form of a printable PDF.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

How many in the bag?

For this activity you will need:

- a bag or large pocket
- different-coloured counters
- paper and pen.

Five counters

a Form pairs then without watching, have a third person (e.g. a teacher) place five counters of two different colours into the bag or pocket. An example of five counters could be two red, three blue but at this point in the activity you will not know this.

b Without looking, one person selects a counter from the bag while the other person records its colour. Replace the counter in the bag.

c Repeat part **b** for a total of 100 trials. Record the results in a table similar to this one.

Colour	Tally	Frequency
Red	𝍸 III...	...
Blue	𝍸 𝍸 II ...	...
Total	100	100

d Find the experimental probability for each colour, for example if 42 red counters were recorded then the experimental probability $= \frac{42}{100} = 0.42$.

e Use these experimental probabilities to help estimate how many of each colour of counter are in the bag. For example: 0.42 is close to $0.4 = \frac{2}{5}$, therefore guess two red and three blue. Use this table to help.

Colour	Frequency	Experimental probability	Closest multiple of 0.2, e.g. 0.2, 0.4, ...	Guess of how many counters of this colour
Total	**100**	**1**	**1**	**5**

f Now take the counters out of the bag to see if your estimate is correct.

More colours and counters

a Repeat the steps above but this time use three colours and 8 counters.

b Repeat the steps above but this time use four colours and 12 counters.

How do Australians get to work?

The collection of data is an important part of statistics. There are a number of ways that data may be collected. Some methods are: a **census** which includes the whole population, a **survey** which includes only a sample of the population, a **controlled experiment** where cause and effect is recorded, and an **observational study** where data is recorded without a controlled experiment.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

If a survey is to be used as the method of data collection, it is important that it is well designed. If the data is to be representative of the *population*, the selection of the *sample* that is surveyed must be thought through carefully.

Sampling

Different methods are used to generate a random sample (a subset of the population) to survey.

Write down some of the problems with the following selection processes for selecting a sample from a population for the given topic.

a A morning survey of the people on a train about their current employment.

b A survey of the people on the electoral roll about their favourite music.

c A phone poll of every 10th person in the phone book about their mobile phone plan.

d A survey of people in a shopping centre on their yearly income.

e A survey of the people in your year level on Australia's most popular television shows.

f A call for volunteers in a newspaper advertisement for a medical trial.

g A phone poll on a television news program about capital punishment.

Census data

The major collection of data about the population of Australia occurs in the national census. In the census, a person in each household completes a range of questions about the people staying in their house that night. Census data can be accessed via the Australian Bureau of Statistics (ABS) website.

a Access the census data and list four topics of interest that contain data on the site.

b Find the data on 'Method of Travel to Work' for 2011 (the last census before 2016).

c Use the data to calculate the proportion of people in each category. Show your results using a table and a graph.

d Design a survey to collect the same information as that recorded in the census information in part **b**. Include at least three questions. Use this to survey a class on their parents' method of travel to work.

e Work out the proportion of people in each category for your data in part **d**. Show your results using a table and a graph.

f Compare your answers in parts **c** and **e** for each category. Comment on any similarities or differences. What can you say about the quality of your sample based on these results? Discuss some of the limitations of your sample and how it could be improved.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 A fair coin is tossed 5 times.

- **a** How many outcomes are there?
- **b** Find the probability of obtaining at least 4 tails.
- **c** Find the probability of obtaining at least 1 tail.

2 Three cards, A, B and C, are randomly arranged in a row.

- **a** Find the probability that the cards will be arranged in the order A B C from left to right.
- **b** Find the probability that the B card will take the right-hand position.

3 Four students, Rick, Belinda, Katie and Chris are the final candidates for the selection of school captain and vice-captain. Two of the four students will be chosen at random to fill the positions.

- **a** Find the probability that Rick will be chosen for:
  - **i** captain
  - **ii** captain or vice-captain.
- **b** Find the probability that Rick and Belinda will be chosen for the two positions.
- **c** Find the probability that Rick will be chosen for captain and Belinda will be chosen for vice-captain.
- **d** Find the probability that the two positions will be filled by two boys or two girls.

4 State what would happen to the mean, median and range of a data set in these situations.

- **a** Five is added to each value in the data set.
- **b** Each value in the data set is doubled.
- **c** Each value in the data set is doubled and then decreased by 1.

5 Three pieces of fruit have an average weight of m grams. After another piece of fruit is added, the average weight doubles. Find the weight of the extra piece of fruit in terms of m.

6
- **a** Five different data values have a range and median equal to 7. If two of the values are 3 and 5, what are the possible combinations of values?
- **b** Four data values have a range of 10, a mode of 2 and a median of 5. What are the four values?

7 Five integer scores out of 10 are all greater than 0. If the median is x and the mode is one more than the median and the mean is one less than the median, find all the possible sets of values if $x < 7$.

8 Thomas works in the school office for work experience, he is given four letters and four addressed envelopes. What is the probability that Thomas, who is not very good at his job, places none of the four letters into their correct envelope?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Probability and statistics

Two-step experiments

These can be represented by tables or tree diagrams. They involve more than one component and can occur with or without replacement .

e.g. a bag contains 2 blue counters and 1 green, 2 are selected at random.

(I) Table with replacement.

		pick 1		
		b	b	g
pick 2	b	(b, b)	(b, b)	(g, b)
	b	(b, b)	(b, b)	(g, b)
	g	(b, g)	(b, g)	(g, g)

Sample space of 9 outcomes

$\Pr(2 \text{ of same colour}) = \frac{5}{9}$

(II) Tree without replacement

Pick 1 Pick 2

b → b bb; g bg

b → b bb; g bg

g → b gb; b gb

6 outcomes

$\Pr(2 \text{ of same colour}) = \frac{2}{6} = \frac{1}{3}$

Set notation

Within a sample space are a number of subsets.

A' = not A

$A \cup B$ means A or B; the union of A and B

$A \cap B$ means A and B; the intersection of A and B

A only is the elements in A but not in B

$n(A)$ is the number of elements in A

$\emptyset$ is the empty or null set

e.g. $A = \{1, 2, 3, 4, 5\}$ $B = \{2, 4, 6, 8\}$

$A \cup B = \{1, 2, 3, 4, 5, 6, 8\}$

$A \cap B = \{2, 4\}$ $n(B) = 4$

B only $= \{6, 8\}$

$3 \in A$ means 3 is an element of A

Venn diagrams and two-way tables

These organise data from two or more categories



Venn diagram

	A	A'	
B	7	3	10
B'	5	6	11
	12	9	21

i.e. 6 in neither category, 7 in both categories

$\Pr(A) = \frac{12}{21} = \frac{4}{7}$

$\Pr(B \text{ only}) = \frac{3}{21} = \frac{1}{7}$

Probability review

The sample space is the list of all possible outcomes of an experiment.

For all possible outcomes:

$\Pr(\text{event}) = \frac{\text{number of favourable outcomes}}{\text{total number of outcomes}}$

e.g. roll a normal six-sided die

$\Pr(>4) = \frac{2}{6} = \frac{1}{3}$

$0 \le \Pr(\text{event}) \le 1$

$\Pr(\text{not A}) = 1 - \Pr(A)$

Experimental probability

This is calculated from results of experiment or survey.

$\text{Experimental probability} = \frac{\text{number of times event occurs}}{\text{total number of trials}}$

$\text{Expected number of occurrences} = \text{probability} \times \text{number of trials}$

Stem-and-leaf plots

These display all the data values using a stem and a leaf.

An ordered back-to-back stem-and-leaf plot.

Leaf	Stem	Leaf	
9 8 7 2	1	0 3	symmetrical
7 4 3 3	2	2 2 4	
5 2 1	3	3 6 7 8	
7	4	4 5 9	
0	5	0	

skewed

3 | 5 means 35

key

Grouped data

Data values can be grouped into class intervals, e.g. 0–4, 5–9, etc. and recorded in a frequency table.

The frequency or percentage frequency of each interval can be recorded in a histogram.

e.g.



Summarising data: Measures of centre

Mode is the most common value (there can be more than one). Two modes means data is bimodal.

Mean = average

$= \frac{\text{sum of all values}}{\text{number of values}}$

Median is the middle value of data that is ordered.

odd data set: 2 4 (7) 10 12 — median

even data set: 2 4 6 10 15 18 — median $= \frac{6+10}{2} = 8$

An outlier is a value that is not in the vicinity of the rest of the data.

Measures of spread

Range = maximum value – minimum value

Interquartile range (IQR) = upper quartile (Q_3) – lower quartile (Q_1)

IQR is the range of the middle 50% of data.

e.g. Finding Q_1 and Q_3. First, locate median (Q_2) then find middle values of upper and lower half.

e.g. 1 2 (5) 6 7 | 9 10 (12) 12 15

Q_1 $Q_2 = 8$ Q_3

For odd number of values exclude median from each half.

Box plots (Ext)



25% of data is in each of the four sections.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

9A **1** A letter is randomly chosen from the word XYLOPHONE. The probability that it is an O is:

A $\frac{1}{8}$ **B** $\frac{2}{9}$ **C** $\frac{1}{4}$ **D** $\frac{1}{9}$ **E** $\frac{1}{3}$

9B **2** The values of x and y in the two-way table are:

	A	not A	Total
B		5	9
not B	8	y	
Total	x		25

A $x = 12, y = 8$
B $x = 12, y = 11$
C $x = 16, y = 4$
D $x = 10, y = 1$
E $x = 14, y = 6$

9C **3** Which shaded region represents A ∪ B?

A


B


C


D


E


9D/E **4** A bag contains 2 green balls and 1 red ball. Two balls are randomly selected *without replacement*. The probability of selecting one of each colour is:

A $\frac{1}{2}$ **B** $\frac{2}{3}$ **C** $\frac{5}{6}$ **D** $\frac{1}{3}$ **E** $\frac{3}{4}$

9F **5** From rolling a biased die, a class finds an experimental probability of 0.3 of rolling a 5. From 500 rolls of the die, the expected number of 5s would be:

A 300 **B** 167 **C** 180 **D** 150 **E** 210

9H **6** The median of the data in this stem-and-leaf plot is:

Stem	Leaf
5	3 5 8
6	1 4 7
7	0 2 4 7 9
8	2 6 6

7 | 4 means 74

A 74 **B** 71 **C** 86 **D** 65 **E** 70

9G **7** If Jacob achieved scores of 12, 9, 7 and 12 on his last four language vocabulary tests, what score must he get on the fifth test to have a mean of 11?

A 16 **B** 14 **C** 11 **D** 13 **E** 15

9I **8** This frequency histogram shows the times of finishers in a fun run. The percentage of competitors that finished in better than 40 minutes was:



A 55% **B** 85% **C** 50% **D** 62.5% **E** 60%

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

9J **9** The interquartile range of the set of ordered data below is as follows.

1.1 2.3 2.4 2.8 3.1 3.4 3.6 3.8 3.8 4.1 4.5 4.7 4.9

A 2–5 **B** 1.7 **C** 3.8 **D** 1.3 **E** 2.1

9K Ext **10** Choose the incorrect statement about the box plot below.



A The range is 36.
B Fifty per cent of values are between 36 and 51.
C The median is 42.
D Twenty-five per cent of values are below 36.
E The interquartile range is 20.

Short-answer questions

9A **1** Determine the probability of each of the following.

a Rolling more than 2 on a normal six-sided die
b Selecting a vowel from the word EDUCATION
c Selecting a pink or white jelly bean from a packet containing 4 pink, 2 white and 4 black jelly beans.

9B **2** From a survey of 50 people, 30 have the newspaper delivered, 25 read it online, 10 do both and 5 do neither.

a Construct a Venn diagram for the survey results.
b How many people only read the newspaper online?
c If one of the 50 people was randomly selected, find:
i Pr(have paper delivered and read it online)
ii Pr(don't have it delivered)
iii Pr(only read it online).

9B/C **3** **a** Copy and complete this two-way table.

	A	A′	Total
B		16	
B′	8		20
Total	17		

b Convert the information into a Venn diagram as shown.



c Find the following probabilities.
i Pr(B′) **ii** Pr(A ∩ B)
iii n(A only) **iv** n(A ∪ B)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9D **4** A spinner with equal areas of red, green and blue is spun and a four-sided die numbered 1 to 4 is rolled.

		Die			
		1	2	3	4
Spinner	red	(red, 1)	(red, 2)		
	green				
	blue				

a Complete a table like the one shown and state the number of outcomes in the sample space.

b Find the probability that:

i the outcome is red and an even number

ii the outcome is blue or green and a 4

iii the outcome does not involve blue.

9E **5** Libby randomly selects two coins from her pocket *without replacement*. Her pocket contains a $1 coin, and two 10-cent coins.

a List all the possible combinations using a tree diagram.

b If a chocolate bar costs $1.10, find the probability that she can hand over the two coins to pay for it.

9F **6** A quality controller records the frequency of the types of chocolates from a sample of 120 off its production line.

Centre	Soft	Hard	Nut
Frequency	50	22	48

a What is the experimental probability of randomly selecting a nut centre?

b In a box of 24 chocolates, how many would be expected to have a non-soft centre?

9G **7** Claudia records the number of emails she receives each weekday for two weeks as follows.

30 31 33 23 29 31 21 15 24 23

Find:

a the mean **b** the median **c** the mode.

9H **8** Two mobile phone salespeople are both aiming for a promotion to be the new assistant store manager. The best salesperson over a 15-week period will achieve the promotion. The number of mobile phones they sold each week is recorded below.

Employee 1 : 21 34 40 38 46 36 23 51 35 25 39 19 35 53 45

Employee 2 : 37 32 29 41 24 17 28 20 37 48 42 38 17 40 45

a Draw an ordered back-to-back stem-and-leaf plot for the data.

b For each employee, find:

i the median number of sales

ii the mean number of sales.

c By comparing the two sets of data, state, with reasons who you think should get the promotion.

d Describe each employee's data as approximately symmetrical or skewed.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

9I

9 The data below represents the finish times, in minutes, of 25 competitors in a local car rally race.

134 147 162 164 145 159 151 143 136 155 163 157 168
128 144 161 158 136 178 152 167 154 161 152 171

a Record the above data in a frequency table in class intervals of 10 minutes. Include a percentage frequency column.

b Construct a frequency histogram.

c Determine:

i the number of competitors that finished in less than 140 minutes

ii the percentage of competitors that finished between 130 and 160 minutes.

9J/K

Ext

10 Scott scores the following runs in each of his innings across the course of a cricket season:

20 5 34 42 10 3 29 55 25 37 51 12 34 22

a Find the range.

b Construct a box plot to represent the data by first finding the quartiles.

c From the box plot, 25% of his innings were above what number of runs?

Extended-response questions

1 The local Sunday market has a number of fundraising activities.

a For $1 you can spin a spinner numbered 1–5 twice. If you spin two even numbers you receive $2 (your dollar back plus an extra dollar), if you spin two odd numbers you get your dollar back and otherwise you lose your dollar.

		First spin				
		1	2	3	4	5
Second spin	1	(1, 1)	(2, 1)			
	2					
	3					
	4					
	5					

i Complete the table shown to list the sample space.

ii What is the probability of losing your dollar?

iii What is the probability of making a dollar profit?

iv In 50 attempts, how many times would you expect to lose your dollar?

v If you start with $100 and have 100 attempts, how much money would you expect to end up with?

b Forty-five people were surveyed as they walked through the market as to whether they bought a sausage and/or a drink from the sausage sizzle. Twenty-five people bought a sausage, 30 people bought a drink, with 15 buying both. Let S be the set of people who bought a sausage and D the set of people who bought a drink.

i Construct a Venn diagram to represent this information.

ii How many people bought neither a drink nor a sausage?

iii How many people bought a sausage only?

iv If a person was randomly selected from the 45, what is the probability they bought a drink but not a sausage?

v Find $\Pr(S')$.

vi Find $\Pr(S' \cup D)$ and state what this probability represents.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 The data below represents the data collected over a month of 30 consecutive days of the delay time (in minutes) of the flight departure of the same evening flight of two rival airlines.

Airline A

2	11	6	14	18	1	7	4	12	14	9	2	13	4	19
13	17	3	52	24	19	12	14	0	7	13	18	1	23	8

Airline B

6	12	9	22	2	15	10	5	10	19	5	12	7	11	18
21	15	10	4	10	7	18	1	18	8	25	4	22	19	26

a Does the data for airline A appear to have an-outliers (numbers not near the majority of data elements)?

b By removing any outliers listed in part **a**, find the following for airline A:

- **i** median (Q_2)
- **ii** lower quartile (Q_1)
- **iii** upper quartile (Q_3).

Ext **c** Hence, complete a box plot of the delay times for airline A.

d Airline A reports that half its flights for that month had a delay time of less than 10 minutes. Is this claim correct? Explain.

Ext **e** On the same axis as in part **c**, construct a box plot for airline B's delay times.

f By finding the range and interquartile range of the two airlines' data, comment on the spread of the delay times for each company.

g Use the previous question parts to explain which airline you would choose based on their delay times and why.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 10

Introduction to quadratic equations and graphs

What you will learn

- 10A Quadratic equations (Extending)
- 10B Solving $ax^2 + bx = 0$ and $x^2 = d$ (Extending)
- 10C Solving $x^2 + bx + c = 0$ (Extending)
- 10D Applications of quadratic equations (Extending)
- 10E The parabola
- 10F Sketching $y = ax^2$ with dilations and reflections
- 10G Sketching $y = x^2$ with translations
- 10H Sketching parabolas using intercept form (Extending)

Australian curriculum

NUMBER AND ALGEBRA

Linear and non-linear relationships

Sketch simple non-linear relations with and without the use of digital technologies AC

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

CSIRO Parkes Observatory

The CSIRO Parkes Observatory in New South Wales is home to the Parkes Radio Telescope, which is famous for providing the first pictures to the world of the Apollo 11 moonwalk in 1969. The telescope's gigantic dish has a diameter of 64 metres and receives radio and microwave signals from outer space.

The shape of the dish is parabolic, meaning that its curvature can be described by a quadratic equation. The parabolic shape guarantees that all the radio and microwave signals bounce off the dish surface and are reflected to the receiver, which sits at a special point (called the focus) above the dish.

The Parkes Radio Telescope is still in use today as part of the Australia Telescope National Facility.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10A Quadratic equations EXTENDING

Quadratic equations are commonplace in theoretical and practical applications of mathematics. They are used to solve problems in geometry and measurement as well as in number theory and physics. The path that a projectile takes while flying through the air, for example, can be analysed using quadratic equations.

The trajectory of this arrow can be modelled using quadratic equations.

A quadratic equation can be written in the form $ax^2 + bx + c = 0$ where a, b and c are constants and $a \neq 0$. Examples include $x^2 - 2x + 1 = 0$, $5x^2 - 3 = 0$ and $-0.2x^2 + 4x = 0$. Unlike a linear equation which has a single solution, quadratic equations can have zero, one or two solutions. For example: $x = 2$ and $x = -1$ are solutions to the quadratic equation $x^2 - x - 2 = 0$ since $2^2 - 2 - 2 = 0$ and $(-1)^2 - (-1) - 2 = 0$. One method for finding the solutions to quadratic equations involves the use of the Null Factor Law where each factor of a factorised quadratic expression is equated to zero.

Let's start: Exploring the Null Factor Law

$x = 1$ is not a solution to the quadratic equation $x^2 - x - 12 = 0$ since $1^2 - 1 - 12 \neq 0$.

- Use trial and error to find at least one of the two numbers which are solutions to $x^2 - x - 12 = 0$.
- Rewrite the equation in factorised form.

  $x^2 - x - 12 = 0$ becomes ( )( ) = 0
- Now repeat the first task above to find solutions to the equation using the factorised form.
- Was the factorised form easier to work with? Discuss.

Key ideas

- A **quadratic equation** can be written in the form $ax^2 + bx + c = 0$
  - This is called **standard form**.
  - a, b and c are constants and $a \neq 0$.
- The **Null Factor Law** states that if the product of two numbers is zero then either or both of the two numbers is zero.
  - If $a \times b = 0$ then $a = 0$ or $b = 0$.
  - If $(x + 1)(x - 3) = 0$ then $x + 1 = 0$ (so $x = -1$) or $x - 3 = 0$ (so $x = 3$).
  - $x + 1$ and $x - 3$ are the linear factors of $(x + 1)(x - 3)$ (which equals $x^2 - 2x - 3$).

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Writing in standard form

Write these quadratic equations in standard form.

a $x^2 = 2x + 7$

b $2(x^2 - 3x) = 5$

c $2x - 7 = -3x^2$

SOLUTION	EXPLANATION
a $x^2 = 2x + 7$ $x^2 - 2x - 7 = 0$	We require the form $ax^2 + bx + c = 0$. Subtract $2x$ and 7 from both sides to move all terms to the left-hand side.
b $2(x^2 - 3x) = 5$ $2x^2 - 6x = 5$ $2x^2 - 6x - 5 = 0$	First expand brackets then subtract 5 from both sides.
c $2x - 7 = -3x^2$ $3x^2 + 2x - 7 = 0$	Add $3x^2$ to both sides.

Example 2 Testing for a solution

Substitute the given x value into the equation and say whether or not it is a solution.

a $x^2 + x - 6 = 0 \quad (x = 2)$ **b** $2x^2 + 5x - 3 = 0 \quad (x = -4)$

SOLUTION	EXPLANATION
a $x^2 + x - 6 = 2^2 + 2 - 6$ $= 6 - 6$ $= 0$ $\therefore x = 2$ is a solution	Substitute $x = 2$ into the equation to see if the left-hand side equals zero. $x = 2$ satisfies the equation so $x = 2$ is a solution.
b $2x^2 + 5x - 3 = 2(-4)^2 + 5(-4) - 3$ $= 2 \times 16 + (-20) - 3$ $= 32 - 20 - 3$ $= 9$ $\therefore x = -4$ is not a solution	Substitute $x = -4$. Recall that $(-4)^2 = 16$ and $5 \times (-4) = -20$. The equation is not satisfied so $x = -4$ is not a solution.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Using the Null Factor Law

Use the Null Factor Law to solve these equations.

a $x(x+2)=0$ **b** $(x-1)(x+5)=0$ **c** $(2x-1)(5x+3)=0$

SOLUTION	EXPLANATION
a $x(x+2)=0$ $x=0$ or $x+2=0$ $x=0$ or $x=-2$	The factors are x and $(x+2)$. Solve each linear factor equal to zero. Check each solution by substituting into the orginal equation.
b $(x-1)(x+5)=0$ $x-1=0$ or $x+5=0$ $x=1$ or $x=-5$	Solve each factor $(x-1)$ and $(x+5)$ equal to zero. Check your solutions using substitution.
c $(2x-1)(5x+3)=0$ $2x-1=0$ or $5x+3=0$ $2x=1$ or $5x=-3$ $x=\frac{1}{2}$ or $x=-\frac{3}{5}$	The two factors are $(2x-1)$ and $(5x+3)$. Each one results in a two-step linear equation. Check your solutions using substitution.

Exercise 10A

1–4(½) | 2(½), 4(½) | —

UNDERSTANDING

1 Evaluate these quadratic expressions by substituting the x value given in the brackets.

a x^2+3 $(x=3)$ **b** x^2-5 $(x=1)$ **c** x^2+x $(x=2)$
d x^2+2x $(x=-1)$ **e** x^2-x $(x=-4)$ **f** $2x^2-x+1$ $(x=-1)$
g $3x^2-x+2$ $(x=5)$ **h** $5x^2+2x-3$ $(x=-1)$ **i** $-2x^2+2x-3$ $(x=4)$

2 Decide if the following equations are quadratics.

a $x+1=0$ **b** $1-2x=0$ **c** $x^2+3x+1=0$
d $5x^2-x+2=0$ **e** $x^2-1=0$ **f** $x^3+x^2-2=0$
g $x^5+1-x=0$ **h** $x^2=x+2$ **i** $x+2=4x^2$

3 Solve these linear equations.

a $x-1=0$ **b** $x+3=0$ **c** $x+11=0$
d $2x+4=0$ **e** $3x-9=0$ **f** $5x+30=0$

4 Copy and complete the following working which uses the Null Factor Law.

a $x(x-5)=0$
$x=0$ or _____ $=0$
$x=0$ or $x=$ ____

b $(2x+1)(x-3)=0$
_____ $=0$ or $x-3=0$
$2x=$ ____ or $x=$ ____
$x=$ ____ or $x=3$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10A

5–6(½), 7, 9–10(½) | 5–6(½), 8, 9–10(½) | 5–6(½), 8, 9–10(½)

FLUENCY

Example 1

5 Write these quadratic equations in standard form ($ax^2 + bx + c = 0$).

a $x^2 + 2x = 5$ **b** $x^2 - 5x = -2$ **c** $x^2 = 4x - 1$

d $x^2 = 7x + 2$ **e** $2(x^2 + x) + 1 = 0$ **f** $3(x^2 - x) = -4$

g $4 = -3x^2$ **h** $3x = x^2 - 1$ **i** $5x = 2(-x^2 + 5)$

Example 2

6 Substitute the given x value into the quadratic equation and say whether or not it is a solution.

a $x^2 - 1 = 0 \ (x = 1)$ **b** $x^2 - 25 = 0 \ (x = 5)$ **c** $x^2 - 4 = 0 \ (x = 1)$

d $2x^2 + 1 = 0 \ (x = 0)$ **e** $x^2 - 9 = 0 \ (x = -3)$ **f** $x^2 + 2x + 1 = 0 \ (x = -1)$

g $x^2 - x - 12 = 0 \ (x = 5)$ **h** $2x^2 - x + 3 = 0 \ (x = -1)$ **i** $5 - 2x + x^2 = 0 \ (x = -2)$

7 Substitute $x = -2$ and $x = 5$ into the equation $x^2 - 3x - 10 = 0$. What do you notice?

8 Substitute $x = -3$ and $x = 4$ into the equation $x^2 - x - 12 = 0$. What do you notice?

Example 3a

Example 3b

9 Use the Null Factor Law to solve these equations.

a $x(x + 1) = 0$ **b** $x(x + 5) = 0$ **c** $x(x - 2) = 0$

d $x(x - 7) = 0$ **e** $(x + 1)(x - 3) = 0$ **f** $(x - 4)(x + 2) = 0$

g $(x + 7)(x - 3) = 0$ **h** $\left(x + \frac{1}{2}\right)\left(x - \frac{1}{2}\right) = 0$ **i** $2x(x + 5) = 0$

j $5x\left(x - \frac{2}{3}\right) = 0$ **k** $\frac{x}{3}\left(x + \frac{2}{3}\right) = 0$ **l** $\frac{2x}{5}(x + 2) = 0$

Example 3c

10 Use the Null Factor Law to solve these equations.

a $(2x - 1)(x + 2) = 0$ **b** $(x + 2)(3x - 1) = 0$ **c** $(5x + 2)(x + 4) = 0$

d $(x - 1)(3x - 1) = 0$ **e** $(x + 5)(7x + 2) = 0$ **f** $(3x - 2)(5x + 1) = 0$

g $(11x - 7)(2x - 13) = 0$ **h** $(4x + 9)(2x - 7) = 0$ **i** $(3x - 4)(7x + 1) = 0$

11 | 11, 12(½) | 12–13(½)

PROBLEM-SOLVING

11 Find the numbers which satisfy the given condition.

a The product of x and a number 3 more than x is zero.

b The product of x and a number 7 less than x is zero.

c The product of a number 1 less than x and a number 4 more than x is zero.

d The product of a number 1 less than twice x and 6 more than x is zero.

e The product of a number 3 more than twice x and 1 less than twice x is zero.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10A

PROBLEM-SOLVING

12 Write these equations as quadratics in standard form. Remove any brackets and fractions.

a $5x^2 + x = x^2 - 1$

b $2x = 3x^2 - x$

c $3(x^2 - 1) = 1 + x$

d $2(1 - 3x^2) = x(1 - x)$

e $\frac{x}{2} = x^2 - \frac{3}{2}$

f $\frac{4x}{3} - x^2 = 2(1 - x)$

g $\frac{5}{x} + 1 = x$

h $\frac{3}{x} + \frac{5}{2} = 2x$

13 These quadratic equations have two integer solutions between –5 and 5. Use trial and error to find them.

a $x^2 - x - 2 = 0$

b $x^2 - 4x + 3 = 0$

c $x^2 - 4x = 0$

d $x^2 + 3x = 0$

e $x^2 + 3x - 4 = 0$

f $x^2 - 16 = 0$

14 | 14, 15 | 15, 16

REASONING

14 Consider the quadratic equation $(x + 2)^2 = 0$.

a Write the equation in the form (_____)(_____) = 0.

b Use the Null Factor Law to find the solutions to the equation. What do you notice?

c Now solve these quadratic equations.

i $(x + 3)^2 = 0$

ii $(x - 5)^2 = 0$

iii $(2x - 1)^2 = 0$

iv $(5x - 7)^2 = 0$

15 Consider the equation $3(x - 1)(x + 2) = 0$.

a First divide both sides of the equation by 3. Write down the new equation.

b Solve the equation using the Null Factor Law.

c Compare the given original equation with the equation found in part **a**. Explain why the solutions are the same.

d Solve these equations.

i $7(x + 2)(x - 3) = 0$

ii $11x(x + 2) = 0$

iii $\frac{(x + 1)(x - 3)}{4} = 0$

16 Consider the equation $(x - 3)^2 + 1 = 0$.

a Substitute these x values to decide if they are solutions to the equation.

i $x = 3$

ii $x = 4$

iii $x = 0$

iv $x = -2$

b Do you think the equation will have a solution? Explain why.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

ENRICHMENT

17 Polynomials are sums of integer powers of x. They are given names according to the highest power of x in the polynomial expression.

Example	Polynomial Name
2	Constant
$2x + 1$	Linear
$x^2 - 2x + 5$	Quadratic
$x^3 - x^2 + 6x - 1$	Cubic
$7x^4 + x^3 + 2x^2 - x + 4$	Quartic
$4x^5 - x + 1$	Quintic

Name these polynomial equations.

a $3x - 1 = 0$ **b** $x^2 + 2 = 0$ **c** $x^5 - x^4 + 3 = 0$

d $5 - 2x + x^3 = 0$ **e** $3x - 2x^4 + x^2 = 0$ **f** $5 - x^5 = x^4 + x$

18 Solve these polynomial equations using the Null Factor Law.

a $(x + 1)(x - 3)(x + 2) = 0$ **b** $(x - 2)(x - 5)(x + 11) = 0$

c $(2x - 1)(3x + 2)(5x - 1) = 0$ **d** $(3x + 2)(5x + 4)(7x + 10)(2x - 13) = 0$

A CNC (computer numerically-controlled) milling machine cuts mechanical components out of solid steel. The software may have to solve thousands of polynomials to cut complex shapes.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10B Solving $ax^2 + bx = 0$ and $x^2 = d$ EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

When using the Null Factor Law we notice that equations must first be expressed as a product of two factors. Hence, any equation not in this form must first be factorised. Two types of quadratic equations are studied here. The first is of the form $ax^2 + bx = 0$ where x is a common factor and the second is of the form $x^2 = d$.

Remember 'null' means 'zero'.

Let's start: Which factorisation technique?

These two equations may look similar but they are not the same: $x^2 - 9x = 0$ and $x^2 - 9 = 0$.

- Discuss how you could factorise each expression on the left-hand side of the equations.
- How does the factorised form help to solve the equations? What are the solutions? Are the solutions the same for both equations?
- By rearranging $x^2 - 9 = 0$ into $x^2 = 9$, can you explain how to get the two solutions from above?

Key ideas

- When solving an equation of the form $ax^2 + bx = 0$, factorise by taking out common factors including x.

$2x^2 - 8x = 0$
$2x(x - 4) = 0$
$2x = 0$ or $x - 4 = 0$
$x = 0$ or $x = 4$

- When solving an equation of the form $ax^2 = d$, divide both sides by a and then take the square root of both sides.

$5x^2 = 20$
$x^2 = 4$
$x = 2$ or $x = -2$

- $x^2 = d^2$ could also be rearranged to $x^2 - d^2 = 0$ and then factorised as a difference of perfect squares.

$x^2 - 4 = 0$
$(x + 2)(x - 2) = 0$
$x = -2$ or $x = 2$

Example 4 Solving when x is a common factor

Solve each of the following equations.

a $x^2 + 4x = 0$ b $2x^2 = 8x$

SOLUTION	EXPLANATION
a $x^2 + 4x = 0$	
$x(x + 4) = 0$	Factorise by taking out the common factor x.
$x = 0$ or $x + 4 = 0$	Using the Null Factor Law, set each factor, x and $(x + 4)$, equal to 0. Solve for x.
$x = 0$ or $x = -4$	Check your solutions using substitution.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $2x^2 = 8x$	Make the right-hand side equal to zero by subtracting $8x$ from both sides.
$2x^2 - 8x = 0$	
$2x(x-4) = 0$	Factorise by taking out the common factor of $2x$ and apply the Null Factor Law to solve.
$2x = 0$ or $x - 4 = 0$	
$x = 0$ or $x = 4$	

Example 5 Solving equations of the form $ax^2 = d$

Solve each of these equations.

a $x^2 = 16$ **b** $3x^2 = 18$

SOLUTION	EXPLANATION
a $x^2 = 16$	Take the square root of both sides. $x = 4$ or -4 since $4^2 = 16$ and $(-4)^2 = 16$.
$x = 4$ or $x = -4$	
Altenative solution:	
$x^2 = 16$	
$x^2 - 16 = 0$	Rearrange into standard form.
$(x+4)(x-4) = 0$	Factorise using $a^2 - b^2 = (a+b)(a-b)$ then use the Null Factor Law to find the solutions.
$x + 4 = 0$ or $x - 4 = 0$	
$x = -4$ or $x = 4$	
b $3x^2 = 18$	Divide both sides by 3 and then take the square root of both sides.
$x^2 = 6$	
$x = \sqrt{6}$ or $x = -\sqrt{6}$	Since 6 is not a square number leave answers in exact form as $\sqrt{6}$ and $-\sqrt{6}$.
Alternative solution:	
$3x^2 = 18$	
$3x^2 - 18 = 0$	Alternatively, express in standard form and then note the common factor of 3.
$3(x^2 - 6) = 0$	
$3(x+\sqrt{6})(x-\sqrt{6}) = 0$	Treat $x^2 - 6 = x^2 - (\sqrt{6})^2$ as a difference of squares.
$x + \sqrt{6} = 0$ or $x - \sqrt{6} = 0$	Apply the Null Factor Law and solve for x.
$x = -\sqrt{6}$ or $x = \sqrt{6}$	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10B

1–3(½) | 2(½) | —

UNDERSTANDING

1 Write down the highest common factor of these pairs of terms.

a $2x$ and 4 **b** $5x$ and 10 **c** $4x$ and 6 **d** $16x$ and 24

e x^2 and $2x$ **f** x^2 and $7x$ **g** $3x^2$ and $6x$ **h** $9x^2$ and $15x$

2 Factorise these expressions fully by first taking out the highest common factor.

a $2x^2 - 8$ **b** $4x^2 - 36$ **c** $3x^2 - 75$ **d** $12x^2 - 12$

e $x^2 - 3x$ **f** $x^2 + 7x$ **g** $2x^2 - 4x$ **h** $5x^2 - 15x$

i $6x^2 + 4x$ **j** $9x^2 - 27x$ **k** $4x - 16x^2$ **l** $14x - 21x^2$

3 Use the Null Factor Law to write down the solutions to these equations.

a $x(x - 3) = 0$ **b** $4x(x + 1) = 0$ **c** $-7x(x + 2) = 0$

4–7(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 4a

4 Solve each of these equations.

a $x^2 + 3x = 0$ **b** $x^2 + 7x = 0$ **c** $x^2 + 4x = 0$ **d** $x^2 - 5x = 0$

e $x^2 - 8x = 0$ **f** $x^2 - 2x = 0$ **g** $x^2 + \frac{1}{3}x = 0$ **h** $x^2 - \frac{1}{2}x = 0$

5 Solve these equations by first taking out the highest common factor.

a $2x^2 - 6x = 0$ **b** $3x^2 - 12x = 0$ **c** $4x^2 + 20x = 0$

d $6x^2 - 18x = 0$ **e** $-5x^2 + 15x = 0$ **f** $-2x^2 - 8x = 0$

Example 4b

6 Solve each of the following equations.

a $x^2 = 3x$ **b** $5x^2 = 10x$ **c** $4x^2 = 16x$

d $3x^2 = -9x$ **e** $2x^2 = -8x$ **f** $7x^2 = -21x$

Example 5a

7 Solve each of the following equations.

a $x^2 = 9$ **b** $x^2 = 36$ **c** $x^2 = 25$

d $x^2 - 144 = 0$ **e** $x^2 - 81 = 0$ **f** $x^2 - 400 = 0$

Example 5b

8 Solve each of the following equations by noting the common factor first.

a $7x^2 = 28$ **b** $5x^2 = 45$ **c** $2x^2 = 50$ **d** $6x^2 = 24$

e $2x^2 = 12$ **f** $3x^2 = 15$ **g** $5x^2 - 35 = 0$ **h** $8x^2 - 24 = 0$

9 | 9, 10 | 10, 11

PROBLEM-SOLVING

9 Rearrange these equations then solve them.

a $4 = x^2$ **b** $-x^2 + 25 = 0$ **c** $-x^2 = -100$

d $-3x^2 = 21x$ **e** $-5x^2 + 35x = 0$ **f** $1 - x^2 = 0$

g $12x = 18x^2$ **h** $2x^2 + x = 7x^2 - 2x$ **i** $9 - 2x^2 = x^2$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10B

PROBLEM-SOLVING

10 Remove brackets or fractions to help solve these equations.

a $x - \frac{4}{x} = 0$ **b** $\frac{36}{x} - x = 0$ **c** $\frac{3}{x^2} = 3$

d $5(x^2 + 1) = 3x^2 + 7$ **e** $x(x - 3) = 2x^2 + 4x$ **f** $3x(5 - x) = x(7 - x)$

11 Write an equation and solve it to find the number.

a The square of the number is 7 times the same number.

b The difference between the square of a number and 64 is zero.

c 3 times the square of a number is equal to –12 times the number.

	12	12	12, 13

REASONING

12 Consider the equation $x^2 + 4 = 0$.

a Explain why it cannot be written in the form $(x + 2)(x - 2) = 0$.

b Are there any solutions to the equation $x^2 + 4 = 0$? Why/Why not?

13 An equation of the form $ax^2 + bx = 0$ will always have two solutions if a and b are not zero.

a Explain why one of the solutions will always be $x = 0$.

b Write the rule for the second solution in terms of a and b.

More quadratic equation forms	—	—	14, 15

ENRICHMENT

14 Note for example that $4x^2 = 9$ becomes $x^2 = \frac{9}{4}$ and then $x = \frac{3}{2}$ or $x = -\frac{3}{2}$, since $\sqrt{\frac{9}{4}} = \frac{3}{2}$.

Now solve these equations.

a $9x^2 = 16$ **b** $25x^2 = 36$ **c** $4 = 100x^2$

d $81 - 25x^2 = 0$ **e** $64 - 121x^2 = 0$ **f** $-49x^2 + 144 = 0$

15 Note for example that $(x - 1)^2 - 4 = 0$ becomes $(x - 1)^2 = 4$ with $x - 1 = 2$ or $x - 1 = -2$. Now solve these equations.

a $(x - 2)^2 = 9$ **b** $(x + 5)^2 = 16$ **c** $(2x + 1)^2 = 1$

d $(5x - 3)^2 - 25 = 0$ **e** $(4 - x)^2 - 9 = 0$ **f** $(3 - 7x)^2 - 100 = 0$

Using a CAS calculator 10B: Solving quadratic equations

This activity is in the interactive textbook in the form of a printable PDF.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10C Solving $x^2 + bx + c = 0$ EXTENDING

Earlier in Chapter 8 we learnt to factorise quadratic trinomials with three terms. For example, $x^2 + 5x + 6$ factorises to $(x + 2)(x + 3)$. This means that the Null Factor Law can be used to solve equations of the form $x^2 + bx + c = 0$.

Let's start: Remembering how to factorise quadratic trinomials

First expand these quadratics using the distributive law:

Distributive law

$(a + b)(c + d) = ac + ad + bc + bd$.

- $(x + 1)(x + 2)$
- $(x - 3)(x + 4)$
- $(x - 5)(x - 2)$

Now factorise these expressions.

- $x^2 + 5x + 6$
- $x^2 - x - 12$
- $x^2 - 8x + 7$

Discuss your method for finding the factors of each quadratic above.

Key ideas

- Solve quadratics of the form $x^2 + bx + c = 0$ by factorising the quadratic trinomial.
  - Ask 'What factors of c add to give b?'
  - Then use the Null Factor Law.
  - $x^2 + bx + c$ is called a monic quadratic since the coefficient of x^2 is 1.
- Perfect squares will give only one solution.

$x^2 - 3x - 28 = 0$ and $-7 \times 4 = -28$

$(x - 7)(x + 4) = 0$ $\quad -7 + 4 = -3$

$x - 7 = 0$ or $x + 4 = 0$

$x = 7$ or $x = -4$

$x^2 - 6x + 9 = 0$

$(x - 3)(x - 3) = 0$

$x - 3 = 0$

$x = 3$

Example 6 Solving equations with quadratic trinomials

Solve these quadratic equations.

a $x^2 + 7x + 12 = 0$ **b** $x^2 - 2x - 8 = 0$ **c** $x^2 - 8x + 15 = 0$

SOLUTION	EXPLANATION
a $x^2 + 7x + 12 = 0$	Factors of 12 which add to 7 are 3 and 4.
$(x + 3)(x + 4) = 0$	$3 \times 4 = 12,\ 3 + 4 = 7$
$x + 3 = 0$ or $x + 4 = 0$	Use the Null Factor Law to solve the equation.
$x = -3$ or $x = -4$	

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $x^2 - 2x - 8 = 0$
$(x-4)(x+2) = 0$
$x - 4 = 0$ or $x + 2 = 0$
$x = 4$ or $x = -2$

Factors of –8 which add to –2 are –4 and 2.
$-4 \times 2 = -8$, $-4 + 2 = -2$,
Finish using the Null Factor Law.

c $x^2 - 8x + 15 = 0$
$(x-5)(x-3) = 0$
$x - 5 = 0$ or $x - 3 = 0$
$x = 5$ or $x = 3$

The factors of 15 must add to give –8.
$-5 \times (-3) = 15$ and $-5 + (-3) = -8$, so –5 and –3 are the two numbers.

Example 7 Solving with perfect squares and other trinomials

Solve these quadratic equations.

a $x^2 - 8x + 16 = 0$ **b** $x^2 = x + 6$

SOLUTION **EXPLANATION**

a $x^2 - 8x + 16 = 0$
$(x-4)(x-4) = 0$
$x - 4 = 0$
$x = 4$

Factors of 16 which add to –8 are –4 and –4.
$(x-4)(x-4) = (x-4)^2$ is a perfect square so there is only one solution.

b $x^2 = x + 6$
$x^2 - x - 6 = 0$
$(x-3)(x+2) = 0$
$x - 3 = 0$ or $x + 2 = 0$
$x = 3$ or $x = -2$

First make the right-hand side equal zero by subtracting x and 6 from both sides. This is standard form. Factors of –6 which add to –1 are –3 and 2.

Exercise 10C

1, 2 | 2(½) | —

UNDERSTANDING

1 Decide what two factors of the first number add to give the second number.

a 6, 5 **b** 8, 6 **c** 2, –3 **d** 10, –7
e –2, 1 **f** –5, 4 **g** –12, –1 **h** –12, –4

2 Copy and complete the working to solve each equation.

a $x^2 + 9x + 20 = 0$
$(x+5)(_____) = 0$
$x + 5 = 0$ or $_____ = 0$
$x = _____$ or $x = _____$

b $x^2 - 2x - 24 = 0$
$(x-6)(_____) = 0$
$x - 6 = 0$ or $_____ = 0$
$x = _____$ or $x = _____$

c $x^2 + 4x - 45 = 0$
$(x+9)(_____) = 0$
$x + 9 = 0$ or $_____ = 0$
$x = _____$ or $x = _____$

d $x^2 - 10x + 16 = 0$
$(x-8)(_____) = 0$
$x - 8 = 0$ or $_____ = 0$
$x = _____$ or $x = _____$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10C

3(½), 4 | 3–5(½) | 3–5(½)

FLUENCY

Example 6

3 Solve these quadratic equations.

a $x^2 + 8x + 12 = 0$ **b** $x^2 + 11x + 24 = 0$ **c** $x^2 + 7x + 10 = 0$

d $x^2 + 5x - 14 = 0$ **e** $x^2 + 4x - 12 = 0$ **f** $x^2 + 7x - 30 = 0$

g $x^2 - 12x + 32 = 0$ **h** $x^2 - 9x + 18 = 0$ **i** $x^2 - 10x + 21 = 0$

j $x^2 - 2x - 15 = 0$ **k** $x^2 - 6x - 16 = 0$ **l** $x^2 - 4x - 45 = 0$

m $x^2 - 10x + 24 = 0$ **n** $x^2 - x - 42 = 0$ **o** $x^2 + 5x - 84 = 0$

p $x^2 + 4x + 3 = 0$ **q** $x^2 - 6x - 27 = 0$ **r** $x^2 - 12x + 20 = 0$

Example 7a

4 Solve these quadratic equations which include perfect squares.

a $x^2 + 6x + 9 = 0$ **b** $x^2 + 4x + 4 = 0$ **c** $x^2 + 14x + 49 = 0$

d $x^2 + 24x + 144 = 0$ **e** $x^2 - 10x + 25 = 0$ **f** $x^2 - 16x + 64 = 0$

g $x^2 - 12x + 36 = 0$ **h** $x^2 - 18x + 81 = 0$ **i** $x^2 - 20x + 100 = 0$

Example 7b

5 Solve these quadratic equations by first rearranging to standard form.

a $x^2 = 3x + 10$ **b** $x^2 = 7x - 10$ **c** $x^2 = 6x - 9$

d $x^2 = 4 - 3x$ **e** $14 - 5x = x^2$ **f** $x^2 + 16 = 8x$

g $x^2 - 12 = -4x$ **h** $6 - x^2 = 5x$ **i** $15 = 8x - x^2$

j $16 - 6x = x^2$ **k** $-6x = x^2 + 8$ **l** $-x^2 - 7x = -18$

6(½), 9 | 6(½), 7–9 | 6–8(½), 9

PROBLEM-SOLVING

6 Solve these equations by taking out a common factor as the first factorising step.

a $2x^2 - 2x - 12 = 0$ **b** $3x^2 + 24x + 45 = 0$ **c** $4x^2 - 24x - 64 = 0$

d $4x^2 - 20x + 24 = 0$ **e** $2x^2 - 8x + 8 = 0$ **f** $3x^2 + 6x + 3 = 0$

g $7x^2 - 70x + 175 = 0$ **h** $2x^2 + 12x = -18$ **i** $5x^2 = 35 - 30x$

7 Remove brackets, decimals or fractions and write in standard form to help solve these equations.

a $x^2 = 5(x - 1.2)$ **b** $2x(x - 3) = x^2 - 9$ **c** $3(x^2 + x - 10) = 2x^2 - 5(x + 2)$

d $x - 2 = \frac{35}{x}$ **e** $2 + \frac{1}{x} = -x$ **f** $\frac{x}{4} = 1 - \frac{1}{x}$

8 Write down a quadratic equation in standard form which has the following solutions.

a $x = 1$ and $x = 2$ **b** $x = 3$ and $x = -2$ **c** $x = -4$ and $x = 1$

d $x = -3$ and $x = 10$ **e** $x = 5$ only **f** $x = -11$ only

9 The temperature in °C inside a room at a scientific base in Antarctica after 10:00 am is given by the expression $t^2 - 9t + 8$ where t is in hours. Find the times in the day when the temperature is 0°C.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10C

10 | 10, 11 | 11, 12

REASONING

10 Consider this equation and solution.

$$x^2 - x - 12 = -6$$
$$(x-4)(x+3) = -6$$
$$x - 4 = -6 \text{ or } x + 3 = -6$$
$$x = -2 \text{ or } x = -9$$

a Explain what is wrong with the solution.

b Find the correct solutions to the equation.

11 Explain why $x^2 - 2x + 1 = 0$ only has one solution.

12 Write down a quadratic equation that has these solutions. Write in factorised form.

a $x = a$ only **b** $x = a$ and $x = b$

Coefficient of x^2 other than 1

— | — | 13

ENRICHMENT

13 Many quadratic equations have a coefficient of x^2 not equal to 1. These are called non-monic quadratics. Factorisation can be trickier but is still possible. You may have covered this in Chapter 8. Here is an example.

$$2x^2 + 5x - 3 = 0 \quad \text{(factors of } 2 \times (-3) = -6 \text{ that add to give 5 are } -1 \text{ and } 6.)$$
$$2x^2 - x + 6x - 3 = 0 \quad (6x - 1x = 5x)$$
$$x(2x-1) + 3(2x-1) = 0$$
$$(2x-1)(x+3) = 0$$
$$2x - 1 = 0 \text{ or } x + 3 = 0$$
$$x = \frac{1}{2} \text{ or } x = -3$$

Solve these quadratic equations.

a $5x^2 + 16x + 3 = 0$ **b** $3x^2 + 4x - 4 = 0$ **c** $6x^2 + x - 1 = 0$

d $10x^2 + 5x - 5 = 0$ **e** $2x^2 = 15 - 7x$ **f** $4x^2 = 12x - 9$

g $x = 3x^2 - 14$ **h** $17x = 12 - 5x^2$ **i** $25 = -9x^2 - 30x$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10D Applications of quadratic equations EXTENDING

When using mathematics to solve problems we often arrive at a quadratic equation. In solving the quadratic equation we obtain the solutions to the problem. Setting up the original equation and then interpreting the solution are important parts of the problem-solving process.

Surveyors work on many problems that involve quadratic equations.

Let's start: Solving for the unknown number

The product of a positive number and 6 more than the same number is 16.

- Using x as the unknown number, write an equation describing the given condition.
- Solve your equation for x.
- Are both solutions feasible (allowed)?
- Discuss how this method compares to the method of trial and error.

Key ideas

- When using quadratic equations to solve problems, follow these steps.
  - Define your variable.
    - Write 'Let x be …'
  - Write an equation describing the situation.
  - Solve your equation using the Null Factor Law.
  - Check that your solutions are feasible.
    - Some problems may not allow solutions that are negative numbers or fractions.
  - Answer the original question in words and check that your answer seems reasonable.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 8 Solving area problems

The length of a book is 4 cm more than its width and the area of the face of the book is 320 cm^2. Find the dimensions of the face of the book.

SOLUTION	EXPLANATION
Let x cm be the width of the book face.	Define a variable for width then write the length in terms of the width.
Length = $(x + 4)$ cm	
Area: $x(x + 4) = 320$	Write an equation to suit the given situation. Expand and subtract 320 from both sides.
$x^2 + 4x - 320 = 0$	
$(x + 20)(x - 16) = 0$	Solve using the Null Factor Law but note that a width of –20 cm is not feasible.
$x + 20 = 0$ or $x - 16 = 0$	
$x = -20$ or $x = 16$	
$\therefore x = 16$ since $x > 0$	Finish by writing the dimensions; width and length as required.
$\therefore$ width = 16 cm and length = 20 cm	Length = $x + 4 = 16 + 4 = 20$ cm

Exercise 10D

1, 3 | 2, 3 | —

UNDERSTANDING

1 This rectangle has an area of 8 cm^2 and a length which is 2 cm more than its width.



- **a** Using length × width = area, write an equation.
- **b** Solve your equation by expanding and subtracting 8 from both sides. Then use the Null Factor Law.
- **c** Which of your two solutions is feasible for the width of the rectangle?
- **d** Write down the dimensions (width and length) of the rectangle.

2 This rectangle has an area of 14 m^2 and a length which is 5 m more than its width.



- **a** Using length × width = area, write an equation.
- **b** Solve your equation by expanding and subtracting 14 from both sides. Then use the Null Factor Law.
- **c** Which of your two solutions is feasible for the width of the rectangle?
- **d** Write down the dimensions (width and length) of the rectangle.

3 Solve these equations for x by first expanding and producing a zero on the right-hand side.

- **a** $x(x + 3) = 18$
- **b** $x(x - 1) = 20$
- **c** $(x - 1)(x + 4) = 6$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10D

4–7 | 5, 7, 8 | 6–8

FLUENCY

4 The product of a number and 2 more than the same number is 48. Write an equation and solve to find the two possible solutions.

5 The product of a number and 7 less than the same number is 60. Write an equation and solve to find the two possible solutions.

6 The product of a number and 13 less than the same number is 30. Write an equation and solve to find the two possible solutions.

Example 8

7 The length of a rectangular brochure is 5 cm more than its width and the area of the face of the brochure is 36 cm^2. Find the dimensions of the face of the brochure.

8 The length of a small kindergarten play area is 20 metres less than its width and the area is 69 m^2. Find the dimensions of the kindergarten play area.

9, 10 | 9–11 | 9–12

PROBLEM-SOLVING

9 A square of side length 10 metres has a square of side length x metres removed from one corner.



- **a** Write an expression for the area remaining after the square of side length x metres is removed. *Hint:* use subtraction.
- **b** Find the value of x if the area remaining is to be 64 m^2.

10 An isosceles triangle has height (h) equal to half its base length. Find the value of h if the area is 25 square units.



11 A rectangular farm shed (3 m by 5 m) is to be extended to form an 'L' shape as shown.



- **a** Write an expression for the total area of the extended farm shed.
- **b** Find the value of x if the total area is to be 99 m^2.

12 Use Pythagoras' theorem to find the value of x in these right-angled triangles.

a



b



c



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

13 | 13, 14 | 14–16

10D

REASONING

13 The equation for the area of this rectangle is $x^2 + 2x - 48 = 0$ which has solutions $x = -8$ and $x = 6$. Which solution do you ignore and why?



14 The product of an integer and one less than the same integer is 6. The equation for this is $x^2 - x - 6 = 0$. How many different solutions are possible and why?

15 This table shows the sum of the first n positive integers. If $n = 3$ then the sum is $1 + 2 + 3 = 6$.

n	1	2	3	4	5	6
sum	1	3	6			

a Write the sum for $n = 4$, $n = 5$ and $n = 6$.

b The expression for the sum is given by $\frac{n(n+1)}{2}$. Use this expression to find the sum if:

i $n = 7$ **ii** $n = 20$

c Use the expression to find n for these sums. Write an equation and solve it.

i sum = 45 **ii** sum = 120

16 The number of diagonals in a polygon with n sides is given by $\frac{n}{2}(n-3)$. Shown here are the diagonals for a quadrilateral and a pentagon.



n	4	5	6	7
Diagonals	2	5		

a Use the given expression to find the two missing numbers in the table.

b Find the value of n if the number of diagonals is:

i 20 **ii** 54

Picture frames

— | — | 17, 18

ENRICHMENT

17 A square picture is to be edged with a border of width x cm. The inside picture has side length of 20 cm.

a Write an expression for the total area.

b Find the width of the frame if the total area is to be 1600 cm^2.



18 A square picture is surrounded by a rectangular frame as shown. The total area is to be 320 cm^2. Find the side length of the picture.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

10A Ext **1** Write these quadratic equations in standard form.

a $x^2 - 3x = 8$ **b** $3(x^2 - 2) = 4x$

c $2(x^2 - 5) = 2x - 7$ **d** $2x(x - 4) = 12 - 5x$

10A Ext **2** Substitute the given x value into the equation and say whether or not it is a solution.

a $x^2 - x - 6 = 0$ $(x = 2)$ **b** $x^2 - x - 6 = 0$ $(x = -2)$

c $x^2 - 9 = 0$ $(x = 3)$ **d** $x^2 - 9 = 0$ $(x = -3)$

10A Ext **3** Use the Null Factor Law to solve these equations.

a $x(x - 7) = 0$ **b** $(x - 5)(x + 2) = 0$

c $3x\left(x + \frac{2}{5}\right) = 0$ **d** $(3x - 1)(4x - 3) = 0$

10B Ext **4** Solve each of the following equations.

a $x^2 + 11x = 0$ **b** $3x^2 - 18x = 0$

c $-2x^2 - 10x = 0$ **d** $5x^2 = 20x$

10B Ext **5** Solve each of these equations.

a $x^2 = 49$ **b** $x^2 - 1 = 0$

c $3x^2 = 12$ **d** $7x^2 - 63 = 0$

10C Ext **6** Solve these quadratic equations.

a $x^2 + 11x + 24 = 0$ **b** $x^2 - 15x + 36 = 0$

c $x^2 - 2x - 35 = 0$ **d** $x^2 + 5x - 36 = 0$

10C Ext **7** Solve these quadratic equations.

a $x^2 + 8x + 16 = 0$ **b** $x^2 - 14x + 49 = 0$

c $x^2 + 100 = 20x$ **d** $x^2 - 24 = 5x$

10D Ext **8** A rectangular lawn is 3 m longer than it is wide and has an area of 54 m^2. Write an equation and solve it to find the dimensions of this lawn.

10D Ext **9** The product of a number and 5 more than the same number is 84. Write an equation and solve to find the two possible values of the number.

10C Ext **10** Write down a quadratic equation in standard form which has the following solutions.

a $x = 3$ and $x = 2$ **b** $x = 6$ and $x = -1$

c $x = 4$ and $x = -4$ **d** $x = -3$ only

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10E The parabola

Interactive

Widgets

HOTsheets

Walkthroughs

Relations that have rules in which the highest power of x is 2, such as $y = x^2$, $y = 2x^2 - 3$ or $y = 3x^2 + 2x - 4$, are called quadratics and their graphs are called parabolas. Parabolic shapes can be seen in many modern day objects or situations such as the arches of bridges, the paths of projectiles and the surface of reflectors.

Jets of water angled away from the vertical show parabolic trajectories.

Let's start: Finding features

A quadratic is given by the equation $y = x^2 - 2x - 3$. Complete these tasks to discover its graphical features.

- Use the rule to complete this table of values.

x	–2	–1	0	1	2	3	4
y							

- Plot your points on a copy of the axes shown at right and join them to form a smooth curve.
- Describe these features:
  - minimum turning point
  - axis of symmetry
  - coordinates of the y-intercept
  - coordinates of the x-intercepts



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- The graph of a quadratic relation is called a **parabola**. Its basic shape is shown here.
  - The basic quadratic rule is $y = x^2$.



- The general equation of a quadratic is $y = ax^2 + bx + c$.
- A parabola is symmetrical about a line called the **axis of symmetry** and it has one **turning point** (a vertex), which may be a **maximum** or a **minimum**.





Here is an example of a parabola with equation $y = x^2 - 4x + 3$, showing all the key features.



Example 9 Identifying features

For this graph state the:

a equation of the axis of symmetry
b type of turning point
c coordinates of the turning point
d x-intercepts
e y-intercept



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $x = -3$	Graph is symmetrical about the vertical line $x = -3$. Graph has its highest y-coordinate at the turning point, so it is a maximum point.
b maximum turning point	Highest point: turning point = $(-3, 5)$
c turning point is $(-3, 5)$	
d x-intercepts: -5 and -1	Axis of symmetry: $x = -3$
e y-intercept: -5	

The trails of the projectiles shot out by this firework can be modelled by quadratic equations.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Plotting a parabola

Use the quadratic rule $y = x^2 - 4$ to complete these tasks.

a Complete this table of values.

x	–3	–2	–1	0	1	2	3
y							

b Draw a set of axes using a scale that suits the numbers in your table. Then plot the points to form a parabola.

c State these features.

i Type of turning point
ii Axis of symmetry
iii Coordinates of the turning point
iv The y-intercept
v The x-intercepts

SOLUTION

a

x	–3	–2	–1	0	1	2	3
y	5	0	–3	–4	–3	0	5

EXPLANATION

Substitute each x value into the rule to find each y value, e.g. $x = -3$, $y = (-3)^2 - 4$
$= 9 - 4 = 5$.

b



Plot each coordinate pair and join to form a smooth curve.

c **i** Minimum turning point
ii $x = 0$ is the axis of symmetry
iii turning point $(0, -4)$
iv y-intercept: -4
v x-intercepts: -2 and 2

The turning point at $(0, -4)$ has the lowest y-coordinate for the entire graph.
The vertical line $x = 0$ divides the graph like a mirror line. The y-intercept is at $x = 0$.
The x-intercepts are at $y = 0$ on the x-axis.

Exercise 10E

1, 2, 3(½) | 3(½) | 3(½)

UNDERSTANDING

1 Choose a word from this list to complete each sentence.

lowest, parabola, vertex, highest, intercepts, zero

a A maximum turning point is the _____ point on the graph.
b The graph of a quadratic is called a _____.
c The x-_____ are the points where the graph cuts the x-axis.
d The axis of symmetry is a vertical line passing through the _____.
e A minimum turning point is the _____ point on the graph.
f The y-intercept is at x equals _____.

2 Write down the equation of a vertical line (e.g. $x = 2$) that passes through these points.

a (3, 0) **b** (1, 5) **c** (–2, 4) **d** (–5, 0)

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9

3 For each of the following graphs, state:

- **i** the equation of the axis of symmetry
- **ii** the type of turning point (maximum or minimum)
- **iii** the coordinates of the turning point
- **iv** the x-intercepts
- **v** the y-intercept.

a



b



c



d



e



f



g



h



i



j



k



l



ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10E

4–6 | 4–7 | 4, 6, 7

FLUENCY

Example 10

4 Use the quadratic rule $y = x^2 - 1$ to complete these tasks.

a Complete the table of values.

x	–2	–1	0	1	2
y					

b Draw a set of axes using a scale that suits the numbers in your table. Then plot the points to form a parabola.

c State these features.

i Type of turning point
ii Axis of symmetry
iii Coordinates of the turning point
iv The y-intercept
v The x-intercepts

5 Use the quadratic rule $y = 9 - x^2$ to complete these tasks.

a Complete the table of values.

x	–3	–2	–1	0	1	2	3
y							

b Draw a set of axes using a scale that suits the numbers in your table. Then plot the points to form a parabola.

c State these features.

i Type of turning point
ii Axis of symmetry
iii Coordinates of the turning point
iv The y-intercept
v The x-intercepts

6 Use the quadratic rule $y = x^2 + 2x - 3$ to complete these tasks.

a Complete the table of values.

x	– 4	–3	–2	–1	0	1	2
y							

b Draw a set of axes using a scale that suits the numbers in your table. Then plot the points to form a parabola.

c State these features.

i Type of turning point
ii Axis of symmetry
iii Coordinates of the turning point
iv The y-intercept
v The x-intercepts

7 Use the quadratic rule $y = -x^2 + x + 2$ to complete these tasks. Recall that $-x^2 = -1 \times x^2$.

a Complete the table of values.

x	–2	–1	0	1	2	3
y						

b Draw a set of axes using a scale that suits the numbers in your table. Then plot the points to form a parabola.

c State these features.

i Type of turning point
ii Axis of symmetry
iii Coordinates of the turning point
iv The y-intercept
v The x-intercepts

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8, 9 | 8, 10, 12 | 10–12

10E

PROBLEM-SOLVING

8 This graph shows the height of a cricket ball, y metres, as a function of time t seconds.



- **a** **i** At what times is the ball at a height of 9 m?
  - **ii** Why are there two different times?
- **b** **i** At what time is the ball at its greatest height?
  - **ii** What is the greatest height the ball reaches?
  - **iii** After how many seconds does it hit the ground?

9 The graph gives the height, h m, at time t seconds, of a rocket which is fired up in the air.



- **a** From what height is the rocket launched?
- **b** What is the approximate maximum height that the rocket reaches?
- **c** For how long is the rocket in the air?
- **d** What is the difference in time for when the rocket is going up and when it is going down?

10 A parabola has two x-intercepts at –2 and 4. The y-coordinate of the turning point is –3.

- **a** What is the equation of its axis of symmetry?
- **b** What are the coordinates of the turning point?

11 A parabola has a turning point at (1, 3) and one x-intercept at 0.

- **a** What is the equation of its axis of symmetry?
- **b** What is the other x-intercept?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

10E

PROBLEM-SOLVING

12 Write the rule for these parabolas. Use trial and error to help and check your rule by substituting a known point.

a



b



c



d



e



f



13, 14 | 13–15 | 13, 15, 16

REASONING

13 Is it possible to draw a parabola with the following properties? If yes, draw an example.

a Two x-intercepts

b One x-intercept

c No x-intercepts

d No y-intercept

14 **a** Mal calculates the y value for $x = 2$ using $y = -x^2 + 2x$ and gets $y = 8$. Explain his error.

b Mai calculates the y value for $x = -3$ using $y = x - x^2$ and gets $y = 6$. Explain her error.

15 This graph shows the parabola for $y = x^2 - 4$.



a For what values of x is $y = 0$?

b For what value of x is $y = -4$?

c How many values of x give a y value which is:

i greater than -4?

ii equal to -4?

iii less than -4?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

16 This table corresponds to the rule $y = x^2 - 2x$.

x	–1	0	1	2	3	4
y	3	0	–1	0	3	8

a Use this table to solve these equations

i $0 = x^2 - 2x$ **ii** $3 = x^2 - 2x$

b How many solutions would there be to the equation $8 = x^2 - 2x$? Why?

c How many solutions would there be to the equation $-1 = x^2 - 2x$? Why?

d How many solutions would there be to the equation $-2 = x^2 - 2x$? Why?

Using software to construct a parabola — — 17

17 Follow the steps below to construct a parabola using a **dynamic geometry package**.

Step 1. Show the coordinate axes system by selecting **Show Axes** from the **Draw** toolbox.

Step 2. Construct a line which is parallel to the x-axis and passes through a point F on the y-axis near the point $(0, -1)$.

Step 3. Construct a line segment AB on this line as shown in the diagram.

Step 4. Hide the line AB and then construct:

- a point C on the line segment AB
- a point P on the y-axis near the point $(0, 1)$.

Step 5. Construct a line which passes through the point C and is perpendicular to AB.

Step 6. Construct the point D which is equidistant from point P and segment AB.

Hint: use the perpendicular bisector of PC.

Step 7. Select **Trace** from the **Display** toolbox and click on the point D.

Step 8. Animate point C and observe what happens.

Step 9. Select **Locus** from the **Construct** toolbox and click at D and then at C.

Step 10. Drag point P and/or segment AB (by dragging F). (Clear the trace points by selecting **Refresh** drawing from the **Edit** menu.) What do you notice?







Using a CAS calculator 10E: Sketching parabolas

This activity is in the interactive textbook in the form of a printable PDF.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

10F Sketching $y = ax^2$ with dilations and reflections

Interactive

In geometry we know that shapes can be transformed by applying reflections, rotations, translations and dilations (enlargement). The same types of transformations can also be applied to graphs including parabolas. Altering the value of a in $y = ax^2$ causes both dilations and reflections.

Widgets

HOTsheets

Walkthroughs

Let's start: What is the effect of a?

This table and graph show a number of examples of $y = ax^2$ with varying values of a. They could also be produced using technology.

x	−2	−1	0	1	2
$y = x^2$	4	1	0	1	4
$y = 2x^2$	8	2	0	2	8
$y = \frac{1}{2}x^2$	2	$\frac{1}{2}$	0	$\frac{1}{2}$	2
$y = -x^2$	−4	−1	0	−1	−4



- Discuss how the different values of a affect the y-values in the table.
- Discuss how the different values of a affect the shape of the graph.
- How would the graphs of the following rules compare to the graphs shown above?

a $y = 3x^2$

b $y = \frac{1}{4}x^2$

c $y = -\frac{1}{2}x^2$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- The equation $y = ax^2$ describes a family of parabolas including $y = x^2, y = -x^2, y = 2x^2, y = -2x^2$ etc. They contain the following features:
  - the vertex (or turning point) is (0, 0)
  - the axis of symmetry is $x = 0$
  - if $a > 0$ the graph is **upright** (or **concave up**) and has a minimum turning point
  - if $a < 0$ the graph is **inverted** (or **concave down**) and has a maximum turning point.
- If $a > 1$ or $a < -1$:
  the graph appears narrower than either $y = x^2$ or $y = -x^2$. For example: $y = 2x^2$ or $y = -2x^2$



- If $-1 < a < 1$:
  the graph appears wider than either $y = x^2$ or $y = -x^2$. For example: $y = \frac{1}{2}x^2$ or $y = -\frac{1}{2}x^2$



- For $y = 2x^2$ we say that the graph of $y = x^2$ is **dilated** from the x-axis by a factor of 2.
- For $y = -x^2$ we say that the graph of $y = x^2$ is **reflected** in the x-axis.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 11 Comparing graphs of $y = ax^2$, $a > 0$

Complete the following for $y = x^2$, $y = 2x^2$ and $y = \frac{1}{2}x^2$.

a Draw up and complete a table of values for $-2 \leq x \leq 2$.

b Plot their graphs on the same set of axes.

c Write down the equation of the axis of symmetry and the coordinates of the turning point.

d **i** Does the graph of $y = 2x^2$ appear wider or narrower than $y = x^2$?

ii Does the graph of $y = \frac{1}{2}x^2$ appear wider or narrower than $y = x^2$?

SOLUTION

a $y = x^2$

x	−2	−1	0	1	2
y	4	1	0	1	4

$y = 2x^2$

x	−2	−1	0	1	2
y	8	2	0	2	8

$y = \frac{1}{2}x^2$

x	−2	−1	0	1	2
y	2	$\frac{1}{2}$	0	$\frac{1}{2}$	2

b



c axis of symmetry: y-axis ($x = 0$)
turning point: minimum at (0, 0)

d **i** The graph of $y = 2x^2$ appears narrower than the graph of $y = x^2$.

ii The graph of $y = \frac{1}{2}x^2$ appears wider than the graph of $y = x^2$.

EXPLANATION

Substitute each x value into $y = x^2$, $y = 2x^2$ and $y = \frac{1}{2}x^2$.

e.g. for $y = 2x^2$, if $x = 2$,

$y = 2(2)^2$
$= 2(4)$
$= 8$

If $x = -1$, $y = 2(-1)^2$
$= 2(1)$
$= 2$

Plot the points for each graph using the coordinates from the tables and join them with a smooth curve.

Look at graphs to see symmetry about the y-axis and a minimum turning point at the origin.

For each value of x, $2x^2$ is twice that of x^2; hence, the graph (y-values) of $2x^2$ rises more quickly.

For each value of x, $\frac{1}{2}x^2$ is half that of x^2; hence, the graph of $\frac{1}{2}x^2$ rises more slowly.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Comparing graphs of $y = ax^2$, $a < 0$

Complete the following for $y = -x^2$, $y = -3x^2$ and $y = -\frac{1}{2}x^2$.

a Draw up and complete a table of values for $-2 \leq x \leq 2$.

b Plot their graphs on the same set of axes.

c Write down the the equation of the axis of symmetry and the coordinates of the turning point.

d **i** Does the graph of $y = -3x^2$ appear wider or narrower than $y = -x^2$?

ii Does the graph of $y = -\frac{1}{2}x^2$ appear wider or narrower than $y = -x^2$?

SOLUTION

a $y = -x^2$

x	-2	-1	0	1	2
y	-4	-1	0	-1	-4

$y = -3x^2$

x	-2	-1	0	1	2
y	-12	-3	0	-3	-12

$y = -\frac{1}{2}x^2$

x	-2	-1	0	1	2
y	-2	$-\frac{1}{2}$	0	$-\frac{1}{2}$	-2

b



c axis of symmetry: y-axis ($x = 0$)
turning point: maximum at $(0, 0)$

d **i** The graph of $y = -3x^2$ appears narrower than the graph of $y = -x^2$.

ii The graph of $y = -\frac{1}{2}x^2$ appears wider than the graph of $y = -x^2$.

EXPLANATION

Substitute each x-value into $y = -x^2$, $y = -3x^2$ and $y = -\frac{1}{2}x^2$.

e.g. for $y = -3x^2$, if $x = 2$,

$y = -3(2)^2$
$= -3(4)$
$= -12$

If $x = -1$, $y = -3(-1)^2$
$= -3(1)$
$= -3$

Plot the coordinates for each graph from the tables and join them with a smooth curve.

Graphs are symmetrical about the y-axis with a maximum turning point at the origin.

For each value of x, $-3x^2$ is three times that of $-x^2$; hence, the graph of $-3x^2$ gets larger in the negative direction more quickly.

For each value of x, $-\frac{1}{2}x^2$ is half that of $-x^2$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10F

1–3 | 2 | —

UNDERSTANDING

1 Shown here are the graphs of $y = x^2$, $y = 3x^2$, $y = \frac{1}{2}x^2$, $y = -x^2$, $y = -3x^2$ and $y = -\frac{1}{2}x^2$.

a Write the rules of the three graphs which have a minimum turning point.



b Write the rules of the three graphs which have a maximum turning point.

c What are the coordinates of the turning point for all the graphs?

d What is the equation of the axis of symmetry for all the graphs?

e Write the rule of the graph which is:

i upright (concave up) and narrower than $y = x^2$

ii upright (concave up) and wider than $y = x^2$

iii inverted (concave down) and narrower than $y = -x^2$

iv inverted (concave down) and wider than $y = -x^2$.

f Write the rule of the graph which is:

i a reflection of $y = x^2$ in the x-axis

ii a reflection of $y = 3x^2$ in the x-axis

iii a reflection of $y = -\frac{1}{2}x^2$ in the x-axis.

2 Select the word *positive* or *negative* to suit each sentence.

a The graph of $y = ax^2$ will be upright (concave up) with a minimum turning point if a is _____.

b The graph of $y = ax^2$ will be inverted (concave down) with a maximum turning point if a is _____.

3 **a** Write the rule of a graph which is a reflection in the x-axis of the graph of the rule $y = x^2$.

b Write the rule of a graph which is a reflection in the x-axis of the graph of the rule $y = 4x^2$.

c Write the rule of a graph which is a reflection in the x-axis of the graph of the rule $y = -5x^2$.

d Write the rule of a graph which is a reflection in the x-axis of the graph of the rule $y = -\frac{1}{3}x^2$.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10F

4, 5–6(½) | 4, 5–6(½) | 4, 6

FLUENCY

Example 11

4 Complete the following for $y = x^2$, $y = 3x^2$ and $y = \frac{1}{3}x^2$.

- **a** Draw up and complete a table of values for $-2 \leq x \leq 2$.
- **b** Plot their graphs on the same set of axes.
- **c** Write down the coordinates of the turning point and the equation of the axis of symmetry.
- **d** **i** Does the graph of $y = 3x^2$ appear wider or narrower than $y = x^2$?
- **ii** Does the graph of $y = \frac{1}{3}x^2$ appear wider or narrower than $y = x^2$?

5 For the equations given below, complete these tasks.

- **i** Draw up and complete a table of values for $-2 \leq x \leq 2$.
- **ii** Plot the graphs of the equations on the same set of axes.
- **iii** Write down the coordinates of the turning point and the equation of the axis of symmetry.
- **iv** Determine whether the graphs of the equations each appear wider or narrower than the graph of $y = x^2$.

a $y = 4x^2$ **b** $y = 5x^2$

c $y = \frac{1}{4}x^2$ **d** $y = \frac{1}{5}x^2$

Example 12

6 For the equations given below, complete these tasks.

- **i** Draw up and complete a table of values for $-2 \leq x \leq 2$.
- **ii** Plot the graphs of the equations on the same set of axes.
- **iii** List the key features for each graph, such as the axis of symmetry, turning point, x-intercept and y-intercept.
- **iv** Determine whether the graphs of the equations each appear wider or narrower than the graph of $y = -x^2$.

a $y = -2x^2$ **b** $y = -3x^2$ **c** $y = -\frac{1}{2}x^2$ **d** $y = -\frac{1}{3}x^2$

7 | 7, 8 | 7, 8

PROBLEM-SOLVING

7 Here are eight quadratics of the form $y = ax^2$.

A $y = 6x^2$ **B** $y = -7x^2$ **C** $y = 4x^2$ **D** $y = \frac{1}{9}x^2$

E $y = \frac{x^2}{7}$ **F** $y = 0.3x^2$ **G** $y = -4.8x^2$ **H** $y = -0.5x^2$

- **a** Which rule would give a graph which is upright (concave up) and the narrowest?
- **b** Which rule would give a graph which is inverted (concave down) and the widest?

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10F

PROBLEM-SOLVING

8 Match each of the following parabolas with the appropriate equation from the list below. Do a mental check by substituting the coordinates of a known point.

i $y = 3x^2$ ii $y = -x^2$ iii $y = 5x^2$

iv $y = \frac{1}{2}x^2$ v $y = -5x^2$ vi $y = 2x^2$

a



b



c



d



e



f



9 | 9, 10 | 10–12

REASONING

9 The graph of $y = -2x^2$ can be obtained from $y = x^2$ by conducting these transformations:

- reflecting in the x-axis
- dilating by a factor of 2 from the x-axis.

In the same way as above, describe the two transformations which take:



a $y = x^2$ to $y = -3x^2$

b $y = x^2$ to $y = -6x^2$

c $y = x^2$ to $y = -\frac{1}{2}x^2$

d $y = -x^2$ to $y = 2x^2$

e $y = -x^2$ to $y = 3x^2$

f $y = -x^2$ to $y = \frac{1}{3}x^2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10F

REASONING

10 Write the rule for the graph after each set of transformations.

a The graph of $y = x^2$ is reflected in the x-axis then dilated by a factor of 4 from the x-axis.

b The graph of $y = -x^2$ is reflected in the x-axis then dilated by a factor of $\frac{1}{3}$ from the x-axis.

c The graph of $y = 2x^2$ is reflected in the x-axis then dilated by a factor of 2 from the x-axis.

d The graph of $y = \frac{1}{3}x^2$ is reflected in the x-axis then dilated by a factor of 4 from the x-axis.

11 The graph of $y = ax^2$ is reflected in the x-axis and dilated from the x-axis by a given factor. Does it matter which transformation is completed first? Explain.

12 The graph of the rule $y = ax^2$ is reflected in the y-axis. What is the new rule of the graph?

Substitute to find the rule — — 13, 14

ENRICHMENT

13 If a rule is of the form $y = ax^2$ and it passes through a point, say (1, 4), we can substitute this point to find the value of a.

So $y = ax^2$,

$4 = a \times (1)^2$

$\therefore a = 4$ and $y = 4x^2$



Use this method to determine the equation of a quadratic relation if it has an equation of the form $y = ax^2$ and passes through:

a (1, 5) **b** (1, 7) **c** (–1, 1) **d** (–2, 7)

e (–5, 4) **f** (3, 26) **g** (4, 80) **h** (–1, –52)

14 This photo shows the parabolic cables of the Golden Gate Bridge. The rule of the form $y = ax^2$ describes the shape of the parabolic cables. If the cable is centred at (0, 0) and the top of the right pylon has the coordinates (492, 67), find a possible equation that describes this shape. The numbers given are in metres.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G Sketching $y = x^2$ with translations

Interactive

Widgets

HOTsheets

Walkthroughs

Added to reflection and dilation is a third type of transformation called translation. This involves a shift of every point on the graph horizontally and/or vertically. Unlike reflections and dilations, a translation alters the coordinates of the turning point. The shape of the curve is unchanged but a horizontal shift changes the equation of the axis of symmetry.

Let's start: Which way: left, right, up or down?

This table and graph shows the quadratics $y = x^2$, $y = (x-2)^2$, $y = (x+1)^2$, $y = x^2 - 4$ and $y = x^2 + 2$. The table could also be produced using technology.

x	–3	–2	–1	0	1	2	3
$y = x^2$	9	4	1	0	1	4	9
$y = (x-2)^2$	25	16	9	4	1	0	1
$y = (x+1)^2$	4	1	0	1	4	9	16
$y = x^2 - 4$	5	0	–3	–4	–3	0	5
$y = x^2 + 2$	11	6	3	2	3	6	11

- Discuss what effect the different numbers in the rules had on the y values in the table.
- Also discuss what effect the numbers in the rules have on each graph. How are the coordinates of the turning point changed?
- What conclusions could you draw on the effect of h in the rule $y = (x-h)^2$?
- What conclusions could you draw on the effect of k in the rule $y = x^2 + k$?
- What if the rule was $y = -x^2 + 2$ or $y = -(x+1)^2$? Describe how the graphs would look.



Key ideas

- A **translation** of a graph involves a shift of every point horizontally and/or vertically.
- Vertical translations: $y = x^2 + k$
  - If $k > 0$, the graph is translated k units up (red curve).
  - If $k < 0$, the graph is translated k units down (green curve).
  - The turning point is $(0, k)$ for all curves.
  - The axis of symmetry is the line $x = 0$ for all curves.
  - The y-intercept is k for all curves.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- Horizontal translations: $y = (x - h)^2$

  If $h > 0$, the graph is translated h units to the right.

  

  If $h < 0$, the graph is translated h units to the left.

  

  - The turning point is $(h, 0)$ in both cases.
  - The axis of symmetry is the line $x = h$ in both cases.
  - The y-intercept is h^2 in both cases.

- The **turning point form** of a quadratic is given by:

$$y = a(x - h)^2 + k$$

$a > 0$ upright (concave up) graph ∪

$a < 0$ graph inverted (concave down) ∩

Translates the graph up or down: $k > 0$ ↑, $k < 0$ ↓

Translates the graph left or right: $h > 0$ →, $h < 0$ ←

Axis of symmetry: $x = h$

Turning point = (h, k)



- To sketch a graph of a quadratic equation in turning point form, follow these steps.
  - Draw and label a set of axes.
  - Identify important points including the turning point and y-intercept.
  - Sketch the curve connecting the key points and making the curve symmetrical.



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Sketching with horizontal and vertical translations

Sketch the graphs of these rules showing the y-intercept and the coordinates of the turning point.

a $y = x^2 + 2$ **b** $y = -x^2 - 1$

c $y = (x - 3)^2$ **d** $y = -(x + 2)^2$

SOLUTION	EXPLANATION
a $y = x^2 + 2$ Turning point is (0, 2) y-intercept: $y = (0)^2 + 2 = 2$	For $y = x^2 + k$, $k = 2$ so the graph of $y = x^2$ is translated 2 units up.
	The point (0, 0) shifts to (0, 2).
b $y = -x^2 - 1$ Turning point is (0, –1) y-intercept: $y = -(0)^2 - 1 = -1$	The graph of $y = -x^2$ is a reflection of the graph of $y = x^2$ in the x-axis.
	For $y = -x^2 + k$, $k = -1$ so the graph of $y = -x^2$ is translated down 1 unit.
c $y = (x - 3)^2$ Turning point is (3, 0) y-intercept: $y = (0 - 3)^2$ $= (-3)^2$ $= 9$	For $y = (x - h)^2$, $h = 3$ so the graph of $y = x^2$ is translated 3 units to the right. The y-intercept is found by substituting $x = 0$ into the rule.
	

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d $y = -(x + 2)^2$

Turning point is $(-2, 0)$

y-intercept: $y = -(0 + 2)^2$

$= -2^2$

$= -4$



For $y = -(x - h)^2$, $h = -2$ since $-(x - (-2))^2 = -(x + 2)^2$. So the graph of $y = -x^2$ is translated 2 units to the left.

The y-intercept is found by substituting $x = 0$.

The negative sign in front means the graph is inverted.

Example 14 Sketching with combined translations

Sketch these graphs on the same set of axes showing the y-intercept and the coordinates of the turning point.

a $y = (x - 2)^2 - 1$ **b** $y = -(x + 3)^2 + 2$

SOLUTION **EXPLANATION**

a $y = (x - 2)^2 - 1$

Turning point is $(2, -1)$

y-intercept: $y = (0 - 2)^2 - 1$

$= 4 - 1$

$= 3$

For $y = (x - h)^2 + k$, $h = 2$ and $k = -1$ so the graph of $y = x^2$ is shifted 2 to the right and 1 down.

Substitute $x = 0$ for the y-intercept.

b $y = -(x + 3)^2 + 2$

Turning point is $(-3, 2)$

y-intercept: $y = -(0 + 3)^2 + 2$

$= -9 + 2$

$= -7$

For $y = -(x - h)^2 + k$, $h = -3$ and $k = 2$ so the graph of $y = x^2$ is shifted 3 to the left and 2 up.



First, position the coordinates of the turning point and y-intercept then join to form each curve.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10G

1–4 | 3, 4 | —

UNDERSTANDING

1 This diagram shows the graphs of $y = x^2$, $y = -x^2$, $y = (x + 2)^2$ and $y = -(x - 3)^2$.



a State the turning point of the graph of:
- **i** $y = (x + 2)^2$
- **ii** $y = -(x - 3)^2$

b State the y-intercept for the graph of:
- **i** $y = (x + 2)^2$
- **ii** $y = -(x - 3)^2$

c Compared to the graph of $y = x^2$, which way has the graph of $y = (x + 2)^2$ been translated (left or right)?

d Compared to the graph of $y = -x^2$ which way has the graph of $y = -(x - 3)^2$ been translated (left or right)?

2 This diagram shows the graphs of $y = x^2$, $y = -x^2$, $y = x^2 - 3$ and $y = -x^2 + 2$.



a State the turning point of the graph of:
- **i** $y = x^2 - 3$
- **ii** $y = -x^2 + 2$

b State the y-intercept for the graph of:
- **i** $y = x^2 - 3$
- **ii** $y = -x^2 + 2$

c Compared to the graph of $y = x^2$, which way has the graph of $y = x^2 - 3$ been translated (up or down)?

d Compared to the graph of $y = -x^2$, which way has the graph of $y = -x^2 + 2$ been translated (up or down)?

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

10G

UNDERSTANDING

3 This diagram shows the graphs of $y = x^2$, $y = -x^2$, $y = -(x-2)^2 + 3$ and $y = (x+1)^2 - 1$.



a State the turning point of the graph of:
- **i** $y = -(x-2)^2 + 3$
- **ii** $y = (x+1)^2 - 1$

b State the y-intercept for the graph of:
- **i** $y = -(x-2)^2 + 3$
- **ii** $y = (x+1)^2 - 1$

c State the missing words and numbers.
- **i** Compared to the graph of $y = x^2$, the graph of $y = (x+1)^2 - 1$ has to be translated _____ unit to the _____ and _____ unit _____.
- **ii** Compared to the graph of $y = -x^2$, the graphof $y = -(x-2)^2 + 3$ has to be translated _____ units to the _____ and _____ units _____.

4 Substitute $x = 0$ to find the y-intercept for these rules.

a $y = x^2 + 3$ **b** $y = -x^2 - 4$ **c** $y = -(x-2)^2$ **d** $y = (x+5)^2$

5–6(½) 5–7(½) 5–7(½)

FLUENCY

Example 13a, Example 13b

5 Sketch the graphs of these rules showing the y-intercept and the coordinates of the turning point.

a $y = x^2 + 1$ **b** $y = x^2 + 3$ **c** $y = x^2 - 2$
d $y = -x^2 + 4$ **e** $y = -x^2 + 1$ **f** $y = -x^2 - 5$

Example 13c, Example 13d

6 Sketch the graphs of these rules showing the y-intercept and the coordinates of the turning point.

a $y = (x-2)^2$ **b** $y = (x-4)^2$ **c** $y = (x+3)^2$
d $y = -(x-3)^2$ **e** $y = -(x+2)^2$ **f** $y = -(x+6)^2$

Example 14

7 Sketch each graph showing the y-intercept and the coordinates of the turning point.

a $y = (x-3)^2 + 2$ **b** $y = (x-1)^2 - 1$ **c** $y = (x+2)^2 - 3$
d $y = (x+1)^2 + 7$ **e** $y = -(x-2)^2 + 1$ **f** $y = -(x-5)^2 + 3$
g $y = -(x+3)^2 - 4$ **h** $y = -(x+1)^2 - 5$ **i** $y = -(x-3)^2 - 6$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G

8 | 8, 9 | 8–10

PROBLEM-SOLVING

8 Match each of the following parabolas with the appropriate equation from the list below.

i $y = x^2$ **ii** $y = (x+2)^2$ **iii** $y = x^2 - 4$ **iv** $y = -x^2 - 3$
v $y = (x-2)^2$ **vi** $y = x^2 + 4$ **vii** $y = 4 - x^2$ **viii** $y = (x+3)^2$
ix $y = (x-5)^2$ **x** $y = x^2 + 3$ **xi** $y = -(x+3)^2$ **xii** $y = -x^2 + 3$

a



b



c



d



e



f



g



h



i



j



k



l



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9 Write the rule for each graph in turning point form.

a



b



c



d



e



f



10 A bike track can be modelled approximately by combining two different quadratic equations. The first part of the bike path can be modelled by the equation $y = -(x-2)^2 + 9$ for $-2 \leq x \leq 5$. The second part of the bike track can be modelled by the equation $y = (x-7)^2 - 4$ for $5 \leq x \leq 10$.

a Find the turning point of the graph of each quadratic equation.

b Sketch each graph on the same set of axes. On your sketch of the bike path you need to show the coordinates of the start and finish of the track and where it crosses the x-axis.

11 | 11, 12 | 12, 13

11 Written in the form $y = a(x-h)^2 + k$, the rule $y = 4 - (x+2)^2$ could be rearranged to give $y = -(x+2)^2 + 4$.

a Rearrange these rules and write in the form $y = a(x-h)^2 + k$.

i $y = 3 - (x+1)^2$ **ii** $y = 4 + (x+3)^2$ **iii** $y = -3 + (x-1)^2$

iv $y = -7 - (x-5)^2$ **v** $y = -2 - x^2$ **vi** $y = -6 + x^2$

b Write down the coordinates of the turning point for each of the above quadratics.

12 A quadratic has the rule $y = a(x-h)^2 + k$.

a What are the coordinates of the turning point?

b Write an expression for the y-intercept.

13 Investigate and explain how the graph of:

a $y = (2-x)^2$ compares to the graph of $y = (x-2)^2$

b $y = (1-x)^2$ compares to the graph of $y = (x-1)^2$.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G Finding rules — — 14–17

ENRICHMENT

14 Find the equation of the quadratic relation which is of the form $y = x^2 + c$ and passes through:

a (1, 4) **b** (3, 5) **c** (2, 1) **d** (2, –1)

15 Find the equation of the quadratic relation which is of the form $y = -x^2 + c$ and passes through:

a (1, 3) **b** (–1, 3) **c** (3, 15) **d** (–2, 6)

16 Find the possible equations of each of the following quadratics if their equation is of the form $y = (x - h)^2$ and their graph passes through the point:

a (1, 16) **b** (3, 1) **c** (–1, 9) **d** (3, 9)

17 Find the rule for each of these graphs with the given turning point (TP) and y-intercept.

a TP = (1, 1), y-int = 0
b TP = (–2, 0), y-int = 4
c TP = (3, 0), y-int = –9
d TP = (–3, 2), y-int = –7
e TP = (–1, 4), y-int = 5
f TP = (3, –9), y-int = 0



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

10H Sketching parabolas using intercept form EXTENDING

So far we have sketched parabolas using rules of the form $y = a(x - h)^2 + k$ where the coordinates of the turning point can be determined directly from the rule. An alternative method for sketching parabolas uses the factorised form of the quadratic rule and the Null Factor Law to find the x-intercepts. The turning point can be found by considering the axis of symmetry halfway between the two x-intercepts.

Let's start: From x-intercepts to turning point

This graph has the rule $y = x^2 - 2x - 3$ but all its important features are not shown.

Find the features by discussing these questions.

- Can the quadratic rule be factorised?
- What is true about the coordinates of both x-intercepts?
- How can the factorised form of the rule help to find the x-intercepts?
- How does the x-coordinate of the turning point relate to the x-intercepts?
- Discuss how the y-coordinate of the turning point can be found.
- Finish by finding the y-intercept.



Key ideas

- All parabolas have one y-intercept and can have two, one or zero x-intercepts.

Two x-intercepts



One x-intercept



Zero x-intercepts



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

- x-intercepts can be found by substituting $y = 0$ and using the Null Factor Law.
- If the graph has two x-intercepts (a and b), the turning point can be found by:
  - calculating the x-coordinate of the turning point, the midpoint of a and b; that is, $x = \frac{a+b}{2}$
  - calculating the y value of the turning point by substituting the x-coordinate into the rule for the quadratic.



$y = (x - a)(x - b)$

x-intercepts: $0 = (x - a)(x - b)$

$x - a = 0$ or $x - b = 0$

$x = a$ or $x = b$

Example 15 Finding intercepts

For each of the following quadratic relations, find:

i the x-intercepts ii the y-intercept

a $y = x(x + 1)$ **b** $y = 2(x + 2)(x - 3)$

SOLUTION | **EXPLANATION**

a i x-intercepts (let $y = 0$):
$x(x + 1) = 0$

$x = 0$ or $x + 1 = 0$

$x = 0$ or $x = -1$

Let $y = 0$ to find the x-intercepts.

Apply the Null Factor Law to set each factor equal to 0 and solve.

ii y-intercept (let $x = 0$):
$y = 0(0 + 1)$

$y = 0$

Let $x = 0$ to find the y-intercept.

b i $y = 2(x + 2)(x - 3)$ has two x-intercepts
x-intercepts (let $y = 0$):

$2(x + 2)(x - 3) = 0$

$x + 2 = 0$ or $x - 3 = 0$

$x = -2$ or $x = 3$

There are two different factors.

Let $y = 0$ to find the x-intercepts. Set each factor equal to 0 and solve.

ii y-intercept (let $x = 0$):
$y = 2(2)(-3)$

$y = -12$

Let $x = 0$ to find the y-intercept.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 16 Sketching using intercept form

For the quadratic relation $y = x^2 - 2x$:

a factorise the relation
b find the y-intercept
c find the x-intercepts
d find the axis of symmetry
e find the turning point
f sketch the graph clearly showing all the key features

SOLUTION	EXPLANATION
a $y = x^2 - 2x$ $= x(x - 2)$	Take out the common factor of x.
b y-intercept (let $x = 0$): $y = 0$	Let $x = 0$ to find the y-intercept.
c x-intercepts (let $y = 0$): $0 = x(x - 2)$ $x = 0$ or $x - 2 = 0$ $x = 0$ or $x = 2$	Let $y = 0$ to find the x-intercepts. Set each factor equal to 0 and solve.
d Axis of symmetry: $x = \frac{0 + 2}{2} = 1$	The axis of symmetry is halfway between the x-intercepts.
e Turning point occurs when $x = 1$. When $x = 1$, $y = (1)^2 - 2(1)$ $y = -1$ $\therefore$ there is a minimum turning point at $(1, -1)$.	Substitute $x = 1$ into $y = x^2 - 2x$ to find the y-coordinate. $x = 1$ and $y = -1$ The coefficient of x^2 is positive therefore the basic shape is ∪.
f 	Sketch the graph, labelling the key features found above.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 17 Sketching a quadratic trinomial

For the quadratic relation $y = x^2 + 2x - 8$:

a factorise the relation
b find the y-intercept
c find the x-intercepts
d find the axis of symmetry
e find the turning point
f sketch the graph clearly showing all the key features.

SOLUTION	EXPLANATION
a $y = x^2 + 2x - 8$ $= (x + 4)(x - 2)$	Factorise the quadratic trinomial. $4 \times (-2) = -8$ and $4 + (-2) = 2$.
b y-intercept (let $x = 0$): $y = -8$	Let $x = 0$ to find the y-intercept.
c x-intercepts (let $y = 0$): $0 = (x + 4)(x - 2)$ $x + 4 = 0$ or $x - 2 = 0$ $x = -4$ or $x = 2$	Let $y = 0$ to find the x-intercepts.
d Axis of symmetry: $x = \frac{-4 + 2}{2} = -1$	The axis of symmetry is halfway between the x-intercepts
e Turning point occurs when $x = -1$. When $x = -1$, $y = (-1)^2 + 2(-1) - 8$ $= -9$ $\therefore$ there is a minimum turning point at $(-1, -9)$.	Substitute $x = -1$ into $y = x^2 + 2x - 8$ to find the y-coordinate. $x = -1$ and $y = -9$ The coefficient of x^2 is positive therefore the basic shape is ∪
f 	Sketch the graph showing the key features.

Exercise 10H

1–3(½) | 3(½) | —

UNDERSTANDING

1 Factorise these quadratics.

a $x^2 + 2x$
b $x^2 - 3x$
c $5x^2 - 10x$
d $x^2 - 9$
e $x^2 - 1$
f $x^2 - 49$
g $x^2 + 3x + 2$
h $x^2 + 5x + 6$
i $x^2 - x - 12$
j $x^2 - 3x - 28$
k $x^2 - 4x + 4$
l $x^2 + 10x + 25$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

10H

UNDERSTANDING

2 For these factorised quadratics, use the Null Factor Law to solve for x then find the x value halfway between.

a $0 = (x-2)(x+2)$ **b** $0 = (x-5)(x+5)$ **c** $0 = (x+1)(x+5)$
d $0 = (x-6)(x-10)$ **e** $0 = (x-1)(x+3)$ **f** $0 = (x-3)(x+5)$
g $0 = (x-2)(x+3)$ **h** $0 = (x-10)(x+1)$ **i** $0 = (x-15)(x+3)$

3 Use substitution to find the y-coordinate of the turning point of these quadratics. The x-coordinate of the turning point is given.

a $y = x^2 - 4, x = 0$ **b** $y = x^2 + 2x, x = -1$ **c** $y = x^2 - 6x, x = 3$
d $y = x^2 + 4x + 3, x = -2$ **e** $y = x^2 + 2x - 8, x = -1$ **f** $y = x^2 - 4x - 5, x = 2$

4–6(½) 4–7(½) 4–7(½)

FLUENCY

Example 15

4 For each of the following quadratic relations, find:

i the x-intercepts **ii** the y-intercept

a $y = x(x+7)$ **b** $y = x(x+3)$ **c** $y = x(x+4)$
d $y = (x-4)(x+2)$ **e** $y = (x+2)(x-5)$ **f** $y = (x-7)(x+3)$
g $y = 2(x+3)(x-1)$ **h** $y = 3(x+4)(x+1)$ **i** $y = (2-x)(3-x)$

Example 16

5 For each of the following quadratic relations:

i factorise the relation **ii** find the y-intercept
iii find the x-intercepts **iv** find the axis of symmetry
v find the turning point **vi** sketch the graph clearly showing all the key features.

a $y = x^2 - 5x$ **b** $y = x^2 + x$ **c** $y = x^2 - 3x$
d $y = 2x + x^2$ **e** $y = 5x + x^2$ **f** $y = 3x - x^2$
g $y = -x^2 - 8x$ **h** $y = -2x - x^2$ **i** $y = -x^2 + x$

Example 17

6 For each of the following quadratic relations:

i factorise the relation **ii** find the y-intercept
iii find the x-intercepts **iv** find the axis of symmetry
v find the turning point **vi** sketch each graph clearly showing all the key features.

a $y = x^2 - 3x + 2$ **b** $y = x^2 - 4x + 3$ **c** $y = x^2 + 2x - 3$
d $y = x^2 + 4x + 4$ **e** $y = x^2 + 2x + 1$ **f** $y = x^2 + 2x - 8$

7 For each of the following relations, sketch the graph clearly showing the x- and y-intercepts and the turning point.

a $y = x^2 - 1$ **b** $y = 9 - x^2$ **c** $y = x^2 + 5x$
d $y = 2x^2 - 6x$ **e** $y = 4x^2 - 8x$ **f** $y = x^2 - 3x - 4$
g $y = x^2 + x - 12$ **h** $y = x^2 + 2x + 1$ **i** $y = x^2 - 6x + 9$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10H

8 | 8, 9 | 8(½), 9, 10

PROBLEM-SOLVING

8 State the missing number in these quadratic graphs.

a



b



c



d



e



f



9 A golf ball's path is given by the rule $y = 30x - x^2$, where y is the height in metres above the ground and x is the horizontal distance in metres. Find:

a how far the ball travels horizontally

b how high the ball reaches mid-flight.

10 A test rocket is fired and follows a path described by $y = 0.1x(200 - x)$. The height is y metres above ground and x is the horizontal distance in metres.

a How far does the rocket travel horizontally?

b How high does the rocket reach mid-flight?

11 | 11, 12 | 12, 13

REASONING

11 Explain why the coordinates of the x-intercept and the turning point for $y = (x - 2)^2$ are the same.

12 Write down an expression for the y-intercept for these quadratics.

a $y = ax^2 + bx + c$ **b** $y = (x - a)(x - b)$

13 $y = x^2 - 2x - 15$ can also be written in the form $y = (x - 1)^2 - 16$.

a Use the second rule to state the coordinates of the turning point.

b Use the first rule to find the x-intercepts then the turning point. Check you get the same result.

c $y = x^2 - 4x - 45$ can be written in the form $y = (x - h)^2 + k$. Find the value of h and k.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 Find the rule for these graphs using intercept form. The first one is done for you.

a



$y = a(x + 1)(x - 3)$

Sub $(0, -3)$ $\quad -3 = a(0 + 1)(0 - 3)$

$-3 = a(1) \times (-3)$

$-3 = -3a$

$a = 1$

$\therefore y = (x + 1)(x - 3)$

b



c



d



e



f



g



ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Investigating non-linear relations

The graph of a quadratic relation called a parabola was thoroughly investigated in this chapter. Many other relations also produce graphs which are non-linear. Two examples are the circle and the hyperbola.

Investigating rules and graphs of circles

The general equation of a circle is given by the rule $(x-a)^2 + (y-b)^2 = r^2$ where a, b and r are constants.

Examples include: $x^2 + y^2 = 1$, $x^2 + y^2 = 25$, $(x-1)^2 + (y+3)^2 = 9$ and $(x+3)^2 + y^2 = 100$.

Use graphing software to investigate graphs of circles with the rule $x^2 + y^2 = r^2$. (Note: for some software you may have to enter the rule for a circle in two parts: $y = \sqrt{r^2 - x^2}$ and $y = -\sqrt{r^2 - x^2}$).

a Sketch the graph of the relation $x^2 + y^2 = r^2$ if r takes the following values.
i $r = 1$ **ii** $r = 2$ **iii** $r = 3$ **iv** $r = 7$

b Describe how the value of r relates to the graphs of the circles.

c Sketch by hand, the graphs of these circles.
i $x^2 + y^2 = 16$ **ii** $x^2 + y^2 = 25$ **iii** $x^2 + y^2 = 10$

d **Extension** Investigate the effect of the values of a and b in the graph of the rule of $(x-a)^2 + (y-b)^2 = r^2$. Write a brief report showing your rules and graphs and describing your conclusions.

Investigating rules and graphs of hyperbolas

The basic form of the rule for a hyperbola is given by $y = \frac{a}{x-b} + c$ where a, b and c are constants.

Examples include: $y = \frac{1}{x}$, $y = -\frac{5}{x}$, $y = \frac{3}{x} - 1$ and $y = \frac{-2}{x-3} + 2$.

Use graphing software to investigate graphs of hyperbolas with the rule $y = \frac{a}{x-b} + c$.

a Sketch the graph of the relation $y = \frac{a}{x}$ if a takes the following values.
i $a = 1$ **ii** $a = 2$ **iii** $a = -1$ **iv** $a = -2$

b Describe the key features of the graphs including the asymptotes. (Research the meaning of the word *asymptote* if you are unsure.) Also describe how changing the value of a changes the shape of your graph.

c Now investigate how changing the value of c in $y = \frac{1}{x} + c$ changes the graph. Show your graphs for your chosen values of c and describe the effect.

d Now investigate how changing the value of b in $y = \frac{1}{x-b}$ changes the graph. Show your graphs for your chosen values of b and describe the effect.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Grazing Crown land

Land along the side of rivers is usually owned by the government and is sometimes called Crown land. Farmers can often lease this land to graze their sheep or cattle.



A farmer has a permit to fence off a rectangular area of land alongside the river. She has 400 m of fencing available and does not need to fence along the river.

A given width

a Find the length of the rectangular area if the width is:
i 50 m **ii** 120 m **iii** 180 m

b Find the area of the land if the width is:
i 50 m **ii** 120 m **iii** 180 m

c Which width from part **b** above gave the most area? Explain why the area decreases for small and large values for the width.

The variable width

a Using x metres to represent the width write an expression for the length showing working.

b Write an expression for the area of the land in terms of x.

c Use your area expression from part **b** to find the area of the land if x is the following value.
i 20 **ii** 80 **iii** 160

The graph

a Using your expression from part **b** above sketch a graph of Area (A) versus x. You should find the following to help complete the graph.
i y-intercept **ii** x-intercepts **iii** axis of symmetry **iv** turning point

b What value of x gives the maximum area of land for grazing? Explain your choice and give the dimensions of the rectangular area of land.

General observations

a What do you notice about the width and the length when there is a maximum area?

b See if the same is true if the farmer had 600 m of fencing instead. Show your expressions and graph.

c **Extension** Prove your observation to parts **a** and **b** above by finding the x value that gives a maximum area using k metres of fencing. *Hint*: use $A = x(k - 2x)$.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 **a** What do you notice about the sum of these numbers?

i $1 + 3$ **ii** $1 + 3 + 5$

iii $1 + 3 + 5 + 7$ **iv** $1 + 3 + 5 + 7 + 9$

b Find the sum of the first 100 odd integers.

2 Solve these equations.

a $6x^2 = 35 - 11x$ **b** $\frac{2}{x^2} = 1 - \frac{1}{x}$ **c** $\sqrt{x-1} = \frac{2}{x-1}$

3 A projectile's height (in metres) above ground is given by the expression $t(14 - t)$ where time t is in seconds. How long is the projectile above a height of 40 m?

4 Find the quadratic rule that relates the number of balls to the term number (n) in the following pattern. If 66 balls are in the pattern, what term number is it?



5 Find the value of x in this diagram.



6 **a** A right-angled triangle's shortest side is of length x, the hypotenuse is 9 units longer than the shortest side while the other side is 1 unit longer than the shortest side. Find the side lengths of the triangle.



b The area of a right-angled triangle is 60 square units and the lengths of the two shorter sides differ by 7 units. Find the length of the hypotenuse.

7 Given $a > 0$, for what values of k does $y = a(x - h)^2 + k$ have:

a two x-intercepts? **b** one x-intercept? **c** no x-intercepts?

8 For the following equations, list the possible values of a that will give integer solutions for x.

a $x^2 + ax + 24 = 0$ **b** $x^2 + ax - 24 = 0$

9 Solve the equation $(x^2 - 3x)^2 - 16(x^2 - 3x) - 36 = 0$ for all values of x.
(*Hint:* let $a = x^2 - 3x$)

10 Solve the equation $x^4 - 10x^2 + 9 = 0$ for all values of x. (*Hint:* let $a = x^2$)

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Introduction to quadratic equations and graphs

Turning point form

$y = a(x - h)^2 + k$
turning point (h, k)
e.g. $y = 2(x + 1)^2 + 3$
TP: $(-1, 3)$
y-int: $x = 0$, $y = 2(0 + 1)^2 + 3$
$= 2(1)^2 + 3$
$= 5$

Forms

A quadratic is of the form
$y = ax^2 + bx + c$, $a \neq 0$

Translation

$y = x^2 + k$ $k > 0$, graph shifts up k units
$k < 0$, graph shifts down k units
$y = (x - h)^2$ $h > 0$, graph shifts h units right
$h < 0$, graph shift h units left

e.g.



Parabola

Basic form $y = x^2$



Turning point form
$y = a(x - h)^2 + k$



Dilation and reflection

$y = ax^2$
$a < 0$, graph is reflected in x-axis



$-1 < a < 1$:
graph appears wider than $y = x^2$ or $y = -x^2$

$a > 1$ or $a < -1$:
graph appears narrower than $y = x^2$ or $y = -x^2$
e.g.



Sketching $y = ax^2 + bx + c$ (Ext)

Find x- and y-intercepts and turning point then sketch.
e.g. $y = x^2 - 6x + 5$
y-int: $x = 0$, $y = 0^2 - 6(0) + 5$
$= 5$
x-int: $y = 0$, $0 = x^2 - 6x + 5$
$0 = (x - 1)(x - 5)$
$x - 1 = 0$ or $x - 5 = 0$
$x = 1$ or $x = 5$
Turning point: halfway between the x-intercepts:
$x = \frac{1 + 5}{2} = 3$
substitute $x = 3$ into rule
$y = 3^2 - 6(3) + 5$
$= -4$
$(3, -4)$ minimum turning point



Applications (Ext)

Define variable.
Set up equation.
Solve using Null Factor Law.
Check answer makes sense.
Answer the question in words.

Solving quadratic equations (Ext)

Rewrite equation in standard form, i.e. $ax^2 + bx + c = 0$
Factorise
Apply Null Factor Law:
If $a \times b = 0$, $a = 0$ or $b = 0$,
Solve remaining equation
e.g. $x^2 + 5x = 0$
$x(x + 5) = 0$
$x = 0$ or $x + 5 = 0$
$x = 0$ or $x = -5$
e.g. $x^2 - 12 = 4x$
$x^2 - 4x - 12 = 0$
$(x - 6)(x + 2) = 0$
$x - 6 = 0$ or $x + 2 = 0$
$x = 6$ or $x = -2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

10A Ext **1** (1, 3) is a point on a curve with which equation?

A $y = x^2$ **B** $y = (x-3)^2$ **C** $y = x^2 + 2x - 3$
D $y = x^2 + 2$ **E** $y = 6 - x^2$

10A Ext **2** The solution(s) to $2x(x-3) = 0$ is/are:

A $x = -3$ **B** $x = 0$ or $x = 3$ **C** $x = 2$ or $x = 3$
D $x = 0$ or $x = -3$ **E** $x = 0$

10A Ext **3** The quadratic equation $x^2 = 7x - 12$ in standard form is:

A $x^2 - 7x - 12 = 0$ **B** $-x^2 + 7x + 12 = 0$ **C** $x^2 - 7x + 12 = 0$
D $x^2 + 7x - 12 = 0$ **E** $x^2 + 7x + 12 = 0$

10B Ext **4** The solution(s) to $x(x+2) = 2x + 9$ are:

A $x = -3$ or $x = 3$ **B** $x = 0$ or $x = -2$ **C** $x = 3$
D $x = 9$ or $x = -1$ **E** $x = 9$ or $x = 0$

The following applies to Questions **5** and **6**.
The height, h metres, of a toy rocket above ground t seconds after launch is given by $h = 6t - t^2$.

10D Ext **5** The rocket returns to ground level after:

A 5 seconds **B** 3 seconds **C** 12 seconds
D 6 seconds **E** 8 seconds

10H Ext **6** The rocket reaches its maximum height after:

A 6 seconds **B** 3 seconds **C** 10 seconds
D 4 seconds **E** 9 seconds

10G **7** The turning point of $y = (x-2)^2 - 4$ is:

A a maximum at (2, 4)
B a minimum at (–2, 4)
C a maximum at (2, 4)
D a minimum at (–2, –4)
E a minimum at (2, –4).

10G **8** The transformation of the graph of $y = x^2$ to $y = x^2 - 2$ is described by:

A a translation of 2 units to the left
B a translation of 2 units to the right
C a translation of 2 units down
D a translation of 2 units up
E a translation of 2 units right and 2 units down.

10F **9** Compared to $y = x^2$, the narrowest graph is:

A $y = 5x^2$ **B** $y = 0.2x^2$ **C** $y = 2x^2$ **D** $y = \frac{1}{2}x^2$ **E** $y = 3.5x^2$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G **10** The graph of $y = -(x-3)^2$ is:

A



B



C



D



E



Short-answer questions

10E **1** Consider the quadratic $y = x^2 - 2x - 3$.

a Complete this table of values for the equation.

x	–3	–2	–1	0	1	2	3
y							

b Plot the points in part **a** on a Cartesian plane and join in a smooth curve.

10A Ext **2** Use the Null Factor Law to solve the following equations.

a $x(x+2) = 0$ **b** $3x(x-4) = 0$ **c** $(x+3)(x-7) = 0$

d $(x-2)(2x+4) = 0$ **e** $(x+1)(5x-2) = 0$ **f** $(2x-1)(3x-4) = 0$

10B/C Ext **3** Solve the following quadratic equations by first factorising.

a $x^2 + 3x = 0$ **b** $2x^2 - 8x = 0$ **c** $x^2 = 25$

d $x^2 = 81$ **e** $5x^2 = 20$ **f** $3x^2 - 30 = 0$

g $x^2 + 10x + 21 = 0$ **h** $x^2 - 3x - 40 = 0$ **i** $x^2 - 8x + 16 = 0$

10C Ext **4** Write the following quadratic equations in standard form and solve for x.

a $x^2 = 5x$ **b** $3x^2 = 18x$ **c** $x^2 + 12 = -8x$

d $2x + 15 = x^2$ **e** $x^2 + 15 = 8x$ **f** $4 - x^2 = 3x$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

10D Ext

5 Set up and solve a quadratic equation to determine the value of x that gives the specified area of the shapes below.

a



$A = 80$ units^2

b



$A = 30$ units^2

10E

6 For the following graphs state:

i the axis of symmetry **ii** the turning point and its type

a



b



10F/G

7 Match the following quadratic rules with their graphs.

$y = x^2 - 4$, $y = 2x^2$, $y = (x+1)^2$, $y = (x-3)^2$, $y = -x^2 + 2$

a



b



c



d



e



10G

8 Sketch the following graphs labelling the turning point and y-intercept.

a $y = x^2 + 2$ **b** $y = -x^2 - 5$ **c** $y = (x+2)^2$

d $y = -(x-3)^2$ **e** $y = (x-1)^2 + 3$ **f** $y = 2(x+2)^2 - 4$

10G

9 State the transformations that take $y = x^2$ to each of the graphs in Question **8**.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

10H

Ext

10 Sketch the following graphs labelling the y-intercept, turning point and x-intercepts.

a $y = x^2 - 8x + 12$

b $y = x^2 + 10x + 16$

c $y = x^2 + 2x - 15$

d $y = x^2 + 4x - 5$

Extended-response questions

Ext

1 A sail of a yacht is in the shape of a right-angled triangle. It has a base length of $2x$ metres and its height is 5 metres more than half its base.

a Write an expression for the height of the sail.

b Give an expression for the area of the sail in expanded form.

c If the area of the sail is 14 m^2, find the value of x.

d Hence, state the dimensions of the sail.

Using quadratic relations, we can find the area of sails with base lengths and height in a given ratio.

Ext

2 Connor and Sam are playing in the park with toy rockets they have made. They each launch their rockets at the same time to see whose is better.

a The path of Sam's rocket is modelled by the equation $h = 12t - 2t^2$, where h is the height of the rocket in metres after t seconds.

i Find the axis intercepts.

ii Find the turning point.

iii Sketch a graph of the height of Sam's rocket over time.

b The path of Connor's rocket is modelled by the equation $h = -(t - 4)^2 + 16$ where h is the height of the rocket in metres after t seconds.

i Find the h-intercept (i.e. $t = 0$).

ii State the turning point.

iii Use the answers from parts **b i** and **ii** to state the two t-intercepts.

iv Sketch a graph of the height of Connor's rocket over time.

c **i** Whose rocket was in the air longest?

ii Whose rocket reached the greatest height and by how much?

iii How high was Sam's rocket when Connor's was at its maximum height?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Semester review 2

Indices and surds

Multiple-choice questions

1 $3a^2b^3 \times 4ab^2$ is equivalent to:

A $12a^2b^6$ **B** $7a^3b^5$ **C** $12a^3b^5$ **D** $12a^4b^5$ **E** $7a^2b^6$

2 $\left(\frac{2x}{5}\right)^3$ is equivalent to:

A $\frac{6x^3}{5}$ **B** $\frac{8x^3}{125}$ **C** $\frac{2x^3}{5}$ **D** $\frac{2x^4}{15}$ **E** $\frac{2x^3}{125}$

3 4^{-2} can be expressed as:

A $\frac{1}{4^{-2}}$ **B** $\frac{1}{8}$ **C** -16 **D** $\frac{1}{16}$ **E** -8

4 $3x^{-4}$ written with positive indices is:

A $-3x^4$ **B** $\frac{1}{3x^4}$ **C** $-\frac{3}{x^4}$ **D** $\frac{1}{3x^{-4}}$ **E** $\frac{3}{x^4}$

5 0.00371 in scientific notation is:

A 0.371×10^{-3} **B** 3.7×10^{-2} **C** 3.71×10^{-3}
D 3.71×10^3 **E** 371×10^3

Short-answer questions

1 Use index laws to simplify the following.

a $\frac{9a^6b^3}{18a^4b^2}$ **b** $\frac{(-3x^4y^2)^2 \times 6xy^2}{27x^6y}$ **c** $(2x^2)^3 - 3x^0 + (5x)^0$

2 Write each of the following using positive indices and simplify.

a $\frac{5}{m^{-2}}$ **b** $\frac{4a^6b^{-4}}{6a^{-2}b}$ **c** $3(x^{\frac{1}{2}})^3y^{-\frac{1}{3}} \times x^{\frac{1}{2}}y^{-\frac{2}{3}}$

3 Convert these numbers to the units given in brackets. Write your answer in scientific notation using three significant figures.

a 30.71 g (kg) **b** 4236 tonnes (kg)
c 3.4 hours (seconds) **d** 235 nanoseconds (seconds)

4 Simplify the following.

a $144^{\frac{1}{2}}$ **b** $27^{\frac{1}{3}}$ **c** $2\sqrt{3} + 3\sqrt{5} + 4\sqrt{5}$ **d** $\sqrt{35} \div \sqrt{5}$

Extended-response question

The average human body contains about 74 billion cells.

a Write this number of cells:

i in decimal form **ii** in scientific notation

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b If the population of a particular city is 2.521×10^6, how many human cells are there in the city? Give your answer in scientific notation correct to three significant figures.

c If the average human weighs 64.5 kilograms, what is the average mass of one cell in grams? Give your answer in scientific notation correct to three significant figures.

Geometry

Multiple-choice questions

1 The supplementary angle to 55° is:

A 55° **B** 35° **C** 125° **D** 135° **E** 70°

2 A quadrilateral with all four sides equal and opposite sides parallel is best described by a:

A parallelogram **B** rhombus **C** rectangle
D trapezium **E** kite

3 The size of the interior angle in a regular pentagon is:

A 108° **B** 120° **C** 96° **D** 28° **E** 115°

4 The test that proves congruence in these two triangles is:

A SAS **B** RHS **C** AAA
D SSS **E** AAS



5 What is the scale factor that enlarges shape 1 to shape 2 in these similar figures, and what is the value of x?

A 2 and $x = 8$
B 2.5 and $x = 7.5$
C 3.33 and $x = 13.33$
D 2.5 and $x = 12.5$
E 2 and $x = 6$



Short-answer questions

1 Find the value of each pronumeral in the following.

a



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

2 Find the value of $\angle ABC$ by adding a third parallel line.



3 Prove $\Delta ABC \equiv \Delta ADC$.



4 For this pair of triangles:

a Give a reason (SSS, SAS, AAA or RHS) why the two triangles are similar.

b Find the value of x.



Extended-response question

A vertical wall is being supported by a piece of timber that touches the ground 10 metres from the base of the wall. A vertical metal support 4.5 m high is placed under the timber support 4 m from the wall.

a Prove $\Delta ABD \,|||\, \Delta ECD$.

b Find how far the timber reaches up the wall.

c How far above the ground is the point halfway along the timber support?

d The vertical metal support is moved so that the timber support is able to reach one metre higher up the wall. If the piece of timber now touches the ground 9.2 m from the wall, find how far the metal support is from the wall. Give your answer correct to one decimal place.



Algebraic techniques

Multiple-choice questions

1 The expanded form of $(x + 4)(3x - 2)$ is:

A $3x^2 + 12x - 8$ **B** $4x^2 + 14x - 8$ **C** $3x^2 + 12x - 10$

D $3x^2 - 8$ **E** $3x^2 + 10x - 8$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 $2(x+2y)-x(x+2y)$ factorises to:

A $2x(x+2y)$ **B** $(x+2y)^2(2-x)$ **C** $(2+x)(x+2y)$

D $(x+2y)(2-x)$ **E** $(x+2y)(2-x^2-2xy)$

3 $x^2-2x-24$ in factorised form is:

A $(x-2)(x+12)$ **B** $(x-6)(x+4)$ **C** $(x-8)(x+3)$

D $(x+6)(x-4)$ **E** $(x-6)(x-4)$

4 $\dfrac{3x+6}{(x-2)(x-4)} \times \dfrac{x^2-4}{(x+2)^2}$ is equivalent to:

A $\dfrac{3}{x-4}$ **B** $\dfrac{3(x-2)}{(x-4)(x+2)}$ **C** $\dfrac{3x-2}{(x+1)^2}$

D $\dfrac{3}{(x+2)(x-2)}$ **E** $\dfrac{3x^2}{(x-2)(x+2)}$

5 $\dfrac{7}{(x+1)^2}-\dfrac{4}{x+1}$ simplifies to:

A $\dfrac{3x+1}{(x+1)^2}$ **B** $\dfrac{6-4x}{(x+1)^2}$ **C** $\dfrac{-9}{(x+1)^2}$ **D** $\dfrac{3-4x}{(x+1)^2}$ **E** $\dfrac{11-4x}{(x+1)^2}$

Short-answer questions

1 Find the area of the following shapes in expanded form.

a



b



c



2 Factorise each of the following fully.

a $8ab+2a^2b$ **b** $9m^2-25$ **c** $3b^2-48$

d $(a+7)^2-9$ **e** x^2+6x+9 **f** $x^2+8x-20$

g $2x^2-16x+30$ **h** $2x^2-11x+12$ **i** $6x^2+5x-4$

3 Factorise the following by grouping.

a $x^2-3x-x+3$ **b** $2x^2-10-5x+4x$

4 **a** Simplify these algebraic fractions.

i $\dfrac{3x+24}{2x+16}$ **ii** $\dfrac{12}{x^2-9} \div \dfrac{3}{x-3}$ **iii** $\dfrac{x+3}{2}+\dfrac{3x}{7}$

iv $\dfrac{2}{x}-\dfrac{5}{3x}$ **v** $\dfrac{7}{x+1}+\dfrac{4}{x-2}$ **vi** $\dfrac{5}{x-5}-\dfrac{3}{x+2}$

b Solve these equations involving algebraic fractions.

i $\dfrac{5}{2x}+\dfrac{1}{3x}=2$ **ii** $\dfrac{4}{x-5}=\dfrac{2}{x+3}$

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response question

A rectangular room 10 metres long and 8 metres wide has a rectangular rug in the middle of it that leaves a border, x metres wide, all the way around it as shown.



a Write expressions for the length and the width of the rug.

b Write an expression for the area of the rug in expanded form.

c What is the area of the rug when $x = 1$?

d Fully factorise your expression in part **b** by first removing the common factor.

e What happens when $x = 4$?

Probability and statistics

Multiple-choice questions

1 The probability of not rolling a number less than three on a normal six-sided die is:

A $\frac{1}{3}$ **B** 4 **C** $\frac{1}{2}$ **D** $\frac{2}{3}$ **E** 3

2 From the two-way table, $\Pr(A \cap B)$ is:

A $\frac{1}{5}$ **B** 4 **C** $\frac{9}{20}$ **D** $\frac{1}{4}$ **E** 16

	A	A′	Total
B		7	
B′	5		
Total		11	20

3 In the selection of 40 marbles, 28 were blue. The experimental probability of the next one selected being blue is:

A 0.28 **B** 0.4 **C** 0.7 **D** 0.54 **E** 0.75

4 The median, mean and range of the data set 12 3 1 6 10 1 5 18 11 15 are, respectively:

A 5.5, 8.2, 1–18 **B** 8, 8.2, 17 **C** 5.5, 8, 17
D 8, 8.2, 1–18 **E** 8, 74.5, 18

5 The interquartile range of the data in the box plot shown is:



A 10 **B** 27 **C** 13 **D** 30 **E** 17

Short-answer questions

1 In a survey of 30 people, 18 people drink coffee, 14 people drink tea and 8 people drink both. Let C be the set of people who drink coffee and T the set of people who drink tea.

a Construct a Venn diagram for the survey results.

b Find:

i $n(C \cup T)$ **ii** $n(T')$

c If one of the 30 people was randomly selected, find:

i Pr(drinks neither coffee nor tea) **ii** Pr(drinks coffee only)

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

2 Two ice creams are randomly selected without replacement from a box containing one vanilla (V), two strawberry (S) and one chocolate (C) flavoured ice creams.

- **a** Draw a tree diagram to show each of the possible outcomes.
- **b** What is the probability of selecting:
  - **i** a vanilla and a strawberry flavoured ice cream?
  - **ii** two strawberry flavoured ice creams?
  - **iii** no vanilla flavoured ice cream?

3 The data below shows the number of aces served by a player in each of their grand slam tennis matches for the year.

15 22 11 17 25 25 12 31 26 18 32 11 25 32 13 10

- **a** Construct a stem-and-leaf plot for the data.
- **b** From the stem-and-leaf plot, find the mode and median number of aces.
- **c** Is the data symmetrical or skewed?

4 The frequency table shows the number of visitors, in intervals of fifty, to a theme park each day in April.

- **a** Complete the frequency table shown. Round to one decimal place where necessary.
- **b** Construct a frequency histogram.
- **c** **i** How many days were there fewer than 100 visitors?
  - **ii** What percentage of days had between 50 and 200 visitors?

Class interval	Frequency	Percentage frequency
0–	2	
50–	4	
100–	5	
150–	9	
200–		
250–	3	
Total	30	

Extended-response question

A game at the school fair involves randomly selecting a green ball and a red ball each numbered 1, 2 or 3.

- **a** List the outcomes in a table.
- **b** What is the probability of getting an odd and an even number?
- **c** Participants win $1 when they draw each ball showing the same number.
  - **i** What is the probability of winning $1?
  - **ii** If someone wins six times, how many games are they likely to have played?
- **d** The ages of those playing the game in the first hour are recorded and are shown below.

12 16 7 24 28 9 11 17 18 18 37 9 40 16 32 42 14

  - **i** Draw a box plot to represent the data.
  - **ii** Twenty-five per cent of the participants are below what age?
  - **iii** If this data is used as a model for the 120 participants throughout the day, how many would be expected to be aged less than 30?

ISBN 978-1-107-57007-8
© Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Introduction to quadratic equations and graphs

Multiple-choice questions

1 The solution(s) to $3x(x + 5) = 0$ is/are:

A $x = -5$ **B** $x = 0$ or $x = -5$ **C** $x = 3$ or $x = 5$
D $x = 5$ **E** $x = 0$ or $x = 5$

2 $x^2 = 3x - 2$ is the same as the equation:

A $x^2 + 3x - 2 = 0$ **B** $x^2 - 3x + 2 = 0$ **C** $x^2 - 3x - 2 = 0$
D $-x^2 + 3x + 2 = 0$ **E** $x^2 + 3x + 2 = 0$

3 The *incorrect* statement about the graph of $y = 2x^2$ is:

A the graph is the shape of a parabola
B the point $(-2, 8)$ is on the graph
C its turning point is at $(0, 0)$
D it has a minimum turning point
E the graph is wider than the graph of $y = x^2$

4 The type and coordinates of the turning point of the graph of $y = -(x + 3)^2 + 2$ are:

A a minimum at $(3, 2)$
B a maximum at $(3, 2)$
C a maximum at $(-3, 2)$
D a minimum at $(-3, 2)$
E a minimum at $(3, -2)$

5 The graph shown has the equation:

A $y = 4x^2$
B $y = x^2 + 4$
C $y = (x + 2)^2$
D $y = x^2 + 2$
E $y = (x - 2)^2$



Short-answer questions

1 Solve the following quadratic equations.

a $(x + 5)(x - 3) = 0$ **b** $(2x - 1)(3x + 5) = 0$
c $4x^2 + 8x = 0$ **d** $5x^2 = 45$
e $x^2 - 9x + 14 = 0$ **f** $8x = -x^2 - 16$

2 The length of a rectangular swimming pool is x m and its width is 7 m less than its length. If the area occupied by the pool is 120 m^2, solve an appropriate equation to find the dimensions of the pool.

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 Sketch the following graphs showing the y-intercept and turning point and state the transformations that have taken place from the graph of $y = x^2$.

a $y = x^2 + 3$ **b** $y = -(x + 4)^2$ **c** $y = (x - 2)^2 + 5$

4 Consider the quadratic relation $y = x^2 - 4x - 12$.

a Find the y-intercept.

b Factorise the relation and find the x-intercepts.

c Find the coordinates of the turning point.

d Sketch the graph.

Extended-response question

The flight path of a soccer ball kicked upwards from the ground is given by the equation $y = 120x - 20x^2$, where y is the height of the ball above the ground in centimetres at any time, x seconds.

a Find the x-intercepts to determine when the ball lands on the ground.

b Find the coordinates of the turning point and state:

i the maximum height reached by the ball

ii after how many seconds the ball reaches this maximum height.

c At what times was the ball at a height of 160 cm?

d Sketch a graph of the path of the ball until it returns to the ground.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Answers

Working with unfamiliar problems

Working with unfamiliar problems: Part 1

1 **a** 999 999 998 000 000 001
b 99 999 999 990 000 000 001

2 31 lockers open
1, 4, 9, 16, 25, 36, 49, 64, 81, 100, 121, 144, 169, 196, 225, 256, 289, 324, 361, 400, 441, 484, 529, 576, 625, 676, 729, 784, 841, 900, 961

3 61

4 12, 23, 34, 45, 56, 67, 78 and 89

5 85 km; Adina: 20 km, 53.13° ; Birubi: 65 km, 306.87°

6 $\frac{1}{3}$ **7** Approximately 70 days **8** Answers will vary

9 20% **10** $x = 15$ **11** 48 **12** 72

13 6 m, 11 m

14 **a** One revolution of a spiral
b 6.18 m
c 75.82 m

15 49 **16** 254 **17** $\frac{x}{y}$

Working with unfamiliar problems: Part 2

1 $x = 1$ and $y = 3$

2 Any prism with a quadrilateral cross section (e.g. cube, rectangular prism, trapezoidal prism), heptagonal pyramid, truncated rectangular pyramid.

3 $x = 20$

4 $2n - 1 + 2m - 1 = 2(n + m - 1)$ which is a multiple of two and is therefore even

5 $xy = 24$ **6** 98° **7** $n + 2\sqrt{n} + 1$

8 **a** 64 cm^2, 32 cm^2, 16 cm^2, 8 cm^2, 4 cm^2
$2^6, 2^5, 2^4, 2^3, 2^2$
b $2^1, 2^0, 2^{-1}, 2^{-2}, 2^{-3}$; 1 cm^2, $\frac{1}{8}$ cm^2
c $A = 2^{7-n}$; $\frac{1}{256}$

9 7 : 5 : 3 **10** 2

11 Sam 36 years, Noah 12 years **12** 20 cm^2

13 **a** 3^{x-1} **b** 0

14 **a** 96 cm^3 **b** $24\frac{1}{12}$ cm^2

15 7 or –4 **16** $2\frac{1}{2}$ hours, $\frac{3}{4}$ hour **17** 5 : 2

Chapter 1

Exercise 1A

1 **a** 1, 2, 4, 8, 16 **b** 1, 2, 4, 7, 8, 14, 28, 56
c HCF = 8 **d** 3, 6, 9, 12, 15, 18, 21
e 5, 10, 15, 20, 25, 30 **f** LCM = 15
g 2, 3, 5, 7, 11, 13, 17, 19, 23, 29
h 83, 89, 97, 101, 103, 107, 109

2 **a** 121 **b** 225 **c** 12 **d** 20
e 27 **f** 125 **g** 2 **h** 4

3 **a** -5 **b** -8 **c** -1 **d** 9
e -1 **f** -16 **g** 15 **h** 9
i -6 **j** -84 **k** 22 **l** 42
m -9 **n** -6 **o** 10 **p** 19

4 **a** 2 **b** 2 **c** 10 **d** 16
e -9 **f** -3 **g** -4 **h** 10
i -11 **j** 2 **k** -3 **l** 4
m -23 **n** 10 **o** 0 **p** 3
q -9 **r** 7 **s** -1 **t** 4

5 **a** 28 **b** 24 **c** 187 **d** 30

6 **a** 4 **b** 5 **c** 1 **d** 23

7 **a** 4 **b** 23 **c** -3 **d** 2
e -2 **f** -18 **g** -6 **h** -1 **i** 1

8 **a** -2 **b** -38 **c** -8 **d** 27 **e** 1
f 24 **g** 21 **h** 0

9 **a** $-2 \times [11 + (-2)] = -18$
b $[-6 + (-4)] \div 2 = -5$
c $[2 - 5] \times (-2) = 6$
d $-10 \div [3 + (-5)] = 5$
e $3 - [(-2) + 4] \times 3 = -3$
f $[(-2)^2 + 4] \div (-2) = -2^2$

10 4

11 252 days

12 **a** 7 and -2 **b** -5 and 2

13 8

14 **a** **i** 16 **ii** 16
b $a = \pm 4$
c $a = 3$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d the square of a negative number has negative signs occurring in pairs and will create a positive answer
e -3
f as the squaring of any number produces a positive answer
g **i** -4 **ii** -125 **iii** -9 **iv** -16
h no
i yes
j Prime numbers have only two factors – itself and one, therefore the only common factor for any pair of prime numbers is 1.
k Again as there are only two factors of any prime, the LCM must be the multiple of primes.

15 **a** False **b** False **c** True **d** True
e False **f** True

16 **a** **i** $1 + 2 + 3 = 6$
ii $28\ (1 + 2 + 4 + 7 + 14 = 28)$
iii $1 + 2 + 4 + 8 + 16 + 31 + 62 + 124 + 248 = 496$
b **i** 

ii 28, 36
c **i** 0, 1, 1, 2, 3, 5, 8, 13, 21, 34
ii $-21, 13, -8, 5, -3, 2, -1, 1, 0, 1 \ldots$
$\therefore -21, -8, -3, -1$

Exercise 1B

1 **a** 40 **b** 270 **c** 7.9 **d** 0.04
2 **a** 32 100 **b** 432 **c** 5.89 **d** 0.443
e 0.00197
3 **a** 60 **b** 57.375 **c** 2.625
4 **a** 17.96 **b** 11.08 **c** 72.99 **d** 47.86
e 63.93 **f** 23.81 **g** 804.53 **h** 500.57
i 821.27 **j** 5810.25 **k** 1005.00 **l** 2650.00
5 **a** 7 **b** 73 **c** 130 **d** 36 200
6 **a** 0.333 **b** 0.286 **c** 1.182 **d** 13.793
7 **a** 2400 **b** 35 000 **c** 0.060 **d** 34
e 110 000 **f** 0.0025 **g** 2.1 **h** 0.71
8 **a** 30 000 **b** 200 **c** 0.05 **d** 0.0006
9 **a** 3600, 3693 **b** 760, 759.4
c 4000, 4127.16 **d** 3000, 3523.78
e 0, 0.72216 **f** 4, 0.716245
g 0.12, 0.1186 **h** 0.02, 0.02254
i 10, 8.4375 **j** 1600, 1683.789156
k 0.08, 0.074957... **l** 11, 10.25538 ...
10 **a** A: 54.3, B: 53.8, 0.5 **b** A: 54.28, B: 53.79, 0.49
c A: 54, B: 54, 0 **d** A: 50, B: 50, 0
11 **a** each to 1 significant figure
b each to 2 significant figures
c each to the nearest integer
12 8.33 m
13 0.143 tonnes
14 2.14999 is closer to 2.1 correct to 1 decimal place $\therefore$ round down
15 as magnesium in this case would be zero if rounded to two decimal places rather than 2 significant figures
16 **a** **i** 50 **ii** 624
b 50
c 600
d The addition is the same as the original but the multiplication is lower ($20 \times 30 < 24 \times 26$)
17 **a** 0.18181818
b **i** 8 **ii** 1 **iii** 8
c 0.1428571428571
d **i** 4 **ii** 2 **iii** 8
e Not possible

Exercise 1C

1 **a** $1\frac{2}{5}$ **b** $4\frac{1}{3}$ **c** $4\frac{4}{11}$ **d** $6\frac{8}{53}$

2 **a** $\frac{11}{7}$ **b** $\frac{16}{3}$ **c** $\frac{19}{2}$ **d** $\frac{238}{13}$

3 **a** $\frac{2}{5}$ **b** $\frac{4}{29}$ **c** $4\frac{1}{6}$ **d** $-72\frac{1}{8}$

4 **a** 9 **b** 24 **c** 21 **d** 35 **e** 3
f 7 **g** 10 **h** 6

5 **a** 2.75 **b** 0.35 **c** 3.4 **d** 1.875
e 2.625 **f** 3.8 **g** 2.3125 **h** 0.21875

6 **a** $0.\overline{27}$ **b** $0.\dot{7}$ **c** $1.\overline{285714}$ **d** $0.41\dot{6}$
e $1.\dot{1}$ **f** $3.8\dot{3}$ **g** $7.2\dot{6}$ **h** $2.\overline{63}$

7 **a** $\frac{7}{20}$ **b** $\frac{3}{50}$ **c** $3\frac{7}{10}$ **d** $\frac{14}{25}$
e $1\frac{7}{100}$ **f** $\frac{3}{40}$ **g** $3\frac{8}{25}$ **h** $7\frac{3}{8}$
i $2\frac{1}{200}$ **j** $10\frac{11}{250}$ **k** $6\frac{9}{20}$ **l** $2\frac{101}{1000}$

8 **a** $\frac{5}{6}$ **b** $\frac{13}{20}$ **c** $\frac{7}{10}$ **d** $\frac{5}{12}$
e $\frac{7}{16}$ **f** $\frac{11}{14}$ **g** $\frac{19}{30}$ **h** $\frac{11}{27}$

9 **a** $\frac{5}{12}, \frac{7}{18}, \frac{3}{8}$ **b** $\frac{5}{24}, \frac{3}{16}, \frac{1}{6}$ **c** $\frac{7}{12}, \frac{23}{40}, \frac{8}{15}$

10 **a** $\frac{9}{20}$ **b** $\frac{3}{20}$ **c** $\frac{32}{45}$ **d** $\frac{23}{75}$

11 **a** $\frac{11}{6}, \frac{7}{3}$ **b** $\frac{2}{5}, \frac{2}{15}$ **c** $\frac{11}{12}, \frac{12}{12}$ **d** $\frac{5}{7}, \frac{11}{14}$

12 Weather forecast

13 **a** $\frac{3}{5}$ **b** $\frac{5}{9}$ **c** $\frac{8}{13}$ **d** $\frac{23}{31}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 **a** 31, 32 **b** 36, 37, 38, . . . , 55 **c** 4, 5
d 2, 3 **e** 43, 44, 45, . . . 55 **f** 4, 5, 6

15 $\frac{ac+b}{c}$

16 **a** yes, e.g. $\frac{7}{14}=\frac{1}{2}$ and 7 is prime
b no as **a** and **b** will have no common factors other than one
c no as then a factor of 2 can be used to cancel
d yes, e.g. $\frac{5}{7}$

17 **a** $\frac{8}{9}$ **b** $1\frac{2}{9}$ **c** $\frac{9}{11}$ **d** $3\frac{43}{99}$
e $9\frac{25}{33}$ **f** $\frac{44}{333}$ **g** $2\frac{917}{999}$ **h** $13\frac{8125}{9999}$

Exercise 1D

1 **a** 6 **b** 63 **c** 65 **d** 30 **e** 4
f 33 **g** 60 **h** 87

2 **a** $\frac{7}{3}$ **b** $\frac{39}{5}$ **c** $\frac{41}{4}$ **d** $\frac{137}{6}$

3 **a** $\frac{9}{6}+\frac{8}{6}=\frac{17}{6}$ **b** $\frac{4}{3}-\frac{2}{5}=\frac{20}{15}-\frac{6}{15}=\frac{14}{15}$
c $\frac{5}{3}\times\frac{7}{2}=\frac{35}{6}$

4 **a** $\frac{3}{5}$ **b** $\frac{4}{9}$ **c** $1\frac{2}{7}$ **d** $\frac{19}{20}$
e $\frac{19}{21}$ **f** $1\frac{7}{40}$ **g** $\frac{7}{10}$ **h** $\frac{17}{27}$

5 **a** 5 **b** $3\frac{2}{5}$ **c** $5\frac{1}{7}$ **d** $6\frac{11}{15}$
e $7\frac{17}{63}$ **f** $17\frac{13}{16}$

6 **a** $\frac{2}{5}$ **b** $\frac{1}{45}$ **c** $\frac{11}{20}$ **d** $\frac{1}{10}$
e $\frac{1}{18}$ **f** $\frac{1}{8}$ **g** $\frac{13}{72}$ **h** $\frac{5}{48}$

7 **a** $1\frac{1}{2}$ **b** $\frac{3}{4}$ **c** $\frac{13}{20}$ **d** $\frac{29}{40}$
e $\frac{5}{6}$ **f** $1\frac{16}{77}$

8 **a** $\frac{6}{35}$ **b** $\frac{1}{2}$ **c** $\frac{1}{12}$ **d** $\frac{4}{9}$
e $4\frac{1}{2}$ **f** $5\frac{1}{3}$ **g** $7\frac{1}{2}$ **h** 5
i 15 **j** 26 **k** $\frac{2}{3}$ **l** $\frac{5}{6}$
m $2\frac{1}{4}$ **n** $3\frac{1}{2}$ **o** 6 **p** $1\frac{1}{3}$

9 **a** $\frac{1}{3}$ **b** $\frac{7}{5}$ **c** 8 **d** $\frac{9}{13}$

10 **a** $\frac{20}{21}$ **b** $1\frac{1}{8}$ **c** $\frac{45}{56}$ **d** $\frac{27}{28}$
e $1\frac{1}{3}$ **f** $1\frac{1}{2}$ **g** 6 **h** $\frac{7}{8}$
i 18 **j** 9 **k** 16 **l** 64
m $\frac{1}{10}$ **n** $\frac{1}{12}$ **o** $\frac{4}{27}$ **p** $3\frac{1}{3}$
q 4 **r** $\frac{1}{6}$ **s** $1\frac{1}{2}$ **t** $\frac{7}{8}$

11 **a** $\frac{2}{7}$ **b** $\frac{8}{15}$ **c** 16 **d** $\frac{66}{85}$
e $2\frac{10}{21}$ **f** $\frac{3}{13}$

12 $\frac{7}{8}$ tonnes

13 $5\frac{29}{56}$ tonnes

14 $\frac{5}{12}$ hours (25 min)

15 7 truckloads

16 3 hours

17 $\frac{5}{6}$, problem is the use of negatives in the method since $\frac{1}{3}<\frac{1}{2}$

18 **a** $\frac{b}{a}$ **b** $\frac{c}{ac+b}$

19 **a** 1 **b** $\frac{a^2}{b^2}$ **c** 1 **d** $\frac{c}{a}$ **e** a
f $\frac{c}{b}$

20 **a** $-\frac{2}{3}$ **b** $\frac{5}{4}$ **c** $\frac{83}{10}$ **d** 1
e $\frac{50}{31}$ **f** $\frac{81}{400}$ **g** $\frac{329}{144}$ **h** $\frac{969}{100}$
i $\frac{583}{144}$ **j** $\frac{5}{11}$

Exercise 1E

1 **a** 4 **b** 12 **c** 24 **d** 72 **e** 3
f 9 **g** 11 **h** 3

2 **a** 9 **b** $\frac{4}{9}$ **c** $\frac{5}{9}$ **d** 8
e 10

3 **a** **i** 240 km **ii** 40 km **iii** 520 km
b **i** 5 h **ii** $4\frac{1}{2}$ h **iii** 15 min

4 **a** \$4 **b** \$3 **c** \$2.50

5 **a** 1 : 5 **b** 2 : 5 **c** 3 : 2 **d** 4 : 3
e 9 : 20 **f** 45 : 28 **g** 3 : 14 **h** 22 : 39
i 1 : 3 **j** 1 : 5 **k** 20 : 7 **l** 10 : 3

6 **a** 1 : 10 **b** 1 : 5 **c** 2 : 3 **d** 7 : 8
e 25 : 4 **f** 1 : 4 **g** 1 : 4 **h** 24 : 5
i 4 : 20 : 5 **j** 4 : 3 : 10 **k** 5 : 72 **l** 3 : 10 : 40

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 a \$200, \$300 b \$150, \$350
c \$250, \$250 d \$175, \$325

8 126 g

9 a \$10, \$20, \$40 b \$14, \$49, \$7
c \$40, \$25, \$5

10 a 15 km/h b 2000 rev/min c 45 strokes/min
d 14 m/s e 8 mL/h f 92 beats/min

11 a 55 km b $16\frac{1}{2}$ km c $5\frac{1}{2}$ km

12 a 3 kg deal b Red delicious c 2.4 L
d 0.7 GB

13 a coffee A: \$3.60, coffee B: \$3.90.
Therefore, coffee A is the best buy.
b pasta A: \$1.25, pasta B: \$0.94.
Therefore, pasta B is the best buy.
c cereal A: \$0.37, cereal B: \$0.40.
Therefore, cereal A is the best buy.

14 120

15 \$3000, \$1200, \$1800 respectively

16 \$15.90

17 108 L

18 \$3600, \$1200, \$4800 respectively

19 \$1.62

20 1 : 4

21 36°, 72°, 108°, 144°

22 Find cost per kilogram or number of grams per dollar.
Cereal A is the best buy.

23 a False b False c True d True

24 a $a + b$ b $\frac{a}{a+b}$ c $\frac{b}{a+b}$

25 a i 100 mL ii 200 mL
b i 250 mL ii 270 mL
c i 300 mL ii 1 : 4
d i 1 : 3 ii 7 : 19 iii 26 : 97 iv 21 : 52
e jugs 3 and 4

Exercise 1F

1 a $\frac{3}{100}$ b $\frac{11}{100}$ c $\frac{7}{20}$ d $\frac{2}{25}$

2 a 0.04 b 0.23 c 0.86 d 0.463

3 a 50% b 60% c 25% d 90%
e 75% f 50% g 20% h $12\frac{1}{2}$%

4 a 34% b 40% c 6% d 70%
e 100% f 132% g 109% h 310%

5 a 0.67 b 0.3 c 2.5 d 0.08
e 0.0475 f 0.10625 g 0.304 h 0.4425

6 a $\frac{67}{100}$ b $\frac{3}{10}$ c $2\frac{1}{2}$ d $\frac{2}{25}$
e $\frac{19}{400}$ f $\frac{17}{160}$ g $\frac{38}{125}$ h $\frac{177}{400}$

7

Percentage	Fraction	Decimal
10%	$\frac{1}{10}$	0.1
50%	$\frac{1}{2}$	0.5
5%	$\frac{1}{20}$	0.05
25%	$\frac{1}{4}$	0.25
20%	$\frac{1}{5}$	0.2
12.5%	$\frac{1}{8}$	0.125
1%	$\frac{1}{100}$	0.01
$11.\dot{1}$%	$\frac{1}{9}$	$0.\dot{1}$
$22.\dot{2}$%	$\frac{2}{9}$	$0.\dot{2}$
75%	$\frac{3}{4}$	0.75
15%	$\frac{3}{20}$	0.15
90%	$\frac{9}{10}$	0.9
37.5%	$\frac{3}{8}$	0.375
$33\frac{1}{3}\%$	$\frac{1}{3}$	$0.\dot{3}$
$66\frac{2}{3}\%$	$\frac{2}{3}$	$0.\dot{6}$
62.5%	$\frac{5}{8}$	0.625
$16.\dot{6}$%	$\frac{1}{6}$	$0.1\dot{6}$

8 a 25% b $33\frac{1}{3}$% c 16% d 200%
e 2800% f 25%

9 a \$36 b \$210 c 48 kg d 30 km
e 15 apples f 350 m g 250 people
h 200 cars i \$49

10 a \$120 b \$700 c \$300 d \$7
e \$0.20 f \$400

11 a \$540 b \$600 c \$508 d \$1250
e \$120 f \$40

12 $16\frac{2}{3}$%

13 $6\frac{1}{4}$%

14 48 kg

15 15 students

16 9 students

17 \$1150

18 a $P = 100$ b $P < 100$ c $P > 100$

19 a $x = 2y$ b $x = 5y$ c $x = \frac{3}{5}y$ (or $5x = 3y$)
d $14x = 5y$

20 a 72 b $\frac{10}{11}$ c 280% d $3\frac{1}{4}$
e 150%

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 1G

1 a 1.4 b 1.26 c 60% d 21%
e 0.8 f 0.27 g 6% h 69%
2 a $30 b 25%
3 a 12 kg b 11.1%
4 a $52.50 b 37.8 min (37 min 48 s) c 375 mL
d 1.84 m e 27.44 kg f 36 watts g $13 585
h $1322.40
5 a 19.2 cm b 24.5 cm c 39.06 kg
d 48.4 min (49 m 24 s) e $78.48 f 202.4 mL
g 18°C h $402.36
6 50%
7 44%
8 28%
9 4%
10 a 22.7% b 26.7% c 30.9% d 38.4 %
11 $21.50
12 30 068
13 $14 895
14 a 10% b 12.5% c 16% d 9.375%
15 $10.91
16 $545.45
17 a $900 b $990
c as 10% of 1000 = 100 but 10% of 900 = 90
18 25%
19 100%
20 42.86%
21 a $635.58 b $3365.08 c $151.20 d $213.54
22 a 79.86 g b $ 97 240.50 c $336 199.68
d 7.10 cm

Exercise 1H

1 a $3 profit, $2.50 loss, $1.40 profit, $7.30, $65.95 loss, $2070
b $30.95, $80, $395.95, $799.95, $18 799, $8995
c $28, $9.05, $22.70, $199, $345.50, $2037
2 a 90% b 80% c 85% d 92%
3 a i $2 ii 20%
b i $5 ii 25%
c i $16.80 ii 14%
d i $2450 ii 175%
4 167.67%
5 40%
6 92.5%
7 $37.50
8 $1001.25
9 28%
10 42.3%
11 $148.75
12 $760.50
13 $613.33
14 $333 333
15 increased by 4%
16 25%
17 a $54.75 b 128%
18 No, either way it gives the same price.
19 $2100
20 a i $54 187.50 ii $33 277.90
b 10 years
21 a $34 440 b $44 000 c $27 693.75
d $32 951.10 e $62 040 f $71 627.10

Progress quiz

1 a −54 b 8
2 a 3.46 b 45.9 c 0.0079 d 46 800 000
3 a 0.75 b 0.8 c 0.35 d $0.\dot{3}$
4 a $\frac{9}{10}$ b $\frac{17}{20}$ c $\frac{1}{8}$
5 a $1\frac{1}{3}$ b $\frac{4}{21}$ c $1\frac{1}{5}$ d $2\frac{1}{12}$
6 a 30 : 1 b 5 : 9 c 20 : 3 d 3 : 32
7 a $250, $150
b 1.8 kg , 4.2 kg
c $266\frac{2}{3}$ cm, $333\frac{1}{3}$ cm, 400 cm
8 a $70/h b 80 km/h
9 B
10 a 80% b 96% c 375% d 8%
11 2040 cm
12 $400
13 a $504 b 475 kg
14 a 20% b 30%
15 a $6375 b $812
16 a $111.30 b 22% c $89.04, 44%

Exercise 1I

1 a $3952 b $912 c $24
2 a $79.80 b $62.70 c $91.20 d $102.60
3 a $200 b $56 c $ 900 d $145.10
4 a $46 166 b $23 247
5 a i $19.50 ii $27 iii $42.50
b i $30 201.60 ii $44 044 iii $20 134.40
6 a $82.80 b $119.60 c $184 d $276
e $257.60 f $404.80
7 a 7 b 18 c 33 d 25
e 37 f 40
8 $14.50 per hour

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 $12.20 per hour
10 $490
11 $4010
12 a i $40 035 ii 17.0%
b i $53 905.80 ii 20.1%
c i $41 218.20 ii 15%
d i $30 052.56 ii 22.2%
13 a $1830 b $8043 c $12 617.50
d $23 772.80
14 Cate, Adam, Ed, Diana, Bill
15 $839.05
16 $1239.75
17 4.58%
18 $67 400
19 a 12 hours b 9 and 2, 6 and 4, 3 and 6
20 a i $920 ii $1500
b i $A = 0.02x$
ii $A = 1200 + 0.025(x - 60\,000)$ or $0.025x - 300$
21 a $5500
b Choose plan A if you expect that you will sell less than $5500 worth of jewellery in a week or plan B if you expect to sell more than $5500.
22 a i $2000 ii $11 500 iii $35 000
b

Income	Rate	Tax payable
$40 001 – $90 000	25%	$3750 + 25% of (income − $40 000)
$90 001 –	33%	$16 250 + 33% of (income − $90 000)

c i $2000 ii $6300 iii $24000 iv $40 000.50
d An extra dollar of income can push you into a higher tax bracket where you don't just pay the higher tax rate on the dollar but on your entire income. No incentive to earn more.

Exercise 1J

1 a $12 000 b 6% p.a. c 3.5 years d $720
e $1440 f $2520
2 a $3000 b $3600 c $416 d $315
3 $2700, $17 700
4 $1980, $23 980
5 $2560
6 9 months
7 16 months
8 $2083.33
9 choice 2
10 a $14 400 b $240
11 10%
12 a $P
b 12.5%
c i 20 years ii 40 years iii double
13 a $51000 b 4 years
14 a $P = \frac{100I}{rt}$ b $t = \frac{100I}{Pr}$ c $r = \frac{100I}{Pt}$
15 a $1750 a month b $18 000 c $6000
d 2%

Exercise 1K

1 a $200 b $2200 c $220 d $2420
e $242 f $2662
2 a 2731.82 b 930.44 c 2731.82 d 930.44
3 a $\$4000 \times (1.2)^3$ b $\$15000 \times (1.07)^6$
c $\$825 \times (1.11)^4$
4 a $6515.58 b $10 314.68 c $34 190.78
d $5610.21
5 $293 865.62
6 a 21.7% b 19.1% c 136.7% d 33.5%
7 $33 776
8 a $23 558 b $33 268 c $28 879 d $25 725
9 $543 651
10 6142 people
11 6.54 kg
12 Trial and error gives 12 years
13 Trial and error gives 5 years
14 a 35%
b 40.26%
c as it calculates each years interest on the original $400 not the accumulated total that compound interest uses
15 a 15.76% b 25.44% c 24.02% d 86.96%
e $\left(\left(1 + \frac{r}{100}\right)^t - 1\right) \times 100\%$
16 a $7509.25 b 9.39% p.a.
17 a 70.81% b 7.08%
18 a 5.39% p.a. b 19.28% p.a.

Problems and challenges

1 Discuss with classmates as more than one answer for each may be possible. Some suggestions are given below (be creative).
$(4 - 4) \times (4 + 4) = 0$
$4 \div 4 + 4 \div 4 = 2$
$4 + (4 - 4) \times 4 = 4$
$(4 + 4 + 4) \div \sqrt{4} = 6$
$\sqrt{4} + \sqrt{4} + \sqrt{4} + \sqrt{4} = 8$
$\sqrt{4} \times \sqrt{4} \times \sqrt{4} + \sqrt{4} = 10$
$(4 - 4) + (4 \div 4) = 1$
$\sqrt{4 \times 4} - (4 \div 4) = 3$
$\sqrt{4 \times 4} + 4 \div 4 = 5$
$4 + 4 - 4 \div 4 = 7$
$4 + 4 + 4 \div 4 = 9$
2 12
3 a $\frac{4}{7}$ b $\frac{14}{17}$
4 125 mL
5 40.95% reduction
6 7.91% p.a.
7 a 44% b 10%

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 200 000 cm^2 (20 m^2)
9 9, 7, 2, 14, 11, 5, 4, 12, 13, 3, 6, 10, 15, 1, 8

Multiple-choice questions

1 D 2 B 3 C 4 A 5 E
6 E 7 D 8 E 9 C 10 A
11 C 12 B

Short-answer questions

1 a -16 b 2 c 0 d 10
e -23 f 1
2 a 21.5 b 29 100 c 0.153 d 0.00241
3 a 200 b 60 c 2
4 a 2.125 b $0.8\dot{3}$ c $1.\overline{857142}$
5 a $\frac{3}{4}$ b $1\frac{3}{5}$ c $2\frac{11}{20}$
6 a $\frac{1}{2}$ b $2\frac{1}{6}$ c $\frac{7}{24}$
d 2 e $3\frac{3}{4}$ f $2\frac{19}{28}$
7 a 5 : 2 b 16 : 9 c 75 : 14
8 a 50, 30 b 25, 55 c 10, 20, 50
9 a store A: \$2.25/kg; store B: \$2.58/kg ∴ A is best buy
b store A: 444 g/\$; store B: 388 g/\$
10

Decimal	Fraction	Percentage
0.6	$\frac{3}{5}$	60%
$0.\dot{3}$	$\frac{1}{3}$	$33\frac{1}{3}$%
0.0325	$\frac{13}{400}$	$3\frac{1}{4}$%
0.75	$\frac{3}{4}$	75%
1.2	$1\frac{1}{5}$	120%
2	2	200%

11 a \$77.50 b 1.65
12 a 150 b 25
13 a 72 b 1.17 c 20%
14 12.5 kg
15 \$1800
16 a \$25 b $16\frac{2}{3}$%
17 a \$18.25 b \$14.30
18 \$50 592
19 \$525
20 $4\frac{1}{2}$ years
21 \$63 265.95
22 \$39 160

Extended-response questions

1 a \$231
b \$651
c i \$63 ii \$34.65
2 a i \$26 625 ii \$46 928.44
b 87.71%
c \$82 420
d 26.26%
e 7.4% p.a.

Chapter 2

Exercise 2A

1 a 2 b 2 c 3 d 1
2 A c B d C b D a E f F e
3 a 5 b -2 c $\frac{1}{3}$ d $-\frac{2}{5}$
4 a i $4 + r$ ii $t + 2$ iii $b + g$ iv $x + y + z$
b i $6P$ ii $10n$ iii $2D$ iv $5P + 2D$
c $\frac{500}{C}$
5 a $2 + x$ b $ab + y$ c $x - 5$ d $3x$
e $3x - 2y$ or $2y - 3x$ f $3p$ g $2x + 4$
h $\frac{x + y}{5}$ i $4x - 10$ j $(m + n)^2$
k $m^2 + n^2$ l $\sqrt{x + y}$ m $a + \frac{1}{a}$ n $(\sqrt{x})^3$
6 a -31 b -25 c -33 d -19 e $\frac{1}{2}$
f 4 g 1 h 85
7 a $1\frac{1}{6}$ b $4\frac{1}{4}$ c $\frac{1}{6}$ d $-1\frac{1}{3}$
8 a 60 m^2 b length $= 12 + x$, width $= 5 - y$
c $A = (12 + x)(5 - y)$
9 a 18 square units b 1, 2, 3, 4, 5
10 a $\frac{P}{10}$ b $\frac{nP}{10}$
11 a i $P = 2x + 2y$ ii $A = xy$
b i $P = 4p$ ii $A = p^2$
c i $P = x + y + 5$ ii $A = \frac{5x}{2}$
12 a A: $2(x + y)$B: $2x + y$, different b Same
13 a B b A: $c^2 = (a + b)^2$
14 a $\frac{n(n + 1)}{2}$
b i 10 ii 55
c $\frac{n^2}{2} + \frac{n}{2}$
d 10, 55
e Half the sum of n and the square of n.

Exercise 2B

1 a variable (pronumeral) b $5x$ c unlike
2 a $\frac{2}{3}$ b $\frac{5}{2}$ c 3 d $\frac{1}{5}$
e $-\frac{2}{7}$ f $-\frac{1}{20}$ g $-\frac{11}{53}$ h -17

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 a like b unlike c unlike d unlike
e like f like g like h unlike
i like

4 a $10m$ b $12b$ c $15p$ d $6xy$
e $18pr$ f $16mn$ g $-14xy$ h $-15mn$
i $-12cd$ j $30ab$ k $-24rs$ l $-40jk$

5 a $24n^2$ b $-3q^2$ c $10s^2$ d $21a^2b$
e $-15mn^2$ f $18gh^2$ g $12x^2y^2$ h $8a^2b^2$
i $-6m^2n^2$

6 a $4b$ b $-\frac{a}{3}$ c $\frac{2ab}{3}$ d $\frac{m}{2}$
e $-\frac{x}{4}$ f $\frac{5s}{3}$ g uv h $\frac{5rs}{8}$
i $\frac{5ab}{9}$ j $\frac{7}{y}$

7 a $\frac{2x}{5}$ b $\frac{4}{3a}$ c $\frac{11mn}{3}$ d $6ab$
e $-\frac{5}{gh}$ f 8 g -3 h $\frac{7n}{3}$
i $-\frac{9q}{2}$ j $3b$ k $-5x$ l $\frac{m}{2}$

8 a $\frac{4x}{y}$ b $\frac{5p}{2}$ c $-6ab$ d $-\frac{3a}{2b}$
e $-\frac{7n}{5m}$ f $\frac{10s}{t}$ g $8n$ h $3y$
i $4b$ j $6xy$ k $5m$ l $3pq^2$

9 a $10a$ b $7n$ c $8y$ d $11x$
e $3ab$ f $7mn$ g $y + 8$ h $3x + 5$
i $7xy + 4y$ j $12ab + 3$ k $2 - 6m$ l $4 - x$

10 a $5a + 9b$ b $6x + 5y$ c $4t + 6$ d $11x + 4$
e $5xy + 4x$ f $7mn - 9$ g $5ab - a$ h 0

11 a xy^2 b $7a^2b$ c $3m^2n$ d p^2q^2
e $7x^2y - 4xy^2$ f $13rs^2 - 6r^2s$
g $-7x - 2x^2$ h $4a^2b - 3ab^2$
i $7pq^2 - 8pq$ j $8m^2n^2 - mn^2$

12 a $x + y$ b $4x + 2y$

13 a $8x$ b $3x^2$

14 a $30x$ cm b $30x^2$ cm^2

15 $\frac{20x + 75}{21}$

16 a True b False c True d False
e False f True

17 a $4x + 4y$ b $8x + 4$ c $2x - 2$

18 a a^3 b $\frac{b^2}{3}$ c $\frac{b^2}{3}$ d $\frac{3ab}{8}$
e $-\frac{2a^3}{3}$ f $-\frac{2}{5a^2}$ g $\frac{2}{5a^5}$ h $\frac{a^2}{4b^3}$
i $3a^3b$ j $\frac{4b^3}{a}$ k $\frac{a^3}{3b}$ l $-\frac{a}{2b^3}$

Exercise 2C

1 a i 5x ii 10
b $5x + 10$ c $x + 2$ d $5(x + 2)$ e $5x + 10$

2 a i -16 ii -4
b No, $-2x - 6$
c i -27 ii -33
d No, $-3x + 3$

3 a $2x + 6$ b $5x + 60$ c $2x - 14$ d $7x - 63$
e $6 + 3x$ f $21 - 7x$ g $28 - 4x$ h $2x - 12$

4 a $-3x - 6$ b $-2x - 22$ c $-5x + 15$
d $-6x + 36$ e $-8 + 4x$ f $-65 - 13x$
g $-180 - 20x$ h $-300 + 300x$

5 a $2a + 2b$ b $5a - 10$
c $3m - 12$ d $-16x - 40$
e $-12x - 15$ f $-4x^2 + 8xy$
g $-18ty + 27t$ h $3a^2 + 4a$
i $2d^2 - 5d$ j $-6b^2 + 10b$
k $8x^2 + 2x$ l $5y - 15y^2$

6 a $2x + 11$ b $6x - 14$ c $15x - 3$ d $3x + 1$
e $4x - 5$ f $2x + 1$ g $-3x - 4$ h $-5x - 19$
i $11 - x$ j $12 - x$ k $2 - 2x$ l $6 - 3x$

7 a $5x + 12$ b $4x - 8$ c $11x - 2$ d $17x - 7$
e $-4x - 6$ f $x - 7$ g $2x - 4$ h $-27x - 4$
i $-4x - 18$ j $-13x - 7$
k $11x - 7$ l $2x - 15$

8 $A = x^2 + 4x$

9 a $2x + 2$ b $2x^2 - 3x$ c $6x^2 - 2x$ d $2x^2 + 4x$
e $x^2 + 2x + 6$ f $20 + 8x - x^2$

10 $20n - 200$

11 $0.2x - 2000$

12 a $2x + 12$ b $x^2 - 4x$ c $-3x - 12$
d $-7x + 49$ e $19 - 2x$ f $x - 14$

13 a $6(50 + 2) = 312$ b $9(100 + 2) = 918$
c $5(90 + 1) = 455$ d $4(300 + 26) = 1304$
e $3(100 - 1) = 297$ f $7(400 - 5) = 2765$
g $9(1000 - 10) = 8910$ h $6(900 - 21) = 5274$

14 a $a =$ \$6000, $b =$ \$21 000
b i \$3000 ii \$12 600 iii \$51 000
c i 0 ii $0.2x - 4000$
iii $0.3x - 9000$ iv $0.5x - 29\,000$
d Answers will vary
e Answers will vary

Exercise 2D

1 a 3 b 40 c 5 d 6

2 a 3 b 2 c 2 d 12
e 12 f -5 g 6 h 1

3 a, d, e, f, h

4 a 2 b 1 c 4 d -1
e -3 f -6 g -4 h $-3\frac{2}{3}$
i $1\frac{2}{3}$ j $4\frac{1}{2}$ k $\frac{1}{2}$ l $1\frac{1}{3}$
m $-\frac{5}{7}$ n $-\frac{1}{8}$ o $-\frac{3}{20}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 **a** 8 **b** 2 **c** 12 **d** -6
e -6 **f** 30 **g** -15 **h** -8
i 12 **j** 20 **k** -5 **l** -10

6 **a** -3 **b** -1 **c** 2 **d** 8
e $-1\frac{2}{5}$ **f** $-2\frac{5}{7}$ **g** $\frac{3}{8}$ **h** $1\frac{3}{4}$

7 **a** 9 **b** 6 **c** $-6\frac{3}{4}$ **d** $-7\frac{1}{2}$ **e** $\frac{2}{3}$
f $-\frac{4}{25}$ **g** 12 **h** 12 **i** -9
j -8 **k** 6 **l** $-1\frac{1}{2}$

8 **a** 11 **b** 6 **c** -10 **d** -12
e -5 **f** -1 **g** 7 **h** 5
i $4\frac{2}{7}$ **j** $5\frac{1}{3}$ **k** -7 **l** 3

9 **a** 26 **b** 28 **c** 3 **d** 28 **e** 8
f $3\frac{3}{7}$ **g** 7 **h** \$900

10 **a** should have $+1$ before $\div 2$
b should have $\times 3$ before -2
c need to $\div -1$ as $-x = 7$
d should have $+4$ before $\times 3$

11 **a** **i** 5 **ii** -3 **iii** $\frac{1}{5}$ **iv** 3
v $-\frac{5}{6}$ **vi** $\frac{3}{10}$
b when the common factor divides evenly into the RHS

12 **a** $a = b + c$ **b** $a = \frac{c - b}{2}$
c $a = \frac{c - 2d}{b}$ **d** $a = c(b + d)$
e $a = -\frac{cd}{b}$ **f** $a = \frac{b}{2c}$ **g** $a = \frac{c(3 - d)}{2b}$
h $a = \frac{2d(b - 3)}{c}$ **i** $a = cd - b$
j $a = b + cd$ **k** $a = \frac{2be + 6c}{d}$
l $a = \frac{d - 3ef}{4c}$

Exercise 2E

1 **a** $4x - 12$ **b** 2 **c** $5x - 9$ **d** $3 - 9x$
e $3x - 7$ **f** $24 - 12x$

2 **a** $2x + 6 = 5$ **b** $5 + 2x - 2 = 7$
c $2x + 1 = -6$ **d** $2x - 3 = 1$

3 **a** $2\frac{1}{2}$ **b** $-1\frac{2}{5}$ **c** $6\frac{1}{3}$ **d** $4\frac{3}{5}$
e $-3\frac{3}{4}$ **f** $9\frac{1}{2}$ **g** $\frac{1}{2}$ **h** $-5\frac{1}{2}$
i $-\frac{4}{5}$ **j** $\frac{1}{14}$ **k** $3\frac{1}{6}$ **l** $\frac{2}{3}$
m $\frac{9}{10}$ **n** $1\frac{1}{6}$ **o** $-\frac{1}{8}$

4 **a** 2 **b** -10 **c** 1 **d** -2 **e** 5
f 0 **g** 1 **h** 5 **i** 3 **j** 3

5 **a** 1 **b** -4 **c** 2 **d** 8 **e** 8
f 3 **g** 4 **h** -1 **i** $\frac{5}{11}$

6 **a** -1 **b** $3\frac{1}{2}$ **c** -9 **d** -14
e -16 **f** 3 **g** 19 **h** -3
i -13 **j** -26 **k** $-2\frac{2}{3}$ **l** $-1\frac{1}{10}$

7 **a** $\frac{1}{2}$ **b** $2\frac{2}{3}$ **c** $1\frac{1}{2}$ **d** $-\frac{5}{6}$ **e** $\frac{2}{5}$
f $1\frac{1}{2}$ **g** -6

8 Let \$w be the wage, $2(3w - 6) = 18$, \$5

9 11 marbles

10 **a** $x = 5$
b $x = 5$
c Dividing both sides by 3 is faster because $9 \div 3$ is an integer

11 **a** $x = 4\frac{1}{3}$
b $x = 4\frac{1}{3}$
c Expanding the brackets is faster because $7 \div 3$ gives a fraction answer

12 **a** $x = 4$ **b** $x = 4$
c Method a: don't have to deal with negatives
Final step in method a: divide both sides by a positive number
Final step in method b: divide both sides by a negative number

13 **a** $x = \frac{d}{a - b}$ **b** $x = \frac{2}{a - b}$
c $x = \frac{c}{5a - b}$ **d** $x = -\frac{6}{3a - 4b}$ or $\frac{6}{4b - 3a}$
e $x = -c$ **f** $x = b$ **g** $x = \frac{d + bd + c}{a - b}$
h $x = -\frac{ab + bc}{a - b + 1}$ or $\frac{ab + bc}{b - a - 1}$

Exercise 2F

1 **a** $x - 3 = 4x - 9$ **b** $3(x + 7) = 9$
c $4(x - 9) = 12$ **d** $2x = x + 5$
e $x - 8 = 3x + 2$

2 **a** Let e be the number of goals for Emma
b $e + 8$ **c** $e + e + 8 = 28$ **d** $e = 10$
e Emma scored 10 goals, Leonie scored 18 goals

3 **a** Let w be the width in centimetres **b** length $= 4w$
c $2w + 2(4w) = 560$ **d** $w = 56$
e length $= 224$ cm, width $= 56$ cm

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 $40x + 50 = 290$, 6 days.
5 $x + 2x + 2 = 32$, 10 km, 20 km.
6 $x + x + 280 = 1000$, \$360, \$640.
7 15, 45
8 19 km
9 A \$102.50, B \$175, C \$122.50
10 4 fiction, 8 non-fiction books
11 I am 10 years old
12 Eric is 18 yrs old now
13 First leg = 54 km, Second leg = 27 km, Third leg = 18 km, Fourth leg = 54 km
14 2 hours
15 8 pm
16 Rectangle $L = 55$ m, $W = 50$ m. Triangle side = 70 m
17 a 27, 28, 29
b i $x, x+2, x+4$ ii 4, 6, 8
c i $x, x+2, x+4$ ii 15, 17, 19
d i $x, x+3, x+6$ ii 24, 27, 30
18 a $T = 8x + 7200$ b 300 c $R = 24x$
d $x = 350$ e 3825
19 \$15 200
20 438 km
21 Anna 6; Henry 4; Chloe 12; twins 11

Progress quiz

1 a $5 + x + y$ b $4y - 15$ c $k^2 + p^2$
d $(m-n)^2$ or $(n-m)^2$ e $\sqrt{x+16}$
2 a 12 b -28 c $\frac{1}{2}$ d -12
3 a $14ab$ b $-40p^2q$ c $\frac{4k}{m}$ d $-6y^2$
4 a $2xy + 7$ b $11 + km$ c $5xy - 3x + 2y$
d $a^2b + ab^2 + b$
5 a $4a + 28$ b $-6x^2 + 15x$
6 a $16 - 3a$ b $5x - 2y$
7 a $x = 4$ b $a = 21$ c $p = -3\frac{1}{2}$
d $x = -6$ e $t = 20$ f $k = \frac{5}{12}$
g $x = -9$ h $k = 7$
8 a $x = 6\frac{1}{3}$ b $a = 3$ c $m = -2$ d $y = 9\frac{1}{2}$
9 a $2(x+5) = 14$ b $x - 9 = 4x + 6$
10 Let a be my age, $4(a+5) = 88$, 17 years old

Exercise 2G

1 a $3 > 2$ b $-1 < 4$ c $-7 < -3$
d $5 > -50$
2 a 

b 

c 

d 

e 

f 

g 

h 

i 

j 

k 

l 

3 a $x < 3$ b $b > 5$ c $y > 6$ d $m < 5$
e $x \geq 3$ f $t > -5$ g $x \geq 12$ h $y \geq -10$
i $m < 6$ j $a \geq 1\frac{1}{2}$ k $x < 1$ l $x > 8$
4 a $x < 4$ b $n \leq -1$ c $x \geq \frac{3}{5}$ d $a \geq 4$
e $x \geq -6$ f $x \geq 10$ g $x < -6$ h $t \leq -2$
i $m > -4\frac{5}{6}$
5 a $x \leq 16$ b $x \leq -9$ c $x \leq 20$ d $x < 11$
e $x > -2\frac{2}{3}$ f $x \geq -2$
6 a $x < 1$ b $a < -8$ c $x \leq -2$ d $x < 2\frac{1}{2}$
e $y < -3\frac{1}{5}$ f $x < -\frac{4}{7}$
7 a $x \geq 2\frac{1}{2}$ b $t > -\frac{3}{5}$ c $y \leq \frac{3}{8}$ d $a < 1\frac{1}{5}$
e $m \geq 6$ f $b < 5\frac{1}{2}$
8 less than 18
9 less than 13 cm
10 a 3 b 2 c 4 d 0
11 $x = 3$ or $x = 4$ or $x = 5$
12 399 km
13 a i -0.9, 0, 0.5, 1, 1.8 etc
ii numbers must be less than 2

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b i $-4, -2, 0, 1, 5$ etc
ii numbers must be greater than -5
c i $x < a$ ii $x > -a$

14 **a** $x < 3$ **b** $x < 3$
c Reverse inequality sign when dividing by a negative number

15 **a** $x < -13$ **b** $x \geq -3$ **c** $x > \frac{4}{7}$ **d** $x \leq \frac{13}{5}$
e $x > \frac{10}{17}$ **f** $x \geq \frac{3}{4}$

16 **a** $x > \frac{b-c}{a}$ **b** $x \geq b - a$
c $x \leq a(b+c)$ **d** $x \leq \frac{ac}{b}$ **e** $x < \frac{cd-b}{a}$
f $x \geq \frac{b-cd}{2}$ **g** $x < \frac{c}{a} - b$
h $x > \frac{b-cd}{a}$ **i** $x < b - \frac{c}{a}$
j $x \leq \frac{b+c}{1-a}$ **k** $x < \frac{b+1}{b-a}$
l $x \leq \frac{c-b}{b-a}$

Exercise 2H

1 **a** A **b** D **c** M **d** A

2 **a** 21 **b** 24 **c** 2 **d** 6
e 452.16 **f** 33.49 **g** 25.06 **h** 14.95
i 249.86 **j** 80

3 **a** 36 **b** 5 **c** 20 **d** 4.14
e 3.39 **f** 18.67 **g** 0.06

4 **a** $r = \frac{A}{2\pi h}$ **b** $r = \frac{100I}{Pt}$
c $n = \frac{p}{m} - x$ **d** $x = \frac{cd-a}{b}$
e $r = \sqrt{\frac{V}{\pi h}}$ **f** $v = \sqrt{PR}$
g $h = \frac{S - 2\pi r^2}{2\pi r}$ **h** $p = -q \pm \sqrt{A}$
i $g = \frac{4\pi^2 l}{T^2}$ **j** $A = (4C - B)^2$

5 **a** 88.89 km/h
b i $d = st$ ii 285 km

6 **a** i 212°F ii 100.4°F
b $C = \frac{5}{9}(F - 32)$
c i -10°C ii 36.7°C

7 **a** 35 m/s **b** 2 s

8 **a** decrease **b** 3988 L **c** 6 hours 57 minutes
d 11 hours 7 minutes

9 **a** $D = \frac{c}{100}$ **b** $d = 100e$ **c** $D = 0.7M$
d $V = 1.15P$ **e** $C = 50 + 18t$ **f** $d = 42 - 14t$
g $C = \frac{c}{b}$

10 **a** $a = \frac{P}{4}$ **b** $a = 180 - b$ **c** $a = 90 - b$
d $a = \frac{180 - b}{2}$ **e** $a = \sqrt{c^2 - b^2}$
f $a = \sqrt{\frac{4A}{\pi}}$

11 **a** 73 **b** 7 **c** 476.3

Exercise 2I

1 **a** $y = 5$ **b** $x = -3$ **c** $x = 10$

2 **a** A **b** C

3 **a** yes **b** no **c** no **d** yes

4 **a** $x = 1, y = 2$ **b** $x = 5, y = 1$
c $x = \frac{1}{2}, y = \frac{3}{2}$ **d** $x = -2, y = -1$
e $x = 2, y = 6$ **f** $x = -3, y = 9$

5 **a** $x = 3, y = 9$ **b** $x = -1, y = 3$
c $x = 1, y = 0$ **d** $x = 6, y = 11$
e $x = 4, y = 3$ **f** $x = 12, y = -3$
g $x = -18, y = -4$ **h** $x = -2, y = 10$
i $x = 2, y = -4$

6 **a** $x = 2, y = 1$ **b** $x = 1, y = 3$
c $x = 0, y = 4$ **d** $x = 3, y = -2$
e $x = 4, y = 1$ **f** $x = -1, y = 4$

7 17, 31

8 10 tonnes, 19 tonnes

9 width $= 1\frac{2}{3}$ cm, length $= 3\frac{5}{6}$ cm

10 $x - (3x - 1) = x - 3x + 1$, to avoid sign error use brackets when substituting

11 **a** $x = \frac{1}{3}, y = 2\frac{1}{3}$ **b** $x = -\frac{5}{6}, y = 6\frac{1}{3}$
c $x = -22, y = -7$

12 **a** $x = \frac{b}{a+b}, y = \frac{b^2}{a+b}$
b $x = \frac{b}{a+1}, y = \frac{1}{a+1}$
c $x = \frac{a-b}{2}, y = \frac{a+b}{2}$
d $x = \frac{a-ab}{a-b}, y = \frac{a-ab}{a-b} - a$
e $x = \frac{2a}{a-b}, y = \frac{2ab}{a-b} + a$
f $x = \frac{2a+ab}{a-b} - b, y = \frac{2a+ab}{a-b}$

Exercise 2J

1 **a** $-$ **b** $+$ **c** $+$ **d** $-$

2 **a** i subtraction ii addition iii subtraction
b i addition ii subtraction iii addition

3 **a** $x = 1, y = 1$ **b** $x = 10, y = 2$
c $x = 1, y = 3$ **d** $x = 1, y = 1$
e $x = 2, y = 2$ **f** $x = 2, y = -1$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 **a** $x = 2, y = 4$ **b** $x = 8, y = -1$
c $x = -2, y = 6$

5 **a** $x = -3, y = -13$ **b** $x = 2, y = 3$
c $x = 1, y = 3$

6 **a** $x = -3, y = 4$ **b** $x = 2, y = 1$
c $x = 2, y = 1$ **d** $x = -2, y = 3$
e $x = 7, y = -5$ **f** $x = 5, y = 4$
g $x = 5, y = -5$ **h** $x = -3, y = -2$
i $x = -1, y = -3$

7 **a** $x = 3, y = -5$ **b** $x = 2, y = -3$
c $x = 2, y = 4$ **d** $x = 3, y = 1$
e $x = -1, y = 4$ **f** $x = 3, y = -2$
g $x = 5, y = -3$ **h** $x = -2, y = -2$
i $x = 2, y = 1$ **j** $x = -5, y = -3$
k $x = -3, y = 9$ **l** $x = -1, y = -2$

8 21 and 9

9 102, 78

10 $L = 261.5$ m, $W = 138.5$ m

11 11 mobile phones, 6 iPads

12 **a** $x = 2, y = 1$
b $x = 2, y = 1$
c Method (b) is preferable as it avoids the use of a negative coefficient.

13 Rearrange one equation to make x or y the subject.
a $x = 4, y = 1$ **b** $x = -1, y = -1$

14 **a** no solution **b** no solution

15 **a** $x = \frac{a+b}{2}, y = \frac{a-b}{2}$

b $x = \frac{b}{2a}, y = -\frac{b}{2}$ **c** $x = -\frac{a}{2}, y = -\frac{3a}{2b}$

d $x = 0, y = b$ **e** $x = \frac{1}{3}, y = \frac{b}{3a}$

f $x = -\frac{4}{a}, y = 6$ **g** $x = \frac{3b}{7a}, y = \frac{b}{7}$

h $x = \frac{3b}{7a}, y = -\frac{b}{7}$ **i** $x = 0, y = \frac{b}{a}$

j $x = -\frac{c}{a}, y = c$ **k** $x = \frac{b-4}{ab-4}, y = \frac{1-a}{ab-4}$

l $x = 1, y = 0$ **m** $x = \frac{c-bd}{a(b+1)}, y = \frac{c+d}{b+1}$

n $x = \frac{a+2b}{a-b}, y = \frac{3a}{a-b}$

o $x = \frac{3b}{a+3b}, y = \frac{3b-2a}{a+3b}$

p $x = -\frac{b}{a-bc}, y = \frac{bc-2a}{a-bc}$

q $x = \frac{c+f}{a+d}, y = \frac{cd-af}{b(a+d)}$

r $x = \frac{c-f}{a-d}, y = \frac{af-cd}{b(a-d)}$

Exercise 2K

1 **a** $x + y = 42, x - y = 6$
b $x = 24, y = 18$
c One number is 18, the other number is 24

2 **a** $l = w + 5, 2l + 2w = 84$
b $l = 23.5, w = 18.5$
c length = 23.5 cm, width = 18.5 cm

3 **a** $l = 3w, 2l + 2w = 120$
b $l = 45, w = 15$
c length = 45 m, width = 15 m

4 **a** Let \$m be the cost of milk
Let \$c be the cost of chips
b $3m + 4c = 17, m + 5c = 13$ **c** $m = 3, c = 2$
d bottle of milk costs \$3 and a bag of chips \$2.

5 **a** Let \$g be the cost of lip gloss.
Let \$e be the cost of eye shadow.
b $7g + 2e = 69, 4g + 3e = 45$ **c** $g = 9, e = 3$
d lip gloss \$9; eye shadow \$3

6 cricket ball \$12; tennis ball \$5

7 4 buckets of chips, 16 hot dogs

8 300 adults, 120 children

9 potatoes 480 ha; corn 340 ha

10 11 five-cent and 16 twenty-cent

11 Michael is 35 years old now.

12 Jenny \$100, Kristy \$50

13 160 adult tickets and 80 child tickets

14 5 hours

15 jogging 3 km/h, cycling 9 km/h

16 **a** Malcolm is 14 years old
b The second digit of Malcolm's age is 3 more than the first digit. **c** 6: 14, 25, 36, 47, 58 or 69

17 Original number is 37

18 Any two-digit number that has the first digit 2 more than the second (e.g. 42 or 64 etc.)

Problems and challenges

1 **a** $x = \frac{k+4}{w-a}$ **b** $K = \frac{a-b}{y}$ **c** $a = \frac{w}{1-km^2}$

2 39

3 \$140

4 8

5 **a** **i** $>$ **ii** $<$ **iii** $>$ **iv** $<$
b c, b, a, d

6 $x = 1, y = -2, z = 5$

7 **a** $x = \frac{ab}{a-b}$ **b** $x = \frac{10}{3}$ or $3\frac{1}{3}$

c $x = -\frac{7}{11}$ **d** $x = \frac{29}{4}$ or $7\frac{1}{4}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

1 C 2 D 3 D 4 C 5 B
6 A 7 A 8 E 9 B 10 A
11 B 12 D

Short-answer questions

1 a 7m b $2(x+y)$ c 3m d $\frac{n}{4}-3$

2 a -7 b 7 c 24 d 8

3 a $8mn$ b $\frac{xy}{3}$ c $6b^2$ d $4-3b$
e $2mn+2m-1$ f $2p+4q$

4 a $2x+14$ b $-6x-15$ c $6x^2-8x$
d $-10a+8a^2$ e $13-4x$ f $27x-10$

5 a $x=9$ b $x=26$ c $x=15$ d $x=1$
e $x=2$ f $x=-9$ g $x=-10$ h $x=\frac{5}{7}$

6 a $2n+3=21, n=9$ b $\frac{l-5}{3}=7,\ l=26$
c $\frac{x}{4}-5=0, x=20$

7 a $x=5$ b $x=1\frac{5}{6}$ c $x=4$ d $x=-5$
e $x=1$ f $x=4$

8 \$260

9 a


b


c


d


e


f


10 a $x<12$ b $m>-1$ c $y\geq -6$ d $x<17$
e $a>4$ f $x\geq 2$

11 n (sales) $\geq$ \$24 000

12 a $E=60$ b $a=5$ c $h=10$

13 a $x=\frac{v^2-u^2}{2a}$ b $\theta=\frac{2A}{r^2}$ c $I=\sqrt{\frac{P}{R}}$
d $a=\frac{2S}{n}-l=\frac{2S-nl}{n}$

14 a $x=8, y=2$ b $x=-\frac{3}{5}, y=-1\frac{3}{5}$
c $x=4, y=11$ d $x=11, y=4$
e $x=-3, y=-5$ f $x=4, y=1$

15 3 show bags, 6 rides

Extended-response questions

1 a $0<b\leq 10$ b $b=\frac{2A}{h}-a$
c 8 m d $h=\frac{2A}{a+b}$ e 8 m

2 a \$5 per ride
b i Let \$$c$ be the cost of a bucket of chips
Let \$$d$ be the cost of a drink
ii $2d+c=11, 3d+2c=19$
iii $d=3, c=5$
iv Chips cost \$5 per bucket and drinks cost \$3 each

Chapter 3

Exercise 3A

1 a 17 b 50 c $\sqrt{8}$

2 a $c^2=a^2+b^2$ b $x^2=y^2+z^2$
c $j^2=k^2+l^2$

3 a 81 b 10.24 c 13 d 106 e 6
f 10 g 4.90 h 3.61

4 a $c=10$ b $c=13$ c $c=17$ d $c=15$
e $c=25$ f $c=41$ g $c=50$ h $c=30$
i $c=25$

5 a 4.47 b 3.16 c 15.62 d 11.35
e 7.07 f 0.15

6 a $\sqrt{5}$ b $\sqrt{58}$ c $\sqrt{34}$ d $\sqrt{37}$
e $\sqrt{109}$ f $\sqrt{353}$

7 a 21.63 mm b 150 mm c 50.99 mm
d 155.32 cm e 1105.71 m
f 0.02 m

8 a 8.61 m b 5.24 m c 13.21 cm d 0.19 m
e 17.07 mm f 10.93 cm

9 42 m

10 4.4 m

11 250 m

12 495 m

13 2.4 m

14 a 5 b $\frac{25}{3}$ or $8\frac{1}{3}$

15 5.83 m

16 a no b no c yes d no
e yes f yes

17 a 5.66 cm b 5.66 cm c yes

18 a 77.78 cm b 1.39 m c reduce is by 8 cm
d 43.73 cm

19 42.43 cm, 66.49 cm

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 3B

1 **a** 14 **b** 11 **c** 12 **d** 20 **e** 4
f 24 **g** 8 **h** 8

2 **a** T **b** F **c** F **d** T **e** T
f F

3 **a** 16 **b** 24 **c** 6 **d** 21
e 60 **f** 27

4 **a** 8.66 **b** 11.31 **c** 5.11 **d** 17.55
e 7.19 **f** 0.74

5 **a** 30 cm **b** 149.67 cm **c** 1.65 cm
d 2.24 km **e** 12 cm **f** 52.92 mm

6 **a** $\sqrt{\frac{25}{2}} = \frac{5}{\sqrt{2}}$ **b** $\sqrt{8}$
c $\sqrt{\frac{1521}{200}} = \frac{39}{\sqrt{200}} = \frac{39}{10\sqrt{2}}$

7 **a** $\sqrt{187}$ **b** $\sqrt{567}$ **c** 40

8 14.2 m

9 5.3 m

10 49 cm

11 1.86 m

12 **a** $\sqrt{\frac{81}{5}} = \frac{9}{\sqrt{5}}$ **b** $\sqrt{5}$ **c** $\sqrt{\frac{5}{2}}$

13 **a** $\sqrt{\frac{5}{2}}, 3\sqrt{\frac{5}{2}}$ **b** $\frac{10}{\sqrt{13}}, \frac{15}{\sqrt{13}}$
c $\frac{25}{\sqrt{74}}, \frac{35}{\sqrt{74}}$

14 **a** the side c **b** $\sqrt{6}$ **c** no, c^2 is enough
d error due to rounding, x would not be exact

15 **a** **i** $\sqrt{8}$ **ii** $\sqrt{7}$ **iii** $\sqrt{6}$
b OB: 2.6, OC: 2.79, OD: 2.96
c differ by 0.04; the small difference is the result of rounding errors
d Answers will vary

Exercise 3C

1 **a** C, II **b** A, III **c** B, I

2 142.9 m

3 3.0 m

4 3823 mm

5 1060 m

6 **a** 6.4 m **b** 5.7 cm **c** 5.4 m **d** 6.0 m

7 466.18 m

8 **a**


b 3.9 cm

9 **a** 47 m **b** 89.8 m

10 171 cm

11 **a** $\frac{5}{\sqrt{2}}$ **b** $6 + \frac{5}{\sqrt{2}}$ **c** 10.2

12 **a** 1.1 km **b** 1.1 km **c** 3.8 km

13 **a** 28.28 cm
b **i** 80 cm **ii** 68.3 cm **iii** 48.3 cm
c Answers will vary
d Answers will vary

Exercise 3D

1 **a** yes **b** yes **c** no **d** yes
e yes **f** no **g** yes **h** no
i yes

2 **a** 11.18 **b** 0.34 **c** 19.75

3 **a** 3.6 **b** 2.5 **c** 3.1

4 **a** 18.0 cm **b** 7 mm **c** 0.037 m

5 **a** $\sqrt{2}$ cm **b** 1.7 cm

6 **a** $\sqrt{208}$ cm **b** 15.0 cm

7 84 m

8 2.86 cm

9 $\sqrt{3} : 2$

10 **a** **i** $\sqrt{8}$ cm **ii** 3.74 cm
b **i** $\sqrt{50}$ cm **ii** 5.45 cm

11 **a** $\sqrt{65}$ **b** 8.06 **c** $\sqrt{69}$, 8.31
d 8.30 **e** Rounding errors have accumulated

12 **a** **i** 11.82 m **ii** 12.15 m **iii** 11.56 m **iv** 11.56 m
b Shortest is 10.44 m

Exercise 3E

1 **a** hypotenuse **b** opposite **c** adjacent
d opposite **e** hypotenuse **f** adjacent

2 **a**


b


c


d


e


f


Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

g 

h 

3 **a** 5 **b** 4 **c** 3 **d** 3 **e** 4

4 **a** $\sin\theta = \frac{4}{7}$ **b** $\tan\theta = \frac{5}{4}$

c $\cos\theta = \frac{3}{5}$ **d** $\sin\theta = \frac{2}{3}$

e $\tan\theta = 1$ **f** $\cos\theta = \frac{x}{y}$

g $\tan\theta = \frac{4}{5}$ **h** $\cos\theta = \frac{a}{2b}$

i $\tan\theta = \frac{5y}{3x}$

5 **a** **i** $\frac{5}{13}$ **ii** $\frac{5}{13}$ **iii** the same

b **i** $\frac{12}{13}$ **ii** $\frac{12}{13}$ **iii** the same

c **i** $\frac{5}{12}$ **ii** $\frac{5}{12}$ **iii** the same

6 **a** $\sin\theta = \frac{3}{5}$ $\cos\theta = \frac{4}{5}$ $\tan\theta = \frac{3}{4}$

b $\sin\theta = \frac{5}{13}$ $\cos\theta = \frac{12}{13}$ $\tan\theta = \frac{5}{12}$

c $\sin\theta = \frac{12}{13}$ $\cos\theta = \frac{5}{13}$ $\tan\theta = \frac{12}{5}$

7 **a** $\frac{4}{5}$ **b** $\frac{3}{5}$ **c** $\frac{3}{5}$ **d** $\frac{3}{4}$

e $\frac{4}{5}$ **f** $\frac{4}{3}$

8 $\frac{3}{4}$

9 **a** $\frac{3}{5}$ **b** $\frac{4}{5}$ **c** $\frac{3}{4}$

10 **a** **i** 5 **ii** $\sin\theta = \frac{3}{5}$

$\cos\theta = \frac{4}{5}$

$\tan\theta = \frac{3}{4}$

b **i** 25 **ii** $\sin\theta = \frac{7}{25}$

$\cos\theta = \frac{24}{25}$

$\tan\theta = \frac{7}{24}$

c **i** 15 **ii** $\sin\theta = \frac{9}{15} = \frac{3}{5}$

$\cos\theta = \frac{12}{15} = \frac{4}{5}$

$\tan\theta = \frac{9}{12} = \frac{3}{4}$

d **i** 10 **ii** $\sin\theta = \frac{8}{10} = \frac{4}{5}$

$\cos\theta = \frac{6}{10} = \frac{3}{5}$

$\tan\theta = \frac{8}{6} = \frac{4}{3}$

11 **a** 

b 8 **c** $\sin\theta = \frac{15}{17}$, $\cos\theta = \frac{8}{17}$, $\tan\theta = \frac{15}{8}$

12 **a** **i** $\frac{1}{2}$ **ii** $\frac{\sqrt{3}}{2}$ **iii** $\frac{1}{\sqrt{3}}$ **iv** $\frac{\sqrt{3}}{2}$

v $\frac{1}{2}$ **vi** $\sqrt{3}$

b **i** they are equal **ii** they are equal

13 **a** answers may vary

b **i** 0.766 **ii** 0.643 **iii** 0.839 **iv** 0.766

v 1.192 **vi** 0.643

c $\sin 40^\circ = \cos 50^\circ$, $\sin 50^\circ = \cos 40^\circ$,

$\tan 50^\circ = \frac{1}{\tan 40^\circ}$ $\tan 40^\circ = \frac{1}{\tan 50^\circ}$

14 **a** yes, any isosceles right-angled triangle

b no, as it would require the hypotenuse (the longest side) to equal the opposite

c no, adjacent side can't be zero

d no, as the numerator $<$ denominator for sin and cos as the hypotenuse is the longest side

15 **a** $\sin\theta = \frac{3}{5}$ $\tan\theta = \frac{3}{4}$

b **i** $\cos\theta = \frac{\sqrt{3}}{2}$ $\tan\theta = \frac{1}{\sqrt{3}}$

ii $\tan\theta = \sqrt{3}$ $\sin\theta = \frac{\sqrt{3}}{2}$

iii $\sin\theta = \frac{1}{\sqrt{2}}$ $\cos\theta = \frac{1}{\sqrt{2}}$

c equals one

d $(\sin\theta)^2 + (\cos\theta)^2 = 1$ (the Pythagorean identity)

Exercise 3F

1 **a** A **b** O **c** H

2 **a** sin **b** tan **c** cos

3 **a** 0.34 **b** 0.80 **c** 2.05 **d** 0.73

e 0.10 **f** 0.25 **g** 0.46 **h** 0.24

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 a 3.06 b 18.94 c 5.03 d 0.91
e 1.71 f 9.00 g 2.36 h 4.79
i 7.60
5 a 5.95 b 0.39 c 12.59 d 3.83
e 8.40 f 1.36 g 29.00 h 1.62
i 40.10 j 4.23 k 14.72 l 13.42
m 17.62 n 5.48 o 9.75 p 1.01
6 1.12 m
7 44.99 m
8 10.11 m
9 a 20.95 m b 10 cm
10 a 65° b 1.69 c 1.69
d They are the same as both are suitable methods for finding x
11 a i 80° ii 62° iii 36° iv 9°
b i both 0.173... ii both 0.469...
iii both 0.587... iv both 0.156...
c $\sin\theta^\circ = \cos(90^\circ - \theta^\circ)$
d i 70° ii 31° iii 54° iv 17°
12 a $\sqrt{2}$
b i $\frac{1}{\sqrt{2}}$ ii $\frac{1}{\sqrt{2}}$ iii 1
c $\sqrt{3}$
d i $\frac{1}{2}$ ii $\frac{\sqrt{3}}{2}$ iii $\frac{1}{\sqrt{3}}$ iv $\frac{\sqrt{3}}{2}$
v $\frac{1}{2}$ vi $\sqrt{3}$

Exercise 3G

1 a $x = 2$ b $x = 5$ c $x = 3$ d $x = 4$
e $x = 7$ f $x = 4$ g $x = 0.5$ h $x = 0.2$
2 a 4.10 b 6.81 c 37.88 d 0.98
e 12.80 f 14.43 g 9.52 h 114.83
i 22.05
3 a 13.45 b 16.50 c 57.90 d 26.33
e 15.53 f 38.12 g 9.15 h 32.56
i 21.75 j 49.81 k 47.02 l 28.70
4 a $x = 7.5, y = 6.4$ b $a = 7.5, b = 10.3$
c $a = 6.7, b = 7.8$ d $x = 9.5, y = 12.4$
e $x = 12.4, y = 9.2$ f $x = 21.1, y = 18.8$
g $m = 56.9, n = 58.2$ h $x = 15.4, y = 6.0$
5 40 m
6 3848 m
7 a 23.7 m b 124.9 m
8 a B as student B did not use an approximation in their working out
b Use your calculator and do not round sin 31° during working.
c i difference of 0.42 ii difference of 0.03
9 a i 10.990 ii 11.695
b i 0.34 ii 0.94 iii 0.36
c equal to tan 20°
d i $\frac{b}{c}$ ii $\frac{a}{c}$ iii $\frac{b}{a}$ iv $\frac{b}{a}$
e same as tan θ

Progress quiz

1 a 6.66 b 7.88
2 a $\sqrt{41}$ b $\sqrt{50}$
3 224.5 cm
4 a 10.4 cm b 12.3 cm
5 a AC b BC c $\frac{3}{5}$ d $\frac{4}{3}$
6 a 7.46 b 6.93 c 70.44
7 a 13.80 b 45.75 c 2.21
8 22.48 m
9 a 3.464 cm b 6.9 cm^2

Exercise 3H

1 a 11.54 b 64.16 c 41.41 d 64.53
e 26.57 f 68.20
2 a $\frac{1}{2}$ b 50° c $45^\circ = \tan^{-1}(1)$
3 a 47° b 12° c 18° d 51°
e 24° f 42° g 79° h 13°
i 3°
4 a sine b sine c cosine d tan
5 a 30° b 60° c 45° d 30°
e 45° f 30° g 90° h 50°
i 90° j 55° k 0° l 70°
6 a 34.85° b 19.47° c 64.16° d 75.52°
e 36.87° f 38.94° g 30.96° h 57.99°
i 85.24°
7 a 43° b 31° c 41° d 16°
e 55° f 50° g 49° h 41°
8 17°
9 23.13°
10 25.4°
11 26.6°
12 a 128.7° b 72.5° c 27.3°
13 a 90°, 37°, 53° b 90°, 23°, 67°
c 90°, 16°, 74°
14 45°
15 $\angle ACM = 18.4^\circ \angle ACB = 33.7^\circ$, no it is not half
16 a 18° b 27° c 45° d 5.67 m
e up to 90°

Exercise 3I

1 $a = 65, b = 25$
2 a 22° b 22°

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 a i 

ii 

b yes, $\theta = \alpha$, alternate angles are equal on parallel lines
4 29 m
5 16 m
6 157 m
7 38 m
8 90 m
9 37°
10 6°
11 10°
12 yes by 244.8 m
13 a 6° b 209 m
14 4634 mm
15 15°, 4319 mm
16 1.25 m
17 a 6.86 m
b 26.6°
c i $m = h + y$ ii $y = x \tan\theta$
iii $m = h + x \tan\theta$
18 $A = \frac{1}{2}a^2 \tan\theta$
19 a i 47.5 km ii 16.25 km
b no, $\sin(2 \times \theta) < 2 \times \sin\theta$
c yes, $\sin\left(\frac{1}{2}\theta\right) > \frac{1}{2}\sin\theta$
20 a yes b 12.42 km
c no, after 10 mins will be above 4 km
d 93 km/h or more
21 a 1312 m b 236 km/h

Exercise 3J

1 a 0° b 045° c 090° d 135°
e 180° f 225° g 270° h 315°
2 a 070° b 130° c 255° d 332°
3 a i 040° T ii 220° T
b i 142° T ii 322° T
c i 210° T ii 030° T
d i 288° T ii 108° T
e i 125° T ii 305° T
f i 067° T ii 247° T
g i 330° T ii 150° T
h i 228° T ii 048° T
i i 206° T ii 26° T
4 3.28 km
5 59.45 km
6 3.4 km
7 11 km
8 a 39 km b 320° T
9 a 11.3 km b 070° T
10 310 km
11 3.6 km
12 6.743 km
13 a $180° + a°$ b $a° - 180°$
14 a 320° T b 245° T c 065° T d 238° T
e 278° T
15 a 620 km b 606 km c 129 km
16 a i 115 km ii 96 km
b 158 km
c i 68 km ii 39.5 min

Problems and challenges

1 $P = 4 + 2\sqrt{8}$
2 10 m^2
3 15 cm
4 010° T
5 round peg square hole
6 122° T
7 a i 3, 4, 5 ii 5, 12, 13
b $m^2 + n^2$

Multiple-choice questions

1 A 2 B 3 A 4 C 5 B
6 C 7 D 8 C 9 A 10 B

Short-answer questions

1 a 37 b $\sqrt{12}$ c $\sqrt{50}$
2 4.49 m
3 a 13 cm b 13.93 cm
4 19 m
5 a 4.91 m b $x = 2.83$, $h = 2.65$
6 a 0.64 b 2.25 c 0.72
7 a 7.83 b 48.02 c 50.71
8 28.01 m
9 25 m
10 a 59.45 km b 53.53 km
11 177.91 m
12 053.13°
13 63.2 m
14 5.3 m
15 a 52.5 km b 13.59 km

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 a 2.15 m
b 0.95 m
c i 3.05 m ii yes

2 a 

b 470 m
c 3° d 1530 m

3 a 35 km b 399 km

Chapter 4

Exercise 4A

1 a A (4, 1) B (2, 3) C (0, 3) D $(-2, 2)$
E $(-3, 1)$ F $(-1, 0)$ G $(-3, -2)$
H $(-2, -4)$ I $(0, -3)$ J $(2, -2)$
K $(3, -4)$ L (2, 0)
b i F, L ii C, I
c i D, E ii J, K

2 a 2 b -1 c -4 d -7

3 a 1 b -5 c 3 d 21

4 a

x	-3	-2	-1	0	1	2	3
y	-4	-3	-2	-1	0	1	2

b

x	-3	-2	-1	0	1	2	3
y	0	1	2	3	4	5	6

c

x	-3	-2	-1	0	1	2	3
y	5	3	1	-1	-3	-5	-7

a $y = x - 1$ b $y = x + 3$ c $y = -2x - 1$



d

x	-3	-2	-1	0	1	2	3
y	-9	-7	-5	-3	-1	1	3

e

x	-3	-2	-1	0	1	2	3
y	7	6	5	4	3	2	1

f

x	-3	-2	-1	0	1	2	3
y	9	6	3	0	-3	-6	-9

d $y = 2x - 3$ e $y = -x + 4$ f $y = -3x$



5 a 1, 1 b $-2, 2$ c 4, 8 d $-5, 10$
e 2, 3 f $7, -3$ g $-11, 5$ h $-2, -5$

6 a yes b no c yes d yes
e no f no

7 a no b yes c no d no
e yes f no

8 a $y = x + 2$ b $y = 2x$ c $y = 2x + 1$
d $y = -x + 2$

9 a $y = -\frac{2}{3}x + 2$ b $y = -\frac{3}{4}x - \frac{3}{4}$
c $y = x - 4$ d $y = 2x + 7$
e $y = \frac{1}{3}x - \frac{1}{3}$ f $y = \frac{4}{7}x - \frac{10}{7}$

10 A c, B d, C b, D a

11 a False b True c True d False

12 a For graph to move 1 down from (1, 1) it moves $\frac{1}{2}$ across.

b For graph to move 1 up from (0, -1) it moves $1\frac{1}{2}$ across.

13 a yes b no c no d yes

14 a $y = 2x + 7$ b $y = -x + 20$
c $y = -3x - 10$ d $y = -5x + 4$
e $y = \frac{1}{2}x + \frac{1}{2}$ f $y = -\frac{1}{2}x - \frac{3}{2}$

Exercise 4B

1 a $y = x + 2$ b $y = \frac{1}{2}x - 1$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

c $y = 3x$ **d** $y = -x + 3$



2 **a** **i** 3 **ii** 4 **iii** −3 **iv** −1
v −6 **vi** 4
b **i** 6 **ii** 10 **iii** 1 **iv** 2
v 6 **vi** −3

3 **a** 4 **b** −5 **c** 3 **d** −4

4 **a** 5 **b** −2 **c** 3 **d** 2

5 **a**



b



c



d



e



f



g



h



i



j



k



l



6 **a**



b



c



d



e



f



g



h



i



7 **a**



b



c



d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

e



f



g



h



i



8 **a** 8 m **b** 4 seconds **c**



9 **a** 100 m **b** 12.5 s

10 **a** $1\frac{2}{3}, -2\frac{1}{2}$ **b** $-7, -1\frac{2}{5}$

c $6\frac{1}{2}, -13$ **d** $-\frac{1}{2}, -1$

e $3, -1\frac{1}{2}$ **f** $\frac{1}{3}, -\frac{1}{7}$

11 **a**



b



c



12 (0, 0) is the x- and y-intercept for all values of a and b

13 **a** $x + y = 4$ **b** $x + y = 2$

c $x - y = 3$ **d** $x - y = -1$

e $x + y = k$ **f** $x + y = -k$

14 **a** $\frac{c}{a}, \frac{c}{b}$ **b** $-\frac{cb}{a}, c$ **c** $\frac{c}{a}, -\frac{c}{b}$ **d** $-\frac{c}{b}, \frac{c}{a}$

e $-\frac{c}{b}, \frac{c}{a}$ **f** $\frac{bc}{a}, \frac{bc}{a}$

Exercise 4C

1 **a** 2 **b** −3 **c** 0

2 **a** 3 **b** −2 **c** 0 **d** 0

3 **a** 5 **b** $\frac{1}{3}$ **c** −4 **d** −0.1

4 **a**



b



c



d



e



f



g



h



5 **a**



b



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c



d



e



f



g



h



6



7 **a** $y = -2$ **b** $y = 4$ **c** $x = -2$ **d** $x = 5$
e $y = 1.5$ **f** $x = -6.7$

8 **a** $y = 3$ **b** $x = 5$ **c** $x = -2$ **d** $y = 0$

9 **a** $y = 250$ **b** $y = -45$

10 **a** $(1, 2)$ **b** $(-3, 5)$ **c** $(0, -4)$ **d** $(4, 0)$
e $(0, 0)$ **f** $(1, 3)$ **g** $(3, -27)$ **h** $(5, 40)$
i $(3, 15)$

11 **a** $A = 15$ square units **b** $A = 68$ square units

12 **a** **i** $y = 1$ or $y = -5$ **ii** $y = 0$ or $y = -4$
iii $y = 3\frac{1}{2}$ or $y = -7\frac{1}{2}$
b **i** $y = 1$ or $y = -5$ **ii** $y = 7$ or $y = -11$
iii $y = 9\frac{1}{2}$ or $y = -13\frac{1}{2}$

13 **a** $y = 2x$ **b** $y = -x$ **c** $y = 3x$ **d** $y = -3x$

14 **a** $y = 3x$ **b** $y = 4x$ **c** $y = -5x$ **d** $y = -2x$

15 **a**



b



c



d



e



f



g



h



16 $x = -1, y = -5, y = 5x$

17 **a** (b, c) **b** $m = \frac{c}{b}$

18 $m = \frac{1}{2}$

Exercise 4D

1 **a** 2 **b** $\frac{1}{2}$ **c** 3 **d** -1
e -3 **f** $-\frac{1}{4}$

2 **a** zero **b** negative **c** positive **d** undefined

3 **a** positive, 1 **b** positive, 2
c zero **d** zero **e** negative, $-\frac{2}{3}$
f negative, $-\frac{3}{4}$ **g** undefined **h** undefined
i positive, $\frac{1}{2}$ **j** positive, 3
k positive, 2 **l** negative, -4

4 **a** 2 **b** 1 **c** $-\frac{1}{4}$ **d** $\frac{4}{3}$ **e** 2
f -2 **g** -1 **h** $\frac{1}{2}$ **i** $\frac{3}{2}$
j $-\frac{5}{2}$ **k** $\frac{1}{3}$ **l** $\frac{5}{2}$

5 **A** 1 **B** -2 **C** 1 **D** $\frac{1}{2}$ **E** -2 **F** 3

6 **a** $-\frac{1}{20}$ **b** 17.5 **c** $-\frac{1}{5}$ **d** 7.5

7 **a** 6 **b** -1 **c** 4 **d** $-\frac{3}{2}$

8 300 m

9 **A** 9 **B** -4 **C** -1 **D** 4
E -0.4 **F** 2.4

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 $\frac{7}{11} = \frac{35}{55}, \frac{3}{5} = \frac{33}{55}$ hence $\frac{7}{11} > \frac{3}{5}$ so $\frac{7}{11}$ is steeper

11 a run $= x_2 - x_1$

b rise $= y_2 - y_1$

c $m = \frac{y_2 - y_1}{x_2 - x_1}$

d i $m = \frac{3}{2}$ ii $m = \frac{5}{4}$ iii $m = -\frac{5}{3}$ iv $m = \frac{4}{3}$

e yes, the rise and the run work out regardless

12 a i -1 ii -3

b 4.5

c i 6 ii 2.4 iii $\frac{9}{7}$ iv 7.5

Exercise 4E

1 a i 10 km ii 20 km iii 30 km

b 10 km/h

c 10

d they are the same

2 a 15 mm

b i 6 days ii 20 days

c

t	0	1	2	3	4
h	0	5	10	15	20

d 

e 5

3 a 100 L/hour

b 

c i 100 ii $V = 100t$

d i $V = 150$ L ii $t = 2$ hours

4 a 25 km/h

b 

c i 25 ii $d = 25t$

d i 62.5 km ii 1.6 hours or 1 h 36 min

5 a $d = 50t$ b $g = 2t$ c $C = 1.25n$

d $P = 20t$

6 a 100 km/h b 7 cm/s c 2.5 cm/min

d 49 mm/min

7 a 10.2 L b 72.25 L c 800 km

8 Sally

9 Leopard

10 25 months

11 a i 0 ii 4π iii 12π

b 

c gradient is 2π, the coefficient of r

12 No, $A = \pi r^2$ so area (A) is proportional to square of radius (r^2).

13 a $A = 2h$

b 2 cm^2 increase for each 1 cm increase in height

14 Yes, for any fixed time, e.g. $t = 5$, $s = \frac{d}{5}$

15 1.2 minutes or 72 seconds

16 $\frac{5}{12}$ km

Exercise 4F

1 a $y = 2x + 5$ b $y = 3x - 1$

c $y = -2x + 3$ d $y = -x - 2$

e $y = -\frac{1}{2}x - 10$ f $y = -\frac{2}{3}x + \frac{5}{2}$

2 a 1 b -5 c -5 d -11 e 9

f 2

3 a $y = x + 7$ b $y = -x + 3$

c $y = 2x + 5$

4 a gradient $= 3$, y-intercept $= -4$

b gradient $= -5$, y-intercept $= -2$

c gradient $= -2$, y-intercept $= 3$

d gradient $= \frac{1}{3}$, y-intercept $= 4$

e gradient $= -4$, y-intercept $= 0$

f gradient $= 2$, y-intercept $= 0$

g gradient $= 1$, y-intercept $= 0$

h gradient $= -0.7$, y-intercept $= 0$

5 a $y = -2x + 3$ b $y = 3x - 1$

c $y = -3x + 2$ d $y = x + 2$

e $2x - y = 1$ f $3x + y = 4$

g $x - 3y = 1$ h $2x - 7y = -2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 **a** 1, −2,



b 2, −1,



c $\frac{1}{2}$, 1,



d $-\frac{1}{2}$, 2,



e −3, 3,



f $\frac{3}{2}$, 1,



g $-\frac{4}{3}$, 0,



h $\frac{5}{3}$, $-\frac{1}{3}$,



7 **a** −1, 4,



b 1, −6,



c $-\frac{1}{2}$, 3,



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d $\frac{1}{2}$, -4,



e $\frac{2}{3}$, -2,



f $-\frac{4}{3}$, 4,



g $\frac{1}{3}$, $\frac{4}{3}$,



h $-\frac{2}{3}$, 2,



i $\frac{3}{4}$, -3,



j $-\frac{1}{4}$, 0,



k $\frac{1}{5}$, 0,



l $\frac{1}{2}$, 0,



8 i d ii f iii c iv b v e vi a

9 a



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

b



c



d



e



f



g



g



10 **a** no **b** no **c** yes **d** no

11 c, d, f, h

12 **a** $y = 2x + 2$, y-intercept is 2

b expand brackets and simplify

13 $y = k$

14 $y = -\frac{a}{b}x + \frac{d}{b}, m = -\frac{a}{b}, c = \frac{d}{b}$

15 **a** $y = 2x + 3$ **b** $y = -x + 2$

c $y = \frac{5}{3}x + \frac{2}{3}$ **d** $y = -\frac{2}{5}x - \frac{1}{5}$

Exercise 4G

1 **a** $y = 2x + 5$ **b** $y = 4x - 1$

c $y = -2x + 5$ **d** $y = -x - \frac{1}{2}$

2 **a** 1 **b** 3 **c** 9 **d** 10 **e** 5

f 2

3 **a** $y = x + 3$ **b** $y = x + 2$

c $y = -2x - 4$ **d** $y = 2x - 2$

e $y = 8x + 8$ **f** $y = -x + 4$

4 **a** $y = \frac{3}{4}x + 3$ **b** $y = -\frac{3}{4}x + 3$

c $y = -\frac{5}{4}x + 3$ **d** $y = \frac{3}{2}x + 4$

e $y = \frac{3}{5}x$ **f** $y = -\frac{1}{3}x - 1$

5 **a** $y = 3x + 5$ **b** $y = -2x - 1$

c $y = -3x + 8$ **d** $y = x - 3$

e $y = -3x + 3$ **f** $y = 5x - 1$

g $y = -x + 8$ **h** $y = -3x + 6$

i $y = -2x + 2$ **j** $y = -4x - 9$

6 **a** **i** 2 **ii** $y = 2x + 2$

b **i** -1 **ii** $y = -x + 3$

c **i** -4 **ii** $y = -4x + 11$

d **i** 1 **ii** $y = x - 4$

7 $x = 2\frac{1}{2}$

8 $\frac{3}{5}, -\frac{3}{4}$

9 $V = -20t + 120$, $V = 120$ L initially

10 **a** $y = 5x$ **b** $y = 6.5x + 2$

11 **a** 1 **b** 8 **c** -6 **d** $\frac{5}{2}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

12 **a** $c = 3$ **b** $c = 3$
c no, y-intercept is fixed for any given line

13 $y = \frac{b}{a}x$

14 **a** $y = 2x$ **b** $y = -2x + 4$ **c** $y = 2x + 5$
d $y = -\frac{3}{2}x + 2$ **e** $y = \frac{5}{7}x + \frac{1}{7}$
f $y = -\frac{13}{3}x - \frac{11}{3}$

Progress quiz

1 **a** 2, −4 **b** 3, 6

2 **a** not on line **b** on line

3 **a**



b



4



5 **a** positive, 2 **b** undefined **c** zero
d negative, $-\frac{2}{3}$

6 **a** $m = 2$ **b** $m = -3$

7 **a** 1500 L/hour

b



c **i** 1500 **ii** $V = 1500t$

d **i** 4500 L **ii** 3.5 hours

8 **a** $y = -5x + 8$ **b** $y - 3x = -5$

9 **a** 3, −2,



b $-\frac{2}{3}$, 3



10 **a** $y = 5x + 8$ **b** $y = -3x - 5$
c $y = 2x - 4$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4H

1 **a** 4 **b** 8 **c** 1 **d** -3

2 **a** 5.5 **b** 2.5 **c** -1.5 **d** -2.5

3 **a** 2.24 **b** 8.60 **c** 10.20

4 **a** (3, 3) **b** (2, 2) **c** (1, 5) **d** (4, 1)
e $(-1, 3)$ **f** $(-1, -1)$ **g** (1.5, 1.5)
h (2.5, 2) **i** (0.5, 3) **j** $(-1.5, -2.5)$
k $(-3, -8.5)$ **l** $(0.5, -2.5)$

5 **a** 5.10 **b** 2.83 **c** 5.39 **d** 4.47
e 3.61 **f** 2.83 **g** 8.94 **h** 7.21
i 6.71

6 $B(8, 0)$ $A(-6, 5)$ $A(-6, 9)$

7 **a** $(-3, 1)$ **b** $(1, -4)$ **c** (8, 2.5)

8 **a** 12.8 **b** 24.2

9 (0, 0) (0, 4) (2, 0) (2, 4)

10 **a** $x = \dfrac{x_1 + x_2}{2}$ **b** $y = \dfrac{y_1 + y_2}{2}$
c $M(1, -0.5)$

11 **a** **i** $x_2 - x_1$ **ii** $y_2 - y_1$
iii $\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$
b Answers will vary

12 **a** $\dfrac{1}{3}$

b $\dfrac{1}{3}$

c **i** (1, 1) **ii** $(-2, -0.5)$ **iii** (2, 1.5)
d **i** $(-1, 1)$ **ii** $(-2, 5)$ **iii** $(0.4, -1.8)$
iv $(-2.4, 2.6)$

Exercise 4I

1 **a** yes **b** yes **c** no **d** yes
e no **f** yes

2 **a** $-\dfrac{1}{5}$ **b** $-\dfrac{1}{10}$ **c** $\dfrac{1}{3}$ **d** $\dfrac{1}{6}$

3 **a** yes **b** no **c** no **d** yes

4 **a** $y = 2x + 1$ **b** $y = 4x + 8$
c $y = -x + 5$ **d** $y = -2x - 7$
e $y = \dfrac{2}{3}x - 5$ **f** $y = -\dfrac{4}{5}x + \dfrac{1}{2}$

5 **a** $y = -\dfrac{1}{3}x + 3$ **b** $y = -\dfrac{1}{5}x + 7$

c $y = \dfrac{1}{2}x - 4$ **d** $y = x + 4$

e $y = \dfrac{1}{7}x - \dfrac{1}{2}$ **f** $y = -x + \dfrac{5}{4}$

6 **a** **i** $y = 1$ **ii** $y = -3$ **iii** $y = 6$ **iv** $y = -2$
b **i** $x = 3$ **ii** $x = -4$ **iii** $x = 1$ **iv** $x = -3$
c **i** $x = 2$ **ii** $x = -1$ **iii** $x = 0$ **iv** $x = 3$
d **i** $y = 7$ **ii** $y = -\dfrac{1}{2}$ **iii** $y = 3$ **iv** $y = \dfrac{1}{2}$

7 **a** $y = -3x + 9$ **b** $y = \dfrac{1}{2}x + \dfrac{5}{2}$

c $y = -\dfrac{1}{5}x + 6\dfrac{1}{5}$ **d** $y = x + 5$

8 $y = 0$, $y = x + 3$, $y = -x + 3$

9 $y = 2x - 10$ or $y = 2x + 10$

10 **a** **i** $-\dfrac{3}{2}$ **ii** -5 **iii** 7 **iv** $\dfrac{11}{3}$

b $-\dfrac{b}{a}$

11 **a** **i** $-\dfrac{1}{2}$ **ii** 3

b **i** 1 **ii** $-\dfrac{1}{7}$

12 **a** $y = -\dfrac{1}{2}x + 4$ **b** $y = \dfrac{2}{3}x + 1\dfrac{2}{3}$

c $y = 2x - 3$ **d** $y = -2x - 5\dfrac{1}{2}$

e $y = \dfrac{3}{7}x - \dfrac{5}{7}$ **f** $y = -\dfrac{5}{6}x + \dfrac{1}{6}$

Exercise 4J

1 B

2 **a** **i** \$1200 **ii** \$1500 **iii** \$2200
b $A = 1000 + 100n$

3 **a** 46 **b** 3.5 **c** 2 **d** 3

4 **a** $W = 20x + 400$
b



(Note: This graph should really be a series of points but a full line segment is used as a guide.)

c \$640
d 30

5 **a** $C = 50n + 40$ **b** \$240 **c** \$640

6 **a** $C = 25n + 500$
b



(Note: This graph should really be a series of points but a full line segment is used as a guide.)

c \$1500
d 70

7 **a** $C = 120t + 300$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b



c $1020

d 3 hours

8 **a** $F = 18t + 12$ **b** 3 minutes **c** 2.5 minutes

9 **a** $V = 4000 - 20t$ **b** 2200 L

c 200 minutes or 3 hours 20 minutes

d 2 hours 55 minutes or 175 minutes

10 **a**



b $V = 1500 - 50t$

c the number of litres drained per minute

d 1250 L **e** 15 minutes

11 **a** 80 km/h

b rate changes i.e. new gradient $= 70$, $d = 50 + 70t$

12 **a** 20 m/s **b** -20 m/s **c** 350 m **d** 17.5 sec

e increasing altitude at rate of 20 m/s

13 **a** **i** $C = 0.4n + 20$ **ii** 160

b **i** $P = 0.8n - 20$ **ii** 25 **iii** 120

14 **a** $C = 10x + 6700$ **b** \$8700 **c** 630

d \$11700 **e** 670 **f** $P = 10x - 6700$

g $T = \dfrac{10x - 6700}{x}$ **h** 1340

Exercise 4K

1 **a** (1, 3) **b** $(-1, 2)$ **c** (2, 2)

2 **a** True **b** False **c** False **d** True

3 **a** yes **b** yes **c** yes

4 **a** yes **b** yes **c** no **d** no

e yes **f** yes **g** no **h** no

5 **a** (2, 2) **b** (3, 2) **c** $(2, -4)$ **d** (3, 2)

e (2, 1) **f** (3, 7) **g** (1, 2) **h** (2, 4)

i (4, 1) **j** $(-1, 3)$ **k** $(-1, -5)$

l (1, 3)

6 **a**



(Note: This graph should really be a series of points but a full line segment is used as a guide.)

b 750

7 1200 DVDs



(Note: This graph should really be a series of points but a full line segment is used as a guide.)

8 10 seconds

9 Parallel lines i.e. same gradient

10 **a** (0, 0) **b** (0, 0) **c** no intersection

d no intersection **e** (0, 1) **f** (0, 3)

11 **a** 2 **b** -3

12 **a** (1, 3) **b** $A = 6.75$ units^2

13 **a** 18.75 units^2 **b** 24 units^2 **c** 16 units^2

d 27 units^2 **e** 7 units^2

Problems and challenges

1 20 days

2 2.5 hours

3 (0.5, 5.5), diagonals intersect at their midpoint

4 $k = -2.5$ or 13.5

5 length $AB =$ length AC

6 $A = 13.5$ square units, $P = 20$ units

7 (6, 7)

8 **a** $BD: y = -2x + 1, AC: y = \dfrac{1}{2}x - \dfrac{3}{2}$

b $b = -4, x = 11$ **c** 80 units^2

9 $k = 11.5$ or -10.5

Multiple-choice questions

1 C **2** D **3** A **4** C **5** E

6 B **7** B **8** A **9** D **10** D

Short-answer questions

1 **a** $-2, 4$

b $3, -2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 a



b



c



d



e



f



g



h



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 a 175 km

b 2.5 hours

c



4 a $y = 3$

b $y = -2$

c $x = -4$



d $x = 5$

e $y = 3x$

f $y = -2x$



5 a 2 b -1 c $-\frac{5}{2}$ d $\frac{4}{3}$ e 2

f $-\frac{10}{3}$

6 a 2000 L/hr

b



c $V = 2000t$

d 2.5 hours

7 a Gradient $= 2$ y-intercept $= 3$



b Gradient $= -3$ y-intercept $= 7$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c Gradient $= -\frac{2}{3}$ y-intercept $= 3$



d Gradient $= \frac{3}{2}$ y-intercept $= 4$



8 **a** $y = 3x + 2$ **b** $y = -2x + 6$

c $y = \frac{4}{3}x - 5$

9 **a** $y = \frac{x}{2} - 1$ **b** $y = -3x + 6$

c $y = 3x - 2$ **d** $y = -2x + 2$

10 **a** **i** $M\,(4, 6)$ **ii** 5.66

b **i** $M\,(7.5, 4.5)$ **ii** 7.07

c **i** $M\,(0, 4)$ **ii** 7.21

d **i** $M\,(-3, 2.5)$ **ii** 9.85

11 **a** $n = 9$ **b** $n = 10$ **c** $n = 6$

12 **a** $y = 2x + 4$ **b** $y = -x - 3$

c $y = -\frac{1}{2}x - 1$ **d** $y = 3x + 4$

e $y = 3x + 1$

f $3x + 2y = 8$ or $y = -\frac{3x}{2} + 4$

13 **a** no **b** yes

14 **a** (2, 0) **b** $(-2, 4)$

Extended-response questions

1 **a** **i** \$40/hr, \$80

ii



iii \$180

iv 5 hours

b **i** $C = 65 + 45n$

ii



c (3, 200)

d After 3 hours

2 **a** $C = 8v + 90$

b **i** \$90 **ii** \$8 per vase

c 23 vases

Chapter 5

Exercise 5A

1 **a** 50 mm **b** 280 cm **c** 52.1 cm **d** 0.837 m

e 4600 m **f** 2.17 km

2 825 cm, 2.25 cm

3 **a** $a = 3, b = 6$ **b** $a = 12, b = 4$

c $a = 6.2\ b = 2$

4 **a** 12 m **b** 27 cm **c** 24 mm **d** 18 km

e 10 m **f** 36 cm

5 **a** 90 cm **b** 80 cm **c** 170 cm **d** 30.57 m

e 25.5 cm **f** 15.4 km

6 **a** 9 cm **b** 4015 m **c** 102.1 cm

7 **a** 8000 mm **b** 110 m **c** 1 cm **d** 20 mm

e 0.284 km **f** 62.743 km

8 **a** $x = 4$ **b** $x = 2.2$ **c** $x = 14$ **d** $x = 9.5$

e $x = 6$ **f** $x = 4.2$

9 108 m

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 **a** 86 cm **b** 13.6 m **c** 40.4 cm
11 **a** $x = 2$ **b** $x = 2.1$ **c** $x = 7$
12 88 cm
13 **a** $P = 2a + 2b$ **b** $P = 4x$ **c** $P = 2a + b$
d $P = 2x + 2y$ **e** $P = 4(a + b)$
f $P = 2x$
14 All vertical sides add to 13 cm and all horizontal sides add to 10 cm
15 **a** 25 cm, 75 cm **b** 40 cm, 60 cm
c 62.5 cm, 37.5 cm **d** 10 cm, 20 cm, 30 cm, 40 cm
16 **a** **i** 96 cm **ii** 104 cm **iii** 120 cm
b $P = 4\ (20 + 2x) \quad \therefore P = 8x + 80$
c **i** 109.6 cm **ii** 136.4 cm
d **i** $x = 1.25$ **ii** $x = 2.75$
e No, as with no frame the picture has a perimeter of 80 cm

Exercise 5B

1 **a** 2.8 cm **b** 96 mm
2 **a** 6π **b** 12π **c** 17.5π **d** $3 + 2\pi$
e $12 + 3\pi$ **f** $10 + 4\pi$ **g** $8 + 2\pi$ **h** $3 + \frac{3\pi}{4}$
i $7 + \frac{\pi}{12}$
3 **a** $\frac{1}{4}$ **b** $\frac{1}{2}$ **c** $\frac{3}{4}$ **d** $\frac{1}{6}$
e $\frac{5}{12}$ **f** $\frac{5}{8}$
4 **a** 50.27 m **b** 87.96 cm **c** 9.42 mm **d** 12.57 km
5 **a** 9.14 cm **b** 14.94 m **c** 33.13 cm **d** 10.00 cm
e 20.05 m **f** 106.73 km
6 **a** 12.56 m **b** 62.8 cm **c** 22 mm **d** 44 m
7 **a** 14π **b** 4π **c** 41π **d** 10π
e 20π **f** 11π
8 **a** $8 + 2\pi$ **b** $4 + 2\pi$ **c** $10\pi + 20$
d $12 + 2\pi$ **e** $5\pi + 6$ **f** $5\pi + 8$
9 28.27 m
10 4.1 m
11 31.42 cm
12 **a** 188.50 cm
b **i** 376.99 cm **ii** 1979.20 cm
c 531
13 **a** 11.5π m **b** $2.4 + 0.6\pi$
c $21 + \frac{7\pi}{2}$ **d** $5 + 1.875\pi$
e $40 + 20\pi$ **f** $23 + 5.75\pi$
14 **a** $r = \frac{C}{2\pi}$
b **i** 1.6 cm **ii** 4.0 m
c $d = \frac{C}{\pi}$
d 67 cm
15 **a** 131.95 m
b 791.68 m
c **i** 3.79 **ii** 15.16
d 63.66 m

Exercise 5C

1 **a** 6 **b** 16 **c** 12 **d** 1
e 12 **f** 153
2 **a** rectangle **b** circle **c** rhombus/kite
d sector of circle **e** triangle **f** trapezium
g parallelogram **h** square **i** semicircle
3 **a** $\frac{1}{4}$ **b** $\frac{1}{3}$ **c** $\frac{3}{4}$ **d** $\frac{1}{6}$
e $\frac{5}{8}$ **f** $\frac{5}{18}$
4 **a** 200 mm^2 **b** 5 cm^2 **c** 21 000 cm^2
d 21 m^2 **e** 1000 m^2 **f** 3.2 km^2
5 **a** 24 m^2 **b** 10.5 cm^2 **c** 20 km^2 **d** 25.2 m^2
e 15 m^2 **f** 36.8 m^2
6 **a** 21 mm^2 **b** 12 cm^2 **c** 17 cm^2 **d** 63 m^2
e 6.205 m^2 **f** 15.19 km^2
7 **a** 12.25 cm^2 **b** 3.04 m^2 **c** 0.09 cm^2
d 6.5 mm^2 **e** 18 cm^2 **f** 2.4613 cm^2
8 **a** 21.23 m^2 **b** 216.51 km^2 **c** 196.07 cm^2
9 **a** 7.07 m^2 **b** 157.08 cm^2 **c** 19.24 cm^2
d 84.82 m^2 **e** 26.53 m^2 **f** 62.86 m^2
10 **a** 1.5×10^{10} (15 000 000 000) cm^2 **b** 5 mm^2
c 0.075 m^2
11 500 000 m^2
12 0.175 km^2
13 0.51 m^2
14 12.89%
15 31%
16 **a** $r = \sqrt{\frac{A}{\pi}}$
b **i** 1.3 cm **ii** 1.5 m **iii** 2.5 km
17 **a** **i** 64° **ii** 318°
b as angle would be greater than 360° which is not possible (28.3 m^2 is the largest area possible, i.e. full circle)
18 **a** **i** 1.5 m **ii** 1.5 m
b 78 m^2
c yes
19 46.7%

Exercise 5D

1 **a** semicircle and rectangle
b triangle and semicircle
c rhombus and parallelogram

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2

a $P = 2 \times 5 + 3 + \frac{1}{2} \times 2\pi r$
$= 10 + 3 + 1.5\pi$
$= 13 + 1.5\pi$
$= 17.7$ m

$A = bh + \frac{1}{2}\pi r^2$
$= 5 \times 2 + \frac{1}{2} \times \pi \times 1.5^2$
$= 10 + 1.125\pi$
$= 13.5$ m^2

b $P = 20 + 12 + 12 + 10 + 6$
$= 60$ cm

$A = lw - \frac{1}{2}bh$
$= 12 \times 20 - \frac{1}{2} \times 8 \times 6$
$= 240 - 24$
$= 216$ cm^2

3 **a** 46 m, 97 m^2 **b** 34 m, 76 m^2
c 40 m, 90 m^2 **d** 18.28 m, 22.28 m^2
e 19.42 m, 26.14 m^2 **f** 85.42 mm, 326.37 mm^2

4 **a** 17 cm^2 **b** 3.5 cm^2 **c** 21.74 cm^2
d 6.75 m^2 **e** 189 cm^2 **f** 115 cm^2

5 **a** 108 m^2 **b** 33 cm^2 **c** 98 m^2
d 300 m^2 **e** 16 cm^2 **f** 22.5 m^2

6 **a** 37.70 m, 92.55 m^2 **b** 20.57 mm, 16 mm^2
c 18.00 cm, 11.61 cm^2 **d** 12.57 m, 6.28 m^2
e 25.71 cm, 23.14 cm^2 **f** 33.56 m, 83.90 m^2

7 **a** 90 cm^2 **b** 15 m^2 **c** 9 m^2 **d** 7.51 cm^2
e 7.95 m^2 **f** 180.03 cm^2 **g** 8.74 mm^2
h 21.99 cm^2 **i** 23.83 mm^2

8 189.27 m^2

9 68.67 cm^2

10 **a** 136.3 cm^2 **b** 42.4 m^2 **c** 345.6 m^2

11 8 cm

12 **a** $36 + 18\pi$ **b** 16 **c** $12 - \frac{\pi}{8}$
d 2π **e** $12.96 + 3.24\pi$ **f** $25 + \frac{75\pi}{4}$

13 7.1 cm

14 **a** hypotenuse (diameter) would equal 4.24 not 5
b hypotenuse (sloped edge) should be 13 cm not 14 cm
c hypotenuse (diameter) should be 5.83 not 8 m

15 5267.1 cm^2

16 **a** 34 cm, 18 cm **b** 226.9 cm^2
c 385.1 cm^2

Exercise 5E

1 **a** Cube



b Rectangular prism



c Triangular prism



d Square pyramid



e Tetrahedron (triangular pyramid)



f Pentagonal pyramid

2 **a** TSA $= 2 \times 8 \times 7 + 2 \times 8 \times 3 + 2 \times 7 \times 3$
$= 112 + 48 + 42$
$= 202$ m^2

b TSA $= 2 \times \frac{1}{2} \times 4 \times 3 + 5 \times 7 + 4 \times 7 + 3 \times 7$
$= 12 + 35 + 28 + 21$
$= 96$ cm^2

3 **a** 52 cm^2 **b** 242 cm^2 **c** 76 m^2 **d** 192 cm^2
e 68.16 m^2 **f** 85.76 m^2

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 a 39 mm^2 b 224 cm^2 c 9.01 m^2
5 a 108 cm^2 b 199.8 cm^2
c 0.96 m^2 d 44.2 m^2
e 22 cm^2 f 28 cm^2
6 6 m^2
7 14.54 m^2
8 34 000 cm^2
9 a 44.4 m^2 b 4.44 L
10 a 1400 cm^2 b 1152 cm^2
11 a 10 cm^2 b 16 cm^2
c 24 cm^2 
12 a [6, 10, 14, 18, 22, 26, 30, 34, 38]
b $S = 4n + 2$ c Answers will vary
13 a 17.7 cm^2 b 96 m^2 c 204 cm^2 d 97.9 m^2
e 137.8 cm^2 f 43.3 mm^2

Exercise 5F

1 a 

b 

2 a 22 cm by 10 cm b 12.57 cm by 8 cm
c 50.27 m by 9 m
3 a 25.13 m^2 b 471.24 cm^2 c 50.27 m^2
4 a 44.0 cm^2 b 603.2 cm^2 c 113.1 m^2
5 395.84 cm^2
6 a 251.33 cm^2 b 207.35 mm^2
c 24.13 m^2
7 a 54.56 m^2 b 218.23 m^2 c 63.98 cm^2
d 71.91 cm^2 e 270.80 m^2
f 313.65 km^2 g 326.41 m^2
h 593.92 m^2 i 43.71 mm^2
8 7539.82 cm^2
9 80 424.8 cm^2
10 a 18 849.556 cm^2
b i 1.88 m^2 ii 37.70 m^2
c 239
11 a 8π m^2 b 150π cm^2 c 16π m^2
12 Half cylinder is more than half surface area as it includes new rectangular surface.
13 a $\left(\frac{135\pi}{2} + 36\right)$ cm^2 b $\left(\frac{70\pi}{3} + 12\right)$ cm^2
c $\left(\frac{29\pi}{12} + 4\right)$ m^2

Progress quiz

1 a 3.54 m b 15.2 cm
2 a C = 25.1 mm, A = 50.3 mm^2
b C = 37.7 cm, A = 113.1 cm^2
3 a 15 cm^2 b 72 cm^2 c 16π cm^2
4 850 cm^2
5 a P = 29.71 m A = 63.27 m^2
b P = 32 cm A = 44 cm^2
6 103.67 m^2
7 a 216 cm^2 b 198.5 cm^2 c 64 cm^2
8 a 4.16 m^2 b 258.50 cm^2

Exercise 5G

1 a , 6 cm b , 10 cm
c , 2 m d , 5 mm
e  , 14 cm f  , 10 m
2 a square b triangle c rectangle d trapezium
e hexagon f triangle
3 a 3000 mm^3 b 2 cm^3 c 8 700 000 cm^3
d 0.0059 m^3 e 10 000 m^3
f 0.0000217 km^3 g 3000 mL h 200 L
i 3.5 L j 21 mL k 37 kL l 42.9 ML
4 a 8 cm^3 b 84 m^3 c 21 mm^3
5 a 4 cm^3 b 10.5 m^3 c 11.96 cm^3
d 29 cm^3 e 14.88 m^3 f 8.1351 cm^3
g 108 m^3 h 29.82 m^3 i 0.382044 cm^3
6 a 75 m^3 b 30 cm^3 c 1.25 cm^3
7 a 16 cm^3 b 42.875 m^3 c 15 cm^3
8 a 8 L b 0.36 L c 0.48 L

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 8000 cm^3
10 0.19 m^3
11 Yes, the tank only holds 20 L
12 a 67.2 cm^3 b 28 m^3 c 8.9 km^3 d 28 m^3
e 0.4 m^3 f 29232 mm^3
13 a 20 L b 75 000 L c 8000 L
14 a 55 m^2 b 825 m^3
15 a i 1000 ii $\frac{1}{1000}$ iii 1000
b i 1000 000 ii 1000 iii 1000 000 or 1000^2
16 a $V = x^2h$ b $V = s^3$ c $V = 6t^3$
17 a Answers will vary b $\frac{1}{3}$
c Answers will vary

Exercise 5H

1 a $r = 4$, $h = 10$ b $r = 2.6$, $h = 11.1$
c $r = 2.9$, $h = 12.8$ d $r = 9$, $h = 23$
e $r = 5.8$, $h = 15.1$ f $r = 10.65$, $h = 10.4$
2 a 12.57 cm^2 b 8.04 m^2 c 78.54 cm^2
d 2.54 km^2
3 a 2 L b 4.3 mL c 3700 cm^3 d 1000 L
e 38 m^3 f 200 mL
4 a 226.19 cm^3 b 18.85 m^3 c 137.44 m^3
d 100.53 cm^3 e 8.48 m^3 f 68.05 m^3
5 a 13 L b 503 L c 20 L d 4712 L
e 589 049 L f 754 L
6 a 25.133 m^3 b 25 133 L
7 37 699 L
8 Cylinder by 0.57 m^3
9 a 502.65 cm^3 b 1.02 m^3 c 294.52 m^3
d 35 342.92 m^3 e 47.12 cm^3
f 1017.88 cm^3
10 a 0.707 b 2.523
11 a 160π m^3 b 320π cm^3 c 54π km^3
d $\frac{3\pi}{4}$ cm^3 e 1500π cm^3 f 144π mm^3
12 A number of answers. Require $h = 2\pi r$.
13 a 113.10 cm^3 b 10471.98 m^3
c 3.73 m^3 d 20.60 cm^3 e 858.41 cm^3
f 341.29 m^3

Problems and challenges

1 100 L
2 non-shaded is half the shaded area
3 163.4 m^2
4 $\sqrt{200}$ cm = 14.14 cm
5 $\frac{1}{6}$ cm
6 16 days
7 $V = 2\pi^2 r^3$
8 $h = \frac{1 - r^2}{r}$
9 Answers can vary but $1000 = \pi r^2$ h needs to hold true for r and h in centimetres. Designers need to consider production costs, material costs and keeping the surface area to a miniumum so that they can maximise profits as well as the ability to use, stack and market their products. If the container is for cold storage then fitting into a standard fridge door is also a consideration.

Multiple-choice questions

1 B 2 C 3 E 4 B 5 A
6 D 7 B 8 E 9 C 10 E

Short-answer questions

1 a 380 cm b 1270 m c 2.73 cm^2 d 52 000 cm^2
e 10 000 cm^3 f 53.1 cm^3 g 3.1 L
h 43 mL i 2830 L
2 a 14 m b 51 mm c 16.2 cm
3 a 4 cm^2 b 1122 mm^2 c 30.34 mm^2
d 7.5 m^2 e 15 cm^2 f 3 cm^2
4 a 2.5 m^2 b 37.4 m^2
5 a $A = 28.27$ cm^2, $P = 18.85$ cm
b $A = 5.38$ m^2, $P = 9.51$ m
6 a $P = 15.24$ m, $A = 13.09$ m^2
b $P = 14.10$ m, $A = 10.39$ m^2
c $P = 24.76$ km, $A = 33.51$ km^2
7 a 8.86 m, 4.63 m^2 b 45.56 cm, 128.54 cm^2
8 a 46 cm^2 b 114 m^2
9 a 659.73 mm^2 b 30.21 m^2
10 a 30 cm^3 b 54 m^3 c 31.42 mm^3

Extended-response questions

1 a 517.08 cm b \$65 c 15853.98 cm^2
d 1.58 m^2, claim is correct
2 a 1 cm b 15.71 cm^2 c 125 680 cm^3
d 0.125 68 m^3 e 18.85 cm f 15 m^2
g \$1200

Semester review 1

Reviewing number and financial mathematics

Multiple-choice questions

1 B 2 E 3 D 4 D 5 A

Short-answer questions

1 a $\frac{19}{28}$ b $\frac{7}{9}$ c $\frac{3}{8}$ d $1\frac{4}{5}$
2 a 60% b 31.25% c 10% d 25%
3 a 5 : 3 b 55 km/h c 2.4 mL/h
4 \$892

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response question

a i $17 500 ii $23 520 iii 9 years iv 27%
b $23635.69
c i Jim by $116 ii Jim by $922

Linear and simultaneous equations

Multiple-choice questions

1 E **2** A **3** C **4** B **5** D

Short-answer questions

1 **a** $x = 6$ **b** $x > \frac{9}{2}$ **c** $m = \frac{3}{8}$ **d** $y = -1$
e $a \leq \frac{1}{11}$ **f** $x = -\frac{3}{14}$

2 **a** $\frac{m-3}{2} = 6$ **b** Noah gets $15 pocket money

3 **a** 155 **b** $I = \frac{2S}{n} - a$ **c** 18

4 **a** $x = 6, y = 3$ **b** $x = -1, y = -5$
c $x = 5, y = -2$ **d** $x = -3, y = 4$

Extended-response question

a i $12x + 20 > 74$ ii 5 games
b i Let $\$x$ be the cost of a raffle ticket and $\$y$ the cost of a badge.
ii $5x + 2y = 11.5$ and $4x + 3y = 12$
iii A raffle ticket costs $1.50 and a badge costs $2.

Pythagoras' theorem and trigonometry

Multiple-choice questions

1 D **2** A **3** C **4** A **5** E

Short-answer questions

1 **a** $x = 15.1$ **b** $x = 5.7$ **c** $x = 11.2$ **d** $\theta = 29.5$
2 **a** $x = 13, y = 14.7$ **b** $x = 9.9$
3 **a** 19.21 m **b** 38.7°
4 **a** 16.3 km west **b** 115°

Extended-response question

a 17.75 m
b 14.3°
c i 18.8 m ii 6.8 s

Linear relations

Multiple-choice questions

1 C **2** D **3** B **4** C **5** A

Short-answer questions

1 **a**


b


c


2 **a** $\frac{2}{3}$ **b** -3 **c** -2 **d** $\frac{4}{3}$

3 **a** $y = -3x + 6$ **b** $y = 3x - 1$
c $y = 2x$ **d** $y = -\frac{1}{3}x + 2$

4 (3, 2)

Extended-response question

a 12 kg/h
b $S = 180 - 12t$
c


d 15 hours
e i $P = 40 + 25h$ ii $415

Measurement

Multiple-choice questions

1 C **2** E **3** D **4** A **5** A

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 a 24.57 m^2 b 36 cm^2
2 4 tins
3 a 216 m^2 b 25.45 m^2
4 a $x = 4$ b $y = 8.5$

Extended-response question

a 45.71 m^2
b i 0.0377 m^2 ii 3.77 m^2
c 1213
d 37.85 m^3
e 19.45 m^3

Chapter 6

Exercise 6A

1 a 25 b 8 c 27 d 16
2 a 3 b 6 c 1.2 d -7 e $\frac{2}{3}$
f y g w h t
3 a 3 b 8 c 7 d 4
e 11 f 13 g 9 h 2
4 a 2, 3 b 3, 5 c 2, 3, 5 d 7, 11
5 a $a \times a \times a \times a$ b $b \times b \times b$
c $x \times x \times x$
d $x \times p \times x \times p \times x \times p \times x \times p \times x \times p \times x \times p$
e $5 \times a \times 5 \times a \times 5 \times a \times 5 \times a$
f $3 \times y \times 3 \times y \times 3 \times y$
g $4 \times x \times x \times x \times y \times y \times y \times y \times y$
h $p \times q \times p \times q$ i $-3 \times s \times s \times s \times t \times t$
j $6 \times x \times x \times x \times x \times y \times y \times y \times y \times y$
k $5 \times y \times z \times y \times z \times y \times z \times y \times z \times y \times z \times y \times z$
l $4 \times a \times b \times a \times b \times a \times b$
6 a 36 b 16 c 243 d 12
e -8 f -1 g 81 h 25
i $\frac{8}{27}$ j $\frac{9}{16}$ k $\frac{1}{216}$ l $\frac{25}{4}$
m $-\frac{8}{27}$ n $\frac{81}{256}$ o $\frac{1}{16}$ p $-\frac{3125}{32}$
7 a 3^3 b 8^6 c y^2 d $3x^3$
e $4c^5$ f 5^3d^2 g x^2y^3 h 7^3b^2
8 a $\left(\frac{2}{3}\right)^4$ b $\left(\frac{3}{5}\right)^5$ c $\left(\frac{4}{7}\right)^2\left(\frac{1}{5}\right)^4$
d $\left(\frac{7x}{9}\right)^2\left(\frac{y}{4}\right)^3$
9 a $3^3x^3y^2$ b $(3x)^2(2y)^2$ or $3^2 2^2 x^2 y^2$
c $(4d)^2(2e)^2$ or $4^2 2^2 d^2 e^2$ d $6^3b^2y^3$
e $(3pq)^4$ or $3^4p^4q^4$ f $(7mn)^3$ or $7^3m^3n^3$
10 a 2×5 b 2^3 c $2^4 \times 3^2$ d 2^9
e $2^3 \times 3^3$ f $2^2 \times 5^3$
11 a 36 b -216 c 1 d $-\frac{8}{27}$
e -18 f 15 g -36 h 216
12 a 4 b 8 c 5 d 2
e -4 f -2 g $\frac{1}{2}$ h 4
13 a i 10 mins ii 20 mins iii 30 mins
b $2^{24} = 16\,777\,216$ cells
14 a $1000 \times 3^5 = \$243\,000$ b 5 years
15 7 months
16 a i 9 ii 9 iii -9 iv -9
b Same signs give positive when multiplying
c A positive answer is multiplied by the negative one out the front
17 a i 8 ii -8 iii -8 iv 8
b i A positive cubed is positive
iv A negative answer is multiplied by negative
c ii A negative number cubed will be negative
iii A positive answer is multiplied by negative one
18 a $\frac{1}{8}$ b $\frac{1}{16}$ c $\frac{1}{125}$ d $\frac{1}{64}$
e $\frac{49}{100}$ f $\frac{81}{16}$ g $\frac{169}{25}$ h $\frac{12769}{100}$
i $\frac{289}{25}$
19 a LCM = 12, HCF = 2 b LCM = 84, HCF = 14
c LCM = 72, HCF = 12 d LCM = 30, HCF = 5
e LCM = 360, HCF = 10 f LCM = 300, HCF = 10
g LCM = 1764, HCF = 14
h LCM = 13068, HCF = 198

Exercise 6B

1 a multiply, base, add b divide, base, subtract
2 a $3 \times 3 \times 3 \times 3 \times 3 \times 3 = 3^6$
b $6 \times 6 \times 6 \times 6 \times 6 \times 6 \times 6 = 6^7$
c $\frac{5 \times 5 \times 5 \times 5 \times 5}{5 \times 5} = 5^2$
d $\frac{9 \times 9 \times 9 \times 9}{9 \times 9} = 9^2$
3 a True b True c False d False
e True f False g False h True
4 a 2^7 b 5^9 c 7^6 d 8^{10}
e 3^8 f 6^{14} g 3^3 h 6^5
i 5^3 j 10 k 9^3 l $(-2)^2$
5 a x^7 b a^9 c t^8 d y^5
e d^3 f y^7 g b^8 h q^{11}
i x^7y^5 j x^9y^4 k $5x^4y^9$ l $4x^2y^5z$
m $15m^5$ n $8e^6f^4$ o $20c^7d^2$ p $18y^2z^7$
6 a a^2 b x^3 c q^{10} d d
e $2b^5$ f $\frac{d^5}{3}$ g $2a^7$ h $2y^8$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

i $9m$ j $14x^3$ k $5y^2$ l $6a$

m $\frac{m^5}{4}$ n $\frac{w}{5}$ o $\frac{a}{5}$ p $\frac{x^4}{9}$

q $\frac{4x^6y^3}{3}$ r $\frac{3st^2}{7}$ s $\frac{4mn}{3}$ t $-5x$

7 a b^6 b y^6 c c^7 d x e t

f p^6 g d^6 h x^{10} i $4x^2y^3$

j $6b^2g$ k $3m^5n^6$ l p^5q^4

8 a $\frac{m^5}{n^5}$ b $\frac{x^4}{y^2}$ c a^3b^3 d $\frac{6a^5}{c^7}$

e $6f^6$ f $12x^4b^2$ g $6k^3m^3$ h $\frac{15x^4y}{2}$

i $\frac{3m^2n^3}{2}$

9 a 12 b 8 c 3 d 3 e 1

f 18 g 12 h 11 i 4

j 15 k 2 l 39

10 a $7^2 = 49$ b 10 c $13^2 = 169$

d $2^3 = 8$ e 101 f $200^2 = 40\,000$

g $7 \times 31 = 217$ h $43 \times 50^2 = 7500$

11 a 7 ways b 14 ways

12 a a^5, power of one not added

b x^6, power of one not subtracted

c $\frac{a^2}{2}$, $3 \div 6$ is $\frac{1}{2}$ not 2

d $\frac{x^4}{2}$, numerator power is larger hence x^4 in numerator

e $6x^{11}$, mutiply coefficients not add

f $= a^3 \times a = a^4$, order of operations done incorrectly

13 a $4x$ b $12x^2$ c $10x^3$ d $-4x$

e $40x^6$ f $\frac{5x}{4}$ g $\frac{8}{5}$ h $-20x^4$

14 a 2^{x+y} b 5^{a+b} c t^{x+y} d 3^{x-y}

e 10^{p-y} f 2^{p+q-r} g 10^{p-q-r}

h 2^{5a} i $a^{3x-2}b^{x+3}$ j $a^{x+y}b^{x+y}$

k $a^{x-y}b^{y-x}$ l $w^{2-x}b^{x+3}$

m a^{x+y-2} n p^aq^{b-5} o $4m^{y-3-2x}$

15 Answers will vary

16 Answers will vary

Exercise 6C

1 a multiply b 1

2 a 16, 8, 4, 2, 1 b 64, 16, 4, 1

3 a $(4 \times 4) \times (4 \times 4) \times (4 \times 4) = 4^6$

b $(12 \times 12 \times 12) \times (12 \times 12 \times 12) \times (12 \times 12 \times 12) = 12^9$

c $(x \times x \times x \times x \times x) \times (x \times x \times x \times x \times x) = x^8$

d $(a \times a) \times (a \times a) \times (a \times a) \times (a \times a) \times (a \times a) = a^{10}$

4 a y^{12} b m^{18} c x^{10} d b^{12}

e 3^6 f 4^{15} g 3^{30} h 7^{10}

i $5m^{16}$ j $4q^{28}$ k $-3c^{10}$ l $2j^{24}$

5 a 1 b 1 c 1 d 1

e -1 f 1 g 1 h 1 i 5

j -3 k 4 l -6 m 1 n 3

o 1 p 0

6 a 4^7 b 3^9 c x d y^{13}

e b^{14} f a^{10} g d^{24} h y^{16}

i z^{25} j $a^{11}f^{13}$ k $x^{14}y^5$ l $5rs^8$

7 a 7^2 b 4 c 3^8 d 1

e y^3 f h^2 g b^6 h x^5

i y^6

8 a $\frac{2}{x^5}$ b $\frac{10}{x^3}$ c $3x^8$ d $\frac{d^2e}{2}$

e $\frac{2m^6n}{5}$ f $\frac{a^{12}}{8}$

9 a i 400 ii 6400 iii 100

b i 800 ii 12 800 iii 102 400

c 13 years

10 5 ways

11 a 4 b 1000 c 1 d 1 e 4 f 1

12 a 4×5 not $4 + 5$, a^{20}

b power of 2 only applies to x^3, $3x^6$

c power zero applies to whole bracket, 1

13 a i 2^{24} ii $(-2)^{30} = 2^{30}$ iii x^{84}

iv a^{48}

b i 2^{abc} ii a^{mnp} iii x^{6yz}

14 a Answers will vary b Answers will vary

15 a 2^{12} b 2^{15} c 3^6 d 3^{20}

e 5^{10} f 3^{50} g 2^{72} h 7^{80}

i 10^{50}

Exercise 6D

1 a $a^m \times b^m$ b $\frac{a^m}{b^m}$

2 a $5a \times 5a \times 5a$

$= 5 \times 5 \times 5 \times a \times a \times a$

$= 5^3 \times a^3$

b $ab \times ab \times ab \times ab$

$= a \times a \times a \times a \times b \times b \times b \times b$

$= a^4 \times b^4$

c $\frac{x}{6} \times \frac{x}{6} \times \frac{x}{6}$

$= \frac{x \times x \times x}{6 \times 6 \times 6}$

$= \frac{x^3}{6^3}$

d $\frac{a}{b} \times \frac{a}{b} \times \frac{a}{b} \times \frac{a}{b} \times \frac{a}{b}$

$= \frac{a \times a \times a \times a \times a}{b \times b \times b \times b \times b}$

$= \frac{a^5}{b^5}$

3 a $8x^3$ b $25y^2$ c $64a^6$ d $9r^2$

e $-81b^4$ f $-343r^3$ g $(-2)^4h^8 = 16h^8$

h $625c^8d^{12}$ i $32x^{15}y^{10}$ j $9p^6q^{12}$ k $2x^6y^2$ l 1

m $-27w^9y^3$ n $-4p^8q^2r^2$ o $25s^{14}t^2$

p $8x^{12}y^3z^9$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 a $\frac{p^3}{q^3}$ b $\frac{x^4}{y^4}$ c $\frac{64}{y^3}$ d $\frac{625}{p^8}$
e $\frac{4}{r^6}$ f $\frac{s^6}{49}$ g $\frac{32m^5}{n^5}$ h $\frac{8a^6}{27}$
i $\frac{27n^9}{8m^{12}}$ j $\frac{16r^4}{n^4}$ k $\frac{9f^2}{64g^{10}}$ l $\frac{25w^8y^2}{4x^6}$
m $\frac{9x^2}{4y^6g^{10}}$ n $\frac{27k^3m^9}{64n^{21}}$ o $-\frac{25w^8y^2}{4x^6}$
p $\frac{9x^4y^6}{4a^{10}b^6}$

5 a $9ab^2$ b $27ab^6$ c $-12a^8b^8$ d $54x^6y^9$
e $-64b^6c^{15}d^3$ f $8a^4$ g $9a^5$
h $-40a^{15}b^3$ i $160m^{15}p^5t^{10}$
j $-49d^4f^8g^2$ k $1024x^{12}y^3z^9$
l $-16a^8b^7$

6 a x^{24} b $256x^{24}$ c $a^{17}b^8$ d $a^{10}b^{11}$
e $8m^5n^3$ f $12c^8d^7$ g $\frac{-27x^6}{125a^{15}b^9}$
h $-3a^4b^5$ i $15n$ j $a^{11}bc^5$ k $x^{11}y^2z$
l $\frac{r^9t^{10}}{s}$

7 a i 8 ii 125
b $N = \frac{t^3}{8}$
c i 27 ii 8
d i 8 ii 2

8 a 2 b 4 c 2 d 2 e 1
f 14

9 a By simplifying, there are smaller numbers to raise to powers
b i 8 ii 16 iii $\frac{1}{81}$ iv $\frac{1}{1000}$

10 a $F, (-2)^2 = +(2)^2$ b $T, (-3)^3 = -(3)^3$
c $T, (-5)^5 = -(5)^5$ d $F, (-4)^4 = +(4)^4$

11 a 25
b 13
c no
d no, $(3-2)^2 \neq 3^2 - 2^2$
e i T ii F iii T iv F

Exercise 6E

1 a $\frac{1}{2^2}$ b $\frac{1}{3^2}$ c $\frac{1}{5^3}$ d $\frac{1}{3^3}$

2 a

Index form	3^4	3^3	3^2	3^1
Whole number or fraction	81	27	9	3

Index form	3^0	3^{-1}	3^{-2}	3^{-3}
Whole number or fraction	1	$\frac{1}{3}$	$\frac{1}{9} = \frac{1}{3^2}$	$\frac{1}{27} = \frac{1}{3^3}$

b

Index form	10^4	10^3	10^2	10^1
Whole number or fraction	10000	1000	100	10

Index form	10^0	10^{-1}	10^{-2}	10^{-3}
Whole number or fraction	1	$\frac{1}{10}$	$\frac{1}{100} = \frac{1}{10^2}$	$\frac{1}{1000} = \frac{1}{10^3}$

3 a $\frac{1}{x}$ b $\frac{1}{a^4}$ c $\frac{1}{b^6}$ d $\frac{1}{25}$
e $\frac{1}{64}$ f $\frac{1}{9}$ g $\frac{5}{x^2}$ h $\frac{4}{y^3}$
i $\frac{3}{m^5}$ j $\frac{p^7}{q^2}$ k $\frac{m}{n^4}$ l $\frac{x^4}{y^4}$
m $\frac{2}{a^3b}$ n $\frac{7}{r^2s^3}$ o $\frac{v^2}{5u^8}$ p $\frac{1}{9m^3n^5}$

4 a y b b^2 c m^5 d x^4
e $7q$ f $3t^2$ g $5h^4$ h $4p^4$
i ab^2 j de k $2m^3n^2$ l $\frac{x^2y^5}{3}$
m $-\frac{3y^4}{7}$ n $-2b^8$ o $-\frac{3gh^3}{4}$ p $\frac{9u^2t^2}{5}$

5 a $\frac{b^3}{a^3}$ b $\frac{y^5}{x^2}$ c $\frac{h^3}{g^2}$ d $\frac{n}{m}$
e $\frac{343}{5}$ f $\frac{64}{9}$ g $\frac{6}{25}$ h 1

6 a $\frac{7x^4}{y^3}$ b $\frac{u^3}{v^2}$ c $\frac{y^3}{5a^3}$ d $\frac{2b^5}{a^4c^2}$
e $\frac{5a^2b^2}{6c^4d}$ f $\frac{4h^3m^2}{5k^2p}$ g $\frac{12w^6}{tu^2v^2}$ h $\frac{mn^4x^2}{16y^5}$

7 a $\frac{1}{5}$ b $\frac{1}{9}$ c $\frac{1}{16}$ d $-\frac{1}{25}$
e $\frac{1}{25}$ f $-\frac{1}{200}$ g $-\frac{3}{4}$ h $\frac{1}{2}$
i $\frac{1}{36}$ j $\frac{1}{8}$ k $\frac{4}{25}$ l $\frac{7}{81}$
m 8 n 100 o -250 p 16
q -10 r 64 s $\frac{64}{9}$ t $-\frac{27}{64}$
u 100 v $\frac{1}{3}$ w -2 x 49

8 1.95 g

9 a -4 b -4 c -4 d -1
e -2 f -1

10 a negative power only applies to x, $\frac{2}{x^2}$
b $5 = 5^1$ has a positive power, $5a^{-4}$
c $\frac{2}{3^{-2}b^{-2}} = 2 \times 3^2 \times b^2 = 18b^2$

11 a $1 \div \frac{2}{3} = 1 \times \frac{3}{2}$
b i $\frac{4}{5}$ ii $\frac{7}{2}$ iii $\frac{3}{x}$ iv $\frac{b}{a}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c (fraction)$^{-1}$ = reciprocal of fraction

d i $\frac{9}{4}$ ii $\frac{25}{16}$ iii 32 iv $\frac{27}{343}$

12 a 4 b 4 c 3 d 2

e 4 f $\frac{3}{2}$ g 4 h $\frac{7}{3}$

Progress quiz

1 a $a \times a \times a \times a$ b $5 \times hk \times hk \times hk$

c $2 \times 2 \times 2 \times 2 = 16$

d $\frac{-3}{4} \times \frac{-3}{4} \times \frac{-3}{4} = -\frac{27}{64}$

2 a $7m^4$ b $\left(\frac{2}{3}\right)^2 \times \left(\frac{1}{5}\right)^3$ c $8^3e^4h^3$

3 a 2^8 b a^9 c $12k^7m^2$ d 5^8

e $2a^6$ f $\frac{a^5m^4}{3}$

4 a x^6 b $3xy$

5 a x^{12} b $-4q^{42}$

6 a 1 b 1 c 7 d -5

7 a a^{14} b m^{22} c 4 d $\frac{4m^8n^4}{3}$

8 a $8b^3$ b $5h^6j^9k^3$ c $-27x^{12}y^6$

d $\frac{64}{c^3}$

e $\frac{-8w^3x^9}{125y^6}$ f a^8c^2

9 a $\frac{1}{m^4}$ b $\frac{7y^5}{x^3}$ c a^5 d $\frac{c^3}{a^2}$

e $-13m^5$ f $\frac{-15u^3w^3}{t^2v^2}$

10 a $\frac{1}{16}$ b 27 c $\frac{1}{36}$ d $\frac{8}{27}$

Exercise 6F

1 a 10 000 b 1000 c 100 000 d 1000

e 100 000 f 10 000

2 a 10^5 b 10^2 c 10^9

3 a positive b negative c positive d negative

4 a 4×10^4 b 2.3×10^{12} c 1.6×10^{10}

d -7.2×10^6 e -3.5×10^3

f -8.8×10^6 g 5.2×10^3

h 3×10^6 i 2.1×10^4

5 a 3×10^{-6} b 4×10^{-4}

c -8.76×10^{-3} d 7.3×10^{-10}

e -3×10^{-5} f 1.25×10^{-10}

g -8.09×10^{-9} h 2.4×10^{-8}

i 3.45×10^{-5}

6 a 6×10^3 b 7.2×10^5

c 3.245×10^2 d 7.86903×10^3

e 8.45912×10^3 f 2×10^{-1}

g 3.28×10^{-4} h 9.87×10^{-3}

i -1×10^{-5} j -4.601×10^8

k 1.7467×10^4 l -1.28×10^2

7 a 57 000 b 3 600 000 c 430 000 000

d 32 100 000 e 423 000 f 90 400 000 000

g 197 000 000 h 709 i 635 700

8 a 0.00012 b 0.0000046 c 0.0000000008

d 0.0000352 e 0.3678 f 0.000000123

g 0.00009 h 0.05 i 0.4

9 a 6×10^{24} b 4×10^7 c 1×10^{-10}

d 1.5×10^8 e 6.67×10^{-11}

f 1.5×10^{-4} g 4.5×10^9

10 a 4 600 000 000 b 8 000 000 000 000

c 384 000 d 0.0038 e 0.00000000000001

f 720 000

11 a 3.6×10^7 b 3.6×10^5

c 4.92×10^{-1} d 3.8×10^{-4}

e 2.1×10^{-6} f 5.2×10^{-8}

g 4×10^{-9} h 1.392×10^{-7}

i 3.95×10^3 j 4.38×10^3

k 8.28×10^6 l 3×10^{11}

12 a $\$1.84 \times 10^9$ b $\$2.647 \times 10^9$

13 1.62×10^9 km

14 2.126×10^{-2} g

15 a 3.2×10^4 b 4.1×10^6

c 3.17×10^4 d 5.714×10^5

e 1.3×10^4 f 9.2×10^1

g 3×10^5 h 4.6×10^5 i 6.1×10^{-2}

j 4.24 k 1.013×10^{-3} l 4.9×10^{-4}

m 2×10^{-5} n 4×10^{-6}

o 3.72×10^{-4} p 4.001×10^{-8}

16 a 8×10^6 b 9×10^8 c 6.25×10^{-4}

d 3.375×10^{-9} e 1.25×10^8

f 4×10^6 g 9×10^{-4} h 2.5×10^4

17 a 6×10^6 b 8×10^{11}

c 2×10^4 d 3×10^9

e 5.6×10^5 f 1.2×10^8

g 1.2×10^3 h 9×10^3

i 9×10^{-9} j 7.5×10^{-8}

k 1.5×10^{-5} l 1

18 $5 \times 10^2 = 500$ seconds

19 a 3×10^{-4} km = 30 cm

b 1×10^{-3} seconds (one thousandth of a second)

$= 0.001$ seconds

Exercise 6G

1 a 57 260, 57 300, 57 000, 60 000

b 4 170 200, 4 170 000, 4 170 000, 4 200 000, 4 000 000

c 0.003661, 0.00366, 0.0037, 0.004

d 24.871, 24.87, 24.9, 25, 20

2 a yes b no c no d no

e yes f yes g yes h no

i no

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 **a** 3 **b** 4 **c** 5 **d** 2 **e** 3
f 1 **g** 3 **h** 3 **i** 3 **j** 4
k 3 **l** 2

4 **a** 2.42×10^5 **b** 1.71×10^5
c 2.83×10^3 **d** 3.25×10^6
e 3.43×10^{-4} **f** 6.86×10^{-3}
g 1.46×10^{-2} **h** 1.03×10^{-3}
i 2.34×10^1 **j** 3.26×10^2
k 1.96×10^1 **l** 1.72×10^{-1}

5 **a** 4.78×10^4 **b** 2.2×10^4
c 4.833×10^6 **d** 3.7×10^1
e 9.95×10^1 **f** 1.443×10^{-2}
g 2×10^{-3} **h** 9×10^{-2}
i 1×10^{-4}

6 **a** 2.441×10^{-4} **b** 2.107×10^{-6}
c -4.824×10^{15} **d** 4.550×10^{-5}
e 1.917×10^{12} **f** 1.995×10^8
g 3.843×10^2 **h** 1.710×10^{-11}
i 1.524×10^8 **j** 3.325×10^{15}
k 4.000×10^3 **l** -8.959×10^3

7 **a** 9.3574×10^1 **b** 2.1893×10^5
c 8.6000×10^5 **d** 8.6288×10^{-2}
e 2.2985×10^{15} **f** 3.5741×10^{28}
g 6.4000×10^7 **h** 1.2333×10^9
i 1.8293 **j** 5.4459×10^{-1}

8 1.98×10^{30} kg

9 1.39×10^6 km

10 1.09×10^{12} km^3

11 2421×10^3, 24.2×10^5, 2.41×10^6, 0.239×10^7, 0.02×10^8

12 **a** 4.26×10^6 **b** 9.1×10^{-3}
c 5.04×10^{11} **d** 1.931×10^{-1}
e 2.1×10^6 **f** 6.14×10^{-11}

13 should be 8.8×10^{10}

14 **a** **i** 2.30×10^2 **ii** 4.90×10^{-2}
iii 4.00×10^6
b It is zero
c It clarifies the precision of the number

15 **a** 5.40046×10^{12}
b **i** 4.32×10^{13} **ii** 1.61×10^{19}
iii 4.01×10^{51}

Exercise 6H

1 **a** 4, 2 **b** 8, 2 **c** 9, 3 **d** 27, 3
e 16, 4 **f** 64, 4

2 **a** True **b** False **c** True **d** True
e False **f** False **g** False

3 **a** 2.6458 **b** 3.6056 **c** 9.1104

4 **a** $\sqrt{3}$ **b** $\sqrt{7}$ **c** $\sqrt[3]{5}$ **d** $\sqrt[3]{12}$
e $\sqrt[5]{31}$ **f** $\sqrt[7]{18}$ **g** $\sqrt[9]{9}$ **h** $\sqrt[8]{3}$

5 **a** $8^{\frac{1}{2}}$ **b** $19^{\frac{1}{2}}$ **c** $10^{\frac{1}{3}}$ **d** $31^{\frac{1}{3}}$
e $5^{\frac{1}{4}}$ **f** $9^{\frac{1}{5}}$ **g** $11^{\frac{1}{8}}$ **h** $20^{\frac{1}{11}}$

6 **a** 5 **b** 7 **c** 9 **d** 13 **e** 2
f 4 **g** 5 **h** 10 **i** 2 **j** 3
k 5 **l** 2

7 **a** a **b** $a^{\frac{2}{3}}$ **c** a^2 **d** $a^{\frac{5}{2}}$
e $x^{\frac{1}{3}}$ **f** x **g** $x^{\frac{5}{6}}$ **h** x
i y **j** y^2 **k** $y^{\frac{3}{2}}$ **l** $x^{\frac{1}{4}}$
m $x^{\frac{8}{3}}$ **n** $a^{\frac{2}{15}}$ **o** $a^{\frac{3}{8}}$ **p** $n^{\frac{4}{3}}$

8 **a** $a^{\frac{4}{3}}$ **b** $a^{\frac{7}{10}}$ **c** $a^{\frac{23}{21}}$
d $a^{\frac{8}{3}}$ **e** $b^{\frac{1}{6}}$ **f** $x^{\frac{2}{15}}$

9 **a** $\frac{1}{2}$ **b** $\frac{1}{2}$ **c** $\frac{1}{2}$ **d** $\frac{1}{3}$ **e** $\frac{1}{5}$
f $\frac{1}{3}$ **g** $\frac{1}{10}$ **h** $\frac{1}{4}$

10 **a** 9 **b** 16 **c** 27 **d** 125
e 32 **f** 32 **g** 729 **h** 3125

11 **a** $\sqrt{29}$ **b** $\sqrt{13}$ **c** $\sqrt{65}$ **d** $\sqrt{125}$
e $\sqrt{10}$ **f** $\sqrt{1700}$

12 **a** $a^{\frac{1}{2}+\left(-\frac{1}{2}\right)} = a^0 = 1$ **b** $a^{\frac{2}{3}+\left(-\frac{2}{3}\right)} = a^0 = 1$
c $a^{\frac{4}{7}-\frac{4}{7}} = a^0 = 1$
d $a^{\frac{5}{6}-\frac{5}{6}} = a^0 = 1$
e $a^{\frac{1}{4}} \times a^{-\frac{1}{4}} = a^{\frac{1}{4}+\left(-\frac{1}{4}\right)} = a^0 = 1$
f $a^2 \div a^2 = a^{2-2} = a^0 = 1$

13 Brackets needed for fractional power, $9 \wedge (\frac{1}{2}) = 3$

14 **a** **i** 3 **ii** 5 **iii** 10
b a
c $(a^2)^{\frac{1}{2}} = a^{2\times\frac{1}{2}} = a$
d **i** 4 **ii** 9 **iii** 36
e a
f $\left(a^{\frac{1}{2}}\right)^2 = a^{\frac{1}{2}\times 2} = a$
g **i** a **ii** a **iii** a **iv** a

15 **a** $\frac{4}{5}$ **b** $\frac{3}{7}$ **c** $\frac{2}{9}$ **d** $\frac{2}{3}$ **e** $\frac{4}{5}$
f $\frac{2}{3}$ **g** $\frac{4}{5}$ **h** $\frac{10}{7}$

16 **a** $\frac{2}{3}$ **b** $\frac{12}{7}$ **c** $\frac{5}{2}$ **d** $\frac{5}{6}$

Exercise 6I

1 **a** like **b** like **c** unlike **d** unlike
e unlike **f** like **g** like **h** unlike

2 **a** both $= 3.162$ **b** both $= 4.583$
c both $= 1.732$ **d** both $= 2.449$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 **a** $8\sqrt{7}$ **b** $8\sqrt{11}$ **c** $9\sqrt{5}$ **d** $4\sqrt{6}$
e $7\sqrt{3}+2\sqrt{5}$ **f** $9\sqrt{7}+3\sqrt{5}$
g $-5\sqrt{5}$ **h** $-4\sqrt{7}$ **i** $5\sqrt{7}$ **j** $-\sqrt{14}$
k $7\sqrt{2}-\sqrt{5}$ **l** $3\sqrt{3}+2\sqrt{7}$

4 **a** $\sqrt{30}$ **b** $\sqrt{21}$ **c** $\sqrt{70}$ **d** 4 **e** 6
f $\sqrt{22}$ **g** 3 **h** 12 **i** $\sqrt{3}$
j $\sqrt{10}$ **k** $\sqrt{7}$ **l** $\sqrt{3}$ **m** 3 **n** 4
o $\sqrt{7}$

5 **a** $8-3\sqrt{3}$ **b** $6\sqrt{2}-\sqrt{3}$ **c** $7\sqrt{5}+1$
d $\frac{5\sqrt{2}}{6}$ **e** $\frac{7\sqrt{7}}{10}$ **f** $-\frac{3\sqrt{6}}{14}$ **g** $\frac{2\sqrt{10}}{3}$
h $5+\frac{\sqrt{3}}{3}$ **i** $-\frac{19\sqrt{8}}{56}$

6 **a** $15\sqrt{6}$ **b** $6\sqrt{21}$ **c** $8\sqrt{30}$ **d** $10\sqrt{18}$
e $2\sqrt{3}$ **f** $3\sqrt{6}$ **g** $4\sqrt{14}$ **h** $\frac{\sqrt{2}}{2}$

7 **a** $6\sqrt{15}+2\sqrt{3}$ **b** $\sqrt{10}+\sqrt{15}$
c $5\sqrt{12}+15\sqrt{30}$ **d** $14\sqrt{30}-70$
e $13-2\sqrt{39}$ **f** $\sqrt{35}-10$

8 **a** $2\sqrt{2}$ **b** $2\sqrt{3}$ **c** $3\sqrt{3}$ **d** $3\sqrt{5}$
e $5\sqrt{3}$ **f** $10\sqrt{2}$ **g** $2\sqrt{15}$ **h** $6\sqrt{2}$

9 **a** $5\sqrt{2}$ **b** $\sqrt{2}$ **c** $4\sqrt{2}$ **d** $\sqrt{3}$
e $6\sqrt{2}$ **f** $5\sqrt{3}$ **g** $2\sqrt{5}$ **h** $4\sqrt{3}$

10 **a** $2+\sqrt{10}+\sqrt{6}+\sqrt{15}$ **b** $3+\sqrt{6}-\sqrt{15}-\sqrt{10}$
c $6\sqrt{10}+8\sqrt{5}-3\sqrt{2}-4$
d $2+3\sqrt{2}-6\sqrt{7}-9\sqrt{14}$ **e** 1 **f** 4
g 15 **h** 123 **i** $3+2\sqrt{2}$ **j** $15-6\sqrt{6}$
k $13-4\sqrt{3}$ **l** $22+4\sqrt{10}$

Problems and challenges

1 **a** 4 **b** 1 **c** 6

2 **a** 6 **b** 30

3 $\frac{9}{4}$

4 **a** $2t^2$ **b** $\frac{2}{t}$

5 100 minutes

6 $-\frac{2}{3}$

7 **a** **i** $2^{\frac{3}{4}}$ **ii** $2^{\frac{7}{8}}$ **iii** $2^{\frac{15}{16}}$
b 2

8 2^7

9 **a** $7\sqrt{2}$ **b** $\frac{3}{\sqrt{2}}$ or $\frac{3\sqrt{2}}{2}$ **c** $12\sqrt{10}$

10 **a–c** Answers will vary

11 **a** $x=0$ or 1 **b** $x=1$ or 2

12 $x=2^2\times3\times5^2=300$

13 $x=-1, y=\frac{1}{2}$

Multiple-choice questions

1 D **2** B **3** E **4** A **5** C
6 B **7** D **8** C **9** E **10** B
11 C **12** A

Short-answer questions

1 **a** 3^4 **b** $2x^3y^2$ **c** $3a^2b^2$
d $\left(\frac{3}{5}\right)^3\times\left(\frac{1}{7}\right)^2$

2 **e** $3^2\times5$ **f** $2^2\times3\times5^2$

3 **a** x^{10} **b** $12a^5b^6c$ **c** $12m^4n^4$ **d** a^9
e x^3y^2 **f** $\frac{b^2}{2a^2}$

4 **a** m^6
b $9a^8$
c $-32a^{10}b^5$
d $3b$
e 2
f $\frac{a^6}{27}$

5 **a** $\frac{1}{x^3}$ **b** $\frac{4}{t^3}$ **c** $\frac{1}{9t^2}$ **d** $\frac{2x^2}{3y^3}$
e $\frac{5}{x^6y^3}$ **f** $5m^3$

6 **a** $\frac{x^2}{2y^2}$ **b** $\frac{x^3y^2}{9}$ **c** $8m^7n^3$

7 $0.0012, 35.4\times10^{-3}, 3.22\times10^{-1}, 0.4, 0.007\times10^2, 2.35$

8 **a** 324 **b** 172 500 **c** 0.2753 **d** 0.00149

9 **a** 2.38×10^7 people **b** 9.63×10^6 km^2
c 3.34×10^{-9} seconds **d** 2.94×10^{-7} m

10 **a** 2.19×10^5 **b** 1.2×10^{-2}
c 4.32×10^{-7}

11 **a** 1.2×10^{55} **b** 4.3×10^{-5}

12 **a** 2 **b** 5 **c** 7 **d** 3 **e** $\frac{1}{3}$
f $\frac{1}{11}$

13 **a** s^2 **b** $15x^{\frac{5}{2}}$ **c** $9m^{\frac{3}{4}}n^4$ **d** $4a^{\frac{2}{3}}$

14 **a** $7\sqrt{7}+2$ **b** $\sqrt{3}+9\sqrt{2}$ **c** 8
d $\sqrt{15}$ **e** $2\sqrt{14}$ **f** $15\sqrt{22}$ **g** $\sqrt{6}$
h 10 **i** $\frac{\sqrt{5}}{2}$

Extended-response questions

1 **a** $\frac{16x^6}{3}$ **b** $\frac{8b^8}{15a^2}$ **c** $\frac{5m^8}{n^{10}}$ **d** $3x$

2 **a** 5.93×10^{-11} N
b **i** 1.50×10^{11} m **ii** 3.5×10^{22} N
c Earth $a=9.81$ ms^{-2}, Mars $a=3.77$ ms^{-2}
Acceleration due to gravity on Earth is more than $2\frac{1}{2}$ times that on Mars

Chapter 7

Exercise 7A

1 **a** right **b** 180° **c** revolution **d** obtuse
e acute **f** 180° **g** 90° **h** supplementary
i 180° **j** equal

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 **a** isosceles triangle **b** obtuse angle triangle
c equilateral triangle **d** isosceles triangle
e acute angled triangle **f** scalene triangle
g right-angled triangle

3 **a** **i** $\angle BAC$ **ii** obtuse
iii Answers will vary **iv** 120°
b **i** $\angle PRQ$ **ii** acute
iii Answers will vary **iv** 30°
c **i** $\angle XYZ$ **ii** reflex
iii Answers will vary **iv** 310°
d **i** $\angle SRT$ **ii** straight angle
iii Answers will vary **iv** 180°
e **i** $\angle ROB$ **ii** obtuse
iii Answers will vary **iv** 103°
f **i** $\angle AOB$ **ii** right
iii Answers will vary **iv** 90°

4 **a** 50° **b** 90° **c** 101° **d** 202°
e 180° **f** 360°

5 **a** **i** 125° **ii** 35°
b **i** 149° **ii** 59°
c **i** 106° **ii** 16°
d **i** 170° **ii** 80°
e **i** 91° **ii** 1°
f **i** 158° **ii** 68°
g **i** 142° **ii** 52°
h **i** 115° **ii** 25°
i **i** 133° **ii** 43°
j **i** 103° **ii** 13°

6 **a** C **b** S **c** N **d** C **e** S
f N **g** S **h** N

7 **a** $a = 63$ **b** $a = 71$ **c** $a = 38$ **d** $a = 147$
e $a = 233$ **f** $a = 33$

8 **a** obtuse isosceles, 40° **b** acute scalene, 30°
c right-angled scalene, 90°
d equilateral, 60° **e** obtuse isosceles, 100°
f right-angled isosceles, 45°
g obtuse scalene, 100° **h** equilateral, 60°
i acute scalene, 70°

9 **a** $s = 120$ **b** $t = 20$ **c** $r = 70$
d $a = 60, x = 120$ **e** $a = 100, b = 140$
f $c = 115, d = 65$

10 **a** 360° **b** 90° **c** 60° **d** 90°
e 432° **f** 6° **g** 720° **h** 8640°

11 **a** $x = 56$ **b** $x = 155$ **c** $x = 116$

12 **a** 90° **b** 150° **c** 15° **d** 165°
e 157.5° **f** 80° **g** 177.5° **h** 171°
i 121.5°

13 $\angle AOB + \angle ABO = 120°$ (exterior angle of triangle)
$\angle AOB = 30°$
(reflex) $x = 330$

14 $AO = BO$ (radii)
ΔAOB is isoceles, 2 sides equal, $\angle AOB = 116°$
$\therefore \angle OAB = 32°$, base angles of isosceles triangle

15 **a** 160° **b** 165°
c $\angle WYZ + a° + b° = 180°$ angle sum of a triangle
$\angle XYZ + \angle WYZ = 180°$ straight line
$\therefore \angle XYZ = a° + b°$

16 Let the interior angles of any triangle be $a°$, $b°$ and $c°$
Now $a + b + c = 180$
The exterior angles become, $180° - a°$, $180° - b°$, $180° - c°$ (straight line)
Exterior sum $= (180 - a)° + (180 - b)° + (180 - c)°$
$= 540° - a° - b° - c°$
$= 540° - (a + b + c)°$
$= 540° - 180°$
$= 360°$

17 **a** $4x = 90, x = 22.5$ **b** $3x = 180, x = 60$
c $10x = 360, x = 36$
d $2(x + 15) + x = 180, x = 50$
e $2x + 20 = 140, x = 60$
f $6x + 90 = 360, x = 45$

Exercise 7B

1 **a** equal **b** equal **c** supplementary

2 **a** 125°, alternate angles in || lines
b 110°, cointerior angles in || lines
c 80°, corresponding angles in || lines
d 66°, alternate angles in || lines
e 96°, vertically opposite
f 126°, corresponding angles on || lines
g 62°, supplementary angles
h 115°, corresponding angles on || lines
i 116°, cointerior angles on || lines

3 **a** no, alternate angles are not equal
b yes, corresponding angles are equal
c yes, alternate angles are equal
d no, cointerior angles don't add to 180°
e yes, cointerior angles add to 180°
f yes, corresponding angles are equal
g no, corresponding angles are not equal
h no, alternate angles are not equal
i no, cointerior angles do not add to 180°

4 **a** $a = 60, b = 120$ **b** $c = 95, d = 95$
c $e = 100, f = 100, g = 100$
d $a = 110, b = 70$ **e** $a = 100, b = 80, c = 80$
f $e = 140, f = 140, d = 140$

5 **a** $x = 70, y = 40$ **b** $t = 58, z = 122$
c $u = 110, v = 50, w = 50$ **d** $x = 118$
e $x = 295$ **f** $x = 79$

6 **a** 105° **b** 105° **c** 56° **d** 105°
e 90° **f** 85°

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 **a** 56 **b** 120 **c** 50

8 **a** $180^\circ - a^\circ$ **b** $180^\circ - a^\circ$

c $180^\circ - (a^\circ + b^\circ)$ **d** $180^\circ - (a^\circ + b^\circ)$

e $a^\circ + c^\circ$ **f** $180^\circ - 2c^\circ$

9 $\angle ABC = 100^\circ$

$\angle BCD = 80^\circ$

$\angle ABC + \angle BCD = 180^\circ$

$\therefore AB \,||\, DC$ as cointerior angles are supplementary

10 **a** cointerior angles on parallel lines add to 180°

b alternate angles are equal, on parallel lines

c $\Delta ABC \Rightarrow a + b + c = 180$ and these are the three angles of the triangle

11 **a** $\angle BAE = 180^\circ - a^\circ$ (alternate angles and $AB \,||\, DE$)

$\angle ABC = 180^\circ - c^\circ - (180 - a)^\circ$ (angle sum of a triangle)

$= 180^\circ - c^\circ - 180^\circ + a^\circ$

$= -c^\circ + a^\circ$

$= a^\circ - c^\circ$

b $\angle ABD = 180^\circ - (a^\circ + b^\circ)$ (angle sum of triangle ΔABD)

$\angle ABC + \angle ABD = 180^\circ$ (straight line)

$\therefore \angle ABC = a^\circ + b^\circ$

c construct XY through B parallel to AE

$\therefore \angle ABY = a^\circ$ (alternate angles, $AE \,||\, XY$)

$\therefore \angle CBY = b^\circ$ (alternate angles, $DC \,||\, XY$)

$\therefore \angle ABC = a^\circ + b^\circ$

d Construct XY through A parallel to ED

$\angle XAD = 180^\circ - b^\circ$ (cointerior angles, $ED \,||\, XY$)

$\angle DAB = 360^\circ - a^\circ$ (revolution)

$\therefore \angle XAB = 360^\circ - a^\circ - (180^\circ - b^\circ)$

$= 180^\circ + b^\circ - a^\circ$

$\angle ABC = \angle XAB$ (alternate angles and $XY \,||\, BC$)

$\therefore \angle ABC = 180^\circ + b^\circ - a^\circ$

Exercise 7C

1 **a** 5 **b** 7 **c** 4 **d** 11 **e** 9

f 12

2 **a** 720° **b** 1080° **c** 1620°

3 **a** parallel **b** right **c** trapezium **d** equal

4 **a** convex quadrilateral **b** non-convex hexagon

c non-convex heptagon

5 **a** 115 **b** 149 **c** 30 **d** 121

e 140 **f** 220

6 **a** 110 **b** 70 **c** 54 **d** 33

e 63 **f** 109

7 **a** 110 **b** 150 **c** 230 **d** 20

e $b = 108, a = 72$ **f** $b = 140, a = 40$

g $b = 120, a = 240$ **h** $b = 128\frac{4}{7}, a = 231\frac{3}{7}$

i 108

8 **a** parallelogram, rectangle, kite

b rectangle, square **c** square, rectangle

d square, rhombus, kite

9 **a** 16 **b** 25 **c** 102

10 **a** 255 **b** 86 **c** 115 **d** 37

e 28 **f** 111

11 A parallelogram has opposite sides parallel and equal. Rectangles, squares and rhombi have these properties (and more) and are therefore all parallelograms.

12 **a** $S = 180(n - 2)$ **b** $I = \frac{180(n-2)}{n}$

c $E = \frac{360}{n}$ **d** 36°

13 **a** **i** one **ii** two **iii** five

b $(n - 3)$

14 $(180 - a) + (180 - b) + (180 - c) + (180 - d) + (180 - e) = 360$

(sum of exterior angles is 360°)

$180 + 180 + 180 + 180 + 180 - (a + b + c + d + e) = 360$

$900 - (a + b + c + d + e) = 360$

$a + b + c + d + e = 540$

a $a + b + c + d + e + f = 720$

b $a + b + c + d + e + f + g = 900$

Exercise 7D

1 **a** size **b** $\Delta ABC \equiv \Delta STU$ **c** SAS, RHS, AAS

2 **a** **i** XY **ii** XZ **iii** YZ

b **i** $\angle A$ **ii** $\angle B$ **iii** $\angle C$

3 **a** $\Delta ABC \equiv \Delta FGH$ **b** $\Delta DEF \equiv \Delta STU$

c $\Delta AMP \equiv \Delta CBD$ **d** $\Delta BMW \equiv \Delta SLK$

4 **a** SAS **b** AAS **c** RHS **d** SAS

e SSS **f** RHS **g** AAS **h** SSS

5 **a** $x = 3, y = 4$ **b** $x = 2, y = 6$

c $a = 105, b = 40$ **d** $a = 65, b = 85$

e $x = 2.5, b = 29$ **f** $a = 142, x = 9.21, b = 7$

g $y = 4.2, a = 28$ **h** $a = 6.5, b = 60$

6 **a** $\Delta ABC \equiv \Delta STU$ (RHS)

b $\Delta DEF \equiv \Delta GHI$ (SSS)

c $\Delta ABC \equiv \Delta DEF$ (SAS)

d $\Delta ABC \equiv \Delta GHI$ (AAS)

e $\Delta ACB \equiv \Delta DEF$ (SAS)

7 $\Delta DEF \equiv \Delta BRP$

$\Delta LMN \equiv \Delta KIJ$

$\Delta BCD \equiv \Delta FGH$

$\Delta MNO \equiv \Delta RQP$

8 **a** $BC = 13$ **b** $BC = 85$

9 no – they can all be different sizes, one might have all sides 2 cm and another all sides 5 cm.

10 **a** one given, the other pair are vertically opposite

b AAS

11 **a** SSS **b** equal

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

12 **a** one given ($BA = BC$) and side BD is common

b SAS

c $\Delta ABD \equiv \Delta CBD$

d $\angle ADB = \angle CDB$ (corresponding angles in congruent triangles)
but $\angle ADB + \angle CDB = 180°$ (straight angle)
$\therefore \angle ADB = \angle CDB = 90°$
and AC is perperdicular to DB

13 **a–e** Answers will vary

Exercise 7E

1 **a** BD **b** AC **c** AC

2 $OA = OB$ radii of circle centre O

3 **a** $\angle ECD$ **b** $\angle CBA$ **c** $\angle DEC$

4 **a** SSS **b** $\angle BMC$

5 **a** $AD = CD$ (given)
$\angle DAB = \angle DCB = 90°$ (given)
DB is common
$\therefore \Delta ABD \equiv \Delta CBD$ (RHS)

b AC is common
$AD = AB$ (given)
$\angle DAC = \angle BAC$ (given)
$\therefore \Delta ADC \equiv \Delta ABC$ (SAS)

c AC is common
$\angle ADC = \angle ABC$ (given)
$\angle DAC = \angle BAC$ (given)
$\therefore \Delta ADC \equiv \Delta ABC$ (AAS)

d AC is common
$AD = AB$ (given)
$DC = BC$ (given)
$\therefore \Delta ADC \equiv \Delta ABC$ (SSS)

e $AC = DC$ (given)
$BC = EC$ (given)
$\angle ACB \equiv \angle DCE$ (vertically opposite)
$\therefore \Delta ABC \equiv \Delta DEC$ (SAS)

f $AC = EC$ (given)
$\angle CAB = \angle CED$ (alternate angles, $AB \,||\, DE$)
$\angle ACB = \angle ECD$ (vertically opposite)
(or $\angle CBA = \angle CDE$ (alternate angles, $AB \,||\, DE$))
$\therefore \Delta ABC \equiv \Delta EDC$ (AAS)

g $DC = BC$ (given)
$\angle EDC = \angle ABC$ (alternate angles, $DE \,||\, AB$)
$\angle DCE = \angle BCA$ (vertically opposite)
(or $\angle DEC = \angle BAC$ (alternate angles, $AB \,||\, DE$))
$\therefore \Delta CDE \equiv \Delta CBA$ (AAS)

h BD is common
$AD = CD$ (given)
$\angle ADB = \angle CDB$ (given)
$\therefore \Delta ABD \equiv \Delta CBD$ (SAS)

i AC is common
$AB = CD$ (given)
$BC = DA$ (given)
$\therefore \Delta ABC \equiv \Delta CDA$ (SSS)

j BD is common
$\angle ABD = \angle CDB$ (alternate angles, $AB \,||\, CD$)
$\angle ADB = \angle CBD$ (alternate angles, $AD \,||\, CB$)
$\therefore \Delta ABD \equiv \Delta CDB$ (AAS)

k $OA = OC$ (radii)
OB is common
$AB = CB$ given
$\therefore \Delta AOB \equiv \Delta COB$ (SSS)

l $OA = OD$ and $OB = OC$ (radii)
$\angle AOB = \angle COD$ (vertically opposite)
$\Delta AOB \equiv \Delta COD$ (SAS)

6 **a** $DC = BC$ (given)
$EC = AC$ (given)
$\angle DCE = \angle BCA$ (vertically opposite)
$\therefore \Delta ABC \equiv \Delta EDC$ (SAS)

b $\angle EDC = \angle ABC$ (corresponding angles in congruent triangles)
$\therefore AB \,||\, DE$ (alternate angles are equal)

7 **a** $AE = CD$ (given)
$BE = BD$ (given)
$\angle ABE = \angle CBD$ (vertically opposite with $\angle ABE$ given 90°)
$\therefore \Delta ABE \equiv \Delta CBD$ (RHS)

b $\angle EAB = \angle DCB$ (corresponding angles in congruent triangles)
$\therefore AE \,||\, CD$ (alternate angles equal)

8 **a** DB is common
$AB = CD$ (given)
$AD = CB$ (given)
$\therefore \Delta ABD \equiv \Delta CDB$ (SSS)

b $\angle ADB = \angle CBD$ (corresponding angles in congruent triangles)
$\therefore AD \,||\, BC$ (alternate angles equal)

9 **a** $OB = OC$ (radii)
$OA = OD$ (radii)
$\angle AOB = \angle DOC$ (vertically opposite)
$\therefore \Delta AOB \equiv \Delta DOC$ (SAS)

b $\angle ABO = \angle DCO$ (corresponding angles in congruent triangles)
$\therefore AB \,||\, CD$ (alternate angles equal)

10 **a** BD is common
$AD = CD$ (given)
$\angle ADB = \angle CDB$ (given)
$\therefore \Delta ABD \equiv \Delta CBD$ (SAS)

b $\angle ABD = \angle CBD$ (corresponding angles in congruent triangles)
and $\angle ABD + \angle CBD = 180°$ (straight line)
$\therefore \angle ABD = \angle CBD = 90°$ and AC is perpendicular to BD

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 **a** DB is common
$\angle ABD = \angle CBD$ (given 90°)
$\angle ADB = \angle CDB$ (given)
$\therefore \Delta ABD \equiv \Delta CBD$ (AAS)

b $AD = CD$ (corresponding side in congruent triangles)
$\therefore \Delta ACD$ is isosceles (2 equal sides)

12 Consider ΔOAD and ΔOBD
OD is common
$OA = OB$ (radii)
$AD = BD$ (given)
$\therefore \Delta OAD \equiv \Delta OBD$ (SSS)
$\angle ODA = \angle ODB = 90°$ (corresponding angles in congruent triangles are equal and supplementary to a straight line)
$\therefore OC \perp AB$

13 Consider ΔADC and ΔCBA
AC is common
$\angle DAC = \angle BCA$ (alternate angles, $AD \,||\, BC$)
$\angle DCA = \angle BAC$ (alternate angles, $DC \,||\, AB$)
$\therefore \Delta ADC \equiv \Delta CBA$ (AAS)
So $AD = BC$, $AB = DC$ are equal corresponding sides in congruent triangles

14 $AB = DC$ (opposite sides of parallelogram)
$\angle AEB = \angle CED$ (vertically opposite)
$\angle BAE = \angle DCE$ (alternate angles $DC \,||\, AB$)
$\therefore \Delta ABE \equiv \Delta CDE$ (AAS)
So $AE = CE$ and $BE = DE$, corresponding sides in congruent triangles

15



Consider ΔADC and ΔBCD
$AD = CB$ and DC is common (opposite sides of a rectangle are equal)
$\angle ADC = \angle BCD = 90°$ (angles of a rectangle)
$\therefore \Delta ADC \equiv \Delta BCD$ (SAS)
So $AC = BD$ (corresponding sides in congruent triangles)
$\therefore$ The diagonals of a rectangle are equal

16 **a** Consider ΔABE and ΔCDE
$AB = CD$ (sides of a rhombus)
$\angle ABE = \angle CDE$ (alternate angles, $AB \,||\, CD$)
$\angle BAE = \angle DCE$ (alternate angles, $AB \,||\, CD$)
$\therefore \Delta ABE \equiv \Delta CDE$ (AAS)

b Consider ΔDCE and ΔBCE
CE is common
$DC = BC$ (sides of a rhombus)
$DE = BE$ (corresponding sides in congruent triangles)
$\therefore \Delta DCE \equiv \Delta BCE$ (SSS)
$\angle DEC = \angle BEC$ (corresponding angles in congruent triangles)
$\angle DEC + \angle BEC = 180°$ (straight line)
$\therefore \angle DEC = \angle BEC = 90°$
and $AE = CE$ (corresponding sides in congruent triangles)
$\therefore AC$ bisects BD at 90°

17



let ΔABC be any equilateral triangle $AB = CB = AC$

Step one
Join C to M the midpoint of AB
Prove $\Delta CAM \equiv \Delta CBM$ (SSS)
$\therefore \angle CAM = \angle CBM$ (corresponding angles in congruent triangles)

Step two
Join A to N, the midpoint of CB
Prove $\Delta ANC \equiv \Delta ANB$
$\therefore \angle ACN = \angle ABN$ (corresponding angles in congruent triangles)
Now $\angle CAB = \angle ABC = \angle ACB$
and as $\angle CAB + \angle ABC + \angle ACB = 180°$ (angle sum of ΔABC)
$\angle CAB = \angle ABC = \angle ACB = 60°$

Progress quiz

1 **a** 37° **b** 127°

2 **a** 60 **b** 56 **c** 50 **d** 142
e 50 **f** 84

3 **a** Yes, as there is a pair of equal alternate angles
b No, as the pair of cointerior angles are not supplementary

4 **a** $a = 68$ (alternate angles equal in parallel lines)
$b = 68$ (corresponding angles equal in parallel lines)
b $w = 98$ (alternate angles equal in parallel lines)
c $x = 92$ (angle sum of a quadrilateral)
d $x = 60$ (exterior angle of a regular hexagon)

5 **a** AAS **b** SAS

6 AC is common
$DC = BC$ given
$\angle ACD = \angle ACB$ (given 90°)
$\therefore \Delta ABC \equiv \Delta ADC$ (SAS)
$AB = AD$ (corresponding sides in congruent triangles)
$\therefore \Delta ABD$ is isosceles

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 **a** $AE = DC$ given
$\angle ABE = \angle DBC$ (*vertically opposite angles*)
$\angle EAB = \angle CDB$ (alternate angles, $AE \parallel CD$)
$\therefore \Delta ABE \equiv \Delta DBC$ (AAS)
b 62°
c 7 cm
d 21 cm^2

Exercise 7F

1 **a** $\angle$F **b** $\angle D$ **c** GH **d** AE **e** 2
2 **a** double **b** double **c** double **d** 2
e yes
3 **a** OA' is a quarter of OA **b** OD' is a quarter of OD
c $\frac{1}{4}$ **d** yes
4 **a** yes **b** 8 cm **c** 25 m
5 **a** $A'B'C'$ should have sides $\frac{1}{3}$ that of ABC
b $A'B'C'$ should have sides double that of ABC
6 **b** **i** $A'B'C'D'$ should have sides lengths $\frac{1}{2}$ that of $ABCD$
ii $A'B'C'D'$ should have side lengths 1.5 times that of $ABCD$
7 **a** **i** 2 **ii** 14 **iii** 10
b **i** $1\frac{1}{2}$ **ii** 9 **iii** 8
c **i** $1\frac{1}{2}$ **ii** 45 **iii** 24
d **i** $\frac{2}{5}$ **ii** 1 **iii** 1.4
e **i** 2.5 **ii** 0.6 **iii** 2
f **i** 1.75 **ii** 3.5 **iii** 3
8 **a** **i** 2 **ii** (0,0)
b **i** $\frac{1}{2}$ **ii** (0,0)
c **i** $\frac{1}{2}$ **ii** (3,0)
d **i** 3 **ii** (1,0)
9 **a** **i** 3.6 m **ii** 9 m **iii** 2.7 m
b **i** 5.4 m **ii** 6.3 m
c **i** 6 m **ii** 3 m
10 **a** 12.7 cm **b** 3 cm **c** 3 m
11 **a** $a > 1$ **b** $a < 1$ **c** $a = 1$
12 **a** all angles of any square equal 90°, with only 1 side length
b all angles in any equilateral triangle equal 60° with only 1 side length
c The length and width might be multiplied by different numbers
d 2 isosceles triangles do not have to have the same size equal angles
13 $\frac{1}{k}$
14 **a** 100 000 cm = 1 km **b** 24 cm
15 **a** N/A
b **i** $\frac{l}{2}$ **ii** $\frac{l}{4}$ **iii** $\frac{l}{128}$
c **i** $\frac{3}{4}$ **ii** $\frac{9}{16}$ **iii** $\frac{243}{1024}$
d zero

Exercise 7G

1 **a** E **b** C **c** DF **d** BC
e $\angle A$ **f** $\angle E$
2 2.5
3 **a** SAS, AAA, and RHS **b** shape, size
4 **a** AAA **b** RHS **c** SSS **d** SAS
e RHS **f** AAA **g** SAS **h** SSS
5 **a** $\Delta ABC \,|||\, \Delta GHI$ **b** $\Delta ABC \,|||\, \Delta MNO$
c $\Delta ABC \,|||\, \Delta ADE$ **d** $\Delta HFG \,|||\, \Delta HJI$
e $\Delta ADC \,|||\, \Delta AEB$ **f** $\Delta ABD \,|||\, \Delta ECD$
6 **a** AAA **b** 12
7 **a** RHS **b** 8
8 **a** **i** $\frac{8}{5}$ **ii** 14.4
b **i** 3.5 **ii** 5
9 **a** AAA **b** 15
10 **a** **i** AAA **ii** 6.5
b **i** AAA **ii** 10
c **i** AAA **ii** 24
11 **a** 2 **b** 16 **c** 2.8
12 **a** ΔDEF **b** ΔDEF **c** ΔABC **d** ΔDEF
13 $\angle ACB = 25°$, AAA
14 $\angle WXY = 55°$, not similar as angles not equal
15 2 pairs of equal alternate angles are always formed
16 AAA, in congruency a side length is needed for the triangles to be the same size, in similarity it is not needed.
17 **a**

Triangle	Original	Image 1	2	3
Length scale factor	1	2	3	4
Area	4	16	36	64
Area scale factor	1	4	9	16
Volume	12	96	324	768
Volume scale factor	1	8	27	64

b Area scale factor = (length scale factor)^2
c n^2
d **i** 100 **ii** 400 **iii** 10 000
e $\frac{1}{4}$
f Volume scale factor = (length scale factor)^3
g n^3
h **i** 125 **ii** 1000 **iii** $\frac{1}{8}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 7H

1 $\angle C$

2 **a** $\angle ACB$ and $\angle ECD$

b $\angle BAC = \angle DEC$ and $\angle CBA = \angle CDE$

3 **a** $\angle C$

b **i** AC **ii** DB

4 **a** $\angle AEB = \angle CDB$ (alternate angles, $EA \parallel DC$)
$\angle EAB = \angle DCB$ (alternate angles, $EA \parallel DC$)
$\angle EBA = \angle DBC$ (vertically opposite)
$\therefore \Delta AEB \parallel\!\parallel\!\parallel \Delta CDB$ (AAA)

b $\angle BAC = \angle DEC$ (alternate angles, $AB \parallel DE$)
$\angle ABC = \angle EDC$ (alternate angles, $AB \parallel DE$)
$\angle ACB = \angle ECD$ (vertically opposite)
$\therefore \Delta ACB \parallel\!\parallel\!\parallel \Delta ECD$ (AAA)

c $\angle C$ is common
$\angle CDB = \angle CEA$ (corresponding angles, $AE \parallel BD$)
$\angle CBD = \angle CAE$ (corresponding angles, $AE \parallel BD$)
$\therefore \Delta CBD \parallel\!\parallel\!\parallel \Delta CAE$ (AAA)

d $\angle A$ is common
$\angle AEB = \angle ADC$ (corresponding angles, $EB \parallel DC$)
$\angle ABE = \angle ACD$ (corresponding angles, $EB \parallel DC$)
$\therefore \Delta AEB \parallel \Delta ADC$ (AAA)

e $\angle A$ is common
$\angle ABE = \angle ADC$ (given)
$\therefore \Delta ABE \parallel\!\parallel\!\parallel \Delta ADC$ (AA)
(note 2 angles is enough $-\ \angle AEB = \angle ACD$ (angle sum of a triangle))

f $\angle ABD = \angle BCD$ (given 90°)
$\angle BAD = \angle CBD$ (given)
$\therefore \Delta ABD \parallel\!\parallel\!\parallel \Delta BCD$ (AA)

5 **a** $\angle C$ is common.

$$\frac{CA}{CD} = \frac{6}{2} = \frac{3}{1} = 3$$

$$\frac{CE}{CB} = \frac{9}{3} = 3$$

$\therefore \Delta CDB \parallel\!\parallel\!\parallel \Delta CAE$ (SAS)

b $\angle D$ is common

$$\frac{AD}{CD} = \frac{28}{7} = 4$$

$$\frac{DB}{DE} = \frac{48}{12} = 4$$

$\therefore \Delta ABD \parallel\!\parallel\!\parallel \Delta CED$ (SAS)

c $\angle DCE = \angle BCA$ (vertically opposite)

$$\frac{EC}{AC} = \frac{2}{5}$$

$$\frac{DC}{BC} = \frac{3}{7.5} = \frac{2}{5}$$

$\therefore \Delta DCE \parallel\!\parallel\!\parallel \Delta BCA$ (SAS)

6 **a** AAA **b** 40 m

7 **a** AAA **b** 7.5 m

8 6 m

9 20 m

10 7.2 m

11 $\frac{55}{6}$

12 **a** Firstly, $\angle ADC = \angle ACD = 80°$ (base angles of isosceles ΔADC)

$\angle ACB = 100°$ (straight angle)

$\angle CAB = 60°$ (angle sum of ΔACB)

Now $\angle DAB = 80°$

Proof $\angle DAC = \angle DBA$ (given 20°)
$\angle D$ is common
$\angle ACD = \angle BAD$ (both 80°)
$\therefore \Delta ACD \parallel\!\parallel\!\parallel \Delta BAD$ (AAA)

b $DC = \frac{20}{3}$ $CB = \frac{25}{3}$

13 **a** **i** $\angle B$ is common
$\angle DAB = \angle ACB$ (given 90°)
$\therefore \Delta ABD \parallel\!\parallel\!\parallel \Delta CBA$ (AAA)

ii $\angle D$ is common
$\angle DCA = \angle DAB$ (given 90°)
$\therefore \Delta ABD \parallel\!\parallel\!\parallel \Delta CAD$ (AAA)

b **i** $BD = \frac{25}{3}$ **ii** $AC = 4$ **iii** $AB = \frac{20}{3}$

14 **a** $\angle ACB = \angle ECD$ (vertically opposite)
$\angle CAB = \angle CED$ (alternate angles, $DE \parallel\!\parallel\!\parallel BA$)
$\therefore \Delta ABC \parallel\!\parallel\!\parallel \Delta EDC$ (AAA)

$\therefore \frac{DC}{BC} = \frac{EC}{AC}$ (ratio of corresponding sides in similar triangles)

$$\frac{6}{2} = \frac{EC}{AC}$$

$\therefore 3AC = CE$
as $AC + CE = AE$
$AE = 4AC$

b $\angle C$ is common
$\angle DBC = \angle AEC$ (given)
$\therefore \Delta CBD \parallel\!\parallel\!\parallel \Delta CEA$ (AAA)

$\therefore \frac{DB}{AE} = \frac{2}{4} = \frac{BC}{CE}$ (ratio of corresponding sides in similar triangles)
$\therefore 4BC = 2CE$

$BC = \frac{1}{2}CE$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c $\angle C$ is common

$\angle CBD = \angle CAE$ (corresponding angles, $BD \parallel AE$)

$\therefore \Delta CBD \parallel\!\parallel\!\parallel \Delta CAE$ (AAA)

$\therefore \frac{CB}{CA} = \frac{CD}{CE}$ (ratio of corresponding sides in similar triangles)

$\therefore \frac{5}{7} = \frac{CD}{CE}$

$\therefore 5CE = 7CD$

$\therefore CE = \frac{7}{5}CD$

d $\angle C$ is common

$\angle CBD = \angle CAE$ (given 90°)

$\therefore \Delta CBD \parallel\!\parallel\!\parallel \Delta CAE$ (AAA)

$\therefore \frac{BD}{AE} = \frac{CE}{CA}$ (ratio of corresponding sides in similar triangles)

$\frac{2}{8} = \frac{CB}{CA}$

$\frac{1}{4} = \frac{CB}{CB + AB}$

$CB + AB = 4CB$

$\therefore AB = 3CB$

Problems and challenges

1



2 15

3 40°

4 A, B and C should be placed where the three altitudes of the triangle intersect the three sides.

5 45°

6 11

7 $\frac{120}{7}$

Multiple-choice questions

1 D	**2** A	**3** B	**4** D	**5** C
6 D	**7** E	**8** B	**9** D	**10** A

Short-answer questions

1 **a** isosceles, $x = 50$, $y = 80$

b right angled, $x = 25$

c obtuse angled, $x = 30$, $y = 110$

2 **a** $a = 30$ (vertically opposite) $b = 150$ (straight angle)

b $x = 60$ (revolution) $y = 120$ (co-interior angles in parallel lines)

c $a = 70$ (alternate angles and parallel lines)

$b = 55$ (angle sum of isosceles triangle)

$c = 55$ (corresponding angles and parallel lines)

3 $\angle ABC = 75°$

4 **a** $a = 70, b = 110$ **b** $x = 15$ **c** $x = 30$

d $a = 120$

5 **a** SSS, $x = 60$ **b** not congruent

c RHS, $x = 8$ **d** AAS, $x = 9$

6 **a** AD is common

$\angle ADC = \angle ADB$ (given 90°)

$CD = BD$ (given)

$\therefore \Delta ADC \equiv \Delta ADB$ (SAS)

b **i** $AC = EC$ (given)

$\angle BAC = \angle DEC$ (given)

$\angle ACB = \angle ECD$ (vertically opposite)

$\therefore \Delta ACB \equiv \Delta ECD$ (AAS)

ii as $\angle BAC = \angle DEC$ (alternate angles are equal)

$\therefore AB \parallel DE$

7 For image $\Delta A'B'C'$, $OA' = 3OA$, $OB' = 3OB$, $OC' = 3OC$

8 **a** yes, SAS **b** yes, AAA **c** not similar

9 **a** 3.5 **b** 4 **c** 18

10 **a** $\angle C$ is common

$\angle DBC = \angle EAC = 90°$ (given)

$\therefore \Delta BCD \parallel\!\parallel\!\parallel \Delta ACE$ (AAA)

b 5 m

Extended-response questions

1 **a** $\angle ABC + \angle BCF = 180°$ (cointerior angles, $AB \parallel CF$)

$\therefore \angle BCF = 70°$

$\therefore \angle DCF = 32°$

Now $\angle EDC + \angle DCF = 32° + 148°$

$= 180°$

$\therefore DE \parallel CF$ as cointerior angles add to 180°

b $\angle CDA = 40°$ (revolution)

reflex $\angle BCD = 270°$ (revolution)

$\angle DAB = 30°$ (angle sum in isosceles triangle)

$BADC$ quadrilateral angle sum 360°

$\therefore a = 360 - (30 + 270 + 40)$

$= 20$

or other proof.

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c $AB = CD$ (given)
$\angle ABC = \angle DCB$ (given)
BC is common
$\therefore \Delta ABC \equiv \Delta DCB$ (SAS)
$\therefore AC = BD$ (corresponding sides in congruent triangles)

2 a $\angle ECD$
b $\angle ABC = \angle EDC$ (given 90°)
$\angle ACB = \angle ECD$ (vertically opposite)
$\therefore \Delta ABC \,|||\, \Delta EDC$ (AAA)
c 19.8 m

Chapter 8

Exercise 8A

1 a x^2, $2x$, $3x$, 6
b $x^2 + 3x + 2x + 6 = x^2 + 5x + 6$

2 a $2x^2$, $2x$, $3x$, 3
b $(2x + 3)(x + 1) = 2x^2 + 2x + 3x + 3$
$= 2x^2 + 5x + 3$

3 a $x^2 + 5x + x + 5 = x^2 + 6x + 5$
b $x^2 + 2x - 3x - 6 = x^2 - x - 6$
c $21x^2 + 6x - 14x - 4 = 21x^2 - 8x - 4$
d $12x^2 - 16x - 3x + 4 = 12x^2 - 19x + 4$

4 a $x^2 + 7x + 10$ b $b^2 + 7b + 12$
c $t^2 + 15t + 56$ d $p^2 + 12p + 36$
e $x^2 + 15x + 54$ f $d^2 + 19d + 60$
g $a^2 + 8a + 7$ h $y^2 + 12y + 20$
i $m^2 + 16m + 48$

5 a $x^2 - x - 12$ b $x^2 + 3x - 10$
c $x^2 - 4x - 32$ d $x^2 - 4x - 12$
e $x^2 + 9x - 10$ f $x^2 + 2x - 63$
g $x^2 + 5x - 14$ h $x^2 - 3x + 2$
i $x^2 - 9x + 20$ j $8x^2 + 26x + 15$
k $6x^2 + 7x + 2$ l $15x^2 + 17x + 4$
m $6x^2 + x - 15$ n $24x^2 + 23x - 12$
o $6x^2 - x - 2$ p $10x^2 - 31x - 14$
q $6x^2 + 5x - 6$ r $16x^2 - 16x - 5$
s $18x^2 - 27x + 10$ t $15x^2 - 11x + 2$
u $21x^2 - 37x + 12$

6 a $a^2 + ac + ab + bc$ b $a^2 + ac - ab - bc$
c $ab + bc - a^2 - ac$ d $xy - xz - y^2 + yz$
e $yz - y^2 - xz + xy$ f $1 + y - x - xy$
g $2x^2 - 3xy - 2y^2$ h $2a^2 - ab - b^2$
i $6x^2 + xy - y^2$ j $6a^2 + 4a - 3ab - 2b$
k $12x^2 - 25xy + 12y^2$ l $3x^2y - yz^2 - 2xyz$

7 a $x^2 + 9x + 20$
b i 56 m^2 ii 36 m^2

8 a $2x^2$ b $2x^2 - 30x + 100$

9 a $150 - 50x + 4x^2$ b 66 m^2

10 a 3 b 2 c 6, 6 d 2, 18
e 2, 6 f 3, 15 g $2x$, $5x$, 3 h $3x$, $15x$, 4
i $7x$, 3, $17x$ j $3x$, 4, $11x$

11 a $a = 3, b = 2$ or $a = 2, b = 3$
b $a = -3, b = -2$ or $a = -2, b = -3$
c $a = 3, b = -2$ or $a = -2, b = 3$
d $a = 2, b = -3$ or $a = -3, b = 2$

12 a $x^3 + 2x^2 + 2x + 1$ b $x^3 - 3x^2 + 5x - 6$
c $4x^3 - 4x^2 + 9x - 4$ d $x^3 + 2x^2 - 2x + 3$
e $10x^3 - 17x^2 + 7x - 6$
f $8x^3 - 18x^2 + 35x - 49$
g $x^3 + ax - a^2x + a^2$ h $x^3 - 2ax^2 + a^3$
i $x^3 + a^3$ j $x^3 - a^3$

13 $x^3 + 6x^2 + 11x + 6$

Exercise 8B

1 a $+3x + 9 = x^2 + 6x + 9$
b $+5x + 25 = x^2 + 10x + 25$
c $-2x + 4 = x^2 - 4x + 4$
d $-7x + 49 = x^2 - 14x + 49$

2 a i $x^2 + 6x + 9$ ii $x^2 + 22x + 121$
iii $x^2 + 30x + 225$
b i $x^2 - 4x + 4$ ii $x^2 - 18x + 81$
iii $x^2 - 60x + 900$

3 a $+4x - 16 = x^2 - 16$ b $-10x - 100 = x^2 - 100$
c $+2x - 2x - 1 = 4x^2 - 1$
d $-12x + 12x - 16 = 9x^2 - 16$

4 a $x^2 + 2x + 1$ b $x^2 + 6x + 9$
c $x^2 + 4x + 4$ d $x^2 + 10x + 25$
e $x^2 + 8x + 16$ f $x^2 + 18x + 81$
g $x^2 + 14x + 49$ h $x^2 + 20x + 100$
i $x^2 - 4x + 4$ j $x^2 - 12x + 36$
k $x^2 - 2x + 1$ l $x^2 - 6x + 9$
m $x^2 - 18x + 81$ n $x^2 - 14x + 49$
o $x^2 - 8x + 16$ p $x^2 - 24x + 144$

5 a $4x^2 + 4x + 1$ b $4x^2 + 20x + 25$
c $9x^2 + 12x + 4$ d $9x^2 + 6x + 1$
e $25x^2 + 20x + 4$ f $16x^2 + 24x + 9$
g $49 + 28x + 4x^2$ h $25 + 30x + 9x^2$
i $4x^2 - 12x + 9$ j $9x^2 - 6x + 1$
k $16x^2 - 40x + 25$ l $4x^2 - 36x + 81$
m $9x^2 + 30xy + 25y^2$ n $4x^2 + 16xy + 16y^2$
o $49x^2 + 42xy + 9y^2$ p $36x^2 + 60xy + 25y^2$
q $16x^2 - 72xy + 81y^2$ r $4x^2 - 28xy + 49y^2$
s $9x^2 - 60xy + 100y^2$ t $16x^2 - 48xy + 36y^2$
u $81x^2 - 36xy + 4y^2$

6 a $9 - 6x + x^2$ b $25 - 10x + x^2$
c $1 - 2x + x^2$ d $36 - 12x + x^2$
e $121 - 22x + x^2$ f $16 - 8x + x^2$
g $49 - 14x + x^2$ h $144 - 24x + x^2$
i $64 - 32x + 4x^2$ j $4 - 12x + 9x^2$
k $81 - 36x + 4x^2$ l $100 - 80x + 16x^2$

7 a $x^2 - 1$ b $x^2 - 9$ c $x^2 - 64$ d $x^2 - 16$
e $x^2 - 144$ f $x^2 - 121$ g $x^2 - 81$ h $x^2 - 25$
i $x^2 - 36$ j $25 - x^2$ k $4 - x^2$ l $49 - x^2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 **a** $9x^2 - 4$ **b** $25x^2 - 16$ **c** $16x^2 - 9$
d $49x^2 - 9y^2$ **e** $81x^2 - 25y^2$
f $121x^2 - y^2$ **g** $64x^2 - 4y^2$
h $100x^2 - 81y^2$ **i** $49x^2 - 25y^2$
j $36x^2 - 121y^2$ **k** $64x^2 - 9y^2$
l $81x^2 - 16y^2$

9 **a** **i** x^2 **ii** $x^2 - 4$
b No, they differ by 4

10 **a** $20 - 2x$ **b** $(20 - 2x)(20 - 2x) = 400 - 80x + 4x^2$
c 196 cm^2 **d** 588 cm^3

11 **a** $a + b$ **b** $(a + b)(a + b) = a^2 + 2ab + b^2$
c $a - b$ **d** $(a - b)(a - b) = a^2 - 2ab + b^2$
e $4ab$ **f** ab so yes four courts area is $4ab$

12 **a** $x^2 - 1$ **b** No, area of rectangle is 1 square unit less

13 **a** $a^2 - b^2$
b **i** $(a - b)^2 = a^2 - 2ab + b^2$
ii $b(a - b) = ab - b^2$ **iii** $b(a - b) = ab - b^2$
c yes, $a^2 - 2ab + b^2 + ab - b^2 + ab - b^2 = a^2 - b^2$

14 **a** $x^2 + 4x$ **b** $-4x + 1$ **c** $x^2 + 6x - 9$
d $-x^2 - 2x$ **e** 1 **f** $4x$
g $-12x - 8$ **h** $-10x + 2$
i $x^2 + 4xy - y^2$ **j** $8x^2 + 18$ **k** $-8x$
l $2x^2 - 12x + 18$ **m** $9x^2 - 48x + 48$
n $x^2 + 6xy + y^2$

Exercise 8C

1 **a** 4 **b** 10 **c** 5 **d** 6 **e** 1
f 25 **g** 8 **h** 36

2 **a** x **b** x **c** a **d** $2a$
e $-2y$ **f** $-3x$ **g** $-2x$ **h** $-10x$
i $-2x$

3 **a** **i** 6 **ii** $3x$ **iii** $6x$
b iii
c terms have no common factor

4 **a** $2x$ **b** $6a$ **c** 2 **d** 4 **e** 3
f 1 **g** $3x$ **h** $3n$ **i** $2y$
j $2x$ **k** $2xy$ **l** $5ab$

5 **a** $7(x + 1)$ **b** $3(x + 1)$ **c** $4(x - 1)$ **d** $5(x - 1)$
e $4(1 + 2y)$ **f** $5(2 + a)$ **g** $3(1 - 3b)$
h $2(3 - x)$ **i** $3(4a + b)$ **j** $6(m + n)$
k $2(5x - 4y)$ **l** $4(a - 5b)$
m $x(x + 2)$ **n** $a(a - 4)$ **o** $y(y - 7)$ **p** $x(1 - x)$
q $3p(p + 1)$ **r** $8x(1 - x)$
s $4b(b + 3)$ **t** $2y(3 - 5y)$
u $3a(4 - 5a)$ **v** $9m(1 + 2m)$
w $16x(y - 3x)$ **x** $7ab(1 - 4b)$

6 **a** $-4(2x + 1)$ **b** $-2(2x + 1)$
c $-5(2x + y)$ **d** $-7(a + 2b)$
e $-3(3x + 4)$ **f** $-2(3y + 4)$
g $-5(2x + 3y)$ **h** $-4(m + 5n)$
i $-3x(x + 6)$ **j** $-4x(2x + 3)$
k $-2y(8y + 3)$ **l** $-5a(a + 2)$
m $-2x(3 + 10x)$ **n** $-3p(2 + 5p)$
o $-8b(2 + b)$ **p** $-9x(1 + 3x)$

7 **a** $(x + 3)(4 + x)$ **b** $(x + 1)(3 + x)$
c $(m - 3)(7 + m)$ **d** $(x - 7)(x + 2)$
e $(a + 4)(8 - a)$ **f** $(x + 1)(5 - x)$
g $(y + 3)(y - 2)$ **h** $(x + 2)(a - x)$
i $(2t + 5)(t + 3)$ **j** $(5m - 2)(m + 4)$
k $(4y - 1)(y - 1)$ **l** $(7 - 3x)(1 + x)$

8 **a** $6(a + 5)$ **b** $5(x - 3)$ **c** $2(4b + 9)$
d $x(x - 4)$ **e** $y(y + 9)$ **f** $a(a - 3)$ **g** $xy(x - 4 + y)$
h $2ab(3 - 5a + 4b)$ **i** $(m + 5)(m + 2)$
j $(x + 3)(x - 2)$ **k** $(b - 2)(b + 1)$
l $(2x + 1)(x - 1)$ **m** $(3 - 2y)(y - 5)$
n $(x + 4)(x + 9)$ **o** $(y + 1)(y - 3)$

9 **a** $4(x + 2)$ **b** $2(x + 3)$ **c** $10(x + 2)$
d $2(x + 7)$ **e** $2(2x + 3)$ **f** $2(x + 7)$

10 $4x$

11 **a** $t(5 - t)$
b **i** 0 m **ii** 6 m **iii** 4 m
c 5 seconds

12 **a** 63 **b** 72 **c** -20 **d** -70
e 69 **f** 189

13 **a** $3(a^2 + 3a + 4)$ **b** $z(5z - 10 + y)$
c $x(x - 2y + xy)$ **d** $2b(2y - 1 + 3b)$
e $-4y(3x + 2z + 5xz)$ **f** $ab(3 + 4b + 6a)$

14 **a** $-4(x - 3) = 4(3 - x)$
b $-3(x - 3) = 3(3 - x)$
c $-8(n - 1) = 8(1 - n)$
d $-3(b - 1) = 3(1 - b)$
e $-5m(1 - m) = 5m(m - 1)$
f $-7x(1 - x) = 7x(x - 1)$
g $-5x(1 - x) = 5x(x - 1)$
h $-2y(2 - 11y) = 2y(11y - 2)$
i $-4n(2 - 3n) = 4n(3n - 2)$
j $-4(2y - 5) = 4(5 - 2y)$
k $-5(3mn - 2) = 5(2 - 3mn)$
l $-15(x - 3) = 15(3 - x)$

15 **a** $(x - 4)(x - 3)$ **b** $(x - 5)(x + 2)$
c $(x - 3)(x + 3)$ **d** $(x - 4)(3x - 5)$
e $(2x - 5)(3 - x)$ **f** $(x - 2)(2x - 1)$
g $(x - 3)(4 - x)$ **h** $(x - 5)(x - 2)$
i $(x - 3)(x - 2)$

Exercise 8D

1 **a** $x^2 - 4$ **b** $x^2 - 49$ **c** $4x^2 - 1$ **d** $x^2 - y^2$
e $9x^2 - y^2$ **f** $a^2 - b^2$

2 **a** 3 **b** 11 **c** 9 **d** 20
e $2x$ **f** $3a$ **g** $5b$ **h** $7y$

3 **a** $(x + 4)(x - 4)$
b $x^2 - (12)^2 = (x + 12)(x - 12)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c $(4x)^2 - (1)^2 = (4x+1)(4x-1)$
d $(3a)^2 - (2b)^2 = (3a+2b)(3a-2b)$

4 a $(x+3)(x-3)$ b $(y+5)(y-5)$
c $(y+1)(y-1)$ d $(x+8)(x-8)$
e $(x+4)(x-4)$ f $(b+7)(b-7)$
g $(a+9)(a-9)$ h $(x+y)(x-y)$
i $(a+b)(a-b)$ j $(4+a)(4-a)$
k $(5+x)(5-x)$ l $(1+b)(1-b)$
m $(6+y)(6-y)$ n $(11+b)(11-b)$
o $(x+20)(x-20)$ p $(30+y)(30-y)$

5 a $(2x+5)(2x-5)$ b $(3x+7)(3x-7)$
c $(5b+2)(5b-2)$ d $(2m+11)(2m-11)$
e $(10y+3)(10y-3)$ f $(9a+2)(9a-2)$
g $(1+2x)(1-2x)$ h $(5+8b)(5-8b)$
i $(4+3y)(4-3y)$ j $(6x+y)(6x-y)$
k $(2x+5y)(2x-5y)$ l $(8a+7b)(8a-7b)$
m $(2p+5q)(2p-5q)$ n $(9m+2n)(9m-2n)$
o $(5a+7b)(5a-7b)$ p $(10a+3b)(10a-3b)$

6 a $3(x+6)(x-6)$ b $10(a+1)(a-1)$
c $6(x+2)(x-2)$ d $4(y+4)(y-4)$
e $2(7+x)(7-x)$ f $8(2+m)(2-m)$
g $5(xy+1)(xy-1)$ h $3(1+xy)(1-xy)$
i $7(3+ab)(3-ab)$

7 a $(x+8)(x+2)$ b $(x+5)(x+1)$
c $(x+14)(x+6)$ d $(x+2)(x-8)$
e $(x-6)(x-8)$ f $(x+3)(x-9)$
g $(10+x)(4-x)$ h $-x(x+4)$
i $(17+x)(1-x)$

8 a $4(3+t)(3-t)$
b i 36 m ii 20 m
c 3 seconds

9 a i x^2 ii $(30+x)(30-x)$
b i 500 cm^2 ii 675 cm^2

10 a $(x+3)(x-3)$ b $(4x+11)(4x-11)$
c $(2+5a)(2-5a)$ d $(x+y)(x-y)$
e $(2b+5a)(2b-5a)$ f $(c+6ab)(c-6ab)$
g $(yz+4x)(yz-4x)$ h $(b+30a)(b-30a)$

11 a Factorise each binomial
$(4x+2)(4x-2) = 2(2x+1)\,2(2x-1)$
$= 4(2x+1)(2x-1)$
b Take out common factor of 4

12 $9-(x-1)^2$
$= (3+x-1)(3-(x-1))$ insert brackets when subtracting a binomial
$= (2+x)(3-x+1)$ remember $-1 \times -1 = +1$
$= (2+x)(4-x)$

13 a $\left(x+\frac{1}{2}\right)\left(x-\frac{1}{2}\right)$ b $\left(x+\frac{2}{5}\right)\left(x-\frac{2}{5}\right)$
c $\left(5x+\frac{3}{4}\right)\left(5x-\frac{3}{4}\right)$ d $\left(\frac{x}{3}+1\right)\left(\frac{x}{3}-1\right)$
e $\left(\frac{a}{2}+\frac{b}{3}\right)\left(\frac{a}{2}-\frac{b}{3}\right)$ f $5\left(\frac{x}{3}+\frac{1}{2}\right)\left(\frac{x}{3}-\frac{1}{2}\right)$
g $7\left(\frac{a}{5}+\frac{2b}{3}\right)\left(\frac{a}{5}-\frac{2b}{3}\right)$
h $\frac{1}{2}\left(\frac{a}{2}+\frac{b}{3}\right)\left(\frac{a}{2}-\frac{b}{3}\right)$ i $(x+y)(x-y)(x^2+y^2)$
j $2(a+b)(a-b)(a^2+b^2)$
k $21(a+b)(a-b)(a^2+b^2)$
l $\frac{1}{3}(x+y)(x-y)(x^2+y^2)$

Exercise 8E

1 a $2x-2$ b $3a+12$ c $-5+5a$ d $-6+2x$
e a^2+5a f $2b-b^2$ g x^2-4x h $4y-y^2$
i $ax+x+2a+2$ j $ax-3a+5x-15$
k $bx-2b-3x+6$ l $c-cx-4+4x$

2 a $2+x$ b $3-x$ c $5-x$ d $x+4$
e $a+1$ f $a-1$ g $1-a$ h $1+2a$

3 a $(x-3)(x-2)$ b $(x+4)(x+3)$
c $(x-7)(x+4)$ d $(2x+1)(3-x)$
e $(3x-2)(4-x)$ f $(2x+3)(2x-3)$
g $(5-x)(3x+2)$ h $(x+1)(2-3x)$
i $(x-2)(x+1)$

4 a $(x+3)(x+2)$ b $(x+4)(x+3)$
c $(x+7)(x+2)$ d $(x-6)(x+4)$
e $(x-4)(x+6)$ f $(x-3)(x+10)$
g $(x+2)(x-18)$ h $(x+3)(x-14)$
i $(x+4)(x-18)$ j $(x-2)(x-a)$
k $(x-3)(x-3c)$ l $(x-5)(x-3a)$

5 a $(3a+5c)(b+d)$ b $(4b-7c)(a+d)$
c $(y-4z)(2x+3w)$ d $(s-2)(5r+t)$
e $(x+3y)(4x-3)$ f $(2b-a)(a-c)$

6 a $(x-b)(x+1)$ b $(x-c)(x+1)$
c $(x+b)(x+1)$ d $(x+c)(x-1)$
e $(x+a)(x-1)$ f $(x-b)(x-1)$

7 a $(x-7)(2x+1)$ b $(x+5)(x+2)$
c $(x+3)(2x-1)$ d $(1-2x)(3x+4)$
e $(x-5)(11+a)$ f $(3-2x)(4y-1)$
g $(n+2)(3m-1)$ h $(3-r)(5p+8)$
i $(2-y)(8x+3)$

8 a $x^2+4x-ax-4a$ b $x^2-dx-cx+cd$
c $2x-xz+2y-yz$ d $ax+bx-a-b$
e $3cx-3bx-bc+b^2$ f $2xy+2xz-y^2-yz$
g $6ab+15ac+2b^2+5bc$
h $3my+mz-6xy-2xz$

9 a $(x+2)(x+5)$ b $(x+3)(x+5)$
c $(x+4)(x+6)$ d $(x-3)(x+2)$
e $(x+6)(x-2)$ f $(x-9)(x-2)$

10 a Method 1: $a(x+7)-3(x+7) = (x+7)(a-3)$
Method 2: $x(a-3)+7(a-3) = (a-3)(x+7)$
b i $(x-3)(b+2)$ ii $(x+2)(y-4)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

iii $(2m+3)(2m-5n)$ iv $(2-n)(m-3)$
v $(1-2b)(4a+3b)$ vi $(3a-1)(b+4c)$

11 Answers will vary

12 a $(a-3)(2-x-c)$ b $(2a+1)(b+5-a)$
c $(a+1)(x-4-b)$ d $(a-b)(3-b-2a)$
e $(1-a)(c-x+2)$ f $(x-2)(a+2b-1)$
g $(a-3c)(a-2b+3bc)$
h $(1-2y)(3x-5z+y)$
i $(x-4)(3x+y-2z)$ j $(ab-2c)(2x+3y-1)$

Exercise 8F

1 a x^2+4x+3 b $x^2+9x+14$
c $x^2+8x-33$ d x^2+x-30
e $x^2+7x-60$ f $x^2+9x-52$
g $x^2-8x+12$ h $x^2-31x+220$
i $x^2-10x+9$

2 a 3, 2 b 5, 2 c 12, 1 d 4, 5
e 5, −1 f −7, 1 g 5, −3 h −6, 5
i −3, −2 j −9, −2 k −5, −8 l −50, −2

3 a $(x+2)(x+1)$ b $(x+3)(x+1)$
c $(x+6)(x+2)$ d $(x+9)(x+1)$
e $(x+7)(x+1)$ f $(x+14)(x+1)$
g $(x+4)(x+2)$ h $(x+3)(x+4)$
i $(x+8)(x+2)$ j $(x+5)(x+3)$
k $(x+4)(x+5)$ l $(x+8)(x+3)$

4 a $(x+4)(x-1)$ b $(x+2)(x-1)$
c $(x+5)(x-1)$ d $(x+7)(x-2)$
e $(x+5)(x-3)$ f $(x+10)(x-2)$
g $(x+6)(x-3)$ h $(x+9)(x-2)$
i $(x+4)(x-3)$

5 a $(x-5)(x-1)$ b $(x-1)(x-1)$
c $(x-1)(x-4)$ d $(x-8)(x-1)$
e $(x-2)(x-2)$ f $(x-6)(x-2)$
g $(x-9)(x-2)$ h $(x-7)(x-3)$
i $(x-3)(x-2)$

6 a $(x-8)(x+1)$ b $(x-4)(x+1)$
c $(x-6)(x+1)$ d $(x-8)(x+2)$
e $(x-6)(x+4)$ f $(x-5)(x+3)$
g $(x-4)(x+3)$ h $(x-12)(x+1)$
i $(x-6)(x+2)$

7 a $2(x+4)(x+1)$ b $2(x+10)(x+1)$
c $3(x+2)(x+4)$ d $2(x+10)(x-3)$
e $2(x-9)(x+2)$ f $4(x-1)(x-1)$
g $2(x-2)(x+3)$ h $6(x-6)(x+1)$
i $5(x-4)(x-2)$ j $3(x-5)(x-6)$
k $2(x-5)(x+2)$ l $3(x-4)(x+3)$

8 a $6x$ b $6x$ or $10x$ c $x, 4x, 11x$ d $x, 4x, 11x$
e $9x, 11x, 19x$ f $9x, 11x, 19x$
g $0x, 6x, 15x$ h $0x, 24x$

9 a i $x(x+2)$ ii $x^2+2x-15$
iii $(x+5)(x-3)$
b i 105 m^2 ii 48 m^2

10 a $(x+4)^2$ b $(x+5)^2$ c $(x+15)^2$
d $(x-1)^2$ e $(x-7)^2$ f $(x-13)^2$
g $2(x+1)^2$ h $5(x-3)^2$
i $-3(x-6)^2$

11 b, c, e, f

12 a $(x-1)^2-9$ b $(x+2)^2-5$
c $(x+5)^2-22$ d $(x-8)^2-67$
e $(x+9)^2-74$ f $(x-16)^2-267$

Exercise 8G

1 a 2, 3 b 2, 6 c 5, −2 d 8, −3
e −6, −3 f −5, −7 g −10, 3 h −7, 4

2 a $= 2x^2+2x+5x+5$
$= 2x(x+1)+5(x+1)$
$= (x+1)(2x+5)$
b $= 3x^2+6x+2x+4$
$= 3x(x+2)+2(x+2)$
$= (x+2)(3x+2)$
c $= 2x^2-3x-4x+6$
$= x(2x-3)-2(2x-3)$
$= (2x-3)(x-2)$
d $= 5x^2+10x-x-2$
$= 5x(x+2)-1(x+2)$
$= (x+2)(5x-1)$
e $= 4x^2+8x+3x+6$
$= 4x(x+2)+3(x+2)$
$= (x+2)(4x+3)$
f $= 6x^2-9x+2x-3$
$= 3x(2x-3)+1(2x-3)$
$= (2x-3)(3x+1)$

3 a $(2x+1)(x+4)$ b $(3x+1)(x+2)$
c $(2x+3)(x+2)$ d $(3x+2)(x+2)$
e $(5x+2)(x+2)$ f $(2x+3)(x+4)$
g $(3x+5)(2x+1)$ h $(4x+1)(x+1)$
i $(4x+5)(2x+1)$

4 a $(3x+5)(x-1)$ b $(5x-4)(x+2)$
c $(2x+3)(4x-1)$ d $(2x+1)(3x-8)$
e $(2x+1)(5x-4)$ f $(x-3)(5x+4)$
g $(2x-5)(2x-3)$ h $(x-6)(2x-3)$
i $(2x-5)(3x-2)$ j $(3x-4)(4x+1)$
k $(2x-3)(2x-3)$ l $(x+3)(7x-3)$
m $(x+5)(9x-1)$ n $(x-2)(3x-8)$
o $(2x-5)(2x+3)$

5 a $(2x+1)(5x+11)$ b $(3x+4)(5x-2)$
c $(2x-3)(10x-3)$ d $(2x+1)(9x-5)$
e $(5x-3)(5x+4)$ f $(4x+1)(8x-5)$
g $(3x+2)(9x-4)$ h $(3x+1)(11x+10)$
i $(6x-5)(9x+1)$ j $(2x-3)(6x-7)$
k $(3x-1)(25x-6)$ l $(6x-1)(15x+8)$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 **a** $2(3x-2)(5x+1)$ **b** $6(x-1)(2x+5)$
c $3(3x-5)(3x-1)$ **d** $7(x-3)(3x-2)$
e $4(3x-2)(3x+5)$ **f** $5(2x-3)(5x+4)$

7 **a** $-(x-2)(2x-3)$ **b** $-(x-1)(5x+8)$
c $-(2x+1)(3x-8)$ **d** $-(x+3)(5x-6)$
e $-(2x-5)(2x-3)$ **f** $-(2x-1)(4x-5)$

8 **a** $(x+4)(2x-5)$
b $(2x-5)(x+4)$
c No, you get the same result
d **i** $(x+3)(3x-4)$ **ii** $(x-2)(5x+7)$
iii $(2x-1)(3x+4)$

9 Answers will vary

10 see answers to Questions **4** and **5**

Progress quiz

1 **a** x^2+6x+8 **b** $a^2+3a-40$
c $2x^2+9x-18$ **d** $3a^2-7ab+2b^2$

2 **a** $y^2+8y+16$ **b** x^2-6x+9
c $4a^2-12a+9$ **d** $49k^2+28km+4m^2$

3 **a** x^2-25 **b** $121x^2-81y^2$

4 **a** $5(5a-3)$ **b** $x(x-7)$
c $-4x(3x+4)$ **d** $(a+3)(2+a)$
e $(8+a)(7-a)$ **f** $(k-4)(k-1)$

5 **a** $(x+9)(x-9)$ **b** $(4a+7)(4a-7)$
c $(5x+y)(5x-y)$ **d** $2(a+5)(a-5)$
e $12(xy+1)(xy-1)$ **f** $(h+11)(h-5)$

6 **a** $(x+7)(x+2)$ **b** $(a+5)(a-4)$
c $(x-h)(x+1)$

7 **a** $(x-3)(2x+3)$ **b** $(3a+2)(p-5)$

8 **a** $(x+4)(x+2)$ **b** $(a+5)(a-3)$
c $(m-6)(m-5)$ **d** $2(k-3)(k+4)$

9 **a** $(2k+3)(k+2)$ **b** $(x+5)(2x+1)$
c $(3a-2)(a+4)$ **d** $(5m-2)(2m-3)$

Exercise 8H

1 **a** $\frac{1}{3}$ **b** $\frac{3}{2}$ **c** $\frac{x}{2}$ **d** $\frac{7x}{2}$ **e** $\frac{3}{x}$
f $\frac{1}{2x}$ **g** $\frac{x+1}{2}$ **h** $2(x-4)$

2 **a** $3(x+2)$ **b** $20(1-2x)$ **c** $x(x-7)$
d $6x(x+4)$

3 **a** $\frac{2(x-2)}{8}=\frac{x-2}{4}$ **b** $\frac{6(2-3x)}{x(2-3x)}$
c $\frac{(x+3)(x+2)}{2(x-1)}$

4 **a** $\frac{3}{4}$ **b** $\frac{1}{3}$ **c** 4 **d** $x-5$
e $\frac{2(x-1)}{3}$ **f** $\frac{2}{x+4}$

5 **a** $x-1$ **b** $\frac{2(x-3)}{5}$ **c** $\frac{2}{3}$ **d** 2
e $x-3$ **f** $\frac{2(2x+5)}{5}$ **g** $\frac{3}{2}$ **h** $\frac{4}{3}$

6 **a** $x-10$ **b** $x-7$ **c** $x-5$ **d** $\frac{2}{x+20}$
e $\frac{5}{x+6}$ **f** $\frac{3}{x-9}$

7 **a** $\frac{x-4}{2}$ **b** $x-3$ **c** $3(x-3)$ **d** $\frac{x+4}{2(x-5)}$

8 **a** x **b** $\frac{2(x-2)}{x+2}$ **c** $\frac{4}{x+1}$ **d** $\frac{x-2}{2(x+2)}$
e $\frac{2(x+2)^2}{3(x+4)}$ **f** $\frac{5}{x+2}$

9 **a** $x+2$ **b** $x+4$ **c** $x-3$ **d** $\frac{1}{x+3}$
e $\frac{1}{x-2}$ **f** $\frac{1}{x-10}$

10 **a** $(x+2)(x-5)$ **b** $\frac{x+2}{x+3}$ **c** $\frac{x-3}{x-4}$
d $\frac{x-5}{x+2}$ **e** $\frac{3x-1}{2-15x}$ **f** $\frac{x-4}{3-x}$ **g** $\frac{x+5}{2(x+4)}$
h $\frac{3}{2(x+3)}$

11 **a** -1 **b** -1 **c** -8 **d** $-\frac{1}{3}$
e $-\frac{1}{6}$ **f** $-(x+3)$

12 **a** $a+1$ **b** $5(a-3)$ **c** $\frac{x+7}{2}$ **d** $\frac{x+2}{6}$
e $\frac{x+3}{2}$ **f** $\frac{11}{x-2}$

13 **a** $-\frac{x+3}{2}$ **b** $-\frac{x-7}{3}$ **c** $-\frac{x-8}{x+8}$ **d** $-\frac{2}{x+2}$
e $-\frac{4}{x+3}$ **f** $\frac{3(x+1)}{4}$ **g** $\frac{3(2x+3)}{2x}$
h $-\frac{1}{2(x+2)}$ **i** $\frac{x}{3}$ **j** $-\frac{2}{x-2}$

Exercise 8I

1 **a** 24 **b** 15 **c** 143 **d** 36

2 **a** $4x$ **b** $21x$ **c** 3 **d** 2 **e** 8
f 90

3 **a** $\frac{3x}{12}+\frac{8x}{12}=\frac{11x}{12}$
b $\frac{25x}{35}-\frac{14x}{35}=\frac{11x}{35}$
c $\frac{2(x+1)}{4}+\frac{(2x+3)}{4}=\frac{2x+2+2x+3}{4}=\frac{4x+5}{4}$

4 **a** 15 **b** 14 **c** 8 **d** 6
e 10

5 **a** $\frac{9x}{14}$ **b** $\frac{2x}{5}$ **c** $\frac{x}{8}$ **d** $\frac{14x}{45}$
e $\frac{y}{56}$ **f** $\frac{13a}{22}$ **g** $\frac{2b}{9}$ **h** $\frac{m}{6}$
i $\frac{11m}{12}$ **j** $\frac{15a}{28}$ **k** $\frac{x}{2}$ **l** $-\frac{20p}{63}$
m $-\frac{5b}{18}$ **n** $\frac{61y}{40}$ **o** $\frac{13x}{35}$ **p** $\frac{5x}{12}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 **a** $\frac{7x+11}{10}$ **b** $\frac{7x}{12}$ **c** $\frac{15a-51}{56}$ **d** $\frac{11y+9}{30}$
e $\frac{13m+28}{40}$ **f** $\frac{5x-13}{24}$ **g** $\frac{11b-6}{24}$
h $\frac{7x}{6}$ **i** $\frac{7y-8}{14}$ **j** $\frac{5t-4}{16}$ **k** $\frac{34-10x}{21}$
l $\frac{8m-9}{12}$

7 **a** $\frac{11}{2x}$ **b** $\frac{1}{3x}$ **c** $-\frac{3}{4x}$ **d** $\frac{14}{9x}$
e $\frac{7}{20x}$ **f** $\frac{13}{15x}$ **g** $-\frac{31}{4x}$ **h** $-\frac{29}{12x}$

8 **a** $\frac{3x+2}{x^2}$ **b** $\frac{5+4x}{x^2}$ **c** $\frac{7x+3}{x^2}$ **d** $\frac{4x-5}{x^2}$
e $\frac{3-8x}{x^2}$ **f** $\frac{x-4}{x^2}$ **g** $\frac{6x-7}{2x^2}$ **h** $\frac{9-2x}{3x^2}$

9 **a** $\frac{8+x^2}{4x}$ **b** $\frac{x^2-10}{2x}$ **c** $\frac{-6-4x^2}{3x}$
d $\frac{6-5x^2}{4x}$ **e** $\frac{9x^2-10}{12x}$ **f** $\frac{3-x^2}{9x}$ **g** $\frac{15x^2-4}{10x}$
h $\frac{-25-6x^2}{20x}$

10 **a** $\frac{x}{3}$ **b** $\frac{x}{8}$ **c** $\frac{x}{2}$ **d** $\frac{x}{5}$
e $\frac{8x}{9}$ **f** $\frac{x}{4}$

11 **a** didn't make a common denominator, $\frac{7x}{15}$

b didn't use brackets: $2(x+1) = 2x+2, \frac{7x+2}{10}$

c didn't use brackets: $3(x-1) = 3x-3, \frac{13x-3}{6}$

d didn't multiply numerator in $\frac{2}{x}$ by x as well as denominator, $\frac{2x-3}{x^2}$

12 **a** $\frac{8x+2}{8} = \frac{2(4x+1)}{8} = \frac{4x+1}{4}$

b $\frac{4x+1}{4}$

c Using denominator 8 does not give answer in simplified form and requires extra steps. Preferable to use actual LCD

13 **a** $-\frac{43x}{30}$ **b** $\frac{5x}{12}$ **c** $\frac{13x}{24}$ **d** $\frac{43x-5}{60}$
e $\frac{23x-35}{42}$ **f** $\frac{29x+28}{40}$ **g** $\frac{14}{3x}$ **h** $\frac{1}{6x}$
i $-\frac{11}{20x}$ **j** $\frac{24-x}{6x^2}$ **k** $\frac{60x-21}{14x^2}$
l $\frac{3-4x}{9x^2}$ **m** $\frac{30-2x^2}{15x}$ **n** $\frac{11x^2-3}{6x}$ **o** $\frac{18-2x^2}{45x}$

Exercise 8J

1 **a** $-2x-6$ **b** $-5x-5$ **c** $-14-21x$
d $-3x+3$ **e** $-30+20x$ **f** $-16+64x$

2 **a** 9 **b** 16 **c** x^2 **d** $2x$
e $(x-1)(x+1)$ **f** $(x-2)(x+3)$
g $(2x-1)(x-4)$ **h** $(x+1)^2$

3 **a** $\frac{1-x}{12}$ **b** $\frac{2x-14}{15}$ **c** $\frac{x-9}{6}$ **d** $\frac{-7x-14}{10}$
e $\frac{9x-4}{8}$ **f** $\frac{-x-24}{28}$ **g** $\frac{5x-3}{12}$
h $\frac{1-18x}{15}$ **i** $\frac{8x-23}{30}$

4 **a** $\frac{13-x}{6}$ **b** $\frac{2x+2}{35}$ **c** $\frac{x-5}{4}$ **d** $\frac{22x-41}{21}$
e $\frac{17x}{20}$ **f** $\frac{30-13x}{24}$ **g** $\frac{14x+4}{9}$ **h** $\frac{20x-9}{28}$
i $\frac{10-11x}{56}$

5 **a** $\frac{7x-1}{(x-1)(x+1)}$ **b** $\frac{7x-7}{(x+4)(x-3)}$
c $\frac{7x+1}{(x-2)(x+3)}$ **d** $\frac{5x+13}{(x-4)(x+7)}$
e $\frac{4x+15}{(x+2)(x+3)}$ **f** $\frac{x-26}{(x+4)(x-6)}$
g $\frac{x+9}{(x+5)(x+1)}$ **h** $\frac{16-6x}{(x-3)(x-2)}$
i $\frac{7-2x}{(x-5)(x-6)}$

6 **a** $\frac{1-3x}{(x+1)^2}$ **b** $\frac{-4x-10}{(x+3)^2}$
c $\frac{3x-2}{(x-2)^2}$ **d** $\frac{18-2x}{(x-5)^2}$
e $\frac{9-x}{(x-6)^2}$ **f** $\frac{14-3x}{(x-4)^2}$
g $\frac{4x+7}{(2x+1)^2}$ **h** $\frac{1-12x}{(3x+2)^2}$
i $\frac{20x-1}{(1-4x)^2}$

7 **a** $\frac{5x-2}{(x-1)^2}$ **b** $\frac{19x+8}{12x}$
c $\frac{10x^2-11x+4}{20x}$ **d** $\frac{x^2+7x}{(x-5)(x+1)}$
e $\frac{2x^2-5x-3}{(4-x)(x-1)}$ **f** $\frac{x^2+2x+1}{(x-3)^2}$
g $d\frac{3-2x}{(x-2)^2}$ **h** $\frac{-x^2-11x}{(2x+1)(x+2)}$
i $\frac{x^2-4x-1}{(x+1)^2}$

8 **a** second line $-2 \times (-2) = +4$ not -4
b $\frac{33x+4}{10}$

9 **a** $\frac{3x+11}{(x+3)(x+4)(x+5)}$
b $\frac{2-2x}{(x+1)(x+2)(x+4)}$
c $\frac{26-10x}{(x-1)(x-3)(2-x)}$
d $\frac{3x-2}{(x+1)(x-5)}$ **e** $\frac{2x+9}{(x-4)(3-2x)}$
f $\frac{7x^2+7x}{(x+4)(2x-1)(3x+2)}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 **a** $\frac{5}{1-x}$ **b** $\frac{4x-3}{5-x}$ **c** $\frac{9}{7x-3}$ **d** $\frac{1-2x}{4-3x}$ **e** 1
f 0

11 **a** $\frac{11}{2(x+2)}$ **b** $\frac{1}{3(x-1)}$ **c** $\frac{23}{4(2x-1)}$
d $\frac{13-3x}{(x+3)(x-3)}$ **e** $\frac{5x-6}{2(x+2)(x-2)}$
f $\frac{30x+33}{(3x-4)(3x+4)}$ **g** $\frac{9x-27}{(x+3)(x+4)(x-5)}$
h $\frac{x+11}{(x-1)(x+3)^2}$ **i** $\frac{2x+5}{5(x-2)(x-5)}$
j $\frac{-2}{x(x-1)(x+1)}$

Exercise 8K

1 **a** 15 **b** 4 **c** 6 **d** 28
e 30 **f** 8

2 **a** $4x$ **b** $3x$ **c** $2(x+3)$ **d** $2x+5$ **e** 3
f $-(x+2)$ **g** $4(x-1)$ **h** $2(1-x)$
i $2x-1$

3 **a** 10 **b** 12 **c** 24 **d** 10 **e** $\frac{6}{7}$
f $7\frac{1}{2}$ **g** -8 **h** 15 **i** 4

4 **a** 13 **b** 1 **c** $1\frac{3}{5}$ **d** 59 **e** 1
f 5 **g** 8 **h** $3\frac{2}{7}$ **i** $-3\frac{1}{4}$

5 **a** -3 **b** -4 **c** 5 **d** 1
e -1 **f** 6

6 **a** $\frac{1}{16}$ **b** $\frac{1}{12}$ **c** $\frac{8}{15}$ **d** $\frac{1}{36}$ **e** $\frac{3}{4}$
f $\frac{5}{24}$ **g** $\frac{5}{12}$ **h** $-\frac{1}{6}$ **i** $2\frac{5}{6}$

7 **a** $-\frac{5}{2}$ **b** -5 **c** -19 **d** -4
e -1 **f** -6

8 **a** $\frac{x}{2}+\frac{2x}{3}=4$ **b** $x=3\frac{3}{7}$

9 **a** $\frac{1}{6}$ **b** 2 **c** 0 **d** $\frac{9}{13}$ **e** $\frac{3}{7}$
f $\frac{2}{11}$ **g** $1\frac{5}{7}$ **h** 0 **i** -12

10 **a** $\frac{x}{3}+\frac{x}{4}=77$ **b** 132 games

11 On the second line, not every term has been multiplied by 12. The $2x$ should be $24x$ to give an answer $x=\frac{3}{29}$.

12 On third line of working, $-2\times(-1)=+2$ not -2, giving answer $x=-4$

13 **a** $4\frac{1}{2}$ **b** $5\frac{2}{3}$ **c** $1\frac{1}{2}$ **d** 3
e 15 **f** -2

14 **a** $x=2ab$ **b** $x=\frac{2bd}{2a-bc}$ **c** $x=\frac{ac}{c-b}$
d $x=\frac{bd+be-ac}{c}$ **e** $x=\frac{4c-3b}{3a-4}$
f $x=\frac{6b+a}{5}$
g $x=-\frac{a^2}{2a-b-a^2}$ or $\frac{a^2}{a^2-2a+b}$
h $x=\frac{ac}{c-a}$ **i** $x=\frac{ac}{b}$ **j** $x=\frac{c-a}{b}$
k $x=\frac{b-bc}{a-c}$ **l** $x=\frac{ad-b}{c-d}$
m $x=ab-2a$ **n** $x=\frac{a+b}{1-a}$
o $x=\frac{2ab-a^2}{a-b}$

Problems and challenges

1 **a** 48, 49 **b** 33, 35 **c** 12, 15

2 **a** 15 **b** 5

3 $a=2$, $b=1$, $c=7$ and $d=8$

4 **a** $(n+1)^2+1$ or n^2+2n+2
b a number of answers

5 $(n-1)(n+1)$
i $n-1$ and $n+1$ are both even, since they are consecutive even numbers one of them is divisible by 4 hence their product is also divisible by 4
ii $n-1$, n, $n+1$ are 3 consecutive numbers, one of them must be divisible by 3. Since n is prime it must be $n-1$ or $n+1$ so their product is divisible by 3
iii n^2-1 is divisible by 3 and 4 and since they have no common factor it must also be divisible by $3\times4=12$.

6 Factorise each expression and cancel.

7 $4x^2-4x+1=(2x-1)^2$ which is always greater than or equal to zero

8 Ryan

Multiple-choice questions

1 A **2** E **3** D **4** C **5** B
6 D **7** A **8** E **9** B **10** A

Short-answer questions

1 **a** x^2+x-12 **b** $x^2-9x+14$
c $6x^2-5x-6$ **d** $9x^2+3x-12$

2 **a** x^2+6x+9 **b** $x^2-8x+16$
c $9x^2-12x+4$ **d** x^2-25 **e** $49-x^2$
f $121x^2-16$

3 **a** $4(a+3b)$ **b** $3x(2-3x)$
c $-5xy(x+2)$ **d** $(x-7)(x+3)$
e $(2x+1)(x-1)$ **f** $(x-2)(x-6)$

4 **a** $(x+10)(x-10)$ **b** $3(x+4)(x-4)$
c $(5x+y)(5x-y)$ **d** $(7+3x)(7-3x)$
e $(x-12)(x+6)$ **f** $(1-x)(1+x)$

5 **a** $(x-3)(x+6)$ **b** $(2x+5)(2x-1)$
c $(x-4)(3+2b)$

6 **a** $(x+3)(x+5)$ **b** $(x-6)(x+3)$
c $(x-6)(x-1)$ **d** $3(x+7)(x-2)$
e $2(x+4)^2$ **f** $(5x+2)(x+3)$
g $(2x-3)(2x+1)$ **h** $(3x-4)(2x-3)$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 a $x + 4$ b $\frac{2}{3}$ c $\frac{x-3}{5}$

8 a $\frac{1}{4}$ b $\frac{x-4}{2}$ c $\frac{x}{3}$ d $\frac{2}{5}$
e $\frac{2x+3}{50x}$ f 4

9 a $\frac{11x}{12}$ b $\frac{x-13}{24}$ c $\frac{5}{4x}$
d $\frac{7x-2}{x^2}$ e $\frac{8x+11}{(x+1)(x+2)}$
f $\frac{15-2x}{(x-4)^2}$

10 a $x = 20$ b $x = \frac{1}{6}$ c $x = 7$ d $x = -1\frac{2}{9}$

Extended-response questions

1 a $(x + 3)$ m
b i No change
ii $(x^2 - 1)$ m^2, 1 square metre less in area
c i width $= (x - 3)$ m, decreased by 3 metres
ii $A = (x + 7)(x - 3) = (x^2 + 4x - 21)$ m^2
iii $A = 0$ m^2

2 a 400 m^2
b i $L = W = (20 + 2x)$ m
ii $(4x^2 + 80x + 400)$ m^2
c $\frac{1}{4}$
d $4x(x + 20)$ m^2
e $x = 5$

Chapter 9

Exercise 9A

1 a i $\frac{1}{4}$ ii 0.25 iii 25%

b 

2

	Percentage	Decimal	Fraction	Number line
a	50%	0.5	$\frac{1}{2}$	
b	25%	0.25	$\frac{1}{4}$	
c	75%	0.75	$\frac{3}{4}$	
d	20%	0.2	$\frac{1}{5}$	
e	60%	0.6	$\frac{3}{5}$	
f	85%	0.85	$\frac{17}{20}$	

3 0.15, $\frac{2}{9}$, 1 in 4, 0.28, $\frac{1}{3}$, $\frac{2}{5}$, $\frac{3}{7}$, 2 in 3, 0.7, 0.9

4 a i $\{1, 2, 3, 4, 5, 6, 7\}$ ii $\frac{1}{7}$ iii $\frac{6}{7}$
iv $\frac{2}{7}$ v $\frac{6}{7}$
b i $\{2, 6, 7\}$ ii $\frac{1}{2}$ iii $\frac{1}{2}$ iv $\frac{1}{2}$
v 1
c i $\{1, 2, 3\}$ ii $\frac{2}{3}$ iii $\frac{1}{3}$ iv $\frac{5}{6}$
v $\frac{5}{6}$
d i $\{1, 2, 3\}$ ii $\frac{1}{3}$ iii $\frac{2}{3}$ iv $\frac{2}{3}$
v $\frac{2}{3}$
e i $\{1, 2, 3, 4\}$ ii $\frac{1}{7}$ iii $\frac{6}{7}$
iv $\frac{3}{7}$ v $\frac{5}{7}$
f i $\{2\}$ ii 1 iii 0 iv 1
v 1

5 a $\frac{1}{2}$ b $\frac{3}{8}$ c $\frac{1}{6}$ d $\frac{1}{4}$ e 1
f 0

6 a $\frac{1}{2}$ b $\frac{5}{8}$ c $\frac{5}{6}$ d $\frac{3}{4}$ e 0
f 1

7 a $\frac{1}{8}$ b $\frac{7}{8}$

8 a $\frac{1}{8}$ b $\frac{1}{4}$ c $\frac{3}{8}$ d $\frac{3}{8}$ e $\frac{5}{8}$
f 1 g 0 h $\frac{1}{4}$ i $\frac{3}{4}$ j $\frac{3}{4}$

9 a {H, A, R, S}
b i $\frac{1}{4}$ ii $\frac{1}{2}$ iii $\frac{1}{2}$

10 a $\frac{1}{52}$ b $\frac{1}{13}$ c $\frac{1}{26}$ d $\frac{1}{2}$
e $\frac{2}{13}$ f $\frac{12}{13}$ g $\frac{23}{26}$ h $\frac{25}{26}$

11 a $\frac{1}{6}$ b $\frac{1}{6}$ c $\frac{5}{6}$ d $\frac{1}{3}$ e $\frac{2}{3}$
f 1 g $\frac{1}{3}$ h $\frac{1}{2}$ i $\frac{5}{6}$

12 a $\frac{2}{11}$ b $\frac{9}{11}$ c $\frac{4}{11}$ d $\frac{7}{11}$
e $\frac{7}{11}$ f $\frac{3}{11}$ g $\frac{7}{11}$ h $\frac{4}{11}$

13 The sample space has four elements as the letter O appears twice {S, L, O, O} Amanda has only considered the name of the letter, not the total number of elements in the sample space. Pr (S) $= \frac{1}{4}$

14 a, d, f

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

15 a $\frac{12}{25}$ b $\frac{8}{25}$ c $\frac{1}{5}$ d $\frac{9}{25}$
e $\frac{8}{25}$ f $\frac{16}{25}$ g $\frac{4}{25}$ h $\frac{17}{25}$ i 0

16 a 31 mins
b $\frac{3}{31}$
c i $\frac{4}{31}$ ii $\frac{4}{31}$ iii $\frac{20}{31}$ iv $\frac{5}{31}$
v $\frac{8}{31}$ vi $\frac{11}{31}$

Exercise 9B

1 a 26
b i 10 ii 14 iii 5 iv 9
v 4 vi 7 vii 19
c i 12 ii 17

2 a B b D c A d C

3 a

	A	Not A	Total
B	7	8	15
Not B	3	1	4
Total	10	9	19

b

	A	Not A	Total
B	2	5	7
Not B	9	4	13
Total	11	9	20

4 a



b i 28 ii 21 iii 6
c i $\frac{1}{10}$ ii $\frac{1}{15}$ iii $\frac{19}{30}$

5 a i $\frac{2}{5}$ ii $\frac{1}{3}$ iii $\frac{7}{15}$ iv $\frac{1}{15}$
v $\frac{13}{15}$ vi $\frac{2}{15}$
b i $\frac{3}{7}$ ii $\frac{12}{35}$ iii $\frac{13}{35}$ iv $\frac{3}{35}$
v $\frac{34}{35}$ vi $\frac{1}{35}$

6 a

	Cream	Not cream	Total
Ice cream	5	20	25
Not ice cream	16	9	25
Total	21	29	50

b i 29 ii 9
c i $\frac{21}{50}$ ii $\frac{8}{25}$ iii $\frac{41}{50}$

7 a i $\frac{5}{8}$ ii $\frac{3}{8}$ iii $\frac{3}{8}$ iv $\frac{3}{4}$
v $\frac{1}{8}$ vi $\frac{1}{4}$
b i $\frac{17}{26}$ ii $\frac{9}{26}$ iii $\frac{11}{26}$ iv $\frac{21}{26}$
v $\frac{2}{13}$ vi $\frac{5}{26}$

8 a

	A	Not A	Total
B	2	6	8
Not B	3	1	4
Total	5	7	12



b

	A	Not A	Total
B	3	4	7
Not B	9	4	13
Total	12	8	20



9 a



b 3
c $\frac{1}{10}$

10 a

	Rain water	No rain water	Total
Tap water	12	36	48
No tap water	11	41	52
Total	23	77	100

b 12 c $\frac{9}{25}$ d $\frac{59}{100}$

11 23

12 $\frac{7}{15}$

13



14 a $T - x - y + z$ b $T - x$ c $T - y$
d $x - z$ e $y - z$ f $y - z$ g $T - x + z$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

15

	A	Not A	Total
B	(0)	12	12
Not B	11	−4	7
Total	11	(8)	19

Filling in table so totals add up requires a negative number– impossible!

16 4

17 a i



ii



iii



b i



ii



iii



c overlap $= (A + B) -$ Total

Exercise 9C

1 a C **b** D **c** E **d** A **e** F **f** B

2 a B **b** D **c** A **d** C

3 a 2 **b** 10 **c** 7 **d** 9

4 a i {1, 2, 3, 4, 5, 6, 7, 8, 9, 10}
ii {1, 3, 5, 7, 9} **iii** {2, 3, 5, 7}

b



c i {3, 5, 7} **ii** {1, 2, 3, 5, 7, 9}
iii {2, 4, 6, 8, 10} **iv** {2}

d i 5 **ii** $\frac{1}{2}$ **iii** 3 **iv** $\frac{3}{10}$

5 a



b i {3, 15} **ii** {1, 3, 5, 6, 9, 12, 15, 18}
iii {1, 2, 4, 5, 7, 8, 10, 11, 13, 14, 16, 17, 19, 20}
iv {1, 5}

c i 4 **ii** $\frac{1}{5}$ **iii** 2 **iv** $\frac{1}{10}$
v 8 **vi** $\frac{2}{5}$

6 a i True **ii** True **iii** False **iv** False
v True **vi** False **vii** True **viii** False
b i $\frac{1}{2}$ **ii** $\frac{1}{2}$ **iii** 0

7 a i $\frac{1}{6}$ **ii** $\frac{11}{12}$ **iii** $\frac{5}{12}$
b i $\frac{6}{25}$ **ii** $\frac{21}{25}$ **iii** $\frac{8}{25}$
c i $\frac{1}{3}$ **ii** $\frac{11}{15}$ **iii** $\frac{2}{5}$
d i $\frac{5}{21}$ **ii** $\frac{17}{21}$ **iii** $\frac{4}{7}$

8 a i {Fred, Ron, Rachel} **ii** {Fred, Rachel, Helen}
iii { } **iv** {Fred, Rachel}
b i $\frac{3}{4}$ **ii** $\frac{1}{4}$ **iii** 0 **iv** 1
v $\frac{1}{2}$ **vi** 1

9 a 26 **b** 5 **c** 3 **d** 18
e $\frac{5}{26}$ **f** $\frac{21}{26}$ **g** $\frac{3}{26}$ **h** $\frac{5}{13}$

10 a 11 **b** 21 **c** 1 **d** $\frac{9}{25}$

11 a own both a dog and a cat
b own dogs or cats or both
c does not own a cat
d owns a cat but no dogs

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

12 a yes



b No as A ∪ B includes only elements from sets A and B

13 B only $= B \cap A'$

14

	A	A′	Total
B	$n(A \cap B)$	$n(B \cap A')$	$n(B)$
B′	$n(A \cap B')$	$n(A' \cap B')$	$n(B')$
Total	$n(A)$	$n(A')$	n(sample space)

15 Mutually exclusive events have no common elements, i.e. $A \cap B = \varnothing$



16 a i $\{2, 3, 5, 7, 11, 13, 17, 19\}$
ii $\{1, 2, 3, 4, 6, 12\}$ iii $\{2, 3\}$
iv $\{1, 2, 3, 4, 5, 6, 7, 11, 12, 13, 17, 19\}$
v $\{1, 4, 6, 12\}$ vi $\{5, 7, 11, 13, 17, 19\}$
vii $\{1, 2, 3, 4, 6, 8, 9, 10, 12, 14, 15, 16, 18, 20\}$
viii $\{2, 3, 5, 7, 8, 9, 10, 11, 13, 14, 15, 16, 17, 18, 19, 20\}$
ix $\{1, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20\}$

b i $\frac{3}{5}$ ii $\frac{1}{10}$ iii $\frac{1}{5}$ iv $\frac{2}{5}$
v $\frac{4}{5}$ vi $\frac{9}{10}$ vii $\frac{9}{10}$ viii $\frac{2}{5}$

c they are equal

Exercise 9D

1 a 9 outcomes

	1	2	3
1	(1, 1)	(2, 1)	(3, 1)
2	(1, 2)	(2, 2)	(3, 2)
3	(1, 3)	(2, 3)	(3, 3)

b 12 outcomes

	1	2	3	4	5	6
H	(1, H)	(2, H)	(3, H)	(4, H)	(5, H)	(6, H)
T	(1, T)	(2, T)	(3, T)	(4, T)	(5, T)	(6, T)

c 6 outcomes

	A	B	C
A	X	(B, A)	(C, A)
B	(A, B)	X	(C, B)
C	(A, C)	(B, C)	X

d 6 outcomes

		1st		
		•	○	○
2nd	•	×	(○, •)	(○, •)
	○	(•, ○)	×	(○, ○)
	○	(•, ○)	(○, ○)	×

2 a Table A

b Table B

c i $\frac{1}{9}$ ii $\frac{1}{6}$

d i 5 ii 4

3 a

		A	
		•	○
B	•	(•, •)	(○, •)
	○	(•, ○)	(○, ○)
	○	(•, ○)	(○, ○)

b 6

c i $\frac{1}{3}$ ii $\frac{1}{2}$ iii $\frac{1}{2}$

4 a

	1	2	3	4
1	(1, 1)	(2, 1)	(3, 1)	(4, 1)
2	(1, 2)	(2, 2)	(3, 2)	(4, 2)
3	(1, 3)	(2, 3)	(3, 3)	(4, 3)
4	(1, 4)	(2, 4)	(3, 4)	(4, 4)

Sample space $= \{(1, 1), (2, 1), \ldots (4, 4)\}$ i.e. all pairs from table.

b $\frac{1}{16}$

c $\frac{1}{4}$

5 a

	1	2	3	4	5	6
1	(1, 1)	(2, 1)	(3, 1)	(4, 1)	(5, 1)	(6, 1)
2	(1, 2)	(2, 2)	(3, 2)	(4, 2)	(5, 2)	(6, 2)
3	(1, 3)	(2, 3)	(3, 3)	(4, 3)	(5, 3)	(6, 3)
4	(1, 4)	(2, 4)	(3, 4)	(4, 4)	(5, 4)	(6, 4)
5	(1, 5)	(2, 5)	(3, 5)	(4, 5)	(5, 5)	(6, 5)
6	(1, 6)	(2, 6)	(3, 6)	(4, 6)	(5, 6)	(6, 6)

b 36

c i $\frac{1}{36}$ ii $\frac{1}{6}$ iii $\frac{1}{12}$ iv $\frac{5}{9}$

6 a

	D	O	G
D	X	(O, D)	(G, D)
O	(D, O)	X	(G, O)
G	(D, G)	(O, G)	X

b $\frac{1}{6}$

c $\frac{2}{3}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 a

		1st			
		1	**2**	**3**	**4**
2nd	**1**	X	(2, 1)	(3, 1)	(4, 1)
	2	(1, 2)	X	(3, 2)	(4, 2)
	3	(1, 3)	(2, 3)	X	(4, 3)
	4	(1, 4)	(2, 4)	(3, 4)	X

b i $\frac{1}{12}$ ii $\frac{1}{12}$

c i $\frac{1}{6}$ ii $\frac{5}{6}$ iii $\frac{1}{6}$ iv $\frac{1}{2}$

8 a

	1	**2**	**3**	**4**
1	2	3	4	5
2	3	4	5	6
3	4	5	6	7
4	5	6	7	8

b i $\frac{1}{16}$ ii $\frac{3}{16}$ iii $\frac{3}{8}$ iv $\frac{3}{16}$

v $\frac{13}{16}$

9 a

	A	**B**	**C**	**D**	**E**
A	(A, A)	(B, A)	(C, A)	(D, A)	(E, A)
B	(A, B)	(B, B)	(C, B)	(D, B)	(E, B)
C	(A, C)	(B, C)	(C, C)	(D, C)	(E, C)
D	(A, D)	(B, D)	(C, D)	(D, D)	(E, D)
E	(A, E)	(B, E)	(C, E)	(D, E)	(E, E)

b i $\frac{1}{25}$ ii $\frac{1}{5}$ iii $\frac{4}{5}$

c i $\frac{8}{25}$ ii $\frac{1}{25}$

10 a i $\frac{1}{36}$ ii $\frac{1}{12}$ iii $\frac{1}{12}$ iv $\frac{7}{12}$

v $\frac{5}{12}$ vi $\frac{1}{6}$ vii $\frac{1}{6}$ viii 0

b 7, $\frac{1}{6}$

11 a i 169 ii 156

b i 25 ii 12

12 yes as if one O is removed another remains to be used.

13 a $\frac{1}{25}$ **b** $\frac{1}{20}$

14 7, 8, 9, 10, 11

15 a $\frac{1}{2500}$ **b** $\frac{1}{50}$ **c** $\frac{1}{1250}$ **d** $\frac{49}{2500}$

e $\frac{23}{1250}$

16 a without replacement

b 2652

c $\frac{1}{1326}$

d i $\frac{1}{221}$ ii $\frac{1}{17}$

Exercise 9E

1 a HHH, HHT, HTH, HTT, THH, THT, TTH, TTT (8 outcomes)

b TT, TO, OT, OO (4 outcomes)

2 a 6 outcomes **b** 6 outcomes

3 a HH, HT, TH, TT



b 4

c i $\frac{1}{4}$ ii $\frac{1}{2}$ iii $\frac{3}{4}$ iv $\frac{3}{4}$

4 a



b 9

c i $\frac{1}{9}$ ii $\frac{5}{9}$ iii $\frac{8}{9}$ iv $\frac{4}{9}$

5 a



b i $\frac{1}{3}$ ii $\frac{2}{3}$ iii 1

6 a



b i $\frac{1}{3}$ ii $\frac{1}{6}$ iii $\frac{1}{6}$ iv $\frac{5}{6}$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 a $\frac{4}{9}$ b $\frac{2}{9}$ c $\frac{1}{27}$ d $\frac{8}{27}$

8 a $\frac{1}{16}$ b $\frac{1}{16}$ c $\frac{5}{16}$ d $\frac{11}{16}$

e $\frac{15}{16}$

9 a



b 12

c i $\frac{1}{12}$ ii $\frac{1}{3}$ iii $\frac{1}{2}$ iv $\frac{1}{4}$

v $\frac{2}{3}$

10 a $\frac{1}{16}$ b $\frac{1}{4}$ c $\frac{3}{8}$ d $\frac{1}{4}$

e $\frac{1}{16}$

11 a 32 b 2^n

12 yes, there is a difference; probability of obtaining two of the same colour is lower without replacement

13 a $\frac{1}{9}$ b $\frac{1}{9}$ c $\frac{7}{18}$ d $\frac{7}{18}$

e $\frac{1}{2}$ f 0 g $\frac{1}{6}$ h $\frac{2}{3}$

i $\frac{1}{9}$ j $\frac{17}{18}$

Exercise 9F

1 a A: $\frac{5}{20} = 0.25$ B: $\frac{30}{100} = 0.3$

b C as it is a larger sample size

2 a 5 b 10 c 50 d 4

3 0.41, from the 100 throws as the more times an experiment is carried out the closer the experimental probability becomes to the actual/theoretical probability

4 a 0.6

b i 60 ii 120 iii 360

5 a $\frac{7}{8}$

b i 350 ii 4375 iii 35

6 a $\frac{1}{15}$ b $\frac{2}{5}$ c $\frac{11}{60}$

7 a 20 b 40 c 60 d 40

8 a 20

b i $\frac{1}{4}$ ii $\frac{7}{20}$

c i 25 ii 20 iii 45

9 a 0.64 b SEE

10 a i 0.52 ii 0.48 iii 0.78

b 78

c $\frac{1}{2}, \frac{1}{4}, \frac{1}{4}$



11 a $\frac{9}{10}$

b No, as the number of throws increases, the experiment should produce results closer to the theoretical probability $\left(\frac{1}{6}\right)$.

12 a fair, close to 0.5 chance of tails

b biased, nearly all results are heads

c can't determine on such a small sample

13 a $\frac{\text{Shaded Area}}{\text{Total Area}} = 0.225 \ \therefore$ 100 shots ≈ 23

b $\frac{1}{10} \times 100 = 10$

c $\frac{150 - 32}{150} \times 100 \approx 79$

d $\frac{225\pi - 25\pi}{225\pi} \times 100 \approx 89$

14 a no b true c no d true

15 3 blue, 2 red, 4 green, 1 yellow

16 2 strawberry, 3 caramel, 2 coconut, 4 nut, 1 mint

Exercise 9G

1 a common b middle c mean

2

	mean	median	mode
a	3	2	2
b	8	9	10
c	7	7	7
d	7	7	3
e	15	16	20
f	7	7	2

3

	mean	median	mode
a	6	7	8
b	8	6	5, 10
c	6	6	2
d	11	12	none
e	4	3.5	2.1
f	5	4.5	none
g	3	3.5	−3
h	0	2	3

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 a outlier = 33 mean = 12 median = 7.5
b outlier = −1.1 mean = 1.075 median = 1.4
c outlier = −4 mean = −49 median = −59
5 a yes b no c no d yes
6 a 24.67 s b 24.8 s
7 a 15 b 26
8 a 90 b 60
9 9
10 answers may vary
a 1, 4, 6, 7, 7 is a set b 2, 3, 4, 8, 8 is a set
c 4, 4, 4, 4, 4 is a set d 2.5, 2.5, 3, 7, 7.5 is a set
e −3, −2, 0, 5, 5 is a set f $0, \frac{1}{2}, 1\frac{1}{4}, 1\frac{1}{4}$, 2 is a set
11 a $1 700 000
b ($354 500 and $324 000) drops $30 500
c ($570 667 and $344 800) drops $225 867
12 An outlier has a large impact on the addition of all the scores and therefore significantly affects the mean. An outlier does not move the middle of the group of scores significantly.
13 a 15 b 1.2 c 1 d 1
e No, as it will still lie in the 1 column.
14 a 2 b 3 c 7
15 a 76.75
b i 71.4, B^+ ii 75, B^+ iii 80.2, A
c 81.4, he cannot get an A^+
d i 43 ii 93
e $M = \frac{307 + m}{5}$
f $m = 5M - 307$

Progress quiz

1 a {1, 2, 3, 4, 5, 6} b {BG, GB, BB, GG}
2 $\frac{4}{11}$
3 a



b 13
c $\frac{27}{40}$
4 $\frac{3}{10} = 0.3$
5 a i {10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20}
ii {10, 12, 14, 16, 18, 20}
iii {12, 15, 18}
iv {10, 12, 14, 15, 16, 18, 20}
b i 2 ii $\frac{7}{11}$ iii $\frac{5}{11}$
6 a $\frac{1}{2}$ b $\frac{1}{6}$ c $\frac{1}{18}$
7 a



b i $\frac{2}{3}$ ii 1 iii $\frac{1}{3}$ iv $\frac{1}{3}$
8 a 0.4
b 0.56
9 140
10 a 7
b 8
c 9
11 100%
12 a $4.15 million
b $1 789 500
c $1 124 500
d Mean = $1 002 667 Median = $849 000

Exercise 9H

1 a 9
b i 8 min ii 35 min
c 21 min
d 21 min
2 a 26
b i 0 mm ii 6 mm
c i 21 mm ii 24 mm
d i 9 mm ii 15 mm
e skewed
f symmetrical
3 a i

stem	leaf
1	9 9
2	3 4 6 6 8 8 8
3	2 2 3 5
4	1
5	4

ii 28 iii 28 iv skewed
b i

stem	leaf
1	5 5
2	1 3 3 3 6
3	0 1 1 3 4 5 5 7 9
4	2 2 5 5 5 8
5	0 0 1

ii 35 iii 23, 45 iv almost symmetrical

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c i

stem	leaf
32	0
33	3 7 8
34	3 4 5 5 7 8 9
35	2 2 4 5 8
36	1 3 5
37	0

ii 34.85 **iii** 35.2, 34.5

iv almost symmetrical

d i

stem	leaf
15	7 8 9 9 9 9
16	1 4 7 7 7
17	3 5 7 7
18	5 5 7 9
19	3 8
20	0 2

ii 173 **iii** 159 **iv** skewed

4 a

stem	leaf
0	5 6 6 8 8 9
1	0 1 1 2 2 2 4 4 5 6 7
2	0 1 2

b 9 **c** 12

5 a i

Set A		Set B
3 2	3	1
9	3	
3 3 0 0	4	0 1 3 4 4
8 7 6 5	4	6 7 8 8 9 9
4 4 3	5	1 3

ii Set A has values spread between 32 and 54 while Set B has most of its values between 40 and 53 with an outlier at 31.

b i

Set A		Set B
9 8 6 4 3 2 2 1	0	9
7 7 6 1 1 0 0	1	8 9 9
9 6 4 3 3 2	2	0 1 3 4 7 8
7 6 6 5 0	3	1 7 7 8 9 9 9
8 3 1	4	0 1 1 3 4 4 5 7
0	5	0 0 1 3 3 4 4 5 6

ii Set A has values between 1 and 50 with the frequency decreasing as the numbers increase whereas Set B has values between 9 and 56 with the frequency increasing as the numbers increase.

c i

Set A		Set B
8 7 4 3	0	1 1 1 2 3 6 6 9 9
9 9 7 6 4	1	2 3 5 8 9
6 5 3 1	2	1 5 6
9 9 6 4 3 2	3	3 4 9
7 3 1	4	3 7 8
7 3 2	5	2 3 7
2 1	6	1 2
8 3	8	3 8
1	9	

ii Set A and B are similar. The frequency decreases as the numbers increase.

6 a

Collingwood		St Kilda
8 3	6	6 8 8
8 7 2 1 0	7	8
9 9 8 2 0	8	0 0 2 2 3 4 7 8
8 7 5 1	9	0 4
4 3 3 3	10	6 9
9 8 5	11	1 3 7 8
7	12	2 5 6
	13	8

b Collingwood $33\frac{1}{3}$% St Kilda $41\frac{2}{3}$%

c Collingwood is almost symmetrical data and based on these results seem to be consistent. St Kilda has groups of similar scores and while less consistent, they have higher scores.

7 a 9 days **b** 18°C **c** 7°C

8 a 16.1 s **b** 2.3 s **c** yes 0.05 s lower

9 a Battery lifetime

Brand A		Brand B
3	7	2 3 4
	7	5 6 8 9 9
4 2	8	0 1 3
9 8 7 5	8	
4 4 3 2 1 0	9	0 1 2 3 4
9 9 8 7 6 5 5	9	5 6 8 8

8 | 3 represents 8.3 hours

b Brand A, 12; Brand B, 8

c Brand A consistently performs better than Brand B.

10 a $c = 2$

b 0.02

c i 5, 6, 7 or 8 **ii** 0,1, 2, 3, 4, 5 or 6

11 a 48%

b 15%

c In general, birth weights of babies are lower for mothers who smoke.

12 In symmetrical data the mean is close to the median as the data is spread evenly from the centre with an even number of data values with a similar difference from the mean above and below it.

13 a 52 **b** 17.8

14 a mean = 41.06 median = 43

b median as more of the scores exist in the higher stems but a few low scores lower the mean.

c the mean is higher for positively skewed data as the majority of the scores are in the lower stems however a few high scores increase the mean.

d symmetrical data

Exercise 9I

1 a 3 **b** 360 000 – 370 000

2 a $a = 15$ $b = 2$ $c = 30$ $d = 40$ $e = 20$ $f = 100$

b $a = 50$ $b = 28$ $c = 12$ $d = 40$ $e = 100$

3 a 2

b 20

c i 30% **ii** 65%

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 a

Class	Frequency	Percentage frequency
0–9	23	46%
10–19	10	20%
20–29	6	12%
30–39	7	14%
40–49	4	8%
	50	100%

b 

c i 33 ii 11

d 34%

5 a

Class	Frequency	Percentage frequency
50–59	8	13.33%
60–69	14	23.33%
70–79	9	15%
80–89	25	41.67%
90–99	4	6.67%
	60	100%

b 

c i 22 ii 48.3%

6 a

Number of goals	Frequency
0–2	1
3–5	8
6–8	7
9–11	7
12–14	7
	30

b 

c 9

d 7

7 a symmetrical data b skewed data

8 a $a = 6$ $b = 27.5$ $c = 17.5$ $d = 4$ $e = 12$ $f = 30$ $g = 100$

b $a = 1$ $b = 18$ $c = 8$ $d = 24$ $e = 20$ $f = 40$ $g = 100$

9 a i 20% ii 55% iii 80% iv 75% v 50%

b i 30 ii 45

c i 2 ii 22

10 85.5%

11 Because you only have the number of scores in the class interval not the individual scores

12 The number of data items within each class

13 a Student A

b Make the intervals for their groups of data smaller so that the graph conveys more information.

14 a minimum wage: \$204; maximum wage: \$940

b i

Weekly wages (\$)	Frequency
200–	2
300–	7
400–	6
500–	6
600–	11
700–	11
800–	5
900–	2

ii

c i

Weekly wages	Frequency
200–	9
400–	12
600–	22
800–	7

ii

d More intervals shows greater detail. Since first graph has each pair of intervals quite similar, these two graphs are quite similar.

Exercise 9J

1 a 6

b 7

c i 5 ii 8

d 3

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 a 12
b 5
c i 3 ii 8
d 5

3

	Range	Q_2	Q_1	Q_3	IQR
a	11	6	2.5	8.5	6
b	23	30	23.5	36.5	13
c	170	219	181.5	284.5	103
d	851	76	28	367	339
e	1.3	1.3	1.05	1.85	0.8
f	34.98	10	0.1	23	22.9

4 a 110 min
b i 119.5 min ii 106 min iii 130 min
iv 24 min
c The middle 50% of videos rented varied in length by 24 min
5 a i \$12 000 ii \$547 000 iii \$71 500 iv \$46 000
v \$78 000 vi \$32 000
b The middle 50% of prices differs by no more than \$32 000
c No effect on Q_1, Q_2 or Q_3 but the mean would increase.
6 a 17.5
b 2.1
7 a 2
b 2
c No, only the maximum value has changed so no impact on IQR.
8 No, as the range is the difference in the highest and lowest score and different sets of two numbers can have the same difference ($10 - 8 = 2, 22 - 20 = 2$)
9 a Yes – the lowering of the highest price reduces the range
b No – the middle price will not change
c No; as only one value, the highest has changed, yet it still remains the highest, Q_1 and Q_3 remain unchanged.
10 a Yes (3, 3, 3, 4, 4, 4; IQR $= 4 - 3 = 1$; Range $= 1$)
b Yes (4, 4, 4, 4, 4, 4 has IQR $= 0$)
11 a i $Q_1 = 25; Q_2 = 26; Q_3 = 27$
ii $Q_1 = 22; Q_2 = 24.5; Q_3 = 27$
b 27 jelly beans
c 22 jelly beans
d i IQR $= 2$ ii IQR $= 5$
e Shop B is less consistent than shop A and its data is more spread out
f Shop A

Exercise 9K

1 a minimum value b lower quartile, Q_1
c median, Q_2 d upper quartile, Q_3
e maximum value f scale g whisker
h box
2 a the minimum from the maximum
b the lower quartile Q_1 from the upper quartile Q_3
3 D
4 a min $= 35$ cm max $= 60$ cm b 25 cm
c 50 cm d 10 cm e 50 cm f 55 cm
g 20 babies
5 a min $= 0$ rabbits, max $= 60$ rabbits b 60
c 25 d 25 e 35 f 25
g 25
6 a i 2 ii 13 iii 8 iv 4
v 11
vi 

b i 10 ii 88 iii 43 iv 34
v 56
vi 

c i 244 ii 933 iii 435 iv 255
v 674
vi 

d i 0.1 ii 1.3 iii 0.6 iv 0.4
v 0.95
vi 

7 a

b i 100% ii 50% iii 75% iv 25%
8 a Africa
b 10 kg
c yes, 25 kg
d i 50% ii 75%
e African
9 a Mac
b 75%
c 50%
d They are the same. Mac has 100% of times within same range as middle 50% of PC start up times. Mac is more consistent.
10 a Waldren b Yeng c Yeng
d Yeng, smaller range and IQR
e Yeng, higher median
11 a 1, 3, 5, 6, 6 b 1, 4, 4, 4, 5, 6
12 No, the median is anywhere within the box, including at times at its edges.
13 Yes, one reason is if an outlier is the highest score, then the mean > Q_3 [e.g. 1, 1, 3, 5, 6, 7, 256]

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 a $Q_1 = 4$

$Q_2 = 6$

$Q_3 = 8$

b yes, 17

c 9

d 

e This calculator was used less often than the others, so the battery lasted longer.

Problems and challenges

1 a $2^5 = 32$ b $\frac{3}{16}$ c $\frac{31}{32}$

2 a $\frac{1}{6}$ b $\frac{1}{3}$

3 a i $\frac{1}{4}$ ii $\frac{1}{2}$

b $\frac{1}{6}$

c $\frac{1}{12}$

d $\frac{1}{3}$

4 a mean and median increase by 5, range unchanged

b mean, median and range all double

c mean and median double and decrease by 1, range doubles

5 $5m$ grams

6 a 3, 5, 7, 8, 10 or 3, 5, 7, 9, 10 b 2, 2, 8, 12

7 1, 4, 6, 7, 7; 2, 3, 6, 7, 7 and 1, 2, 5, 6, 6

8 $\frac{3}{8}$

Multiple-choice questions

1 B 2 A 3 D 4 B 5 D

6 B 7 E 8 C 9 B 10 E

Short-answer questions

1 a $\frac{2}{3}$ b $\frac{5}{9}$ c $\frac{3}{5}$

2 a 

b 15

c i $\frac{1}{5}$ ii $\frac{2}{5}$ iii $\frac{3}{10}$

3 a

	A	A′	Total
B	9	16	25
B′	8	12	20
Total	17	28	45

b 

c i $\frac{4}{9}$ ii $\frac{1}{5}$ iii 8 iv 33

4 a 12 outcomes

	1	2	3	4
red	(red, 1)	(red, 2)	(red, 3)	(red, 4)
green	(green, 1)	(green, 2)	(green, 3)	(green, 4)
blue	(blue, 1)	(blue, 2)	(blue, 3)	(blue, 4)

b i $\frac{1}{6}$ ii $\frac{1}{6}$ iii $\frac{2}{3}$

5 a 

b $\frac{2}{3}$

6 a $\frac{48}{120} = \frac{2}{5}$ b 14

7 a 26 b 26.5 c 23, 31

8 a

Employee 1				Employee 2				
		9	1	7	7			
	5	3	1	2	0	4	8	9
9 8 6	5	5	4	3	2	7	7	8
	6	5	0	4	0	1	2	5 8
		3	1	5				

2 | 4 means 24

b i Employee 1: 36, Employee 2: 37

ii Employee 1: 36, Employee 2: 33

c Employee 1, they have a higher mean and more sales at the high end.

d Employee 1 symmetrical, employee 2 skewed

9 a

Class interval	Frequency	Percentage frequency
120–	1	4
130–	3	12
140–	4	16
150–	8	32
160–	7	28
170–180	2	8
Total	25	100%

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b



c i 4 ii 60%

10 **a** 52 runs

b



c 37 runs

Extended-response questions

1 **a** i

		1st spin				
		1	**2**	**3**	**4**	**5**
2nd spin	**1**	(1, 1)	(2, 1)	(3, 1)	(4, 1)	(5, 1)
	2	(1, 2)	(2, 2)	(3, 2)	(4, 2)	(5, 2)
	3	(1, 3)	(2, 3)	(3, 3)	(4, 3)	(5, 3)
	4	(1, 4)	(2, 4)	(3, 4)	(4, 4)	(5, 4)
	5	(1, 5)	(2, 5)	(3, 5)	(4, 5)	(5, 5)

ii $\frac{12}{25}$ iii $\frac{4}{25}$ iv 24 v \$68

b i



ii 5

iii 10 iv $\frac{1}{3}$ v $\frac{4}{9}$

vi $\frac{7}{9}$, the probability a person did not buy a sausage on its own

2 **a** Yes, 52 mins

b i 12 ii 4 iii 15.5

c and **e**



d No, the median time is 12 mins so half the flights have less than 12 minute delay.

f Airline A: range = 24, IQR = 11.5
Airline B: range = 25, IQR = 11
Both airlines have a very similar spread of their data when the outlier is removed.

g There is not much difference when airline A's outlier is removed. It has a marginally better performance with 75% of flights delayed less than 15.5 mins compared with 18 mins for airline B.

Chapter 10

Exercise 10A

1 **a** 12 **b** −4 **c** 6 **d** −1
e 20 **f** 4 **g** 72 **h** 0
i −27

2 **a** no **b** no **c** yes **d** yes
e yes **f** no **g** no **h** yes
i yes

3 **a** 1 **b** −3 **c** −11 **d** −2 **e** 3
f −6

4 **a** $x - 5 = 0, x = 5$
b $2x + 1 = 0, 2x = -1$ or $x = 3, x = -\frac{1}{2}$ or $x = 3$

5 **a** $x^2 + 2x - 5 = 0$ **b** $x^2 - 5x + 2 = 0$
c $x^2 - 4x + 1 = 0$ **d** $x^2 - 7x - 2 = 0$
e $2x^2 + 2x + 1 = 0$ **f** $3x^2 - 3x + 4 = 0$
g $3x^2 + 4 = 0$ **h** $x^2 - 3x - 1 = 0$
i $2x^2 + 5x - 10 = 0$

6 **a** yes **b** yes **c** no **d** no
e yes **f** yes **g** no **h** no
i no

7 both are solutions

8 both are solutions

9 **a** 0, −1 **b** 0, −5 **c** 0, 2 **d** 0, 7
e −1, 3 **f** 4, −2 **g** −7, 3 **h** $-\frac{1}{2}, \frac{1}{2}$
i 0, −5 **j** $0, \frac{2}{3}$ **k** $0, -\frac{2}{3}$ **l** 0, −2

10 **a** $\frac{1}{2}, -2$ **b** $-2, \frac{1}{3}$ **c** $-\frac{2}{5}, -4$ **d** $1, \frac{1}{3}$
e $-5, -\frac{2}{7}$ **f** $\frac{2}{3}, -\frac{1}{5}$ **g** $\frac{7}{11}, \frac{13}{2}$ **h** $-\frac{9}{4}, \frac{7}{2}$
i $\frac{4}{3}, -\frac{1}{7}$

11 **a** 0, −3 **b** 0, 7 **c** 1, −4 **d** $\frac{1}{2}, -6$
e $-\frac{3}{2}, \frac{1}{2}$

12 **a** $4x^2 + x + 1 = 0$ **b** $3x^2 - 3x = 0$
c $3x^2 - x - 4 = 0$ **d** $5x^2 + x - 2 = 0$
e $2x^2 - x - 3 = 0$ **f** $3x^2 - 10x + 6 = 0$
g $x^2 - x - 5 = 0$ **h** $4x^2 - 5x - 6 = 0$

13 **a** −1, 2 **b** 1, 3 **c** 0, 4 **d** 0, −3
e −4, 1 **f** −4, 4

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 **a** $(x+2)(x+2)=0$
b both solutions are the same, $x=-2$
c **i** -3 **ii** 5 **iii** $\frac{1}{2}$ **iv** $\frac{7}{5}$

15 **a** $(x-1)(x+2)=0$
b $x=1, x=-2$
c multiplying by a constant doesn't change a zero value.
d **i** $-2, 3$ **ii** $0, -2$ **iii** $-1, 3$

16 **a** **i** no **ii** no **iii** no **iv** no
b It has no solutions as $(x-3)^2$ is always ≥ 0, so $(x-3)^2+1 \geq 1$

17 **a** Linear **b** Quadratic **c** Quintic **d** Cubic
e Quartic **f** Quintic

18 **a** $-2, -1, 3$ **b** $-11, 2, 5$ **c** $-\frac{2}{3}, \frac{1}{5}, \frac{1}{2}$
d $-\frac{10}{7}, -\frac{4}{5}, -\frac{2}{3}, \frac{13}{2}$

Exercise 10B

1 **a** 2 **b** 5 **c** 2 **d** 8 **e** x
f x **g** $3x$ **h** $3x$

2 **a** $2(x-2)(x+2)$ **b** $4(x-3)(x+3)$
c $3(x-5)(x+5)$ **d** $12(x-1)(x+1)$
e $x(x-3)$ **f** $x(x+7)$
g $2x(x-2)$ **h** $5x(x-3)$
i $2x(3x+2)$ **j** $9x(x-3)$
k $4x(1-4x)$ **l** $7x(2-3x)$

3 **a** $x=0, x=3$ **b** $x=0, x=-1$
c $x=0, x=-2$

4 **a** $x=0, x=-3$ **b** $x=0, x=-7$
c $x=0, x=-4$ **d** $x=0, x=5$
e $x=0, x=8$ **f** $x=0, x=2$
g $x=0, x=-\frac{1}{3}$ **h** $x=0, x=\frac{1}{2}$

5 **a** $x=0, x=3$ **b** $x=0, x=4$
c $x=0, x=-5$ **d** $x=0, x=3$
e $x=0, x=3$ **f** $x=0, x=-4$

6 **a** $x=0, x=3$ **b** $x=0, x=2$
c $x=0, x=4$ **d** $x=0, x=-3$
e $x=0, x=-4$ **f** $x=0, x=-3$

7 **a** $x=3, x=-3$ **b** $x=6, x=-6$
c $x=5, x=-5$ **d** $x=12, x=-12$
e $x=9, x=-9$ **f** $x=20, x=-20$

8 **a** $x=2, x=-2$ **b** $x=3, x=-3$
c $x=5, x=-5$ **d** $x=2, x=-2$
e $x=\sqrt{6}, x=-\sqrt{6}$ **f** $x=\sqrt{5}, x=-\sqrt{5}$
g $x=\sqrt{7}, x=-\sqrt{7}$ **h** $x=\sqrt{3}, x=-\sqrt{3}$

9 **a** $x=2, x=-2$ **b** $x=5, x=-5$
c $x=10, x=-10$ **d** $x=0, x=-7$
e $x=0, x=7$ **f** $x=-1, x=1$
g $x=0, x=\frac{2}{3}$ **h** $x=0, x=\frac{3}{5}$
i $x=-\sqrt{3}, x=\sqrt{3}$

10 **a** $x=-2, x=2$ **b** $x=-6, x=6$
c $x=-1, x=1$ **d** $x=-1, x=1$
e $x=0, x=-7$ **f** $x=0, x=4$

11 **a** 0 or 7 **b** 8 or -8 **c** 0 or -4

12 **a** $(x+2)(x-2)=x^2-4$ not x^2+4
b No, $x^2 \geq 0$, so $x^2+4 \geq 4$

13 **a** $ax^2+bx=x(ax+b)=0, x=0$ is always one solution
b $x=-\frac{b}{a}$

14 **a** $x=-\frac{4}{3}, x=\frac{4}{3}$ **b** $x=-\frac{6}{5}, x=\frac{6}{5}$
c $x=-\frac{1}{5}, x=\frac{1}{5}$ **d** $x=-\frac{9}{5}, x=\frac{9}{5}$
e $x=-\frac{8}{11}, x=\frac{8}{11}$ **f** $x=-\frac{12}{7}, x=\frac{12}{7}$

15 **a** $x=-1, x=5$ **b** $x=-1, x=-9$
c $x=-1, x=0$ **d** $x=-\frac{2}{5}, x=\frac{8}{5}$
e $x=1, x=7$ **f** $x=-1, x=\frac{13}{7}$

Exercise 10C

1 **a** 3, 2 **b** 4, 2 **c** $-2, -1$ **d** $-5, -2$
e 2, -1 **f** 5, -1 **g** $-4, 3$ **h** $-6, 2$

2 **a** $(x+5)(x+4)=0$
$x+5=0$ or $x+4=0$
$x=-5$ or $x=-4$
b $(x-6)(x+4)=0$
$x-6=0$ or $x+4=0$
$x=6$ or $x=-4$
c $(x+9)(x-5)=0$
$x+9=0$ or $x-5=0$
$x=-9$ or $x=5$
d $(x-8)(x-2)=0$
$x-8=0$ or $x-2=0$
$x=8$ or $x=2$

3 **a** $-6, -2$ **b** $-8, -3$ **c** $-5, -2$ **d** $-7, 2$
e $-6, 2$ **f** $-10, 3$ **g** 4, 8 **h** 3, 6
i 3, 7 **j** $-3, 5$ **k** $-2, 8$ **l** $-5, 9$
m 4, 6 **n** $-6, 7$ **o** $-12, 7$ **p** $-3, -1$
q $-3, 9$ **r** 2, 10

4 **a** -3 **b** -2 **c** -7 **d** -12 **e** 5
f 8 **g** 6 **h** 9 **i** 10

5 **a** $-2, 5$ **b** 2, 5 **c** 3 **d** $-4, 1$
e $-7, 2$ **f** 4 **g** $-6, 2$ **h** $-6, 1$
i 3, 5 **j** $-8, 2$ **k** $-4, -2$ **l** $-9, 2$

6 **a** $-2, 3$ **b** $-5, -3$ **c** $-2, 8$ **d** 2, 3 **e** 2
f -1 **g** 5 **h** -3 **i** $-7, 1$

7 **a** 2, 3 **b** 3 **c** $-10, 2$ **d** $-5, 7$
e -1 **f** 2

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 **a** $x^2 - 3x + 2 = 0$ **b** $x^2 - x - 6 = 0$
c $x^2 + 3x - 4 = 0$ **d** $x^2 - 7x - 30 = 0$
e $x^2 - 10x + 25 = 0$ **f** $x^2 + 22x + 121 = 0$

9 11 am, 6 pm

10 **a** Equation is not written in standard form $x^2 + bx + c = 0$ so cannot apply Null Factor Law in this form.
b $x = -2, x = 3$

11 It is a perfect square, $(x-1)(x-1), (x-1)^2 = 0, x = 1$

12 **a** $(x-a)(x-a) = 0$ or $(x-a)^2 = 0$
b $(x-a)(x-b) = 0$

13 **a** $x = -3$ or $x = -\frac{1}{5}$ **b** $x = \frac{2}{3}$ or $x = -2$
c $x = \frac{1}{3}$ or $x = -\frac{1}{2}$ **d** $x = \frac{1}{2}$ or $x = -1$
e $x = \frac{3}{2}$ or $x = -5$ **f** $x = \frac{3}{2}$
g $x = \frac{7}{3}$ or $x = -2$ **h** $x = \frac{3}{5}$ or $x = -4$
i $x = -\frac{5}{3}$

Exercise 10D

1 **a** $x(x+2) = 8$ **b** 2, −4 **c** 2, width > 0
d $L = 4$ cm, $W = 2$ cm

2 **a** $x(x+5) = 14$ **b** 2, −7 **c** 2, width > 0
d $L = 7$ m, $W = 2$ cm

3 **a** −6, 3 **b** 5, −4 **c** 2, −5

4 −8, 6

5 −5, 12

6 −2, 15

7 $L = 9$ cm, $W = 4$ cm

8 $L = 3$ m, $W = 23$ m

9 **a** $A = 100 - x^2$ **b** $x = 6$

10 $h = 5$

11 **a** $A = x^2 + 5x + 15$ **b** $x = 7$

12 **a** $x = 3$ (−4 not valid) **b** $x = 12$ **c** $x = 25$

13 −8 not valid because dimensions must be > 0

14 $x = -2$ or $x = 3$ both valid as both are integers

15 **a** 10, 15, 21
b **i** 28 **ii** 210
c **i** 9 **ii** 15

16 **a** 9, 14
b **i** 8 **ii** 12

17 **a** $A = (20 + 2x)^2 = 4x^2 + 80x + 400$
b 10 cm

18 4 cm

Progress quiz

1 **a** $x^2 - 3x - 8 = 0$ **b** $3x^2 - 4x - 6 = 0$
c $2x^2 - 2x - 3 = 0$ **d** $2x^2 - 3x - 12 = 0$

2 **a** $x = 2$ is not a solution **b** $x = -2$ is a solution
c $x = 3$ is a solution **d** $x = -3$ is a solution

3 **a** $x = 0$ or $x = 7$ **b** $x = 5$ or $x = -2$
c $x = 0$ or $x = -\frac{2}{5}$ **d** $x = \frac{1}{3}$ or $x = \frac{3}{4}$

4 **a** $x = 0$ or $x = -11$ **b** $x = 0$ or $x = 6$
c $x = 0$ or $x = -5$ **d** $x = 0$ or $x = 4$

5 **a** $x = 7$ or $x = -7$ **b** $x = 1$ or $x = -1$
c $x = 2$ or $x = -2$ **d** $x = 3$ or $x = -3$

6 **a** $x = -3$ or $x = -8$ **b** $x = 3$ or $x = 12$
c $x = -5$ or $x = 7$ **d** $x = -9$ or $x = 4$

7 **a** $x = -4$ **b** $x = 7$ **c** $x = 10$
d $x = -3$ or $x = 8$

8 length 9 m; width 6 m

9 The number is −12 or 7

10 **a** $x^2 - 5x + 6 = 0$ **b** $x^2 - 5x - 6 = 0$
c $x^2 - 16 = 0$ **d** $x^2 + 6x + 9 = 0$

Exercise 10E

1 **a** highest **b** parabola **c** intercepts **d** vertex
e lowest **f** zero

2 **a** $x = 3$ **b** $x = 1$ **c** $x = -2$ **d** $x = -5$

3

	i Axis of symmetry	ii Type of turning point	iii Turning point	iv x-intercepts	v y-intercept
a	$x = 2$	minimum	(2, −1)	1, 3	3
b	$x = 0$	minimum	(0, −4)	−2, 2	−4
c	$x = 0$	maximum	(0, 3)	−1, 1	3
d	$x = 0$	maximum	(0, 4)	−2, 2	4
e	$x = 2$	minimum	(2, 1)	none	4
f	$x = -1$	maximum	(−1, 7)	−4, 2	6
g	$x = 0$	minimum	(0, 0)	0	0
h	$x = 0$	minimum	(0, −4)	−2, 2	−4
i	$x = 3$	maximum	(3, 4)	1, 5	−5
j	$x = 3$	minimum	$\left(3, -\frac{1}{2}\right)$	2, 4	4
k	$x = 0$	maximum	(0, 2)	−1, 1	2
l	$x = -2$	maximum	(−2, −1)	none	−4

4 **a**

x	−2	−1	0	1	2
y	3	0	−1	0	3

$y = x^2 - 1$

b, c



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 **a**

x	-3	-2	-1	0	1	2	3
y	0	5	8	9	8	5	0

$y = 9 - x^2$

b, c



6 **a**

x	-4	-3	-2	-1	0	1	2
y	5	0	-3	-4	-3	0	5

$y = x^2 + 2x - 3$

b, c



7 **a**

x	-2	-1	0	1	2	3
y	-4	0	2	2	0	-4

$y = -x^2 + x + 2$

b,c



8 **a** **i** 1 s, 3 s

ii one time is on the way up and the other is on the way down

b **i** 2 s **ii** 12 m **iii** 4 s

9 **a** 100 m **b** 155 m **c** 5 s

d journey takes 1 s longer to go down to the ground

10 **a** $x = 1$

b $(1, -3)$

11 **a** $x = 1$ **b** 2

12 **a** $y = x^2$ **b** $y = x^2 - 4$ **c** $y = 1 - x^2$

d $y = x^2 - 2x + 1$ **e** $y = -x^2 - 2x$

f $y = x^2 - 3x - 4$

13 **a** Yes



Two x-intercepts

b Yes



One x-intercept

c Yes



Zero x-intercepts

d No

14 **a** $-2^2 = -1 \times 2^2 = -4$. It is not $(-2)^2 = 4$, so correct solution is $y = -2^2 + 2 \times 2 = -4 + 4 = 0$

b $-(-3)^2 = -1 \times 9 = -9$. It is not $-3^2 = +9$, so correct solution is $y = -3 - (-3)^2 = -3 - 9 = -12$

15 **a** $x = -2, x = 2$

b $x = 0$

c **i** infinite **ii** one **iii** none

16 **a** **i** $x = 0, x = 2$ **ii** $x = -1, x = 3$

b two, a parabola is symmetrical

c one, this is the minimum turning point

d none, -1 is the minimum y-value so there are no values of y less than -1

17 Answers will vary

Exercise 10F

1 **a** $y = 3x^2, y = x^2, y = \frac{1}{2}x^2$

b $y = -3x^2, y = -x^2, y = -\frac{1}{2}x^2$

c (0, 0)

d $x = 0$

e **i** $y = 3x^2$ **ii** $y = \frac{1}{2}x^2$ **iii** $y = -3x^2$

iv $y = -\frac{1}{2}x^2$

f **i** $y = -x^2$ **ii** $y = -3x^2$ **iii** $y = \frac{1}{2}x^2$

2 **a** positive **b** negative

3 **a** $y = -x^2$ **b** $y = -4x^2$ **c** $y = 5x^2$

d $y = \frac{1}{3}x^2$

4 **a**

x	-2	-1	0	1	2
y	4	1	0	1	4

x	-2	-1	0	1	2
y	12	3	0	3	12

x	-2	-1	0	1	2
y	$\frac{4}{3}$	$\frac{1}{3}$	0	$\frac{1}{3}$	$\frac{4}{3}$

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b



c For all 3 graphs, the turning point is a minimum at (0, 0) and the axis of symmetry is $x = 0$

d i narrower **ii** wider

5 a i

x	−2	−1	0	1	2
y	16	4	0	4	16

ii



iii axis of symmetry: $x = 0$; turning point: (0, 0)

iv narrower

b i

x	−2	−1	0	1	2
y	20	5	0	5	20

ii See part a

iii axis of symmetry: $x = 0$; turning point: (0, 0); x- and y-intercept: (0, 0) **iv** narrower

c i

x	−2	−1	0	1	2
y	1	$\frac{1}{4}$	0	$\frac{1}{4}$	1

ii See part a

iii axis of symmetry: $x = 0$; turning point: (0, 0)

iv wider

d i

x	−2	−1	0	1	2
y	$\frac{4}{5}$	$\frac{1}{5}$	0	$\frac{1}{5}$	$\frac{4}{5}$

ii See part a

iii axis of symmetry: $x = 0$; turning point: (0, 0)

iv wider

6 a i

x	−2	−1	0	1	2
y	−8	−2	0	−2	−8

ii



iii axis of symmetry: $x = 0$; turning point: (0, 0); x- and y-intercept: 0 **iv** narrower

b i

x	−2	−1	0	1	2
y	−12	−3	0	−3	−12

ii See part a

iii axis of symmetry: $x = 0$; turning point: (0, 0); x- and y-intercept: 0 **iv** narrower

c i

x	−2	−1	0	1	2
y	−2	$-\frac{1}{2}$	0	$-\frac{1}{2}$	−2

ii See part a

iii axis of symmetry: $x = 0$; turning point: (0, 0); x- and y-intercept: 0 **iv** wider

d i

x	−2	−1	0	1	2
y	$-\frac{4}{3}$	$-\frac{1}{3}$	0	$-\frac{1}{3}$	$-\frac{4}{3}$

ii See part a

iii axis of symmetry: $x = 0$; turning point: (0, 0); x- and y-intercept: 0 **iv** wider

7 a A **b** H

8 **i** d **ii** c **iii** a **iv** e **v** f **vi** b

Essential Mathematics for the Australian Curriculum Year 9 2ed ISBN 978-1-107-57007-8 © Greenwood et al. 2016 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 **a** reflection in the x-axis, dilating by a factor of 3 from the x-axis
b reflection in the x-axis, dilating by a factor of 6 from the x-axis
c reflection in the x-axis, dilating by a factor of $\frac{1}{2}$ from the x-axis
d reflection in the x-axis, dilating by a factor of 2 from the x-axis
e reflection in the x-axis, dilating by a factor of 3 from the x-axis
f reflection in the x-axis, dilating by a factor of $\frac{1}{3}$ from the x-axis

10 **a** $y = -4x^2$ **b** $y = \frac{1}{3}x^2$ **c** $y = -4x^2$
d $y = -\frac{4}{3}x^2$

11 No because both transformations are multiplying to 'a' and multiplication is commutative: $bc = cb$

12 $y = ax^2$, has y-axis as axis of symmetry so it is symmetrical about the y-axis

13 **a** $y = 5x^2$ **b** $y = 7x^2$ **c** $y = x^2$ **d** $y = \frac{7}{4}x^2$
e $y = \frac{4}{25}x^2$ **f** $y = \frac{26}{9}x^2$
g $y = 5x^2$ **h** $y = -52x^2$

14 $y = \frac{67}{242064}x^2$

Exercise 10G

1 **a** **i** $(-2, 0)$ **ii** (3, 0)
b **i** 4 **ii** -9
c left
d right

2 **a** **i** $(0, -3)$ **ii** (0, 2)
b **i** -3 **ii** 2
c down
d up

3 **a** **i** (2, 3) **ii** $(-1, -1)$
b **i** -1 **ii** 0
c **i** one, left, one, down **ii** two, right, three, up.

4 **a** 3 **b** -4 **c** -4 **d** 25

5 **a** $y = x^2 + 1$ **b** $y = x^2 + 3$
c $y = x^2 - 2$



d $y = -x^2 + 4$ **e** $y = -x^2 + 1$
f $y = -x^2 - 5$



6 **a** $y = (x - 2)^2$ **b** $y = (x - 4)^2$
c $y = (x + 3)^2$



d $y = -(x - 3)^2$ **e** $y = -(x + 2)^2$
f $y = -(x + 6)^2$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



7 a $y = (x - 3)^2 + 2$



b $y = (x - 1)^2 - 1$



c $y = (x + 2)^2 - 3$



d $y = (x + 1)^2 + 7$



e $y = -(x - 2)^2 + 1$



f $y = -(x - 5)^2 + 3$



g $y = -(x + 3)^2 - 4$



h $y = -(x + 1)^2 - 5$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

i $y = -(x-3)^2 - 6$



8 i j ii d iii b iv h
v k vi g vii a viii e
ix l x i xi f xii c

9 a $y = (x-1)^2 + 1$ b $y = (x+2)^2 + 2$
c $y = (x+1)^2 - 3$ d $y = -(x-1)^2 + 4$
e $y = -(x-2)^2 - 2$ f $y = -(x+2)^2 + 4$

10 a $y = -(x-2)^2 + 9$, turning point $(2, 9)$
$y = (x-7)^2 - 4$, turning point $(7, -4)$

b



11 a i $y = -(x+1)^2 + 3$ ii $y = (x+3)^2 + 4$
iii $y = (x-1)^2 - 3$ iv $y = -(x-5)^2 - 7$
v $y = -x^2 - 2$ vi $y = x^2 - 6$
b i $(-1, 3)$ ii $(-3, 4)$ iii $(1, -3)$ iv $(5, -7)$
v $(0, -2)$ vi $(0, -6)$

12 a (h, k) b $y = ah^2 + k$

13 a $(2-x)^2 = (-1(x-2))^2 = (-1)^2(x-2)^2 = (x-2)^2$, so graphs are the same
b graphs are the same

14 a $y = x^2 + 3$ b $y = x^2 - 4$
c $y = x^2 - 3$ d $y = x^2 - 5$

15 a $y = -x^2 + 4$ b $y = -x^2 + 4$
c $y = -x^2 + 24$ d $y = -x^2 + 10$

16 a $y = (x+3)^2$ or $y = (x-5)^2$
b $y = (x-2)^2$ or $y = (x-4)^2$
c $y = (x+4)^2$ or $y = (x-2)^2$
d $y = x^2$ or $y = (x-6)^2$

17 a $y = -(x-1)^2 + 1$ b $y = (x+2)^2$
c $y = -(x-3)^2$ d $y = -(x+3)^2 + 2$
e $y = (x+1)^2 + 4$ f $y = (x-3)^2 - 9$

Exercise 10H

1 a $x(x+2)$ b $x(x-3)$ c $5x(x-2)$
d $(x+3)(x-3)$ e $(x+1)(x-1)$
f $(x+7)(x-7)$ g $(x+2)(x+1)$
h $(x+3)(x+2)$ i $(x-4)(x+3)$
j $(x-7)(x+4)$ k $(x-2)(x-2) = (x-2)^2$
l $(x+5)(x+5) = (x+5)^2$

2 a 0 b 0 c -3 d 8
e -1 f -1 g -0.5 h 4.5 i 6

3 a -4 b -1 c -9 d -1
e -9 f -9

4 a i 0, -7 ii 0
b i 0, -3 ii 0
c i 0, -4 ii 0
d i 4, -2 ii -8
e i $-2, 5$ ii -10
f i $-3, 7$ ii -21
g i $-3, 1$ ii -6
h i -4, -1 ii 12
i i 2, 3 ii 6

5 a $y = x(x-5)$



b $y = x(x+1)$



c $y = x(x-3)$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d $y = x(2 + x)$



e $y = x(5 + x)$



f $y = x(3 - x)$



g $y = -x(x + 8)$



h $y = -x(2 + x)$



i $y = -x(x - 1)$



6 a $y = (x - 2)(x - 1)$



b $y = (x - 3)(x - 1)$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c $y = (x + 3)(x - 1)$



d $y = (x + 2)^2$



e $y = (x + 1)^2$



f $y = (x + 4)(x - 2)$



7 **a** $y = x^2 - 1$



b $y = 9 - x^2$



c $y = x^2 + 5x$



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d $y = 2x^2 - 6x$



e $y = 4x^2 - 8x$



f $y = x^2 - 3x - 4$



g $y = x^2 + x - 12$



h $y = x^2 + 2x + 1$



i $y = x^2 - 6x + 9$



8 **a** -3 **b** 2 **c** 3 **d** -4
e -5 **f** 6

9 **a** 30 m **b** 225 m

10 **a** 200 m **b** 1000 m

11 There is only one x-intercept so this must be the turning point

12 **a** $y = c$ **b** $y = ab$

13 **a** $(1, -16)$

b $(5, 0)$, $(-3, 0)$, turning point x-coordinate: $\frac{5 + (-3)}{2} = 1$, TP$(1, -16)$

c $y = (x - 2)^2 - 49, h = 2, k = -49$

14 **b** $y = (x + 3)(x - 1)$ **c** $y = 2(x + 5)(x - 1)$

d $y = -(x + 1)(x - 5)$ **e** $y = -(x + 8)(x + 2)$

f $y = \frac{1}{2}(x + 8)(x - 2)$ **g** $y = -\frac{1}{3}(x + 3)(x - 7)$

Problems and challenges

1 **a** they are square numbers;

b $100^2 = 10\,000$

2 **a** $\frac{5}{3}, -\frac{7}{2}$ **b** $2, -1$ **c** $2^{\frac{2}{3}} + 1$

3 6 seconds

4 $\frac{n(n+1)}{2}; n = 11$

5 $x = 2$

6 **a** 20 units, 21 units, 29 units **b** 17 units

7 **a** $k < 0$ **b** $k = 0$ **c** $k > 0$

8 **a** 10, -10, 11, -11, 14, -14, 25, -25

b $a = 2, -2, 5, -5, 10, -10, 23, -23$

9 $x = -3, 1, 2, 6$

10 $x = -3, -1, 1, 3$

Multiple-choice questions

1 D **2** B **3** C **4** A **5** D
6 B **7** E **8** C **9** A **10** B

Short-answer questions

1 **a** $y = x^2 - 2x - 3$

x	-3	-2	-1	0	1	2	3
y	12	5	0	-3	-4	-3	0

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b



2 **a** 0, −2 **b** 0, 4 **c** −3, 7 **d** 2, −2
e $-1, \frac{2}{5}$ **f** $\frac{1}{2}, \frac{4}{3}$

3 **a** 0, −3 **b** 0, 4 **c** −5, 5 **d** −9, 9
e −2, 2 **f** $-\sqrt{10}, \sqrt{10}$ **g** −3, −7
h −5, 8 **i** 4

4 **a** $x^2 - 5x = 0; x = 0, 5$ **b** $3x^2 - 18x = 0; x = 0, 6$
c $x^2 + 8x + 12 = 0; x = -6, -2$
d $x^2 - 2x - 15 = 0; x = -3, 5$
e $x^2 - 8x + 15 = 0; x = 3, 5$
f $x^2 + 3x - 4 = 0; x = -4, 1$

5 **a** $x^2 + 2x - 80 = 0; x = 8$ units
b $x^2 + 5x - 24 = 0; x = 3$ units

6 **a** **i** $x = 3$ **ii** minimum (3, −2)
b **i** $x = -1$ **ii** maximum (−1, 3)

7 **a** $y = 2x^2$ **b** $y = -x^2 + 2$ **c** $y = (x + 1)^2$
d $y = (x - 3)^2$ **e** $y = x^2 - 4$

8 **a** $y = x^2 + 2$



b $y = -x^2 - 5$



c $y = (x + 2)^2$



d $y = -(x - 3)^2$



e $y = (x - 1)^2 + 3$



f $y = 2(x + 2)^2 - 4$



9 **a** $y = x^2$ translated up 2 units
b $y = x^2$ reflected in the x-axis and translated down 5 units
c $y = x^2$ translated 2 units left
d $y = x^2$ reflected in the x-axis then translated 3 units right
e $y = x^2$ translated 1 unit right then 3 units up
f $y = x^2$ dilated by a factor of 2 from the x-axis, translated 2 units left and then down 4 units

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 a $y = x^2 - 8x + 12$



b $y = x^2 + 10x + 16$



c $y = x^2 + 2x - 15$



d $y = x^2 + 4x - 5$



Extended-response questions

1 a $x + 5$ **b** $A = x^2 + 5x$
c $x = 2$ ($x = -7$ not valid as $x > 0$)
d Base = 4 m, Height = 7 m

2 a i (0, 0), (6, 0) **ii** Maximum at (3, 18)

iii



b i (0, 0) **ii** (4, 16) **iii** (0, 0), (8, 0)

iv



c i Connor's rocket, 8 s **ii** Sam's rocket, 2 m higher
iii 16 m, the same height

Semester review 2

Indices and surds

Multiple-choice questions

1 C **2** B **3** D **4** E **5** C

Short-answer question

1 a $\frac{a^2b}{2}$ **b** $2x^3y^5$ **c** $8x^6 - 2$

2 a $5m^2$ **b** $\frac{2a^8}{3b^5}$ **c** $\frac{3x^2}{y}$

3 a 3.07×10^{-2} kg **b** 4.24×10^6 kg
c 1.22×10^4 seconds **d** 2.35×10^{-7} seconds

4 a 12 **b** 3 **c** $2\sqrt{3} + 7\sqrt{5}$
d $\sqrt{7}$

Extended-response question

a i 74 000 000 000 **ii** 7.4×10^{10}
b 1.87×10^{17}
c 8.72×10^{-7}

Geometry

Multiple-choice questions

1 C
2 B
3 A
4 E
5 B

Short-answer questions

1 a $a = 100, b = 140$ **b** $a = 70, b = 55$
c $x = 67, y = 98$ **d** $x = 35$

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 85°

3 $CB = CD$ (given equal sides)
$\angle ACB = \angle ACD$ (given equal angles)
AC is common
$\therefore \Delta ABC \,|||\, \Delta ADC$ (SAS)

4 a AAA b 2.4

Extended-response question

a $\angle ABD = \angle ECD$ (given right angles)
$\angle ADB = \angle EDC$ (common angle)
$\angle DAB = \angle DEC$ (corresponding angles in parallel lines are equal)
$\therefore \Delta ABD \equiv \Delta ECD$ (AAA)

b 7.5 m c 3.75 m d 4.3 m

Algebraic techniques

Multiple-choice questions

1 E
2 D
3 B
4 A
5 D

Short-answer questions

1 a $x^2 - 9$ b $x^2 + 4x + 4$
c $6x^2 - 17x + 12$

2 a $2ab(4 + a)$ b $(3m - 5)(3m + 5)$
c $3(b - 4)(b + 4)$ d $(a + 4)(a + 10)$
e $(x + 3)^2$ f $(x - 2)(x + 10)$
g $2(x - 3)(x - 5)$ h $(2x - 3)(x - 4)$
i $(2x - 1)(3x + 4)$

3 a $(x - 3)(x - 1)$ b $(x + 2)(2x - 5)$

4 a i $\frac{3}{2}$ ii $\frac{4}{x + 3}$ iii $\frac{13x + 21}{14}$ iv $\frac{1}{3x}$
v $\frac{11x - 10}{(x + 1)(x - 2)}$ vi $\frac{2x + 25}{(x - 5)(x + 2)}$

b i $x = \frac{17}{12}$ ii $x = -11$

Extended-response question

a $10 - 2x$ and $8 - 2x$
b $(10 - 2x)(8 - 2x) = 80 - 36x + 4x^2$
c 48 m^2
d $4(x - 4)(x - 5)$
e Area of rug is 0 as it has no width

Probability and statistics

Multiple-choice questions

1 D
2 A
3 C
4 B
5 C

Short-answer questions

1 a



b i 24 ii 16
c i $\frac{1}{5}$ ii $\frac{1}{3}$

2 a



b i $\frac{1}{3}$ ii $\frac{1}{6}$ iii $\frac{1}{2}$

3 a

Stem	Leaf							
1	0	1	1	2	3	5	7	8
2	2	5	5	5	6			
3	1	2	2					

1 | 3 means 13 aces

b mode = 25, median = 20

c skewed

4 a

Class interval	Frequency	Percentage frequency
0–	2	6.7
50–	4	13.3
100–	5	16.7
150–	9	30
200–	7	23.3
250–	3	10
Total	30	100

Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b



c i 6 ii 60%

Extended-response question

a

		Red		
		1	2	3
Green	1	(1, 1)	(1, 2)	(1, 3)
	2	(2, 1)	(2, 2)	(2, 3)
	3	(3, 1)	(3, 2)	(3, 3)

b $\frac{4}{9}$

c i $\frac{1}{3}$ ii 18

d i



ii 11.5 yrs iii 90

Introduction to quadratic equations and graphs

Multiple-choice questions

1 B
2 B
3 E
4 C
5 E

Short-answer questions

1 a $x = -5$ or $x = 3$
b $x = \frac{1}{2}$ or $x - \frac{5}{3}$
c $x = 0$ or $x = -2$
d $x = -3$ or $x = 3$
e $x = 2$ or $x = 7$
f $x = -4$

2 15 m by 8 m

3 a translated 3 units up



b reflected in the x-axis and translated 4 units left



c translated 2 units right and 5 units up



4 a $y = -12$
b $x = -2, 6$
c $(2, -16)$
d



Extended-response question

a Lands after 6 seconds.
b i 180 cm ii 3 seconds
c After 2 seconds and 4 seconds
d



Essential Mathematics for the Australian Curriculum Year 9 2ed
ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Acknowledgements

The author and publisher wish to thank the following sources for permission to reproduce material:

Cover: Used under licence 2015 from Shutterstock.com / pixelparticle (background) / PT Images (boy).

Images: ©Adam.J.W.C. Creative Commons Attribution-Share Alike 2.5 Generic licence, **p.392**; ©Alamy / Photos12, **pp.212–213 /** Didier ZYLBERYNG, **pp.288–289 /** RGB Ventures / SuperStock, **pp.624–625**; ©Donaldytong. Creative Commons Attribution-ShareAlike 3.0 Licence, **p.472**; Photo by Erwinrossen, **p.390**; Getty Images / Collection Mix: Subjects, **p.104 /** E+, **p.128(b) /** SPL Creative, **pp.356–357**; ©Hideki Kimura, Kouhei Sagawa. Creative Commons Attribution 3.0 Unported licence, **p.244**; ©Martin Pettitt. Creative Commons Attribution 2.0 Generic licence, **p.606(t)**; ©iStockphoto / Petrovich9, **pp.142–143 /** Jodi Jacobson, **pp.544–545**; Used under licence 2015 from Shutterstock.com / Tanya Lapidus, **p.xv /** bikeriderlondon, **pp.2–3**, **189**, **490**, **524**, **550(t) /** Marzolino, **p.4 /** Baloncici, **p.7 /** AJYI, **p.8 /** Four Oaks, **p.9 /** William Perugini, **p.12 /** dotshock, **p.13 /** Brocreative, **p.17 /** egd, **p.18 /** mikeledray, **p.19 /** tridland, **p.20 /** cbpix, **p.24 /** Photographee.eu, **p.26 /** Ensuper, **p.29 /** Maurizio Milanesio, **p.30(t) /** David Kay, **p.30(b) /** Matej Kastelic, **p.31 /** Evgeny Litvinov, **p.32 /** cozyta, **p.33 /** paintings, **pp.37**, **132(b) /** Bikeworldtravel, **p.38 /** Dmitry Yashkin, **p.41(t) /** Valeriy Velikov, **p.41(b) /** JohnKwan, **p.43(t) /** joyfull, **p.43(b) /** DeiMosz, **p.45 /** Konstantin Sutyagin, **pp.46(t)**, **595(t) /** tatniz, **p.46(b) /** cobalt88, **p.47 /** wacpan, **p.49(t) /** Photobac, **p.49(b) /** wavebreakmedia, **pp.50(t)**, **608 /** dauf, **p.50(b) /** auremar, **p.54 /** michaeljung, **p.55(t) /** Philip Lange, **p.55(b) /** ChameleonsEye, **p.57 /** GeorgeMPhotography, **p.58 /** Kzenon, **pp.59**, **112 /** Lars Hallstrom, **p.61 /** karamysh, **p.62 /** koya979, **p.63 /** romakoma, **p.66 /** Sylvie Bouchard, **pp.70**, **89 /** Olga Miltsova, **p.74 /** oksana2010, **p.75 /** Vincent St. Thomas, **pp.76–77 /** Wouter Tolenaars, **p.78 /** Janet Faye Hastings, **p.79 /** Jamie Hooper, **p.81 /** Shebeko, **p.84 /** janecat, **p.87 /** Warren Goldswain, **p.88 /** Brooke Becker, **p.93 /** R. Gino Santa Maria, **p.94 /** macka, **p.97 /** Monkey Business Images, **pp.99**, **119**, **535 /** Gary Paul Lewis, **p.101 /** gamble19, **p.102 /** Prod-akszyn, **p.103 /** Gerardvhemeren, **p.105 /** aspen rock, **p.106 /** c.byatt-norman, **p.107(t) /** Anna Paff, **p.107(b) /** MaszaS, **p.117 /** kezza, **p.118 /** Andrey_Popov, **pp.120**, **497**, **498 /** Adisa, **p.123 /** Frontpage, **p.128(t) /** Anton Balazh, **p.129 /** Ollyy, **pp.130**, **590 /** HomeStudio, **p.132(t) /** StockLite, **p.133 /** Shane White, **p.139 /** i-m-a-g-e, **p.140 /** Cheryl Casey, **p.141 /** Rawpixel, **p.150 /** Bjorn Heller, **p.151 /** Nicholas Rjabow, **p.156 /** Maridav, **p.158 /** vetala, **p.159 /** Mitrofanov Alexander, **p.160 /** Kanuman, **p.161 /** theowl84, **p.165 /** Dan Breckwoldt, **p.166 /** Timothy Craig Lubcke, **p.170 /** Danilo Ascione, **p.171 /** m.pilot, **p.172 /** Bitanga87, **p.177 /** Minerva Studio, **p.179 /** Nadezhda1906, **p.185 /** Stephen Finn, **p.190 /** Nicholas Georgiou, **p.193 /** Aitormmfoto, **p.194(t) /** skynetphoto, **p.194(b) /** kurhan, **p.195 /** ID1974, **p.196(t) /** Steve Mann, **p.196(b) /** Blend Images, **p.197 /** cpaulfell, **p.203 /** Bplanet, **p.205 /** irabel8, **p.206 /** stoupa, **p.211 /** Lisa F. Young, **p.214 /** Matyas Rehak, **p.219 /** Vladitto, **p.220 /** Carlos Neto, **p.224 /** Mattz90, **p.225 /** Paul Brennan, **p.233 /** upthebanner, **p.238 /** Alexander Chaikin, **p.239 /** Maksud, **p.241 /** homydesign, **pp.243**, **435 /** Volodymyr Burdiak, **p.245 /** leungchopan, **p.252 /** Renate Micallef, **p.256 /** Alan Freed, **p.257 /** Jim Parkin, **p.264 /** Natursports, **p.268 /** Francisco Caravana, **p.270 /** Eviled, **p.271 /** Rainer Plendl, **p.272 /** Alister G Jupp, **p.273 /** Ventura, **p.276 /** cycreation, **p.278 /** steamroller_blues, **p.280 /** Gilles Paire, **p.281 /** Pashin Georgiy, **p.285 /** Dmitry Kalinovsky, **pp.287**, **626**, **631 /** MaxyM, **p.290 /** Photoseeker, **p.294 /** Civil, **p.296 /** Helder Almeida, **p.300 /** Vitally, **p.301 /** imging, **p.308 /** Shi Yali, **p.310 /** Elzbieta Sekowska, **p.314 /** Inozemtsev Konstantin, **p.321 /** branislavpudar, **p.324 /** Coprid, **p.325 /** dragon_fang, **p.333 /** IR Stone, **p.334 /** Denys Kurylow, **p.335 /** muratart, **p.338 /** PRILL, **p.341 /** NikkiHoff, **p.342 /** Greg McGill, **p.347 /** WitR, **p.358 /** ballemans, **p.362(t) /** Tanis Saucier, **p.362(b) /** mironov, **p.364 /** Apollofoto, **p.370 /** biletskiy, **p.374 /** anyaivanova, **p.375 /** Gayvoronskaya_Yana, **p.379 /** zentilia, **p.380 /** James Laurie, **p.385 /** Videowokart, **p.387 /** Suppakij1017, **p.388 /** gfdunt, **p.391 /** Revenant, **p.393 /** Alex Staroseltsev, **p.394 /** Chromatika Multimedia snc, **p.398 /** MichaelTaylor, **p.408 /** Orla, **p.415 /** Michelangelus, **pp.416–417 /** TK Kurikawa, **p.418 /** after6pm, **p.422(b) /** Dimedrol68, **p.425 /** WDG Photo, **p.427 /** Air Images, **p.431 /** Alan Smillie, **p.434 /** nito, **p.441 /** Vladislavs Zarovs, **p.442 /** Mmaxer, **p.449 /** Tischenko Irina, **p.456 /** Rikke, **p.462 /** Albisoima, **p.463(b) /** psamtik, **p.464 /** Rob Byron, **p.485 /** Tatiana Popova, **pp.486–487 /** Phillip W. Kirkland, **p.488 /** Dainis Derics, **p.492 /** Steve Collender, **p.496 /** ewa b, **p.501 /** Aaron Amat, **p.505 /** Sharlotta, **p.506 /** photosync, **p.507 /** shooarts, **p.513 /** Jeka, **p.514 /** Dragon Images, **p.528 /** Ppaauullee, **p.543 /** 3523studio, **p.546 /** Christos Georghiou, **p.550(b) /** Rudy Umans, **p.551 /** John Leung, **p.554 /** Luiz Rocha, **p.556 /** IM_photo, **p.557 /** lenetstan, **p.558 /** Deyan Georgiev, **p.559 /** Jagodka, **p.563 /** Boule, **p.564 /** Robyn Mackenzie, **pp.566**, **571 /** Twenty20 Inc, **p.570 /** Anton Prado PHOTO, **p.574 /** Lisa A, **p.575 /** Alexander Raths, **p.576 /** zstock, **p.578 /** Kletr, **p.580 /** Baevskiy Dmitry, **p.581 /** Stephen Mcsweeny, **p.584 /** violetkaipa, **p.588 /** Rido, **p.591 /** Neale Cousland, **p.592 /** Olesya Feketa, **p.594 /** linerpics, **p.595(b) /** Arena Photo UK, **p.598 /** simez78, **p.599 /** jabiru, **p.600 /** BrunoRosa, **p.602 /** B Calkins, **p.603 /** DoublePHOTO studio, **p.605 /** Brian A Jackson, **pp.606(b)**, **607(t) /** Teddy Leung, **p.607(t) /** Shots Studio, **p.609 /** RioPatuca, **p.611 /** Leena Robinson, **p.612 /** Eric Isselee, **p.613 /** Aspen Photo, **p.614 /** P.D.T.N.C, **p.615 /** Janfilip, **p.620 /** Adam Gregor, **p.621 /** 06photo, **p.623 /** Martin Capek, **p.632 /** steve estvanik, **p.638 /** Joe Iera, **p.639 /** Tom Wang, **p.640 /** Tungphoto, **p.643 /** Kristina Postnikova, **p.645 /** michael watson, **p.647 /** imagedb.com, **p.651 /** Christian Carollo, **p.654 /** M Reel, **p.661 /** czdast, **p.666 /** Giancarlo Liguori, **p.667 /** Chernetskiy, **p.670 /** Ruud Morijn Photographer, **p.679 /** John Lindsay-Smith, **p.685 /** Fotokostic, **p.693**.

Every effort has been made to trace and acknowledge copyright. The publisher apologises for any accidental infringement and welcomes information that would redress this situation.

ISBN 978-1-107-57007-8
© Greenwood et al. 2016
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.