
learnon
www.jacplus.com.au

SMITH | SMART | JAMES | MAHONY | LANGSFORD WILLING

JACARANDA

MATHS QUEST 7

AUSTRALIAN CURRICULUM | FOURTH EDITION



jacaranda
A Wiley Brand

JACARANDA

MATHS QUEST 7

AUSTRALIAN CURRICULUM | FOURTH EDITION

JACARANDA MATHS QUEST 7

AUSTRALIAN CURRICULUM | FOURTH EDITION

CATHERINE SMITH

JAMES SMART

GEETHA JAMES

CAITLIN MAHONY

BEVERLY LANGSFORD WILLING

CONTRIBUTING AUTHORS

Michael Sheedy | Kahni Burrows | Paul Menta

jacaranda
A Wiley Brand

Fourth edition published 2021 by
John Wiley & Sons Australia, Ltd
42 McDougall Street, Milton, Qld 4064

First edition published 2011
Second edition published 2014
Third edition published 2018

Typeset in 10/14 pt Times LT Std

© John Wiley & Sons Australia, Ltd 2011, 2014, 2018, 2021

The moral rights of the authors have been asserted.

ISBN: 978-0-7303-9305-4

Reproduction and communication for educational purposes
The Australian *Copyright Act 1968* (the Act) allows a maximum of one chapter or 10% of the pages of this work, whichever is the greater, to be reproduced and/or communicated by any educational institution for its educational purposes provided that the educational institution (or the body that administers it) has given a remuneration notice to Copyright Agency Limited (CAL).

Reproduction and communication for other purposes
Except as permitted under the Act (for example, a fair dealing for the purposes of study, research, criticism or review), no part of this book may be reproduced, stored in a retrieval system, communicated or transmitted in any form or by any means without prior written permission. All inquiries should be made to the publisher.

Trademarks
Jacaranda, the JacPLUS logo, the learnON, assessON and studyON logos, Wiley and the Wiley logo, and any related trade dress are trademarks or registered trademarks of John Wiley & Sons Inc. and/or its affiliates in the United States, Australia and in other countries, and may not be used without written permission. All other trademarks are the property of their respective owners.

Front cover image: © Perepadia Y/Shutterstock

Illustrated by diacriTech and Wiley Composition Services

Typeset in India by diacriTech

NATIONAL LIBRARY OF AUSTRALIA

A catalogue record for this book is available from the National Library of Australia

Contents

NAPLAN practice vii
About this resource viii
Acknowledgements xiv
Powering up for Year 7 xvii

online only

Powering up for Year 7

Week 1 Knowing your place
Week 2 Numbering up
Week 3 Thinking quickly
Week 4 Fishing for fractions
Week 5 Getting to the point
Week 6 Giving 100%

online only

NAPLAN practice

Set A Calculator allowed
Set B Non-calculator
Set C Calculator allowed
Set D Non-calculator
Set E Calculator allowed
Set F Non-calculator

1 Positive integers 1

1.1 Overview 2
1.2 Place value 4
1.3 Strategies for adding and subtracting positive integers 10
1.4 Algorithms for adding and subtracting positive integers 16
1.5 Multiplying positive integers 25
1.6 Dividing positive integers 34
1.7 Rounding and estimating 41
1.8 Order of operations 45
1.9 Review 52
Answers 62

2 Positive and negative integers 67

2.1 Overview 68
2.2 Integers on the number line 70
2.3 Integers on the number plane 76
2.4 Adding integers 81
2.5 Subtracting integers 86
2.6 Multiplying and dividing integers (extending) 92
2.7 Order of operations with integers (extending) 98
2.8 Review 102
Answers 110

3 Factors, multiples, indices and primes 115

3.1 Overview 116
3.2 Factors and multiples 118
3.3 Lowest common multiple and highest common factor 123
3.4 Index notation 128
3.5 Prime and composite numbers 133
3.6 Squares and square roots 141
3.7 Divisibility tests 147
3.8 Cubes and cube roots (extending) 150
3.9 Review 155
Answers 163

4 Fractions and percentages 169

4.1 Overview 170
4.2 What are fractions? 172
4.3 Simplifying fractions 184
4.4 Mixed numbers and improper fractions 188
4.5 Adding and subtracting fractions 194
4.6 Multiplying fractions 202
4.7 Dividing fractions 210
4.8 Working with mixed numbers 215
4.9 Percentages as fractions 222
4.10 Calculating percentages of an amount 227
4.11 One amount as a percentage of another 232
4.12 Common percentages and short cuts 238
4.13 Review 244
Answers 254

5 Ratios, rates and best buys 263

5.1 Overview 264
5.2 Ratios 267
5.3 Rates 273
5.4 The unitary method and best buys 278
5.5 Review 283
Answers 289

6 Decimals 291

6.1 Overview 292
6.2 Decimals and place value 294
6.3 Converting decimals to fractions and fractions to decimals 302
6.4 Rounding and repeating decimals (extending) 307
6.5 Adding and subtracting decimals 313
6.6 Multiplying decimals 319
6.7 Dividing decimals 325
6.8 Decimals and percentages 332

6.9 Review ... 335
Answers ... 343

7 Algebra 349

7.1 Overview ... 350
7.2 Introduction to algebra ... 352
7.3 Substituting and evaluating ... 360
7.4 Simplifying expressions using like terms ... 364
7.5 Multiplying and dividing terms ... 369
7.6 Number laws ... 373
7.7 Expanding brackets (extending) ... 377
7.8 Review ... 381
Answers ... 388

Semester review 1 online only 392

8 Equations 395

8.1 Overview ... 396
8.2 Introduction to equations ... 398
8.3 Building up expressions and backtracking ... 404
8.4 Solving equations using backtracking ... 410
8.5 Solving equations using inverse operations ... 417
8.6 Checking solutions ... 426
8.7 Review ... 431
Answers ... 438

9 Geometry 443

9.1 Overview ... 444
9.2 Measuring angles ... 447
9.3 Constructing angles with a protractor ... 455
9.4 Types of angles and naming angles ... 461
9.5 Triangles ... 467
9.6 Quadrilaterals and their properties ... 479
9.7 Parallel and perpendicular lines ... 489
9.8 Review ... 500
Answers ... 510

10 Measurement 519

10.1 Overview ... 520
10.2 Units of measurement ... 523
10.3 Reading scales and measuring length ... 530
10.4 Perimeter ... 538
10.5 Area ... 546
10.6 Area of composite shapes (extending) ... 559
10.7 Volume of rectangular prisms ... 564
10.8 Capacity ... 572
10.9 Drawing solids ... 576
10.10 Review ... 587
Answers ... 599

11 Coordinates and the Cartesian plane 607

11.1 Overview ... 608
11.2 The Cartesian plane ... 611
11.3 Linear number patterns ... 619
11.4 Plotting simple linear relationships ... 626
11.5 Interpreting graphs ... 633
11.6 Review ... 645
Answers ... 654

12 Transformations 665

12.1 Overview ... 666
12.2 Line and rotational symmetry ... 668
12.3 Translations ... 674
12.4 Reflections ... 680
12.5 Rotations and combined transformations ... 687
12.6 Review ... 698
Answers ... 704

13 Introduction to probability 715

13.1 Overview ... 716
13.2 The language of chance ... 718
13.3 The sample space ... 723
13.4 Simple probability ... 728
13.5 Experimental probability (extending) ... 734
13.6 Review ... 742
Answers ... 750

14 Representing and interpreting data 755

14.1 Overview ... 756
14.2 Collecting and classifying data ... 759
14.3 Displaying data in tables ... 766
14.4 Measures of centre and spread ... 772
14.5 Column graphs and dot plots ... 783
14.6 Stem-and-leaf plots ... 789
14.7 Pie charts and divided bar graphs (extending) ... 795
14.8 Comparing data ... 806
14.9 Review ... 812
Answers ... 822

Semester review 2 online only 834

online only

15 Algorithmic thinking


15.1 Overview
15.2 Variables
15.3 Expressions
15.4 Sequences
15.5 Algorithms
15.6 Review
Answers

Glossary ... 836
Index ... 842

NAPLAN practice

Go online to complete practice NAPLAN tests. There are 6 NAPLAN-style question sets available to help you prepare for this important event. They are also useful for practising your Mathematics skills in general.

Also available online is a video that provides strategies and tips to help with your preparation.



SET A
Calculator allowed

SET B
Non-calculator

SET C
Calculator allowed

SET D
Non-calculator

SET E
Calculator allowed

SET F
Non-calculator


Everything you need (and *want*) at your fingertips

A full lesson on one screen in your online course. Trusted, curriculum-aligned theory. Engaging, rich multimedia. All the teacher support resources you need. Deep insights into progress. Immediate feedback for students. Create custom assignments in just a few clicks.

Practical teaching advice and ideas

Teaching videos for all lessons

Reading content and rich media






Differentiated question sets
Teacher and student views
Textbook questions
eWorkbook
Solutions
Digital documents
Video eLessons
Interactivities
ProjectsPLUS
Extra teaching resources
Questions with immediate feedback
Teacher
Student
Year7A-Jacaranda-VC-...
Help
Samwell Tarly
3.2 Ex 1
3.2 TBQ
RESOURCES
Topic PDF
eWorkbook
Solutions
Digital documents
Video eLessons
Interactivities
ProjectsPLUS
Weblinks
TEACHER eWorkbook
TEACHER Digital documents
TEACHER Weblinks
UR PATHWAY
PRACTISE
CONSOLIDATE
MASTER
Questions: 1, 6, 9, 12, 14, 17, 18, 21, 24, 26
Questions: 2, 7, 10, 15, 22, 23, 25, 28
ing numbers on a number line.
1 mark(s)
3.3 ADDING AND SUBTRACTING FRACTIONS

About this resource


Online, these new editions are the complete package — with trusted Jacaranda theory plus tools to support teaching and make learning more engaging, personalised and visible.

Available in learnON, our most powerful online learning platform







Instant reports give teachers and students deep insights into progress, including mapping of results against the cognitive processes.




Three differentiated question sets, with immediate feedback in every lesson, enable students to challenge themselves at their own level.



An in-built testmaker enables teachers to create assignments using any question in the resource for immediate, spaced and mixed practice.




Every question has immediate, corrective feedback to help students overcome misconceptions as they occur and study independently — in class and at home.



A six-week 'Powering up for Year 7' online program is designed to plug any gaps from earlier years.



New teaching videos for every lesson are designed to help students learn concepts by having a 'teacher at home', and are flexible enough to be used for pre- and post-learning, flipped classrooms, class discussions, remediation and more.




For teachers, the online teachON section contains practical teaching advice including learning intentions and three levels of differentiated teaching programs.



The eWorkbook enables teachers and students to download additional activities to support deeper learning.

Embedded interactivities and videos enable students to explore concepts and learn deeply by 'doing'.



Acknowledgements

The authors and publisher would like to thank the following copyright holders, organisations and individuals for their assistance and for permission to reproduce copyright material in this book.

© Australian Curriculum, Assessment and Reporting Authority (ACARA) 2010 to present, unless otherwise indicated. This material was downloaded from the Australian Curriculum website (www.australiancurriculum.edu.au) (Website) (accessed October 2020) and was not modified. The material is licensed under CC BY 4.0 (https://creativecommons.org/licenses/by/4.0). Version updates are tracked on the 'Curriculum version history' page (www.australiancurriculum.edu.au/Home/CurriculumHistory) of the Australian Curriculum website.

Images

• © AIhero/Shutterstock: **xvii** • a.Chones/Shutterstock; b.M. Unal Ozmen/Shutterstock; c.M. Unal Ozmen/Shutterstock: **404** • a.Eva Speshneva/Shutterstock; b.Sudowoodo/Shutterstock: **364** • a.Raphael Christinat/Shutterstock; b.Raphael Christinat/Shutterstock: **125** • © imageBROKER/Alamy Stock Photo: **247** • © Lucy Rock/Alamy Australia Pty Ltd: **1** • © PA Images/Alamy Stock Photo: **2**, **292**, **318** • © PANAGIOTIS KARAPANAGIOTIS/Alamy Stock Photo: **54** • © Digital Stock/Corbis Corporation: **91**, **464** • © Digital Vision: **637** • © Christopher Futcher/Getty Images: **817** • © ET-ARTWORKSGetty Images: **687** • © jgroup/Getty Images: **715** • © trigga/Getty Images: **74** • © Image Disk Photography: **7** • © Image Addict: **231** • © IT Stock: **464** • © c John Wiley & Sons Australia/Jennifer Wright: **181** • © John Wiley & Sons Australia: **34** • © John Wiley & Sons Australia/Carolyn Mews: **488** • © John Wiley & Sons Australia/Carolyn Mews: **452** • © John Wiley & Sons Australia/Taken by Kari-Ann Tapp: **198** • © John Wiley & Sons Australia/Jennifer Wright: **181** • © Kari-Ann Tapp: **734** • © National Council of Teachers of Mathematics: **737** • © News Ltd/Newspix: **482** • © Photodisc: **23, 200**, **465**, **764**, **766**, **793** • Angela Matthews/Shutterstock: **vii•**/Shutterstock: **1** • Daniel Jedzura/Shutterstock: **220** • dikkenss/Shutterstock: **589** • freevideophotoage/Shutterstock: **160** • Nerthuz/Shutterstock: **286** • nortongo/Shutterstock: **564**, **566** • Oleksandr Lytvyne/Shutterstock: **17** • Rostislav Král/Shutterstock: **219** • Syda Productions/Shutterstock: **183** • Tomasz Czajkowski/Shutterstock: **528** • Tum3000/Shutterstock: **589** • wolfman57/Shutterstock: **227**/Shutterstock: **355** • © Aaron Amat/Shutterstock: **324** • © abriendomundo/Shutterstock: **9** • © Adam Middleton/Shutterstock: **647** • © aekikuis/Shutterstock: **285** • © Africa Studio/Shutterstock: **350**, **368**, **380** • © al7Shutterstock: **436** • © Alberto Loyo/Shutterstock: **251** • © alessandro 0770Shutterstock: **230** • © Alexander Limbach/Shutterstock: **67** • © Alexandra Lande/Shutterstock: **668** • © Alinute Silzeviciute/Shutterstock: **810** • © ALPA PROD/Shutterstock: **133** • © alterfalter/Shutterstock: **157** • © alybaba/Shutterstock: **700** • © AmaPhoto/Shutterstock: **252** • © Andrew Burgess/Shutterstock: **6** • © Andrey Armyagov/Shutterstock: **126** • © Andrey Bayda/Shutterstock: **273** • © Andrey_Popov/Shutterstock: **760** • © Andrii_M/Shutterstock: **100** • © Annches/Shutterstock: **400** • © Anthony Hall/Shutterstock: **467** • © Anton Balazh/Shutterstock: **607** • © Antonio Guillem/Shutterstock: **280** • © Aptyp_koK/Shutterstock: **647** • © ArliftAtoz2205Shutterstock: **436** • © auddmin/Shutterstock: **741** • © AustralianCamera/Shutterstock: **237** • © Axel Bueckert/Shutterstock: **294**, **298** • © Azat1976Shutterstock: **665** • © bernashafo/Shutterstock: **338** • © BEST-BACKGROUNDS/Shutterstock: **6** • © Bilanol/Shutterstock: **40** • © Blend Images/Shutterstock: **33** • © Bloomicon/Shutterstock: **331** • © CapturePB/Shutterstock: **732** • © Carlos Gutierrez Photo/Shutterstock: **75** • © Carsten Reisinger/Shutterstock: **180** • © Celso Pupo/Shutterstock: **433** • © ChameleonsEye/Shutterstock: **24** • © Chekyravaa/Shutterstock: **172** • © Chris Jenner/Shutterstock: **647** • © clearviewstock/Shutterstock: **748** • © Corepics VOF/Shutterstock: **23** • © cpaulfell/Shutterstock: **436** • © Damian Pankowiec/Shutterstock: **33** • © David Carillet/Shutterstock: **443** • © debra hughes/Shutterstock: **119** • © Denis Kuvaev/Shutterstock: **296** • © Denphumi/Shutterstock: **722** • © dim.po/Shutterstock: **272** • © DisobeyArt/Shutterstock: **101** • © Dmitry Eagle Orlov/Shutterstock: **383** • © Dmytro Zinkevych/Shutterstock: **413** • © docstockmedia/Shutterstock: **666** • © dolomite-summits/Shutterstock: **159** • © DOUG RAPHAEL/Shutterstock: **222** • © Dragon Images/Shutterstock: **133** • © Dragon Images/Shutterstock: **771•** © Dusan Pavlic: **xvii**/Shutterstock: • © Dusan Petkovic/Shutterstock: **359** • © eAlisa/Shutterstock: **246** • © egd/Shutterstock: **333** • © Ekaterina Markelova/Shutterstock: **426** • © Elartico/Shutterstock: **116** • © Elena Veselova/Shutterstock: **266** • © ESB Professional/Shutterstock: **769** • © ESB Professional/Shutterstock: **236** • © Etaphop photo/Shutterstock: **491** • © Eva Speshneva/Shutterstock: **364** • © f11photo/Shutterstock: **50** • © Fabrik Bilder/Shutterstock: **777** • © Fedor Selivanov/Shutterstock: **53** • © Fertas/Shutterstock: **435** • © frenchiestravel/Shutterstock: **58** • © fresher/Shutterstock: **34** • © Fresnel/Shutterstock: **351** • © fritz16/Shutterstock: **8** • © garagestock/Shutterstock: **280** • © Gary Reinwald/Shutterstock: **668** • © Gentian Polovina/Shutterstock: **286** • © givaga/Shutterstock: **281** • © Gjermund/Shutterstock: **619** • © goodluz/Shutterstock: **132** • © Gorodenkoff/Shutterstock: **75** • © GraphicsRF/Shutterstock: **41** • © Gringoann/Shutterstock: **286** • © grum_l/

Shutterstock: **731** • © gualtiero boffi/Shutterstock: **232** • © Halfpoint/Shutterstock: **126** • © hddigital/Shutterstock: **318** • © HG Photography/Shutterstock: **194** • © Hong Vo/Shutterstock: **385** • © Hquality/Shutterstock: **746** • © Hquality/Shutterstock: **306** • © Hugo Felix/Shutterstock: **154** • © Iakov Filimonov/Shutterstock: **86**, **214** • © Ilja Generalov/Shutterstock: **632** • © IM_photo/Shutterstock: **349** • © ingehogenbijl/Shutterstock: **8** • © Ingrid Balabanova/Shutterstock: **338** • © Ivan Marjanovic/Shutterstock: **80**• © JANNTA/Shutterstock: **xvii** • © Jan Hopgood/Shutterstock: **396** • © Jaroslaw Grudzinski/Shutterstock: **377** • © Jasni/Shutterstock: **732** • © Jeni Jenny Jeni/Shutterstock: **170** • © jokerpro/Shutterstock: **44** • © Jorge Casais/Shutterstock: **639** • © Joshua Resnick/Shutterstock: **338** • © JPL Designs/Shutterstock: **699** • © JR-stock/orge CasaisShutterstock: **363** • © Julinzy/Shutterstock: **271** • © K2 PhotoStudio/Shuttertock: **169** • © Kampol Taepanich/Shutterstock: **358** • © kan_chana/Shutterstock: **755**• © Katie Dickinson/Shutterstock: **23** • © Katilda/Shutterstock: **491** • © Kostyazar/Shutterstock: **386** • © Krakenimages.com/Shutterstock: **748** • © Kutlayev Dmitry/Shutterstock: **266** • © l i g h t p o e t/Shutterstock: **33** • © Lance Bellers/Shutterstock.com: **722** • © Lesya Dolyuk/Shutterstock: **193** • © LightField Studios/Shutterstock: **266** • © M. Unal Ozmen/Shutterstock: **58** • © Madeleine R/Shutterstock: **281** • © Mak3t/Shutterstock: **669** • © Maks Narodenko/Shutterstock: **191** • © Maliutina Anna/Shutterstock: **97** • © mammothis/Shutterstock: **38** • © MaraZe/Shutterstock: **45** • © MarcelClemens/Shutterstock: **395** • © Maridav/Shutterstock: **640** • © mashurov/Shutterstock: **39** • © matimix/Shutterstock: **726** • © Maxisport/Shutterstock: **432** • © Maxisport/Shutterstock: **317** • © MCruzUA/Shutterstock: **35** • © Mega Pixel/Shutterstock: **728** • © Micah Burke/Shutterstock: **115** • © Michael D Brown/Shutterstock: **745** • © Michael Rosskothen/Shutterstock: **647** • © MichaelJayBerlin/Shutterstock: **138** • © michaeljung/Shutterstock: **425** • © Mila Supinskaya Glashchenko/Shutterstock: **39** • © Milagli/Shutterstock: **55** • © Mind Pro Studio/Shutterstock: **234** • © Minerva Studio/Shutterstock: **312** • © Minerva Studio/Shutterstock: **781** • © MiniDoodle/Shutterstock: **743** • © mirtmirt/Shutterstock: **727** • © Mitch Hutchinson/Shutterstock: **716** • © Monkey Business Images/Shutterstock: **40**, **122**, **409** • © Monkey Business Images/Shutterstock: **209** • © Monkey Business Images/Shutterstock: **193**, **403**, **770** • © Monkey Business Images/Shutterstock: **225**, **226**, **265** • © monticello/Shutterstock.com: **733** • © monticello/Shutterstock: **242** • © mooinblack/Shutterstock: **242** • © Murni/Shutterstock: **358** • © naito29Shutterstock: **351** • © Nataliya Peregudova/Shutterstock: **227** • © Neale Cousland/Shutterstock: **59** • © Neale Cousland/Shutterstock: **722** • © Neale Cousland/Shutterstock: **231** • © Neirfy/Shutterstock: **383** • © Nejron Photo/Shutterstock: **86** • © Nerthuz/Shutterstock: **282** • © New Africa/Shutterstock: **125** • © New Africa/Shutterstock: **760** • © Nicholas Piccillo/Shutterstock: **416** • © NicoElNino/Shutterstock: **407** • © nobeastsofierce/Shutterstock: **133** • © nortongo/Shutterstock: **380** • © Oez/Shutterstock: **501** • © oksana2010/Shutterstock: **282** • © Oleksiy Mark/Shutterstock: **252** • © Olga Kashubin/Shutterstock: **668** • © Orhan Cam/Shutterstock: **668** • © PanyaStudio/Shutterstock: **360** • © Pepgooner/Shutterstock: **91** • © Petrenko Andriy/Shutterstock.com: **183** • © Phatthanit/Shutterstock: **232** • © Phils Mommy/Shutterstock: **430** • © Photoagriculture/Shutterstock: **423** • © photokup/Shutterstock: **429** • © Pixel-Shot/Shutterstock: **385**, **820** • © Popartic/Shutterstock: **39** • © ppart/Shutterstock: **669** • © PPstock/Shutterstock: **160** • © Pressmaster/Shutterstock: **359** • © ProStockStudio/Shutterstock: **398** • © Qilins prance Filmmaker/Shutterstock: **101** • © Radu Bercan/Shutterstock: **278**, **483** • © ratselmeister/Shutterstock: **265** • © Rawpixel.com/Shutterstock: **251** • © Renovacio/Shutterstock: **733** • © rfranca/Shutterstock: **354** • © Richard Semik/Shutterstock: **423** • © Rido/Shutterstock: **126** • © Rinelle/Shutterstock: **263** • © Robyn Mackenzie/Shutterstock: **341** • © Roma Koshel/Shutterstock: **740** • © Roman Samborskyi/Shutterstock: **32** • © ROMSVETNIK/Shutterstock: **718** • © Ronald Sumners/Shutterstock: **50** • © Ruth Black/Shutterstock: **50** • © Sabelskaya/Shutterstock: **xvii** • © Sandarina/Shutterstock: **40** • © sculpies/Shutterstock: **444** • © Sentavio/Shutterstock: **xvii** • © Serg64/Shutterstock: **334** • © Sergey Nivens/Shutterstock: **72** • © Sergey Novikov/Shutterstock: **236** • © Shuang Li/Shutterstock: **278** • ©/Shutterstock: **291**, **306**, **316**, **341** • © sirtravelalot/Shutterstock: **467** • © sirtravelalot/Shutterstock: **264**, **403** • © Songsak P/Shutterstock: **488** • © Sonia Alves-Polidor/Shutterstock: **720** • © Sonulkaster/Shutterstock: **104** • © stockcreations/Shutterstock: **91** • © Sundraw Photography/Shutterstock: **639** • © Susan Schmitz/Shutterstock: **820** • © Swapan Photography/Shutterstock: **740** • © Syda Productions/Shutterstock: **101** • © Syda Productions/Shutterstock: **764** • © szefei/Shutterstock: **466** • © szefei/Shutterstock: **445** • © Tadeusz Wejkszo/Shutterstock: **359** • © Taras Vyshnya/Shutterstock: **668**• © technotr/Getty Images: **22** • © Tetyana Kokhanets/Shutterstock: **719** • © Thiti Sukapan/Shutterstock: **819** • © THPStock/Shutterstock: **727** • © TK Kurikawa/Shutterstock: **334**• © Tomasz Pado/Shutterstock: **23** • © TORWAISTUDIO/Shutterstock: **644** • © tr3gin/Shutterstock: **669** • © Tyler Olson/Shutterstock.com: **312** • © Tyler Olson/Shutterstock: **284**, **386** • © UnknownLatitude Images/Shutterstock: **7** • © upthebanner/Shutterstock: **219** • © VisualArtStudio/Shutterstock: **22** • © Vitalii Petrenko/Shutterstock: **xvii**• © Vectors bySkop/Shutterstock: **xvii** • © v74/Shutterstock: **720** • © Velychko/Shutterstock: **201** • © Vereshchagin Dmitry/Shutterstock: **764** • © Viktor Fedorenko/Shutterstock: **724**, **729** • © vkilikov/Shutterstock: **17** • © VladisChern/Shutterstock: **70** • © Volodymyr TVERDOKHLIB: **122** • © VovanIvanovich/Shutterstock: **68** • © VP Photo Studio/Shutterstock: **721** • © vvvita/Shutterstock: **73** • © wavebreakmedia/Shutterstock: **140** • © wavebreakmedia/Shutterstock: **728** • © Yeti Studio/Shutterstock: **731** • © Yevgenij_D/Shutterstock: **608** • © You Touch Pix of EuToch/Shutterstock: **231** • © zbindere/Getty Images: **7** • © Zbigniew Guzowski/Shutterstock: **732** • © zentilia/Shutterstock: **726** • /Shutterstock/nortongo: **564**

• © John Wiley & Sons Australia: **209** • © Bruno Herdt/Getty Images: **451** • © Digital Stock: **451** • © Dimedrol68/Shutterstock: **454** • © diskoVisnja/Shutterstock: **499** • © diskoVisnja/Shutterstock: **499** • © Eugene Buchko/Shutterstock: **485** • © Haali/Shutterstock: **53** • © John Wiley & Sons Australia/Photo by Kari-Ann Tapp: **485** • © John Wiley & Sons Australia/Photo by Theresa Pagon: **486** • © Kitch Bain/Shutterstock.com: **352** • © Lilyana Vynogradova/Shutterstock: **452** • © Olesia Bilkei/Shutterstock: **454** • © Photo Melon/Shutterstock: **485** • © PhotoDisc: **452**, **477** • © Photodisc: **477** • © pornvit_v/Shutterstock: **485** • © Ruud Morijn Photographer/Shutterstock: **499** • © Sheila Fitzgerald/Shutterstock: **355**

Every effort has been made to trace the ownership of copyright material. Information that will enable the publisher to rectify any error or omission in subsequent reprints will be welcome. In such cases, please contact the Permissions Section of John Wiley & Sons Australia, Ltd.

Powering up for Year 7

We care deeply about ensuring that all students feel confident in knowing they are equipped with the essential core skills in Mathematics as they transition into Year 7.

Powering up for Year 7 is a brand-new online resource developed to fill learning gaps in key mathematical areas to ensure that all students have the building blocks needed to move smoothly into Year 7. The course is organised around key skills over a period of six weeks:




Students will learn key skills such as as place value, operations with whole numbers, mental strategies for calculations, fractions, decimals and percentages.

All questions are automatically marked, with instant feedback and worked solutions. This incredible resource is available online only in our digital learnON platform.

Powering up for Year 7

Week 1: Finding your place

Reading, writing and understanding whole numbers



- **Numbers** are made up of digits in the same way that words are made up of letters.

10 Ten

- The **digits** that make up numbers are:

0 1 2 3 4

5 6 7 8 9

Just as you can combine the letters of the alphabet to make an infinite number of words, you can do the same with these ten digits; they can be combined in many ways to make an infinite number of numbers.

- **Whole numbers** are the numbers 0, 1, 2, 3, 4, ... and so on. Fun fact: there is no biggest whole number! Examples of whole numbers include 15, 134, 1091 and 1 000 823.
- Whole numbers cannot be fractions or decimals.
- **Counting numbers** are the same as whole numbers, but without 0 as you can't count zero objects.
- The position or *place* of a digit within a number determines the value of the number.
  For example, 23 is not the same number as 32, although they both have the same digits, 2 and 3.

Let's illustrate the values of these two numbers.

23 =



32 =




It is clear from this illustration that 32 has a higher value than 23 as there are nine more blue squares in 32 than 23.
Another way to think about these numbers is to use groups. 23 is made up of 2 groups of ten and 3 units (or ones). 32 is made up of 3 groups of ten and 2 units (or ones).

23 = 2 tens and 3 ones



32 = 3 tens and 2 ones



That is, because of the way the digits are placed, in the number 23, 2 has a value of 20 and 3 has a value of 3 ones. In the number 32, 3 has a value of 30 and 2 has a value of 2 ones.

In the number 1234 the value of each digit is:	
1	represents 1 thousand (1000)
2	represents 2 hundreds (200)
3	represents 3 tens (30)
4	represents 4 ones (4)

- To help understand the value of each digit in a number, it is helpful to use a **place value** table.

Place value table			
Thousands	**Hundreds**	**Tens**	**Ones**
1	2	3	4

To make bigger numbers, add a new column to the left, as each column to the left is ten times bigger than the one on its right.

For example, the number 51 436 would have the following place value table.

Place value table				
Ten-thousands	**Thousands**	**Hundreds**	**Tens**	**Ones**
5	1	4	3	6

- **Expanded notation** is a way to write the value of each digit. For example,

$$51\,436 = 50\,000 + 1000 + 400 + 30 + 6$$



WORKED EXAMPLE 1 Expanding numbers

Show 2 469 000 in expanded notation.

THINK	WRITE
1. There is a 2 in the millions column, as shown in pink 2 469 000	2 000 000
2. There is a 4 in the hundred thousands column, as shown in red: 2 469 000	2 000 000 + 400 000
3. There is a 6 in the ten thousands column, as shown in plum: 2 469 000.	2 000 000 + 400 000 + 60 000
4. There is a 9 in the thousands column, as shown in purple: 2 469 000.	2 000 000 + 400 000 + 60 000 + 9000
5. Write 2 469 000 in expanded form.	2 469 000 = 2 000 000 + 400 000 + 60 000 + 9000

- Knowing place value helps you to read numbers. The number 2 469 000 is read as 'two million, four hundred and sixty-nine thousand'.
- Spaces (or commas) are used between groups of 3 digits when numbers are written.

Spaces are not used when writing 4-digit numbers such as 4357.

Place value chart: Families										
Millions			**First space**	Thousands			**Second space**	Ones		
Hundred millions	Ten millions	Millions		Hundred thousands	Ten thousands	Thousands		Hundreds	Tens	Ones
		8		1	6	8		6	4	9

The number 8 168 649 is read as:

eight million, one hundred and sixty-eight thousand, six hundred and forty-nine

Comparing whole numbers

- Numbers can be compared to determine if one number is:
  - the **same** size as another number
  - **less** (smaller) **than** another number
  - **greater** (bigger) **than** another number.



Recording numbers in a place value table is a good strategy to use to compare numbers.

For example, which ice-cream flavour is the more popular of the two shown below?



	Place value					
	Hundred thousands	Ten thousands	Thousands	Hundreds	Tens	Ones
Chocolate	3	4	5	7	6	0
Strawberry	3	4	5	7	0	6
	Digits have the same value ✓ Look at the next column →	Digits have the same value ✓ Look at the next column →	Digits have the same value ✓ Look at the next column →	Digits have the same value ✓ Look at the next column →	Digits have a different value 6 is greater than 0	

This tells us that more chocolate-flavoured ice creams were sold than strawberry-flavoured ice creams.

- We can use symbols in place of words when comparing numbers.

Symbol	Description	Example
=	When two values are the same, we use the 'equals' symbol.	$5 = 5$
<	When one value is smaller than another, we use the 'less than' symbol.	$4 < 7$
>	When one value is bigger than another, we use the 'greater than' symbol.	$8 > 3$

So, 345 760 is greater than 345 706: $345\,760 > 345\,706$

Ordering numbers

- Numbers ordered from smallest to largest are in **ascending order**.
  For example: 3, 6, 10, 16
- Numbers ordered from largest to smallest are in **descending order**.
  For example: 16, 10, 6, 3

WORKED EXAMPLE 2 Ordering numbers

Place the following numbers in ascending order. 756, 687, 435, 742, 498, 659

THINK	WRITE
1. All of the numbers are in the hundreds. Write the numbers with the lowest hundreds value.	435, 498
2. Check the digit to the right of 4. '3' in 435 is smaller than '9' in 498, so the numbers are in ascending order.	435, 498
3. Write the numbers with the next lowest hundreds values.	687, 659
4. Check the digit to the right of 6. '8' in 687 is larger than '5' in 659, so swap these numbers.	659, 687
5. Write the numbers with the highest hundreds values.	756, 742
6. Check the digit to the right of 7. '5' in 756 is larger than '4' in 742, so swap these numbers.	742, 756
7. Write the numbers in ascending order.	435, 498, 659, 687, 742, 756

Rounding whole numbers

- **Rounding** means to make a number simpler but similar. We often need to round when estimating calculations.
  For example, when trying to quickly calculate 21 times 4, it is easier to estimate the answer by multiplying 20 by 4. The result of 80 is less accurate, but a close estimate to the real answer of 84.

Rounding up and down

When rounding numbers, it is useful to remember the following:

0, 1, 2, 3, 4	Round down
5, 6, 7, 8, 9	Round up



When rounding numbers, decide which is the last digit to keep.

- Keep it the same if the next digit is 0, 1, 2, 3 or 4, and replace all other digits with zeros.
- Increase it by 1 if the next digit is 5, 6, 7, 8, or 9 and replace all other digits with zeros.

WORKED EXAMPLE 3 Rounding to the nearest 10

a. Round 64 to the nearest 10.
b. Round 57 to the nearest 10.


THINK	WRITE
a. 1. In the number 64, we want to keep or increase '6' because it is in the tens position. Highlight the next digit (4).	64
2. Since this next digit is 4, we round down. That is, keep '6' and replace '4' with '0'.	60
3. Write the answer.	Rounding 64 to the nearest 10 gives 60.
b. 1. In the number 57, we want to keep or increase '5' because it is in the tens position. Highlight the next digit (7).	57
2. Since this next digit is 7, we round up. That is, increase '5' by 1 (to '6') and replace '7' with '0'.	60
3. Write the answer.	Rounding 57 to the nearest 10 gives 60.

WORKED EXAMPLE 4 Rounding to the nearest 100

a. Round 827 to the nearest 100.
b. Round 194 to the nearest 100.

THINK	WRITE
a. 1. In the number 827, we want to keep or increase '8' because it is in the hundreds position. Highlight the next digit (2).	827
2. Since the next digit is 2, we round down. That is, keep '8' and make all other digits zero.	800
3. Write the answer.	Rounding 827 to the nearest 100 gives 800.
b. 1. In the number 194, we want to keep or increase '1' because it is in the hundreds position. Highlight the next digit (9).	194
2. Since the next digit is 9, we round up. That is, increase '1' by 1 (to '2') and make all other digits zero.	200
3. Write the answer.	Rounding 194 to the nearest 100 gives 200.

- When rounding whole numbers, we could think of a number line and locate which interval of 10 or 100 a number is closest to.
  For example, when rounding the number 194 to the nearest 100, use a number line to decide whether it is closer to 100 or 200.



  Since it is closer to 200, we can say that the number 194 rounded to the nearest hundred is 200.

Estimating

- Rounded numbers can be used to estimate or do calculations in your head. For example, 12 times 53 could be estimated as 10 times 50, which gives approximately 500.

Week 1 Exercise: Finding your place

1. **MC** Select from the following options. What are numbers made of?

   A. Numerals **B.** Digits **C.** Letters
   D. Words **E.** Sentences

2. **MC** Select which of the following is a whole number.

   A. 9.8 **B.** 652 **C.** $\frac{1}{2}$
   D. 0.5 **E.** 1.2

3. **WE1** Write 678 215 in expanded form.

4. **MC** The number 3245 in expanded form is:

   A. $3000 + 2000 + 4000 + 5000$ **B.** $3 + 2 + 4 + 5$ **C.** $300 + 200 + 400 + 5$
   D. $3000 + 200 + 40 + 5$ **E.** $3000 + 200 + 40 + 50$

5. **MC** Select which number could be written in the expanded form as $90\,000 + 300 + 20 + 9$.

   A. 9329 **B.** 90 239 **C.** 93 290 **D.** 95 329 **E.** 90 329

6. **MC** Select the smallest number from the following.

   A. 43 657 **B.** 43 675 **C.** 43 567 **D.** 43 576 **E.** 43 765

7. **MC** Select the largest number from the following.

   A. 43 657 **B.** 43 675 **C.** 43 567 **D.** 43 576 **E.** 43 765

8. **MC** Select the smallest number from the following.

   A. 178 534 **B.** 148 537 **C.** 187 534 **D.** 178 354 **E.** 178 543

9. **MC** Select the largest number from the following.

   A. 2 364 792 **B.** 2 364 972 **C.** 2 369 742 **D.** 2 362 794 **E.** 2 364 297

10. Determine whether the following statements are true or false.

a. $187 < 178$ **b.** $187 > 178$

11. Determine whether the following statements are true or false.

a. $3865 < 3658$ **b.** $3865 > 3658$



12. Complete the statement below by inserting the correct symbol (=, < or >) between the two numbers.

$145 \square 154$

13. Complete the statement below by inserting the correct symbol (=, < or >) between the two numbers.

$6875 \square 6857$

14. Complete the statement below by inserting the correct symbol (=, < or >) between the two numbers.

$12\,102 \square 12\,102$

15. WE2 Write the following numbers in ascending order.

12, 21, 19, 11, 20, 33, 46, 31, 26, 15, 10

16. Write the following numbers in descending order.

1254, 1524, 1425, 1452, 1245, 1542

17. MC The numbers 34 857, 34 875, 35 487, 35 748, 35 847, 37 548, 38 754 are in:

A. Ascending order **B.** Descending order **C.** No particular order
D. Multiples of 2 **E.** None of these

18. WE3 Round 152 to the nearest 10.

19. Round 1675 to the nearest 10.

20. WE4 Round 7654 to the nearest 100.

21. Round 87 345 to the nearest 100.

22. Round 8967 to the nearest 1000.

23. Round 9865 to the nearest 1000.

24. Round 45 984 to the nearest 10 000.

25. Round 536 973 to the nearest 10 000.


Week 2: Numbering up

Adding whole numbers




- Adding whole numbers means bringing two (or more) numbers together to make a new total.
- When adding numbers, the plus symbol (+) is used.

Five pink blocks plus two blue blocks can be represented by the diagram below. Counting all the blocks, there are 7 altogether. Therefore $5 + 2 = 7$



What happens if we swap the numbers around?
Two blue blocks plus five pink blocks equal 7 blocks altogether. Therefore, $2 + 5 = 7$. If you swap the position of the numbers you are adding, you will get the same result.



WORKED EXAMPLE 1 Adding whole numbers


If $11 + 5 = 16$, what does $5 + 11$ equal?

THINK	WRITE
If $11 + 5 = 16$, then swapping the position of the numbers around will give the same result.	$5 + 11 = 16$


- Larger numbers can be added in columns. One number is written below the other number, as shown below. The numbers are lined up so that digits with the same place value are underneath each other.

$$\begin{array}{r} 24 \\ +\ 14 \\ \hline \end{array} \qquad \begin{array}{r} 167 \\ +\ 23 \\ \hline \end{array} \qquad \begin{array}{r} 49 \\ +35 \\ \hline \end{array}$$


1. Add the two numbers together in the last (ones) column first.



2. Move to the next column (tens column) and add all the numbers together in that column. Make sure you include any numbers that were carried over.



3. If there are no more columns to add, then the addition is finished. Otherwise, continue adding columns until completed.



WORKED EXAMPLE 2 Adding whole numbers in columns

Evaluate the following:

a. **45 + 53** **b.** **114 + 139**




THINK	WRITE
a. 1. Write one number below the other number in columns. Make sure the last two digits are lined up.	45 + 53
2. Add the numbers in each column, working right to left. Ones column: 5 + 3 = 8 Tens column: 4 + 5 = 9	45 + 53 98
3. Write the answer.	45 + 53 = 98
b. 1. Write one number below the other number in columns. Make sure the last two digits are lined up.	114 + 139
2. Add the numbers in each column, working right to left. Carry any tens over to the next column. This is written as a small 1 above the column.	1 1 114 + 139 253
3. Write the answer.	114 + 139 = 253

Subtracting whole numbers

- Subtracting means taking a number away from another number. A minus symbol (−) is used when subtracting numbers. Other names used for subtraction are take away, difference, minus, less and decrease.

We have five pink blocks at the start. If we subtract two pink blocks, we are left with three pink blocks. This is written as $5 - 2 = 3$.





Checking subtraction

- You can always check your subtraction by adding the two smaller numbers to see if you get the larger number.


Check whether $5 - 2 = 3$ is correct.

The two smaller numbers added together $(2 + 3)$ should equal the larger number (5).

$2 + 3 = 5$. Therefore, $5 - 2 = 3$ is correct.

WORKED EXAMPLE 3 Writing a subtraction statement from a diagram

What subtraction is this picture showing?





THINK	WRITE
1. Count how many blocks there are in total.	8
2. Count how blocks are being subtracted (crossed out).	3
3. Count how many blocks are left over.	5
4. Write the subtraction.	$8 - 3 = 5$

WORKED EXAMPLE 4 Evaluating a subtraction using a diagram

a. Draw a diagram showing $7 - 5$.

b. Calculate the value of $7 - 5$.

THINK	WRITE
a. 1. Draw 7 blocks, as this is the total number of blocks.	
2. Take away and cross out 5 blocks.	
b. Count the number of blocks left over from part a and state the answer.	Two blocks are left over. $7 - 5 = 2$

- Larger numbers can be subtracted in columns. Write the first number on top and then the second number below it and make sure the numbers are lined up so the last two digits in each number are underneath each other. The steps are shown below.

1. Line up columns	2. Subtract last column	3. Subtract first column	4. Answer
87 − 14	87 − 14 = 3 (7 − 4 = 3)	87 − 14 = 73 (8 − 1 = 7)	87 − 14 = 73



Q: What happens if we need to subtract but the digit on top is smaller than the digit underneath?

A: We need to borrow 10 from the next column.

1. Line up columns.

$$\begin{array}{r} 73 \\ -\ 16 \\ \hline \end{array}$$

2. Subtract last column. Need to borrow first.

$$\begin{array}{r} 73 \\ -\ 16 \\ \hline \end{array}$$

3 is less than 6.
We need to borrow
from the next column.

3. Rewrite numbers after borrowing. Subtract last column.

$$\begin{array}{r} 6\,13 \\ \cancel{7}\,3 \\ -\ 16 \\ \hline 7 \end{array}$$

3 is now 13
as we have borrowed
10 from the first column.
13 − 6 = 7

4. Subtract first column.

$$\begin{array}{r} 6 \\ \cancel{7}\,3 \\ -\ 16 \\ \hline 57 \end{array}$$

6 − 1 = 5

5. Answer

$$\begin{array}{r} 73 \\ -\ 16 \\ \hline 57 \end{array}$$

WORKED EXAMPLE 5 Subtracting whole numbers

Evaluate the following.

a. **68 – 32**

b. **1457 – 183**

THINK	WRITE
a. 1. Write the numbers in columns, aligning the digits according to place value.	$\begin{array}{r} 68 \\ -\ 32 \\ \hline \end{array}$
2. Subtract the two numbers in the ones column first. Ones: $8 - 2 = 6$	$\begin{array}{r} 6\ 8 \\ -\ 3\ 2 \\ \hline \end{array}$
3. Moving to the next column, subtract the two numbers in the tens column next. Tens: $6 - 3 = 3$	$\begin{array}{r} 6\ 8 \\ -\ 3\ 2 \\ \hline 3\ 6 \end{array}$
4. Write the answer	$68 - 32 = 36$
b. 1. Write the numbers in columns, aligning the digits according to place value.	$\begin{array}{r} 1457 \\ -\ 183 \\ \hline \end{array}$
2. Subtract each column, working right to left. • In the tens column, 5 is smaller than 8, so we cannot evaluate $5 - 8$. • Borrow from the next column by crossing out 4 and making it a 3. • Write the number 1 in front of 5, making it 15. • We can now calculate $15 - 8 = 7$ in the tens column.	$\begin{array}{r} {}^{3}\not{4}\ {}^{15}5\ 7 \\ -\ 1\ 8\ 3 \\ \hline 1\ 2\ 7\ 4 \end{array}$
3. Write the answer	$1457 - 183 = 1274$

Multiplying whole numbers

- Multiplication is the same as repeated additions.
- It can be thought of as 'counting by' a number of times.
- There are lots of strategies that can be used to help multiply numbers.




Multiplication

- Multiplication can also be called: product, times, of, lots of.
- The symbol used for multiplication is a cross: $\times$.
- When we multiply two numbers, the order does not matter.
  For example, 2×3 gives the same answer as 3×2.


Understanding multiplication

- Multiplication can be used to help simplify repeated additions in a simpler format.
- When multiplying single digit numbers, it can be useful to use blocks, counters or a diagram to help answer the problem.

Consider the 12 blocks shown.



Arranging these blocks into **2 groups of 6** would look something like the diagram at right.




The total amount of blocks can be thought of as:

- an addition: $6 + 6$
- a multiplication: '2 lots of 6' or 6×2.

So, 6 multiplied by 2 is the same as taking the number 6 and adding it 2 times:

$$6 \times 2 = 6 + 6 = 12$$

Arranging these blocks into **3 groups of 4** would look something like the diagram at right.



The total amount of blocks can be thought of as:

- an addition: $4 + 4 + 4$
- a multiplication: '3 lots of 4' or 4×3.


So, 4 multiplied by 3 is the same as taking the number 4 and adding it 3 times:

$$4 \times 3 = 4 + 4 + 4 = 12$$

Using some blocks, counters or a diagram, arrange 15 blocks into 3 groups of 5 and write the answer to the problem 5×3.

WORKED EXAMPLE 6 Evaluating a multiplication using a diagram

a. Draw a diagram to show 4 groups of 7.
b. State what 7×4 is equal to.

THINK	WRITE
a. Draw a diagram showing 4 groups of blocks, where each group has 7 blocks.	
b. 1. Count how many blocks there are altogether.	There are 28 blocks.
2. Write the answer.	$7 \times 4 = 28$

- The method shown above is useful for multiplying single digit numbers.
- When multiplying multi-digit numbers, other strategies are more useful.

Learning the multiplication tables (times tables)

- Once you understand that multiplication is used for representing repeated additions or adding equal groups, it is time to learn the times tables.
- The times tables are a summary of the answers when two numbers are multiplied together.
- Strategies for learning the patterns in the times tables are covered in Week 3: Thinking quickly in this topic.
- The table below shows the times tables up to and including 10.

×	**1**	**2**	**3**	**4**	**5**	**6**	**7**	**8**	**9**	**10**
1	1	2	3	4	5	6	7	8	9	10
2	2	4	6	8	10	12	14	16	18	20
3	3	6	9	12	15	18	21	24	27	30
4	4	8	12	16	20	24	28	32	36	40
5	5	10	15	20	25	30	35	40	45	50
6	6	12	18	24	30	36	42	48	54	60
7	7	14	21	28	35	42	49	56	63	70
8	8	16	24	32	40	48	56	64	72	80
9	9	18	27	36	45	54	63	72	81	90
10	10	20	30	40	50	60	70	80	90	100

Multiplying a number by a single-digit number

- We will investigate different strategies for multiplying larger numbers.
- It is important that you spend time learning your times tables and continue to practice them.

Multiplying using the long-multiplication algorithm

- The long-multiplication algorithm is a method that helps you multiply larger numbers.
- It only needs knowledge of up to and including the ten times tables.

Consider the problem 132×6

1. Arrange the two numbers in columns, placing:
   - the digits in the ones column underneath each other.
   - the digits in the tens column underneath each other.
   - the digits in the hundreds column underneath each other and so on.

   Important: The larger number should be written on top.

$$\begin{array}{rrr} 1 & 3 & 2 \\ \times & & 6 \\ \hline \end{array}$$

2. Starting from the digit in the ones column of the smaller number, multiply it by each of the digits in the larger number. $2 \times 6 = 12$, so write the 2 below the line and carry the 1 into the next column.

$$\begin{array}{rrr} 1 & {}^{1}3 & 2 \\ \times & & 6 \\ \hline & & 2 \end{array}$$

3. $3 \times 6 = 18$ but we need to **add** the 1 we carried over, so $18 + 1 = 19$. Write the 9 below the line and carry the 1 into the next column.

$$\begin{array}{rrr} {}^{1}1 & {}^{1}3 & 2 \\ \times & & 6 \\ \hline & 9 & 2 \end{array}$$

4. $1 \times 6 = 6$ but we need to **add** the 1 we carried over, so $6 + 1 = 7$.
   Write the 7 below the line.

$$\begin{array}{rccc} & {}^{1}1 & {}^{1}3 & 2 \\ \times & & & 6 \\ \hline & 7 & 9 & 2 \end{array}$$

5. We can now write the answer. $132 \times 6 = 792$

- We can apply this algorithm to any multiplication problem.

Multiplying using expanded form

- Recall that writing a number in expanded form means breaking the number up into units, tens, hundreds, thousands and so on.
  For example, the expanded form of $321 = 300 + 20 + 1$ and $1725 = 1000 + 700 + 20 + 5$.

Multiplying using expanded form

We can multiply numbers by writing the larger number in expanded form first, and then multiplying each component by the smaller number.

Consider the multiplication problem 68×4.

1. Write the larger number in expanded form first. $68 = 60 + 8$
2. Multiply each component by 4 and evaluate.
$$\begin{aligned} 68 \times 4 &= (60 \times 4) + (8 \times 4) \\ &= 240 + 32 \\ &= 272 \end{aligned}$$
3. Write the answer. $68 \times 4 = 272$

Consider the multiplication problem 127×3.

1. Write the larger number in expanded form first. $127 = 100 + 20 + 7$
2. Multiply each component by 3 and evaluate.
$$\begin{aligned} 127 \times 3 &= (100 \times 3) + (20 \times 3) + (7 \times 3) \\ &= 300 + 60 + 21 \\ &= 381 \end{aligned}$$
3. Write the answer. $127 \times 3 = 381$

Consider the multiplication problem 1348×6.


1. Write the larger number in expanded form first. $1348 = 1000 + 300 + 40 + 8$
2. Multiply each component by 6 and evaluate.
$$\begin{aligned} 1348 \times 6 &= (1000 \times 6) + (300 \times 6) + (40 \times 6) + (8 \times 6) \\ &= 6000 + 1800 + 240 + 48 \\ &= 8088 \end{aligned}$$
3. Write the answer. $1348 \times 6 = 8088$

Multiplying using an area model

- An area model can be used to help multiply large numbers.
- It involves displaying the multiplication problem as the area of a rectangle.
- We then break the rectangle into smaller chunks to make the multiplication easier.

Consider the multiplication problem 256×3.

1. Firstly, show the problem as the area of a rectangle.



2. Using the expanded form of the larger number, split the rectangle into smaller pieces.

$256 = 200 + 50 + 6$



3. Next, multiply to calculate the area of each smaller rectangle.



4. Last, add the products to calculate the area of the original rectangle.

$600 + 150 + 18 = 768$

5. We can now answer the original problem.

$256 \times 3 = 768$

Multiplying a number by a double-digit number

- When we are multiplying a two-digit number by a two-digit number, we need to remember to add 0 in the second row (as shown in Step 2 below).
- We do this because when we are multiplying by a digit from the tens column, we are multiplying by a multiple of 10.

  Let us look at calculating 43×18.
- In Step 2, when multiplying 1 by 43, we are really calculating 10×43 since 1 is in the tens position. $10 \times 43 = 430$, so this is why we must add 0 in the second row.

1.
$$\begin{array}{r} {\scriptstyle 2} \\ 43 \\ \times\ 18 \\ \hline 344 \end{array}$$

1. Multiply $8 \times 3 = 24$
   Write the 4 and carry the 2.
2. Multiply $8 \times 4 + 2 = 34$

2.
$$\begin{array}{r} 43 \\ \times\ 18 \\ \hline 344 \\ 430 \end{array}$$

Write 0 in the second row.

Multiply 43 by 1.
1. Multiply $1 \times 3 = 3$
2. Multiply $1 \times 4 = 4$

3.
$$\begin{array}{r} 43 \\ \times\ 18 \\ \hline 344 \\ 430 \\ \hline 774 \end{array}$$

Add 344 and 430 in columns.
$43 \times 18 = 774$

4. Final answer:
$43 \times 18 = 774$

WORKED EXAMPLE 7 Multiplying whole numbers

Evaluate 287×23.

THINK	WRITE
1. Arrange the two numbers in columns, placing: • the digits in the ones column underneath each other. • the digits in the tens column underneath each other. • the digits in the hundreds column underneath each other and so on. **Important:** The larger number should be written on top.	$\begin{array}{rrr} 2 & 8 & 7 \\ \times & 2 & 3 \\ \hline \end{array}$
2. i. Starting from the digit in the ones column of the smaller number, multiply it by each of the digits in the larger number. $7 \times 3 = 21$, so write the 1 below the line and carry the 2 into the next column.	$\begin{array}{rrr} 2 & {}^{2}8 & 7 \\ \times & 2 & 3 \\ \hline & & 1 \end{array}$
ii. $8 \times 3 = 24$ but we need to **add** the 2 we carried over, so $24 + 2 = 26$. Write the 6 below the line and carry the 2 into the next column.	$\begin{array}{rrr} {}^{2}2 & {}^{2}8 & 7 \\ \times & 2 & 3 \\ \hline & 6 & 1 \end{array}$
iii. $2 \times 3 = 6$ but we need to **add** the 2 we carried over, so $6 + 2 = 8$. Write the 8 below the line.	$\begin{array}{rrr} {}^{2}2 & {}^{2}8 & 7 \\ \times & 2 & 3 \\ \hline 8 & 6 & 1 \end{array}$
3. i. Starting from the digit in the tens column of the smaller number, multiply it by each of the digits in the larger number. **Important:** Because we have moved into the tens column of the smaller number, place a zero in the ones column (as shown in plum). This allows us to start in the tens column. $7 \times 2 = 14$, so write the 4 below the line and carry the 1 into the next column.	$\begin{array}{rrr} 2 & {}^{1}8 & 7 \\ \times & 2 & 3 \\ \hline 8 & 6 & 1 \\ & 4 & \mathbf{0} \end{array}$
ii. $8 \times 2 = 16$ but we need to **add** the 1 we carried over, so $16 + 1 = 17$. Write the 7 below the line and carry the 1 into the next column.	$\begin{array}{rrr} {}^{1}2 & {}^{1}8 & 7 \\ \times & 2 & 3 \\ \hline 8 & 6 & 1 \\ 7 & 4 & 0 \end{array}$
iii. $2 \times 2 = 4$ but we need to **add** the 1 we carried over, so $4 + 1 = 5$. Write the 5 below the line.	$\begin{array}{rrrr} & {}^{1}2 & {}^{1}8 & 7 \\ \times & & 2 & 3 \\ \hline & 8 & 6 & 1 \\ 5 & 7 & 4 & 0 \end{array}$
4. Add the two results together, starting from the ones columns and moving left.	$861 + 5740 = 6601$
5. Write the answer.	$287 \times 23 = 6601$

Dividing whole numbers

- Division involves splitting something into equal parts or groups.
- It can be thought of as 'sharing equally'.
- Commonly used symbols for division are ÷, /, $\frac{\square}{\square}$ and $\overline{)\ \ }$.

If a fruit and nut cake is cut into 8 equally sized portions and is to be shared between 4 people, how many pieces will each person get?



THINK

8 pieces of cake divided into 4 equal parts means that each person will get 2 pieces.

This can be written mathematically as:

$8 \div 4 = 2$ or $\frac{8}{4} = 2$

If a fruit and nut cake is cut into 8 equally sized portions and is to be shared between 2 people, how many pieces will each person get?



THINK

8 pieces of cake divided into 2 equal parts means that each person will get 4 pieces.

This can be written mathematically as:

$8 \div 2 = 4$ or $\frac{8}{2} = 4$

Checking division

- Division and multiplication are opposite operations; that is, division undoes multiplication.
- This means that division can always be checked by multiplying.

So if $4 \times 2 = 2 \times 4 = 8$

then $8 \div 2 = 4$

or $8 \div 4 = 2$.

- The times tables can also be used to help answer a division problem.

×	1	2	3	4	5
1	1	2	3	4	5
2	2	4	6	8	10
3	3	6	9	12	15
4	4	8	12	16	20
5	5	10	15	20	25
6	6	12	18	24	30
7	7	14	21	28	35
8	8	16	24	32	40
9	9	18	27	36	45
10	10	20	30	40	50

- There are special names for each number in a division.
  - The number which we divide is called the **dividend**.
  - The number by which we divide is called the **divisor**.
  - The result obtained is called the **quotient**.
  - The number left over (if any) is called the **remainder**.

  For example,

$$8 \div 2 = 4 \qquad \frac{8}{2} = 4 \qquad 2\overline{)8}\,4$$

$$\text{dividend} \div \text{divisor} = \text{quotient} \qquad \frac{\text{dividend}}{\text{divisor}} = \text{quotient} \qquad \text{divisor}\overline{)\text{dividend}}\ \text{quotient}$$


- When we need to divide large numbers, there are a few different methods we can use.

Using skip-counting to divide

- Division without remainder can be visualised using skip-counting.

  For example, 0, 2, 4, 6, 8, ...

  Count in 2s until you reach 8.



  We have added four lots of the number 2 to reach 8; therefore $8 \div 2 = 4$.

Using expanded form to divide

We can divide numbers by writing the larger number in expanded form first and then dividing each component by the smaller number.

Consider the division problem $84 \div 4$.

1. Write the larger number in expanded form first. $84 = 80 + 4$
2. Divide each component by 4 and evaluate.
$$\begin{aligned} 84 \div 4 &= (80 \div 4) + (4 \div 4) \\ &= 20 + 1 \\ &= 21 \end{aligned}$$
3. Write the answer. $84 \div 4 = 21$
4. Check using multiplication. $21 \times 4 = 84$ ✓

- We can use this method to divide larger numbers as well.

Consider the division problem $396 \div 3$.

1. Write the larger number in expanded form first. $396 = 300 + 90 + 6$
2. Divide each component by 3 and evaluate.
$$\begin{aligned} 396 \div 3 &= (300 \div 3) + (90 \div 3) + (6 \div 3) \\ &= 100 + 30 + 2 \\ &= 132 \end{aligned}$$
3. Write the answer. $396 \div 3 = 132$
4. Check using multiplication. $132 \times 3 = 396$ ✓

Dividing with remainder

- Sometimes we cannot divide things up evenly.
- When this happens there will be something left over, and this is known as the **remainder**.

For example, there are 7 bones to share between two puppies.

Seven cannot be divided exactly into 2 groups, so each puppy gets 3 bones and there is **1 left over**.



We can write this as $7 \div 2 = 3$ r 1.

The division algorithm (short division)

- Short division is a quick and effective method for working out division with larger numbers.
- The short division algorithm does not show all the steps, it only shows the carried numbers.
- It is best to use the $\overline{)}$ layout when completing short division.
- An example of the algorithm is demonstrated below.



Consider $184 \div 4$

1. Rewrite the problem using $\overline{)}$ — $4\overline{)184}$
2. 4 into 1 does not go. (Place a 0 on top of the 1.) — $4\overline{)\,0\;184}$
3. 4 into 18 goes 4 times, remainder 2. (Place a 4 on top of the 8 and carry the 2 over to the next number) — $4\overline{)\,0\;4\;1\;8^{2}4}$
4. 4 into 24 goes 6 times, remainder 0. (Place a 6 on top of the 4.) — $4\overline{)\,0\;4\;6\;1\;8^{2}4}$
5. Write the answer. — $184 \div 4 = 46$

Consider another division problem, $5176 \div 7$

1. Set out the problem correctly. — $7\overline{)5\;\;1\;\;7\;\;6}$
2. 7 into 5 does not go.
   7 into 51 goes 7 times, remainder 2.
   7 into 27 goes 3 times, remainder 6.
   7 into 66 goes 9 times, remainder 3. — $7\overline{)\,\;\;7\;\;3\;\;9\;\;\text{r}\,3\;\;5\;\;1\;\;{}^{2}7\;\;{}^{6}6}$
3. Write the answer. — $5176 \div 7 = 739$ remainder 3

WORKED EXAMPLE 8 Dividing whole numbers

Evaluate the following:

a. **$1112 \div 4$** **b.** **$9831 \div 8$**

THINK

a. 1. Set up the problem using the $\overline{)}$ symbol.

2. Divide each digit inside the $\overline{)}$ symbol by 4, making sure you insert any carried numbers.
4 into 1 does not go.
4 into 11 goes 2 times, remainder 3.
4 into 31 goes 7 times, remainder 3.
4 into 32 goes 8 times, remainder 0.

3. Write the answer.

b. 1. Set up the problem using the $\overline{)}$ symbol.

WRITE

a. $4\overline{)1\;\;1\;\;1\;\;2}$

$4\overline{)\,\;\;2\;\;7\;\;8\;\;1\;\;{}^{3}1\;\;{}^{3}2}$

$1112 \div 4 = 278$

b. $8\overline{)9\;\;8\;\;3\;\;1}$

2. Divide each digit inside the ⟌ symbol by 8, making sure you insert any carried numbers.
   8 into 9 goes 1 time, remainder 1.
   8 into 18 goes 2 times, remainder 2
   8 into 23 goes 2 times, remainder 7.
   8 into 71 goes 8 times, remainder 7.

$$\begin{array}{r} 1\ \ 2\ \ 2\ \ 8\ \text{r}\ 7 \\ 8\overline{)9\ \ {}^{1}8\ \ {}^{2}3\ \ {}^{7}1} \end{array}$$

3. Write the answer.

$9831 \div 8 = 1228$ remainder 7

Week 2 Exercise: Numbering up

1. **WE1** State whether the following are true or false.
   a. $3 + 4 = 4 + 3$ b. $5 + 6 + 1 = 1 + 5 + 6$ c. $4 + 8 + 11 = 12 + 11$
2. **WE2** Evaluate each of the following.
   a. $24 + 56$ b. $342 + 59$ c. $1945 + 345$
3. **MC** Which of the following gives the correct answer for $503 + 717$?
   A. 1210 B. 214 C. 1201
   D. 1220 E. 1222
4. **WE5** Evaluate each of the following.
   a. $65 - 22$ b. $79 - 42$ c. $187 - 65$
5. Evaluate each of the following.
   a. $76 - 48$ b. $90 - 24$ c. $153 - 47$
6. State whether the following are true or false.
   a. $147 - 79 = 78$ b. $543 - 98 = 445$ c. $1465 - 775 = 790$
7. Evaluate the following.
   a. $56 + 123 - 91$ b. $578 - 143 + 231$
8. **WE6** Answer the following questions.
   a. Represent 4×3 as a diagram.
   b. Use the diagram to calculate 4×3.
9. Calculate 315×4 by breaking the larger number up into expanded form.
10. **WE7a** Evaluate the following.
    a. 56×9 b. 623×6 c. 108×3
11. **WE7b** Evaluate the following.
    a. 62×31 b. 93×18
12. Answer the following questions.
    a. Use an area model to show 123×6.
    b. Using the model, calculate 123×6.

13. State whether the following are true or false.

a. $81 \div 3 = 26$ **b.** $243 \div 9 = 27$

14. WE8a Evaluate the following.

a. $171 \div 9$ **b.** $264 \div 8$

15. WE8b Evaluate the following.

a. $597 \div 7$ **b.** $302 \div 4$

16. Calculate $1384 \div 4$ by breaking 1384 up into expanded form.

17. State whether the following are true or false.

a. $30 \times 3 > 18 \times 5$ **b.** $98 \div 2 < 75 \div 3$

18. Circle the larger number.
$327 + 98$ or $287 + 133$

19. A shop owner sells 84 bananas each day. Calculate the number of bananas sold in 2 weeks.

20. Lisa has saved up money from her last three birthdays. The amounts are \$45, \$53 and \$31.



a. Calculate the total money Lisa has saved.
b. She wishes to purchase an item for \$58. Calculate how much money will Lisa have left over after the purchase.

21. Answer the following questions.

a. State the difference between 98 and 64.
b. State the sum of 98 and 64.

22. A total of 145 students are going on an excursion by bus. Each bus can hold 40 students.




a. Calculate the number of buses required to fit all the students.
b. Determine the number of spare seats.

23. A school has eight Year 7 classes, with 26 students in each class. Calculate the total number of students in Year 7.

24. Mila says the product of 51 and 37 is 1887 while her friend Kafeel calculated the answer to be 1507. Explain who calculated the correct answer: Mila or Kafeel.

25. Determine the product of 8, 17 and 3.

Week 3: Thinking quickly




Essential ideas for addition

- Before looking at some of the mental strategies used to add numbers together, there are four essential ideas, outlined below, that should be understood and mastered.

Addition on the number line

- A number line provides a picture to aid in understanding addition.
- Each addition is a jump to the right.

3 + 9 = 12 is shown on the number line.



Tens complement

- Looking for numbers that add to 10 or a multiple of 10 can help when adding larger numbers.
- Understanding of the tens complement is an essential part of other mental strategies.
  Recall:

$$10 = 0 + 10 = 1 + 9 = 2 + 8 = 3 + 7 = 4 + 6 = 5 + 5 = 6 + 4 = 7 + 3 = 8 + 2 = 9 + 1 = 10 + 0$$

The commutative and associative laws for addition

- The commutative law for addition states that numbers can be added in any order.
  For example,
  $7 + 4 = 4 + 7$
- The associative law for addition states that when adding it doesn't matter how we group the numbers.
  For example,
  $(2 + 6) + 13 = 2 + (6 + 13)$
  $= (2 + 13) + 6$

Decomposition



- Decomposition involves breaking a number up into smaller parts. This can help add numbers by looking for patterns.
- Most numbers can be written as an addition involving smaller numbers.
- When decomposing a number, try to include a number ending in a 0 or 5 or identify the tens complements.
  For example, the number 17 can be decomposed in many ways.
  Two examples are:
  $17 = 10 + 7$
  $17 = 15 + 2$

Mental strategies for addition


- Mental strategies for addition offer different ways of adding numbers together without the use of a calculator.
- Some mental strategies are more useful than others depending on the numbers used.
- There are many words that mean addition, such as *add, plus, put together with* and *sum*.
- The symbol used for addition is +.

Jump strategy for addition

- The jump strategy involves breaking the number being added into smaller parts (decomposition). For example,

Break 8 into 2 and 6.	$38 + 8 = 38 + 2 + 6$
Recognise the tens complement and add 2 to 38 to get 40.	$= 40 + 6$
Add the final two numbers together.	$= 46$

- On the number line, this corresponds to jumping to the first number, then jumping to the nearest ten above it, then jumping the rest of the way.



Below are three different ways to calculate $143 + 89$ using the jump strategy.

Method 1:

Break 89 into 82 and 7.	$143 + 89 = 143 + 80 + 7$
Recognise the tens complement and add 7 to 143 to get 150.	$= 150 + 82$
Add 82 to 150 to get 232.	$= 232$

Method 2:

Break 89 into 80, 7 and 2.	$143 + 89 = 143 + 80 + 7 + 2$
Recognise the tens complement and add 7 to 143 to get 150.	$= 150 + 80 + 2$
Add 80 to 150 to get 230.	$= 230 + 2$
Add 2 to 230 to get 232.	$= 232$

Method 3:

Break 89 into 80 and 9.	$143 + 89 = 143 + 80 + 9$
Add 80 to 143 to get 223.	$= 223 + 9$
Add 9 to 223 to get 232.	$= 232$

Note: There will always be many ways to decompose a number. The choice of numbers depends on your ability to skip count.

Split strategy for addition

- The split strategy involves splitting both numbers being added into expanded form first, then adding the parts with the same place value.

For example, to add 236 + 149 using the split strategy:

1. Split 236 into 2 hundreds, 3 tens and 6 ones.	$236 = 200 + 30 + 6$
2. Split 149 into 1 hundred, 4 tens and 9 ones.	$149 = 100 + 40 + 9$
3. Rewrite the addition using expanded form.	$236 + 149 = 200 + 30 + 6 + 100 + 40 + 9$
4. Rearrange the addition so that numbers with the same place value are next to each other.	$= 200 + 100 + 30 + 40 + 6 + 9$
5. Add the numbers with the same place value.	$= 300 + 70 + 15$
6. Add the numbers with the same place value again due to carry with the ones.	$= 300 + 85$
7. Add the final two numbers together.	$= 385$

WORKED EXAMPLE 1 Using the jump and split strategy to add numbers

a. Calculate 674 + 167 using the jump strategy.
b. Calculate 546 + 398 using the split strategy.

THINK	WRITE
a. 1. Write the question.	$674 + 167 =$
2. Break 167 into 6 + 161.	$= 674 + 6 + 161$
3. Recognise the tens complement.	$= 680 + 161$
4. Add the final two numbers.	$= 841$
5. Write the answer.	$674 + 167 = 841$
b. 1. Write the question.	$546 + 398 =$
2. Split each number up by writing it in expanded form.	$546 = 500 + 40 + 6$ $398 = 300 + 90 + 8$
3. Add the numbers with the same place value together.	$500 + 300 + 40 + 90 + 6 + 8$ $= 800 + 130 + 14$ $= 930 + 14$ $= 944$
4. Write the answer.	$546 + 398 = 944$

Compensation strategy for addition

- The compensation strategy for addition involves rounding up one of the numbers being added to the nearest ten, hundred, thousand, and so on, and then *subtracting* the added amount.

For example, to determine 214 + 59:

1. Round the 59 up to 60 by adding 1.	$214 + 60$
2. Add the numbers together.	$= 274$
3. Subtract 1 from the answer (the amount that was added at the start).	$274 - 1$
4. This is the answer.	$= 273$ $\therefore 214 + 59 = 273$

Rearrange strategy for addition

- This involves rearranging the numbers being added to form numbers that add up to multiples of 10 – it is an extension of the tens complement.

For example:

Swap the order of the numbers and add 21 and 19 first, as this gives a multiple of 10.

$$\begin{aligned} 21 + 33 + 19 &= 21 + 19 + 33 \\ &= 40 + 33 \\ &= 73 \end{aligned}$$

WORKED EXAMPLE 2 Using the compensation and rearrange strategy to add numbers

a. Calculate 274 + 97 using the compensation strategy.
b. Calculate 11 + 16 + 39 using the rearrange strategy.

THINK	WRITE
a. 1. Write the question.	$274 + 97 =$
2. Round 97 up to 100 by adding 3.	$274 + 100$
3. Add the numbers together.	$= 374$
4. Subtract 3 from this answer to compensate for the addition of 3.	$374 - 3$ $= 371$
5. Write the answer.	$274 + 97 = 371$
b. 1. Write the question.	$11 + 16 + 39 =$
2. Rearrange the numbers so that a multiple of 10 can be formed.	$= 11 + 39 + 16$ $= 50 + 16$
3. Add these numbers first.	$= 66$
4. Add 16 to 50.	
5. Write the answer.	$11 + 16 + 39 = 66$

WORKED EXAMPLE 3 Using mental strategies to add numbers

Calculate 673 + 178 using an appropriate mental strategy.

THINK	WRITE
1. Write the question.	$673 + 178$
2. Select a strategy. Since the numbers are both large, it may be easier to split them up	Use the split strategy.
3. Use the strategy to add numbers.	
i. Write both numbers in expanded form.	$673 = 600 + 70 + 3$ $178 = 100 + 70 + 8$
ii. Add numbers with the same place value.	$600 + 100 + 70 + 70 + 3 + 8$
iii. Complete the addition.	$= 700 + 140 + 11$ $= 840 + 11$ $= 851$
4. Write the answer.	$673 + 178 = 851$


Mental strategies for subtraction

- Mental strategies for subtraction offer different ways of subtracting numbers without the use of a calculator or the algorithm.
- Some mental strategies are more useful than others depending on the numbers used.
- There are many words that mean subtraction, such as *take away, minus, subtract* and *difference*.
- The symbol used for subtraction is −.

Subtraction on the number line

- The number line provides a picture to aid in understanding subtraction.
- A subtraction can be thought of as a jump to the left on the number line.


For example, for $18 - 11 = 7$ we start at the number 18, and take a jump of 11 to the left.



Subtraction as difference

- Another way to think about subtraction is the difference between the size of two collections.
- Consider the following problem: What is the difference between 18 and 11?

Line up 18 counters and then line up 11 counters, placing them directly below one another.



We can see that there is a difference of 7 squares between 18 and 11.

We say that the difference between 18 and 11 is 7.

Subtraction by equal addition

- By adding the same amount to both numbers, you can make the problem easier.
  For example,
  $87 - 39 = 88 - 40 = 48$
  We added 1 to both 87 and 39 to make the calculation easier.


Jump strategy for subtraction

- The jump strategy for subtraction is similar to the strategy used for addition, but we will jump to the **left**.
- The number being subtracted is broken (decomposed) into smaller parts and then each part is subtracted.
  For example:

1. Break 77 into 4, 70 and 3.
2. Subtract 4 from 134 first to get 130.
3. Subtract 70 from 130 to get 60.
4. Complete the final subtraction.

$$134 - 77 = 134 - 4 - 70 - 3$$
$$= 130 - 70 - 3$$
$$= 60 - 3$$
$$= 57$$





A different decomposition could be used:

Break 77 into 70 and 7.	$134 - 77 = 134 - 70 - 7$
Subtract 70 from 134 first to get 64.	$= 64 - 7$
Subtract 7 from 64 to get 57.	$= 57$

Adding up the difference

- Subtraction can also be calculated by using complementary addition.
  For example, to determine $74 - 39$ we can ask: what do you need to add to 39 in order to get 74?

  $39 + 1 = 40$
  $40 + 34 = 74$

  The total amount added to 39 was 35, so we can say that $74 - 39 = 35$.

  Even with larger numbers this method can be an effective way to calculate a subtraction.
  For example, to determine $763 - 389$, ask: what do you need to add to 389 in order to get 763?

  $389 + 11 = 400$
  $400 + 363 = 763$

  The total amount added to 389 was 374 $(11 + 363)$, so we can say that $763 - 389 = 374$.

WORKED EXAMPLE 4 Using mental strategies to subtract numbers

a. Calculate 937 – 253 using the jump strategy.
b. Calculate 461 – 182 using the adding up the difference strategy.

THINK	WRITE
a. 1. Write the question.	$937 - 253$
2. Break 253 into 200 plus 53.	$253 = 200 + 53$
3. Subtract 200 from 937.	$937 - 200 = 737$
4. Subtract 53 from 737. If this subtraction is too difficult, you can break up the 53 into smaller parts.	$737 - 53 = 684$ Alternatively, $737 - 53 = 737 - 50 - 3$ $= 687 - 3$ $= 684$
5. Write the answer.	$937 - 253 = 684$
b. 1. Write the question.	$461 - 182$
2. Starting with the smaller number, determine what needs to be added to 182 in order to get 461.	$182 + 8 = 190$ $190 + 10 = 200$ $200 + 200 = 400$ $400 + 61 = 461$
3. Add up all the parts.	$8 + 10 + 200 + 61 = 279$
4. Write the answer.	$461 - 182 = 279$

Compensation strategy for subtraction

- The compensation strategy for subtraction involves rounding up the number being subtracted to the nearest ten, hundred, thousand and so on, and then *adding on* whatever amount was rounded up.
  For example, to determine 223 – 74:

1. Round the 74 up to 80 by adding 6.	223 – 80
2. Subtract the numbers.	= 143
3. Add 6 to this number (this is the amount needed to round 74 up to 80).	143 + 6
4. This is the answer.	= 149
	∴ 223 – 74 = 149

WORKED EXAMPLE 5 Using the compensation strategy to subtract

Calculate 254 – 36 using the compensation strategy.

THINK	WRITE
1. Write the question.	254 – 36
2. Round the 36 up to the nearest 10 by adding 4.	36 + 4 = 40
3. Subtract 40 from 254.	254 – 40 = 214
4. Add 4 to this result since 36 was rounded up to 40.	214 + 4 = 218
5. Write the answer.	254 – 36 = 218



The relationship between subtraction and addition

Because subtraction is the inverse operation to addition, we can check our answer to any subtraction problem by:

- adding the two smaller numbers to see if they add up to the larger number.
  For example, if 254 – 36 = 218, then 218 + 36 should equal 254 (which it does).

Learning the 2, 5 and 10 times tables

- Multiplication tables or times tables have a lot of patterns that can help us when we need to multiply. We will investigate the patterns and tricks to help us learn the 2, 5 and 10 times tables.

Skip counting

- Skip counting is counting by a number that is not 1.
- Learning to skip count can help learn the times tables.
- We can skip count by any number.

Skip counting by 2

- Skip counting by 2 involves adding by 2 to get to the next number.
  For example, starting at 2 and counting by 2s, we have:

$$2, 4, 6, 8, 10, 12, 14, 16, 18, 20, 22, 24, ...$$

Skip counting by 5

- Skip counting by 5 involves adding by 5 to get to the next number.
  For example, starting at 5 and counting by 5s, we have:

$$5, 10, 15, 20, 25, 30, 35, 40, 45, 50, 55, 60, ...$$

Skip counting by 10

- Skip counting by 10 involves adding by 10 to get to the next number.
  For example, starting at 10 and counting by 10s, we have:

$$10, 20, 30, 40, 50, 60, 70, 80, 90, 100, 110, 120, ...$$

- Using skip counting, we have listed the 2, 5 and 10 times tables.
- Do you notice any patterns which may be helpful to remember? Let us look at the 2, 5 and 10 times tables.

The 2 times table

- All the numbers are even.
- The numbers all end in 0, 2, 4, 6 and 8.
- Multiplying by 2 is the same as doubling the number.

$$\begin{aligned}
2 \times 1 &= 2 \\
2 \times 2 &= 4 \\
2 \times 3 &= 6 \\
2 \times 4 &= 8 \\
2 \times 5 &= 10 \\
2 \times 6 &= 12 \\
2 \times 7 &= 14 \\
2 \times 8 &= 16 \\
2 \times 9 &= 18 \\
2 \times 10 &= 20 \\
2 \times 11 &= 22 \\
2 \times 12 &= 24
\end{aligned}$$



The 5 times table

- All the numbers end in 0 or 5.

$5 \times 1 = 5$
$5 \times 2 = 10$
$5 \times 3 = 15$
$5 \times 4 = 20$
$5 \times 5 = 25$
$5 \times 6 = 30$
$5 \times 7 = 35$
$5 \times 8 = 40$
$5 \times 9 = 45$
$5 \times 10 = 50$
$5 \times 11 = 55$
$5 \times 12 = 60$



The 10 times table

- All the numbers end in 0.
- When multiplying by 10, simply place 0 after the number, e.g. $10 \times 3 = 30$.

$10 \times 1 = 10$
$10 \times 2 = 20$
$10 \times 3 = 30$
$10 \times 4 = 40$
$10 \times 5 = 50$
$10 \times 6 = 60$
$10 \times 7 = 70$
$10 \times 8 = 80$
$10 \times 9 = 90$
$10 \times 10 = 100$
$10 \times 11 = 110$
$10 \times 12 = 120$



WORKED EXAMPLE 6 Multiplying using skip counting

Use skip counting to work out the following:
a. 2×6 **b.** 5×7 **c.** 10×8

THINK	WRITE
a. 1. Starting at 0, count by 2 s a total of six times.	0, 2, 4, 6, 8, 10, 12
2. Write the answer.	$2 \times 6 = 12$
b. 1. Starting at 0, count by 5 s a total of seven times.	0, 5, 10, 15, 20, 25, 30, 35
2. Write the answer.	$5 \times 7 = 35$

c. 1.	Starting at 0, count by 10 s a total of eight times.	0, 10, 20, 30, 40, 50, 60, 70, 80
2.	Write the answer.	$10 \times 8 = 80$

WORKED EXAMPLE 7 Using patterns to multiply

Use patterns to determine why these calculations are incorrect and write the correct answer.
a. $5 \times 6 = 31$ **b.** $2 \times 9 = 19$ **c.** $10 \times 4 = 45$

THINK		WRITE
a. 1.	Look at the pattern for the 5 times table and determine why $5 \times 6 = 31$ is incorrect.	The numbers in the 5 times table end in 5 or 0. Therefore $5 \times 6 = 31$ is not correct, as 31 does not end in 5 or 0.
2.	Write the correct answer.	$5 \times 6 = 30$
b. 1.	Look at the pattern for the 2 times table and determine why $2 \times 9 = 19$ is incorrect.	The numbers in the 2 times table end in 2, 4, 6, 8, or 0. Therefore $2 \times 9 = 19$ is not correct, as 19 does not end in 2, 4, 6, 8, or 0.
2.	Write the correct answer.	$2 \times 9 = 18$
c. 1.	Look at the pattern for the 10 times table and determine why $10 \times 4 = 45$ is incorrect.	All numbers in the 10 times table end in 0. Therefore $10 \times 4 = 45$ is not correct, as 45 does not end in 0.
2.	Write the correct answer.	$10 \times 4 = 40$

Strategies for learning other times tables

- We have looked at patterns for the 2, 5 and 10 times tables. Now let us consider some other times tables and see if there are any patterns or tricks we can use to learn them.

The 3 times table

- A useful way to remember the 3 times table is to use your knowledge of the 2 times table.
- A number multiplied by 3 = the number $\times 2$ + the number

For example:

$1 \times 3 = (1 \times 2) + 1 = 2 + 1 = 3$
$2 \times 3 = (2 \times 2) + 2 = 4 + 2 = 6$
$3 \times 3 = (3 \times 2) + 3 = 6 + 3 = 9$
$4 \times 3 = (4 \times 2) + 4 = 8 + 4 = 12$
$5 \times 3 = (5 \times 2) + 5 = 10 + 5 = 15$
$6 \times 3 = (6 \times 2) + 6 = 12 + 6 = 18$
...

Using this pattern, we can easily recall and calculate the 3 times table.

$3 \times 1 = 3$
$3 \times 2 = 6$
$3 \times 3 = 9$
$3 \times 4 = 12$
$3 \times 5 = 15$
$3 \times 6 = 18$
$3 \times 7 = 21$
$3 \times 8 = 24$
$3 \times 9 = 27$
$3 \times 10 = 30$
$3 \times 11 = 33$
$3 \times 12 = 36$



The 4 times table

- The numbers form a pattern that ends in 4, 8, 2, 6, 0, 4, 8, 2, 6, 0, ...
- The four times table is simply the double of the 2 times table.
- To multiply a number by 4, you can simply double the number and then double that result.
  For example, to calculate 5×4, first calculate $5 \times 2 = 10$, then $10 \times 2 = 20$.
  It could also be written as shown below.

Double the number first

$5 \times 4 = (2 \times 5) \times 2$ ← Double the result
$= 10 \times 2$
$= 20$

$4 \times 1 = 4$
$4 \times 2 = 8$
$4 \times 3 = 12$
$4 \times 4 = 16$
$4 \times 5 = 20$
$4 \times 6 = 24$
$4 \times 7 = 28$
$4 \times 8 = 32$
$4 \times 9 = 36$
$4 \times 10 = 40$
$4 \times 11 = 44$
$4 \times 12 = 48$



The 6 times table

- The numbers form a pattern that ends in 6, 2, 8, 4, 0, 6, 2, 8, 4, 0, ...
- When 6 is multiplied by an even number, the result ends in the same digit as the number.
  For example:

$$6 \times 4 = 24$$
$$6 \times 6 = 36$$

- If you are familiar with the 5 times table, then:

  a number multiplied by 6 = the number × 5 + the number

$1 \times 6 = (1 \times 5) + 1 = 5 + 1 = 6$

$2 \times 6 = (2 \times 5) + 2 = 10 + 2 = 12$

$3 \times 6 = (3 \times 5) + 3 = 15 + 3 = 18$

$4 \times 6 = (4 \times 5) + 4 = 20 + 4 = 24$

$5 \times 6 = (5 \times 5) + 5 = 25 + 5 = 30$

$6 \times 6 = (6 \times 5) + 6 = 30 + 6 = 36$

...

$6 \times 1 = 6$
$6 \times 2 = 12$
$6 \times 3 = 18$
$6 \times 4 = 24$
$6 \times 5 = 30$
$6 \times 6 = 36$
$6 \times 7 = 42$
$6 \times 8 = 48$
$6 \times 9 = 54$
$6 \times 10 = 60$
$6 \times 11 = 66$
$6 \times 12 = 72$



The 8 times table

- The numbers form a pattern that ends in 8, 6, 4, 2, 0, 8, 6, 4, 2, 0, ...
- Multiplying by 8 is the same as *double, double* and *double* again.
  For example, to calculate 8×2*: double* 2 *is* 4, *double* 4 *is* 8, *and double* 8 *is* 16.

  Therefore, $8 \times 2 = 16$.

$8 \times 1 = 8$
$8 \times 2 = 16$
$8 \times 3 = 24$
$8 \times 4 = 32$
$8 \times 5 = 40$
$8 \times 6 = 48$
$8 \times 7 = 56$
$8 \times 8 = 64$
$8 \times 9 = 72$
$8 \times 10 = 80$
$8 \times 11 = 88$
$8 \times 12 = 96$



The ones digits form the pattern: 8, 6, 4, 2, 0 ...

8, 16, 24, 32, 40 ...

The tens digits form the pattern: 0, 1, 2, 3, 4, 5, 6, 7, 8, 8, 9 ...

8, 16, 24, 32, 40 ...

The 9 times table

- The ones digits form the pattern: 9, 8, 7, 6, 5, 4, 3, 2, 1, 0 ...

  9, 18, 27, 36, 45 ...

- The tens digits form the pattern: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 ...

  9, 18, 27, 36, 45 ...

- If you are familiar with the 10 times table, then:

  A number multiplied by 9 = the number $\times 10$ − the number

  For example:

$$\begin{aligned} 6 \times 9 &= (6 \times 10) - 6 \\ &= 60 - 6 \\ &= 54 \\ &\ldots \\ 8 \times 9 &= (8 \times 10) - 8 \\ &= 80 - 8 \\ &= 72 \\ &\ldots \\ 12 \times 9 &= (12 \times 10) - 12 \\ &= 120 - 12 \\ &= 108 \\ &\ldots \end{aligned}$$

$9 \times 1 = 9$
$9 \times 2 = 18$
$9 \times 3 = 27$
$9 \times 4 = 36$
$9 \times 5 = 45$
$9 \times 6 = 54$
$9 \times 7 = 63$
$9 \times 8 = 72$
$9 \times 9 = 81$
$9 \times 10 = 90$
$9 \times 11 = 99$
$9 \times 12 = 108$



The 11 times table

- The numbers form a pattern counting up from 1.

$$11,\ 22,\ 33,\ 44,\ 55$$

- From 11×1 up to 11×9, just repeat the number.

$$11 \times 2 = 22$$
$$11 \times 5 = 55$$

$11 \times 1 = 11$
$11 \times 2 = 22$
$11 \times 3 = 33$
$11 \times 4 = 44$
$11 \times 5 = 55$
$11 \times 6 = 66$
$11 \times 7 = 77$
$11 \times 8 = 88$
$11 \times 9 = 99$
$11 \times 10 = 110$
$11 \times 11 = 121$
$11 \times 12 = 132$



The matching pair trick

- Every multiplication has a matching pair.
- If you know one of the pairs then you automatically know the other.

For example, *If you know the answer to 2×7 then you also know the answer to 7×2.*
If you are uncertain of a multiplication, its matching pair might make it easier to work out the answer.

WORKED EXAMPLE 8 Multiplying numbers

Use any strategy to calculate:
a. 11×4 **b.** 8×7 **c.** 6×8

THINK	WRITE
a. 1. Write the question.	11×4
	$11 \times 4 = 44$
2. Use the 11 times table strategy — repeat the number. Or: Use the 4 times table strategy — double, then double again.	Double $11 = 22$ Double $22 = 44$
3. Write the answer.	$11 \times 4 = 44$

b. **1.** Write the question. 8×7

2. Use the 8 times table strategy — double, double and double again.
Double $7 = 14$
Double $14 = 28$
Double $28 = 56$

3. Write the answer. $8 \times 7 = 56$

c. **1.** Write the question. 6×8

2. Use the 6 times table strategy — multiply by 5, then add the number.
$8 \times 5 + 8 = 40 + 8$
$= 48$

Or:

2. Use the 8 times table strategy — double, double and double again.
Double $6 = 12$
Double $12 = 24$
Double $24 = 48$

3. Write the answer. $6 \times 8 = 48$

Week 3 Exercise: Thinking quickly

1. **WE1a** Use the jump strategy to calculate the following.
   a. $372 + 45$ **b.** $1196 + 528$
2. **WE1b** Use the split strategy to calculate the following.
   a. $422 + 319$ **b.** $670 + 88$
3. **WE2a** Use the compensation strategy to calculate the following.
   a. $506 + 49$ **b.** $67 + 48$
4. **WE2b** Use the rearrange strategy to calculate the following.
   a. $21 + 54 + 19$ **b.** $17 + 28 + 33$
5. State whether the following are true or false.
   $747 + 395$ calculated using the split strategy becomes $700 + 300 + 40 + 90 + 7 + 5$.
6. **MC** Select a number whose expanded form is $22 + 31 + 58$.
   A. 109 **B.** 110 **C.** 111
   D. 121 **E.** 144
7. **WE3** Calculate $820 + 71 + 334$ using an appropriate mental strategy.
8. **WE4a** Use the jump strategy to calculate the following.
   a. $95 - 62$ **b.** $649 - 415$
9. **WE4b** Add up the difference to calculate the following.
   a. $83 - 27$ **b.** $483 - 391$
10. **WE5** Use the compensation strategy to calculate the following.
    a. $63 - 49$ **b.** $941 - 618$
11. Calculate $953 - 675$ using an appropriate mental strategy.

12. MC Select a number whose expanded form is $199 + 544 - 361$.

A. 743 **B.** 1104 **C.** 706
D. 382 **E.** 687

13. Complete the following sentences.

a. All the numbers in the 10 times tables end in …….. .
b. The …… times tables all end in 0 or 5.

14. WE6 Use skip counting to calculate the following.

a. 2×9 **b.** 5×8

15. State whether the following are true or false.

a. The 6 times tables are all even numbers.
b. The 3 times tables are all odd numbers.

16. WE7 Use the patterns for the times tables to determine why these calculations are incorrect.

a. $5 \times 7 = 36$ **b.** $7 \times 8 = 54$

17. Calculate the following:

a. $4 \times 3 =$ **b.** $4 \times 7 =$ **c.** $4 \times 9 =$ **d.** $4 \times 12 =$

18. WE8 Calculate the following:

a. $9 \times 3 =$ **b.** $6 \times 9 =$ **c.** $9 \times 11 =$

19. MC 7×4 can be calculated by:

A. doubling 7 and doubling again
B. repeating the number 4
C. writing a 0 after the number 7
D. doubling 4 and doubling again
E. Adding 7 and 4

20. State whether the following are true or false.

a. $4 \times 7 = 28$ **b.** $6 \times 3 = 21$ **c.** $5 \times 8 = 55$

21. A student has shown the following working on a test.
$428 + 195 = 400 + 80 + 2 + 100 + 50 + 9 = 641$.

a. Explain where the student made the error.
b. Calculate the correct answer.

22. There are 746 students at a senior school campus. Of these, 314 students are currently completing exams. Calculate the number of students that are not completing exams.


23. Use skip counting to show that 4×5 and 5×4 equal the same number.

24. Matthew is sorting football cards into different teams. When he is finished, he counts that he has 7 groups with 8 cards in each. Calculate the number of cards Matthew has in total.



25. Harriet has $275 in savings. She adds $87 to her savings account. The next day she spends $191 from her account. Calculate the amount of money left in her savings account.

Week 4: Fishing for fractions



What are fractions?

- A **fraction** of an object is a piece or part of that object.
- Fractions are used to compare the size of a part of an object with the size of the whole object.
- The rectangle below has been divided into 5 equal parts.



If we shade 1 out of the 5 parts, we can say we have shaded one-fifth $\left(\frac{1}{5}\right)$ of the rectangle.



If we shade 2 out of the 5 parts, we can say we have shaded two-fifths $\left(\frac{2}{5}\right)$ of the rectangle.



If we shade 3 out of the 5 parts, we can say we have shaded three-fifths $\left(\frac{3}{5}\right)$ of the rectangle.



If we shade 4 out of the 5 parts, we can say we have shaded four-fifths $\left(\frac{4}{5}\right)$ of the rectangle.



If we shade 5 out of the 5 parts, we can say we have shaded five-fifths $\left(\frac{5}{5}\right)$ of the rectangle, or the whole rectangle.



WORKED EXAMPLE 1 Writing a fraction

Determine the fraction of the rectangle that has been shaded.






THINK	WRITE
1. Count the number of parts in the rectangle.	7 parts
2. Count the number of shaded parts in the rectangle.	3 shaded parts
3. Write this as a fraction (3 out of 7 parts).	$\frac{3}{7}$

WORKED EXAMPLE 2 Displaying a fraction visually

a. Draw a rectangle and divide it into 8 equal parts.

b. Shade parts of the rectangle to represent the fraction $\frac{5}{8}$.

THINK	WRITE
a. 1. Use a ruler to draw a rectangle.	
2. Divide the rectangle into 8 equal parts. (This can be drawn in lots of different ways.)	
b. 1. Write out the meaning of the fraction $\frac{5}{8}$.	$\frac{5}{8}$ means '5 out of 8 parts'.
2. Shade 5 out of the 8 parts. (You can shade any of the 5 parts.)	

- In daily life, fractions are used to divide things into equal parts.
- A pizza is cut into three equal slices, as shown.

One slice is $\frac{1}{3}$ of the pizza.

Two slices are $\frac{2}{3}$ of the pizza.

Three slices are $\frac{3}{3}$ of the pizza, or 1 whole pizza!



- The **numerator** is the top number of a fraction. The numerator shows the number of equal parts required.
- The **denominator** is the bottom number of a fraction. The denominator shows the number of equal parts the whole has been divided into.

Numerator – shows the number of equal parts

$\frac{2}{3}$

Denominator – shows the total number of parts the whole has been divided into and the size of the parts.



Types of fractions

- Fractions come in many different forms.
- A **proper fraction** is a fraction where the number on top (numerator) is smaller than the number on the bottom (denominator).
  For example, $\frac{7}{9}$ is a proper fraction.
- An **improper fraction** is a fraction where the number on top (numerator) is larger than the number on the bottom (denominator).
  For example, $\frac{20}{3}$ is an improper fraction.
- A **mixed number** has a whole number and a proper fraction.
  The picture below shows apples cut in halves. We can say there are 3 halves. This can be written as $\frac{3}{2}$.



We can also say we have one apple (2 halves) and half an apple, or $1\frac{1}{2}$ apples.

So $\frac{3}{2}$, is an improper fraction and can also be written as $1\frac{1}{2}$, which is called a mixed number.

- The table below shows the different types of fractions.

Proper fraction	Improper fraction	Mixed fraction
Proper fractions have a numerator *less than* the denominator.	**Improper fractions** have a numerator *greater than* the denominator.	**Mixed fractions** consist of a whole number and a proper fraction.
$\frac{1}{4}, \frac{3}{4}$	$\frac{5}{3}, \frac{3}{2}$	$1\frac{1}{2}, 5\frac{7}{8}$

- The value of a proper fraction is less than 1.
- The value of an improper fraction is greater than 1.
- If the numerator and the denominator have the same value, the fraction is equal to 1 (or one whole).

WORKED EXAMPLE 3 Classifying fractions

Classify the following fractions:

a. $\frac{3}{8}$ **b.** $\frac{10}{7}$ **c.** $\frac{13}{13}$ **d.** $2\frac{1}{4}$

THINK

WRITE

a. The number on the top of the fraction (3) is smaller than the number on the bottom (8).

WRITE $\frac{3}{8}$ is a proper fraction.

b. The number on the top of the fraction (10) is larger than the number on the bottom (7).

WRITE $\frac{10}{7}$ is an improper fraction.

c. The number on the top of the fraction is the same as the number on the bottom.

WRITE $\frac{13}{13}$ is equal to 1 (one whole).

d. This fraction has a whole number and a proper fraction.


WRITE $2\frac{1}{4}$ is a mixed number.

Changing an improper fraction to a mixed number

- An improper fraction can be changed to a mixed number by converting the fraction parts into a whole.

For example, write $\frac{7}{4}$ as a mixed number.

Let's draw a diagram for $\frac{7}{4}$.

$\frac{7}{4} = \frac{\text{7 shaded parts}}{\text{each whole has 4 parts}} =$  $= 1\frac{3}{4}$

1 whole + $\frac{3}{4}$

A more formal process for changing an improper fraction to a mixed number is demonstrated in Worked example 4 below.

WORKED EXAMPLE 4 Converting an improper fraction into a mixed number

Sandwiches were cut into quarters. You ate seven of the sandwiches' quarters $\left(\frac{7}{4}\right)$.

Determine how many whole and quarter sandwiches you ate. Convert $\frac{7}{4}$ to a mixed number.


THINK	WRITE
1. To convert $\frac{7}{4}$ into a mixed number, divide the denominator into the numerator.	$4\overline{)\,7}$
2. Complete the division problem $7 \div 4$.	1 remainder 3 $4\overline{)\,7}$
3. The answer (1) shows the number of 'wholes'. The remainder (3) is the numerator for the original fraction (the number of quarters).	1 and $\frac{3}{4}$
4. Write down the number of whole and quarter sandwiches eaten.	You ate $1\frac{3}{4}$ whole sandwiches

Changing a mixed number to an improper fraction

- A mixed number can be changed to an improper fraction by converting the whole number into a fraction.

  For example, write $2\frac{3}{4}$ as an improper fraction.

  Let's draw a diagram for $2\frac{3}{4}$ (i.e. 2 and three-quarters).



A more formal process for changing a mixed number to an improper fraction is demonstrated in Worked example 5 below.

WORKED EXAMPLE 5 Converting a mixed number into an improper fraction

At the end of a party there was $1\frac{2}{3}$ pies left over. The pies had been cut into thirds.

How many thirds of a pie were left to share? Convert $1\frac{2}{3}$ to an improper fraction.

THINK	WRITE
1. To convert $1\frac{2}{3}$ into an improper fraction, multiply the whole number (1) by the denominator (3). Add the answer to the numerator (2).	$\frac{1 \times 3 \times 2}{3}$
2. Write the answer.	There are $\frac{5}{3}$ pies left.



- Quantities greater than 1 can be shown as either a mixed number or an improper fraction.

  For example, there are $1\frac{1}{2}$ oranges shown below.


  If the whole orange was cut into two equal parts, there would be three halves or $\frac{3}{2}$ oranges.



Adding and subtracting fractions with the same denominator

- Fractions that have the same denominator are called 'like fractions'.
- 'Like fractions' can be added or subtracted.
- To add or subtract fractions with the same denominator, add or subtract the numerators and leave the denominator unchanged.

For example, if a pizza was divided into 4 equal sections (quarters), and you had 2 quarters and your friend had 1 quarter, that would make 3 quarters of the pizza.



This scenario can be written mathematically as: $\frac{2}{4} + \frac{1}{4} = \frac{2+1}{4} = \frac{3}{4}$


Important: Only the numerators should be added.

WORKED EXAMPLE 6 Adding fractions using diagrams

a. Draw a diagram to represent the fraction $\frac{2}{9}$.

b. Draw a diagram to represent the fraction $\frac{5}{9}$.

c. Use your diagrams to calculate $\frac{2}{9} + \frac{5}{9}$.

THINK	WRITE
a. 1. Draw a rectangle, divided into 9 equal parts.	
2. Shade in 2 of the parts, to represent the fraction $\frac{2}{9}$.	
b. 1. Draw a rectangle, divided into 9 equal parts.	
2. Shade in 5 of the parts, to represent the fraction $\frac{5}{9}$.	
c. 1. Draw a rectangle, divided into 9 equal parts.	
2. Shade in 2 of the parts to represent $\frac{2}{9}$ (blue) and shade in 5 of the parts to represent $\frac{5}{9}$ (pink).	
3. Count the number of shaded parts out of the 9 parts.	Number of shaded parts $= 2 + 5$ $= 7$ out of the total of 9 parts
4. Use the information to calculate $\frac{2}{9} + \frac{5}{9}$.	$\frac{2}{9} + \frac{5}{9} = \frac{2+5}{9}$ $= \frac{7}{9}$

WORKED EXAMPLE 7 Subtracting fractions using diagrams

a. Draw a diagram to represent the fraction $\frac{8}{11}$.

b. Use your diagram to calculate $\frac{8}{11} - \frac{3}{11}$.

THINK

a. 1. Draw a rectangle, divided into 11 equal parts.


2. Shade in 8 of the parts, to represent the fraction $\frac{8}{11}$.

b. 1. Since we need to subtract $\frac{3}{11}$ (3 out of 11 parts) from $\frac{8}{11}$, cross out 3 shaded parts.

2. There are now only 5 shaded parts left.

3. Use the information to calculate $\frac{8}{11} - \frac{3}{11}$.

WRITE



$$\frac{8}{11} - \frac{3}{11} = \frac{8-3}{11}$$
$$= \frac{5}{11}$$



Remember:
- Only add or subtract fractions with the same denominator.
- Add or subtract the numerator.
- Leave the denominator unchanged.



WORKED EXAMPLE 8 Adding and subtracting fractions with the same denominator

Evaluate each of the following:

a. $\frac{1}{9} + \frac{7}{9}$ **b.** $\frac{8}{11} - \frac{3}{11}$ **c.** $\frac{3}{7} - \frac{2}{7} + \frac{4}{7}$

THINK

a. 1. Write the question.

2. Add the numerators together and leave the denominator unchanged.

3. Write the answer.

WRITE

$$\frac{1}{9} + \frac{7}{9}$$
$$= \frac{1+7}{9}$$
$$= \frac{8}{9}$$
$$\frac{1}{9} + \frac{7}{9} = \frac{8}{9}$$

b. **1.** Write the question.

$$\frac{8}{11} - \frac{3}{11}$$

2. Subtract the numerators in the order given and leave the denominator unchanged.

$$= \frac{8-3}{11}$$
$$= \frac{5}{11}$$

3. Write the answer.

$$\frac{8}{11} - \frac{3}{11} = \frac{5}{11}$$

c. **1.** Write the question.

$$\frac{3}{7} - \frac{2}{7} + \frac{4}{7}$$

2. Add and subtract the numerators in the order given and leave the denominator unchanged.

$$= \frac{3-2+4}{7}$$
$$= \frac{5}{7}$$

3. Write the answer.

$$\frac{3}{7} - \frac{2}{7} + \frac{4}{7} = \frac{5}{7}$$

WORKED EXAMPLE 9 Adding fractions with the same denominator

Evaluate $\frac{7}{8} + \frac{5}{8}$, expressing your answer as a mixed number.

THINK

1. Write the question.

2. Add the numerators together and leave the denominator unchanged.


3. To change the improper fraction into a mixed number, draw a diagram.

$$\frac{12}{8} = \frac{12 \text{ shaded parts}}{\text{each whole has 8 parts}}$$

4. Write the simplified answer.

WRITE

$$\frac{7}{8} + \frac{5}{8}$$
$$= \frac{7+5}{8}$$
$$= \frac{12}{8}$$



$$\frac{7}{8} + \frac{5}{8} = \frac{12}{8}$$
$$= 1\frac{1}{2}$$

Week 4 Exercise: Fishing for fractions

1. WE1 In the following question state what part of the rectangle has been shaded.

a.



b.



c.



2. WE2 Draw a rectangle, divided into parts to represent:


a. $\frac{3}{4}$ **b.** $\frac{2}{7}$ **c.** $\frac{7}{9}$

3. State whether the following are true or false.


a. The numerator of $\frac{7}{12}$ is 7. **b.** The denominator of $\frac{8}{5}$ is 5. **c.** The numerator of $\frac{5}{7}$ is 7.

4. State what fraction of the following shapes has been shaded.


a.



b.




c.



5. State what fraction of chocolate biscuits in this packet:

a. remains to be eaten
b. has already been eaten.



6. WE3 Classify the following fractions as proper fractions, improper fractions or whole numbers.

a. $\frac{7}{12}$ **b.** $\frac{5}{7}$ **c.** $\frac{17}{12}$ **d.** $\frac{51}{51}$

7. MC Select which of the following fractions is a proper fraction.

A. $\frac{5}{5}$ **B.** $\frac{6}{5}$ **C.** $\frac{8}{6}$ **D.** $\frac{6}{8}$ **E.** $2\frac{9}{10}$

8. Identify the numerators and denominators of the following fractions.

a. $\frac{3}{4}$ **b.** $\frac{7}{2}$ **c.** $\frac{5}{6}$

9. Match each of the following fractions with its type.

Fractions.	Fraction types
a. $1\frac{3}{5}$	**A.** A Whole number
b. $\frac{5}{3}$	**B.** Proper fraction
c. $\frac{8}{1}$	**C.** Improper fraction
d. $\frac{23}{71}$	**D.** Mixed number

10. **WE4** Convert the following improper fractions to mixed numbers.

a. $\frac{21}{5}$ **b.** $\frac{13}{3}$ **c.** $\frac{19}{4}$ **d.** $\frac{23}{7}$

11. **WE5** Convert the following mixed numbers to improper fractions.

a. $2\frac{2}{3}$ **b.** $1\frac{4}{5}$ **c.** $3\frac{1}{4}$ **d.** $4\frac{1}{2}$

12. Match each of the following fractions with its type.

a. $\frac{3}{17}$ A Whole number


b. $\frac{82}{1}$ B Proper fraction

c. $11\frac{5}{11}$ C Improper fraction

d. $\frac{15}{7}$ D Mixed number


13. Write the fraction that is described.

a.




White squares

b.



Blue buttons

c.



Orange fish

14. WE6 **a.** Draw a diagram to represent the fraction $\frac{3}{13}$.

b. Draw a diagram to represent the fraction $\frac{7}{13}$.

c. Use your diagrams to calculate $\frac{3}{13} + \frac{7}{13}$.

15. WE7 **a.** Draw a diagram to represent the fraction $\frac{8}{13}$.

b. Use your diagram to calculate $\frac{8}{13} - \frac{5}{13}$.

16. WE8a, c Evaluate each of the following.

a. $\frac{6}{11} + \frac{3}{11}$ **b.** $\frac{8}{25} + \frac{9}{25}$ **c.** $\frac{5}{21} + \frac{8}{21}$ **d.** $\frac{9}{20} + \frac{1}{20} + \frac{3}{20}$

17. WE8b Evaluate each of the following.

a. $\frac{6}{11} - \frac{3}{11}$ **b.** $\frac{18}{25} - \frac{9}{25}$ **c.** $\frac{19}{21} - \frac{8}{21}$ **d.** $\frac{29}{30} - \frac{7}{30} - \frac{11}{30}$

18. Evaluate each of the following.

a. $\frac{9}{11} - \frac{3}{11} + \frac{1}{11}$ **b.** $\frac{3}{4} + \frac{5}{4} - \frac{1}{4}$ **c.** $\frac{13}{7} - \frac{3}{7} - \frac{5}{7}$ **d.** $\frac{1}{5} + \frac{2}{5} + \frac{3}{5}$

19. Evaluate the following.

a. $\frac{9}{20} + \frac{3}{20} - \frac{1}{20}$ **b.** $\frac{7}{8} + \frac{3}{8} - \frac{5}{8}$ **c.** $\frac{23}{27} - \frac{4}{27} - \frac{8}{27}$ **d.** $\frac{11}{15} - \frac{4}{15} + \frac{7}{15}$

20. State whether the following are true or false.

a. $\frac{1}{5} + \frac{3}{5} = \frac{4}{5}$ **b.** $\frac{2}{9} + \frac{8}{9} = \frac{10}{9}$ **c.** $\frac{7}{11} + \frac{3}{11} = \frac{10}{22}$ **d.** $\frac{4}{5} - \frac{1}{5} + \frac{2}{5} = \frac{7}{5}$

21. Jack and Jill were given a box of 25 chocolates to share. Jack ate 7 chocolates and Jill ate 6 chocolates.



a. Calculate what fraction of the box of chocolates Jack ate.
b. Calculate what fraction of the box of chocolates Jill ate.
c. Calculate what fraction of the box of chocolates Jack and Jill ate together.
d. Calculate what fraction of the box of chocolates was left uneaten.

22. Determine what fraction of the jelly beans in the photograph are:



a. blue
b. green
c. yellow
d. purple.

23. **WE9** Evaluate the following.

a. $\frac{3}{4} + \frac{3}{4}$
b. $\frac{7}{8} - \frac{5}{8}$
c. $\frac{1}{4} + \frac{3}{4}$
d. $\frac{11}{12} - \frac{5}{12}$

24. State whether the following are true or false.

a. $\frac{15}{17} > \frac{8}{17}$
b. $\frac{5}{8} < \frac{3}{8}$


25. **a.** Convert the following mixed numbers to improper fractions.

i. $2\frac{1}{5}$
ii. $1\frac{3}{5}$

b. By writing the mixed numbers as improper fractions, calculate the value of the following.

i. $2\frac{1}{5} + 1\frac{3}{5}$
ii. $2\frac{1}{5} - 1\frac{3}{5}$

Week 5: Getting to the point



Reading, writing and understanding decimals

- **Decimal** numbers contain whole numbers and decimal fractions.
- In a decimal number, the *decimal point* separates the whole number part and the fractional part.
- Place values in numbers are extended to show the decimal fraction. For example:
  - Tenths $= \frac{1}{10} = 0.1$
  - Hundredths $= \frac{1}{100} = 0.01$
  - Thousandths $= \frac{1}{1000} = 0.001$





- The **place-value table** can be extended to include decimal place values. It can be continued to an infinite number of decimal places.
- Just like in whole numbers, a zero in a decimal number shows that a place value column is empty.

Thousands	Hundreds	Tens	Ones •	Tenths	Hundredths	Thousandths	Ten thousandths
1000	100	10	1 •	$\frac{1}{10}$	$\frac{1}{100}$	$\frac{1}{1000}$	$\frac{1}{10\,000}$

- In the decimal number 73.064 shown above:
  - 7 represents 70 (seventy)
  - 3 represents 3 (three)
  - 0 represents 0.0 (no tenths)
  - 6 represents 0.06 (six hundredths)
  - 4 represents 0.004 (four thousandths).
- To help understand the value of each digit in a decimal number, it is helpful to use a place value table.

Place value table				
Tens	**Ones •**	**Tenths**	**Hundredths**	**Thousandths**
7	3 •	0	6	4

- As with whole numbers, expanded notation is a way to write the value of each digit.

For example:

$$73.064 = 7 \times 10 + 3 + 0 \times \frac{1}{10} + 6 \times \frac{1}{100} + 4 \times \frac{1}{1000}$$

or

$$73.064 = 70 + 3 + 0.0 + 0.06 + 0.004$$

WORKED EXAMPLE 1 Determining the value of a digit in a decimal number

Write the value of the digit 5 in each of the following decimal numbers.

a. **2.005** **b.** **498.57** **c.** **0.05**

THINK	WRITE
a. The value is the third place to the right of the decimal point, so the value is thousandths.	$\frac{5}{1000}$
b. The value is the first place to the right of the decimal point, so the value is tenths.	$\frac{5}{10}$
c. The value is the second place to the right of the decimal point, so the value is hundredths.	$\frac{5}{100}$

- Knowing place value helps you to read numbers. When reading and writing the fractional part of a decimal number, the place value column that contains the **final digit** gives the decimal fraction its **name**.
  For example:
  - 0.6 is read as 6 tenths because the final digit is tenths.
  - 0.42 is read as 42 hundredths because the final digit is hundredths.
  - 0.375 is read as 375 thousandths because the final digit is thousandths.

  The number 123.405 is read as 'one hundred and twenty-three and four hundred and five thousandths'.



WORKED EXAMPLE 2 Writing decimal numbers

Write each of the following as a decimal.

a. **4 tenths** **b.** 5 **hundredths and 8 thousandths**

THINK	WRITE
a. Because there is no whole part, write 0, followed by the decimal point. The number of tenths is shown in the first decimal place, so write 4 directly after the decimal point.	4 tenths = 0.4
b. There is no whole part, so write 0, followed by the decimal point. The first place after the point is the tenths place. Because there are no tenths, write 0 there. The second decimal place is the hundredths place. Because there are 5 hundredths in the given number, write 5 in the hundredths place. The third decimal place is the thousandths place. There are 8 thousandths in the given number, so write 8 in the thousandths place.	5 hundredths and 8 thousandths = 0.058

Comparing decimal numbers



- Decimal numbers can be compared to determine if one decimal number is:
  - the **same** as another number
  - **less** (smaller) **than** another number
  - **greater** (larger) **than** another number.
- Decimals are compared by looking at the digits each number has in the same place value.
- The decimal with the largest number in the highest place value column is the largest decimal, *regardless of the number of decimal places.*
- A place value table can be used to compare decimal numbers.

  For example, which MP3 file is larger, the 2.527 MB or the 2.53 MB file?



Place value chart: Families						
Thousands	**Hundreds**	**Tens**	**Ones**	**Tenths**	**Hundredths**	**Thousands**
			2 •	5	2	7
			2 •	5	3	
			Same value ✓ Look at the next column ⟶	Same value ✓ Look at the next column ⟶	Different value. 3 is greater than 2.	

The 2.53 MB file is larger than the 2.527 MB file because it has **more** hundredths.

So, $2.53 > 2.527$.

Which MP3 file is smaller, the 2.6 MB or the 2.53 MB file?

Place value chart: Families						
Thousands	**Hundreds**	**Tens**	**Ones**	**Tenths**	**Hundredths**	**Thousands**
			2 •	6		
			2 •	5	3	
			Same value ✓ Look at the next column ⟶	Different value. 5 is greater than 6.		

2.53 is less than 2.6 because it has **fewer** tenths.

So, $2.53 < 2.6$.

- Remember, we can use symbols in place of words when comparing decimal numbers or whole numbers.

Symbol	Description	Example
=	When two values are the same, we use the 'equals' symbol.	$1.05 = 1.05$
>	When one value is bigger than another, we use the 'greater than' symbol.	$2.53 > 2.527$
<	When one value is smaller than another, we use the 'less than' symbol.	$2.53 < 2.6$

Ordering decimal numbers

- Decimal numbers ordered from smallest to largest are in **ascending order**.
  For example: 0.06, 0.25, 0.407, 0.55
- Decimal numbers ordered from largest to smallest are in **descending order**.
  For example: 0.55, 0.407, 0.25, 0.06
- The number of decimal places does not show whether the decimal number is larger or smaller than another decimal number.

WORKED EXAMPLE 3 Arranging decimal numbers in ascending order

Place the following decimal numbers in ascending order.

0.567, 0.49, 0.589, 0.438, 0.098

THINK	WRITE
1. All of the numbers are decimals. Write the number(s) with the smallest tenths value.	0.098
2. • Write the numbers with the next highest tenths value. • There are two numbers, so look at the hundredths values. 3 is smaller than 9, so swap the order.	0.49 and 0.438 becomes: 0.438, 0.49
3. • Write the numbers with the next highest tenths value. • There are two numbers, so look at the hundredths values. 6 is smaller than 8, so the numbers are in ascending order.	0.567 and 0.589
4. Write the numbers in ascending order.	0.098, 0.438, 0.49, 0.567, 0.589

- Another way of placing decimal numbers in either ascending or descending order would be to record them in a place value table. Worked example 3 is shown below.

Place value table				
Number	**Ones •**	**Tenths**	**Hundredths**	**Thousandths**
0.567	0 •	5	6	7
0.49	0 •	4	9	
0.589	0 •	5	8	9
0.438	0 •	4	3	8
0.098	0 •	0	9	8

- In descending order, from largest to smallest, start with the highest tenths digit. In this case there are two, 0.567 and 0.58. Look for the highest hundredths digit.

  So, the largest number is 0.58 followed by 0.567.

  This gives the decimal numbers in descending order: 0.589, 0.567, 0.49, 0.438, 0.098.



Remember:

The decimal with the **largest** number in the **highest** place value column is the **largest** decimal, *regardless of the number of decimal places*.

Adding decimal numbers

- Decimal numbers can be added using a similar method to adding whole numbers.
- To add decimal numbers, follow the steps below.
  1. Set out the addition as you would for whole numbers. Line up the digits of the same place value. That is, line up the ones in the ones column, the tenths in the tenths column, and so on.
  2. If a column doesn't have a digit, write zero in the column.
  3. Moving from right to left, add numbers as if they were whole numbers.
  4. Place the decimal point in the answer directly under the decimal points in the question.

WORKED EXAMPLE 4 Adding decimal numbers

Calculate 1.26 + 3.5.

THINK	WRITE
1. Set out the addition, lining up the digits in their correct place value.	1.26 + 3.5
2. There are no hundredths in 3.5, so add a zero.	1.26 + 3.50
3. • Begin in the hundredths column. Add 6 and 0. Write 6, as shown in red colour. • In the tenths column, add 2 and 5. Write 7, as shown in plum colour. • In the ones column, add 1 and 3. Write 4, as shown in purple colour.	1.26 + 3.50 4.76
4. Write the answer with the decimal point.	1.26 + 3.5 = 4.76

WORKED EXAMPLE 5 Adding decimal numbers

In a local diving competition, Jack's scores were 4.3 and 5 points. What was Jack's total score for the two dives?



THINK	WRITE
1. Set out the addition, lining up the digits in their correct place value.	4.3 + 5
2. There are no tenths in 5, so add a zero to the tenths place value. Remember the decimal point.	4.3 + 5.0
3. • Begin in the tenths column. • Add 3 and 0. Write 3, as shown in plum. • In the ones column, add 4 and 5. Write 9, as shown in purple.	4.3 + 5.0 9.3
4. Write the answer with the decimal point.	Jack's total score was 9.3.

Subtracting decimal numbers

- Decimal numbers can be subtracted using a similar method to subtracting whole numbers.
- To subtract decimal numbers, follow the steps below.
  1. Set out the subtraction as you would for whole numbers. Line up the digits of the same place value. That is, line up the ones in the ones column, the tenths in the tenths column, and so on.
  2. If a column doesn't have a digit, write zero in the column.
  3. Moving from right to left, subtract numbers as if they were whole numbers.
  4. Place the decimal point in the answer directly under the decimal points in the question.

WORKED EXAMPLE 6 Subtracting decimal numbers

What is the difference between Jack's diving scores?

THINK	WRITE
1. Set out the subtraction, lining up the digits in their correct place value.	.5 + 4.3
2. There are no tenths in 5, so add a zero to the tenths place value. Remember the decimal point.	5.0 − 4.3
3. • Begin with the tenths column. To take 3 tenths away from 0 tenths, the 5 ones needs to be renamed as 4 ones and 10 tenths, as shown in pink colour. • Take 3 tenths away from 10 tenths (10 – 3 = 7). Write the 7 in the tenths column, as shown in plum colour. • Take 4 ones away from 4 ones (4 – 4 = 0). Write 0 in the ones column, as shown in purple colour.	4 10 5 . 0 − 4 . 3 0 . 7
4. Write the answer with the decimal point.	The difference in Jack's diving scores is 0.7.

WORKED EXAMPLE 7 Subtracting decimal numbers

Calculate 6.35 – 4.52.

THINK	WRITE
1. Set out the subtraction, lining up the digits in their correct place value.	6.35 −4.52
2. • Begin with the hundredths column. 5 – 2 = 3. Write 3 in the hundredths column, as shown in red. • In the tenths column, you can't take 5 from 3. You need to rename 6 ones and 3 tenths as 5 ones and 13 tenths, as shown in pink. Take 5 tenths away from 13 tenths (13 – 5 = 8). Write the 8 in the tenths column, as shown in plum. • Take 4 ones away from 5 ones (5 – 4 = 1). Write 1 in the ones column, as shown in purple.	5 13 ~~6~~ . 3 5 – 4 . 5 2 1 . 8 3
3. Write the answer with the decimal point.	6.35 – 4.52 = 1.83

Week 5 Exercise: Getting to the point

1. MC In the decimal number 15.436, the digit 3 is:
   A. 3 tens **B.** 3 ones **C.** 3 tenths **D.** 3 hundredths **E.** 3 thousandths
2. MC The number 42.035 in expanded form is:
   A. 40 + 2 + 3 + 5 **B.** 400 + 20 + 3 + 5 **C.** 42 + 0.3 + 0.5
   D. 40 + 2 + 0.03 + 0.005 **E.** 40 + 2 + 0.3 + 0.05
3. Write the number 4.218 in expanded form.
4. WE1 Write the value of the 2 in the following decimal numbers.
   a. 1.002 **b.** 5.2 **c.** 0.02
5. WE2 Write each of the following as a decimal number.
   a. 6 tenths **b.** 8 hundredths **c.** 5 tenths and 3 thousandths
6. Fill in the blanks.
   a. '0.08 is read as 8 _____ because the final digit is _____.'
   b. '0.2 is read as 2 _____ because the final digit is _____.'
   c. '0.045 is read as _____ thousandths because the _____digit is thousandths.'
7. MC Select the smallest number from the following.
   A. 2.579 **B.** 2.583 **C.** 2.7 **D.** 2.57 **E.** 2.58
8. MC Select the largest number from the following.
   A. 2.579 **B.** 2.583 **C.** 2.7 **D.** 2.57 **E.** 2.58

9. MC Select the smallest number from the following.

A. 3.748 **B.** 3.784 **C.** 3.874 **D.** 3.847 **E.** 3.708

10. MC Select the largest number from the following.

A. 3.748 **B.** 3.784 **C.** 3.874 **D.** 3.847 **E.** 3.708

11. State whether the following are true or false.

a. $0.187 < 0.178$ **b.** $2.37 > 2.369$ **c.** $0.05 < 0.005$

12. Write the correct symbol (=, > or <) between the decimal numbers to make the following statements true.

a. 2.36 □ 2.63 **b.** 4.072 □ 4.702 **c.** 0.312 □ 0.213

13. WE3 Write the following numbers in ascending order.

0.427 0.27 0.247 0.724 0.742

14. Write the following numbers in descending order.

1.456 1.654 1.465 1.645 1.564

15. WE4 Calculate the following:

a. $1.35 + 2.6$ **b.** $2.61 + 1.3$ **c.** $4.2 + 1.37$

16. WE5 In a diving competition, Jill scores 2.9 and 4 points for two dives. Calculate Jill's total score for the two dives.



17. Calculate the following:

a. $2.3 + 4.2$
b. $2.31 + 5.24$
c. $7.2 + 2.7$

18. Complete the following statements:

a. $3.54 + 4.79 =$ _____
b. $9.27 + 2.54 =$ _____
c. $0.035 + 3.05 =$ _____

19. WE6 State the difference between a diving score of 7 and a diving score of 5.7.

20. WE7 Calculate the following:

a. $7.3 - 4.2$ **b.** $7.1 - 1.4$ **c.** $5.35 - 3.62$

21. Complete the following statements:

a. $0.85 - 0.76 =$ _____
b. $7.54 - 4.72 =$ _____
c. $2.51 - 1.6 =$ _____


22. Your favourite song takes up 3.56 MB on your phone and your best friend's favourite song takes up 3.65 MB on their phone. Determine which song file is larger.



23. Determine the difference between the heights of two friends if one is 1.62 metres tall and the other is 1.48 metres tall.

24. In a shop, the cost of a hamburger is $6.95 and a soft drink is $2.40. Calculate the total cost of a hamburger and a soft drink.

25. A pizza shop advertises a Hawaiian pizza for $9.90 and a Pepperoni pizza for $13.40.
Calculate the difference in the costs of the pizzas.




Week 6: Giving 100%

Understanding percentages





- The symbol % means ‘per cent’.
- *Per cent* means ‘out of 100’ or ‘per hundred’.
- 20% means 20 out of 100.
- The diagram below has been divided into 100 squares, 20 of which have been shaded blue. We say that 20 out of the 100, or 20% of the diagram, has been shaded blue.





- Every day, we see percentage signs. Sales in shops are often shown with % signs.
- The photo below shows a Coles supermarket with items marked as '20% off'.



- These casual shoes are on sale at '50% off' the normal price.



WORKED EXAMPLE 1 Writing a percentage

Write the following as a percentage:
a. 75 out of 100 **b. 6 out of 100**

THINK	WRITE
a. 'Out of 100' means per cent, so 75 out of 100 is 75%.	75%
b. 'Out of 100' means per cent, so 6 out of 100 is 6%.	6%.

WORKED EXAMPLE 2 Writing a percentage

Alex scored 86 out of 100 on a Maths test. Calculate Alex's result as a percentage.

THINK	WRITE
'Out of 100' means per cent, so 86 out of 100 is 86%.	86%

WORKED EXAMPLE 3 Representing a percentage as a diagram


Draw a diagram and shade in part of the diagram to represent 45%.


THINK

1. What does 45% mean?
2. Draw a square and divide it into 100 small squares.
3. Count and shade in 45 small squares.
   Note: You can choose to colour in any 45 of the 100 small squares.

WRITE


45 out of 100





- 100% of something means *all* of it.
- The square below has been divided into 100 tiny squares and *all* have been shaded green. We say that 100 out of the 100, or 100%, of the rectangle has been shaded green.

100 out of 100 blocks are shaded.




100% of the blocks are shaded.

- This square below has been divided into 100 tiny squares, with 40 shaded blue and the remaining 60 shaded orange.

40 out of 100 blocks are shaded blue.

60 out of 100 blocks are shaded orange.



40% of the blocks are shaded blue.

60% of the blocks are shaded orange.

We say 40% are shaded blue and the remaining 60% are shaded orange, giving the total of 100% shaded.

From the above square, we can see that 40% + 60% gives the total, 100%, of the rectangle.

WORKED EXAMPLE 4 Adding to 100%

An orchestra has 100 musicians. There are 24 musicians who play the violin.

a. Calculate the percentage of the orchestra that play the violin.

b. Calculate the percentage of the orchestra that do not play the violin.



THINK	WRITE
a. The orchestra has 100 musicians. State the number who play the violin. Write this as a percentage.	24 out of 100 play the violin. 24% of the orchestra play the violin.
b. The remainder do not play the violin. State the number who do not play the violin. Write this as a percentage.	100 – 24 = 76 do not play the violin. 76% of the orchestra do not play the violin.

WORKED EXAMPLE 5 Adding to 100%

In a survey of a Year 7 class, 85% played football.
Calculate the percentage of the class that did not play football.



THINK	WRITE
1. State the percentage that played football.	85% played football
2. The total of the Year 7 class is 100%. The remaining percentage do not play football. Write the answer.	100% – 85% = 15% 15% of the class did not play football.

Strategies for calculating 10% and 50% of an amount

Common percentages: 10% and 50%


- Percentages are used in many aspects of everyday life.
- Being able to calculate certain percentages of an amount can be very helpful, especially if something you want to buy is discounted by a percentage.
- In this section we look at how to find 10% and 50% of an amount.

Calculating 10% of an amount

- 10% means 10 out of 100.
- $\frac{10}{100} = \frac{1}{10}$ if we divide the top and bottom of the fraction by 10.

So:

- 10% off means we take off (subtract) 10% or $\frac{1}{10}$ from an amount.





Calculating 50% of an amount

- 50% means 50 out of 100.
- $\frac{50}{100} = \frac{1}{2}$ if we divide the top and bottom of the fraction by 50.

So:

- 50% off means we take off (subtract) 50% or $\frac{1}{2}$ from an amount.





Tips for calculating 10% and 50% of an amount

- 10% means $\frac{10}{100} = \frac{1}{10}$, which is the same as dividing by 10.
- To find 10% of something, just divide by 10.
- 50% means $\frac{50}{100} = \frac{1}{2}$, which is the same as dividing by 2.
- To find 50% of something, just divide by 2.

WORKED EXAMPLE 6 Calculating 10% of an amount

Calculate 10% of $300.

THINK	WRITE
1. State the percentage.	10%
2. Write this as a fraction.	$\frac{10}{100} = \frac{1}{10}$
3. $\frac{1}{10}$ means divide by 10, so divide $300 by 10.	$300 ÷ 10 = $30
4. Write the answer.	10% of $300 = $30

WORKED EXAMPLE 7 Calculating 50% of an amount

Calculate 50% of 6 metres.

THINK	WRITE
1. State the percentage.	50%
2. Write this as a fraction.	$\frac{50}{100} = \frac{1}{2}$
3. $\frac{1}{2}$ means divide by 2, so divide 6 metres by 2.	6 metres ÷ 2 = 3 metres
4. Write the answer.	50% of 6 metres = 3 metres

10% tax

- In Australia, consumers pay a 10% Goods and Service Tax (GST) on most items they purchase, such as shoes, mobile phones, takeaway food and clothes.
- In most cases, GST is included in the price shown on the items you purchase.
- GST is also charged on services, such as a plumber repairing a burst pipe or an electrician replacing an air conditioning unit.
- The GST goes to the government, as it is a tax.



WORKED EXAMPLE 8 Calculating GST

A plumber quotes you $550 plus GST to fix a leaky toilet. Calculate the GST charged by the plumber.

THINK	WRITE
1. State the percentage for GST.	10%
2. Write this as a fraction.	$\frac{10}{100} = \frac{1}{10}$
3. $\frac{1}{10}$ means divide by 10, so divide $550 by 10.	$550 ÷ 10 = $55
4. Write the answer.	The plumber will charge $55 for GST.

WORKED EXAMPLE 9 Calculating GST and the final price

The recommended retail price of a new television is $850 plus GST.
a. Calculate the GST payable.
b. Determine the final price, including GST, that a customer would pay for the new television.

THINK	WRITE
a. 1. State the percentage for GST.	10%.
2. Write this as a fraction.	$\frac{10}{100} = \frac{1}{10}$
3. $\frac{1}{10}$ means divide by 10, so divide $850 by 10.	$850 ÷ 10 = $85
4. Answer the question.	The GST charged on $850 is $85
b. 1. State the recommended retail price without GST.	$850
2. State the GST.	$85
3. Add the GST to the recommended price.	$850 + $85 = $935
4. Write the answer.	Final price including GST = $935

Discounts

- During certain times of the year most retail stores and shops offer discounts on items (for example, Boxing Day sales, end of season sales, end of financial year sales and 'Cyber Monday' deals).
- Knowing how to calculate the final price you will pay for an item is an essential skill to have and can help you stick to your budget.
- In this section we will consider discounts of 10% and 50% only.

WORKED EXAMPLE 10 Calculating the discount and final price of an item

At the summer sale, Ben saw these shirts marked at 50% off and decided to buy one as a present for his grandfather. The shirt was originally priced at $74.50.
a. Calculate the discount.
b. Determine how much Ben paid for the shirt.



THINK	WRITE
a. 1. State the percentage off for the sale.	50%
2. Write this as a fraction	$\frac{50}{100} = \frac{1}{2}$
3. $\frac{1}{2}$ means divide by 2, so divide $74.50 by 2.	$\$74.50 \div 2 = \$37.25$
4. Answer the question.	The discount is $37.25.
b. 1. State the retail price before the sale.	$74.50
2. State the discount.	$37.25
3. Subtract the discount from the original price.	$\$74.50 - \$37.25 = \$37.25$
4. Write the answer.	Ben paid $37.25 for the shirt.

WORKED EXAMPLE 11 Calculating the discount and final price of an item

The local cafe was advertising a 10% discount on all takeaway food and drinks.
Jack and Jill ordered hamburgers and drinks for lunch to take to the local park. The total bill came to $16.50 before the discount was applied.
a. Calculate the discount.
b. Determine how much Jack and Jill paid for lunch.



THINK	WRITE
a. 1. State the percentage discount.	10%.
2. Write this as a fraction.	$\frac{10}{100} = \frac{1}{10}$
3. $\frac{1}{10}$ means divide by 10, so divide $16.50 by 10.	$\$16.50 \div 10 = \$1.65$
4. Write the answer.	The discount is $1.65.
b. 1. State the cost of the lunch.	$16.50
2. State the discount.	$1.65
3. Subtract the discount from the cost of lunch.	$\$16.50 - \$1.65 = \$14.85$
4. Write the answer.	Jack and Jill paid $14.85 for lunch.

Week 6 Exercise: Giving 100%

1. WE1 Write the following as a percentage.

a. 16 out of 100


b. 27 out of 100

2. WE2 Zara scored 74 out of 100 on her last Maths test. Calculate Zara's result as a percentage.


3. Peter scored 72 out of 100 on his Science test. Calculate Peter's result as a percentage.

4. Calculate the percentage of each of the following shapes has been shaded.


a.




b.



c.




d.




5. WE3 Shade the given percentage of each of the following.


a. 50%




b. 75%



c. 60%



d. 82%



6. WE4 A sports club has 100 members. There are 78 members who play cricket.

a. Calculate the percentage of the club members that play cricket.

b. Calculate the percentage of the club members that do not play cricket.

7. During basketball practice, you shot 100 free throws, 40 of which went in the basket.
   a. Calculate the percentage of your free throws that went in the basket.
   b. Calculate the percentage of your free throws that missed the basket.

8. **WE5** In a survey of a Year 7 class, 15% rode their bikes to school each day. Calculate the percentage of the class that did not ride bikes to school each day.

9. The last Australian census found that 29% of the Australian population was born overseas. Calculate the percentage of the Australian population that was born in Australia.

10. Approximately 59% of the athletes at the 2000 Sydney Olympics were male. Calculate the percentage of the athletes that were female.



11. **WE6** Calculate the following:
   a. 10% of $400
   b. 10% of $850
   c. 10% of $12
   d. 10% of $36.50

12. **WE7** Calculate the following:
   a. 50% of $600
   b. 50% of $750
   c. 50% of $27
   d. 50% of $126.50

13. **WE8** An IT technician quotes you $260 plus GST to fix your laptop. Calculate the GST charged by the technician.

14. Calculate the GST payable on a pair of shoes if the price, not including GST, was $87.

15. **WE9** The recommended retail price of a new laptop computer is $950 plus GST.
   a. Calculate the GST payable.
   b. Determine the final price, including GST, a customer would pay for the new computer.

16. A store was advertising a Blu-ray DVD player for $295 plus GST.
   a. Calculate the GST payable.
   b. Determine the final price, including GST, a customer would pay for the new player.

17. **WE10** At the summer sales, a store advertised shirts for sale with discount of 50% off the marked price. Terry purchased a shirt marked at $115.50.
   a. Calculate the discount.
   b. Calculate how much Terry paid for the shirt.

18. A store was having a clearance sale with 50% off all marked prices. Patricia wanted to buy the dress marked at $189, the top marked at $57 and the pants marked at $76.
   a. Calculate the cost for these three items.
   b. Calculate the discount Patricia would receive during the clearance sale.
   c. Calculate how much would Patricia pay for these three items with the discount.



19. WE11 The local café was advertising a special of a 10% discount for lunch on Thursdays. Peter, Paul and Mary went to the café for lunch the next Thursday. The total bill came to $85.50 before the discount.

a. Calculate the discount.
b. Calculate how much Peter, Paul and Mary paid for the lunch.

20. A store was offering a 10% discount when paying by cash. You purchased a jacket marked at $79.

a. Calculate the discount.
b. Determine how much you would pay if you paid cash for the jacket.

21. A store had just received a shipment of T-shirts marked at $49 plus GST.

a. Calculate the GST.
b. Calculate the price a customer would need to pay for a Tee shirt.



22. A jar of mayonnaise is advertised as 98% fat free. Calculate the percentage of the mayonnaise is fat.

23. An investment fund is advertising 10% interest on any investment over $10 000. Calculate the interest on an investment of $25 000.

24. An electrician increased his hourly rate of $80 per hour by 10%.

a. Calculate the amount of the increase.
b. Calculate the new hourly rate.



25. Approximately 27.2% of the world population is aged between 0 and 14 years and 65.2% is aged between 15 and 64 years. Calculate the percentage of the world population that is aged 65 and over.




Answers

Week 1 Exercise: Finding your place

1. B
2. B
3. 678 215 = 600 000 + 70 000 + 8000 + 200 + 10 + 5
4. D
5. E
6. C
7. E
8. B
9. C
10. a. False b. True
11. a. False b. True
12. <
13. >
14. =
15. 10, 11, 12, 15, 19, 20, 21, 26, 31, 33, 46
16. 1542, 1524, 1452, 1425, 1254, 1245
17. A
18. 150
19. 1680
20. 7700
21. 87 300
22. 9000
23. 10 000
24. 50 000
25. 540 000

Week 2 Exercise: Numbering up

1. a. True b. True c. True
2. a. 80 b. 401 c. 2290
3. D
4. a. 43 b. 37 c. 122
5. a. 28 b. 66 c. 106
6. a. False b. True c. False
7. a. 88 b. 666
8. a.



   b. 12
9. (300 × 4) + (10 × 4) + (5 × 4) = 1200 + 40 + 20 = 1260
10. a. 504 b. 3738 c. 324
11. a. 1922 b. 1674
12. a.

	100	20	3
6	600	120	18

   600 + 120 + 18 = 738

   b. 738
13. a. False b. True
14. a. 19 b. 33
15. a. 85 r 2 b. 75 r 2
16. (1000 ÷ 4) + (300 ÷ 4) + (80 ÷ 4) + (4 ÷ 4)
    = 250 + 75 + 20 + 1 = 346
17. a. False b. False
18. Larger number is 327 + 98
19. 1176 bananas
20. a. $129 in total b. $71 left over
21. a. 34 b. 162
22. a. 4 buses b. 15 left over
23. 208
24. Mila is correct, the product of 51 and 37 is 1887.
25. 408

Week 3 Exercise: Thinking quickly

1. a. 417 b. 1724
2. a. 741 b. 758
3. a. 555 b. 115
4. a. 94 b. 78
5. True
6. C
7. 1225
8. a. 33 b. 234
9. a. 56 b. 92
10. a. 14 b. 323
11. 278
12. D
13. a. 0 b. 5
14. a. 18 b. 40
15. a. True b. False
16. a. The 5 times tables end in 5 or 0 ; therefore, it is impossible for 5 × 7 to equal 36.

    b. The 8 times tables can be calculated using doubling 3 times: double 7 = 14; double 14 = 28; double 28 = 56 Therefore 7 × 8 = 56, not 54.
17. a. 12 b. 28 c. 36 d. 48
18. a. 27 b. 54 c. 99
19. A
20. a. True b. False c. False

21. a. The student has not listed the tens and ones correctly.

b. 623

22. 432

23. 4, 8, 12, 16, 20
5, 10, 15, 20
Therefore 4×5 and 5×4 both equal 20.

24. 56

25. $171

Week 4 Exercise: Fishing for fractions

1. a. $\frac{5}{6}$ **b.** $\frac{7}{12}$ **c.** $\frac{3}{10}$


2. a.



b.



c.



3. a. True **b.** True **c.** False

4. a. $\frac{1}{4}$ **b.** $\frac{1}{2}$ **c.** $\frac{3}{8}$

5. a. $\frac{8}{11}$ **b.** $\frac{3}{11}$

6. a. proper fraction **b.** proper fraction
c. improper fraction **d.** a whole number

7. D

8. a. Numerator = 3
Denominator = 4

b. Numerator = 7
Denominator = 2

c. Numerator = 5
Denominator = 6

9. a. D **b.** C **c.** A **d.** B

10. a. $4\frac{1}{5}$ **b.** $4\frac{1}{3}$ **c.** $4\frac{3}{4}$ **d.** $3\frac{2}{7}$

11. a. $\frac{8}{3}$ **b.** $\frac{9}{5}$ **c.** $\frac{13}{4}$ **d.** $\frac{9}{2}$

12. a. B **b.** A **c.** D **d.** C

13. a. $\frac{12}{24}$ or $\frac{1}{2}$ **b.** $\frac{4}{12}$ or $\frac{1}{3}$ **c.** $\frac{6}{8}$ or $\frac{3}{4}$

14. a. See the table at the foot of the page.*

b. See the table at the foot of the page.*

c. $\frac{10}{13}$

15. a. See the table at the foot of the page.*

b. $\frac{3}{13}$

16. a. $\frac{9}{11}$ **b.** $\frac{17}{25}$ **c.** $\frac{13}{21}$ **d.** $\frac{13}{20}$

17. a. $\frac{3}{11}$ **b.** $\frac{9}{25}$ **c.** $\frac{11}{21}$ **d.** $\frac{11}{30}$

18. a. $\frac{7}{11}$ **b.** $\frac{7}{4}$ **c.** $\frac{5}{7}$ **d.** $\frac{6}{5}$

19. a. $\frac{11}{20}$ **b.** $\frac{5}{8}$ **c.** $\frac{11}{27}$ **d.** $\frac{14}{15}$

20. a. True **b.** True **c.** False **d.** False

21. a. $\frac{7}{25}$ **b.** $\frac{6}{25}$ **c.** $\frac{13}{25}$ **d.** $\frac{12}{25}$

22. a. $\frac{8}{24}$ or $\frac{1}{3}$ **b.** $\frac{6}{24}$ or $\frac{1}{4}$
c. $\frac{4}{24}$ or $\frac{1}{6}$ **d.** $\frac{2}{24}$ or $\frac{1}{12}$

23. a. $\frac{6}{4}$ or $\frac{3}{2}$ **b.** $\frac{2}{8}$ or $\frac{1}{4}$
c. $\frac{4}{4}$ or 1 **d.** $\frac{6}{12}$ or $\frac{1}{2}$

24. a. True **b.** False

25. a. i. $\frac{11}{5}$ **ii.** $\frac{8}{5}$
b. i. $\frac{19}{5}$ or $3\frac{4}{5}$ **ii.** $\frac{3}{5}$

Week 5 Exercise: Getting to the point

1. D

2. D

3. $4.218 = 4 + 0.2 + 0.01 + 0.008$

4. a. 2 thousandths or $\frac{2}{1000}$


b. 2 tenths or $\frac{2}{10}$

c. 2 hundredths or $\frac{2}{100}$


***14. a.**



***14. b.**




***15. a.**




5. **a.** 0.6 **b.** 0.08 **c.** 0.503
6. **a.** hundredths, hundredths
   b. tenths, tenths
   c. 45, final
7. D
8. C
9. E
10. C
11. **a.** False **b.** True **c.** False
12. **a.** < **b.** < **c.** >
13. 0.247, 0.27, 0.427. 0.724, 0.742
14. 1.654, 1.645, 1.564, 1.465, 1.456
15. **a.** 3.95 **b.** 3.91 **c.** 5.57
16. 6.9
17. **a.** 6.5 **b.** 7.55 **c.** 9.9
18. **a.** 8.33 **b.** 11.81 **c.** 3.085
19. 1.3
20. **a.** 3.1 **b.** 5.7 **c.** 1.73
21. **a.** 0.09 **b.** 2.82 **c.** 0.91
22. Your friend's song is bigger. 3.65 MB > 3.56 MB
23. 0.14 metres (or 14 centimetres)
24. $9.35
25. $3.50

Week 6 Exercise: Giving 110%


1. **a.** 16% **b.** 27%
2. 74%
3. 72%
4. **a.** 50% **b.** 30% **c.** 23% **d.** 50%
5. **a.**




b.



c.



d.



6. **a.** 78% **b.** 22%
7. **a.** 40% **b.** 60%
8. 85%
9. 71%
10. 41%
11. **a.** $40 **b.** $85 **c.** $1.20 **d.** $3.65
12. **a.** $300 **b.** $375 **c.** $13.50 **d.** $63.25
13. $26
14. $8.70
15. **a.** $95 **b.** $1045
16. **a.** $29.50 **b.** $324.50
17. **a.** $57.75 **b.** $57.75
18. **a.** $322 **b.** $161 **c.** $161
19. **a.** $8.55 **b.** $76.95
20. **a.** $7.90 **b.** $71.10
21. **a.** $4.90 **b.** $53.90
22. 2%
23. $2 500
24. **a.** $8 per hour **b.** $88 per hour
25. 7.6%


NAPLAN practice

Overview

Why learn this?

Understanding numeracy helps us make sense of mathematical ideas and how they relate to everyday life.

Numeracy includes counting, addition, subtraction, multiplication and division, fractions, decimals, measuring, understanding shapes and graphs.



on Resources

Video eLesson NAPLAN: strategies and tips (eles-1688)

Set A

Calculator allowed



1. Our feet produce approximately 100 litres of sweat a year. Approximately how many millilitres of sweat do your feet produce each day?

A. 270 mL
B. 27 mL
C. 37 mL
D. 2.7 mL

2. The brain grows at an amazing rate during development. At times during development 250 000 neurons (nerve cells) are added every minute. If neurons multiplied at the given rate for an hour, how many neurons would be added?

A. 1 500 000 **B.** 15 000 000 **C.** 6 000 000 **D.** 600 000

3. Nerve impulses to and from the brain travel as fast as 274 metres every second. Which is the closest estimate of the number of metres a nerve impulse travels in an hour?

A. 970 000 **B.** 980 000 **C.** 990 000 **D.** 100 000



4. On average, human beings blink their eyes 6 205 000 times each year. How many times do you blink in a day?

5. How much timber would be left if eleven 1.75 m lengths are cut from a 22 m piece of timber?

A. 3.25
B. 2.25
C. 2.35
D. 2.75



6. On three tests, a student scored a total of 255 marks. If the student improved her performance on each successive test by 4 marks, what was the mark for each test?

A. 80, 84, 88
B. 81, 85, 89
C. 78, 86, 91
D. 79, 83, 87

7. A student scored 42 out of 50 for a Maths test. What percentage did she obtain for the Maths test?

A. 82% **B.** 84%
C. 75% **D.** 16%

8. In a notebook, an author writes a short story of 4000 words. He can type 125 words in three minutes. Keeping the same rate, how long would it take him to type the story?

A. 32 minutes **B.** $41\frac{2}{3}$ minutes **C.** 96 minutes **D.** $10\frac{2}{3}$ minutes

9. In a soccer team, $\frac{1}{3}$ of the players ride a bike to practice, 25% walk to practice and the remaining 15 players are driven by their parents. How many players are there in the team?

A. 42 **B.** 36 **C.** 30 **D.** 21

10. Jonathan is saving his money for a two-week surfing trip to Hawaii. He has estimated the costs of his adventure to be:

- return airfare — $2000
- accommodation — $1400
- food — $500
- extra costs — $400.

If Jonathan can earn $80 per day laying bathroom tiles, how many full days of work does he need to complete in order to save the money for the trip?

11. A bottle containing 1 litre of lemonade was poured into big glasses of volume 120 mL and small glasses of volume 80 mL. How much lemonade was left in the bottle after 5 big glasses and 4 small glasses of lemonade had been poured out?



A. 620 mL
B. 378 mL
C. 280 mL
D. 80 mL

12. There are 184 students who need to be seated for a dinner in a hall. If all the tables need to be full, select whether the school should use:

A. 18 tables **B.** 19 tables **C.** 23 tables **D.** 31 tables

13. The following table shows the cost of road tax for motor cars.

Engine capacity	Road tax
1001 to 1600 cc	75 cents per cc
1601 to 2000 cc	85 cents per cc
2001 to 2600 cc	95 cents per cc

The road tax on a motor car of engine capacity 2400 cc is:

A. 95 cents **B.** $950 **C.** $228 **D.** $2280

14. A waiter works 40 hours in order to earn $640. Assuming the same rate of pay per hour, calculate how much she will earn in 15 hours.



15. There is space in a multistorey car park for 15 rows of 20 cars on each of the 8 floors. How many spaces are left if 2124 cars have already parked?

16. Your friend is training for a triathlon. On one training day she swam 1500 m, rode a bike 47 000 m and ran 14 km. How many kilometres did she complete?

17. A total of $5320 was raised by a group of students to give to 38 refugees. How much does each refugee receive?

18. A plane leaves Melbourne at 09:35 and arrives in Osaka at 20:07 (Melbourne time). How long did the trip take?




A. 9 hours 42 minutes **B.** 10 hours 72 minutes
C. 9 hours 28 minutes **D.** 10 hours 32 minutes

19. During the day, a patient had her temperature measured as 37.3 °C, 38 °C, 37.8 °C and 38.5 °C. Her average temperature was:

A. 37.8 °C **B.** 37.9 °C **C.** 38 °C **D.** 38.2 °C

20. Boxes for packaging are in the shape of a cuboid, as shown. A company offers a promotion of an extra 20% volume. What is the new volume?

A. 1200 cm^3
B. 240 cm^3
C. 1440 cm^3
D. 81.4 cm^3



21. A couple bought a laptop with an interest-free loan of $2400. They paid a deposit of $800, and paid off the remainder over the next 5 months. How much were the monthly repayments?

A. $480 **B.** $320
C. $160 **D.** $200



22. A restaurant served 315 meals. One-third of the people ate a two-course meal while the remainder ate a three-course meal. How many courses did the chef prepare?

A. 840 **B.** 210
C. 630 **D.** 1575

23. The following is the exchange rate as given by Travelex.

	A$1
US$	0.92
€	0.58

You have $1500 in Australian currency and you want to change $500 to US currency and the remainder to euros. How much will you receive of each currency?

24. At the Healesville supermarket, shopping trolleys are 1 metre long. You work collecting them and stacking them into an area. Each shopping trolley that is added to the stack adds on 25 cm. How long would the line be if you stacked 20 trolleys?

A. 6 m **B.** 5.75 m
C. 60 m **D.** 57.5 m



25. At another supermarket, shopping trolleys are also 1 metre long. Your friend works collecting them and stacking them into an area. Each shopping trolley in the stack adds on 0.25 m. How many trolleys could be stacked in a single line of 10 metres?

A. 37
B. 36
C. 35
D. 34

26. There are 128 Year 7 students. Three-quarters of them own a pet. A survey shows that 37 students have cats, $\frac{1}{3}$ of the students who own a pet have dogs and the remaining students have horses. How many have horses?

27. How many 55 cent stamps can you buy for $10?

A. 2 **B.** 18 **C.** 11 **D.** 19

28. In 1969 the first 12-sided 50 cent coin (as shown) came into existence. It weighs 15.55 g. Coins are usually stored in bags of 400 coins for transport. How much would the bag weigh (in kilograms)?



29. Clare buys a fashion magazine for $10.25 and chocolates for $3.99. She pays with a $20 note. How much change does she receive? (Assume rounding to the nearest 5c.)

A. $6.75 **B.** $5.80 **C.** $5.76 **D.** $5.75

30. What number would you insert into the following expression to get an answer of 19?
$5 \times 3 + _ \div 6$

Set B


Non-calculator

1. The figure 2 010 415 is closest to:

A. 2 000 000 **B.** 2 010 000 **C.** 2 020 000 **D.** 2 100 000

2. Jennifer's softball match will take 90 minutes from start to finish, including breaks. Her team must finish by 12.20 pm. What is the latest time the match can start?

3. Jug A and Jug B contain different amounts of water. How much more water is in Jug B?



4. What is the probability of choosing a number from the following table that is divisible by 7?

1	2	3	4	5
6	7	8	9	10
11	12	13	14	15
16	17	18	19	20
21	22	23	24	25

A. $\frac{1}{25}$ **B.** $\frac{2}{25}$ **C.** $\frac{3}{25}$ **D.** $\frac{4}{25}$

5. Human blood travels 675 780 km per week on its journey through the body. How far does the blood travel, to the nearest thousand km, in one week?

A. 670 000
B. 700 000
C. 675 000
D. 676 000

6. The average human heart will beat three thousand million times in its lifetime. This can be represented as:

A. 3×10^6 **B.** 3×10^7 **C.** 3×10^8 **D.** 3×10^9



7. A chef made ten apple pies. For one apple pie he used $\frac{7}{12}$ of a tablespoon of cinnamon and $\frac{5}{12}$ of a tablespoon of nutmeg. How much more cinnamon than nutmeg was used for all the apple pies?

A. $\frac{1}{6}$ **B.** $\frac{5}{6}$ **C.** $\frac{5}{3}$ **D.** $1\frac{1}{3}$

8. Hue leaves home and rides on a bike 4 km west, then 2 km north, followed by 4 km east and finally 5 km south. Which direction and how far must Hue ride to get back home?

A. South 3 km **B.** South 1 km **C.** North 3 km **D.** North 1 km

9. Peta has 36 small buttons and n large buttons. Which expression shows how many buttons Peta has altogether?

A. $n - 36$
B. $36 - n$
C. 36
D. $n + 36$



10. Of the 48 children in the park, $\frac{3}{4}$ are wearing a hat. How many children are not wearing a hat?


A. 12 **B.** 36 **C.** 1 **D.** 48

11. Three-quarters of the students on the athletics team compete in the high jump. Of the students who do the high jump, one-half also do the long jump. What fraction of the athletics team does the long jump?

A. $\frac{1}{2}$ **B.** $\frac{3}{8}$ **C.** $\frac{2}{3}$ **D.** $\frac{3}{4}$

12. The Ambelfield aquifer pumps 15 million litres per day from its bore field. If the water is to be shared among the 200 000 residents, how many litres would each person receive per day?

A. 750 L
B. 75 L
C. 30 L
D. 7.5 L



13. The Ambelfield aquifer is estimated to hold 50 billion litres. Assuming no addition or depletion of water, for approximately how many days could water be pumped if 15 million litres were extracted each day?

A. 34 **B.** 340 **C.** 3400 **D.** 34 000

14. A boy borrowed two-fifths of his friend's DVD collection. If he borrowed 20 DVDs, how many were in the collection?

A. 50 **B.** 70 **C.** 8 **D.** 24



15. On a map, the distance between Port Fairy and Warrnambool is represented by 10.3 cm. What is the actual distance if 1 cm represents 7 km?

A. 17.3 km **B.** 103 km **C.** 72.1 km **D.** 70 km

16. Seven cubic metres can be written as:

A. $(7\text{ m})^3$ **B.** 7m^3 **C.** 21 m **D.** 343 m

17. At the local Sunday market, you have sold $\frac{2}{3}$ of your mangoes. You started with 24 boxes, each containing 20 mangoes. How many mangoes are left?

A. 320 **B.** 160 **C.** 16 **D.** 32


18. Six thousand people attended a tennis match. If $\frac{3}{10}$ of them entered with a free pass, how many people paid for a ticket?

A. 1800 **B.** 600 **C.** 2000 **D.** 4200

19. The difference between the volumes of water in two tanks is 436 L. If the smaller tank has a volume of 7844 L, what is the volume of water in the larger tank?

20. A nurse takes your temperature at 9 am and then again at 4 pm. The results are shown in the diagram. What is the difference in the temperature?

A. 0.3 °C **B.** 0.1 °C **C.** 0.4 °C **D.** 1.1 °C



21. It takes Lyng 15 minutes to walk to school. If school begins at 9.03 am, what time must she leave home so that she can get to school just as school begins?

22. There are 42 apples in a box. If you picked up 28 apples, what fraction of apples would be left in the box?

A. One-quarter
B. One-third
C. One-half
D. Three-quarters

23. It takes Shannon exactly three hours to walk 18 km. How long would it take Shannon to walk (assuming the same speed) 30 km?

24. A piece of rope had 160 cm cut from the end. The rope that remained measured 75 metres. How long was the original piece of rope?

25. Jarrod goes to sleep at 21:30 and wakes at 6:00 am. His brother goes to sleep at 22:15 and sleeps for the same length of time that Jarrod did. What time does he wake up?

26. A student works in a shop each day from 14 January to 24 January, inclusive. The student is paid $40 for each day. How much does he earn in total?

27. You can walk 100 m per minute and can run 200 m per minute. How far can you travel if you walk for 20 minutes and run for 15 minutes?


A. $20 \times 100 + 15 \times 200$
B. $20 \times 200 - 15 \times 200$
C. $15 \times 100 + 20 \times 200$
D. $20 \times 200 + 15 \times 100$

28. A DVD recorder was set to begin taping a show at 18:35. It ended at 20:15. How long was the show?

A. 110 min **B.** 100 min **C.** 85 min **D.** 80 min

29. What is the difference between Jo's height and David's height?

A. 0.32 m
B. 0.38 m
C. 0.42 m
D. 0.48 m



30. A sketchbook contains 100 pieces of paper and is 14 mm thick. What is the thickness of one sheet of paper?

A. 1.4 mm **B.** 10 mm **C.** 0.14 mm **D.** 7.14 mm

Set C

Calculator allowed

1. A school has 434 DVDs in its collection. It has been decided to store them in boxes that hold 32 DVDs each. How many boxes are needed?

A. 13 **B.** 13.5 **C.** 13.6 **D.** 14

2. A cardboard box weighs 244 grams. It contains 48 smaller boxes, each weighing 127 grams. Which of the following is the closest to the total weight of the large box and its contents?

A. 6.3 kg **B.** 6.31 kg **C.** 6.309 kg **D.** 6.4 kg


3. A truck is carrying 12 boxes, each weighing 250 kg, and 20 pipes, each weighing 17 kg. How many excess kilograms is the truck carrying if it has a weight limit of 2.8 tonnes?

A. 2737 **B.** 310
C. 540 **D.** 217



4. The following is the exchange rate given by Travelex.
A$1 = US$0.92
A$1 = €0.58
Jinny has just had a holiday and has brought back US$100 and €150. If she exchanges this into Australian dollars with the above rates, how much will she receive for each?

5. What is the total cost of the petrol shown in the diagram?



6. Block chocolate is sold in the following sizes.

   A. 100 g for $3.20
   B. 150 g for $3.95
   C. 250 g for $6.90
   D. 300 g for $8.60

   Which is the best buy?

7. The following table shows the number of items sold in one year by a company in each of the locations. In which location was the highest number of items sold per salesperson?

Location	Number of salespeople	Number of items sold
North	52	49 192
North-west	36	61 164
City	34	23 154
East	20	50 518
South	23	48 048

8. A customer has to wait 8 days for a leaking pipe to be repaired. In 1 hour the pipe loses 4 litres of water. The amount of water that will be lost while the customer is waiting is approximately:
   A. 760 L **B.** 770 L **C.** 780 L **D.** 790 L

9. Each number in a sequence is multiplied by 7, and then 1 is added. The first three numbers in the new pattern are 15, 43, 71. What is the fifth number in the original sequence?
   A. 99 **B.** 14 **C.** 127 **D.** 18

10. Molecules generally are approximately one billionth of a metre in size. Which one of the following represents that measurement?
    A. 1 000 000 000 **B.** 100 000 000
    C. 0.000 000 000 000 1 **D.** 0.000 000 001

11. The area of a square is 9 cm^2. If the length of each side is doubled, what is the area now?
    A. 18 cm^2 **B.** 36 cm^2 **C.** 81 cm^2 **D.** 324 cm^2

12. If each small cake needs 10 g of chocolate and 50 g of rice crispies, how many grams of rice crispies are needed for 50 g of chocolate?



13. A ship's container is loaded with nine boxes each weighing $1\frac{1}{4}$ tonnes. If the container itself weighs 850 kg, what is the total weight of the loaded container?
    A. 2100 kg
    B. 10 075 kg
    C. 11 250 kg
    D. 12 100 kg

14. Jodie earns $15.00 an hour for 40 hours and $17.50 per hour for any hours of overtime. During one week she earned $810. How many hours did she work?

15. A survey of 300 students in Year 7 looked at the most popular reality TV shows. How many watched *Big Brother*?


TV show	Number of people
The Masked Singer	177
Big Brother	
Survivor	20%
Who do you think you are?	63

A. 40 **B.** 20 **C.** 0 **D.** 54

16. Blueberries cost $14 per kg. You paid $1.75 for a punnet. How many grams of blueberries did you purchase?

A. 125 g **B.** 0.75 g **C.** 200 g **D.** 175 g

17. There are 200 Year 7 students. The diagram shows the percentage of students who were late on four days of the week. Which day had the most latecomers? How many students were late on that day?



18. Hayden purchased some content for his MP3 player using the internet. He bought 6 songs at $1.70 each and 4 music videos at $3.20 each. If he used his $20 gift card, how much extra did he need to pay?

19. The hospital has just installed a new scanner to help in the diagnosis of cancer. The state of the art machine detects a tumour as small as 0.5 cm^3. Tumours are made up of individual cells, each of which is 0.000 000 1 cm^3. How many cells are needed in a tumour before it is detected by the new scanner?

A. $5 \times 0.000\ 000\ 1$ **B.** $0.5 \times 100\ 000$
C. $5 \times 100\ 000$ **D.** $50 \times 100\,000$


20. A cancer tumour doubles in size every five days. Beginning from one cell, after 50 days how many cells will the tumour contain?

A. 10 **B.** 100 **C.** 512 **D.** 1024

21. A room measures 7 m by 3 m. If 4 pages of *The Australian* newspaper measure one square metre, how many pages are needed to cover the floor area with no overlap?

22. What fraction is halfway between one-quarter and one-half?

23. Anne is standing halfway between her two friends on a number line at 2.9. Jane is at a position 0.8 on the line and John is at x. What is John's position?



24. A square has an area of 36 square cm. If the sides are enlarged by a factor of 5, what is the area of the new square?

A. 188 cm^2 **B.** 150 cm^2 **C.** 900 cm^2 **D.** 875 cm^2

25. Ten teenagers were weighed in kilograms as follows:
47, 53, 51, 62, 58, 53, 48, 52, 67, 54
What is the mean of these measurements?




26. A cube is made up of 125 small cubes. How many cubes will make up one face?

A. 5 **B.** 10 **C.** 15 **D.** 25

27. How much wire is needed to create this cuboid?

A. 17.1 cm
B. 34.2 cm
C. 68.4 cm
D. 94.64 cm




28. Think of two 2-digit numbers, both less than seventy-five. Both numbers have factors of 6, 3 and 5. One number is half the size of the other number. What are the two numbers?

29. Which is the odd one out in the following?

A. 0.8 **B.** $\frac{4}{5}$ **C.** 80% **D.** $\frac{16}{80}$

30. The regular octagon shown has an area of 125 cm^2. The square surrounding the octagon has a perimeter of 60 cm. What is the area of one triangle if all the triangles are the same size?




Set D

Non-calculator


1. You spin the spinner on the right once. What is the probability of selecting a prime number?

A. $\frac{1}{8}$ **B.** $\frac{5}{8}$ **C.** $\frac{4}{8}$ **D.** $\frac{6}{8}$



2. In the graph shown, when was the biggest change in temperature?

A. 6 am – 7 am **B.** 1 pm – 2 pm **C.** 11 am – 12 pm **D.** 10 am – 11 am




3. Jason packed $5\frac{1}{4}$ shelves in the supermarket and Charlie packed $8\frac{1}{2}$ shelves. How many more shelves did Charlie pack?

A. $3\frac{1}{2}$ **B.** $2\frac{1}{4}$ **C.** $2\frac{1}{2}$ **D.** $3\frac{1}{4}$


4. A class contains 12 boys and 18 girls. Five have red hair, 7 have brown hair and the rest have blond hair. What is the probability that a student chosen has blond hair?

5. A cuboid is made from 1 cm cubes, stacked in layers on the rectangular base shown. If there are 5 layers, how many cubes will be used?




6. The diagram shows a cubic object whose side lengths are 20 cm. A smaller cube with a side length of 4 cm has been cut out of the larger cube. What is the volume of the object that is left?

A. 16 cm^3
B. 56 cm^3
C. 736 cm^3
D. 7936 cm^3



7. The graph shows how 60 students travel to school. How many students travel on wheels?






8. A rectangle is twice as long as it is wide. The perimeter of the rectangle is 60 cm. What is the area of the rectangle?

A. 100 cm^2 **B.** 200 cm^2 **C.** 400 cm^2 **D.** 60 cm^2

9. Suem bought a packet of chocolates and shared it with six friends. They each received 4 chocolates and three were left over. If you share the same number of chocolates equally with five friends, how many chocolates will be left over?


A. 2 **B.** 1 **C.** 4 **D.** 0

10. What is the equation represented by the following balance?



11. The Temple of Kukulcan (El Castillo) in Mexico sits on a pyramid-shaped platform. The height of the temple is 6 m and the height to the top of the platform on which it sits is 24 m.
What is the ratio of the height of the platform to the height of the temple?

A. 1 : 6
B. 6 : 1
C. 6 : 24
D. 4 : 1




12. Which two numbers will have a difference of 2.5?
$-3, -2.5, -2, -1.5, -1, -0.5$

13. Julia walked to her friend's house and arrived at 4.10 pm. It took one hour and thirty-five minutes. What time did she begin her walk?

14. What is the value of $3 + 6 \div 3 \times 2$?

A. 6 **B.** 4 **C.** 7 **D.** 1.5

15. What is the range between A and B?



A. 600
B. 700
C. 800
D. 900

16. To make a batch of chocolate mousse, you need 20 g of chocolate. How many batches can you make from 280 g of chocolate?

17. On a map, a distance of 30 km is represented by 24 cm. What actual distance would be represented by 16 cm on a map?

18. Which of the following is equivalent to $\frac{3}{4}$?

A. $\frac{21}{28}$ **B.** $\frac{8}{40}$ **C.** $\frac{33}{45}$ **D.** $\frac{13}{14}$

19. A plane leaves Brisbane at 0935 and arrives in Perth at 1342 (Brisbane time). How long did the trip take?

A. 3 hours 42 minutes
B. 3 hours 72 minutes
C. 4 hours 28 minutes
D. 4 hours 7 minutes

20. A kindergarten has 120 students. On one day, 42 students were absent. The fraction of students who were present is closest to:

A. one-third **B.** one-quarter **C.** two-thirds **D.** three-quarters

21. In this recipe, how many more teaspoons of sugar than salt are needed?

Marinade for chicken wings

1 cup soy sauce

$\frac{1}{2}$ cup maple syrup

5 cloves of garlic

$1\frac{1}{4}$ teaspoons of salt

$1\frac{2}{3}$ teaspoon brown sugar

2 tablespoons of vinegar

22. The attendance at a Melbourne Storm football match was given as 38 479. Rounded off to the nearest thousand, this number is:

A. 30 000 **B.** 38 500 **C.** 38 000 **D.** 40 000

23. The temperatures shown in the table were measured in cities worldwide. What was the largest difference in temperature between any two cities?

City	Temp.
Athens	37 °C
Cairo	17 °C
Hobart	8 °C
Stockholm	5 °C
Anchorage	−9 °C
New York	7 °C
Helsinki	−5 °C
Paris	18 °C
Rome	35 °C
Perth	23 °C


24. The temperature at midnight was −3 °C. By 8 am it had risen by 6 °C. What was the temperature at 8 am?

A. 6 °C **B.** 9 °C
C. 3 °C **D.** 8 °C

25. At 9 pm, the temperature was 2 °C. By midnight, the temperature had dropped to −5 °C. By how many degrees had the temperature fallen?

A. 5 °C **B.** −5 °C
C. 3 °C **D.** 7 °C

26. From Yangs, how much further is it to Londsdale than to Bell Post? (Give your answer in simplest form.)




27. A coloured card is chosen and a coin is tossed. The results are recorded. How many different combinations are possible?






A. 3 **B.** 9 **C.** 14 **D.** 21

28. How far is it from Lobethal to Kyeton?



29. Johan Vaaler was the first person to patent the paperclip (1899). If this paperclip is made from 12.5 cm of wire, how much wire do you need to fill a box containing 200 paperclips?



A. 250 cm **B.** 250 m **C.** 25 m **D.** 2.5 m

30. Which one of the following is another way of writing $4 \times 4 \times 4$?

A. 4^3 **B.** $4 + 4 + 4$ **C.** 3×4 **D.** 3^4

Set E

Calculator allowed

1. In May 2013 the number of students at a school was 1200. Given that the number of pupils in May 2014 was 1320, find the percentage increase in the number of students.

2. A carpenter is looking for the smallest nail diameter in order to construct a cabinet. Choose the smallest diameter from the following sizes:

A. 0.22 mm **B.** 0.109 mm **C.** 0.072 mm **D.** 0.284 mm

3. Jamie earns $26 from mowing lawns and $27 from delivering pamphlets each week. Jamie also receives $20 per week in pocket money from his parents. Each week he keeps $27 in spending money and banks the rest. Calculate the amount that Jamie banks each week.

4. Twenty students were surveyed on the type of music they liked. The results were:


- $\frac{1}{5}$ liked pop
- $\frac{1}{10}$ liked rock
- $\frac{1}{4}$ liked hip hop
- $\frac{1}{20}$ liked classical
- the rest of the students liked more than one type.

How many students liked more than one type of music?

5. A rectangular luggage label has an area of 96 cm^2 and a width of 8 cm. What is the perimeter of the label?

A. 40 cm **B.** 20 cm **C.** 12 cm **D.** 32 cm

6. The area of this parallelogram is 40 cm^2. What will be the perimeter of the rectangle created by moving the right-angled triangle as shown?



7. A computer costs $1200. It is reduced by 5% in a sale. What is the sale price of the computer?

A. $1000 **B.** $1195 **C.** $1140 **D.** $60

8. Gordon is given a new PIN for his debit card. He calculates that if he divides his PIN by his age, which is 14, and then adds his house number, which is 105, the answer will be 225. What is the PIN?



9. A skip that holds 3.6 cubic metres has been delivered. You can use a wheelie bin with a capacity of 240 L to transport your rubbish to the skip. How many trips will you make to fill the skip? (1 m^3 = 1000 litres.)

A. 15 **B.** 14 **C.** 150 **D.** 140

10. I buy 12 comics at a cost of $65.00. If I return 25% of them to the shop, how much money will I get back?

A. $3.00 **B.** $59.58 **C.** $16.25 **D.** $21.67

11. How many of these cards show values the same as $\frac{2}{5}$?

20%	$\frac{20}{50}$	$\frac{6}{30}$	40%	0.40

A. 4 **B.** 3 **C.** 2 **D.** 1

12. When 2^8 is divided by 2^4, the answer is:

A. 2^2 **B.** 2^4 **C.** 2^{12} **D.** 4^4

13. Which of the following has the largest value?

A. $3^2 \times 3^2$ **B.** $3^3 \times 3^2$ **C.** $\frac{3^8}{3^2}$ **D.** $\frac{3^2}{3^8}$

14. The table shows the time that Angela spent running this week. What was the average time spent running?

A. 210 minutes **B.** 50 minutes
C. 35 minutes **D.** 30 minutes


Day	Time
Monday	35 minutes
Tuesday	25 minutes
Wednesday	30 minutes
Thursday	42 minutes
Friday	50 minutes
Saturday	28 minutes

15. Justin buys some footy cards for $8.95 and soft drink for $3.80. He pays with a $20 note. How much change does he receive?

A. $6.75 **B.** $7.80 **C.** $7.25 **D.** $7.76


16. The students of Year 7 did a survey on how they travel to school, and recorded their data in a pictograph. How many students are in Year 7?

A. 150 **B.** 147 **C.** 141 **D.** 132



17. The column graph represents the shoe sizes of 27 Year 7 students in a mathematics class. What percentage of students has a shoe size greater than 7.5?

A. 25% **B.** 30% **C.** 60% **D.** 70%



18. Ann, Meg and Sally shared a pizza. Ann ate $\frac{1}{4}$ and Meg ate $\frac{1}{6}$ of the pizza. What was left for Sally?

A. $\frac{1}{5}$ **B.** $\frac{4}{5}$ **C.** $\frac{5}{12}$ **D.** $\frac{7}{12}$

19. You buy 3.5 kg of chicken at $15.30 per kg and 2.5 kg of potatoes at 90 cents per kg. You have only $40. You try to work out by how much you are short. Which number sentence best describes your problem?

A. $(3.5 \times 15.30 + 2.5 \times 90) - 40$
B. $40 - 3.5 \times 15.30 + 2.5 \times 0.90$
C. $3.5 + 2.5 \times 15.30 \times 0.90 - 40$
D. $40 - (3.5 \times 15.30 + 2.5 \times 0.90)$

20. The planet Mercury has a diameter that is 38% less than the planet Earth's diameter, which is 12 756 km. What is the diameter of Mercury? (Round to the nearest kilometre.)

21. The table shows the prices for admission to the museum.

Admission	
Adults	$19.80
Children	$12.25
Family (2 adults and 2 children)	$49.75

How much do you save by buying a family ticket instead of buying 2 adults and 2 children?

A. $14.35 **B.** $17.75 **C.** $10.75 **D.** $7.55

22. The maximum temperatures in Perth and at Mt Buller were recorded for one week.


	Mon.	**Tues.**	**Wed.**	**Thurs.**	**Fri.**	**Sat.**	**Sun.**
Perth	16	12	14	10	8	9	11
Mt Buller	−3	−1	−6	−2	−3	−1	−4

On which day is the temperature difference the greatest?

A. Monday **B.** Wednesday **C.** Friday **D.** Sunday

23. What is the area of this star-shaped diagram?

A. 56 unit^2
B. 52 unit^2
C. 61 unit^2
D. 96 unit^2



24. The following table shows the ages of people on a bus.

	0–19	20–29	30–39	40–49	50–59	60–69	70–79	> 79
Male	3	1	5	2	0	4	1	0
Female	2	2	7	1	3	4	0	1

Which is the closest percentage of people on the bus who were less than 30 years old?

A. 20% **B.** 22% **C.** 24% **D.** 26%

25. Fill in the missing terms in the following number pattern.
45, ___, 37, 33, ___, ___ ... .

26. I have a dripping tap that increases my water consumption by 3%. I used 64 kilolitres over a 3 – month period and my tap was constantly dripping over that period of time. How many litres could I have saved by fixing my tap?




27. The average bath uses two-and-a-half times as much water as a three-minute shower. If the average shower uses 15 litres of water per minute, how many more litres are used by having a bath?


A. 80 L **B.** 67.5 L **C.** 77 L **D.** 60.5 L

28. At 10 drips per minute, a leaking tap wastes 3000 litres of water in a year. At this rate, how many millilitres of water are wasted per drip? (Round to 2 decimal places.)

A. 1.92 mL **B.** 13 mL **C.** 0.57 mL **D.** 14 mL


29. A star shape is made by combining four copies of the single triangle shown. What is the star's perimeter?





A. 32 cm **B.** 26 cm **C.** 24 cm **D.** 20 cm

30. You have a number of regular hexagon tiles with sides of 6 cm. If 6 tiles are joined in the pattern presented, what will be the perimeter?




A. 172 cm **B.** 156 cm **C.** 164 cm **D.** 160 cm

Set F

Non-calculator

Use the following map to answer questions **1**, **2** and **3**.



1. What is the direct (straight line) distance from the front of Greg's house to the car park entrance near the school?

A. 1000 m **B.** 750 m **C.** 625 m **D.** 500 m


2. I meet a friend at E6. We walk west 0.75 km, then 1.25 km north and finally 1 km east. Where are we on the map?

A. D2 **B.** E2 **C.** F2 **D.** F1

3. Which of the following directions will I need to follow to get to the railway station from the house?

A. Turn left and walk 625 m, turn left and walk 500 m, turn left and walk 250 m.
B. Turn right and walk 625 m, turn left and walk 500 m, turn left and walk 500 m.
C. Turn left and walk 625 m, turn left and walk 500 m, turn left and walk 500 m.
D. Turn left and walk 625 m, turn right and walk 500 m, turn left and walk 500 m.


4. How many of the shapes below are the same as X?



A. 0 **B.** 1 **C.** 2 **D.** 3

5. From the graph, how many of the children are less than 7 years of age?

A. 30 **B.** 25 **C.** 70 **D.** 27




6. Students were asked to state how many SMSs they sent in one day. From the tally chart, what are the values of x, y and z?

Number of SMS	Tally	Frequency
0	| | |	3
1	𝍸 | |	x
2	𝍸 | | | |	y
3	𝍸 𝍸 𝍸 |	z
4	| | | |	4
5	𝍸 |	6

A. 7, 9 and 16 **B.** 6, 8 and 15 **C.** 8, 10 and 17 **D.** 7, 18 and 48

7. What is the value in degrees of the angle x in the triangle shown in the figure?




8. Jacinta is painting her bedroom. The area of the walls is 59 m^2, and each can of paint will cover an area of about 11 m^2. Estimate how many cans of paint Jacinta will need to buy.


A. 4 cans **B.** 1 can **C.** 5 cans **D.** 6 cans

9. The diagram shows the plan of a swimming pool. What is its perimeter?

A. 36.5 m **B.** 51 m **C.** 46 m **D.** 62 m



10. What is the reading on this scale?



A. 1.50 **B.** 1.55
C. 1.75 **D.** 1.8

11. Which of the following is most likely to be the diameter of a dinner plate?




A. 12 cm **B.** 25 cm **C.** 50 cm **D.** 75 cm

12. You arrive at a backpackers on 29 March and leave on 3 April. If you pay $45 per night, what is your total bill?

A. $225 **B.** $270 **C.** $315 **D.** $45

13. Let



= 6

= 7, and

+ = + .

What number is represented by ?

A. 6 **B.** 7 **C.** 8 **D.** 9

14. In a classroom, $\frac{6}{10}$ of the students are female. What percentage are boys?

A. 60% **B.** 50% **C.** 35% **D.** 40%

15. A map has a scale of 1 : 35 000. How much does 1 cm on the map represent in real life?

A. 350 m **B.** 3 m **C.** 3500 m **D.** 35 km

16. You divided 60 sweets between your two brothers in the ratio of their ages. If Nyg is 7 and Tyng is 5, how many does Tyng receive?

A. 25 **B.** 35 **C.** 5 **D.** 12

17. One angle of an isosceles triangle measures 40°. If the other two angles are the equal angles, find the measure of each of those angles.

A. 50° **B.** 140° **C.** 70° **D.** 40°

18. If X represents the number of stamps that Alice had, and Alice then gave 15 stamps to her friend, which expression shows how many stamps Alice has now?



A. 15 + X **B.** 15 − X **C.** X − 15 **D.** X ÷ 15


19. What are the whole numbers that make 9− __ > 4 true?


A. 0, 1, 2, 3, 4, 5 **B.** 0, 1, 2, 3, 4
C. 0, 1, 2 **D.** 5

20. A calculator display shows 4.33333. Which problem could have given that answer on the calculator?


A. 4 + .3 **B.** 4 × .3
C. 33 333 + .4 **D.** $\frac{13}{3}$

21. You are given 4 cards, each with a fraction on it. Can you arrange them from the smallest to the largest?









A. $\frac{1}{12}, \frac{1}{3}, \frac{3}{6}, \frac{3}{4}$ **B.** $\frac{1}{3}, \frac{3}{4}, \frac{3}{6}, \frac{1}{12}$ **C.** $\frac{1}{12}, \frac{1}{3}, \frac{3}{4}, \frac{3}{6}$ **D.** $\frac{1}{3}, \frac{1}{12}, \frac{3}{6}, \frac{3}{4}$

22. 120 people attended the Year 7 production. Tickets cost $16.70. Half the people bought programs at $4.00. How much money was collected?



23. The table below shows information about a Year 7 class and mobile phones.

	Own mobile	Do not own mobile
Boys	8	10
Girls	10	4

What is the probability of choosing a girl who owns a mobile phone?

A. $\frac{7}{16}$ **B.** $\frac{5}{16}$ **C.** $\frac{9}{16}$ **D.** $\frac{5}{9}$

24. Which one of the following does not represent 12×6?

A. $10 \times 6 + 2 \times 6$
B. $7 \times 6 + 5 \times 6$
C. $12 \times 4 + 12 \times 2$
D. $12 \times 3 + 12 \times 2$

25. $5 is taken off the price of all items for one day only. How much would you pay for items worth $32, $48.85, $57.95, $114, $151.75, $201.65?

A. $601.20 **B.** $575.20 **C.** $600.35 **D.** $576.20

26. When you rotate the following diagram anticlockwise 90° about the point, which of the following will be the result?



A. 

B. 

C. 

D. 

27. Which of these has the lowest value?

A. 20%

B. $\frac{3}{5}$

C. $\frac{1}{10}$

D. 0.3

28. Hector is sixty-nine years old. He was born on 29 February. How many times has he had a birthday?



29. A rope measures $3\frac{2}{3}$ m. Which of the following has the same measurement?


A. $\frac{7}{3}$ m

B. $\frac{8}{3}$ m


C. $\frac{10}{3}$ m

D. $\frac{11}{3}$ m

30. Let




= 600, and



= 350.

What do these shapes total when they are combined?



= ?

A. 750

B. 850

C. 950

D. 1050

Answers

NAPLAN practice

Set A Calculator allowed

1. A
2. B
3. C
4. 17 000
5. D
6. B
7. B
8. C
9. B
10. 54 days
11. D
12. C
13. D
14. $240
15. 276
16. 62.5 km
17. $140
18. D
19. B
20. C
21. B
22. A
23. US$460, €580
24. B
25. A
26. 27
27. B
28. 6.22 kg
29. D
30. 24

Set B Non-calculator

1. B
2. 10:50 am
3. 100 mL
4. C
5. D
6. D
7. C
8. C
9. D
10. A
11. B
12. B
13. C
14. A
15. C
16. B
17. B
18. D
19. 8280 L
20. C
21. 8:48 am
22. B
23. 5 hours
24. 76.6 m
25. 6:45 am
26. $440
27. A
28. B
29. B
30. C

Set C Calculator allowed

1. D
2. B
3. C
4. $108.70 and $258.62
5. $66.37
6. B
7. East
8. B
9. D
10. D
11. B
12. 250 g
13. D
14. 52
15. C
16. A
17. Thursday; 80 students
18. $3
19. D
20. D
21. 84 pages
22. $\frac{3}{8}$
23. 5
24. C
25. 54.5
26. D
27. C
28. 60 and 30
29. D
30. 25 cm^2

Set D Non-calculator

1. C
2. C
3. D

4. $\frac{3}{5}$
5. 160
6. D
7. 44
8. B
9. B
10. $x + 5 = 2x + 4$
11. D
12. -3 and -0.5
13. 2:35 pm
14. C
15. A
16. 14
17. 20 km
18. A
19. D
20. C
21. $\frac{5}{12}$ teaspoon
22. C
23. 46 °C
24. C
25. D
26. $5\frac{1}{2}$ km
27. C
28. $14\frac{1}{2}$ km
29. C
30. A

Set E Calculator allowed

1. 10%
2. C
3. $46
4. 8
5. A
6. 26 cm
7. C
8. 1680
9. A
10. C
11. B
12. B
13. C
14. C
15. C
16. C
17. A
18. D
19. D
20. 7909 km
21. A
22. B
23. B
24. B
25. 41, 29 and 25
26. 1920 L
27. B
28. C
29. C
30. B

Set F Non-calculator

1. B
2. D
3. C
4. C
5. C
6. A
7. 69°
8. D
9. B
10. C
11. B
12. A
13. C
14. D
15. A
16. A
17. C
18. C
19. B
20. D
21. A
22. $2244
23. B
24. D
25. D
26. A
27. C
28. 17 times
29. D
30. B

1 Positive integers

LEARNING SEQUENCE

1.1 Overview 2
1.2 Place value 4
1.3 Strategies for adding and subtracting positive integers 10
1.4 Algorithms for adding and subtracting positive integers 16
1.5 Multiplying positive integers 25
1.6 Dividing positive integers 34
1.7 Rounding and estimating 41
1.8 Order of operations 45
1.9 Review 52



1.1 Overview

Why learn this?

Positive integers are whole numbers. We use positive integers every day. Addition, subtraction, multiplication and division of positive integers are the building blocks of Mathematics.

When you count the number of runs you make in a game of cricket, you are using integers. When you add your runs to the runs your teammates scored, the total number of runs will be a positive integer. This result is found by the addition of integers.

Many daily activities depend on knowing how to answer simple questions like, 'When you went for that walk, how far did you go?' or 'How many people live in your house?'

Every day we see integers displayed on screens — for example when we look at the weather forecast or check our unread messages. We normally don't even think about integers — they are just the numbers we see all around us.



Understanding integers and their addition, subtraction, multiplication and division is important for everyday life and work. Many jobs, including hospitality, banking, construction, design, engineering, nursing, teaching, finance and medicine all require an understanding of the use of integers.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 1.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Choose the largest of the following numbers.
A. 5656 **B.** 5665 **C.** 5566 **D.** 5556 **E.** 5666

2. State how many three-digit numbers you can make from the digits 6, 9 and 1 if you are allowed to repeat digits.

3. Calculate the following additions.
a. $1366 + 948 + 97$
b. $654 + 937 + 23 + 68\,941$
c. $3085 + 38 + 20\,389 + 3000 + 235$

4. Calculate the following subtractions.
a. $987 - 365$ **b.** $9432 - 2175$ **c.** $3001 - 1739$

5. Calculate the following using a mental strategy.
$2 \times 8 \times 6 \times 5$

6. Evaluate the following.
$3\overline{)1248}$

7. A large chicken farm sorts its eggs into cartons of 12 eggs. If they have 3852 eggs to sort, calculate the number of complete cartons that can be sorted.

8. A landscape gardener charges an initial fee of $165, plus $52 per hour. Determine how much the landscape gardener will charge for a job that takes 35 hours if a customer has taken advantage of a special offer of $120 off the total.

9. If an order was made for 25 boxes of Fanta and each box contains 24 cans, use factors to calculate the total amount of cans.

10. Round 32 895 to the first digit.

11. Calculate the following.
a. $48 \div 4$ **b.** $168 \div 8$ **c.** $625 \div 25$

12. Complete each statement by placing $<$, $>$ or $=$ in the empty box so that the statement is true.
a. $2 \times 4 \square 8 \times 2$ **b.** $16 \div 2 \square 8$ **c.** $16 \times 2 \square 32 \div 8$

13. Evaluate the following.
a. $7 \times 6 \div 3 \div 7$ **b.** $3 \times 8 \div 6 + 4$ **c.** $7 + [66 - (5 \times 5)] \times 3$

14. Evaluate the following using long division.
a. $2752 \div 16$ **b.** $7548 \div 17$ **c.** $4935 \div 21$

15. Aziz takes 3 minutes to complete one lap of a running course, while Jani takes 4 minutes to complete one lap. Not counting the start of the race, determine when Aziz will next be running beside Jani.

1.2 Place value

LEARNING INTENTION

At the end of this subtopic you should be able to:

- understand that the value of each digit in a number depends on its position or place value.

1.2.1 Place value

eles-3643

- Numbers are made up of the digits 0, 1, 2, 3, 4, 5, 6, 7, 8 and 9.
- The position of a digit in a number gives a different value to the digit. The table below shows the value of the digit 6 in some different numbers.

Number	Name of number	Value of the digit 6
1**6**	Sixteen	6
35**6**2	Three thousand, five hundred and sixty-two	60
18 **6**34	Eighteen thousand, six hundred and thirty-four	600

- Each position in a number has its own **place value**. The number 59 376 can be represented in a place-value table as shown.

Ten thousands	Thousands	Hundreds	Tens	Ones
5	9	3	7	6

WORKED EXAMPLE 1 Expanded form

Write 59 376 in expanded form.

THINK

1. 59 376 is the same as 5 ten thousands, 9 thousands, 3 hundreds, 7 tens and 6 ones.
2. Multiply each of the digits by its place value.
3. Perform each of the multiplications to show how the expanded form is written.

WRITE

Ten thousands	Thousands	Hundreds	Tens	Ones
5	9	3	7	6

$59\,376 = 5 \times 10\,000 + 9 \times 1000 + 3 \times 100 + 7 \times 10 + 6 \times 1$

$= 50\,000 + 9000 + 300 + 70 + 6$

Place-holding zeros

- On 6 November 2020, at 10:15 am, the Australian Bureau of Statistics' population clock estimated Australia's population to be 25 718 205. In a place-value table, this number appears as follows.

Ten millions	Millions	Hundred thousands	Ten thousands	Thousands	Hundreds	Tens	Ones
2	5	7	1	8	2	0	5

- The zero (0) in the place-value table means that there are no tens. The zero must be written to hold the place value, otherwise, the number would be written as 2 571 825 and would no longer have the same value.

Reading numbers

- To make numbers easier to read and name, they are written in groups of three digits with a space between each group. The only exception to this rule is that four-digit numbers are usually written as a group of four digits.

Number	Name of number
4357	Four thousand, three hundred and fifty-seven
12 345	Twelve thousand, three hundred and forty-five
102 345	One hundred and two thousand, three hundred and forty-five
123 456 789	One hundred and twenty-three million, four hundred and fifty-six thousand, seven hundred and eighty-nine

1.2.2 Ordering and comparing numbers

eles-3644

- Numbers in **ascending order** are placed from smallest to largest, starting on the left. The numbers, 1, 25, 192, 908 and 1115 are in ascending order.



- Numbers in **descending order** are placed from largest to smallest, starting on the left. The numbers 8532, 934, 105, 53 and 5 are in descending order.



- Numbers are ordered according to their place values. For whole numbers, the number with the most digits is the greatest in value because the first digit will have the highest place value.
- If two numbers have the same number of digits, then the digits with the highest place value are compared. If they are equal, the next highest place values are compared, and so on.

WORKED EXAMPLE 2 Ordering numbers

Write the following numbers in descending order.
858, 58, 85, 8588, 5888, 855

THINK	WRITE
1. Write the numbers with the most digits.	8588 and 5888
2. There are two numbers with 4 digits. The number with the higher digit in the thousands column is larger. The other number is placed second.	8588, 5888
3. Compare the two numbers with 3 digits. Both have the same hundreds and tens values, so compare the value of the units.	858, 855
4. Compare the two 2-digit numbers.	85, 58
5. Write the answer.	8588, 5888, 858, 855, 85, 58

- The < symbol means **is less than**. The number sentence $3 < 5$ is read from left to right like a normal sentence. It is read as 'three is less than five'.
- The > symbol means **is greater than**. The number sentence $5 > 3$ is also read from left to right. It is read as 'five is greater than three'.
- When comparing two numbers using the symbols < and >, think of a crocodile's mouth. To work out the right symbol to place between two numbers so the number sentence is correct, just remember that the crocodile always wants to eat the bigger number.



WORKED EXAMPLE 3 Writing number sentences

Copy and complete the following number sentences by placing the < or > symbol in each box.

a. **52 □ 160** **b.** **8764 □ 4720**

THINK	WRITE
a. 1. Examine the two numbers and determine which number is larger.	**a.** 160 is larger than 52.
2. Recall that the symbols < and > are like a crocodile's mouth. To work out the correct symbol to insert between 52 and 160, remember that the crocodile always wants to eat the larger number.	The crocodile opens its mouth to eat the larger number. $52 < 160$
3. The correct number sentence should read '52 is less than 160'. Write the correct statement.	$52 < 160$
b. 1. Examine the two numbers and determine which number is larger.	**b.** 8764 is larger than 4720.
2. Recall that the symbols < and > are like a crocodile's mouth. To determine the correct symbol to be inserted between 8764 and 4720, remember that the crocodile always wants to eat the larger number.	The crocodile opens its mouth to eat the larger number. $8764 > 4720$
3. The correct number sentence should read '8764 is greater than 4720'. Write the correct statement.	$8764 > 4720$

on Resources

eWorkbook	Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)
Digital documents	SkillSHEET Place value (doc-6409)
	SkillSHEET Ascending and descending order (doc-6410)
Interactivities	Individual pathway interactivity: Place value (int-4311)
	Place value (int-3921)

Exercise 1.2 Place value

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 9, 10, 13, 16, 17, 19, 22, 25	2, 5, 8, 11, 14, 18, 20, 23, 26	3, 6, 12, 15, 21, 24, 27

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 Write the following numbers in expanded form.
   a. 925 b. 28 469 c. 800 002 d. 1 080 100
2. Write the following numbers in words.
   a. 765 b. 9105 c. 90 450 d. 100 236
3. Write each of the following as a numeral.
   a. Four hundred and ninety-five
   b. Two thousand, six hundred and seventy
   c. One hundred and nine thousand, six hundred and five
4. Using words, write the value of the 4 in the distance to Yancannia.



5. Using words, write the value of the 2 in the distance to Esperance.



6. Using words, write the value of the 0 in the distance to Katherine.



7. Using words, write the value of the 3 in the distance to Coober Pedy.



8. Using words, write the value of the 5 in the distance to Alice Springs.



Understanding

9. MC Select the largest of the following numbers.
   A. 4884 B. 4488 C. 4848 D. 4844 E. 4888

10. MC Select the smallest of the following numbers.
    A. 4884 B. 4488 C. 4848 D. 4844 E. 4888

11. WE2 Write the following numbers in descending order.
    8569, 742, 48 987, 28, 647

12. Rearrange the following numbers so that they are in descending order.
    47 890, 58 625, 72 167, 12 947, 32 320

13. Organise the following numbers into descending order.
    6477, 7647, 7476, 4776, 6747

14. Change the order of the following numbers to put them in descending order.
    8088, 8800, 8080, 8808, 8008, 8880

15. Write the following numbers in ascending order.
    58, 9, 743, 68 247, 1 258 647

16. Rearrange the following numbers so that they are in ascending order.
    78 645, 58 610, 60 000, 34 108, 84 364

17. Organise the following numbers into ascending order.
    9201, 2910, 1902, 9021, 2019, 1290

18. Change the order of the following numbers so that they are in ascending order.
    211, 221, 212, 1112, 222, 111

19. WE3 Copy and complete the following number sentences by placing the < or > symbol in each box.

a. 345 ☐ 567 **b.** 89 ☐ 98 **c.** 234 596 ☐ 23 459 **d.** 7765 ☐ 7756

20. We can use the abbreviation K to represent $1000. For example, $50 000 can be written as $50K. Using this rule, determine what amounts each of the following represent.

a. $6K **b.** $340K **c.** $58K

21. Write the following using K as an abbreviation, as shown in **Question 20**.

a. $430 000 **b.** $7000 **c.** $800 000

Reasoning

22. Determine the largest five-digit number you can write if each digit must be different and no digit may be prime. Show your working.

23. A new mobile phone company is investigating the habits of phone users. From the following sample of phone calls, determine the most common length of call. Start by rounding each call time to the nearest half-minute (30 seconds).

132 s	10 s	43 s	71 s	243 s	52s
142 s	332 s	6 s	38 s	63 s	32 s
132 s	32 s	43 s	52 s	352 s	101 s
124 s	28 s	153 s	10 s	243 s	34 s

24. Astronomers and other scientists use scientific notation when working with very large or very small numbers. For example, the 'astronomical unit' (AU) is the average distance of the Earth from the Sun; it is equal to 150 million km or 1.5×10^{13} cm. Explain why scientists use scientific notation.



Problem solving

25. Determine how many two-digit numbers you can make using the digits 1 and 2 if:

a. you are not allowed to repeat any digits
b. you can repeat the digits.

26. Determine how many three-digit numbers you can make using the digits 1, 2 and 3 if:

a. you are not allowed to repeat any digits
b. you can repeat the digits.

Explain whether there is a relationship between the initial number of digits and the number of arrangements when:

c. repetition is not allowed
d. repetition is allowed.

27. Without actually counting to one million, determine a way of estimating the time it would take to count out loud from 0 to 1 000 000.

1.3 Strategies for adding and subtracting positive integers

LEARNING INTENTION

At the end of this subtopic you should be able to:

- add and subtract positive integers using mental strategies.

eles-3645

1.3.1 Mental strategies for addition

- Mental strategies for addition are different ways to add up large numbers or integers in your head without a calculator.
- There are lots of different methods that can help you add 2- and 3-digit numbers in your head.

Jump strategy for addition

- The jump strategy for addition involves breaking the number being added into smaller parts.


  For example:

$$535 + 87 =$$

Break 87 into 80 and 7.

$$535 + 80 = 615$$

$$615 + 7 = 622$$



Split strategy for addition

- The split strategy for addition involves splitting both numbers being added into their expanded forms and then adding the parts that have the same place value.

  For example:

$$165 + 432 =$$

Split 165 into 1 hundred, 6 tens and 5 ones: $165 = 100 + 60 + 5$

Split 432 into 4 hundreds, 3 tens and 2 ones: $432 = 400 + 30 + 2$

$$\begin{aligned} 165 + 432 &= 100 + 60 + 5 + 400 + 30 + 2 \\ &= 100 + 400 + 60 + 30 + 5 + 2 \\ &= 500 + 90 + 7 \\ &= 597 \end{aligned}$$

WORKED EXAMPLE 4 Using mental strategies to add numbers

a. Calculate 514 + 88 using the jump strategy.
b. Calculate 759 + 412 using the split strategy.

THINK	WRITE
a. 1. Write the question.	$514 + 88$
2. Break 88 into 80 plus 8.	$88 = 80 + 8$
3. Add 80 to 514 to get 594.	$514 + 80 = 594$
4. Add 8 to 594 to get 602.	$594 + 8 = 602$
5. Write the answer.	$514 + 88 = 602$
b. 1. Write the question.	$759 + 412$
2. Split each number up by writing it in expanded form.	$759 = 700 + 50 + 9$ $412 = 400 + 10 + 2$
3. Add the numbers with the same place value together.	$700 + 400 + 50 + 10 + 9 + 2 = 1100 + 60 + 11$ $= 1171$
4. Write the answer.	$759 + 412 = 1171$

Compensation strategy for addition

- The compensation strategy for addition involves making one of the numbers being added larger by rounding up to the nearest ten or hundred, completing the addition, and then subtracting the added amount.

  For example:

$$243 + 78 =$$

1. Round 78 up to 80.

$$243 + 80 = 323$$

2. Now subtract 2, since 78 was rounded up to 80 by adding 2.

$$323 - 2 = 321$$

Rearrange strategy for addition

- The rearrange strategy for addition involves rearranging the numbers being added to form numbers that add up to multiples of 10.

  For example:

$$16 + 17 + 14 =$$

Swap the order and add 16 and 14 first, since this will result in a multiple of 10.

$$16 + 14 + 17 =$$

$$30 + 17 = 47$$

WORKED EXAMPLE 5 Using mental strategies to add numbers

a. Calculate 576 + 86 using the compensation strategy.
b. Calculate 38 + 13 + 22 using the rearrange strategy.

THINK	WRITE
a. 1. Write the question.	576 + 86
2. Round 86 up to the nearest 10.	86 becomes 90 when rounded up by adding 4.
3. Add 576 to the rounded-up number (90).	576 + 90 = 666
4. Subtract 4, since 86 was rounded up to 90 by adding 4.	666 − 4 = 662
5. Write the answer.	576 + 86 = 662
b. 1. Write the question.	38 + 13 + 22
2. Rearrange the numbers so that a multiple of 10 can be formed. 38 + 22 = 60, so add these numbers first.	= 38 + 22 + 13 = 60 + 13
3. Add 13 to 60.	= 73
4. Write the answer.	38 + 13 + 22 = 73

WORKED EXAMPLE 6 Using mental strategies to add numbers

Calculate 713 + 143 using an appropriate mental strategy.

THINK	WRITE
1. Write the question.	713 + 143
2. Select a strategy. Since the numbers are both large numbers, it may be easiest to split them up.	Split strategy
3. Use the strategy to add numbers. • Write each number in expanded form. • Add numbers with the same place values. • Complete the final addition.	713 = 700 + 10 + 3 143 = 100 + 40 + 3 700 + 100 + 10 + 40 + 3 + 3 = 800 + 50 + 6 = 856
4. Write the answer.	713 + 143 = 856

eles-3646

1.3.2 Mental strategies for subtraction

- Mental strategies for subtraction are different ways to subtract numbers without doing lots of working.
- There are lots of different methods that can help you subtract two- and three-digit numbers in your head.

Jump strategy for subtraction

- The jump strategy for subtraction is like the jump strategy for addition, but you jump backward instead of forward.
- The number being subtracted is broken into smaller parts and then each part is subtracted one by one.

For example:


$$635 - 127 =$$

Break 127 into 100, 20 and 7.

$$635 - 100 = 535$$

$$535 - 20 = 515$$

$$515 - 7 = 508$$



Adding up to find the difference

- Sometimes, even though you are subtracting, it can be helpful to use addition when trying to subtract numbers mentally.
- Start with the smaller number and add to that number in parts until you get to the larger number.

For example:

$$672 - 613 =$$

$$613 + 7 = 620$$
$$620 + 50 = 670$$
$$670 + 2 = 672$$

The numbers added are 7, 50 and 2, which give a total of 59.

Therefore $672 - 613 = 59$.

WORKED EXAMPLE 7 Using mental strategies to subtract numbers

Calculate the following.

a. 854 – 84 using the jump strategy.

THINK	WRITE
a. 1. Write the question.	$854 - 84$
2. Break 84 into 80 plus 4.	$84 = 80 + 4$
3. Subtract 80 from 854 to get 774.	$854 - 80 = 774$
4. Subtract 4 from 774 to get 770.	$774 - 4 = 770$
5. Write the answer.	$854 - 84 = 770$

b. 436 – 381 using the adding strategy.

THINK	WRITE
b. 1. Write the question.	$436 - 381$
2. Starting at the smaller number, determine what needs to be added to get to the larger number.	$381 + 9 = 390$ $390 + 40 = 430$
3. Add up all the parts.	$430 + 6 = 436$
4. Write the answer.	$9 + 40 + 6 = 55$ $436 - 381 = 55$

Compensation strategy for subtraction

- The compensation strategy for subtraction is like the compensation strategy for addition, except that you will round up the number being subtracted to the nearest ten or hundred and then add the amount used to do the rounding up.

  For example:

$$94 - 49 =$$

Round up 49 to 50 by adding 1.

$$94 - 50 = 44$$

Add 1 to the answer, since 49 was rounded up to 50 by adding 1.

$$44 + 1 = 45$$

$$94 - 49 = 45$$

WORKED EXAMPLE 8 Using the compensation strategy to subtract numbers

Calculate 174 – 38 using the compensation strategy.

THINK	WRITE
1. Write the question.	$174 - 38$
2. Round 38 up to the nearest 10 by adding 2.	38 becomes 40.
3. Subtract 40 from 174.	$174 - 40 = 134$
4. Add 2 since, 38 was rounded up to 40 by adding 2.	$134 + 2 = 136$
5. Write the answer.	$174 - 38 = 136$

Checking subtraction by adding

Remember, a subtraction can always be checked by adding the two smaller numbers to see if they add up to the larger number.

DISCUSSION

What techniques have you used to mentally add numbers? What shortcuts have you used?

on Resources

eWorkbook	Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)
Digital document	SkillSHEET Adding and subtracting whole numbers less than 20 (doc-6411)
Interactivity	Individual pathway interactivity: Strategies for adding and subtracting positive integers (int-8731)

Exercise 1.3 Strategies for adding and subtracting positive integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 7, 12, 13, 16	3, 6, 8, 11, 14, 17	4, 9, 10, 15, 18

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE4a Use the jump strategy to calculate the following.
   a. $143 + 85$ b. $1537 + 266$
2. WE4b Use the split strategy to calculate the following.
   a. $645 + 261$ b. $370 + 78$
3. WE5a Use the compensation strategy to calculate the following.
   a. $471 + 89$ b. $74 + 28$
4. WE5b Use the rearrange strategy to calculate the following.
   a. $27 + 36 + 23$ b. $14 + 34 + 16$

Understanding

5. State whether the following statement is true or false. Show your working.
   $346 + 451$ calculated using the split strategy becomes $300 + 400 + 40 + 50 + 6 + 1$.
6. MC $56 + 12 + 14$ is equal to:
   A. 60 B. 82 C. 70 D. 92 E. 72
7. WE6 Calculate $421 + 54 + 372$ using an appropriate mental strategy.
8. WE7a Use the jump strategy to calculate the following.
   a. $88 - 43$ b. $674 - 323$
9. WE7b Add up the difference to calculate the following.
   a. $351 - 287$ b. $79 - 46$
10. WE8 Use the compensation strategy to calculate the following.
    a. $65 - 48$ b. $956 - 729$
11. Calculate $953 - 675$ using an appropriate mental strategy.
12. Fill in the gaps for the following sentences.
    a. All the numbers in the 5-times table end in _____ or _____.
    b. The numbers in the _____-times tables all end in 0.

Reasoning

13. A student calculates $145 + 671 - 472$. They give their answer as 344. State whether you agree with their answer. Explain your response.

14. A student has shown the following working on a test.

$$641 + 357 = 600 + 10 + 4 + 300 + 70 + 5 = 989$$

a. Determine where the student made an error.
b. Determine the correct answer.

15. Twenty children were playing in the playground. Eight of the children left for home, then six more children came to the playground. Determine how many children are in the playground now. Show your working.

Problem solving

16. There are 763 students at a senior school campus. Of these, 213 students are currently completing exams. Calculate how many students are not completing exams.

17. Harriet has $243 in savings. She adds $93 to her savings account. The next day she spends $175 from her account. Determine how much is left in her savings account.

18. The sum of two numbers is 19 and their difference is 7. Evaluate the two numbers.

1.4 Algorithms for adding and subtracting positive integers

LEARNING INTENTION

At the end of this subtopic you should be able to:
- add and subtract positive integers using algorithms.

1.4.1 Addition of positive integers using algorithms

eles-3647

- To add numbers or positive integers, write them in columns according to place value and then add them, starting at the ones column.
- The **sum** is the result obtained when numbers are added together.

WORKED EXAMPLE 9 Adding integers in columns

Arrange these numbers in columns, then add them.

$$\mathbf{1462 + 78 + 316}$$

THINK

1. Set out the numbers in columns according to place value.
2. Add the digits in the ones column in your head ($2 + 8 + 6 = 16$). Write the 6 in the ones column of your answer and carry the 1 to the tens column, as shown in the plum colour.
3. Add the digits in the tens column ($1 + 6 + 7 + 1 = 15$). Write the 5 in the tens column of your answer and carry the 1 to the hundreds column, as shown in pink.

WRITE

	Thousands	Hundreds	Tens	Ones
	1	$^{1}4$	$^{1}6$	2
			7	8
+		3	1	6
	1	8	5	6

4. Add the digits in the hundreds column ($1 + 4 + 3 = 8$). Write 8 in the hundreds column of your answer, as shown in pink. There is nothing to carry.
5. There is only a 1 in the thousands column. Write 1 in the thousands column of your answer.
6. State the answer.

The sum of 1462, 78 and 316 is 1856.

WORKED EXAMPLE 10 Adding by making a multiple of 10

Perform the addition $27 + 19 + 141 + 73$ by finding suitable pairs of numbers to make multiples of 50.

THINK	WRITE
1. Write the question.	$27 + 19 + 141 + 73$
2. Look for pairs of numbers that can be added to make a multiple of 10. Reorder the sum, pairing these numbers.	$= (27 + 73) + (141 + 19)$
3. Add the number pairs.	$= 100 + 160$
4. Complete the addition.	$= 260$

eles-3648

1.4.2 Commutative and associative laws for addition

- The **Commutative Law for addition** means that you can add numbers in any order. For example, $3 + 4$ gives the same result as $4 + 3$.
- The **Associative Law for addition**, simply stated, means that the order in which additions are calculated is not important and does not change the result. For example, $2 + 3 + 7$ could be calculated as $5 + 7 = 12$ or $2 + 10 = 12$
  This is a very useful property when performing mental calculations.

ACTIVITY: There's something about Gauss

In the late 1780s, a German teacher gave his class the task of adding the numbers from 1 to 100. One student came up with the correct answer in less than a minute. That student, Johann Carl Friedrich Gauss, used grouping in pairs to work out the sum. He paired the smallest number with the largest number, then the second smallest with the second largest, and so on. Gauss went on to become one of the world's most famous mathematicians.

Try the technique that Gauss used with the numbers from 1 to 10, then 1 to 20, then 1 to 50 and finally 1 to 100. Did you notice any patterns?



eles-3649

1.4.3 Subtraction of positive integers using algorithms

- Subtraction is the opposite (or 'inverse') of addition. To work out 800 – 360 you could ask the question, 'What do I need to add to 360 to get 800?' The answer is 440.
- The **difference** is the result when one number is subtracted from another number. For example, the difference between 800 and 360 is 440.
- One of the main differences between addition and subtraction is the fact that the order in which you subtract numbers is very important. For example, 6 – 3 does not give the same result as 3 – 6.
- This means that subtraction is neither commutative nor associative.

Subtraction of positive integers with no borrowing

- To subtract two numbers, write them in columns according to their place values and then subtract each column in order, starting with the ones column.

WORKED EXAMPLE 11 Subtracting numbers without borrowing

Perform the subtraction 395 – 174.

THINK

1. Set out the difference in columns according to place value.

WRITE

	Hundreds	Tens	Ones
	3	9	5
–	1	7	4

2. Subtract the digits in the ones column (5 – 4 = 1). Write the 1 in the ones column of your answer.

	3	9	5
–	1	7	4
			1

3. Subtract the digits in the tens column (9 – 7 = 2). Write the 2 in the tens column of your answer.

	3	9	5
–	1	7	4
		2	1

4. Subtract the digits in the hundreds column (3 – 1 = 2). Write the 2 in the hundreds column of your answer.

	3	9	5
–	1	7	4
	2	2	1

5. State the answer.

The difference between 395 and 174 is 221.

Not all subtraction problems are as simple as the one shown in Worked example 11. For example, working out 32 – 14 requires a different approach because you can't subtract 4 from 2 in the ones column. A subtraction like this requires borrowing.

	3	2
–	1	4
		?


Subtraction of positive integers with borrowing

- The most common method of subtraction is to use borrowing, which is called the **decomposition method**.
- It's called 'decomposition' because the larger number is decomposed, or taken apart.
- A visual representation of the decomposition method is shown here to help you understand how it works.

Visual representation of subtracting using decomposition

Evaluate 32 – 14.


1. Decompose each number by breaking it up into place value parts (tens and ones in this case).




2. Since we can't take 4 ones from 2 ones, we instead borrow a block of 10 and split them into ones.

3. Rewrite 32 as 2 tens and 12 ones.
Note: Effectively we have borrowed a ten from the tens column and given it to the ones column so that we can work out the subtraction.

Borrowing step:



4. We can now complete the subtraction.
   - Subtracting the ones first gives:
     12 – 4 = 8 ones
   - Subtracting the tens next gives:
     2 – 1 = 1 ten
   - This gives us 1 ten and 8 ones left over after the subtraction.
   - This is the same as 18 individual blocks.



5. State the answer.

32 – 14 = 18

Algorithmic approach to subtraction using decomposition

The subtraction 32 – 14 can be solved more formally using the following algorithm (set of steps).

1. Set out the difference in columns according to place value.

$$\begin{array}{r} 3\ \ 2 \\ -\ 1\ \ 4 \\ \hline \\ \hline \end{array}$$

2. Because 4 can't be subtracted from 2, take one 10 from the tens column of the larger number and add it to the ones column of the same number. So 2 becomes 12, and the 3 tens become 2 tens.

$$\begin{array}{r} {}^{2}\not{3}\ \ {}^{1}2 \\ -\ 1\ \ 4 \\ \hline 1\ \ 8 \\ \hline \end{array}$$

3. Subtract 4 units from 12 units (12 – 4 = 8).
4. Subtract 1 ten from the remaining 2 tens (2 – 1 = 1).
5. Write the answer.

32 – 14 = 18

WORKED EXAMPLE 12 Subtracting numbers using decomposition

Subtract the following:

a. 6892 – 467 **b. 3000 – 467**

THINK

a. 1. Since 7 cannot be subtracted from 2, take one ten from the tens column of the larger number and add it to the units column of the same number. The 2 becomes 12 and the 9 tens become 8 tens.

2. Subtract the 7 units from the 12 units (12 – 7 = 5).

3. Subtract 6 tens from the 8 remaining tens (8 – 6 = 2).

4. Subtract 4 hundreds from the 8 hundreds (8 – 4 = 4).

5. Subtract 0 thousands from the 6 thousands (6 – 0 = 6).

6. State the answer.

WRITE

a.

$$\begin{array}{r} 6\ {}^{8}\not{8}\ {}^{1}\not{9}\ {}^{1}2 \\ -\ \ 4\ 6\ 7 \\ \hline 6\ 4\ 2\ 5 \\ \hline \end{array}$$

6892 – 467 = 6425

b. 1. Since 7 cannot be taken from 0, 0 needs to become 10.

2. We cannot take 10 from the tens column because it is also 0. The first column that we can take anything from is the thousands, so 3000 is decomposed to 2 thousands, 9 hundreds, 9 tens and 10 units.

3. Subtract the units (10 – 7 = 3).

4. Subtract the tens (9 – 6 = 3).

5. Subtract the hundreds (9 – 4 = 5).

6. Subtract the thousands (2 – 0 = 2).

7. State the answer.


b.

$$\begin{array}{r} {}^{2}\not{3}\ {}^{9}\not{0}\ {}^{9}\not{0}\ {}^{1}0 \\ -\ \ \ 4\ 6\ 7 \\ \hline \ \ 2\ 5\ 3\ 3 \\ \hline \end{array}$$


3000 – 467 = 2533

Digital technology

Scientific calculators can evaluate sums of two or more numbers.



Scientific calculators can evaluate differences between two numbers.



Resources

eWorkbook Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)

Interactivities Individual pathway interactivity: Algorithms for adding and subtracting positive integers (int-8732)
Addition of positive integers (int-3922)
Subtraction of positive integers (int-3924)

Exercise 1.4 Algorithms for adding and subtracting positive integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 6, 9, 12, 13, 18, 22, 25	3, 5, 7, 14, 15, 17, 19, 23, 26	4, 8, 10, 11, 16, 20, 21, 24, 27, 28

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Answer these questions by doing the working in your head.

a. $7 + 8$ **b.** $20 + 17$ **c.** $195 + 15$
d. $227 + 13$ **e.** $1000 + 730$

2. Answer these questions by doing the working in your head.

a. $17\,000 + 1220$ **b.** $125\,000 + 50\,000$ **c.** $2 + 8 + 1 + 9$
d. $6 + 8 + 9 + 3 + 2 + 4 + 1 + 7$ **e.** $12 + 5 + 3 + 7 + 15 + 8$


3. Add the following numbers, setting them out in columns as shown. Check your answers using a calculator.

a.
$$\begin{array}{r} 34 \\ +\ 65 \\ \hline \end{array}$$

b.
$$\begin{array}{r} 68\,069 \\ 317 \\ 8 \\ +\ 4254 \\ \hline \end{array}$$

c.
$$\begin{array}{r} 399 \\ 1489 \\ 2798 \\ +\ 8943 \\ \hline \end{array}$$

4. **WE9** Arrange the following numbers in columns, then add them.



   a. $137 + 841$
   b. $149 + 562 + 55$
   c. $376 + 948 + 11$
   d. $8 + 12\,972 + 59 + 1423$
   e. $1700\,245 + 378 + 930$

   Check your answers with a calculator.

5. **WE10** Mentally perform each of the following additions by pairing suitable numbers together.

   a. $56 + 87 + 24 + 13$
   b. $74 + 189 + 6 + 11$
   c. $98 + 247 + 305 + 3 + 95 + 42$
   d. $180 + 364 + 59 + 141 + 47 + 20 + 16$

6. Answer the following questions without using a calculator.

   a. $11 - 5$
   b. $53 - 30$
   c. $100 - 95$
   d. $150 - 25$
   e. $1100 - 200$

7. Work out the following without using a calculator.

   a. $1700 - 1000$
   b. $100 - 20 - 10$
   c. $1000 - 50 - 300 - 150$
   d. $24 - 3 - 16$
   e. $54 - 28$

8. Calculate the following.

   a. $10 + 8 - 5 + 2 - 11$
   b. $40 + 15 - 35$
   c. $120 - 40 - 25$
   d. $15 + 45 + 25 - 85$
   e. $100 - 70 + 43$
   f. $1000 - 400 + 250 + 150 + 150$

9. **WE11&12** Work out the following subtractions.

   a. $167 - 132$
   b. $47\,836 - 12\,713$
   c. $642\,803 - 58\,204$

Understanding

10. Solve the following subtractions.
   a. $664 - 397$
   b. $12\,900 - 8487$
   c. $69\,000 - 3561$
   d. $2683 - 49$

   Check your answers using a calculator.

11. Work out the following subtractions.
   a. $70\,400 - 1003$
   b. $27\,321 - 25\,768$
   c. $812\,741 - 462\,923$
   d. $23\,718\,482 - 4\,629\,738$


   Check your answers using a calculator.

12. Hella was performing in a ballet and needed to buy a tutu, ballet shoes and white tights. Based on the prices shown in the photograph, calculate how much she spent in total on her costume.




13. A print dictionary is split into two volumes. There are 1544 pages in the A–K volume and 1488 pages in the L–Z volume. Calculate how many pages the dictionary has in total.

14. Nathan has taken his sister and her friends to lunch for her birthday. Determine what the total cost of the items shown will be.




15. Of all the world's rivers, the Amazon in South America and the Nile in Africa are the two longest. The Amazon is 6437 kilometres in length and the Nile is 233 kilometres longer than the Amazon. Calculate the length of the Nile.


16. An **arithmagon** is a triangular figure in which the two numbers at the end of each line add to the number along the line, like in the example shown. Solve each of these arithmagons.




a.



b.



c.



17. The following photographs show three of the highest waterfalls in the world. Determine how much higher:

a. Victoria Falls is than Iguazu Falls
b. Iguazu Falls is than Niagara Falls
c. Victoria Falls is than Niagara Falls.




18. Prithvi received a box of 36 chocolates. They ate 3 on Monday, 11 on Tuesday and gave 7 away on Wednesday. Calculate how many they had left.

19. A crowd of 24 083 attended an NRL match between Canterbury-Bankstown Bulldogs and St George Illawarra Dragons. If 14 492 people supported the Bulldogs and the rest supported the Dragons, calculate how many supporters the Dragons had.

20. A school bus left Laurel High School with 31 students aboard. Thirteen of these passengers disembarked at Hardy Railway Station. The bus collected 24 more students at Hardy High School and a further 11 students disembarked at Laurel Swimming Pool. Calculate how many students were still on the bus.

21. Shu-Ling and Ty were driving from Melbourne to Sydney for a holiday. The distance between Melbourne and Sydney via the Hume Highway is 867 kilometres, but they chose the more scenic Princes Highway even though the distance is 1039 kilometres. They drove to Lakes Entrance on the first day (339 kilometres), a further 347 kilometres to Narooma on the second day, and arrived in Sydney on the third day.



a. Calculate how much further it is from Melbourne to Sydney via the Princes Highway than via the Hume Highway.

b. Determine how far Shu-Ling and Ty travelled on the third day.

Reasoning

22. Fill in the missing numbers. The * can represent any digit.

a.
$$\begin{array}{r} 6*8*2* \\ -4884\,17 \\ \hline *4999*4 \end{array}$$


b.
$$\begin{array}{r} 3*9* \\ -*6*5 \\ \hline 1*07 \end{array}$$

23. In less than 10 seconds, without using a calculator, calculate the answer to $6\,849\,317 - 999\,999$. Explain how you reached your answer.

24. A beetle has fallen into a hole that is 15 metres deep. It is able to climb a distance of 3 metres during the day, but at night the beetle is tired and must rest. However, during the night it slides back 1 metre. How many days will it take the beetle to reach the top of the hole to freedom? Explain your answer.

Problem solving

25. Five termites start munching through a log.
Pixie is 19 mm ahead of Bitsie.
Trixie is 5 mm ahead of Mixie.
Mixie is twice as far ahead as Itsie.
Itsie is 10 mm behind Bitsie.
Mixie has eaten through 52 mm.
Determine which termite has eaten the most. Show your working.



26. In a class of 22 students, each attends swimming practice or lifesaving, or both. If 16 students attend swimming practice and 9 attend lifesaving, work out how many attend both.



27. Zaina works in a restaurant where people work from Monday to Friday, on weekends only, or from Monday to Sunday. There are 15 employees at the restaurant. If 13 employees work every Monday and 14 employees work every Sunday, evaluate how many employees do not work from Monday to Sunday.

28. There are 20 chocolate bars on the table all containing only fruit, only nuts, or fruit and nuts together. If 12 chocolate bars contain nuts and 14 chocolate bars contain fruit, evaluate the number of chocolate bars that contain both fruit and nuts.

1.5 Multiplying positive integers

LEARNING INTENTION

At the end of this subtopic you should be able to:

- multiply positive integers using mental strategies and algorithms.

1.5.1 Multiplying positive integers


eles-3650

- **Multiplication** is a short way of performing repeated addition of the same number.
  For example, $3+3+3+3+3$ represents 5 groups of 3 and can be written as 5×3.
- The **product** is the answer you get when numbers are multiplied.
  For example, the product of 5 and 3 is 15 because $5 \times 3 = 15$.
- Multiplication is commutative because the order in which numbers are multiplied is not important.
  For example, $3 \times 8 = 8 \times 3$.

Multiplying using diagrams


- The following diagram shows 2 groups of balls with 4 balls in each group. There are 8 balls in total. This can be written as a multiplication.

$$2 \times 4 = 8$$



- Instead, what if we looked at the picture as 4 groups of balls with 2 balls in each group? Would we get the same answer? Count the balls and see. There are still 8 balls in total.

$$4 \times 2 = 8$$



Multiplying two numbers

When two numbers are multiplied, the order does not matter; the answer will be the same.

WORKED EXAMPLE 13 Using a diagram to multiply numbers


a. Draw a diagram to show 2×6. **b. State what 2×6 is equal to.**

THINK

a. Draw a diagram with 2 groups of 6.

WRITE/DRAW

Group 1 Group 2



b. Count how many circles there are altogether. There are 12 circles.

c. Write the answer. $2 \times 6 = 12$

- To multiply small numbers, we learn the times tables. We can also use diagrams.
- To multiply larger numbers, we need to use other methods. These methods are discussed later in this topic.


Multiplying using expanded form

- In this method of multiplication the larger number being multplied is broken up into expanded form first, then each component is multiplied by the smaller number.
  For example, here is how the expanded form can be used to calculate 215×4.
  The expanded form of $215 = 200 + 10 + 5$

$$\begin{aligned} 215 \times 4 &= (200 \times 4) + (10 \times 4) + (5 \times 4) \\ &= 800 + 40 + 20 \\ &= 860 \end{aligned}$$

Multiplying using the area mode

- The area model of multiplication involves using the expanded form of the larger number and constructing rectangles for each component, arranged according to place value.
  This diagram shows how to calculate 215×4 using an area model. (*Note:* This graph is not drawn to scale.)



1.5.2 The short multiplication algorithm

eles-3651

- The short multiplication algorithm can be used when multiplying a large number by a single digit number.
- Start by lining up the numbers in columns, with one number under the other number. Place the larger number on top.
- Next, multiply each place value in the larger number by the smaller number, starting with the units column.
- Write the answer to each multiplication underneath the smaller number in the appropriate column.
- If an answer has two place values, carry the larger place value to the next column on the left and add it to the result of the next multiplication.

$$\begin{array}{r} {\scriptstyle 2} \\ 215 \\ \times\ \ 4 \\ \hline 860 \end{array}$$

1. $5 \times 4 = 20$
2. Write the 0 in the units column and carry the 2 over to the tens column.
3. Perform the next multiplication and add the carried number to the result.
   $1 \times 4 = 4;\ 4 + 2 = 6$
4. Write the 6 in the tens column.
5. $2 \times 4 = 8$
6. Write the 8 in the hundreds column.

WORKED EXAMPLE 14 Multiplying using short multiplication

Calculate 1456×5.

THINK	WRITE
1. Write the numbers in columns according to place value, with the larger number on top.	$\begin{array}{r} 1\ 4\ 5\ 6 \\ \times\ \ \ \ 5 \\ \hline \\ \hline \end{array}$
2. Multiply the units by 5 ($5 \times 6 = 30$). Write down the 0 and carry the 3 to the tens column. 3. Multiply the tens by 5 and add the carried number ($5 \times 5 = 25; 25 + 3 = 28$). Write the 8 in the tens column and carry the 2 to the hundreds column. 4. Multiply the hundreds by 5 and add the carried number ($5 \times 4 = 20; 20 + 2 = 22$) .. Write the last 2 in the hundreds column and carry the other 2 to the thousands column. 5. Multiply the thousands by 5 and add the carried number ($5 \times 1 = 5;\ 5 + 2 = 7$). Write 7 in the thousands column of the answer.	$\begin{array}{r} {}^{2}1{}^{2}4{}^{3}5\ \ 6 \\ \times\ \ \ \ 5 \\ \hline 7\ 2\ 8\ 0 \end{array}$
6. Write the answer.	$1456 \times 5 = 7280$

1.5.3 The long multiplication algorithm

eles-3652

- The long multiplication algorithm is used to multiply numbers that both have more than one digit. The process is the same as that for short multiplication, but it is repeated for each additional digit.
- When multiplying two numbers that both have more than one digit, a 0 is added in the second row.

WORKED EXAMPLE 15 Multiplying whole numbers

Evaluate the following.

a. 547×6

b. 35×62

THINK	WRITE
a. 1. Set up the multiplication in columns, with the smaller number on the bottom.	$\begin{array}{r} 547 \\ \times\ 6 \\ \hline \end{array}$
2. Multiply each digit in 547 by 6. • $7 \times 6 = 42$. Write 2 and carry 4. • $4 \times 6 + 4 = 28$. Write 8 and carry 2. • $5 \times 6 + 2 = 32$. Write 32.	$\begin{array}{r} {}^{2}5^{4}4\ 7 \\ \times\ 6 \\ \hline 3\ 2\ 8\ 2 \end{array}$
3. Write the answer.	$547 \times 6 = 3282$
b. 1. Set up the multiplication in columns.	$\begin{array}{r} 35 \\ \times\ 62 \\ \hline \end{array}$
2. Multiply 35 by 2. • $5 \times 2 = 10$. Write 0 and carry 1. • $3 \times 2 + 1 = 7$. 6+1= 7. Write 7.	$\begin{array}{r} {}^{1}3\ 5 \\ \times\ 6\ 2 \\ \hline 7\ 0 \end{array}$
3. Add a 0 to the second row because you are multiplying by a number in the tens column.	$\begin{array}{r} {}^{3}3\ 5 \\ \times\ 6\ 2 \\ \hline 7\ 0 \\ 2\ 1\ 0 \end{array}$
4. Multiply 35 by 6. • $5 \times 6 = 30$. Write 0 and carry 3. • $3 \times 6 + 3 = 21$. Write 21.	$\begin{array}{r} {}^{3}3\ 5 \\ \times\ 6\ 2 \\ \hline 7\ 0 \end{array}$
5. Add 70 and 2100 to get the answer.	$\begin{array}{r} +2\ 1\ 0\ 0 \\ \hline 2\ 1\ 7\ 0 \end{array}$
6. Write the answer.	$35 \times 62 = 2170$

WORKED EXAMPLE 16 Multiplying using long multiplication

Calculate 1456×132 using long multiplication.


THINK	WRITE
1. Set the product up in columns according to place value, writing the larger number on top.	$\begin{array}{r} 1456 \\ \times\ 132 \\ \hline \end{array}$
2. Multiply the larger number by the units digit in the smaller number using short multiplication ($1456 \times 2 = 2912$). Write the answer directly below the problem.	$\begin{array}{r} {}^{1}1{}^{1}4{}^{1}56 \\ \times\ 132 \\ \hline 2912 \end{array}$
3. Place a zero in the units column, as shown in pink, when multiplying the larger number by the tens digit of the smaller number ($1456 \times 3 = 4368$) This is because you are really working out $1456 \times 30 = 43\,680$. Write the answer directly below the previous answer.	$\begin{array}{r} {}^{1}1{}^{1}4{}^{1}56 \\ \times\ 132 \\ \hline 2912 \\ 43680 \end{array}$
4. Place zeros in the units and tens columns, as shown in pink, when multiplying the larger number by the hundreds digit of the smaller number ($1456 \times 1 = 1456$). This is because you are really working out $1456 \times 100 = 145\,600$. Write the answer directly below the previous answer.	$\begin{array}{r} 1456 \\ \times\ 132 \\ \hline 2912 \\ 43680 \\ +145600 \\ \hline 192192 \end{array}$
5. Add the numbers in each column of the three rows to determine the answer.	
6. Write the answer.	$1456 \times 132 = 192\,192$

- The **Distributive Law** applies only to multiplication. It states that $a(b + c) = ab + ac$. The Distributive Law helps with mental calculation because it means, for example, that 8×13 can be thought of as:

$$\begin{aligned} 8 \times 13 &= 8 \times (3 + 10) \\ &= 8 \times 3 + 8 \times 10 \\ &= 24 + 80 \\ &= 104 \end{aligned}$$

Digital technology

Scientific calculators can evaluate the multiplication of large numbers.



1.5.4 Mental strategies for multiplication

eles-4838

- In many cases it is not practical to use pen and paper (or even a calculator) to perform multiplication.
- There are mental strategies that can make multiplication easier.
- Multiplication is associative — this means smaller numbers can be paired up for multiplication.
  For example, $\begin{aligned} 2 \times 17 \times 5 &= 17 \times (2 \times 5) \\ &= 17 \times 10 \\ &= 170 \end{aligned}$
  This calculation has been simplified by finding the pair of numbers that multiply to equal 10.

WORKED EXAMPLE 17 Using mental strategies for multiplication

Use mental strategies to calculate $4 \times 23 \times 25$.

THINK	WRITE
1. Write the question.	$4 \times 23 \times 25$
2. Look for a number pair that makes a simpler multiplication and rearrange. $4 \times 25 = 100$, and multiplying by 100 is simpler than multiplying by either 4 or 25.	$= 23 \times (4 \times 25)$
3. Mentally calculate 4×25.	$= 23 \times 100$
4. Mentally calculate the final answer.	$= 2300$

WORKED EXAMPLE 18 Using mental strategies for multiplication

Use a mental strategy to calculate 34×200.

THINK	WRITE
1. Write the question.	34×200
2. Write 200 as 2×100.	$= 34 \times 2 \times 100$
3. Mentally calculate 34×2.	$= 68 \times 100$
4. Mentally calculate 68×100.	$= 6800$

Multiplying multiples of 10 or 100

If both numbers are **multiples** of 10, 100 and so on, ignore the zeros, multiply the remaining numbers, then add the total number of zeros to the answer.

For example, $900 \times 6000 = 5\,400\,000$.

- Consider the multiplication 9×58. This multiplication can be regarded as $10 \times 58 - 1 \times 58$. Using this way of writing the multiplication, the answer can be mentally calculated by multiplying 58 by 10 and then subtracting 58 from the answer. This can be thought of as the 'multiply by 10' strategy.

WORKED EXAMPLE 19 Using mental strategies for multiplication

Use a mental strategy to calculate 77×9.

THINK	WRITE
1. Write the question.	77×9
2. Use the strategy of 'multiply by 10'.	$= 77 \times 10 - 77 \times 1$
3. Calculate 77×10 and then subtract 77.	$= 770 - 77$ $= 693$

Resources

eWorkbook	Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)
Digital documents	SkillSHEET Times tables (doc-6412) SkillSHEET Multiplying whole numbers (doc-6413)
Interactivities	Individual pathway interactivity: Multiplying positive integers (int-4313) Multiplying positive integers (int-3958) Mental strategies for multiplication (int-3925)

Exercise 1.5 Multiplying positive integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 6, 8, 11, 13, 16, 17, 22, 23, 24, 27, 30, 33	3, 4, 9, 12, 14, 18, 19, 25, 26, 31, 34	5, 7, 10, 15, 20, 21, 28, 29, 32, 35, 36

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE13 Represent each of the following as a diagram and then use the diagram to calculate the product.
   a. 8×3 b. 6×9 c. 12×5 d. 13×2 e. 15×3
2. Calculate the product of each of the following without using a calculator.
   a. 25×4 b. 45×2 c. 16×2 d. 21×3 e. 54×2
3. Calculate the product of each of the following without using a calculator.
   a. 25×3 b. $3 \times 4 \times 6$ c. $3 \times 3 \times 3$ d. $5 \times 6 \times 3$ e. $8 \times 5 \times 2$
4. Calculate 267×3 by rewriting the larger number in expanded form.
5. Use an area model to:
   a. show 523×4
   b. calculate 523×4.
6. WE14 Calculate the following using short multiplication.
   a. 16×8 b. 137×9 c. 857×3 d. 4920×5
7. Calculate the following using short multiplication.
   a. 7888×8 b. 2015×8 c. $10\,597 \times 6$ d. $41\,060 \times 12$
   Check your answers using a calculator.
8. WE16 Calculate the following using long multiplication.
   a. 52×44 b. 97×31 c. 59×28
9. Calculate the following using long multiplication.
   a. 16×57 b. 850×76 c. 407×53
10. Calculate the following using long multiplication.
    a. $80\,055 \times 27$ b. $57\,835 \times 476$ c. 8027×215
    Check your answers using a calculator.

11. WE17 Use mental strategies to calculate the following.
a. $2 \times 8 \times 5$ **b.** $4 \times 19 \times 25$ **c.** $50 \times 45 \times 2$ **d.** $4 \times 67 \times 250$

12. WE18 Use mental strategies to calculate the following.
a. 45×20 **b.** 62×50 **c.** 84×200 **d.** 86×2000

13. Calculate each of the following.
a. 200×40 **b.** 600×800 **c.** 1100×5000 **d.** $900\,000 \times 7000$

14. Calculate each of the following.
a. 90×80 **b.** 800×7000 **c.** 9000×6000 **d.** $12\,000 \times 1100$

15. WE19 Use mental strategies to calculate each of the following.
a. 34×9 **b.** 628×9 **c.** 75×99 **d.** 26×8

16. **a.** Calculate 56×100.
b. Calculate 56×10.
c. Use your answers to parts **a** and **b** to calculate the answer to 56×90.

17. Use the method demonstrated in question **16** to calculate each of the following.
a. 48×90 **b.** 125×90 **c.** 32×900

18. **a.** Calculate 25×6.
b. Multiply your answer to part **a** by 2.
c. Now calculate 25×12.

19. Use one of the methods demonstrated in this subtopic to mentally calculate the value of each of the following.
a. 15×12 **b.** 70×12 **c.** 40×16 **d.** 34×20

20. Answer the following questions.
a. Calculate the value of 9×10.
b. Calculate the value of 9×3.
c. Calculate the value of 9×13.

21. Use one of the methods demonstrated in this subtopic to mentally calculate the value of each of the following.
a. 25×13 **b.** 24×13

Understanding

22. A school has eight Year 7 classes with 26 students in each class. Calculate how many students there are in Year 7 in total.

23. A shop owner sells 84 bananas each day. Calculate how many bananas are sold in 2 weeks.

24. Ezra wants to make a telephone call to her friend Aasuka, who lives in San Francisco. The call will cost her $3 per minute. If Ezra speaks to Aasuka for 24 minutes:
a. calculate what the call will cost
b. calculate what Ezra would pay if she made this call every month for 2 years.



25. Santilla is buying some generators. The generators cost $12 000 each. She needs 11 of them. Calculate how much they will cost her in total.



26. Julie was saving money to buy a digital camera. She was able to save $75 each month.

- **a.** Calculate how much she saved over 9 months.
- **b.** Calculate how much she saved over 16 months.
- **c.** If Julie continues to save money at the same rate, calculate how much she will save over a period of 3 years.

27. A car can travel 14 kilometres using 1 litre of fuel. Calculate how far it could travel with 35 litres of fuel.

28. In 1995 a team of British soldiers in Hamelin, Germany, constructed a bridge in the fastest time ever. The bridge spanned an 8-metre gap and took the soldiers 8 minutes and 44 seconds to build. Determine how many seconds in total it took to build the bridge.



29. Narissa does a paper round each morning before school. She travels 2 kilometres each morning on her bicycle, delivers 80 papers and is paid $35. She does her round each weekday.

- **a.** Calculate how far she travels in 1 week.
- **b.** Determine how much she gets paid in 1 week.
- **c.** Calculate how far she travels in 12 weeks.
- **d.** Calculate how much she would be paid over 52 weeks.
- **e.** Calculate how many papers she would deliver in 1 week.
- **f.** Determine how many papers she would deliver in 52 weeks.

Reasoning

30. Jake says the product of 42 and 35 is 1428. His friend Ben worked out the answer to be 1470. State who is correct, Jake or Ben. Explain your answer.

31. Explain whether the mathematical statement $23 \times 4 > 20 \times 7$ is true.

32. Imagine a simplified form of a car numberplate that consists of one letter followed by one number, from A0 up to Z9. Determine how many numberplates could be issued under this system.
Remember that all numberplates issued have to be different.



Problem solving

33. Evaluate the product of 4, 16 and 9 using expanded form.

34. Consider numbers with two identical digits multiplied by 99. Determine:

$$11 \times 99,\ 22 \times 99,\ 33 \times 99$$

Can you see a pattern? Explain it.
Without using a calculator or long multiplication, write down the answers to the following.

- **a.** 44×99
- **b.** 55×99
- **c.** 66×99
- **d.** 77×99
- **e.** 88×99
- **f.** 99×99

35. Theo eats one of the strawberries in a basket, then he and his two friends split them evenly. If Theo's friends get 15 strawberries each, determine how many there were in the basket to begin with.

36. The product of two consecutive numbers is 1190. Evaluate the two numbers and their sum.



1.6 Dividing positive integers

LEARNING INTENTION

At the end of this subtopic you should be able to:
- divide positive integers using mental strategies and the short division algorithm.

1.6.1 Dividing positive integers

eles-3653

- **Division** is the process of sharing (or dividing) a number into equal parts. If 10 is divided into five parts, you can write this as $10 \div 5 = 2$.
- Division is the opposite (or inverse) of multiplication. To evaluate $56 \div 8$, you could ask the question, 'By which number do I multiply 8 to get 56?' $8 \times 7 = 56$, so the answer is 7.
- The commutative law does not apply to division. This means the order in which you divide numbers is important. For example, $10 \div 5$ is not the same as $5 \div 10$.
- A division can be written in a variety of ways, as shown.

$$10 \div 5 = 2$$

$$5\overline{)10}\ 2$$

$$\frac{10}{5} = 2$$

The vinculum represents the division symbol.

- Consider a box of chocolates that is going to be shared between a group of friends.
  There are 20 chocolates in total and 4 people sharing the box.
  How can the chocolates be divided evenly between the 4 friends?
  20 chocolates divided by 4 people means they will get 5 chocolates each.
  We can write this mathematically as:
  $20 \div 4 = 5$



Checking division by multiplying

A division can always be checked by multiplying.

If $20 \div 4 = 5$, then $4 \times 5 = 20$.

Dividing using expanded form

- One way to divide numbers is to first break the dividend (the number being divided) into expanded form and then divide each part by the divisor (the number of parts that the dividend is being divided into).

For example, calculate $636 \div 6$.

1. Write the dividend (636) in expanded form. $636 = 600 + 30 + 6$
2. Divide each part by the divisor (6).
3. Add the results.

$$600 \div 6 = 100$$
$$30 \div 6 = 5$$
$$6 \div 6 = 1$$
$$\text{so } 636 \div 6 = 100 + 5 + 1 = 106$$

1.6.2 The short division algorithm

eles-3654

- Another way to divide numbers is to use an algorithm known as short division.
- Here is an example demonstration of how to use this algorithm.

$6\overline{)636}$

1
$6\overline{)636}$ ← Divide 6 into 6. $6 \div 6 = 1$. Write 1 on top.

10
$6\overline{)63^{3}6}$ ← Divide 6 into 3. 6 cannot divide into 3. Therefore 0 is placed on top. 3 is carried over to the next digit (6).

106
$6\overline{)63^{3}6}$ ← When 3 is carried over to 6, the new number formed is 36. Divide 6 into 36. $36 \div 6 = 6$. Write 6 on top.

- Sometimes there is a number left over after numbers have been divided. This number is called a **remainder**. The letter r is used to show that a number is a remainder.
  A box of 9 chocolates needs to be shared evenly between 2 people. Because 9 cannot be divided exactly into 2 groups, each person will get 4 chocolates, with 1 chocolate left over.



$9 \div 2 = 4$ remainder 1
or
$9 \div 2 = 4$ r 1

WORKED EXAMPLE 20 Dividing using short division

Evaluate the following.

a. **834 ÷ 2** **b.** **466 ÷ 3**

THINK

a. 1. Write the equation as a short division.

2. Divide each digit by 2.
- 8 ÷ 2 = 4. Write 4 on top.
- 3 ÷ 2 = 1 r 1. Write 1 on top and carry the remainder of 1 to the next digit. The next digit becomes 14.
- 14 ÷ 2 = 7. Write 7 on top.

3. Write the answer.

b. 1. Write the equation as a short division.

2. Divide each digit by 3.
- 4 ÷ 3 = 1 r 1. Write 1 on top and carry the remainder of 1 to the next digit. The next digit becomes 16.
- 16 ÷ 3 = 5 r 1. Write 5 on top and carry the remainder of 1 over to the next digit. The next digit becomes 16.
- 16 ÷ 3 = 5 r 1. Write 5 r 1 on top.

3. Write the answer.

WRITE

$2\overline{)834}$

$\begin{array}{r} 417 \\ 2\overline{)83^{1}4} \end{array}$

$834 \div 2 = 417$

$3\overline{)466}$

$\begin{array}{r} 1\ 5\ 5\text{ r }1 \\ 3\overline{)4^{1}6^{1}6^{1}} \end{array}$

$466 \div 3 = 155\text{ r }1$

WORKED EXAMPLE 21 Dividing using short division

Calculate 89 656 ÷ 8 using short division.

THINK

1. Write the equation as a short division.

2. Divide 8 into the first digit and carry the remainder to the next digit. 8 divides into 8 once. Write 1 above the 8 as shown. There is no remainder.

3. Divide 8 into the second digit and carry the remainder to the next digit. 8 divides into 9 once, with 1 left over. Write 1 above the 9 and carry 1 to the hundreds column.

4. Divide 8 into the third digit and carry the remainder to the next digit. 8 divides into 16 twice, with no remainder. Write 2 above the 6.

5. Divide 8 into the fourth digit and carry the remainder to the next digit. 8 doesn't divide into 5. Write 0 above the 5. Carry 5 to the next digit.

6. Divide 8 into 56. 8 divides into 56 seven times. Write 7 above the 6. There is no remainder.

7. Write the answer.

WRITE

$8\overline{)89\,656}$


$\begin{array}{r} 1\ 1\ 2\ 0\ 7 \\ 8\overline{)8\,9^{1}6\,5^{5}6} \end{array}$

$89\,656 \div 8 = 11\,207$

eles-3655

1.6.3 Dividing numbers that are multiples of 10

- When we are dividing numbers that are multiples of 10, an equivalent number of zeros can be cancelled from both the **dividend (numerator)** and the **divisor (denominator)**.
- The dividend is the quantity to be divided.
- The divisor is the number by which the dividend is to be divided.
- The **quotient** is the answer obtained when one number is divided by another number.



WORKED EXAMPLE 22 Dividing numbers that are multiples of 10

Calculate 48 000 ÷ 600. Note that both numbers are multiples of 10.

THINK	WRITE
1. Write the question.	$48\,000 \div 600$
2. Write the question as a fraction.	$= \frac{48\,0\cancel{0}\cancel{0}}{6\cancel{0}\cancel{0}}$
3. Cancel as many zeros as possible, crossing off the same number of zeros in both numerator and denominator.	$= \frac{480}{6}$
4. Perform the division.	$6\overline{)4^{6}80}$ → 080
5. Write the answer.	$48\,000 \div 600 = 80$

Note: The principle of associativity is not true for division. This means that, for example, $(80 \div 8) \div 2$ is not equivalent to $80 \div (8 \div 2)$. This is shown by the following.

$$(80 \div 8) \div 2 = 10 \div 2 = 5 \qquad 80 \div (8 \div 2) = 80 \div 4 = 20$$

Digital technology

Scientific calculators can evaluate the division of large numbers.



ACTIVITY: Magic division

1. **a.** Choose a digit from 2 to 9. Write it 6 times to form a 6-digit number. For example, if you choose 4 your 6-digit number will be 444 444.
   b. Divide your 6-digit number by 33.
   c. Divide your result from part **b** by 37.
   d. Divide your result from part **c** by 91.
   e. What do you notice about your result from part **d**?
2. Repeat question **1** with a different 6-digit number and explain how the 'magic division' works.

Resources

eWorkbook	Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)
Digital document	SkillSHEET Dividing whole numbers (doc-6414)
Interactivities	Individual pathway interactivity: Dividing positive integers (int-8733)
	Dividing numbers that are multiples of 10 (int-3926)

Exercise 1.6 Dividing positive integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 6, 8, 12, 15, 18	2, 4, 7, 9, 13, 14, 16, 19	3, 5, 10, 11, 17, 20

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Calculate these divisions without using a calculator. There should be no remainder.
   - **a.** $24 \div 6$
   - **b.** $36 \div 9$
   - **c.** $96 \div 12$
   - **d.** $56 \div 7$
   - **e.** $26 \div 2$
   - **f.** $45 \div 15$
2. Calculate these divisions without using a calculator. There should be no remainder.
   - **a.** $27 \div 3 \div 3$
   - **b.** $96 \div 8 \div 6$
   - **c.** $48 \div 12 \div 2$
   - **d.** $56 \div 7 \div 4$
   - **e.** $100 \div 2 \div 10$
   - **f.** $90 \div 3 \div 2$

   Check your answers using multiplication.
3. Perform the following calculations, which involve a combination of multiplication and division. Remember to work from left to right.
   - **a.** $4 \times 5 \div 2$
   - **b.** $80 \div 10 \times 7$
   - **c.** $144 \div 12 \times 7$
   - **d.** $120 \div 10 \times 5$
   - **e.** $121 \div 11 \times 4$
4. **WE20** Calculate the following using short division.
   - **a.** $3\overline{)1455}$
   - **b.** $7\overline{)43\,456}$
   - **c.** $11\overline{)30\,371}$
   - **d.** $8\overline{)640\,360}$
5. **WE21** Calculate the following using short division.
   - **a.** $3\overline{)255\,194}$
   - **b.** $6\overline{)516\,285}$
   - **c.** $7\overline{)6\,328\,520}$
   - **d.** $8\overline{)480\,594}$

   Check your answers using a calculator.
6. Divide the following numbers, which are multiples of 10.
   - **a.** $4200 \div 6$
   - **b.** $210 \div 30$
   - **c.** $720\,000 \div 800$
7. Divide the following numbers, which are multiples of 10.
   - **a.** $4\,000\,000 \div 8000$
   - **b.** $600\,000 \div 120$
   - **c.** $480\,000 \div 600$
8. Calculate $144 \div 2$ by breaking 144 up into expanded form.
9. Calculate $642 \div 3$ by breaking 642 up into expanded form.
10. Calculate $4256 \div 8$ by breaking 4256 up into expanded form.

Understanding



11. Kelly works part time at the local pet shop. Last year she earned $2496.

a. Calculate how much Kelly earned each month.

b. Calculate how much Kelly earned each week.

12. At the milk processing plant, the engineer asked Farid how many cows he had to milk each day. Farid said he milked 192 cows, because he had 1674 litres of milk at the end of each day and each cow produced 9 litres. Determine whether Farid really milks 192 cows each day. If not, calculate how many cows he does milk.



13. When Juan caters for a celebration like a wedding, he confirms the arrangements with the client by filling out a form. Juan has been called to answer the phone, so it has been left to you to fill in the missing details. Copy and complete this planning form.

Celebration type	Wedding
Number of guests	152
Number of people per table	8
Number of tables required	
Number of courses for each guest	4
Total number of courses to be served	
Number of courses each waiter can serve	80
Number of waiters required	
Charge per guest	$55
Total charge for catering	

14. Janet is a land developer. She has bought 10 450 square metres of land. She intends to subdivide the land into 11 separate blocks.

a. Calculate how many square metres each block will be.

b. If she sells each block for $72 250, determine how much she will receive for the subdivided land.

Reasoning

15. Kayla divides 243 by 9 and works out the answer to be 27. Her friend Tristan calculates the answer to be 26. State whether either Kayla or Tristan calculated the correct answer.

16. Explain whether this statement is true: $1148 \div 4 = 282$. Justify your answer by breaking 1148 up into expanded form.

17. Some people like to keep mice as pets. Female mice give birth to about six litters of babies per year, with about six babies in each litter.



a. If you own a female mouse, how many pet mice will you have at the end of one year if none of the female's babies have any litters of their own? Explain how you reached your answer.

b. Explain how many female mice you had at the start of the year if, at the end of the year, you had 111 mice and none of your females' babies had any litters of their own. Show your working.

Problem solving

18. Danh has booked a beach house for a week over the summer period for a group of 12 friends. The house costs $1344 for the week. If all 12 people stayed for 7 nights, determine how much each person will pay per night.



19. A total of 62 people have been invited to a dinner party. Each table can seat 8 people. Determine how many tables are needed.



20. List the first four whole numbers that will have a remainder of 2 when you divide by 8. Describe the pattern and explain how you found these numbers.

1.7 Rounding and estimating

LEARNING INTENTION

At the end of this subtopic you should be able to:

- provide an estimate to a problem by rounding to the first digit.


eles-3656

1.7.1 Rounding integers

- Numbers or integers can be rounded to different degrees of accuracy.

Rounding to the nearest 10

- To round to the nearest 10, think about which multiple of 10 the number is closest to. For example, if 34 is rounded to the nearest 10, the result is 30 because 34 is closer to 30 than it is to 40.




(Note: The symbol ≈ means 'is approximately equal to'.)


Rounding to the nearest 100

- To round to the nearest 100, think about which multiple of 100 the number is closest to. For example, if 177 is rounded to the nearest 100, the result is 200 because 177 is closer to 200 than it is to 100.

Rounding to the first (or leading) digit

- To round to the first (or leading) digit, use the following guidelines:
  - Consider the digit after the leading one (i.e. the second digit).
  - If the second digit is 0, 1, 2, 3 or 4, the first digit stays the same and all the following digits are replaced with zeros.
  - If the second digit is 5, 6, 7, 8 or 9, the first digit is raised by 1 (rounded up) and all the following digits are replaced with zeros.
- For example, if 2345 is rounded to the first digit, the result is 2000 because 2345 is closer to 2000 than it is to 3000.





WORKED EXAMPLE 23 Rounding to the first digit

Round the following numbers to the first (or leading) digit.
a. 2371 **b. 872**

THINK	WRITE
a. Since the second digit (3) is less than 5, leave the leading digit unchanged and replace all other digits with zeros.	a. $2371 \approx 2000$
b. Since the second digit (7) is greater than 5, add 1 to the leading digit and replace all other digits with zeros.	b. $872 \approx 900$

eles-3657

1.7.2 Estimation

- An estimate is not the same as a guess, because an estimate is based on information.
- When you do not need to know an exact amount, an estimate or approximation is enough.
- To estimate the answer to a mathematical problem, round the numbers to the first digit and find an approximate answer.
- Estimations can be made when multiplying, dividing, adding or subtracting. They can also be used when there is more than one operation in the same question.

WORKED EXAMPLE 24 Estimating by rounding to the first digit

Estimate $48\,921 \times 823$ by rounding to the first digit.

THINK	WRITE
1. Write the question.	$48\,921 \times 823$
2. Round each part of the question to the first digit.	$= 50\,000 \times 800$
3. Multiply and write the answer.	$= 40\,000\,000$

DISCUSSION

Is the estimated answer to the multiplication in Worked example 24 higher or lower than the actual answer? Justify your response.

on Resources

eWorkbook	Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)
Digital document	SkillSHEET Rounding to the first (leading) digit (doc-6418)
Interactivities	Individual pathway interactivity: Estimation (int-4318)
	Rounding (int-3932)

Exercise 1.7 Rounding and estimating

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 5, 6, 15, 18	2, 7, 8, 13, 14, 16, 19	3, 9, 10, 11, 12, 17, 20

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE23 Round each of the following to the first (or leading) digit.

a. 6 **b.** 45 **c.** 1368
d. 12 145 **e.** 168 879 **f.** 4 985 452

2. WE24 Estimate $67\,451 \times 432$ by rounding to the first digit.

3. Copy and complete the following table by rounding the numbers to the first digit. The first row has been completed as an example.

- In the 'Estimate' column, round each number to the first digit.
- In the 'Estimated answer' column, calculate the answer.
- In the 'Prediction' column, guess whether the actual answer will be higher or lower than your estimate.
- Use a calculator to work out the actual answer and record it in the 'Calculation' column to determine whether it is higher or lower than your estimate.

		Estimate	Estimated answer	Prediction	Calculation
Example	$4129 \div 246$	$4000 \div 200$	20	Lower	16.784 553, so lower
a.	$487 + 962$				
b.	$33\,041 + 82\,629$				
c.	$184\,029 + 723\,419$				
d.	$93\,261 - 37\,381$				
e.	$321 - 194$				
f.	$468\,011 - 171\,962$				
g.	36×198				
h.	$623 \times 12\,671$				
i.	$29\,486 \times 39$				
j.	$31\,690 \div 963$				
k.	$63\,003 \div 2590$				
l.	$69\,241 \div 1297$				

4. MC Select which of the following is the best estimate of $4372 + 2587$.

A. 1000 **B.** 5527 **C.** 6000 **D.** 7000 **E.** 7459

5. MC Choose which of the following is the best estimate of 672×54.

A. 30 000 **B.** 35 000 **C.** 36 000 **D.** 40 000 **E.** 42 000

6. MC Select which of the following is the best estimate of $67\,843 \div 365$.

A. 150 **B.** 175 **C.** 200 **D.** 230 **E.** 250

Understanding

7. Estimate the answers to each of the following by rounding to the first digit.

a. $5961 + 1768$ **b.** $48\,022 \div 538$ **c.** 9701×37
d. $98\,631 + 608\,897$ **e.** $6501 + 3790$

8. Estimate the answers to each of the following by rounding to the first digit.

a. $11\,890 - 3642$ **b.** $112\,000 \times 83$ **c.** $66\,501 \div 738$
d. $392 \times 113\,486$ **e.** $12\,476 \div 24$

Questions 9 to 12 relate to the following information.

Su-Lin was using her calculator to answer some mathematical questions, but she got a different answer each time she performed the same calculation. Using your estimation skills, predict which of Su-Lin's answers is most likely to be correct.

9. MC 217×489

A. 706 **B.** 106 113 **C.** 13 203 **D.** 19 313 **E.** 105 203

10. MC $89\,344 \div 256$

A. 39 **B.** 1595 **C.** 89 088 **D.** 349 **E.** 485

11. MC 78×6703

A. 522 834 **B.** 52 260 **C.** 6781 **D.** 56 732 501 **E.** 51 624

12. MC $53\,669 \div 451$

A. 10 **B.** 1076 **C.** 53 218 **D.** 119 **E.** 183

13. Kody is selling tickets for his school's theatre production of *South Pacific*. So far he has sold 439 tickets for Thursday night's performance, 529 for Friday's and 587 for Saturday's. The costs of the tickets are $9.80 for adults and $4.90 for students.

a. Round the figures to the first digit to estimate the number of tickets Kody has sold so far.
b. If approximately half the tickets sold were adult tickets and the other half were student tickets, estimate how much money has been received so far by rounding the cost of the tickets to the first digit.

14. For the following calculations:

i. estimate the answer by rounding to the first digit
ii. calculate the answer using a written method.

Check your answers using a calculator.

a. $6650 - 1310$ **b.** 36×223 **c.** $18\,251 \div 391$

Reasoning

15. Ava wants to buy three items that cost $5.58, $15.92 and $7.22. Estimate the total cost of the three items by rounding each number to the nearest whole number, and then adding.

16. Estimate the number of graduating students shown in the photograph. (Do not count all of the students in the photograph.) If the hall where they are graduating holds 12 times this number, estimate the total capacity of the hall.
Show your working and write a sentence explaining how you solved this problem.



17. At Kooboora Secondary College there are 127 students in Year 7, 152 students in Year 8 and 319 students in Years 9 and 10. Estimate the total number of students in Years 7–10.

Problem solving

18. Describe a situation in everyday life where it is *not* appropriate to estimate values.

19. Shari bought a car five years ago for $21 798. The car's value has decreased to one-third of its initial value. Determine the approximate value of the car today.

20. During the intermission of the school production of *South Pacific*, Jia is planning to run a stall selling hamburgers to raise money for the school. She has priced the items she needs and made a list in order to estimate her expenses.



   a. By rounding the item price to the first digit, use the following table to estimate how much each item will cost Jia for the quantity she requires.
   b. Estimate what Jia's total shopping bill will be.
   c. If Jia sells 300 hamburgers over the 3 nights for $2 each, determine how much money she will receive for the hamburgers.
   d. Determine approximately how much money Jia will raise through selling hamburgers over the 3 nights.

Item	Item price	Quantity required	Estimated cost
Bread rolls	$2.90/dozen	25 packets of 12	
Hamburgers	$2.40/dozen	25 packets of 12	
Tomato sauce	$1.80/litre	2 litres	
Margarine	$2.20/tub	2 tubs	
Onions	$1.85/kilogram	2 kilograms	
Tomatoes	$3.50/kilogram	2 kilograms	
Lettuce	$1.10 each	5 lettuces	

1.8 Order of operations

LEARNING INTENTION

At the end of this subtopic you should be able to:
- understand how the order of operations is to be applied
- apply the order of operations to solve problems.


1.8.1 BIDMAS

eles-3658

- There are rules in mathematics that ensure everyone has the same understanding of mathematical operations. These rules are known as the **order of operations**.
- The acronym **BIDMAS** (**B**rackets, **I**ndices or roots, **D**ivision and **M**ultiplication, **A**ddition and **S**ubtraction) can be used to remember the correct order of operations.

BIDMAS

BIDMAS helps us to remember the correct order in which we perform the various operations, working from left to right.



WORKED EXAMPLE 25 Applying the order of operations

Calculate $6 + 12 \div 4$.

THINK	WRITE
1. Write the question.	$6 + 12 \div 4$
2. Follow BIDMAS. • Brackets: there are none. • Indices or roots: there are none. • Division and multiplication: there is one division. • Addition and subtraction: there is one addition.	
3. Apply BIDMAS by working out the division before the addition.	$6 + 12 \div 4$ $= 6 + 3$
4. Calculate the answer.	$= 9$

WORKED EXAMPLE 26 Applying the order of operations

Calculate the following.

a. $12 \div 2 + 4 \times (4 + 6)$ **b.** $80 \div [((11 - 2) \times 2) + 2]$

THINK	WRITE
a. 1. Write the question.	a. $12 \div 2 + 4 \times (4 + 6)$
2. Apply BIDMAS. Remove the brackets by working out the addition inside.	$= 12 \div 2 + 4 \times 10$
3. Perform the division and multiplication next, doing whichever occurs first as you work from left to right. Work out $12 \div 2$ first, then work out 4×10.	$= 12 \div 2 + 4 \times 10$ $= 6 + 40$
4. Complete the addition last and calculate the answer.	$= 46$
b. 1. Write the question.	$80 \div [((11 - 2) \times 2) + 2]$
2. Remove the innermost brackets first by working out the subtraction inside them.	$= 80 \div [(9 \times 2) + 2]$
3. Remove the next pair of brackets by working out the multiplication inside them.	$= 80 \div [18 + 2]$
4. Remove the final pair of brackets by working out the addition inside them.	$= 80 \div 20$
5. Perform the division last and calculate the answer.	$= 4$

ACTIVITY: Order of operations

Using the expressions from Worked example 26, investigate whether the order of operations is applied on different devices such as your mobile phone or a computer. Do you have to do anything different to ensure that the order of operations is followed?

WORKED EXAMPLE 27 Inserting brackets to make a statement true

Insert one set of brackets in the appropriate place to make the following statement true.
$3 \times 10 - 8 \div 2 + 4 = 7$

THINK	WRITE
1. Write the left-hand side of the equation.	$3 \times 10 - 8 \div 2 + 4$
2. Place one set of brackets around the first two values.	$= (3 \times 10) - 8 \div 2 + 4$
3. Perform the multiplication inside the bracket.	$= 30 - 8 \div 2 + 4$
4. Perform the division.	$= 30 - 4 + 4$
5. Perform the subtraction and addition working from left to right. *Note*: Since this is not the answer, the above process must be repeated.	$= 26 + 4$ $= 30$ Since this is not equal to 7 we must place the brackets in a different position.
6. Place one set of brackets around the second and third values.	$3 \times 10 - 8 \div 2 + 4$ $= 3 \times (10 - 8) \div 2 + 4$
7. Perform the subtraction inside the bracket.	$= 3 \times 2 \div 2 + 4$
8. Perform the multiplication and division working from left to right.	$= 6 \div 2 + 4$ $= 3 + 4$
9. Perform the addition last and calculate the answer.	$= 7$
10. Write the answer.	$3 \times (10 - 8) \div 2 + 4 = 7$


WORKED EXAMPLE 28 Using the order of operations

Calculate $58 - (2 \times 8 + 3^2)$ using the order of operations.

THINK	WRITE
1. Write the question.	$58 - (2 \times 8 + 3^2)$
2. Apply BIDMAS. • Remove the brackets first. • Calculate the indices inside the brackets. • Work out the multiplication inside the brackets. • Do the addition inside the brackets. • Do the subtraction.	$= 58 - (2 \times 8 + 9)$ $= 58 - (16 + 9)$ $= 58 - (25)$
3. Write the answer.	$= 33$

Digital technology

Scientific calculators can evaluate the expression using the order of operations.



DISCUSSION

Use a calculator to work out the answer to Worked example 28. Do you think it is easier or harder to perform the calculation using a calculator? What do you think the advantages and disadvantages are of using a calculator compared to calculating using mental strategies?

Resources

eWorkbook	Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)
Digital document	SkillSHEET Order of operations I (doc-6415)
Video eLesson	BIDMAS (eles-2425)
Interactivities	Individual pathway interactivity: Order of operations (int-4315)
	Order of operations (int-3707)

Exercise 1.8 Order of operations

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 6, 9, 14, 17, 20, 21	3, 7, 10, 12, 13, 16, 18, 22, 23	4, 5, 8, 11, 15, 19, 24, 25

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE25 & 26 Follow the order of operations rules and calculate each of the following.
   - **a.** $3+4\div2$
   - **b.** $8+1\times1$
   - **c.** $24\div(12-4)$
   - **d.** $15\times(17-15)$
   - **e.** $11+6\times8$
2. Follow the order of operations rules and calculate each of the following.
   - **a.** $30-45\div9$
   - **b.** $56\div(7+1)$
   - **c.** $12\times(20-12)$
   - **d.** $(7+5)-(10+2)$
3. Follow the order of operations rules and calculate each of the following.
   - **a.** $3\times4+23-10-5\times2$
   - **b.** $42\div7\times8-8\times3$
   - **c.** $10+40\div5+14$
   - **d.** $81\div9+108\div12$
   - **e.** $16+12\div2\times10$
   - **f.** $(18-15)\div3\times27$

4. Follow the order of operations rules and calculate each of the following.

a. $4+(6+3\times 9)-11$
b. $52\div 13+75\div 25$
c. $88\div(24-13)\times 12$
d. $(4+5)\times(20-14)\div 2$
e. $\{[(16+4)\div 4]-2\}\times 6$
f. $60\div\{[(12-3)\times 2]+2\}$

Understanding

5. WE27 Insert one set of brackets in the appropriate place to make these statements true.

a. $12-8\div 4=1$
b. $4+8\times 5-4\times 5=40$
c. $3\times 10-2\div 4+4=10$
d. $12\times 4+2-12=60$
e. $10\div 5+5\times 9\times 9=81$
f. $18-3\times 3\div 5=9$

6. Calculate the following, using the order of operations.

a. $6+3\times 4$
b. $18-12\div 3$
c. $2-4-6$
d. $17-3+8$

7. Calculate the following, using the order of operations.

a. $6\times 3\div 9$
b. $72\div 8\times 3$
c. $7-(3+4)$
d. $(6+3)\div 9$

8. Calculate the following, using the order of operations.

a. $3\times 2-3\times 1$
b. $6\times 5-2\times 6$
c. $4\times(6+4)$
d. $(8+3)\times 7$

9. WE28 Evaluate each of the following.

a. $4+7\times 3-2$
b. $6-4+(4)^2$
c. $(2)^3-3\times 2$
d. $3+(8-2)+6$

10. Evaluate each of the following.

a. $8\div 2+(2)^2$
b. $4\times 8-\left[2+(3)^2\right]$
c. $(7+5)+24\div 6$
d. $30\div(5-2)-10$

11. Evaluate each of the following.

a. $54\div 6+8\times 9\div 4$
b. $(9+6)\div 5-8\times 0$
c. $7+7\div 7\times 7+7$
d. $9\times 5-(3+2)-48\div 6$

12. MC $20-6\times 3+28\div 7$ is equal to:

A. 46 **B.** 10 **C.** 6 **D.** 4 **E.** 2

13. MC Choose which of the following is the correct order of the two signs that can replace * in the equation $7*2*4-3=12$.

A. $-,+$ **B.** $+,\times$ **C.** $=,\div$ **D.** $\div,\times$ **E.** $\times,\div$

14. MC Select which of the following the expression $6-2\times 5+10\div 2$ is equal to.

A. 25 **B.** 40 **C.** 30 **D.** 1 **E.** 3

15. Insert brackets (if necessary) to make each statement true.

a. $6+2\times 4-3\times 2=10$
b. $6+2\times 4-3\times 2=26$
c. $6+2\times 4-3\times 2=16$
d. $6+2\times 4-3\times 2=8$

16. Model each situation with integers, then calculate the result.

a. Jemma starts out with $274 in the bank. She makes 2 withdrawals of $68 each, then 3 deposits of $50 each. Calculate how much money Jemma now has in the bank.
b. If 200 boxes of apples were each 3 short of the stated number of 40 apples, calculate the overall shortfall in the number of apples.
c. A person with a mass of 108 kg wants to reduce his mass to 84 kg in 3 months. Determine what average mass reduction is needed per month.

Reasoning

17. Discuss a real-life situation in which performing calculations in the wrong order could cause problems.

18. Keenan and Amona discovered that they had different answers to the same question, which was to calculate $6 + 6 \div 3$. Keenan thought the answer was 8. Amona thought the answer was 4. State who was correct, Keenan or Amona. Explain your response.



19. I have a pile of pebbles. Arranging them in piles of 7 leaves 1 extra pebble, and arranging them in piles of 5 leaves 3 extra pebbles. If there are more than 10 pebbles in my pile, determine the smallest number of pebbles possible for my pile to have in it. Show your working.

Problem solving

20. The student lockers at Jacaranda College are to be numbered consecutively from 1 to 800 using plastic digits. Each digit costs 10c. Calculate the total cost of all the digits.

21. Xanthe bakes and sells cupcakes. A customer ordered 3 lemon cupcakes at $4.25 each, 3 chocolate cupcakes at $4.75 each and 2 original cupcakes at $3.75 each.

a. Write an expression to help Xanthe calculate the amount the customer has to pay.

b. Use this expression to calculate the amount that the customer has to pay.



22. Local time in Sydney is 3 hours ahead of Singapore time, which is 5 hours behind Auckland (NZ) time. Auckland is 11 hours ahead of Berlin (Germany) time. Determine the time difference between:

a. Sydney and Berlin

b. Singapore and Berlin.



23. Minh was asked to buy enough ice creams for everyone in his class. There are 31 people in the class. At the supermarket, ice creams come in packets of 3 or packets of 5. Minh is told that the cost of one ice cream is the same from either packet. Determine how many packets (or what combination of packets) Minh should buy.

24. Use the digits $1, 2, 3$ and 4 and the operators $+, -, \times$ and $\div$ to construct equations that result in the numbers 1 to 5 (the numbers 2 and 4 are already done for you). You must use each digit in each expression, and you may not use the digits more than once. You may combine the digits to form larger numbers (such as 21). You may also use brackets to make sure the operations are done in the correct order.

$1 =$
$2 = 4 - 3 + 2 - 1$
$3 =$
$4 = 4 - 2 + 3 - 1$
$5 =$

25. Use the digits $1, 2, 3$ and 4 and the operators $+, -, \times$ and $\div$ to construct equations that result in the numbers 5 to 10 (the numbers 7 and 10 have already been done for you). You must use each digit in each expression and you may not use the digits more than once. You may combine the digits to form larger numbers (such as 21). You may also use brackets to make sure the operations are done in the correct order.

$5 =$
$6 =$
$7 = 24 \div 3 - 1$
$8 =$
$9 =$
$10 = 1 + 2 + 3 + 4$

1.9 Review

1.9.1 Topic summary

Place value

The position of a digit in a number gives a different value to the digit.

For example, the place value of each digit in the number 613 452 is:

Hundred thousands	Ten thousands	Thousands	Hundreds	Tens	Ones
6	1	3	4	5	2

- The number 613 452 is read as '*six hundred and thirteen thousand, four hundred and fifty-two*'.

Rounding and estimating

To round to the first digit, use the following guidelines:

- If the second digit is 0, 1, 2, 3 or 4, the first digit stays the same and all the following digits are replaced with zeros.
- If the second digit is 5, 6, 7, 8 or 9, the first digit is increased by 1 (rounded up) and all the following digits are replaced with zeros.

POSITIVE INTEGERS

Positive integers

Positive integers are whole numbers including 0 without decimals or fractions.

- The integers 1, 2, 3,… are called positive integers.
- 0 is neither positive nor negative.…

Addition of positive integers

Some mental strategies and algorithms used to add up numbers without a calculator are:

- jump strategy
- split strategy
- compensation strategy
- rearrange strategy
- algorithm to add positive integers.

e.g. 462 + 78 + 316

$$\begin{array}{r} {}^{1}4\ {}^{1}6\ 2 \\ 7\ 8 \\ 3\ 1\ 6 \\ \hline 8\ 5\ 6 \end{array}$$

Subtraction of positive integers

Some mental strategies and algorithms used to subtract numbers without a calculator are:

- jump strategy
- adding up to find the difference
- compensation strategy
- algorithm to subtract positive integers.

e.g. 892 – 467

$$\begin{array}{r} 8\,{}^{8}\not{9}\,{}^{1}2 \\ 4\ 6\ 7 \\ \hline 4\ 2\ 5 \end{array}$$

Multiplication of positive integers

- A short way of performing repeated addition of the same number
- Expanded form, area model, short and long multiplication algorithms are used to multiply.

e.g.

Long multiplication

$$\begin{array}{r} 1456 \\ \times\ 132 \\ \hline 2912 \\ 43680 \\ 145600 \\ \hline 192192 \end{array}$$

Short multiplication

$$\begin{array}{r} {}^{2}1{}^{2}456 \\ \times\ 5 \\ \hline 7280 \end{array}$$



Division of positive integers

- The process of sharing or dividing a number into equal parts.
- Expanded form and short division algorithm are used to divide.

e.g.

$$2\overline{)83{}^{1}4}\ 417$$

Quotient: 2

$5\overline{)10}$

Divisor: 5 Dividend: 10

Order of operations

- The order of operations is a set of rules we must follow so that we all have a common understanding of mathematical operations.
- The set order in which we calculate problems is:
  1. **Brackets** ( ) or [ ]
  2. **Indices or roots** a^x or $\sqrt[n]{x}$
  3. **Division and Multiplication** (working left to right) ÷ or ×
  4. **Addition and Subtraction** (working left to right) + or −
- The acronym **BIDMAS** can be used to remember the correct order of operations.

1.9.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
1.2	I understand that the value of each digit in a number depends on its position or place value.			
1.3	I can add and subtract positive integers using mental strategies.			
1.4	I can add and subtract positive integers using algorithms.			
1.5	I can multiply positive integers using mental strategies and algorithms.			
1.6	I can divide positive integers using mental strategies and the short division algorithm.			
1.7	I can provide an estimate to a problem by rounding to the first digit.			
1.8	I understand how the order of operations is to be applied.			
	I can apply the order of operations to solve problems.			

1.9.3 Project

Ancient number systems

All ancient civilisations developed methods to count and use numbers. The methods they used to represent numbers did not involve the ten digits 1, 2, 3, 4, 5, 6, 7, 8, 9 and 0 that we use today. Instead they involved different systems like letters, other symbols, pebbles, tying knots in ropes, or cutting notches in sticks. As the need to use and represent larger numbers became more and more important, many old systems fell out of use.




Egyptian numbers

The ancient Egyptians were one of the oldest known civilisations to have a recorded number system. In about 5000 BCE, Egyptians used a system of symbols called hieroglyphs. An example of hieroglyphs can be seen in the photograph.

The hieroglyphs used for numbers are shown in this table.

Number	1	10	100	1000	10 000	100 000	1 000 000	10 000 000
Symbol								

The following example shows how the symbols are used to represent numbers. As the numbers get larger in value, the symbols are simply repeated. This set of symbols represents 241 513.




1. What number is represented by the following Egyptian hieroglyphs?



2. Show how the ancient Egyptians would have represented the number 2147.
   The ancient Egyptian system of numbers was not limited to simply representing numbers. Addition and subtraction could also be performed when it was required. Perform the following additions and subtractions, giving your answers as Egyptian numbers.

3. 

4. 

5. 

6. 

7. Comment on any difficulties you encountered when performing the calculations using Egyptian hieroglyphs.

Greek numbers




The ancient Greeks used an alphabet that had 27 letters (the modern Greek alphabet has only 24 letters). These letters were also used to represent numbers.

The first nine letters of the alphabet represented the numbers 1 to 9. The middle nine letters of the alphabet represented the tens from 10 to 90. The last nine letters of the alphabet represented the hundreds from 100 to 900. Numbers were written by combining these letters.

8. Search online to find the 27 symbols used in the ancient Greek number system and the number that each symbol represented.
9. How did the ancient Greeks represent numbers greater than or equal to 1000?

10. Search online to find out about number systems used by other ancient civilisations. Try to find out what symbols were used to represent numbers and how those symbols were used in calculations. Discuss any advantages of these systems and suggest why the system may have fallen out of use. Present your findings on a separate sheet of paper.



Resources

eWorkbook Topic 1 Workbook (worksheets, code puzzle and project) (ewbk-1902)

Interactivities Crossword (int-2586)
Sudoku puzzle (int-3163)

Exercise 1.9 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. State the place value of the digit shown in pink in each of the following.
   a. 74 037 **b.** 541 910 **c.** 1 904 000 **d.** 290

2. Write each of the following numbers in expanded form.
   a. 392 **b.** 4109 **c.** 42 001 **d.** 120 000

3. List the numbers 394, 349, 943, 934, 3994, 3499 in ascending order.

4. List the numbers 1011, 101, 110, 1100, 1101 in descending order.

5. Calculate the sum of these numbers.

a. $43 + 84$ **b.** $139 + 3048$

c. $3488 + 91 + 4062$ **d.** $3\,486\,208 + 38\,645 + 692\,803$

6. Calculate each of the following.

a. $20 - 12 + 8 - 14$ **b.** $35 + 15 + 5 - 20$

c. $300 - 170 + 20$ **d.** $18 + 10 - 3 - 11$

7. Calculate the difference between the following numbers.

a. $688 - 273$ **b.** $400 - 183$

c. $68\,348 - 8026$ **d.** $46\,234 - 8476$

e. $286\,005 - 193\,048$

8. Use mental strategies to multiply each of the following.

a. $2 \times 15 \times 5$ **b.** $4 \times 84 \times 25$ **c.** 62×20

d. 67×9 **e.** 31×19

9. Evaluate the following multiplications using a diagram.

a. 3×6 **b.** 5×4 **c.** 2×7

10. Calculate the following using expanded form.

a. 24×4 **b.** 134×8 **c.** 642×5

11. Calculate the following using an area model.

a. 236×6 **b.** 347×4 **c.** 675×5

12. Calculate the following using the short multiplication algorithm.

a. 128×9

b. 762×3

c. 3840×5

13. Calculate the following using the long multiplication algorithm.

a. 64×72 **b.** 542×57 **c.** $50\,426 \times 364$

14. Calculate each of the following using expanded form.

a. $645 \div 5$ **b.** $1040 \div 4$ **c.** $15\,063 \div 3$

15. Calculate each of the following.

a. $6 \times 4 \div 3$ **b.** $4 \times 9 \div 12$ **c.** $49 \div 7 \times 12$

d. $81 \div 9 \times 5$ **e.** $6 \times 3 \div 9 \div 2$

16. Divide the following multiples of 10.

a. $84\,000 \div 120$ **b.** $4900 \div 700$ **c.** $12\,300 \div 30$

17. Evaluate the following using short division.

a. $4704 \div 3$ **b.** $6867 \div 7$ **c.** $3762 \div 7$

d. $5702 \div 17$ **e.** $11\,852 \div 13$

18. By rounding each number to its first digit, estimate the answer to each of the following calculations.

a. $6802 + 7486$
b. $8914 - 3571$
c. $5304 \div 143$
d. 5706×68
e. $49\,581 + 73\,258$
f. 289×671

19. MC Choose which of the following is an integer.

A. $2\frac{1}{2}$
B. 0.45
C. 0
D. 201.50
E. $\frac{7}{2}$

20. Complete each statement by inserting $=$, $<$ or $>$ in the box to make the statement correct.

a. $6 - 4 \square 3 + 2$
b. $1 \square 7 \div 7$
c. $5 - 4 \square 0 \times 5$
d. $100 - 50 \square 9 \times 5$

21. Calculate the following using a mental strategy.

a. $315 + 12$
b. $1010 + 80$
c. $735 + 54$
d. $154 + 62$

22. Calculate the following using a mental strategy.

a. $152 - 25$
b. $135 - 54$
c. $745 - 34$
d. $354 - 76$

23. Evaluate the following.

a. $(6 - 2) \times 7$
b. $4 \times (4 + 2)$
c. 2×5
d. $(10 - 6) \times 2$
e. $7 + 8 \div 2$
f. $3 \times 5 + (6 \times 2)$

24. Calculate the following.

a. $36 \div 3$
b. $210 \div 7$
c. $45 \div 9$
d. $1800 \div 2$
e. $672 \div 48$
f. $625 \div 25$

25. Complete the following by inserting $=$, $<$ or $>$ in the box to make the statement correct.

a. $3.5 \square 3.75$
b. $22 \times 2 \square 44$
c. $4 \times 3 \square 8 \times 0.5$
d. $5 \times 2 \square 15$

26. Complete the following by inserting $=$, $<$ or $>$ in the box to make the statement correct.

a. $12 \div -4 \square 3$
b. $5 \times (2 + 10) \div 4 \square 25$
c. $10 \times 6.5 \square 50$
d. $5 \times 2 - 6 \div 4 \square 2.5$

27. The lowest temperature recorded on a particular day in Melbourne was 4 °C and the highest was 27.5 °C. Calculate the difference between these two temperatures.

28. Follow the rules for the order of operations to calculate each of the following.

a. $35 \div (12 - 5)$
b. $11 \times 3 + 5$
c. $8 \times 3 \div 4$
d. $5 \times 12 - 11 \times 5$
e. $(6 + 4) \times 7$
f. $5 + [21 - (5 \times 3)] \times 4$


Problem solving

29. Uluru is a sacred Aboriginal site. The following map shows some roads between Uluru and Alice Springs. The distances (in kilometres) along particular sections of road are indicated.

a. Calculate how far Kings Canyon Resort is from Ayers Rock Resort near Uluru.

b. Determine the shortest distance by road from Kings Canyon Resort to Alice Springs.

c. If you are travelling in a hire car in this part of Australia, you must travel only on sealed roads. Work out the distance you need to travel if you are driving in a hire car from Kings Canyon Resort to Alice Springs.



30. In summer, an ice cream factory operates 16 hours a day and makes 28 ice creams an hour.

a. Calculate how many ice creams are made each day.

b. If the factory operates 7 days a week, determine how many ice creams are made in one week.

c. If there are 32 staff who run the machines over a week, calculate how many ice creams each person would make.



31. When you add two even positive integers, the answer is even. The sum of an even and an odd positive integer is an odd integer. Two odd positive integers add to give an even integer.
Determine what happens if you perform multiplication on these types of integers. Give examples to support your answers. Write a general statement to summarise what would happen if you multiplied more than two positive integers.

32. Complete the following subtraction by adding the missing digits to the boxes.

$$\begin{array}{r} 8\ 2\ \square\ 0 \\ -\ 3\ \square\ 8\ \square \\ \hline \square\ 5\ 5\ 9 \end{array}$$

33. A lolly factory machine dispenses 760 lollies into 8 jars. Assuming that an equal number of lollies is dispensed into each jar, evaluate how many lollies there are in each jar.

34. Julie sells 8 bottles of soft drink for $3 each and 12 bottles of water for $2 each.
a. Write a calculation that will find the total value of Julie's sales.
b. Calculate the total value of Julie's sales.

35. Dara estimates the crowd at a football match to be 20 000 people. If Dara's estimate is correct to the nearest 1000 people, evaluate the greatest number of people that could possibly be at the match.



36. **a.** Complete the addition table below.

+	6		3
	11	15	
12			
	15		

b. Complete the multiplication table below.

×	4		6
	12	24	18
5			
	8		

37. Minimum and maximum temperatures are recorded at many locations around the world.

a. In Melbourne the temperature often changes rapidly during the day. On one very hot day the temperature reached 42 °C. A cool change arrived during the afternoon and the temperature dropped by 18 °C. Determine the temperature after the cool change.

b. In Alaska the weather often changes suddenly as storms sweep across the frozen plains. On one day, the temperature was 3 °C, but a storm caused the temperature to drop by 24 °C. Determine the temperature during the storm.

38. You have 30 questions to answer on a multiple choice test. Each correct answer scores one mark (+1). Each incorrect answer loses two marks (−2). Any unmarked questions will be counted as incorrect. Evaluate the lowest number of questions that you can answer correctly and still obtain a score greater than 0. Determine how many marks you would earn. Explain your reasoning.

39. Place the digits 1–9 (with no repeats) in the grid shown so that the equations reading across and down are true.

	+		×		=	32
+		×		+		
	−		+		=	7
×		÷		÷		
	−		−		=	4
=		=		=		
29		10		15		

40. The following table lists a business's profit over the past four years. Evaluate which two consecutive years had the greatest difference. Show your working.

Year	2016	2017	2018	2019
$ Profit/loss	1020	2620	3808	8222



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1902) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0690) ☐

Digital documents

1.2 SkillSHEET Place value (doc-6409) ☐
SkillSHEET Ascending and descending order (doc-6410) ☐
1.3 SkillSHEET Adding and subtracting whole numbers less than 20 (doc-6411) ☐
1.5 SkillSHEET Times tables (doc-6412) ☐
SkillSHEET Multiplying whole numbers (doc-6413) ☐
1.6 SkillSHEET Dividing whole numbers (doc-6414) ☐
1.7 SkillSHEET Rounding to the first (leading) digit (doc-6418) ☐
1.8 SkillSHEET Order of operations I (doc-6415) ☐

Video eLessons

1.2 Place value (eles-3643) ☐
Ordering and comparing numbers (eles-3644) ☐
1.3 Mental strategies for addition (eles-3645) ☐
Mental strategies for subtraction (eles-3646) ☐
1.4 Addition of positive integers using algorithms (eles-3647) ☐
Commutative and associative laws for addition (eles-3648) ☐
Subtraction of positive integers using algorithms (eles-3649) ☐
1.5 Multiplying positive integers (eles-3650) ☐
The short multiplication algorithm (eles-3651) ☐
The long multiplication algorithm (eles-3652) ☐
Mental strategies for multiplication (eles-4838) ☐
1.6 Dividing positive integers (eles-3653) ☐
The short division algorithm (eles-3654) ☐
Dividing numbers that are multiples of 10 (eles-3655) ☐
1.7 Rounding integers (eles-3656) ☐
Estimation (eles-3657) ☐
1.8 BIDMAS I (eles-3658) ☐
BIDMAS II (eles-2425) ☐

Interactivities

1.2 Individual pathway interactivity: Place value (int-4311) ☐
Place value (int-3921) ☐
1.3 Individual pathway interactivity: Strategies for adding and subtracting positive integers (int-8731) ☐
1.4 Individual pathway interactivity: Algorithms for adding and subtracting positive integers (int-8732) ☐
Addition of positive integers (int-3922) ☐
Subtraction of positive integers (int-3924) ☐
1.5 Individual pathway interactivity: Multiplying positive integers (int-4313) ☐
Multiplying positive integers (int-3958) ☐
Mental strategies for multiplication (int-3925) ☐
1.6 Individual pathway interactivity: Long division (int-4316) ☐
Dividing positive integers (int-8733) ☐
Dividing numbers that are multiples of 10 (int-3926) ☐
1.7 Individual pathway interactivity: Estimation (int-4318) ☐
Rounding (int-3932) ☐
1.8 Individual pathway interactivity: Order of operations (int-4315) ☐
Order of operations (int-3707) ☐
1.9 Crossword (int-2586) ☐
Sudoku puzzle (int-3163) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers

Topic 1 Positive integers

Exercise 1.1 Pre-test

1. E
2. 27
3. a. 2411 b. 70 555 c. 26 747
4. a. 622 b. 7257 c. 1262
5. 480
6. 416
7. 321
8. $1865
9. 600
10. 30 000
11. a. 12 b. 21 c. 25
12. a. < b. = c. >
13. a. 2 b. 8 c. 130
14. a. 172 b. 444 c. 235
15. 12 minutes after the race has started.

Exercise 1.2 Place value

1. a. $900 + 20 + 5$
   b. $20\,000 + 8000 + 400 + 60 + 9$
   c. $800\,000 + 2$
   d. $1\,000\,000 + 80\,000 + 100$
2. a. Seven hundred and sixty-five
   b. Nine thousand, one hundred and five
   c. Ninety thousand, four hundred and fifty
   d. One hundred thousand, two hundred and thirty-six
3. a. 495 b. 2670 c. 109 605
4. Forty
5. Two hundred
6. Zero
7. Three hundred
8. Fifty
9. E
10. B
11. 48 987, 8569, 742, 647, 28
12. 72 167, 58 625, 47 890, 32 320, 12 947
13. 7647, 7476, 6747, 6477, 4776
14. 8880, 8808, 8800, 8088, 8080, 8008
15. 9, 58, 743, 68 247, 1 258 647
16. 34 108, 58 610, 60 000, 78 645, 84 364
17. 1290, 1902, 2019, 2910, 9021, 9201
18. 111, 211, 212, 221, 222, 1112
19. a. $345 < 567$ b. $89 < 98$ c. $234\,596 > 23\,459$
    d. $7765 > 7756$
20. a. $6000 b. $340 000 c. $58 000
21. a. $430K b. $7K c. $800K
22. 98 641
23. Half a minute (30 s)
24. Astronomers and other scientists work with very small or very large numbers. Scientific notation is a system that makes working with very small or very large numbers easier.
25. a. 2
    b. 4
26. a. 6
    b. 27
    c. In part **a**, the number of two-digit numbers is the same as the number of digits. In part **b** the number of three-digit numbers is double the number of digits because the number can begin with any one of the three digits, and then there are two digits to choose from for the second place and one digit for the third place; this makes six possible numbers.
    d. In part **a**, the number of two-digit numbers is 2^2. In part **b** the number of three-digit numbers is 3^3.
27. About 11 days at a rate of 1 number per second

Exercise 1.3 Strategies for adding and subtracting positive integers

1. a. 228 b. 1803
2. a. 906 b. 448
3. a. 560 b. 102
4. a. 86 b. 64
5. True
6. B
7. 847
8. a. 45 b. 351
9. a. 64 b. 33
10. a. 17 b. 227
11. 278
12. a. 5 or 0 b. 10
13. Yes. Working shown:
    $145 + 671$: Break into 600, 70 and 1
    $145 + 600 = 745$
    $745 + 70 = 815$
    $815 + 1 = 816$
    $816 - 472$: Break into 400, 70 and 2
    $816 - 400 = 416$
    $416 - 70 = 346$
    $346 - 2 = 344$
14. a. The student has not listed the tens and ones correctly.
    b. 998
15. There are 18 children on the playground now.
16. 550 students are not completing exams.
17. Harriet has $161 left in her savings account.
18. The two numbers are 13 and 6.

Exercise 1.4 Algorithms for adding and subtracting positive integers

1. a. 15 b. 37 c. 210
   d. 240 e. 1730
2. a. 18 220 b. 175 000 c. 20
   d. 40 e. 50

3. a. 99 b. 72 648 c. 13 629

4. a. 978 b. 766 c. 1335
d. 14 462 e. 1 701 553

5. a. 180 b. 280 c. 790
d. 827

6. a. 6 b. 23 c. 5
d. 125 e. 900

7. a. 700 b. 70 c. 500
d. 5 e. 26

8. a. 4 b. 20 c. 55
d. 0 e. 73 f. 1150

9. a. 35 b. 35 123 c. 584 599

10. a. 267 b. 4413 c. 65 439
d. 2634

11. a. 69 397 b. 1553 c. 349 818
d. 19 088 744

12. $247

13. 3032 pages

14. $71

15. 6670 km

16. a. 7, 6, 14 b. 15, 10, 15 c. 8, 20, 36

17. a. 26 m b. 26 m c. 52 m

18. 15

19. 9591

20. 31

21. a. 172 km b. 353 km

22. a. 638 321 − 488 417 = 149 904
b. 3492 − 1685 = 1807 (other answers possible)

23. 5 849 318

24. 7 days

25. Trixie

26. Three students attend both swimming practice and lifesaving.

27. Three people do not work Monday to Sunday.

28. 6

Exercise 1.5 Multiplying positive integers


1. a. 24 b. 54 c. 60
d. 26 e. 45

2. a. 100 b. 90 c. 32
d. 63 e. 108

3. a. 75 b. 72 c. 27
d. 90 e. 80

4. 801

5. a.



b. 2092

6. a. 128 b. 1233
c. 2571 d. 24 600

7. a. 63 104 b. 16 120
c. 63 582 d. 492 720

8. a. 2288 b. 3007 c. 1652

9. a. 912 b. 64 600 c. 21 571

10. a. 2 161 485 b. 27 529 460 c. 1 725 805

11. a. 80 b. 1900
c. 4500 d. 67 000

12. a. 900 b. 3100
c. 16 800 d. 172 000

13. a 8000 b 480 000
c 5 500 000 d 6 300 000 000

14. a. 7200 b. 5 600 000
c. 54 000 000 d. 13 200 000

15. a. 306 b. 5652
c. 7425 d. 208

16. a. 5600 b. 560 c. 5040

17. a 4320 b 11 250 c 28 800

18. a. 150 b. 300 c. 300

19. a. 180 b. 840 c. 640 d. 680

20. a. 90 b. 27 c. 117

21. a. 325 b. 312

22. 208

23. 1176

24. a. $72 b. $1728

25. $132 000

26. a. $675 b. $1200 c. $2700

27. 490 km

28. 524 seconds

29. a. 10 km b. $175 c. 120 km
d. $9100 e. 400 papers f. 20 800 papers

30. The correct answer is 1470 so Ben is correct.

31. 92 > 140 False

32. 260

33. 576

34. 108 921 783 267
a. 4356 b. 5445 c. 6534
d. 7623 e. 8712 f. 9801

35. 46

36. The two numbers are 34 and 35. Their sum is 69.

Exercise 1.6 Dividing positive integers

1. a. 4 b. 4 c. 8
d. 8 e. 13 f. 3

2. a. 3 b. 2 c. 2
d. 2 e. 5 f. 15

3. a. 10 b. 56 c. 84
d. 60 e. 44

4. a. 485 b. 6208
c. 2761 d. 80 045

5. a. 85 064 remainder 2 b. 86 047 remainder 3
c. 904 074 remainder 2 d. 60 074 remainder 2

6. a. 700 b. 7 c. 900
7. a. 500 b. 5000 c. 800
8. 72
9. 214
10. 532
11. a. \$208 b. \$48
12. 186 cows
13. Number of tables required: 19; total number of courses to be served: 608; number of waiters required: 8; total charge for catering: \$8360
14. a. 950 m^2 b. \$794 750
15. Kayla: $243 \div 9 = 27$

$$9\overline{)2^{2}4^{6}3}\ \ 027$$

16. The statement is false.
17. a. 37 b. 3
18. \$16 per night
19. There needs to be 8 tables.
20. 10, 18, 26. Students should mention that the pattern in the solution differs by the divisor and that it is found by adding the remainder to each of the multiples.

Exercise 1.7 Rounding and estimating

1. a. 10 b. 50 c. 1000
   d. 10 000 e. 200 000 f. 5 000 000
2. 28 000 000
3. Estimation table:

	Estimate	Estimated answer	Actual answer
a.	500 + 1000	1500	1449
b.	30 000 + 80 000	110 000	115 670
c.	200 000 + 700 000	900 000	907 448
d.	90 000 − 40 000	50 000	55 880
e.	300 − 200	100	127
f.	500 000 − 200 000	300 000	296 049
g.	40 × 200	8000	7128
h.	600 × 10 000	6 000 000	7 894 033
i.	30 000 × 40	1 200 000	1 149 954
j.	30 000 ÷ 1000	30	32.907 58
k.	60 000 ÷ 3000	20	24.325 483
i.	70 000 ÷ 1000	70	53.385 505

4. D
5. B
6. B
7. a. 8000 b. 100 c. 400 000
   d. 700 000 e. 11 000
8. a. 6000 b. 8 000 000 c. 100
   d. 40 000 000 e. 500
9. B
10. D
11. A
12. D
13. a. 1500 tickets b. \$11 250
14. a. i. 6000 ii. 5340
    b. i. 8000 ii. 8028
    c. i. 50 ii. 46.677 749
15. \$29
16. ≈ 1200 (10 × 10 × 12). There are approximately 10 seats in each row and about 10 rows of students, so there are approximately 100 students in the photograph.
17. 900 students
18. It is important not to estimate calculations by rounding when a very accurate answer is needed.
19. \$7270
20. a.

Item	Estimated cost
Bread rolls	\$75
Hamburgers	\$50
Tomato sauce	\$4
Margarine	\$4
Onions	\$4
Tomatoes	\$8
Lettuce	\$5

    b. \$150 c. \$600 d. \$450

Exercise 1.8 Order of operations

1. a. 5 b. 9 c. 3
   d. 30 e. 59
2. a. 25 b. 7 c. 96
   d. 0
3. a. 15 b. 24 c. 32
   d. 18 e. 76 f. 27
4. a. 7 b. 12 c. 96
   d. 27 e. 18 f. 3
5. a. $(12 - 8) \div 4 = 1$
   b. $(4 + 8) \times 5 - 4 \times 5 = 40$
   c. $3 \times (10 - 2) \div 4 + 4 = 10$
   d. $12 \times (4 + 2) - 12 = 60$
   e. $10 \div (5 + 5) \times 9 \times 9 = 81$
   f. $(18 - 3) \times 3 \div 5 = 9$
6. a. 18 b. 14 c. 0 d. 22
7. a. 2 b. 27 c. 0 d. 1
8. a. 3 b. 18 c. 40 d. 77
9. a. 23 b. 18 c. 2 d. 15

10. **a.** 8 **b.** 21 **c.** 16 **d.** 0

11. **a.** 27 **b.** 3 **c.** 21 **d.** 32

12. C

13. B

14. D

15. **a.** $6 + 2 \times (4 - 3) \times 2 = 10$
b. $(6 + 2) \times 4 - 3 \times 2 = 26$
c. $6 + (2 \times 4 - 3) \times 2 = 16$
d. $6 + 2 \times 4 - 3 \times 2 = 8$, no brackets required

16. **a.** $274 + 2 \times -68 + 3 \times 50 = \$288$
b. 600 apples
c. 8 kg

17. When dealing with money.

18. Keenan ($6 + 6 \div 3 = 6 + 2 = 8$)

19. 43 pebbles

20. $229.20

21. **a.** $3 \times (4.25 + 4.75) + 2 \times 3.75$
b. $34.50

22. **a.** Sydney 9h ahead
b. Singapore 6h ahead

23. Two possible solutions: 2 packets with 3 ice creams and 5 packets with 5 ice creams, or 7 packets with 3 ice creams and 2 packets with 5 ice creams.
With further investigation of the number pattern obtained by summing 3s and 5s, it appears that there are combinations of 3 packs and 5 packs that will amount to any quantity of ice creams equal to or larger than 8.

24. An example is shown below.
$1 = (4 - 3) \div (2 - 1)$
$3 = 21 \div (3 + 4)$
$5 = 3 + 4 - (2 \times 1)$

25. An example is shown below.
$5 = 4 + 3 - (2 \times 1)$
$6 = 3 \times 4 \div (2 \times 1)$
$8 = 4 \times (3 - 2 + 1)$
$9 = 4 + 3 + 2 \div 1$

Project

1. 1 530 430
2. 
3. 
4. 
5. 
6. 
7. List any difficulties you encountered.

8.

Symbol	Value	Symbol	Value
α	1	ξ	60
β	2	o	70
γ	3	π	80
δ	4	φ or ζ	90
ε	5	ρ	100
ζ or F	6	σ	200
ξ	7	τ	300
η	8	υ	400
θ	9	ϕ	500
ι	10	χ	600
κ	20	ψ	700
λ	30	ω	800
μ	40	$\bar{\text{3}}$	900
ν	50		

9. Adding a subscript or superscript *iota* (Greek letter for 10) with the symbols used for 1 to 9 represented the numbers 1000 to 9000. *M* was used to represent 10 000. When symbols were placed on top of the *M*, this meant that the value of the symbols was multiplied by 10 000. This enabled the ancient Greeks to represent larger numbers.

10. Sample response can be found in the worked solutions in the online resources.

Exercise 1.9 Review questions

1. **a.** 7 **b.** 40 000
c. 1 000 000 **d.** 90

2. **a.** $300 + 90 + 2$ **b.** $4000 + 100 + 9$
c. $40\,000 + 2000 + 1$ **d.** $100\,000 + 20\,000$

3. 349, 394, 934, 943, 3499, 3994

4. 1101, 1100, 1011, 110, 101


5. **a.** 127 **b.** 3187
c. 7641 **d.** 4 217 656

6. **a.** 2 **b.** 35 **c.** 150 **d.** 14

7. **a.** 415 **b.** 217 **c.** 60 322
d. 37 758 **e.** 92 957


8. **a.** 150 **b.** 8400 **c.** 1240
d. 603 **e.** 589

9. a. 3×6




There are 18 balls = 18

b. 5×4



There are 20 balls = 20

c. 2×7



There are 14 balls = 14

10. a. 96 **b.** 1072 **c.** 3210

11. a. 1416 **b.** 1388 **c.** 3375

12. a. 1152 **b.** 2286 **c.** 19 200

13. a. 4608 **b.** 30 894 **c.** 18 355 064

14. a. 129 **b.** 260 **c.** 5021

15. a. 8 **b.** 3 **c.** 84 **d.** 45 **e.** 1

16. a. 700 **b.** 7 **c.** 410

17. a. 1568 **b.** 981 **c.** 537 r 3
d. 335 r 7 **e.** 911 r 9

18. a. 14 000 **b.** 5000 **c.** 50
d. 420 000 **e.** 120 000 **f.** 210 000

19. C

20. a. < **b.** = **c.** > **d.** >

21. a. 327 **b.** 1090 **c.** 789 **d.** 216

22. a. 127 **b.** 81 **c.** 711 **d.** 278

23. a. 28 **b.** 24 **c.** 10 **d.** 8 **e.** 11 **f.** 27

24. a. 12 **b.** 30 **c.** 5
d. 900 **e.** 14 **f.** 25

25. a. < **b.** = **c.** > **d.** <

26. a. < **b.** < **c.** > **d.** >

27. 23.5

28. a. 5 **b.** 38 **c.** 6 **d.** 5 **e.** 70 **f.** 29

29. a. 306 km **b.** 322 km **c.** 482 km

30. a. 448 **b.** 3136 **c.** 98

31. As long as one of the factors in a multiplication is even, the result will be even. Otherwise, the answer will be odd.

32.
$$\begin{array}{r} 8240 \\ -3681 \\ \hline 4559 \end{array}$$

33. 95

34. a. $8 \times 3 + 12 \times 2$ **b.** $48

35. 20 499

36. a.

+	6	10	3
5	11	15	8
12	18	22	15
9	15	19	12

b.

×	4	8	6
3	12	24	18
5	20	40	30
2	8	16	12

37. a. 24 °C **b.** −21 °C

38. 21 questions for 3 marks

39.

8	+	4	×	6	=	32
+	■	×	■	×	■	■
3	−	5	+	9	=	7
×	■	÷	■	÷	■	■
7	−	2	−	1	=	4
=	■	=	■	=		
29	■	10	■	15		

40. 2019 and 2018

2 Positive and negative integers

LEARNING SEQUENCE


2.1 Overview 68
2.2 Integers on the number line 70
2.3 Integers on the number plane 76
2.4 Adding integers 81
2.5 Subtracting integers 86
2.6 Multiplying and dividing integers (extending) 92
2.7 Order of operations with integers (extending) 98
2.8 Review 102



2.1 Overview

Why learn this?

Integers are whole numbers. They can be positive, negative or equal to zero. Positive integers have values above zero and negative integers have values below zero.



If you live in the southern parts of Australia, overnight temperatures often fall below zero in winter. These very cold temperatures are written as negative integers. In summer the generally very hot temperatures are written as positive integers.

Using your understanding of the basic operations of addition, subtraction, multiplication and division, you can measure the temperature changes throughout a single day. You can also measure the average daily temperature over a month and use those measurements to compare your home town to other parts of Australia, or other parts of the world.

In finance, positive numbers are used to represent the amount of money in someone's bank account, while negative numbers are used to represent how much money someone owes, for example how much they have to pay back after borrowing money or taking out a loan from a bank.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 2.1 Pre-test

learnON


Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. Write an integer to express the following.
   a. A debt of $250
   b. 15 metres below sea level
   c. The temperature is 20°C

2. Complete each statement by placing $<, >$ or $=$ in the empty box so that the statement is true.
   a. $-3 \square 2$ b. $-5 \square -7$ c. $-21 \square -17$ d. $0 \square -8$

3. MC Select which of the following options has the numbers $-5, 8, 2, 0, -1, -8, 3$ arranged in ascending order.
   A. $8, -5, -1, 0, 2, 3, -8$ B. $-8, -5, -1, 0, 2, 3, 8$ C. $0, -1, 2, 3, -5, -8, 8$
   D. $-8, 5, -1, 0, 2, 3, 8$ E. $-1, 0, 2, 3, -5, -8, 8$

4. Determine the coordinates of point A in the graph.



5. MC Select the quadrant in which the point $(-7, -1)$ is located.
   A. First B. Second C. Third D. Fourth E. On the x-axis

6. MC If the points $(-2, -2)$, $(-2, 2)$, $(2, 2)$ and $(2, -2)$ were plotted on a Cartesian plane and joined by straight lines, select the shape this would make.
   A. Rectangle B. Circle C. Square D. Trapezium E. Kite

7. Calculate the following.
   a. $3 + -5 =$ b. $7 - -6 =$ c. $-7 + -12 =$ d. $-16 + 5 =$

8. Write the number that is 12 more than -5.

9. Narelle went for a hike at Mount Baw Baw. From her starting point, she climbed up 72 m and then descended 15 m, before ascending a further 21m. Determine how far above her starting point she is now.

10. Evaluate -8×-6.

11. Evaluate the following.
    a. $7 \times 6 \div 3 \div 7$ b. $3 \times 8 \div 6 + 4$ c. $7 + [66 - (5 \times 5)] \times 3$

12. MC Select the simplified form of the algebraic expression $5g \times -3h \times -6k$.
    A. $-15\,ghk$ B. $18\,ghk$ C. $-90\,ghk$ D. $90\,gh$ E. $90\,ghk$

13. If $a = -5$, $b = 4$ and $c = -2$, evaluate $4(a - b) \div 3c$.

14. Hang has $340 in the bank. She makes a deposit of $75 each month for the next three months, before withdrawing $185 to buy a new dress. Determine the amount of money Hang has left in her account.

15. To improve goal kicking a new training drill was developed. In this training run, kicking a goal scores you 6 points, but missing a goal loses you 2 points. If a team had 30 shots at goal and kicked 21 goals, determine how many points they scored.

2.2 Integers on the number line

LEARNING INTENTION

At the end of this subtopic you should be able to:
- place integers on a number line
- compare integer values.

2.2.1 Integers

eles-3695

- **Whole numbers** are the numbers 0, 1, 2, 3, 4 ...
- **Integers** are positive and negative whole numbers. 0 is also an integer.
- The numbers ... − 3, −2, −1, 0, 1, 2, 3 ... are integers.
- The integers −1, −2, −3 ... are **negative integers**.
- The integers 1, 2, 3 ... are **positive integers**. They can also be written as +1, +2, +3 ...
- 0 is an integer. It is neither positive nor negative.
- The direction of an integer indicates whether it is positive or negative. The + sign can be used to represent either an addition (if it appears between two quantities) or the direction of an integer (if it appears in front of an integer). In the same way, the − sign can be used to represent either a subtraction or the direction of an integer.



DISCUSSION

Can you think of an example of negative numbers that we encounter in everyday life?

WORKED EXAMPLE 1 Converting a description into an integer

Write the integer that is suggested by the following descriptions.
a. My flat is on the 5th floor.
b. This town is 20 m below sea level.

THINK	WRITE
a. Numbers above 0 are positive, so place a + sign before the number.	a. +5 (or 5)
b. Numbers below 0 are negative, so place a – sign before the number.	b. −20


2.2.2 The number line

eles-3696

- Integers can be represented on a number line. On a number line, positive integers are written to the right of 0, while negative integers are written to the left of 0.



- The **magnitude** of an integer shows the size of the integer in terms of its distance from 0. For example, the number −3 is negative and has a magnitude of 3. This means it is a distance of 3 units from 0.
- The further a number is to the right of any number on a number line, the larger it is. For example, +5 is greater than +2, while + 2 is greater than 0 and 0 is greater than −5.
- **Opposite integers** are the same distance from 0, but on opposite sides of 0. For example, 3 and −3 are opposite integers because they are both 3 units from 0.




WORKED EXAMPLE 2 Placing integers on a number line

Place the integers 9, −2, −7, 5 on a number line.

THINK

1. Draw a number line from −10 to 10 so that you can include all of the numbers.
2. Mark the values 9, −2, −7, 5 on the number line.

WRITE




WORKED EXAMPLE 3 Writing integers in numerical order

Use a number line to help list the integers −4, 2, − 3, 1 in numerical order.

THINK

1. Draw a number line from −5 to 5 so that you can include all of the numbers.
2. Mark the values. As you move from left to right on the number line, the numbers become larger.

WRITE



In numerical order: −4, −3, 1, 2

WORKED EXAMPLE 4 Determining the opposite of an integer

Write opposites for the following integers.

a. -2 **b.** 3 **c.** 4

THINK	WRITE
a. An opposite integer is the same distance from 0, but has the opposite sign.	**a.** The opposite of -2 is 2.
b. An opposite integer is the same distance from 0, but has the opposite sign.	**b.** The opposite of 3 is -3.
c. An opposite integer is the same distance from 0, but has the opposite sign.	**c.** The opposite of 4 is -4.

Comparing integers

- The following inequality symbols can be used when comparing integers.
  $>$ means 'greater than'
  $<$ means 'less than'
  $\geq$ means 'greater than or equal to'
  $\leq$ means 'less than or equal to'
- Remember that inequality signs look a little bit like a crocodile's mouth. When placing an inequality symbol between two numbers, the crocodile's mouth always opens up to eat the larger number.

WORKED EXAMPLE 5 Comparing integers

Complete each statement by inserting the correct symbol: < or >.


a. $2 \square 5$ **b.** $-4 \square -1$ **c.** $0 \square -3$ **d.** $6 \square -2$

THINK	WRITE
a. 2 sits to the left of 5 on the number line, so 2 is smaller.	**a.** $2 < 5$
b. -4 sits to the left of -1 on the number line, so -4 is smaller.	**b.** $-4 < -1$
c. 0 is to the right of -3 on the number line, so 0 is larger.	**c.** $0 > -3$
d. 6 is to the right of -2 on the number line, so 6 is larger.	**d.** $6 > -2$

eles-3697

2.2.3 Using positive and negative numbers in daily life

- Sometimes we need to use numbers smaller than zero in everyday situations.
- Because positive and negative numbers show both their size and their direction away from zero, they are often referred to as **directed numbers**.
- Directed numbers are often used to measure objects from a reference point, for example, the temperature above or below zero, the height above or below sea level, or archaeological measurements that show the depth beneath the Earth's surface. Directed numbers are also used when describing banking transactions. Withdrawals of money from a bank account are shown using negative signs while deposits into a bank account are shown using positive signs.



WORKED EXAMPLE 6 Converting a statement into a directed number

Write the integer that is suggested by each of the following situations.
a. The temperature was 1 degree below zero.
b. Romie has $500 in her bank account.

THINK	WRITE
a. 'Below zero' means negative.	a. -1
b. Romie has money in her account, so the integer is positive.	b. $+500$

on Resources

eWorkbook	Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)
Digital documents	SkillSHEET Using < or > to compare the size of numbers (doc-6563) SkillSHEET Ascending and descending order (doc-6564) SkillSHEET Marking numbers on a number line (doc-6565) SkillSHEET Working with numbers on a number line (doc-6566)
Interactivities	Individual pathway interactivity: Integers on the number line (int-4367) Number line (int-4033)

Exercise 2.2 Integers on the number line

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10	2, 5, 8, 11	3, 6, 9, 12

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency



1. WE1&6 Write the integer suggested by each of the following descriptions.
   a. The temperature today is 7 degrees below zero.
   b. The penthouse is on the 10th floor.
   c. The Dead Sea is 422 m below sea level.
   d. Mount Kosciuszko is 2228 m above sea level.
   e. The Dow Jones dropped 3 points overnight.
   f. Chloe borrowed $30 from her mother.

2. WE2 Draw a number line from -10 to 10. Mark the following values on your number line.

a. 2	b. -4	c. -9	d. 7
e. 5	f. -1	g. 0	h. -3

Understanding

3. WE3 Use a number line to place the following numbers in numerical order.
   a. $5, -2, 3, -6, 7$ b. $0, -1, 3, -4, -6$ c. $-5, 7, -2, -3, 1$ d. $-4, 2, 1, -3, 5$

4. WE4 Write opposite integers for the following.
   a. -6 b. 7 c. 1 d. -8

5. WE5 Complete the following by inserting $<$ or $>$ in the box.
   a. $2 \square -5$ b. $3 \square 7$ c. $-2 \square -6$
   d. $6 \square -2$ e. $-1 \square 3$ f. $-10 \square -6$

6. From the following lists, select:
   i. the smallest number
   ii. the largest number.
   a. $-3, 7, -5$ b. $2, -4, 5, 3, -2$ c. $7, -10, 5, -2, -4$ d. $-4, -1, 3, 0, -2$

Reasoning

7. The temperature in Oslo dropped to -6 °C overnight. During the day, the temperature rose by 4 °C. Determine the maximum temperature on that day. Show full working.

8. A new apartment building is being built. It will include a ground floor reception area. If there will be 10 floors of apartments and 3 floors of underground parking, how many buttons will be needed in the lift? Explain your answer.

9. Lake Mungo, part of Mungo National Park in New South Wales, is a World Heritage listed area. Archaeologists estimate that the lake dried out 1800 years ago and, before that, Aboriginal people lived on the shores of the lake. Lake Mungo became one of the world's most significant archaeological sites following the discovery there of some of the oldest remains of human civilisation on Earth.
   Explain what $-60\,000$ could mean in terms of human occupation in the area around Lake Mungo.



Problem solving

10. Raj and Vanessa are going home from school in opposite directions. Raj lives 1.2 km south of the school and Vanessa lives 1.6 km north of the school.



a. Draw a number line to represent the three locations: Raj's house, Vanessa's house and the school. Label the three locations with directed numbers.

b. Determine how far apart Raj and Vanessa live from each other.

11. An aeroplane flying at 12 km above sea level flies directly over a submarine travelling at 500 m below sea level.

a. Draw a number line to represent the three locations: the aeroplane, the submarine and the ocean level. Label the three locations with directed numbers.

b. Evaluate the distance between the submarine and the aeroplane.

12. a. Historians use BCE (Before Common Era) and CE (Common Era) when discussing dates. Explain what is meant by 2000 CE.

b. If the millennium year 2000 CE (+2000) was considered to be zero, determine the:

i. integer value that the year 2010 would represent

ii. integer value that the year 1894 would represent.

c. Human exploration of space started in 1957, which led to new discoveries. The successful orbit of Earth by Sputnik I gave hope to humans that one day they would enter space and even walk on the Moon. If we consider 1957 as being zero, state the directed numbers that could be used to describe the following information.



i. Cosmonaut Yuri Gagarin was the first man to enter space — 1961

ii. Neil Armstrong and Edwin 'Buzz' Aldrin of Apollo 11 were the first humans to walk on the Moon — 1969

iii. Sally Ride was the first American woman in space — 1983

iv. *Discovery* was the first shuttle to dock with the International Space Station — 1999

v. *Rosetta* was the first man-made probe to make a soft landing on a comet — 2014

d. Draw a number line from −10 to 60 to show your answers to part **c**.

2.3 Integers on the number plane

LEARNING INTENTION


At the end of this subtopic you should be able to:

- understand the number plane (also called the Cartesian plane), origin and coordinates
- infer the location of a point described by its coordinates
- plot one or more points using their coordinates.

2.3.1 Positive integers and zero on the number plane


eles-3698

- The **number plane,** also called the Cartesian plane, has two axes: the horizontal axis, also called the x-axis, and the vertical axis, also called the y-axis.
- Every point on the number plane can be described by its position relative to the x- and y-axes.
- A pair of coordinates, also called an ordered pair (x, y), fixes the position of a point. The x value shows the point's distance along the x-axis, while the y value shows the point's distance along the y-axis.
- The x- and y-axes on the number plane can be extended to include negative integers, as shown in this graph.



WORKED EXAMPLE 7 Determining the coordinates

Determine the coordinates of the following points in the number plane shown.



a. A **b. B**

THINK

a. Point A is 1 unit to the right of zero along the x-axis and 4 units above zero along the y-axis.

b. Point B lies on the y-axis, so it is 0 units to the right of zero along the x-axis. It is 2 units above zero along the y-axis.

WRITE


a. A (1, 4)

b. B (0, 2)

2.3.2 Integers on the number plane


eles-3699

- The origin (0, 0) is the point where the x- and y-axes intersect to divide the number plane into 4 quadrants. The origin is labelled as '0'.
- Each of the 4 quadrants of the number plane is numbered in an anticlockwise direction.
- The first quadrant is the quadrant with positive x and positive y values.
- The second quadrant is the quadrant with negative x and positive y values.
- The third quadrant is the quadrant with negative x and negative y values.
- The fourth quadrant is the quadrant with positive x and negative y values.
- The illustration demonstrates the position of points on the number plane.
  - A (3, 2) — move 3 right and 2 up
  - B (−3, 2) — move 3 left and 2 down
  - C (−3, −2) — move 3 left and 2 down
  - D (3, −2) — move 3 right and 2 down



WORKED EXAMPLE 8 Determining the coordinates, quadrant and axis

Write the coordinates and state the quadrant or axis of each point on this number plane.



THINK

a. 1. A is 2 units to the right of the origin along the x-axis and 3 units down from the origin along the y-axis.

2. A is in the lower right-hand corner.

b. 1. B is 1 unit to the left of the origin along the x-axis and 0 units up or down from the origin along the y-axis.

2. B is on the x-axis.

WRITE

a. A (2, −3)

A is in the fourth quadrant.

b. B (− 1, 0)

B is on the x-axis.

on Resources

eWorkbook Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)

Interactivities Individual pathway interactivity: Integers on the number plane (int-4368)
Integers on the number plane (int-4035)
Positive integers and zero on the number plane (int-4034)

Exercise 2.3 Integers on the number plane

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 4, 7, 10, 13, 16, 19	3, 6, 8, 12, 15, 17, 20	5, 9, 11, 14, 18, 21, 22

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


Questions **1** and **2** refer to the graph shown.

1. WE7 Determine the coordinates of the following.

a. A **b.** B **c.** C **d.** D **e.** E

2. Match a letter to the points with the following coordinates.

a. (0, 0) **b.** (6, 6) **c.** (8, 1) **d.** (1, 8)



3. MC Select the quadrant in which all the points have negative x and negative y coordinates.

A. Quadrant 1 **B.** Quadrant 2 **C.** Quadrant 3
D. Quadrant 4 **E.** None of the above

4. MC Select the quadrant in which all the points have positive x and negative y coordinates.

A. Quadrant 1 **B.** Quadrant 2 **C.** Quadrant 3
D. Quadrant 4 **E.** None of the above


5. If the x-axis represents the direction from west to east, and the y-axis represents the direction from south to north, calculate the coordinates if a person starts at the origin and walks 5 m west and then 2 m north.

Understanding

Use the graph shown to work out the answers to questions **6** through **10**.

6. WE8 Write the coordinates and state the quadrant or axis of each of the following points.

a. A
b. B
c. H
d. F
e. J



7. Match the following points to a letter and state their quadrant or axis.

a. $(-5, 2)$ **b.** $(0, 5)$ **c.** $(3, -3)$ **d.** $(2, 5)$ **e.** $(-3, 0)$

8. Calculate the x-coordinate of the following points.

a. A **b.** D **c.** K **d.** L

9. Calculate the y-coordinate of the following points.

a. C **b.** J **c.** G **d.** F

10. State all the points lying in the third quadrant in the number plane.

11. Determine whether the following statements are true or false.

a. The origin has coordinates $(0, 0)$.
b. The point at $(3, 5)$ is the same point as at $(5, 3)$.
c. The point at $(-5, 4)$ is in the third quadrant.
d. The point at $(0, 2)$ must lie on the y-axis.

12. MC Select where the point $(5, -2)$ lies.

A. In the first quadrant **B.** In the second quadrant
C. In the third quadrant **D.** In the fourth quadrant
E. On the x-axis

13. MC Select where the point $(0, 4)$ lies.

A. In the first quadrant **B.** On the y-axis
C. In the third quadrant **D.** In the fourth quadrant
E. On the x-axis

14. MC Select where the point $(-4, 5)$ lies.

A. In the first quadrant **B.** In the second quadrant
C. In the third quadrant **D.** In the fourth quadrant
E. On the x-axis

15. Draw a number plane with both axes scaled from -6 to 6. Plot the points listed and join them with straight lines in the order given. State the name for each completed shape.


a. $(5, 5), (3, 2), (-2, 2), (0, 5), (5, 5)$
b. $(4, -1), (4, -5), (-1, -3), (4, -1)$
c. $(-4, 4), (-2, 1), (-4, -5), (-6, 1), (-4, 4)$
d. $(-2, 1), (1, 1), (1, -2), (-2, -2), (-2, 1)$

Reasoning

16. Consider the graph relating to question **6** and explain whether the points F and D have the same y-coordinate, and whether points A and D have the same x-coordinate.

17. Consider the graph shown.

a. Determine the coordinates of a point, C, so that ABCD is a parallelogram.
b. Determine the coordinates of a point, F, so that DBEF is a kite shape.
c. Show that the point $(4, -1)$ lies on the line that passes through D and the origin.
d. List 2 points on the line joining D to E.
e. Give the coordinates of a point, T, in the third quadrant that would complete the isosceles triangle ADT.




18. **a.** If you were moving east and then you did a U-turn, determine the direction you would then be moving in. Assume that a U-turn is the same as putting a negative sign in front of you.
b. Determine the direction you would be facing if you had two negative signs in front of you.
c. Determine the direction you would be facing if you had three negative signs in front of you.
d. Determine the direction you would be facing if you had ten negative signs in front of you.
e. Determine the direction you would be facing if you had 101 negative signs in front of you. Explain your answer.
f. Explain what would happen if you were moving north and then you made a U-turn (which would mean putting a negative sign in front of you). Determine the direction you would be moving in after you did the U-turn.
g. If you were moving north, explain which direction you would be facing after an odd number of negative signs. Explain which direction you would be facing after an even number of negative signs.

Problem solving


19. Eugenia uses a remote control to move a robot car on a grid map. The robot car moves from point (7, 5) to point (7, −4). Determine the distance travelled by the robot car.



20. The streets in Metropolis run north–south and east–west, as shown in the diagram. Adam wants to visit Betty. If he can travel only south or east, determine how many paths he can follow.



21. The tennis court shown is enclosed in an area that has a post in each corner.



a. Draw a number plane with the origin in the centre of the court.
b. Determine the coordinates of the four posts on the number plane drawn in part **a**.

22. If you swap the x- and y-coordinates of a point, the position of the point may change to another quadrant. Determine what happens to points from each quadrant if you swap their coordinates.

2.4 Adding integers


LEARNING INTENTION

At the end of this subtopic you should be able to:
- understand how a number line can be used to add integers
- use a number line to add integers
- add integers without the aid of a number line.


2.4.1 Addition of integers


eles-3700

- A number line can be used to add integers.
- When adding a positive integer, move right along the number line.
- When adding a negative integer, move left along the number line.



- Consider the addition of $-1+(+4)$.





Symbol	Meaning	Action to take
-1	Starting point	Start at -1.
$+$	Direction to face on the number line	Face right for addition $+$.
$(+)$	Direction to move on the number line	Move forward for positive $(+)$.
(4)	Number of steps to take from the starting point	Move 4 places from -1.
$=$	Finishing point	Stop at $+3$.

Therefore, $-1+(+4)=+3$

WORKED EXAMPLE 9 Adding integers using a number line

Calculate the value of each of the following, using a number line.

a. $-5 + (+3)$ **b.** $-5 + (-3)$

THINK

a. 1. Start at -5 and face right (because this is an addition). Move 3 steps forward (because this number is positive). The finishing point is -2.


2. Write the answer.

b. 1. Start at -5 and face right (because this is an addition). Take 3 steps backwards (because this number is negative). The finishing point is -8.

2. Write the answer.


WRITE

a.



$-5 + (+3) = -2$

b.




$-5 + (-3) = -8$


WORKED EXAMPLE 10 Writing a number sentence from a number line

Write number sentences to show the addition problems in the following diagrams.

a.



b.



THINK

a. 1. The first integer is 2 units to the left of zero, so start at -2. The second integer is 4 units to the left of -2, finishing at -6.


2. Write the number sentence.

b. 1. The first integer is 2 units to the left of zero, so start at -2. The second integer is 5 units to the right of -2, finishing at $+3$.

2. Write the number sentence.


WRITE

a.



$-2 + (-4) = -6$

b.



$-2 + (+5) = +3$

Addition of integers using the sign model

- In the sign model, a − sign and a + sign cancel each other out. This model can be used to add integers, as shown in Worked example 11.

WORKED EXAMPLE 11 Adding integers using the sign model

Use the sign model to calculate each of the following.

a. $-4+(+1)$ **b.** $+5+(-3)$

THINK	WRITE
a. 1. Show −4 as four negative signs.	**a.** $----$
2. Show +1 as one positive sign.	$+$
3. Cancel out the opposite signs. There are 3 negative signs left over.	$\not{+}\not{-}\not{-}\not{-}$ $\not{+}$
4. Write the answer.	$-4+(+1)=-3$
b. 1. Show +5 as 5 positive signs.	**b.** $+++++$
2. Show −3 as 3 negative signs.	$---$
3. Cancel out the opposite signs. There are 2 positive signs left over.	$\not{+}\not{+}\not{+}\not{-}\not{-}\not{-}++$
4. Write the answer.	$+5+(-3)=+2$


WORKED EXAMPLE 12 Evaluating an algebraic expression

Evaluate the algebraic expression $a+2b+c$, if $a=-2$, $b=1$ and $c=-5$.

THINK	WRITE
1. Write the algebraic expression.	$a+2b+c$
2. Substitute each pronumeral with the appropriate integer.	$=-2+2\times1+(-5)$
3. Evaluate the expression by using the addition rule for addition of integers.	$=-2+2-5$
4. Write the answer.	$=-5$

Digital technology

Scientific calculators can evaluate the addition of positive and negative numbers.



Resources

eWorkbook Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)
Interactivities Individual pathway interactivity: Adding integers (int-8458)
Addition of integers (int-4036)

Exercise 2.4 Adding integers

learnON

Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 10, 13, 16	2, 4, 7, 11, 14, 17	5, 8, 9, 12, 15, 18, 19


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency


1. WE9 Calculate the value of each of the following.
   a. $-25+(+10)$ b. $-7+(-3)$ c. $6+(-7)$
   d. $-8+(-5)$ e. $13+(+6)$ f. $16+(-16)$


2. WE10 Write number sentences to show the addition problems in the following diagrams.

a. 

b. 

c. 

d. 

e. 

f. 

3. WE11 Use the sign model to calculate each of the following.
   a. $+2+(-3)$ b. $+3+(-4)$ c. $+4+(-4)$
   d. $+3+(-2)$ e. $-4+(+2)$

4. Calculate each of the following using number sentences. (Draw a number line or other model if you wish.)
   a. $5+(-2)$ b. $-3+(-4)$ c. $-2+2$
   d. $6+(-5)$ e. $-5+5$

5. Calculate each of the following using number sentences. (Draw a number line or other model if you wish.)
   a. $4+(-6)$ b. $-5+7$ c. $6+(-9)$ d. $3+(-3)$ e. $0+(-6)$

6. Write the answer for each of the following.
   a. $-5+(-2)$ b. $-6+4$ c. $-8+8$
   d. $3+(-7)$ e. $-3+7$ f. $-3+(-7)$

7. Write the answer for each of the following.
   a. $-8+12$ b. $19+(-22)$ c. $-64+(-36)$
   d. $-80+90$ e. $-2+4$ f. $-15+(-7)$

8. Copy and complete this addition table.

+	–13	5
21		
–18		

9. **WE12** Evaluate each algebraic expression, if $a = 3, b = 2, c = -4$.

a. $a + b$ **b.** $b + c$ **c.** $a + b + c$ **d.** $c + 2b + a$

Understanding

10. Determine the missing number in each of these incomplete number sentences.

a. $8 + ____ = 0$ **b.** $-2 + ____ = -8$ **c.** $_____ + (-6) = 4$

d. $_____ + 5 = -2$ **e.** $_____ + (-5) = -2$

11. **a.** Copy and complete the addition table shown.

b. **i.** Determine the pattern shown along the leading (dotted) diagonal.

ii. Determine the pattern shown along the other (unmarked) diagonal.

iii. State whether the chart is symmetrical about the leading diagonal.

+	–2	–1	0	1	2
–2		–3			
–1				0	
0	–2				
1					
2					

12. Model each situation with an integer number sentence that shows the result of the following.

a. From ground level, a lift went down 2 floors, then up another 3 floors.

b. From ground level, a lift went down 3 floors, then up 5 floors.

c. Australia was 50 runs behind, then made another 63 runs.

d. A submarine at sea level, dived 50 metres then rose 26 m.

e. An account with a balance of $200 had $350 withdrawn from it.

Reasoning

13. Describe a situation to fit each of the following number sentences.

a. $-3 + (-2) = -5$ **b.** $-10 + (-40) = -50$ **c.** $2 + (-6) = -4$

d. $-20 + 20 = 0$ **e.** $-8 + 10 = 2$

14. **a.** Write a rule starting with 'When adding two negative numbers…'

b. Write a rule starting with 'When adding a negative number and a positive number…'

15. Arrange the numbers in this magic square so that all rows, columns and diagonals add up to the same value. No numbers can be used twice.

2		
4	–1	–6

Problem solving

16. Kuni has a sporting equipment business. Due to a financial crisis, she lost $2500 after six months and then lost $3075 by the end of the year. Calculate the total amount that Kuni lost by the end of the year.



17. In an AFL match, Dustin Martin scored two goals in the first quarter and was awarded six points for each. He scored three behinds in the fourth quarter and was awarded 1 point for each. Calculate the total points gained by Dustin for his team.

18. Avery parks her car in a car park two floors below ground level. She takes a lift to the shopping centre and goes up seven floors. Then she takes a lift down three floors to catch up with her friend Lucy. Determine the floor at which Avery gets off to meet Lucy.



19. Determine the effect of adding a number to its opposite integer.

2.5 Subtracting integers


LEARNING INTENTION

At the end of this subtopic you should be able to:
- understand how a number line can be used to subtract integers
- use a number line to subtract integers
- subtract integers without using a number line.


2.5.1 Subtraction of integers


eles-3701

- A number line can be used to subtract integers.
- Subtracting a number gives the same result as adding its opposite integer.
- When subtracting a positive integer, move left along the number line.
- When subtracting a negative integer, move right along the number line.



- Consider the subtraction of $12 - (+4)$.





Symbol	Meaning	Action to take
12	Starting point	Start at 12.
–	Direction to face on the number line	Face left for subtraction –.
(+)	Direction to move on the number line	Move forward for positive (+).
(4)	Number of steps to take from the starting point	Move 4 places from 12.
=	Finishing point	Stop at +8.

Therefore, $12 - (+4) = +8$

WORKED EXAMPLE 13 Subtracting integers using a number line

Calculate the value of each of the following, using a number line.

a. $-2 - (+3)$ **b.** $-2 - (-3)$

THINK

a. 1. Start at −2 and face left (because this is subtraction). Take 3 steps forwards (because the number being subtracted is positive). The finishing point is −5.


2. Write the answer.

b. 1. Start at −2 and face left (because this is subtraction). Take 3 steps backwards (because the number being subtracted is negative). The finishing point is +1.

2. Write the answer.


WRITE

a.



$-2 - (+3) = -5$

b.



$-2 - (-3) = +1$

2.5.2 Subtracting integers by adding opposites

eles-4091

- By developing and extending a pattern, we can show that subtracting negatives has the same effect as adding a positive. This means that subtracting a negative integer is the same as adding the opposite integer. For example, as demonstrated in part **b** of Worked example 13:

$$\begin{aligned} -2-(-3) &= -2+(+3) \\ &= -2+3 \\ &= +1 \end{aligned}$$

WORKED EXAMPLE 14 Subtracting integers

Calculate the following.

a. $2-5$ **b.** $-3-6$ **c.** $5-(-3)$ **d.** $-5-(-4)$

THINK

a. 1. Write the question.

2. Rewrite the equation, changing subtraction to addition of the opposite integer.

3. Add, using the addition rule for addition of integers.
- Start at +2.
- Face right for addition.
- Move backwards 5 units.

b. 1. Write the question.

2. Rewrite the equation, changing subtraction to addition of the opposite integer.

3. Add, using the addition rule for addition of integers.
- Start at −3.
- Face right for addition.
- Move backwards 6 units.

c. 1. Write the question.

2. Rewrite the equation, changing subtraction to addition of the opposite integer.

3. Add, using the addition rule for addition of integers.
- Start at +5.
- Face right for addition.
- Move forward 3 units.

d. 1. Write the question.

2. Rewrite the equation, changing subtraction to addition of the opposite integer.

3. Add, using the addition rule for addition of integers.
- Start at −5.
- Face right for addition.
- Move forward 4 units.

WRITE

a.
$$\begin{aligned} 2-5 &= 2-(+5) \\ &= 2+(-5) \\ &= -3 \end{aligned}$$

b.
$$\begin{aligned} -3-6 &= -3-(+6) \\ &= -3+(-6) \\ &= -9 \end{aligned}$$

c.
$$\begin{aligned} 5-(-3) &= 5+(+3) \\ &= 5+3 \\ &= 8 \end{aligned}$$

d.
$$\begin{aligned} -5-(-4) &= -5+(+4) \\ &= -5+4 \\ &= -1 \end{aligned}$$


WORKED EXAMPLE 15 Application of adding or subtracting integers

A news flash in Freezonia announced that there had been a record drop in temperature overnight. At 6 pm the temperature was 10 °C and by 4 am it had fallen by 25 °C. What was the temperature at 4 am?

THINK	WRITE
1. The original temperature is 10 °C, so write the number 10. The temperature fell by 25 °C, so write this as 10 – 25. Write the number sentence. Rewrite as the addition of the opposite.	$10 - 25$ $= 10 + (-25)$
2. Complete the addition by starting at +10, facing right, then moving backwards by 25 units.	$= -15$
3. Write the answer in a sentence.	The temperature in Freezonia at 4 am was −15°C.

Digital technology


Scientific calculators can evaluate subtraction of positive and negative numbers.



ACTIVITY: Radial diagrams

Insert the integers from −6 to +2 into the circles on the diagram so that each straight line of three circles has each of the following totals.

a. −6
b. −3
c. −9



on Resources

eWorkbook Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)
Video eLesson Addition and subtraction of positive and negative numbers (eles-1869)
Interactivities Individual pathway interactivity: Subtracting integers (int-8341)
Subtraction of integers (int-4037)

Exercise 2.5 Subtracting integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 5, 9, 12, 14, 17	2, 4, 6, 8, 11, 15, 18	3, 7, 10, 13, 16, 19, 20

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE13 Calculate the value of each of the following.

a. $7-(+2)$ **b.** $-18-(+6)$ **c.** $3-(+8)$
d. $17-(-9)$ **e.** $-28-(-12)$ **f.** $-17-(-28)$

2. WE14 Calculate the value of each of the following.


a. $7-5$ **b.** $8-(-2)$ **c.** $-4-6$
d. $-6-(-8)$ **e.** $1-10$

3. Calculate the value of each of the following.


a. $-5-5$ **b.** $-8-(-8)$ **c.** $0-4$
d. $0-(-3)$ **e.** $-10-(-20)$ **f.** $-5-(-5)$

4. Write number sentences to show the subtraction problems in the following diagrams.


a.




b.



c.



d.



Understanding

5. Mentally calculate the following and write the answer.

a. $-7-3$ **b.** $8-(-5)$ **c.** $-6-(-9)$ **d.** $-0-(-12)$

6. Mentally calculate the following and write the answer.

a. $-8-8$ **b.** $3-20$ **c.** $20-(-3)$ **d.** $-4-8$

7. Determine the missing number in these incomplete number sentences.

a. $_____ - 7 = -6$ **b.** $-8 - _____ = -17$
c. $-8 - _____ = 17$ **d.** $_____ - (-2) = 7$


8. Write each of the numbers that can be described by the following.

a. 6 less than -2 **b.** 5 less than -8
c. 8 °C below -1 °C **d.** 3 °C below 2 °C
e. 3 to the left of $+4$ **f.** 4 to the left of -3

9. MC Select which of the following is equal to $7+(-4)-(-2)$.

A. 9 **B.** 1 **C.** 13
D. 5 **E.** -5

10. Model each situation with an integer number sentence that shows the result of the following.



- **a.** From ground level, a lift went down 2 floors, then down another 3 floors.
- **b.** An Olympian dived down 5 metres from a board 3 metres above water level.
- **c.** At 5:00 pm in Falls Creek the temperature was 1 °C. It then fell 6 °C by 11:00 pm.
- **d.** A bank account with a balance of $500 had $150 withdrawn from it.

11. MC From ground level, a lift went down 2 floors, then down another 3 floors to a level 5 floors below the ground. Select which of the following number sentences describes this situation.

A. $2+3=5$ **B.** $-2+(-3)=-5$ **C.** $-2+3=1$
D. $2+(-3)=-1$ **E.** $-3+(-2)=5$

12. State whether the following number sentences are true or false. Show your full working.



- **a.** $7-9=7+-9$
- **b.** $0-8=-8-0$
- **c.** $8-12=-12+8$
- **d.** $0-p=-p$

13. WE15 The temperature in the freezer was −20 °C. Just before he went to bed, Chen had a spoonful of ice cream and left the freezer door open all night. The temperature in the freezer rose by 18 °C and the ice cream melted. Determine the temperature in the freezer when Chen's mother found the ice cream in the morning.

Reasoning

14. Nihal has to hand in an essay for English class with a maximum of 400 words. Currently his essay has 520 words. Calculate the number of words Nihal has to cut out of his essay.

15. Jill is climbing up a steep and slippery path to fetch a bucket of water. When she is 6 m above her starting point, she slips back 1m, grabs onto some bushes by the side of the path and climbs 7 m more to a flat section of the path. Determine how far above her starting point Jill is when she reaches the flat section. Show your working.

16. Sharyn opened a bank account when she started working at her local fish and chip shop. Below is a week-by-week breakdown of her transactions.
Week 1: deposited $56.00, then withdrew $45.00
Week 2: deposited $44.00, then withdrew $75.00
Week 3: deposited $52.80, then withdrew $22.00
Week 4: deposited $39.20, then withdrew $50.00
Sharyn's bank account was opened with a $10 deposit.



- **a.** Determine how much money was in Sharyn's account at the end of the month.
- **b.** Show full working to determine in which week the balance of Sharyn's account was negative.

Problem solving

17. Stuart is diving in the ocean. He starts at a depth of 5 m below the water's surface, then rises 2 m. He then dives a further 12 m down. Calculate the final depth that he reached.

18. A hospital building has 6 floors above ground level and 4 floors below ground level. Over a 10-minute period one busy morning, the lift started from ground level (reception) and made the following moves: up 2 floors, up 1 floor, down 4 floors, down 2 floors, up 3 floors, down 4 floors and up 6 floors.

a. Determine the floor on which the lift finished.

b. Determine the number of floors the lift travelled in the whole 10 minutes.

19. Rendah has a maths trick. For her trick she asks people to do the following mental maths steps:

1. Pick a number between 1 and 10.
2. Multiply the number by 9.
3. Add the digits of the number. For example, if you chose the number 25 you would add 2 and 5 to get 7.
4. _____
5. Match your number to a letter of the alphabet; for example, 1 is A, 2 is B, 3 is C and so on.
6. Think of an animal that starts with your letter.

When the trick is done, Rendah asks people if they are thinking of a dog, and they almost always say yes. If they say no, it's usually because they picked a donkey, a dolphin or a dugong. Determine the missing step in Rendah's trick.

20. Determine the effect of subtracting a number from its opposite integer.

2.6 Multiplying and dividing integers

LEARNING INTENTION

At the end of this subtopic you should be able to:

- understand the patterns for multiplying and dividing integers
- multiply positive and negative integers
- divide positive and negative integers.

2.6.1 Multiplication of integers

eles-3702

- Patterns from multiplication tables can be used to determine the product when two directed numbers are multiplied.
- Consider the following multiplication table – we already know how to complete part of the table.
  - Notice that multiplying by 0 always results in 0.
  - Notice that multiplying by 1 does not change the value of the number.

×	−3	−2	−1	0	1	2	3
3				0	3	6	9
2				0	2	4	6
1				0	1	2	3
0				0	0	0	0
−1							
−2							
−3							

- Using a calculator to help with the multiplication of negative numbers, we can complete the table, as shown here.

×	−3	−2	−1	0	1	2	3
3	−9	−6	−3	0	3	6	9
2	−6	−4	−2	0	2	4	6
1	−3	−2	−1	0	1	2	3
0	0	0	0	0	0	0	0
−1	3	2	1	0	−1	−2	−3
−2	6	4	2	0	−2	−4	−6
−3	9	6	3	0	−3	−6	−9

- From this table, we can develop the following rules for multiplying integers.

Rules for multiplying integers

- When multiplying two integers with the *same* sign, the answer is always *positive*.
  $+ \times + = +$ or $- \times - = +$
- When multiplying two integers with *different* signs, the answer is always *negative*.
  $+ \times - = -$ or $- \times + = -$

WORKED EXAMPLE 16 Multiplying integers

Evaluate:

a. $-5 \times +2$ **b.** -4×-6

THINK

a. 1. Write the question.

2. Negative × positive = negative.

b. 1. Write the question.

2. Negative × negative = positive.

WRITE

a. $-5 \times +2$

$= -10$

b. -4×-6

$= 24$

- Brackets can also be used to represent multiplication. For example, the expression $(-3)(5)$ is the same as -3×5. Likewise, the expression $(2-4)(11-3)$ is the same as $(2-4) \times (11-3)$.

2.6.2 Division of integers

eles-3703

- Division is the inverse, or opposite, of multiplication.
- The multiplication rules for directed numbers can be used to work out the division rules for directed numbers.
  Since $3 \times 2 = 6$ then $6 \div 3 = 2$ and $6 \div 2 = 3$.
  Since $3 \times -2 = -6$ then $-6 \div 3 = -2$ and $-6 \div -2 = 3$
  Since $-2 \times -3 = 6$ then $6 \div -3 = -2$ and $6 \div -2 = -3$.

From this, we can develop the following rules for dividing integers.

Rules for dividing integers

- When dividing two integers with the *same* sign, the answer is always *positive*.
  $+ \div + = +$ or $- \div - = +$
- When dividing two integers with *different* signs, the answer is always *negative*.
  $+ \div - = -$ or $- \div + = -$

WORKED EXAMPLE 17 Dividing integers

Evaluate the following.

a. $10 \div -2$ b. $-12 \div 4$ c. $-20 \div -5$

THINK	WRITE
a. 1. Write the question.	a. $10 \div -2$
2. The two integers have different signs, so the answer will be negative.	$= -5$
b. 1. Write the question.	b. $-12 \div 4$
2. The two integers have different signs, so the answer will be negative.	$= -3$
c. 1. Write the question.	c. $-20 \div -5$
2. Both numbers have the same sign, so the answer will be positive.	$= 4$

WORKED EXAMPLE 18 Multiplying and dividing integers

Evaluate:


a. $\dfrac{-16}{+2}$ b. $-5 \times \dfrac{4}{20}$

THINK	WRITE
a. 1. Write the question. *Note:* $\dfrac{-16}{+2}$ is the same as $-16 \div +2$.	a. $\dfrac{-16}{+2}$
2. Evaluate the expression. *Note:* negative $\div$ positive $=$ negative	$= -8$
b. 1. Write the question.	b. $-5 \times \dfrac{4}{20}$
2. Write the integer as a fraction with a denominator of 1 and simplify by cancelling.	$= \dfrac{-5}{1} \times \dfrac{\cancel{4}^{1}}{\cancel{20}^{5}}$


3. Multiply the numerators then multiply the denominators and simplify.
   Note: negative ÷ positive = negative
   $= \frac{-5}{5}$
4. Write the answer.
   $= -1$

Digital technology

Scientific calculators can evaluate multiplication of positive and negative numbers.



Scientific calculators can evaluate division of positive and negative numbers.



Resources

eWorkbook Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)

Interactivities Individual pathway interactivity: Multiplication and division of integers (int-4370)
Multiplication of integers (int-4038)
Division of integers (int-4039)

Exercise 2.6 Multiplying and dividing integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 10, 15, 16, 19	2, 5, 7, 9, 11, 12, 17, 20	3, 6, 8, 13, 14, 18, 21

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE16 Calculate the following.

   a. 2×-5
   b. -6×3
   c. -7×9
   d. 6×-5
   e. -2×-3

2. Evaluate the following.

a. -6×-3 **b.** -5×-5 **c.** 0×-7 **d.** -8×-1

3. Calculate the following.

a. 10×-1 **b.** -15×2 **c.** -20×-10 **d.** -6×-6

4. WE17 Evaluate the following.

a. $-8 \div -2$ **b.** $-8 \div 2$ **c.** $12 \div -3$

d. $-16 \div -8$ **e.** $-90 \div -10$

5. Calculate the following.

a. $88 \div -11$ **b.** $-6 \div 1$ **c.** $0 \div -4$

d. $-84 \div 4$ **e.** $-184 \div 2$

6. Evaluate the following.

a. $-125 \div -5$ **b.** $-67 \div -1$ **c.** $129 \div -3$

d. $-284 \div 4$ **e.** $336 \div -6$

Understanding

7. WE18(a) Calculate the following.

a. $\frac{-6}{2}$ **b.** $\frac{-24}{-8}$ **c.** $\frac{-8}{8}$

8. WE18(b) Evaluate the following.

a. $3 \times \frac{-2}{-6}$ **b.** $4 \times \frac{-5}{10}$ **c.** $-9 \times \frac{-3}{18}$

9. Calculate the value of each of the following.

a. $2 \times -3 \times 4$ **b.** $-4 \times -3 \times 3$ **c.** $-8 \times 9 \times -2$

10. Fill in the missing numbers in these number sentences.

a. $6 \times _____ = -18$ **b.** $_____ \times 3 = -18$ **c.** $-8 \times _____ = -8$

d. $-8 \times _____ = 8$ **e.** $-8 \times _____ = 0$

11. Fill in the missing numbers in these number sentences.

a. $-21 \div _____ = -7$ **b.** $_____ \div -8 = -4$ **c.** $_____ \div -9 = 8$

d. $-11 \div _____ = 1$ **e.** $_____ \div -7 = 0$ **f.** $-150 \div -25 = _____$

12. Evaluate the following expressions.

a. $-4 + (-4)$

b. 2×-4

c. $-2 + (-2) + (-2)$

d. 3×-2

e. $-5 + (-5) + (-5) + (-5)$

f. 4×-5

13. MC Select which of the following could be the missing numbers in the number sentence $16 \div ___ = ____$.

A. $2, -8$ **B.** $-2, -8$ **C.** $-4, 4$ **D.** $-2, 8$ **E.** $1, -16$

14. MC Select which of the following could be the missing numbers in the number sentence $____ \div ____ = -5$.

A. $-15, 3$ **B.** $15, 5$ **C.** $25, 5$ **D.** $-30, -6$ **E.** $-25, -5$

15. MC Six people each owe the bank \$50. Calculate the combined total of their six bank accounts.

A. \$300 **B.** $-\$50$ **C.** \$50 **D.** $-\$\frac{6}{5}$ **E.** $-\$300$

Reasoning

16. Evaluate the following multiplications.

a. **i.** $(-1)(-2)$ **ii.** $(-3)(-2)(-1)$
iii. $(-2)(-3)(-1)(-4)$ **iv.** $(-4)(-1)(-5)(-2)(-1)$

b. Write a rule for multiplying more than two negative numbers.

c. Does this rule also apply to the division of negative numbers? Explain your answer.

17. When you multiply two integers, is the result an integer? What about when you divide two integers? Explain your answer.

18. A spider is running down the stairs from the first floor of an old lady's house to the basement below. It stops every 5 steps to catch a fly. If there are 26 steps above the ground floor and 14 steps below the ground floor, determine how many flies the spider catches.

Problem solving

19. Blake is jumping down the stairs, stepping on every second step only.
He jumps a total of ten times.

a. Determine the number of steps he has skipped.

b. Determine the number of steps there are altogether.

c. If each step is 25 cm high, determine how far he has travelled in total.

d. If going up the stairs is considered going in a positive direction and going down the stairs is considered going in a negative direction, rewrite your answer to part **c**.



20. Manu is working on the expression $8 \div 2 \times (2 + 2)$ and says the answer is 1. Her friend Kareen says the answer should be 16. Show, with full working, who is correct.

21. On a test, each correct answer scores 5 points, each incorrect answer scores -2 points, and each question left unanswered scores 0 points. A student answers 16 questions on the test correctly, 3 incorrectly, and does not answer 1 question. Write an expression for the student's score and calculate the score.

2.7 Order of operations with integers

LEARNING INTENTION

At the end of this subtopic you should be able to:


- understand how to apply the order of operations with integers when more than one operation is involved
- apply the order of operations with positive and negative integers to solve expressions that involve more than one operation.

eles-3704

2.7.1 Applying BIDMAS to positive and negative integers

- Subtopic 1.8 in topic 1 explored how the order of operations is applied to positive integers when more than one mathematical operation is involved.
- The same order of operations is also applied for negative integers.
- The order of operations involves solving the brackets first, then solving powers or indices, then multiplication and division (working from left to right) and finally addition and subtraction (working from left to right).
- The order of operations can be written as BIDMAS (**B**rackets, **I**ndices and roots, **D**ivision and **M**ultiplication, **A**ddition and **S**ubtraction).

BIDMAS



- Examples of these operations are shown in this table.

B	**Brackets**	$8 \times (3 + 5) = 8 \times (8) = 64$
I	**Indices**	$5 + 3^2 = 5 + 9 = 14$
D	**Division**	$17 - 8 \div 4 = 17 - 2 = 15$
M	**Multiplication**	$7 + 6 \times 3 = 7 + 18 = 25$
A	**Addition**	$6 \times 2 + 5 = 12 + 5 = 17$
S	**Subtraction**	$21 \div 3 - 4 = 7 - 4 = 3$

WORKED EXAMPLE 19 Calculating an expression using order of operations

Calculate $58 - (2 \times -8 + 3^2)$ using the correct order of operations.

THINK	WRITE
1. Write the question.	$58 - (2 \times -8 + 3^2)$
2. Using BIDMAS, start inside the brackets and simplify the squared term (indices).	$= 58 - (2 \times -8 + 3^2)$ $= 58 - (2 \times -8 + 9)$

3. Perform the multiplication within the brackets.	$= 58 - (2 \times -8 + 9)$ $= 58 - (-16 + 9)$
4. Perform the addition within the brackets.	$= 58 - (-16 + 9)$ $= 58 - (-7)$
5. When the brackets have been removed, perform the subtraction that had been outside the brackets.	$= 58 - -7$ $= 58 + 7$
6. Write the answer.	$= 65$


WORKED EXAMPLE 20 Evaluating an expression using order of operations

Evaluate $5a \div b$, if $a = -20$ and $b = 4$.

THINK	WRITE
1. Write the expression as given.	$5a \div b$
2. Substitute the given value for each pronumeral, inserting operation signs as required.	$= 5 \times -20 \div 4$
3. Perform the operations as they appear, from left to right.	$= -100 \div 4$
4. Write the answer.	$= -25$

Digital technology

Scientific calculators can calculate expressions using order of operations.



on Resources

eWorkbook Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)
Interactivities Individual pathway interactivity: Combined operations (int-4371)
Combined operations (int-4040)

Exercise 2.7 Order of operations with integers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 7, 9, 11, 14, 17	2, 4, 8, 10, 12, 15, 18	5, 6, 13, 16, 19, 20


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE19 Calculate the following using the correct order of operations.
   a. $6+3\times-4$ b. $18-12\div-3$ c. $8+-4-10$ d. $17-3+-8$
2. Evaluate each of the following expressions using the correct order of operations.
   a. $6\times-3\div9$ b. $72\div8\times-3$ c. $7+(-3-4)$ d. $(6+3)\div-9$
3. Calculate each of the following expressions using the correct order of operations.
   a. $-3\times-2+3\times-1$ b. $-6\times5-2\times-6$
   c. $-4\times(6--4)$ d. $(-8+3)\times-7$
4. Evaluate each of the expressions using the correct order of operations.
   a. $4+7\times-3-2$ b. $-6-4+(-3)^2$
   c. $(-2)^3-3\times-2$ d. $3+(2-8)+-6$
5. Calculate each of the expressions using the correct order of operations.
   a. $-8\div2+(-2)^2$ b. $-4\times-8-[2+(-3)^2]$
   c. $(-7+5)--24\div6$ d. $-15\div(2-5)-10$
6. Evaluate each of the expressions using the correct order of operations.
   a. $54\div-6+8\times-9\div-4$ b. $(9--6)\div-5+-8\times0$
   c. $-7+-7\div-7\times-7--7$ d. $-9\times-5-(3--2)+-48\div6$
7. WE20 Evaluate each of the following expressions.
   a. $2x+3x$, if $x=-4$ b. $5+3d$, if $d=-2$ c. $-5b-3$, if $b=-7$
8. Evaluate each of the following expressions.
   a. $a(b+c)$, if $a=6, b=-2, c=-4$
   b. x^3-y, if $x=-4, y=4$
   c. $2a(3b-24)$, if $a=-2,\ b=6$
9. MC The expression $6+2\times-5--10\div2$ is equal to:
   A. -15 B. -35 C. -60 D. 1 E. 3
10. MC The expression $(9--6)\div-5+-8\times0$ is equal to:
    A. -15 B. -3 C. -60 D. 0 E. 30

Understanding

11. A submarine dives 100 m below sea level, rises 60 m, then dives 25 m. Calculate its final position.
12. Jini has \$2075 in the bank. She makes 2 withdrawals of \$150 each, then 5 deposits of \$60 each. Calculate the amount of money Jini now has in the bank.



13. Sami weighs 156 kg and wants to reduce his weight to 64 kg in 4 months. Calculate the average weight loss per month Sami will need to achieve in order to meet his weight loss goal.

Reasoning

14. Darcy says there is no difference between the expressions $8-2\times(4+2)$ and $8-2\times4+2$. Do you agree with Darcy? Justify your answer with correct working.

15. Are the following expressions true or false? Justify your answer with correct working.

a. $5\times6-3+(5-2)<5\times(6-3)+5-2$
b. $2+(15\div3)\times1=2+15\div(3\times1)$

16. Merlin is riding his bike east at a steady pace of 10 km/h, while Morgan is riding her bike west at a steady 8 km/h. They pass each other on Backpedal Bridge at 12 noon. Assume that east is the positive direction and west is negative, and that time before noon is negative and after noon is positive.



a. Determine the location of each person with respect to the bridge at 9 am.
b. Determine their locations with respect to the bridge at 2 pm.
c. Determine how far apart they were at 10 am.
d. Determine how far apart they will be at 4 pm.

Problem solving

17. Ryan buys 5 vanilla cupcakes at $5.75 each, 2 cinnamon donuts at $3.25 each, and 3 chocolate chip cookies at $2.50 each. Determine the total amount Ryan has to pay.



18. A snail begins to climb up the side of a bucket. It climbs 3 cm and slips back 2 cm, then climbs a further 4 cm and slips back 1 cm. Write a number sentence to help you determine how far the snail is from the bottom of the bucket.

19. At many locations around the world, minimum and maximum temperatures are recorded. On one particular day, the minimum temperature in the Arctic circle was recorded as -24 °C and the maximum temperature was recorded as -7 °C. In London the maximum temperature was 10 °C and the minimum temperature was -2 °C. In Mexico City the maximum temperature was 38 °C and the minimum temperature was 16 °C. Calculate the difference in maximum and minimum temperatures at each of these three places.

20. In a Maths competition marks are awarded as follows: 3 marks for a hard question (H), 2 marks for a medium question (M) and 1 mark for an easy question (E). If an answer is incorrect (I), 1 mark is deducted.
The top three students had the following scores:
Student 1: 10H, 3M, 5E, 2I
Student 2: 7H, 7M, 3E, 3I
Student 3: 9H, 6M, 5E, 0I



a. Determine the number of marks each student received.
b. Determine who won the competition.


2.8 Review

2.8.1 Topic summary

Number line

Integers can be represented on a number line.


- Positive integers are written to the right of 0.
- Negative integers are written to the left of 0.



Number plane

- The number plane, or Cartesian plane, has two axes:
  - the horizontal axis (x-axis)
  - the vertical axis (y-axis).
- The origin (0, 0) is where the two axes intersect.

e.g. A (3, 2) move 3 right and 2 up
B (−3, 2) move 3 left and 2 up
C (−3, −2) move 3 left and 2 down
D (3, −2) move 3 right and 2 down



POSITIVE AND NEGATIVE INTEGERS

Integers

Integers are positive and negative whole numbers including 0.


- The integers −1, −2, −3.. are called negative integers.
- The integers 1, 2, 3… are called positive integers.
- 0 is neither positive nor negative.

Addition of integers

A number line can be used to add integers.

- To add a positive integer, move to the right.
  e.g. −4 + 1 = −3
- To add a negative integer, move to the left.
  e.g. 5 + (−3) = 2

Move right when adding a positive integer →
← Move left when adding a negative integer





Subtraction of integers

- Subtracting a number gives the same result as adding its opposite.
  e.g. 2 − (5) = 2 + (−5) = −3 or
  −6 − (−11) = −6 + (+11) = 5

Division of integers

- When dividing integers with the same sign, the answer is positive.
  e.g. −20 ÷ −4 = 5 or 24 ÷ 6 = 4
- When dividing integers with different signs, the answer is negative.
  e.g. 10 ÷ −5 = −2 or $\frac{-35}{7} = -5$

Multiplication of integers

- When multiplying integers with the same sign, the answer is positive.
  e.g. −4 × −6 = 24 or 7 × 8 = 56
- When multiplying integers with different signs, the answer is negative.
  e.g. −5 × 2 = −10 or 9 × −3 = −27

Order of operations

- The order of operations is a set of rules that is followed so there is a common understanding of the order in which to solve mathematical operations.
- The set order in which we calculate problems is:
  1. **Brackets** ( ) or [ ]
  2. **Indices or roots** a^x or $\sqrt[n]{x}$
  3. **Division and Multiplication** (working left to right) ÷ or ×
  4. **Addition and Subtraction** (working left to right) + or −
- The acronym **BIDMAS** can be used to remember the correct order of operations.

2.8.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
2.2	I can place integers on a number line.			
	I can compare integer values.			
2.3	I understand the number plane (Cartesian plane), origin and coordinates.			
	I can work out the location of a point described by its coordinates.			
	I can plot one or more points given their coordinates.			
2.4	I understand how a number line can be used to add integers.			
	I can use a number line to add integers.			
	I can add integers without using a number line.			
2.5	I understand how a number line can be used to subtract integers.			
	I can use a number line to subtract integers.			
	I can subtract integers without using a number line.			
2.6	I understand the patterns for multiplying and dividing integers.			
	I can multiply positive and negative integers.			
	I can divide positive and negative integers.			
2.7	I understand how to apply the order of operations with integers when more than one operation is involved.			
	I can apply the order of operations with positive and negative integers to solve expressions with more than one operation.			

2.8.3 Project

Directed numbers dice game



In this game, the winner is the first to complete a row of three numbers, horizontally, vertically or diagonally.

Equipment: 2 players, 2 standard dice, Connect-3 board (shown), dice placement sheet (shown), 9 blue counters, 9 red counters


Instructions:

- Roll the two dice and decide whether to add or subtract the numbers on the dice.
- Put the dice on one of the squares on the dice placement sheet to produce a total shown on the Connect-3 board shown.
- Once you have worked out the answer, place your counter on the appropriate number on the Connect-3 board. You should check each other's answers.
- You cannot cover a number that has already been covered. If you are unable to find a total that has not been covered, you must pass. The winner is the first to complete a row of three numbers either horizontally, vertically or diagonally.

Make your own board game using dice with negative numbers on each face and put different numbers on the board. The dice placement sheet could also be changed to include × or ÷ symbols.

Connect-3 board

	–5	–4	–3	–2
–1	0	1	2	3
4	5	6	7	8
9	10	11	12	



Resources

eWorkbook Topic 2 Workbook (worksheets, code puzzle and project) (ewbk-1903)

Interactivities Crossword (int-2604)
Sudoku puzzle (int-3172)

Exercise 2.8 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency


1. Select which of the following are integers.
   a. $-2\frac{1}{2}$ **b.** 0.45 **c.** 0 **d.** -201


2. Complete each statement by inserting the correct symbol: $>$, $<$ or $=$.
   a. $-6 \square -2$ **b.** $-7 \square 7$ **c.** $0 \square -5$ **d.** $-100 \square 9$

3. List the integers between -21 and -15.

4. Arrange the numbers -3, 2, 0, -15 in descending order.

5. Describe the integers shown on each number line.
   a.
   

   b.
   

   c.
   

6. Graph each of the following sets of integers on a number line.
   a. integers between -7 and -2 **b.** integers > -3 **c.** integers ≤ -4

7. State whether the following points are on the x-axis, the y-axis, both axes or in the first quadrant.
a. (0, 0) **b.** (0, 5) **c.** (3, 0) **d.** (3, 2)

8. Draw and appropriately label a set of axes. Plot the following points in the order given, joining each point to the next one. Name the shape that you have drawn.
$(-2, 3), (1, 3), (2, -2), (-1, -2), (-2, 3)$

9. Determine in which quadrant or on which axes the following points lie.
a. $(-2, 3)$ **b.** $(3, -1)$ **c.** $(-4, -1)$ **d.** $(0, 2)$ **e.** $(-1, 0)$ **f.** $(7, 9)$

10. Calculate the following.
a. $-12 + 7$ **b.** $-9 + -8$ **c.** $18 + -10$ **d.** $5 + 1$

11. Write the number that is 2 more than each of the following integers.
a. -4 **b.** 5 **c.** -1 **d.** 0 **e.** -2

12. Calculate the following.
a. $-5 - 3$ **b.** $17 - -9$ **c.** $-6 - -9$ **d.** $6 - 8$ **e.** $12 - 20$ **f.** $-10 - -12$

13. Evaluate the following.
a. -6×7 **b.** 4×-8 **c.** -2×-5 **d.** $(-8)^2$ **e.** -8^2 **f.** $-2 \times (-8)^2$

14. Calculate the following.
a. $-36 \div 3$ **b.** $-21 \div -7$ **c.** $45 \div -9$ **d.** $\frac{-18}{-2}$ **e.** $64 \div -4$ **f.** $-100 \div 25$

15. Evaluate the following expressions.
a. $10 - 6 \times 2$ **b.** $-7 - -8 \div 2$ **c.** $-3 \times -5 - -6 \times 2$
d. $(-2)^3$ **e.** $(-3 - 12) \div (-10 + 7)$

16. Calculate the following expressions.
a. $2c + 3c$, if $c = -4$ **b.** $-2x(x + 5)$, if $x = -2$
c. $2a^2 + a$, if $a = -3$ **d.** b^3, if $b = -5$
e. $2a - 5b + c$, if $a = -2$, $b = 2$, $c = 5$

17. Replace the box with $=$, $<$ or $>$ to make each of the following statements correct.
a. $-5 \square -3$ **b.** $-22 \times -2 \square 44$ **c.** $4 \square 2$
d. $-5 \times -3 \square -15$ **e.** $0 \square -7$ **f.** $-2(-4 + 7) \square 6$

18. Replace the box with $=$, $<$ or $>$ to make each of the following statements correct.
a. $-2 \times 5 \square -9$ **b.** $5 \times (-2 - 18) \div -4 \square 25$ **c.** $12 \div -4 \square 3$
d. $5 \times (-2 - 18) \div 4 \square -25$ **e.** $-10 \times -5 \square 50$ **f.** $5 \times -2 - 18 \div 4 \square 2.5$

19. Model the following situation with integers, then find the result. A scuba diver at 52 metres below sea level made her ascent in 3 stages of 15 metres each. Determine how far below sea level she was then.

20. Some historians believe that the Roman era began in 146 BCE and ended in 455 CE. According to this theory, calculate the length of the Roman era.

21. The lowest temperature recorded on Earth was -90 °C in Antarctica and the highest was 58 °C in Africa. Determine the difference between these two temperatures.


22. Nazeem's bank account has a balance of −$43. He pays a bill of $51 using direct debit. Calculate his bank balance now.

Problem solving

23. For the following expressions, determine if the answer will be negative or positive. Explain your answers using mathematical reasoning.

a. −17 489 − 25 636 **b.** −65 234 + 123 468 **c.** −44 322 + 31 212

24. Examine the graph shown.



a. Determine the coordinates of a point, D, that can be added to the graph so that ABCD is a square.

b. Name the combination of points that make:

i. a right-angled triangle

ii. an isosceles triangle that doesn't include a right angle.

(There may be more than one solution.)


c. Determine the coordinates of a point, F, that can be added to the graph so that ACFE is a parallelogram. Mark point F on the grid and draw the parallelogram.

d. State the coordinates of the midpoint of CA.

e. State the coordinates of the midpoint of AE.

f. Estimate the coordinates of G.

25. Answer the following questions.



a. Add numbers to the empty sections in this diagram so that the numbers in each circle add up to zero.

b. Add numbers to the empty sections in a different way so that the numbers in each circle add up to −2.

26. If $(X - Y > X)$, $(Y - X < Y)$ and Y are integers, determine whether X and Y are positive or negative values.

27. The negative integers −2 to −1000 are to be arranged in 5 columns as shown.

Column 1	Column 2	Column 3	Column 4	Column 5
	−2	−3	−4	−5
−9	−8	−7	−6	
	−10	−11	−12	−13
−17	−16	−15	−14	

Identify the column in which −1000 should be placed.

28. **a.** Copy this table and use your calculator to complete it.

Integer (x)	x^2	x^3	x^4	x^5
2				
−2				
3				
−3				
4				
−4				

b. Look at your results in the x^2 column. State the sign of all the numbers.

c. Look at the sign of the numbers in the x^3 column. What do you notice?

d. Describe the resulting sign of the numbers in the x^4 and x^5 columns.

e. Is the resulting sign in the x^2 column the same as the sign in the x^4 column? Comment about the signs of the numbers in the x^3 and x^5 columns.

f. Now consider the inverse of raising a number to a power: taking the root of a number. You will notice that $2^2 = 4$ and $(-2)^2 = 4$. It follows that, if we take the square root of 4, we can get $+2$ or -2 . (Your calculator will only give you the positive answer.) The shorthand way of writing this is as $\sqrt{4} = \pm 2$. Similarly, you will notice that $\sqrt[4]{16} = \pm 2$. This pattern only applies to even roots. Now that you know this, write a statement showing the square root of 100.

g. It is not possible to take the even root of a negative number, because no number raised to an even power can produce a negative number. Explain what happens when you try to evaluate $\sqrt{-144}$ on the calculator.

h. Notice that with odd-numbered roots the sign of the answer is the same as the sign of the original number. For example, $\sqrt[3]{8} = 2$, but $\sqrt[3]{-8} = -2$. Now that you know this, calculate $\sqrt[3]{-125}$.

i. Copy and complete the following table by filling in the blocks that are not shaded. Consider each answer carefully – some of these calculations are not possible.

Integer (x)	$\sqrt{x}$	$\sqrt[3]{x}$	$\sqrt[4]{x}$	$\sqrt[5]{x}$
16	±4			
−16				
27				
−27				
32				
−32				
81				
−81				
64				
−64				

j. In your own words, describe the sign that results from taking odd and even roots of positive and negative numbers.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1903) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0691) ☐

Digital documents

2.2 SkillSHEET Using < or > to compare the size of numbers (doc-6563) ☐
SkillSHEET Ascending and descending order (doc-6564) ☐
SkillSHEET Marking numbers on a number line (doc-6565) ☐
SkillSHEET Working with numbers on a number line (doc-6566) ☐
2.7 SkillSHEET Evaluating squares, cubes and cube roots (doc-6567) ☐
SkillSHEET Order of operations II (doc-6568) ☐

Video eLessons

2.2 Integers (eles-3695) ☐
The number line (eles-3696) ☐
Using positive and negative numbers in daily life (eles-3697) ☐
2.3 Positive integers and zero on the number plane (eles-3698) ☐
Integers on the number plane (eles-3699)
2.4 Addition of integers (eles-3700) ☐
2.5 Subtraction of integers (eles-3701) ☐
Subtracting integers by adding opposites (eles-4091) ☐
Addition and subtraction of positive and negative numbers (eles-1869) ☐
2.6 Multiplication of integers (eles-3702) ☐
Division of integers (eles-3703) ☐
2.7 Applying BIDMAS to positive and negative integers (eles-3704) ☐

Interactivities

2.2 Individual pathway interactivity: Integers on the number line (int-4367) ☐
Number line (int-4033) ☐
2.3 Individual pathway interactivity: Integers on the number plane (int-4368) ☐
Integers on the number plane (int-4035) ☐
Positive integers and zero on the number plane (int-4034) ☐
2.4 Individual pathway interactivity: Adding integers (int-8458) ☐
Addition of integers (int-4036) ☐
2.5 Individual pathway interactivity: Subtracting integers (int-8341) ☐
Subtraction of integers (int-4037) ☐
2.6 Individual pathway interactivity: Multiplication and division of integers (int-4370) ☐
Multiplication of integers(int-4038) ☐
Division of integers (int-4039) ☐
2.7 Individual pathway interactivity: Combined operations (int-4371) ☐
Combined operations (int-4040) ☐
2.8 Crossword (int-2604) ☐
Sudoku puzzle (int-3172) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.


Answers


Topic 2 Positive and negative integers


Exercise 2.1 Pre-test


1. a. −250 b. −15 c. +20 °C
2. a. −3 < 2 b. −5 > −7 c. −21 < −17
   d. 0 > −8
3. B
4. A (3, −2)
5. C
6. C
7. a. −2 b. 13 c. −19 d. −11
8. 7
9. 78 m
10. 48
11. a. 2 b. 8 c. 130
12. E
13. 6
14. $380
15. 108

Exercise 2.2 Integers on the number line

1. a. −7 b. 10 or + 10
   c. −422 d. 2228 or + 2228
   e. −3 f. −30
2. 

3. a. −6, −2, 3, 5, 7 b. −6, −4, −1, 0, 3
   c. −5, −3, −2, 1, 7 d. −4, −3, 1, 2, 5
4. a. 6 b. −7 c. −1 d. 8
5. a. > b. < c. >
   d. > e. < f. <
6. a. i. −5 ii. 7
   b. i. −4 ii. 5
   c. i. −10 ii. 7
   d. i. −4 ii. 3
7. −2 °C
8. 14
9. Sample response: There were human settlements here 60 thousand years ago.
10. a. 


    b. 2.8 km
11. a. 

    b. 12.5 km
12. a. 2000 years in Common Era.
    b. i. 10 ii. −106
    c. i. 4 ii. 12 iii. 26 iv. 42 v. 57
    d. 

Exercise 2.3 Integers on the number plane

1. a. (3, 4) b. (8, 4) c. (4, 8)
   d. (0, 7) e. (5, 0)
2. a. G b. F c. H d. J
3. C
4. D
5. (−5, 2)
6. a. (3, 1); 1st quadrant
   b. (−2, 4); 2nd quadrant
   c. (−6, −5); 3rd quadrant
   d. (0, −3); *y*-axis
   e. (6, −6); 4th quadrant
7. a. C; 2nd quadrant b. L; *y*-axis
   c. D; 4th quadrant d. E; 1st quadrant
   e. G; *x*-axis
8. a. 3 b. 3 c. 7 d. 0
9. a. 2 b. −6 c. 0 d. −3
10. H
11. a. True b. False c. False
    d. True
12. D
13. B
14. B

15.



a. Parallelogram **b.** Isosceles triangle
c. Kite **d.** Square

16. According to the graph, both points F and D are 3 units down from the origin along the *y*-axis. Therefore they have the same *y*-coordinate. Similarly, both A and D are 3 units to the right along the *x*-axis. Therefore, they have the same *x*-coordinate.


17. a. (2, 1)
b. (1, −2)
c. Draw line DO
d. (−3, 1), (−2, 1), (−1, 1) etc.
e. (−5, −2)

18. a. West **b.** East
c. West **d.** East
e. An odd number of negative signs turns you west, and an even number of negative signs turns you east.
f. South
g. An odd number of negative signs turns you south, and an even number of negative signs turns you north.


19. 9 units

20. 210

21. a.



b.



Top left post (−18.288, 9.144)
Top right post (18.288, 9.144)
Bottom right post (18.288, −9.144)
Bottom left post (−18.288, −9.144)

22. Points in the first quadrant are in the form (+, +). Swapping the *x*- and *y*-coordinates creates a point in the form (+, +), so the point will remain in the first quadrant.
Points in the second quadrant are in the form (−, +). Swapping the *x*- and *y*-coordinates creates a point in the form (+, −), so the point will change to the fourth quadrant.
Points in the third quadrant are in the form (−, −). Swapping the *x*- and *y*-coordinates creates a point in the form (−, −), so the point will remain in the third quadrant.
Points in the fourth quadrant are in the form (+, −). Swapping the *x*- and *y*-coordinates creates a point in the form (−, +), so the point will change to the second quadrant.

Exercise 2.4 Adding integers

1. a. −15 **b.** −10 **c.** −1
d. −13 **e.** 19 **f.** 0

2. a. −4 + (+4) = 0 **b.** −1 + (+3) = +2
c. −2 + (−4) = −6 **d.** +2 + (−4) = −2
e. +6 + (−4) = +2 **f.** −1 + (−3) = −4

3. a. −1 **b.** −1 **c.** 0
d. +1 **e.** −2

4. a. 5 + (−2) = 3 **b.** −3 + (−4) = −7
c. −2 (+2) = 0 **d.** 6 + (−5) = 1
e. −5 (+5) = 0

5. a. 4 + (−6) = −2 **b.** −5 + 7 = 2
c. 6 + (−9) = −3 **d.** 3 + (−3) = 0
e. 0 + (−6) = −6

6. a. −7 **b.** −2 **c.** 0
d. −4 **e.** 4 **f.** −10

7. a. 4 **b.** −3 **c.** −100
d. 10 **e.** 2 **f.** −22

8.

+	−13	5
21	8	26
−18	−31	−13

9. a. 5 **b.** −2 **c.** 1 **d.** 3

10. a. −8 **b.** −6 **c.** 10
d. −7 **e.** 3

11. a.

+	−2	−1	0	1	2
−2	−4	−3	−2	−1	0
−1	−3	−2	−1	0	1
0	−2	−1	0	1	2
1	−1	0	1	2	3
2	0	1	2	3	4

b. i. Even numbers, doubles
ii. Zeros (addition of opposites)
iii. Yes

12. a. −2 + 3 = 1 **b.** −3 + 5 = 2
c. −50 + 63 = 13 **d.** −50 + 26 = −24 m
e. 200 + (−350) = −150

13. a. Sample response: A diver is 3 m deep and dives a further 2 m deeper until she is 5 m deep.
    b. Sample response: A water pipe was drilled to 10 m deep, but a further 40 m was required to reach the water, which was 50 m deep.
    c. Sample response: The lift was on the second floor and then travelled six floors down, stopping at the fourth-floor basement car park.
    d. Sample response: Billy borrowed $20 from his mum. One week later he paid the loan back in full.
    e. Sample response: Shalini gave eight lollies to her brother and later she got ten more lollies from her dad, leaving her with two extra lollies.
14. a. 'When adding two negative numbers, add the a number as if they were positive numbers and then write a negative sign in front of the answer.'
    b. 'When adding a negative numbers and a positive number, ignore the signs, subtract the smaller number and then write the sign the large number has.'
15. Sample response.

2	–12	7
4	–1	–6
–9	10	–4

16. $5575
17. 15 points
18. 2nd floor
19. If you add a number to its opposite, the answer will always be zero. For example: $-2 + 2 = 0$.

Exercise 2.5 Subtracting integers

1. a. 5 b. -24 c. -5
   d. 26 e. -16 f. 11
2. a. 2 b. 10 c. -10
   d. 2 e. -9
3. a. -10 b. 0 c. -4
   d. 3 e. 10 f. 0
4. a. $2-(+5)=-3$ b. $-3-(+6)=-9$
   c. $-4-(-9)=5$ d. $5-(-7)=12$
5. a. -10 b. 13 c. 3
   d. 12
6. a. -16 b. -17 c. 23
   d. -12
7. a. 1 b. 9 c. -25 d. 5
8. a. $-2-6=-8$ b. $-8-5=-13$
   c. $-1-8=-9$ d. $2-3=-1$
   e. $4-3=1$ f. $-3-4=-7$
9. D
10. a. $-2-3=-5$ b. $3-5=-2$
    c. $1-6=-5$ d. $\$500-\$150=\$350$
11. B
12. a. True b. True
    c. True d. True
13. -2 °C
14. $400-520=-120$. Nihal has to cut 120 words.
15. 12 m
16. a. Balance at end of month: $10
    b. During the second week her balance was negative.
17. Depth of 5 m below the surface $= -5$
    An ascent of 2 m $= +2$
    A descent of 12 m $= -12$
    Total depth $= -5+2-12=-15$
    $-15 =$ 15 m below the surface
18. a. 2nd floor
    b. It travelled 22 floors in 10 minutes.
19. Subtract 5 from the number: $9-5=4$
20. If you subtract a number from its opposite, the answer will be double the original number value, but it can be positive or negative. For example: $2-(-2)=4$, or $-2-2=-4$.

Exercise 2.6 Multiplying and dividing integers

1. a. -10 b. -18 c. -63
   d. -30 e. 6
2. a. 18 b. 25 c. 0 d. 8
3. a. -10 b. -30 c. 200 d. 36
4. a. 4 b. -4 c. -4
   d. 2 e. 9
5. a. -8 b. -6 c. 0
   d. -21 e. -92
6. a. 25 b. 67 c. -43
   d. -71 e. -56
7. a. -3 b. 3 c. -1
8. a. 1 b. -2 c. $1\frac{1}{2}$
9. a. -24 b. 36 c. 144
10. a. -3 b. -6 c. 1 d. -1 e. 0
11. a. 3 b. 32 c. -72
    d. -11 e. 0 f. 6
12. a. -8 b. -8 c. -6
    d. -6 e. -20 f. -20
13. B
14. A
15. E
16. a. i. 2 ii. -6 iii. 24 iv. -40
    b. When multiplying an even number of negative numbers, the answer is always positive. When multiplying an odd number of negative numbers, the answer is always negative.
    c. Yes, because multiplication and division have the same rules when working with negative numbers.
17. Agree. When you multiply two integers, the result is always an integer. When you divide two integers, the answer is not always an integer. If the integers do not divide equally, the answer will be a fraction.
18. 8 flies
19. a. 10 b. 20 c. 5 m d. -5 m

20. According to Kareen: $8 \div 2 \times (2 + 2)$ applying BIDMAS to this expression

$$= 8 \div 2 \times (4)$$
$$= 4 \times 4$$
$$= 16$$

Kareen is correct, We do need to apply BIDMAS when more than one operation is used in an expression.

21. $16 \times 5 + 3 \times -2 + 0 = 80 - 6 = 74$ marks

Exercise 2.7 Order of operations with integers

1. a. -6 b. 22 c. -6 d. 6

2. a. -2 b. -27 c. 0 d. -1

3. a. 3 b. -18 c. -40 d. 35

4. a. -19 b. -1 c. -2 d. -9

5. a. 0 b. 21 c. 2 d. -5

6. a. 9 b. -3 c. -7 d. 32

7. a. -20 b. -1 c. 32

8. a. -36 b. -68 c. 24

9. D

10. B

11. $-100 + 60 + -25 = -65$

12. \$2075

13. 23 kg per month

14. The two expressions are different due to the placement of the bracket in the first expression. See the working below.
First expression: $8 - 2 \times (4 + 2)$, apply BIDMAS

$$= 8 - 2 \times (6)$$
$$= 8–12 = –4$$

Second expression: $8 - 2 \times (4 + 2)$, apply BIDMAS

$$= 8 - 8 + 2$$
$$= 8–6 = 2$$

15. a. False. See the working below.
$5 \times 6 - 3 + (5–2) < 5 \times (6 - 3) + 5–2$
Apply BIDMAS to both of the expressions.
$5 \times 6 - 3 + (5 - 2) = 5 \times 6 - 3 + (3)$
$= 30 - 3 + 3 = 33 - 3 = 30$ (larger)

$5 \times (6 - 3) + 5 - 2 = 5 \times (3) + 5 - 2$
$= 15 + 5 - 2 = 20 - 2 = 18$ (smaller)

$5 \times 6 - 3 + (5 - 2) >$
$5 \times (6 - 3) + 5 - 2.$
Therefore, the statement given is not true.

b. True. See the working below.
$2 + (15 \div 3) \times 1 = 2 + 15 \div (3 \times 1)$
Apply BIDMAS to both of the expressions.
$2 + (15 \div 3) \times 1 = 2 + (5) \times 1 = 2 + 5 = 7$
$2 + 15 \div (3 \times 1) = 2 + 15 \div (3) = 2 + 5 = 7$
Because both the expressions are equal to 7, the statement is true.

16. a. Merlin: $-3 \times 10 = -30$, 30 km west of bridge
Morgan: $-3 \times -8 = 24$, 24 km east of bridge

b. Merlin: $2 \times 10 = 20$, 20 km east of bridge
Morgan: $2 \times -8 = -16$, 16 km west of bridge

c. 36 km

d. 72 km

17. The total amount Ryan paid to the bakery is \$42.75.

18. $3 + -2 + 4 + -1 = 4$
The snail is 4 cm from the bottom of the bucket.

19. a. Arctic Circle 17 °C,
London 34 °C,
Mexico 22 °C

20. a. Student 1: 39 marks; Student 2: 35 marks; Student 3, 44 marks

b. Student 3 won the competition with 44 marks.

Project

Students should play the game to understand how it works. Then students should present a game they have created, which should include positive and negative numbers and any operation.

Exercise 2.8 Review questions


1. a. No b. No c. Yes d. Yes


2. a. < b. < c. > d. <


3. $-20, -19, -18 - 17, -16$

4. $2, 0, -3, -15$


5. a. < 1 or ≤ 0 b. Between -6 and -3
c. > -12 or ≥ -11

6. a.


b.


c.


7. a. Both axes b. *y*-axis
c. *x*-axis d. First quadrant

8.


Parallelogram

9. a. Second quadrant b. Fourth quadrant
c. Third quadrant d. *y*-axis
e. *x*-axis f. First quadrant

10. a. -5 b. -17 c. 8 d. 6

11. a. -2 b. 7 c. 1 d. 2
e. 0

12. a. -8 b. 26 c. 3 d. -2
e. -8 f. 2

13. a. -42 b. -32 c. 10 d. 64
e. -64 f. -128

14. a. -12 b. 3 c. -5 d. 9
e. -16 f. -4

15. a. -2 b. -3 c. 27 d. -8
e. 5

16. a. -20 **b.** 12 **c.** 15
d. -125 **e.** -9

17. a. $-5 < -3$ **b.** $-22 \times -2 = 44$
c. $4 > 2$ **d.** $-5 \times 3 > -15$
e. $0 > -7$ **f.** $-2(-4 + 7) < 6$

18. a. $-2 \times 5 < -9$ **b.** $5 \times (-2 - 18) \div -4 = 25$
c. $12 \div -4 < 3$ **d.** $5 \times (-2 - 18) \div 4 = -25$
e. $-10 \times -5 = 50$ **f.** $5 \times -2 - 18 \div 4 < 2.5$

19. $-52 + 3 \times 15 = -7$

20. 601 years

21. 148 °C

22. −$94

23. a. Negative

b. Positive


c. Negative
Two negative numbers added together will always be negative. When a positive and a negative number are added together, if the larger number is positive the result will be positive. If the larger number is negative the result will be negative.

24. a. D(−1, 0)

b. i. CBA, BAD (Others are possible).

ii. ADE or BCE

c. F(−3, −1)




d. (1, 1.5)


e. (2, −2)

f. G(−4, −2.5)

25. a.



b.



26. *X* is positive and *Y* is negative.

27. Column 2

28. a.

Integer (x)	x^2	x^3	x^4	x^5
2	4	8	16	32
−2	4	−8	16	−32
3	9	27	81	243
−3	9	−27	81	−243
4	16	64	256	1024
−4	16	−64	256	−1024

b. Positive

c. If x was negative, then x^3 is negative.

d. For x^4, all the results are positive; for x^5, if x is negative then x^5 is negative.

e. The sign in the x^2 column is the same as the sign in the x^4. The sign in the x^3 is the same as the matching term in the x^5 column.

f. The square root of 100 is 10 or −10.

g. It will give an error message.

h. −5

i.


Integer (x)	$\sqrt{x}$	$\sqrt[3]{x}$	$\sqrt[4]{x}$	$\sqrt[5]{x}$
16	4		2	
−16	Not possible		Not possible	
27		3		
−27		−3		
32				2
−32				−2
81	9		3	
−81	Not possible		Not possible	
64	8	4		
−64	Not possible	−4		

j. When taking an even root of a positive number, the answer can be positive or negative.
It is not possible to take the even root of a negative number.
When taking the odd root of a positive number, the answer is always positive.
When taking the odd root of a negative number, the answer is always negative.

3 Factors, multiples, indices and primes

LEARNING SEQUENCE

3.1 Overview 116
3.2 Factors and multiples 118
3.3 Lowest common multiple and highest common factor 123
3.4 Index notation 128
3.5 Prime and composite numbers 133
3.6 Squares and square roots 141
3.7 Divisibility tests 147
3.8 Cubes and cube roots (extending) 150
3.9 Review 155



3.1 Overview

Why learn this?




Whole numbers can be written in different ways that can make calculations easier if you do not have your calculator handy. You have been using multiplication tables already without necessarily realising that the they give you numbers that are multiples of each other. Knowing how to write numbers in different ways helps in understanding how numbers are connected.

Indices are short ways of writing a repeated multiplication and are very useful in everyday life, because they allow us to write very large and very small numbers more easily. Indices can simplify calculations involving these very large or very small numbers. Astronomy is a branch of science in which very large distances are involved. The stars we see in the Southern Hemisphere night sky are different to the stars people see in the Northern Hemisphere. Alpha Crucis, the brightest and closest star to us in the Southern Cross constellation, is approximately 3000 million billion kilometres from Earth. That is a huge number — 3 followed by 15 zeros! Other scientists and engineers also need to be able to communicate and work with numbers of all sizes.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 3.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC The first 3 multiples of 8 are:
A. 2, 4, 8 **B.** 8, 16, 24 **C.** 4, 8, 16 **D.** 1, 8, 16 **E.** 1, 2, 4

2. Kate earned $7 pocket money each week for 5 weeks for emptying the dishwasher. Given she saves all her money, calculate how much she would have saved at the end of the 5 weeks.

3. Determine the highest common factor of 42 and 66.

4. Fred takes 3 minutes to complete one lap of a running course, while Sam takes 4 minutes to complete one lap. After the start, determine when Fred will next be running beside Sam.

5. Write $5 \times 3 \times 5 \times 3 \times 3 \times 3$ in simplified index notation.

6. Select all the prime numbers from the following.
A. 21 **B.** 109 **C.** 33 **D.** 81 **E.** 17 **F.** 31 **G.** 91

7. Select two pairs of prime numbers whose sum is 20.
A. 1, 19 **B.** 2, 18 **C.** 3, 17 **D.** 5, 15 **E.** 7, 13 **F.** 9, 11

8. Select all the prime factors of 40.
A. 1 **B.** 2 **C.** 3 **D.** 4 **E.** 5
F. 8 **G.** 10 **H.** 20 **I.** 40

9. Determine the lowest common multiple (LCM) and highest common factor (HCF) of 54 and 96 by first expressing each number as a product of its prime factors.

10. A chessboard is a large square with sides that are 8 small squares in length. Calculate the total number of small squares on a chessboard.

11. Evaluate the following.
$3^2 + \sqrt{16} \times 5^2$

12. Determine between which two integers $\sqrt{70}$ lies.

13. Evaluate the following.
$\sqrt[3]{27}$

14. Sarah wants to organise a party with her friends at short notice. She decides to send a text to three of her friends, who contact another three friends each, and then they all contact a further three friends each.
Determine the number of friends that are invited to the party.

15. Evaluate the following.
$$\frac{11^2 - \sqrt[3]{216} \times \sqrt{144}}{\sqrt{49}}$$

3.2 Factors and multiples

LEARNING INTENTION

At the end of this subtopic you should be able to:
- list multiples and factors of a whole number
- determine multiples and factor pairs.

3.2.1 Multiples

eles-3725

- A **multiple** of a number is the result of **multiplying** that number by another whole number. For example, all numbers in the 5 times table are multiples of 5: so 5, 10, 15, 20, 25, ... are all multiples of 5.

×	1	2	3	4	5
1	1	2	3	4	5
2	2	4	6	8	10
3	3	6	9	12	15
4	4	8	12	16	20
5	5	10	15	20	25

WORKED EXAMPLE 1 Listing multiples of a whole number

List the first five multiples of 7.

THINK	WRITE
1. The first multiple is the number × 1, that is, 7 × 1.	7
2. The second multiple is the number × 2, that is, 7 × 2.	14
3. The third multiple is the number × 3, that is, 7 × 3.	21
4. The fourth multiple is the number × 4, that is, 7 × 4.	28
5. The fifth multiple is the number × 5, that is, 7 × 5.	35
6. Write the answer as a sentence.	The first five multiples of 7 are 7, 14, 21, 28 and 35.

WORKED EXAMPLE 2 Determining multiples

State which numbers in the following list are multiples of 8.

18, 8, 80, 100, 24, 60, 9, 40

THINK	WRITE
1. The biggest number in the list is 100. List multiples of 8 using the 8 times table just past 100; that is, 8 × 1 = 8, 8 × 2 = 16, 8 × 3 = 24, 8 × 4 = 32, 8 × 5 = 40, and so on.	8, 16, 24, 32, 40, 48, 56, 64, 72, 80, 88, 96, 104
2. Write any multiples that appear in the given list.	Numbers in the given list that are multiples of 8 are 8, 24, 40 and 80.

3.2.2 Factors

eles-3726

- A **factor** of a whole number **divides** into that whole number exactly. For example, the number 4 is a factor of 8 because 4 divides into 8 twice or $8 \div 4 = 2$.
- Factors of a number can be written as factor pairs. For example, since $4 \times 2 = 8$, it follows that 2 and 4 are a factor pair of 8.



Unique factors

Except for the number 1, every whole number has at least two unique factors, 1 and itself.

For example, the factors of 5 are 1 and 5.

WORKED EXAMPLE 3 Listing factors of a whole number

List all the factors of 14.

THINK	WRITE
1. 1 is a factor of every number, and the number itself is a factor of itself, that is, $1 \times 14 = 14$.	1, 14
2. 14 is an even number, so 14 is divisible by 2; therefore, 2 is a factor. Divide the number by 2 to find the other factor ($14 \div 2 = 7$). There are no other whole numbers that divide evenly into 14.	2, 7
3. Write the answer as a sentence, placing the factors in order from smallest to largest.	The factors of 14 are 1, 2, 7 and 14.


WORKED EXAMPLE 4 Determining factor pairs

List the factor pairs of 30.

THINK	WRITE
1. 1 and the number itself are factors, that is, $1 \times 30 = 30$.	1, 30
2. 30 is an even number, so 2 and 15 are factors, that is, $2 \times 15 = 30$.	2, 15
3. Divide the next smallest number into 30. Therefore, 3 and 10 are factors, that is, $3 \times 10 = 30$.	3, 10
4. 30 ends in 0 so 5 divides evenly into 30, that is, $5 \times 6 = 30$.	5, 6
5. Write the answer as a sentence by listing the factor pairs.	The factor pairs of 30 are: 1, 30; 2, 15; 3, 10 and 5, 6.

COLLABORATIVE TASK: Sorting multiples and factors

1. As a class, draw a large 10×5 number chart on the board and number the boxes from 1 to 50.
2. Your teacher will share the numbers 1 to 50 among the class. For each of your numbers, list the multiples up to and including 50.
3. Your teacher will call out the numbers between 1 and 50 one at a time. When one of your numbers is called, write it in each box on the chart that is a multiple of your number. For example, if your number is 10, write 10 in each box that corresponds to a multiple of 10.
4. At the end of the activity, the numbers written in each of the boxes are the factors of the box numbers. You can see that different numbers have different numbers of factors.
5. As a class, investigate:
   a. which numbers have one factor, two factors, three factors or four factors
   b. which numbers have more than four factors
   c. whether there are more numbers with an odd or even number of factors
   d. how factors and multiples are related.



Resources

eWorkbook	Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)
Digital documents	SkillSHEET Multiples (doc-6416) SkillSHEET Factor pairs (doc-6417)
Video eLesson	Factors and multiples (eles-2310)
Interactivities	Individual pathway interactivity: Factors and multiples (int-4316) Multiples (int-3929) Factors (int-3930)

Exercise 3.2 Factors and multiples

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 8, 10, 12, 15, 18, 22, 23, 26	2, 5, 9, 13, 16, 19, 24, 27	3, 7, 11, 14, 17, 20, 21, 25, 28

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 List the first five multiples of the following numbers.
   a. 3 b. 6 c. 100 d. 11
2. List the first five multiples of the following numbers.
   a. 120 b. 45 c. 72 d. 33

3. WE2 Select the numbers in the following list that are multiples of 10.
10, 15, 20, 100, 38, 62, 70

4. Select the numbers in the following list that are multiples of 7.
17, 21, 7, 70, 47, 27, 35

5. Write the numbers in the following list that are multiples of 16.
16, 8, 24, 64, 160, 42, 4, 32, 1, 2, 80

6. List the multiples of 9 that are less than 100.

7. List the multiples of 6 between 100 and 160.

8. MC The first three multiples of 9 are:

A. 1, 3, 9 B. 3, 6, 9 C. 9, 18, 27 D. 9, 18, 81 E. 18, 27, 36

9. MC The first three multiples of 15 are:

A. 15, 30, 45 B. 30, 45, 60 C. 1, 15, 30 D. 45 E. 3, 5, 15

10. WE3 List all the factors of the following numbers.

a. 12 b. 40

11. A list of numbers is: 2, 7, 5, 20, 25, 15, 10, 3, 1.
From this list, select all the numbers that are factors of each of the following values.

a. 28 b. 60 c. 100

Understanding

12. List all factors of the following numbers in ascending order.

a. 72 b. 250

13. A list of numbers is: 21, 5, 11, 9, 1, 33, 3, 17, 7.
From this list, select all the numbers that are factors of each of the following values.

a. 85 b. 99 c. 51

14. List the factor pairs of 20.

15. List the factor pairs of 132.

16. MC Select all the factor pairs of 18.

A. 1, 9 B. 3, 6 C. 2, 9 D. 6, 12 E. 1, 18

17. Three is a factor of 12. State the smallest number greater than 12 that has 3 as one of its factors.

18. MC A factor pair of 24 is:

A. 2, 4 B. 4, 6 C. 6, 2 D. 2, 8 E. 3, 9

19. MC A factor pair of 42 is:

A. 6, 7 B. 20, 2 C. 21, 1 D. 16, 2 E. 6, 8

20. Determine which of the numbers 3, 4, 5 and 11 are factors of 2004.


21. Alex and Nadia were racing down a flight of stairs. Nadia took the stairs two at a time while Alex took the stairs three at a time. In each case, they reached the bottom with no steps left over.



a. Determine how many steps there are in the flight of stairs. List three possible answers.
b. Determine the smallest number of steps there could be.
c. If Alex can also take the stairs five at a time with no steps left over, determine the smallest number of steps in the flight of stairs.

Reasoning

22. Place each of the first six multiples of 3 into the separate circles around the triangle so the numbers along each side of the triangle add up to 27. Use each number once only.



23. Ms Pythagoras is trying to organise her Year 4 class into rows for their class photograph.
If Ms Pythagoras wishes to organise the 20 students into rows containing equal numbers of students, determine what possible arrangements she can have.
Note: Ms Pythagoras will not be in the photograph.



24. My age is a multiple of 3 and a factor of 60. The sum of the digits of my age is 3. Determine my age. (There are three possible answers.)

25. A man and his grandson share the same birthday. For exactly six consecutive years the grandson's age is a factor of his grandfather's age. Determine how old each of them is at the sixth of these birthdays, given that the grandson is no more than 10.



Problem solving

26. I am a two-digit number that can be divided by 3 with no remainder. The sum of my digits is a multiple of 4 and 6. My first digit is double my second digit. Evaluate the number. Show your working.

27. Determine the following number. I am a multiple of 5 with factors of 6, 4 and 3. The sum of my digits is 6. Show your working.

28. Identify a two-digit number such that if you subtract 3 from it, the result is a multiple of 3; if you subtract 4 from it, the result is a multiple of 4; and if you subtract 5 from it, the result is a multiple of 5. Explain how you reached the answer.

3.3 Lowest common multiple and highest common factor

LEARNING INTENTION


At the end of this subtopic you should be able to:

- determine the lowest common multiple and the highest common factor of two or more whole numbers.

3.3.1 The LCM and HCF

eles-3727

- **Common multiples** are numbers that are multiples of more than one number.
  Multiples of 3: 3, 6, 9, **12**, 15, 18, 21, **24**, …
  Multiples of 4: 4, 8, **12**, 16, 20, **24**, 28, …
  The first two common multiples of 3 and 4 are 12 and 24.
- The **lowest common multiple (LCM)** is the smallest multiple that is common to two or more numbers.
  The LCM of 3 and 4 is 12.
- **Common factors** are numbers that are factors of more than one number.
  Factors of 16: **1**, **2**, **4**, **8** and 16
  Factors of 24: **1**, **2**, 3, **4**, 6, **8**, 12 and 24
  The common factors of 16 and 24 are 1, 2, 4 and 8.
- The common factors of 16 and 24 can be seen in the overlapping region of a Venn diagram, as shown.
- The **highest common factor (HCF)** is the largest of the common factors. The HCF of 16 and 24 is 8.



WORKED EXAMPLE 5 Determining the lowest common multiple of two numbers

a. **List the first nine multiples of 8.**
b. **List the first nine multiples of 12.**
c. **List the multiples that 8 and 12 have in common.**
d. **State the lowest common multiple of 8 and 12.**

THINK	WRITE
a. Write out the first nine numbers of the 8 times table.	8, 16, 24, 32, 40, 48, 56, 64, 72
b. Write out the first nine numbers of the 12 times table.	12, 24, 36, 48, 60, 72, 84, 96, 108
c. Choose the numbers that appear in both lists.	24, 48, 72
d. State the lowest of these numbers to give the lowest common multiple (LCM).	LCM is 24.

WORKED EXAMPLE 6 Determining the highest common factor

a. Determine the common factors of 8 and 24 by:
- **i. listing the factors of 8**
- **ii. listing the factors of 24**
- **iii. listing the factors common to both 8 and 24.**

b. State the highest common factor of 8 and 24.

THINK	WRITE
a. i. 1. List the pairs of factors of 8.	a. i. 1, 8, 2, 4
2. Write them in order.	Factors of 8 are 1, 2, 4, 8.
ii. 1. List the pairs of factors of 24.	ii. 1, 24; 2, 12; 3, 8; 4, 6
2. Write them in order.	Factors of 24 are 1, 2, 3, 4, 6, 8, 12, 24.
iii. Write the common factors.	iii. Common factors are 1, 2, 4, 8.
b. State the highest common factor, that is, the largest of the common factors.	b. HCF is 8.

Resources

eWorkbook Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)

Interactivities Individual pathway interactivity: Lowest common multiple and highest common factor (int-4317)
Lowest common multiple (int-3931)
Highest common factor (int-4545)

Exercise 3.3 Lowest common multiple and highest common factor

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 7, 10, 11, 12, 16, 19	3, 4, 8, 13, 14, 17, 20	5, 6, 9, 15, 18, 21

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. a. WE5 List the first ten multiples of 4.
   b. List the first ten multiples of 6.
   c. In your lists, circle the multiples that 4 and 6 have in common (that is, circle the numbers that appear in both lists).
   d. State the lowest multiple that 4 and 6 have in common. This is the lowest common multiple (LCM) of 4 and 6.

2. State the LCM for each of the following pairs of numbers.
   a. 3 and 9 b. 6 and 15 c. 7 and 10 d. 12 and 16 e. 4 and 15

3. State whether the following statement is true or false.
   20 is a multiple of 10 and 2 only.

4. State whether the following statement is true or false.
   15 and 36 are both multiples of 3.

5. State whether the following statement is true or false.
60 is a multiple of 2, 3, 6, 10 and 12.

6. State whether the following statement is true or false.
100 is a multiple of 2, 4, 5, 10, 12 and 25.

7. WE6 By listing the factors of each number, determine the highest common factor (HCF) for each of the following pairs of numbers.
   a. 21 and 56 b. 7 and 28 c. 48 and 30

8. Determine the HCF for each of the following pairs of numbers.
   a. 9 and 36 b. 42 and 77

9. Determine the HCF of the following numbers.
   a. 36 and 64 b. 45, 72 and 108

Understanding

10. Kate goes to the gym every second evening, while Ian goes every third evening.
    a. On Monday evening, Kate and Ian are at the gym together. Determine how many days it will be before both attend the gym again on the same evening.
    b. Explain how this answer relates to the multiples of 2 and 3.

11. Vinod and Elena are riding around a mountain bike trail. Vinod completes one lap in the time shown on the stopwatch on the left, and Elena completes one lap in the time shown on the stopwatch on the right.
    a. If they both begin cycling from the starting point at the same time, determine how long it will be before they pass the starting point again at exactly the same time.
    b. Relate your answer to the multiples of 5 and 7.









12. A warehouse owner employs Bob and Charlotte as security guards. Each security guard checks the building at midnight. Bob then checks the building every 4 hours, and Charlotte checks every 6 hours.
    a. Determine how long it will be until both Bob and Charlotte are next at the warehouse at the same time.
    b. Relate your answer to the multiples of 4 and 6.



13. Two smugglers, Bill Bogus and Sally Seadog, have set up signal lights that flash continuously across the ocean. Bill's light flashes every 5 seconds and Sally's light flashes every 4 seconds. If they start together, determine how long it will take for both lights to flash again at the same time.

14. Twenty students in Year 7 were each given a different number from 1 to 20 and then asked to sit in numerical order in a circle. Three older girls — Milly, Molly and Mandy — came to distribute jelly beans to the class. Milly gave red jelly beans to every second student, Molly gave green jelly beans to every third student and Mandy gave yellow jelly beans to every fourth student.
    a. Determine which student had jelly beans of all 3 colours.
    b. Calculate how many students received exactly 2 jelly beans.
    c. Calculate how many students did not receive any jelly beans.



15. Wah needs to cut tubing into the largest pieces of equal length that he can, without having any offcuts left over. He has three sections of tubing: one 6 metres long, another 9 metres long and the third 15 metres long.
    a. Calculate how long each piece of tubing should be.
    b. Determine how many pieces of tubing Wah will end up with.

Reasoning

16. Two candles of equal length are lit at the same time. The first candle takes 6 hours to burn out and the second takes 3 hours to burn out. Determine how many hours it will be until the slower-burning candle is twice as long as the faster-burning candle.



17. Mario, Luigi, Zoe and Daniella are playing a video game. Mario takes 2 minutes to play one level of the game, Luigi takes 3 minutes, Zoe takes 4 minutes and Daniella takes 5 minutes. They have 12 minutes to play.
    a. If they play continuously, determine which player would be in the middle of a game as time ran out.
    b. Determine after how many minutes this player began the last game.

18. Six church bells ring repeatedly at intervals of 2, 4, 6, 8, 10 and 12 minutes respectively. Determine how many times three or more bells will ring together in 30 minutes.


Problem solving

19. Carmen types 30 words per minute on her laptop while Evan types 40 words per minute on his laptop. They have to type the same number of words and they both end up typing for a whole number of minutes.
    a. Determine how long Carmen has been typing for.
    b. Determine how long Evan has been typing for.




20. Alex enjoys running around the park after school. It takes him 10 minutes to complete one lap. His mother Claire walks the family dog at the same time. It takes her 15 minutes to complete one lap. They decide to go home when they meet next. Determine how long it will take them to meet again.

21. The runners in a 100 m race are lined up next to each other while those in a 400 m race are staggered around the track. Look at the following diagram of a standard 400 m athletic track and take note of both the starting position and finish line for a 100 m race.



a. State the shapes of the two curved ends of the track.
b. Explain why the starting line for a 100 m race has been positioned in the straight section.
c. Explain why the finish line for a 100 m race has been positioned where it is.

Track events such as the 200 m, 400 m and 800 m races have staggered starting positions. The following diagram illustrates the position of the starting blocks S_1–S_8 for each lane in the 400 m race.



d. Explain why there is a need to stagger the starting blocks in the 200 m, 400 m and 800 m track events.
e. A runner completing one lap of the inside lane (lane 1) runs a distance of 400 m, while if there is no staggered start a runner completing one lap in the next lane (lane 2) runs a distance of 408 m. If this pattern continues, determine how far runners in lanes 3–8 run. Enter these results in the appropriate column in the table.

Lane number	Distance travelled (m)	Difference
1	400 m	
2	408 m	
3		
4		
5		
6		
7		
8	456 m	

f. Calculate the difference between the distances travelled by the runners in each of the lanes compared to the distance travelled by the runner in lane 1. Enter these results in the appropriate column in the table.
g. Comment on what you notice about the values obtained in part **f**.

3.4 Index notation

LEARNING INTENTION

At the end of this subtopic you should be able to:

- understand that index or exponent notation is a short way of writing a repeated multiplication
- write expressions in index notation
- simplify expressions using index notation
- use place value to write and evaluate numbers in expanded form with index notation.

3.4.1 Introduction to indices

eles-3728

- An **index** (or **exponent** or **power**) is a short way of writing a repeated multiplication.
- The **base** is the number that is being repeatedly multiplied and the index (plural *indices*) is the number of times it is multiplied.



$$\underbrace{8^6}_{\text{Index form}} = \underbrace{8 \times 8 \times 8 \times 8 \times 8 \times 8}_{\text{Expanded form}} = \underbrace{262\ 144}_{\text{Basic numeral}}$$

- Numbers in index form are read using the value of both the base and the power.

8^6 is read as '8 to the power of 6'.
12^4 is read as '12 to the power of 4'.

WORKED EXAMPLE 7 Identifying the base and index

For the following expressions, state:
i. the number or pronumeral that is the base
ii. the number or pronumeral that is the index.

a. 6^7 **b.** x^9 **c.** 3^a **d.** y^b

THINK

The base is the number or pronumeral that is repeatedly multiplied, and the index is the number of times that it is multiplied.

WRITE

a. 6^7
i. Base is 6
ii. Index is 7

b. x^9
i. Base is x
ii. Index is 9

c. 3^a
i. Base is 3
ii. Index is a

d. y^b
i. Base is y
ii. Index is b

WORKED EXAMPLE 8 Writing an expression using index notation

Write the following expressions using index notation.

a. $5\times5\times5\times5\times5\times5\times5$ **b.** $3\times3\times3\times3\times7\times7$

THINK	WRITE
a. 1. Write the multiplication.	**a.** $5\times5\times5\times5\times5\times5\times5$
2. Write the number being repeatedly multiplied as the base, and the number of times it is written as the index (the number 5 is written 7 times).	$=5^7$
b. 1. Write the multiplication.	**b.** $3\times3\times3\times3\times7\times7$
2. Write the number being multiplied as the base, and the number of times it is written as the index (the number 3 is written 4 times, and 7 is written 2 times).	$=3^4\times7^2$

WORKED EXAMPLE 9 Simplifying expressions using index notation

Simplify each of the following expressions by first writing each expression as a repeated multiplication and then in index notation.

a. $3^4\times3^6$ **b.** $(4^3)^3$ **c.** $(3\times5)^2$

THINK	WRITE
a. 1. Write the expression.	**a.** $3^4\times3^6$
2. Write the expression using repeated multiplication (that is, in expanded form).	$=(3\times3\times3\times3)\times(3\times3\times3\times3\times3\times3)$ $=3\times3\times3\times3\times3\times3\times3\times3\times3\times3$
3. Write the repeated multiplication using index notation. The number being repeatedly multiplied is 3 (base), and the number of times it is written is 10 (index).	$=3^{10}$
b. 1. Write the expression.	**b.** $(4^3)^3$
2. Write the expression using repeated multiplication (that is, in expanded form).	$=4^3\times4^3\times4^3$ $=(4\times4\times4)\times(4\times4\times4)\times(4\times4\times4)$ $=4\times4\times4\times4\times4\times4\times4\times4\times4$
3. Write the repeated multiplication using index notation. The number being repeatedly multiplied is 4 (base) and the number of times it is written is 9 (index).	$=4^9$
c. 1. Write the expression.	**c.** $(3\times5)^2$
2. Write the expression using repeated multiplication (that is, in expanded form).	$=(3\times5)\times(3\times5)$ $=3\times5\times3\times5$ $=3\times3\times5\times5$
3. Write the repeated multiplication using index notation. The numbers being repeatedly multiplied are 3 and 5 (base) and the number of times they are written is 2 (index) in each case.	$=3^2\times5^2$

3.4.2 Indices and place values

eles-3729

- By using place value, you can write numbers in expanded form with index notation.
  For example:

$$\begin{aligned} 2700 &= 2000 + 700 \\ &= 2 \times 10 \times 10 \times 10 + 7 \times 10 \times 10 \\ &= 2 \times 10^3 + 7 \times 10^2 \end{aligned}$$

WORKED EXAMPLE 10 Expressing numbers in expanded form using index notation

Write the following numbers in expanded form using index notation.
a. 59 176 **b. 108 009**

THINK	WRITE
a. 1. Write the number as the sum of each place value.	a. $59\,176 = 50\,000 + 9000 + 100 + 70 + 6$
2. Write each place value in multiples of 10.	$59\,176 = 5 \times 10 \times 10 \times 10 \times 10 + 9 \times 10 \times 10 \times 10 + 1 \times 10 \times 10 + 7 \times 10 + 6$
3. Write each place value in index notation.	$59\,176 = 5 \times 10^4 + 9 \times 10^3 + 1 \times 10^2 + 7 \times 10^1 + 6$
b. 1. Write the number as the sum of each place value.	b. $108\,009 = 100\,000 + 8000 + 9$
2. Write each place value in multiples of 10.	$108\,009 = 1 \times 10 \times 10 \times 10 \times 10 \times 10 + 8 \times 10 \times 10 \times 10 + 9$
3. Write each place value in index notation.	$108\,009 = 1 \times 10^5 + 8 \times 10^3 + 9$

WORKED EXAMPLE 11 Evaluating indices

Evaluate each of the following.
a. 2^5 **b. $3^2 \times 2^3$** **c. $3^2 + 5^2 - 2^4$**


THINK	WRITE
a. 1. Write in expanded form.	$2^5 = 2 \times 2 \times 2 \times 2 \times 2$
2. Multiply the terms.	$= 32$
3. Write the answer.	$2^5 = 32$
b. 1. Write both terms in expanded form.	$3^2 \times 2^3 = (3 \times 3) \times (2 \times 2 \times 2)$
2. Calculate the product of the numbers in the brackets.	$= 9 \times 8$
3. Multiply the terms.	$= 72$
4. Write the answer.	$3^2 \times 2^3 = 72$
c. 1. Write all terms in expanded form.	$3^2 + 5^2 - 2^4 = (3 \times 3) + (5 \times 5) - (2 \times 2 \times 2 \times 2)$
2. Calculate the product of the numbers in the brackets.	$= 9 + 25 - 16$

3. Remember the order of operations. Since the operations are addition and subtraction, work left to right.
$= 34 - 16$
$= 18$

4. Write the answer. $3^2 + 5^2 - 2^4 = 18$

Digital technology

Scientific calculators can evaluate expressions in index form where the base is a number.



Resources

eWorkbook Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)
Interactivities Individual pathway interactivity: Index notation (int-4319)
Index notation (int-3957)

Exercise 3.4 Index notation

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 7, 10, 12, 13, 16	3, 6, 8, 14, 17, 18	4, 9, 11, 15, 19, 20, 21

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE 7 In each of the following expressions, enter the missing number into the box and state what the base and index are.
   a. $7^{\square} = 49$ b. $4^{\square} = 4096$ c. $\square^4 = 81$ d. $\square^3 = 1000$

2. WE8a Write each of the following expressions in index notation.
   a. $7 \times 7 \times 7 \times 7$ b. $8 \times 8 \times 8 \times 8 \times 8 \times 8$
   c. $3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3$ d. $13 \times 13 \times 13$

3. WE8b Write the following expressions in index notation.
   a. $4 \times 4 \times 4 \times 4 \times 4 \times 6 \times 6 \times 6$ b. $2 \times 2 \times 3$
   c. $5 \times 5 \times 2 \times 2 \times 2 \times 2$ d. $3 \times 3 \times 2 \times 2 \times 5 \times 5 \times 5$

4. Write the following using repeated multiplication (that is, in expanded form).
   a. 6^5 b. 11^3

5. WE9 Simplify each of the following expressions by first writing each expression as a repeated multiplication and then using index notation.
   a. $5^8 \times 5^3$ b. $4^8 \times 4^5$ c. $(2^7)^3$

6. WE10 Write the following numbers in expanded form using index notation.
   a. 300 b. 4500 c. 6705 d. 10 000

Understanding

7. WE9 Simplify each of the following expressions by first writing each expression as a repeated multiplication and then using index notation.
   a. $(9^5)^3$ b. $(3 \times 13)^6$

8. MC The value of 4^4 is:
   A. 8 B. 16 C. 64 D. 256 E. 484

9. WE11 Evaluate each of the following.
   a. 7^3 b. $6^2 \times 2^3$ c. $5^3 - 4^3 + 2^4$

10. Evaluate each of the following.
    a. $2^3 \times 3^2$ b. $3^4 \times 4^3$ c. $3^5 \times 9^3$

11. Evaluate each of following.
    a. $6^4 - 9^3$ b. $5^3 + 2^5 \times 9^2$ c. $2^7 - 4^5 \div 2^6$

Reasoning

12. a. MC Which of the following expressions has the greatest value?
    A. 2^8 B. 8^2 C. 3^4 D. 4^3 E. 9^2
    b. Justify your answer using mathematical reasoning.

13. We know that $12^2 = 144$ and $21^2 = 441$. It is also true that $13^2 = 169$ and $31^2 = 961$. If $14^2 = 196$, is $41^2 = 691$? Try to justify your answer without calculating 41^2.

14. Write < (less than) or > (greater than) in the boxes below to make each statement true.
    a. $1^3 \square 3^1$ b. $2^3 \square 3^2$ c. $5^3 \square 3^5$ d. $4^4 \square 3^5$

15. You have a choice of how your weekly allowance is increased for 15 weeks.
    Option 1: Start a 1 cent and double your allowance every week.
    Option 2: Start at $1 and increase your allowance by $1 every week.
    a. Explain which option you would choose and why.
    b. Explain whether powers can be used to help with these calculations.

Problem solving

16. Jessica has a 'clean-up' button on her mobile phone that will clear half of the read messages in her inbox. She pressed the button six times, causing just one message to be left in her inbox. Calculate how many messages were in her inbox before the clean-up.


17. A student sent an email to eight of his cousins, who then each forwarded the email to eight different friends, who in turn forwarded the email to another eight friends each.
    a. Calculate how many emails in total were sent during this process.
    b. Assuming that everyone received the email only once, determine how many people in total received the email by the end of this process.



18. You received a text message from your friend. After 5 minutes, you forward the text message to two of your other friends. After 5 more minutes, those two friends forward it to two more friends. If the text message is sent every 5 minutes in this way, calculate how many people have received it in 30 minutes.



19. Bacteria such as those shown in the image grow at an alarming rate. Each bacterium can split itself in half, forming two new cells each hour.



a. If you start with one bacterium cell, calculate how many you will have after 12 hours. Show your working to include the number of bacteria after each hour.
b. If a bacterium could successfully divide into three new cells each hour, calculate how many bacteria you would have after 12 hours.
c. Show how powers can be applied to the calculations in parts **a** and **b**.

20. A knock-out tennis competition ends with 2 players in the grand final. If the grand final is the 8th round of the competition, and half the players are knocked out in each round, determine how many players there were at the start of the competition.



21. A particular rule applies to each of these three sets of numbers.
Set A: 1, 2, 5 Set B: 2, 5, 26 Set C: 3, 10, ?
Explain how you can determine the rule and the missing number.

3.5 Prime and composite numbers

LEARNING INTENTION

At the end of this subtopic you should be able to:

- understand the difference between prime and composite numbers
- determine prime factors by drawing a factor tree
- write a composite number in index form
- determine the highest common factor (HCF) and lowest common multiple (LCM) of large numbers as products of their prime factors.


3.5.1 Prime numbers

eles-3730

- A **prime number** is a counting number that has exactly 2 unique factors: itself and 1.
  (Counting numbers are 1, 2, 3, 4, …)
  The number 3 is a prime number; its only factors are 3 and 1.
  The number 2 is the only even prime number; its only factors are 2 and 1.
- A **composite number** is one that has more than two factors.
  The number 4 is a composite number; its factors are 1, 2 and 4.
- The number 1 is a special number. It is neither a prime number nor a composite number because it has only one factor, 1.

COLLABORATIVE TASK: The sieve of Eratosthenes

Eratosthenes (pronounced 'e-rah-toss-thee-knees') was a Greek mathematician who lived around 200 BC. He worked out a way to sort prime numbers from composite numbers.



1. As a class, draw a 10×10 grid on the board and number the boxes from 1 to 100.
2. Shade the number 1. It is not a prime or composite number.
3. Circle the number 2. Cross out all other multiples of 2.
4. Circle the next smallest uncrossed number, 3. Cross out all other multiples of 3.
5. Continue this process until all the numbers in the grid are either circled or crossed out.
6. Describe the circled numbers.
7. Describe the crossed out numbers.
8. **a.** Are there more prime numbers or composite numbers?
   b. What connections can you make between composite numbers and multiples?

1	2	3	4	5	6	7	8	9	10
11	12	13	14	15	16	17	18	19	20
21	22	23	24	25	26	27	28	29	30
31	32	33	34	35	36	37	38	39	40
41	42	43	44	45	46	47	48	49	50
51	52	53	54	55	56	57	58	59	60
61	62	63	64	65	66	67	68	69	70
71	72	73	74	75	76	77	78	79	80
81	82	83	84	85	86	87	88	89	90
91	92	93	94	95	96	97	98	99	100

WORKED EXAMPLE 12 Listing prime numbers

List the prime numbers between 50 and 70.

THINK

1. The only even prime number is 2. The prime numbers between 50 and 70 will be odd. Numbers ending in 5 are divisible by 5 so 55 and 65 are not primes.
2. Check the remaining odd numbers between 50 and 70:
   $51 = 3 \times 17$ and 1×51. It has four factors so it is composite.
   $53 = 1 \times 53$. It has two unique factors only so it is prime.
   $57 = 3 \times 19$ and 1×57. It has four factors so it is composite.
   $59 = 1 \times 59$. It has two unique factors only so it is prime.
   $61 = 1 \times 61$. It has two unique factors only so it is prime.
   $63 = 7 \times 9$, 3×21 and 1×63. It has six factors so it is composite.
   $67 = 1 \times 67$. It has two unique factors only so it is prime.
   $69 = 3 \times 23$ and 1×69. It has four factors so it is composite.

WRITE

The prime numbers are: 53, 59, 61, 67.

WORKED EXAMPLE 13 Checking for composite and prime numbers

State whether the following numbers are prime or composite.

a. 45 **b. 37** **c. 86**

THINK

a. Factors of 45 are 1, 3, 5, 9, 15 and 45.

b. The only factors of 37 are 1 and 37.

c. Factors of 86 are 1, 2, 43 and 86. All even numbers except 2 are composite.

WRITE

a. 45 is composite.

b. 37 is prime.

c. 86 is composite.

DISCUSSION

Explain your method of working out whether a number is a prime number.

eles-3731


3.5.2 Composite numbers and factor trees

- Every composite number can be written as the product of its prime factors.
- Writing any number as a product of its prime factors simply means to rewrite a number using **multiplication** of **prime numbers** only. For example:

$$12 = 2 \times 2 \times 3 = 2^2 \times 3$$

Prime numbers that multiply to give 12

- A **factor tree** shows the **prime factors** of a composite number.
- Each branch shows a factor of the number above it.
- Branches stop at factors that are prime numbers, as shown at right in pink.
- In the factor tree shown, 20 can be written as $2 \times 2 \times 5$; this is known as writing a number as a product of its prime factors.



$20 = 2 \times 2 \times 5 = 2^2 \times 5$

WORKED EXAMPLE 14 Determining the prime factors by drawing a factor tree

a. Determine the prime factors of 50 by drawing a factor tree.

b. Write 50 as a product of its prime factors in index form.


THINK


a. 1. Write a factor pair of the given number and draw the factor tree ($50 = 5 \times 10$).

2. If a branch is prime, no other factors can be found (5 is prime). If a branch is composite, write factors of that number: 10 is composite, so $10 = 5 \times 2$.

WRITE

a.





3. Continue until all branches end in a prime number, then stop.
4. Write the prime factors.

The prime factors of 50 are 2 and 5.

b. Write 50 as a product of prime factors in index form found in part a.

b. $50 = 5 \times 5 \times 2$
$= 5^2 \times 2$


WORKED EXAMPLE 15 Writing composite numbers in index form

Write 72 as a product of its prime factors in index form.

THINK

1. Draw a factor tree. When all factors are prime numbers you have found the prime factors.

WRITE



2. Write 72 as a product of its prime factors in index form.

$72 = 2 \times 2 \times 2 \times 3 \times 3$
$= 2^3 \times 3^2$


WORKED EXAMPLE 16 Writing composite numbers in index form

Write 360 as a product of prime factors using index notation.

THINK

1. Draw a factor tree. If the number on the branch is a prime number, stop. If not, continue until a prime number is reached.

WRITE




2. Write the number as a product of prime factors.

$360 = 2 \times 2 \times 2 \times 3 \times 3 \times 5$

3. Write your answer using index notation.

$360 = 2^3 \times 3^2 \times 5$

There can often be more than one way of drawing a factor tree for a number, as shown below.



$48 = 12 \times 4$
$= 2 \times 3 \times 2 \times 2 \times 2$
$= 2^4 \times 3$

$48 = 3 \times 16$
$= 3 \times 2 \times 2 \times 2 \times 2$
$= 2^4 \times 3$

$48 = 2 \times 24$
$= 2 \times 3 \times 2 \times 2 \times 2$
$= 2^4 \times 3$

eles-3732

3.5.3 Lowest common multiple and highest common factor using prime factors

- Expressing large numbers as products of their prime factors makes it easier to determine their lowest common multiple (LCM) or highest common factor (HCF).

Lowest common multiple (LCM)

The LCM of two numbers expressed as the products of their prime factors is the product of the prime factors that are factors of **either** number.

Highest common factor (HCF)

The HCF of two numbers expressed as the products of their prime factors is the product of the prime factors **common** to both numbers.

WORKED EXAMPLE 17 Determining HCF and LCM using prime factors

Determine the highest common factor and lowest common multiple of 270 and 900.

THINK	WRITE
1. Write 270 and 900 as products of their prime factors. Alternatively, a factor tree may be used to determine the prime factors.	$270 = 2 \times 3 \times 3 \times 3 \times 5$ $900 = 2 \times 2 \times 3 \times 3 \times 5 \times 5$
2. Circle the prime factors common to both numbers.	$270 = \textcircled{2} \times \textcircled{3} \times \textcircled{3} \times 3 \times \textcircled{5}$ $900 = 2 \times \textcircled{2} \times \textcircled{3} \times \textcircled{3} \times 5 \times \textcircled{5}$
3. For the HCF, multiply the prime factors common to both numbers.	$2 \times 3 \times 3 \times 5 = 90.$ The HCF of 270 and 900 is 90.
4. For the LCM, multiply the prime factors that are factors of either number. *Hint:* Only include one circled pair.	$2 \times 2 \times 3 \times 3 \times 3 \times 5 \times 5 = 2700$ The LCM of 270 and 900 is 2700.

COLLABORATIVE TASK: Goldbach's conjecture

In 1742, mathematician Christian Goldbach suggested that every even number greater than 2 could be written as the sum of two prime numbers.

In pairs, test this for the even numbers greater than 2 and less than 40.

In pairs, choose 5 even numbers between 100 and 300. Test these numbers to see if Goldbach's conjecture is true.

Do you agree with Christian Goldbach?



Resources

eWorkbook Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)

Interactivities Individual pathway interactivity: Prime numbers and composite numbers (int-4320)
Prime numbers (int-3933)
Composite numbers and factor trees (int-3934)

Exercise 3.5 Prime and composite numbers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 4, 8, 10, 13, 15, 16, 21, 24, 25, 28	5, 7, 9, 12, 17, 19, 20, 22, 26, 29	3, 6, 11, 14, 18, 23, 27, 30

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE12 List four prime numbers that are between 20 and 40.

2. WE13 State whether each of the following numbers is prime or composite.
a. 9 **b.** 13 **c.** 55 **d.** 41

3. State whether each of the following numbers is prime or composite.
a. 64 **b.** 79 **c.** 98 **d.** 101

4. i. WE14 Determine the prime factors of each of the following numbers by drawing a factor tree.
ii. Write each one as a product of its prime factors in index form.
a. 15 **b.** 30 **c.** 100 **d.** 49

5. i. Determine the prime factors of each of the following numbers by drawing a factor tree.
ii. Write each one as a product of its prime factors in index form.
a. 72 **b.** 56 **c.** 45

6. **i.** Determine the prime factors of each of the following numbers by drawing a factor tree.
ii. Write each one as a product of its prime factors in index form.
a. 84 **b.** 112 **c.** 40

7. **i.** WE15 Determine the prime factors of the following numbers by drawing a factor tree.
ii. Express the number as a product of its prime factors in index form.
a. 96 **b.** 32 **c.** 3000

8. Determine the prime factors of each of the following numbers.
a. 48 **b.** 200 **c.** 81 **d.** 18

9. Determine the prime factors of each of the following numbers.
a. 300 **b.** 60 **c.** 120 **d.** 80

Understanding

10. WE16 Write the following as a product of prime factors using index notation.
a. 60 **b.** 75 **c.** 220

11. Write the following as a product of prime factors using index notation.
a. 192 **b.** 124

12. WE17 By expressing the following pairs of numbers as products of their prime factors, determine their lowest common multiple and their highest common factor.
a. 36 and 84 **b.** 48 and 60 **c.** 120 and 400 **d.** 220 and 800

13. State whether each of the following is true or false.

a. All odd numbers are prime numbers.
b. No even numbers are prime numbers.
c. 1, 2, 3 and 5 are the first four prime numbers.
d. A prime number has two factors only.
e. 2 is the only even prime number.

14. State whether each of the following is true or false.

a. The sum of two prime numbers is always even.
b. The product of two prime numbers is always odd.
c. There are no consecutive prime numbers.

15. MC The number of primes less than 10 is:
A. 4 **B.** 3 **C.** 5 **D.** 2 **E.** 1

16. MC The first three prime numbers are:
A. 1, 3, 5 **B.** 2, 3, 4 **C.** 2, 3, 5 **D.** 3, 5, 7 **E.** 2, 5, 7

17. MC The number 15 can be written as the sum of two prime numbers. These are:
A. $3 + 12$ **B.** $1 + 14$ **C.** $13 + 2$ **D.** $7 + 8$ **E.** $9 + 6$


18. MC Factors of 12 that are prime numbers are:
A. 1, 2, 3, 4 **B.** 2, 3, 6 **C.** 2, 3 **D.** 2, 4, 6, 12 **E.** 1, 2, 3, 4, 6, 12

19. The following numbers are not primes. Each of them is the product of two primes. Determine the two primes in each case.


a. 365
b. 187

20. MC A factor tree for 21 is:


A.




B.




C.



D.




E.




21. MC A factor tree for 36 is:


A.




B.




C.



D.



E.



22. MC The prime factors of 16 are:

A. 1, 2 **B.** 1, 2, 4 **C.** 2 **D.** 1, 2, 4, 8, 16 **E.** 2, 4, 8

23. MC The prime factors of 28 are:

A. 1, 28 **B.** 2, 7 **C.** 1, 2, 14 **D.** 1, 2, 7 **E.** 2, 7, 14

Reasoning

24. Determine the largest three-digit prime number in which each digit is a prime number. Prove that this number is a prime number.

25. Is the sum of two prime numbers always a prime number? Explain your answer.

26. Determine a prime number greater than 10 with a sum of digits that equals 11. Show your working.

27. My age is a prime number. I am older than 50. The sum of the digits in my age is also a prime number. If you add a multiple of 13 to my age the result is 100. Determine my age.



28. Determine two prime numbers with a product of:

a. 21 **b.** 26 **c.** 323.

29. Determine how many even integers between 2 and 20 can be the sum of two different prime numbers.

30. Twin primes are pairs of prime numbers that differ by 2. Except for the pair of primes 2 and 3, this is the smallest difference between two prime numbers. The first twin primes are 3 and 5, followed by 5 and 7, then 11 and 13. Identify other twin primes below 100.

3.6 Squares and square roots

LEARNING INTENTION


At the end of this subtopic you should be able to:

- determine values of squares and square roots
- estimate the value of the square root of other numbers by using the perfect squares that lie on either side of the number
- evaluate squares or square roots using BIDMAS.

3.6.1 Square numbers

eles-3733

- The process of multiplying a number by itself is known as **squaring a number**.
- **Square numbers** or **perfect squares** are numbers that can be arranged in a square, as shown.



$1^2 = 1 \times 1 = 1$ $2^2 = 2 \times 2 = 4$ $3^2 = 3 \times 3 = 9$ $4^2 = 4 \times 4 = 16$

- A square number is the number we get after multiplying a whole number by itself.
- The first four square numbers are: 1, 4, 9 and 16.
- All square numbers can be written in index notation, for example, $4^2 = 16$.


WORKED EXAMPLE 18 Determining square numbers

Determine the square numbers between 90 and 150.

THINK	WRITE
1. Use your knowledge of multiplication tables to determine the first square number after 90.	$10^2 = 10 \times 10 = 100$
2. Determine the square numbers that come after that one, but before 150.	$11^2 = 11 \times 11 = 121$ $12^2 = 12 \times 12 = 144$ $13^2 = 13 \times 13 = 169$ (too big)
3. Write the answer in a sentence.	The square numbers between 90 and 150 are 100, 121 and 144.

WORKED EXAMPLE 19 Determining approximate values of square numbers

Write the two whole square numbers between which 5.7^2 will lie.

THINK	WRITE
1. Write the whole numbers either side of 5.7.	5.7 is between 5 and 6.
2. Consider the square of each whole number.	5.7^2 is between 5^2 and 6^2.
3. Simplify 5^2 and 6^2, then write the answer in a sentence.	So 5.7^2 is between 25 and 36.
4. Verify your answer with a calculator.	$5.7^2 = 32.49$, which lies between 25 and 36.
5. To determine the value of 5.7^2 press 5 . 7 x^2 enter.	

We have confirmed that 5.7^2 lies between 25 and 36.

DISCUSSION

Can you predict whether the perfect square of a number will be odd or even? Give some examples.

- When a composite number is squared, the result is equal to the product of the squares of its factors.

For example: $10^2 = (2 \times 5)^2$
$= 2^2 \times 5^2$
$= 4 \times 25$
$= 100$

3.6.2 Square roots

eles-3734

- Evaluating the **square root** of a number is the opposite of squaring the number; for example, since $4^2 = 16$, then $\sqrt{16} = 4$.
- The symbol for square root is called the radical symbol. It is written as $\sqrt{\ }$.
- Using the illustrations of the squares shown earlier, a square of area 16 square units must have a side length of 4 units. This may help understand why $\sqrt{16} = 4$.

Square roots

When determining the square root of a number, you are determining the number that, when multiplied by itself, equals the number underneath the radical symbol.

For example, to determine $\sqrt{9}$, identify the number that when multiplied by itself gives 9.

Since $3 \times 3 = 9$, we can conclude that $\sqrt{9} = 3$.

- To determine the square roots of larger numbers, it helps to break the number up as a product of two smaller square roots with which we are more familiar. For example:

$$\begin{aligned}\sqrt{900} &= \sqrt{9} \times \sqrt{100} \\ &= 3 \times 10 \\ &= 30\end{aligned}$$

WORKED EXAMPLE 20 Determining square roots

Evaluate the following square roots.

a. $\sqrt{49}$ **b.** $\sqrt{3600}$


THINK	WRITE
a. Determine a number that when multiplied by itself gives 49.	**a.** $\sqrt{49} = 7$ $(7 \times 7 = 49)$
b. 1. Write 3600 as the product of two smaller numbers for which we can calculate the square root.	**b.** $\sqrt{3600} = \sqrt{36} \times \sqrt{100}$
2. Take the square root of each of these numbers.	$= 6 \times 10$
3. Determine the product and write the answer.	$\sqrt{3600} = 60$

- Only perfect squares have square roots that are whole numbers.
- The value of the square root of other numbers can be estimated by using the perfect squares that lie on either side of the number.

WORKED EXAMPLE 21 Estimating square roots

Between which two numbers do the following numbers lie?

a. $\sqrt{74}$ **b.** $\sqrt{342}$


THINK	WRITE
a. 1. Write the square numbers on either side of 74.	**a.** 74 is between 64 and 81.
2. Consider the square root of each number.	$\sqrt{74}$ is between $\sqrt{64}$ and $\sqrt{81}$.
3. Simplify $\sqrt{64}$ and $\sqrt{81}$.	So $\sqrt{74}$ is between 8 and 9.
4. Verify your answer with a calculator. To determine the value of $\sqrt{74}$ press 2nd x^2 7 4) enter.	$\sqrt{74} \approx 8.6023$  We have confirmed that $\sqrt{74}$ lies between 8 and 9.
b. 1. Write the square numbers on either side of 342.	**b.** 342 is between 324 (18^2) and 361 (19^2).
2. Consider the square root of each number.	$\sqrt{342}$ is between $\sqrt{324}$ and $\sqrt{361}$.

3. Simplify $\sqrt{324}$ and $\sqrt{361}$.

So $\sqrt{342}$ is between 18 and 19.

4. Verify your answer with a calculator.
To determine the value of $\sqrt{342}$ press
2nd x^2 3 4 2 } enter.

$\sqrt{342} \approx 18.4932$



We have confirmed that $\sqrt{342}$ lies between 18 and 19.

Order of operations

- The square or square root is an index represented by the letter I in BIDMAS, which determines the order in which operations are evaluated in a mathematical expression (see topic 2).

WORKED EXAMPLE 22 Evaluating square roots using the order of operations


Evaluate:
a. $\sqrt{16+9}$ **b.** $\sqrt{16}+9$

THINK	WRITE
a. 1. Simplify the expression inside the square root and write the answer.	**a.** $\sqrt{16+9} = \sqrt{25}$
2. Complete the calculation by evaluating the square root and write the answer.	$= 5$
b. 1. Evaluate the square root. *Note:* There is no expression inside the square root to evaluate first.	**b.** $\sqrt{16}+9 = 4+9$
2. Perform the addition to complete the calculation and write the answer.	$= 13$

COLLABORATIVE TASK: How many squares?

Work in pairs to answer the following question.


How many squares of any size can be found in the following diagram?




Hint: Count the number of single squares, count the number of 2×2 squares, then count the number of 3×3 squares. Look for a pattern in these numbers, and use the pattern to help you.

Digital technology

Scientific calculators can evaluate squares of decimal numbers.



Scientific calculators can evaluate square roots of decimal numbers.



on Resources

eWorkbook	Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)
Digital documents	SkillSHEET Finding the square of a number (doc-6427) SkillSHEET Finding the square root of a number (doc-6428)
Interactivities	Individual pathway interactivity: Squares and square roots (int-4321) Square numbers (int-3936) Square roots (int-3937)

Exercise 3.6 Squares and square roots

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 11, 13, 16, 19, 22	2, 5, 7, 9, 12, 17, 20, 23	3, 8, 10, 14, 15, 18, 21, 24, 25

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Evaluate the following and verify your answers with a calculator.
   a. 8^2 **b.** 11^2 **c.** 15^2 **d.** 25^2
2. **WE18** State the square numbers between 50 and 100.
3. State the square numbers between 160 and 200.
4. **WE19** Write two whole square numbers between which each of the following will lie.
   a. 6.4^2 **b.** 7.8^2 **c.** 9.2^2 **d.** 12.5^2
5. **WE20** Evaluate:
   a. $\sqrt{25}$ **b.** $\sqrt{81}$ **c.** $\sqrt{144}$ **d.** $\sqrt{400}$

6. Evaluate the following and verify your answers with a calculator.
   a. $\sqrt{4900}$ b. $\sqrt{14\,400}$ c. $\sqrt{360\,000}$ d. $\sqrt{160\,000}$

7. **WE21** Write the two whole numbers between which each of the following will lie.
   a. $\sqrt{60}$ b. $\sqrt{14}$ c. $\sqrt{200}$ d. $\sqrt{2}$

8. **WE22** Evaluate:
   a. $\sqrt{144+25}$ b. $\sqrt{144}+25$

9. State the even square numbers between 10 and 70.

10. State the odd square numbers between 50 and 120.

Understanding

11. **MC** For which of the following square roots can we calculate an exact answer?
   A. $\sqrt{10}$ B. $\sqrt{25}$ C. $\sqrt{50}$ D. $\sqrt{75}$ E. $\sqrt{82}$

12. **MC** For which of the following square roots can we not calculate the exact value?
   A. $\sqrt{160}$ B. $\sqrt{400}$ C. $\sqrt{900}$ D. $\sqrt{2500}$ E. $\sqrt{3600}$

13. Evaluate the following. Verify your answers with a calculator.
   a. $2^2+\sqrt{25}$ b. $9^2-\sqrt{36}$ c. $5^2\times2^2\times\sqrt{49}$ d. $3^2+2^2\times\sqrt{16}$

14. Evaluate the following. Verify your answers with a calculator.
   a. $3^2-2^2\div\sqrt{4}+\sqrt{49}$ b. $\sqrt{9}\times4^2-\sqrt{144}\div2^2$

15. a. Determine between which two whole numbers $\sqrt{150}$ will lie.
   b. Use your answer to part **a** to estimate the value of $\sqrt{150}$ and check your answer with a calculator.

Reasoning

16. a. Evaluate 15^2.
   b. Evaluate $3^2\times5^2$.
   c. Are your answers to parts **a** and **b** equal? Explain why or why not.

17. a. Evaluate $\sqrt{225}$.
   b. Evaluate $\sqrt{25}\times\sqrt{9}$.
   c. Are your answers to parts **a** and **b** equal? Explain why or why not.

18. a. Express 196 as a product of its prime factors.
   b. Express 200 as a product of its prime factors.
   c. Use the answers to parts **a** and **b** to explain how you can use prime factors to determine whether the square root of a number is an integer.

19. a. Evaluate $\sqrt{36}+\sqrt{64}$.
   b. Evaluate $\sqrt{36+64}$.
   c. Are your answers to parts **a** and **b** equal? Explain why or why not.

20. a. Evaluate $\sqrt{25}+\sqrt{144}$.
   b. Evaluate $\sqrt{169}$.
   c. $169=25+144$. Does $\sqrt{169}=\sqrt{25}+\sqrt{144}$? Explain your answer.

21. Megan has 3 different game scores that happen to be square numbers. The first 2 scores have the same three digits. The total of the 3 scores is 590.
   Determine the 3 scores. Explain how you solved this question.

Problem solving

22. **a.** Evaluate each of the following using a calculator.
i. $25^2 - 24^2$ **ii.** $24^2 - 23^2$ **iii.** $23^2 - 22^2$ **iv.** $22^2 - 21^2$ **v.** $21^2 - 20^2$
b. Comment on any pattern in your answers.
c. Discuss whether this pattern occurs with other numbers that are squared. Try some examples.

23. Guess the number that matches the following:
It is odd and it has an odd number of factors.
The sum of the digits is a two-digit prime.
The number is less than $\sqrt{10\,000}$ but greater than $\sqrt{100}$.

24. Rewrite the following in ascending order.
a. 8^2, $\sqrt{56}$, 62, $\sqrt{72}$, 8, 7, 3^2, $\sqrt{100}$ **b.** 100, $\sqrt{121}$, $\sqrt{10}$, 3×4, 9^2, $\sqrt{169}$, 2×7

25. The sum of two numbers is 20 and the difference between their squares is 40. Determine the two numbers.

3.7 Divisibility tests

LEARNING INTENTION

At the end of this subtopic you should be able to:
- test for factors of a given number using divisibility tests.

3.7.1 Tests of divisibility

eles-3736

- Divisible means that one number divided by another gives a result that is a whole number.
- **Divisibility tests** are a quick way of testing for factors of a given number.
- These tests save time compared with dividing by each possible factor to determine whether the number is divisible by the chosen divisor.
- All positive integers are divisible by 1.

Divisibility by 2	Divisibility by 3	Divisibility by 4	Divisibility by 5
The last digit is 0, 2, 4, 6 or 8. e.g. 324 ÷ 2, since the last digit is 4. 24, 74, 108, 324	The sum of the digits can be divided by 3. e.g. 615 ÷ 3, since the sum of the digits is 12 (6 + 1 + 5) and 12 is divisible by 3. 12, 72, 234, 615	The last two digits together (as a 2-digit number) can be divided by 4. e.g. 532 ÷ 4, since the last two digits are 32, and 32 is divisible by 4. 84, 184, 324, 532	The last digit is either 0 or 5. e.g. 135 ÷ 5, since the last digit is 5. 25, 135, 640, 1870

Divisibility by 6	Divisibility by 8	Divisibility by 9	Divisibility by 10
The number can be divided by 2 and also divided by 3. e.g. 420 ÷ 6, since the last digit is 0 (0 ÷ 2), and the sum of the digits is 6 (4 + 2 + 0) and 6 is divisible by 3. 36, 144, 258, 420	The last three digits can be divided by 8. e.g. 1816 ÷ 8, since the last three digits are 816, and 816 is divisible by 8. 96, 208, 1816, 5232	The sum of the digits can be divided by 9. e.g. 756 ÷ 9, since the sum of the digits is 18 (7 + 5 + 6), and 18 is divisible by 9. 81, 198, 414, 756	The last digit is 0. e.g. 770 ÷ 10, since the last digit is 0. 80, 350, 600, 770

WORKED EXAMPLE 23 Applying divisibility tests

Determine whether the results of the following divisions are whole numbers.

a. $3454 \div 2$ **b.** $6381 \div 9$

THINK	WRITE
a. 1. To be divisible by 2, the last digit must be 0, 2, 4, 6 or 8.	**a.** In the number 3454, the last digit is 4.
2. Write the answer in a sentence.	Therefore, 3454 is divisible by 2.
b. 1. To be divisible by 9, the sum of all the digits must by divisible by 9.	**b.** The sum of all the digits: $6 + 3 + 8 + 1 = 18$ 18 is divisible by 9.
2. Write the answer in a sentence.	Therefore, 6381 is divisible by 9.

WORKED EXAMPLE 24 Checking divisibility

Check the divisibility of the following numbers.

a. $816 \div 4$ **b.** $7634 \div 6$

THINK	WRITE
a. 1. To be divisible by 4, the last two digits together must be divisible by 4.	**a.** In the number 816, the last two digits are 16. 16 is divisible by 4.
2. Write the answer in a sentence.	Therefore, 816 is divisible by 4.
b. 1. To be divisible by 6, the number must be divisible by 2 and also by 3.	
2. To be divisible by 2, the last digit must be 0, 2, 4, 6 or 8.	**b.** In the number 7634, the last digit is 4. Therefore, 7634 is divisible by 2.
3. To be divisible by 3, the sum of all the digits must be divisible by 3.	In the number 7634, the sum of all the digits: $7 + 6 + 3 + 4 = 20$ 20 is **not** divisible by 3.
4. Write the answer in a sentence.	The number 7634 is divisible by 2 but not divisible by 3. Therefore, 7634 is not divisible by 6.

on Resources

eWorkbook Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)

Interactivity Individual pathway interactivity: Divisibility tests (int-8342)

Exercise 3.7 Divisibility tests

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 8, 11, 14	2, 5, 9, 12, 15	3, 7, 10, 13, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. State the divisibility tests for 2, 4 and 6 with an example for each.
2. State the divisibility tests for 3, 5 and 9 with an example for each.
3. State how the divisibility tests for 3 and 9 are similar.
4. WE23 Determine whether or not the results of the following divisions are whole numbers.
   a. $54 \div 2$ b. $150 \div 9$ c. $295 \div 5$ d. $1293 \div 3$
5. WE24 Check the divisibility of the following.
   a. $1816 \div 4$ b. $2638 \div 6$ c. $62\,873 \div 9$ d. $876 \div 8$

Understanding

6. State the factors (from 1 to 10) of the following numbers.
   a. 144 b. 264 c. 1456 d. 567 844
7. Use the divisibility rules to determine the factors (from 1 to 10) of the following numbers.
   a. 760 b. 535 c. 3457 d. 234 568
8. Apply the divisibility rules to determine the factors (from 1 to 10) of the following numbers.
   a. 76 b. 30 c. 458 d. 227
9. Without using a calculator, use divisibility tests to determine whether the following are True or False.
   a. 2 is a factor of 65
   b. 3 is a factor of 96
   c. 4 is a factor of 22
   d. 5 is a factor of 44
   e. 6 is a factor of 72
   f. 10 is a factor of 85
10. a. Use the tests of divisibility to determine whether the following numbers are divisible by 2, 3, 4, 5, 6 or 10.
    i. 415 ii. 600 iii. 935
    iv. 1010 v. 4321 vi. 55 112
    b. Use a calculator to check your answers to part a.

Reasoning

11. WE24b Jack says that 34 281 is divisible by 6, but Julie says that Jack is incorrect. Explain whether you agree with Jack or Julie, and why.
12. If a number is divisible by 9, determine another factor (2, 3, 4, 5, 6, 7, 8, or 10) for that number.
13. 6 is a factor of 4572 and 2868. Is 6 a factor of $4572 + 2868$ and $4572 - 2868$? Show full working to justify your answer.

Problem solving

14. Determine the missing digit to create the number.

a. Divisible by 3 : _____316
b. Divisible by 6 : 9_____32
c. Divisible by 8 : 59_____16
d. Divisible by 9 : 1543_____

15. Determine 2 two-digit numbers that are divisible by 4, 5 and 8.

16. A number between 550 and 560 is divisible by 6 and 4. Determine the number.

3.8 Cubes and cube roots


LEARNING INTENTION

At the end of this subtopic you should be able to:
- determine values of cubes and cube roots
- evaluate cubes or cube roots using BIDMAS.

3.8.1 Cube numbers

eles-3737

- **Cube numbers** are numbers that can be arranged in a cube, as shown.



$1^3 = 1 \times 1 \times 1$
$= 1$

$2^3 = 2 \times 2 \times 2$
$= 8$

$3^3 = 3 \times 3 \times 3$
$= 27$

- The first cube number, 1, equals $1 \times 1 \times 1$.
- The second cube number, 8, equals $2 \times 2 \times 2$.
- The third cube number, 27, equals $3 \times 3 \times 3$.
- Each new perfect cube is found by multiplying a number by itself three times.
  This is known as *cubing a number* and is written using an index (or power) of 3. For example,
  $4^3 = 4 \times 4 \times 4 = 64$.

WORKED EXAMPLE 25 Calculating the value of a cube

Calculate the value of 5^3.

THINK	WRITE
1. Write 5^3 as the product of three lots of 5.	$5^3 = 5 \times 5 \times 5$
2. Evaluate and write the answer.	$= 125$

Order of operations

- When working with squares and cubes, remember to evaluate the index as part of the I in BIDMAS.

WORKED EXAMPLE 26 Calculating cubes using the order of operations

Calculate the value of $3^3 + 4 \times 5^2$.

THINK	WRITE
1. According to the order of operations (BIDMAS), first simplify both the cubed and the square terms.	$3^3 + 4 \times 5^2 = (3 \times 3 \times 3) + 4 \times (5 \times 5)$ $= 27 + 4 \times 25$
2. Then complete the multiplication.	$= 27 + 100$
3. Write the answer.	$= 127$

3.8.2 Cube roots

eles-3738

- Evaluating the **cube root** of a number is the opposite of cubing a number.
- The cube root symbol is similar to the square root symbol but with a small 3 written in front, and is written as $\sqrt[3]{\ }$.
  For example, since $2^3 = 8$, then $\sqrt[3]{8} = 2$.
- Using the illustrations of the cubes in section 3.8.1, a cube of 8 cubic units has a side length of 2 units.

WORKED EXAMPLE 27 Calculating cube roots

Calculate $\sqrt[3]{27}$.

THINK	WRITE
Look for a number that when multiplied by itself three times gives 27, and write the answer.	$27 = 3 \times 3 \times 3$ $\sqrt[3]{27} = 3$

WORKED EXAMPLE 28 Calculating cube roots using the order of operations

Calculate:

a. $\sqrt[3]{64 + 61}$ **b.** $\sqrt[3]{64} + 61$.

THINK	WRITE
a. 1. First simplify the expression inside the cube root.	a. $\sqrt[3]{64 + 61} = \sqrt[3]{125}$
2. To complete the calculation, evaluate the cube root by identifying the number that when multiplied by itself three times gives 125, and write the answer.	$= 5$

b. 1. Evaluate the cube root first. (Identify the number that when multiplied by itself three times gives 64.)


b. $\sqrt[3]{64} + 61 = 4 + 61$

2. Perform the addition to complete the calculation, and write the answer.


$= 65$

Digital technology

Scientific calculators can evaluate cubes of decimal numbers.



Scientific calculators can evaluate cube roots of decimal numbers.



on Resources

eWorkbook	Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)
Digital documents	SkillSHEET Finding the cube of a number (doc-6429) SkillSHEET Finding the cube root of a number (doc-6430)
Interactivities	Individual pathway interactivity: Cubes and cube roots (int-4322) Cube numbers (int-3959) Cube roots (int-3960)

Exercise 3.8 Cubes and cube roots

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 12, 15	2, 5, 13, 16	3, 6, 8, 9, 11, 14, 17

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE25 Evaluate:

a. 4^3 **b.** 2^3 **c.** 3^3

2. Evaluate:

a. 6^3 **b.** 10^3

3. Write the first eight cube numbers.

4. **WE26** Evaluate $3^2 + 4^3 \times 2$.

5. Evaluate the following.
   a. $10^3 - 5^2 \times 2^3$ b. $4^3 - 3^3 - 2^3$

6. **WE27** Evaluate:
   a. $\sqrt[3]{8}$ b. $\sqrt[3]{64}$

Understanding

7. Evaluate each of the following. Verify your answers with a calculator.
   a. $\sqrt[3]{216}$ b. $\sqrt[3]{343}$
   (*Hint:* Use your answer to question 3.)

8. **WE28** Determine the value of:
   a. $\sqrt[3]{125 + 91}$ b. $\sqrt[3]{125} + 91$

9. Evaluate each of the following:
   a. $\sqrt[3]{343 + 169}$ b. $\sqrt[3]{343} + \sqrt{169}$

10. a. Determine between which two whole numbers $\sqrt[3]{50}$ will lie.
    b. Use your answer to part a to estimate the value of $\sqrt[3]{50}$ and check your answer with a calculator.

11. a. Determine between which two whole numbers $\sqrt[3]{90}$ will lie.
    b. Use your answer to part a to estimate the value of $\sqrt[3]{90}$ and check your answer with a calculator.

Reasoning

12. Determine the first four numbers that could be arranged as a triangle-based pyramid (where all triangles are equilateral).

13. a. Express 216 as a product of its prime factors.
    b. Express 135 as a product of its prime factors.
    c. Use the answers to parts a and b to explain how you can use prime factors to determine whether the cube root of a number is an integer.

14. The first five square numbers are $1, 4, 9, 16, 25$. If we find the difference between these numbers, we get $4 - 1 = 3$, $9 - 4 = 5$, $16 - 9 = 7$ and $25 - 16 = 9$.
    These numbers all differ by 2. Representing this in a table, we get:

Square numbers	1	4	9	16	25
First difference	3	5	7	9	
Second difference	2	2	2		

    Repeat this process for the first six cube numbers. Explain how many times you needed to determine the difference until they were equal.
    If you look at $1^4, 2^4, 3^4, 4^4, \ldots$, explain how many differences you would need to find until they are equal.

Problem solving

15. Dave said that $a^3 = \sqrt[a]{a}$ is a true statement for all numbers. Show your working to prove or disprove this statement.

16. Jack was organising a get-together of all his football mates from the last three years. He decided to phone 4 footballer mates and ask them to phone 4 footballers each, who in turn would phone 4 more footballers.
Each team member was given a list of 4 names so that no-one received more than one call.



a. Calculate how many footballers would receive a phone call about the party.

b. Jack's friend Karin liked the idea, so she decided to contact 258 people about a 10-year reunion using Jack's method.
Assuming there were three rounds of calls, calculate how many people each person should call.

17. It's an interesting fact that the sum of the digits of a cube of an integer, when reduced to a single digit, can only be $1, 8$ or 9.
For example:

$$12^3 = 1728$$
$$1 + 7 + 2 + 8 = 18$$
$$1 + 8 = 9$$

There is a pattern in the sequence of these numbers.

a. Use this rule with the cubes of the first 10 integers.

b. Determine the single-digit sum of 35^3.

c. Explain your answer.

3.9 Review

3.9.1 Topic summary

Multiples

- A multiple of a number is the result of multiplying that number by another whole number.
- The times table gives lists of multiples.

e.g.
Multiples of 4 are: 4, 8, 12, 16, 20, …
Multiples of 6 are: 6, 12, 18, 24, 30, …

LCM and HCF

- The lowest common multiple (LCM) is the smallest multiple that is common to two or more numbers.
  e.g.
  Consider the numbers 8 and 12.
  Multiples of 8: 8, 16, **24**, 32, …
  Multiples of 12: 12, **24**, 36, 48, …
  LCM(8,12) = 24
- The highest common factor (HCF) is the largest number that is a factor of both numbers.
  e.g.
  Factors of 8: 1, 2, **4**, 8
  Factors of 12: 1, 2, 3, **4**, 6, 12
  HCF(8,12) = 4

Factors

- A factor of a whole number divides that number exactly.
- Factors are also numbers that multiply together to get another number.

e.g.
Since $20 = 4 \times 5$, or 2×10, or 1×20, then the factors of 20 are 1, 2, 4, 5, 10 and 20.



FACTORS, MULTIPLES, INDICES AND PRIMES

Index notation

- Index notation is a short way of writing a repeated multiplication.
  e.g. $2 \times 2 \times 2 \times 2 \times 2 \times 2$ can be written as 2^6, which is read as '2 to the power of 6'.
- The base is the number that is being repeatedly multiplied, and the index is the number of times it is multiplied.
  $2^6 = 2 \times 2 \times 2 \times 2 \times 2 \times 2 = 64$

Divisibility tests

Divisibility tests determine whether or not the number is divisible by the chosen divisor.
2: last digit is 0, 2, 4, 6 or 8
3: sum of the digits is divisible by 3
4: last 2 digits together are divisible by 4
5: last digit is either 0 or 5
6: divisible by 2 and divisible by 3
8: last 3 digits together are divisible by 8
9: sum of the digits is divisible by 9
10: last digit is 0

Squares

- The process of multiplying a number by itself is known as squaring a number.
  e.g.
  $1 \times 1 = 1^2 = 1$
  $2 \times 2 = 2^2 = 4$
- A square number is the number we get after multiplying a whole number by itself.
- The first four square numbers are 1, 4, 9 and 16.

Cubes

- A cube number is found by multiplying a number by itself three times.
  e.g.
  $1 \times 1 \times 1 = 1^3 = 1$
  $2 \times 2 \times 2 = 2^3 = 8$
  $3 \times 3 \times 3 = 3^3 = 27$
- The first four cube numbers are 1, 8, 27 and 64.

Prime and composite numbers

- A *prime* number has exactly two unique factors: 1 and itself.
- The first six prime numbers are 2, 3, 5, 7, 11 and 13.
- A *composite* number has more than two unique factors.
- Some examples of composite numbers are 4, 6, 8, 9 and 10.

Square roots

- The radical or square root symbol is $\sqrt{}$.
- The square root of a number is the opposite of squaring the number.
  e.g. If $4^2 = 16$ then $\sqrt{16} = 4$.

Cube roots

- The cube root symbol is $\sqrt[3]{}$.
- The cube root of a number is the opposite of cubing the number.
  e.g. If $5^3 = 125$ then $\sqrt[3]{125} = 5$.

One — a special number

The number 1 has only one unique factor: itself. It is neither prime nor composite but a special number.

3.9.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
3.2	I can list multiples and factors of a whole number.			
	I can determine multiples and factor pairs.			
3.3	I can determine the lowest common multiple and the highest common factor of two or more whole numbers.			
3.4	I understand that index or exponent notation is a short way of writing a repeated multiplication.			
	I can write expressions in index notation.			
	I can simplify expressions using index notation.			
	I can use place value to write and evaluate numbers in expanded form with index notation.			
3.5	I understand the difference between prime and composite numbers.			
	I can determine prime factors by drawing a factor tree.			
	I can write a composite number in index form.			
	I can determine the highest common factor (HCF) and lowest common multiple (LCM) of large numbers as products of their prime factors.			
3.6	I can determine values of squares and square roots.			
	I can estimate the value of the square root of other numbers by using the perfect squares that lie on either side of the number.			
	I can evaluate squares or square roots using BIDMAS.			
3.7	I can test for factors of a given number using divisibility tests.			
3.8	I can determine values of cubes and cube roots.			
	I can evaluate cubes or cube roots using BIDMAS.			

3.9.3 Project

Alphabet sizes

Bob's business, Reading Resources, produces individual letters of the alphabet printed on cardboard. He caters for the market of visually impaired students who are learning to read.




Teachers use the cards to form words for students to read. Because the students have varying difficulties with their sight, the letters are printed in heights of 1 cm, 2 cm, 3 cm, …, 10 cm. Bob has a set of all the letters at 1 cm and uses these as the basis for forming the larger letters.

Bob's factory has 10 machines. Each machine performs only one specific job, as indicated:

- Machine 1 makes letters 1 cm high.
- Machine 2 enlarges the letters so they are twice as high.
- Machine 3 enlarges the letters so they are 3 times as high.
- Machine 4 enlarges the letters so they are 4 times as high.
- Machine 10 enlarges the letters so they are 10 times as high.

Bob's business is thriving and he relies heavily on all his machines working. This morning he arrived to process a large order of letters that need to be 6 cm high, only to find that machine 6 was not working. He gathered his staff together to discuss the problem.



'No problem!' said Ken. 'As long as the other machines are working we can still get this order done.'

1. Suggest a solution that Ken might have proposed.
2. If Bob can do without machine 6, are there others he can also do without?
3. What is the minimum number of machines that Bob needs to make letters up to 10 cm high?

As Bob's business has become more successful, there has been a demand for letters of a greater height.

4. For Bob to make letters of every whole number up to a height of 20 cm, would he need twice as many machines as he currently has? Explain.
5. Having become very excited about needing fewer machines than he first thought, Bob considered expanding his business to make advertising signs using letters of all whole number heights up to 100 cm. To succeed in this new market, what is the minimum number of machines he would need?
6. Explain why it is necessary to have some specific machine numbers, while some others are not necessary.

Resources

eWorkbook Topic 3 Workbook (worksheets, code puzzle and project) (ewbk-1904)

Interactivities Crossword (int-2588)
Sudoku puzzle (int-3164)

Exercise 3.9 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. List the first 5 multiples of each number.
a. 11 **b.** 100 **c.** 5 **d.** 20 **e.** 35

2. Calculate the lowest common multiple (LCM) of the following pairs of numbers.
a. 3 and 12 **b.** 6 and 15 **c.** 4 and 7 **d.** 5 and 8

3. List all the factors of each of the following numbers.
a. 27 **b.** 50

4. List all the factors of each of the following numbers.
a. 16 **b.** 42 **c.** 72

5. List the factor pairs of the following numbers.
a. 24 **b.** 40 **c.** 48 **d.** 21 **e.** 99 **f.** 100

6. Evaluate:
a. 6^2 **b.** 14^2 **c.** 19^2 **d.** 80^2

7. Write the two whole square numbers between which each of the following will lie.
a. 3.8^2 **b.** 5.1^2 **c.** 10.6^2 **d.** 15.2^2

8. Evaluate:
a. $\sqrt{49}$ **b.** $\sqrt{256}$ **c.** $\sqrt{900}$ **d.** $\sqrt{1369}$

9. Calculate:
a. 4^3 **b.** 7^3 **c.** 15^3 **d.** 30^3

10. Evaluate each of the following.
a. $\sqrt[3]{27}$ **b.** $\sqrt[3]{125}$ **c.** $\sqrt[3]{1000}$ **d.** $\sqrt[3]{8000}$

11. Write the following using index notation.
a. $2 \times 3 \times 3 \times 3$
b. $5 \times 5 \times 6 \times 6 \times 6 \times 6$
c. $2 \times 5 \times 5 \times 5 \times 9 \times 9 \times 9$

12. Use your calculator to evaluate:
a. 3^5 **b.** 7^3 **c.** 8^4 **d.** 11^5

13. List all of the prime numbers less than 30.

14. List all of the single-digit prime numbers.

15. State the prime number that comes next after 50.

16. State the prime factors of:
a. 99 **b.** 63 **c.** 125 **d.** 124.

17. Express the following numbers as products of their prime factors, in index form.
a. 280 **b.** 144

18. Write the following numbers in expanded form using index notation.
a. 1344 **b.** 30 601

19. Determine the highest common factor and lowest common multiple of 120 and 384 by first expressing each number as a product of its prime numbers.

20. Determine the highest common factor and lowest common multiple of 72 and 224 by first expressing each number as a product of its prime numbers.

Problem solving

21. Hung and Frank are cyclists who are riding around a track. They ride past the finish line together, and from that point Hung takes 25 seconds to complete a lap and Frank takes 40 seconds.
a. Calculate how long it will be until they next pass the finish line together.
b. Determine how many laps each will have ridden when this occurs.



22. Joe, Claire and Daniela were racing up and down a flight of stairs. Joe took the stairs three at a time, Daniela took the stairs two at a time, while Claire took the stairs four at a time. In each case, they reached the bottom with no steps left over.
a. Calculate how many steps are in the flight of stairs. List three possible answers.
b. Determine the smallest number of steps there could be.
c. If Joe can also take the stairs five at a time with no steps left over, determine the smallest number of steps in the flight of stairs.

23. A perfect number is one whose factors (all except the number itself) add up to the number. For example, 6 is a perfect number because $1 + 2 + 3$ (the sum of its factors, excluding 6) is equal to 6. Show why 496 is a perfect number.

24. In a race, one dirt bike rider completes each lap in 40 seconds while another completes a lap in 60 seconds. Determine how long after the start of the race the two bikes will pass the starting point together.



25. A three-digit number is divisible by 6. The middle digit is a prime number. The sum of the digits is 9. The number is between 400 and 500. The digits are in descending order. Determine the number.

26. Explain why we cannot determine the exact value of $\sqrt{20}$.

27. Write the following numbers in the order of size, starting with the smallest.

$$5, \sqrt{64}, 2, \sqrt[3]{27}$$

28. Calculate the smallest possible number which, when multiplied by 120, will give a result that is a square number. Now calculate the smallest possible number that will give a result that is a cube number.

29. List the prime numbers up to 100. Some prime numbers are separated by a difference of 2 or 6. (For example, $5 - 3 = 2$ and $19 - 17 = 2$.)

a. Calculate the prime number pairs up to 100 that have a difference of 2.

b. Calculate the prime number pairs up to 100 that have a difference of 6.

c. Explain why there are no prime number pairs with a difference of 7.

30. Determine the smallest number that is both a square number and a cube number. Identify the next smallest number.

31. Complete the following sequence: $2, 3, 5, 7, 11, 13,$ ___, ___, ___.

32. Write each of the numbers 250, 375 and 625 as a product of its prime factors and:

a. determine the highest common *prime* factor

b. determine the HCF.

33. A motor boat requires an engine service every 5000 nautical miles, refuelling every 300 nautical miles and an oil change after 2250 nautical miles. Determine how many nautical miles the motor boat will have travelled before all three services are required simultaneously.



34. By folding a sheet of paper in half, you divide it into 2 regions.

a. If you fold it in half again, determine how many regions there are.

b. Set up a table similar to the one shown and fill it in.

c. Explain how the number of regions increases with each new fold.

d. Write a formula for the number of regions (R) for n folds.

n (number of folds)	R (number of regions made)
0	1
1	2
2	4
3	
4	
5	
6	

35. Look at the following table. As you read down each column, you'll notice that the equations follow a pattern. Continue the patterns to complete the table.

$2^5 = 32$	$3^5 = 243$
$2^4 = 16$	$3^4 = 81$
$2^3 = 8$	$3^? = 27$
$2^2 =$	$3^2 =$
$2^1 =$	$3^1 =$
$2^0 =$	$3^0 =$
$2^{-1} =$	$3^{-1} =$

a. State what 5^0 equals.

b. State what 2^{-2} is equal to.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1904) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0692) ☐

Digital documents

3.2 SkillSHEET Multiples (doc-6416) ☐
SkillSHEET Factor pairs (doc-6417) ☐
3.6 SkillSHEET Finding the square of a number (doc-6427) ☐
SkillSHEET Finding the square root of a number (doc-6428) ☐
3.8 SkillSHEET Finding the cube of a number (doc-6429) ☐
SkillSHEET Finding the cube root of a number (doc-6430) ☐

Video eLessons

3.2 Multiples (eles-3725) ☐
Factors (eles-3726) ☐
Factors and multiples (eles-2310) ☐
3.3 The LCM and HCF (eles-3727) ☐
3.4 Introduction to indices (eles-3728) ☐
Indices and place values (eles-3729) ☐
3.5 Prime numbers (eles-3730) ☐
Composite numbers and factor trees (eles-3731) ☐
Lowest common multiple and highest common factor using prime factors (eles-3732) ☐
3.6 Square numbers (eles-3733) ☐
Square roots (eles-3734) ☐
3.7 Tests of divisibility (eles-3736) ☐
3.6 Cube numbers (eles-3737) ☐
Cube roots (eles-3738) ☐

Interactivities

3.2 Individual pathway interactivity: Factors and multiples (int-4316) ☐
Multiples (int-3929) ☐
Factors (int-3930) ☐
3.3 Individual pathway interactivity: Lowest common multiple and highest common factor (int-4317) ☐
Lowest common multiple (int-3931) ☐
Highest common factor (int-4545) ☐
3.4 Individual pathway interactivity: Index notation (int-4319) ☐
Index notation (int-3957) ☐
3.5 Individual pathway interactivity: Prime numbers and composite numbers (int-4320) ☐
Prime numbers (int-3933) ☐
Composite numbers and factor trees (int-3934) ☐
3.6 Individual pathway interactivity: Squares and square roots (int-4321) ☐
Square numbers (int-3936) ☐
Square roots (int-3937) ☐
3.7 Individual pathway interactivity: Divisibility tests (int-8342) ☐
3.8 Individual pathway interactivity: Cubes and cube roots (int-4322) ☐
Cube numbers (int-3959) ☐
Cube roots (int-3960) ☐
3.9 Crossword (int-2588) ☐
Sudoku puzzle (int-3164) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.


Answers

Topic 3 Factors, multiples, indices and primes

Exercise 3.1 Pre-test

1. B
2. $35
3. 6
4. 12 minutes
5. $5^2 \times 3^4$
6. 17, 31, 109
7. C, E
8. B, E
9. LCM = 864; HCF = 6
10. 64
11. 109
12. 8 and 9
13. 3
14. 39
15. 7

Exercise 3.2 Factors and multiples

1. a. 3, 6, 9, 12, 15 b. 6, 12, 18, 24, 30
   c. 100, 200, 300, 400, 500 d. 11, 22, 33, 44, 55
2. a. 120, 240, 360, 480, 600 b. 45, 90, 135, 180, 225
   c. 72, 144, 216, 288, 360 d. 33, 66, 99, 132, 165
3. 10, 20, 100, 70
4. 21, 7, 70, 35
5. 16, 64, 160, 32, 80
6. 9, 18, 27, 36, 45, 54, 63, 72, 81, 90, 99
7. 102, 108, 114, 120, 126, 132, 138, 144, 150, 156
8. C
9. A
10. a. 1, 2, 3, 4, 6, 12 b. 1, 2, 4, 5, 8, 10, 20, 40
11. a. 1, 2, 7
    b. 1, 2, 3, 5, 10, 15, 20
    c. 1, 2, 5, 10, 20, 25
12. a. 1, 2, 3, 4, 6, 8, 9, 12, 18, 24, 36, 72
    b. 1, 2, 5, 10, 25, 50, 125, 250
13. a. 1, 5, 17 b. 1, 3, 9, 11, 33 c. 1, 3, 17
14. 1, 20; 2, 10; 4, 5
15. 1, 132; 2, 66; 3, 44; 4, 33; 6, 22; 11, 12
16. B, C, E
17. 15
18. B
19. A
20. 3, 4
21. a. 6, 12, 18 (or any other multiple of 6)
    b. 6
    c. 30
22. 

23. 4 rows of 5 students or 5 rows of 4 students; 2 rows of 10 students or 10 rows of 2 students; 1 row of 20 students or 20 rows of 1 student
24. 3, 12 or 30
25. Boy 6, grandfather 66
26. 84
27. 60
28. 60

Exercise 3.3 Lowest common multiple and highest common factor

1. a. 4, 8, 12, 16, 20, 24, 28, 32, 36, 40
   b. 6, 12, 18, 24, 30, 36, 42, 48, 54, 60
   c. 12, 24, 36
   d. 12
2. a. 9 b. 30 c. 70 d. 48 e. 60
3. False
4. True
5. True
6. False
7. a. HCF = 7 b. HCF = 7 c. HCF = 6
8. a. 9 b. 7
9. a. 4 b. 9
10. a. 6 days
    b. 6 is the lowest common multiple of 2 and 3.
11. a. 35 minutes
    b. 35 is the lowest common multiple of 5 and 7.
12. a. 12 hours
    b. 12 is the lowest common multiple of 4 and 6.
13. 20 seconds
14. a. 12 b. 6 c. 7
15. a. 3 metres b. 10
16. 2 hours
17. a. Daniella b. 10 minutes
18. 6 times
19. a. 4 minutes and any multiple of 4 thereafter
    b. 3 minutes and any multiple of 3 thereafter
20. 30 minutes
21. a. Two semicircles
    b. The starting line for a 100 m race has been positioned in the extended section so the athletes can all start from the same starting line.
    c. The finish line for a 100 m race has been positioned so that all athletes can run in a direct line without having to have staggered starting positions.
    d. There is a need to stagger the starting blocks in the 200 m, 400 m and 800 m track events so that the outside runners will not be running further than the inside runners.

e. and **f.**

Lane number	Distance travelled	Difference
1	400 m	0
2	408 m	8
3	416 m	16
4	424 m	24
5	432 m	32
6	440 m	40
7	448 m	48
8	456 m	56

g. The runner in lane 8 is running 56 metres further than the runner in lane 1.

Exercise 3.4 Index notation

1. a. $7^2 = 49$ Base is 7 and index is 2.
b. $4^5 = 4096$ Base is 4 and index is 5.
c. $3^4 = 81$ Base is 3 and index is 4.
d. $10^3 = 1000$ Base is 10 and index is 3.

2. a. 7^4 **b.** 8^6 **c.** 3^9 **d.** 13^3

3. a. $4^5 \times 6^3$ **b.** $2^2 \times 3$
c. $2^4 \times 5^2$ **d.** $2^2 \times 3^2 \times 5^3$

4. a. $6 \times 6 \times 6 \times 6 \times 6$ **b.** $11 \times 11 \times 11$

5. a. 5^{11} **b.** 4^{13} **c.** 2^{21}

6. a. $300 = 3 \times 10^2$
b. $4500 = 4 \times 10^3 + 5 \times 10^2$
c. $6705 = 6 \times 10^3 + 7 \times 10^2 + 0 \times 10^1 + 5$
d. $10\,000 = 1 \times 10^4$

7. a. 9^{15} **b.** $3^6 \times 13^6$

8. D

9. a. 343 **b.** 288 **c.** 77

10. a. 72 **b.** 5184 **c.** 177 147

11. a. 567 **b.** 2717 **c.** 112

12. a. A
b. At first the base number 2 would appear to be the smallest, but it has the highest power. Although the other numbers have a higher base, they have relatively small powers — therefore 2^8 will be the largest number. This can easily be verified by evaluating each number.

13. $41^2 \neq 691$. Notice that $31^2 = 961$, therefore 41^2 will need to be larger than 961.

14. a. $<$ **b.** $<$ **c.** $<$ **d.** $>$

15. a. Option 1: \$327.68; Option 2 : \$120 after the 15 weeks
b. Option 1: 2^{15} cents after week 15

16. 64

17. a. $8^3 = 512$ **b.** 584

18. 127

19. a. $2^{12} = 4096$
b. $3^{12} = 531\,441$
c. Using powers is a quick way of getting answers that are really large.

20. 256

21. Square the first number and add one to calculate the second number. Square the second number and add one to calculate the third number. The missing number is 101.


Exercise 3.5 Prime numbers and composite numbers

1. 23, 29, 31, 37


2. a. Composite **b.** Prime
c. Composite **d.** Prime

3. a. Composite **b.** Prime
c. Composite **d.** Prime


4. a. i. 3, 5 **ii.** $15 = 3 \times 5$




b. i. 2, 3, 5 **ii.** $30 = 2 \times 3 \times 5$




c. i. 2, 5 **ii.** $100 = 2^2 \times 5^2$




d. i. 7 **ii.** $49 = 7^2$




5. a. i. 2, 3 **ii.** $72 = 2^3 \times 3^2$




b. i. 2, 7 **ii.** $56 = 2^3 \times 7$




c. i. 3, 5 **ii.** $45 = 3^2 \times 5$




6. a. i. 2, 3, 7 **ii.** $84 = 2^2 \times 3 \times 7$




b. i. 


2, 7 **ii.** $112 = 2^4 \times 7$

c. i. 


2, 5 **ii.** $40 = 2^3 \times 5$

7. a. i. 

2, 3 **ii.** $96 = 2^5 \times 3$

b. i. 

2 **ii.** $32 = 2^5$

c. i. 

2, 3, 5 **ii.** $3000 = 2^3 \times 3 \times 5^3$

8. a. 2, 3 **b.** 2, 5 **c.** 3 **d.** 2, 3

9. a. 2, 3, 5 **b.** 2, 3, 5 **c.** 2, 3, 5 **d.** 2, 5

10. a. $2^2 \times 3 \times 5$ **b.** 3×5^2 **c.** $2^2 \times 5 \times 11$

11. a. $2^6 \times 3$ **b.** $2^2 \times 31$

12. a. LCM is 252; HCF is 12.
b. LCM is 240; HCF is 12.
c. LCM is 1200; HCF is 40.
d. LCM is 8800; HCF is 20.

13. a. False **b.** False **c.** False
d. True **e.** True

14. a. False **b.** False **c.** False

15. A

16. C

17. C

18. C

19. a. $365 = 5 \times 73$ **b.** $187 = 11 \times 17$

20. A

21. D

22. C

23. B

24. 773

25. No. $3 + 7 = 10$, 3 and 7 are prime numbers, but their sum 10 is not a prime number.

26. 29 or 47 or 83 or 137. Others may be possible.

27. 61

28. a. 3, 7 **b.** 2, 13 **c.** 17, 19

29. 6 integers

30. 17 and 19, 29 and 31, 41 and 43, 59 and 61, 71 and 73

Exercise 3.6 Squares and square roots

1. a. 64 **b.** 121 **c.** 225 **d.** 625

2. 64, 81

3. 169, 196

4. a. 36 and 49 **b.** 49 and 64
c. 81 and 100 **d.** 144 and 169

5. a. 5 **b.** 9 **c.** 12 **d.** 20

6. a. 70 **b.** 120 **c.** 600 **d.** 400

7. a. 7 and 8 **b.** 3 and 4
c. 14 and 15 **d.** 1 and 2

8. a. 13 **b.** 37

9. 16, 36, 64

10. 81

11. B

12. A

13. a. 9 **b.** 75 **c.** 700 **d.** 25

14. a. 14 **b.** 45

15. a. 12 and 13 **b.** 12.2

16. a. 225
b. 225
c. Yes, if two squares are multiplied together, then the result is equal to the square of the base numbers multiplied together.

17. a. 15
b. 15
c. Yes, if two square roots are multiplied together, then the result is equal to the square root of the base numbers multiplied together.

18. a. $2^2 \times 7^2$
b. $2^3 \times 5^2$
c. If all of the prime factors of a number are squares, then the square root of that number will be an integer.

19. a. 14
b. 10
c. No, the square root of two numbers that have been added together is not equal to adding the square roots of these two numbers together.

20. a. 17
b. 13
c. No. You have to evaluate the individual square roots first before adding.

21. 169, 196, 225

22. a. **i.** 49 **ii.** 47 **iii.** 45 **iv.** 43 **v.** 41
b. Answer is the sum of the two numbers.
c. No

23. 49

24. a. $7, \sqrt{56}, 8, \sqrt{74}, 3^2, \sqrt{100}, 62, 8^2$
    b. $\sqrt{10}, \sqrt{121}, 3 \times 4, \sqrt{169}, 2 \times 7, 9^2, 100$
25. 9 and 11

Exercise 3.7 Divisibility tests

1. A number is divisible by 2 if the last digit is 0, 2, 4, 6 or 8. For example, 56 is divisible by 2 because the last digit is 6.
   A number is divisible by 4 if the last two digits together (as a two-digit number) are divisible by 4. For example, 3416 is divisible by 4 because the last two digits are 16, which is divisible by 4.
   A number is divisible by 6 if it is divisible by 2 and divisible by 3. For example, 354 is divisible by 2 because the last digit is 6; and the sum of the digits $(3 + 5 + 4)$ is 12, which is divisible by 3. Therefore, 354 is divisible by 6.
2. A number is divisible by 3 if the sum of the digits is divisible by 3. For example, 156 is divisible by 3 because the sum of the digits $(1 + 5 + 6)$ is 12, which is divisible by 3.
   A number is divisible by 5 if the last digit is either 0 or 5. For example, 845 is divisible by 5 because the last digit is 5.
   A number is divisible by 9 if the sum of the digits is divisible by 9. For example, 54 is divisible by 9 because the sum of the digits $(5 + 4)$ is 9, which is divisible by 9.
3. The sum of the digits is calculated to test for divisibility by 3 and by 9.
4. a. 54 is divisible by 2 as the last digit is 4.
   b. 150 is not divisible by 9 as the sum of the digits is 6 $(1 + 5 + 0)$, which is not divisible by 9.
   c. 295 is divisible by 5 as the last digit is 5.
   d. 1293 is divisible by 3 as the sum of the digits is 15 $(1 + 2 + 9 + 3)$, which is divisible by 3.
5. a. Divisible by 4 as the last two digits are divisible by 4
   b. Not divisible by 6 as the number is divisible by 2 but not by 3
   c. Not divisible by 9 as the sum of digits is not divisible by 9
   d. Not divisible by 8; incorrect rule
6. a. 1, 2, 3, 4, 6, 8, 9 b. 1, 2, 3, 4, 6, 8
   c. 1, 2, 4, 7, 8 d. 1, 2, 4
7. a. 1, 2, 4, 5, 8, 10 b. 1, 5
   c. 1 d. 1, 2, 4, 8
8. a. 1, 2, 4 b. 1, 2, 3, 5, 6
   c. 1, 2 d. 1
9. a. False b. True
   c. False d. False
   e. True f. False
10. a. i. 5 only ii. 2, 3, 4, 5, 6 and 10
    iii. 5 only iv. 2, 5 and 10
    v. None vi. 2 and 4
11. Julie is correct. 34 281 is not divisible by 6.
12. 3
13. Yes, $4572 + 2868$ and $4572 - 2868$ are divisible by 6.
14. a. 2 b. 1, 4 or 7
    c. 0, 2, 4, 6 or 8 d. 5
15. The two 2-digit numbers that are divisible by 4, 5 and 8 are 40 and 80.
16. 552

Exercise 3.8 Cubes and cube roots

1. a. 64 b. 8 c. 27
2. a. 216 b. 1000
3. 1, 8, 27, 64, 125, 216, 343, 512
4. 137
5. a. 800 b. 29
6. a. 2 b. 4
7. a. 6 b. 7
8. a. 6 b. 96
9. a. 8 b. 20
10. a. 3 and 4 b. 3.7
11. a. 4 and 5 b. 4.5
12. 3, 6, 10, 15 (not including 1, which would not really be a triangle at all).
13. a. $2^3 \times 3^3$
    b. $3^3 \times 5$
    c. If all of the prime factors of a number are cubes, then the cube root of that number will be an integer.
14. For cube numbers, it was necessary to find the third difference. If we look at the power 4, it will be necessary to find the fourth difference.
15. Dave is incorrect.
16. a. 84 footballers would receive a call.
    b. Each person would call 6 people.
17. a. 1, 8, 9, 1, 8, 9, 1, 8, 9, 1
    b. 8
    c. The single-digit sums of cube numbers repeat in the order 1, 8, 9.

Project

1. Enlarge the letters using machine 2, then machine 3.
2. 4, 6, 8, 9 and 10
3. 5
4. No. Numbers not required can be made using their prime factors.
5. Machine 1 and the prime numbers less than 100. Total of 26 machines.
6. Machine 1 is needed to make letters one centimetre high. Machines whose numbers are prime numbers can make all the sizes up to 100 centimetres.

Exercise 3.9 Review questions

1. a. 11, 22, 33, 44, 55
   b. 100, 200, 300, 400, 500
   c. 5, 10, 15, 20, 25
   d. 20, 40, 60, 80, 100
   e. 35, 70, 105, 140, 175

2. **a.** 12 **b.** 30 **c.** 28 **d.** 40

3. **a.** 1, 3, 9, 27 **b.** 1, 2, 5, 10, 25, 50

4. **a.** 1, 2, 4, 8, 16
b. 1, 2, 3, 6, 7, 14, 21, 42
c. 1, 2, 3, 4, 6, 8, 9, 12, 18, 24, 36, 72

5. **a.** 1, 24; 2, 12; 3, 8; 4, 6
b. 1, 40; 2, 20; 4, 10; 5, 8
c. 1, 48; 2, 24; 3, 16; 4, 12; 6, 8
d. 1, 21; 3, 7
e. 1, 99; 3, 33; 9, 11
f. 1, 100; 2, 50; 4, 25; 5, 20; 10, 10

6. **a.** 36 **b.** 196 **c.** 361 **d.** 6400

7. **a.** 9 and 16 **b.** 25 and 36
c. 100 and 121 **d.** 225 and 256

8. **a.** 7 **b.** 16 **c.** 30 **d.** 37

9. **a.** 64 **b.** 343 **c.** 3375 **d.** 27 000

10. **a.** 3 **b.** 5 **c.** 10 **d.** 20

11. **a.** 2×3^3 **b.** $5^2 \times 6^4$ **c.** $2 \times 5^3 \times 9^3$

12. **a.** 243 **b.** 343 **c.** 4096 **d.** 161 051

13. 2, 3, 5, 7, 11, 13, 17, 19, 23, 29

14. 4

15. 53

16. **a.** 3, 11 **b.** 3, 7 **c.** 5 **d.** 2, 31

17. **a.** $280 = 2 \times 2 \times 2 \times 5 \times 7 = 2^3 \times 5 \times 7$
b. $144 = 2^4 \times 3^2$

18. **a.** $1344 = 1 \times 10^3 + 3 \times 10^2 + 4 \times 10^1 + 4$
b. $30\,601 = 3 \times 10^4 + 0 \times 10^3 + 6 \times 10^2 + 0 \times 10^1 + 1$

19. HCF is 24; LCM is 1920.

20. HCF is 8; LCM is 2016.

21. **a.** 200s
b. Hung 8 laps
Frank 5 laps

22. **a.** 12, 24, 36 **b.** 12 **c.** 60

23. The sum of its factors (except for 496) add up to give 496.

24. 120 seconds or 2 minutes

25. 432

26. 20 is not a perfect square, so we can only find an approximate answer. It will be between 4 and 5.

27. 2, $\sqrt[3]{27}$, 5, $\sqrt{64}$

28. 30, 225

29. **a.** 3, 5; 5, 7; 11, 13; 17, 19; 29, 31; 41, 43; 59, 61; 71, 73
b. 5, 11; 7, 13; 11, 17; 13, 19; 17, 23; 23, 29; 31, 37; 37, 43; 41, 47; 47, 53; 53, 59; 61, 67; 67, 73; 73, 79; 83, 89
c. For 2, the number that's 7 higher is 9, which is not prime. For odd primes, the number that's 7 higher is even and therefore not prime.

30. 1 , 64

31. 2, 3, 5, 7, 11, 13, 17, 19, 23

32. **a.** 5 **b.** 125

33. 45 000

34. **a.** 4 regions

b.

***n* (number of folds)**	0	1	2	3	4	5	6
***R* (number of regions made)**	1	2	4	8	16	32	64

c. Each time the page is folded the number of regions is multiplied by 2 (doubled).

d. $R = 2^n$

35.

$2^5 = 32$	$3^5 = 243$
$2^4 = 16$	$3^4 = 81$
$2^3 = 8$	$3^3 = 27$
$2^2 = 4$	$3^2 = 9$
$2^1 = 2$	$3^1 = 3$
$2^0 = 1$	$3^0 = 1$
$2^{-1} = \frac{1}{2}$	$3^{-1} = \frac{1}{3}$

a. $5^0 = 1$ **b.** $2^{-2} = \frac{1}{4}$

4 Fractions and percentages



LEARNING SEQUENCE

4.1 Overview 170
4.2 What are fractions? 172
4.3 Simplifying fractions 184
4.4 Mixed numbers and improper fractions 188
4.5 Adding and subtracting fractions 194
4.6 Multiplying fractions 202
4.7 Dividing fractions 210
4.8 Working with mixed numbers 215
4.9 Percentages as fractions 222
4.10 Calculating percentages of an amount 227
4.11 One amount as a percentage of another 232
4.12 Common percentages and short cuts 238
4.13 Review 244

4.1 Overview

Why learn this?

There are many everyday situations in which we do not work with whole numbers. You may share a pizza with a friend, so you would eat part of the pizza. Fractions are a way of expressing parts of whole things, amounts or quantities. They are important in many situations, such as cooking, shopping and telling the time. Did you know that approximately one quarter $\left(\frac{1}{4}\right)$ of the population of Australia lives in Victoria?



Percentages, like fractions, are a way of expressing parts of a whole. They are commonly used in advertising, statistics and shopping. Did you know that the area of New South Wales is approximately 10%, or one tenth $\left(\frac{1}{10}\right)$, of the size of Australia? Fractions and percentages can be used interchangeably to represent the same part of a whole. Many different professions use fractions and percentages extensively in their work, including hospitality, finance, statistics and journalism. When you are next in a shopping centre, check out how many percentage (%) signs you see. You might be surprised.



Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 4.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Select the equivalent fraction to $\frac{2}{3}$:

   A. $\frac{3}{2}$ B. $\frac{30}{45}$ C. $\frac{30}{40}$ D. $\frac{12}{15}$ E. $\frac{21}{30}$

2. Luke's football team scored 16 goals. Luke scored 6 of the team's goals. Answer the following questions, giving your answers in simplified form.
   a. Calculate the fraction of the team's goals that Luke scored.
   b. Calculate the fraction of the team's goals that the rest of the team scored.

3. A bowl of apples was handed out to kindergarten students. If 23 students ate $\frac{1}{4}$ of an apple each, calculate how many apples the students ate in total. Give your answer as a mixed number in simplified form.

4. Evaluate the following, giving your answer as a simplified fraction.

$$\frac{2}{3} - \frac{1}{6} + \frac{3}{12}$$

5. An AFL match went for 120 minutes. If Patrick Cripps played $\frac{5}{6}$ of the game time, calculate how many minutes he played.

6. MC Select the simplified answer to $\frac{18}{56} \div \frac{27}{64}$.

   A. $\frac{16}{21}$ B. $\frac{18}{21}$ C. $\frac{2}{3}$ D. $\frac{15}{24}$ E. $\frac{243}{1792}$

7. Yuto gets $16 a week for cleaning his room, but if he also empties the dishwasher and feeds the dogs he can get $2\frac{1}{4}$ times his pay. If Yuto completes all his chores in the week, calculate how much he earned.

8. When Thomas started school he was the shortest in his class, at 85 cm tall. By the time he finished grade 12 he was the tallest in his class. His height had increased by $2\frac{1}{5}$ times. Calculate how tall he was at the end of grade 12.

9. Newcastle East Public School is having a cupcake sale to raise money for a local charity. They have 250 cupcakes to sell. Of these, $\frac{1}{5}$ are chocolate and the remainder are vanilla. At the end of the day, $\frac{24}{25}$ of the chocolate cupcakes were sold, and $\frac{7}{10}$ of all the cupcakes were sold. Calculate what fraction of the vanilla cupcakes were sold.

10. MC Max spends 78% of his weekly pocket money on his mobile phone plan. Calculate what fraction of his pocket money is spent on the phone plan.

    A. $\frac{38}{50}$ B. $\frac{37}{50}$ C. $\frac{39}{50}$ D. $\frac{18}{25}$ E. $\frac{19}{25}$

11. The cost of the new model PlayStation has increased by 12% compared to the previous model. Write the percentage increase as a:
a. simplified fraction **b.** decimal.

12. At a particular soccer game, 62% of the crowd supported the Matildas. If 17 800 people attended the game, determine how many supported the Matildas.

13. Alexander got 24 marks out of a possible 32. Calculate his percentage score to the nearest whole number.

14. MC A survey of 20 students found that 9 like Coke, 6 like Solo, 3 like Fanta and 2 like lemonade. Select the percentage of students who like Fanta.
A. 3% **B.** 6% **C.** 10% **D.** 15% **E.** 20%

15. Sarah purchased a dress that was on sale for a discount of 10%.
If the dress originally cost $155.75, calculate how much she saved, to the nearest cent.

4.2 What are fractions?


LEARNING INTENTION

At the end of this subtopic you should be able to:
- understand the concept of a fraction
- convert between equivalent fractions
- compare fractions.


4.2.1 Understanding fractions

eles-3798

- **Fractions** are used to describe parts of a whole.



- The **numerator**, or top number of the fraction, shows how many parts are required. The numerator must be an integer.
- The **denominator**, or bottom number, shows the number of parts into which the whole can be divided. The denominator must be an integer, but cannot be zero.
- The horizontal bar separating the numerator from the denominator is called the **vinculum**.



Proper fractions	Improper fractions	Mixed numbers
Proper fractions have a numerator *less than* the denominator.	**Improper fractions** have a numerator *greater than* the denominator.	**Mixed numbers** consist of a whole number and a proper fraction.
$\frac{1}{4}, \frac{2}{3}, \frac{27}{68}$	$\frac{5}{3}, \frac{3}{2}, \frac{123}{17}$	$1\frac{1}{2}, 5\frac{7}{8}, 14\frac{152}{986}$

Understanding fractions

A fraction can be understood as numerator *out of* denominator.

For example: the fraction $\frac{6}{10}$ means 6 *out of* 10.


When the numerator is equal to the denominator, we have a 'whole', which is equivalent to 1.

For example: $\frac{10}{10}$ means 10 *out of* 10 and is one 'whole'.

- To express one quantity as a fraction of another, write the first quantity as a fraction of the second quantity.

WORKED EXAMPLE 1 Identifying fractions of a quantity

a. Identify the fraction of the rectangle that has been shaded.
b. Express the number of unshaded squares as a fraction of the number of squares in total.



THINK

a. 1. Count how many equal parts the rectangle has been divided into.

2. State how many parts are shaded.

3. Write the number of shaded parts as a fraction of the total number of parts.

b. 1. Count the number of unshaded squares.

2. State the number of squares in total.

3. Write the number of unshaded squares as a fraction of the total number of squares.

WRITE

a. Total number of parts = 8

3 parts are shaded.

$\frac{3}{8}$ of the rectangle has been shaded.

b. There are 5 unshaded squares.

There are 8 squares in total.


$\frac{5}{8}$ of the squares are unshaded.

4.2.2 Equivalent fractions


eles-3799

- **Equivalent fractions** are equal fractions. For example, the fractions $\frac{1}{2}$, $\frac{2}{4}$, $\frac{5}{10}$, $\frac{8}{16}$ are all equivalent because they are all equal to a half.
- Equivalent fractions can be shown using diagrams. Equivalent fractions for $\frac{2}{3}$ are shown in the following diagrams.


Note that the same portion, $\frac{2}{3}$ of the rectangle, has been shaded in each case.



$\frac{4}{6} = \frac{2}{3}$



$\frac{6}{9} = \frac{2}{3}$



$\frac{8}{12} = \frac{2}{3}$

Equivalent fractions

Equivalent fractions are equal fractions. Equivalent fractions can be found by multiplying or dividing the numerator and denominator by the same number.

For example:

$$\frac{2}{3} \overset{\times 2}{=} \frac{4}{6} \qquad \frac{10}{20} \overset{\div 10}{=} \frac{1}{2}$$

WORKED EXAMPLE 2 Determining the multiplier

For the equivalent fractions $\frac{4}{5} = \frac{8}{10}$, determine the number (multiplier) that has been used to multiply both numerator and denominator of the first fraction in order to get the second.

THINK

1. What number is 4 multiplied by to equal 8? $(4 \times _ = 8)$ What number is 5 multiplied by to equal 10? $(5 \times _ = 10)$
2. Write the answer.

WRITE

$\frac{4}{5} = \frac{4 \times 2}{5 \times 2} = \frac{8}{10}$

The number used is 2.

WORKED EXAMPLE 3 Determining equivalent fractions

From the list, determine those fractions that are equivalent to $\frac{1}{2}$.

$$\frac{3}{9}, \frac{3}{6}, \frac{9}{18}, \frac{10}{15}, \frac{7}{14}, \frac{17}{34}$$

THINK	WRITE
1. Multiply the numerator and denominator of $\frac{1}{2}$ by the numerator of the first fraction in the list (3) to check whether the new fraction is in the list.	$\frac{1\times3}{2\times3}=\frac{3}{6}$
2. Multiply the numerator and denominator of $\frac{1}{2}$ by the next different numerator in the list (9) and check whether the new fraction is in the list.	$\frac{1\times9}{2\times9}=\frac{9}{18}$
3. Continue until all fractions have been considered.	$\frac{1\times10}{2\times10}=\frac{10}{20}$ $\frac{1\times7}{2\times7}=\frac{7}{14}$ $\frac{1\times17}{2\times17}=\frac{17}{34}$
4. Write the equivalent fractions.	From the given list, the equivalent fractions of $\frac{1}{2}$ are $\frac{3}{6}, \frac{9}{18}, \frac{7}{14}, \frac{17}{34}$.

WORKED EXAMPLE 4 Writing a sequence of equivalent fractions


Write the sequence of the first three equivalent fractions for $\frac{2}{3}$.

THINK	WRITE
1. Write the first three equivalent fractions in the sequence by multiplying both the numerator and denominator by 2, 3 and 4.	$\frac{2}{3}=\frac{2\times2}{3\times2}=\frac{4}{6}$ $=\frac{2\times3}{3\times3}=\frac{6}{9}$ $=\frac{2\times4}{3\times4}=\frac{8}{12}$
2. Write the equivalent fractions.	$\frac{2}{3}=\frac{4}{6}=\frac{6}{9}=\frac{8}{12}$
3. Write your answer.	The first three equivalent fractions for $\frac{2}{3}$ are $\frac{4}{6}, \frac{6}{9}$ and $\frac{8}{12}$.

eles-3800

4.2.3 Fractions on a number line

- The space between each whole number on a number line can be divided into equal parts. The number of equal parts is determined by the denominator of the fraction.




WORKED EXAMPLE 5 Placing fractions on a number line

Show the positions of $\frac{5}{6}$ and $1\frac{1}{6}$ on a number line.

THINK

1. Draw a number line from 0 to 2.
2. The denominator of both fractions is 6. Divide the sections between 0 and 1 and between 1 and 2 into 6 equal parts each.
3. To place $\frac{5}{6}$, count 5 marks from 0. To place $1\frac{1}{6}$ count 1 mark from the whole number 1.

WRITE



- When choosing a scale for your number lines, take into account the number of equal parts each whole number has been divided into. For example, when plotting thirds it is easier to use a scale of 3 cm for each whole number (for each part) as opposed to a scale of 1cm for each whole number.

COLLABORATIVE TASK: Peg the fraction

Equipment: one long piece of string, one smaller piece of string for each group, laundry pegs, sticky notes

Your task is to place a peg on the string to show a fraction, following the steps below.


1. Two students hold the ends of a long piece of string across the front of the classroom.
2. The teacher calls out a fraction and, with the help of the class, another student places a peg on the string to show the position of that fraction.
3. The two students holding the ends of the string then fold the string into equal lengths to see how accurately the peg was placed.
4. Repeat steps 1 to 3 in small groups using the smaller lengths of string.
5. As a class, discuss the following.
   a. How do you visually estimate fractions when the numerator is 1?
   b. How can this strategy be used to estimate the position of a fraction in which the numerator is more than 1?

6. Two students divide the long piece of string in half and place a peg at the halfway mark. They hold the ends of the string so that it stretches across the front of the classroom. Another student writes the number 1 on a sticky note and attaches it to the peg.
7. The teacher calls out a fraction, which will be a mixed or an improper fraction, such as $1\frac{1}{2}$ or $\frac{7}{4}$. With the help of the class, another student places a peg on the string to show the position of that fraction on the string.
8. The two students holding the ends of the string then fold the string into equal lengths to see how accurately the peg was placed.
9. Repeat steps **6** to **8** in small groups using the smaller lengths of string.
10. As a class, discuss the effect the denominator has on determining the position of the peg.

4.2.4 Comparing fractions

eles-3801

- If we cut a block into 4 equal pieces, then 1 piece is less than 2 pieces. This means that $\frac{1}{4}$ of the block is smaller than $\frac{2}{4}$.
- Fraction walls, or number lines, are useful tools when comparing fractions. The following figure shows an example of a fraction wall.



- With a diagram such as a fraction wall or a number line, we can see that $\frac{1}{4}$ is less than $\frac{1}{3}$. That is, if we divided a block into 4 equal parts, each part would be smaller than if we divided it into 3 equal parts.
- If the numerators are the same, the smaller fraction is the one with the larger denominator. For example, $\frac{1}{7}$ is less than $\frac{1}{6}$, and $\frac{3}{10}$ is less than $\frac{3}{7}$.

Comparing fractions

If the fractions you wish to compare do not have the same denominator:



- use equivalent fractions to convert both fractions so that they have the same denominator
- use the lowest common multiple of the two denominators (which is the best choice for the denominator).

Once the fractions have the same denominator, compare the numerators. The fraction with the largest numerator is bigger.


WORKED EXAMPLE 6 Comparing fractions

a. Identify which is the bigger fraction, $\frac{2}{3}$ or $\frac{3}{5}$.


b. Justify your answer using a fraction wall and a number line.

THINK	WRITE
a. 1. Determine the lowest common multiple of the denominators. First, list the multiples of 3 and 5. Identify the lowest number that is common to both lists.	**a.** Multiples of 3 are 3, 6, 9, 12, (15), 18, ... Multiples of 5 are 5, 10, (15), 20, ... The lowest common multiple is 15.
2. Write each fraction as an equivalent fraction using the lowest common multiple (15) as the denominator.	$\frac{2}{3} = \frac{2 \times 5}{3 \times 5} = \frac{10}{15}$ and $\frac{3}{5} = \frac{3 \times 3}{5 \times 3} = \frac{9}{15}$
3. Decide which is bigger by comparing the numerators of the equivalent fractions.	$\frac{10}{15} = \frac{2}{3}$ is bigger than $\frac{9}{15} = \frac{3}{5}$.
4. Answer the question in words.	$\frac{2}{3}$ is bigger than $\frac{3}{5}$.
b. 1. Create a fraction wall showing thirds and fifths.	**b.** 
2. Shade $\frac{2}{3}$ and $\frac{3}{5}$.	
3. Compare the lengths of the shaded areas to compare the fractions. Answer the question in words.	$\frac{2}{3}$ is bigger than $\frac{3}{5}$.

4. Draw a number line showing 0 to 1 in intervals of $\frac{1}{15}$ (found by using the lowest common multiple of the denominators).



5. Mark $\frac{2}{3}$ and $\frac{3}{5}$.



6. Answer the question in words.

$\frac{2}{3}$ is bigger than $\frac{3}{5}$.

Comparison symbols

- The symbol '>' means *is bigger than* or *is greater than*.
- The symbol '<' means *is smaller than* or *is less than*.
- When we write $\frac{1}{2} < \frac{3}{4}$, it means that $\frac{1}{2}$ is less than $\frac{3}{4}$.

WORKED EXAMPLE 7 Comparing fractions

Insert the appropriate symbol, < or >, between each pair of fractions to make a true statement.

a. $\frac{6}{7} \quad \frac{7}{8}$ **b.** $\frac{7}{12} \quad \frac{5}{9}$

THINK

a. 1. Determine the lowest common multiple of the denominators.

2. Write each fraction as an equivalent fraction using the lowest common multiple (56) as the denominator.

3. Decide which fraction is bigger by comparing the numerators of the equivalent fractions.

4. Answer the question.

b. 1. Determine the lowest common multiple of the denominators.

2. Write each fraction as an equivalent fraction using the lowest common multiple (36) as the denominator.

3. Decide which fraction is bigger by comparing the numerators of the equivalent fractions.

4. Answer the question.

WRITE

a. Multiples of 7 are: 7, 14, 21, 28, 35, 42, 49, (56), 63, ...
Multiples of 8 are: 8, 16, 24, 32, 40, 48, (56), 64, ...
The lowest common multiple is 56.

$\frac{6}{7} = \frac{6 \times 8}{7 \times 8} = \frac{48}{56}$ and $\frac{7}{8} = \frac{7 \times 7}{8 \times 7} = \frac{49}{56}$

$\frac{48}{56} = \frac{6}{7}$ is less than $\frac{49}{56} = \frac{7}{8}$.

$\frac{6}{7} < \frac{7}{8}$

b. Multiples of 12 are: 12, 24, (36), 48, …
Multiples of 9 are: 9, 18, 27, (36), 45, ...
The lowest common multiple is 36.

$\frac{7}{12} = \frac{7 \times 3}{12 \times 3} = \frac{21}{36}$ and $\frac{5}{9} = \frac{5 \times 4}{9 \times 4} = \frac{20}{36}$

$\frac{21}{36} = \frac{7}{12}$ is greater than $\frac{20}{36} = \frac{5}{9}$.

$\frac{7}{12} > \frac{5}{9}$

Resources

eWorkbook	Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Digital documents	SkillSHEET Types of fractions (doc-6437) SkillSHEET Equivalent fractions I (doc-6438) SkillSHEET Equivalent fractions II (doc-6439) SkillSHEET Lowest common multiple (doc-6440) SkillSHEET Ordering fractions (doc-6441)
Interactivities	Individual pathway interactivity: What are rational numbers? (int-4323) Understanding fractions (int-3938) Expressing one quantity as a fraction of another (int-3939) Equivalent fractions (int-3940) Fractions on a number line (int-3941) Comparing fractions (int-3942)

Exercise 4.2 What are fractions?

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 4, 7, 9, 12, 14, 16, 19, 25, 28	3, 5, 8, 10, 13, 17, 20, 21, 23, 26, 29	6, 11, 15, 18, 22, 24, 27, 30

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE1 Identify the fraction of each of the following rectangles that has been shaded.


a.



b.



c.



2. Identify the fraction of this flag that is coloured red.



3. Identify the fraction of this flag that is coloured red.




4. Calculate the fraction of the total number of pieces of fruit in the photograph that is made up of:

a. bananas **b.** oranges.



5. Calculate the fraction of chocolate biscuits in this packet that has been eaten.



6. Express 17 minutes as a fraction of an hour.

7. **WE2** For the following equivalent fractions, determine the number that has been used to multiply both numerator and denominator.

a. $\frac{3}{8} = \frac{9}{24}$ **b.** $\frac{1}{4} = \frac{3}{12}$ **c.** $\frac{3}{5} = \frac{12}{20}$ **d.** $\frac{2}{3} = \frac{10}{15}$

8. For the following equivalent fractions, determine the number that has been used to multiply both numerator and denominator.

a. $\frac{5}{6} = \frac{30}{36}$ **b.** $\frac{9}{10} = \frac{81}{90}$ **c.** $\frac{7}{8} = \frac{77}{88}$ **d.** $\frac{7}{8} = \frac{84}{96}$

9. **WE3** From the list, identify the fractions that are equivalent to the fraction marked in pink.

$\frac{2}{3}$ $\frac{20}{30}$ $\frac{5}{8}$ $\frac{12}{16}$ $\frac{14}{21}$ $\frac{40}{60}$

10. From the list, identify the fractions that are equivalent to the fraction marked in pink.

$\frac{4}{5}$ $\frac{12}{15}$ $\frac{15}{20}$ $\frac{36}{45}$ $\frac{16}{20}$ $\frac{28}{35}$ $\frac{80}{100}$

11. From the list, identify the fractions that are equivalent to the fraction marked in pink.

$\frac{7}{10}$ $\frac{18}{25}$ $\frac{35}{50}$ $\frac{14}{21}$ $\frac{21}{30}$ $\frac{14}{20}$ $\frac{140}{200}$

12. **WE4** Write a sequence of the first three equivalent fractions for $\frac{5}{6}$.

13. Write a sequence of the first three equivalent fractions for $\frac{7}{8}$.

14. WE5 Draw a number line from 0 to 2. Show the position of each of the following fractions on the number line.

a. $\frac{1}{5}$ **b.** $\frac{4}{5}$ **c.** $\frac{7}{5}$ **d.** $1\frac{3}{5}$

15. Draw a number line from 0 to 3. Show the position of each of the following fractions on the number line.

a. $\frac{1}{3}$ **b.** $\frac{4}{3}$ **c.** $\frac{8}{3}$ **d.** $\frac{3}{3}$

Understanding

16. WE6 Identify which is the bigger fraction. Justify your answer using a fraction wall or number line.

a. $\frac{2}{5}$ or $\frac{3}{5}$ **b.** $\frac{5}{8}$ or $\frac{7}{8}$ **c.** $\frac{1}{5}$ or $\frac{1}{6}$ **d.** $\frac{1}{8}$ or $\frac{1}{10}$

17. Identify which is the bigger fraction. Justify your answer using a fraction wall or number line.

a. $\frac{3}{4}$ or $\frac{3}{5}$ **b.** $\frac{2}{5}$ or $\frac{5}{8}$ **c.** $\frac{3}{5}$ or $\frac{5}{8}$ **d.** $\frac{4}{5}$ or $\frac{5}{8}$

18. WE7 Insert the appropriate symbol, < or >, between each pair of fractions to make a true statement.

a. $\frac{5}{8}$ $\frac{3}{8}$ **b.** $\frac{3}{8}$ $\frac{1}{4}$ **c.** $\frac{3}{4}$ $\frac{3}{5}$ **d.** $\frac{3}{10}$ $\frac{2}{5}$

19. MC Select which fraction is smaller than $\frac{5}{8}$.

A. $\frac{7}{8}$ **B.** $\frac{17}{24}$ **C.** $\frac{11}{12}$ **D.** $\frac{3}{5}$ **E.** $\frac{13}{16}$

20. MC Select which fraction is equivalent to $\frac{3}{4}$.

A. $\frac{3}{8}$ **B.** $\frac{6}{8}$ **C.** $\frac{9}{16}$ **D.** $\frac{12}{24}$ **E.** $\frac{15}{24}$

21. Write the following fractions with the same denominator and then write them in ascending order (smallest to largest).

$$\frac{3}{8}, \frac{1}{2}, \frac{1}{3}$$

22. Write the following fractions with the same denominator and then write them in descending order (largest to smallest).

$$\frac{3}{4}, \frac{2}{3}, \frac{7}{15}$$

23. Fill in the gaps.

$$\frac{3}{4} = \frac{\quad}{40} = \frac{18}{\quad} = \frac{\quad}{36}$$

24. Fill in the gaps.

$$\frac{5}{6} = \frac{15}{\quad} = \frac{\quad}{42} = \frac{40}{\quad}$$

Reasoning

25. Explain why a scale of 2 cm per whole number would not be the most appropriate scale if you are displaying sevenths on a number line.

26. On the number line shown, the fractions have the same numerator but the denominator is always double the previous one. Explain, with reasons, the relationship between these denominators and the distance between the numbers.



27. Four hungry teenagers ordered individual pizzas, but none could eat the whole pizza. Sally ate $\frac{6}{8}$ of her seafood pizza. Hanna ate $\frac{1}{2}$ of her Hawaiian pizza. Sonya ate $\frac{3}{4}$ of her special pizza. Vanessa ate $\frac{5}{6}$ of her vegetarian pizza.



a. Draw the four pizzas and shade the amount that each girl ate.

b. Determine who ate the most pizza.


c. State who ate more pizza, Sally or Sonya.

Problem solving

28. Five students came in at lunchtime to get help with mathematics. Macy used $\frac{1}{4}$ of the time asking questions, Lee Yin used $\frac{1}{3}$ of the time and Lachlan used $\frac{1}{6}$ of the time. Abbey also asked questions for $\frac{2}{12}$ of the time and Tao $\frac{1}{12}$ of the time. Determine which of the students used most of the lunchtime asking questions.

29. Meilin puts four equally spaced points on a number line. The first point is at the $\frac{3}{10}$ mark and the last point is at the $\frac{7}{20}$ mark. Determine where she placed the two points in between.

30. Shirly is sitting $2\frac{5}{7}$ m from the classroom door and Brent is $2\frac{2}{11}$ m from the classroom door. Place Shirly's and Brent's seats on the number line given.





4.3 Simplifying fractions


LEARNING INTENTION

At the end of this subtopic you should be able to:
- simplify fractions
- simplify mixed numbers.

4.3.1 Simplifying fractions

eles-3802

- Simplifying fractions means to write them in the simplest form possible. For example, $\frac{4}{8}$ can be simplified to $\frac{2}{4}$, which can be further simplified to $\frac{1}{2}$.



- Generally, fractions are written in their simplest form. In other words, we reduce the fraction to its lowest equivalent form.
- To simplify a fraction, divide the numerator and the denominator by the same number.

$$\frac{10}{50} \overset{\div 10}{=} \frac{1}{5}$$

- The highest common factor (HCF) of two numbers is the largest factor of both numbers.
- A fraction is in simplest form when it cannot be simplified further. This occurs when the numerator and denominator share no common factor.

Simplifying fractions

There are two ways to convert a fraction into its simplest form:
1. Divide the numerator by the highest common factor (HCF) of the numerator and denominator.
2. Simplify repeatedly, by whichever common factor you like, until there are no common factors between the numerator and denominator.

WORKED EXAMPLE 8 Simplifying fractions

Write $\frac{3}{6}$ in simplest form.

THINK	WRITE
1. Write the fraction and determine the highest common factor (HCF) or the largest number that is a factor of both the numerator and the denominator.	$\frac{3}{6}$, HCF = 3
2. Divide the numerator and denominator by this factor ($3 \div 3 = 1, 6 \div 3 = 2$).	$\frac{3}{6} \overset{\div 3}{=} \frac{1}{2}$
3. Write the answer in simplest form.	$= \frac{1}{2}$

Simplifying mixed numbers

- To simplify a mixed number, leave the whole number part and simplify the fraction part.

WORKED EXAMPLE 9 Simplifying mixed numbers

Simplify $7\frac{40}{64}$.

THINK	WRITE
1. Write the mixed number and determine the HCF of the numerator and denominator of the fraction part.	$7\frac{40}{64}$, HCF = 8
2. Divide both numerator and denominator by this factor ($40 \div 8 = 5, 64 \div 8 = 8$).	$\frac{40}{64} \overset{\div 8}{=} \frac{5}{8}$
3. Write your answer as a mixed number in simplest form.	$= 7\frac{5}{8}$

DISCUSSION

When simplifying a fraction, how do you know when it has been fully simplified? What method do you use to simplify fractions?

Resources

eWorkbook Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Digital document SkillSHEET Highest common factor (doc-6442)
Interactivities Individual pathway interactivity: Simplifying rational numbers (int-4324)
Simplifying fractions (int-3943)

Exercise 4.3 Simplifying fractions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 7, 11, 14	2, 5, 8, 10, 12, 15	3, 9, 13, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE8 Write the following fractions in simplest form.
   a. $\frac{5}{10}$ b. $\frac{8}{12}$ c. $\frac{21}{24}$ d. $\frac{48}{60}$
2. Write the following fractions in simplest form.
   a. $\frac{100}{120}$ b. $\frac{48}{50}$ c. $\frac{63}{72}$ d. $\frac{49}{70}$
3. Write the following fractions in simplest form.
   a. $\frac{33}{36}$ b. $\frac{22}{50}$ c. $\frac{21}{56}$ d. $\frac{49}{56}$
4. WE9 Simplify.
   a. $4\frac{21}{35}$ b. $7\frac{45}{54}$ c. $10\frac{10}{20}$ d. $1\frac{44}{48}$
5. Simplify.
   a. $6\frac{21}{28}$ b. $5\frac{16}{48}$ c. $3\frac{11}{55}$ d. $2\frac{16}{64}$
6. MC Select the equivalent fraction to $\frac{26}{28}$.
   A. $\frac{2}{3}$ B. $\frac{2}{6}$ C. $\frac{3}{8}$ D. $\frac{9}{12}$ E. $\frac{13}{14}$

Understanding

7. Kylie's netball team scored 28 goals. Kylie scored 21 of her team's goals. Calculate the fraction of the team's goals that Kylie scored. Simplify the answer.
8. Angelo's basketball team scored 36 points. Angelo scored 20 of the team's points.
   a. Calculate the fraction of the team's points that Angelo scored. Simplify the answer.
   b. Calculate the fraction of the team's points that the rest of the team scored. Simplify the answer.

9. Year 7 students at Springfield High School ran a car wash to raise money for the local hospital. They raised a total of $1000 and drew up a table showing how much money each class raised.


7A	7B	7C	7D	7E
$200	$150	$320	$80	$250

Express as a simple fraction how much of the total each class raised.

10. Below are the results of a book-reading competition.

Mark	5 books
Ken	10 books
Samantha	8 books
Jules	6 books
Ahmed	4 books
Darren	7 books


a. Determine how many books were read in total.
b. For each contestant, record the number of books read as a fraction of the total number of books read. Where possible, reduce the fractions to their simplest forms.



Reasoning

11. The Newcastle to Sydney train runs on time 3 out of every 5 trains.
The Sydney to Newcastle train runs on time 4 out of every 7 trains.
Determine which train is more reliable.

12. **a.** Draw three lines to divide the triangle shown into 4 equal parts.
b. State what fraction of the original triangle is one of the new triangles.
c. Halve each smaller triangle.
d. State what fraction of the smaller triangle is one of these even smaller triangles.
e. Using all the triangles available, explain why $\frac{2}{8} = \frac{1}{4}$.




13. The fraction $\frac{13}{n}$ is not written in its simplest form. Explain what number the denominator could be.

Problem solving

14. Sarina orders pizza for 22 friends. Each friend must get $\frac{1}{4}$ of a pizza.
a. Determine the number of pizzas Sarina needs to order.
b. Calculate the amount of leftover pizza.

15. **a.** Arrange the digits 1, 2, 3, 4, 5, 6, 7, 8 and 9 to form a fraction that is equivalent to $\frac{1}{2}$.
For example, one arrangement is $\frac{7329}{14\,658}$. Can you find two others?
Hint: Try starting with a numerator beginning with 72 for one of them and 67 for the other.
b. Arrange the nine digits so that they form a fraction equivalent to $\frac{1}{3}$.

16. One of the designs for a patchwork motif is made up of squares and right-angled isosceles triangles as shown. Determine what fraction of the whole has been shaded.



4.4 Mixed numbers and improper fractions

LEARNING INTENTION

At the end of this subtopic you should be able to:

- convert between mixed numbers and improper fractions.


4.4.1 Converting improper fractions to mixed numbers

eles-3803

- An improper fraction has a numerator larger than the denominator: for example, $\frac{3}{2}$.
- An improper fraction can be changed to a mixed number by dividing the denominator into the numerator and writing the remainder over the same denominator.

Mixed numbers and improper fractions

Mixed numbers and improper fractions are different ways of writing the same quantity.




WORKED EXAMPLE 10 Converting improper fractions to mixed numbers

Draw a diagram to show $\frac{5}{4}$ as parts of a circle, then write the improper fraction as a mixed number.

THINK

1. Draw a whole circle and divide it into the number of parts shown by the denominator.

WRITE



This is 4 quarters or $\frac{4}{4}$.

2. Determine the number of parts left over and draw them.




Extra $\frac{1}{4}$ needed.

3. Write the improper fraction as a mixed number.

$\frac{5}{4} = 1\frac{1}{4}$

WORKED EXAMPLE 11 Converting improper fractions to mixed numbers

Express $\frac{11}{5}$ as a mixed number.

THINK	WRITE
1. Write the improper fraction.	$\frac{11}{5}$
2. Determine how many times the denominator can be divided into the numerator and what the remainder is. The whole number is part of the answer and the remainder becomes the numerator of the fractional part with the same denominator as the original improper fraction.	$= 11 \div 5$ $= 2$ remainder 1 
3. Write the answer.	$= 2\frac{1}{5}$


eles-3804

4.4.2 Converting mixed numbers to improper fractions

- A mixed number can be changed to an improper fraction by first multiplying the whole number by the denominator and then adding the numerator. The denominator stays the same.
- You may wish to draw a diagram to help visualise the conversion.

Mixed numbers to improper fractions

$$2\frac{1}{4} = \frac{(2 \times 4) + 1}{4} = \frac{8 + 1}{4} = \frac{9}{4}$$



$2\frac{1}{4}$ = $\frac{9}{4}$


WORKED EXAMPLE 12 Converting mixed numbers to improper fractions

Draw a diagram to illustrate $2\frac{1}{3}$ as pieces of a circle, then write $2\frac{1}{3}$ as an improper fraction.

THINK

1. Draw two whole circles and $\frac{1}{3}$ of a circle.
2. Divide the whole circles into thirds.
3. Count the number of thirds and write the mixed number as an improper fraction.

WRITE



$2\frac{1}{3} = \frac{7}{3}$

WORKED EXAMPLE 13 Converting mixed numbers to improper fractions

Express $2\frac{3}{4}$ as an improper fraction.

THINK

1. Write the mixed number.
2. Multiply the whole number by the denominator, then add the numerator. The result becomes the numerator, and the denominator stays the same.
3. Evaluate the top line of the fraction.
4. Write the answer.

WRITE

$2\frac{3}{4}$


$= \frac{2 \times 4 + 3}{4}$

$= \frac{8 + 3}{4}$


$= \frac{11}{4}$

Digital technology

Scientific calculators usually give answers in decimal form. Most calculators have a button that converts decimals and fractions. Depending on the brand of calculator, this may appear as f ◅▻ d, S ⇔ or similar. The screenshot on the right shows how to convert a decimal to a fraction.



Most scientific calculators have a button that can convert between improper fractions and mixed numbers. The button may appear as $\frac{n}{d}$ ◅▻ U$\frac{n}{d}$ or similar.



Resources

eWorkbook	Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Digital documents	SkillSHEET Converting an improper fraction into a mixed number (doc-6443) SkillSHEET Converting a mixed number into an improper fraction (doc-6444)
Interactivities	Individual pathway interactivity: Mixed numbers and improper fractions (int-4325) Mixed numbers to improper fractions (int-3944)

Exercise 4.4 Mixed numbers and improper fractions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 4, 7, 10, 12, 14, 17, 20, 22, 25	5, 9, 11, 15, 18, 21, 23, 26	3, 6, 8, 13, 16, 19, 24, 27, 28

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE10 Draw a diagram to show the following improper fractions as pieces of a circle, then write each improper fraction as a mixed number.
   a. $\frac{5}{2}$ b. $\frac{4}{3}$ c. $\frac{13}{8}$
2. Aamira ate $\frac{3}{2}$ or 3 halves of an apple. Draw the amount of apple that Aamira ate and express $\frac{3}{2}$ as a mixed number.



3. Dean ate $\frac{9}{4}$ or 9 quarters of pizza. Draw the amount of pizza that Dean ate and express $\frac{9}{4}$ as a mixed number.
4. WE11 Express these improper fractions as mixed numbers.
   a. $\frac{7}{5}$ b. $\frac{11}{4}$ c. $\frac{21}{2}$ d. $\frac{51}{12}$ e. $\frac{92}{11}$

5. Express these improper fractions as mixed numbers.

a. $\frac{29}{13}$ **b.** $\frac{100}{3}$ **c.** $\frac{25}{2}$ **d.** $\frac{20}{3}$ **e.** $\frac{8}{5}$

6. Change these improper fractions to mixed numbers.

a. $\frac{27}{8}$ **b.** $\frac{11}{2}$ **c.** $\frac{58}{7}$ **d.** $\frac{117}{10}$ **e.** $\frac{67}{8}$

7. MC Select which of the following is the same as $\frac{61}{8}$.

A. $5\frac{5}{8}$ **B.** $6\frac{5}{8}$ **C.** $7\frac{5}{8}$ **D.** $8\frac{5}{8}$ **E.** $9\frac{5}{8}$

8. MC Select which of the following is the same as $\frac{74}{10}$.

A. $3\frac{7}{10}$ **B.** $7\frac{2}{5}$ **C.** $7\frac{7}{10}$ **D.** $7\frac{4}{5}$ **E.** $7\frac{4}{10}$

9. WE12 Draw a diagram to show the following mixed numbers as pieces of a circle and then write each one as an improper fraction.

a. $1\frac{2}{3}$ **b.** $3\frac{1}{4}$ **c.** $2\frac{3}{5}$

10. WE13 Express the following mixed numbers as improper fractions.

a. $1\frac{1}{8}$ **b.** $3\frac{3}{4}$ **c.** $2\frac{1}{6}$ **d.** $1\frac{1}{7}$ **e.** $1\frac{4}{5}$

11. Express the following mixed numbers as improper fractions.

a. $3\frac{1}{3}$ **b.** $6\frac{1}{4}$ **c.** $4\frac{1}{9}$ **d.** $11\frac{1}{2}$ **e.** $7\frac{4}{5}$

12. Express the following mixed numbers as improper fractions.

a. $6\frac{3}{5}$ **b.** $9\frac{2}{5}$ **c.** $3\frac{1}{2}$ **d.** $4\frac{1}{5}$ **e.** $6\frac{5}{7}$

13. Express the following mixed numbers as improper fractions.

a. $2\frac{9}{10}$ **b.** $3\frac{7}{12}$ **c.** $9\frac{4}{7}$ **d.** $1\frac{10}{11}$ **e.** $8\frac{5}{6}$

14. MC Select which of the following is the same as $10\frac{2}{7}$.

A. $\frac{27}{10}$ **B.** $\frac{72}{10}$ **C.** $\frac{10}{27}$ **D.** $\frac{72}{7}$ **E.** $\frac{72}{2}$

15. MC Select which of the following is the same as $8\frac{5}{6}$.

A. $\frac{85}{6}$ **B.** $\frac{58}{6}$ **C.** $\frac{56}{8}$ **D.** $\frac{53}{6}$ **E.** $\frac{68}{5}$

16. MC Select which of the following is the same as $7\frac{9}{11}$.

A. $\frac{86}{11}$ **B.** $\frac{99}{7}$ **C.** $\frac{79}{11}$ **D.** $\frac{97}{11}$ **E.** $\frac{77}{9}$

Understanding

17. Kim and Carly arrived home from school quite hungry and cut up some fruit. Kim ate 9 quarters of apple and Carly ate 11 quarters. Calculate how many apples they each ate.

18. Thanh was selling pieces of quiche at the school fete. Each quiche was divided into 8 pieces. If Thanh sold 52 pieces, calculate how many quiches Thanh sold.



19. It was Cecilia's responsibility to supply oranges for her soccer team at half-time. If 19 players ate $\frac{1}{4}$ of an orange each, calculate how many oranges were eaten.

20. Insert the appropriate $<$ or $>$ sign between each pair of fractions to make a true statement.

a. $\frac{8}{5} \quad 1\frac{2}{5}$ **b.** $\frac{19}{2} \quad 8\frac{1}{2}$ **c.** $\frac{33}{32} \quad 1\frac{3}{32}$ **d.** $\frac{15}{2} \quad 5\frac{1}{2}$

21. Insert the appropriate $<$ or $>$ sign between each pair of fractions to make a true statement.

a. $7\frac{1}{7} \quad \frac{65}{7}$ **b.** $2\frac{1}{3} \quad \frac{8}{3}$ **c.** $1\frac{16}{17} \quad \frac{35}{17}$ **d.** $4\frac{3}{8} \quad \frac{36}{8}$

Reasoning

22. A catering company provided 12 quiches that were each cut into 8 pieces for a luncheon. At the end of the luncheon, 12 pieces of quiche were left over. Calculate how many whole quiches were eaten. Show your full working.

23. **a.** Convert the following numbers to improper fractions.

i. $3\frac{2}{7}$ **ii.** $5\frac{3}{4}$

b. Explain with the use of diagrams why $3\frac{2}{7} = \frac{23}{7}$.

24. A bakery makes birthday cakes to serve 24 people. Arabella takes one to school to celebrate her birthday, but there are 30 people in her class. Determine what fraction of the original slices each student will receive.



Problem solving

25. a. Nasira made apple pies for her Grandma's 80th birthday party. She divided each pie into 6 pieces, and after the party she noted that $4\frac{1}{6}$ pies had been eaten. Calculate how many pieces were eaten.

b. Nasira's cousin Ria provided cordial for the same party and calculated that she could make 20 drinks from each bottle. At the end of the party, $3\frac{17}{20}$ bottles had been used. Calculate how many drinks were consumed.



26. Baljinder walks to school four days a week and her father drives her to school on Fridays. If she lives $2\frac{1}{3}$km from school, calculate:

a. the distance Baljinder walks to school and back home each day

b. the total distance walked by Baljinder over the four days

c. the total distance she travels to school either walking or by car over the whole week.

State your answers in improper fractions and mixed numbers if possible.

27. The following mixed numbers are missing their denominators. The missing denominators are 3, 4, 6, 8 and 14. The mixed numbers are placed in order from smallest to largest. Determine the missing numbers.

$$1\frac{1}{a}, \quad 2\frac{1}{b}, \quad 2\frac{1}{c}, \quad 3\frac{1}{d}, \quad 3\frac{1}{e}$$

28. Explain the strategies you use to write an improper fraction as a mixed number.

4.5 Adding and subtracting fractions

LEARNING INTENTION

At the end of this subtopic you should be able to:

- add and subtract fractions.

4.5.1 Adding and subtracting proper fractions

eles-3805

- Fractions can be added and subtracted if they have the same denominator.


Adding and subtracting fractions with equal denominators

To add or subtract fractions of the same denominator, simply add or subtract the numerators. Leave the denominator unchanged.

For example:

$$\frac{1}{5}+\frac{2}{5}=\frac{1+2}{5}=\frac{3}{5} \qquad \frac{5}{8}-\frac{2}{8}=\frac{5-2}{8}=\frac{3}{8}$$

- Addition and subtraction of fractions can be visualised using areas of shapes.



$\frac{1}{4}$ $\frac{2}{4}$ $\frac{3}{4}$

WORKED EXAMPLE 14 Adding proper fractions

Evaluate $\frac{5}{9} + \frac{1}{9}$.

THINK	WRITE
1. Write the question.	$\frac{5}{9} + \frac{1}{9}$
2. Since the denominators are the same, add the numerators.	$= \frac{6}{9}$
3. Simplify the answer if possible by cancelling. Divide by the highest common factor ($6 \div 3 = 2, 9 \div 3 = 3$).	$= \frac{\cancel{6}^{2}}{\cancel{9}^{3}}$ $= \frac{2}{3}$

Lowest common denominator

- The lowest common denominator (LCD) is the lowest number that is a multiple of the denominators. This is also known as the lowest common multiple (LCM) of the numbers in the denominators.

Adding and subtracting fractions with different denominators

To add or subtract fractions with different denominators, convert to equivalent fractions with the lowest common denominator (LCD), then add the numerators.


For example: $\frac{1}{2} + \frac{1}{3}$

The LCD of 2 and 3 is 6.

Add the intermediate step to the equation and calculate the answer:



$$\frac{1}{2} + \frac{1}{3} = \frac{3}{6} + \frac{2}{6} = \frac{3+2}{6} = \frac{5}{6}$$

- Let us visualise the previous example using areas of circles. We can divide both circles into the same number of parts and then add the parts.






WORKED EXAMPLE 15 Subtracting proper fractions

Evaluate $\frac{5}{6} - \frac{1}{12}$, expressing the answer in simplest form.

THINK	WRITE
1. List multiples of each denominator.	Multiples of 6 are 6, 12, ... Multiples of 12 are 12, ...
2. Identify the lowest common denominator.	LCD is 12.
3. Rewrite the fractions as equivalent fractions with 12 as the LCD.	$\frac{5}{6} - \frac{1}{12} = \frac{5 \times 2}{6 \times 2} - \frac{1}{12} = \frac{10}{12} - \frac{1}{12}$
	= 
4. Subtract the numerators.	$= \frac{9}{12}$ 
5. Simplify the answer if possible by cancelling. Divide by the highest common factor ($9 \div 3 = 3, 12 \div 3 = 4$).	$= \frac{\cancel{9}^{3}}{\cancel{12}_{4}}$ $= \frac{3}{4}$



WORKED EXAMPLE 16 Subtracting a fraction from a whole number

Evaluate $4 - \frac{1}{3}$, expressing the answer as a mixed number.

THINK	WRITE
1. Express the whole number as a fraction over 1.	$4 - \frac{1}{3} = \frac{4}{1} - \frac{1}{3}$ 
2. Equate the denominators.	$= \frac{12}{3} - \frac{1}{3}$ 
3. Perform the subtraction.	$= \frac{11}{3}$ 
4. Convert to a mixed number.	$= 3\frac{2}{3}$

WORKED EXAMPLE 17 Application of adding and subtracting fractions

A farmer picks the fruit from $\frac{2}{3}$ of her orange trees and her partner collects fruit from another $\frac{1}{6}$ of the trees. Determine the fraction of the total number of trees that still need to have their fruit picked.

THINK	WRITE
1. Calculate the total fraction of trees that have had fruit picked, by adding the fractions.	$\frac{2}{3} + \frac{1}{6} = \frac{4}{6} + \frac{1}{6}$  $= \frac{5}{6}$ 

2. Using the diagram, determine the remaining fraction of trees that have not yet had the fruit picked.

$\frac{1}{6}$

Or, alternatively

$1 - \frac{5}{6} = \frac{6}{6} - \frac{5}{6}$

$= \frac{1}{6}$

3. Write the answer.

$\frac{1}{6}$ of the orange trees still have fruit that needs to be picked.

COLLABORATIVE TASK: Dice fractions

Equipment: dice

Work in pairs or in small groups to play this game.



1. The first player rolls both dice. One number rolled is the numerator of the fraction and the other number rolled is the denominator. The player makes the smallest possible fraction with the numbers rolled.
2. The first player rolls the dice again to make another fraction, which should be as close as possible to the first fraction.
3. The first player works out the difference between the two fractions rolled by subtracting one fraction from the other. This amount is recorded as their result for this round.
4. Repeat steps 1 to 3 until every player has a result for the first round.
5. Compare the results for the round. The player with the smallest difference between their two fractions receives 1 point. If two players have the smallest difference, they both receive 1 point. The game is over when a player has collected 5 points.
6. What strategy did you use to make the smallest difference between your fractions?

on Resources

eWorkbook	Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Digital document	SkillSHEET Adding and subtracting fractions with the same denominator (doc-6445)
Video eLesson	Addition and subtraction of fractions (eles-1866)
Interactivities	Individual pathway interactivity: Adding and subtracting rational numbers (int-4326) Addition and subtraction of proper fractions (int-3945)

Exercise 4.5 Adding and subtracting fractions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 5, 7, 11, 14, 16, 20, 23	2, 6, 8, 9, 12, 15, 17, 21, 24	4, 10, 13, 18, 19, 22, 25, 26

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE14 Evaluate:

a. $\frac{1}{5}+\frac{3}{5}$ **b.** $\frac{9}{11}-\frac{3}{11}$ **c.** $\frac{3}{6}+\frac{2}{6}$ **d.** $\frac{20}{50}+\frac{11}{50}$

2. Evaluate the following, expressing the answers in simplest form.

a. $\frac{5}{12}+\frac{1}{12}$ **b.** $\frac{7}{16}-\frac{3}{16}$ **c.** $\frac{9}{15}-\frac{4}{15}$ **d.** $\frac{37}{100}+\frac{13}{100}$

3. Evaluate:

a. $\frac{15}{25}-\frac{6}{25}$ **b.** $\frac{12}{12}-\frac{1}{12}$ **c.** $\frac{5}{8}-\frac{1}{8}+\frac{3}{8}$ **d.** $\frac{4}{7}+\frac{5}{7}-\frac{3}{7}$

4. Evaluate the following, expressing the answers in simplest form.

a. $\frac{4}{7}+\frac{5}{7}-\frac{2}{7}$ **b.** $\frac{13}{16}+\frac{9}{16}-\frac{10}{16}$ **c.** $\frac{11}{28}+\frac{10}{28}$ **d.** $\frac{21}{81}+\frac{21}{81}+\frac{30}{81}$

5. WE15 Evaluate the following, expressing the answers in simplest form.

a. $\frac{1}{2}+\frac{1}{4}$ **b.** $\frac{1}{2}-\frac{1}{4}$ **c.** $\frac{1}{3}+\frac{2}{21}$ **d.** $\frac{1}{8}+\frac{20}{32}$

6. Evaluate the following, expressing the answers in simplest form.

a. $\frac{9}{18}+\frac{1}{6}$ **b.** $\frac{7}{9}-\frac{8}{27}$ **c.** $\frac{31}{35}-\frac{3}{7}$ **d.** $\frac{8}{10}-\frac{28}{70}$

7. a. Determine the lowest common multiple of each of the following pairs of numbers.

i. 2 and 3 **ii.** 3 and 5 **iii.** 5 and 10 **iv.** 4 and 6

b. Use the answers that were found in part **a** as the lowest common denominators to add or subtract these fractions.

i. $\frac{1}{2}-\frac{1}{3}$ **ii.** $\frac{2}{3}-\frac{2}{5}$ **iii.** $\frac{3}{5}+\frac{3}{10}$ **iv.** $\frac{3}{4}-\frac{1}{6}$

8. a. Determine the lowest common multiple of each of the following pairs of numbers.

i. 9 and 6 **ii.** 4 and 8 **iii.** 6 and 8 **iv.** 7 and 5

b. Use the answers from part **a** as the lowest common denominators to add or subtract these fractions.

i. $\frac{1}{9}+\frac{5}{6}$ **ii.** $\frac{1}{4}+\frac{3}{8}$ **iii.** $\frac{5}{6}-\frac{3}{8}$ **iv.** $\frac{5}{7}-\frac{2}{5}$

9. Answer the following by first identifying the lowest common denominator. Simplify your answer if necessary.

a. $\frac{7}{10} + \frac{2}{15}$ **b.** $\frac{5}{12} + \frac{2}{9}$ **c.** $\frac{7}{11} + \frac{1}{4}$ **d.** $\frac{3}{10} - \frac{1}{20}$

10. Answer the following by first identifying the lowest common denominator. Simplify your answer if necessary.

a. $\frac{5}{9} - \frac{2}{7}$ **b.** $\frac{2}{3} - \frac{1}{13}$ **c.** $\frac{4}{5} - \frac{2}{3}$ **d.** $\frac{6}{11} - \frac{1}{3}$

11. MC The lowest common denominator of $\frac{1}{3}$, $\frac{1}{4}$ and $\frac{1}{6}$ is:

A. 16 **B.** 24 **C.** 18 **D.** 12 **E.** 72

Understanding

12. Answer the following:

a. $\frac{1}{2} + \frac{1}{3} - \frac{1}{4}$ **b.** $\frac{3}{10} + \frac{4}{15} - \frac{1}{6}$ **c.** $\frac{7}{8} - \frac{3}{4} + \frac{4}{6}$ **d.** $\frac{11}{12} - \frac{8}{15} - \frac{3}{20}$

13. Answer the following:

a. $\frac{1}{16} + \frac{1}{8} + \frac{1}{4}$ **b.** $\frac{5}{6} - \frac{7}{18} - \frac{1}{9}$ **c.** $\frac{1}{2} + \frac{2}{3} + \frac{3}{4}$ **d.** $\frac{3}{4} + \frac{1}{3} + \frac{5}{6}$

14. WE16 Evaluate the following, expressing the answers as proper fractions or mixed numbers.

a. $1 - \frac{1}{4}$ **b.** $1 - \frac{3}{7}$ **c.** $1 - \frac{11}{71}$ **d.** $2 - \frac{2}{5}$

15. Evaluate the following, expressing the answers as proper fractions or mixed numbers.

a. $3 - \frac{7}{15}$ **b.** $5 - \frac{5}{6}$ **c.** $10 - \frac{1}{3}$ **d.** $23 - \frac{9}{10}$

16. Melissa and Antonio went berry picking. Melissa picked $\frac{3}{10}$ of a bucket of berries and Antonio picked $\frac{1}{6}$ of a bucket.

a. Calculate how much they picked altogether.
b. If they needed 1 full bucket of berries, calculate what fraction more they still need to pick.

17. A loaf of bread needed to be cooked at 200 °C for $\frac{3}{4}$ hour then a further $\frac{1}{2}$ hour at 150 °C. Calculate the total cooking time in hours.



18. Robert, Jason and Luke play football in the same team. Last Saturday, Robert kicked $\frac{1}{4}$ of the team's goals, Jason kicked $\frac{1}{3}$ and Luke kicked $\frac{5}{12}$. Calculate what fraction of the team's goals were kicked by:

a. Jason and Luke
b. Robert and Jason
c. the three together.

19. Suraya and her friend decided to climb the tree in her front yard. It took Suraya 10 minutes to climb halfway up, 10 more minutes to climb another sixth of the way and yet another 10 minutes to reach a further tenth of the way. Here she sat admiring the view for 5 minutes before beginning her descent.



a. Calculate what fraction of the height of the tree Suraya had climbed after 20 minutes.

b. Calculate what fraction of the tree Suraya climbed in total.

Reasoning

20. Yuna sold $\frac{2}{3}$ of the cupcakes she made. She had 45 cupcakes left. Calculate how many cupcakes she made.

21. Explain why $\frac{1}{3}+\frac{2}{5}\neq\frac{3}{8}$.

22. Chris lives on a farm and has a horse he rides every day. He fills up the horse's trough with $\frac{2}{3}$ hay, $\frac{1}{6}$ carrots, $\frac{1}{12}$ oats and the rest maize. Calculate the fraction of the trough that is filled with maize.

Problem solving

23. a. Without using a calculator, perform the following additions:

i. $\frac{1}{2}+\frac{1}{3}$ **ii.** $\frac{1}{3}+\frac{1}{4}$ **iii.** $\frac{1}{4}+\frac{1}{5}$

b. Explain any pattern you noticed.

24. a. Without using a calculator, perform the following subtractions:

i. $\frac{1}{2}-\frac{1}{3}$ **ii.** $\frac{1}{3}-\frac{1}{4}$ **iii.** $\frac{1}{4}-\frac{1}{5}$


b. Explain any pattern you noticed.

c. Using your answer to part **b**, state the answer to the subtraction $\frac{1}{n}-\frac{1}{n+1}$.

25. Explain the difficulties you might experience when adding and subtracting fractions with different denominators and how you could overcome them.

26. Arrange the following fractions in the circles in the diagram so that each row adds up to the same value.

$$\frac{1}{12},\ \frac{1}{4},\ \frac{1}{2},\ \frac{1}{6},\ \frac{3}{4},\ \frac{1}{3},\ \frac{2}{3}$$



4.6 Multiplying fractions

LEARNING INTENTION


At the end of this subtopic you should be able to:

- multiply fractions by a whole number
- multiply fractions by another fraction
- calculate fractions of a fraction
- calculate fractions of an amount.

4.6.1 Multiplying fractions

eles-3806

- Multiplication by a whole number can be thought of as repeated addition.
  For example, $3 \times 4 = 4 + 4 + 4 = 12$.
  The same principle holds when multiplying a fraction by a whole number.
  For example, $3 \times \frac{1}{4} = \frac{1}{4} + \frac{1}{4} + \frac{1}{4} = \frac{3}{4}$



- A quicker way of multiplying a fraction by a whole number is to simply multiply the numerator by the whole number.

Multiplying a fraction by a whole number

To multiply a fraction by a whole number, simply multiply the numerator by the whole number and keep the denominator the same.

For example:


$$\frac{1}{5} \times 6 = \frac{1 \times 6}{5} = \frac{6}{5}$$

WORKED EXAMPLE 18 Multiplying a fraction by a whole number

Calculate $6 \times \frac{1}{3}$.

THINK	WRITE
1. Write the question.	$6 \times \frac{1}{3}$

2. Multiply by a whole number using repeated addition. Add $\frac{1}{3}$ six times.



3. Alternatively, multiply the numerator by the whole number.

$$= \frac{6 \times 1}{3}$$

$$= \frac{6}{3}$$

4. Simplify and write the answer.

$$= 2$$

- The multiplication $\frac{1}{3} \times \frac{1}{2}$ is the same as one-third of a half; this is the same as one-sixth of a whole unit, as shown here.



$$\frac{1}{3} \times \frac{1}{2} = \frac{1}{6} \text{ (of a whole unit)}$$

Multiplying a fraction by another fraction

To multiply a fraction by another fraction, simply multiply the numerators and then multiply the denominators.

For example:

$$\frac{1}{2} \times \frac{3}{4} = \frac{1 \times 3}{2 \times 4} = \frac{3}{8}$$

Fractions don't need to have the same denominator to be multiplied together.

WORKED EXAMPLE 19 Multiplying a fraction by another fraction

Calculate $\frac{1}{5} \times \frac{3}{4}$.

THINK	WRITE
1. Write the question.	$\frac{1}{5} \times \frac{3}{4}$
2. Multiply the numerators and the denominators.	$= \frac{1 \times 3}{5 \times 4}$
3. Write the answer.	$= \frac{3}{20}$

- Before being multiplied, fractions can be simplified by dividing both the numerator and denominator by their highest common factor. This is often called *cancelling*.
- When multiplying fractions, cancelling can only occur:
  - vertically, for example, $\frac{\cancel{3}^{1}}{\cancel{24}^{8}} \times \frac{5}{7} = \frac{1 \times 5}{8 \times 7} = \frac{5}{56}$
  - diagonally, for example, $\frac{\cancel{2}^{1}}{3} \times \frac{5}{\cancel{6}^{3}} = \frac{1 \times 5}{3 \times 3} = \frac{5}{9}$

DISCUSSION

Why is cancelling pairs of numerators or denominators not allowed?

WORKED EXAMPLE 20 Multiplying fractions

Calculate $\frac{2}{3} \times \frac{9}{10}$.

THINK	WRITE
1. Write the question.	$\frac{2}{3} \times \frac{9}{10}$
2. Simplify by dividing the numbers in the numerator and denominator by their highest common factor. The HCF of 2 and 10 is 2, and the HCF of 3 and 9 is 3. *Note*: This may be done vertically or diagonally.	$= \frac{\cancel{2}^{1} \times \cancel{9}^{3}}{\cancel{3}^{1} \times \cancel{10}^{5}}$
3. Multiply the numerators, then the denominators and simplify the answer if appropriate.	$\frac{1 \times 3}{1 \times 5} = \frac{3}{5}$

COLLABORATIVE TASK: Fractions of fractions

Equipment: string, pegs, counters

1. Form small groups. One student from each group should collect a piece of string and two pegs.
2. Your teacher will give each group a multiplication of two fractions.
3. As a group, place a peg on the length of string to show the position of one of your fractions.
4. Using this peg as a new marker for the end of the string, find the second fraction of this new string length and place a second peg in the correct position on the string.
5. Check the position of the second peg by calculating the product of the fractions and then folding the complete length of string into the appropriate number of parts to find the position of the product.
6. Repeat steps 2 to 5 with other fraction multiplications.
7. One student from each group should collect a handful of counters.
8. Your teacher will give each group a fraction of an amount.
9. As a group, divide up the counters to show your allocated fraction.
10. Write a description of the process that your group used to find your fraction of an amount.

4.6.2 Using the word *of*

eles-3807

- Sometimes the word *of* means 'multiply'. For example, $\frac{1}{2}$ of $\frac{1}{3}$ can be visualised as



Half of $\frac{1}{3} = \frac{1}{2} \times \frac{1}{3} = \frac{1}{6}$

- A third of an hour, or $\frac{1}{3}$ of 60 minutes, is the same as $\frac{1}{3} \times \frac{60}{1} = 20$ minutes.
- If a customer wants to buy $\frac{1}{4}$ of the remaining 8 pizzas, it is the same as $\frac{1}{4} \times \frac{8}{1} = 2$ pizzas. The customer buys 2 pizzas.
- A diagram can also be used to display multiplication of a fraction by another fraction. The following model shows how to calculate $\frac{2}{3}$ of $\frac{4}{5}$.




The rectangle is divided vertically into fifths; $\frac{4}{5}$ is shaded blue.

The rectangle is divided horizontally into thirds; $\frac{2}{3}$ of the blue rectangles are now shaded purple.
The purple shading represents $\frac{2}{3}$ of $\frac{4}{5}$.

$$\frac{2}{3} \times \frac{4}{5} = \frac{8}{15}$$

WORKED EXAMPLE 21 Calculating a fraction of a fraction

Calculate $\frac{2}{3}$ of $\frac{1}{4}$.

THINK	WRITE
1. Write the question.	$\frac{2}{3}$ of $\frac{1}{4}$
	
2. Change 'of' to × and cancel if appropriate.	$= \frac{\cancel{2}^{1}}{3} \times \frac{1}{\cancel{4}^{2}}$
3. Perform the multiplication and write the answer.	$= \frac{1}{6}$

WORKED EXAMPLE 22 Calculating fractions of an amount

Mum put a 2-litre carton of flavoured milk in the refrigerator. When the children came home from school, Joanna drank one quarter of the milk, Kieren drank one half of it and Daisy drank one sixth of it. Calculate how much milk, in litres, each person drank.

THINK	WRITE
1. Write the fraction of the milk that Joanna drank and simplify the answer.	Joanna: $\frac{1}{4}$ of $2 = \frac{1}{4} \times 2$
2. Perform the multiplication.	$= \frac{1}{\cancel{2}^{1}\cancel{4}} \times \frac{\cancel{2}^{1}}{1}$ $= \frac{1}{2}$
3. Write the fraction of the milk that Kieren drank and simplify the answer.	Kieren: $\frac{1}{2}$ of $2 = \frac{1}{2} \times 2$
4. Perform the multiplication.	$= \frac{1}{\cancel{1}\cancel{2}} \times \frac{\cancel{2}^{1}}{1}$ $= 1$

5. Write the fraction of the milk that Daisy drank and simplify the answer.

Daisy: $\frac{1}{6}$ of $2 = \frac{1}{6} \times 2$

6. Perform the multiplication.

$= \frac{1}{\cancel{6}^{3}} \times \frac{\cancel{2}^{1}}{1}$

$= \frac{1}{3}$

7. Write a sentence giving the answer in litres.

Joanna drank half a litre, Kieren drank 1 litre and Daisy drank a third of a litre of milk.

WORKED EXAMPLE 23 Calculating a fraction of a fraction of an amount

Before a road trip John completely fills up his car's fuel tank with 72 litres of petrol. On the first day of the trip, the car uses $\frac{3}{8}$ of the full tank. On the second day, the car uses $\frac{2}{5}$ of the remaining amount. Determine how much petrol was used on the second day.

THINK

a. 1. Determine the fraction left after $\frac{3}{8}$ of the petrol is used on the first day.

2. Calculate the total fraction of the tank of petrol that has been used on day 2.

3. Calculate the amount of petrol used on day 2 as the answer. Remember to state the units.

WRITE

a. $1 - \frac{3}{8} = \frac{5}{8}$

$\frac{5}{8}$ remains after the first day.

$\frac{2}{5}$ of $\frac{5}{8}$ of a tank $= \frac{2 \times 5}{5 \times 8}$

$= \frac{1}{4}$ of the full tank is used on day 2.

$\frac{1}{4} \times 72 = \frac{72}{4} = 18$


18 litres of petrol were used on the second day.

DISCUSSION

Is repeated addition an efficient method of multiplying fractions?

Digital technology

Scientific calculators can evaluate the multiplication of a fraction by another fraction or a whole number.



Resources

eWorkbook	Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Video eLesson	Multiplication and division of fractions (eles-1867)
Interactivities	Individual pathway interactivity: Multiplying rational numbers (int-4327)
	Repeated addition (int-2738)
	Multiplication of rational numbers (int-3946)
	Using the word *of* (int-3947)

Exercise 4.6 Multiplying fractions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 8, 10, 13, 15, 18	3, 6, 9, 11, 16, 19	4, 7, 12, 14, 17, 20

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE18 Calculate the following.

a. $\frac{2}{3} \times 3$ **b.** $\frac{5}{14} \times 7$ **c.** $\frac{15}{22} \times 11$ **d.** $\frac{5}{16} \times 4$

2. WE19 Calculate the following using written methods, then check your answers with a calculator.

a. $\frac{1}{2} \times \frac{1}{4}$ **b.** $\frac{1}{3} \times \frac{2}{3}$ **c.** $\frac{5}{9} \times \frac{4}{3}$ **d.** $\frac{11}{13} \times \frac{1}{2}$

3. Calculate the following using written methods, then check your answers with a calculator.

a. $\frac{6}{7} \times \frac{9}{11}$ **b.** $\frac{11}{12} \times \frac{11}{12}$ **c.** $\frac{8}{9} \times \frac{5}{9}$ **d.** $\frac{5}{8} \times \frac{1}{3}$

4. Calculate the following using written methods, then check your answers with a calculator.

a. $\frac{5}{6} \times \frac{11}{12}$ **b.** $\frac{5}{11} \times \frac{5}{12}$ **c.** $\frac{2}{3} \times \frac{4}{13}$ **d.** $\frac{4}{7} \times \frac{2}{3}$

5. WE20 Calculate the following using written methods, then check your answers with a calculator.

a. $\frac{4}{8} \times \frac{3}{9}$ **b.** $\frac{2}{5} \times \frac{1}{2}$ **c.** $\frac{3}{7} \times \frac{5}{6}$ **d.** $\frac{3}{8} \times \frac{4}{15}$

6. Calculate the following using written methods, then check your answers with a calculator.

a. $\frac{10}{11} \times \frac{22}{25}$ **b.** $\frac{24}{27} \times \frac{9}{8}$ **c.** $\frac{18}{32} \times \frac{64}{72}$ **d.** $\frac{48}{56} \times \frac{24}{60}$

7. Calculate the following using written methods, then check your answers with a calculator.

a. $\frac{15}{27} \times \frac{36}{45}$ **b.** $\frac{8}{49} \times \frac{14}{16}$ **c.** $\frac{4}{9} \times \frac{6}{8}$ **d.** $\frac{5}{25} \times \frac{12}{48}$

8. WE21 Calculate:

a. $\frac{1}{2}$ of $\frac{1}{4}$ **b.** $\frac{3}{4}$ of $\frac{2}{3}$ **c.** $\frac{5}{6}$ of $\frac{5}{6}$ **d.** $\frac{8}{9}$ of $\frac{1}{4}$

9. Calculate:

a. $\frac{7}{8}$ of 32 **b.** $\frac{9}{10}$ of 50 **c.** $\frac{3}{5}$ of 25 **d.** $\frac{4}{5}$ of 20

Understanding

10. WE22 Joshua's dad made 6 litres of cordial for his birthday party. Emily drank $\frac{1}{3}$ of the cordial, Tracy drank $\frac{1}{12}$ and Jonathan drank $\frac{1}{18}$. Calculate how much cordial, in litres, each person drank.

11. Zoe and Jimin play basketball with the Sharp Shooters. Each game lasts 40 minutes. Zoe played $\frac{4}{5}$ of last week's game and Jimin played $\frac{7}{8}$. Calculate how many minutes of the game:

a. Zoe played
b. Jimin played.




12. Mark's uncle gave him a family-size block of chocolate. He divided it into thirds to share with his two sisters. His friends Tao and Nick then arrived to visit, and Mark shared his portion of the chocolate with them, so that they each had the same amount.

a. Draw a block of chocolate with 9×6 pieces, and shade Mark's third of the block. Then draw lines to represent Tao's share.
b. Identify the fraction of the block of chocolate that Nick received.

13. WE23 A car's petrol tank holds 48 litres of fuel. The tank was full at the start of a trip.

a. By examining the gauge shown, determine what fraction of the tank of petrol has been used.
b. Determine how many litres of petrol have been used.



14. Answer the following questions.

a. State how many half pizzas are in 1 pizza.
b. State how many half pizzas are in 2 whole pizzas.
c. State how many half pizzas are in 5 whole pizzas.

Reasoning

15. **a.** Draw a quarter of a pie.
b. Shade half of this piece of pie.
c. Determine what fraction of the whole pie is shaded.
d. Complete the mathematical sentence $\frac{1}{4} \times \frac{1}{2} =$ __ to show how the answer was found.

16. To make a loaf of fruit bread in a breadmaker, the fruit needs to be added after the second rise stage and the top of the bread needs to be glazed two-thirds of the way through the baking stage. The recipe shows how long each stage of the total cycle takes.



Stage	Length of time
First knead	5 minutes
Second knead	20 minutes
First rise then punch down	40 minutes
Second rise then punch down	25 minutes
Third rise	50 minutes
Bake	40 minutes

a. State when the fruit should be added.
b. Express this length of time as a fraction of the total time in the breadmaker.
c. Calculate the length of time during which the bread should be glazed.

17. a. Without using a calculator, evaluate the following:

i. $\frac{1}{2} \times \frac{2}{3}$ **ii.** $\frac{1}{2} \times \frac{2}{3} \times \frac{3}{4}$ **iii.** $\frac{1}{2} \times \frac{2}{3} \times \frac{3}{4} \times \frac{4}{5}$

b. Describe any pattern you see in part **a**.
c. Hence, evaluate the solution to:

$$\frac{1}{2} \times \frac{2}{3} \times \frac{3}{4} \ldots \times \frac{98}{99} \times \frac{99}{100}$$

18. Gustave's monthly take-home pay is $2400. From this he spends a quarter on his home loan payments, one half on food and drink and one sixth on clothing. One half of the remainder goes into his savings account. Determine how much money Gustave deposits into his savings account each month.

19. On a given map, one kilometre is represented by $\frac{2}{9}$ cm. If a distance on the map is 27 cm, determine how many kilometres this represents.

20. Andrea requires $5\frac{2}{7}$ m of fabric to make a pattern on a quilt. One third of this fabric has to be red and $\frac{1}{4}$ must be green. Determine how many metres of red and green fabric she needs.

4.7 Dividing fractions

LEARNING INTENTION

At the end of this subtopic you should be able to:
- divide fractions.

4.7.1 Dividing fractions

eles-3808

- To divide fractions you need to know what their reciprocal is.
- The **reciprocal** of a fraction is found by turning the fraction upside down. So $\frac{3}{5}$ is the reciprocal of $\frac{5}{3}$.
- A whole number can be written as a fraction by putting it over 1. Therefore, the reciprocal of a whole number is 1 over the number. For example, since $4 = \frac{4}{1}$, the reciprocal of 4 is $\frac{1}{4}$.

WORKED EXAMPLE 24 Reciprocal of a proper fraction

Identify the reciprocal of $\frac{2}{3}$.

THINK	WRITE
Turn the fraction upside down and write the answer in a sentence.	The reciprocal of $\frac{2}{3}$ is $\frac{3}{2}$.


- To determine the reciprocal of a mixed number, first express it as an improper fraction.

WORKED EXAMPLE 25 Reciprocal of a mixed number


Determine the reciprocal of $1\frac{2}{3}$.

THINK	WRITE
1. Write $1\frac{2}{3}$ as an improper fraction.	$1\frac{2}{3} = \frac{5}{3}$
2. Turn the improper fraction upside down and write the answer in a sentence.	The reciprocal of $1\frac{2}{3}$ is $\frac{3}{5}$.

- Try to think of division as a question. For example, $10 \div 4$ can be interpreted as 'How many groups of 4 are there in 10?'



- Division of fractions follows the same logic. For example, $3 \div \frac{1}{2}$ can be interpreted as 'How many halves are there in 3?'



- This method is great for understanding the concept of division of fractions, but is not so good for evaluating many divisions involving fractions.

Dividing fractions

To divide fractions, multiply the first fraction by the reciprocal of the second fraction.

For example: $\frac{1}{3} \div \frac{2}{5} = \frac{1}{3} \times \frac{5}{2} = \frac{5}{6}$

This process can be remembered easily by the saying KEEP, CHANGE, FLIP.

$$\underset{\text{KEEP}}{\frac{3}{4}} \quad \underset{\text{CHANGE}}{\div} \quad \underset{\text{FLIP}}{\frac{2}{7}}$$
$$\downarrow \qquad \downarrow \qquad \downarrow$$
$$\frac{3}{4} \qquad \times \qquad \frac{7}{2}$$

WORKED EXAMPLE 26 Dividing fractions

Evaluate $\frac{2}{3} \div \frac{4}{9}$.


THINK	WRITE
1. Write the question.	$\frac{2}{3} \div \frac{4}{9}$
2. Keep the first fraction the same. Change the division sign to a multiplication sign and flip the second fraction.	$= \frac{2}{3} \times \frac{9}{4}$
3. Cancel diagonally.	$= \frac{\cancel{2}^{1}}{\cancel{3}^{1}} \times \frac{\cancel{9}^{3}}{\cancel{4}^{2}}$
4. Perform the multiplication.	$= \frac{3}{2}$

DISCUSSION

Explore what happens when you multiply and divide positive numbers by a fraction between 0 and 1. Discuss the results.

Digital technology

Scientific calculators can evaluate division of fractions.



Resources

eWorkbook Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)

Interactivities Individual pathway interactivity: Dividing rational numbers (int-4328)
Division of rational numbers (int-3948)

Exercise 4.7 Dividing fractions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13	2, 6, 8, 11, 14	3, 5, 9, 12, 15

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE24 Identify the reciprocals of each of the following.
   a. $\frac{3}{4}$ b. $\frac{2}{7}$ c. $\frac{6}{5}$ d. $\frac{5}{3}$ e. 5
2. Identify the reciprocals of each of the following.
   a. $\frac{5}{12}$ b. $\frac{9}{2}$ c. $\frac{5}{3}$ d. $\frac{10}{3}$ e. 20
3. Identify the reciprocals of each of the following.
   a. $\frac{1}{12}$ b. $\frac{3}{15}$ c. $\frac{2}{22}$ d. $\frac{1}{6}$ e. 1
4. WE25 Determine the reciprocals of these mixed numbers.
   a. $1\frac{2}{3}$ b. $4\frac{3}{7}$ c. $9\frac{2}{7}$ d. $3\frac{3}{8}$ e. $6\frac{9}{10}$
5. Determine the reciprocals of these mixed numbers.
   a. $3\frac{6}{7}$ b. $5\frac{1}{3}$ c. $7\frac{1}{2}$ d. $10\frac{2}{9}$ e. $2\frac{5}{9}$
6. Multiply each of these numbers by its reciprocal.
   a. $\frac{5}{7}$ b. $\frac{3}{5}$ c. $2\frac{1}{8}$

Understanding

7. WE26 Evaluate the following using written methods, then check your answers with a calculator.
   a. $\frac{1}{4} \div \frac{2}{3}$ b. $\frac{8}{9} \div \frac{7}{6}$ c. $\frac{1}{12} \div \frac{2}{3}$ d. $\frac{4}{11} \div \frac{5}{6}$ e. $\frac{10}{3} \div \frac{15}{21}$

8. Evaluate the following using written methods, then check your answers with a calculator.

a. $\frac{2}{7} \div \frac{20}{21}$ **b.** $\frac{4}{9} \div \frac{4}{9}$ **c.** $\frac{4}{7} \div 10$ **d.** $\frac{4}{3} \div 12$ **e.** $\frac{15}{11} \div 5$

9. Evaluate the following using written methods, then check your answers with a calculator.

a. $\frac{5}{6} \div \frac{3}{2}$ **b.** $\frac{3}{11} \div 6$ **c.** $\frac{9}{10} \div \frac{5}{7}$ **d.** $\frac{20}{17} \div \frac{5}{3}$ **e.** $\frac{50}{7} \div 5$

Reasoning

10. Lucy says that the following statement is correct.

$$3\frac{1}{2} \div \frac{4}{6} > \frac{4}{3} \div \frac{2}{15}$$

However, Lucy's friend Lily does not agree. Explain who is correct.

11. Mai is making sushi. The recipe requires $\frac{1}{4}$ cup of rice. She has a 2 kg bag of rice. If 1 cup of rice weighs 250 g, calculate the number of batches of the recipe she can make.



12. Maytreyi bought $1\frac{1}{2}$ kg of chocolates for her birthday party. She is going to give each friend attending her birthday $\frac{1}{10}$ kg. Calculate the number of friends attending her birthday party.

Problem solving

13. A plumber has a piece of pipe that is $\frac{26}{4}$ cm long. He divides the pipe into pieces that are $\frac{3}{2}$ cm long. Determine the number of pieces he has now.

14. Calculate the average of $\frac{1}{4}, \frac{1}{5}, \frac{1}{10}$ and $\frac{1}{20}$.

15. Determine the value of the following expression.

$$\frac{1}{2 + \frac{1}{2\frac{1}{2}}}$$

4.8 Working with mixed numbers

LEARNING INTENTION

At the end of this subtopic you should be able to:

- add, subtract, multiply and divide mixed numbers.

eles-3809

4.8.1 Adding and subtracting mixed numbers

- To add or subtract mixed numbers, first convert to improper fractions, and then add and subtract as usual.
- To perform operations on mixed numbers, first convert them to improper fractions, and then use the rules for operations on fractions to evaluate.

Working with mixed numbers

To add, subtract, multiply or divide mixed numbers, convert them to improper fractions and then perform the operation as usual.

WORKED EXAMPLE 27 Adding mixed numbers

Evaluate $2\frac{3}{4} + 1\frac{1}{2}$.

THINK	WRITE
1. Write the question.	$2\frac{3}{4} + 1\frac{1}{2}$
2. Convert each mixed number into an improper fraction.	$= \frac{11}{4} + \frac{3}{2}$
3. Write both fractions with the lowest common denominator (LCD).	$= \frac{11}{4} + \frac{3 \times 2}{2 \times 2}$ $= \frac{11}{4} + \frac{6}{4}$
4. Add the numerators.	$= \frac{17}{4}$
5. Convert to a mixed number if appropriate and write the answer.	$= 4\frac{1}{4}$

WORKED EXAMPLE 28 Subtracting mixed numbers

Evaluate $3\frac{1}{5} - 1\frac{3}{4}$.

THINK	WRITE
1. Write the question.	$3\frac{1}{5} - 1\frac{3}{4}$
2. Convert each mixed number into an improper fraction.	$= \frac{16}{5} - \frac{7}{4}$
3. Write both fractions with the lowest common denominator (LCD).	$= \frac{16 \times 4}{5 \times 4} - \frac{7 \times 5}{4 \times 5}$ $= \frac{64}{20} - \frac{35}{20}$
4. Subtract the numerators.	$= \frac{29}{20}$
5. Convert to a mixed number if appropriate and write the answer.	$= 1\frac{9}{20}$

Estimation

- Estimation can be used to determine approximate answers to addition and subtraction of mixed numbers.
- This allows you to check easily whether your answer to a calculation is reasonable.
- To estimate, add or subtract the whole number parts. The answer should be close to the result obtained by this method.

WORKED EXAMPLE 29 Checking answers by estimation

Evaluate $3\frac{1}{3} + 2\frac{1}{2}$ and check the answer by estimation.

THINK	WRITE
1. Write the question.	$3\frac{1}{3} + 2\frac{1}{2}$
2. Convert each mixed number into an improper fraction.	$= \frac{10}{3} + \frac{5}{2}$
3. Write both fractions with the lowest common denominator (LCD).	$= \frac{10 \times 2}{3 \times 2} + \frac{5 \times 3}{2 \times 3}$ $= \frac{20}{6} + \frac{15}{6}$
4. Add the numerators.	$= \frac{35}{6}$

5. Convert to a mixed number if appropriate.	$= 5\frac{5}{6}$
6. Check the answer by adding the whole numbers to determine an approximation.	$3\frac{1}{3} + 2\frac{1}{2} \simeq 3 + 2$ $3\frac{1}{3} + 2\frac{1}{2} \simeq 5$ The approximation shows that the answer we obtain should be close to 5.

eles-3810

4.8.2 Multiplying and dividing mixed numbers

- To multiply mixed numbers, first convert to improper fractions, and then multiply as usual.
- To divide mixed numbers, first convert them into improper fractions, and then divide as usual.

WORKED EXAMPLE 30 Multiplying mixed numbers

Evaluate $1\frac{1}{2} \times 3\frac{3}{5}$.

THINK	WRITE
1. Write the question.	$1\frac{1}{2} \times 3\frac{3}{5}$
2. Change mixed numbers to improper fractions and cancel if possible.	$= \frac{3}{\cancel{2}_{1}} \times \frac{\cancel{18}^{9}}{5}$
3. Multiply the numerators and then the denominators.	$= \frac{27}{5}$
4. Convert to a mixed number if appropriate and write the answer.	$= 5\frac{2}{5}$

WORKED EXAMPLE 31 Dividing mixed numbers

Evaluate $1\frac{1}{2} \div 3\frac{2}{5}$.

THINK	WRITE
1. Write the question.	$1\frac{1}{2} \div 3\frac{2}{5}$
2. Convert the mixed numbers to improper fractions.	$= \frac{3}{2} \div \frac{17}{5}$

3. Change the ÷ to × and flip the second fraction. $= \frac{3}{2} \times \frac{5}{17}$

4. Multiply the numerators, then the denominators and simplify the answer if necessary. $= \frac{15}{34}$

Resources

eWorkbook Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)

Interactivities Individual pathway interactivity: Working with mixed numbers (int-4330)
Addition and subtraction of mixed numbers (int-3951)

Exercise 4.8 Working with mixed numbers

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 5, 6, 8, 10, 14, 17, 20, 23	2, 7, 11, 12, 16, 18, 21, 24, 25	4, 9, 13, 15, 19, 22, 26

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE27, WE28 Evaluate the following, giving answers as mixed numbers in simplest form.

   a. $1\frac{1}{5} + 3\frac{1}{2}$ b. $3\frac{2}{3} - 2\frac{1}{3}$ c. $5\frac{2}{3} - 2\frac{1}{4}$ d. $9\frac{3}{8} + 4$

2. Evaluate the following, giving answers as mixed numbers in simplest form.

   a. $2\frac{3}{5} - 1\frac{1}{2}$ b. $3\frac{1}{2} + 2\frac{3}{4}$ c. $7 - 5\frac{2}{3}$ d. $2\frac{1}{3} - \frac{5}{6}$

3. Evaluate the following, giving answers as mixed numbers in simplest form.

   a. $3\frac{1}{2} - 1\frac{7}{8}$ b. $4\frac{3}{5} - 2\frac{9}{10}$ c. $5\frac{1}{4} - 1\frac{7}{12}$ d. $5\frac{3}{4} - 3\frac{5}{6}$

4. Evaluate the following, giving answers as mixed numbers in simplest form.

   a. $\frac{1}{5} + 2\frac{2}{7}$ b. $\frac{5}{8} + 3\frac{3}{4} - \frac{1}{2}$ c. $2\frac{2}{9} + 1\frac{1}{3} + \frac{1}{6}$ d. $4\frac{2}{3} + 1\frac{3}{8} - 3$

5. WE29 Evaluate the following and check the answers by estimation.

   a. $5\frac{1}{3} + 2\frac{1}{4}$ b. $1\frac{1}{6} + 2\frac{1}{2}$ c. $3\frac{1}{3} + 1\frac{1}{6}$ d. $6\frac{1}{2} - 2\frac{1}{4}$

6. WE30 Evaluate:

   a. $1\frac{1}{4} \times \frac{2}{3}$ b. $1\frac{1}{2} \times 1\frac{1}{2}$ c. $2\frac{5}{8} \times 1\frac{3}{4}$ d. $2\frac{1}{5} \times 3\frac{1}{2}$

7. Evaluate:

a. $3\frac{5}{6} \times 9\frac{5}{7}$ **b.** $5\frac{1}{5} \times 6\frac{2}{3}$ **c.** $3\frac{3}{4} \times 2\frac{2}{3}$ **d.** $\frac{7}{8} \times 3\frac{1}{3}$

8. WE31 Evaluate:

a. $1\frac{1}{4} \div \frac{3}{4}$ **b.** $\frac{9}{4} \div 3\frac{1}{2}$ **c.** $\frac{10}{3} \div 3\frac{1}{3}$ **d.** $7\frac{4}{9} \div \frac{1}{3}$


9. Evaluate:

a. $1\frac{1}{2} \div \frac{1}{2}$ **b.** $10\frac{9}{10} \div 4$ **c.** $3\frac{2}{7} \div 2\frac{1}{7}$ **d.** $3\frac{5}{8} \div 1\frac{3}{4}$

Understanding

10. One-third of a litre of cordial is mixed with $1\frac{1}{2}$ litres of water. Calculate how many litres of drink have been made.

11. The lengths of bolts and nails are often measured in inches. For the bolt shown, calculate the length of the threaded section if the total length of the bolt is $3\frac{1}{4}$ inches.



12. Julia is planning a holiday to the US. She has 5 months and has worked out the following itinerary. She will be in California for $1\frac{1}{2}$ months, in Colorado for $1\frac{2}{3}$ months and in Florida for $\frac{3}{4}$ of a month. The other state she will be visiting is New York. Determine how long she will spend in New York.



13. Theo is building a house. Before the frame of the house can be assembled, the footings need to be dug. The digging will take $3\frac{1}{2}$ days. The concrete slab that is then needed will take $2\frac{3}{4}$ days to pour and set. Determine how long it will be before Theo can start assembling the frame.

14. Felicity is dividing $1\frac{1}{2}$ kilograms of minced steak into 8 hamburger portions. Calculate how many kilograms of mince are in each portion.

15. Ned spends his school holidays helping his father with shearing sheep.

a. It takes Ned $\frac{1}{4}$ hour to shear one sheep. Calculate how many sheep Ned will shear in $5\frac{1}{2}$ hours.

b. Ned's father, Wesley, shears a sheep every $\frac{1}{12}$ of an hour. If Wesley worked continuously for 8 hours, calculate how many sheep he would shear.



16. Lachlan was looking for something to do one Saturday afternoon and his dad suggested he cook something for afternoon tea. Lachlan found a recipe for peanut butter muffins.



Ingredients:

$\frac{1}{4}$ cup sugar

$\frac{1}{4}$ cup margarine

$\frac{1}{2}$ cup peanut butter

2 eggs

$1\frac{1}{2}$ cups milk

$2\frac{1}{2}$ cups self-raising flour

$\frac{1}{4}$ teaspoon baking soda

Method:

Blend the sugar, margarine and peanut butter. Beat in the eggs and milk. Add the self-raising flour and baking soda. Place the mixture in greased muffin pans and sprinkle with cinnamon sugar. Bake for 15–20 minutes in a 200 °C oven.

This recipe makes 10 muffins, but Lachlan wants enough mixture to make 15. He needs to multiply the quantities by $1\frac{1}{2}$. Write the quantities of each ingredient Lachlan needs to make 15 muffins.

17. Anh bought $7\frac{3}{4}$ kg of prawns for a party and $\frac{3}{5}$ of them were eaten. Calculate how many kilograms of prawns were left over.


18. Teagan buys $8\frac{3}{4}$ kg of sugar. She wants to store it in containers that can hold $1\frac{1}{4}$ kg. Calculate how many containers she needs.





19. Max works as a train driver and is paid $21 per hour. If Max works on a public holiday, he is paid double time and a half, which means he earns $2\frac{1}{2}$ times his normal hourly rate. Calculate what Max earns per hour working on a public holiday.

Reasoning

20. To make the casing for a simple collapsible telescope, you need two cylinders, one of which fits inside the other.







a. Calculate the width of the cylinder in the middle diagram that would slide over the one shown at right.

b. Calculate the width of the cylinder in the left diagram that would slide into the one shown at right.

21. Worldwide figures indicate that $\frac{1}{10}$ of men are left-handed, while $\frac{2}{25}$ of women are left-handed. If there are 400 men in a room, calculate how many women would need to be there so that there are the same number of left-handed men as left-handed women.

22. Explain how you could you convince someone that $\frac{1}{2}$ of $3\frac{1}{3}$ is $1\frac{2}{3}$.

Problem solving

23. Five-eighths of a class were girls and $\frac{2}{3}$ of the girls were brunette.



a. Calculate what fraction of the class were brunette girls.

b. If there were 24 people in the class, calculate how many were brunette girls.

24. Michelle can run one lap of a cross-country course in $\frac{1}{5}$ hour.

a. Calculate how many laps she completed in $1\frac{1}{3}$ hours. (Assume she can keep up the same pace.)

b. Calculate the number of minutes it takes for Michelle to run one lap.

25. A skydiver opens his parachute at 846 m above ground level. He has already fallen five-sevenths of the distance to the ground. Calculate the height of the plane when he jumped.

26. A new vending machine stocking water and sports drinks was installed at the local gymnasium. The number of bottles sold each day over the first 5 weeks after its installation is shown.

4,	39,	31,	31,	50,	43,	60,	45,	57,	61,	18,	26,	3,	52,	51,	59,	33,
51,	27,	62,	30,	40,	3,	30,	37,	9,	33,	44,	53,	16,	22,	6,	42,	33,	19

The gymnasium realises that the number of daily sales varies, depending particularly on the weather. The machine is stocked with 60 bottles at the start of each day. The supplier advises that, because of electricity costs and other running expenses, the machine is not worthwhile having unless at least three-quarters of the bottles are sold on average 2 days per week.
Round these sales to the nearest 5 and analyse the figures to determine whether the gymnasium should keep the vending machine.



4.9 Percentages as fractions

LEARNING INTENTION

At the end of this subtopic you should be able to:
- convert percentages to fractions.

eles-3812

4.9.1 Definition of a percentage

- The term **per cent** means 'per hundred' or 'out of a hundred'.
- The symbol for per cent is %. For example, 7% means 7 out of 100.

WORKED EXAMPLE 32 Writing a percentage as a fraction

Write 47% as a fraction.

THINK	WRITE
Recall the definition of a percentage. 47% means 47 out of 100.	$47\% = \frac{47}{100}$

Percentages as fractions

- All percentages can be expressed as fractions.
  - To convert a whole number percentage into a fraction, write it over 100 and simplify.



WORKED EXAMPLE 33 Converting a percentage into a fraction

Write 20% as a fraction in simplest form.

THINK	WRITE
1. Write the percentage as a fraction with a denominator of 100.	$20\% = \frac{20}{100}$
2. Simplify the fraction.	$= \frac{1}{5}$

- To convert a percentage containing a decimal number into a fraction:
  - write it as a fraction over 100
  - change the numerator to a whole number by multiplying both the numerator and denominator by the appropriate power of 10
  - simplify if possible.

  For example: $28.2\% = \frac{28.2}{100} = \frac{282}{1000} = \frac{141}{500}$

WORKED EXAMPLE 34 Converting percentages to fractions

Write 36.4% as a fraction in simplest form.

THINK	WRITE
1. Write the percentage as a fraction out of 100.	$36.4\% = \frac{36.4}{100}$
2. Change the numerator to a whole number by multiplying it by an appropriate power of 10, and multiply the denominator by the same power of 10.	$= \frac{36.4 \times 10}{100 \times 10}$ $= \frac{364}{1000}$
3. Simplify the fraction.	$= \frac{91}{250}$

- To convert a percentage that is a proper fraction into a fraction, multiply the denominator by 100 and simplify if possible.
  For example: $\frac{5}{8}\% = \frac{5}{800} = \frac{1}{160}$
- To convert a mixed number percentage into a fraction:
  - change the mixed number into an improper fraction
  - multiply the denominator by 100
  - simplify if possible.

  For example: $12\frac{1}{2}\% = \frac{25}{2}\% = \frac{25}{200} = \frac{1}{8}$

Converting percentages into fractions

In simple terms, to convert a percentage into a fraction, place the percentage as a fraction over 100, then manipulate so that both the numerator and denominator are whole numbers with no common factors.

$$x\% = \frac{x}{100}$$

WORKED EXAMPLE 35 Converting percentages to fractions

Write the following percentages as fractions in simplest form.

a. $\frac{1}{4}\%$ **b.** $15\frac{1}{3}\%$

THINK	WRITE
a. 1. Write the percentage and then multiply the denominator by 100.	a. $\frac{1}{4}\% = \frac{1}{4 \times 100}$
2. Simplify.	$= \frac{1}{400}$

b. 1. Convert the mixed number to an improper fraction.

2. Multiply the denominator by 100.

3. Simplify the fraction.

b. $15\frac{1}{3}\% = \frac{46}{3}\%$

$= \frac{46}{3 \times 100}$

$= \frac{46}{300}$

$= \frac{23}{150}$

Resources

eWorkbook	Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Digital documents	SkillSHEET Simplifying fractions with a denominator of 100 (doc-6470) SkillSHEET Converting a mixed number into an improper fraction (doc-6471) SkillSHEET Changing fractions to equivalent fractions with a denominator of 100 (doc-6472)
Interactivities	Individual pathway interactivity: Percentages as fractions (int-4343) Percentages as fractions (int-3992)

Exercise 4.9 Percentages as fractions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 9, 12, 15, 16, 17, 19, 22	2, 4, 7, 10, 13, 20, 23, 24	5, 8, 11, 14, 18, 21, 25

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE32 Write the following percentages as fractions.
   a. 17 % **b.** 29 % **c.** 79 % **d.** 99 % **e.** 3 %
2. Write the following percentages as fractions.
   a. 19% **b.** 33% **c.** 9% **d.** 243% **e.** 127%
3. WE33 Write the following percentages as fractions in simplest form.
   a. 50% **b.** 80% **c.** 35% **d.** 60% **e.** 10%
4. Write the following percentages as fractions in simplest form.
   a. 45% **b.** 12% **c.** 5% **d.** 74% **e.** 2%
5. Write the following percentages as fractions in simplest form. Change the answer to a mixed number where appropriate.
   a. 150% **b.** 180% **c.** 200% **d.** 500% **e.** 112%
6. WE34 Write the following percentages as fractions in simplest form.
   a. 3.5% **b.** 7.2% **c.** 19.7% **d.** 32.4%

7. Write the following percentages as fractions in simplest form.

a. 15.5% **b.** 16.2% **c.** 28.3% **d.** 41.38%

8. Write the following percentages as fractions in simplest form.

a. 18.14% **b.** 57.99% **c.** 12.15% **d.** 0.05%

9. WE35 Write the following percentages as fractions in simplest form.

a. $\frac{1}{2}\%$ **b.** $\frac{1}{5}\%$ **c.** $\frac{2}{3}\%$ **d.** $\frac{1}{10}\%$ **e.** $\frac{6}{11}\%$

10. Write the following percentages as fractions in simplest form.

a. $8\frac{1}{4}\%$ **b.** $20\frac{2}{3}\%$ **c.** $9\frac{2}{3}\%$ **d.** $15\frac{1}{2}\%$ **e.** $11\frac{1}{5}\%$

11. Write the following percentages as fractions in simplest form. Leave the answer as a mixed number where appropriate.)

a. $10\frac{3}{8}\%$ **b.** $11\frac{2}{3}\%$ **c.** $150\frac{1}{2}\%$ **d.** $120\frac{1}{2}\%$ **e.** $33\frac{1}{3}\%$

Understanding

12. MC 40% as a fraction in simplest form is:

A. $\frac{1}{4}$ **B.** $\frac{2}{5}$ **C.** $\frac{4}{100}$ **D.** $\frac{4000}{1}$ **E.** $\frac{0.4}{1000}$

13. MC $10\frac{1}{2}\%$ as a fraction is:

A. $\frac{21}{2}$ **B.** $\frac{10.5}{100}$ **C.** $\frac{2100}{2}$ **D.** $\frac{42}{100}$ **E.** $\frac{21}{200}$

14. MC 1.5% as a fraction in simplest form is:

A. $\frac{1.5}{100}$ **B.** $\frac{3}{100}$ **C.** $\frac{3}{200}$ **D.** $\frac{15}{100}$ **E.** $\frac{15}{1000}$

15. Imran saves 20% of his pocket money each week. Calculate the fraction that he saves.

16. In one game, 35% of a football team is injured. Calculate what fraction of the team is injured.



17. Each week Jodie spends 45% of her wages at the supermarket. Calculate what fraction of Jodie's wages is spent at the supermarket.


18. Calculate what fraction of a class were born overseas if 68% were born in Australia.

Reasoning

19. Of the students in a Year 7 class, 80% have pets and 20% have blue eyes.


- **a.** Calculate what fraction of students have pets.
- **b.** Calculate what fraction of students have blue eyes.
- **c.** Explain whether this means that none of the students with blue eyes have pets.

20. a. In a molecule of methane (natural gas), 80% of the atoms are hydrogen. Calculate the fraction of the methane molecule that is composed of hydrogen atoms.



Methane molecule

- **b.** The diagram represents a molecule of glycolaldehyde, a simple form of sugar found in the gas surrounding a young star called IRAS 16293-2422, located around 400 light-years away from Earth. Hydrogen atoms make up 50% of the atoms of this molecule. Calculate the fraction of the glycolaldehyde molecule that is composed of hydrogen atoms.



Glycolaldehyde molecule

- **c.** Although both molecules have the same number of hydrogen atoms, explain why they represent different fractions.

21. Shirley plays basketball in her school's team. In the last game she scored 50 baskets from 75 shots but in the previous game she scored 45 baskets from 60 shots.



- **a.** Compare the percentage of baskets scored relative to the number of shots for each game to determine which game she performed best in.
- **b.** Explain how the percentage is affected by:
  - **i.** increasing the number of baskets when the number of shots stays the same
  - **ii.** increasing the number of shots when the number of baskets stays the same
  - **iii.** increasing both the number of baskets and the number of shots at the same percentage rate.

Problem solving



22. Less than 50% of the estimated 200 000 Australian invertebrate species have been described. Determine what fraction this is.

23. If the unemployment rate in Australia is 8%, calculate :

- **a.** what fraction of the population is unemployed
- **b.** what fraction of the population is employed
- **c.** out of 100 people, the number you would expect to be unemployed.

24. Determine what fraction remains if:

- **a.** 65% of winnings have been spent
- **b.** 19% of an audience hated a movie
- **c.** all stock was discounted by 15%
- **d.** 93.5% of the school population supports the uniform policy.

25. Seventeen per cent of visitors to Australia are from New Zealand.

- **a.** State the fraction of visitors to Australia from New Zealand.
- **b.** Calculate the fraction of visitors to Australia not from New Zealand.
- **c.** Out of 100 visitors to Australia, state how many you would expect to be from New Zealand.

4.10 Calculating percentages of an amount

LEARNING INTENTION

At the end of this subtopic you should be able to:

- calculate percentages of amounts using fractions.

4.10.1 Calculating percentages of an amount using fractions

eles-3814

- To calculate a percentage of an amount using fractions, follow these steps.
  Step 1: Convert the percentage into a fraction.
  Step 2: Multiply by the amount.
- When calculating a percentage of an amount, the unit of the answer will always be the unit of the initial quantity. For example, the percentage of an amount of kilograms will be a certain number of kilograms.

COLLABORATIVE TASK: Elastic percentages



Equipment: scissors, wide rubber bands, rulers, A4 paper

1. Working in pairs, cut a rubber band in half to make one long rubber strip.
2. Use your ruler to draw an even scale on the rubber strip from 0 to 100, using intervals of 10. Make sure the rubber strip is not stretched in any way during this process.
3. Select five different objects around the classroom for which you will identify a percentage of their length, width or height; an object may be a book, a pencil or even someone's arm.

4. On an A4 sheet of paper, write the percentage that you will measure for each object.
   Your teacher may allocate your pair a percentage, or you may like to choose your own. Measure the same percentage for each of your objects; for example, you may choose to calculate 60% of the heights of a chair, a table, a computer screen, a poster and a bookshelf.
5. For each of your five objects, work with your partner to record the measurement of your given percentage using the following steps.
   - Stretch the rubber strip along the edge of the object that you wish to measure. The 0 mark on the strip must be at one end of the object you are measuring, and the 100 mark must be at the other end of the object. Hold onto the rubber strip tightly.
   - Place a pencil point on the object next to the position of your percentage on the rubber strip.
   - Use a ruler to measure the distance from the end of the object to the pencil point.
   - Draw a line of this length on your sheet of paper, and then label the line with a description of the object that you measured.
6. Each line on your paper represents the same percentage of different lengths. With your partner, discuss why the lines are different lengths.
7. As a class, discuss the relationship between the size of a percentage and the size of the whole object being measured. For example, is 60% of the length of a book more or less than 60% of the height of a door? Why?

WORKED EXAMPLE 36 Calculating a percentage of an amount using fractions

Calculate 40% of $135.

THINK	WRITE
1. Write the question.	40% of $135
2. Write the percentage as a fraction with a denominator of 100, change *of* to × and write the amount as a fraction over 1.	$= \frac{40}{100} \times \frac{135}{1}$
3. Simplify as appropriate.	$= \frac{40}{20} \times \frac{27}{1}$ $= \frac{2}{1} \times \frac{27}{1}$
4. Perform the multiplication.	$= \frac{54}{1}$
5. State the answer.	= $54

WORKED EXAMPLE 37 Calculating a percentage of an amount using fractions

Of the 250 students selected at random to complete a survey, 18% were in Year 11. Calculate how many students were in Year 11.

THINK	WRITE
1. Decide what percentage of the total is required and write an expression to determine the percentage of the total.	18% of 250
2. Write the percentage as a fraction, change *of* to × and write the total as a fraction.	$= \frac{18}{100} \times \frac{250}{1}$

3. Simplify as appropriate.

$$= \frac{18}{2} \times \frac{5}{1}$$
$$= \frac{9}{1} \times \frac{5}{1}$$

4. Perform the multiplication.

$$= \frac{45}{1}$$
$$= 45$$

5. Answer the question by writing a sentence.

45 of the 250 students were in Year 11.

DISCUSSION

What method would you use to calculate 60% of an amount? Are there other ways? Which is the most efficient?

Resources

eWorkbook	Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Digital documents	SkillSHEET Multiplying fractions by a whole number (doc-6475) SkillSHEET Rounding money to the nearest 5 cents (doc-6477) SkillSHEET Rounding to the nearest whole number (doc-6476)
Video eLesson	Percentages of an amount (eles-1882)
Interactivities	Individual pathway interactivity: Calculating percentages of an amount (int-4346) Percentages of an amount using fractions (int-3996)

Exercise 4.10 Calculating percentages of an amount

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 9, 12, 16, 18, 23, 25, 28, 31	2, 4, 7, 10, 13, 15, 19, 21, 24, 27, 29, 32	5, 8, 11, 14, 17, 20, 22, 26, 30, 33

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Copy each of the following problems and then calculate the answers by completing the working.

a. $90\% \text{ of } 200 = \frac{90}{100} \times \frac{200}{1}$ **b.** $8\% \text{ of } 50 = \frac{8}{100} \times \frac{50}{1}$ **c.** $50\% \text{ of } 120 = \frac{50}{100} \times \frac{120}{1}$

2. Copy each of the following problems and then calculate the answers by completing the working.

a. $5\% \text{ of } 30 = \frac{5}{100} \times \frac{30}{1}$ **b.** $15\% \text{ of } 70 = \frac{15}{100} \times \frac{70}{1}$ **c.** $65\% \text{ of } 120 = \frac{65}{100} \times \frac{120}{1}$

3. WE36 Calculate the following by converting the percentage to a fraction.
   a. 50% of 20 b. 20% of 80 c. 10% of 30 d. 9% of 200 e. 40% of 15

4. Calculate the following by converting the percentage to a fraction.
   a. 12% of 50 b. 70% of 110 c. 80% of 5000 d. 44% of 150 e. 68% of 25

5. Calculate the following by converting the percentage to a fraction.
   a. 52% of 75 b. 38% of 250 c. 110% of 50 d. 150% of 8 e. 125% of 20

6. Calculate the following by converting the percentage to a fraction. Write the answer as a mixed number.
   a. 18% of 20 b. 16% of 30 c. 11% of 70 d. 74% of 25 e. 66% of 20

7. Calculate the following by converting the percentage to a fraction. Write the answer as a mixed number.
   a. 55% of 45 b. 15% of 74 c. 95% of 62 d. 32% of 65 e. 82% of 120

8. MC 45% written as a fraction is:
   A. $\frac{45}{100}$ B. $\frac{45}{1}$ C. $\frac{450}{1}$ D. $\frac{1}{45}$ E. $\frac{90}{45}$

9. MC To evaluate 17% of 22, *of* should be changed to:
   A. ÷ B. of C. + D. × E. −

10. MC Select which of the following would determine 15% of 33.
    A. 15 of 33 B. $\frac{15}{1} \times 33$ C. $\frac{15}{100} \times \frac{33}{100}$ D. $\frac{15}{1} \times \frac{33}{100}$ E. $\frac{15}{100} \times \frac{33}{1}$

11. MC 60% of 30 is:
    A. $19\frac{4}{5}$ B. $\frac{31}{5}$ C. 186 D. 19 E. 18

12. MC 8% of 50 equals:
    A. 40 B. 4 C. 140 D. 14 E. 16

13. MC 40% of 160 equals:
    A. 400 B. 6400 C. 640 D. 0.64 E. 64

14. MC 60% of 30 equals:
    A. 180 B. 1.8 C. 400 D. 18 E. 300

Understanding

15. WE37 Of the 300 Year 7 students selected to complete a questionnaire on ice cream, 70% said that their favourite flavour was chocolate chip. Calculate how many students favoured chocolate chip ice cream.



16. A thunder day at a given location is a calendar day on which thunder is heard at least once. About 20% of days near Darwin are thunder days.
    Calculate the number of thunder days you would expect in Darwin in one year.

17. Two per cent of Australians play lawn bowls. In a group of 50 people, state how many you would expect to play lawn bowls.

18. Two thousand people entered a marathon. Some walked and the rest jogged. If 20% walked, calculate:

a. what percentage jogged
b. how many people jogged.



19. William earns $550 per week. He has just received a pay rise of 4%.

a. Calculate how much more William will earn per week.
b. Calculate William's total pay after the pay rise.

20. The lotto jackpot for Saturday night is $20 million. If you win 8% of the jackpot, calculate how much money you would win.

21. The Australian cricket team was fined 15% of their match payments for a slow over rate. If the team was paid $80 000 for the match, calculate how much the team was fined.

22. Australia has 315 species of mammals. Of these, 15% are threatened. Calculate how many threatened species of mammals Australia has. Round your answer to the nearest whole number.

23. Two million people attended at least one AFL game last year. Of these people, 30% attended 10 games or more. Calculate how many people attended 10 or more AFL games.



24. The water content of a particular brand of shampoo is 35%. After performing a calculation, Peter claims that an 800 mL bottle of this particular shampoo contains 28 mL of water.

a. Explain why Peter's calculation is incorrect.
b. Calculate how much of the shampoo in the 800 mL bottle is actually water.



25. In Sydney, 14% of adults use a telephone to pay bills and 38% use the internet. If 50 adults need to pay bills, calculate how many will use the:

a. telephone **b.** internet.

26. In Weburbia, 85% of all households have access to the internet. If there were 34 houses in Website Street, calculate how many you would expect to have access to the internet. Write the answer to the nearest whole number.

27. Terry runs a factory that makes parts for trucks. He has increased his staff by 12%. If Terry originally had 34 workers, calculate how many workers he has after the increase. Write the answer to the nearest whole number.

Reasoning

28. In the year 2020, 60% of households in Geelong had a smoke alarm. Of these smoke alarms, 94% worked. A street in Geelong has 20 houses.

- **a.** Calculate how many houses you would expect to have a smoke alarm.
- **b.** Calculate how many would have a smoke alarm that works. Write the answer to the nearest whole number.

29. In some parts of Africa, 6% of women die during pregnancy or childbirth. Of 50 women living in these parts who are pregnant, calculate how many are likely to die during pregnancy or childbirth.

30. For a radioactive substance, a half-life is the time it takes for half of the radioactive atoms in the substance to decay (lose their radioactivity). For 400 g of a given radioactive substance, the decay rate is 50% every 20 days.



- **a.** Calculate the quantity of radioactive substance left after 20 days, 40 days, 60 days, 80 days and 100 days.
- **b.** Calculate the percentage of the initial quantity remaining after 20 days, 40 days, 60 days, 80 days and 100 days.
- **c.** The quantity of the radioactive substance halves every 20 days. Explain why the percentage decrease is smaller after every 20 days.

Problem solving

31. Squeezy fruit drink is 36% pure orange juice and 64% water. If 1 litre of Squeezy fruit drink is mixed with 600 mL of water, determine the concentration of juice in the new mixture.

32. The students in Year 7A were voting for class captain. There were only two candidates. Rachel received 84% of the votes and Susi received 28% of the votes. It was then discovered that some students had voted twice. If the class consisted of 25 students, determine how many of them voted twice.



33. A department store stocked a selection of denim jeans. At the start of December, the store had 320 of these jeans. During December, it sold 50% of the jeans. In January, it sold 25% of the remaining denim jeans. Determine how many were left at the end of January.

4.11 One amount as a percentage of another

LEARNING INTENTION

At the end of this subtopic you should be able to:

- express an amount as a percentage of another amount.

4.11.1 One amount as a percentage of another

eles-3815

- To express one amount as a percentage of another, write the amounts as a fraction $\frac{\text{amount}}{\text{total amount}}$, then convert the fraction to a percentage.
  (*Remember:* To change a fraction into a percentage, multiply by 100 and add the % sign.)
- When expressing one amount as a percentage of another, make sure that both amounts are in the same unit.

WORKED EXAMPLE 38 Expressing one amount as a percentage of another

Express:
a. **15 as a percentage of 20**
b. **9 as a percentage of 33. Write the answer as a mixed number.**

THINK	WRITE
a. 1. Write the amount as a fraction of the total: $\frac{\text{amount}}{\text{total amount}}$.	a. $\frac{15}{20}$
2. Multiply by $\frac{100}{1}$ and include the % sign.	$= \frac{15}{20} \times \frac{100}{1}\%$
3. Simplify and then multiply.	$= \frac{15}{1} \times \frac{5}{1}\%$ $= \frac{75}{1}\%$
4. State the answer.	$= 75\%$
b. 1. Write the amount as a fraction of the total: $\frac{\text{amount}}{\text{total amount}}$.	b. $\frac{9}{33}$
2. Multiply by $\frac{100}{1}$ and include the % sign.	$= \frac{9}{33} \times \frac{100}{1}\%$
3. Simplify and then multiply.	$= \frac{3}{11} \times \frac{100}{1}\%$ $= \frac{300}{11}\%$
4. Write as a mixed number by dividing the denominator into the numerator.	$= 27\frac{3}{11}\%$

WORKED EXAMPLE 39 Calculating percentages with different units

Express 45c as a percentage of $2.

THINK	WRITE
1. Write the larger amount using the smaller unit.	$\$2 = 200$ cents
2. Write the first amount as a fraction of the second amount: $\frac{\text{amount}}{\text{total amount}}$.	$\frac{45}{200}$
3. Multiply by $\frac{100}{1}$ and include the % sign.	$= \frac{45}{200} \times \frac{100}{1}\%$
4. Simplify and then multiply.	$= \frac{45}{2} \times \frac{1}{1}\%$ $= \frac{45}{2}\%$

5. Convert to a mixed number. $= 22\frac{1}{2}\%$

6. Write the answer. 45c is $22\frac{1}{2}\%$ of \$2.

WORKED EXAMPLE 40 Calculating percentages of test marks


Kye obtained 17 out of 30 on his Science test. Calculate his percentage score. Round your answer to the nearest whole number.



THINK	WRITE
1. Write the amount as a fraction of the total: $\frac{\text{amount}}{\text{total amount}}$.	$\frac{17}{30}$
2. Multiply by $\frac{100}{1}$ and include the % sign.	$= \frac{17}{30} \times \frac{100}{1}\%$
3. Simplify and then multiply.	$= \frac{17}{3} \times \frac{10}{1}\%$ $= \frac{170}{3}\%$
4. Convert to a mixed number.	$= 56\frac{2}{3}\%$
5. Round to the nearest whole number. (If the fraction is a half or more, add one to the number.)	$\approx 57\%$
6. Write the answer as a sentence.	Kye obtained 57% for his Science test.

Digital technology

Scientific calculators can calculate one amount as a percentage of another. The answer could be either in fraction or mixed number format.



Resources

eWorkbook Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)

Interactivities Individual pathway interactivity: One amount as a percentage of another (int-4347)
One amount as a percentage of another (int-3998)

Exercise 4.11 One amount as a percentage of another

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 12, 14, 21, 23, 26	2, 5, 8, 11, 15, 17, 19, 22, 24, 27, 28	3, 6, 9, 13, 16, 18, 20, 25, 29, 30

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE38a Express:
   - a. 2 as a percentage of 10
   - b. 13 as a percentage of 52
   - c. 8 as a percentage of 80
   - d. 8 as a percentage of 20
   - e. 15 as a percentage of 60.

2. Express:
   - a. 120 as a percentage of 150
   - b. 8 as a percentage of 25
   - c. 12 as a percentage of 30
   - d. 40 as a percentage of 200
   - e. 10 as a percentage of 200.

3. WE38b Express (writing the answers as mixed numbers):
   - a. 180 as a percentage of 720
   - b. 63 as a percentage of 200
   - c. 25 as a percentage of 400
   - d. 32 as a percentage of 500
   - e. 620 as a percentage of 3000.

4. Express (writing the answers as mixed numbers):
   - a. 70 as a percentage of 80
   - b. 12 as a percentage of 42
   - c. 52 as a percentage of 78
   - d. 11 as a percentage of 30
   - e. 4 as a percentage of 15.

5. Express (writing the answers as mixed numbers):
   - a. 5 as a percentage of 70
   - b. 4 as a percentage of 18
   - c. 3 as a percentage of 7
   - d. 64 as a percentage of 72
   - e. 15 as a percentage of 21.

6. Express (rounding all answers to the nearest whole number):
   - a. 7 as a percentage of 42
   - b. 18 as a percentage of 54
   - c. 95 as a percentage of 150
   - d. 7 as a percentage of 65.

7. Express (rounding all answers to the nearest whole number):
   - a. 30 as a percentage of 36
   - b. 14 as a percentage of 18
   - c. 80 as a percentage of 450
   - d. 8 as a percentage of 68.

8. WE39 Express the first amount as a percentage of the second amount.
   - a. 30c and $3
   - b. 200 m and 6 km
   - c. 5 mm and 4 cm

9. Express the first amount as a percentage of the second amount.
   - a. 6 days and 3 weeks
   - b. 15 minutes and 1 hour
   - c. 25 mL and 2 L

10. MC 4 as a percentage of 50 is:
    - A. 2%
    - B. 12.5%
    - C. 46%
    - D. 8%
    - E. 4%

11. MC 9 out of 36 as a percentage is:
    - A. 25%
    - B. 9%
    - C. 400%
    - D. 27%
    - E. 36%

12. MC 14 as a percentage of 35 is:

A. 14% **B.** 40% **C.** 20% **D.** 35% **E.** $2\frac{1}{2}\%$

13. MC Alice got 42 out of 60 for her Mathematics test. Her mark as a percentage is:

A. 58% **B.** 60% **C.** 30% **D.** 42% **E.** 70%

Understanding

14. WE40 Ash Barty has won 7 out of her last 10 singles matches. Calculate the number of wins in her last 10 matches as a percentage.



15. Three out of five people prefer chocolate ice cream to vanilla. Calculate what percentage of people prefer chocolate ice cream to vanilla.

16. Caillan's pocket money increased from $15 per week to $20 per week.

a. Calculate how much Caillan's pocket money has increased by.

b. Calculate this as a percentage increase.

17. Daniel earns $500 per week. He spends $50 on petrol, $70 on rent and $60 on food.

a. Calculate the percentage Daniel spends on:

i. petrol **ii.** rent **iii.** food.

b. Calculate what percentage of his total wage Daniel spends on petrol, rent and food combined.

c. Calculate the percentage Daniel has left.



18. David shot 40 baskets from the free-throw line. Twenty-five of the 40 shots went in. Calculate the percentage of scored shots.

19. Jordan had a mass of 60 kg. After one month of not eating fast food, he lost 4 kg. Calculate his weight loss as a percentage.

20. After practising for one month, Tayla increased the speed of her tennis serve from 120 km/h to 140 km/h. Give exact answers for the following.

a. Calculate how much her serve speed increased by.

b. Calculate this as a percentage increase.



21. There are 28 students in a class. A survey showed that 12 walk home, 8 catch a bus and 8 ride in a car. Write the answers as mixed numbers.

a. Calculate the percentage of students who walk.

b. Calculate the percentage of students who catch a bus.

c. Calculate the total percentage who walk or catch a bus.

d. Calculate the percentage of students who do not walk.

22. During one AFL season, the GWS Giants won 16 out of 22 games. Calculate the percentage of games the Giants lost.

Reasoning

23. A baker uses 200 g of flour for 500 g of dough in one recipe, and 250 g of flour for 500 g of dough in another recipe.

- **a.** Identify which recipe contains the higher percentage of flour. Explain your choice..
- **b.** Explain what happens when the quantity of flour is increased but the quantity of dough remains constant.

24. **a.** If you increase $100 by 25% and then decrease the new amount by 25%, will you end up with more than $100, less than $100 or exactly $100? Give reasons for your answer.

- **b.** Choose another amount and another percentage to test your reasoning.

25. My mother is four times older than I am. My sister is 75% of my age. She is also 10% of my grandfather's age. My father is 50, which is 2 years older than my mother. Calculate how old my sister and my grandfather are.

Problem solving

26. The teacher's mark book shows Karina has achieved the following test results in Maths.

Topic	Probability	Measurement	Algebra	Equations	Geometry
Score	$\frac{15}{20}$	$\frac{13}{15}$	$\frac{27}{30}$	$\frac{70}{80}$	$\frac{95}{100}$
Percentage					

- **a.** Copy and complete the table to show Karina's percentage for each test. Round answers to the nearest whole number.
- **b.** Compare the percentage results to determine which test Karina performed best in.
- **c.** Calculate Karina's average percentage mark by adding up the percentages and dividing by 5, the number of tests.

27. Determine which of the following quantities represents:

- **a.** the highest percentage
- **b.** the lowest percentage
- **c.** the same percentage.

200 g out of 500 g
300 g out of 450 g
420 g out of 840 g
350 g out of 700 g

28. Suggest why we need to be able to express one quantity as a percentage of another quantity.

29. A type of concrete uses 10 kg of cement for a quantity of 65 kg of concrete. Another type of concrete uses 10 kg of cement for 85 kg of concrete.

- **a.** Explain which type of concrete contains the higher percentage of cement.
- **b.** Explain what happens when the quantity of cement is constant but the quantity of concrete increases.

30. Roseanne is planning a tour of Australia. She calculates that 70% of the distance will be on sealed roads and the remainder on dirt roads. If there are 1356 km of dirt roads, determine how long Roseanne's journey will be.



4.12 Common percentages and short cuts

LEARNING INTENTION

At the end of this subtopic you should be able to:

- recognise commonly used percentages
- use common percentages as short cuts to calculate related percentages.

4.12.1 Common percentages and short cuts

eles-3816

- Common percentages that are often used in everyday life include 10%, 20%, 25%, 50%, 75%.
- It is useful to remember the fraction equivalents of the commonly used percentages to make calculations involving them quicker and easier.
- The table below shows the fractional equivalents of some commonly used fractions and how to use these to speed up calculations.

Percentage	Fraction	How to calculate this percentage
1%	$\frac{1}{100}$	Divide by 100
5%	$\frac{1}{20}$	Divide by 20
10%	$\frac{1}{10}$	Divide by 10
$12\frac{1}{2}\%$	$\frac{1}{8}$	Divide by 8
20%	$\frac{1}{5}$	Divide by 5

Percentage	Fraction	How to calculate this percentage
25%	$\frac{1}{4}$	Divide by 4
$33\frac{1}{3}\%$	$\frac{1}{3}$	Divide by 3
50%	$\frac{1}{2}$	Divide by 2
$66\frac{2}{3}\%$	$\frac{2}{3}$	Divide by 3, then multiply by 2
75%	$\frac{3}{4}$	Divide by 4, then multiply by 3

- Calculating 10% without a calculator is easy. As it is equivalent to dividing by 10, the decimal place just needs to be moved 1 space to the left. Once you have found 10% of the amount, it is easy to calculate some other percentages. For example:
  - to calculate 5%, halve 10%
  - to calculate 20%, double 10%.

Short cut for calculating whole number percentages

Calculate 1% by dividing the amount by 100 (move the decimal point 2 spaces to the left), then multiply 1% by the whole number that you are looking for.

For example, to calculate 12%, calculate 1%, then multiply by 12.

WORKED EXAMPLE 41 Calculating 10% of an amount

Calculate 10% of each of the following, rounding the answer to the nearest 5 cents.
a. $37 **b. $120**

THINK	WRITE
a. Write the question and move the position of the decimal point 1 place to the left for the answer. Remember that if there is no decimal point, put it at the end of the number. ($37 = $37.00)	a. 10% of $37 = $3.70
b. Write the question and move the position of the decimal point 1 place to the left for the answer.	b. 10% of $120 = $12

WORKED EXAMPLE 42 Calculating common percentages of an amount

Calculate:
a. 5% of $180 **b. 20% of $7** **c. 25% of $46**

THINK	WRITE
a. 1. Calculate 10% of the amount.	a. 10% of $180 = $18
2. Calculate 5% by halving the amount obtained in step 1. Write the answer.	5% of $180 = $18 ÷ 2 = $9
b. 1. Calculate 10% of the amount.	b. 10% of $7 = $0.70
2. Calculate 20% by doubling the amount obtained in step 1. Write the answer.	20% of $7 = 2 × $0.70 = $1.40
c. 1. To calculate 25% of an amount divide it by 4.	25% of $46 = $46 ÷ 4
2. Perform the division.	= $11.50
3. Write the answer.	25% of $46 = $11.50

WORKED EXAMPLE 43 Calculating percentages using short cuts

Calculate:
a. 12% of $53 **b. 43% of $120**
Round your answers to the nearest 5 cents.

THINK	WRITE
a. 1. Break up the percentage into lots of 10% and 1%.	a. 12% = 10% + 2 × 1%
2. Calculate 10% of the amount.	10% of $53 = $5.30
3. Calculate 1% of the amount and then double.	1% of $53 = $0.53 2% of $53 = 2 × $0.53 = $1.06
4. Determine 12% of the amount by adding 10% and 2 × 1%.	12% of 53% = $5.30 + $1.06 = $6.36
5. Round the answer to the nearest 5 cents.	= $6.35

Alternatively, you could use the short-cut method shown below.

1. First calculate 1% of \$53 by moving the decimal point 2 places to the left.

$1\% \text{ of } \$53 = \$0.53$

2. Multiply by 12.

$$\begin{aligned} 12\% \text{ of } \$53 &= 12 \times 1\% \text{ of } \$53 \\ &= 12 \times \$0.53 \\ &= \$6.36 \end{aligned}$$

3. Round the answer to the nearest 5 cents.

$= \$6.35$

b. 1. Break up the percentage into lots of 10% and 1%.

b. $43\% = 4 \times 10\% + 3 \times 1\%$

2. Calculate 10% and 1% of the amount.

$$\begin{aligned} 10\% \text{ of } \$120 &= \$12 \\ 1\% \text{ of } \$120 &= \$1.20 \end{aligned}$$

3. Use the values of 10% and 1% to calculate 43% of \$120.

$$\begin{aligned} 43\% \text{ of } \$120 &= 4 \times \$12 + 3 \times \$1.20 \\ &= \$48 + \$3.60 \\ &= \$51.60 \end{aligned}$$

Alternatively, you could use the short-cut method shown below.

1. First calculate 1% of \$120 by moving the decimal point 2 places to the left.

$1\% \text{ of } \$120 = \$1.20$

2. Multiply by 43 and write the answer.

$$\begin{aligned} 43\% \text{ of } \$120 &= 43 \times 1\% \text{ of } \$120 \\ &= 43 \times \$1.20 \\ &= \$51.60 \end{aligned}$$

Resources

eWorkbook Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)

Interactivities Individual pathway interactivity: Common percentages and short cuts (int-4348)
Common percentages and short cuts (int-3999)

Exercise 4.12 Common percentages and short cuts

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13, 16, 19, 22, 24, 27, 30, 33	2, 5, 8, 11, 14, 17, 20, 23, 25, 28, 31, 34	3, 6, 9, 12, 15, 18, 21, 26, 29, 32, 35

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title on www.jacplus.com.au.

Fluency

1. WE41 Calculate 10% of each of the following, rounding the answer to the nearest 5 cents.

a. \$10.00 **b.** \$18.00 **c.** \$81.00 **d.** \$150.00 **e.** \$93.00

2. Calculate 10% of each of the following, rounding the answer to the nearest 5 cents.
   a. $22.00 b. $17.20 c. $12.60 d. $1.50 e. $47.80

3. Calculate 10% of each of the following, rounding the answer to the nearest 5 cents.
   a. $192.40 b. $507.00 c. $1926.00 d. $3041.50 e. $1999.90

4. Calculate 10% of the following. Round your answers to the nearest 5 cents.
   a. $15 b. $51 c. $9 d. $137 e. $4.29

5. Calculate 10% of the following. Round your answers to the nearest 5 cents.
   a. $6.37 b. $39.17 c. $74.81 d. $102.75 e. $67.87

6. Calculate 10% of the following. Round your answers to the nearest 5 cents.
   a. $517.83 b. $304.77 c. $628.41 d. $100.37 e. $207.08

7. WE42 Calculate 5% of each of the following. Round the answers to the nearest 5 cents.
   a. $8.20 b. $6.40 c. $2.20 d. $140.20 e. $42.40

8. Calculate 5% of each of the following. Round the answers to the nearest 5 cents.
   a. $10.60 b. $304.80 c. $1000 d. $103.27 e. $31.70

9. Calculate 20% of the following. Round the answers to the nearest 5 cents.
   a. $21.50 b. $42.30 c. $3.30 d. $74.10 e. $0.79

10. Calculate 20% of the following. Round the answers to the nearest 5 cents.
    a. $16.40 b. $135.80 c. $261.70 d. $1237 e. $5069

11. Calculate the following. Round the answers to the nearest 5 cents.
    a. 15% of $12 b. 15% of $8.00 c. 15% of $60.00

12. Calculate the following. Round the answers to the nearest 5 cents.
    a. 25% of $30.00 b. 25% of $90.00 c. 25% of $220.00

13. Calculate the following. Round the answers to the nearest 5 cents.
    a. 30% of $15.00 b. 30% of $25.00 c. 30% of $47.50

14. Calculate 1% of the following. Round the answers to the nearest 5 cents.
    a. $268 b. $713 c. $604 d. $5.60 e. $13

15. Calculate 1% of the following. Round the answers to the nearest 5 cents.
    a. $14.80 b. $81.75 c. $19.89 d. $4.25 e. $6.49

16. WE43 Calculate the following. Round the answers to the nearest 5 cents.
    a. 12% of $11 b. 21% of $50 c. 3% of $22 d. 6% of $40 e. 13% of $14

17. Calculate the following. Round the answers to the nearest 5 cents.
    a. 35% of $210 b. 9% of $17 c. 2% of $53 d. 7% of $29 e. 45% of $71.50

18. Calculate the following. Round the answers to the nearest 5 cents.
    a. 33% of $14.50 b. 42% of $3.80 c. 31% of $1.45 d. 64% of $22.50 e. 41% of $1200

Understanding

19. MC 10% of $7.25 equals:
    A. $725 B. $7.30 C. $72.50 D. $0.73 E. $0.72

20. MC 1% of $31.48 equals:
    A. $3.14 B. $0.31 C. $0.32 D. $31.50 E. $3.15

21. MC 15% of $124 equals:

A. $12.40 **B.** $1.24 **C.** $6.20 **D.** $13.64 **E.** $18.60

22. MC 22% of $5050 equals:

A. $60.60 **B.** $50.50 **C.** $1111 **D.** $43.56 **E.** $55.55



23. Maria is buying a new set of golf clubs. The clubs are marked at $950, but if Maria pays cash, the shop will take 10% off the marked price. Determine how much the clubs will cost if Maria pays cash.

24. Thirty per cent of residents in a district are over the age of 65. If there are 180 000 residents, determine how many are over the age of 65.

25. Jay is buying a new lounge suite worth $2150. Jay has to leave a 15% deposit and then pay the balance in monthly instalments.

a. Calculate the deposit Jay needs to pay.

b. Determine how much Jay will have to pay each month if he plans to pay the balance off in one year.

26. Ninety per cent of students at a school were present for school photographs. If the school has 1100 students, calculate how many were absent on the day that the photographs were taken.

27. Jim can swim 50 m in 31 seconds. If he improves his time by 10%, calculate Jim's new 50 m time.



28. In a survey, 40 people were asked if they liked or disliked Vegemite. Of the people surveyed, 5% said they disliked Vegemite.
Calculate how many people:

a. disliked Vegemite **b.** liked Vegemite.

29. 35 800 went to the SCG to watch a Swans versus Giants football match. Of the crowd, 30% went to the game by car and 55% caught public transport.
Calculate how many people:

a. arrived by car

b. caught public transport

c. did not arrive at the game by car or public transport.

Reasoning

30. When I am 5% older than I am now, I will be 21 years old. How old am I now?




31. The price of bread is now 250% of what it cost 20 years ago, which is an increase of 150%. If a loaf of bread costs $2.00 now, determine how much it cost 20 years ago.

32. I am six months old. If I gain 10% of my current mass I will be three times my birth mass. If my birth mass was 3 kg, determine my current mass. Round your answer to 1 decimal place.

Problem solving

33. I am 33 years old. I have lived in England for 8 years. If I stay in England, determine how old I will be when the number of years I have lived here is 50% of my age. Show how you reached your answer.

34. Kate is a carpenter and has made a cutting board as shown.



a. One of her customers asked Kate to make her a similar cutting board but to double its width. Calculate the percentage increase of the width of the board.

b. A second customer asked Kate to make her a cutting board with dimensions 30 cm by 30 cm. Calculate:

i. the percentage increase of the width of the board

ii. the percentage increase of the length of the board

iii. the percentage increase of the perimeter of the board.

c. Explain whether there is a connection between the percentage increase of a side and the percentage increase of the perimeter.

35. Ten per cent of the messages received by a business were from customers dissatisfied with the product bought. Of these customers, 32% were male.

a. Calculate the overall percentage of dissatisfied male customers.

b. Calculate the overall percentage of dissatisfied female customers.

c. Explain what happens when you apply a percentage to another percentage.

4.13 Review

4.13.1 Topic summary

Working with fractions

- When working with fractions, mixed numbers provide the user with a good understanding of the value.
- However, when computing operations with fractions (addition, subtraction, multiplication and division), it is best to have all fractions expressed as proper fractions.

Types of fractions

- Fractions are used to represent parts of a whole.
- **Proper fractions** have a numerator that is less than the denominator, e.g. $\frac{2}{7}$.
- **Improper fractions** have a numerator that is greater than the denominator, e.g. $\frac{10}{3}$.
- A **mixed number** consists of an integer and a proper fraction, e.g. $2\frac{1}{4}$.

Finding a percentage of a quantity

- Finding a percentage of a number or a quantity is the same as finding an equivalent fraction of that number or quantity.
- Remember that in mathematics the word 'of' means multiply.

e.g. Determine 15% of $80.

$$15\% \text{ of } \$80 = \frac{15}{100} \times 80$$
$$= \frac{15}{10\cancel{0}} \times \frac{8\cancel{0}}{1}$$
$$= \frac{120}{10}$$
$$= 12$$

Simplifying fractions

- Fractions can be simplified by dividing the numerator and denominator by the same number.
- A fraction is in its simplest form when there are no factors (other than 1) that are common to both the numerator and denominator.

e.g. Simplify $\frac{80}{200}$.


Divide the numerator and denominator by 10.

$$\frac{80^{\div 10}}{200^{\div 10}} = \frac{8}{20}$$

There are still numbers that divide into both 8 and 20.

Divide the numerator and denominator by 4.

$$\frac{80^{\div 10}}{200^{\div 10}} = \frac{8^{\div 4}}{20^{\div 4}} = \frac{2}{5}$$



FRACTIONS AND PERCENTAGES

Multiplying fractions

To multiply fractions together, follow the three steps below:

1. Multiply the numerators.
2. Multiply the denominators.
3. Simplify the fraction if possible.

e.g. Evaluate $\frac{1}{2} \times \frac{4}{9}$.

$$\frac{1}{2} \times \frac{4}{9} = \frac{1 \times 4}{2 \times 9} = \frac{4}{18} = \frac{2}{9}$$

Dividing fractions

To divide two fractions, follow the KEEP, CHANGE, FLIP method outlined below and then multiply the fractions together.

1. **KEEP** the fraction to the left of the ÷ symbol the same.
2. **CHANGE** the division sign to a multiplication sign.
3. **FLIP** (invert) the fraction to the right of the symbol.

e.g. Evaluate $\frac{3}{4} \div \frac{2}{7}$.

KEEP $\frac{3}{4}$ CHANGE $\times$ FLIP $\frac{7}{2}$

$$\frac{3}{4} \div \frac{2}{7} = \frac{3}{4} \times \frac{7}{2} = \frac{3 \times 7}{4 \times 2} = \frac{21}{8}$$

Addition and subtraction of fractions

To add or subtract fractions, follow the steps below:

1. Examine the denominators of all fractions and determine the lowest common multiple (LCM).
2. Use the method of equivalent fractions to change each fraction so that the denominators are all the same.
3. Depending on the symbol in the question, add or subtract the numerators leaving the denominator unchanged.

e.g. Evaluate $\frac{2}{3} + \frac{7}{4}$.

LCM = 12

$$\frac{2}{3} + \frac{7}{4} = \frac{2}{3} \times \frac{4}{4} + \frac{7}{4} \times \frac{3}{3} = \frac{8}{12} + \frac{21}{12}$$
$$= \frac{8 + 21}{12} = \frac{29}{12}$$

Expressing a percentage as a fraction

- To convert a percentage to a fraction, simply divide by 100 and remove the percentage symbol.

e.g. Express 80% as a common fraction.

$$80\% = 80 \div 100$$
$$= \frac{80^{\div 20}}{100^{\div 20}} = \frac{4}{5}$$
$$= 0.54$$

Equivalent fractions

- Equivalent fractions are fractions that have the same value but look different.

  e.g. $\frac{1}{2}$, $\frac{2}{4}$ and $\frac{50}{100}$ are equivalent fractions. The value of each fraction is 0.5.
- Equivalent fractions can be created by multiplying both the numerator and denominator by the same number.

  e.g.
  $\frac{1}{2} \times \frac{2}{2} = \frac{2}{4}$
  $\frac{1}{2} \times \frac{50}{50} = \frac{50}{100}$

Converting fractions to percentages

- To express a fraction as a percentage, simply multiply by 100 and include the percentage symbol.

e.g. Express $\frac{9}{20}$ as a percentage.

$$\frac{9}{20} \times 100\% = \frac{9}{2\cancel{0}} \times \frac{10\cancel{0}}{1}\%$$
$$= \frac{90}{2}\%$$
$$= 45\%$$

4.13.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
4.2	I understand the concept of a fraction.			
	I can convert between equivalent fractions.			
	I can compare fractions.			
4.3	I can simplify fractions.			
	I can simplify mixed numbers.			
4.4	I can convert between mixed numbers and improper fractions.			
4.5	I can add and subtract fractions.			
4.6	I can multiply fractions by a whole number.			
	I can multiply fractions by another fraction.			
	I can calculate fractions of a fraction.			
	I can calculate fractions of an amount.			
4.7	I can divide fractions.			
4.8	I can add, subtract, multiply and divide mixed numbers.			
4.9	I can convert percentages to fractions.			
4.10	I can calculate percentages of amounts using fractions.			
4.11	I can express an amount as a percentage of another amount.			
4.12	I can recognise commonly used percentages.			
	I can use common percentages as short cuts to calculate related percentages.			

4.13.3 Project

The Memory game

The game Memory is played with a standard deck of playing cards. All cards are placed face-side down on a table and each player takes turns to reveal 2 cards. If the 2 cards contain the same number or suit, they are a pair and the player gets another turn. If they are not a pair, they are returned to their original spot and turned face-down. The object of the game is to remember where the same cards are and collect as many pairs as you can. The winner is the person with the most pairs.



Your task is to develop a version of Memory with a fractions flavour. Each of your cards will have a fraction written on it and its pair will be an equivalent fraction.

1. As an introduction to the game, match the pairs of equivalent fractions on the cards below.

$\frac{6}{8}$	$\frac{3}{9}$	$\frac{1}{3}$	$\frac{3}{4}$	$\frac{4}{8}$	$\frac{1}{2}$
A	B	C	D	E	F

The requirements for your game are as follows.

- There are 15 pairs of equivalent fractions in this game — that makes 30 cards.
- One of the fractions of each pair must be in simplest form.
- For example, $\frac{1}{3}$ and $\frac{4}{12}$ are an acceptable pair, but $\frac{10}{30}$ and $\frac{4}{12}$ are not.
- Fractions don't have to be proper fractions. Equivalent mixed numbers and improper fractions are allowed.

2. Using the information in step 1, write down the 15 pairs of fractions that will be a part of your memory game.

When the game is packaged for sale, additional information accompanies the cards. This information includes a list of the fractions enclosed and instructions for the game. The list of fractions is given in order from smallest to largest.

3. List your fraction pairs in order from smallest to largest.

When items are placed for sale, presentation of the packaging is important. Eye-catching designs will attract attention, and mistakes must be avoided at all costs. You are now the designer for a company that is going to market the new game.

4. In your workbook or on a blank piece of paper, draw two rectangles the size of playing cards. In the first rectangle, design the back of your cards, and in the second rectangle, design how the fractions will appear on the face of the cards.

The playing instructions are very important pieces of information in games. They explain the number of players allowed, how the game is to be played and who wins.

5. Taking into consideration the information that has been provided for you throughout this task, write a set of instructions that show how your Memory game is played.
6. Now construct your own game cards and present them in a suitable package. Remember, presentation of the game is important. When you have finished, try the game out with your friends.

Resources

eWorkbook Topic 4 Workbook (worksheets, code puzzle and project) (ewbk-1905)
Interactivities Crossword (int-2590)
Sudoku puzzle (int-3165)


Exercise 4.13 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for every question, go to your learnON title at www.jacplus.com.au.

Fluency

1. State the fraction of the eggs in this carton that are white.



2. Write the sequence of the first three equivalent fractions for the following.
   a. $\frac{3}{8}$ b. $\frac{4}{9}$ c. $\frac{5}{11}$ d. $\frac{6}{7}$

3. Fill the gaps to make equivalent fractions.
   a. $\frac{1}{2} = \frac{\quad}{4} = \frac{3}{\quad}$ b. $\frac{1}{3} = \frac{3}{\quad} = \frac{\quad}{15}$ c. $\frac{3}{4} = \frac{9}{\quad} = \frac{\quad}{28}$ d. $\frac{2}{5} = \frac{\quad}{10} = \frac{16}{\quad}$

4. Ricky, Leo and Gabriel were the highest goal scorers for their local football team throughout the season. Ricky scored $\frac{2}{7}$ of the team's goals, Leo scored $\frac{1}{3}$ of the goals and Gabriel scored $\frac{1}{4}$ of the goals.
   a. Determine who scored most of the goals.
   b. State who scored more goals: Ricky or Gabriel.



5. Simplify these fractions.
   a. $\frac{42}{49}$ b. $\frac{81}{108}$ c. $\frac{18}{20}$ d. $\frac{21}{28}$

6. Simplify these fractions.
   a. $\frac{50}{150}$ b. $\frac{75}{125}$ c. $\frac{2}{80}$ d. $\frac{36}{72}$

7. Simplify the following mixed numbers.

a. $6\frac{8}{10}$ **b.** $3\frac{6}{9}$ **c.** $4\frac{15}{20}$ **d.** $1\frac{20}{100}$

8. Determine what fraction of months of the year begin with the letter J. Express your answer in simplest form.

9. Convert these improper fractions to mixed numbers.

a. $\frac{16}{3}$ **b.** $\frac{21}{5}$ **c.** $\frac{12}{7}$ **d.** $\frac{11}{2}$

10. Convert these improper fractions to mixed numbers.

a. $\frac{5}{4}$ **b.** $\frac{80}{7}$ **c.** $\frac{55}{9}$ **d.** $\frac{72}{10}$

11. Express these mixed numbers as improper fractions.

a. $2\frac{3}{4}$ **b.** $9\frac{7}{8}$ **c.** $3\frac{5}{7}$ **d.** $5\frac{5}{6}$

12. Express these mixed numbers as improper fractions.

a. $3\frac{2}{3}$ **b.** $9\frac{9}{10}$ **c.** $3\frac{11}{12}$ **d.** $8\frac{1}{2}$

13. Marcella was in charge of baking and selling lemon slice at the school fete. Each tray she baked contained 15 pieces of lemon slice. If Marcella sold 68 slices, determine how many empty trays there were.



14. Evaluate:

a. $\frac{5}{6}+\frac{1}{8}$ **b.** $\frac{7}{9}-\frac{2}{5}$ **c.** $\frac{12}{5}-\frac{4}{3}$

15. Evaluate:

a. $\frac{4}{7}\times\frac{5}{9}$ **b.** $\frac{2}{5}\times\frac{3}{5}$ **c.** $\frac{25}{36}\times\frac{18}{20}$ **d.** $\frac{56}{81}\times\frac{18}{64}$

16. Evaluate:

a. $\frac{4}{5}$ of 55 **b.** $\frac{2}{11}$ of 121 **c.** $\frac{7}{9}$ of $\frac{18}{84}$ **d.** $\frac{1}{12}$ of 200

17. Write the reciprocals of:

a. $\frac{5}{2}$ **b.** $\frac{1}{9}$ **c.** $\frac{1}{4}$ **d.** $5\frac{3}{4}$

18. Evaluate:

a. $\frac{4}{5}\div\frac{8}{15}$ **b.** $\frac{9}{10}\div\frac{27}{40}$ **c.** $\frac{7}{9}\div 4$ **d.** $\frac{3}{7}\div 10$

19. Evaluate:

a. $1\frac{7}{8}+2\frac{5}{6}$ **b.** $10\frac{3}{7}-8\frac{1}{2}$ **c.** $6\frac{1}{3}-2\frac{5}{9}$ **d.** $5\frac{1}{2}-2\frac{5}{6}$

20. Evaluate:

a. $8\frac{2}{9}-4\frac{5}{8}$ **b.** $12\frac{6}{11}-11\frac{7}{9}$ **c.** $1\frac{1}{5}+3\frac{1}{3}-\frac{13}{15}$ **d.** $4\frac{7}{9}-1\frac{5}{6}+3\frac{1}{3}$

21. Evaluate:

a. $10\frac{2}{7}\times 6\frac{2}{9}$ **b.** $\frac{4}{9}\times 2\frac{1}{4}\times\frac{3}{5}$ **c.** $3\frac{5}{12}\times 1\frac{3}{5}\times 2\frac{1}{2}$ **d.** $\frac{6}{17}\times 1\frac{1}{4}\times 3\frac{2}{5}$

22. Evaluate:

a. $1\frac{1}{2}\div 4\frac{4}{5}$ **b.** $6\frac{2}{3}\div 4\frac{1}{6}$ **c.** $4\frac{1}{5}\div 2\frac{7}{8}$ **d.** $10\frac{1}{3}\div 12\frac{5}{7}$

23. Write the following percentages as fractions in simplest form.

a. 13% **b.** 70% **c.** 26% **d.** 132%

24. Change the following fractions to percentages.

a. $\frac{15}{100}$ **b.** $\frac{11}{20}$ **c.** $\frac{3}{5}$ **d.** $\frac{18}{36}$

25. Change the following fractions to percentages.

a. $\frac{30}{80}$ **b.** $\frac{8}{15}$ **c.** $\frac{5}{6}$ **d.** $\frac{4}{11}$

26. Calculate the following percentages using fractions.

a. 5% of 120 **b.** 60% of 20 **c.** 75% of 52 **d.** 130% of 30

27. Calculate the following percentages using fractions.

a. 14% of 45 **b.** 7% of 530 **c.** 32% of 15 **d.** 17% of 80

28. Express:

a. 30 as a percentage of 50 **b.** 18 as a percentage of 60

c. 32 as a percentage of 80 **d.** 28 as a percentage of 70.

29. Express:

a. 4 days as a percentage of 8 weeks

b. 20 minutes as a percentage of 3 hours.

30. Calculate 5% of the following by finding 10% and halving your answer. Round your answer to the nearest 5 cents.

a. \$8.00 **b.** \$21.00 **c.** \$64.00 **d.** \$104.00

31. Calculate the following using short cuts. Round your answer to the nearest 5 cents.

a. 1% of \$16.00 **b.** 1% of \$28.00 **c.** 12% of \$42.00 **d.** 30% of \$90.00

Problem solving


32. Year 7 students at Camberwell Secondary College raised a total of $1600 for the Royal Children's Hospital Good Friday Appeal. The table below shows how much money each class raised.

Class	7.1	7.2	7.3	7.4	7.5	7.6
Amount raised ($)	$200	$400	$250	$250	$280	$220

Express as a simple fraction how much of the total each class raised.

33. Anthony's monthly take-home pay is $2800. He spends a quarter on his home loan payments, one-half on food and drink, and one-seventh on clothing. One-half of the remainder goes into his savings account. Calculate how much money Anthony saves each month.

34. On a balance scale, a brick exactly balances $\frac{2}{3}$ of a brick and a $\frac{2}{3}$ kg weight. How heavy is the brick?



35. Complete the following:

a. $\frac{5}{12} = \frac{1}{4} + ?$ **b.** $\frac{5}{12} = \frac{2}{3} - ?$ **c.** $\frac{5}{12} = \frac{3}{4} \times ?$ **d.** $\frac{5}{12} = \frac{4}{5} \div ?$

36. Explain how you can determine a fraction whose numerator and denominator have a product of 252, and that is equivalent to $\frac{4}{7}$.

37. Tomas buys a 24-piece pizza and eats 8 pieces. Drew buys a 16-piece pizza of the same size, and eats 5 pieces. Identify who ate the most pizza and explain your choice.

38. An Egyptian fraction is one that can be written as the sum of a set of different unit fractions: for example, $\frac{3}{4} = \frac{1}{2} + \frac{1}{4}$. (*Note*: The numerator of each unit fraction is 1.) Write $\frac{4}{5}$ as the sum of a set of different unit fractions.

39. Mr Thompson earned $2400 per month. Recently, he had a pay increase. He now earns $1\frac{1}{4}$ times his old salary. Calculate his new salary.

Mr Thompson's colleague, Mr Goody, earned $3000 per month and had a pay cut. He now gets $\frac{1}{6}$ less of his old salary. Calculate Mr Goody's new salary.

40. A shopping centre has 250 parking spaces. Of these, $\frac{3}{10}$ are suitable for small cars only. The remaining spaces are for standard cars. Last Friday small cars took up $\frac{14}{15}$ of their allocated spots, but overall the car park was $\frac{7}{10}$ full.

Determine the fraction of standard car spaces that were filled.

41. Byron needs $\frac{2}{5}$kg of catalyst mixed with $4\frac{1}{2}$kg of resin to create one surfboard.

a. If he has $2\frac{1}{4}$kg of catalyst and $20\frac{1}{4}$kg of resin, how many whole surfboards can Byron build?

b. Calculate how much more catalyst and resin Byron needs to build one more surfboard. Explain your reasoning.

42. Calculate the percentage that remains if:

a. 38% of the winnings have been spent

b. all stock was discounted 25%.

43. Eighty per cent of a Year 7 Maths class got question 1 correct on their percentages test. If there are 30 students in the class, calculate how many got the question correct.

44. Forty per cent of primary-school children can sing the national anthem. In a group of 675 primary-school children, calculate how many you would expect to be able to sing the national anthem.

45. Lake Eyre in South Australia has an annual rainfall of around 100 mm. If 8 mm fell in one week, give this as a percentage of the annual rainfall.



46. A tennis player agreed to pay her coach 8% of her winnings from tournaments. If she wins $145 000 in a tournament, calculate how much her coach receives.

47. At Queens High School, there are 900 students.
45% walk to school.
55% don't walk to school.
12% of students wear glasses.

Identify which of the following statements is definitely false. (There may be more than one answer.)

a. There are 100 students who don't walk to school and who wear glasses.

b. 10% of the students who don't walk to school and 2% of the students who do walk to school wear glasses.

c. 20% of the students who walk to school wear glasses.

d. More than 22% of the students who don't walk to school wear glasses.



48. The label on a 500 g pack of butter states that it contains 81% fat. A milk bottle label says that the milk contains 3 grams of fat per 100 mL. Determine the number of litres of this milk that contains the same amount of fat as there is in the butter.

49. In a recent survey of house occupancy in a town, it was discovered that 40% of the houses contained 2 or more people. Of those houses that contain only 1 person, 25% of them contained a male. Of all the houses in a town, calculate the percentage that contains only 1 female and no males.

50. A television set has a ticketed price of $2500. A 10% discount is allowed on the set.



- **a.** Calculate the negotiated price of the television set.
- **b.** If a further 10% is negotiated off the price of the set, calculate the price paid.
- **c.** Calculate the total discount as a percentage of the original ticketed price.
- **d.** Explain why two successive 10% discounts do not equal a 20% discount.

51. Joseph wants to spend $2500 on a new barbecue. Since he works at a BBQ store he can get a staff discount of 10%. He can also get a discount of 30% in the stocktake sale.



Joseph wants to know whether he should ask the salesman to apply his staff discount or the sale discount first to achieve the cheapest price.

- **a.** Calculate how much the barbecue will cost if the staff discount is taken off first and then the sale discount is taken off.
- **b.** Calculate how much it will cost if done the opposite way.
- **c.** Decide which method Joseph should select to get the best price.

52. Two triangles have the same area. Show that if one triangle has a 25% wider base than the other, then it must be 20% shorter (that is, its height must be 20% less).

To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1905) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0693) ☐

Digital documents

4.2 SkillSHEET Types of fractions (doc-6437) ☐
SkillSHEET Equivalent fractions I (doc-6438) ☐
SkillSHEET Equivalent fractions II (doc-6439) ☐
SkillSHEET Lowest common multiple (doc-6440) ☐
SkillSHEET Ordering fractions (doc-6441) ☐
4.3 SkillSHEET Highest common factor (doc-6442) ☐
4.4 SkillSHEET Converting an improper fraction into a mixed number (doc-6443) ☐
SkillSHEET Converting a mixed number into an improper fraction (doc-6444) ☐
4.5 SkillSHEET Adding and subtracting fractions with the same denominator (doc-6445)
4.9 SkillSHEET Simplifying fractions with a denominator of 100 (doc-6470) ☐
SkillSHEET Converting a mixed number into an improper fraction (doc-6471) ☐
SkillSHEET Changing fractions to equivalent fractions with a denominator of 100 (doc-6472) ☐
4.10 SkillSHEET Multiplying fractions by a whole number (doc-6475) ☐
SkillSHEET Rounding to the nearest whole number (doc-6476) ☐
SkillSHEET Rounding money to the nearest 5 cents (doc-6477) ☐

Video eLesssons

4.2 Understanding fractions (eles-3798) ☐
Equivalent fractions (eles-3799) ☐
Fractions on a number line (eles-3800) ☐
Comparing fractions (eles-3801) ☐
4.3 Simplifying fractions (eles-3802) ☐
4.4 Converting improper fractions to mixed numbers (eles-3803) ☐
Converting mixed numbers to improper fractions (eles-3804) ☐
4.5 Adding and subtracting proper fractions (eles-3805) ☐
Addition and subtraction of fractions (eles-1866) ☐
4.6 Multiplying fractions (eles-3806) ☐
Using the word of (eles-3807) ☐
Multiplication and division of fractions (eles-1867) ☐
4.7 Dividing fractions (eles-3808) ☐
4.8 Adding and subtracting mixed numbers (eles-3809) ☐
Multiplying and dividing mixed numbers (eles-3810) ☐
4.9 Definition of a percentage (eles-3812) ☐
4.10 Calculating percentages of an amount using fractions (eles-3814) ☐
Percentages of an amount (eles-1882) ☐
4.9 One amount as a percentage of another (eles-3815) ☐
4.9 Common percentages and short cuts (eles-3816) ☐

Interactivities

4.2 Individual pathway interactivity: What are rational numbers? (int-4323) ☐
Understanding fractions (int-3938) ☐
Expressing one quantity as a fraction of another (int-3939) ☐
Equivalent fractions (int-3940) ☐
Fractions on a number line (int-3941) ☐
Comparing fractions (int-3942) ☐
4.3 Individual pathway interactivity: Simplifying rational numbers (int-4324) ☐
Simplifying fractions (int-3943) ☐
4.4 Individual pathway interactivity: Mixed numbers and improper fractions (int-4325) ☐
Mixed numbers to improper fractions (int-3944) ☐
4.5 Individual pathway interactivity: Adding and subtracting rational numbers (int-4326) ☐
Addition and subtraction of proper fractions (int-3945) ☐
4.6 Individual pathway interactivity: Multiplying rational numbers (int-4327) ☐
Repeated addition (int-2738) ☐
Multiplication of rational numbers (int-3946) ☐
Using the word *of* (int-3947) ☐
4.7 Individual pathway interactivity: Dividing rational numbers (int-4328) ☐
Division of rational numbers (int-3948) ☐
4.8 Individual pathway interactivity: Working with mixed numbers (int-4330) ☐
Addition and subtraction of mixed numbers (int-3951) ☐
4.9 Individual pathway interactivity: Percentages as fractions (int-4343) ☐
Percentages as fractions (int-3992) ☐
4.10 Individual pathway interactivity: Calculating percentages of an amount (int-4346) ☐
Percentages of an amount using fractions (int-3996) ☐
4.11 Individual pathway interactivity: One amount as a percentage of another (int-4347) ☐
One amount as a percentage of another (int-3998) ☐
4.12 Individual pathway interactivity: Common percentages and short cuts (int-4348) ☐
Common percentages and short cuts (int-3999) ☐
4.13 Crossword (int-2590) ☐
Sudoku puzzle (int-3165) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.


Answers


Topic 4 Fractions and percentages


Exercise 4.1 Pre-test


1. B
2. a $\frac{3}{8}$ b $\frac{5}{8}$
3. $5\frac{3}{4}$
4. $\frac{3}{4}$
5. 100 minutes
6. A
7. 36
8. 187 cm
9. $\frac{127}{200}$
10. C
11. a. $\frac{3}{25}$ b. 0.12
12. 11 036
13. 75%
14. D
15. $15.58

Exercise 4.2 What are fractions?

1. a. $\frac{3}{4}$ b. $\frac{15}{16}$ c. $\frac{7}{8}$
2. $\frac{1}{3}$
3. $\frac{3}{4}$
4. a. $\frac{3}{11}$ b. $\frac{2}{11}$
5. $\frac{3}{11}$
6. $\frac{17}{60}$ of an hour
7. a. 3 b. 3 c. 4 d. 5
8. a. 6 b. 9 c. 11 d. 12
9. $\frac{20}{30}, \frac{14}{21}, \frac{40}{60}$
10. $\frac{12}{15}, \frac{36}{45}, \frac{16}{20}, \frac{28}{35}, \frac{80}{100}$
11. $\frac{35}{50}, \frac{21}{30}, \frac{14}{20}, \frac{140}{200}$
12. $\frac{5}{6} = \frac{10}{12} = \frac{15}{18} = \frac{20}{24}$
13. $\frac{7}{8} = \frac{14}{16} = \frac{21}{24} = \frac{28}{32}$
14. 

15. 

16. a. $\frac{3}{5}$ b. $\frac{7}{8}$ c. $\frac{1}{5}$ d. $\frac{1}{8}$
17. a. $\frac{3}{4}$ b. $\frac{5}{8}$ c. $\frac{5}{8}$ d. $\frac{4}{5}$
18. a. > b. > c. > d. <
19. D
20. B
21. $\frac{9}{24}, \frac{12}{24}, \frac{8}{24}; \frac{1}{3}, \frac{3}{8}, \frac{1}{2}$
22. $\frac{45}{60}, \frac{40}{60}, \frac{28}{60}; \frac{7}{15}, \frac{2}{3}, \frac{3}{4}$
23. $\frac{30}{40} = \frac{18}{24} = \frac{27}{36}$
24. $\frac{15}{18} = \frac{35}{42} = \frac{40}{48}$
25. 7 does not divide into 2 evenly, so it would be difficult to mark the equal parts. It would be more appropriate to use a scale of 3.5 cm or 7 cm per whole number.
26. As the denominator doubles, the distance between fractions halves, because doubling the denominator is the same as dividing the fraction by 2.
27. a. 

b. Vanessa
c. They ate the same amount.
28. Lee Yin
29. $\frac{19}{60}, \frac{1}{3}$
30. 

Exercise 4.3 Simplifying fractions

1. a. $\frac{1}{2}$ b. $\frac{2}{3}$ c. $\frac{7}{8}$ d. $\frac{4}{5}$
2. a. $\frac{5}{6}$ b. $\frac{24}{25}$ c. $\frac{7}{8}$ d. $\frac{7}{10}$
3. a. $\frac{11}{12}$ b. $\frac{11}{25}$ c. $\frac{3}{8}$ d. $\frac{7}{8}$
4. a. $4\frac{3}{5}$ b. $7\frac{5}{6}$ c. $10\frac{1}{2}$ d. $1\frac{11}{12}$
5. a. $6\frac{3}{4}$ b. $5\frac{1}{3}$ c. $3\frac{1}{5}$ d. $2\frac{1}{4}$
6. E
7. $\frac{21}{28} = \frac{3}{4}$

8. a. $\frac{20}{36} = \frac{5}{9}$ b. $\frac{16}{36} = \frac{4}{9}$


9. 7A: $\frac{1}{5}$, 7B: $\frac{3}{20}$, 7C: $\frac{8}{25}$, 7D: $\frac{2}{25}$, 7E: $\frac{1}{4}$

10. a. 40

b. Mark: $\frac{5}{40} = \frac{1}{8}$, Ken: $\frac{10}{40} = \frac{1}{4}$, Samantha: $\frac{8}{40} = \frac{1}{5}$, Jules: $\frac{6}{40} = \frac{3}{20}$, Ahmed: $\frac{4}{40} = \frac{1}{10}$, Darren: $\frac{7}{40}$


11. Newcastle to Sydney is more reliable.

12. a.



b. $\frac{1}{4}$

c.



d. $\frac{1}{8}$

e. Because two smallest triangles form one middle size triangle

13. The denominator could be any multiple of 13 because the fraction is not written in its simplest form and 13 is a prime number.

14. a. Six pizzas


b. Two quarters (one half) of a pizza are left over.

15. a. $\frac{7293}{14\,586}, \frac{6792}{13\,584}$ b. $\frac{5823}{17\,469}$


16. $\frac{2}{5}$

Exercise 4.4 Mixed numbers and improper fractions


1. a.




b.




c.



2.



3.



4. a. $1\frac{2}{5}$ b. $2\frac{3}{4}$ c. $10\frac{1}{2}$ d. $4\frac{1}{4}$ e. $8\frac{4}{11}$


5. a. $2\frac{3}{13}$ b. $33\frac{1}{3}$ c. $12\frac{1}{2}$ d. $6\frac{2}{3}$ e. $1\frac{3}{5}$

6. a. $3\frac{3}{8}$ b. $5\frac{1}{2}$ c. $8\frac{2}{7}$ d. $11\frac{7}{10}$ e. $8\frac{3}{8}$


7. C

8. B


9. a.



b.



c.



10. a. $\frac{9}{8}$ b. $\frac{15}{4}$ c. $\frac{13}{6}$ d. $\frac{8}{7}$ e. $\frac{9}{5}$

11. a. $\frac{10}{3}$ b. $\frac{25}{4}$ c. $\frac{37}{9}$ d. $\frac{23}{2}$ e. $\frac{39}{5}$

12. a. $\frac{33}{5}$ b. $\frac{47}{5}$ c. $\frac{7}{2}$ d. $\frac{21}{5}$ e. $\frac{47}{7}$

13. a. $\frac{29}{10}$ b. $\frac{43}{12}$ c. $\frac{67}{7}$ d. $\frac{21}{11}$ e. $\frac{53}{6}$

14. D

15. D

16. A

17. Kim: $2\frac{1}{4}$, Carly: $2\frac{3}{4}$

18. $6\frac{1}{2}$

19. $4\frac{3}{4}$


20. a. > b. > c. < d. >

21. a. < b. < c. < d. <

22. $10\frac{1}{2}$

23. a. i. $\frac{23}{7}$ ii. $\frac{23}{4}$

b.



24. $\frac{4}{5}$

25. a. 25 **b.** 77

26. a. $\frac{14}{3}$ or $4\frac{2}{3}$ km

b. $\frac{56}{3}$ or $18\frac{2}{3}$ km

c. $\frac{70}{3}$ or $23\frac{1}{3}$ km

27. $1\frac{1}{4}, 2\frac{1}{12}, 2\frac{1}{6}, 3\frac{1}{8}, 3\frac{1}{3}$

28. To write an improper fraction as a mixed number we divide the denominator into the numerator and write the remainder over the same denominator. Alternatively, we can draw circles to determine how many whole numbers we have, and the parts left over will be the fraction part of the mixed number.

Exercise 4.5 Adding and subtracting fractions

1. a. $\frac{4}{5}$ **b.** $\frac{6}{11}$ **c.** $\frac{5}{6}$ **d.** $\frac{31}{50}$

2. a. $\frac{1}{2}$ **b.** $\frac{1}{4}$ **c.** $\frac{1}{3}$ **d.** $\frac{1}{2}$

3. a. $\frac{9}{25}$ **b.** $\frac{11}{12}$ **c.** $\frac{7}{8}$ **d.** $\frac{6}{7}$

4. a. 1 **b.** $\frac{3}{4}$ **c.** $\frac{3}{4}$ **d.** $\frac{8}{9}$

5. a. $\frac{3}{4}$ **b.** $\frac{1}{4}$ **c.** $\frac{3}{7}$ **d.** $\frac{3}{4}$

6. a. $\frac{2}{3}$ **b.** $\frac{13}{27}$ **c.** $\frac{16}{35}$ **d.** $\frac{2}{5}$

7. a. **i.** 6 **ii.** 15 **iii.** 10 **iv.** 12

b. **i.** $\frac{1}{6}$ **ii.** $\frac{4}{15}$ **iii.** $\frac{9}{10}$ **iv.** $\frac{7}{12}$

8. a. **i.** 18 **ii.** 8 **iii.** 24 **iv.** 35

b. **i.** $\frac{17}{18}$ **ii.** $\frac{5}{8}$ **iii.** $\frac{11}{24}$ **iv.** $\frac{11}{35}$

9. a. $\frac{5}{6}$ **b.** $\frac{23}{36}$ **c.** $\frac{39}{44}$ **d.** $\frac{1}{4}$

10. a. $\frac{17}{63}$ **b.** $\frac{23}{39}$ **c.** $\frac{2}{15}$ **d.** $\frac{7}{33}$

11. D

12. a. $\frac{7}{12}$ **b.** $\frac{2}{5}$ **c.** $\frac{19}{24}$ **d.** $\frac{7}{30}$

13. a. $\frac{7}{16}$ **b.** $\frac{1}{3}$ **c.** $1\frac{11}{12}$ **d.** $1\frac{11}{12}$

14. a. $\frac{3}{4}$ **b.** $\frac{4}{7}$ **c.** $\frac{60}{71}$ **d.** $1\frac{3}{5}$

15. a. $2\frac{8}{15}$ **b.** $4\frac{1}{6}$ **c.** $9\frac{2}{3}$ **d.** $22\frac{1}{10}$

16. a. $\frac{7}{15}$ **b.** $\frac{8}{15}$

17. $1\frac{1}{4}$ hours

18. a. $\frac{3}{4}$ **b.** $\frac{7}{12}$ **c.** 1

19. a. $\frac{2}{3}$ **b.** $\frac{23}{30}$

20. 135

21. To add fractions, you must convert to equivalent fractions with the same denominators. You cannot simply add the numerators and add the denominators.

22. $\frac{1}{12}$

23. a. **i.** $\frac{5}{6}$ **ii.** $\frac{7}{12}$ **iii.** $\frac{9}{20}$

b. When adding two fractions, both with the numerator of 1 and denominators that are consecutive numbers, the answer is $\frac{\text{sum of denominators}}{\text{product of denominators}}$.


24. a. **i.** $\frac{1}{6}$ **ii.** $\frac{1}{12}$ **iii.** $\frac{1}{20}$

b. When subtracting two fractions that both have a numerator of 1 and denominators that are consecutive numbers, the answer is $\frac{1}{\text{product of denominators}}$.


c. $\frac{1}{n(n+1)}$

25. Fractions cannot be added or subtracted unless they have the same denominator. This is because we need to be adding or subtracting like fractions. If the denominators are different, we can make the two fractions into equivalent fractions by finding the lowest common denominator (LCD). The LCD is the smallest multiple of all the denominators in a set of fractions.

26.



Exercise 4.6 Multiplying fractions

1. a. 2 b. $2\frac{1}{2}$ c. $7\frac{1}{2}$ d. $1\frac{1}{4}$
2. a. $\frac{1}{8}$ b. $\frac{2}{9}$ c. $\frac{20}{27}$ d. $\frac{11}{26}$
3. a. $\frac{54}{77}$ b. $\frac{121}{144}$ c. $\frac{40}{81}$ d. $\frac{5}{24}$
4. a. $\frac{55}{72}$ b. $\frac{25}{132}$ c. $\frac{8}{39}$ d. $\frac{8}{21}$
5. a. $\frac{1}{6}$ b. $\frac{1}{5}$ c. $\frac{5}{14}$ d. $\frac{1}{10}$
6. a. $\frac{4}{5}$ b. 1 c. $\frac{1}{2}$ d. $\frac{12}{35}$
7. a. $\frac{4}{9}$ b. $\frac{1}{7}$ c. $\frac{1}{3}$ d. $\frac{1}{20}$
8. a. $\frac{1}{8}$ b. $\frac{1}{2}$ c. $\frac{25}{36}$ d. $\frac{2}{9}$
9. a. 28 b. 45 c. 15 d. 16
10. Emily drank 2 L. Tracy drank $\frac{1}{2}$ L. Jonathan drank $\frac{1}{3}$ L.
11. a. 32 minutes b. 35 minutes
12. a. 
Here is one example answer.
b. $\frac{1}{9}$
13. a $\frac{3}{4}$ b 36 litres
14. a. 2 b. 4 c. 10
15. a.  b. 
c. $\frac{1}{8}$ d. $\frac{1}{2} \times \frac{1}{4} = \frac{1}{8}$
16. a. 90 minutes
b. $\frac{90}{180} = \frac{1}{2}$
c. $140 + 26\frac{2}{3} = 166\frac{2}{3}$ minutes
17. a. i. $\frac{1}{3}$ ii. $\frac{1}{4}$ iii. $\frac{1}{5}$
b. The result from the numerator of the first fraction and the denominator of the last fraction
c. $\frac{1}{100}$
18. $\frac{1}{24} \times 2400 = \$100$
19. $121\frac{1}{2}$km
20. Red $= 1\frac{16}{21}$m, green $= 1\frac{9}{28}$m

Exercise 4.7 Dividing fractions

1. a. $\frac{4}{3}$ b. $\frac{7}{2}$ c. $\frac{5}{6}$ d. $\frac{3}{5}$ e. $\frac{1}{5}$
2. a $\frac{12}{5}$ b $\frac{2}{9}$ c $\frac{3}{5}$ d $\frac{3}{10}$ e $\frac{1}{20}$
3. a. 12 b. 5 c. 11 d. 6 e. 1
4. a. $\frac{3}{5}$ b. $\frac{7}{31}$ c. $\frac{7}{65}$ d. $\frac{8}{27}$ e. $\frac{10}{69}$
5. a. $\frac{7}{27}$ b. $\frac{3}{16}$ c. $\frac{2}{15}$ d. $\frac{9}{92}$ e. $\frac{9}{23}$
6. a. 1 b. 1 c. 1
7. a. $\frac{3}{8}$ b. $\frac{16}{21}$ c. $\frac{1}{8}$ d. $\frac{24}{55}$ e. $4\frac{2}{3}$
8. a. $\frac{3}{10}$ b. 1 c. $\frac{2}{35}$ d. $\frac{1}{9}$ e. $\frac{3}{11}$
9. a. $\frac{5}{9}$ b. $\frac{1}{22}$ c. $\frac{63}{50}$ d. $\frac{12}{17}$ e. $\frac{10}{7}$
10. Lily is correct.
11. 32
12. 15 people
13. $\frac{13}{3}$
14. $\frac{3}{20}$
15. $\frac{5}{12}$

Exercise 4.8 Working with mixed numbers

1. a. $4\frac{7}{10}$ b. $1\frac{1}{6}$ c. $3\frac{5}{12}$ d. $13\frac{3}{8}$
2. a. $1\frac{1}{10}$ b. $6\frac{1}{4}$ c. $1\frac{1}{3}$ d. $1\frac{1}{2}$
3. a. $1\frac{5}{8}$ b. $1\frac{7}{10}$ c. $3\frac{2}{3}$ d. $1\frac{11}{12}$
4. a. $2\frac{17}{35}$ b. $3\frac{7}{8}$ c. $3\frac{13}{18}$ d. $3\frac{1}{24}$
5. a. $7\frac{7}{12}$; 7 b. $3\frac{2}{3}$; 3 c. $4\frac{1}{2}$; 4 d. $4\frac{1}{4}$; 4
6. a. $\frac{5}{6}$ b. $2\frac{1}{4}$ c. $4\frac{19}{32}$ d. $7\frac{7}{10}$
7. a. $37\frac{5}{21}$ b. $34\frac{2}{3}$ c. 10 d. $2\frac{11}{12}$
8. a. $1\frac{2}{3}$ b. $\frac{9}{14}$ c. 1 d. $22\frac{1}{3}$
9. a. 3 b. $2\frac{29}{40}$ c. $1\frac{8}{15}$ d. $2\frac{1}{14}$
10. $1\frac{5}{6}$L
11. $1\frac{5}{16}$ inches

12. $1\frac{1}{12}$ months
13. $6\frac{1}{4}$ days
14. $\frac{3}{16}$ kg
15. a. 22 b. 96
16. $\frac{3}{8}$ cup sugar
$\frac{3}{8}$ cup margarine
$\frac{3}{4}$ cup peanut butter
3 eggs
$2\frac{1}{4}$ cups milk
$3\frac{3}{4}$ cups self-raising flour
$\frac{3}{8}$ teaspoon baking soda
17. $3\frac{1}{10}$ kg
18. 7 containers
19. $52.50
20. a. $3\frac{15}{16}$cm b. $2\frac{15}{16}$cm
21. 500 women
22. We could convert $3\frac{1}{3}$ to an improper fraction, $\frac{10}{3}$. We would then multiply it by $\frac{1}{2}$.
$\frac{10}{3} \times \frac{1}{2} = \frac{10}{6} = \frac{5}{3} = 1\frac{2}{3}$
Alternatively, we could draw a picture of $3\frac{1}{3}$ circles and divide each by $\frac{1}{2}$, and then add these fractions together, giving us a result of $1\frac{2}{3}$.
23. $\frac{5}{12}$, 10
24. a. $6\frac{2}{3}$ laps b. 12 minutes
25. 2961 m
26. The gymnasium should keep the drink machine.

Exercise 4.9 Percentages as fractions

1. a. $\frac{17}{100}$ b. $\frac{29}{100}$ c. $\frac{79}{100}$ d. $\frac{99}{100}$ e. $\frac{3}{100}$
2. a. $\frac{19}{100}$ b. $\frac{33}{100}$ c. $\frac{9}{100}$ d. $\frac{243}{100}$ e. $\frac{127}{100}$
3. a. $\frac{1}{2}$ b. $\frac{4}{5}$ c. $\frac{7}{20}$ d. $\frac{3}{5}$ e. $\frac{1}{10}$
4. a. $\frac{9}{20}$ b. $\frac{3}{25}$ c. $\frac{1}{20}$ d. $\frac{37}{50}$ e. $\frac{1}{50}$
5. a. $1\frac{1}{2}$ b. $1\frac{4}{5}$ c. $\frac{2}{1} = 2$ d. $\frac{5}{1} = 5$ e. $1\frac{3}{25}$
6. a. $\frac{7}{200}$ b. $\frac{9}{125}$ c. $\frac{197}{1000}$ d. $\frac{81}{250}$
7. a. $\frac{31}{200}$ b. $\frac{81}{500}$ c. $\frac{283}{1000}$ d. $\frac{2069}{5000}$
8. a. $\frac{907}{5000}$ b. $\frac{5799}{10\,000}$ c. $\frac{243}{2000}$ d. $\frac{1}{2000}$
9. a. $\frac{1}{200}$ b. $\frac{1}{500}$ c. $\frac{1}{150}$ d. $\frac{1}{1000}$ e. $\frac{3}{550}$
10. a. $\frac{33}{400}$ b. $\frac{31}{150}$ c. $\frac{29}{300}$ d. $\frac{31}{200}$ e. $\frac{14}{125}$
11. a. $\frac{83}{800}$ b. $\frac{7}{60}$ c. $1\frac{101}{200}$ d. $1\frac{41}{200}$ e. $\frac{1}{3}$
12. B
13. E
14. C
15. $\frac{20}{100} = \frac{1}{5}$
16. $\frac{35}{100} = \frac{7}{20}$
17. $\frac{45}{100} = \frac{9}{20}$
18. 32% were born overseas $\frac{8}{25}$
19. a. $\frac{4}{5}$
b. $\frac{1}{5}$
c. Not necessarily. There could be an overlap of students with blue eyes who have pets.
20. a. $\frac{4}{5}$
b. $\frac{1}{2}$
c. Although the two molecules contain the same number of hydrogen atoms, the total number of atoms differs between the two molecules.
21. a. She scored a higher percentage in the second game (75%).
b. i. Increased percentage
ii. Unchanged
iii. Decreased percentage
22. Less than $\frac{1}{2}$
23. a. $\frac{2}{25}$ b. $\frac{23}{25}$ c. 8 people
24. a. $\frac{7}{20}$ b. $\frac{81}{100}$ c. $\frac{17}{20}$ d. $\frac{13}{200}$
25. a. $\frac{17}{100}$ b. $\frac{83}{100}$ c. 17

Exercise 4.10 Calculating percentages of an amount

1. a. 180 b. 4 c. 60
2. a. $1\frac{1}{2}$ b. $10\frac{1}{2}$ c. 78

3. a. 10 b. 16 c. 3 d. 18 e. 6

4. a. 6 b. 77 c. 4000 d. 66 e. 17

5. a. 39 b. 95 c. 55 d. 12 e. 25

6. a. $3\frac{3}{5}$ b. $4\frac{4}{5}$ c. $7\frac{7}{10}$ d. $18\frac{1}{2}$ e. $13\frac{1}{5}$

7. a. $24\frac{3}{4}$ b. $11\frac{1}{10}$ c. $58\frac{9}{10}$ d. $20\frac{4}{5}$ e. $98\frac{2}{5}$

8. A

9. D

10. E

11. E

12. B

13. E

14. D

15. 210 students

16. 73 days

17. 1 person

18. a. 80% b. 1600 people

19. a. $22 b. $572

20. $1 600 000

21. $12 000

22. 47 species

23. 600 000 people

24. a. Peter calculated 35% of 80 mL rather than 800 mL.
b. 280 mL

25. a. 7 adults b. 19 adults

26. 29 houses

27. 38 workers

28. a. 12 houses b. 11 houses

29. 3

30. a. 200 g, 100 g, 50 g, 25 g and 12.5g
b. 50%, 25%, 12.5%, 6.25% and 3.125%
c. Every 20 days the quantity of the radioactive substance is smaller so there is a 50% reduction of an already reduced quantity.

31. 22.5%

32. 3 students voted twice.

33. 120

Exercise 4.11 One amount as a percentage of another

1. a. 20% b. 25% c. 10% d. 40% e. 25%

2. a. 80% b. 32% c. 40% d. 20% e. 5%

3. a. 25% b. $31\frac{1}{2}\%$ c. $6\frac{1}{4}\%$ d. $6\frac{2}{5}\%$ e. $20\frac{2}{3}\%$

4. a. $87\frac{1}{2}\%$ b. $28\frac{4}{7}\%$ c. $66\frac{2}{3}\%$ d. $36\frac{2}{3}\%$ e. $26\frac{2}{3}\%$

5. a. $7\frac{1}{7}\%$ b. $22\frac{2}{9}\%$ c. $42\frac{6}{7}\%$ d. $88\frac{8}{9}\%$ e. $71\frac{3}{7}\%$

6. a. 17% b. 33% c. 63% d. 11%

7. a. 83% b. 78% c. 18% d. 12%

8. a. 10% b. $3\frac{1}{3}\%$ c. $12\frac{1}{2}\%$

9. a. $28\frac{4}{7}\%$ b. 25% c. $1\frac{1}{4}\%$

10. D

11. A

12. B

13. E

14. 70%

15. 60%

16. a. $5 b. $33\frac{1}{3}\%$

17. a. i. 10% ii. 14% iii. 12%
b. 36%
c. 64%

18. $62\frac{1}{2}\%$

19. $6\frac{2}{3}\%$

20. a. 20 km/h b. $16\frac{2}{3}\%$

21. a. $42\frac{6}{7}\%$ b. $28\frac{4}{7}\%$ c. $71\frac{3}{7}\%$ d. $57\frac{1}{7}\%$

22. $27\frac{3}{11}\%$

23. a. Second recipe. The second recipe contains 50% flour compared to 40% in the first recipe.
b. The percentage of flour increases

24. a. Less than $100 because 25% of the new amount is larger than the amount added. So, a higher amount is subtracted.
b. Sample responses can be found in the worked solutions in the online resources.

25. Sister is 9; grandfather is 90.

26. a.

Topic	Prob.	M'ment	Algebra	Eqns	Geo.
Score	$\frac{15}{20}$	$\frac{13}{15}$	$\frac{27}{30}$	$\frac{70}{80}$	$\frac{95}{100}$
Percentage	75	87	90	88	95

b. Geometry
c. 87%

27. a. 300 g out of 450 g (300 g out of 450 g represents 67%.)
b. 200 g out of 500 g (200 g out of 500 g represents 40%.)
c. 420 g out of 840 g and 350 g out of 700 g (420 g out of 840 g and 350 g out of 700 g both represent 50%.)

28. Expressing one quantity as a percentage of another quantity allows us to compare the two quantities.

29. a. First recipe. The first type of concrete contains 15.4% cement, and the second type of concrete contains 11.8% cement.
b. The percentage of cement decreases.

30. 4520 km

Exercise 4.12 Common percentages and short cuts

1. a. $1.00 b. $1.80 c. $8.10 d. $15.00 e. $9.30
2. a. $2.20 b. $1.70 c. $1.25 d. $0.15 e. $4.80
3. a. $19.25 b. $50.70 c. $192.60 d. $304.15 e. $200.00
4. a. $1.50 b. $5.10 c. $0.90 d. $13.70 e. $0.45
5. a. $0.65 b. $3.90 c. $7.50 d. $10.30 e. $6.80
6. a. $51.80 b. $30.50 c. $62.85 d. $10.05 e. $20.70
7. a. $0.40 b. $0.30 c. $0.10 d. $7.00 e. $2.10
8. a. $0.55 b. $15.25 c. $50 d. $5.15 e. $1.60
9. a. $4.30 b. $8.45 c. $0.65 d. $14.80 e. $0.15
10. a. $3.30 b. $27.15 c. $52.35 d. $247.40 e. $1013.80
11. a. $1.80 b. $1.20 c. $9.00
12. a. $7.50 b. $22.50 c. $55.00
13. a. $4.50 b. $7.50 c. $14.25
14. a. $2.70 b. $7.15 c. $6.05 d. $0.05 e. $0.15
15. a. $0.15 b. $0.80 c. $0.20 d. $0.05 e. $0.05
16. a. $1.30 b. $10.50 c. $0.65 d. $2.40 e. $1.80
17. a. $73.50 b. $1.55 c. $1.05 d. $2.05 e. $32.20
18. a. $4.80 b. $1.60 c. $0.45 d. $14.40 e. $492
19. D
20. B
21. E
22. C
23. $855
24. 54 000 residents
25. a. $322.50 b. $152.30
26. 110 students
27. 27.9 seconds
28. a. 2 people b. 38 people
29. a. 10 740 people
    b. 19 690 people
    c. 5370 people
30. 20 years old
31. $0.80
32. 8.2kg
33. 50 years old
34. a. 100%
    b. i. 100% ii. 50% iii. 71.4%
    c. No, because the two lengths have changed at different percentages
35. a. 3.2%
    b. 6.8%
    c. The overall percentage is a lot smaller.

Project

1. A and D, B and C, E and F

2–6. Sample responses can be found in the worked solutions in the online resources.

Exercise 4.13 Review questions

1. $\frac{3}{20}$
2. a. $\frac{6}{16}, \frac{9}{24}, \frac{12}{32}$ b. $\frac{8}{18}, \frac{12}{27}, \frac{16}{36}$ c. $\frac{10}{22}, \frac{15}{33}, \frac{20}{44}$ d. $\frac{12}{14}, \frac{18}{21}, \frac{24}{28}$
3. a. $\frac{2}{4} = \frac{3}{6}$ b. $\frac{3}{9} = \frac{5}{15}$ c. $\frac{9}{12} = \frac{21}{28}$ d. $\frac{4}{10} = \frac{16}{40}$
4. a. Leo b. Ricky
5. a. $\frac{6}{7}$ b. $\frac{3}{4}$ c. $\frac{9}{10}$ d. $\frac{3}{4}$
6. a. $\frac{1}{3}$ b. $\frac{3}{5}$ c. $\frac{1}{40}$ d. $\frac{1}{2}$
7. a. $6\frac{4}{5}$ b. $3\frac{2}{3}$ c. $4\frac{3}{4}$ d. $1\frac{1}{5}$
8. $\frac{3}{12} = \frac{1}{4}$
9. a. $5\frac{1}{3}$ b. $4\frac{1}{5}$ c. $1\frac{5}{7}$ d. $5\frac{1}{2}$
10. a. $1\frac{1}{4}$ b. $11\frac{3}{7}$ c. $6\frac{1}{9}$ d. $7\frac{1}{5}$
11. a. $\frac{11}{4}$ b. $\frac{79}{8}$ c. $\frac{26}{7}$ d. $\frac{35}{6}$
12. a. $\frac{11}{3}$ b. $\frac{99}{10}$ c. $\frac{47}{12}$ d. $\frac{17}{2}$
13. 4 trays
14. a. $\frac{23}{24}$ b. $\frac{17}{45}$ c. $1\frac{1}{15}$
15. a. $\frac{20}{63}$ b. $\frac{6}{25}$ c. $\frac{5}{8}$ d. $\frac{7}{36}$
16. a. 44 b. 22 c. $\frac{1}{6}$ d. $\frac{50}{3}$ or $16\frac{2}{3}$
17. a. $\frac{2}{5}$ b. 9 c. 4 d. $\frac{4}{23}$
18. a. $\frac{3}{2}$ or $1\frac{1}{2}$ b. $\frac{4}{3}$ or $1\frac{1}{3}$ c. $\frac{7}{36}$ d. $\frac{3}{70}$
19. a. $4\frac{17}{24}$ b. $1\frac{13}{14}$ c. $3\frac{7}{9}$ d. $2\frac{2}{3}$
20. a. $3\frac{43}{72}$ b. $\frac{76}{99}$ c. $3\frac{2}{3}$ d. $6\frac{5}{18}$
21. a. 64 b. $\frac{3}{5}$ c. $13\frac{2}{3}$ d. $1\frac{1}{2}$
22. a. $\frac{5}{16}$ b. $1\frac{3}{5}$ c. $1\frac{53}{115}$ d. $\frac{217}{267}$
23. a. $\frac{13}{100}$ b. $\frac{7}{10}$ c. $\frac{13}{50}$ d. $\frac{33}{25} = 1\frac{8}{25}$
24. a. 15% b. 55% c. 60% d. 50%

25. **a.** $37\frac{1}{2}\%$ **b.** $53\frac{1}{3}\%$ **c.** $83\frac{1}{3}\%$ **d.** $36\frac{4}{11}\%$

26. **a.** 6 **b.** 12 **c.** 39 **d.** 39

27. **a.** $6\frac{3}{10}$ **b.** $37\frac{1}{10}$ **c.** $4\frac{4}{5}$ **d.** $13\frac{3}{5}$

28. **a.** 60% **b.** 30% **c.** 40% **d.** 40%

29. **a.** $7\frac{1}{7}\%$ **b.** $11\frac{1}{9}\%$

30. **a.** \$0.40 **b.** \$1.05 **c.** \$3.20 **d.** \$5.20

31. **a.** \$0.15 **b.** \$0.30 **c.** \$5.05 **d.** \$27.00

32. $7.1 = \frac{1}{8}$, $7.2 = \frac{1}{4}$, $7.3 = \frac{5}{32}$, $7.4 = \frac{5}{32}$, $7.5 = \frac{7}{40}$, $7.6 = \frac{11}{80}$

33. \$150

34. 2kg

35. **a.** $\frac{1}{6}$ **b.** $\frac{1}{4}$
c. $\frac{5}{9}$ **d.** $\frac{48}{25} = 1\frac{23}{25}$

36. All fractions that are equivalent to $\frac{4}{7}$ will be of the form $\frac{4n}{7n}$ where n is some number. The product of the numerator and denominator is therefore $4nx7n = 28n^2$. Equating this product to 252:
$252 = 28n^2$
$n^2 = 9$
$n = \pm 3$
Substituting $n = +3$ gives a fraction of $\frac{12}{21}$, which is equivalent to $\frac{4}{7}$ and for which the product of the numerator and denominator is 252.
$\frac{12}{21}$

37. Tomas

38. $\frac{1}{2} + \frac{1}{4} + \frac{1}{20}$ or $\frac{1}{2} + \frac{1}{5} + \frac{1}{10}$

39. Mr Thompson \$3000, Mr Goody \$2500

40. $\frac{3}{5}$ of the standard spots were filled.

41. **a.** 4 complete surfboards
b. $2\frac{1}{4}$kg of resin, 0 catalyst

42. **a.** 62% **b.** 75%

43. 24 students

44. 270 children

45. 8%

46. \$11 600

47. **b**, **d**

48. 13.5 litres of milk would be needed to make the fat of 500 g of butter.

49. 45%

50. **a.** \$2250
b. \$2025
c. 19%
d. The second 10% discount is not 10% of the original price but 10% of an amount, which is only 90% of the original.

51. **a.** \$1575
b. \$1575
c. It doesn't matter which discount is applied first; the final price will be the same.

52. Sample responses can be found in the worked solutions in the online resources.

5 Ratios, rates and best buys

LEARNING SEQUENCE

5.1 Overview 264
5.2 Ratios 267
5.3 Rates 273
5.4 The unitary method and best buys 278
5.5 Review 283



5.1 Overview

Why learn this?



Ratios and rates are used to compare different quantities. Ratios compare quantities of the same kind. For example, in a class of Year 7 students, if 20% walk to school and 80% don't, this can be expressed as a ratio of 1 to 4. This means that for every 1 student who walks to school, 4 students don't. Ratios are used in design or architectural drawings, with a drawing being an exact 'miniature' or scale diagram of the item to be made. Plans for a new home would be drawn at a ratio of 1 : 1000, which means that every 1 mm on the plan represents 1000 mm in the new home. In comparison, rates enable you to compare quantities expressed in different units. Speed is an example of a rate; it compares distance travelled with the time taken, and is measured in km/h or m/s. You will see speed signs whenever you go for a drive. Rates and ratios help you make choices, too, such as when you decide which box of chocolates to purchase. Civil engineers examine rates of water flow, which helps them to design pipes that ensure the water gets to your home. Electrical engineers examine rates for stepping up and stepping down voltage, which ensures electricity is able to get to your home. Business managers explore various types of costed rates to ensure they always get the 'best deal'. Carpenters evaluate different rates to ensure they order enough timber to complete a job, and doctors and pharmacists calculate different rates to ensure you take the right amount of medicine based upon your height and weight. By comparing price and quantity, you can choose the 'best buy', which is the item with the lowest price per unit. Architects, chefs, engineers, fashion designers and builders all use rates and ratios in their field of work.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.




Exercise 5.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. A cake mixture contains 1 cup of sugar and 2 cups of flour. Express this statement as a ratio.

2. For the diagram shown, write the following ratios in simplest terms.
   a. shaded parts: unshaded parts
   b. shaded parts: total number of parts



3. Express each of the following as a fraction.
   a. 5 pears to 7 oranges
   b. 500 m to 2 km
   c. 7 basketballs to 35 tennis balls
   d. 8 hours to 120 minutes

4. MC Select which of the following options is the simplest form of the ratio 8 : 32.
   A. 4 : 1 B. 1 : 4 C. 4 : 2 D. 2 : 8 E. 4 : 16

5. A school has 2 students who wear glasses to every 5 students who don't wear glasses. A particular class where this ratio applies has 8 students who wear glasses. Calculate how many students don't wear glasses in this class.



6. MC Select which of the following are the same as the ratio 5 cm to 1 m. Select all answers that apply.
   A. 1 : 20 B. 5 : 100 C. 2 : 50
   D. 2 : 25 E. 25 : 500

7. MC Select which of the following is the best buy when buying a packet of cookies.
   A. 150 g for $1.75 B. 200 g for $2.30 C. 250 g for $2.75
   D. 350 g for $3.55 E. 500 g for $5.45

8. A bus is travelling at a speed of 60 km per hour. Calculate how long it takes to travel 145 km.

9. Hot chocolate can be bought in 250 g jars for $9.50 or in 100 g jars for $4.10. Calculate the cheaper way to buy the hot chocolate, and how much cheaper it is per 100 g.



10. Write 16 hours to 1 day as a simplified ratio.

11. Express the following as rates in the units given.

a. 464 words written in 8 minutes, in the unit words/minute

b. 550 litres of water flowing through a pipe in 12 minutes, in the unit kL/h



12. The price of an item is reduced by 10%, then increased by 11.1%. This takes the item back to its original price (to the nearest dollar). True or false?

13. Out of 100 customers selected for a mobile internet usage survey, 63 customers were aged less than 25 years, 28 customers were aged 25–65 years and the rest were aged over 65 years.

a. Write the ratio of customers aged 25–65 years to those aged less than 25 years.

b. Write the ratio of customers aged over 65 years to those aged 25–65 years.

c. Write the ratio of customers aged less than 25 years to the total number of customers surveyed.

d. Write the number of customers aged less than 25 years as a fraction of the total number of customers surveyed.

14. If 12 oranges costs $6.00, explain how much it will cost to buy 5 oranges.



15. If Eva takes 3 hours to clean a room and Will takes 5 hours to clean a room, determine how long it will take to clean a room if they work together.

5.2 Ratios

LEARNING INTENTION

At the end of this subtopic you should be able to:

- compare quantities using ratios
- simplify ratios.

5.2.1 Introduction to ratios

eles-3886

- **Ratios** are used to compare quantities of the same kind in the same unit.
- The basketball team finished the season with a loss : win ratio of 1 to 4.
- The order of the numbers in a ratio is important. If the ratio of loss to win is 1 : 4, the 1 corresponds to the loss and the 4 corresponds to the win.



1 : 4

There is **one** blue square to **four** pink squares.

Expressing ratios

- A ratio of 1 to 4 is written as 1 : 4 (the quantities are separated by a colon) and is read as 'one to four'.
- Ratios can also be written in fraction form:

$$1:4 \longleftrightarrow \frac{1}{4}$$

- Ratios **do not** have **names** or **units** of measurement.
- Ratios contain only whole numbers.

WORKED EXAMPLE 1 Expressing quantities as ratios

Express each of the following statements as a ratio.

a. The fertiliser contains 3 parts of phosphorus to 2 parts of potassium.

b. Mix 1 teaspoon of salt with 3 teaspoons of flour.

THINK	WRITE
a. Write the 3 parts of phosphorus to 2 parts of potassium as a ratio (the number of parts of phosphorus should be written first).	a. 3 : 2
b. Write the 1 teaspoon of salt with 3 teaspoons of flour as a ratio (the number of teaspoons of salt should be written first).	b. 1 : 3

WORKED EXAMPLE 2 Expressing quantities as fractions

Express each of the following as a fraction.
a. 5 cm to 7 cm
b. 3000 m to 2 km

THINK	WRITE
a. 1. Write the 5 cm to 7 cm as a ratio by replacing 'to' with ':' (5 cm should be written first). As the two numbers have the same unit, units are not included.	**a.** 5 : 7
2. Write the ratio as a fraction by placing the first number as a numerator and the second number as a denominator (no unit required).	$\frac{5}{7}$
b. 1. Express both quantities in the same units. Convert 3000 m to km or 2 km to m.	**b.** 3000 m to 2 km 3000 m to 2000 m
2. Write the 3000 m to 2000 m as a ratio by replacing 'to' with ':' (3000 m should be written first). Omit the units and simplify.	3000 : 2000 3 : 2
3. Write the ratio as a fraction by placing the first number as a numerator and the second number as a denominator.	$\frac{3}{2}$

5.2.2 Simplifying ratios

eles-3887

- Equivalent ratios are ratios in which both numbers are multiplied or divided by the same number.
  For instance, the ratios 2 : 3 and 4 : 6 are equivalent, as the second ratio can be obtained by multiplying both parts of the first ratio by 2.
  The ratios 10 : 5 and 2 : 1 are also equivalent, as the second ratio is obtained by dividing both parts of the first ratio by 5.
- Ratios are usually written in simplest form — that is, reduced to lowest terms. This is achieved by dividing each number in the ratio by the highest common factor (HCF).


Simplification of ratios

Equivalent ratios are always multiplied or divided by the same number. They work in the same way as equivalent fractions.



WORKED EXAMPLE 3 Simplifying ratios


Express the ratio 9 : 15 in simplest form.

THINK	WRITE
1. Determine the largest number by which both 9 and 15 can be divided (that is, the highest common factor, HCF). It is 3.	The HCF is 3.
2. To go from the ratio with the larger values to the ratio with the smaller values, divide both 9 and 15 by 3 to obtain an equivalent ratio in simplest form.	
3. Write the answer.	3 : 5

Digital technology


Since simplifying ratios follows a similar process to simplifying fractions, a calculator can be used to help check your answer. For example, in Worked example 3 the ratio 9 : 15 was simplified to 3 : 5.

Using a calculator, input 9 ÷ 15, then use the decimal to fraction button to display the answer as a fraction in simplest form.



WORKED EXAMPLE 4 Simplifying ratios of quantities expressed in different units

Write the ratio of 10 cm to 30 mm in simplest form.

THINK	WRITE
1. Write the question.	10 cm to 30 mm
2. Express both quantities in the same units by changing 10 cm into mm (1 cm = 10 mm).	100 mm to 30 mm
3. Omit the units and write the two numbers as a ratio.	100 : 30
4. Determine the HCF by which both 100 and 30 can be divided. It is 10.	The HCF is 10.
5. Simplify the ratio by dividing both sides by the HCF.	
6. Write the answer.	10 : 3

Resources

eWorkbook Topic 5 Workbook (worksheets, code puzzle and project) (ewbk-1906)

Interactivities Individual pathway interactivity: Introduction to ratios (int-4412)
Introduction to ratios (int-3956)
Simplification of ratios (int-3949)

Exercise 5.2 Ratios

learnON

Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 4, 5, 10, 12, 15, 18	2, 6, 8, 11, 13, 16, 19	3, 7, 9, 14, 17, 20

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 Express each of the following statements as a ratio.
   a. The cake mixture contains 2 cups of flour and 5 cups of water.
   b. Mix 1 cup of sugar with 3 cups of milk.
   c. Sebastian Vettel's F1 car is twice as fast as Mick's delivery van.
   d. The Tigers team finished the season with a win to loss ratio of 5 to 2.

2. For the rectangle shown:
   a. write the ratio of unshaded parts to shaded parts
   b. write the ratio of unshaded parts to the total number of parts.



3. Explain why order is important when writing ratios.

4. WE2 Express each of the following as a fraction.
   a. 5 wins to 7 losses
   b. 3500 m to 25 km
   c. 3 apples to 4 oranges
   d. 10 basketballs to 3 tennis balls

5. WE3 Express the following ratios in simplest form.
   a. 75 : 60 b. 154 : 24 c. 36 : 6 d. 48 : 42

6. WE4 Express the following ratios in simplest form.
   a. 7 cm : 9 cm
   b. 120 minutes : 2 hours
   c. 240 g : 2 kg
   d. 5 weeks to 2 months

7. Express the following ratios in simplest form.
   a. 5 cm : 10 mm
   b. 600 g : 8 kg
   c. 24 hours : 16 minutes
   d. 21 boys : 14 girls

8. Draw rectangles to represent the following ratios.
   a. Shaded area to unshaded area is 1 : 1
   b. Shaded area to unshaded area is 2 : 7
   c. Unshaded area to shaded area is 2 : 3
   d. Unshaded area to shaded area is 3 : 1

9. Complete the patterns of equivalent ratios.

a. 1 : 4
2 : 8
_____ : 12
_____ : 16
5 : _____


b. 2 : 3
4 : 6
8 : _____
_____ : 15
_____ : 21

c. 64 : 32
_____ : 16
_____ : 8
8 : _____
_____ : 1

d. 48 : 64
_____ : 32
_____ : 16
6 : _____
_____ : 4

Understanding

10. The length to width ratio of the Australian flag is 2 : 3. If the length of the flag is 60 cm, determine the width of the flag.



11. Compare the following, using a mathematical ratio (in simplest form).

a. The Tigers beat the Cats by 81 points to 60 points.
b. The cost of a bag of Maltesers chocolate is $3, but Darrell Lea chocolate costs $5.
c. In the movie audience, there were 160 children and 24 adults.
d. During the race, Rebecca's average speed was 300 km/h while Donna's average speed was 120 km/h.

12. Copy and complete each of the following equivalent ratios.
a. 1 : 3 = ___ : 12 **b.** 2 : 3 = 4 : ___ **c.** 66 : 48 = : ___ : 8 **d.** 36 : 72 = 12 : ___

13. Copy and complete each of the following equivalent ratios.
a. 20 : 12 = : __ : 3 **b.** __ : 6 = 8 : 24 **c.** 8 : 6 = __ : 72 **d.** 40 : __ = 5 : 6

14. The table shows the nutritional information from a box of cereal.

Nutritional information	Average quantity per serving
Energy	660 kJ
Protein	4.5 g
Fat	0.1 g
Carbohydrates	22 g
Sugars	2 g
Fibre	3 g
Sodium	55 mg



Write the following ratios in simplest form.

a. Sugar to total carbohydrate
b. Fat to protein
c. Protein to fibre
d. Sodium to protein

Reasoning

15. The cost of tickets to two different concerts is in the ratio 4 : 7. If the more expensive ticket costs $560, then determine the cost of the cheaper ticket.

16. A student received a score of $\frac{77}{100}$ for a Maths test.

a. Write the ratio of the total marks received compared with the total marks lost.
b. Write the ratio of the total marks lost compared with the total possible marks.

17. The total attendance at a concert was 62 400 people. Of this total, 24 800 people were male.

a. Calculate how many females attended the concert.
b. Compare the number of females to males by writing the ratio in simplest form.
c. Write the number of females as a fraction of the number of males.

Problem solving

18. The ratio of gold coins to silver coins in a purse is 2 : 5. If there are 10 gold coins in the purse, determine the smallest number of coins that needs to be added so that the ratio of gold coins to silver coins changes to 3 : 4.

19. Out of 200 people selected for a school survey, 168 were students, 20 were teachers and the rest were support staff.

a. Write the ratio of teachers to students.
b. Write the ratio of support staff to teachers.
c. Write the ratio of students to people surveyed.
d. Write the number of teachers as a fraction of the number of people surveyed.

20. You drop a rubber ball from a height of 10 m. The ball rebounds to a height of 8 m and then to a height of 6.4 m. The ball continues to bounce in the same ratio.

a. Calculate the height of the ball when the top of its bounce is less than 3 m.
b. Determine on which number bounce this occurs.

5.3 Rates

LEARNING INTENTION

At the end of this subtopic you should be able to:

- identify and express a rate from a written context
- simplify a rate and express the rate in its simplest form
- apply a rate to calculate the total value of an unknown quantity.

5.3.1 Identifying rates

eles-3888

- A **rate** is used to compare two measurements of different kinds that are in different units.
- A rate describes and compares how quantities change.
- Rates have units. An example of a rate is speed (measured in km/h or m/s). A speed limit sign tells the driver that the maximum speed they are allowed to drive is 25 kilometres per hour.
- A slash (/), which is the mathematical symbol for 'per', is used to separate two different units.
- A rate is in its simplest form if it is per one unit.
- Rates are often written out as one quantity **per** another quantity.
- In this way, you can easily compare the first quantity to the second.



Expressing rates

First quantity per second quantity

or

$$\frac{\text{first quantity}}{\text{second quantity}}$$

WORKED EXAMPLE 5 Expressing rate from a worded problem

Jennifer goes for a run every Monday morning and knows that she can run 3 kilometres in 15 minutes. Express, as a rate, the speed at which she can run.

THINK

1. Speed is a rate the measures distance over time. From the question, determine the values for distance and time.
2. Express the rate as first quantity (distance) per second quantity (time) and write the answer.

WRITE

Distance = 3 km
Time = 15 minutes

3 km per 15 min

WORKED EXAMPLE 6 Expressing rate from a worded problem


Max notices on his food packaging there is a warning that tells him the sugar content in one serving is equal to 25 g. Rewrite this information in the form of a rate.

THINK	WRITE
1. Read the question carefully and determine two quantities. In this question, quantities are sugar and serving size.	Sugar = 25 g Serving size = 1 serve
2. Express rate as first quantity (sugar) per second quantity (serve) and write the answer.	25 g per 1 serve
3. As there is only 1 serving size, this can be written more simply as 25 g per serve.	25 g per serve


eles-3889

5.3.2 Simplifying rates

- It is often most useful to express rates in their simplest form.
- For instance, in Worked example 5, Jennifer knows she can run 3 kilometres in 15 minutes — speeds are usually given in kilometres per hour.
- To **convert** this rate of 3 km per 15 minutes into a rate of kilometres per hour (km/h), we multiply minutes by 4. That is because there are four lots of 15 minutes in every hour.




- To keep the rate the same, what we do to one side of the rate is what we also have to do to the other. This ensures that we do not change the rate's **value**.
- This only works for multiplying and dividing, and not for adding or subtracting.



- Thus, the rate in kilometres per hour (km/h) is written as 12 km/h.

Converting units



WORKED EXAMPLE 7 Simplifying rates


Madison works for 4 hours at her local bakery. At the end of the week, she has earned $100 for her work. Calculate how much Madison earns in dollars per hour.

THINK

1. Read the question carefully and determine two quantities. In this question, the quantities are dollars and hours.
2. Express as a ratio of the first quantity (dollars) to the second quantity (hours). Remember to write out the units.
3. To convert the rate unit to dollars per hour we need to divide the hours by 4, to reduce 4 hours to 1 hour. Remember that what we do to one side of the rate, we must also do to the other side. Therefore, we also divide dollars by 4.
4. Write the answer as a rate in the correct units.

WRITE

Dollars = 100
Hours = 4



Madison earns $25 per hour.

eles-3890

5.3.3 Applications of rates


- Rates can be applied to find the total quantity of a measure being compared.
- For example, rate (speed) and time (second quantity) can be applied in order to calculate the total distance (first quantity) covered.

Arranging rate formula

$$\text{Rate} = \frac{\text{first quantity}}{\text{second quantity}}$$

$$\text{First quantity} = \text{rate} \times \text{second quantity}$$

$$\text{Second quantity} = \text{first quantity} \div \text{rate}$$



WORKED EXAMPLE 8 Applying rate to calculate an unknown quantity


Rick has a job at the local cinema, where he is able to earn $22 per hour. If Rick works for 12 hours this week, calculate how much money he will earn in total.

THINK

1. Express the quantities given in the question as rate. The first quantity is dollars and the second quantity is hours.

WRITE

Rate = dollars per hour



2. To calculate the first quantity (money earned), rearrange the rate formula.	First quantity = rate × second quantity
3. State the number of hours worked.	Hours worked = 12
4. To calculate the total payment, multiply the hourly payment by the total number of hours worked.	Total payment = \$22 × 12 = \$264
5. Write the answer with correct units (in this case the unit is dollars).	Rick will earn \$264 in 12 hours.

Resources

eWorkbook Topic 5 Workbook (worksheets, code puzzle and project) (ewbk-1906)

Digital documents
SkillSHEET Converting a mixed number into an improper fraction (doc-6471)
SkillSHEET Multiplying decimals by 10, 100 and 1000 (doc-6466)
SkillSHEET Multiplying a whole number by a fraction (doc-6894)
SkillSHEET Converting minutes to a fraction of an hour (doc-6895)

Interactivities
Individual pathway interactivity: Rates (int-4417)
Rates (int-3738)

Exercise 5.3 Rates

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13	2, 5, 8, 11, 14	3, 6, 9, 12, 15

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE 5 & 6 Identify the rates in the following circumstances and write them out in the form of one quantity per another quantity.
   a. Amir is watering the garden. He notices that he can fill his watering can up with water in one minute. The watering can is able to hold 7 litres of water. Express this as the rate at which the water is filling the can.
   b. James is training for his upcoming cricket game. If his current rate of runs per ball continues, he will make 33 runs from 7 balls. Write this as the rate of runs per ball.
   c. Tilly pays \$6.00 for a bunch of bananas. State the cost of bananas per bunch.
   d. Cherese works at the local supermarket where, in a four-hour shift, she earns \$80.00. Calculate the rate at which she is being paid.
   e. Jessica swims every second morning. She knows that, in a 25-metre pool, she is able to swim 20 lengths in 15 minutes. Write her rate of swimming. Give your answer in metres per minute. You do not need to simplify your answer.

2. WE7 Simplify the following rates, giving your answer as the unit rate where possible.
   a. 15 km per 30 minutes. Give your answer in the units km per hour.
   b. \$150.00 for 6 hours of work. Give your answer in the units dollars per hour.
   c. A 14 m length of timber costs \$21.00. Give your answer in the units dollars per metre.

3. Simplify the following rates, giving your answer as the unit rate where possible.
   a. 100 m was covered in 20 seconds. How many metres were covered per second?
   b. It cost $180.00 to wallpaper a room with a wall space of 50 m^2. How much did the wallpaper cost per square metre?
   c. If a 5.5 kg bag of almonds cost $19.25, how much do almonds cost per kilogram?
   d. It costs $300.00 to carpet a room that is 8 m^2. What is the cost of carpet per square metre?

4. WE8 Patrick cycles for 2 hours, at a speed of 18 km/h. Calculate how far he has cycled.

5. Jackson works a 5-hour shift at the local bakery. If he is paid $85.00 for this shift, calculate his hourly pay rate.

6. A train is travelling at a speed of 50 km per hour. Calculate how long it takes to travel 150 km.

Understanding

7. Larah is working in the garden and buys 50 kg of premium potting mix for $75.00. Calculate how much the potting mix costs per kilogram.

8. Jacob was driving at a constant speed for 30 minutes. If he travelled for 35 km, calculate his speed.

9. Anthony was riding his bike at an average speed of 25 km/h. If he managed to cover a distance of 40 km, calculate how long his bike ride was (to the nearest minute).

Reasoning

10. If 10 pears costs $15.00, explain how much it will cost to buy 5 pears.

11. If Michael can run 30 km in 3 hours, explain how long it will take him to run 20 km at a constant speed.

12. If Jaye can swim 400 metres in a time of 6 minutes and 45 seconds, calculate how long it will take her to swim 800 metres if she is swimming at a constant speed.

Problem solving

13. Water is poured into a canister at a rate of 6 L/ min. If the canister can hold 24 litres of water, calculate:
   a. how long will it take to fill the canister
   b. how long will it take to fill two canisters of the same size
   c. how long will it take until the canister is half full
   d. how long will it take to fill the canister with 18 litres of water.

14. Kelly is paid $14.25 per hour for her job working in retail. She is looking to save $240 to buy a new monitor for her computer and she knows she can only be rostered on for 4-hour shifts at work.
   a. Calculate how many hours she will need to work in order to buy the monitor. Round your answer to the nearest hour.
   b. Calculate how many 4-hour shifts she will need to complete in order to achieve this.
   c. After working enough 4-hour shifts, determine how much money is left over if she were to buy the monitor.

15. Charlee works two jobs, one at a supermarket and another as a basketball coach at weekends. She earns an hourly wage of $13.75 for her job at the supermarket and is paid a flat rate of $25.00 per week for coaching basketball. At the supermarket, the work roster is such that each shift goes for three hours and she cannot do more than one shift per day.
   a. If she is rostered on to work for 4 days this week, calculate how much money she will earn for the entire week, including her work as a basketball coach.
   b. At this rate, calculate how much money Charlee will earn for 3 weeks of work.
   c. Charlee worked for 24 hours at the supermarket over a 3-week period. Calculate how much money she earned in this time.

5.4 The unitary method and best buys

LEARNING INTENTION

At the end of this subtopic you should be able to:

- use the unitary method to determine the best value option
- apply the unitary method to find amounts from a partial amount.

5.4.1 Unit price

eles-3891

- The **unit price** is the price per unit. Examples include the price per 100 mL, the price per kg or the price of a single item.
- The **unitary method** can be used to work out the best buy for an item by comparing the unit price.
- Supermarkets in Australia are now obliged to show the unit price on most products.
- To determine the 'best buy' when comparing similar items:
  - decide what unit you will use in your comparison
  - divide the price of each item by its number of units
  - identify the item with the smallest unit price. This is the best value item.



Price per unit

$$\text{Price per unit} = \frac{\text{price}}{\text{number of units}}$$

Remember to represent the same units when you are making comparisons.

WORKED EXAMPLE 9 Determining the best buy using the unitary method

Three shampoos are sold in the following quantities.

Brand A: 200 mL for $5.38
Brand B: 300 mL for $5.98
Brand C: 400 mL for $8.04

Determine which shampoo is the best buy.



THINK	WRITE
1. Determine the number of 100-mL units for each shampoo.	Brand A $= \frac{200}{100} = 2$ units Brand B $= \frac{300}{100} = 3$ units Brand C $= \frac{400}{100} = 4$ units
2. Determine the price per unit for each shampoo. Price per unit $= \frac{\text{price}}{\text{100-mL units}}$	Brand A $= \frac{5.38}{2} = \$2.69$ per 100 mL Brand B $= \frac{5.98}{3} = \$1.99$ per 100 mL Brand C $= \frac{8.04}{4} = \$2.01$ per 100 mL
3. Write the answer.	Brand B: 300 mL of shampoo for $5.98 is the best buy.

5.4.2 Unitary method in percentages

eles-3892

- The unitary method can be used to determine the whole amount when given a partial amount and the percentage of the total that it corresponds to.

Determining the whole amount from a partial amount

- Step 1: Find 1% of the total amount.
- Step 2: Multiply the value of the 1% by 100 to get the whole amount (100).

WORKED EXAMPLE 10 Determining total price from a partial amount

Calculate the whole amount if 5% is represented by $25.

THINK	WRITE
1. Five per cent of a number equals 25. Calculate 1% of the $25 by dividing the number by 5.	$5\% = \$25$ $1\% = \$25 \div 5$ $= \$5$
2. Calculate 100% by multiplying the amount by 100.	$100\% = \$5 \times 100$ $= \$500$
3. Write the answer.	The whole amount is $ 500.

- The same method can also be applied when given a percentage that is greater than 100%.

WORKED EXAMPLE 11 Determining values from an increased amount

Marcie receives a pay rise of 12%, taking her salary to $72 000 a year. Calculate her annual salary before the pay rise, to the nearest dollar.



THINK	WRITE
1. A pay rise of 12% means that Marcie's new salary is 112% of her old salary.	$112\%\ \text{of previous salary} = \$72\,000$
2. Calculate what 1% of her previous salary was by dividing by 112.	$1\%\ \text{of previous salary} = \frac{\$72\,000}{112}$ $= \$642.8571$
3. Calculate 100% of her previous salary by multiplying by 100.	$100\%\ \text{of previous salary} = \$642.8571 \times 100$ $= \$64\,285.71$
4. Write the answer, rounding to the nearest dollar.	Marcie's previous salary was $64 286

ACTIVITY: Price comparison websites

Use the internet to research different price comparison websites. Investigate what goods and services price comparison websites display and present your research to your class.



on Resources

eWorkbook Topic 5 Workbook (worksheets, code puzzle and project) (ewbk-1906)

Interactivities Individual pathway interactivity: The unitary method and best buys (int-4396)
Unitary method (int-4154)
Unitary method in percentages (int-4155)

Exercise 5.4 The unitary method and best buys

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 8, 9, 11, 17, 21	2, 5, 6, 12, 13, 15, 18, 22	3, 7, 10, 14, 16, 19, 20, 23

To answer questions online and to receive **immediate feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE9 Determine which of the following is the best buy.

Chocolate weight	Cost
150 g	$3.25
250 g	$4.75
325 g	$5.50



2. Determine which of the following is the best buy.

No. of pages	Cost
80	$1.98
160	$3.38
200	$3.98

3. Compare the cost of 400 g of biscuits for $2.48 and 500 g for $3.10 to identify which is the better buy.
4. WE10 Calculate the original amount if:
   a. 10% is $18 b. 20% is $6 c. 25% is $60 d. 40% is $900
5. Calculate the original amount if:
   a. 90% is $380 b. 200% is $800 c. 120% is $420 d. 9% is $54.
6. Calculate:
   a. 60%, if 40% is $120 b. 38%, if 20% is $6 c. 50%, if 25% is $60
7. Calculate:
   a. 150%, if 50% is $900 b. 12%, if 75% is $250 c. 86%, if 14% is $4200.
8. Calculate how much you would pay for 4.5 kg of apples, given that 2 kg cost $3.80.

Understanding



9. You spend 40% of this month's allowance on a pair of used inline skates. Determine your monthly allowance if you spend $20 on the skates.
10. Hannah saves 32% of her wages each week. If she saves $220, calculate her weekly wage.
11. WE11 Alex receives a 15% pay rise. He now receives $97 290 a year. Calculate his annual income before the pay rise.

12. Compare the following to identify the best buy:
500 g of cheese for $12.80, 200 g of cheese for $5.62 or 80 g of cheese for $2.10.

13. After a discount of 15%, a pair of wireless headphones is worth $183. Calculate its value before the discount.



14. During a sale, a retailer allows a discount of 15% off the marked price. The sale price of $60 still gives the retailer a profit of 10%.

a. Calculate the cost of the article.
b. Calculate the marked price.

15. A discount of 15% reduced the price of a pen by $3.20.

a. Calculate the original price of the pen.
b. Calculate its reduced selling price.

16. Supermarkets are obliged by law to display the unit price when selling the same items in different quantities. Calculate the price per 100 g for the following amounts of chocolate. Give your answers correct to the nearest cent.

a. 250 g for $5.95 **b.** 400 g for $8.50 **c.** 60 g for $2.00

Reasoning

17. In some situations it is not always practical to go for the best buy. Suggest two reasons this might occur.

18. Explain some of the different situations in which you would use the unitary method.

19. While shopping in a sale, Carly spots a sign that says 'Buy 2 items, get the third half price (the least expensive item will be counted as the third item)'. If she finds a shirt for $25.99, a skirt for $87.99 and a belt for $15.97 and pays cash for the items, determine how much Carly will pay and justify your answer.

20. Penny loves to make bracelets. To make them, she needs to buy some beads. Brand A costs $7.50 for a box that contains 1000 beads; Brand B costs $17.50 for a box that contains 2500 beads. Determine which brand is the better buy.



Problem solving

21. Ice-cream sticks are sold in the following multi-packs. Compare the following to identify the best buy.

Cost ($)	Number of ice-cream sticks
$3.25	6
$4.99	10
$7.50	15

22. Some players from a soccer club went to a café to celebrate their win. Each had a burger and a drink. The bill came to $80. When it came time to pay the bill, 3 people had left without paying, so the remaining members had to pay an extra $2 each to cover the bill. If there were originally n people in the group, and the burger and drink deal cost $$b$, write an equation using these pronumerals to show how the bill was settled. Do not attempt to solve your equation.

23. The price of entry into a theme park has increased by 10% every year since the theme park opened. If the latest price rise increased the tickets to $8.80, determine the price of a ticket 2 years ago.

5.5 Review

5.5.1 Topic summary



RATIOS, RATES AND BEST BUYS

Ratios

- Ratios compare quantities in the same unit.
- 1 : 3 is read as 'the ratio of 1 to 3'.
- Ratios contain only integer values without units.
- They can be converted into fractions.

e.g. $2 : 5 \Rightarrow \frac{2}{7}$ and $\frac{5}{7}$

Equivalent ratios

- Ratios are equivalent if one can be converted into the other by multiplying or dividing by a factor.

e.g. $\frac{1}{5} \overset{\times 2}{=} \frac{2}{10}$ ($\times 2$)

- Ratios are generally written in simplest form.


Rates

- A rate compares two different types of quantities in different units.
  e.g. 12 km/h or 12 cm/day
- A rate is in simplified form if it is per one unit.

$\$100 : 4 \text{ hours} \xrightarrow{\div 4} \$100 : 1 \text{ hour} \xrightarrow{\div 4} \$25 : 1 \text{ hour}$

- A rate can be applied to find the total quantity of a measure being compared.

$$\text{Rate} = \frac{\text{first quantity}}{\text{second quantity}}$$



Unitary method

- The unitary method is used to calculate the whole amount when a partial percentage amount is known.
  - First find 1% of the total amount.
  - Multiply this value of 1% by 100 to get the whole amount.

Discount

- A discount is a reduction in price.

$$\text{Percentage discount} = \frac{\text{discount}}{\text{original selling price}} \times \frac{100\%}{1}$$

- The new sale price can be obtained either by subtracting the discount amount from the original price, or by calculating the remaining percentage.
  e.g. A 10% discount means there is 90% remaining of the original selling price.

Unit price

- The unit price is the price per single unit, such as kg, m or item.

$$\text{Price per unit} = \frac{\text{price}}{\text{number of units}}$$

- The 'best buy' is the option with the lowest cost per unit.

5.5.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand.)

Subtopic	Success criteria			
5.2	I can compare quantities using ratios.			
	I can simplify ratios.			
5.3	I can identify and express a rate from a written context.			
	I can simplify a rate and express the rate in its simplest form.			
	I can apply a rate to calculate the total value of an unknown quantity.			
5.4	I can use the unitary method to determine the best value option.			
	I can apply the unitary method to find amounts from a partial amount.			

5.5.3 Project

Successive discounts



Tony is a mechanic who has bought $250 worth of equipment at a tool store. Tony received 15% off the marked price of all items and received a further 5% trade discount. When two discounts are given on the same item or group of items, they are called successive discounts. In this case, Tony received successive discounts of 15% and 5%. Is this equal to a single discount of 20%?

Answer the following questions.

1. Calculate the amount that was due after Tony was given the first 15% discount.
2. From this amount, apply the trade discount of 5% to evaluate the amount that was due.
3. How much is the cash discount that Tony received?
4. Now calculate the amount that would have been due had Tony received a single discount of 20%. Is this the same answer?
5. Calculate the amount of cash discount that Tony received as a percentage of the original bill.
6. Explain whether the discount is the same if the 5% discount is applied before the 15% discount.

on Resources

eWorkbook Topic 5 Workbook (worksheets, code puzzle and project) (ewbk-1906)

Interactivities Crossword (int-8415)

Sudoku puzzle (int-8416)


Exercise 5.5 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. For the diagram shown, write the following ratios in simplest terms.



a. shaded parts: unshaded parts

b. shaded parts: total number of parts

2. Express in simplest form.

a. 8 : 10 **b.** 14 : 21 **c.** 16 : 64 **d.** 24 : 18

3. Express the following in simplest form.

a. $\frac{1}{2} : 4$ **b.** $\frac{3}{5} : \frac{1}{5}$ **c.** $1\frac{1}{2} : \frac{3}{4}$

d. 0.8 : 10 **e.** $10^2 : 10^3$ **f.** $\frac{3}{5} : \frac{3}{10}$

4. Rewrite each of the following ratios in simplest terms.

a. 4 m to 10 cm **b.** 3 oranges to 1 dozen (12) oranges

c. 8 months to 1 year **d.** 3 cm to 12 mm

e. 70 cents to $2.00

5. Rewrite each of the following ratios in simplest terms.

a. 3.5 kilograms to 500 grams

b. 1.2 cm to 10 mm

c. $\frac{1}{2}$ of a melon to 3 melons

d. 2 hours and 40 minutes to 30 minutes

e. $3\frac{1}{5}$ cm to $\frac{2}{5}$ m

6. Calculate the unit rate for each of the following.

a. If 35 copies can be made in 7 minutes, how many copies can be made in one minute?

b. If 9 crates can hold 216 bottles, how many bottles can one crate hold?

c. If James can drive 180 km in 3 hours and 20 minutes, how many kilometres can he drive in one hour?

d. If 6 movie tickets cost $50.40, how much does each movie ticket cost?

7. Calculate the given rates for each of the following.

a. The total cost of 1.5 kg of potatoes at $2.99/ kg

b. The distance travelled at 65 km/h for 3.75 hours

c. The time taken to travel 110 km at 80 km/h

8. When the AFL Grand Final was held in Queensland in 2020, 30 000 people attended. If there were 9872 women, 11 300 Richmond supporters, 8400 Geelong supporters and 2100 children in attendance, choose the best approximation of the ratio for each of the following.

a. MC The number of Geelong supporters to the number of Richmond supporters

A. 8400 : 1130 **B.** 113 : 84 **C.** 11 300 : 8400 **D.** 84 : 113

b. MC The number of children to the number of adults

A. 2100 : 30 000 **B.** 2100 : 9872 **C.** 7 : 93 **D.** 2100 : 19 700

c. MC The number of women to the total number of people in attendance

A. 1234 : 3750 **B.** 9872 : 3000 **C.** 9872 : 39 872 **D.** 617 : 1870

9. Look at the bunch of flowers and write the ratios of:

a. red flowers to yellow flowers

b. red flowers to non-red flowers

c. purple flowers to white flowers.



10. Find the values of the pronumeral in the following ratios.

a. $a : 7 = 3 : 14$ **b.** $12 : 4 = 9 : b$

Problem solving

11. Justin uses 375 grams of cream cheese to make a cheesecake that serves 12 people, using the recipe shown.

Ingredients

250 g sweet plain biscuits
125 g unsalted butter
375 g cream cheese, softened
1 lemon, zested
2 tsp vanilla essence

a. Write the ratio of cream cheese to butter.

b. Calculate how many grams of cream cheese Justin needs to make a cheesecake that serves 8 people.



12. If it takes 15 people 12 days to complete a job, explain how long it would take 20 people to complete the same job.

13. After a 10% discount, a PlayStation costs $320. Calculate the original cost of the PlayStation.

14. Identify which is the better value — 400 g of biscuits costing $2.98, or a pack of biscuits with 400 g + 25% extra, costing $3.28.

15. The rate of ascent for the Discovery space shuttle was 114 000 m in 8.0 minutes.

a. Write this speed in km/min.

b. Write this speed in km/h.

16. Mitch is a very fast runner who can run 3 km in 9 minutes. If Mitch is able to maintain this rate, calculate how long it will take him to run 9 km.



17. The dimensions (length and width) of rectangle B are double those of rectangle A. Explain whether the area of rectangle B is double of the area of rectangle A.



18. A rectangle has dimensions (length and width) that are in the ratio 3 : 5. Complete the following table to find the dimensions of the rectangle if it has an area of 135 cm^2. The first row has been done for you.

Length (cm)	Width (cm)	Area (cm^2)
3	**5**	**15**

19. Tammy walks to school at an average rate (speed) of 6 km/h.

a. It takes her 30 minutes to walk to school. Calculate the distance from her house to the school.

b. If the total time she spends walking to school and back home is 70 minutes, calculate the rate at which she is walking on her way home.

20. At a Year 7 social, the ratio of females to males was 3 : 2. Four additional females arrived and 4 males left, and the ratio was then 2 : 1. Determine the number of people at the social.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1906) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0694) ☐

Digital documents

5.3 SkillSHEET Converting a mixed number into an improper fraction (doc-6471) ☐
SkillSHEET Multiplying decimals by 10, 100 and 1000 (doc-6466) ☐
SkillSHEET Multiplying a whole number by a fraction (doc-6894) ☐
SkillSHEET Converting minutes to a fraction of an hour (doc-6895) ☐

Video eLesson

5.2 Introduction to ratios (eles-3886) ☐
Simplifying ratios (eles-3887) ☐
5.3 Identifying rates (eles-3888) ☐
Simplifying rates (eles-3889) ☐
Applications of rates (eles-3890) ☐
5.4 Unit price (eles-3891) ☐
Unitary method in percentages (eles-3892) ☐

Interactivities

5.2 Individual pathway interactivity: Introduction to ratios (int-4412) ☐
Introduction to ratios (int-3956) ☐
Simplification of ratios (int-3949) ☐
5.3 Individual pathway interactivity: Rates (int-4417) ☐
Rates (int-3738) ☐
5.4 Individual pathway interactivity: The unitary method and best buys (int-4396) ☐
Unitary method (int-4154) ☐
Unitary method in percentages (int-4155) ☐
5.5 Crossword (int-8415) ☐
Sudoku puzzle (int-8416) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers


Topic 5 Ratios, rates and best buys


Exercise 5.1 Pre-test

1. 1 : 2
2. a. 7 : 3 b. 7 : 10
3. a. $\frac{5}{7}$ b. $\frac{1}{4}$ c. $\frac{1}{5}$ d. $\frac{4}{1}$
4. B
5. 20 students
6. A, B, E
7. D
8. 2 hours 25 minutes
9. The 250 g jar is cheaper by 30 cents per 100 g.
10. 2 : 3
11. a. 58 words/minute, b. 2.75 kL/h
12. True
13. a. 28 : 63 b. 9 : 28
    c. 63 : 100 d. $\frac{63}{100}$
14. $2.50
15. $1\frac{7}{8}$ hours *or* 1 hour 52 minutes 30 seconds

Exercise 5.2 Ratios

1. a. 2 : 5 b. 1 : 3 c. 2 : 1 d. 5 : 2
2. a. 7 : 5 b. 7 : 12
3. The order is very important in ratios. By changing the order of a ratio, the meaning changes. For example, if the ratio of losses to wins is 2 : 3, the 2 corresponds to the losses and the 3 corresponds to the wins. If we change the order of the ratio to 3 : 2 then the 3 corresponds to the losses and the 2 corresponds to the wins, which is not correct.
4. a. $\frac{5}{7}$ b. $\frac{7}{50}$ c. $\frac{3}{4}$ d. $\frac{10}{3}$
5. a. 5 : 4 b. 77 : 12 c. 6 : 1 d. 8 : 7
6. a. 7 : 9 b. 1 : 1 c. 3 : 25 d. 5 : 8
7. a. 5 : 1 b. 3 : 40 c. 90 : 1 d. 3 : 2
8. a.


b.


c.


d.


9. a. 1 : 4
   2 : 8
   3 : 12
   4 : 16
   5 : 20
   b. 2 : 3
   4 : 6
   8 : 12
   10 : 15
   14 : 21
   c. 64 : 32
   32 : 16
   16 : 8
   8 : 4
   2 : 1
   d. 48 : 64
   24 : 32
   12 : 16
   6 : 8
   3 : 4
10. The width of the flag is 90 cm.
11. a. 27 : 20 b. 3 : 5 c. 20 : 3 d. 5 : 2
12. a. 1 : 3 = 4 : 12 b. 2 : 3 = 4 : 6
    c. 66 : 48 = 11 : 8 d. 36 : 72 = 12 : 24
13. a. 20 : 12 = 5 : 3 b. 2 : 6 = 8 : 24
    c. 8 : 6 = 96 : 72 d. 40 : 46 = 5 : 6
14. a. 1 : 11 b. 1 : 45 c. 3 : 2 d. 11 : 900
15. The cost of the cheaper ticket is $320.
16. a. 77 : 23 b. 23 : 100
17. a. 37 600 female b. 47 : 31 c. $\frac{47}{31}$
18. Fourteen coins need to be added to the purse. Three silver coins and 11 gold coins will change the ratio of gold to silver.
19. a. 5 : 42 b. 3 : 5 c. 21 : 25 d. $\frac{1}{10}$
20. a. 2.6 m b. Bounce 6

Exercise 5.3 Rates

1. a. 7 litres per minute
   b. 4.71 runs per ball
   c. 6 dollars per bunch
   d. 20 dollars per hour
   e. $\frac{100}{3}$ metres per minute
2. a. 30 km/h
   b. $25.00 per hour
   c. $1.50 per metre
3. a. 5 m/s b. $3.60 per m^2
   c. $3.50 per kg d. $37.50 per m^2
4. 36 km
5. $17.00 per hour
6. 3 hours
7. $1.50 per kg
8. 70 km/h
9. 1 hour and 36 minutes
10. $7.50
11. 2 hours
12. 13.5 minutes or 13 minutes and 30 seconds

13. a. 4 minutes b. 8 minutes
c. 2 minutes d. 3 minutes
14. a. 17 hours b. 5 shifts c. $45.00
15. a. $190.00 b. $570.00 c. $405.00

Exercise 5.4 The unitary method and best buys

1. The 325-g option is the best buy.
2. The 200-page option is the best buy.
3. Neither is better (they are both 62 cents per 100 g).
4. a. $180 b. $30 c. $240 d. $2250
5. a. $422.22 b. $400 c. $350 d. $600
6. a. $180 b. $11.40 c. $120
7. a. $2700 b. $40 c. $25 800
8. $8.55
9. $50
10. $687.50
11. $84 600
12. 500 g of cheese is the best buy.
13. $215.29
14. a. $54.55 b. $70.59
15. a. $21.33 b. $18.13
16. a. $2.38 b. $2.13 c. $3.33
17. The amount required should always be considered, as the best buy will often be for the largest quantity. Waste due to spoilage and the best before date of the item should also be taken into account. The size of the item and storage space may also need to be considered. The total cost should also be considered, particularly if shopping on a budget.
18. There are various situations in which it would be used. Generally they involve comparing different types of a certain item.
19. Brand B. The cost for each bead for Brand B is cheaper (7c compared to 7.5c).
a. $21.33 b. $18.13
20. $121.97
21. Options are 50 c per ice-cream stick, 49.9 c per ice-cream stick and 54.17 c per ice-cream stick. Therefore the $4.99 pack is the best buy.
22. $(n - 3)(b + 2) = 80$
23. $7.27

Project

1. $212.50
2. $201.88
3. $48.13
4. No
5. 19.25%
6. Yes

Exercise 5.5 Review questions

1. a. 2 : 2 = 1 : 1 b. 2 : 4 = 1 : 2
2. a. 4 : 5 b. 2 : 3 c. 1 : 4 d. 4 : 3
3. a. 1 : 8 b. 3 : 1 c. 2 : 1
d. 2 : 25 e. 1 : 10 f. 2 : 1
4. a. 40 : 1 b. 1 : 4 c. 2 : 3
d. 5 : 2 e. 7 : 20
5. a. 7 : 1 b. 6 : 5 c. 1 : 6
d. 16 : 3 e. 2 : 25
6. a. 5 copies b. 24 bottles
c. 54 km d. $8.40
7. a. $4.485 \approx $4.49 b. 243.75 km
c. 1.375 hours
8. a. D b. C c. A
9. a. 5 : 3 b. 5 : 7 c. 3 : 1
10. a. $\frac{3}{2}$ b. 3
11. a. 3 : 1 b. 250 g
12. 9 days
13. The original cost of the PlayStation was $355.55.
14. 400 g + 25% extra
15. a. 14.25 km/minutes b. 855 km/h
16. It will take Mitch 27 minutes to run 9 km.
17. No, the area of rectangle *B* will not be double. It will be four times greater.
18.

Length (cm)	Width (cm)	Area (cm^2)
3	**5**	**15**
6	10	60
9	15	135

19. a. The school is 3 km away from her house.
b. The rate is 4.5 km/h.
20. The total number of people at the social is 60.

6 Decimals



LEARNING SEQUENCE

6.1 Overview 292
6.2 Decimals and place value 294
6.3 Converting decimals to fractions and fractions to decimals 302
6.4 Rounding and repeating decimals (extending) 307
6.5 Adding and subtracting decimals 313
6.6 Multiplying decimals 319
6.7 Dividing decimals 325
6.8 Decimals and percentages 332
6.9 Review 335

6.1 Overview

Why learn this?



You have already seen that whole numbers cannot be used to measure everything. How much did you pay for that burger and chips? $12.60? Our money system is in dollars and cents and uses decimals to represent parts of the dollar. Decimals play an important part in our daily lives. You could have been using decimals without realising how important they are. Since our lives are so dependent on money, knowing how to work with decimals is very important. We all need to be skilled in the basic operations of addition, subtraction, multiplication and division with decimals.

Decimals are used not only with money but also with time and measurement. They are also used as another way of expressing a fraction or percentage of something. Did you know that Cathy Freeman won the gold medal in the 400-metre event at the 2000 Sydney Olympics in a time of 49.11 seconds, a winning margin of just 0.02 seconds? Usain Bolt set the men's 100-metre world record in 2009 with a time of just 9.58 seconds. Every person will use decimals in some aspect of their lives, including when checking their pay or their bank balance. Understanding and using decimals is vital in retail, hospitality, design, commerce, construction, the health industry and all areas of business.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 6.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Select which of the following is the largest number.
   A. 3.098 B. 3.089 C. 3.100 D. 2.999 E. 3.079

2. The cost of the new PlayStation has increased by 12% compared to the previous model. Write the percentage increase as a decimal.

3. MC The decimal 0.56 in simplest fractional form is:
   A. $\frac{56}{100}$ B. $\frac{12}{25}$ C. $\frac{28}{50}$ D. $\frac{15}{24}$ E. $\frac{14}{25}$

4. Josh swam his race in 22.370 seconds and Ren swam his in $22\frac{3}{8}$ seconds. State who was the fastest.

5. Write the number 23.8951 rounded to 2 decimal places.

6. Walter wants to withdraw all the money from his bank account. He has a total of $378.93, but can only withdraw an amount to the nearest 5 cents. State how much he can withdraw.

7. MC The third largest number from the following choices is:
   A. 0.276 B. $0.27\dot{6}$ C. $0.2\dot{6}\dot{9}$ D. $0.2\dot{6}\dot{7}\dot{9}$ E. $0.27\dot{5}$

8. Calculate:

$$\begin{array}{rr} & 2.375 \\ + & 3.442 \\ \hline & \end{array}$$

9. MC Michael works at McDonald's. If a customer had an order of $23.75 and he handed over a $50 note, calculate the change Michael gave to the customer.
   A. $25.25 B. $26.75 C. $26.25 D. $23.75 E. $36.25

10. Calculate 8.2×400.

11. MC Callum coaches tennis on Sundays and he gets 1.5 times his usual hourly pay of $18.70. His Sunday hourly rate is:
   A. $37.40 B. $28.05 C. $25.70 D. $27.70 E. $27.05

12. Kat bought 2.6 kg of sausages for her BBQ at a cost of $5.25 per kg. Calculate how much Kat paid for her sausages.

13. Calculate $34.792 \div 0.4$.

14. If Mei filled her car with petrol and it cost $53.68 at $1.22 per litre, calculate how many litres of petrol she put in her car.

15. Leah pours drinks for a group of people at a volume of 0.32 litres each. If she has 40 litres of the beverage to use, calculate how many drinks she can pour.

6.2 Decimals and place value

LEARNING INTENTION

At the end of this subtopic you should be able to:

- understand the place values used in decimal numbers
- determine the value of digits in decimal numbers
- compare the sizes of decimal numbers.

6.2.1 Whole numbers and decimal parts

eles-3940

- Each position in a number has its own place value.


Hundred thousands	Ten thousands	Thousands	Hundreds	Tens	Units
100 000	10 000	1000	100	10	1

- Each place to the left of another position has a value that is 10 times larger.
- Each place to the right of another position has a value that is $\frac{1}{10}$ of the previous position.
- The position of a digit in a number gives the value of the digit.
- The table shows the value of the digit 3 in some numbers.



Number	Value of 3 in number
132	3 tens or 30
3217	3 thousands or 3000
4103	3 units (ones) or 3

- In a decimal number, the whole number part and the fractional part are separated by a **decimal point.**



- A place value table can be extended to include decimal place values. It can be continued to an infinite number of **decimal places**.

Thousands	Hundreds	Tens	Units	.	Tenths	Hundredths	Thousandths	Ten thousandths
1000	100	10	1	.	$\frac{1}{10}$	$\frac{1}{100}$	$\frac{1}{1000}$	$\frac{1}{10\,000}$

- The table shows the value of the digit 3 in some decimal numbers.

Number	Value of 3 in the number
14.32	The 3 is 3 tenths or $\frac{3}{10}$.
106.013	The 3 is 3 thousandths or $\frac{3}{1000}$.
0.000 03	The 3 is 3 hundred thousandths or $\frac{3}{100\,000}$.

- The number of decimal places in a decimal is the number of digits after the decimal point. The number 73.064 has 3 decimal places.
- The zero (0) in 73.064 means that there are no tenths. The zero must be written to hold the place value; otherwise the number would be written as 73.64, which does not have the same value.

DISCUSSION

How do you know how many zeros the denominator should have when calculating the value of a digit to the right of the decimal point?

WORKED EXAMPLE 1 Stating the place value

State the value of the 7 in each of the following.

a. **10.74** **b.** **0.173** **c.** **321.037**

THINK	WRITE
a. The value of the first place to the right of the decimal point is tenths, so the value of the 7 is seven tenths.	**a.** $\frac{7}{10}$
b. The second place after the decimal point is hundredths, so the value of the 7 is seven hundredths.	**b.** $\frac{7}{100}$
c. The third place after the decimal point is thousandths, so the value of the 7 is seven thousandths.	**c.** $\frac{7}{1000}$

WORKED EXAMPLE 2 Expressing place values in words

For the number 76.204, write the value of each digit in words and numbers.

THINK	WRITE
1. 7 is in the tens position.	Seventy, 70
2. 6 is in the units position.	Six, 6
3. 2 is in the first position after the decimal point, so it is tenths.	Two tenths, $\frac{2}{10}$
4. 0 is in the hundredths position.	Zero hundredths, $\frac{0}{100}$
5. 4 is in the thousandths position.	Four thousandths, $\frac{4}{1000}$

Expanded notation

A number can be written in expanded notation by adding the values of each digit.

The number 76.204 can be written in expanded notation as:

$$(7 \times 10) + (6 \times 1) + \left(2 \times \frac{1}{10}\right) + \left(4 \times \frac{1}{1000}\right)$$

WORKED EXAMPLE 3 Writing in expanded notation

Write 3.4501 in expanded notation.

THINK	WRITE
1. Write the decimal.	3.4501
2. Determine the place value of each digit. 3 : 3 units 4 : 4 tenths 5 : 5 hundredths 0 : 0 thousandths 1 : 1 ten thousandth	= 3 units + 4 tenths + 5 hundredths +0 thousandths + 1 ten thousandth
3. Write the number in expanded notation.	$= (3 \times 1) + \left(4 \times \frac{1}{10}\right) + \left(5 \times \frac{1}{100}\right) + \left(1 \times \frac{1}{10\,000}\right)$

6.2.2 Comparing decimals

eles-3941

- Decimals are compared using digits with the same place value.

Comparing decimals

- The decimal with the largest number in the highest place-value column is the largest decimal, *regardless of the number of decimal places.*
  For example, 15.71 is larger than 15.702 because the first place value with different digits (moving from left to right) is hundredths, and 1 is greater than 0; that is, 15.71 > 15.702.

Tens	Units (ones)	.	Tenths	Hundredths	Thousandths
1	5	.	7	1	
1	5	.	7	0	2




WORKED EXAMPLE 4 Determining the largest number with a decimal

State the largest number in each of the following.

a. **0.126, 0.216, 0.122** **b.** **2.384, 2.388, 2.138** **c.** **0.506, 0.605, 0.612**

THINK	WRITE
a. 1. As the units digit is 0 in each number, compare the tenths. The number 0.216 has 2 tenths, the others have 1 tenth so 0.216 is the largest number.	**a.** 0.216 is larger than 0.126 and 0.122.
2. Answer the question.	The largest number is 0.216.
b. 1. As the units digits are the same, compare the tenths. 2.138 has 1 tenth, the others have 3 tenths, so 2.138 is the smallest.	**b.** 2.384 and 2.388 are both larger than 2.138.
2. The hundredths are the same, so compare the thousandths. 2.388 has 8 thousandths, 2.384 has 4 thousandths, so 2.388 is the largest.	2.388 is larger than 2.384 and 2.138.
3. Answer the question.	The largest number is 2.388.
c. 1. As the units digits are the same, compare the tenths. 0.506 has 5 tenths, the others have 6 tenths, so 0.506 is the smallest.	**c.** 0.605 and 0.612 are larger than 0.506.
2. Compare the hundredths. 0.612 has 1 hundredth, 0.605 has 0 hundredths, so 0.612 is the largest.	0.612 is larger than 0.605 and 0.506.
3. Answer the question.	The largest number is 0.612.

- Decimals can also be compared using the *area model*. For example, we could use the area model to determine whether 0.67 or 0.7 is larger. From the following area model, it can be seen that 0.7 covers a greater area than 0.67 and is therefore larger.
- When comparing two numbers, it is easier to use symbols instead of words, as shown in topic 4 on fractions.
- In Worked example 4a, the result '0.216 is larger than 0.126' could be written as $0.216 > 0.126$. We could also say that 0.126 is less than 0.216, or write it as $0.126 < 0.216$.



WORKED EXAMPLE 5 Comparing numbers with decimals

Insert the appropriate < or > sign between the following pairs of numbers to make true statements.

a. **0.312 0.318** **b.** **0.0246 0.0168**

THINK	WRITE
a. Compare the numbers. Both numbers have the same number of tenths and the same number of hundredths, so compare thousandths and insert the correct sign.	**a.** $0.312 < 0.318$
b. Compare the numbers. Both numbers have no tenths, so compare hundredths and insert the correct sign.	**b.** $0.0246 > 0.0168$

DISCUSSION

You may read statements in the media quoting decimals that are not achievable every day. Some examples are 'The average number of tries scored by the Roosters is 3.6' or 'The number of children in the average family is 2.3'. Do you think these statements are reasonable?

COLLABORATIVE TASK: Some points about decimals

In English-speaking countries, the decimal point is a full stop and spaces are left between groups of three digits: for example, 12 345.67. In many other countries, a comma is used as a decimal point and full stops are used to separate groups of three digits; for example, 12.345, 67.



In groups discuss the following:

- What are some of the problems associated with these different methods of writing decimal numbers?
- What could be done to fix these problems?
- Which method of displaying decimals do you think we should use and why?

Use the internet to investigate how the number 12 345.67 would be written in each of the following countries.

a. China **b.** India **c.** Japan
d. United States of America **e.** United Kingdom **f.** France
g. Turkey **h.** Saudi Arabia

on Resources

eWorkbook Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)

Digital documents SkillSHEET Writing decimals (doc-6458)
SkillSHEET Comparing decimals (doc-6459)

Interactivities Individual pathway interactivity: Place value and comparing decimals (int-4337)
Whole numbers (int-3974)
Decimal parts (int-3975)
Comparing decimals (int-3976)
Comparing decimals using the area model (int-3977)

Exercise 6.2 Decimals and place value

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13, 16, 19, 21, 24, 27	2, 5, 8, 11, 14, 17, 20, 23, 25, 28	3, 6, 9, 12, 15, 18, 22, 26, 29, 30

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 State the value of the 2 in each of the following.
   a. 5.2 b. 19.12 c. 100.29 d. 0.982 047
2. State the value of the 2 in each of the following.
   a. 6.1342 b. 90.0002 c. 12.14 d. 1.8902
3. State the value of the 9 in each of the following.
   a. 0.9 b. 14.98 c. 18.89 d. 12.090
4. State the value of the 9 in each of the following.
   a. 3.4629 b. 1.276 89 c. 900.76 d. 9.612
5. For each of the following numbers write the value of each digit in *numbers*.
   a. 0.4 b. 2.7 c. 5.23 d. 0.763
6. For each of the following numbers write the value of each digit in *numbers*.
   a. 0.1101 b. 7.2964 c. 0.330 24 d. 300.03
7. WE2 For the following numbers write the value of each digit in *words* and *numbers*.
   a. 1.85 b. 0.271 c. 16.001 d. 3.402 07
8. WE3 Write the following numbers in expanded notation.
   a. 1.25 b. 56.01 c. 39.01 d. 5.987
9. Write the following numbers in expanded notation.
   a. 13.482 b. 0.3062 c. 0.5002 d. 2.47
10. MC Five hundredths, 2 thousandths and 7 ten thousandths equals:
    A. 527 B. 52.7 C. 5.27 D. 0.0527 E. 0.527
11. Copy and complete the table by putting only one digit in each box.

		Tens	Units		Tenths	Hundredths	Thousandths
Example	37.684	3	7	.	6	8	4
a	0.205			.			
b	1.06			.			
c	74.108			.			
d	0.108			.			
e	50.080			.			

12. WE4 State the largest number in each of the following.
    a. 0.24, 0.32, 0.12 b. 0.57, 0.51, 0.59 c. 0.192, 0.191, 0.901

13. State the largest number in each of the following.

a. 0.0392, 0.039 90, 0.0039 **b.** 2.506, 2.305, 2.559 **c.** 0.110 43, 0.110 49, 0.110 40

14. WE5 Insert the appropriate < or > sign between each of the following pairs of numbers to make true statements.

a. 3.2 2.9 **b.** 8.6 8.9 **c.** 0.64 0.67

d. 0.29 0.39 **e.** 13.103 13.112

15. Insert the appropriate < or > sign between each of the following pairs of numbers to make true statements.

a. 0.427 0.424 **b.** 0.580 0.508 **c.** 0.0101 0.0120

d. 0.048 01 0.4801 **e.** 1.3830 1.3824

Understanding

16. **a.** State how many decimal places we use in our currency.

b. Write the amount of money shown in the photograph:

i. in words **ii.** in numbers.



17. Write the following in order from smallest to largest (ascending order).

a. 0.21, 0.39, 0.17, 0.45, 0.33

b. 0.314, 0.413, 0.420, 0.391, 0.502

c. 0.821, 0.803, 0.811, 0.807, 0.902

18. Write the following in order from smallest to largest (ascending order).

a. 0.9864, 0.9812, 0.9943, 0.9087, 0.9189

b. 4.6249, 4.5097, 4.802, 4.6031, 4.0292

c. 0.004 65, 0.005 02, 0.003, 0.0056, 0.009

19. Write the following in order from largest to smallest (descending order).

a. 0.36, 0.31, 0.39, 0.48, 0.19

b. 0.91, 0.97, 0.90, 0.95, 0.99

c. 1.264, 1.279, 1.273, 1.291, 1.288

20. Write the following in order from largest to smallest (descending order).

a. 0.372, 0.318, 0.390, 0.309, 0.317

b. 0.8207, 0.8889, 0.8823, 0.8217, 0.8448

c. 1.349 54, 1.486 59, 1.702 96, 1.843 21, 1.486 13

21. MC The largest number in the list 0.4261, 0.4265, 0.4273, 0.4199, 0.3999 is:

A. 0.4261 **B.** 0.4199 **C.** 0.4265 **D.** 0.3999 **E.** 0.4273

22. MC The smallest number in the list 0.4261, 0.4265, 0.4273, 0.4199, 0.3999 is:

A. 0.4261 **B.** 0.4199 **C.** 0.4265 **D.** 0.3999 **E.** 0.4273

23. MC The list 0.4261, 0.4265, 0.4273, 0.4199, 0.3999 when arranged from smallest to largest is:

A. 0.4273, 0.4265, 0.4261, 0.4199, 0.3999

B. 0.4273, 0.4261, 0.4265, 0.4199, 0.3999

C. 0.3999, 0.4199, 0.4265, 0.4261, 0.4273

D. 0.3999, 0.4199, 0.4261, 0.4273, 0.4265

E. 0.3999, 0.4199, 0.4261, 0.4265, 0.4273

Reasoning

24. Write True (T) or False (F) for each of the following and justify your response.

- **a.** 76.34 has 4 decimal places.
- **b.** $\frac{6}{10} + \frac{3}{100} + \frac{4}{10\,000}$ is the same as 0.6304.
- **c.** 4.03 has the same value as 4.3.

25. Write True or False for each of the following and justify your response.

- **a.** 29.60 has the same value as 29.6.
- **b.** 1.2804 could be written as $1 + \frac{2}{10} + \frac{8}{100} + \frac{4}{1000}$.
- **c.** 1090.264 51 has 5 decimal places.

26. **a.** Calculate the decimal values of the following fractions.

$$\frac{1}{7}, \frac{2}{7}, \frac{3}{7}, \frac{4}{7}, \frac{5}{7}, \frac{6}{7}$$

Write as many decimals as possible.

- **b.** Is there a pattern? Explain.

Problem solving

27. For each of the numbers listed from **a** to **e**:

- **i.** state the place value of the zero
- **ii.** state whether the value of the number would change if the zero wasn't there. (Write yes or no.)

a. 6.02 **b.** 7.360 **c.** 0.65 **d.** 20 **e.** 108.62

28. Year 7 students competing in their school swimming sports recorded the following times in the 50-metre freestyle, backstroke and breaststroke events.

	Time (seconds) recorded by contestants						
Event	**Carolyn**	**Jessica**	**Mara**	**Jenika**	**Robyn**	**Shelley**	**Kyah**
Freestyle	37.23	39.04	40.90	38.91	37.45	37.02	37.89
Backstroke	40.23	43.87	44.08	42.65	41.98	40.29	41.05
Breaststroke	41.63	42.70	41.10	41.21	42.66	41.33	41.49



- **a.** State who won the freestyle event and calculate how much they won by.
- **b.** State who won the backstroke event and calculate how much they won by.
- **c.** State who won the breaststroke event and calculate how much they won by.
- **d.** List the first 3 placings of the freestyle event.
- **e.** List the first 3 placings of the backstroke event.
- **f.** List the first 3 placings of the breaststroke event.
- **g.** Determine whether any students obtained a placing in all three events.

29. Determine my number.
My number contains four different even digits and has 3 decimal places. The digit in the thousandths position is half the value of the digit in the units position. The sum of the digits in the units and tenths positions is the same as the sum of the digits in the hundredths and thousandths positions.
The digit in the thousandths position is bigger than the digit in the tenths position.

30. Your friend said, 'You don't have to worry about the zeros in decimals; you can just leave them out.' Explain why your friend is correct or incorrect.

6.3 Converting decimals to fractions and fractions to decimals

LEARNING INTENTION

At the end of this subtopic you should be able to:
- convert decimals to fractions and fractions to decimals.

6.3.1 Converting decimals to fractions

eles-3943

- Decimals can be written as fractions by using place values.

Number	Ones	·	Tenths	Hundredths
0.3	0	·	3	0
1.25	1	·	2	5

- The decimal 0.3 can be written as $\frac{3}{10}$.
- The decimal 1.25 can be thought of as $1 + \frac{2}{10} + \frac{5}{100} = 1 + \frac{20}{100} + \frac{5}{100} = 1\frac{25}{100}$.

Converting decimals to fractions

- The digits after the decimal point become the numerator, and the place value of the last digit gives the denominator.
- Simplify fractions by dividing the denominator and numerator by a common factor, e.g. $1\frac{25}{100} = 1\frac{1}{4}$.

WORKED EXAMPLE 6 Converting decimals to fractions

Write the following decimals as fractions, then simplify where appropriate.
a. **0.2** **b.** **0.86** **c.** **0.6021**

THINK	WRITE
a. 1. Write the decimal.	**a.** 0.2
2. The numerator is 2 and the last decimal place is tenths so the denominator is 10.	$= \frac{2}{10}$
3. Simplify the fraction and write the answer.	$= \frac{1}{5}$
b. 1. Write the decimal.	**b.** 0.86
2. The numerator is 86. The last decimal place is hundredths so the denominator is 100.	$= \frac{86}{100}$
3. Simplify the fraction and write the answer.	$= \frac{43}{50}$
c. 1. Write the decimal.	**c.** 0.6021
2. The numerator is 6021. The last place is tens of thousandths so the denominator is 10 000.	$= \frac{6021}{10\,000}$

WORKED EXAMPLE 7 Converting mixed numbers to fractions

Write each of the following as a mixed number in its simplest form.

a. **3.041** **b.** **7.264**

THINK	WRITE
a. 1. Write the decimal.	**a.** 3.041
2. Write the whole number part and change the decimal part to a fraction. The numerator is 41. The last decimal place is thousandths so the denominator is 1000.	$= 3\frac{41}{1000}$
b. 1. Write the decimal.	**b.** 7.264
2. Write the whole number part and change the decimal part to a fraction. The numerator is 264 and the denominator is 1000.	$= 7\frac{264}{1000}$
3. Simplify the fraction.	$= 7\frac{264 \div 8}{1000 \div 8}$
4. Write the answer in simplest form.	$= 7\frac{33}{125}$

eles-3944

6.3.2 Converting fractions to decimals

- Fractions can be written as decimals by dividing the numerator by the denominator.
  For example, to convert $\frac{1}{4}$ into a decimal, divide 1 by 4 : $4\overline{)1.00}$ 0.25
- Add trailing zeros to the numerator where required.

WORKED EXAMPLE 8 Converting fractions to decimals

Change the following fractions into decimals.

a. $\frac{2}{5}$ **b.** $\frac{1}{8}$

THINK	WRITE
a. 1. Set out the question as for division of whole numbers, adding a decimal point and the required number of zeros.	**a.** $5\overline{)2.0}$
2. Divide, writing the answer with the decimal points aligned.	$5\overline{)2.0}$ 0.4
3. Write the answer.	$\frac{2}{5} = 0.4$
b. 1. Set out the question as for division of whole numbers, adding a decimal point and the required number of zeros. *Note:* $\frac{1}{8} = 1 \div 8$.	**b.** $8\overline{)1.000}$ 0.125
2. Divide, writing the answer with the decimal point exactly in line with the decimal point in the question, and write the answer.	$\frac{1}{8} = 0.125$

- By knowing the decimal equivalent of any fraction, it is possible to determine the equivalent of any multiple of that fraction. The following worked example illustrates this.

WORKED EXAMPLE 9 Converting multiples of a known fraction to decimals

Use the results of Worked example 8 to determine decimal equivalents for:

a. $\frac{3}{8}$ **b.** $4\frac{5}{8}$

THINK	WRITE
a. 1. Write the decimal equivalent for the fraction with 1 as the numerator.	**a.** $\frac{1}{8} = 0.125$
2. Multiply both sides of this equation by the appropriate multiple (3 in this case).	$\frac{1}{8} \times 3 = 0.125 \times 3$
3. Write the answer.	$\frac{3}{8} = 0.375$
b. 1. Consider only the fraction part of the mixed number. Write the decimal equivalent of this fraction with 1 as the numerator.	**b.** $\frac{1}{8} = 0.125$
2. Multiply both sides of this equation by the appropriate multiple (5 in this case).	$\frac{1}{8} \times 5 = 0.125 \times 5$
3. Simplify both sides.	$\frac{5}{8} = 0.625$
4. Combine with the whole number and write the answer.	$4\frac{5}{8} = 4.625$

on Resources

eWorkbook Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)

Interactivities Individual pathway interactivity: Converting decimals to fractions and fractions to decimals (int-4338)
Conversion of decimals to fractions (int-3978)
Conversion of fractions to decimals (int-3979)

Exercise 6.3 Converting decimals to fractions and fractions to decimals

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 12, 15, 18	2, 5, 8, 11, 13, 16, 19	3, 6, 9, 14, 17, 20

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE6 Write the following decimals as fractions, then simplify where appropriate.
   a. 0.3 b. 0.5 c. 0.21 d. 0.4 e. 0.44
2. Write the following decimals as fractions, then simplify where appropriate.
   a. 0.49 b. 0.502 c. 0.617 d. 0.30 e. 0.64
3. Write the following decimals as fractions, then simplify where appropriate.
   a. 0.28 b. 0.9456 c. 0.9209 d. 0.4621 e. 0.120
4. WE7 Write the following decimals as mixed numbers in simplest form.
   a. 1.3 b. 2.7 c. 9.4 d. 1.2 e. 4.2
5. Write the following decimals as mixed numbers in simplest form.
   a. 8.5 b. 5.27 c. 19.182 d. 3.15 e. 6.25
6. Write the following decimals as mixed numbers in simplest form.
   a. 9.140 b. 16.682 c. 2.4917 d. 4.3386 e. 100.0048

Understanding

7. MC 0.13 as a fraction is:
   A. $\frac{13}{10}$ B. $\frac{13}{100}$ C. $\frac{13}{1000}$ D. $\frac{1.3}{100}$ E. $1\frac{3}{10}$
8. MC 0.207 as a fraction is:
   A. $\frac{207}{1000}$ B. $\frac{207}{100}$ C. $2\frac{7}{10}$ D. $20\frac{7}{10}$ E. 207
9. MC 0.52 as a fraction in simplest form is:
   A. $\frac{52}{100}$ B. $\frac{26}{50}$ C. $\frac{13}{25}$ D. $\frac{26}{100}$ E. $\frac{13}{50}$
10. MC 0.716 as a fraction in simplest form is:
    A. $\frac{716}{10\,000}$ B. $\frac{368}{560}$ C. $\frac{716}{1000}$ D. $\frac{179}{250}$ E. $\frac{358}{1000}$
11. MC 5.325 as a fraction in simplest form is:
    A. $\frac{5325}{1000}$ B. $\frac{325}{1000}$ C. $5\frac{325}{1000}$ D. $5\frac{65}{200}$ E. $5\frac{13}{40}$
12. WE8 Change the following fractions to decimals.
    a. $\frac{3}{4}$ b. $\frac{1}{2}$ c. $\frac{4}{5}$ d. $\frac{1}{20}$
13. Change the following fractions to decimals.
    a. $\frac{3}{12}$ b. $\frac{1}{50}$ c. $\frac{8}{25}$ d. $\frac{3}{15}$

14. Write $\frac{1}{8}$ as a decimal. Using this value, write:

a. $\frac{3}{8}$ as a decimal **b.** $\frac{7}{8}$ as a decimal **c.** $\frac{1}{16}$ as a decimal.

Reasoning

15. The twin sisters in the photograph are keen tennis players. One of the twins has won 37 of her last 51 games and claims to be a much better player than her sister, who has won 24 out of her last 31 games.

a. Compare the twins' results to determine who is the better player.

b. Explain your answer to the twins.



16. In a survey, 24 people were asked: 'What is the maximum distance you would walk to a train station?' A person who says '800 m' will walk up to 800 m, but no more. The survey responses are:

100 m	200 m	250 m	1 km	$\frac{1}{2}$ km	$\frac{3}{4}$ km
600 m	450 m	500 m	100 m	1.2 km	800 m
1.5 km	1.4 km	200 m	300 m	1.2 km	350 m
900 m	750 m	300 m	650 m	320 m	100 m

Determine the longest distance (as a multiple of 100 m) that at least $\frac{3}{4}$ of the people would walk to the train station. Justify your response.

17. You are competing in a long jump contest. Your first jump was 3.78 m, your second jump was $3\frac{8}{9}$ m and your third jump is $3\frac{4}{5}$ m. You are congratulated on your third jump, as being your best. Explain whether you agree.



Problem solving

18. A student received the following scores in his last three tests:
History $\frac{12}{17}$, English $\frac{7}{10}$ and Science $\frac{71}{101}$. Place his test scores in order from highest to lowest score (by first converting each score to a decimal).

19. Place the following fractions in order from smallest to largest by first converting the fractions to decimals:

$$\frac{3}{7}, \frac{4}{15}, \frac{8}{25}, \frac{3}{11}, \frac{30}{100}, \frac{4}{12}, \frac{325}{1000}$$

20. The decimal equivalents of $\frac{1}{7}, \frac{2}{7}, \frac{3}{7} \ldots \frac{6}{7}$ can be found in the sequence 142 857 142 857 142 857 …
If $\frac{1}{7} = 0.\dot{1}42\,857\dot{1}$ and $\frac{2}{7} = 0.\dot{2}85\,71\dot{4}$, without using a calculator, write $\frac{3}{7}, \frac{4}{7}, \frac{5}{7}$ and $\frac{6}{7}$ as decimals.

6.4 Rounding and repeating decimals

LEARNING INTENTION

At the end of this subtopic you should be able to:

- round decimal numbers to the required number of decimal places.

6.4.1 Rounding

eles-3945

- When rounding decimals, look at the first digit after the number of decimal places required.

Rules for rounding

- If the first digit after the number of decimal places required is 0, 1, 2, 3 or 4, write the number without any change.
- If the first digit after the number of decimal places required is 5, 6, 7, 8 or 9, add one to the digit in the last required decimal place.

- We can use the ≈ symbol to represent approximation when rounding has occurred, as shown in Worked example 10.

WORKED EXAMPLE 10 Rounding decimal numbers

Round the following to 2 decimal places.

a. **3.641 883** **b.** **18.965 402 0**

THINK	WRITE
a. 1. Write the number and underline the required decimal place.	**a.** $3.6\underline{4}1\,883$
2. Circle the next digit and round according to the rule. *Note:* Since the circled digit is less than 5, we leave the number as it is.	$= 3.6\underline{4}\textcircled{1}883$ ≈ 3.64
b. 1. Write the number and underline the required decimal place.	**b.** $18.9\underline{6}5\,402\,0$
2. Circle the next digit and round according to the rule. *Note:* Since the circled digit is greater than or equal to 5, add 1 to the last decimal place that is being kept.	$= 18.9\underline{6}\textcircled{5}4020$ ≈ 18.97

- If you need to add 1 to the last decimal place and the digit in this position is a 9, the result is 10. The 0 is put in the last required place and the 1 is added to the digit in the next place to the left.
For example, 0.298 rounded to 2 decimal places is 0.30.

WORKED EXAMPLE 11 Rounding decimals to a given number of decimal places

Round the following to the number of decimal places shown in the brackets.
a. **27.462 973 (4)** **b.** **0.009 94 (3)**

THINK	WRITE
a. 1. Write the number and underline the required decimal place.	**a.** $27.462\underline{9}73$
2. Circle the next digit and round according to the rule. *Note:* Since the circled digit is greater than 5, add 1 to the last decimal place that is being kept. As 1 is being added to 9, write 0 in the last place and add 1 to the previous digit.	$= 27.462\underline{9}\textcircled{7}3$ ≈ 27.4630
b. 1. Write the number and underline the required decimal place.	**b.** $0.00\underline{9}94$
2. Circle the next digit and round according to the rule. *Note:* Since the circled digit is greater than 5, add 1 to the last decimal place that is being kept. As 1 is being added to 9, write 0 in the last place and add 1 to the previous digit.	$= 0.00\underline{9}\textcircled{9}4$ ≈ 0.010

WORKED EXAMPLE 12 Rounding decimals to the nearest unit

Round 8.672 to the nearest unit.

THINK	WRITE
1. Write the decimal.	8.672
2. Look at the first digit after the decimal point. Since it is greater than 5, add 1 to the whole number.	≈ 9

- When trying to answer Worked example 12, you can think of the question this way: 'Is 8.672 closer to 8 or 9?'

6.4.2 Rounding to the nearest 5 cents

eles-3946

- As the smallest denomination of physical money in Australia is the 5-cent coin, prices must be rounded to the nearest 5 cents upon payment.
- Rounding to the nearest 5 cents works in the same way as rounding to the nearest 10: determine whether the number is closest to 0, 5 or 10, then round accordingly.

Rounding guidelines for cash transactions	
Final cash amount	**Round to:**
1 and 2 cents	nearest 10
3 and 4 cents	nearest 5
6 and 7 cents	nearest 5
8 and 9 cents	nearest 10

Source: www.accc.gov.au

WORKED EXAMPLE 13 Rounding to the nearest 5 cents

Melinda had $51.67 in her bank account. She wanted to withdraw all her money, so the bank rounded the amount to the nearest 5 cents. State how much money the teller gave Melinda.

THINK	WRITE
1. Write the actual amount she had in her account.	$51.67
2. Determine whether the last digit is closer to 5 or closer to 10, then rewrite the approximate value. *Note:* Alternatively it can be seen that 67 cents is closer to 65 cents than 70 cents.	$\approx \$51.65$
3. Write the answer in a sentence.	Melinda will receive $51.65 from the bank.

6.4.3 Repeating decimals

eles-3947

- A **terminating decimal** is a decimal number that ends (terminates) after any number of decimal places; for example, $\frac{9}{20} = 0.45$ is a terminating decimal.
- A **recurring decimal**, or a repeating decimal, occurs when we divide the denominator into the numerator and the answer keeps repeating.
  For example, $\frac{1}{3} = 0.333\cdots$
  $\frac{1}{6} = 0.1666\cdots$

WORKED EXAMPLE 14 Repeating decimals

Convert $\frac{1}{11}$ to a decimal. Continue dividing until a pattern emerges, then round the answer to 2 decimal places.

THINK	WRITE
1. Set out the question as for division of whole numbers, adding a decimal point and enough zeros to see a pattern emerging.	$11\overline{)1.0000}$
2. Divide, writing the answer with the decimal point exactly in line with the decimal point in the question. (The amount left over each time is 10 then 1, then 10 then 1 again. The decimal answer is also repeating.)	$11\overline{)1.^{1}0^{10}0^{1}0^{10}0^{1}0^{10}0^{1}0^{10}0}\ \begin{matrix}0.0\ 9\ 0\ 9\ 0\ 9\ 0\ 9\ldots\end{matrix}$
3. Write the approximate answer rounded to 2 decimal places.	$\frac{1}{11} \approx 0.09$

- Recurring decimals can be written in one of the following shorter ways for an exact answer.
  - 4.6666 ... could be written as $4.\dot{6}$ (with a dot above the repeating part of the decimal).
  - 3.512 512 ... could be written as $3.\dot{5}1\dot{2}$ (with a dot above the first and last digits of the repeating part) or as $3.\overline{512}$ (with a line above the repeating part of the decimal).
  - Like terminating decimals, the decimal equivalent of a fraction can be used to determine the decimal equivalent of any multiple of that fraction.


WORKED EXAMPLE 15 Equivalent repeating fractions

Use the result from Worked example 14 to calculate the decimal equivalent for $\frac{6}{11}$.

THINK	WRITE
1. Write the decimal equivalent for the fraction with 1 as the numerator. In this case, it is an infinite recurring decimal. Therefore 0.090 909 ... can be written as $0.\overline{09}$.	$\frac{1}{11} = 0.090\,909\ldots$
2. Multiply both sides of this equation by the appropriate multiple (6 in this case).	$\frac{1}{11} \times 6 = 0.090\,909\ldots \times 6$ $= 0.545\,454\ldots$
3. Simplify and write the answer.	$\frac{6}{11} = 0.\overline{54}$

DISCUSSION

When using a calculator to perform a calculation, for example $2 \div 3$, the answer may show an approximation to a recurring decimal, for example 0.666 666 667. Why do you think this may be?



Resources

eWorkbook Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)

Digital document SkillSHEET Rounding to the nearest whole number (doc-6476)

Interactivities Individual pathway interactivity: Rounding and repeating decimals (int-4339)
Rounding (int-3980)
Repeating decimals (int-3981)

Exercise 6.4 Rounding and repeating decimals

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 9, 13, 15, 18, 21, 22, 26	2, 5, 8, 10, 11, 16, 19, 25, 27	3, 6, 12, 14, 17, 20, 23, 24, 28

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE10 Round the following to 2 decimal places.
a. 0.3241 **b.** 0.863 **c.** 1.246 10 **d.** 13.049 92 **e.** 3.0409

2. Round the following to 2 decimal places.
a. 7.128 63 **b.** 100.813 82 **c.** 71.260 39 **d.** 0.0092 **e.** 2.386 214

3. Round the following to 2 decimal places.
a. 0.185 00 **b.** 19.6979 **c.** 0.3957 **d.** 0.999 **e.** 8.902

4. Round the following to 1 decimal place.
a. 0.410 **b.** 0.87 **c.** 9.27 **d.** 25.25 **e.** 3.92

5. Round the following to 1 decimal place.
a. 300.06 **b.** 12.82 **c.** 99.91 **d.** 8.88 **e.** 14.034 59

6. Round the following to 1 decimal place.
a. 17.610 27 **b.** 0.8989 **c.** 93.994 **d.** 0.959 027 **e.** 96.280 49

7. MC 13.179 rounded to 2 decimal places is:
A. 13.17 **B.** 13.20 **C.** 13.18 **D.** 13.27 **E.** 13.19

8. MC 2.998 rounded to 1 decimal place is:
A. 3.0 **B.** 2.9 **C.** 2.8 **D.** 3.1 **E.** 3.9

9. WE12 Round the following to the nearest unit.
a. 10.7 **b.** 8.2 **c.** 3.6 **d.** 92.7 **e.** 112.1

10. Round the following to the nearest unit.
a. 21.76 **b.** 42.0379 **c.** 2137.50 **d.** 0.12 **e.** 0.513

11. Write the following infinite recurring decimals using one of the short forms.
a. 2.555 ... **b.** $0.666\cdots$ **c.** 49.111 11 ... **d.** 0.262 626 ...

12. Write the following infinite recurring decimals using one of the short forms.
a. 0.913 913 ... **b.** 8.641 864 18 ... **c.** 133.946 246 2 ... **d.** 0.127 777 7 ...

Understanding

13. WE11 Convert each of the following to a decimal. Continue dividing until a pattern emerges, then round the answer to the number of decimal places indicated in the brackets.
a. $\frac{1}{3}$ (1) **b.** $\frac{1}{9}$ (1) **c.** $\frac{5}{12}$ (3)

14. Convert each of the following to a decimal. Continue dividing until a pattern emerges, then round the answer to the number of decimal places indicated in the brackets.
a. $\frac{1}{6}$ (2) **b.** $\frac{2}{11}$ (3) **c.** $\frac{7}{15}$ (2)

15. MC 1.8888 ... written as an exact answer is:

A. $1.\dot{8}$ **B.** 1.888 **C.** 1.88 **D.** 1.9 **E.** 1.889

16. MC $\frac{3}{7}$ as a decimal in exact form is:

A. $0.\dot{4}28\,57\dot{1}$ **B.** $0.\overline{428}$ **C.** 0.4 **D.** 0.428 517 4 **E.** $2.\dot{3}$

17. Determine decimal equivalents for the following fractions.

a. $\frac{7}{2}$ **b.** $4\frac{2}{3}$ **c.** $\frac{3}{4}$

18. Round the following to the nearest ten.

a. 13 **b.** 76 **c.** 138 **d.** 262 **e.** 175

19. Round the following to the nearest hundred.

a. 320 **b.** 190 **c.** 138 **d.** 6751 **e.** 9750.051

20. Round the following to the nearest thousand.

a. 3426 **b.** 12 300 **c.** 18 640 **d.** 9462 **e.** 1098

Reasoning

21. WE13 In the supermarket, Christine's shopping bill came to $27.68. As there are no 1- or 2-cent pieces, this amount must be rounded to the nearest 5 cents. State how much Christine will pay in cash for her shopping.



22. Rank the following decimals from smallest to largest:
$0.295, 0.29\dot{5}, 0.2\dot{9}\dot{5}, 0.\dot{2}9\dot{5}$

23. Write a decimal that is greater than $0.\dot{5}432\dot{1}$ and less than 0.543 22.

24. Using a calculator, Greg worked out that the piece of timber required to finish making a support for a gate should be 3.567 82 metres. Realistically, the timber can be measured only to the nearest millimetre (nearest thousandth of a metre). What measurement should be used for the length of the timber? Explain why 3.567 82 m is unreasonable as a measurement for timber.



25. Barney rounds a decimal to 0.6 correct to 1 decimal place. Fred then says that the number before being rounded off could not have been bigger than 0.64. Explain whether Fred is correct.

Problem solving

26. The maximum temperature was recorded as 24.7°C. In the news broadcast, the presenter quoted this to the nearest degree. Write the temperature quoted.

27. a. Round the decimal number 0.8375 to the nearest:

i. tenth **ii.** hundredth **iii.** thousandth.

b. Explain whether the rules for rounding a decimal up or down depend on the number of decimal places.

28. Divide 100 by the first 10 prime numbers. Write the answers correct to 4 decimal places.

6.5 Adding and subtracting decimals

LEARNING INTENTION

At the end of this subtopic you should be able to:

- add and subtract decimal numbers.

6.5.1 Adding decimals

eles-3948

- Decimals can be added using a method similar to that for whole numbers.
- Set out the addition in vertical columns and line up the decimal points so that the digits with the same place value are underneath each other.
- If the question is not written in columns, it is necessary to rewrite it with the decimal points lined up.
- Fill the empty places with zeros.

WORKED EXAMPLE 16 Adding numbers with decimals

Calculate:

a. $\begin{array}{r} 1.3 \\ +0.5 \\ \hline \end{array}$ **b.** $\begin{array}{r} 12.84 \\ +2.33 \\ \hline \end{array}$ **c.** $\begin{array}{r} 1.25 \\ 3.146 \\ +7.0 \\ \hline \end{array}$

THINK

a. Copy the question exactly and add the digits as for whole numbers, working from right to left.
Write the decimal point directly below the decimal points in the question.

b. Copy the question exactly and add the digits as for whole numbers, working from right to left.
Write the decimal point directly below the decimal points in the question.

c. Write the question, replacing the spaces with zeros.
Add the digits as for whole numbers, working from right to left.
Write the decimal point directly below the decimal points in the question.

WRITE

a. $\begin{array}{r} 1.3 \\ +0.5 \\ \hline 1.8 \end{array}$

b. $\begin{array}{r} 12.48 \\ +2.33 \\ \hline 14.81 \end{array}$

c. $\begin{array}{r} 1.250 \\ 3.146 \\ +7.000 \\ \hline 11.396 \end{array}$

WORKED EXAMPLE 17 Adding numbers with decimals

Rewrite in columns, then add $0.26 + 1.8 + 12.214$.

THINK

1. Write the question in columns with the decimal points directly beneath each other with the zeros included.
2. Add the digits as for whole numbers. Write the decimal point directly below the decimal points in the question.

WRITE

$\begin{array}{r} 0.260 \\ 1.800 \\ +12.214 \\ \hline 14.274 \end{array}$

6.5.2 Subtracting decimals

eles-3949

- Decimals can be subtracted using a method similar to that for whole numbers.
- Set out the subtraction in vertical columns and line up the decimal points so that the digits with the same place value are underneath each other.
- If the question is not written in columns, it is necessary to rewrite it with the decimal points lined up.
- Fill the empty places with zeros.

WORKED EXAMPLE 18 Subtracting numbers with decimals

Calculate: $\begin{array}{r} 0.56 \\ -0.14 \\ \hline \end{array}$

THINK	WRITE
Copy the question exactly and subtract the digits as for whole numbers, working from right to left. Write the decimal point directly below the decimal points in the question.	$\begin{array}{r} 0.56 \\ -0.14 \\ \hline 0.42 \end{array}$

WORKED EXAMPLE 19 Subtracting numbers with decimals

Rewrite the following in columns, then subtract.

a. **1.82 – 0.57** **b.** **2.641 – 0.85**

THINK	WRITE
a. Write in columns with the decimal points directly under each other. Subtract, and insert the decimal point directly below the other decimal points in the question.	**a.** $\begin{array}{r} {\scriptstyle 7} \\ 1.8\not{2}^{\checkmark} \\ -0.57 \\ \hline 1.25 \end{array}$
b. Write in columns with the decimal points directly under each other, adding zeros as appropriate. Subtract as for whole numbers and insert the decimal point directly below the other decimal points.	**b.** $\begin{array}{r} {\scriptstyle 5} \\ 2.\not{6}^{\checkmark}41 \\ -0.850 \\ \hline 1.791 \end{array}$

Checking by estimating

- Answers to decimal addition and subtraction can be checked by estimating. Round each decimal to the nearest whole number or to a similar number of decimal places and then add or subtract them.
  For example, in Worked example 17, you could check the answer by rounding to get an estimate by adding $0.3 + 2 + 12 = 14.3$, which is close to 14.274.
  In Worked example 18, you could check the answer by rounding to get an estimate $0.6 - 0.1 = 0.5$, which is close to 0.42.

DISCUSSION

What is your method for estimating the answer to a decimal addition or subtraction?

Resources

eWorkbook	Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)
Digital documents	SkillSHEET Adding decimals (same number of decimal places) (doc-6461) SkillSHEET Adding decimals (different number of decimal places) (doc-6462) SkillSHEET Subtracting decimals (same number of decimal places) (doc-6463) SkillSHEET Subtracting decimals (different number of decimal places) (doc-6464)
Interactivities	Individual pathway interactivity: Adding and subtracting decimals (int-4340) Addition of decimals (int-3982) Checking by estimating (int-3983) Subtraction of decimals (int-3984)

Exercise 6.5 Adding and subtracting decimals

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 8, 11, 15, 18, 21, 24, 25, 28, 29	2, 4, 9, 12, 16, 19, 22, 26, 30, 31, 32	5, 7, 10, 13, 14, 17, 20, 23, 27, 33, 34, 35

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. **WE16a, b** Calculate the following.

   a. $\begin{array}{r} 1.2 \\ +2.3 \\ \hline \end{array}$ b. $\begin{array}{r} 1.67 \\ +1.02 \\ \hline \end{array}$ c. $\begin{array}{r} 8.062 \\ +5.177 \\ \hline \end{array}$ d. $\begin{array}{r} 10.0364 \\ +92.1494 \\ \hline \end{array}$

2. **WE16c** Calculate the following, after filling the blank spaces.

   a. $\begin{array}{r} 6.27 \\ +0.5 \\ \hline \end{array}$ b. $\begin{array}{r} 3.26 \\ +18.6460 \\ \hline \end{array}$ c. $\begin{array}{r} 4.2 \\ 62.013 \\ +1946.12 \\ \hline \end{array}$ d. $\begin{array}{r} 48.129\,06 \\ 9 \\ +204.32 \\ \hline \end{array}$

3. **WE17** Rewrite the following in columns, then add. Check your answer by rounding to get an estimate.

   a. $1.4 + 3.2$ b. $6.5 + 0.4$ c. $3.261 + 0.21$ d. $15.987 + 1.293$

4. Rewrite the following sums, then add. Check your answer by rounding to get an estimate.

   a. $10.8271 + 6.5$
   b. $1.8 + 18.6329$
   c. $0.24 + 3.16 + 8.29$
   d. $14.23 + 1.06 + 86.29 + 3.64$

5. Rewrite the following sums, then add. Check your answer by rounding to get an estimate.

   a. $5.27 + 1.381 + 12.3$
   b. $100 + 4.3 + 0.298 + 1.36$
   c. $82.3 + 100.6 + 0.9949 + 9$
   d. $126 + 372.8 + 100.0264 + 2020.13$

6. **WE18** Calculate the following, filling the spaces with zeros as required. Check your answer by rounding to get an estimate.

   a. $\begin{array}{r} 6.87 \\ -6.27 \\ \hline \end{array}$ b. $\begin{array}{r} 12.231 \\ -8.026 \\ \hline \end{array}$ c. $\begin{array}{r} 0.6301 \\ -0.5495 \\ \hline \end{array}$ d. $\begin{array}{r} 3.0091 \\ -1.6723 \\ \hline \end{array}$

7. Calculate the following, filling the spaces with zeros as required. Check your answer by rounding to get an estimate.

a. $\begin{array}{r} 31.02 \\ -26 \\ \hline \end{array}$ b. $\begin{array}{r} 98.26 \\ 9.07 \\ \hline \end{array}$ c. $\begin{array}{r} 146 \\ -58.91 \\ \hline \end{array}$ d. $\begin{array}{r} 3.2 \\ -0.467 \\ \hline \end{array}$

8. WE19 Rewrite the following in columns, then subtract. Check your answer by rounding to get an estimate.
   a. $5.64 - 2.3$ b. $12.07 - 6.14$ c. $0.687 - 0.36$ d. $15.226 - 11.08$

9. Rewrite the following in columns, then subtract. Check your answer by rounding to get an estimate.
   a. $6.734 - 4.8$ b. $12.2 - 8.911$ c. $100.562 - 86.0294$ d. $38 - 21.234$

10. Rewrite the following in columns, then subtract. Check your answer by rounding to get an estimate.
    a. $47 - 8.762$ b. $5 - 0.8864$ c. $0.2 - 0.0049$ d. $3.279 - 2.506\,84$

Understanding

11. MC $1.6 + 4.8$ equals:
    A. 5.4 B. 6.4 C. 0.54 D. 0.64 E. 64

12. MC $3.26 + 0.458$ equals:
    A. 3.718 B. 0.784 C. 0.037 18 D. 3.484 E. 7.84

13. MC $1.84 + 0.61 + 4.07$ equals:
    A. 6.52 B. 6.42 C. 5.42 D. 5.52 E. 0.652

14. MC $216 + 1.38 + 0.002\,64$ equals:
    A. 217.4064 B. 0.618 C. 217.644 D. 217.382 64 E. 21.7644

15. MC $0.39 - 0.15$ equals:
    A. 0.0024 B. 0.024 C. 0.24 D. 2.4 E. 24

16. MC $1.4 - 0.147$ would be rewritten as:
    A. $\begin{array}{r} 1.4 \\ -0.417 \\ \hline \end{array}$ B. $\begin{array}{r} 1.400 \\ -0.417 \\ \hline \end{array}$ C. $\begin{array}{r} 1.40 \\ -1.47 \\ \hline \end{array}$ D. $\begin{array}{r} 1.004 \\ -0.147 \\ \hline \end{array}$ E. $\begin{array}{r} 1.040 \\ -0.147 \\ \hline \end{array}$

17. MC $0.3 - 0.024$ equals:
    A. 0.06 B. 0.276 C. 0.7 D. 0.76 E. 76

18. MC $150.278 - 0.99$ equals:
    A. 150.728 B. 149.288 C. 1.49288 D. 159.388 E. 1.593 88

19. Josh deposited $27.60 into his bank account. If his balance before the deposit was $139.40, determine Josh's new bank balance.

20. Jessica bought the following items at the school canteen: 1 can of Coke for $1.60, 1 sausage roll for $1.20, 1 packet of chips for $1.50 and 2 red frogs for $0.40 (red frogs cost 20 cents each). Calculate how much Jessica spent.



21. A triathlon consists of a 0.5-kilometre swim, a 15.35-kilometre bike ride and a 4.2-kilometre run. Calculate how far the competitors travel altogether.



22. Amy walked 3.6 kilometres to school, 0.8 kilometres from school to the shops, 1.2 kilometres from the shops to a friend's house and finally 2.5 kilometres from her friend's house to her home. Calculate how far Amy walked.

23. For lunch Paula ordered 1 potato cake, 1 dim sim, minimum chips and a milkshake from the menu below. Calculate how much Paula spent on her lunch.

MENU			
Flake	$3.50	Coffee	$2.20
Whiting	$3.50	Tea	$2.20
Dim sims	$0.60	Soft drinks	$1.80
Potato cakes	$0.50	Milkshakes	$3.00
Minimum chips	$2.50	Water	$1.80

24. Ryan works in a newsagency. A customer buys $9.65 worth of goods and gives Ryan a $20 note. Calculate the change Ryan gives the customer.

Reasoning

25. A jockey has a mass of 52.3 kilograms. After exercising and training for 2 days and spending time in a sauna, the jockey has lost 1.82 kilograms. Determine the jockey's mass now.



26. If 1.27 metres is cut from a piece of material that is 13 metres long, calculate how much material is left.

27. Gary and Liz are replacing the skirting boards in their lounge room. They know the perimeter of the room is 34.28 metres. If there is a door 0.82 metres wide and a fireplace 2.18 metres wide that do not require skirting boards, explain (with working) how much wood they will need to buy for their lounge room.

Problem solving



28. Cathy Freeman won a particular 400 metre race in 51.35 seconds. In her next race, her time was 2.97 seconds faster than this. Determine Cathy's time for the later race.

29. Without using a calculator, determine the average of the numbers 0.1, 0.11 and 0.111.

30. Explain how rounding is used in estimation.

31. Jo and Anton made a certain number of telephone calls over a 2-month period. There is a charge of 25 cents for each call, and the monthly rental of the phone line is $13.60. The bill for the 2 months comes to $39.45. Determine how many calls they made in the 2-month period.

32. The following table shows the times recorded for each swimmer in the under-13, 50-metre freestyle relay for 6 teams.

Times for each swimmer (seconds)				
Team	**Swimmer 1**	**Swimmer 2**	**Swimmer 3**	**Swimmer 4**
1	36.7	41.3	39.2	35.8
2	38.1	46.5	38.8	35.9
3	34.6	39.2	39.9	35.2
4	41.6	40.8	43.7	40.5
5	37.9	40.2	38.6	39.2
6	38.3	39.1	40.8	37.6

a. Determine the total time for each team. Put your results in a table.
b. Identify which team won the relay.
c. Determine the difference in time between the first and second placed teams.

33. Australian coins, which are minted by the Royal Australian Mint, have the following masses:



5c	2.83 g	10c	5.65 g	20c	11.3 g
50c	15.55 g	$1	9.0 g	$2	6.6 g

I have 6 coins in my pocket, with a total value of $2.45. What could the total mass of these coins be?

34. You purchased some shares over a 4-month period. The price fell by $4.23 in the first month, rose by $6.67 in the second month, rose by $1.35 in the third month and fell by $3.28 in the fourth month. Explain whether the shares increased or decreased in value over the four months, and by how much.

35. Arrange the digits 1 to 9 into the boxes at right to make a true decimal addition.

$$\square\square\cdot\square\square$$
$$+\ \square\square\cdot\square\square$$
$$\overline{\qquad\square\square\cdot\square\square}$$

6.6 Multiplying decimals

LEARNING INTENTION


At the end of this subtopic you should be able to:
- multiply decimals, including by multiples of 10
- square decimal numbers.

6.6.1 Multiplying decimals

eles-3950

- The following calculation shows the multiplication 1.7×2.3. The diagram is a visual representation of each step in the calculation. There are 1.7 rows of 2.3, or 1.7 groups of 2.3.

$$\begin{array}{rl} 1.7 & \\ \times 2.3 & \\ \hline 0.51 & \leftarrow 0.3 \times 1.7 = 0.51 \\ 3.40 & \leftarrow 2.0 \times 1.7 = 3.40 \\ \hline 3.91 & \leftarrow \textbf{Total} \end{array}$$



- The smallest place value in the answer is determined by multiplying the smallest place values from each of the decimal numbers. The first multiplication is $\frac{3}{10} \times \frac{7}{10} = \frac{21}{100}$, so the smallest place value in the answer will be hundredths.

Multiplying decimals

The number of decimal places in the answer is equal to the total number of decimal places in the numbers being multiplied.

WORKED EXAMPLE 20 Multiplying numbers with decimals

Calculate the following.

a. 12.6×7

b.
$$\begin{array}{r} 3.26 \\ \times 0.4 \\ \hline \\ \hline \end{array}$$

c.
$$\begin{array}{r} 0.4629 \\ \times 2.6 \\ \hline \\ \hline \end{array}$$

THINK

a. 1. Rewrite and multiply the digits, ignoring the decimal places.

2. Count the number of decimal places altogether (1) and put in the decimal point.

3. Check the answer by rounding: $10 \times 7 = 70$, which is close to 88.2.

WRITE

a.
$$\begin{array}{r} 126 \\ \times 7 \\ \hline 882 \end{array}$$

$12.6 \times 7 = 88.2$

b. 1. Multiply, ignoring the decimal places.

b.
$$\begin{array}{r} 326 \\ \times\ 4 \\ \hline 1304 \end{array}$$

2. Count the number of digits after the point in both the decimals being multiplied and insert the decimal point in the answer. There are 2 decimal places in 3.26 and 1 in 0.4 so there will be 3 decimal places in the answer.

$3.26 \times 0.4 = 1.304$

3. Check the answer by rounding: $3 \times 0.4 = 1.2$, which is close to 1.304.

c. 1. Multiply, ignoring the decimal places.

c.
$$\begin{array}{r} 4629 \\ \times\ 26 \\ \hline 27\,774 \\ 92\,580 \\ \hline 120\,354 \end{array}$$


2. Count the number of digits after the point in both the decimals being multiplied. Insert the decimal point in that position in the answer.

There are 4 decimal places in 0.4629 and 1 decimal place in 2.6, so there will be 5 decimal places in the answer.

$0.4629 \times 2.6 = 1.203\,54$

Digital technology

Scientific calculators can evaluate multiplication of numbers with decimals.



DISCUSSION

Does multiplication always result in a larger number?

6.6.2 Squaring decimals


eles-3951

- To square a decimal, multiply the number by itself.


Squaring decimals

- The number of decimal places in the square is twice the number of decimal places in the original number.


- The following diagrams show how squaring decimal numbers can be represented visually.




$1.5^2 = 2.25$



$1.2^2 = 1.44$



$0.75^2 = 0.5625$



$0.5^2 = 0.25$

WORKED EXAMPLE 21 Squaring decimal numbers


Calculate the following.

a. **0.5^2** b. **1.2^2**

THINK	WRITE
a. 1. Multiply the number by itself, ignoring the decimal places.	a. $5 \times 5 = 25$
2. Count the number of digits after the point in both the decimals being multiplied and insert the decimal point in the answer. There will be 2 decimal places in the answer.	$0.5 \times 0.5 = 0.25$
3. Write the answer.	$0.5^2 = 0.25$
b. 1. Multiply the number by itself, ignoring the decimal places.	b. $12 \times 12 = 144$
2. Count the number of digits after the point in both the decimals being multiplied and insert the decimal point in the answer. There will be 2 decimal places in the answer.	$1.2 \times 1.2 = 1.44$
3. Write the answer.	$1.2^2 = 1.44$

6.6.3 Multiplying by multiples of 10

eles-3952



- The multiples of 10 are 10, 20, 30, 40, ... 120, ... 1000, ... 1500, ... 20 000 and so on.
- Multiplying by a multiple of 10 can be carried out by writing the multiple of 10 as the product of two factors.
- The factors used are the non-zero digits from the multiple of 10 and the corresponding power of 10.
- For example, $8700 = 87 \times 100$, so multiplying by 8700 is the same as multiplying by 87 and then multiplying by 100.
- To multiply a number with a decimal by a power of 10, move the decimal point to the right by the number of zeros.
  For example:
  - to multiply by 10, move the decimal point one place to the right
  - to multiply by 100, move the decimal point two places to the right
  - to multiply by 1000, move the decimal point three places to the right.

WORKED EXAMPLE 22 Multiplying by multiples of 10

Calculate:

a. 5.1×600 **b.** $0.0364 \times 24\,000$

THINK	WRITE
a. 1. Multiplying by 600 is the same as first multiplying by 6 then multiplying by 100. Calculate 5.1×6.	**a.** $\begin{array}{r} 5.1 \\ \times\ 6 \\ \hline 30.6 \end{array}$
2. Multiply the result by 100. Move the position of the decimal point 2 places to the right.	$30.6 \times 100 = 3060$
3. Write the answer.	$5.1 \times 600 = 3060$
b. 1. Multiplying by 24 000 is the same as first multiplying by 24 then multiplying by 1000. Calculate 0.0364×24.	**b.** $\begin{array}{r} 0.0364 \\ \times\ 24 \\ \hline 1456 \\ 7280 \\ \hline 0.8736 \end{array}$
2. Multiply the result by 1000. Move the position of the decimal point 3 places to the right.	$0.8736 \times 1000 = 873.6$
3. Write the answer.	$0.0364 \times 24\,000 = 873.6$

Recognising short cuts

- When multiplying by some common decimals, such as 0.1 or 0.25, you can use short cuts to help you complete the calculation more efficiently.

  For example, the fractional equivalent of 0.1 is $\frac{1}{10}$, so instead of multiplying by 0.1 you can multiply by $\frac{1}{10}$, which is the same as dividing by 10. Similarly, the fractional equivalent of 0.25 is $\frac{1}{4}$, so 0.25 of \$60 is equivalent to $\frac{1}{4}$ of \$60, which is equivalent to $\$60 \div 4$.

on Resources

eWorkbook	Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)
Digital documents	SkillSHEET Multiplying decimals by a single-digit number (doc-6465) SkillSHEET Multiplying decimals by 10, 100, 1000 (doc-6466)
Video eLesson	Multiplication of decimals (eles-2311)
Interactivities	Individual pathway interactivity: Multiplying decimals (including by multiples of 10) (int-4341) Multiplication of decimals (int-3985)

Exercise 6.6 Multiplying decimals

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13, 15, 20, 22, 24, 27	2, 5, 8, 11, 14, 16, 19, 25, 28	3, 6, 9, 12, 17, 18, 21, 23, 26, 29

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Calculate the following.
   a. 3.5×4 b. 15.7×8 c. 10.2×6 d. 22.34×5

2. Calculate the following.
   a. 27.18×7 b. 64.87×8 c. 1.064×6 d. $0.264\,81 \times 3$

3. WE20a Calculate the following.
   a. 1.4×0.6 b. 4.2×0.7 c. 0.8×0.4 d. 9.7×0.8

4. Calculate the following.
   a. 0.35×0.4 b. 0.64×0.3 c. 0.77×0.5 d. 0.49×0.9

5. Calculate the following.
   a. 5.38×0.8 b. 0.347×0.6 c. 4.832×0.6 d. 12.2641×0.4

6. Calculate the following.
   a. 0.002×0.05 b. 0.003×0.004 c. 0.7×0.09 d. 0.037×0.006

7. Calculate the following.
   a. $0.000\,061 \times 0.04$ b. 0.004×0.09 c. 0.56×0.7 d. $0.030\,31 \times 0.02$

8. WE20b Calculate the following.
   a. 0.25×1.2 b. 0.37×2.3 c. 0.47×5.4 d. 0.05×3.5

9. Calculate the following.
   a. 0.79×8.3 b. 4.68×3.6 c. 8.04×7.5 d. 5.06×6.2

10. MC When calculating 8.32×0.64, the number of decimal places in the answer is:
    A. 0 B. 1 C. 2 D. 3 E. 4

11. MC 0.2×0.2 equals:
    A. 0.004 B. 0.04 C. 0.4 D. 4 E. 40

12. MC 1.4×0.8 equals:
    A. 1.12 B. 8.2 C. 82 D. 11.2 E. 112

13. MC 0.0312×0.51 equals:
    A. 0.001 591 2 B. 0.015 912 C. 0.156 312 D. 0.159 12 E. 1.5912

Understanding

14. WE21 Calculate the following.
    a. 0.02^2 b. 1.3^2 c. 2.05^2

15. WE22 Calculate the following.
    a. 0.127×8000 b. $0.543 \times 11\,000$ c. $8.1 \times 54\,000$

16. Calculate the following.

a. 3.64×300 **b.** 7.58×600 **c.** 42.6×900

17. Calculate the following by moving the position of the decimal point.

a. 6.48×10 **b.** 13.896×100 **c.** 0.2708×1000

d. $217.148\,96 \times 1000$ **e.** $0.820\,496\,783 \times 100\,000$

18. Evaluate the following by moving the position of the decimal point.

a. $32.689\,043\,267 \times 100\,000$ **b.** $0.984\,326\,641 \times 1\,000\,000$

c. $0.000\,278\,498\,32 \times 1\,000\,000$ **d.** 0.46×1000

19. For the following calculations:

i. Estimate the answer by rounding each number to the first digit.

ii. Calculate the answers by using written methods.

iii. Check your answer by using a calculator.

a. 5.6×4400 **b.** $10.2 \times 32\,510$ **c.** 33.3×1515


20. Change the following amounts of money to cents. (*Hint:* There are 100 cents in one dollar.)

a. \$35 **b.** \$127 **c.** \$11 **d.** \$25.35 **e.** \$58.20

21. One thousand Year 7 students contributed 75 cents each to the bushfire appeal. Calculate how many dollars they contributed altogether.

22. Benjamin and Robyn were providing ice cream for 600 children. Calculate how much ice cream would be needed if each child was expected to eat 0.18 litres.

23. Calculate the area of the tennis court shown, given that area = length × width.



Reasoning

24. Judy bought 34.5 litres of petrol at 92.9 cents per litre. She paid 3200 cents at the counter.

a. Convert 3200 cents into dollars.

b. Do you think Judy paid the correct amount for her petrol? Explain your answer.

25. A sheet of paper is 0.012 cm thick. Explain whether you would notice the difference in the height between a stack of 500 sheets and a stack of 550 sheets.

26. A ball is dropped from a height of 1 metre. If it reaches 0.7 times the height of the previous bounce at each bounce, determine the number of times the ball bounces until the height is less than 1 centimetre.

Problem solving

27. Michael bought 0.65 kilograms of cubed steak at a butcher's shop. The meat costs \$8.50 per kilogram. Calculate how much Michael paid for the steak. *Note:* Round to the nearest 5c.

28. James is using the recipe for chocolate chip muffins to make 1.5 times the given amount. If the recipe lists 0.25 litres of milk in the ingredients, determine the amount of milk James should use for his muffins.



29. Sophie, Hamish and Thomas shared a pizza and paid according to what they ate. Sophie ate 4 slices, Hamish ate 3 slices and Thomas ate 5 slices. If Thomas's share of the bill was \$4.50, calculate the amount Sophie and Hamish had to pay.

6.7 Dividing decimals

LEARNING INTENTION


At the end of this subtopic you should be able to:

- divide a decimal number by a whole number or a decimal number
- divide a decimal number by a multiple of 10.

6.7.1 Dividing a decimal by a whole number

eles-3954

- The method for dividing a decimal number by a whole number is the same as the method used for dividing whole numbers.
- A visual representation of $2.4896 \div 4$ is shown here.



$2.4896 \div 4$ can be interpreted as 'how many times does 4 divide into 2.4896?' As shown, 4 divides into 2.4896 less than once.

WORKED EXAMPLE 23 Dividing a decimal by a whole number

Calculate the value of $2.4896 \div 4$.

THINK	WRITE
1. Set out the question as you would for whole numbers.	$4\overline{)2.4896}$
2. Divide 4 into the first digit of 2.4896 ($2 \div 4 = 0$ remainder 2). Write the 0 above the 2, and write the remainder beside the next digit, as shown in black.	$\begin{array}{r} 0 \\ 4\overline{)2.^{2}4896} \end{array}$
3. The second digit in the number being divided is to the right of the decimal point, so write the decimal point in the answer directly above the decimal point in the question, as shown in pink.	$\begin{array}{r} 0. \\ 4\overline{)2.^{2}4896} \end{array}$
4. Divide 4 into the second digit, which includes the carried 2 ($24 \div 4 = 6$ remainder 0). Write the 6 above the 4, as shown in plum.	$\begin{array}{r} 0.\ 6 \\ 4\overline{)2.^{2}4896} \end{array}$
5. Divide 4 into the third digit ($8 \div 4 = 2$). Write the 2 above the 8, as shown in pink.	$\begin{array}{r} 0.\ 62 \\ 4\overline{)2.^{2}4896} \end{array}$
6. Divide 4 into the fourth digit ($9 \div 4 = 2$ remainder 1). Write the 2 above the 9, and write the remainder beside the next digit, as shown in purple.	$\begin{array}{r} 0.622 \\ 4\overline{)2.^{2}489^{1}6} \end{array}$
7. Divide 4 into the fifth digit, which includes the carried 1 ($16 \div 4 = 4$). Write the 4 above the 6, as shown in orange.	$\begin{array}{r} 0.\ 6224 \\ 4\overline{)2.^{2}489^{1}6} \end{array}$
8. Write the answer.	$2.4896 \div 4 = 0.6224$

- Sometimes, when you are dividing numbers, there will be a remainder. For example $15.3 \div 4$:

$$4\overline{)15.^{3}3} \quad \text{remainder } 1$$

- Instead of leaving a remainder, add zeros to the end of the decimal and keep dividing until there is no remainder.

$$4\overline{)15.^{3}3^{1}0^{2}0} \quad 3.\ 8\ 2\ 5$$

WORKED EXAMPLE 24 Dividing a decimal by a whole number

Calculate $21.76 \div 5$. Add zeros and keep dividing until there is no remainder.

THINK

1. Set up the division. Write the decimal point in the answer directly above the decimal point in the question and divide as for short division, adding zeros as required.
2. Check the answer by rounding: $20 \div 5 = 4$, which is close to 4.352.

WRITE

$$5\overline{)21.^{1}7^{2}6^{1}0} \quad 4.\ 3\ 5\ 2$$

6.7.2 Dividing a decimal number by a multiple of 10

eles-3955

- When dividing by a multiple of 10, factorise the multiple to give a power of 10 and its other factor. Divide by the other factor first, and then by the power of 10.
  For example, to divide by 500, divide first by 5 and then by 100.
- To divide by a power of 10, move the decimal point to the left by the number of zeros.
  For example, to divide by 10, move the decimal point one place to the left;
  to divide by 100, move the decimal point two places to the left;
  to divide by 1000, move the decimal point three places to the left, and so on.

WORKED EXAMPLE 25 Dividing a decimal by a multiple of 10

Calculate:

a. **$4.8 \div 40$**

b. **$19.2 \div 6000$**

THINK

a. 1. Dividing by 40 is the same as first dividing by 4 then dividing by 10. First, divide by 4.

2. To divide by 10, move the position of the decimal point 1 place to the left.

3. Write the answer.

b. 1. Dividing by 6000 is the same as dividing by 6 then dividing by 1000. First, divide by 6 .

2. To divide by 1000, move the position of the decimal point 3 places to the left.

3. Write the answer.

WRITE

a. $4\overline{)4.8} \quad 1.2$

$1.2 \div 10 = 0.12$

$4.8 \div 40 = 0.12$

b. $6\overline{)19.2} \quad 3\ .2$

$3.2 \div 1000 = 0.0032$

$19.2 \div 6000 = 0.0032$


COLLABORATIVE TASK: Decimal division patterns

1. As a class, work out the following divisions using a calculator and write each part with its answer on the board.
   a. $10 \div 0.1$ **b.** $10 \div 0.2$ **c.** $10 \div 0.3$ **d.** $10 \div 0.4$ **e.** $10 \div 0.5$
   f. $10 \div 0.6$ **g.** $10 \div 0.7$ **h.** $10 \div 0.8$ **i.** $10 \div 0.9$ **j.** $10 \div 1.0$
2. Have you noticed any pattern in your answers? Discuss.
3. Now repeat the calculations, this time using $20 \div 0.1, 20 \div 0.2$ and so on.
4. Discuss with your class what is happening when you divide by a decimal.
5. Make up some divisions of your own and check if your assumptions about dividing by a decimal hold true.

6.7.3 Dividing a decimal number by another decimal number

eles-3956

- A visual representation of $2.724 \div 0.4$ is shown below.



$2.724 \div 0.4$ can be interpreted as 'how many times does 0.4 divide into 2.724?'

$$2.724 \div 0.4 = 6.81$$

Dividing one decimal number by another

- When dividing one decimal by another, multiply the decimal you are dividing by (divisor) by a power of 10 to make it a whole number.
  Multiply the other decimal *by the same power of* 10, as shown in the following example.

First multiply this number by 10 to make a whole number.

$$2.724 \div 0.4$$

Then multiply this number by 10 also.

- This is the same as writing an equivalent fraction with a whole number as the denominator:

$$\frac{2.724}{0.4} \times \frac{10}{10} = \frac{27.24}{4}$$


WORKED EXAMPLE 26 Dividing a decimal by a decimal

Calculate:
a. **26.724 ÷ 0.4** **b.** **3.0276 ÷ 0.12**

THINK	WRITE
a. 1. Rewrite the question as a fraction.	**a.** $26.724 \div 0.4 = \frac{26.724}{0.4}$
2. Multiply both the numerator and the denominator by the appropriate power of 10.	$= \frac{26.724}{0.4} \times \frac{10}{10}$ $= \frac{267.24}{4}$
3. Divide the decimal by the whole number.	$4\overline{)26^{2}7.^{3}24}$ $6\ \ 6.\ 81$
4. Write the answer.	$26.724 \div 0.4 = 66.81$
b. 1. Rewrite the question as a fraction.	**b.** $3.0276 \div 0.12 = \frac{3.0276}{0.12}$
2. Multiply both the numerator and the denominator by the appropriate power of 10.	$= \frac{3.0276}{0.12} \times \frac{100}{100}$ $= \frac{302.76}{12}$
3. Divide the decimal by the whole number.	$12\overline{)30^{6}2.^{2}7^{3}6}$ $2\ \ 5.\ 2\ \ 3$
4. Write the answer.	$3.0276 \div 0.12 = 25.23$

Digital technology

Scientific calculators can evaluate division of numbers with decimals.



WORKED EXAMPLE 27 Dividing a decimal by a decimal

Calculate how many litres of petrol could be purchased for $50.88 if 1 litre costs $1.06.

THINK	WRITE
1. Write the question.	$50.88 \div 1.06$
2. Rewrite the question as a fraction.	$= \frac{50.88}{1.06}$
3. Multiply the numerator and denominator by the appropriate multiple of 10, in this case 100. Alternatively, the decimal point could be moved twice to the right in both numbers so that the divisor is a whole number ($50.88 \div 1.06 = 5088 \div 106$).	$= \frac{50.88}{1.06} \times \frac{100}{100}$ $= \frac{5088}{106}$
4. Divide the decimal by the whole number. Alternatively, use a calculator.	$= 106\overline{)508^{84}8}$ (4 8) $50.88 \div 1.06 = 48$
5. Write the answer in a sentence.	Forty-eight litres of petrol could be purchased for $50.88.

Resources

eWorkbook	Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)
Digital documents	SkillSHEET Dividing decimals by a single-digit number (doc-6467) SkillSHEET Dividing decimals by 10, 100, 1000 (doc-6468)
Video eLesson	Division of decimals (eles-1877)
Interactivities	Individual pathway interactivity: Dividing decimals (including by multiples of 10) (int-4342) Division of decimals by a multiple of 10 (int-3990) Division of a decimal by another decimal (int-3991)

Exercise 6.7 Dividing decimals

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 10, 13, 15, 17, 20, 23, 24, 25	2, 5, 6, 8, 11, 14, 18, 21, 26, 27	3, 7, 9, 12, 16, 19, 22, 28, 29, 30

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE23 Calculate:
   a. $3.6 \div 6$ b. $21.7 \div 7$ c. $4.86 \div 9$ d. $8.05 \div 5$ e. $9.68 \div 4$

2. Calculate:
   a. $1.576 \div 2$ b. $8.029 \div 7$ c. $32.5608 \div 8$ d. $20.5782 \div 3$ e. $126.4704 \div 4$

3. Calculate:
   a. $46.80 \div 15$ b. $24.541 \div 11$ c. $17.108 \div 14$ d. $77.052 \div 12$ e. $121.3421 \div 11$

4. WE24 Calculate the following. In each case, add zeros and keep dividing until there is no remainder.
   a. $3.7 \div 2$ b. $9.5 \div 2$ c. $7.3 \div 5$

5. Calculate the following. In each case, add zeros and keep dividing until there is no remainder.
   a. $9.8 \div 4$ b. $7.5 \div 6$ c. $55.6 \div 8$

6. Calculate the following by changing the position of the decimal point.
   a. $14.07 \div 10$ b. $968.13 \div 100$ c. $620.8 \div 1000$
   d. $3592.87 \div 1000$ e. $2349.78 \div 100\,000$

7. Calculate the following by changing the position of the decimal point.
   a. $9.0769 \div 100\,000$ b. $802\,405.6 \div 1\,000\,000$ c. $152.70 \div 1\,000\,000$
   d. $0.7205 \div 10\,000$ e. $0.0032 \div 1\,000\,000$

8. WE25 Calculate the following.
   a. $15.9 \div 60$ b. $23.7 \div 30$ c. $238 \div 400$ d. $8.79 \div 6000$ e. $5.22 \div 3000$

9. WE26a Calculate each of the following.
   a. $2.5 \div 0.5$ b. $4.2 \div 0.6$ c. $8.1 \div 0.9$ d. $2.8 \div 0.7$ e. $0.248 \div 0.8$

10. Calculate each of the following.
    a. $1.32 \div 0.6$ b. $39.6 \div 0.6$ c. $57.68 \div 0.8$ d. $0.2556 \div 0.3$ e. $0.5468 \div 0.4$

11. WE26b Calculate:
    a. $172.0488 \div 0.11$ b. $0.510\,48 \div 0.12$ c. $21.470\,10 \div 0.15$

12. Calculate:
    a. $142.888 \div 0.08$ b. $0.028\,692 \div 0.06$ c. $32.619 \div 0.02$

Understanding

13. MC To calculate $9.84 \div 0.8$, it can be rewritten as:
    A. $9.84 \div 8$ B. $0.984 \div 0.8$ C. $98.4 \div 0.8$ D. $98.4 \div 8$ E. $984 \div 8$

14. MC To calculate $151.368 \div 1.32$, it can be rewritten as:
    A. $151.368 \div 132$ B. $151.368 \div 13.2$ C. $1513.68 \div 132$ D. $15\,136.8 \div 132$ E. $151\,368 \div 132$

15. MC $0.294 \div 0.7$ equals:
    A. 0.042 B. 0.42 C. 4.2 D. 42 E. 420

16. MC $21.195 \div 0.15$ equals:
    A. 0.1413 B. 1.413 C. 14.13 D. 141.3 E. 1413

17. For the following calculations:
    i. Estimate the answer by rounding each number to the first digit.
    ii. Calculate the answers by using written methods.
    iii. Check your answer by using a calculator.
    a. $6600 \div 24$ b. $1044 \div 4.5$ c. $384 \div 0.16$

18. Change the following to dollars ($) by dividing by 100.

a. 365 cents **b.** 170 cents **c.** 5685 cents
d. 75 cents **e.** 90 cents **f.** 6350 cents

19. Calculate $100\,987.5412 \div 10^4$.
Round the answer to the nearest hundredth.

Reasoning

20. The carat is a unit of measure used to weigh precious stones. A 2.9-carat diamond weighs 8.9494 grains. Calculate how many grains one carat is equal to.

21. You are helping to beautify the gardens at your school and have been given the responsibility for paving the path. The path is 6.715 m (or 671.5 cm) long and the width of only two pavers. The pavers you will use are shown at right.



a. Calculate how many pavers you should buy to minimise waste.
b. If each paver costs $2.32, calculate how much the pavers cost in total.

22. A jug is $\frac{1}{5}$ full of water. Jack added more water to the jug until it was $\frac{3}{4}$ full. At that stage there was 1.5 L of water in the jug. Show with working how much water was originally in the jug.

Problem solving

23. Stephanie spent $6.95 on these chocolates. Determine the cost of each chocolate. Give your answer to the nearest 5 cents.



24. WE27 Calculate how many 1.25-litre bottles of water could be poured into a 25-litre drink dispenser.

25. Calculate how many burgers could be bought for $562.80 if each burger costs $2.80.

26. If you have $22.50 for bus fares to school for the week, calculate how much you would spend on each of the 5 days.

27. The area of an office floor is 85.8 square metres. Calculate how many people could fit in the office if each person takes up 1.2 square metres.

28. Emily wants to make 10 cushions from 6.75 metres of material that she found on a table of remnants at a fabric shop. Determine how much material she would have for each cushion.

29. Calculate how many books can be stacked on a shelf that is 28.6 centimetres high if each book is 1.1 centimetres high.



30. Anna has a wooden rod that is 2.4 metres long. She needs to cut 3 lengths, each of 0.4 metres, and 2 lengths, each of 0.2 metres. Determine the fraction of the original rod left over after she has cut the required lengths.

6.8 Decimals and percentages

LEARNING INTENTION

At the end of this subtopic you should be able to:

- convert percentages to fractions.

6.8.1 Percentages as decimals

eles-3957

- Percentages can be expressed as decimals.
- To convert a percentage to a decimal, divide the percentage by 100; that is, move the decimal point 2 spaces to the left.

WORKED EXAMPLE 28 Converting percentages to decimals

Write the following percentages as decimals.

a. **81**%

b. **16.8**%

THINK

a. 1. To convert to a decimal, divide by 100.

2. Move the position of the decimal point 2 places to the left and place a zero in the units column.

b. 1. To convert to a decimal divide by 100.

2. Move the position of the decimal point 2 places to the left and place a zero in the units column.

WRITE

a. $81\% = 81 \div 100$

$$= \frac{81}{100}$$

$$= 0.81$$

b. $16.8\% = 16.8 \div 100$

$$= \frac{16.8}{100}$$

$$= 0.168$$

on Resources

eWorkbook Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)

Interactivities Individual pathway interactivity: Percentages as decimals (int-4344)

Percentages as decimals (int-3993)

Exercise 6.8 Decimals and percentages

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 8, 10, 12, 15, 18, 21	2, 5, 7, 13, 16, 19, 22	3, 6, 9, 11, 14, 17, 20, 23, 24

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE28a Write the following percentages as decimals.
   a. 36% b. 14% c. 28% d. 73% e. 66%
2. Write the following percentages as decimals.
   a. 59% b. 99% c. 9% d. 4% e. 1%
3. Write the following percentages as decimals.
   a. 25% b. 200% c. 150% d. 360% e. 100%
4. WE28b Write the following percentages as decimals.
   a. 12.3% b. 31.6% c. 59.2% d. 84.9% e. 42.1%
5. Write the following percentages as decimals.
   a. 37.6% b. 21.9% c. 16.9% d. 11.1% e. 3.1%
6. Write the following percentages as decimals.
   a. 9.2% b. 5.9% c. 8.8% d. 14.25% e. 31.75%
7. Write the following percentages as decimals.
   a. 23.55% b. 45.75% c. 0.05% d. 4.01% e. 0.02%

Understanding

8. MC 41% as a decimal is:
   A. 41 B. 0.41 C. 4.100 D. 4.1 E. 0.041
9. MC 8% as a decimal is:
   A. 8 B. 0.008 C. 0.08 D. 0.8 E. 800
10. MC 43.64% as a decimal is:
    A. 0.4364 B. 4.364 C. 43.6400 D. 436.4 E. 4364.0
11. MC 110% as a decimal is:
    A. $\frac{110}{100}$ B. 1100 C. 0.11 D. 1.10 E. 11.0
12. Car prices dropped by 17% during a recent 8-year period. Write this percentage as a:
    a. fraction
    b. decimal.
13. The maximum legal blood alcohol concentration (BAC) for drivers in New South Wales is 0.05%. Write the BAC as a:
    a. fraction
    b. decimal.



14. In 2020, the number of visitors to Australia was 80.7% lower than the previous year. Write this percentage as a decimal.

15. Over the past decade, insurance premiums have risen by 218%. Write this percentage as a decimal.

16. In the three months following a drought, the price of vegetables fell by 13.8%. Write this percentage as a decimal.

17. Government funding to state schools has risen by 8.35%. Write this percentage as a decimal.



Reasoning

18. **a.** Round the following percentages to the nearest whole number: 23.2%, 23.5%, 23.8%, 23.9%
b. Round the following decimal numbers to 2 decimal places: 0.232, 0.235, 0.238, 0.239
c. The percentages in part **a** are the same as the decimal numbers in part **b**. Explain whether it matters if you round the percentages or the decimal values up or down.

19. Consider the following percentages: 23.6%, $23.\dot{6}7\%$, 23.66%

a. Which one of the three percentages is the largest? Justify your answer.
b. Convert these percentages to decimals. State your answer to 4 decimal places.

20. Consider the following percentages: 37.8%, 39.6%, 30.9%, 34.5%, 32.8%

a. Convert these numbers to decimals.
b. Arrange the percentages in order from highest to lowest.
c. Arrange the decimal numbers in order from highest to lowest.
d. Explain whether it was easier to arrange the numbers in the order required using decimals or percentages.

Problem solving

21. Brent buys a used car for $7500. The dealer requires a 15% deposit. Calculate the value of the deposit he must pay the dealer.

22. The price of entry into a theme park has increased by 10% every year since the theme park opened.
If the latest price rise increased the ticket price to $8.80, determine the cost of a ticket 2 years ago.



23. Consider the following percentages:
7.291%, 72.91%, 729.1%.

a. Convert the following percentages to decimal numbers.
i. 7.291% **ii.** 72.91% **iii.** 729.1%
b. Explain the effect of the conversion on the numbers.

24. Suggest when it is more convenient to express a percentage as a decimal rather than as a fraction.

6.9 Review

6.9.1 Topic summary

Decimal numbers and place value

- Decimal numbers can be identified easily because the whole number part and the fractional part are separated by a decimal point (.).

  e.g. 11.234 is a decimal number.
- Decimal numbers can also be written in expanded form.

  e.g. $11.234 = 11 + \frac{2}{10} + \frac{3}{100} + \frac{4}{1000}$

Rounding decimals

When rounding decimal numbers, follow the steps below.

1. Decide which digit is the last digit to keep (underline it).
2. Leave this underlined digit the same if the **next digit** is 0, 1, 2, 3 or 4 (this is called rounding down).
- Increase the underlined digit by 1 if the **next digit** is 5, 6, 7, 8 or 9 (this is called rounding up).

e.g. 2.3456 = 2.3 correct to 1 decimal place.

2.3456 = 2.35 correct to 2 decimal places.

Types of decimals

- **Terminating (finite) decimals** are decimal numbers that finish (terminate).

  e.g. $\frac{3}{8} = 0.375$
- **Recurring (repeating) decimals** are decimal numbers that keep on going forever and never finish.

  e.g. $\frac{1}{3} = 0.3333333\ldots = 0.\dot{3}$

  (The 3 never stops.)

  $\frac{5}{11} = 0.45454545\ldots = 0.\overline{45}$

  (The 45 pattern continues forever.)

DECIMALS



Addition and subtraction

- To add or subtract decimal numbers, set the problem out in columns according to place value and make sure the decimal points are aligned.
- Add and subtract using the same method as for whole numbers.

e.g. Calculate 1.23 + 7.894.

$$\begin{array}{r} 1.230 \\ +\ 7.894 \\ \hline 9.124 \end{array}$$

Division by a whole number

- When dividing a decimal number by a whole number, use the same method as for division with whole numbers.

  e.g. $5\overline{)10.375}$ 2.075

Multiplying decimal numbers

- To multiply decimal numbers, use the method for multiplying whole numbers.
- To know where to place the decimal point in the answer, *count the total number of decimal places in the entire question.*
- The answer must have the same number of decimal places as your count.

Dividing decimal numbers

- When dividing by a decimal number, convert the denominator to a whole number by multiplying by a power of 10.
  (Put simply, just move the decimal point to the right as many places as needed to make the denominator a whole number.)
- Multiply the numerator by the same power of 10 as the denominator to keep it balanced.
  (Move the decimal point in the numerator exactly the same number of places to the right as you did in the denominator.)
- Divide as normal.

e.g. Calculate $\frac{0.135}{0.5}$.

To make the denominator a whole number, multiply it by 10 (or move the decimal point one place to the right). Do the same to the numerator.

$\frac{0.135}{0.5} = \frac{1.35}{5} = 0.27$

Multiplying by powers of 10

- Count the number of zeros in the power of 10 being multiplied.
  e.g. 1000 has three zeros.
- Move the decimal point to the *right* by the same number.

e.g. 23.4567 × 1000 = 23456.7

(1000 has three zeros, so move the decimal point three places to the right.)

Dividing by powers of 10

- Count the number of zeros in the power of 10 being divided.
  e.g. 100 has two zeros.
- Move the decimal point to the *left* by the same number.

e.g. 23.4567 ÷ 100 = 0.234567

(100 has two zeros, so move the decimal point two places to the left.)

Converting percentages to decimal

- To convert a percentage to a fraction or a decimal, simply divide by 100 and remove the percentage symbol.

e.g. Express 54% as a decimal. number

54% = 54 ÷ 100
= 0.54

(Follow the rules for dividing by powers of 10; that is, move the decimal point two places to the left.)

6.9.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
6.2	I can understand the place value of digits in decimal numbers.			
	I can the value of digits in decimal numbers.			
	I can compare the sizes of decimal numbers.			
6.3	I can convert decimals to fractions and fractions to decimals.			
6.4	I can round decimal numbers to the required number of decimal places.			
6.5	I can add and subtract decimal numbers.			
6.6	I can multiply decimals, including by multiples of 10.			
	I can square decimal numbers.			
6.7	I can divide a decimal number by a whole number or a decimal number.			
	I can divide a decimal number by a multiple of 10.			
6.8	I can convert percentages to fractions.			

6.9.3 Project

Eating out

When we eat out or buy takeaway food, a number of factors are taken into consideration before we make our purchases. What types of foods are available? What is the size of each serving? What is the cost of the meal? These are examples of things we consider when we try to decide what and where we eat.

In a group of four, you and your friends have decided to eat at a local restaurant. Your parents have given each of you $30.00 to spend on your meal.



EAT EASY RESTAURANT MENU

SALADS

Tossed Green Salad	$5.50
Caesar Salad	$7.50
Chicken Caesar Salad	$8.95
Greens with Tomato	$6.50

STARTERS

Garlic or Herb Bread	$3.50
Bruschetta	$4.50
Dips & Bread	$3.50
Potato Skins – served with sour cream	$6.50
Basket of fries	$4.25
Nachos with cheese, salsa and sour cream	$6.50
Italian style baby potatoes	$6.50

SANDWICHES

All served with salad and fries on your choice of bread

Bacon, Lettuce & Tomato	$5.50
Ham & Cheese	$5.00
Ham, Cheese & Tomato	$5.50
Grilled Chicken & Cheese	$6.00
Egg & Lettuce	$5.50
Top Quality Steak & Onions	$9.95

BURGERS AND HOT DOGS

All served with salad and fries

Jumbo Hot Dog	$5.95
Gourmet Dog – includes smoked sausage	$6.95
Double Beef Burger	$5.95
Grilled Chicken Burger	$6.95
Fresh Fish Burger	$7.55
Vegetable Burger	$4.95

Additional items

Bacon	$0.50
Grilled onion	$0.50
Olives	$0.75
Cheddar	$0.75

HOUSE SPECIAL

Today's Special is 250 gram Rib Eye Steak served with fries, vegetables with your choice of sauce	$18.95

PASTA

Your choice of Spaghetti, Fettuccine, Gnocchi, Ravioli or Tagliatelle with the sauces below

Mama's Meaty Bolognaise	$9.95
Creamy Chicken	$9.95
Fresh Seafood Marinara	$10.95
Pesto	$9.95
Tomato and Hot Chilli	$8.95
Vegetable Lasagne	$9.95
Rich and Meaty Lasagne	$9.95

DESSERTS

Homemade Fruit Pie	$3.75
Brownie	$3.50
Cheesecake	$3.95
Frozen Yoghurt – Chocolate or Vanilla	$2.50
Jumbo Banana Split	$4.50

1. Using the menu provided, work out how much each of the following meals would cost. On a separate piece of paper, set out each order as it would appear on the final bill. An example is shown at right.
   - **a.** Tossed green salad and Homemade fruit pies.
   - **b.** Chicken Caesar salad, Jumbo hot dog and Vanilla-flavoured yoghurt.
   - **c.** Garlic bread, Potato skins, House special and Jumbo banana split.
   - **d.** Vegetable burger with cheddar, Basket of fries and Brownie.

EAT EASY RESTAURANT

Item	Cost
Tossed green salad	$5.50
Homemade fruit pies	$3.75
Total	$9.25

Your group has decided to order a three-course meal. The first course consists of items from the Salads and Starters sections and the third course is from the Desserts section. The second course is ordered from the remaining sections.

The group also decides to buy a large jug of orange juice to drink, and plans to share its cost of $4.60 evenly.

2. Calculate your share of the cost of the drinks.
3. How much does this leave you to spend on your food order?
4. Select your three-course meal, keeping in mind the amount of money you have to spend. Write down your order, and set it out as you did for question **1**.

Obtain the orders from three of your classmates. This will represent your group of four.

5. Write down each group member's order on a separate sheet of paper. Present the information as you would like it to appear on your final bill. Include the total cost of each person's order.
6. Calculate how much change each group member received from their $30.
7. Imagine that the restaurant's final bill for your group showed only the total amount owing; that is, there was no information on the breakdown of charges. Comment on how you would feel about this and how you think bills should be presented for group bookings.





Resources

eWorkbook Topic 6 Workbook (worksheets, code puzzle and project) (ewbk-1907)

Interactivities Crossword (int-2594)
Sudoku puzzle (int-3167)

Exercise 6.9 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Give the value of the 7 in each of the following.
   a. 1.719 b. 3.0726 c. 0.2078

2. Give the vaue of the 7 in each of the following.
   a. 23.1487 b. 0.002 57 c. 17.592

3. Write the following numbers in expanded notation.
   a. 2.64 b. 18.406 c. 96.3428

4. Add 2 tenths to the following.
   a. 6.2 b. 0.743 c. 3.91

5. Add 3 thousandths to the following.
   a. 0.456 b. 1.6 c. 2.79

6. Put < or > between the following.
   a. 8.72 8.27 b. 0.35 0.37 c. 10.214 10.219

7. Put < or > between the following.
a. 13.0496 13.149 **b.** 0.804 06 0.804 17 **c.** 0.000 879 0.000 876

8. Write the following decimals in order from smallest to largest.
a. 0.13, 0.86, 0.34, 0.71, 0.22 **b.** 0.247, 0.274, 0.124, 0.258, 0.285

9. Write the following decimals in order from smallest to largest.
a. 0.834, 0.826, 0.859, 0.888, 0.891 **b.** 0.356, 0.358, 0.365, 0.385, 0.217

10. Write the following decimals as fractions in simplest form.
a. 0.8 **b.** 0.17 **c.** 0.36 **d.** 0.187

11. Write the following decimals as fractions in simplest form.
a. 0.125 **b.** 0.568 **c.** 0.205 **d.** 0.950

12. Write the following decimals as mixed numerals in simplest form.
a. 1.5 **b.** 4.60 **c.** 3.48 **d.** 5.25

13. Write the following decimals as mixed numerals in simplest form.
a. 2.75 **b.** 2.625 **c.** 1.56 **d.** 8.32

14. Round the following to 2 decimal places.
a. 2.047 **b.** 13.8649 **c.** 17.898 193

15. Round the following to the number of decimal places indicated in the brackets.
a. 1.29 (1) **b.** 0.0482 (3) **c.** 1.925 96 (4)

16. Round the following to the nearest whole number.
a. 13.6 **b.** 29.02 **c.** 86.99 **d.** 100.09

17. Calculate the following.
a. $1.8 + 7.3$ **b.** $4.21 + 5.88$ **c.** $6.75 + 0.243$

18. Calculate the following.
a. $12.047 + 3.6$ **b.** $194 + 18.62 + 3.1$ **c.** $34.1 + 7.629 + 0.008\,45$

19. Calculate the following.
a. $9.6 - 4.3$ **b.** $18.25 - 9.18$ **c.** $3.92 - 1.88$

20. Calculate the following.
a. $100 - 9.341$ **b.** $4.876 - 3.927$ **c.** $1.6 - 0.025$

21. Calculate the following.
a. 6.2×3 **b.** 4.67×9 **c.** 13.2036×5 **d.** 0.7642×7

22. Calculate the following.
a. 0.23×11 **b.** 16.28×41 **c.** 182.94×28 **d.** $0.028\,94 \times 32$

23. Calculate the following.
a. 0.26×10 **b.** 1.345×10 **c.** 0.0645×100 **d.** 1.8294×100

24. Calculate the following.
a. 146.6281×100 **b.** $0.048\,064\,3 \times 1000$ **c.** $0.839\,204 \times 1000$ **d.** 0.368×1000

25. Calculate the following.
a. 3.2×0.41 **b.** 1.72×0.3 **c.** 0.87×0.9 **d.** 0.03×0.006

26. Calculate the following.
a. 0.58×1.5 **b.** 2.83×0.96 **c.** 11.468×1.3 **d.** 1.248×0.82

27. Calculate each of the following.
a. 2.5^2 **b.** 0.03^2 **c.** 0.64^2 **d.** 0.0025^2

28. Calculate each of the following.
a. $1.64 \div 4$ **b.** $12.48 \div 6$ **c.** $147.24 \div 2$ **d.** $1.76 \div 11$

29. Calculate each of the following.
a. $14.623 \div 10$ **b.** $102.36 \div 10$ **c.** $9612.347 \div 1000$

30. Calculate each of the following.
a. $20.032 \div 100$ **b.** $264\,983.0026 \div 1000$ **c.** $3462.94 \div 100$

31. Write each of these fractions as a terminating decimal or as an infinite recurring decimal.
a. $\frac{1}{20}$ **b.** $\frac{5}{8}$ **c.** $\frac{5}{16}$ **d.** $\frac{2}{16}$

32. Write these infinite recurring decimals using a short form.
a. 4.555 ... **b.** 0.8282 ... **c.** 19.278 127 81 ... **d.** 83.016 262 62 ...

33. Calculate the following.
a. $4.8 \div 0.6$ **b.** $35.7 \div 0.7$ **c.** $12.1 \div 1.1$ **d.** $13.72 \div 0.4$

34. Calculate the following.
a. $17.8946 \div 0.02$ **b.** $372.045\,72 \div 0.06$ **c.** $0.289\,56 \div 0.12$ **d.** $3214.0170 \div 0.15$

35. Write the following percentages as decimals.
a. 42% **b.** 5% **c.** 94% **d.** 139%

36. Write the following percentages as decimals.
a. 6.7% **b.** 19.7% **c.** 58.03% **d.** 0.8%

37. Calculate the following percentages by converting the percentage to a decimal.
a. 20% of 25 **b.** 12% of 31 **c.** 4.5% of 50 **d.** 9.2% of 75

38. Calculate the following percentages by converting the percentage to a decimal.
a. 21.4% of 90 **b.** 32.3% of 120 **c.** 76.5% of 8 **d.** 42.3% of 96.2

Problem solving



39. Jim saved the following amounts of pocket money to take away on holiday: $12.50, $15.00, $9.30, $5.70 and $10.80.
Calculate how much money Jim had to spend while on holiday.

40. Mandie poured 0.375 litres from a 1.5-litre bottle of juice. Calculate how much juice was left in the bottle.

41. Tara bought 0.350 kilograms of shaved ham at $10.50 per kilogram. Calculate how much Tara paid for the ham.

42. The decimal equivalent of $\frac{3}{13}$ is $0.\overline{230\,769}$.

a. Determine the decimal equivalent of $\frac{1}{13}$.

b. Determine the decimal equivalent of $\frac{5}{13}$.

43. Lena saved $32 when she purchased a pair of jeans at a sale. If the sale had 40% marked off any item, calculate the original price for the pair of jeans.

44. You are given two options at work:
Option 1: Your salary can be raised by 10% this month and then reduced by 10% next month.
Option 2: Your salary will be reduced by 10% this month and increased by 10% next month.
Compare the two options to determine which is the better option.

45. Leesa has 3 m of ribbon. It takes 0.15 m of ribbon to make a bow. Calculate how many bows she can make with the ribbon.

46. Steven lives $\frac{3}{4}$ km from school. He can walk at 6.25 km/h. Determine how long it takes him to walk to school.



on To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1907) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0695) ☐

Digital documents

6.2 SkillSHEET Writing decimals (doc-6458) ☐
SkillSHEET Comparing decimals (doc-6459) ☐
6.4 SkillSHEET Rounding to the nearest whole number (doc-6476) ☐
6.5 SkillSHEET Adding decimals (same number of decimal places) (doc-6461) ☐
SkillSHEET Adding decimals (different number of decimal places) (doc-6462) ☐
SkillSHEET Subtracting decimals (same number of decimal places) (doc-6463) ☐
SkillSHEET Subtracting decimals (different number of decimal places) (doc-6464) ☐
6.6 SkillSHEET Multiplying decimals by a single-digit number (doc-6465) ☐
SkillSHEET Multiplying decimals by 10, 100, 1000 (doc-6466) ☐
6.7 SkillSHEET Dividing decimals by a single-digit number (doc-6467) ☐
SkillSHEET Dividing decimals by 10, 100, 1000 (doc-6468) ☐

Video eLessons

6.2 Whole numbers and decimal parts (eles-3940) ☐
Comparing decimals (eles-3941) ☐
6.3 Converting decimals to fractions (eles-3943) ☐
Converting fractions to decimals (eles-3944) ☐
6.4 Rounding (eles-3945) ☐
Rounding to the nearest 5 cents (eles-3946) ☐
Repeating decimals (eles-3947) ☐
6.5 Adding decimals (eles-3948) ☐
Subtracting decimals (eles-3949) ☐
6.6 Multiplying decimals (eles-3950) ☐
Squaring decimals (eles-3951) ☐
Multiplying by multiples of 10 (eles-3952) ☐
Multiplication of decimals (eles-2311) ☐
6.7 Dividing a decimal by a whole number (eles-3954) ☐
Dividing a decimal number by a multiple of 10 (eles-3955) ☐
Dividing a decimal number by another decimal number (eles-3956) ☐
Division of decimals (eles-1877) ☐
6.8 Percentages as decimals (eles-3957) ☐

Interactivities

6.2 Individual pathway interactivity: Place value and comparing decimals (int-4337) ☐
Whole numbers (int-3974) ☐
Decimal parts (int-3975) ☐
Comparing decimals (int-3976) ☐
Comparing decimals using the area model (int-3977) ☐
6.3 Individual pathway interactivity: Converting decimals to fractions and fractions to decimals (int-4338) ☐
Conversion of decimals to fractions (int-3978) ☐
Conversion of fractions to decimals (int-3979) ☐
6.4 Individual pathway interactivity: Rounding and repeating decimals (int-4339) ☐
Rounding (int-3980) ☐
Repeating decimals (int-3981) ☐
6.5 Individual pathway interactivity: Adding and subtracting decimals (int-4340) ☐
Addition of decimals (int-3982) ☐
Subtraction of decimals (int-3984) ☐
Checking by estimating (int-3983) ☐
6.6 Individual pathway interactivity: Multiplying decimals (including by multiples of 10) (int-4341) ☐
Multiplication of decimals (int-3985) ☐
6.7 Individual pathway interactivity: Dividing decimals (including by multiples of 10) (int-4342) ☐
Division of decimals by a multiple of 10 (int-3990) ☐
Division of a decimal by another decimal (int-3991) ☐
6.8 Individual pathway interactivity: Percentages as decimals (int-4344) ☐
Percentages as decimals (int-3993) ☐
6.9 Crossword (int-2594) ☐
Sudoku puzzle (int-3167) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers

Topic 6 Decimals

Exercise 6.1 Pre-test

1. C
2. 0.12
3. E
4. Josh
5. 23.90
6. $378.95
7. E
8. 5.817
9. C
10. 3280
11. $28.05
12. $13.65
13. 86.98
14. 44 litres
15. 125

Exercise 6.2 Decimals and place value

1. a. $\frac{2}{10}$ b. $\frac{2}{100}$ c. $\frac{2}{10}$ d. $\frac{2}{1000}$
2. a. $\frac{2}{10\,000}$ b. $\frac{2}{10\,000}$ c. 2 d. $\frac{2}{10\,000}$
3. a. $\frac{9}{10}$ b. $\frac{9}{10}$ c. $\frac{9}{100}$ d. $\frac{9}{100}$
4. a. $\frac{9}{10\,000}$ b. $\frac{9}{100\,000}$ c. 900 d. 9
5. a. $\frac{4}{10}$ b. $2+\frac{7}{10}$
   c. $5+\frac{2}{10}+\frac{3}{100}$ d. $\frac{7}{10}+\frac{6}{100}+\frac{3}{1000}$
6. a. $\frac{1}{10}+\frac{1}{100}+\frac{1}{10\,000}$
   b. $7+\frac{2}{10}+\frac{9}{100}+\frac{6}{1000}+\frac{4}{10\,000}$
   c. $\frac{3}{10}+\frac{3}{100}+\frac{2}{10\,000}+\frac{4}{100\,000}$
   d. $300+\frac{3}{100}$
7. a. One unit, 1; eight tenths, $\frac{8}{10}$; five hundredths, $\frac{5}{100}$; $1+\frac{8}{10}+\frac{5}{100}$
   b. Two tenths, $\frac{2}{10}$; seven hundredths, $\frac{7}{100}$; one thousandth, $\frac{1}{1000}$; $\frac{2}{10}+\frac{7}{100}+\frac{1}{1000}$
   c. One ten, 10; six units, 6; one thousandth, $\frac{1}{1000}$; $16+\frac{1}{1000}$
   d. Three units, 3; four tenths, $\frac{4}{10}$; two thousandths, $\frac{2}{1000}$; seven hundred thousandths, $\frac{7}{100\,000}$; $3+\frac{4}{10}+\frac{2}{1000}+\frac{7}{100\,000}$
8. a. $(1\times 1)+\left(2\times\frac{1}{10}\right)+\left(5\times\frac{1}{100}\right)$
   b. $(5\times 10)+(6\times 1)+\left(1\times\frac{1}{100}\right)$
   c. $(3\times 10)+(9\times 1)+\left(1\times\frac{1}{100}\right)$
   d. $(5\times 1)+\left(9\times\frac{1}{10}\right)+\left(8\times\frac{1}{100}\right)+\left(7\times\frac{1}{1000}\right)$
9. a. $(1\times 10)+(3\times 1)+\left(4\times\frac{1}{10}\right)+\left(8\times\frac{1}{100}\right)+\left(2\times\frac{1}{1000}\right)$
   b. $\left(3\times\frac{1}{10}\right)+\left(6\times\frac{1}{1000}\right)+\left(2\times\frac{1}{10\,000}\right)$
   c. $\left(5\times\frac{1}{10}\right)+\left(2\times\frac{1}{10\,000}\right)$
   d. $(2\times 1)+\left(4\times\frac{1}{10}\right)+\left(7\times\frac{1}{100}\right)$
10. D
11. See the table at the foot of the page.*
12. a. 0.32 b. 0.59 c. 0.901
13. a. 0.039 90 b. 2.559 c. 0.110 49
14. a. > b. < c. < d. < e. <
15. a. > b. > c. < d. < e. >
16. a. 2
    b. i. Seventy-eight dollars and fifty-five cents
       ii. $78.55
17. a. 0.17, 0.21, 0.33, 0.39, 0.45
    b. 0.314, 0.391, 0.413, 0.420, 0.502
    c. 0.803, 0.807, 0.811, 0.821, 0.902
18. a. 0.9087, 0.9189, 0.9812, 0.9864, 0.9943
    b. 4.0292, 4.5097, 4.6031, 4.6249, 4.802
    c. 0.003, 0.004 65, 0.005 02, 0.0056, 0.009
19. a. 0.48, 0.39, 0.36, 0.31, 0.19
    b. 0.99, 0.97, 0.95, 0.91, 0.90
    c. 1.291, 1.288, 1.279, 1.273, 1.264

*11.

		Tens	Units		Tenths	Hundredths	Thousandths
a.	0.205	0	0	·	2	0	5
b.	1.06	0	1	·	0	6	0
c.	74.108	7	4	·	1	0	8
d.	0.108	0	0	·	1	0	8
e.	50.080	5	0	·	0	8	0

20. a. 0.390, 0.372, 0.318, 0.317, 0.309
    b. 0.8889, 0.8823, 0.8448, 0.8217, 0.8207
    c. 1.843 21, 1.702 96, 1.486 59, 1.486 13, 1.349 54
21. E
22. D
23. E
24. a. False b. True c. False
25. a. True b. False c. True
26. a. 0.142 857 142 9
    i. 0.285 714 285 7
    ii. 0.428 571 428 57
    iii. 0.571 428 571 4
    iv. 0.714 285 714 3
    v. 0.857 142 857 14
    b. Each number has a repeated group of decimals in the same sequence: 142 857.
27. a. i. Tenths ii. Yes
    b. i. Thousandths ii. No
    c. i. Units ii. No
    d. i. Units ii. Yes
    e. i. Tens ii. Yes
28. a. Shelley, 0.21 seconds
    b. Carolyn, 0.06 seconds
    c. Mara, 0.11 seconds
    d. Shelley, Carolyn, Robyn
    e. Carolyn, Shelley, Kyah
    f. Mara, Jenika, Shelley
    g. Yes, Shelley
29. 8.264
30. They are correct for trailing zeros (to the right) of a decimal. They are incorrect for zeros that are enclosed by non-zero digits, as they would indicate a place value of zero.

Exercise 6.3 Converting decimals to fractions and fractions to decimals

1. a. $\frac{3}{10}$ b. $\frac{1}{2}$ c. $\frac{21}{100}$ d. $\frac{2}{5}$ e. $\frac{11}{25}$
2. a. $\frac{49}{100}$ b. $\frac{251}{500}$ c. $\frac{617}{1000}$ d. $\frac{3}{10}$ e. $\frac{16}{25}$
3. a. $\frac{7}{25}$ b. $\frac{591}{625}$ c. $\frac{9209}{10\,000}$ d. $\frac{4621}{10\,000}$ e. $\frac{3}{25}$
4. a. $1\frac{3}{10}$ b. $2\frac{7}{10}$ c. $9\frac{2}{5}$ d. $1\frac{1}{5}$ e. $4\frac{1}{5}$
5. a. $8\frac{1}{2}$ b. $5\frac{27}{100}$ c. $19\frac{91}{500}$ d. $3\frac{3}{20}$ e. $6\frac{1}{4}$
6. a. $9\frac{7}{50}$ b. $16\frac{341}{500}$ c. $2\frac{4917}{10\,000}$ d. $4\frac{1693}{5000}$
   e. $100\frac{3}{625}$
7. B
8. A
9. C
10. D
11. E
12. a. 0.75 b. 0.5 c. 0.8 d. 0.05
13. a. 0.25 b. 0.02 c. 0.32 d. 0.2
14. a. 0.375 b. 0.875 c. 0.0625
15. a. Darya
    b. Compare the fraction of wins as decimals. Darya has a larger fraction of wins.
16. 300 m
16. No, the second jump was best.
18. History, Science, English
19. $\frac{4}{15}, \frac{3}{11}, \frac{30}{100}, \frac{8}{25}, \frac{325}{1000}, \frac{4}{12}, \frac{3}{7}$
20. $\frac{3}{7} = 0.\dot{4}28\,571$, $\frac{4}{7} = 0.\dot{5}71\,42\dot{8}$, $\frac{5}{7} = 0.\dot{7}14\,28\dot{5}$, $\frac{6}{7} = 0.\dot{8}57\,14\dot{2}$

Exercise 6.4 Rounding and repeating decimals

1. a. 0.32 b. 0.86 c. 1.25 d. 13.05 e. 3.04
2. a. 7.13 b. 100.81 c. 71.26 d. 0.01 e. 2.39
3. a. 0.19 b. 19.70 c. 0.40 d. 1.00 e. 8.90
4. a. 0.4 b. 0.9 c. 9.3 d. 25.3 e. 3.9
5. a. 300.1 b. 12.8 c. 99.9 d. 8.9 e. 14.0
6. a. 17.6 b. 0.9 c. 94.0 d. 1.0 e. 96.3
7. C
8. A
9. a. 11 b. 8 c. 4 d. 93 e. 112
10. a. 22 b. 42 c. 2138 d. 0 e. 1
11. a. $2.\dot{5}$ b. $0.\dot{6}$ c. $49.\dot{1}$ d. $0.\dot{2}\dot{6}$
12. a. $0.\dot{9}1\dot{3}$ b. $8.\dot{6}41\dot{8}$ c. $133.\overline{9462}$ d. $0.12\dot{7}$
13. a. 0.3 b. 0.1 c. 0.417
14. a. 0.17 b. 0.182 c. 0.47
15. A
16. A
17. a. 3.5 b. $4.\dot{6}$ c. 0.75
18. a. 10 b. 80 c. 140 d. 260 e. 180
19. a. 300 b. 200 c. 100 d. 6800 e. 9800
20. a. 3000 b. 12 000 c. 19 000 d. 9000 e. 1000
21. $27.70
22. $0.295, 0.2\dot{9}5\dot{}, 0.29\dot{5}, 0.2\dot{9}\dot{5}$
23. An example answer is 0.543216.
24. A more reasonable measurement would be 3.568 m. With the instruments we have available, it would not be possible to cut the timber more accurately.
25. Fred is incorrect; any number between 0.5 and 0.65 will round to 0.6.
26. 25°C
27. a. i. 0.8 ii. 0.84 iii. 0.838
    b. The rules are the same regardless of the number of decimals.
28. 50.0000, 33.3333, 20.0000, 14.2857, 9.0909, 7.6923, 5.8824, 5.2632, 4.3478, 3.4483

Exercise 6.5 Adding and subtracting decimals

1. a. 3.5 b. 2.69 c. 13.239 d. 102.1858
2. a. 6.77 b. 21.906 c. 2012.333 d. 261.449 06
3. a. 4.6 b. 6.9 c. 3.471 d. 17.28
4. a. 17.3271 b. 20.4329 c. 11.69 d. 105.22
5. a. 18.951 b. 105.958 c. 192.8949 d. 2618.9564
6. a. 0.60 b. 4.205 c. 0.0806 d. 1.3368
7. a. 5.02 b. 89.19 c. 87.09 d. 2.733
8. a. 3.34 b. 5.93 c. 0.327 d. 4.146
9. a. 1.934 b. 3.289 c. 14.5326 d. 16.766
10. a. 38.238 b. 4.1136 c. 0.1951 d. 0.772 16
11. B
12. A
13. A
14. D
15. C
16. B
17. B
18. B
19. $167.00
20. $4.70
21. 20.05 kilometres
22. 8.1 kilometres
23. $6.60
24. $10.35
25. 50.48 kilograms
26. 11.73 metres
27. 31.28 metres
28. 48.38 seconds
29. 0.107
30. When we estimate an answer we use rounding to make the numbers simple to calculate; for example, 11 may be rounded to 10.
31. 49 calls
32. a. See the table at the foot of the page.*
    b. Team 3
    c. 4.1 seconds
33. 65.53 g, 43.43 g, 32.03 g or 32.04 g
34. Increase 51c
35. One possible solution is $5.83 + 1.46 = 7.29$.

Exercise 6.6 Multiplying decimals

1. a. 14.0 b. 125.6 c. 61.2 d. 111.70
2. a. 190.26 b. 518.96 c. 6.384 d. 0.794 43
3. a. 0.84 b. 2.94 c. 0.32 d. 7.76
4. a. 0.140 b. 0.192 c. 0.385 d. 0.441
5. a. 4.304 b. 0.2082 c. 2.8992 d. 4.905 64
6. a. 0.0001 b. 0.000 012 c. 0.063 d. 0.000 222
7. a. 0.000 002 44 b. 0.000 36
   c. 0.392 d. 0.000 606 2
8. a. 0.3 b. 0.851 c. 2.538 d. 0.175
9. a. 6.557 b. 16.848 c. 60.300 d. 31.372
10. E
11. B
12. A
13. B
14. a. 0.0004 b. 1.69 c. 4.2025
15. a. 1016 b. 5973 c. 437 400
16. a. 1092 b. 4548 c. 38 340
17. a. 64.8 b. 1389.6 c. 270.8
    d. 217 148.96 e. 82 049.6783
18. a. 3 268 904.3267 b. 984 326.641
    c. 278.498 32 d. 460
19. a. i. 24 000 ii. 24 640
    b. i. 300 000 ii. 331 602
    c. i. 60 000 ii. 50 449.5
20. a. 3500 b. 12 700 c. 1100 d. 2535 e. 5820
21. $750
22. 108 L
23. 260.7569 m^2
24. a. $32.00 b. $32.05
25. The 50 extra sheets are 6 mm thick. You might notice the difference.
26. 13
27. $5.55
28. 0.375 L
29. Together they pay $6.30: Sophie pays $3.60 and Hamish pays $2.70.

Exercise 6.7 Dividing decimals

1. a. 0.6 b. 3.1 c. 0.54 d. 1.61 e. 2.42
2. a. 0.788 b. 1.147 c. 4.0701 d. 6.8594 e. 31.6176
3. a. 3.12 b. 2.231 c. 1.222 d. 6.421 e. 11.0311
4. a. 1.85 b. 4.75 c. 1.46
5. a. 2.45 b. 1.25 c. 6.95
6. a. 1.407 b. 9.6813 c. 0.6208
   d. 3.592 87 e. 0.023 497 8
7. a. 0.000 090 769 b. 0.802 405 6 c. 0.000 152 7

*32.

Team	1	2	3	4	5	6
Time (seconds)	153	159.3	148.9	166.6	155.9	155.8

d. 0.000 072 05 **e.** 0.000 000 0032

8. a. 0.265 **b.** 0.79 **c.** 0.595
d. 0.001 465 **e.** 0.001 74

9. a. 5 **b.** 7 **c.** 9 **d.** 4 **e.** 0.31

10. a. 2.2 **b.** 66 **c.** 72.1 **d.** 0.852 **e.** 1.367

11. a. 1564.08 **b.** 4.254 **c.** 143.134

12. a. 1786.1 **b.** 0.4782 **c.** 1630.95

13. D

14. D

15. B

16. D

17. a. **i.** 350 **ii.** 275
b. **i.** 200 **ii.** 232
c. **i.** 2000 **ii.** 2400

18. a. $3.65 **b.** $1.70 **c.** $56.85
d. $0.75 **e.** $0.90 **f.** $63.50

19. 10.10

20. 3.086 grains

21. a. 32 **b.** $74.24

22. 0.4 L

23. $0.60

24. 20

25. 201

26. $4.50

27. 71

28. 0.675 m

29. 26

30. $\frac{1}{3}$

Exercise 6.8 Decimals and percentages

1. a. 0.36 **b.** 0.14 **c.** 0.28 **d.** 0.73 **e.** 0.66

2. a. 0.59 **b.** 0.99 **c.** 0.09 **d.** 0.04 **e.** 0.01

3. a. 0.25 **b.** 2.00 **c.** 1.5 **d.** 3.6 **e.** 1

4. a. 0.123 **b.** 0.316 **c.** 0.592 **d.** 0.849 **e.** 0.421

5. a. 0.376 **b.** 0.219 **c.** 0.169 **d.** 0.111 **e.** 0.031

6. a. 0.092 **b.** 0.059 **c.** 0.088 **d.** 0.1425 **e.** 0.3175

7. a. 0.2355 **b.** 0.4575 **c.** 0.0005 **d.** 0.0401 **e.** 0.0002

8. B

9. C

10. A

11. D

12. a. $\frac{17}{100}$ **b.** 0.17

13. a. $\frac{1}{2000}$ **b.** 0.0005

14. 0.807

15. 2.18

16. 0.138

17. 0.807

18. a. 23, 24, 24, 24
b. 0.23, 0.24, 0.24, 0.24
c. It does not matter as long as both values are rounded up or down at the same digit.

19. a. 23.67%
b. 0.2360, 0.2367, 0.2366

20. a. 0.378, 0.396, 0.309, 0.345, 0.328
b. 39.6%, 37.8%, 34.5%, 32.8%, 30.9%
c. 0.396, 0.378, 0.345, 0.328, 0.309
d. Sample response: It is easier to arrange the numbers in the order using percentages as you can actually see the numbers and order them without any calculation. Decimals are more difficult to determine order, because there are more place values to look at.

21. $1125

22. $7.27

23. a. **i.** 0.072 91 **ii.** 0.7291 **iii.** 7.291
b. When converting a percentage to a decimal number, the number becomes 100 times smaller.

24. When dealing with measurements it is easier to use decimals rather than percentages or fractions.

Project

1. a. $9.25 **b.** $17.40 **c.** $33.45 **d.** $13.45

2. $1.15

3. $28.85

4. Sample response:

Item	Cost
Nachos with cheese, salsa and sour cream	$6.50
Vegetable burger	$4.95
Cheesecake	$3.95
Total	**$15.40**

5. Sample response:

Your order	
Item	**Cost**
Nachos with cheese, salsa and sour cream	$6.50
Vegetable burger	$4.95
Cheesecake	$3.95
Total	**$15.40**

Classmate 1	
Item	**Cost**
Chicken caesar salad	$8.95
Tomato and hot chilli pasta	$8.95
Brownie	$3.50
Total	**$21.40**

Classmate 2	
Item	**Cost**
Bruschetta	$4.50
Double beef burger with bacon	$6.45
Jumbo banana split	$4.50
Total	**$15.45**

Classmate 3	
Item	**Cost**
Garlic bread	$3.50
Rib eye steak	$18.95
Chocolate frozen yoghurt	$2.50
Total	**$24.95**

Item	Cost
Nachos with cheese, salsa and sour cream	$6.50
Chicken caesar salad	$8.95
Bruschetta	$4.50
Garlic bread	$3.50
Vegetable burger	$4.95
Tomato and hot chilli pasta	$8.95
Double beef burger with bacon	$6.45
Rib eye steak	$18.95
Cheesecake	$3.95
Brownie	$3.50
Jumbo banana split	$4.50
Chocolate frozen yoghurt	$2.50
Jug of orange juice	$4.60
Total	**$81.80**

6. Sample response:
You: $14.60
Classmate 1: $8.60
Classmate 2: $14.55
Classmate 3: $5.05

7. If the bill only showed the total amount and not the breakdown then it would be very difficult to work out how much each person owes individually. To counter this, the restaurant could use a bill similar to that shown in the answer to question **5** above.

Exercise 6.9 Review questions

1. **a.** 7 tenths **b.** 7 hundredths **c.** 7 thousandths

2. **a.** 7 ten thousandths
b. 7 hundred thousandths
c. 7 units

3. **a.** $(2\times 1)+\left(6\times\frac{1}{10}\right)+\left(4\times\frac{1}{100}\right)$
b. $(1\times 10)+(8\times 1)+\left(4\times\frac{1}{10}\right)+\left(6\times\frac{1}{1000}\right)$
c. $(9\times 10)+(6\times 1)+\left(3\times\frac{1}{10}\right)+\left(4\times\frac{1}{100}\right)+\left(2\times\frac{1}{1000}\right)+\left(8\times\frac{1}{10\,000}\right)$

4. **a.** 6.4 **b.** 0.943 **c.** 4.11

5. **a.** 0.459 **b.** 1.603 **c.** 2.793

6. **a.** > **b.** < **c.** <

7. **a.** < **b.** < **c.** >

8. **a.** 0.13, 0.22, 0.34, 0.71, 0.86
b. 0.124, 0.247, 0.258, 0.274, 0.285

9. **a.** 0.826, 0.834, 0.859, 0.888, 0.891
b. 0.217, 0.356, 0.358, 0.365, 0.385

10. **a.** $\frac{4}{5}$ **b.** $\frac{17}{100}$ **c.** $\frac{9}{25}$ **d.** $\frac{187}{1000}$

11. **a.** $\frac{1}{8}$ **b.** $\frac{71}{125}$ **c.** $\frac{41}{200}$ **d.** $\frac{19}{20}$

12. **a.** $1\frac{1}{2}$ **b.** $4\frac{3}{5}$ **c.** $3\frac{12}{25}$ **d.** $5\frac{1}{4}$

13. **a.** $2\frac{3}{4}$ **b.** $2\frac{5}{8}$ **c.** $1\frac{14}{25}$ **d.** $8\frac{8}{25}$

14. **a.** 2.05 **b.** 13.86 **c.** 17.90

15. **a.** 1.3 **b.** 0.048 **c.** 1.9260

16. **a.** 14 **b.** 29 **c.** 87 **d.** 100

17. **a.** 9.1 **b.** 10.09 **c.** 6.993

18. **a.** 15.647 **b.** 215.72 **c.** 41.737 45

19. **a.** 5.3 **b.** 9.07 **c.** 2.04

20. **a.** 90.659 **b.** 0.949 **c.** 1.575

21. **a.** 18.6 **b.** 42.03 **c.** 66.0180 **d.** 5.3494

22. **a.** 2.53 **b.** 667.48 **c.** 5122.32 **d.** 0.926 08

23. **a.** 2.6 **b.** 13.45 **c.** 6.45 **d.** 182.94

24. **a.** 14 662.81 **b.** 48.0643 **c.** 839.204 **d.** 368

25. **a.** 1.312 **b.** 0.516 **c.** 0.783 **d.** 0.000 18

26. **a.** 0.87 **b.** 2.7168 **c.** 14.9084 **d.** 1.023 36

27. **a.** 6.25 **b.** 0.0009 **c.** 0.4096 **d.** 0.000 006 25

28. **a.** 0.41 **b.** 2.08 **c.** 73.62 **d.** 0.16

29. **a.** 1.4623 **b.** 10.236 **c.** 9.612 347

30. **a.** 0.200 32 **b.** 264.983 002 6 **c.** 34.6294

31. **a.** 0.05 **b.** 0.625 **c.** 0.3125 **d.** 0.125

32. **a.** $4.\dot{5}$ **b.** $0.\overline{82}$ **c.** $19.\overline{2781}$ **d.** $83.01\dot{6}\dot{2}$

33. **a.** 8 **b.** 51 **c.** 11 **d.** 34.3

34. **a.** 894.73 **b.** 6200.762 **c.** 2.413 **d.** 21 426.78

35. **a.** 0.42 **b.** 0.05 **c.** 0.94 **d.** 1.39

36. **a.** 0.067 **b.** 0.197 **c.** 0.5803 **d.** 0.008

37. **a.** 5 **b.** 3.72 **c.** 2.25 **d.** 6.9

38. **a.** 19.26 **b.** 38.76 **c.** 6.12 **d.** 40.6926

39. $53.30

40. 1.125 L

41. $3.70 (rounded to nearest 5c) or $3.68

42. **a.** $0.\overline{076\,923}$ **b.** $0.\overline{384\,615}$

43. $80

44. No. Overall, after two months your salary will decrease by 1% using either option. However, option 1 gives an extra income (10% of the original salary) in the first month.

45. 20

46. 7 min 12s

7 Algebra

LEARNING SEQUENCE

7.1 Overview 350
7.2 Introduction to algebra 352
7.3 Substituting and evaluating 360
7.4 Simplifying expressions using like terms 364
7.5 Multiplying and dividing terms 369
7.6 Number laws 373
7.7 Expanding brackets (extending) 377
7.8 Review 381



7.1 Overview

Why learn this?



Algebra is a fundamental building block of mathematics. Algebra is, in fact, a mathematical language in which you are able to use the basic operations of addition, subtraction, multiplication and division. Using algebra, you are able to break down a problem or a puzzle into smaller parts and then find the solution or answer. Sometimes it is hard to imagine how we would apply algebra in our everyday lives, but we use algebra frequently without even realising it. The methods used to solve problems and the reasoning skills learned will be useful no matter what you do in life.

Every five years, on one particular night, every person in Australia completes a census form. The census collects information such as the number of people living at an address, their ages and their incomes. Statisticians use algebraic techniques to interpret the information, which can then be used in policymaking and to make predictions about future requirements for such things as schools, hospitals and aged care services. Scientists, architects, accountants and engineers all use algebra frequently in their work. Without algebra there would be no space travel, no electrical appliances, no television, no smartphones, no iPads, no computers and no computer games.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 7.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Given the pattern 8, 13, 18 …, the next three numbers are:
   A. 23, 28, 35 B. 23, 28, 33 C. 22, 26, 30 D. 22, 27, 32 E. 23, 29, 34

2. Calculate the value of q when the given substitution is made to the following formula: $q = 3p$ when $p = 8$.

3. In a tennis match, Charlie scored 12 more points than twice Lachlan's score. Lachlan scored 36 points. Calculate the number of points Charlie scored.



4. MC An expression that shows the difference between K and L, where K is bigger than L, is:
   A. $L - K$ B. $K \div L$ C. $2K$ D. $K + L$ E. $K - L$

5. Simplify the expression $3x + 2y - x + 4y$ by collecting like terms.

6. Simplify the expression $4(2x + 3y) + 4(3x - 2y)$.

7. Identify two consecutive numbers with a product of 420.

8. Explain what happens when the result of $(5k + 3)$ is doubled.

9. Complete the following: $3x + 7 - \square = 2 + \square - x$.

10. Simplify the following expressions.
    a. $3a \times 5b \times 2c$ b. $4ab \times 13b^2$ c. $\dfrac{15pq}{3p}$ d. $\dfrac{36mn}{6n^2}$

11. If $a = 2$, $b = 5$ and $c = 3$, determine the value of the following expression: $c(4a - b) - 3a$.

12. Expand and simplify the following expression: $3(7p - 4q) - 2(2p - 5q)$.

13. A rectangle has a width of $3x$ and a length of $5y$. Determine the simplest expression for the perimeter of the rectangle.

14. Is the expression $a \times a = 2a$ true or false? Justify your answer.

15. Ashton has 2 pairs of basketball shoes and 5 pairs of runners, and Alyssa has 1 pair of basketball shoes and 3 pairs of runners. Given b is the number of basketball shoes and r is the number of runners, determine the simplified expression that shows the total number of basketball shoes and runners they have together.



7.2 Introduction to algebra

LEARNING INTENTION

At the end of this subtopic you should be able to:
- understand the use of pronumerals in algebra
- identify algebraic terminology
- construct expressions from given information.

eles-3986

7.2.1 Pronumerals

- A **pronumeral** is a letter or symbol that is used to represent a number. For example, p could represent the number of pies in a shop.
- Any letter can be used as a pronumeral.
- A pronumeral can also be called a **variable**.

Using pronumerals

- Pronumerals are used to represent unknown quantities.
- For example, without knowing the number of fish in a pond, this number could be represented by the pronumeral f.

WORKED EXAMPLE 1 Use of pronumerals and constants

We don't know exactly how many lollies there are in a jar, but we know each jar has the same number. We will refer to this unknown number as l, where l is the pronumeral.
a. Draw a jar and label the number of lollies in the jar as l.
b. There is a jar of lollies plus one lolly. Represent this information using pictures and using symbols.

THINK

a. The number of lollies in the jar is unknown.

WRITE

Let l be the number of lollies in the jar.



l

b. Draw a jar of lollies and one lolly. Use 'l' in an algebraic expression to represent this information.




$l + 1$

7.2.2 Terms and expressions

eles-3987

- **Terms** can be numbers or pronumerals, or a combination of numbers and pronumerals multiplied together. For example, $2, p, 3x$ and $6xy$ are all terms.
- In terms that contain numbers and pronumerals multiplied together, the number is placed at the front and the multiplication signs are removed.
  For example, $2 \times a \times c$ would be simplified to $2ac$.
- Pronumerals in a term are written in alphabetical order.
  For example, $5 \times y \times x = 5xy$.
- The number in front of the pronumeral(s) is known as the **coefficient**. For example, in the term $3t$, the coefficient is 3.
- Terms such as $m \times m$ are expressed as m^2. Similarly, $m \times m \times m$ is expressed as m^3.
- Numbers without pronumerals are called **constant** terms.
- **Expressions** are mathematical sentences made up of terms separated by $+$ or $-$ signs.
  For example, $3m + 5$, $9 - 2t$ and $a^2 + 2ab + b^2$ are all expressions.
- The definitions for this section are summarised in the following diagram.



WORKED EXAMPLE 2 Writing terms and expressions

If Y represents any number, write terms or expressions for:

a. 5 times that number
b. 2 less than that number
c. 8 more than that number
d. the number divided by 4 (or the quotient of Y and 4)
e. the next consecutive number (that is, the counting number after Y).

THINK	WRITE
In each case think about which operations are being used and the order in which they occur.	
a. An expression with '5 times' means 'multiply by 5'. When multiplying, the multiplication sign is not shown. Remember to put the number first.	**a.** $5 \times Y = 5Y$
b. An expression with '2 less' means 'subtract 2'.	**b.** $Y - 2$
c. An expression with '8 more' means 'add 8'.	**c.** $Y + 8$
d. An expression with 'divided by 4' means 'write as a quotient (fraction)'.	**d.** $\frac{Y}{4}$
e. An expression with 'the next consecutive number' means 'add 1 to the number'.	**e.** $Y + 1$

WORKED EXAMPLE 3 Writing simple algebraic expressions

Suppose there are d dogs currently at a lost dogs' home.

a. If three dogs find homes, write an expression to represent the total number of dogs at the lost dogs' home.
b. Just after the three dogs find homes, the number of dogs at the lost dogs' home is doubled. Write an expression to represent the new number of dogs at the lost dogs' home.
c. The dogs are then sorted into 10 pens with the same number of dogs in each pen. Write another expression to represent the number of dogs in each pen.



THINK	WRITE
a. The original number of dogs (d) is decreased by three.	**a.** $d - 3$
b. The number of dogs left at the lost dogs' home is doubled.	**b.** $2 \times (d - 3)$
c. The dogs are divided into 10 pens.	**c.** $2 \times (d - 3) \div 10$ or $\frac{2d - 6}{10}$

WORKED EXAMPLE 4 Simplifying when terms or pronumerals are multiplied

If one jar of lollies has l lollies, then two jars of lollies will have double the number of lollies, that is $2 \times l = 2l$. In algebra, $2l$ means two lots of l, $3l$ means three lots of l, and so on.

a. There are two jars of lollies and three loose lollies. Each jar has the same number of lollies. Write an expression using symbols.

b. There are three jars of lollies, four packets of lollipops and four loose lollies. Each jar has the same number of lollies and each packet of lollipops has the same number of lollipops. Write an expression using symbols.

THINK

a. There are two jars of lollies (l) plus (+) the three that are loose.



b. There are three jars of lollies (l) and four packets of lollipops (p) plus (+) the four loose lollies.



WRITE

a. Let l be the number of lollies in the jar.

$2 \times l + 3 = 2l + 3$

b. Let l be the number of lollies in each jar and p be the number of lollipops in each packet.

$3 \times l + 4 \times p + 4 = 3l + 4p + 4$

COLLABORATIVE TASK: How many shoes?

You own a certain number of pairs of shoes. Your friend owns five pairs more than you own, and your sister owns three pairs fewer than you own. Your brother owns four pairs fewer than your friend owns.



1. Write an expression to individually represent each of the following.
   - **a.** The number of pairs of shoes you own
   - **b.** The number of pairs of shoes your friend owns
   - **c.** The number of pairs of shoes your sister owns
   - **d.** The number of pairs of shoes your brother owns
2. Share your answers with a partner. Discuss any differences between your answers.
3. As a class, discuss any differences that you found.
4. Does it matter if each student in the class uses a different symbol? Why? Why not?

on Resources

eWorkbook	Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)
Digital document	SkillSHEET Alternative expressions used to describe the four operations (doc-6502)
Interactivities	Individual pathway interactivity: Using variables (int-4429) Terms and expressions (int-4004)

Exercise 7.2 Introduction to algebra

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 4, 7, 11, 12, 13, 18, 19, 24, 25, 26, 28, 31	2, 5, 6, 8, 14, 15, 20, 21, 27, 29, 32	9, 10, 16, 17, 22, 23, 30, 33, 34

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. State what pronumerals are used for in algebra.
2. **WE1** If b represents the total number of bananas in a fruit bowl, write a short paragraph that could explain the following table.

Day	Number of bananas in the fruit bowl
Monday	b
Tuesday	$b-4$
Wednesday	$b-6$
Thursday	$b+8$
Friday	$b+5$

3. **WE2** Write an expression for the total number of coins in each of the following. The symbol  represents a full piggy bank and represents one coin. Use c to represent the number of coins in a full piggy bank.

a. 

b. 

c. 

d. 

4. Write an expression for the total number of coins in each of the following, using c to represent the number of coins in a piggy bank.

a. 

b. 


c. 

d. 


5. Christie and Jane each had two full piggy banks and seventeen coins. They combined their money and spent every cent on a day out in town.




Write an expression to represent the number of coins they had in total. Use c to represent the number of coins in a piggy bank.

6. Luke has three macadamia nut trees in his backyard. He saves takeaway containers to store the nuts in. He has two types of containers, rectangular  and round  .
Using m to represent the number of nuts in a rectangular container and n to represent the number of nuts in a round container, write expressions for the following.

a. 

b. 

c. 

d.  where ● represents one nut.

e. 

7. Using a and b to represent numbers, write an expression for:

a. the sum of a and b
b. the difference between a and b
c. the product of a and b
d. a multiplied by 3 and the result divided by b.

8. **WE3** Using a and b to represent numbers, write an expression for:

a. 15 divided by negative a
b. five times b subtracted from three times a
c. b divided by negative 5
d. seven less than a.

9. Write the following expressions in ascending order.

a. $m+3,\ m-2,\ m+1,\ m-8$
b. $n-15,\ n+25,\ n-10.3$

10. Write your own descriptions for what the following expressions could represent.

a. $d+2,\ d,\ d-1$
b. $t,\ 2t,\ t+1$
c. $y,\ 3y,\ 10y$

11. **WE4** Write an expression for each of the following.

a. The sum of B and 2
b. 3 less than T
c. 6 added to D
d. 5 taken away from K

12. Write an expression for each of the following.

a. The sum of G, N and W
b. D increased by H
c. N increased by N
d. H added to C

13. Write an expression for each of the following.

a. G subtracted from 12
b. The product of D and 4
c. B multiplied by F
d. Y added to the product of 3 and M

14. If A, B and C represent any 3 numbers, write an expression for each of the following.

a. The sum of all 3 numbers
b. The difference between A and C
c. The product of A and C
d. The product of all 3 numbers

15. If A, B and C represent any 3 numbers, write an expression for each of the following.


a. The quotient of B and C (that is, B divided by C)
b. The sum of A and C, divided by B
c. 3 more than A
d. The difference between C and the product of A and B

16. Write expressions for the following rules.

a. The number of students left in the class if X students leave for the canteen out of a total group of T students
b. The amount of money earned by selling B cakes, where each cake is sold for $4.00
c. The total number of sweets if there are G bags of sweets with 45 sweets in each bag
d. The cost of one concert ticket if 5 tickets cost $\$T$

Understanding

17. There are n mice in a cage. If the number of mice doubles each month, write an expression for the number of mice:



a. 1 month from now
b. 2 months from now
c. 3 months from now.

18. MC M is used to represent an unknown whole number. Choose the answer that matches the description 'six more than the number'.

A. $6 + M$ **B.** $6M$
C. $M - 6$ **D.** $M \div 6$
E. $6 - M$

19. MC M is used to represent an unknown whole number. Choose the answer that matches the description 'a fifth of the number'.

A. $5M$ **B.** $M - 5$ **C.** $\frac{M}{5}$ **D.** $M + \frac{1}{5}$ **E.** $\frac{1}{5} - M$

20. MC M is used to represent an unknown whole number. Choose the answer that matches the description 'the number just before that number'.

A. $M + 1$ **B.** $M - 1$ **C.** M **D.** $M + 2$ **E.** $M - 2$

21. MC M is used to represent an unknown whole number. Choose the answer that matches the description 'eight more than the product of that number and 10'.

A. $10\,(M + 8)$ **B.** $10M + 8$ **C.** $8M + 10$ **D.** $8\,(M + 10)$ **E.** $88M$

22. MC M is used to represent an unknown whole number. Choose the answer that matches the description 'five more than three times the number'.

A. $5M + 3$ **B.** $3M - 5$ **C.** $3M + 5$ **D.** $5M - 3$ **E.** $3(M-)$

23. Answer True or False for each of the statements below.

a. $3x$ is a term.
b. $3\,mn$ is a term.
c. $g = 23 - t$ is an expression.
d. $g = 5t - 6$ is an equation.

24. Answer True or False for each of the statements below.

a. $rt = r \times t$
b. $5 + A = A + 5$
c. $3d + 5$ is an expression.
d. $7 - B = B - 7$

25. Answer True or False for each of the statements below.

a. $3x = 9$ is an expression.
b. The expression $g + 2t$ has two terms.
c. $2f + 4 = 4 + 2f$
d. $5a - 7t + h$ is an equation.

26. There are a apples at your house. At your friend's house there are six more apples than there are at your house. Your friend uses eight apples to make an apple pie. Use this information to write an expression describing the number of apples at your friend's house:



a. before making the apple pie
b. after making the apple pie.

27. Your friend spends $\$d$ on a bus fare each day.




- **a.** If she uses the bus three days a week, state how much she spends on bus fares for the week.
- **b.** There are forty school weeks in a year and she travels three times a week on the bus. Write an expression for how much it will cost her for the bus fare each year.
- **c.** It costs an adult an extra \$1.50 for the same bus trip. Write an expression for the cost of an adult catching the bus three days per week.

Reasoning

28. Compare the expressions $\frac{x+1}{3}$ and $\frac{x}{3}+1$. Give possible examples for each expression.

29. Explain the difference between $y+y+y$ and $y \times y \times y$

30. p represents a number between 1 and 2 as shown:



Draw a number line for each of the following:

a. $p+1$ **b.** $p-2$ **c.** $3-p$

Problem solving

31.
- **a.** Ali earns \$7 more per week than Halit. If Halit earns $\$x$, write an expression for their total earnings per week.
- **b.** Sasha is twice as old as Kapila. If Kapila is x years old, write an expression for their total age.
- **c.** Frank has had 3 more birthdays than James. If James is $2x$ years old, write an expression for their total age.

32.
- **a.** Write a rule to describe how you would calculate the total cost of two hamburgers and one drink.
- **b.** Let h represent the cost of a hamburger. If the drink costs \$3.75 and the total costs \$7.25, write an equation that links all this information.



33. Two friends each had five \$1 coins and a piggy bank full of 20 c coins. They combined their money and spent it all at a games arcade. Assume that both friends had the same amount of money in their piggy banks.

- **a.** Write an expression for the total amount of money that the two friends had.
- **b.** If there were 85 coins in each piggy bank, calculate the total amount of money spent.



34. Ten couples go out for dinner. If everyone shakes hands once with everyone else except their partner, determine how many handshakes there are.

7.3 Substituting and evaluating

LEARNING INTENTION

At the end of this subtopic you should be able to:

- substitute a number for a pronumeral to evaluate an algebraic expression.

7.3.1 Substituting

eles-3988

- The value of an expression can be determined by substituting in values that are represented by the pronumeral.
- **Substitution** means replacing the pronumeral with the number it represents.
- Be careful when substituting into a term that contains a coefficient. You must remember that a coefficient is a number multiplied by the pronumeral.



WORKED EXAMPLE 5 Substituting into an expression

If $n = 3$, evaluate the following expressions.

a. $n + 4$ **b.** $2n$ **c.** $4n - 2$

THINK

a. 1. Substitute $n = 3$ into the expression.

2. Perform the addition and write the answer.

b. 1. Substitute $n = 3$ into the expression.

2. Perform the multiplication and write the answer.

c. 1. Substitute $n = 3$ into the expression.

2. Perform the multiplication first.

3. Perform the subtraction and write the answer.

WRITE

a. $n + 4 = 3 + 4$

$= 7$

b. $2n = 2 \times 3$

$= 6$

c. $4n - 2 = 4 \times 3 - 2$

$= 12 - 2$

$= 10$

WORKED EXAMPLE 6 Substituting to complete a table of values

If $x = 3t - 6$, determine the value of x by substituting the value of t given.

t	1	2	5	12
x				

THINK

1. Write the formula.
2. Substitute $t = 1$ into the formula.

WRITE

$x = 3t - 6$

$x = 3 \times 1 - 6$

3. Evaluate the right-hand side. $x = 3 - 6 = -3$

4. Substitute $t = 2$ into the formula. $x = 3 \times 2 - 6$

5. Evaluate the right-hand side. $x = 12 - 6 = 6$

6. Substitute $t = 5$ into the formula. $x = 3 \times 5 - 6$

7. Evaluate the right-hand side. $x = 15 - 6 = 9$

8. Substitute $t = 12$ into the formula. $x = 3 \times 12 - 6$

9. Evaluate the right-hand side. $x = 36 - 6 = 30$

10. Write the values of x.

t	1	2	5	12
x	−3	6	9	31

WORKED EXAMPLE 7 Substituting into a formula

When researching holiday destinations, Jack saw that the temperature in Hawaii was 88 °F. He uses the formula $C = \frac{5}{9}(F - 32)$ to convert this temperature to Celsius. Calculate the temperature in Hawaii in degrees Celsius.

THINK

1. Write the formula.

2. Substitute $F = 88$ into the equation.

3. Evaluate the right-hand side and write the answer.

WRITE


$C = \frac{5}{9}(F - 32)$

$C = \frac{5}{9}(88 - 32)$

$= 31.1°C$

Digital technology

Scientific calculators have a fraction button that can be used to compute calculations involving fractions.



WORKED EXAMPLE 8 Substituting into a formula

Calculate the value of m by substituting the given value of x into the following formula.

$$m = 3(2x + 3)$$
$$x = 4$$

THINK	WRITE
1. Write the formula.	$m = 3(2x + 3)$
2. Substitute $x = 4$ into the equation.	$m = 3(2 \times 4 + 3)$
3. Evaluate the right-hand side of the equation. Use BIDMAS to perform the operations in the correct order.	$m = 3(8 + 3)$ $m = 3(11)$ $m = 3 \times 11$ $m = 33$

Resources

- **eWorkbook** Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)
- **Video eLesson** Substitution (eles-2426)
- **Interactivities** Individual pathway interactivity: Substitution (int-4351)
  Substitution (int-4003)

Exercise 7.3 Substituting and evaluating

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 8, 12, 17, 20	2, 5, 9, 11, 13, 14, 18, 21	3, 6, 10, 15, 16, 19, 22

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE5 If $a = 4$, evaluate the following expressions.
   a. $a + 7$ b. $5a$ c. $2a - 10$ d. $3 + 3a$
2. If $b = 6$, evaluate the following expressions.
   a. $b - 7$ b. $11b$ c. $3b + 1$ d. $-8b + 7$
3. If $c = 3$, evaluate the following expressions.
   a. $c - 16$ b. $-4c$ c. $12 + 7c$ d. $11 - c$
4. WE6 Substitute the given values into each formula to determine the value of d if $d = g - 2$.
   a. $g = 4$ b. $g = 5$ c. $g = 2$ d. $g = 102$

5. Substitute the given values into each formula to determine the value of e if $e = 2t - 3$.
a. $t = 7$ **b.** $t = 2$ **c.** $t = 100$ **d.** $t = 8$

6. Substitute the given values into each formula to determine the value of f if $f = 12h + 7$.
a. $h = 1$ **b.** $h = 0$ **c.** $h = 5$ **d.** $h = 20$

7. Substitute the given values into each formula to determine the value of g if $g = 25 - 4w$.
a. $w = 1$ **b.** $w = 3$ **c.** $w = 6$ **d.** $w = 0$

8. WE8 Calculate the value of h by substituting the given value of the pronumeral into the formula $h = 2(g + 1)$.
a. $g = 1$ **b.** $g = 0$ **c.** $g = 12$ **d.** $g = 75$

9. Calculate the value of i by substituting the given value of the pronumeral into the formula $i = 5(x - 2)$.
a. $x = 6$ **b.** $x = 10$ **c.** $x = 11$ **d.** $x = 2$

10. Calculate the value of j by substituting the given value of the pronumeral into the formula $j = 4(12 - p)$.
a. $p = 2$ **b.** $p = 3$ **c.** $p = 12$ **d.** $p = 11$

11. Calculate the value of k by substituting the given value of the pronumeral into the formula $k = 5(2g - 3)$.
a. $g = 2$ **b.** $g = 14$ **c.** $g = 5$ **d.** $g = 9$

Understanding

12. Calculate the value of l by substituting the given value of the pronumeral into the formula $l = 2(d + 2) - 3$.
a. $d = 3$ **b.** $d = 0$ **c.** $d = 7$ **d.** $d = 31$

13. Calculate the value of m by substituting the given value of the pronumeral into the formula $m = 3(f - 1) + 17$.
a. $f = 1$ **b.** $f = 3$ **c.** $f = 6$ **d.** $f = 21$

14. Calculate the value of n by substituting the given value of the pronumeral into the formula $n = 4s - s$.
a. $s = 3$ **b.** $s = 1$ **c.** $s = 101$ **d.** $s = 72$

15. Calculate the value of o by substituting the given value of the pronumeral into the formula $o = 3(y + 5) - 2$.
a. $y = 1$ **b.** $y = 5$ **c.** $y = 0$ **d.** $y = 12$


16. Calculate the value of p by substituting the given value of the pronumeral into the formula $p = 50 - 6v$.
a. $v = 4$ **b.** $v = 7$ **c.** $v = 1$ **d.** $v = 8$

17. The area of a triangle is given by $A = \frac{1}{2} \times w \times h$. Find the height h and width w that gives an area of 12 square units.

Reasoning

18. WE7 The formula $M = 0.62K$ can be used to convert distances in kilometres (K) into miles (M). Use the formula to convert the following distances into miles:
a. 100 kilometres **b.** 250 kilometres **c.** 15 kilometres

19. The formula for finding the perimeter (P) of a rectangle of length l and width w is $P = 2l + 2w$. Use this formula to calculate the perimeter of the rectangular swimming pool shown.



Problem solving

20. Determine the values of x when the result of $5x - 2$ is a two-digit number.

21. In Australian rules football, a goal is worth 6 points and a behind is worth 1 point. The equation $S = 6g + b$ can be used to determine a team's total score (S) from the number of goals (g) and behinds (b) that it scores.

a. The Giants kicked 16 goals and 13 behinds. Calculate their total score.
b. The Swans kicked 12 goals and 21 behinds. Calculate their total score.
c. The Swans had a total of 33 scoring shots. If they'd been more accurate and kicked 15 goals instead of 12, would they have scored more than the Giants?

22. When he was a young man, the mathematician Carl Friedrich Gauss discovered that the sum (S) of the first n natural numbers is given by the formula $S = \frac{n(n+1)}{2}$.

Using this formula, find the answer to the sum of the following series of numbers:

a. $1 + 2 + 3 + 4 + ... + 46 + 47 + 48 + 49$
b. $54 + 55 + 56 + 57 + ... + 85 + 86 + 87 + 88$

7.4 Simplifying expressions using like terms

LEARNING INTENTION

At the end of this subtopic you should be able to:
- simplify expressions by adding or subtracting like terms.


7.4.1 Simplifying expressions containing like terms

eles-3989


- Terms that contain the exact same pronumerals are called **like terms**.
- Terms that do not contain the exact same pronumerals are called **unlike terms**.
- Examples of like and unlike terms are:

Like terms	Unlike terms
$2a$ and $5a$	$2a$ and $5b$
x and $13x$	$3x$ and $5xy$
$2bc$ and $4cb$	$4abc$ and $3cbd$
$3g^2$ and $45g^2$	$16g$ and $45g^2$

- Note that the order of pronumerals in a term does not matter. The terms ab and ba are like terms because they both contain the exact same pronumerals.
- Like terms can be combined by adding or subtracting coefficients. For example, $3a + 2a = 5a$.



- Unlike terms can't be combined or simplified in any way. For example $3a + 2b$ cannot be written in a simpler way.



WORKED EXAMPLE 9 Simplifying expressions

Where possible, simplify the following expressions by adding or subtracting like terms.

a. $4g + 6g$ **b.** $11ab - ab$ **c.** $6ad + 5da$ **d.** $4t + 7t - 5$ **e.** $8x + 3y$

THINK	WRITE
a. The pronumerals are the same. The terms can be added.	**a.** $4g + 6g = 10g$
b. The pronumerals are the same. The terms can be subtracted. Note: ab is the same as $1ab$ or $1ba$ or ba.	**b.** $11ab - ab = 10ab$
c. Although the order of the pronumerals is different, the terms are like terms and can be added.	**c.** $6ad + 5da = 6ad + 5ad$ $= 11ad$
d. The pronumerals are the same and the first two terms can be added. Do not subtract the other term.	**d.** $4t + 7t - 5 = 11t - 5$
e. The pronumerals are **not** the same. These are not like terms and therefore cannot be simplified.	**e.** $8x + 3y$ cannot be simplified.

WORKED EXAMPLE 10 Evaluating expressions containing like terms

First simplify the following expressions, then determine the value of the expression by substituting $a = 4$.

a. $5a + 2a$ **b.** $7a - a + 5$

THINK	WRITE
a. 1. Add the like terms.	**a.** $5a + 2a = 7a$
2. Substitute $a = 4$ into the simplified expression.	$= 7 \times 4$ $= 28$
b. 1. Subtract the like terms.	**b.** $7a - a + 5 = 6a + 5$
2. Substitute $a = 4$ into the simplified expression.	$= 6 \times 4 + 5$ $= 24 + 5$ $= 29$

DISCUSSION

$3x^2 + 4x^2 = 7x^2$

The terms $3x^2$ and $4x^2$ are called *like terms*. Explain why.

$3x^2$ and $4x$ are called *unlike terms*. Explain why.

Equivalent algebraic expressions

- Terms that are identical but are displayed in different ways are called **equivalent expressions**.
- For example, you can simplify the expression $x + x + y + y - 2$ to $2x + 2y - 2$. This means that $x + x + y + y - 2$ and $2x + 2y - 2$ are equivalent expressions.
- The following are all pairs of equivalent expressions:

$$a + a + a + a = 4a$$
$$b \times b = b^2$$
$$c \times d = cd$$
$$e \div f = \frac{e}{f}$$

COLLABORATIVE TASK: Silently collecting like terms

Equipment: 25 – 30 cards, each containing an algebraic term. Across the set of cards there should be 5 – 6 different pronumerals, and each card should have different coefficients.

1. Each student chooses a card with a term written on it. They must not look at their cards or talk.
2. Each student displays their card facing outward so that the rest of the class can see their term, but the student holding the card cannot.
3. Without talking or looking at their own card, students then help each other to form groups around the classroom with other like terms.
4. Once the class is happy that they are all in like-term groups, students can look at their own card and talk.
5. Each group then simplifies by adding and subtracting like terms.
6. Each group then writes their part of the expression on the board to provide the fully simplified class expression.
7. Discuss any difficulties experienced when gathering and simplifying like terms.

on Resources

eWorkbook	Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)
Video eLesson	Simplification of expressions (eles-1884)
Interactivities	Individual pathway interactivity: Simplifying expressions using like terms (int-8460)
	Simplifying expressions containing like terms (int-4006)

Exercise 7.4 Simplifying expressions using like terms

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 9, 12, 15, 18, 21, 22, 25	2, 5, 8, 10, 13, 16, 20, 23, 26	3, 6, 11, 14, 17, 19, 24, 27, 28

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE 9 Where possible, simplify the following expressions by adding or subtracting like terms.

   a. $3a + 2a$ b. $9y + 5y$ c. $3c + 12c$ d. $4u - 2u$ e. $7e + 13e$

2. Where possible, simplify the following expressions by adding or subtracting like terms.
a. $7t - 2t$ **b.** $12ab + 2ab$ **c.** $8fg - 2fg$ **d.** $4e - e$ **e.** $6t + t$

3. Where possible, simplify the following expressions by adding or subtracting like terms.
a. $f + 4f$ **b.** $6y - 6y$ **c.** $4x + 14x$ **d.** $3m + 16m - 7m$ **e.** $6a + 4a - 2a$

4. Simplify the following expressions (if possible).
a. $24ab + ab - 7$ **b.** $5y + y - 3y$ **c.** $5t + 5s$ **d.** $4t + 8t - 3 + 2t$ **e.** $7r + 2r + 5r - r$

5. Simplify the following expressions (if possible).
a. $7y + 6$ **b.** $4 + 3g - g$ **c.** $6t - 5t$ **d.** $18bg - 18bg$ **e.** $11pq + 3qp$

6. Simplify the following expressions (if possible).
a. $7t + 4t - 5$ **b.** $32t - 31t$ **c.** $7xy - 7x$ **d.** $5t + 6t - 8$ **e.** $5t - t + 3$

7. Simplify each of the following.
a. $3t - 3t$ **b.** $18r - 18r$ **c.** $12ab - 12ab$ **d.** $5x - 5x + 8$

8. Simplify each of the following.
a. $6t + 7 - 6t$ **b.** $13xyz - 13xyz$ **c.** $5x + 7 - 5x$ **d.** $5y + 2y - y$

9. WE10 Simplify the following expressions, then determine the value of the expression by substituting $a = 7$.
a. $3a + 2a$ **b.** $7a + 2a$ **c.** $6a - 2a$ **d.** $9a + a$

10. First simplify the following expressions, then determine the value of the expression by substituting $a = 7$.
a. $13a + 2a - 5a$ **b.** $3a + 7a$ **c.** $17 + 5a + 3a$ **d.** $6a - a + 2$

11. First simplify the following expressions, then determine the value of the expression by substituting $a = 7$.
a. $a + a$ **b.** $7a - 6a$ **c.** $7a - 7a$ **d.** $12a + 5a - 16$

Understanding

12. Answer True or False to each of the following statements.
a. $4t$ and $6t$ are like terms. **b.** $3x$ and x are like terms. **c.** $5g$ and $5t$ are like terms.
d. $5a$ and $6a$ are like terms. **e.** $4a$ and $4ab$ are like terms.

13. Answer True or False to each of the following statements.
a. $6gh$ and $7gk$ are like terms. **b.** yz and $45zy$ are like terms. **c.** $3acd$ and $6cda$ are like terms.
d. $5g$ and $5fg$ are like terms. **e.** $8gefh$ and $3efgh$ are like terms.

14. Answer True or False to each of the following statements.
a. $6ab$ and $3ba$ are like terms. **b.** $8xy$ and $5xy$ are like terms. **c.** $7eg$ and $7g$ are like terms.
d. $7y$ and $18yz$ are like terms. **e.** $12ep$ and $4pe$ are like terms.

15. MC Which one of the following is a like term for $7t$?
A. $7g$ **B.** $5tu$ **C.** 2 **D.** $6f$ **E.** $5t$

16. MC Which one of the following is a like term for $3a$?
A. $5ab$ **B.** $6a$ **C.** $3w$ **D.** $a + 2$ **E.** $3 + a$

17. MC Which one of the following is a like term for $5ab$?
A. $6abe$ **B.** $4b$ **C.** $4ba$ **D.** 5 **E.** $5abe$

18. MC Which one of the following is a like term for $7bgt$?
A. $7t$ **B.** $5gt$ **C.** $2gb$ **D.** btg **E.** $a + b + e$

19. MC Which one of the following is a like term for $2fgk$?
A. $fg + k$ **B.** $5fg$ **C.** $2fgk$ **D.** $2f$ **E.** $12p$

20. MC Which one of the following is a like term for $20m$?

A. $11m$ **B.** $20mn$ **C.** $20f$ **D.** $m+2$ **E.** 20

21. MC Which one of the following is a like term for $9xyz$?

A. $9x$ **B.** $2yz$ **C.** $8xz$ **D.** xzy **E.** $9z$

Reasoning

22. Answer True or False to each of the following statements and justify your answer.

a. The equation $y = 4x + 3x$ can be simplified to $y = 7x$.
b. The equation $k = 8y + 4y$ can be simplified to $k = 10y$.
c. The equation $y = 4x + 3$ can be simplified to $y = 7x$.

23. Answer True or False to each of the following statements and justify your answer.

a. The equation $b = 3a - a$ can be simplified to $b = 2a$.
b. The equation $k = 7a + 4d$ can be simplified to $k = 11ad$.
c. The equation $y = 5x - 3x$ can be simplified to $y = 2x$.

24. Answer True or False to each of the following statements and justify your answer.

a. The equation $m = 7 + 2x$ can be simplified to $m = 9x$.
b. The equation $t = 3h + 12h + 7$ can be simplified to $t = 15h + 7$.
c. The equation $y = 16g + 6g - 7g$ can be simplified to $y = 15g$.

Problem solving


25. There are x chocolates in each box. Ahmed buys 7 boxes while Kevin buys 3 boxes. Write an expression for the total number of chocolates.




26. There are d mangoes in a kilogram. Nora buys 4 kg but they are so good she buys 2 kg more. Write an expression for the total number of mangoes Nora bought.

27. Find the simplest expression for the perimeter of the following shapes:


a.



b.



28. Given that OD bisects COE, that $\angle COD = (4x + 16)°$ and that $\angle DOE = (6x + 4)°$, explain if there is enough information for you to determine the angles for COD and DOE. If so, what are the measures for each?



7.5 Multiplying and dividing terms

LEARNING INTENTION

At the end of this subtopic you should be able to:

- simplify expressions when multiplying, using indices where appropriate
- simplify expressions when diving by identifying common factors.

7.5.1 Multiplying terms

eles-3990

- When you multiply a pronumeral by itself, it is the same as squaring the pronumeral. For example: $2 \times 2 = 2^2$.
- As a pronumeral represents an unknown number, index notation can be applied to pronumerals as well, such that $x \times x \times x = x^3$.

WORKED EXAMPLE 11 Simplify by using index notation where appropriate

Simplify:

a. $2 \times k$ **b.** $3 \times 2k$ **c.** $k \times 2kx$ **d.** $3k \times 2k$ **e.** $3k \times 2k^2x$

THINK	WRITE
a. 1. The coefficient of a pronumeral represents multiples of the pronumeral. Remove the multiplication sign.	**a.** $2 \times k$ $= 2k$
b. 1. Rewrite in expanded form.	**b.** $3 \times 2 \times k$
2. Multiply the numbers.	$= 6 \times k$
3. Remove the multiplication sign.	$= 6k$
c. 1. Rewrite in expanded form.	**c.** $k \times 2 \times k \times x$
2. Write pronumerals with index.	$= 2 \times k^2 \times x$
3. Remove the multiplication sign.	$= 2k^2x$
d. 1. Rewrite in expanded form.	**d.** $3 \times k \times 2 \times k$
2. Multiply the numbers and write pronumerals with index.	$= 6 \times k^2$
3. Remove the multiplication sign.	$= 6k^2$
e. 1. Rewrite in expanded form.	**e.** $3 \times k \times 2 \times k \times k \times x$
2. Multiply the numbers and write pronumerals with index.	$= 6 \times k^3 \times x$
3. Remove the multiplication sign.	$= 6k^3x$

Multiplying pronumerals

- When we multiply pronumerals, order is not important. For example:

$$3 \times 6 = 6 \times 3$$
$$6 \times w = w \times 6$$
$$a \times b = b \times a$$

- The multiplication sign (×) is usually omitted for reasons of convention.

$$3 \times g \times h = 3gh$$

- Although order is not important, conventionally the pronumerals in each term are written in alphabetical order. For example:

$$2 \times b \times a \times c = 2abc$$

7.5.2 Dividing terms

eles-3991

- In algebra, division is normally written as a fraction.
- If a pronumeral is a common factor of both the numerator and the denominator, it can be cancelled.
- You can simplify by cancelling pronumerals only if the pronumeral is a common factor of the whole of the numerator and the whole of the denominator.
- If the pronumeral is a common factor of both the numerator and the denominator, all terms in both the numerator and the denominator will be joined by multiplication symbols.

Simplifying terms

- The expression $\frac{2x+4}{3x}$ cannot be simplified by cancelling a common factor of x, since there is an addition symbol in the numerator.
- When cancelling a common factor that is a pronumeral, remember to cancel one of the pronumerals in the numerator for one of the pronumerals in the denominator.
- Just as $\frac{7}{7} = 1$, a pronumeral divided by the same pronumeral is equal to 1. For example: $\frac{a}{a} = 1$.

WORKED EXAMPLE 12 Simplify by identifying and simplifying common factors

Simplify:

a. $\frac{16f}{4}$ **b.** $16f \div 2f$ **c.** $\frac{4f}{16f^2}$ **d.** $\frac{36fg}{40f^2g}$

THINK	WRITE
a. 1. Write in expanded form.	**a.** $\frac{16 \times f}{4}$
2. Divide numerator and denominator by the highest common factor (HCF), 4.	$= \frac{\overset{4}{\cancel{16}} \times f}{1\cancel{4}}$
3. Write in simplest terms.	$= 4f$
b. 1. Write as a fraction in expanded form.	**b.** $\frac{16 \times f}{2 \times f}$
2. Divide numerator and denominator by HCF 2 and f.	$= \frac{\overset{8}{\cancel{16}} \times \cancel{f}}{1\cancel{2} \times \cancel{f}}$
3. Write in simplest terms.	$= 8$

c. 1. Write in expanded form.

2. Divide numerator and denominator by HCF, 4 and f.

3. Write in simplest terms. Omit the multiplication sign.

c. $\dfrac{4 \times f}{16 \times f \times f}$

$= \dfrac{{}^{1}\cancel{4} \times \cancel{f}}{{}_{4}\cancel{16} \times \cancel{f} \times f}$

$= \dfrac{1}{4f}$

d. 1. Write in expanded form.

2. Divide numerator and denominator by HCF 4 and f.

3. Write in simplest terms. Omit the multiplication sign.

d. $\dfrac{36 \times f \times g}{40 \times f \times f \times g}$

$= \dfrac{{}^{9}\cancel{36} \times \cancel{f} \times \cancel{g}}{{}_{10}\cancel{40} \times \cancel{f} \times f \times \cancel{g}}$

$= \dfrac{9}{10f}$

on Resources

eWorkbook Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)

Interactivity Individual pathway interactivity: Multiplying and dividing terms (int-8343)

Exercise 7.5 Multiplying and dividing terms

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 6, 9, 11, 14	3, 7, 12, 15	4, 8, 10, 13, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE11 Simplify the following.

a. $2a \times a$ **b.** $ab \times 7a$ **c.** $7pq \times 3p$ **d.** $3b^2 \times 2cd$ **e.** $20m^{12} \times 2m^3$

2. Simplify the following.

a. $4 \times 3g$ **b.** $7 \times 3h$ **c.** $4d \times 6$ **d.** $3z \times 5$ **e.** $6 \times 5r$

3. Simplify the following.

a. $5t \times 7$ **b.** $4 \times 3u$ **c.** $7 \times 6p$ **d.** $7gy \times 3$ **e.** $2 \times 11ht$

4. Simplify the following.

a. $4x \times 6g$ **b.** $10a \times 7h$ **c.** $9m \times 4d$ **d.** $3c \times 5h$ **e.** $9g \times 2x$

5. WE12 Simplify the following.

a. $\dfrac{8f}{2}$ **b.** $\dfrac{6h}{3}$ **c.** $\dfrac{15x}{3}$ **d.** $9g \div 3$ **e.** $10r \div 5$

6. Simplify the following.

a. $4x \div 2x$ **b.** $8r \div 4r$ **c.** $\frac{16m}{8m}$ **d.** $14q \div 21q$ **e.** $\frac{3x}{6x}$

7. Simplify the following.

a. $\frac{12h}{14h}$ **b.** $50g \div 75g$ **c.** $\frac{8f}{24f}$ **d.** $35x \div 70x$ **e.** $24m \div 36m$

8. Simplify the following:

a. $\frac{3 \times a}{a^2}$ **b.** $\frac{25p^{12} \times 4q^7}{15p^2}$ **c.** $\frac{8x^3 \times 7y^2}{6x \times 14y^3}$ **d.** $w \times \frac{5}{w^2}$ **e.** $\frac{12x^3y^2}{6x^4 \times 14y^3}$

Understanding

9. Simplify the following.

a. $3a \times a$ **b.** $-2p \times 2p$ **c.** $5 \times 2x \times x$ **d.** $ab \times 5a$

10. Simplify the following.

a. $-3xy \times 2 \times 6x$ **b.** $4pq \times 3p \times 2q$

c. $5m \times n \times 2nt \times -t$ **d.** $-7 \times xyz \times -3z \times -2y$

Reasoning

11. A student shows the following working:

$$\frac{2+3x^1}{5x^1}$$

Explain whether you agree with their working.

12. Consider the expression $\frac{24xy^2}{7ab} \times \frac{14a^2}{27y}$.

a. Multiply the numerators and multiply the denominators, then cancel any common factors.

b. Cancel the common factors in the numerators and denominators first, then multiply the remaining factors accordingly.


c. Compare your answer to part **a** with your answer to part **b**. Which process do you feel is better to use?

13. Explain why $x \div (yz)$ is equivalent to $\frac{x}{yz}$ and $x \div (y \times z)$, but is not equivalent to $x \div y \times z$ or $\frac{x}{y} \times z$.


Problem solving

14. Calculate the areas of the following shapes.


a.



b.



c.



15. Evaluate the expression $\frac{4ht}{3dk} \times \frac{-12hk}{9dt}$, by substituting the values of $h = 1$, $d = 2$, $k = 3$ and $t = 4$.


16. A rectangle has been cut out of a corner of a square.

a. Find the perimeter of the shape.

b. Find the area of the shape if:

i. $x = 2$ cm **ii.** $x = 3$ cm.

c. Find the area of the shape in terms of x.



7.6 Number laws

LEARNING INTENTION

At the end of this subtopic you should be able to:

- understand and apply the Commutative Law for addition and multiplication
- understand and apply the Associative Law for addition and multiplication
- understand that the commutative and associative laws do not apply to subtraction or division.

eles-3992

7.6.1 The Commutative Law

- The **Commutative Law** refers to the order in which two numbers are added or multiplied.
- It holds true for addition and multiplication but not for subtraction or division.

The Commutative Law for addition

- $a + b = b + a$
- For example, $5 + 3 = 8$ and $3 + 5 = 8$; $x + y = y + x$.
- This law *does not hold for subtraction*.
  For example, $5 - 3 \neq 3 - 5$; $x - y \neq y - x$.

The Commutative Law for multiplication

- $a \times b = b \times a$
- For example, $2 \times 3 = 6$ and $3 \times 2 = 6$; $x \times y = y \times x$.
- This law *does not hold for division*.
  For example, $6 \div 2 \neq 2 \div 6$; $x \div y \neq y \div x$.

WORKED EXAMPLE 13 Testing the Commutative Law

Evaluate the following expressions if $a = 2$ and $b = 3$. Comment on the results obtained.

a. i. $a + b$ **ii.** $b + a$ **b. i.** $5a - 2b$ **ii.** $2b - 5a$
c. i. $a \times b$ **ii.** $b \times a$ **d. i.** $a \div b$ **ii.** $b \div a$

THINK

a. i. 1. Substitute the correct value for each pronumeral.

2. Evaluate and write the answer.

ii. 1. Substitute the correct value for each pronumeral.

2. Evaluate and write the answer.

WRITE

a. i. $a + b = 2 + 3$
$= 5$

ii. $b + a = 3 + 2$
$= 5$

3. Compare the result with the answer obtained in part **a i**.

The same result is obtained; therefore, order is not important when adding two terms.

b. i. 1. Substitute the correct value for each pronumeral.
2. Evaluate and write the answer.

b. i. $5a - 2b = 5 \times 2 - 2 \times 3$
$= 4$

ii. 1. Substitute the correct value for each pronumeral.
2. Evaluate and write the answer.
3. Compare the result with the answer obtained in part **b i**.

ii. $2b - 5a = 2 \times 3 - 5 \times 2$
$= -4$

Two different results are obtained; therefore, order is important when subtracting two terms.

c. i. 1. Substitute the correct value for each pronumeral.
2. Evaluate and write the answer.

c. i. $a \times b = 2 \times 3$
$= 6$

ii. 1. Substitute the correct value for each pronumeral.
2. Evaluate and write the answer.
3. Compare the result with the answer obtained in part **c i**.

ii. $b \times a = 3 \times 2$
$= 6$

The same result is obtained; therefore, order is not important when multiplying two terms.

d. i. 1. Substitute the correct value for each pronumeral.
2. Evaluate and write the answer.

d. i. $a \div b = 2 \div 3$
$= \frac{2}{3} (\approx 0.67)$

ii. 1. Substitute the correct value for each pronumeral.
2. Evaluate and write the answer.
3. Compare the result with the answer obtained in part **d i**.

ii. $b \div a = 3 \div 2$
$= \frac{3}{2} (1.50)$

Two different results are obtained; therefore, order is important when dividing two terms.

7.6.2 The Associative Law

eles-3993

- The **Associative Law** refers to the grouping of three numbers that are added, subtracted, multiplied or divided.
- It holds true for addition and multiplication but not for subtraction or division.

The Associative Law for addition

- $(a + b) + c = a + (b + c) = a + b + c$
- For example, $(9 + 3) + 7 = 12 + 7 = 19$ and $9 + (3 + 7) = 9 + 10 = 19$.
- This law *does not hold for subtraction*.
  For example, $(8 - 3) - 2 = 5 - 2 = 3$, but $8 - (3 - 2) = 8 - 1 = 7$.

The Associative Law for multiplication

- $(a \times b) \times c = a \times (b \times c) = a \times b \times c$
- For example, $(2 \times 3) \times 5 = 6 \times 5 = 30$ and $2 \times (3 \times 5) = 2 \times 15 = 30$.
- This law *does not hold for division*.
  For example, $(24 \div 6) \div 2 = 4 \div 2 = 2$, but $24 \div (6 \div 2) = 24 \div 3 = 8$.

WORKED EXAMPLE 14 Applying the Associative Law

Use the Associative Law to complete the following.

a. $2w + (8d + __) = (__ + 8d) + 5h$ **b.** $(x \times __) \times 4g = __ (d \times 4g)$

THINK	WRITE
a. The Associative Law states that the numbers can be regrouped. $2w$, $8d$ and $5h$ are numbers. $5h$ is missing from the left-hand side and $2w$ is missing from the right-hand side.	**a.** $2w + (8d + 5h) = (2w + 8d) + 5h$
b. The Associative Law states that the numbers can be regrouped. d is missing from the left-hand side and x is missing from the right-hand side.	**b.** $(x \times d) \times 4g = x \times (d \times 4g)$

WORKED EXAMPLE 15 Applying the associative and commutative laws

Use the associative and commutative laws to complete the following.

a. $4r + (6t + __) = 5g + (__ + __)$ **b.** $a \times (3t \times 2w) = (2w \times __) __ a$

THINK	WRITE
a. The associative and commutative laws state that the numbers can be regrouped and rearranged. $5g$ is missing from the left-hand side. Both $4r$ and $6t$ are missing from the right-hand side.	**a.** $4r + (6t + 5g) = 5g + (4r + 6t)$
b. The associative and commutative laws state that the numbers can be regrouped and rearranged. $3t$ and a multiplication sign are missing from the right-hand side.	**b.** $a \times (3t \times 2w) = (2w \times 3t) \times a$

on Resources

eWorkbook Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)

Interactivities Individual pathway interactivity: Number laws (int-8461)
The associative law for multiplication (int-4008)
The commutative law for multiplication (int-4009)

Exercise 7.6 Number laws

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 9, 12	3, 6, 7, 10, 13	4, 8, 11, 14

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE13 State whether the following are True or False. *Hint:* If you're not sure, try substituting values for the pronumerals to help you decide.
   - a. $2s + (3w + 5z) = (2s + 3w) + 5z$
   - b. $x \times (d + y) = (x \times d) + y$
   - c. $g(jk) = (gj)k$
   - d. $4 \div (a \div c) = (4 \div a) \div c$

2. WE14 Use the Associative Law to complete the following.
   - a. $w + (r__6y) = (__ + __) + 6y$
   - b. $6t \times (4r \times __) = (6__ \times 4r)\ __3s$
   - c. $(9y + __) + 3w = __ + (2r + 3w)$
   - d. $(z + 2p) + __ = z__\ (__ + 6t)$

3. WE15 Use the associative and commutative laws to complete the following.
   - a. $6t + (3w + __) = __ + (6t + 7v)$
   - b. $s \times (9r \times __) = 2c \times (__ \times __)$
   - c. $(3c + w) + __ = d + (__ + __)$
   - d. $(g \times __) \times 2y = 2y \times (3b \times __)$

4. State whether the following are True or False. *Hint:* If you're not sure, try substituting values for the pronumerals to help you decide.
   - a. $3g + (k \div m) = (3g + k) \div m$
   - b. $4t - (p + 2b) = (4t - p) + 2b$
   - c. $3r + (a + 4c) = a + (3r + 4c)$
   - d. $a + (b \times c) = (a \times c) + b$

Understanding

5. Calculate the values of the following expressions and comment on the results if $a = 3$, $b = 8$ and $c = 2$.
   - a. $a + (2b + 4c)$
   - b. $(3a + 2b) + 4c$

6. Calculate the values of the following expressions and comment on the results if $a = 3$, $b = 8$ and $c = 2$.
   - a. $9a - (2b - 5c)$
   - b. $(9a - 2b) - 5c$

7. Determine the values of the following expressions and comment on the results if $a = 3$, $b = 8$ and $c = 2$.
   - a. $a \times (b \times c)$
   - b. $(a \times b) \times c$

8. Calculate the values of the following expressions and comment on the results if $a = 3$, $b = 8$ and $c = 2$.
   - a. $4a \div (3b \div 2c)$
   - b. $(4a \div 3b) \div 2c$

Reasoning

9. The Commutative Law does not hold for subtraction. What can you say about the results of $x - a$ and $a - x$?

10. Explain whether the Associative Law holds when you are adding fractions.

Problem solving

11. Use the numbers 1, 5, 6 and 7 with any arithmetic operations to give 21 as the result.

12. **a.** If $x = 1$, $y = 2$ and $z = 3$, find the value of:
i. $(x - y) + z$ **ii.** $x - (y - z)$.
b. Comment on the answers with special reference to the Associative Law.

13. Janet and Judy want to buy a set of Blu-rays together. Janet has $47 less than the cost of the Blu-rays and Judy has $2 less than the cost. Both girls have at least $1 each. If they pool their money, they still do not have enough to buy the Blu-rays. If the cost of the set is a whole number, calculate how much the Blu-rays cost.



14. Andrew thinks of a number, adds 9 and multiplies the result by 3. Andrea thinks of a number, multiplies it by 3 and adds 9 to the result. Both Andrew and Andrea get an answer of 60. Explain whether Andrew and Andrea began by selecting the same number. Show your working to support your answer.

7.7 Expanding brackets

LEARNING INTENTION


At the end of this subtopic you should be able to:
- write expressions in an expanded form by using the Distributive Law.

7.7.1 The Distributive Law

eles-3994

- Expanding brackets means writing an equivalent expression without brackets.
- The Distributive Law can be used to expand or remove brackets.
- In the diagram, the blue rectangles represent a, the pink squares represent b and the green rectangles represent $a + b$.
- As can be seen in the diagram, $3(a + b) = 3a + 3b$.
- This can also be determined by collecting like terms:

$$\begin{aligned} 3(a + b) &= (a + b) + (a + b) + (a + b) \\ &= a + a + a + b + b + b \\ &= 3a + 3b \end{aligned}$$



- Expressions such as this may be written in factorised form or expanded form.

$$\overbrace{3(a + b)}^{\text{factorised form}} = \overbrace{3a + 3b}^{\text{expanded form}}$$

The Distributive Law

The Distributive Law provides a quick method of expanding expressions that are in factorised form.

$$a(b + c) = ab + ac$$

The term that is out at the front of the brackets gets distributed to each of the terms inside the brackets.

The Distributive Law also applies when the terms inside the brackets are subtracted.

$$a(b - c) = ab - ac$$

- The Distributive Law holds true no matter how many terms there are inside the brackets. For example, $a(b + c - d) = ab + ac - ad$.
- The Distributive Law is not used when the terms inside the brackets are multiplied or divided. For example, $2(4 \times 5) = 2 \times 4 \times 5$ and not $(2 \times 4) \times (2 \times 5)$.

WORKED EXAMPLE 16 Applying the Distributive Law

Write the following expressions in expanded form, then simplify them.

a. $4(2a + d)$ **b.** $a(3x + 2y)$ **c.** $3(k + 4a - m)$

THINK

a. 1. According to the Distributive Law, the number 4 is distributed (or multiplied) to both $2a$ and d.

2. Simplify the terms and write the answer.

b. 1. According to the Distributive Law, the number represented by the pronumeral a is distributed to both $3x$ and $2y$.

2. Simplify the terms and write the answer.

c. 1. According to the Distributive Law, the number 3 is distributed to k, $4a$ and m.

2. Simplify the terms and write the answer.

WRITE

a. $4(2a + d) = 4 \times 2a + 4 \times d$

$= 8a + 4d$

b. $a(3x + 2y) = a \times 3x + a \times 2y$

$= 3ax + 2ay$

c. $3(k + 4a - m) = 3 \times k + 3 \times 4a - 3 \times m$

$= 3k + 12a - 3m$

WORKED EXAMPLE 17 Applying the Distributive Law

Use the Distributive Law to expand and simplify the following.

a. $4(2s + 3k) - 2k$ **b.** $a(3 - c) + a$

THINK	WRITE
a. 1. Use the Distributive Law to expand $4(2s + 3k)$.	**a.** $4(2s + 3k) - 2k = 4 \times 2s + 4 \times 3k - 2k$
2. Simplify the terms.	$= 8s + 12k - 2k$
3. Collect like terms and write the answer.	$= 8s + 10k$
b. 1. Use the Distributive Law to expand $a(3 - c)$.	**b.** $a(3 - c) + a = a \times 3 - a \times c + a$
2. Simplify the terms.	$= 3a - ac + a$
3. Collect like terms and write the answer.	$= 4a - ac$

Resources

eWorkbook Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)

Interactivity Individual pathway interactivity: Expanding brackets (int-8344)

The distributive law (int-4007)

Exercise 7.7 Expanding brackets

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 8, 11, 14	4, 7, 9, 12, 15	2, 5, 10, 13, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE16 Write the following expressions in expanded form, then simplify (if possible).
   a. $3(a + 2b)$ **b.** $5(x - 4z)$ **c.** $10(2g + 3h)$ **d.** $b(2c - 3a)$
2. Write the following expressions in expanded form, then simplify (if possible).
   a. $2c(8d - q)$ **b.** $3b(3b - 2g)$ **c.** $x(9a + 7b)$ **d.** $7k(t + 3m)$
3. WE17 Use the Distributive Law to expand the following expressions.
   a. $5(a + 2b) - 3a$ **b.** $4(n - 2c) + n$ **c.** $9(b + 2c) - 9b$ **d.** $x(a - b) + x$
4. Use the Distributive Law to expand each of the following.
   a. $3(2d + 7e)$ **b.** $3h(6j - 5) + 4h$ **c.** $4(k + 5a - 3)$ **d.** $4x(x + 1) - 2(2x - 3)$
5. Use the Distributive Law to expand the following expressions.
   a. $y(3 + 2z) + 2y$ **b.** $3x(d - 3) + 4x$ **c.** $6u(2f - 1) + 20u$ **d.** $7n(10 + 3h) - 50n$

6. Expand each of the following expressions and then simplify by collecting like terms.

a. $8(5r+2)+14r$ **b.** $3(t-6)-12$ **c.** $3y+3(12-2y)$ **d.** $2x-(16-3x)$

7. Expand each of the following expressions and then simplify by collecting like terms.

a. $5-3t+6(2t-8)$ **b.** $14+3ry+8(r+2ry)$

c. $12ty+2t(7y-8h)+6h$ **d.** $16r^2+12r(2-r)-6r+3$

8. Expand each of the following expressions and then simplify by collecting like terms.

a. $3(x+2)+2(3-x)$ **b.** $6(4h-3)+7h(4x-8)$

c. $5(4x+y)-2(3y+3)$ **d.** $6(3-t^2)-8(t^2+3)$

Understanding

9. Expand each of the following and then simplify.

a. $3(x-y)+5(y+2x)$ **b.** $5(a-2y)+a(7+6y)$ **c.** $6c(g+3d)+g(3c+d)$ **d.** $y(6d-r)+2y(3d+2r)$

10. In expressions such as $a(b+c)=ab+ac$, the left-hand side is in *factor form* and the right-hand side is in *expanded form*. Write each of the following in factor form.

a. $2x+4$ **b.** $6x-6y$ **c.** $4x+12$ **d.** $12fg-16gh$

Reasoning

11. The formula for the perimeter (P) of a rectangle of length l and width w is $P=2(l+w)$. Use the rule to calculate the perimeter of a magazine cover with $l=28.6$ cm and $w=21$ cm.



12. For each of the following expressions, show three different ways to make the statements true by placing appropriate terms in the boxes.

a. $\square(\square+2)=12ab+\square$

b. $\square(\square+2)=36kn+\square$

13. Consider the expression $2(1-5x)$. If x is a negative integer, explain why the expression will be a positive integer.

Problem solving

14. Expanding and simplifying the expression $2(8c-16a)$ gives $16c-32a$. Determine three expressions that give the same result.

15. a. Expand and simplify $2(x+y)-3x$.

b. Verify that your simplified expression is correct by substituting $x=2$ and $y=3$ into both the original and simplified expressions.

16. The price of a pair of shoes is \$50. During a sale, the price of the shoes is discounted by \$$d$.



a. Write an expression to represent the sale price of the shoes.

b. If you buy three pairs of shoes during the sale, write an expression to represent the total purchase price:

i. containing brackets

ii. in expanded form (without brackets).

c. Write an expression to represent the total change you would receive from \$200 for the three pairs of shoes purchased during the sale.

7.8 Review

7.8.1 Topic summary



The language of algebra

- **Pronumerals** are letters used to represent numbers.
  e.g. t: the number of tickets sold
- A pronumeral is also called a **variable**.
- The number in front of a pronumeral is called the **coefficient**.
  e.g. The coefficient of $7x$ is 7.
  The coefficient of p is 1.
- **Terms** can contain a combination of numbers and one or more pronumerals, or may consist of a number only.
  e.g. $3t$, $2y$, $5gh$, 7 and m are examples of terms.
- A **constant term** is a term containing only a number.
  e.g. 7, 10 and +4 are examples of constant terms.
- **Expressions** are made up of terms separated by + and − signs.
  e.g. $5x + 4 - 2y$ is an example of an expression.
  - This expression has 3 terms: $5x$, $+4$ and $-2y$ ($+4$ is called a constant term).
  - The coefficient of x is 5 and the coefficient of y is -2.

ALGEBRA

Like terms

- **Like terms** have identical pronumeral parts.
  e.g. $3x$ and x are like terms.
  $5ab$ and $-6ba$ are like terms.
  $-5xy$ and $11y$ are **not** like terms.
- Like terms can be added together or subtracted.

Substitution

- Substitution is the process of replacing a pronumeral with its known value.
- By using substitution, the value of an expression can be determined.

e.g. $2x + 5$ when $x = 6$ becomes:
$2(6) + 5 = 2 \times 6 + 5 = 12 + 5 = 17$

Multiplying and dividing expressions

- When multiplying expressions, multiply the numbers and write the pronumerals in alphabetical order. Remove the multiplication sign.
  e.g. $5b \times 2a = 10ab$
- When dividing, write the division as a fraction and simplify by cancelling.
  e.g. $\frac{16f}{4} = 4f$

Algebraic laws

- Only addition and multiplication are commutative. This means that the order in which we add or multiply does not matter. The **Commutative Law** for addition and multiplication states that:
  $a + b = b + a$ and $a \times b = b \times a$
- Only addition and multiplication are associative. This means that it does not matter how we group the numbers together when adding or multiplying. The **Associative Law** for addition and multiplication states that:
  $(a + b) + c = a + (b + c) = a + b + c$
  $(a \times b) \times c = a \times (b \times c) = a \times b \times c$
- The **Distributive Law** states that multiplying a number by a group of numbers added together is the same as doing each multiplication separately. The Distributive Law is useful for expanding brackets.
  The Distributive Law states that:
  $a \times (b + c) = a \times b + a \times c$
  $= ab + ac$

Equivalent expressions

- Equivalent expressions are always equal when pronumerals are substituted.

e.g. $4 + 6x$ and $11 + 6x - 7$ are equivalent.

7.8.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
7.2	I understand the use of pronumerals in algebra.			
	I can identify algebraic terminology.			
	I can construct expressions from given information.			
7.3	I can substitute a number for a pronumeral to evaluate an algebraic expression.			
7.4	I can simplify expressions by adding or subtracting like terms.			
7.5	I can simplify expressions when multiplying, using indices where appropriate.			
	I can simplify expressions when dividing by identifying common factors.			
7.6	I understand and can apply the Commutative Law for addition and multiplication.			
	I understand and can apply the Associative Law for addition and multiplication.			
	I understand that the associative and commutative laws do not apply to subtraction or division.			
7.7	I can write expressions in expanded form by using the Distributive Law.			

7.8.3 Project

Landscaping


A town's local council wants to create more garden beds in the parklands around the town as part of its beautification program. All garden beds are to be square, but can vary in size. They will be surrounded by 1 m^2 pavers, as shown in the diagram.



Garden bed 1



Garden bed 2



Garden bed 3

- The blue areas represent the square garden beds.
- The white squares represent the 1 m^2 pavers.

1. Use these three diagrams of the garden beds to complete the following table.

Measurements	Garden bed 1	Garden bed 2	Garden bed 3
Side length of the garden bed (m)			
Area of the garden bed (m^2)			
Number of pavers used			
Total length around the outside of pavers (m)			

Let s represent the side length of the garden bed.
Let a represent the area of the garden bed.
Let p represent the number of pavers used.
Let l represent the total length around the outside of the pavers.



2. Examine the patterns formed in your table and write formulas linking:
   - a and s
   - l and s
   - p and s
   - p and l.
3. You just got a job as the council's new landscape gardener. Your first task is to design a 10 m × 10 m square garden bed that is to be constructed in the same way as demonstrated in the previous diagram. How many pavers will be needed for this design?
4. The council has decided to put a large, square garden bed on the grounds near the entrance to its offices. The area of ground measures 18 m × 20 m. The council wants you to place the largest possible square garden bed here. You also have to put 1 m^2 pavers around it. Draw a design of the council's plan for this area of ground on a sheet of paper, with clear labels showing the measurements involved. Indicate the number of pavers that will be required for the project.



Resources

eWorkbook Topic 7 Workbook (worksheets, code puzzle and project) (ewbk-1908)
Interactivities Crossword (int-2598)
Sudoku puzzle (int-3169)

Exercise 7.8 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Simplify the following expressions by adding or subtracting like terms.
a. $3g + 4g$ **b.** $8y - 2y$ **c.** $4h + 5h$ **d.** $7ag - 2ag$ **e.** $6gy - 3yg$

2. Simplify the following expressions by adding or subtracting like terms.
a. $8r - 8r$ **b.** $6y - 2y + y$ **c.** $4t + 6 + 3t$ **d.** $12gh + 6hg$ **e.** $8t - 2m + 3t$

3. Simplify the following expressions by adding or subtracting like terms.
a. $3m + m$ **b.** $7g + 8g + 8 + 4$ **c.** $7h + 4t - 3h$
d. $2b + 7c + 8b$ **e.** $11axy - 3axy$

4. First simplify the following expressions, then find the value of the expression if $x = 5$.
a. $7x + 3x$ **b.** $2x + 3x - 4$ **c.** $11x + 12x$ **d.** $x + 2x$

5. First simplify the following expressions, then find the value of the expression if $x = 5$.
a. $3x - 2x + 16$ **b.** $21x - 13x + 7$ **c.** $11 + 2x + 5x$ **d.** $7x - 4x + 3x$

6. Use the Distributive Law to expand the following expressions.
a. $7(m - 3k)$ **b.** $w(g + 9a)$ **c.** $2y(8h - 7)$

7. Use the Distributive Law to expand the following expressions.
a. $10m(7r - 2p)$ **b.** $3g(2a + 2c)$ **c.** $4j(6x - 3y)$

8. Expand the following and simplify (if possible).
a. $5(t - 2s) - 3t$ **b.** $4(a + 3g) - 2g$ **c.** $d(3f + 9) - 2d$

9. Expand the following and simplify (if possible).
a. $4z(2 - a) + 7z$ **b.** $3p(f - 2q) + 7p$ **c.** $10b(a + 6) + 5b$

10. Use the Associative Law to complete the following equations.
a. $a + (3b + __) = (__ + __) + 5c$ **b.** $\frac{1}{a} + (2b + __) = (__ + 2b)__7g$

11. Use the Associative Law to complete the following equations.
a. $(d \times 3y) \times z = __(__ \times __)$ **b.** $\left(\frac{a}{b} \times c\right) \times __ = \frac{a}{__}(__ \times f)$

12. Use the associative and commutative laws to complete the following equations.
a. $g + (3m + __) = (2k + __) + 3m$ **b.** $(w + __) + 4r = __ + (5g + w)$

13. Use the associative and commutative laws to complete the following equations.
a. $\frac{2}{3} \times (2d \times __) = (r \times 2d) \times __$ **b.** $(3z \times 5b) \times __ = __ \times (6m \times 5b)$

14. Write an expression for:

a. the difference between M and C
b. money earned by selling B cakes for $3 each
c. the product of X and Y
d. 15 more than G
e. 1 more than D
f. the cost of 12 bananas at H cents each
g. T multiplied by 5.

15. Otto works in a warehouse, packing boxes of chocolates for distribution across the country. An order from a store in Wollongong fills 35 boxes, with 18 chocolates left over.



a. Write an expression to represent the number of chocolates ordered, using the pronumeral x to represent a full box of chocolates.
b. If each full box contains 30 chocolates, use your expression to calculate how many chocolates the store ordered.

16. Are the following equations True or False for all values of the pronumerals?

a. $7x - 10y = 10y - 7x$ **b.** $9x \times -y = -y \times 9x$ **c.** $16 \times 2x \times x = 32x^2$

17. Simplify the following.

a. $3g \times 7g$ **b.** $6xy \times 3y$ **c.** $7ad \times 6a^2$ **d.** $-3z^2 \times 8zy$

18. Simplify each of the following.

a. $\frac{16m}{8}$ **b.** $\frac{13x}{13}$ **c.** $\frac{20d}{60d}$ **d.** $\frac{6th}{12h}$ **e.** $\frac{63r}{27rt}$

19. Simplify each of the following.

a. $\frac{15kt^3}{r^2}$ **b.** $\frac{8m^2n}{18mn^2}$ **c.** $\frac{72def^2}{-18d^2e}$ **d.** $\frac{9a^2b}{12ab^2}$ **e.** $\frac{33k^2m^2}{11m^2k}$

20. Place the appropriate terms in the boxes below to make the following statements true. Remember to simplify the equation by multiplying by the reciprocal.

a. $\square \div 3pq = 4p^2$ **b.** $21x^2 \div \square = \frac{3x}{y}$ **c.** $\square \div \frac{2a}{5b} = \frac{35b^2}{2a^2}$ **d.** $\frac{7x}{2y} \div \square = \frac{7y^2}{24}$

Problem solving

21. Mary has y books. Tom has 4 more books than Mary. Cindy has 5 times as many books as Tom. Write down an expression, in terms of y, that can be used to work out the number of books that Cindy has. (Don't actually calculate the number of books.)

22. It's Bianca's birthday today. She is m years old. She asks the ages of people at her party. Write expressions to describe the ages of the following people.



a. Bianca's cousin Paul is 8 years older than Bianca.
b. Bianca's sister Kate is 5 years younger than Bianca.
c. Bianca's aunt Delia is three times Bianca's age.
d. Delia's friend Nic is 3 years older than Delia.

23. Use the pronumeral x to make a general statement in the form ___ × ___ = ___ from the following clues.

$4 \times \frac{1}{4} = 1; \qquad 30 \times \frac{1}{30} = 1; \qquad 1.2 \times \frac{1}{1.2} = 1$

24. A couple spends $\$x$ on developing 80 small wedding photos and $\$y$ for 60 large wedding photos. Determine how much more they need to spend if they want an extra dozen photos of each size.



25. It costs $\$x$ for four adults' tickets at the cinema. A child's ticket costs $3 less than an adult's ticket. On family night, all the tickets go for half price. Develop a formula in terms of x to calculate how much it will cost for a family of 2 adults and 3 children on family night.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1908)

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0696) ☐

Digital document

7.2 SkillSHEET Alternative expressions used to describe the four operations (doc-6502) ☐

Video eLessons

7.2 Pronumerals (eles-3986) ☐
Terms and expressions (eles-3987) ☐
7.3 Substituting (eles-3988) ☐
Substitution (eles-2426) ☐
7.4 Simplifying expressions containing like terms (eles-3989) ☐
Simplification of expressions (eles-1884) ☐
7.5 Multiplying terms (eles-3990) ☐
Dividing terms (eles-3991) ☐
7.6 The Commutative Law (eles-3992) ☐
The Associative Law (eles-3993) ☐
7.7 The Distributive Law (eles-3994) ☐

Interactivities

7.2 Individual pathway interactivity: Introduction to algebra (int-4429) ☐
Terms and expressions (int-4004) ☐
7.3 Individual pathway interactivity: Substitution (int-4351) ☐
Substitution (int-4003) ☐
7.4 Individual pathway interactivity: Simplifying expressions using like terms (int-8460) ☐
Simplifying expressions containing like terms (int-4006) ☐
7.5 Individual pathway interactivity: Multiplying and dividing terms (int-8343) ☐
7.6 Individual pathway interactivity: Number laws (int-8461) ☐
The commutative law for multiplication (int-4009) ☐
The associative law for multiplication (int-4008) ☐
7.7 Individual pathway interactivity: Expanding brackets (int-8344) ☐
The distributive law (int-4007) ☐
7.8 Crossword (int-2598) ☐
Sudoku puzzle (int-3169) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.


Answers

Topic 7 Algebra

Exercise 7.1 Pre-test

1. B
2. 24
3. 84
4. E
5. $2x + 6y$
6. $20x + 4y$
7. 20, 21
8. $10k + 6$
9. 5, $4x$
10. a. $30abc$ b. $52ab^3$ c. $5q$ d. $\frac{13m}{3n}$
11. 3
12. $17p - 2q$
13. $6x + 10y$
14. False, $a \times a = a^2$
15. $3b + 8r$

Exercise 7.2 Introduction to algebra

1. Pronumerals are used in algebra to represent unknown numbers.
2. As an example, on Monday there were b bananas in the bowl; on Tuesday 4 bananas were taken out; on Wednesday 2 bananas were taken out; on Thursday 14 bananas were added; on Friday 3 bananas were taken out.
3. a. $2 \times c + 4$ b. $3 \times c + 4$ c. $2 \times c + 2$ d. $2 \times c + 3$
4. a. $c + 3$ b. $2c$ c. $2c + 5$ d. $4c + 3$
5. $4c + 34$
6. a. $2m$ b. $2m + n$ c. $4m + 3n$ d. $m + 2n + 5$ e. $3m + 2n + 8$
7. a. $a + b$ b. $a - b$ c. ab d. $\frac{3a}{b}$
8. a. $\frac{-15}{a}$ b. $3a - 5b$ c. $\frac{-b}{5}$ d. $a - 7$
9. a. $m - 8, m - 2, m + 1, m + 3$
   b. $n - 15, n - 10.3, n + 25$
10. Examples are given here.
    a. Let d be the number of dogs at my house. My friend has 2 more dogs at her house than I do $(d + 2)$, while another friend has 1 dog less at his house than I do $(d - 1)$.
    b. Let t be the number of textbooks in my schoolbag. My friend has double that number in his schoolbag $(2t)$ while another friend has 1 more textbook than I do, in his schoolbag $(t + 1)$.
    c. Let y be the number of dollars in my wallet. My friend has 3 times the number of dollars as I have, in her wallet $(3y)$, while another friend has 10 times the number of dollars as I do, in her wallet $(10y)$.
11. a. $B + 2$ b. $T - 3$ c. $D + 6$ d. $K - 5$
12. a. $G + N + W$ b. $D + H$ c. $2N$ d. $C + H$
13. a. $12 - G$ b. $4D$ c. BF d. $3M + Y$
14. a. $A + B + C$ b. $A - C$ c. AC d. ABC
15. a. $\frac{B}{C}$ b. $\frac{A + C}{B}$ c. $A + 3$ d. $C - AB$
16. a. $T - X$ b. $\$4B$ c. $45G$ d. $\frac{\$T}{5}$
17. a. $2 \times n$ b. $4 \times n$ c. $8 \times n$
18. A
19. C
20. B
21. B
22. C
23. a. True b. True c. False d. True
24. a. True b. True c. True d. False
25. a. False b. True c. True d. False
26. a. $a + 6$ b. $a - 2$
27. a. $\$3d$ b. $\$120d$ c. $\$3(d + 1.5)$
28. In $\frac{(x + 1)}{3}$, 1 is added to x and then the result is divided by 3. In $\frac{x}{3} + 1$, x is divided by 3 first and then 1 is added.
29. $y + y + y = 3y$ and $y \times y \times y = y^3$
30. 

31. a. $\$(2x + 7)$ b. $3x$ c. $4x + 3$
32. a. Cost of a hamburger + cost of a hamburger + cost of a drink = total cost (or cost of the drink + twice the cost of a hamburger = total cost)
    b. $\$3.75 + 2h = \$7.25$
33. a. $10 + \frac{2n}{5}$, where n is the number of coins in each piggy bank.
    b. \$44
34. 180

Exercise 7.3 Substituting and evaluating

1. a. 11 b. 20 c. -2 d. 15
2. a. -1 b. 66 c. 19 d. -41
3. a. -13 b. -12 c. 33 d. 8
4. a. $d = 2$ b. $d = 3$ c. $d = 0$ d. $d = 100$
5. a. $e = 11$ b. $e = 1$ c. $e = 197$ d. $e = 13$
6. a. $f = 19$ b. $f = 7$ c. $f = 67$ d. $f = 247$
7. a. $g = 21$ b. $g = 13$ c. $g = 1$ d. $g = 25$
8. a. $h = 4$ b. $h = 2$ c. $h = 26$ d. $h = 152$
9. a. $i = 20$ b. $i = 40$ c. $i = 45$ d. $i = 0$

10. **a.** $j = 40$ **b.** $j = 36$ **c.** $j = 0$ **d.** $j = 4$

11. **a.** $k = 5$ **b.** $k = 125$ **c.** $k = 35$ **d.** $k = 75$

12. **a.** $l = 7$ **b.** $l = 1$ **c.** $l = 15$ **d.** $l = 63$

13. **a.** $m = 17$ **b.** $m = 23$ **c.** $m = 32$ **d.** $m = 77$

14. **a.** $n = 9$ **b.** $n = 3$ **c.** $n = 303$ **d.** $n = 216$

15. **a.** $o = 16$ **b.** $o = 28$ **c.** $o = 13$ **d.** $o = 49$

16. **a.** $p = 26$ **b.** $p = 8$ **c.** $p = 44$ **d.** $p = 2$

17. $w = 4$ and $h = 6$
(There are many possible solutions for this question.)

18. **a.** 62 miles **b.** 155 miles **c.** 9.3 miles

19. 38 m

20. The values of x are between 3 and 20.

21. **a.** 109
b. 93
c. No, they would have scored 108.

22. **a.** 1255 **b.** 2485

Exercise 7.4 Simplifying expressions using like terms

1. **a.** $5a$ **b.** $14y$ **c.** $15c$ **d.** $2u$ **e.** $20e$

2. **a.** $5t$ **b.** $14ab$ **c.** $6fg$ **d.** $3e$ **e.** $7t$

3. **a.** $5f$ **b.** 0 **c.** $18x$ **d.** $12m$ **e.** $8a$

4. **a.** $25ab - 7$
b. $3y$
c. Cannot be simplified
d. $14t - 3$
e. $13r$

5. **a.** Cannot be simplified
b. $4 + 2g$
c. t
d. 0
e. $14pq$

6. **a.** $11t - 5$
b. t
c. Cannot be simplified
d. $11t - 8$
e. $4t + 3$

7. **a.** 0 **b.** 0 **c.** 0 **d.** 8

8. **a.** 7 **b.** 0 **c.** 7 **d.** $6y$

9. **a.** $5a, 35$ **b.** $9a, 63$ **c.** $4a, 28$ **d.** $10a, 70$

10. **a.** $10a, 70$ **b.** $10a, 70$ **c.** $17 + 8a, 73$
d. $5a + 2, 37$

11. **a.** $2a, 14$ **b.** $a, 7$ **c.** $0, 0$
d. $17a - 16, 103$

12. **a.** True **b.** True **c.** False
d. True **e.** False

13. **a.** False **b.** True **c.** True
d. False **e.** True

14. **a.** True **b.** True **c.** False
d. False **e.** True

15. E

16. B

17. C

18. D

19. C

20. A

21. D

22. **a.** True **b.** False **c.** False

23. **a.** True **b.** False **c.** True

24. **a.** False **b.** True **c.** True

25. $10x$

26. $6d$

27. **a.** $2L + 2W$ **b.** $2A + B$

28. $\angle COD = \angle DOE = 40°$

Exercise 7.5 Multiplying and dividing terms

1. **a.** $2a^2$ **b.** $7a^2b$ **c.** $21p^2q$
d. $6b^2cd$ **e.** $40m^{15}$

2. **a.** $12g$ **b.** $21h$ **c.** $24d$ **d.** $15z$ **e.** $30r$

3. **a.** $35t$ **b.** $12u$ **c.** $42p$
d. $21\,gy$ **e.** $22\,ht$

4. **a.** $24gx$ **b.** $70ah$ **c.** $36\,dm$
d. $15ch$ **e.** $18gx$

5. **a.** $4f$ **b.** $2h$ **c.** $5x$ **d.** $3g$ **e.** $2r$

6. **a.** 2 **b.** 2 **c.** 2 **d.** $\frac{2}{3}$ **e.** $\frac{1}{2}$

7. **a.** $\frac{6}{7}$ **b.** $\frac{2}{3}$ **c.** $\frac{1}{3}$ **d.** $\frac{1}{2}$ **e.** $\frac{2}{3}$

8. **a.** $\frac{3}{a}$ **b.** $\frac{20p^{10}q^7}{3}$ **c.** $\frac{2x^2}{3y}$
d. $\frac{5}{w}$ **e.** $\frac{1}{7xy}$

9. **a.** $3a^2$ **b.** $-4p^2$ **c.** $10x^2$ **d.** $5a^2b$

10. **a.** $-36x^2y$ **b.** $24p^2q^2$
c. $-10mn^2t^2$ **d.** $-42xy^2z^2$

11. The student's working is not correct. Factors can only be simplified when in product form. This question has addition.

12. **a.** $\frac{16axy}{9b}$
b. $\frac{16axy}{9b}$
c. The answers to parts a and b are the same.

13. The order of operations needs to be applied when dealing with algebraic expressions. Also, terms that contain more than one pronumeral should be dealt with as a single term.
The first expressions are all equivalent to $\frac{x}{yz}$ and the final two terms are equivalent to $\frac{xz}{y}$.

14. **a.** $3x^2$ **b.** $2bx$ **c.** $5(x + 3)$

15. $-\frac{4}{9}$

16. a. $P = 4 \times 9 = 36$ cm
    b. i. When $x = 2$, $A = 81 - (7 \times 7) = 32$ cm^2
    ii. When $x = 3$, $A = 81 - (6 \times 6) = 45$ cm^2
    c. $A = 81 - (9 - x)^2$ cm^2

Exercise 7.6 Number laws

1. a. True b. False c. True d. False
2. a. $w + \underline{(r + 6y)} = \underline{(w + r)} + 6y$
   b. $6t \times (4r) \times \underline{3s} = \underline{(6t \times 4r)} \times 3$
   c. $\underline{(9y + 2r)} + 3w = \underline{9y} + (2r + 3w)$
   d. $(z + 2p) + \underline{6t} = z + \underline{(2p + 6t)}$
3. a. $6t + \underline{(3w + 7v)} = \underline{3w} + (6t + 7v)$
   b. $s \times \underline{(9r \times 2c)} = 2c \times \underline{(s \times 9r)}$
   c. $(3c + w) + \underline{d} = d + \underline{(3c + w)}$
   d. $\underline{(g + 3b)} \times 2y = 2y \times \underline{(3b \times g)}$
4. a. False b. False c. True d. False
5. a. 27 b. 33. They are the same.
6. a. 21 b. 1. They are different.
7. a. 48 b. 48. They are the same.
8. a. 2 b. $\frac{1}{8}$. They are different.
9. These expressions will have different results unless $x = a$.
10. The Associative Law does hold for fractions because, just like whole numbers, they are rational numbers. You can check this by adding a number of fractions in different orders.
11. $6 \div (1 - 5 \div 7) = 21$
12. a. i. -4 ii. 2
    b. The answers are equal because of the use of the Associative Law.
13. \$47 or \$48
14. They did not start with the same number. Andrew started with 11 and Andrea started with 17.

Exercise 7.7 Expanding brackets

1. a. $3a + 6b$ b. $5x - 20z$ c. $20g + 30h$
   d. $2bc - 3ab$
2. a. $16cd - 2cq$ b. $9b^2 - 6bg$ c. $9ax + 7bx$
   d. $7kt + 21km$
3. a. $2a + 10b$ b. $5n - 8c$ c. $18c$
   d. $ax - bx + x$
4. a. $6d + 21e$ b. $18hj - 11h$ c. $4k + 20a - 12$
   d. $4x^2 + 6$
5. a. $5y + 2yz$ b. $3dx - 5x$ c. $12fu + 14u$
   d. $20n + 21hn$
6. a. $54r + 16$ b. $3t - 30$ c. $36 - 3y$ d. $5x - 16$
7. a. $9t - 43$ b. $19ry + 8r + 14$
   c. $26ty - 16ht + 6h$ d. $4r^2 + 18r + 3$
8. a. $x + 12$ b. $28hx - 32h - 18$
   c. $20x - y - 6$ d. $-14t^2 - 6$
9. a. $13x + 2y$ b. $12a - 10y + 6ay$
   c. $9cg + 18cd + dg$ d. $12dy + 3ry$
10. a. $2(x + 2)$ b. $6(x - y)$ c. $4(x + 3)$
    d. $4g(3f - 4h)$
11. Perimeter = 99.2 cm
12. Sample responses are given.
    a. $3a(4b + 2) = 12ab + 6a$
    b. $4n(9k + 2) = 36nk + 8n$
13. If x is a negative integer, then $-5x$ will be a positive integer. Adding this positive integer to 1 will result in another positive integer. The result will be positive.
14. $4(4c - 8a)$, $8(2c - 4a)$ and $16(c - 2a)$
15. a. $2y - x$ b. Both expressions equal 4.
16. a. $\$(50 - d)$
    b. i. Sale price $(P) = 3(50 - d)$
    ii. $P = 150 - 3d$
    c. Amount of change $(C) = 200 - (150 - 3d) = 50 + 3d$

Project

1.

Measurements	Garden bed 1	Garden bed 2	Garden bed 3
Side length of the garden bed (m)	1	2	3
Area of the garden bed (m^2)	1	4	9
Number of pavers used	8	12	16
Total length around the outside of pavers (m)	12	16	20

2. $a = s \times s$, $l = 4s + 8$, $p = 4s + 4$, $p = l - 4$
3. 44
4. 68

Exercise 7.8 Review questions

1. a. $7g$ b. $6y$ c. $9h$ d. $5ag$ e. $3gy$
2. a. 0 b. $5y$ c. $7t + 6$
   d. $18gh$ e. $11t - 2m$
3. a. $4m$ b. $15g + 12$ c. $4h + 4t$
   d. $10b + 7c$ e. $8axy$
4. a. $10x$, 50 b. $5x - 4$, 21
   c. $23x$, 115 d. $3x$, 15
5. a. $x + 16$, 21 b. $8x + 7$, 47
   c. $11 + 7x$, 46 d. $6x$, 30
6. a. $7m - 21k$ b. $gw + 9aw$ c. $16hy - 14y$
7. a. $70mr - 20mp$ b. $6ag + 6cg$ c. $24jx - 12jy$
8. a. $2t - 10s$ b. $4a + 10g$ c. $3df + 7d$

9. **a.** $15z - 4az$ **b.** $3fp - 6pq + 7p$
c. $10ab + 65b$

10. In this question, the order of the terms is important.
a. $a + (3b + 5c) = (a + 3b) + 5c$
b. t

11. In this question, the order of the terms is important.
a. $(d \times 3y) \times z = d \times (3y \times z)$
b. $\left(\frac{a}{b} \times c\right) \times f = \frac{a}{b}(c \times f)$

12. In this question, the order of the terms is important.
a. $g + (3m + 2k) = (2k + g) + 3m$
b. $(w + 5g) + 4r = 4r + (5g + w)$

13. In this question, the order of the terms is important.
a. $\frac{2}{3} \times (2d + r) = (r \times 2d) \times \frac{2}{3}$
b. $(3z + 5b) \times 6m = 3z \times (6m \times 5b)$

14. **a.** $M - C$ or $C - M$ **b.** $\$3B$
c. XY **d.** $G + 15$
e. $D + 1$ **f.** $12H$ cents
g. $5T$

15. **a.** $35x + 18$ **b.** 1068

16. **a.** False **b.** True **c.** True

17. **a.** $21g^2$ **b.** $18xy^2$ **c.** $42a^3d$ **d.** $-24yz^3$

18. **a.** $2m$ **b.** x **c.** $\frac{1}{3}$ **d.** $\frac{t}{2}$ **e.** $\frac{7}{3t}$

19. **a.** $15kt$ **b.** $\frac{4m}{9n}$ **c.** $-\frac{4f^2}{d}$ **d.** $\frac{3a}{4b}$ **e.** $3k$

20. **a.** $12p^3q$ **b.** $7xy$ **c.** $\frac{7b}{a}$ **d.** $\frac{12x}{y^3}$

21. $5y + 20$

22. **a.** $m + 8$ **b.** $m - 5$ **c.** $3m$ **d.** $3m + 3$

23. $x \times \frac{1}{x} = 1$

24. $\$\frac{3x + 4y}{20} = \frac{3x}{20} + \frac{y}{5}$


25. $\$\frac{5x - 36}{8}$

Semester review 1

The learnON platform is a powerful tool that enables students to complete revision independently and allows teachers to set mixed and spaced practice with ease.

Student self-study

Review the **Course Content** to determine which topics and subtopics you studied throughout the year. Notice the green bubbles showing which elements were covered.



Review your results in **My Reports** and highlight the areas where you may need additional practice.





Use these and other tools to help identify areas of strengths and weakness and target those areas for improvement.

Teachers


It is possible to set questions that span multiple topics. These assignments can be given to individual students, to groups or to the whole class in a few easy steps.

Go to **Menu** and select **Assignments** and then **Create Assignment**. You can select questions from one or many topics simply by ticking the boxes as shown below.





Once your selections are made, you can assign to your whole class or subsets of your class, with individualised start and finish times. You can also share with other teachers.



More instructions and helpful hints are available at www.jacplus.com.au.

8 Equations

LEARNING SEQUENCE

8.1 Overview 396
8.2 Introduction to equations 398
8.3 Building up expressions and backtracking 404
8.4 Solving equations using backtracking 410
8.5 Solving equations using inverse operations 417
8.6 Checking solutions 426
8.7 Review 431



8.1 Overview

Why learn this?



We use equations to write sentences and information containing mathematical symbols and algebra. Many everyday situations can be represented by equations. Most likely you have been solving equations without even realising it. For example, if you pay for an item that costs $4.25 and you hand a $5.00 note to the shop assistant, you will expect to receive 75 cents in change. This answer is obtained using an equation. Solving equations means finding the numbers you didn't originally know.

Understanding how to solve equations is one of the most useful skills you will learn in algebra. To work out which mobile phone plan gives the best value requires you to solve equations. If you are travelling overseas to a country that uses a different currency, you can use the exchange rate and equations to work out the cost of an item in Australian dollars. The computer chips used in washing machines, dryers, laptops, cars and other items are based on mathematical equations and algorithms. Equations are also put to use in traffic control systems, space programs, aircraft, medicine and in many other areas. Scientists, architects, engineers and accountants are just some of the people who use algebra and equations frequently in their work.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 8.1 Pre-test

learnON


Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. Write an equation that represents the following:
   A number, x, is multiplied by 6 and the answer is 72.

2. Solve, by inspection, the equation $\frac{t}{4} = 8$.

3. A tennis team won 4 more games than it lost. If the team played 18 games, how many did they win?

4. Calculate the output number for the following flowchart.




5. MC Select which of the following is a correct step to solve for m in the equation $\frac{m}{2} = -5$.

   A. $m = 5 \times 2$ B. $m = -5 - 2$ C. $m = -5 \times 2$ D. $m = -5 + 2$ E. $m = \frac{-5}{2}$

6. When 4 is added to a number and the result is doubled, it gives a value of 16. Determine the number.

7. If 5 less than a number divided by 4 gives a result of 3, determine the number.

8. MC In order, identify the steps required to backtrack the following to x.



   A. -5 then $\div 3$ B. -5 then $\times -3$ C. $+5$ then $\div 3$ D. $+5$ then $\times -3$ E. -3 then $\div 5$

9. MC I think of a number, add 5 to it and then multiply the result by 3. I then divide this result by 2. The final value is 21. Select the expression that describes these steps.

   A. $\frac{5(x+3)}{2} = 21$ B. $\frac{3(x+5)}{2} = 21$ C. $\frac{3(x+5)}{3} = 21$ D. $\frac{3(x-5)}{2} = 21$ E. $\frac{2(x-3)}{2} = 21$

10. Kyle is 5 years older than Noah. If the sum of their ages is 29, calculate Noah's age.

11. Use backtracking to solve $4x - 5 = 7$.

12. Simplify the equation $8x - 15 - 3x - 7 = 28$ and then solve using backtracking.

13. The sum of three consecutive even numbers is 84. Determine the lowest number.

14. In a class of 27 students there are 5 more boys than girls. Calculate the number of boys.

15. A triangle has side lengths of x, $4x + 3$ and $5x - 7$, and a perimeter of 51 cm. Determine the value of x.

8.2 Introduction to equations


LEARNING INTENTION

At the end of this subtopic you should be able to:
- write an equation to represent a worded problem
- solve equations by inspection
- solve equations using trial and error.


8.2.1 Equations

eles-4012

- **Equations** are mathematical statements that say two expressions are equal.
- For a mathematical statement to be classified as an equation it must contain an equals sign (=).
- The expression on the left of the equals sign is called the left-hand side (LHS).
- The expression on the right of the equals sign is called the right-hand side (RHS).
- The statement $x + 45 = 50$ is an example of an equation because it contains an equals sign. The left-hand side is $x + 45$ and the right-hand side is 50.



This logic puzzle uses 4 different equations. Can you solve the final equation?



Equations

- An equation is a mathematical statement containing an equals sign (=).
- The LHS of an equation is always equal to (has the same value as) the RHS of the equation.

Writing an equation from words

- Mathematical equations can be created based on words or sentences.
- Some English words can be changed into mathematical operations.
  - Words such as *sum, more than, increased, add* or *added* refer to addition and can be replaced with a plus sign (+).
  - Words such as *difference, less than, decreased* or *minus* refer to subtraction and can be replaced with a minus sign (−).
  - Words such as *product, multiply* or *times* refer to multiplication and can be replaced with a multiplication sign (×).
  - Words such as *quotient* or *divide* refer to division and can be replaced with a division sign (÷).

WORKED EXAMPLE 1 Writing an equation for a worded problem

Write an equation to represent each of these worded problems.

a. When I multiply a number by 8, the answer is 24.
b. When I divide a number by 5, the answer is 7.
c. When I divide 60 by a number, the answer is 10.
d. When I subtract 7 from a number, the answer is 25.
e. When a number is increased by 9, the answer is 35.
f. When I square a number, the result is 36.

THINK	WRITE
a. 1. Use a pronumeral to describe the number.	**a.** Let m be the number.
2. Multiply the number by 8 to form the LHS of the expression.	LHS $= m \times 8 = 8m$
3. Write the RHS of the expression.	RHS $= 24$
4. Write the equation by writing that the LHS is equal to the RHS.	$8m = 24$
b. 1. Use a pronumeral to describe the number.	**b.** Let t be the number.
2. Divide the number by 5 to form the LHS of the expression.	LHS $= t \div 5 = \frac{t}{5}$
3. Write the RHS of the expression.	RHS $= 7$
4. Write the equation by writing that the LHS is equal to the RHS.	$\frac{t}{5} = 7$
c. 1. Use a pronumeral to describe the number.	**c.** Let s be the number.
2. Divide 60 by the number to form the LHS of the expression.	LHS $= 60 \div s = \frac{60}{s}$
3. Write the RHS of the expression.	RHS $= 10$
4. Write the equation by writing that the LHS is equal to the RHS.	$\frac{60}{s} = 10$
d. 1. Use a pronumeral to describe the number.	**d.** Let l be the number.
2. Subtract 7 from the number (that is, take 7 away from the number) to form the LHS of the expression.	LHS $= l - 7$
3. Write the RHS of the expression.	RHS $= 25$
4. Write the equation by writing that the LHS is equal to the RHS.	$l - 7 = 25$
e. 1. Use a pronumeral to describe the number.	**e.** Let a be the number.
2. The word *increased* refers to addition. To increase the number a by 9, add 9 to it.	LHS $= a + 9$
3. Write the RHS of the expression.	RHS $= 35$
4. Write the equation by writing that the LHS is equal to the RHS.	$a + 9 = 35$
f. 1. Use a pronumeral to describe the number.	**f.** Let z be the number.
2. Square the number (that is, multiply the number by itself) to form the LHS of the expression.	LHS $= z \times z = z^2$
3. Write the RHS of the expression.	RHS $= 36$
4. Write the equation by writing that the LHS is equal to the RHS.	$z^2 = 36$

8.2.2 Solving an equation by inspection

eles-4013

- To solve an equation you must determine the value of the pronumeral that makes the LHS of the equation equal to the RHS.
- Some basic equations can be solved by **inspection**. This process involves determining the answer by simply inspecting (or looking at) the equation.

WORKED EXAMPLE 2 Solving an equation by inspection

Solve the following equations by inspection.


a. $\frac{w}{3} = 4$ **b.** $h - 9 = 10$

THINK	WRITE
a. 1. Write the equation.	**a.** $\frac{w}{3} = 4$
2. Think of a number that, when divided by 3, gives 4. Try 12.	$12 \div 3 = 4$
3. Based on this, w must be 12.	$w = 12$
b. 1. Write the equation.	**b.** $h - 9 = 10$
2. Think of a number that equals 10 when 9 is subtracted from it. Try 19.	$19 - 9 = 10$
3. Based on this, h must be 19.	$h = 19$

8.2.3 Guess, check and improve

eles-4014

- Sometimes equations cannot be solved easily by inspection.
- In these cases, one possible method that could be used is called 'guess, check and improve'.
- For example, you can solve $4x + 6 = 46$ using the following method.



Solve $4x + 6 = 46$			
Guess	**Check**		**Improve**
$x = 3$	LHS $= 4 \times 3 + 6$ $= 18$	RHS $= 46$	$x = 3$ makes the LHS too small. Since x appears on the LHS only, choose a larger value for x to make the LHS larger.
$x = 11$	LHS $= 4 \times 11 + 6$ $= 50$	RHS $= 46$	$x = 11$ makes the LHS too large, but closer than before. Choose a value for x that is less than 11 but greater than 3.
$x = 10$	LHS $= 4 \times 10 + 6$ $= 46$	RHS $= 46$	LHS = RHS, so $x = 10$ is the solution.

WORKED EXAMPLE 3 Solving an equation by guess, check and improve

Use guess, check and improve to solve the equation $2x + 21 = 4x - 1$.

THINK

1. Set up a table with 4 columns displaying the value of x, the value of the LHS and RHS equations (after substitution) and a comment on how these two values compare to the equation.
2. Substitute the first guess, say $x = 1$, into the LHS and RHS equations and comment on the results.
3. Repeat step **2** for the other guesses until the correct answer is found.
4. Write the answer.

WRITE

	Check		
Guess x	**$2x + 21$**	**$4x - 1$**	**Comment**
1	23	3	$4x - 1$ is too small.
6	33	23	This is closer.
10	41	39	Very close.
11	43	43	That's it!

The answer is $x = 11$.

WORKED EXAMPLE 4 Using guess and check to determine unknown numbers

Use guess, check and improve to determine two numbers whose sum is 31 and whose product is 150.

THINK

1. The numbers add up to 31, so guess 2 numbers that do this. Then check by finding their product.
2. Guess 1 and 30, then calculate the product.
3. Guess 10 and 21, then calculate the product.
4. Try other numbers between 1 and 10 for the first number. Determine the product of the two numbers.
   Stop when the product of the two numbers is 150.
5. Write the answer.

WRITE

Guess the sum (small number first)	Check the product (P)	Comment
1 and 30	$1 \times 30 = 30$	P is too low.
10 and 21	$10 \times 21 = 210$	P is too high.
5 and 26	$5 \times 26 = 130$	P is too low.
8 and 23	$8 \times 23 = 184$	P is too high.
6 and 25	$6 \times 25 = 150$	That's it!

The two numbers that add up to 31 and have a product of 150 are 6 and 25.

on Resources

eWorkbook Topic 8 Workbook (worksheets, code puzzle and project) (ewbk-1909)

Digital documents SkillSHEET Completing number sentences (doc-6571)
SkillSHEET Writing number sentences from written information (doc-6572)
SkillSHEET Applying the four operations (doc-6573)

Interactivities Individual pathway interactivity: Solving equations using trial and error (int-4372)
Writing equations (int-4041)
Guess, check and improve (int-4042)

Exercise 8.2 Introduction to equations

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 8, 11, 14	2, 5, 9, 12, 15	3, 7, 10, 13, 16, 17

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 Write an equation to represent each of these worded problems.
   a. When I add 7 to a number, the answer is 11.
   b. When I add 12 to a number, the answer is 12.
   c. When I subtract 7 from a number, the answer is 1.
   d. When I subtract 4 from a number, the answer is 7.

2. Write an equation to represent each of these worded problems.
   a. When I multiply a number by 2, the answer is 12.
   b. When I multiply a number by 5, the answer is 30.
   c. When I divide a number by 7, the answer is 1.
   d. When I divide a number by 5, the answer is 2.

3. Write an equation to represent each of these worded problems.
   a. When I subtract a number from 15, the answer is 2.
   b. When I subtract a number from 52, the answer is 8.
   c. When I divide 21 by a number, the answer is 7.
   d. When I square a number, the answer is 100.

4. WE2 Solve the following equations by inspection.
   a. $x + 7 = 18$ b. $y - 8 = 1$ c. $3m = 15$ d. $\frac{m}{10} = 3$

5. Solve the following equations by inspection.
   a. $\frac{k}{5} = 0$ b. $b + 15 = 22$ c. $b - 2.1 = 6.7$ d. $\frac{c}{3} = 1.4$ e. $5x = 14$

Understanding

6. WE3 Use guess, check and improve to solve the following equations.
   a. $3x + 11 = 5x - 1$ b. $5x + 15 = x + 27$ c. $x + 20 = 3x$

7. Use guess, check and improve to solve the following equations.
   a. $12x - 18 = 10x$ b. $6(x - 2) = 4x$ c. $3(x + 4) = 5x + 4$

8. WE4 Use guess, check and improve to find two numbers whose sum and product are given:
   a. sum = 21, product = 98 b. sum = 26, product = 165
   c. sum = 54, product = 329 d. sum = 178, product = 5712

9. Use guess, check and improve to find two numbers whose sum and product are given:
   a. sum = 153, product = 4662 b. sum = 242, product = 14 065
   c. sum = 6.1, product = 8.58 d. sum = 978, product = 218 957

10. Copy and complete this table by substituting each x-value into $x^2 + 4$ and $4x + 1$. The first row has been completed for you. Use the table to determine a solution to the equation $x^2 + 4 = 4x + 1$. (Remember, x^2 means $x \times x$.)

x	$x^2 + 4$	$4x + 1$
0	4	1
1		
2		9
3	13	
4		

Reasoning

11. Explain the thought process you would use to determine the solution to $8x = 48$ by inspection.

12. Explain why the inspection method is not suitable to solve the equation $5x = 34$.

13. Annisa is trying to find the solution to the equation $3x - 7 = 17$ using the guess and check method. Her first guess is $x = 5$, which is not the solution. Should her next guess be greater than or less than 5?

Problem solving

14. A football team won four more games than it lost. The team played 16 games. Determine how many games the team won.



15. A plumber cut a 20-metre pipe into two pieces. One of the pieces is three times as long as the other. Determine the lengths of the two pieces of pipe.

16. Lily is half the age of Pedro. Ross is 6 years older than Lily and 6 years younger than Pedro. Determine Pedro's age.

17. Angus and his grandfather share a birthday. Both their ages are prime numbers. Angus's age has the same two digits as Grandpa's but in reverse order. In 10 years' time, Grandpa will be three times as old as Angus. Determine how old both Grandpa and Angus will be in 10 years.



8.3 Building up expressions and backtracking

LEARNING INTENTION

At the end of this subtopic you should be able to:
- complete a flowchart to determine the output
- construct a flowchart from a given expression.


8.3.1 Flowcharts

eles-4016

- A flowchart is useful for keeping track of the steps in a sequence.




- In the preceding diagram, the instructions for each step are written above the arrows that join the boxes.
  - The first box shows what you start with.
  - The box in the middle shows what happens along the way as you complete the steps.
  - The last box shows what you finish with.
- Flowcharts can be used to keep track of expressions as operations are performed on them.
- In the following flowchart, the starting number is 8. This is called the **input number**. Performing the operations in the order displayed results in 1, the number in the last box. This is called the **output number**.




WORKED EXAMPLE 5 Completing a flowchart

Build up an expression by following the instructions on these flowcharts.

a.



b.



THINK


a. **1.** The instruction above the first arrow says × 3. The result is $m \times 3 = 3m$.

2. The instruction above the second arrow says + 5. Adding 5 to $3m$ gives the result $3m + 5$.

3. State the expression (output).

WRITE

a.




The expression is $3m + 5$.

b. 1. The instruction above the first arrow says $+5$. Adding 5 to m gives the result $m+5$.

2. The instruction above the second arrow says $\times 3$. That means multiply all of $m+5$ by 3. The result is $3(m+5)$.

3. State the expression (output).

b.



The expression is $3(m+5)$.

WORKED EXAMPLE 6 Drawing a flowchart

Draw a flowchart whose input number is m and whose output number is given by the following expressions.

a. $2m-11$ **b.** $\dfrac{m+9}{5}$ **c.** $4\left(\dfrac{m}{3}+2\right)$

THINK

a. 1. The first step is to obtain $2m$. Do this by multiplying m by 2.

2. Next, subtract 11.

b. 1. The expression $m+9$ is grouped as though it is in a pair of brackets, so we must work out this part first. This means we add 9 to m first.


2. Next, the whole expression is divided by 5.

c. 1. The brackets indicate we must first work from within the brackets, so:
- divide m by 3
- then add 2 to the result.


2. Multiply the result obtained in step 1 by 4.

WRITE


a.



b.



c.



8.3.2 Backtracking

eles-4017

- **Backtracking** is a method used to work backwards through a flowchart. It involves moving from the output towards the input.
- When working backwards through a flowchart, use **inverse** (or **opposite**) **operations**.
- A list of operations and their inverses (opposites) is highlighted in the following box.

Inverse operations


− is the inverse operation of +

+ is the inverse operation of −

÷ is the inverse operation of ×

× is the inverse operation of ÷


- Examine the following flowchart and the operations that were applied to the input to produce the output (working left to right). These are shown in purple.
- Using backtracking we can identify the opposite operations that need to be applied when working backwards through the flowchart. These are shown in pink.



- Being able to backtrack through a flowchart is an important skill for solving equations, as shown later in this topic.

WORKED EXAMPLE 7 Backtracking a flowchart


Complete the following flowchart by writing in the operations that need to be carried out in order to backtrack to x.





THINK

1. Copy the flowchart and look at the operations that have been performed.
   Starting from the input, two operations have been performed: a multiplication by 5 and then the number 2 has been added.
2. Starting with the output, work backwards towards the input using inverse operations.
   The inverse operation of + 2 is − 2. Show this on the bottom of the flowchart by adding an arrow pointing towards the left (input).
3. The inverse operation of × 5 is ÷ 5. Show this on the flowchart at the bottom, with an arrow pointing towards the left (input).

WRITE








COLLABORATIVE TASK: Secret numbers

1. Think of a number by yourself and write it in your workbook. Don't tell anyone! Multiply your number by 4 and write down the answer. Next, add 20 and write down the answer. Then divide by 2 and write down the answer. Finally, subtract 5 and write down the answer.
2. As a class, write the flowchart for these instructions on the board.
3. Show how the flowchart works for different starting numbers.
4. Work out some of your classmates' secret numbers by working backwards through the flowchart.



Resources

eWorkbook Topic 8 Workbook (worksheets, code puzzle and project) (ewbk-1909)
Interactivities Individual pathway interactivity: Building up expressions (int-4374)
Flowcharts (int-4044)

Exercise 8.3 Building up expressions and backtracking

learnON


Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 3, 7, 10, 13, 16	2, 5, 8, 11, 14, 17	4, 6, 9, 12, 15, 18, 19


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE5 Build up an expression by following the instructions on these flowcharts.

a.



b.


c.



d.


2. Build up an expression by following the instructions on these flowcharts.


a.




b.



c.




d.




3. Build up an expression by following the instructions on the flowcharts. Use brackets or fractions as a grouping device, for example, $2(x+3)$ or $\frac{x-5}{4}$.


a.




b.



c.




d.




4. Build up an expression by following the instructions on the flowcharts. Use brackets or fractions as a grouping device, for example, $2(x+3)$ or $\frac{x-5}{4}$.


a.




b.



c.




d.




5. Copy and complete the following flowcharts by filling in the missing expressions.


a.




b.



c.




d.




6. Copy and complete the following flowcharts by filling in the missing expressions.


a.




b.



c.



d.



Understanding

7. WE6 Draw a flowchart whose input number is x and whose output is given by the following expressions.

a. $5x + 9$ **b.** $2(x + 1)$ **c.** $\frac{x - 8}{7}$

8. Draw a flowchart whose input number is x and whose output is given by the following expressions.


a. $12(x - 7)$ **b.** $\frac{x}{5} - 2$ **c.** $\frac{x + 6}{3}$

9. Draw a flowchart whose input number is x and whose output is given by the following expressions.


a. $3(x + 7) - 5$ **b.** $\frac{3x + 7}{2}$ **c.** $4(3x + 1)$

10. WE7 Complete the following flowcharts by writing in the operations that must be carried out in order to backtrack to x.


a.



b.




c.




11. Add the operations to complete these flowcharts.


a.




b.



c.




d.




12. Add the operations to complete these flowcharts.


a.




b.



c.



d.




Reasoning

13. Starting from p, the expression $2(p - 3)$ is built using the operations $\times 2$ and -3. Identify which operation should be performed first.

14. I think of a number and add 8 to it. I multiply the result by 5 and then divide the result by 4. The answer is 30. Use a flowchart to build up an expression and write these steps in the form of an equation.

15. I think of a number, multiply it by 5 and add 15. The result is 3 less than 4 times the original number. If the original number is n, write an equation to show the relation. Show all your working.



Problem solving

16. Rachel and Jackson are 7 years apart in age. Jackson is older than Rachel. The sum of their ages is 51. Determine Rachel's age.

17. The sum of two numbers is 32 and their product is 247. Determine the two numbers.

18. Marcus and Melanie pooled their funds and purchased shares on the stock exchange. Melanie invested $350 more than Marcus. Together they invested $2780. Determine how much money Marcus invested.

19. The equation $1+2+3+4+5+6+7+8+9=100$ is clearly incorrect. By removing some + signs, including some − signs and combining some of the digits to make larger numbers, see if you can make the equation correct. Remember, only + and − signs are allowed and the equation must equal 100.
One example is shown below. Determine as many other possible solutions as you can, showing full working.

$$123+45-67+8-9=100$$

8.4 Solving equations using backtracking

LEARNING INTENTION

At the end of this subtopic you should be able to:
- solve equations using backtracking.

8.4.1 Using backtracking to solve equations

eles-4018


- Most simple equations can be solved by inspection, but sometimes it is hard to see the solution immediately.
- Backtracking is a process that can be used to solve equations. It can be used for simple equations, or more complicated equations.

Solving equations using backtracking


To solve an equation using backtracking, follow these steps.
1. Use a flowchart to build up the equation.
2. Work backwards through the flowchart using inverse operations to determine the solution.

- For example, if we are asked to solve the equation $2x+9=23$, we must first build up the equation and then use backtracking to determine the solution.

Build up the equation



Backtrack to determine the solution



- The solution of the equation $2x+9=23$ is $x=7$.
- We can also check that we have found the correct answer by substitution.
That is, LHS $= 2(7)+9=2\times7+9=14+9=23=$ RHS.

WORKED EXAMPLE 8 Drawing a flowchart and solving by backtracking

Draw a flowchart to represent the following worded problem and then solve it by backtracking.
I am thinking of a number. When I multiply it by 4 and then add 2, the answer is 14.


THINK


1. Build an expression using x to represent the number. Start with x, multiply by 4 and add 2. The output number is 14.

2. Backtrack to determine the value of x.
   - The inverse operation of $+2$ is -2 $(14 - 2 = 12)$.
   - The inverse operation of $\times 4$ is $\div 4$ $(12 \div 4 = 3)$.

3. Write the solution.

WRITE





The solution is $x = 3$. Therefore the number is 3.

WORKED EXAMPLE 9 Solving equations by backtracking

Solve the following equations by backtracking.

a. $3(x + 7) = 24$

b. $\frac{x}{3} + 5 = 6$

THINK


a. 1. Build the expression on the left-hand side of the equation. Start with x, then add 7 and then multiply by 3. The output number is 24.


2. Backtrack to determine the value of x.
   - The inverse operation of $\times 3$ is $\div 3$ $(24 \div 3 = 8)$.
   - The inverse operation of $+7$ is -7 $(8 - 7 = 1)$.

3. Write the solution.

WRITE

a.







The solution for the equation is $x = 1$.

b. 1. Build the expression on the left-hand side of the equation. Start with x, then divide by 3 and then add 5. The output number is 6.

b.



2. Backtrack to determine the value of x.
- The inverse operation of $+5$ is -5, so subtract -5 from 6 ($6 - 5 = 1$).
- The inverse operation of $\div 3$ is $\times 3$, so multiply 1 by 3 ($1 \times 3 = 3$).



3. Write the solution.

The solution for the equation is $x = 3$.

WORKED EXAMPLE 10 Simplifying and solving equations by backtracking

Simplify and then solve the following equation by backtracking.
$5x + 13 + 2x - 4 = 23$

THINK

1. Simplify by adding the like terms together on the left-hand side of the equation. $5x + 2x = 7x$, $13 - 4 = 9$


2. Draw a flowchart and build the left-hand side of the equation $7x + 9$. Start with x, multiply by 7 and add 9. The output number is 23.


3. Backtrack to determine the value of x.
- The inverse operation of $+9$ is -9, so subtract 9 from 23 ($23 - 9 = 14$).
- The inverse operation of $\times 7$ is $\div 7$, so divide 14 by 7 ($14 \div 7 = 2$).

4. Write the solution.

WRITE

$5x + 13 + 2x - 4 = 23$
$7x + 9 = 23$





The solution for the equation is $x = 2$.

COLLABORATIVE TASK: Think of a number

In pairs, discuss and investigate Mel's 'think of a number' puzzle, which is described below.



Mel loves playing 'Think of a number' with friends. Here's an example of one of her puzzles.

- Think of a number.
- Double it.
- Add 10.
- Divide by 2.
- Take away the number you first thought of.
- Your answer is … 5!

Let's investigate to see why the answer is always 5, whatever number you first think of. We can form expressions for each of the steps, using a variable as the starting value.

• Think of a number.	n
• Double it.	$n \times 2 = 2n$
• Add 10.	$2n + 10$
• Divide by 2.	$(2n + 10) \div 2 = n + 5$
• Take away the number you first thought of.	$n + 5 - n = 5$
• Your answer is...	5

As you can see, the answer will always be 5 for any starting number.

Now you try

1. Write expressions for each step in the following, showing that you can determine the answer in each case.

a. Puzzle 1: Your birth year

- Take the year in which you were born.
- Subtract 500.
- Multiply by 2.
- Add 1000.
- Divide by 2.
- Your answer is … your birth year!

b. Puzzle 2: Your age

- Take your age (in years).
- Add 4.
- Multiply by 10.
- Subtract 10.
- Divide by 5.
- Subtract your age.
- Take away 6.
- Your answer will be your age!

c. Puzzle 3: Think of a number…

- Think of a number.
- Divide it by 2.
- Add 2.
- Multiply by 4.
- Take away your original number.
- Subtract your original number again.
- Your answer should be …

2. Write some 'Think of a number' puzzles yourself. Try them out on friends. They will marvel at your mystical powers!

Resources

eWorkbook	Topic 8 Workbook (worksheets, code puzzle and project) (ewbk-1909)
Digital document	SkillSHEET Combining like terms (doc-6575)
Interactivities	Individual pathway interactivity: Solving equations using backtracking (int-4375)
	Backtracking (int-4045)

Exercise 8.4 Solving equations using backtracking

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 11, 12, 15, 16	2, 5, 8, 10, 13, 17, 18, 19, 20	3, 6, 9, 14, 21, 22, 23, 24

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE8 Draw a flowchart to represent each of the following worded problems and then solve them by backtracking.
   a. When I multiply a number by 2 and then add 7 the answer is 11.
   b. When I add 3 to a number and then multiply by 5 the answer is 35.
   c. When I divide a number by 4 and then add 12 the answer is 14.
   d. When I add 5 to a number and then divide by 3 the answer is 6.
   e. When I subtract 7 from a number and then multiply by 6 the answer is 18.

2. Draw a flowchart to represent each of the following worded problems and then solve them by backtracking.
   a. When I subtract 4 from a number and then divide by 9 the answer is 7.
   b. When I divide a number by 11 and then subtract 8 the answer is 0.
   c. When I multiply a number by 6 and then add 4 the answer is 34.
   d. When I multiply a number by 5 and then subtract 10 the answer is 30.
   e. When I subtract 3.1 from a number and then multiply by 6 the answer is 13.2.

3. Draw a flowchart to represent each of the following worded problems and then solve them by backtracking.
   a. When I add $\frac{2}{5}$ to a number and then divide by 6 the answer is $\frac{4}{5}$.
   b. When I subtract $\frac{3}{4}$ from a number and then divide by $\frac{2}{3}$ the answer is $\frac{1}{6}$.

4. Draw a flowchart and use backtracking to determine the solution to the following equations.
   a. $5x + 7 = 22$
   b. $9y - 8 = 1$
   c. $4x + 12 = 32$
   d. $8w + 2 = 26$
   e. $4w + 5.2 = 28$

5. WE9a Solve the following equations by backtracking.
   a. $3(x + 7) = 24$
   b. $2(x - 7) = 22$
   c. $11(x + 5) = 99$
   d. $6(x + 9) = 72$
   e. $4(w + 5.2) = 26$

6. WE9b Solve the following equations by backtracking.
   a. $\frac{x}{3} + 5 = 6$
   b. $\frac{x}{9} - 2 = 3$
   c. $\frac{x}{2} - 11 = 6$
   d. $\frac{x}{7} - 5 = 6$
   e. $\frac{x}{5} + 2.3 = 4.9$

Understanding

7. Solve the following equations by backtracking.

a. $\frac{x+4}{3}=6$ **b.** $\frac{x-8}{7}=10$ **c.** $\frac{x+11}{2}=6$

d. $\frac{x-5}{7}=0$ **e.** $\frac{x+2.21}{1.4}=4.9$

8. Use backtracking to find the solution to the following equations.

a. $3x-7=23$
b. $4(x+7)=40$
c. $\frac{x}{5}-2=8$
d. $5(x-3)=15$
e. $6(x-4)=18$

9. Use backtracking to find the solution to the following equations.


a. $\frac{x}{2.1}-1.7=3.6$
b. $\frac{x+5}{3}-3=7$
c. $4(x-2)+5=21$
d. $3\left(\frac{x}{2}+1\right)=15$
e. $2(3x+4)-5=15$

10. **WE10** Simplify and then solve the following equations by backtracking.


a. $2x+7+3x+5=27$
b. $3x+9+x-4=17$
c. $3x+5x+2x=40$
d. $6x+6-x-4=37$
e. $7x-4x+8-x=10$

11. **MC** The correct flowchart required to solve the equation $6x+5=8$ is:


A.




B.




C.



D.




E.



Reasoning

12. Based on the scales in the diagram, identify the operations you need to apply to find the value of x. Calculate the value of x.



13. Chloe wrote the following explanation to solve the equation $3(x-6)+5=8$ by the backtracking method:
To solve this equation, work backwards and do things in the reverse order.
First add 5*, then subtract* 6*, then finally multiply by* 3.
Explain why her instructions are not correct.

14. The equation $4x-20=8$ can be solved using backtracking by adding 20, then dividing by 4. Explain whether the equation could also be solved by dividing by 4 first.

Problem solving

15. Kevin is 5 years older than his brother Gareth. The sum of their ages is 31 years. Determine Gareth's age, letting x represent Gareth's age. Show your working.

16. The sum of three consecutive whole numbers is 51. Determine the numbers. (*Hint:* Let the smallest number equal x.)

17. Melanie and Callie went tenpin bowling together. Melanie scored 15 more pins than Callie. Their total score was 207. Determine what Callie scored.

18. The sum of three consecutive odd numbers is 27. Determine the 3 numbers.

19. The sum of 3 consecutive odd numbers is 39. Determine the 3 numbers.

20. In the high jump event Chris leapt 12 centimetres higher than Tim. Their two jumps made a total of 3 metres. Determine how high Chris jumped.

21. In three basketball games Karina has averaged 12 points each game. In the first game she scored 11 points. In the second she scored 17 points. In the third game she scored x points.



a. From the given information, calculate the average of 11, 17 and x.
b. Write an equation using the answer to part **a**.
c. Solve the equation.
d. State how many points Karina scored in the third game.

22. Three consecutive multiples of 5 add up to 90. Determine the 3 numbers.

23. David is 5 years younger than his twin brothers. If the sum of their ages is 52, then how old is David?

24. Using the six consecutive numbers from 4 to 9, complete the magic square shown so that each row, column and diagonal totals 15.

	1	
3		
		2

8.5 Solving equations using inverse operations

LEARNING INTENTION


At the end of this subtopic you should be able to:
- solve equations using the balancing method
- solve equations using inverse operations.

8.5.1 Keeping equations balanced

eles-4019


- A balance scale can be used to show whether things have equal mass.

If two pans have the **same mass**, then the two sides are side to be **balanced** or equal.



Equal


If the two pans are **different in mass**, then the two sides are said to be **unbalanced or unequal**.



Not equal


Any change that is made to **one side** must also be made to the **other side** to maintain the balance.

If we **double** what is on the **LHS**, we must **double** the amount on the **RHS**.




Equal

If we **add** 3 to the **LHS**, we must also add 3 to the **RHS**.



Equal

- For example, the scale in this diagram can be described by the equation $x + 3 = 7$.
- Making changes to both sides of the scale lets you work out how many weights are in the bag (the value of the pronumeral).
- If we remove 3 weights from each side of the scale, we can see that the bag with x weights in it weighs the same as 4 weights. That means $x = 4$.



Equal

WORKED EXAMPLE 11 Applying operations to keep an equation balanced

Apply the given operation to the LHS and RHS of the following equations to maintain the balance between both sides.

a. $x + 2 = 5$ **[multiply both sides by 3]**
b. $2x = 8$ **[add 2 to both sides]**
c. $5x = 15$ **[subtract 2 from both sides]**
d. $4x = 16$ **[divide both sides by 4]**

THINK	WRITE
a. 1. Write the equation.	**a.** $x + 2 = 5$
2. Multiply the LHS and RHS of the equation by 3.	$3(x + 2) = 5 \times 3$
3. Write the answer by simplifying both sides.	$3x + 6 = 15$
b. 1. Write the equation.	**b.** $2x = 8$
2. Add 2 to the LHS and RHS of the equation.	$2x + 2 = 8 + 2$
3. Write the answer by simplifying both sides.	$2x + 2 = 10$
c. 1. Write the equation.	**c.** $5x = 15$
2. Subtract 2 from the LHS and RHS of the equation.	$5x - 2 = 15 - 2$
3. Write the answer by simplifying both sides.	$5x - 2 = 13$
d. 1. Write the equation.	**d.** $4x = 16$
2. Divide the LHS and RHS of the equation by 4	$\frac{4x}{4} = \frac{16}{4}$
3. Write the answer by simplifying both sides.	$x = 4$


8.5.2 Solving equations using balancing

eles-4020

- The balancing method can be used to solve equations.
- The solution to the equation can be found by removing weights from the scales until one side contains the pronumeral only.

WORKED EXAMPLE 12 Solving an equation by keeping equations balanced

For the following balance scale:
a. write the equation represented by the scale
b. calculate the value of the pronumeral.



THINK

a. 1. Examine the balance scale. On the LHS there are 2 bags with h weights in each, and 2 weights outside the bags. On the RHS there are 8 weights.


2. Write this as an equation.

b. 1. Remove 2 weights from both sides so that the balance will be maintained (−2). This leaves 2 bags on the LHS and 6 weights on the RHS.

2. To work out the value of h (the value of 1 bag), divide both sides by 2 and then simplify.


WRITE

a.




$2h + 2 = 8$

b.



$2h + 2 - 2 = 8 - 2$

$2h = 6$



$\frac{(2h)}{2} = \frac{6}{2}$

$h = 3$


Each bag is equivalent to 3 weights.
That means $h = 3$.

8.5.3 Solving equations using inverse operations

eles-4021

- Both backtracking and the balance method of solving equations use inverse operations to calculate the value of an unknown.
- For example, the equation $2q + 3 = 11$ can be solved as follows.


Backtracking



The equivalent equations made when backtracking are:

$$2q + 3 = 11$$
$$2q = 8$$
$$q = 4$$


Balance method



Equal

$$2q + 3 = 11$$


Remove three counters from both sides (-3).



Equal

$$2q + 3 - 3 = 11 - 3$$
$$2q = 8$$

Halve the contents on each side ($\div 2$).



Equal

$$\frac{2q}{2} = \frac{8}{2}$$
$$q = 4$$

- Both methods are equivalent, and use inverse operations to simplify the LHS of the equation until only the pronumeral remains.
- The operations that solve the equation and the order in which they are performed are the same.
- The equivalent equations created on the way to the solution are the same.
- The aim is to isolate the unknown value on one side of the equation.
- The last operation that was performed on the unknown value when building the equation is the first operation that is undone.

How to solve equations using inverse operations

- To solve an equation using inverse operations:
  1. determine the operations used to build the expression containing the pronumeral
  2. apply the inverse operations in reverse order to both sides of the equation.
- You can use a flowchart or a written list to determine the operations and their inverse.

Note: Building up expressions was covered in subtopic 8.3.

WORKED EXAMPLE 13 Using inverse operations

Use inverse operations to solve the following equations.

a. $2y + 3 = 11$

b. $\frac{h}{5} + 1 = 3$

c. $2(k - 4) = 4$

THINK	WRITE
a. 1. Write the equation.	$2y + 3 = 11$
2. Note that on the LHS, y is multiplied by 2 and 3 is added to it. Apply inverse operations to: • remove 3 by subtracting 3 from both sides first • divide both sides by 2 to remove 2.	$2y + 3 - 3 = 11 - 3$ $2y = 8$ $\frac{2y}{2} = \frac{8}{2}$
3. Simplify.	$y = 4$
4. Write the solution.	The solution for the equation is $y = 4$.
b. 1. Write the equation.	$\frac{h}{5} + 1 = 3$
2. Note that on the LHS, h is divided by 5 and 1 is added to it. Apply inverse operations to: • remove 1 by subtracting 1 from both sides first • multiply both sides by 5 to remove 5.	$\frac{h}{5} + 1 - 1 = 3 - 1$ $\frac{h}{5} = 2$ $\frac{h}{5} \times 5 = 2 \times 5$
3. Simplify.	$h = 10.$
4. Write the solution.	The solution for the equation is $h = 10$.
c. 1. Write the equation.	$2(k - 4) = 4$
2. Note that on the LHS, 2 is multiplied by $k - 4$ and 4 is subtracted from k. Apply inverse operations to: • remove 2 by dividing both sides by 2 first • add 4 to both sides to remove −4.	$\frac{2(k-4)}{2} = \frac{4}{2}$ $k - 4 = 2$ $k - 4 + 4 = 2 + 4$
3. Simplify.	$k = 6.$
4. Write the solution.	The solution for the equation is $k = 6$.

- When solving equations, the solution may be a fraction or decimal.

WORKED EXAMPLE 14 Solving equations with non-integer solutions

Solve the following equations.

a. $5d = 4$ **b.** $3c + 1 = 6$

THINK	WRITE
a. 1. Write the equation.	$5d = 4$
2. Note that on the LHS, d is multiplied by 5. Apply inverse operation to: • remove 5 by dividing both sides by 5.	$\frac{5d}{5} = \frac{4}{5}$
3. Simplify.	$d = \frac{4}{5}$
4. State the solution.	The solution for the equation is $d = \frac{4}{5}$.
b. 1. Write the equation.	$3c + 1 = 6$
2. Note that on the LHS, c is multiplied by 3 and 1 is added to it. Apply inverse operations to: • remove 1 by subtracting 1 from both sides first • divide both sides by 3 to remove 3.	$3c + 1 - 1 = 6 - 1$ $3c = 5$ $\frac{3c}{3} = \frac{5}{3}$
3. Simplify.	$c = \frac{5}{3}$
4. Write the solution.	The solution for the equation is $c = \frac{5}{3}$ or $c = 1\frac{2}{3}$.

eles-4022

8.5.4 Solving equations by making the pronumeral positive

- When an equation includes a pronumeral that is being subtracted (for example, $28 - 3x = 7$), an effective way to solve the equation is to add the pronumeral part to both sides first, then solve as normal using balancing or backtracking.

WORKED EXAMPLE 15 Solving equations by making the pronumeral positive

Solve the following equations.

a. $5 - v = 2$ **b.** $17 - 2a = 11$

THINK	WRITE
a. 1. Undo the subtraction of v by adding v to both sides and simplify.	**a.** $5 - v = 2$ $5 - v + v = 2 + v$ $5 = 2 + v$
2. To isolate v, subtract 2 from both sides and simplify.	$5 - 2 = 2 + v - 2$ $3 = v$
3. State the solution.	$v = 3$

b. **1.** Undo subtracting $2a$ by adding $2a$ to both sides and simplify.

2. The last operation performed on the RHS when building $17 = 11 + 2a$ was $+11$. Subtract 11 from both sides and simplify.

3. To isolate a, divide both sides by 2 and simplify.

4. State the solution.

b.
$$17 - 2a = 11$$
$$17 - 2a + 2a = 11 + 2a$$
$$17 = 11 + 2a$$
$$17 - 11 = 11 + 2a - 11$$
$$6 = 2a$$
$$\frac{6}{2} = \frac{2a}{2}$$
$$3 = a$$
$$a = 3$$

COLLABORATIVE TASK: How many was that?

Work in pairs to answer the following questions and then share your ideas with others in your class.



1. A farmer told two friends that they could pick peaches from his tree but that they must not take more than 30 peaches each. They worked for a while, and then the taller one asked her friend, 'Have you picked your limit yet?'
He replied, 'Not yet, but if I had twice as many as I have now, plus half as many as I have now, I would have reached my limit.'
How many peaches did he have?



2. Your aunt from overseas sent an enormous box of chocolates for your mother's birthday. You were told not to eat any of the chocolates. Nevertheless, over the next five days you sneaked into the pantry when your mother was out and ate some of the chocolates. Each day you ate six more than the day before. After five days you were caught and your mother found out that you had eaten 100 chocolates. Your mother was extremely cross!
How many chocolates did you eat on *each* of the five days?

on Resources

eWorkbook Topic 8 Workbook (worksheets, code puzzle and project (ewbk-1909)

Interactivities Individual pathway interactivity: Keeping equations balanced (int-4377)
Keeping equations balanced (int-4047)
Equations with rational number solutions (int-4048)
Negative integers (int-4049)

Exercise 8.5 Solving equations using inverse operations

learnON

Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 9, 14, 17	2, 4, 7, 10, 13, 15, 18	5, 8, 11, 12, 16, 19, 20, 21

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE11 Apply the given operations to the LHS and RHS of the following equations to maintain the balance of the two sides.
   - a. $x + 3 = 6$ [multiply both sides by 3]
   - b. $3x = 15$ [subtract 2 from both sides]
   - c. $4x + 12 = 24$ [divide both sides by 4]


2. WE12 For each of the following balance scales:
   - i. write the equation represented by the scale
   - ii. calculate the value of the pronumeral.

a.


Equal

b.


Equal

c.


Equal

3. WE13 Use inverse operations to solve the following.
   - a. $3g + 7 = 10$
   - b. $4m - 6 = 6$
   - c. $\frac{q}{3} + 8 = 11$

4. Use inverse operations to solve the following.
   - a. $5b - 2 = 8$
   - b. $2z + 13 = 37$
   - c. $\frac{v}{4} + 31 = 59$

5. Use inverse operations to solve the following.
   - a. $2(n - 5) = 8$
   - b. $\frac{g - 2}{4} = 3$
   - c. $4(y + 1) = 16$

6. WE14 Solve the following equations.
   - a. $3h = 7$
   - b. $2k = 5$
   - c. $2w + 1 = 8$

7. Solve the following equations.
   - a. $3t - 4 = 9$
   - b. $6h - 3 = 10$
   - c. $3l + 4 = 8$

8. Solve the following equations.
   - a. $5g + 3 = 11$
   - b. $3h - 10 = 1$
   - c. $8n - 4 = 0$

Understanding

9. WE15 Solve the following equations.
   - a. $6 - m = 2$
   - b. $4 - d = 1$
   - c. $12 - 3v = 6$

10. Solve the following equations.

a. $13 - 2s = 7$ **b.** $19 - 3g = 4$ **c.** $30 - 5k = 20$

11. Solve the following equations.

a. $2(x + 3) = 11$ **b.** $p + 3 = 6\frac{1}{4}$ **c.** $7 - x = 5$

12. Solve the following equations.

a. $3(5 - y) = 12$ **b.** $5(8 - 2h) = 15$ **c.** $2(x + 3) = 7$

13. The formula $C = \frac{5(F - 32)}{9}$ is used to convert degrees Fahrenheit to degrees Celsius. Use the formula to find:

a. 45° Fahrenheit in degrees Celsius **b.** 45° Celsius in degrees Fahrenheit.

Reasoning

14. A taxi company charges a $3.60 flag fall (a fixed fee before the journey starts). An additional $2.19 per km is charged for the journey.

a. Calculate the cost of a 4.6 km journey.

b. If the journey cost $110.91, determine the distance travelled.

15. While shopping for music online, Olivia found an album she liked. She could buy the whole album for $17.95 or buy songs from the album for $1.69 each. Determine the number of individual songs Olivia could buy to make it cheaper to buy the whole album.

16. Explain why the order of inverse operations is important, using the equation $2x + 3 = 15$ as an example. In your explanation, use balanced scales to represent the equation.


Problem solving

17. A class of 25 students has 7 more boys than girls. Determine how many boys there are.




18. When 12 is subtracted from 7 times a number, the result is 9. Create an equation that represents this statement, then solve your equation to determine the number.

19. Given that the perimeter of the following triangle is 22 cm, calculate the value of x.



20. A number x becomes the fifth number in the set of numbers $\{3, 7, 9, 13\}$ to make the mean of the five members equal to their median. Determine all possible positive values for x.

21. These scales show that two bricks are equal to 2 kilograms plus half a brick. Determine the weight of each brick.



8.6 Checking solutions

LEARNING INTENTION

At the end of this subtopic you should be able to:
- check the solution of an equation using substitution.

8.6.1 Checking solutions by substituting

eles-4023

- Once the solution to an equation has been determined, the method of **substitution** can be used to check whether that solution is correct.
- Substitution involves:
  - replacing the pronumeral with the numerical value of the solution
  - simplifying the equation to determine the value of the LHS and RHS of the equation.
- If the LHS = RHS after substitution, then the solution is correct.



WORKED EXAMPLE 16 Checking solutions by substitution

For each of the following equations, use substitution to determine whether $x = 7$ is the solution to the equation.

a. $\frac{x+5}{3} = 4$ **b.** $2x - 8 = 10$

THINK	WRITE
a. 1. Write the equation.	**a.** $\frac{x+5}{3} = 4$
2. Write the LHS of the equation and substitute $x = 7$.	If $x = 7$, LHS $= \frac{x+5}{3}$ $= \frac{7+5}{3}$
3. Perform the calculation.	$= \frac{12}{3}$ $= 4$
4. Compare the LHS with the RHS of the equation.	LHS $= 4$, RHS $= 4$
5. Comment on the answer.	Since LHS = RHS, $x = 7$ is the solution.
b. 1. Write the equation.	**b.** $2x - 8 = 10$
2. Write the LHS of the equation and substitute $x = 7$.	If $x = 7$, LHS $= 2x - 8$ $= 2(7) - 8$
3. Perform the calculation.	$= 14 - 8$ $= 6$
4. Compare the LHS with the RHS of the equation.	LHS $= 6$, RHS $= 10$
5. Comment on the answer.	$x = 7$ is not the solution, since LHS $\neq$ RHS.

Digital technology

Scientific calculators can be used to check solutions by substitution. Replace pronumerals with the desired value in brackets.

For example, the solution to the equation $3x - 15 = 12$ is $x = 9$.



WORKED EXAMPLE 17 Verifying solutions by substitution

A solution is given for each equation below. Verify whether the solution is correct.

a. $\dfrac{x+2}{3} = 2x - 12, x = 10$ **b.** $3x - 7 = 2x + 3, x = 10$

THINK	WRITE
a. 1. Write the equation.	**a.** $\dfrac{x+2}{3} = 2x - 12$
2. Write the LHS of the equation and substitute $x = 10$.	If $x = 10$, LHS $= \dfrac{x+2}{3}$ $= \dfrac{10+2}{3}$
3. Perform the calculation.	$= \dfrac{12}{3} = 4$
4. Write the RHS of the equation and substitute $x = 10$.	If $x = 10$, RHS $= 2x - 12$ $= 2(10) - 12$
5. Perform the calculation.	$= 20 - 12 = 8$
6. Comment on the answer.	$x = 10$ is not the solution, since LHS $\neq$ RHS.
b. 1. Write the equation.	**b.** $3x - 7 = 2x + 3$
2. Write the LHS of the equation and substitute $x = 10$.	If $x = 10$, LHS $= 3x - 7$ $= 3(10) - 7$
3. Perform the calculation.	$= 30 - 7 = 23$
4. Write the RHS of the equation and substitute $x = 10$.	If $x = 10$, RHS $= 2x + 3$ $= 2(10) + 3$
5. Perform the calculation.	$= 20 + 3 = 23$
6. Comment on the answer.	Since LHS = RHS, $x = 10$ is the correct solution.

on Resources

eWorkbook	Topic 8 Workbook (worksheets, code puzzle and project) (ewbk-1909)
Digital document	SkillSHEET Checking solutions by substitution (doc-6576)
Interactivities	Individual pathway interactivity: Checking solutions (int-4376) Checking solutions (int-4046)

Exercise 8.6 Checking solutions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 10, 13	2, 7, 8, 11, 14	3, 5, 9, 12, 15

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE16 Use substitution to determine whether each of the following is correct.
   a. $x = 3$ is the solution to the equation $x + 2 = 6$
   b. $x = 3$ is the solution to the equation $2x - 1 = 5$
   c. $x = 4$ is the solution to the equation $6x - 6 = 24$

2. Use substitution to determine whether each of the following is correct.
   a. $x = 5$ is the solution to the equation $4(x - 3) = 8$
   b. $x = 7$ is the solution to the equation $3(x - 2) = 25$
   c. $x = 8$ is the solution to the equation $5(x + 1) = 90$

3. Use substitution to determine whether each of the following is correct.
   a. $x = 81$ is the solution to the equation $3x - 53 = 80$
   b. $x = 2.36$ is the solution to the equation $5x - 7 = 4.8$
   c. $x = 4.4$ is the solution to the equation $7x - 2.15 = 18.64$.

4. WE17 Verify whether the solution given for each of the following equations is correct.
   a. $5x + 1 = 2x - 7, x = 8$ b. $5x = 2x + 12, x = 4$ c. $4x = 3x + 8, x = 8$

5. Verify whether the solution given for each of the following equations is correct.
   a. $3x - 1.2 = x + 2.9, x = 1.9$ b. $6x + 1.5 = 2x + 41.5, x = 10$
   c. $1.2(x + 1.65) = 0.2(x + 9.85), x = 0.45$

Understanding

6. Complete the following table to determine the value of $2x + 3$ when $x = 0, 1, 2, 3, 4$.

x	0	1	2	3	4
$2x + 3$					

   a. Identify the solution (that is, the value of x) for $2x + 3 = 11$.
   b. Identify the solution (that is, the value of x) for $2x + 3 = 5$.

7. Complete the following table to determine the value of $5(x - 2)$ when $x = 2, 3, 4, 5, 6$.

x	2	3	4	5	6
$5(x - 2)$					

   a. Identify the solution (that is, the value of x) for $5(x - 2) = 10$.
   b. Identify the solution (that is, the value of x) for $5(x - 2) = 20$.
   c. Guess the solution (that is, the value of x) to $5(x - 2) = 30$. Check your guess.

8. a. Copy and complete the following table.

x	$2x+1$	$3x-5$
3		
4		
5		10
6		
7		

b. Identify the solution to $2x+1=3x-5$.

9. a. Copy and complete the following table.


x	$\frac{x+3}{2}$	$2x-6$
3	3	
5		
7		8
9		
11		

b. Identify the solution to $\frac{x+3}{2}=2x-6$.

Reasoning

10. Substitution is a method used to check that a solution to an equation is correct. Explain how you could use substitution to answer a multiple choice question that has potential solutions as the options.

11. Consider the diagram shown.



a. Explain whether you need to know both the length and width of this rectangle to be able to calculate the value of y.

b. Calculate the value of y.

c. Explain how you would check the solution.

12. Carol is making a quilt for her granddaughter. The quilt pattern requires that $\frac{1}{7}$ of the quilt is made of a pink fabric. Carol has $0.5\ m^2$ of pink fabric. She intends to use all the pink material in the quilt.

Calculate how much more fabric she needs for the entire quilt.



a. Write an equation for this problem.

b. Calculate the value of the unknown variable.

c. Check your solution.

Problem solving


13. James and Alison share $125 between them, but Alison gets $19 more than James. Create an equation to describe this situation. Calculate how much money James and Alison each receive.

14. Aiko and Miyu are sisters who receive pocket money based on their age. Their parents pay them according to the equation $\$P = 3x - 25$, where $\$P$ represents their weekly pocket money and x is their age in years.

- **a.** Determine at what age Aiko and Miyu start receiving pocket money.
- **b.** Miyu is 2 years older than Aiko. Determine how much more pocket money Miyu receives each week compared to her sister. (Assume the sisters are both old enough to be receiving pocket money.)
- **c.** When Aiko is 11 years old, calculate how much pocket money each child receives.

15. Ivan is trying to find the solution to the equation $n + (n + 1) + (n + 2) = 393$. He believes the solution is $n = 133$.

- **a.** Show that Ivan is incorrect.
- **b.** Determine the correct solution, and prove that it is the solution using substitution.
- **c.** Write a worded problem that this equation represents.



8.7 Review

8.7.1 Topic summary

EQUATIONS

What is an equation?

- An equation is a mathematical statement that says two expressions are equal.

e.g. $7x + 9 = 23$ is an example of an equation.

- The left-hand side (LHS) is $7x + 9$.
- The right-hand side (RHS) is 23.
- This equation states that the LHS and the RHS are equal (have the same value).

Developing an equation from words

- When developing an equation from words, some English phrases or words can be turned into mathematical symbols.

e.g.

- Words such as *sum*, *more than*, *increased*, *add* or *added* imply addition and can be replaced with +.
- Words such as *difference*, *less than*, *decreased* or *minus* imply subtraction and can be replaced with −.
- Words such as *product* or *times* imply multiplication and can be replaced with ×.
- Words such as *quotient* or *divide* imply division and can be replaced with ÷.


Solving equations

- Solving an equation is the process of finding pronumeral values to make the equation true.
  e.g. The equation $7x + 9 = 23$ is true only when $x = 2$.
  Hence, the solution of the equation is $x = 2$.
- Equations can be solved using many different techniques.

Building expressions using flowcharts

- Flowcharts can be used to build an expression from words, steps, instructions or operations.
- In a flowchart, the starting number or position is the *input* and the final number or position is the *output*.

e.g.



Solving equations using guess, check and improve

- Solving equations using the guess, check and improve method involves selecting a number for the pronumeral that you think might be a solution to the equation.
- Use substitution to check whether your guess is correct or not.
- After checking your guess, make improvements to your chosen number by either increasing or decreasing it until you find the solution.

e.g. For $2x + 5 = 11$
Guess: $x = 2$
Check: LHS $= 2(2) + 5 = 4 + 5 = 9 \neq$ RHS
Improve: Try $x = 3$
LHS $2(3) + 5 = 6 + 5 = 11 =$ RHS
Solution is $x = 3$.

Inverse operations


- Inverse (or opposite) operations are often used to help solve equations.

+ is the inverse operation of −
− is the inverse operation of +
× is the inverse operation of ÷
÷ is the inverse operation of ×

Solving equations using backtracking

- Backtracking uses inverse operations to determine the solution of an equation by moving backwards through a flowchart.

e.g. Solving $7x + 9 = 23$ using backtracking gives:



Solution is $x = 2$.



Solving equations using balancing

- By performing the same operation on *both* sides of an equation, it remains balanced.
- Equations can be solved using inverse operations with balancing, that is, applying an inverse operation to both sides of the equation.

e.g. $x - 20 = 12$
$x - 20 + 20 = 12 + 20$
$x = 32$

8.7.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
8.2	I can write an equation to represent a worded problem.			
	I can solve equations by inspection.			
	I can solve equations using trial and error.			
8.3	I can complete a flowchart to determine the output.			
	I can construct a flowchart from a given expression.			
8.4	I can solve equations using backtracking.			
8.5	I can solve equations using the balancing method.			
	I can solve equations using inverse operations.			
8.6	I can check the solution of an equation using substitution.			

8.7.3 Project


Equations at the Olympic Games

The Olympic Games is held every four years between competing nations from all over the world. You might know that Sydney was the host city for the 2000 Olympic Games. A feature of this international sporting event is that records continue to be broken. Every Olympic Games sees competitors run faster, lift heavier weights, and so on. The desire to become better urges competitors to train harder in the hope that they will become record holders.

This project looks at running times for the men's and women's 100-metre running events. The running times for these events can be approximated using the following equations:

- Men's 100-metre event $t = -0.0094y + 28.73$
- Women's 100-metre event $t = -0.0173y + 45.31$

where t represents the running time (in seconds) and y represents the year.



For example, the men's time in 1996 can be approximated by substituting 1996 into the equation as shown.

$$\begin{aligned} t &= -0.0094y + 28.73 \\ &= -0.0094 \times 1996 + 28.73 \\ &= 9.9676 \text{ seconds} \end{aligned}$$

1. Use the equations provided to calculate the men's and women's running times for the 100-metre event in the following years.
   a. 1928 **b.** 1968 **c.** 1988 **d.** 2016
2. The following table shows the winners and their running times for the 100-metre event final at four Olympic Games events. How well do these actual results compare with the times you calculated using the equations? What does this say about the equations?

Year	Men's winner	Time taken (seconds)	Women's winner	Time taken (seconds)
1928	Percy Williams	10.80	Elizabeth Robinson	12.20
1968	James Hines	9.95	Wyomia Tyus	11.08
1988	Carl Lewis	9.92	Florence Griffith Joyner	10.54
2016	Usain Bolt	9.81	Elaine Thompson	10.71

3. Predict the times for both men and women at the 2024 Olympic Games.



When making predictions about the future, we must remember that these predictions are based on the assumption that the patterns we observe now will continue into the future.

Your answers to question 1 show you that men have historically run faster times than women in the 100-metre event. However, closer inspection of the times shows that women are making greater improvements in their times over the years.

4. If running times continue to follow these patterns in future Olympic Games, decide whether it is possible that women's times will become equal to men's times. Discuss your answer.
5. Suggest reasons that running times are getting shorter. Do you think they will follow this pattern forever?

on Resources

eWorkbook Topic 8 Workbook (worksheets, code puzzle and project) (ewbk-1909)

Interactivities Crossword (int-2606)
Sudoku puzzle (int-3173)

Exercise 8.7 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Solve these equations by inspection.


a. $m + 7 = 12$ **b.** $5h = 30$ **c.** $s - 12 = 7$ **d.** $\frac{d}{5} = 4$

2. Use guess, check and improve to find two numbers whose sum and product are given.


a. sum = 83, product = 1632 **b.** sum = 86, product = 1593

3. Calculate the output number for each of the following flowcharts.


a.




b.



c.




d.




4. Use backtracking and inverse operations to calculate the input number for each of the following flowcharts.


a.




b.



c.




d.




5. Build up an expression by following the instructions on the flowchart.


a.




b.



c.




d.




6. Build up an expression by following the instructions on the flowchart.

a.



b.



7. Draw a flowchart that has an input of x and an output that is given by the expressions below.

a. $5(x+7)$ **b.** $\frac{x}{4}-3$ **c.** $6x-14$ **d.** $\frac{x+2}{5}$

8. Draw a flowchart and use backtracking to calculate the solution to the following equations.

a. $7x+6=20$ **b.** $9(y-8)=18$ **c.** $\frac{m}{5}-3=9$ **d.** $\frac{s+7}{5}=5$

9. Use backtracking to determine the solution to these equations.

a. $3(d+1)=15$ **b.** $\frac{t}{4}-11=14$ **c.** $6d-3=15$ **d.** $\frac{a+6}{4}=3$

10. Simplify the expression and then solve the equation for each of the following.

a. $7v+3+3v+4=37$ **b.** $6c+15-5c-8=19$

11. For each of the following equations there is a solution given. Is the solution correct?


a. $5x-7=2x+2,\ x=3$ **b.** $\frac{x+9}{2}=2x-7,\ x=5$

12. For each of the following balance scales:

i. write the equation represented by the scale


ii. calculate the value of the pronumeral.

a.




Equal

b.



Equal

c.



Equal

13. Use inverse operations to solve the following equations.

a. $2v+1=7$ **b.** $\frac{x}{2}+3=4$ **c.** $4w-3=9$ **d.** $2(g+1)=10$

14. Solve the following equations. Make sure you check your solutions.

a. $4k+3=10$ **b.** $2p-3=8$ **c.** $3q+6=7$ **d.** $5t+1=3$

15. Solve the following equations. Make sure you check your solutions.

a. $3-x=1$ **b.** $7-2p=3$ **c.** $10-4r=2$ **d.** $13-3z=7$

Problem solving

16. Sophie and Jackie each have a collection of football cards. Jackie has 5 more cards than Sophie. Together Jackie and Sophie have 67 cards. Create and solve an equation that shows how many cards Sophie owns.



17. Andreas has completed 2 more pieces of homework than Richard, who submitted x pieces of homework for the semester. If the total number of pieces of homework submitted by the two boys is 12, determine how many pieces of homework Andreas submitted.

18. Keith is 6 years younger than his twin brothers. If the sum of the brothers' ages is 48, determine Keith's age.

19. Margaret bought six 2-hour tickets and four daily tickets for $28. If the cost of one daily ticket is $4, write and solve an equation to calculate the cost of a 2-hour ticket.

20. Jetski hire is $10 per hour, plus a $30 deposit.

a. Calculate the cost of hiring a jetski for:

i. 1 hour **ii.** 2 hours **iii.** 3 hours.

b. Write a rule that could be used to calculate the cost of hiring a jetski for h hours.

c. Use your rule to calculate the cost of hiring a jetski for 8 hours.

d. You have $85 to spend. Write an equation to help you work out how many hours of jetski hire you can afford. Solve this equation.

e. Work out how much money (if any) you would have left over after you paid the hire charge and hire the jetski for 5 hours.

f. After spending 5 hours on the water you return the jetski with no damage. Explain whether you would have enough money for a hamburger on the way home.



21. Suppose it costs $30 for an adult and $15 for a child to enter the Sydney Royal Easter Show.

a. Calculate the entry cost for two adults and three children.

b. Calculate the entry cost for one adult and five children.

c. Determine the maximum number of children who could get into the Show for $100.

d. Identify the possible combinations of adults and children that could get in for exactly $300.



22. Judy is watching her daughter play in the park. She notices that some children are riding tricycles and some are riding bicycles. Altogether, 19 children are on cycles. She counts that there are 43 wheels on the cycles. Determine how many children are on tricycles and how many are on bicycles.

23. Two angles in a triangle have the same magnitude. The sum of the magnitudes of these angles is the magnitude of the third angle. Determine the magnitudes of the angles and use this information to describe the triangle in this scenario.

24. A stage screen is 4 times as long as it is wide. If it were 5 metres wider and 4 metres shorter it would be a square. Determine the dimensions of the stage screen.



25. The largest angle in a triangle is 65 degrees more than the smallest angle. The third angle is 10 degrees more than the smallest angle. Calculate the size of the smallest angle.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1909) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0697) ☐

Digital documents

8.2 SkillSHEET Completing number sentences (doc-6571) ☐
SkillSHEET Writing number sentences from written information (doc-6572) ☐
SkillSHEET Applying the four operations (doc-6573) ☐
8.4 SkillSHEET Combining like terms (doc-6575) ☐
8.6 SkillSHEET Checking solutions by substitution (doc-6576) ☐

Video eLessons

8.2 Equations (eles-4012) ☐
Solving an equation by inspection (eles-4013) ☐
Guess, check and improve (eles-4014) ☐
8.3 Flowcharts (eles-4016) ☐
Backtracking (eles-4017) ☐
8.4 Using backtracking to solve equations (eles-4018) ☐
8.5 Keeping equations balanced (eles-4019) ☐
Solving equations using balancing (eles-4020) ☐
Solving equations using inverse operations (eles-4021) ☐
Solving equations by making the pronumeral positive (eles-4022) ☐
8.6 Checking solutions by substituting (eles-4023) ☐

Interactivities

8.2 Individual pathway interactivity: Solving equations using trial and error (int-4372) ☐
Writing equations (int-4041) ☐
Guess, check and improve (int-4042) ☐
8.3 Individual pathway interactivity: Building up expressions (int-4374) ☐
Flowcharts (int-4044) ☐
8.4 Individual pathway interactivity: Solving equations using backtracking (int-4375) ☐
Backtracking (int-4045) ☐
8.5 Individual pathway interactivity: Keeping equations balanced (int-4377) ☐
Keeping equations balanced (int-4047) ☐
Equations with rational number solutions (int-4048) ☐
Negative integers (int-4049) ☐
8.6 Individual pathway interactivity: Checking solutions (int-4376) ☐
Checking solutions (int-4046) ☐
8.7 Crossword (int-2606) ☐
Sudoku puzzle (int-3173) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au.**

Answers

Topic 8 Equations

Exercise 8.1 Pre-test

1. $6x = 72$
2. 32
3. 11 games
4. 4
5. C
6. 4
7. 32
8. A
9. B
10. 12 years old
11. $x = 3$
12. $x = 10$
13. 26
14. 16 boys
15. 5.5 cm

Exercise 8.2 Introduction to equations

1. a. $x + 7 = 11$ b. $x + 12 = 12$
   c. $x - 7 = 1$ d. $x - 4 = 7$
2. a. $2x = 12$ b. $5x = 30$
   c. $\frac{x}{7} = 1$ d. $\frac{x}{5} = 2$
3. a. $15 - x = 2$ b. $52 - x = 8$
   c. $\frac{21}{x} = 7$ d. $x^2 = 100$
4. a. $x = 11$ b. $y = 9$
   c. $m = 5$ d. $m = 30$
5. a. $k = 0$ b. $b = 7$
   c. $b = 8.8$ d. $c = 4.2$
   e. $x = 2.8$
6. a. $x = 6$ b. $x = 3$ c. $x = 10$
7. a. $x = 9$ b. $x = 6$ c. $x = 4$
8. a. 7 and 14 b. 11 and 15
   c. 7 and 47 d. 42 and 136
9. a. 42 and 111 b. 97 and 145
   c. 2.2 and 3.9 d. 347 and 631
10.


x	$x^2 + 4$	$4x + 1$
0	4	1
1	5	5
2	8	9
3	13	13
4	20	17

    $x = 1$ and $x = 3$ are both solutions.
11. Think of the 8 times table. Determine which multiple of 8 is equal to 48. $6 \times 8 = 48$, so the answer is $x = 6$.
12. 34 does not appear in the 5 times table. Therefore the solution will not be a whole number.
13. Greater than 5
14. 10
15. 5 metres, 15 metres
16. 24 years old
17. Angus will be 27 and his grandfather will be 81.


Exercise 8.3 Building up expressions and backtracking

1. a. $\xrightarrow{\times 5}$ $\boxed{x}$ $\xrightarrow{\boxed{5x}}$ $\xrightarrow{-2}$ $\boxed{5x - 2}$
   b. $\xrightarrow{\div 3}$ $\boxed{x}$ $\xrightarrow{\boxed{\frac{x}{3}}}$ $\xrightarrow{+1}$ $\boxed{\frac{x}{3} + 1}$
   c. $\xrightarrow{\times 2}$ $\boxed{x}$ $\xrightarrow{\boxed{2x}}$ $\xrightarrow{+7}$ $\boxed{2x + 7}$
   d. $\xrightarrow{\div 5}$ $\boxed{x}$ $\xrightarrow{\boxed{\frac{x}{5}}}$ $\xrightarrow{+11}$ $\boxed{\frac{x}{5} + 11}$
2. a. $\xrightarrow{\times \frac{1}{2}}$ $\boxed{x}$ $\xrightarrow{\boxed{\frac{x}{2}}}$ $\xrightarrow{-3}$ $\boxed{\frac{x}{2} - 3}$
   b. $\xrightarrow{\div 8}$ $\boxed{x}$ $\xrightarrow{\boxed{\frac{x}{8}}}$ $\xrightarrow{-2}$ $\boxed{\frac{x}{8} - 2}$
   c. $\xrightarrow{\div 7}$ $\boxed{x}$ $\xrightarrow{\boxed{\frac{x}{7}}}$ $\xrightarrow{+9}$ $\boxed{\frac{x}{7} + 9}$
   d. $\xrightarrow{\times 3.1}$ $\boxed{x}$ $\xrightarrow{\boxed{3.1x}}$ $\xrightarrow{+1.8}$ $\boxed{3.1x + 1.8}$
3. a. $\xrightarrow{+5}$ $\boxed{x}$ $\xrightarrow{\boxed{x + 5}}$ $\xrightarrow{\times 4}$ $\boxed{4(x + 5)}$
   b. $\xrightarrow{+10}$ $\boxed{x}$ $\xrightarrow{\boxed{x + 10}}$ $\xrightarrow{\div 3}$ $\boxed{\frac{x + 10}{3}}$
   c. $\xrightarrow{-2}$ $\boxed{x}$ $\xrightarrow{\boxed{x - 2}}$ $\xrightarrow{\div 7}$ $\boxed{\frac{x - 2}{7}}$
   d. $\xrightarrow{+3}$ $\boxed{x}$ $\xrightarrow{\boxed{x + 3}}$ $\xrightarrow{\times 9}$ $\boxed{9(x + 3)}$


4. a.




b.




c.




d.




5. a.




b.




c.




d.




6. a.




b.




c.




d.




7. a.




b.




c.




8. a.




b.




c.




9. a.




b.




c.




10. a.




b.




c.




11. a.




b.




c.




d.




12. a.




b.



c.



d.



13. -3 should be performed first, then $\times 2$.

14. $\frac{5(x+8)}{4} = 30$

15. $5n + 15 = 4n - 3$

16. 22 years old

17. The two numbers are 19 and 13.

18. $1215

19. Some examples are:
$12 + 3 - 4 + 5 + 67 + 8 + 9 = 100$
$123 + 4 - 5 + 67 - 89 = 100$
$123 - 45 - 67 + 89 = 100$

Exercise 8.4 Solving equations using backtracking

1. a. 2 **b.** 4 **c.** 8 **d.** 13 **e.** 10

2. a. 67 **b.** 88 **c.** 5 **d.** 8 **e.** 5.3

3. a. $4\frac{2}{5}$ **b.** $\frac{31}{36}$

4. a. $x = 3$ **b.** $y = 1$ **c.** $x = 5$
d. $w = 3$ **e.** $w = 5.7$

5. a. $x = 1$ **b.** $x = 18$ **c.** $x = 4$
d. $x = 3$ **e.** $w = 1.3$

6. a. $x = 3$ **b.** $x = 45$ **c.** $x = 34$
d. $x = 77$ **e.** $x = 13$

7. a. $x = 14$ **b.** $x = 78$ **c.** $x = 1$
d. $x = 5$ **e.** $x = 4.65$

8. a. $x = 10$ **b.** $x = 3$ **c.** $x = 50$
d. $x = 6$ **e.** $x = 7$

9. a. $x = 11.13$ **b.** $x = 25$ **c.** $x = 6$
d. $x = 8$ **e.** $x = 2$

10. a. $x = 3$ **b.** $x = 3$ **c.** $x = 4$
d. $x = 7$ **e.** $x = 1$

11. A

12. First subtract 2 from both sides, then divide both sides by 4; $x = 2$.

13. Inverse operations must be performed in the reverse order. The forward order is: First subtract 6, then multiply by 3 and finally add 5. The reverse order is: Subtract 5, divide by 3, then add 6.

14. Yes. Dividing both sides by 4 gives $x - 5 = 2$. By then adding 5 to both sides, the solution $x = 7$ is obtained.

15. Gareth is 13 years old.

16. 16, 17 and 18

17. Callie scored 96 pins.

18. 7, 9 and 11

19. 11, 13 and 15

20. Chris jumped 156 centimetres.

21. a. 12
b. $\frac{x+28}{3} = 12$
c. $x = 8$
d. Karina scored 8 points in the third game.

22. 25, 30 and 35

23. David is 14 years old.

24.

8	1	6
3	5	7
4	9	2

Exercise 8.5 Solving equations using inverse operations

1. a. $3x + 9 = 18$ **b.** $3x - 2 = 13$ **c.** $x + 3 = 6$

2. a. **i.** $4r = 12$ **ii.** $r = 3$
b. **i.** $2n + 3 = 7$ **ii.** $n = 2$
c. **i.** $3t + 5 = 8$ **ii.** $t = 1$

3. a. $g = 1$ **b.** $m = 3$ **c.** $q = 9$

4. a. $b = 2$ **b.** $z = 12$ **c.** $v = 112$

5. a. $n = 9$ **b.** $g = 14$ **c.** $y = 3$

6. a. $h = 2\frac{1}{3}$ **b.** $k = 2\frac{1}{2}$ **c.** $w = 3\frac{1}{2}$

7. a. $t = 4\frac{1}{3}$ **b.** $h = 2\frac{1}{6}$ **c.** $l = 1\frac{1}{3}$

8. a. $g = \frac{8}{5}$ **b.** $h = \frac{11}{3}$ **c.** $n = \frac{1}{2}$

9. a. $m = 4$ **b.** $d = 3$ **c.** $v = 2$

10. a. $s = 3$ **b.** $g = 5$ **c.** $k = 2$

11. a. $x = 2\frac{1}{2}$ **b.** $p = 3\frac{1}{4}$ **c.** $x = 2$

12. a. $y = 1$ **b.** $h = 2\frac{1}{2}$ **c.** $x = \frac{1}{2}$

13. a. $7\frac{2}{9}$ °C **b.** 113 °F

14. a. $13.67 **b.** 49 km

15. 11 songs

16. The removal of the three weights from the right-hand side needs to be done before the weights on each side are halved. If the division is performed first, the odd numbers of weights on each side of the scales would have to be halved, which will not result in whole numbers.
17. 16 boys
18. 3
19. 4 cm
20. 3, 8, 13
21. $1\frac{1}{3}$ kilograms

Exercise 8.6 Checking solutions

1. a. No b. Yes c. No
2. a. Yes b. No c. No
3. a. No b. Yes c. No
4. a. No b. Yes c. Yes
5. a. No b. Yes c. No

6.

x	0	1	2	3	4
$2x + 3$	3	5	7	9	11

a. $x = 4$ b. $x = 1$

7.

x	2	3	4	5	6
$5(x - 2)$	0	5	10	15	20

a. $x = 4$ b. $x = 6$ c. $x = 8$

8. a.

x	$2x + 1$	$3x - 5$
3	7	4
4	9	7
5	11	10
6	13	13
7	15	16

b. $x = 6$

9. a.

x	$\frac{x+3}{2}$	$2x - 6$
3	3	0
5	4	4
7	5	8
9	6	12
11	7	16

b. $x = 5$

10. You could substitute all of the options into the equation and see which one makes that equation true.
11. a. No. Length is enough.
    b. 34.8m
    c. Adding 3.9 and the value of y. The answer should be 38.7m.
12. a. $\frac{1}{7}x = 0.5$ b. $x = 3.5$
13. James \$53 and Alison \$72
14. a. 9
    b. \$6
    c. Aiko \$8 , Miyu \$14
15. a. $133 + (133 + 1) + (133 + 2) = 402$
    $\neq 393$
    b. $n = 130$, $130 + (130 + 1) + (130 + 2) = 393$
    c. Sample response: The sum of three consecutive numbers is 393. What is the smallest of these numbers?


Project

1. Men's: 1928, 10.607 s; 1968, 10.231 s; 1988, 10.043 s; 2016, 9.780 s
   Women's: 1928, 11.956 s; 1968, 11.264 s; 1988, 10.918 s; 2016, 10.433 s
2. All calculated times are well within 0.4 seconds of the actual running times.
3. Using the formula: Men's time = 9.7044 s; Women's time = 10.2948 s.
4. Women's times are coming down faster than men's. It is possible only if these patterns continue.
5. Different training programs, fitter athletes, better shoes, etc. There must be some levelling out, as the times cannot keep coming down forever – it will be impossible to run 100 metres in 0 seconds.


Exercise 8.7 Review questions

1. a. $m = 5$
   b. $h = 6$
   c. $s = 19$
   d. $d = 20$
2. a. 32, 51 b. 27, 59
3. a. 11
   b. 2
   c. 16
   d. 35
4. a. 16 b. 42 c. 11 d. 8
5. a. $7x + 8$
   b. $\frac{x}{3} - 5$
   c. $6(x + 2)$
   d. $\frac{x-7}{5}$
6. a. $5(x + 3) - 9$ b. $\frac{4x + 11}{8}$


7. a.




b.



c.



d.



8. a. $x = 2$ **b.** $y = 10$ **c.** $m = 60$ **d.** $s = 18$

9. a. $d = 4$ **b.** $t = 100$ **c.** $d = 3$ **d.** $a = 6$

10. a. $v = 3$ **b.** $c = 12$

11. a. Yes **b.** No

12. a. i. $4x + 1 = 5$
ii. $x = 1$
b. i. $3p + 5 = 11$
ii. $p = 2$
c. i. $2q + 3 = 13$
ii. $q = 5$

13. a. $v = 3$ **b.** $x = 2$ **c.** $w = 3$ **d.** $g = 4$

14. a. $k = 1\frac{3}{4}$ **b.** $p = 5\frac{1}{2}$ **c.** $q = \frac{1}{3}$ **d.** $t = \frac{2}{5}$

15. a. $x = 2$ **b.** $p = 2$ **c.** $r = 2$ **d.** $z = 2$

16. Sophie owns 31 cards.

17. 7 pieces of homework

18. 12 years old

19. $2

20. a. i. $40 **ii.** $50 **iii.** $60
b. Cost $= 30 + 10h$
c. $110
d. $85 = 30 + 10h$; $h = 5.5$ hours
e. $5
f. Your deposit is returned ($30), which means you could buy a hamburger on the way home.

21. a. $105
b. $105
c. 6 children
d. 10 adults; 9 adults and 2 children; 8 adults and 4 children; 7 adults and 6 children; 6 adults and 8 children; 5 adults and 10 children; 4 adults and 12 children; 3 adults and 14 children; 2 adults and 16 children; 1 adult and 18 children; 20 children

22. 14 bicycles and 5 tricycles

23. 45°, 45°, 90°. This is a right-angled isosceles triangle.

24. Length 12 m, width 3 m

25. 35°

9 Geometry

LEARNING SEQUENCE

9.1 Overview 444
9.2 Measuring angles 447
9.3 Constructing angles with a protractor 455
9.4 Types of angles and naming angles 461
9.5 Triangles 467
9.6 Quadrilaterals and their properties 479
9.7 Parallel and perpendicular lines 489
9.8 Review 500



9.1 Overview

Why learn this?

The word geometry comes from the Greek terms *geo-* (meaning *earth*) and *metron* (meaning *measurement*). Geometry is one of the oldest areas of mathematics, and it allows us to explore our world in a very precise way. Have you ever wondered how early sailors such as Captain Cook navigated around the world? They didn't have computers to guide them. They navigated using the stars and their knowledge of geometry. The famous Greek philosopher Thales of Miletus, who lived around 600 BC, used geometry to calculate the height of the pyramids in Egypt.



The geometry we study today can be traced back to around the year 300 BC and the work of another Greek mathematician, Euclid. Builders, architects, surveyors and engineers all use their knowledge of geometry to ensure buildings are stable and visually pleasing. Navigation, both in the air and at sea, is based on geometric principles. Travel in outer space involves the use of complex geometry. Geometry is also involved in sport. You need to carefully estimate the angle required when you are shooting for a goal in hockey or football. If you have played or watched someone playing pool, you will know that understanding angles is vital to play well. Many professions, including landscape gardening and interior design, use geometry every day.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 9.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. State the type of angle that describes an angle of 125°.

2. If an analogue clock is showing 1:30 pm, determine the smaller angle between the big and small hands.




3. State how many degrees are in a right angle.

4. **MC** A reflex angle is between:
   - **A.** 45° and 180°
   - **B.** 0° and 90°
   - **C.** 90° and 120°
   - **D.** 180° and 360°
   - **E.** 0° and 45°


5. **MC** Two acute angles that sum to be an acute angle are:
   - **A.** 180° and 360°
   - **B.** 90° and 180°
   - **C.** 30° and 70°
   - **D.** 50° and 30°
   - **E.** 20° and 70°

6. **MC** An analogue clock is showing 4 am. The obtuse and reflex angles that the big and small hands make respectively are:
   - **A.** 90° and 180°
   - **B.** 240° and 120°
   - **C.** 120° and 240°
   - **D.** 20° and 40°
   - **E.** 100° and 200°

7. Name the acute angle in the following diagram.




8. **MC** Identify the values of p and q in the following diagram.
   - **A.** $p = 110°, q = 70°$
   - **B.** $p = 10°, q = 170°$
   - **C.** $p = 100°, q = 80°$
   - **D.** $p = 110°, q = 80°$
   - **E.** $q = 110°, p = 70°$




9. **MC** If you measure the three angles of a triangle and then add the three angles together, what is the result?
   - **A.** 90°
   - **B.** 120°
   - **C.** Between 90° and 180°
   - **D.** Between 120° and 240°
   - **E.** 180°

10. Classify each of the following triangles, based on side length and angle type.


a.




b.




c.



d.




11. Calculate the value of x in the following diagram.



12. ΔABC is an isosceles triangle with $AB = AC$ and $\angle ABC = 64°$.
Calculate the magnitude of $\angle BAC$.

13. Calculate the value of x in the following diagram.



14. MC Three angles in a quadrilateral are 135°, 72° and 38°. Identify the fourth angle.

A. 135° **B.** 38° **C.** 72° **D.** 115° **E.** 105°

15. A driveway inclined at an angle of 18° from the horizontal has vertical posts along the driveway. Determine the acute angle between the posts and the driveway.

9.2 Measuring angles

LEARNING INTENTION


At the end of this subtopic you should be able to:

- understand what an angle is
- estimate angles
- measure angles using a protractor.

9.2.1 Understanding angles


eles-4089

- An angle is a way of measuring the space between two lines that meet at a point.
- The point where the two lines meet is called a **vertex** and the lines are the arms of the angle.
- Instead of writing the word *angle*, we use the symbol ∠.
- Angles are measured in degrees.
- The symbol for degrees is °.




Estimating angles


- There are four important angles: 90°, 180°, 270° and 360°, used in estimating angles.




Right angle (90°)



Two right angles (180°)
Straight angle



Three right angles (270°)



Four right angles (360°)
One revolution


Estimating an angle

- First: determine which important angle it would measure closest to
- Second: decide whether it is greater or less than that angle
- Third: make an estimate.


WORKED EXAMPLE 1 Estimating the angle

Estimate the size of the following angles.


a.



b.



c.



THINK

a. 1. The angle is closest to 90°.

2. The angle is less than 90°.

3. Make an estimate.

WRITE

a. The estimate is 60°.

b. **1.** The angle is closest to 90°.
2. The angle is more than 90°.
3. Make an estimate.

b. The estimate is 120°.

c. **1.** The angle is roughly halfway between 270° and 360°.
2. Halfway between 270° and 360° is 270° + 45° = 315°
Note: You add 45° because 45° is half of 90°.
3. Write your estimate.


c. The estimate is 315°.

9.2.2 Measuring angles


eles-4090

- The tool for measuring angles is called a **protractor**.
- There are two types of protractors: circular and semicircular.

Circular protractor




Semicircular protractor




Using a protractor

To use a protractor, follow these steps.

1. Place the protractor on the angle so that:
   - the zero line is along one line of the angle
   - the centre of the protractor lines up with where the two lines meet (the vertex).




2. Read the angle by looking at where the other line crosses the protractor numbers.




WORKED EXAMPLE 2 Measuring angles

Measure the size of each of the following angles.

a.



b.



THINK


a. 1. Place the centre of the protractor on the vertex of the angle.

2. Match the line that passes through the centre of the protractor and points to 0° with one of the arms of the angle.

3. Read the size of the angle indicated by the other arm. (You may need to extend the line so that you can read it on the protractor.)

WRITE

a.




The size of this angle is 60°.

b. 1. Place the centre of the protractor on the vertex of the angle.

2. Match the line that passes through the centre of the protractor and points to 0° with one of the arms of the angle.

3. Read the size of the angle indicated by the other arm. (You may need to extend the line so that you can read it on the protractor.)

b.





The size of this angle is 120°.

- A semicircular protractor has angles only up to 180°. To measure angles larger than 180°:
  1. measure the part of the angle that is bigger than 180°
  2. determine the total angle by adding the measured angle to 180°.

WORKED EXAMPLE 3 Measuring angles using a semicircular protractor

Measure the size of this angle using a semicircular protractor.



THINK	WRITE
1. Measure the angle after 180°.	 The angle after 180° is 130°.
2. Add the measured angle to 180°.	130° + 180° = 310°
3. Write the answer.	The size of the angle is 310°.

Resources

eWorkbook	Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)
Digital documents	SkillSHEET Reading the scale on a protractor (doc-6447) SkillSHEET Comparing the size of angles (doc-6448) SkillSHEET Estimating the size of an angle (doc-6449) SkillSHEET Measuring angles with a protractor (doc-6450)
Interactivities	Individual pathway interactivity: Measuring angles (int-4331) The circular protractor (int-3952) The semicircular protractor (int-3953)

Exercise 9.2 Measuring angles

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 7, 10	3, 5, 8, 11	4, 6, 9, 12


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE 1

   a. MC The size of the angle shown is closest to:

   A. 20° B. 30° C. 40° D. 150° E. 140°




b. The size of the angle shown is closest to:

A. 42° **B.** 138° **C.** 142° **D.** 145° **E.** 38°




2. **WE 2,3** Measure the size of each of the following angles.

a.




b.



c.



d.




3. Measure the size of each of the following angles.


a.



b.



c.




d.



4. Measure the size of each of the following angles.


a.



b.



c.



d.



e. Comment on the accuracy of your measurement compared with the answer in the text.

Understanding

5. In each of the photographs, measure the indicated angle.


a.



b.



c.



d.



6. The recommended slope for wheelchair access is 4° from the horizontal. An angle greater than this makes it more difficult for the person in the wheelchair to travel up the ramp.




   a. Would you rate the slope of the bottom section of this ramp as 'difficult', 'as recommended' or 'easy'? Justify your rating.
   b. Describe how you would rate the second section of the ramp.

Reasoning

7. Consider the four different angles shown.
   a. Carefully measure each angle and write the measurements.
   b. Identify which two of these angles combined add to 90°.
   c. Identify which two of these angles combined add to 180°.
   d. Suggest one way of combining these angles to add to 360°. You can repeat angles.


i.




ii.




iii.




iv.




8. Sal is designing a new slide for her water park. She wants the slide to be both fun and safe. Below are side views of four possible designs:


Design 1


Design 2


Design 3



Design 4

a. State which design will give riders the fastest ride. What is the angle of that slide?
b. State which design will give riders the slowest ride. What is the angle of that slide?
c. The safety requirements are that slides for people aged 12 years and older must have an angle of no more than 35°. Identify which slides fit the safety requirements for Sal's park.
d. The safety requirements are that slides for people aged less than 12 years must have an angle of no more than 20°. Identify which slides fit the safety requirements for Sal's park.

Sal needs to choose the designs that give the fastest ride but also fit the safety requirements.

e. Identify which design Sal should use for the slide for people aged 12 and older.
f. Identify which design Sal should use for the slide for people aged less than 12 years.

9. Study the cartoon of the golfer to help you answer the following questions.



Copy the following table to record your answers.

Diagram	Estimate of angle	Measured angle	Difference
1			
2			
3			
4			

a. Without using a protractor, estimate the size of each angle in the first four diagrams of the golf sequence above and complete the second column of the table.
b. Explain how you obtained an estimate. Discuss the steps you followed.
c. Complete the third column by measuring each angle with a protractor.
d. Calculate the difference between your estimate and the actual value of each angle.
e. Describe how you could improve your skills in estimating the size of an angle.
f. Try these improvements for estimating the size of the angles in the remaining four diagrams. Copy and complete the following table.


Diagram	Estimate of angle	Measured angle	Difference
5			
6			
7			
8			

g. Has the difference between the estimated and actual value for each angle become smaller? Comment on whether your estimating skills have improved.

Problem solving

10. Sean is flying a kite. Depending on the position of the kite, the angle between the string and the horizontal line changes.
Complete the following statements:

a. As the kite moves from point A to point B, the angle increases from _____ to _____.
b. As the kite moves from point B to point C, the angle decreases from _____ to _____.



11. a. Using a protractor, measure the angles between the two clock hands shown in the diagrams.

i.


ii.


iii.



iv.



v.



vi.


b. Calculate the angle between the two arms without using a protractor.

12. Abby and Brinda are having an argument. Abby says there isn't a pattern when you measure the angles inside triangles and add them together. Brinda says there is a pattern.
Three triangles are shown.


Triangle 1


Triangle 2


Triangle 3

a. Measure the angles in the corners of each triangle.
b. Add the angles of each triangle.
c. Explain who is right, Abby or Brinda.

9.3 Constructing angles with a protractor

LEARNING INTENTION


At the end of this subtopic you should be able to:

- draw an angle using a protractor.


9.3.1 Constructing angles with a protractor


eles-4092

- Protractors can be used to draw angles.
- To draw an angle, start by drawing a straight line (arm) and putting a dot (vertex) at one end.




- Next, line up the protractor so that the dot (vertex) is in the centre and the line points to 0°.
- Place a dot for the angle you want to measure (for example 60°).





- Lastly, join the dots, and label the angle by drawing an arc between the two lines.



WORKED EXAMPLE 4 Constructing angles using a protractor

Construct each of the following angles.

a. **50°** **b.** **152.5°**

THINK

a. 1. Draw a horizontal line. Put a dot at one end. This line is the arm and the dot is the vertex.

2. Place the protractor so that its centre is on the vertex and 0° is on the line.

3. Find 50° on the scale and mark a dot at the edge of the protractor.

4. Join the dot and the vertex with a straight line using a ruler.

5. Draw the arc and label the angle.

b. 1. Repeat steps **1** and **2** from part **a**.


2. Find 152.5° on the scale and mark a dot at the edge of the protractor. Remember to start at 0° and use the inside scale.


3. Join the dots with a straight line using a ruler.

4. Draw the arc and label the angle.


WRITE


a.





b.







eles-4093

9.3.2 Constructing angles greater than 180° using a semicircular protractor


- To draw an angle greater than 180°, recall that 180° is a straight line.
- Subtract 180° from the given angle to determine how much larger than 180° the angle is.
  For example, for an angle of 220°: 220° − 180° = 40°
  220° is 40° more than 180°.

- To draw the angle, draw the arm (line) and the vertex (dot) as described in section 9.3.1.
- Use the semicircular protractor upside down and start counting at 0° (inner scale) or 180° (outer scale) to measure the given angle (40° in the above example).





- Lastly, join the dots and label the outer angle by drawing the arc.



WORKED EXAMPLE 5 Constructing angles using a semicircular protractor


Construct an angle of 210° using a semicircular protractor.


THINK

1. Subtract 180° from 210°.
2. Draw a horizontal line. Put a dot at one end. The line is the arm and the dot is the vertex.
3. Place the protractor upside down on the line so that its centre is on the dot.
4. Start at 0° on the left-hand side. Mark the position of 30° with a dot.
5. Remove the protractor and join the dots using a ruler.
6. Draw the arc and label the outer angle as 210°.


WRITE

$210° - 180° = 30°$





- *Note:* It is possible to draw an angle greater than 180° with the protractor upright. This diagram shows the angle of 210° (the same as in Worked example 5) constructed by placing the protractor in the upright position.



Resources

eWorkbook	Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)
Digital document	SkillSHEET Constructing angles with a protractor (doc-6451)
Interactivities	Individual pathway interactivity: Constructing angles with a protractor (int-4332) Construction of angles using a circular protractor (int-3954) Construction of angles using a semicircular protractor (int-3955)

Exercise 9.3 Constructing angles with a protractor

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13, 16	2, 5, 8, 11, 14, 17	3, 6, 9, 12, 15, 18

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE 4a Construct each of the following angles.
   a. 15° b. 9° c. 53° d. 75°
2. Construct each of the following angles.
   a. 45° b. 40° c. 88° d. 76°
3. WE 4b Construct each of the following angles.
   a. 96° b. 92° c. 165° d. 143°
4. Construct each of the following angles.
   a. 140° b. 156° c. 127° d. 149°
5. WE5 Construct each of the following angles using a semicircular protractor.
   a. 185° b. 210.5° c. 235° d. 260°
6. Construct each of the following angles using a semicircular protractor.
   a. 243° b. 192° c. 249° d. 214°
7. MC How much larger is an angle of 220° than an angle of 180°?
   A. 212° B. 58° C. 32° D. 112° E. None of these
8. Construct each of the following angles.
   a. 295° b. 269° c. 307° d. 349°
9. Construct each of the following angles.
   a. 328° b. 300° c. 345° d. 358°

Understanding

10. a. Draw the following angles.


i. 45° **ii.** 90° **iii.** 180° **iv.** 270° **v.** 360°

b. Use the angles you have drawn to help fill in the gaps.

i. The angle _____ is half of the angle 90°.
ii. The angle _____ is half of the angle 180°.
iii. The angle _____ is half of the angle 360°.
iv. The angle _____ is a third of the angle 270°.
v. The angle _____ is an eighth of the angle 360°.

11. a. Construct a 20° angle.
b. Draw a 45° angle on one side of this angle.
c. On the second arm of the angle in part **b** draw a 108° angle.
d. What is the remaining reflex angle? Hint: a reflex angle is more than 180° but less than 360°.
e. What is the total sum of the angles?

12. Windmills use wind power to produce electricity, pump water and mill grain. The three types of machines shown in the diagram have blades constructed at equal angles. Using a protractor, measure the angles between the blades.





Reasoning

13. Explain the method you would use to construct a reflex angle if you only had a 180° protractor.

14. It is possible to draw angles larger than 360°.
a. Draw an angle of 400°.
b. What smaller (0° to 90°) angle is the same as 400°?

15. We see the objects surrounding us because light reflects off the surface of the objects, as shown in the first diagram. The two angles shown are always equal.
Imagine you are in a room lit by a light globe as shown in the second diagram.





a. Using a protractor and a ruler, draw the next four paths followed by the ray of light shown in the diagram.
b. Draw another ray of light in a different direction.
c. Use the same procedure as in part **a** to draw the first four paths of the line drawn in part **b**.

Problem solving


16. **a.** Draw a horizontal line that is 3 cm long. Use that line as the base to draw a triangle with angles of 60° in each corner.
b. Draw a horizontal line that is 6 cm long. Use that line as the base to draw a triangle with angles of 60° in each corner.
c. Compare the two triangles and state the similarities and differences.
d. If you drew a triangle with base length 10 m and two corner angles of 60° each, determine the angle of the third corner.

17. On an A4 sheet of paper, draw a 20 cm long straight horizontal line close to the bottom of the page. Label this line AB.




a. Using a protractor construct an angle of 30° at point A and an angle of 30° at point B. Extend the two lines until they intersect.
b. Cut out the triangle and compare it with the triangles constructed in this way by other students.
c. Write a statement about your findings.

18. Draw any triangle on an A4 sheet of paper.
a. Use a protractor to measure the three angles.
b. Cut out the triangle and then cut the angles as shown in the diagram.



c. Place the angles next to each other so that their arms touch (see diagram).



d. Measure the new angle formed.
e. Compare your results with those of other students and write a statement to summarise your findings.

9.4 Types of angles and naming angles

LEARNING INTENTION


At the end of this subtopic you should be able to:

- classify different types of angles according to size
- name angles using three points.

9.4.1 Types of angles

eles-4094


- Angles can be classified according to their size.



An **acute angle** is greater than 0°, but less than 90°.




A **right angle** is an angle that equals exactly 90°.



An **obtuse angle** is greater than 90° but less than 180°.



A **straight angle** equals exactly 180°.



A **reflex angle** is greater than 180° but less than 360°.



An angle of **complete revolution** or a **perigon** is an angle of (a full 360°circle).

WORKED EXAMPLE 6 Classifying angles

Classify each of the following angles according to its size.

a. 115° **b.** 27° **c.** 300°

THINK

a. The given angle is larger than 90°, but smaller than 180°, so classify it accordingly.

b. The given angle is between 0° and 90°, so classify it accordingly.

c. The given angle is larger than 180°, but less 360°, so classify it accordingly.

WRITE

a. 115° is an obtuse angle.


b. 27° is an acute angle.

c. 300° is a reflex angle.

9.4.2 Naming angles

eles-4095

- Angles are named using letters by
  - using three letters: two letters to represent the arms of the angle, and a third letter to represent its vertex. The letter representing the vertex is always placed in the middle. For example, the angle shown can be named either ∠PNM or ∠MNP.




  - writing the letter that represents the vertex only. For example, the angle shown could be named ∠N.
  - writing the pronumeral that represents the angle inside the arms. For example, the angle shown could be named *a*.


WORKED EXAMPLE 7 Naming angles

Name each of the following angles.

a.



b.



THINK

a. Name the angle by starting either with X or with Y, then placing O (the letter representing the vertex) in the middle. You could also simply use the letter at the vertex. Remember to place the angle symbol (∠) before the letters.

b. Name the angle by starting either with A or with C, then placing B (the letter representing the vertex) in the middle. You could also simply use the letter at the vertex. Remember to place the angle symbol (∠) before the letters.

WRITE

a. ∠XOY or ∠YOX or ∠O

b. ∠ABC or ∠CBA or ∠B


WORKLED EXAMPLE 8 Drawing angles

Draw an acute angle ∠ADG.

THINK

1. Construct any acute angle (an angle greater than 0°, but less than 90°).
2. Letter D is in the middle, so place it at the vertex.
3. Place letter A at the end of one arm of the angle and letter G at the end of the other arm.
   (*Note:* It does not matter which arm is represented by AD or GD.)

WRITE



Resources

eWorkbook	Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)
Digital documents	SkillSHEET Classifying angles (doc-6452) SkillSHEET Naming angles (doc-6453)
Interactivities	Individual pathway interactivity: Types of angles and naming angles (int-4333) Types of angles (int-3961) Names of angles (int-3962)

Exercise 9.4 Types of angles and naming angles

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 12, 15, 20, 23	2, 5, 8, 11, 14, 16, 18, 21, 24	3, 6, 9, 13, 17, 19, 22, 25

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.




Fluency

1. WE 6 Classify each of the following angles according to its size.
   a. 12° b. 215.3° c. 156° d. 180° e. 355.2°

2. Classify each of the following angles according to its size.
   a. 90° b. 4.8° c. 360° d. 45° e. 270°


3. The following list gives values of particular angles.
   3°, 45°, 65°, 123°, 69°, 234°, 90°, 360°, 300°, 270°, 165°, 210°, 180°
   a. List the acute angles.
   b. List the obtuse angles.
   c. List the reflex angles.


4. State whether each of the following is true or false. The list of angles in question 3 contains:
   a. at least one right angle
   b. at least one straight angle
   c. at least one full revolution.


5. Consider the following diagrams and write down the type of angle shown in each case.
   a. 
   b. 
   c. 
   d. 
   e. 
   f. 

6. WE7 Name each of the following angles.

a. 

b. 

c. 

d. 


e. 

Understanding

7. WE 8 Draw each of the following angles as specified in the brackets.
   a. ∠CDE (acute)
   b. ∠TRE (obtuse)
   c. ∠QAS (straight)

8. Draw each of the following angles as specified in the brackets.
   a. ∠FGH (reflex)
   b. ∠KJF (right)
   c. ∠VBN (acute)

9. Name the type of angle shown in this photograph.




10. Name the type of angle shown in this photograph.




11. Name the type of angle shown in this photograph.



12. Name each acute and obtuse angle in the following diagram.




13. Name each acute and obtuse angle in the following diagram.




14. Name each acute and obtuse angle in the following diagram.

a.



b.



15. State the type of angle that the minute hand of a clock makes when it moves for the following lengths of time.

a. 10 minutes **b.** 15 minutes **c.** 20 minutes

16. State the type of angle that the minute hand of a clock makes when moving for the following lengths of time.

a. 30 minutes **b.** 45 minutes **c.** 1 hour

17. At various times of the day the hands of an analogue clock form two angles: the inside angle (the smaller one) and the outside angle (the larger one).
State the type of the inside angle formed by the hands of a clock at the following times.

a. 1 o'clock **b.** 20 minutes to 12 **c.** 6 o'clock
d. 9 o'clock **e.** quarter to 4

18. At various times of the day the hands of an analogue clock form two angles: the inside angle (the smaller one) and the outside angle (the larger one).
Write two different times when the inside angle of the clock is:

a. acute **b.** obtuse **c.** right.

19. In this photograph, acute, right-angled and obtuse angles have been used.



a. Name an acute angle.
b. Name two right angles.
c. Name an obtuse angle.
d. State the name of a reflex angle.

Reasoning

20. Give reasons for the following statements.

a. The sum of two acute angles can be an acute angle.
b. The sum of two acute angles can be a right angle.
c. The sum of two acute angles can be an obtuse angle.
d. The sum of two acute angles can be a reflex angle.

21. a. State whether it is possible to construct a complete revolution using one 90° angle, one straight angle and two acute angles.
b. Construct a diagram to represent the complete revolution in part **a**.

22. Watchmakers take particular care that the angles between the hands of an analogue clock represent the time accurately. Determine the size of the smaller angle between the hour and minute hands when an analogue clock displays the time as 10 past 9.



Problem solving


23. Explain why it is important to always put the letter representing the vertex in the middle of an angle's name.

24. Label each angle marked in this photograph with the word describing the type of angle it is.



25. **a.** Consider the figure and identify how many angles are shown.

b. At midday, the hour hand, the minute hand and the second hand on an analogue clock are all pointing to the 12.
Determine the size of the smaller angle between the hour hand and the minute hand after the second hand has completed 30 revolutions.
Hint: It is not 180°— draw a separate diagram to help.



9.5 Triangles

LEARNING INTENTION


At the end of this subtopic you should be able to:
- classify triangles according to the lengths of their sides or the sizes of their angles
- calculate both interior and exterior angles of a triangle.

9.5.1 Naming triangles

eles-4096





- **Triangles** are closed shapes that have three edges (or sides) and three vertices (or angles).
- Capital letters are used at each vertex to name a triangle.
  For example, the triangle in the following bicycle frame can be named Δ PQR. (It can also be named Δ RPQ or Δ QRP, and so on)






Classifying triangles

- Triangles can be classified according to:
  - the lengths of their sides
  - the sizes of their angles.
- These classifications are shown in the following table.


Lengths of sides		Sizes of angles	
Triangle name and distinguishing features	**Shape**	**Triangle name and distinguishing features**	**Shape**
Equilateral triangle All edges are the same length and all angles are the same size. This is shown by the identical marks on each edge and each angle.		**Acute-angled triangle** All interior angles are less than 90°.	
Isosceles triangle Two edges are the same length. The third edge is a different length. It is often called the base of the triangle. The two base angles are the same size.		**Right-angled triangle** One angle is exactly 90°. This angle is marked by a small square. The edge opposite the right angle is called the hypotenuse.	
Scalene triangle All edges are different lengths and all angles are different sizes. This is shown by the unique markings on each edge and each angle.		**Obtuse-angled triangle** One angle is greater than 90°.	

DISCUSSION

1. In the triangle shown, count the number of:
   a. equilateral triangles
   b. right-angled triangles
   c. isosceles triangles.




2. Count the number of triangles in this shape.




WORKED EXAMPLE 9 Classifying triangles by sides

Classify each of these triangles according to the lengths of its sides.


a.



b.



c.



THINK	WRITE
a. Sides AB and AC have identical markings on them, which means that they are equal in length. So ΔABC has 2 equal sides. Classify this triangle based on that infomation.	**a.** ΔABC is an isosceles triangle.
b. The 3 sides of ΔMNP have identical markings on them, which means that all 3 sides are equal in length. Classify this triangle based on that information.	**b.** ΔMNP is an equilateral triangle.
c. All 3 sides of ΔPRS are marked differently, which means no sides in this triangle are equal in length. Classify this triangle based on that information.	**c.** ΔPRS is a scalene triangle.

WORKED EXAMPLE 10 Classifying triangles by angles

Classify each of the triangles in Worked example 9 according to the size of its angles.

THINK	WRITE
a. In ΔABC, ∠CAB is marked as the right angle. Classify this triangle based on that information.	**a.** ΔABC is a right-angled triangle.
b. In ΔMNP all angles are less than 90°. Classify this triangle based on that information.	**b.** ΔMNP is an acute-angled triangle.
c. In ΔPRS, ∠PRS is greater than 90°; that is, it is obtuse. Classify this triangle based on that information.	**c.** ΔPRS is an obtuse-angled triangle.

- We can classify triangles by both their side lengths and the sizes of their angles. For example, the triangle from part **a** of Worked example 9 can be classified as a right-angled isosceles triangle.

COLLABORATIVE TASKS

Sketching triangles from a verbal description

Pair up with a classmate and each of you draw a triangle without the other person seeing. Take turns describing your triangles using only verbal descriptions and asking your partner to draw the triangle you have described. How accurate is their drawing compared to the triangle you described?


Investigating the angles

Pair up with a classmate and cut out a triangle. Tear off the three angles (the points of your triangle) and pass them to your partner. Can you make a straight line with the three angles your partner has given you?

9.5.2 Angles in a triangle

eles-4097

- The sum of the three angles in any triangle is always 180°.



$a° + b° + c°$ makes a straight angle.


Sum of angles in a triangle

The three angles of a triangle add up to 180°. That is, $a° + b° + c° = 180°$.


WORKED EXAMPLE 11 Calculating angles in triangles

Calculate the value of the pronumeral in each of the following triangles.

a.



b.




THINK

a. 1. The sum of the 3 angles (b, 35° and 58°) must be 180°. Write this as an equation.

2. Simplify by adding 35° and 58° together.

3. Use inspection or backtracking to solve for b.



WRITE

a. $b + 35° + 58° = 180°$

$b + 93° = 180°$


$b = 180° - 93°$

$b = 87°$

b. 1. The sum of the three angles (d, 37° and 42°) must be 180°. Write this as an equation.

2. Simplify by adding 37° and 42° together.

3. Use inspection or backtracking to calculate the value of d.



b. $d + 37° + 42° = 180°$


$d + 79° = 180°$

$d = 180° - 79°$

$d = 101°$

WORKED EXAMPLE 12 Calculating angles in triangles


Calculate the value of the pronumeral in the following triangle.



THINK	WRITE
1. The markings on the diagram indicate that ΔABC is isosceles because AB = BC. Therefore, the angles at the base are equal in size; that is, ∠BCA = ∠BAC = 74°. Write this as an equation.	$\angle BCA = \angle BAC = 74°$
2. All 3 angles in a triangle must add up to 180°. Write this as an equation.	$\angle ABC + \angle BAC + \angle BCA = 180°$ $h + 74° + 74° = 180°$
3. Simplify by adding 74° and 74° together.	$h + 148° = 180°$
4. Subtract 148° from 180° to calculate the value of h .	$h = 180° - 148°$ $h = 32°$


WORKED EXAMPLE 13 Calculating angles in triangles

Calculate the value of the pronumeral in the following triangle.



THINK	WRITE
1. The markings on the diagram indicate that ΔMNP is isosceles because MN = NP. Therefore the angles at the base are equal in size. Write this as an equation.	$\angle NPM = \angle NMP = a$
2. All 3 angles in a triangle must add up to 180°. Write this as an equation.	$\angle NMP + \angle NPM + \angle MNP = 180°$ $a + a + 40° = 180°$
3. Simplify by collecting like terms. In this example $a + a = 2a$.	$2a + 40° = 180°$

4. Use inspection or backtracking to calculate the value of a.



$2a = 180° - 40°$

$2a = 140°$


$a = \frac{140°}{2}$

$a = 70°$

9.5.3 Interior and exterior angles of a triangle

eles-4098


- The angles inside a triangle are called **interior angles**.
- When a side of a triangle is extended outwards, the angle formed is called an **exterior angle**.
- The exterior angle and the interior angle adjacent (next) to it add up to 180°.
- The sum of the two interior opposite angles is equal to the exterior angle.



$\angle ACB + \angle BCD = 180°$


and

$\angle BAC + \angle ABC = \angle BCD$



WORKED EXAMPLE 14 Calculating angles in triangles

Determine the value of the pronumerals in the following diagram.



THINK

1. $\angle DAB = 125°$. $\angle BAC$ (angle p) and its adjacent exterior angle ($\angle DAB$) add up to 180°. Write this as an equation.

2. Subtract 125° from 180° to determine the value of p.

3. The interior angles of ΔABC add up to 180°. Identify the values of the angles and write this as an equation.

WRITE

$\angle BAC = p; \angle DAB = 125°$

$\angle BAC + \angle DAB = 180°$

$p + 125° = 180°$

$p = 180° - 125°$

$p = 55°$

$\angle BCA + \angle BAC + \angle ABC = 180°$

$\angle BCA = 83°; \angle BAC = p = 55°; \angle ABC = n$

$83° + 55° + n = 180°$

4. Simplify by adding 83° and 55°. $n + 138° = 180°$

5. Subtract 138° from 180° to determine the value of n. $n = 180° - 138°$
$n = 42°$

Resources

eWorkbook Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)

Digital documents SkillSHEET Classifying triangles according to the length of their sides (doc-6454)
SkillSHEET Classifying triangles according to the size of their angles (doc-6455)

Interactivities Individual pathway interactivity: Triangles (int-4334)
Classification of triangles — sides (int-3963)
Classification of triangles — angles (int-3964)
Angles in a triangle (int-3965)
Interior and exterior angles of a triangle (int-3966)

Exercise 9.5 Triangles

learnON


Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 10, 13, 15, 17, 20	3, 6, 7, 9, 11, 14, 18, 21	4, 8, 12, 16, 19, 22


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency


1. WE9 Name each of the following triangles using the capital letters, then classify each triangle according to the lengths of its sides.

a.


b.



c.



d.



e.



2. WE10 Classify each of the triangles in question 1 according to the size of its angles.


3. MC Select which of these triangles is an equilateral triangle.

A. 


B. 


C. 


D. 


E. 

4. MC Select which of these triangles is not a scalene triangle.

A. 


B. 


C. 


D. 


E. 


5. MC Select the triangle that is both right-angled and scalene.

A. 

B. 


C. 

D. 


E. 

6. MC Select which of these triangles is both acute-angled and isosceles.


A.




B.




C.



D.




E.




7. WE11 Calculate the value of the pronumeral in each of the following triangles.


a.




b.




c.




d.



e.




f.




8. Calculate the value of the pronumeral in each of the following right-angled triangles.


a.



b.




c.




9. WE12 Calculate the value of the pronumeral in each of the following triangles, giving reasons for your answer.


a.



b.




c.




10. **WE13** Calculate the value of the pronumeral in each of the following triangles, giving reasons for your answer.


a.




b.




c.




d.



e.




f.




11. **WE14** Calculate the value of the pronumerals in each of the following diagrams.


a.




b.



c.




d.




12. Calculate the value of the pronumerals in each of the following diagrams.


a.




b.



c.




d.




Understanding

13. Add side and angle markings to these diagrams to show that:


a. ΔRST is an equilateral triangle



b. ΔUVW is an isosceles triangle




c. ΔPQR is a scalene triangle.




14. Add side and angle markings to these diagrams to show that:


a. ΔMNP is a right-angled triangle



b. ΔABC is a right-angled and isosceles triangle



c. ΔMNO is a right-angled and scalene triangle.




15. Use your ruler, pencil and protractor to accurately draw:


a. an equilateral triangle with side lengths 6 cm and all angles 60°
b. an isosceles triangle with two sides that are 6 cm each with a 40° angle between them
c. a right-angled triangle whose two short sides are 6 cm and 8 cm (How long is the longest side?)
d. a scalene triangle with two of the sides measuring 4 cm and 5 cm and an angle of 70° between the two sides.

16. Calculate the missing angle in each of the triangles marked on the following photographs.

a.



b.



Reasoning

17. Calculate the magnitudes of the unknown angles in the following triangles.

- **a.** ΔMNP is an isosceles triangle with MN = MP and ∠MNP = 72°. Calculate the sizes of ∠MPN and ∠NMP.
- **b.** ΔMNP is an isosceles triangle with MN = MP and ∠NMP = 72°. Calculate the sizes of ∠MPN and ∠MNP

18. **a.** Explain in your own words why it is impossible to construct a triangle with two obtuse angles.
- **b.** Explain why the longest side of a triangle is always opposite the largest angle of the triangle.
- **c.** Explain why the sum of the lengths of two sides of a triangle must be greater than the length of the third side.

19. **a.** Construct the isosceles triangle ABC with ∠B = ∠C = 80°.
- **b.** Extend the line BC to the right and label the other end D where BD = AB and form the ΔABD.
- **c.** Calculate the size of ∠D.
- **d.** Extend the line CD to the right and label the other end E where DE = AD and form the ΔADE.
- **e.** Calculate the size of ∠E.
- **f.** Repeat this process again and discuss any pattern you observe.

Problem solving


20. **a.** An isosceles triangle has two angles of 55° each. Calculate the third angle.
- **b.** An isosceles triangle has two angles of 12° each. Calculate the third angle.
- **c.** Two angles of a triangle are 55° and 75°. Calculate the third angle.
- **d.** Two angles of a triangle are 48° and 68°. Calculate the third angle.

21. For each of the following sets of three angles, state whether it is possible to construct a triangle with these angles. Give a reason for your answer.


- **a.** 40°, 40°, 100°
- **b.** 45°, 60°, 70°
- **c.** 45°, 55°, 85°
- **d.** 111°, 34.5°, 34.5°

22. Determine the value of the pronumerals in the following shapes.

a.



b.



9.6 Quadrilaterals and their properties


LEARNING INTENTION

At the end of this subtopic you should be able to:
- classify quadrilaterals from a given diagram
- calculate the angles in a quadrilateral.


9.6.1 Types of quadrilaterals

eles-4100





- A **quadrilateral** is a 2-dimensional closed shape with four straight sides.
- Quadrilaterals can be either **convex** or non-convex.
- In a convex quadrilateral, each of the interior angles is less than 180° and the two diagonals lie inside the quadrilateral.
- In a non-convex quadrilateral, one interior angle is more than 180° and one of the two diagonals lies outside of the quadrilateral.
- Quadrilaterals can be divided into two major groups: **parallelograms** and other quadrilaterals.
- Parallelograms are quadrilaterals with:
  1. both pairs of opposite sides equal in length and parallel
  2. opposite angles equal.
- A *rectangle*, a *square* and a *rhombus* (diamond) are all examples of parallelograms.






Convex quadrilaterals



Non-convex quadrilaterals


Parallelograms	Shape	Properties
Parallelogram		Opposite sides are equal in length. Opposite angles are equal in size.
Rectangle		Opposite sides are equal in length. Adjacent sides are perpendicular. All angles are the same and equal 90°.
Rhombus		All sides are equal in length. Opposite angles are equal in size.
Square		All sides are equal in length. Adjacent sides are perpendicular. All angles are the same and equal 90°.


- Examples of other quadrilaterals (non-parallelograms) include *trapeziums*, *kites* and *irregular quadrilaterals*.

Other quadrilaterals	Shape	Properties
Trapezium		One pair of opposite sides is parallel.
Kite		Two pairs of adjacent (next to each other) sides are equal in length. One pair of opposite angles (the ones that are between the sides of unequal length) are equal.
Irregular quadrilateral		This shape does not have any special properties.

WORKED EXAMPLE 15 Naming quadrilaterals

Name the following quadrilaterals, giving reasons for your answers.

a. 

b. 

THINK

a. The markings on this quadrilateral indicate that all sides are equal in length and all angles equal 90°. Name the quadrilateral by finding the matching description in the table.

b. The arrows on the sides of this quadrilateral indicate that there are two pairs of parallel sides. Therefore it is a parallelogram. Check the descriptions in the table to see if it is a particular type of parallelogram.

WRITE

a. This quadrilateral is a square, since all sides are equal and all angles are 90°.


b. This quadrilateral is a parallelogram, since it has two pairs of parallel sides.

9.6.2 Angles in a quadrilateral


eles-4101

To investigate the sum of the angles in a quadrilateral, consider the following:

- All quadrilaterals have four internal angles.



- Quadrilaterals are made up of two triangles.



From earlier work, we know that the sum of angles in a triangle = 180°.

Therefore:

$$\begin{aligned} 2 \text{ triangles} &= 2 \times 180° \\ &= 360° \end{aligned}$$

Sum of angles in a quadrilateral

The four angles of a quadrilateral add up to 360°. That is, $a° + b° + c° + d° = 360°$

WORKED EXAMPLE 16 Determining angles in a quadrilateral

Calculate the value of the pronumeral in the diagram.



THINK

1. The sum of the angles in a quadrilateral is 360°. Write this as an equation.
2. Simplify by adding 100°, 136° and 65°.
3. Subtract 301° from 360° to calculate the value of d.

WRITE

$d + 100° + 136° + 65° = 360°$

$d + 301° = 360°$

$d = 360° - 301°$
$d = 59°$

WORKED EXAMPLE 17 Evaluating angles in a parallelogram


Determine the value of the pronumerals in the photograph, giving a reason for your answer.



THINK	WRITE
1. According to the markings, the opposite sides of the quadrilateral in the photograph are parallel and equal in length. Therefore, this quadrilateral is a parallelogram. In a parallelogram, opposite angles are equal. Write down the value of the pronumerals.	Opposite angles in a parallelogram are equal in size. Therefore, $j = 65°$ and $i = k$.
2. The interior angles of a quadrilateral add up to 360°. Form an equation by writing the sum of the angles on one side and 360° on the other side of an equals sign.	$65 + j + i + k = 360°$
3. Replace j in the equation with 65°.	$65 + 65 + i + k = 360°$
4. Simplify, by adding 65° and 65° together.	$130 + i + k = 360°$
5. Subtract 130° from 360° to determine the value of $i + k$.	$i + k = 360 - 130°$ $i + k = 230°$
6. We know that $i = k$, so each angle must be half of the remaining 230°. Divide 230° by 2.	$\frac{230°}{2} = 115°$
7. Angles i and k are both equal to 115°.	$i = 115°$ and $k = 115°$
8. Write the answer.	$i = 115°, j = 65°, k = 115°$

WORKED EXAMPLE 18 Evaluating angles in a kite


Calculate the value of the pronumerals in the diagram.



THINK	WRITE
1. Form an equation by writing the sum of the angles on one side, and 360° on the other side of an equals sign.	$k + t + 50° + 136° = 360°$
2. The quadrilateral shown in the diagram is a kite. Referring to the description of a kite in the table, angle t and angle 136° are the angles between unequal sides and therefore must be equal in size.	The figure is a kite. $t = 136°$
3. Replace t in the equation with 136°.	$k + 136° + 50° + 136° = 360°$
4. Simplify by adding 136°, 50° and 136° together.	$k + 322° = 360°$
5. Subtract 322° from 360° to calculate the value of k.	$k = 360° - 322°$ $k = 38°$

COLLABORATIVE TASK: Sketching quadrilaterals from a verbal description

Pair up with a classmate and each of you draw a quadrilateral without the other person seeing. Take turns describing your quadrilaterals using only verbal descriptions. Your partner must try to draw the quadrilateral you describe. How accurate is the drawing compared to the quadrilateral you described?



on Resources

eWorkbook Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)

Interactivities Individual pathway interactivity: Quadrilaterals and their properties (int-4335)
Types of quadrilaterals (int-4025)
Angles in a quadrilateral (int-3967)

Exercise 9.6 Quadrilaterals and their properties

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 11, 12, 15, 18, 19, 22	2, 4, 7, 10, 13, 16, 20, 23	5, 8, 9, 14, 17, 21, 24


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. State whether the quadrilaterals show are convex or non-convex.


a.



b.



c.



d.



2. **WE 15** Name the following quadrilaterals, giving reasons for your answers.


a. i.


ii.


iii.


iv.


v.



vi.


b. Name each of the quadrilaterals in the photographs, giving reasons for your answers.

i.



ii.



iii.




iv.




3. MC Identify the quadrilateral shown.

A. Square
B. Rectangle
C. Kite
D. Parallelogram
E. Rhombus




4. MC Identify the quadrilateral shown.

A. Trapezium
B. Square
C. Kite
D. Rhombus
E. Parallelogram





5. MC Identify the quadrilateral shown.


A. Trapezium
B. Parallelogram
C. Rhombus
D. Kite
E. Square





6. **WE16** Calculate the value of the pronumeral in each of the following diagrams.


a.


b.



c.



d.


e.



f.



7. **WE17** Calculate the value of the pronumeral in each of the following diagrams, giving reasons for your answers.


a.


b.


c.



d.


e.


f.



8. Use the following photographs to determine the values of the unknown angles.

a.



b.


9. WE18 Calculate the value of the pronumerals in each of the following diagrams.


a.




b.




c.




d.



e.




f.




10. MC Identify the the value of t in the diagram.

A. 360°
B. 112°
C. 222°
D. 138°
E. 180°



11. MC Identify the value of r in the diagram.

A. 117°
B. 180°
C. 234°
D. 126°
E. 63°



Understanding

12. State whether each of the following statements is true or false.

a. All squares are rectangles.
b. All squares are rhombuses.
c. All rectangles are squares.
d. Any rhombus with at least one right angle is a square.
e. A rectangle is a parallelogram with at least one angle equal to 90°.

13. MC A rectangle is a quadrilateral because:

A. it has 4 right angles
B. it has 2 pairs of parallel sides
C. its opposite sides are equal in length
D. it has 4 straight sides
E. it has 2 pairs of parallel sides and 4 right angles.

14. The photograph shows the roof of a gazebo. Calculate the value of p.



15. Determine the size of the obtuse angle in the following photograph of a kite.



16. Two angles in a parallelogram are 45° and 135°. Calculate the values of the other 2 angles.

17. Tom measures 2 angles of a kite at 60° and 110°, but forgets which angle is which. Draw three different kites that Tom may have measured, showing the size of all angles in each diagram.

18. For each of the following sets of four angles, decide whether it is possible to construct a quadrilateral. Explain your answer.

a. 25°, 95°, 140°, 100°

b. 40°, 80°, 99°, 51°

Reasoning


19. Three angles of a quadrilateral are 60°, 70° and 100°.

a. Calculate the size of the fourth angle of this quadrilateral.

b. Determine how many quadrilaterals with this set of angles are possible.

c. Construct a quadrilateral with the given angle sizes. The choice of the length of the sides is up to you.

20. Val and Peter want to replace their front gate with another of the same design. To have this gate made, they need to supply a diagram of it with all measurements and angles shown. Study the photograph of Val and Peter's gate and use it to help you answer the following questions.




a. There are 4 different shapes formed by the metal bars of the gate. How many different types of triangles are there? Identify them.

b. State how many types of quadrilaterals there are. Identify them.

c. Draw a diagram of the gate showing the length measurements and the one angle that is given.

d. Use this angle to calculate all the remaining angles in the diagram.

21. a. Consider the diagram. Prove that the sum of all angles in a quadrilateral is 360°.



b. Using a similar method, determine the sum of all angles in the following shapes. *Hint*: Draw the shape first.

i. Pentagon

ii. Hexagon


iii. Octagon

iv. Decagon


Problem solving

22. Determine the values of the pronumerals in the following shapes.

a.




b.




23. Calculate the values of the pronumerals in each of the following quadrilaterals.


a.




b.



c.



d.



24. Draw a quadrilateral PQRS. Label angle P as 100° and angle R as a right angle. Angle Q is two-thirds of angle S. Determine the measurement of angle S.

9.7 Parallel and perpendicular lines

LEARNING INTENTION


At the end of this subtopic you should be able to:

- identify and determine the size of vertically opposite angles
- identify and determine the size of angles formed when a transversal intersects parallel lines.


9.7.1 Vertically opposite and adjacent angles

eles-4102


- When two straight lines intersect they form four angles with a common vertex.
- The angles that are opposite each other are called **vertically opposite angles**.
- Vertically opposite angles are equal in size.
- In this diagram there are two pairs of vertically opposite angles:
  $\angle AOB = \angle COD$ and $\angle BOC = \angle AOD$
- **Adjacent angles** share a common arm and a common vertex. In this diagram $\angle AOB$ is adjacent to $\angle BOC$



- **Complementary angles** are adjacent angles that add up to 90°.
  In this diagram, $x + y = 90°$.




- **Supplementary angles** are adjacent angles that add up to 180°.
  In this diagram, $x + y = 180°$.



WORKED EXAMPLE 19 Calculating a complementary angle


Calculate the value of x in the diagram.



THINK	WRITE
1. These angles are supplementary because they add up to 90°.	$x + 30° = 90°$
2. Subtract 30° from 90° to calculate the value of x.	$x = 90° - 30°$ $x = 60°$
3. Write the answer.	The value of x is 60°.

WORKED EXAMPLE 20 Calculating a supplementary angle


Calculate the value of x in the diagram.



THINK	WRITE
1. These angles are supplementary because they add up to 180°.	$x + 85° = 180°$
2. Subtract the known angle from 180° to calculate the value of x.	$x = 180° - 85°$ $x = 95°$
3. Write the answer.	The value of x is 95°.

WORKED EXAMPLE 21 Determining vertically opposite angles

Determine the value of the pronumerals in the diagram.




THINK	WRITE
1. The angle y and 120° are vertically opposite, so they are equal.	$y = 120°$
2. The angle z and the angle marked 120° form a straight line, so they are supplementary angles (that is, they add to 180°). Subtract 120° from 180° to find the value of z.	$z = 180° - 120°$ $= 60°$
3. The angles x and z are vertically opposite, so they are equal.	$x = 60°$





eles-4103

9.7.2 Parallel and perpendicular lines

- **Parallel lines** are two or more lines that are simple translations of each other.
- The distance between parallel lines is the same across their entire lengths. They never intersect each other. The two rails of the train tracks in this picture are parallel to each other.
- To write 'the line segments AB and CD are parallel' using mathematical symbols, simply write AB ∥ CD.
- The symbol ∥ means 'is parallel to'.
- The term 'transverse' means 'crossways'. A line that intersects with a pair of parallel lines is called a **transversal**.
- When a transversal cuts a set of parallel lines, a number of angles are created. The following table shows how pairs of angles are related.





Angle identification	Relationship	Example
Corresponding angles are positioned on the same side of the transversal and are either both above or both below the parallel lines. Think of them as F-shaped.	$\angle a = \angle b$	
Co-interior angles are positioned 'inside' the parallel lines, on the same side of the transversal. Think of them as C-shaped. Co-interior angles are also called **allied angles**.	Angles are supplementary: $\angle a + \angle b = 180°$	
Alternate angles are positioned 'inside' the parallel lines on alternate sides of the transversal. think of them as Z-shaped.	$\angle a = \angle b$	
Vertically opposite angles are created when two lines intersect. The angles opposite each other are equal in size. Think of them as X-shaped.	$\angle a = \angle a$ $\angle b = \angle b$	


eles-4104

9.7.3 Calculating angles associated with parallel lines

- Angle relationships can be used to calculate the size of missing angles, as shown in the following worked examples.
- Remember that the Z, F or C shapes may be upside-down or backwards in some diagrams.

WORKED EXAMPLE 22 Calculating angles

For the diagram shown:
a. state the type of angle relationship
b. calculate the value of the pronumeral.




THINK

a. 1. Study the diagram: which shape, Z, F or C, would include both angles that are shown? Copy the diagram into your workbook and highlight the appropriate shape.

2. Write the answer by stating the name of the angles suggested by a C shape.

WRITE

a.





The highlighted angles are co-interior.

b. 1.	Co-interior angles add up to 180°. Write this as an equation.	**b.** $m + 45° = 180°$
2.	Solve for m by subtracting 45° from 180°.	$m = 180° - 45°$ $m = 135°$
3.	Write the answer.	The value of m is 135°

WORKED EXAMPLE 23 Calculating angles

Calculate the value of the pronumeral in the diagram shown, giving reasons.



THINK	WRITE
1. The two angles shown are neither C, Z nor F angles. So we must find some other angle first that will enable us to determine the size of angle x.	
2. This other angle must be in a certain relationship with *both* given angles. Draw an F shape that includes a 120° angle.	
3. The other angle in this F shape is related to both given angles: it corresponds to the 120° angle and is supplementary to angle x. Call this angle y.	
4. State the size of angle y, specifying the reason (the angle relation).	$y = 120°$ (because corresponding angles are equal)
5. The angles x and y are supplementary (add to 180°) as they lie on a straight line. State this as an equation.	$x + y = 180°$ (because the angle sum of a straight line is 180°)
6. Substitute the value of y into the equation.	$x + 120° = 180°$
7. Solve for x by subtracting 120° from 180°	$x = 180° - 120°$ $x = 60°$
8. Write the answer.	The value of x is 60°.


9.7.4 Testing for parallel lines

eles-4105

- Two lines are parallel if:
  - corresponding angles are equal
  - alternate angles are equal
  - co-interior angles are supplementary.

WORKED EXAMPLE 24 Determining parallel lines


Are the following lines A and B parallel? Explain your answer.



THINK

1. The given angles are equal to each other. They are both 110°.
2. Identify the type of angles provided by considering the Z, F or C shapes.
   The Z shape is most appropriate. Therefore the angles are alternate.
3. Since the two angles are alternate and equal, then the lines A and B must be parallel.


WRITE



A ∥ B

Perpendicular lines

- **Perpendicular** means 'at right angles'.
- In this diagram, the angles ∠AOX and ∠XOB are both right angles, which means the lines AB and OX are perpendicular.
- To write 'the line segments AB and OX are perpendicular' using mathematical symbols, simply write AB⊥ OX.
- The symbol ⊥ means 'is perpendicular to'.



Resources

eWorkbook Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)
Video eLesson Parallel lines (eles-2309)
Interactivities Individual pathway interactivity: Parallel and perpendicular lines (int-4336)
Vertically opposite and adjacent angles (int-3968)
Corresponding angles (int-3969)
Co-interior angles (int-3970)
Alternate angles (int-3971)
Calculation of angles associated with parallel lines (int-3972)
Testing for parallel lines (int-3973)

Exercise 9.7 Parallel and perpendicular lines

learnON


Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 8, 11, 15, 18, 20, 23	2, 5, 9, 12, 14, 17, 21, 24	3, 6, 10, 13, 16, 19, 22, 25

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE19 Calculate the value of the pronumeral in the following diagram.




2. Calculate the value of the pronumeral in each of the following diagrams.


a.



b.



3. WE20 Calculate the size of ∠BOC.




4. Calculate the value of the pronumeral in each of the following diagrams.


a.



b.




c.




5. WE21 Calculate the value of the pronumerals in each of the following diagrams.


a.



b.




c.




6. Determine the value of the pronumerals in each of the following diagrams.


a.




b.



c.



7. MC In the diagram:



a. which angle is vertically opposite to angle p?

A. k **B.** m **C.** r **D.** q **E.** t

b. which angle is corresponding to angle p?

A. k **B.** m **C.** r **D.** q **E.** t

c. which angle is co-interior to angle p?

A. k **B.** m **C.** r **D.** q **E.** n

d. which angle is alternate to angle p?


A. k **B.** m **C.** r **D.** q **E.** n

8. WE22 For each of the following diagrams:


a. state the type of angle relationship

b. determine the value of the pronumeral.


i.




ii.




iii.




iv.



v.




vi.




9. **WE23** Calculate the value of the pronumeral in each of the following diagrams. Give reasons for your answers.


a.



b.




c.




10. Calculate the value of the pronumerals in each of the following diagrams. Give reasons for your answers.

a.



b.



Understanding

11. Identify which of the following pairs of angles are complementary.

a. 32° and 60°
b. 70° and 30°
c. 45° and 45°
d. 28° and 72°
e. 30° and 150°
f. 42° and 48°


12. Identify which of the following pairs of angles are supplementary.

a. 30° and 60°
b. 70° and 110°
c. 145° and 45°
d. 118° and 72°
e. 35° and 145°
f. 42° and 138°

13. **a.** Determine the complement of 65°.
b. Determine the supplement of 123°.


14. **a.** If the angle allied to x is 135°, calculate the size of angle x.
b. If the angle corresponding to y is 55°, calculate the size of angle y.

15. Copy and complete this table.


Diagram	Type of angle relation	Associated shape	Rule
	Corresponding		Are equal in size
	Alternate	Z	
			Add up to 180°

16. Match each diagram with the appropriate angle name from the four options listed.


a.




b.



c.




d.



A. Co-interior angles (C)
B. Corresponding angles (F)
C. Alternate angles (Z)
D. None of the above


17. Look at the diagram. List all pairs of:

a. vertically opposite angles
b. corresponding angles
c. co-interior angles
d. alternate angles.




18. Calculate the value of the pronumerals in the following diagrams.


a.



b.




c.




19. Calculate the value of the pronumerals in the following diagrams.


a.



b.




c.




Reasoning

20. WE24 Is the line AB parallel to the line CD? Explain your answer.




21. **a.** Calculate the size of angle a. Explain how you found it.
b. Is the line KL parallel to MN? Explain your answer.
c. Calculate all of the remaining internal and external angles of the triangle in the centre of the diagram.




22. Look at the following optical illusions. Are any of the lines parallel? Explain your answer.

a.




b.




Problem solving

23. A hill is at an angle of 30° to the horizontal. A fence is put in, consisting of a railing parallel to the ground and a series of vertical fence posts. Calculate the angle, p, between the top of the fence post and the rail.




24. Two gates consist of vertical posts, horizontal struts and diagonal beams. Calculate the angle, a, as shown in the following gates.


a.



b.



25. In the diagram shown, calculate the magnitude of the acute angle ∠PQR and the reflex angle ∠PQR.



9.8 Review

9.8.1 Topic summary

GEOMETRY

Types of angles

- **Acute angle** (greater than 0°, but less than 90°)
- **Right angle** (equals exactly 90°)
- **Obtuse angle** (greater than 90°, but less than 180°)
- **Straight line angle** (equals exactly180°)
- **Reflex angle** (greater than 180°, but less than 360°)
- **Revolution (perigon)** (equals exactly 360°)

Triangles

- A triangle is a closed shape with three edges.
- Triangles can be classified according to the lengths of their sides or the sizes of their angles.
- The sum of the three angles in a triangle is always 180°.

Triangles by side lengths:

- **Equilateral** (all sides equal)
- **Isosceles** (two sides equal)
- **Scalene** (no sides equal)

Triangles by angles:

- **Acute-angled**
- **Right-angled**
- **Obtuse-angled**

Quadrilaterals

- A quadrilateral is a closed shape with four edges.
- Quadrilaterals can be either convex or non-convex.
- The sum of the four angles in a quadrilateral is always 360°.
- Quadrilaterals can be divided into two major groups: **parallelograms** and **other quadrilaterals**.


Parallelograms:
- rectangle
- square
- rhombus

Other quadrilaterals:
- kite
- trapezium



Measuring and constructing angles


- An angle is made when two lines meet at a point.
- The point where the two lines meet is called the *vertex* and the lines are called the *arms* of the angle.
- Angles are measured in degrees (°).
- There are four important angles used in estimating angles: 90°, 180°, 270° and 360°.
- Circular and semicircular protractors can be used for measuring angles.




The angle is 65° (The other arm is at 0° on the inside scale, so we use the inside scale)

Parallel and perpendicular lines


- **Complementary angles** add to 90°.
- **Supplementary angles** add to180°.
- **Corresponding angles** are equal (F-shaped). $a = b$




- **Co-interior angles** add to180° (C-shaped). $x + y = 180°$



- **Alternate angles** are equal (Z-shaped). $a = b$



- **Vertically opposite angles** are equal (X-shaped). $a = b$



- Two lines are **perpendicular** if they meet at right angles (90°).

9.8.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
	I understand what an angle is.			
9.2	I can estimate angles.			
	I can measure angles using a protractor.			
9.3	I can draw an angle using a protractor.			
9.4	I can classify different types of angles according to size.			
	I can name angles using three points.			
9.5	I can classify triangles according to the lengths of their sides or the sizes of their angles.			
	I can calculate both interior and exterior angles of a triangle.			
9.6	I can classify quadrilaterals from a given diagram.			
	I can calculate the angles in a quadrilateral.			
9.7	I can identify and determine the size of vertically opposite angles.			
	I can identify and determine the size of angles formed when a transversal intersects parallel lines.			

9.8.3 Project

Tangrams

A tangram is an ancient Chinese puzzle game, also called *ch'i ch'ae pan* or Seven-board of Cunning. The first tangram books were printed in 1813, but the word *ch'i ch'ae* dates back to 740 – 330 BCE.


According to one Chinese legend:

> A servant of a Chinese emperor was carrying a very expensive square ceramic tray and, when he tripped and fell, it was shattered into seven pieces (called *tans*). He was unable to arrange the pieces back into the original shape, but he realised that there were many other shapes that could be built from the pieces.




Instructions

Trace the following tangram pieces onto cardboard and cut out each piece, then follow the instructions below.



1. Using only the two small triangles, make and draw the following shapes, showing the joins in your book.

a.



Square

b.



Triangle


c.



Parallelogram


2. Using the square, the two small triangles, the parallelogram and the medium triangle, make and draw the following shapes.

a.



Square

b.




Hexagon

c.




Trapezium


d.




Parallelogram

3. Using all the pieces, make and draw the following shapes.

a. 
Triangle

b. 
Rectangle

c. 
Hexagon

4. Use all of the pieces to make the following shapes and all of the other shapes from the previous questions.
   a. A rocket
   b. The letter E

Resources

eWorkbook Topic 9 Workbook (worksheets, code puzzle and project) (ewbk-1910)

Interactivities Crossword (int-2592)
Sudoku puzzle (int-3166)


Exercise 9.8 Review questions


learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


1. State the type of each of the angles shown here.


a. 


b. 

c. 

2. State the type of each of the angles shown here.

a. 

b. 


c. 

3. MC An acute angle has a magnitude that is:
   A. more than 90°
   B. less than 90°
   C. exactly 90°
   D. more than 90° but less than 180°
   E. less than 180°

4. MC A straight angle has a magnitude of:

A. 90° **B.** 270° **C.** 360° **D.** 180° **E.** 60°

Questions 5 and 6 refer to the following diagram.




5. MC The angle shown in the diagram has a magnitude of:

A. 50° **B.** 40° **C.** 90° **D.** 100° **E.** 190°

6. MC The angle shown in the diagram is:


A. a right angle **B.** a straight angle **C.** an acute angle
D. an obtuse angle **E.** a reflex angle

7. Name the angle shown.




8. Name the following triangles according to the lengths of their sides.


a.



b.




c.




9. Name the following triangles according to the sizes of their angles.


a.



b.




c.




10. Calculate the value of the pronumeral in each of the following.


a.



b.




c.




11. Calculate the value of the pronumeral in each of the following.


a.



b.




c.



12. Name the following quadrilaterals, giving reasons for your answers.


a.



b.




c.




13. Name the following quadrilaterals, giving reasons for your answers.


a.



b.




c.




14. Calculate the value of the pronumeral in each of the following quadrilaterals.


a.



b.




c.




15. Calculate the value of the pronumeral in each of the following quadrilaterals.


a.



b.




c.




16. Determine the value of each of the pronumerals, giving reasons for your answer.


a.



b.



c.




17. For each diagram:


a. state the type of angle relation that you use

b. calculate the value of the pronumeral.


i.



ii.



iii.



18. MC Select which of the following terms describes the angles a and b.

Hint: There may be more than one correct answer.


A. Equal

B. Corresponding

C. Allied

D. Alternate

E. Supplementary



19. MC Select which of the following terms describes the angles a and b.

Hint: There may be more than one correct answer.


A. Vertically opposite

B. Corresponding

C. Co-interior

D. Alternate

E. Equal



20. MC Select which of the following terms describes the angles a and b.

Hint: There may be more than one correct answer.


A. Corresponding

B. Co-interior

C. Alternate

D. Supplementary

E. Equal



21. MC Select which of the following terms describes the angles a and b.

Hint: There may be more than one correct answer.


A. Vertically opposite

B. Corresponding

C. Allied


D. Alternate

E. Supplementary




Problem solving

22. The teepee shown has an angle of 46° at its peak. What is the size of the angle, w, that the wall makes with the floor?




23. A circus trapeze is attached to a rope as shown in the diagram. Calculate the size of angle t.




24. Triangles can be classified according to the number of sides of equal length (scalene, isosceles or equilateral) and by the type of angles (acute, obtuse or right). Decide which of the following combinations are possible. Draw examples of the combinations that are possible.


- Right–scalene, right–isosceles, right–equilateral
- Acute–scalene, acute–isosceles, acute–equilateral
- Obtuse–scalene, obtuse–isosceles, obtuse–equilateral

25. The following triangles are both equilateral triangles, but the side length of triangle ABC is 3 units and the side length of triangle DEF is 6 units. Determine how many of the smaller triangles would you need to fill the larger triangle.







26. If angle AOE is obtuse, name all of the acute angles in the diagram below.



27. An equilateral triangle EDC is drawn inside a square ABCD as shown below. Determine the size of ∠AED.



28. WXYZ is a rectangle as shown here. Points P and Q are drawn so that XY = PY and ∠XPQ = 100°. Determine the size of ∠PQX.





To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1910) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0698) ☐

Digital documents

9.2 SkillSHEET Reading the scale on a protractor (doc-6447) ☐
SkillSHEET Comparing the size of angles (doc-6448) ☐
SkillSHEET Estimating the size of an angle (doc-6449) ☐
SkillSHEET Measuring angles with a protractor (doc-6450) ☐
9.3 SkillSHEET Constructing angles with a protractor (doc-6451) ☐
9.4 SkillSHEET Classifying angles (doc-6452) ☐
SkillSHEET Naming angles (doc-6453) ☐
9.5 SkillSHEET Classifying triangles according to the length of their sides (doc-6454) ☐
SkillSHEET Classifying triangles according to the size of their angles (doc-6455) ☐

Video eLessons

9.2 Understanding angles (eles-4089) ☐
Measuring angles (eles-4090) ☐
9.3 Constructing angles with a protractor (eles-4092) ☐
Constructing angles greater than 180° using a semicircular protractor (eles-4093) ☐
9.4 Types of angles (eles-4094) ☐
Naming angles (eles-4095)
9.5 Naming triangles (eles-4096) ☐
Angles in a triangle (eles-4097) ☐
Interior and exterior angles of a triangle (eles-4098) ☐
9.6 Types of quadrilaterals (eles-4100) ☐
Angles in a quadrilateral (eles-4101) ☐
9.7 Vertically opposite and adjacent angles (eles-4102) ☐
Parallel and perpendicular lines (eles-4103) ☐
Calculation of angles associated with parallel lines (eles-4104) ☐
Testing for parallel lines (eles-4105) ☐
Parallel lines (eles-2309) ☐

Interactivites

9.2 Individual pathway interactivity: Measuring angles (int-4331) ☐
The circular protractor (int-3952) ☐
The semicircular protractor (int-3953) ☐
9.3 Individual pathway interactivity: Constructing angles with a protractor (int-4332) ☐
Construction of angles using a circular protractor (int-3954) ☐
Construction of angles using a semicircular protractor (int-3955) ☐
9.4 Individual pathway interactivity: Types of angles and naming angles (int-4333) ☐
Types of angles (int-3961) ☐
Names of angles (int-3962) ☐
9.5 Individual pathway interactivity: Triangles (int-4334) ☐
Classification of triangles – sides (int-3963) ☐
Classification of triangles – angles (int-3964)
Angles in a triangle (int-3965) ☐
Interior and exterior angles of a triangle (int-3966) ☐
9.6 Individual pathway interactivity: Quadrilaterals and their properties (int-4335) ☐
Types of quadrilaterals (int-4025) ☐
Angles in a quadrilateral (int-3967) ☐
9.7 Individual pathway interactivity: Parallel and perpendicular lines (int-4336) ☐
Vertically opposite and adjacent angles (int-3968) ☐
Corresponding angles (int-3969) ☐
Co-interior angles (int-3970) ☐
Alternate angles (int-3971) ☐
Calculation of angles associated with parallel lines (int-3972) ☐
Testing for parallel lines (int-3973) ☐
9.8 Crossword (int-2592) ☐
Sudoku puzzle (int-3166) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**

Answers

Topic 9 Geometry

Exercise 9.1 Pre-test

1. Obtuse
2. 135°
3. 90°
4. D
5. D
6. C
7. ∠ADB
8. A
9. E
10. a. Scalene, right-angled triangle
    b. Isosceles, acute-angled triangle
    c. Scalene, obtuse-angled triangle
    d. Isosceles, right-angled triangle
11. 59°
12. 52°
13. 68°
14. D
15. 72°

Exercise 9.2 Measuring angles


1. a. B b. B
2. a. 40° b. 81° c. 75° d. 13°
3. a. 142° b. 107° c. 162° d. 103°
4. a. 240° b. 201° c. 316° d. 356°
    e. The accuracy of your measurement will depend on the thickness of your pencil, the position of the protractor and the side from where the angle is read.
5. a. 45° b. 155° c. 180° d. 63°
6. a. Difficult, as angle is approximately 7°
    b. As recommended
7. a. 57°, 105°, 33°, 75°
    b. 57° and 33°
    c. 105°, and 75°
    d. Multiple correct answers: four 57°, and four 33°, two 105° and two 75°, two 57°, two 33°, one 105° and one 75°
8. a. Design 4. 45°
    b. Design 1. 15°
    c. Design 1, Design 2 and Design 3
    d. Design 1
    e. Design 3
    f. Design 1
9. a, b, d, e, f, g. — various answers are possible.
    c.


Diagram	Measured angle
1	190°
2	130°
3	110°
4	40°
5	300°
6	200°
7	140°
8	290


10. a. As the kite moves from point A to point B, the angle increases from 0° to 90°
    b. As the kite moves from point B to point C, the angle decreases from 90° to 0°.
11. a. i. 210° (reflex angle) and 150° (obtuse angle)
    ii. 180° (straight angle) and 180° (straight angle)
    iii. 150° (obtuse angle) and 210° (reflex angle)
    iv. 15° (acute angle) and 345° (reflex angle)
    v. 108° (obtuse angle) and 252° (reflex angle)
    vi. 114° (obtuse angle) and 246°(reflex angle)
    b. 360° ÷ 60 minutes = 6°; 360° ÷ 12 hours = 30°
12. a. Triangle 1: 45°, 45°, 90°, Triangle 2: 80°, 40°, 60°, Triangle 3: 70°, 60°, 50°
    b. 180°, 180°, 180°
    c. Brinda is correct, there is a pattern. The pattern is that the angles within a triangle always add to 180°.


Exercise 9.3 Constructing angles with a protractor


1. a. 


b. 


c. 

d. 


2. a. 

b. 


c. 

d. 


3. a.




b.




c.




d.




4. a.




b.




c.




d.



5. a.




b.



c.



d.




6. a.



b.



c.



d.




7. E

8. a.




b.



c.




d.




9. a.



b.




c.




d.




10. a. (i)




(ii)



(iii)



(iv)




(v)




b. 45°, 90°, 180°, 90°, 45°


11. a.



b.



c.




d. 187°

e. 360°

12. 120°, 20° and 90°


13. Construct the corresponding acute angle and then label the reflex angle.

14. a.




b. 40°


15. a.




b.



c.




16. a.



3 cm

b.




6 cm

c. Sample response: Similarities include angles, ratios of sides, same shape. Differences include sizes, areas, accuracy.

d. 60°

17. a.



b. All triangles should be identical.

c. If two equal angles are drawn at the ends of a straight line of set length, there is only one size triangle that forms.

18. Draw any triangle on an A4 sheet of paper.

a-d. Student activity; responses will vary.

e. Despite different triangles drawn by students, the sum of the angles of a triangle is always 180°.

Exercise 9.4 Types of angles and naming angles

1. a. Acute b. Reflex c. Obtuse
   d. Straight e. Reflex

2. a. Right b. Acute c. Revolution
   d. Acute e. Reflex

3. a. 4; 3°, 45°, 65°, 69°
   b. 2; 123°, 165°
   c. 4; 234°, 300°, 270°, 210°


4. a. True b. True c. True

5. a. Right b. Straight c. Obtuse
   d. Acute e. Reflex f. Revolution


6. a. ∠XUV or ∠VUX b. ∠PQR or ∠RQP
   c. ∠SDX or ∠XDS d. ∠GPZ or ∠ZPG
   e. ∠PFH or ∠HFP

7. In each case the middle letter should be at the vertex of the angle.


a.




b.



c.




8. a.




In each case the middle letter should be at the vertex of the angle.

b.



In each case the middle letter should be at the vertex.

c.



9. Acute

10. Revolution

11. Obtuse

12. Acute: ∠NOM, ∠MOY
Obtuse: ∠MOX

13. Acute: ∠PQS, ∠RQO
Obtuse: ∠SQR, ∠SQO, ∠RQP

14. a. Acute: ∠MLN, ∠NLO, ∠OLP, ∠PLK, ∠NLP, ∠OLK
Obtuse: ∠MLO, ∠MLP, ∠NLK

b. Acute: ∠YOX, ∠WOQ, ∠POQ
Obtuse: ∠XOW, ∠YOP, ∠YOW, ∠XOP, ∠YOQ, ∠POW

15. a. Acute **b.** Right **c.** Obtuse

16. a. Straight **b.** Reflex **c.** Revolution

17. a. Acute **b.** Obtuse
c. Straight **d.** Right
e. Obtuse

18. a. Sample responses:
1 o'clock, 10 o'clock

b. Sample responses:
4 o'clock, 20 past 11

c. Sample responses:
9 o'clock, 3 o'clock

19. In each case the middle letter should be at the vertex of the angle.

a. ∠DEF

b. ∠ABC, ∠XWY

c. ∠PQR

d. Sample responses:
outside angle ∠DEF,
outside angle ∠RQP

20. a. This statement is true if the sum of the two angles is less than 90°.


b. This statement is true if the sum of the two angles is equal to 90°.

c. This statement is true if the sum of the two angles is greater than 90°.

d. This statement is untrue because two acute angles can't add up to more than 180°.

21. a. Yes


b.



22. 145°

23. It is the naming custom to always put the letter representing the vertex in the middle of the angle's name because this allows anyone to understand the name of the angle.

24.



25. a. 25 including revolutions, 20 if revolutions not included

b. 165°

Exercise 9.5 Triangles

1. a. ΔABC Scalene
b. ΔLMN Equilateral
c. ΔXYZ Isosceles
d. ΔPQR Isosceles
e. ΔRST Scalene

2. a. Right-angled triangle
b. Acute-angled triangle
c. Acute-angled triangle
d. Acute-angled triangle
e. Obtuse-angled triangle

3. A

4. B

5. D

6. A

7. a. $x = 57°$ **b.** $g = 125°$ **c.** $t = 44°$
d. $k = 60°$ **e.** $f = 93°$ **f.** $z = 90°$

8. a. $d = 45°$ **b.** $b = 65°$ **c.** $a = 50°$


9. a. $c = 70°$ **b.** $e = 76°$ **c.** $n = 52°$

10. a. $u = 66°$ **b.** $k = 45°$ **c.** $d = 76°$
d. $t = 74°$ **e.** $f = 57°$ **f.** $p = 70°$


11. a. $p = 50°; n = 70°$ **b.** $a = 22°; b = 28°$
c. $x = 40°; y = 50°$ **d.** $t = 35°; s = 55°$

12. a. $b = 46°$ **b.** $n = 21°$
c. $m = 60°$ **d.** $t = 28°$


13. a.




b.




c.




14. a.



b.



c.



15. c. Please see the worked solutions; The longest side is 10 cm in length. (**a**, **b**, **d**; Please see the worked solutions).

16. a. $b = 20°$ **b.** $k = 30°$

17. a. $\angle MPN = 72°$ and $\angle NMP = 36°$

b. $\angle MPN = 54°$ and $\angle MNP = 54°$

18. a. The sum of the angles will be greater than 180°.


b. Start with an equilateral triangle ABC, equal sides and 3 equal angles. If point A and C are fixed and point B is extended, length AB increases. This in turn means that length BC increases and therefore $\angle C$ increases in size. The longest side (in this case AB) will be opposite the largest angle (in this case $\angle C$). This is true for all triangles, with the longest side always being opposite the largest angle.

c. Imagine that the base of a triangle is the longest side. The other two side lengths must be attached to opposite vertices of the base of the triangle. If the sum of these two lengths was shorter than the base length then these two sides could not meet and complete the triangle. Similarly, if the sum of these two lengths was equal to the base length then they could only meet in a straight line along the base, and a triangle would not be created. Therefore the sum of the two lengths must be longer than the base length to create a triangle.

19. a.




b.




c. 40°

d.



e. 20°

f.



$\angle F = 10°$

The angle is halved every time a new triangle is constructed.

20. a. 70° **b.** 156° **c.** 50° **d.** 64°

21. a. Yes, angles add up to 180°.

b. No, angles add up to 175°.

c. No, angles add up to 185°.

d. Yes, angles add up to 180°.

22. a. $a = 69°, k = 10, b = 114°$

b. $a = 60°, c = 120°$

Exercise 9.6 Quadrilaterals and their properties

1. a. Non-convex
b. Convex
c. Convex
d. Non-convex

2. a. i. Square
ii. Trapezium
iii. Kite
iv. Rhombus
v. Rectangle
vi. Irregular quadrilateral

b. i. Square: 4 sides equal, 4 angles equal
ii. Trapezium: one pair of parallel sides
iii. Square: 4 equal sides and angles
iv. Kite: adjacent sides equal

3. E

4. E

5. A

6. a. $t = 138°$ **b.** $t = 90°$ **c.** $t = 202°$
d. $p = 92°$ **e.** $c = 66°$ **f.** $k = 67°$

7. a. $m = 78°$ (opposite angles of parallelogram equal)
b. $u = 75°$ (opposite angles of rhombus equal)
c. $t = 132°$ (opposite angles of a kite equal)
d. $f = 108°$ (opposite angles of a kite equal)
e. $p = 63°$ (opposite angles of rhombus equal)
f. $z = 73°$ (opposite angles of parallelogram equal)

8. a. $a = 129°, b = 51°, c = 129°$
b. $h = 130°$

9. a. $m = 113°$
b. $c = 98°, d = 82°$
c. $t = 116°$
d. $p = 52°, m = 106°$
e. $t = 103°,\ x = 91°$
f. $m = 65°,\ p = 115°, n = 65°$

10. D

11. E

12. a. True **b.** True
c. False **d.** True
e. True


13. D

14. $p = 61°$

15. 115°

16. 45° and 135°


17.



18. a. Yes, angles add up to 360°.
b. No, angles add up to 270°.

19. a. 130°
b. Infinite number


c.



20. a. Two smaller obtuse-angled isosceles triangles, one larger size obtuse-angled isosceles triangle and two right-angled scalene triangles.

b. Two types: rectangles (of different sizes) and a rhombus.

c.



d. In both right-angled triangles, the angles are: 27°, 63°, 90°; in all isosceles triangles, angles are: 126°, 27°, 27°; in the rhombus, angles are: 126°, 54°, 126°, 54°; in all rectangles, all angles are 90° each.

21. a. Consider the sum of the angles of the two triangles ABC and ACD.
In ΔABC : $n + p + q = 180°$
In ΔACD : $m + r + s = 180°$
In quadrilateral ABCD : $n + p + q + m + r + s = 360°$

b. i. 540°
ii. 720°
iii. 1080°
iv. 1440°

22. a. $a = 70°, b = 125°, c = 125°$
b. $x = 78°, k = 102°, m = 74°$

23. a. $a = 108°, b = 72°, c = 90°$
b. $g = 100°, h = 80°, i = 50°$
c. $d = 115°, e = 106.5°, f = 82°$
d. $j = 45°, k = 135°$

24. 102°

Exercise 9.7 Parallel and perpendicular lines

1. 65°

2. a. 19° **b.** 45°

3. 136°

4. a. 10° **b.** 60° **c.** 13°

5. a. 38° **b.** 110° **c.** 22°

6. a. 19°

b. $e = 39°, f = 141°, g = 141°$

c. $i = 13°, h = 15°, k = 152°, j = 152°$

7. a. C **b.** D **c.** B **d.** A

8. a. i. Corresponding angles

ii. Alternate angles

iii. Vertically opposite angles

iv. Corresponding angles

v. Co-interior angles

vi. Co-interior angles

b. i. $p = 60°$

ii. $q = 45°$

iii. $s = 65°$

iv. $t = 72°$

v. $m = 110°$

vi. $n = 48°$

9. a. $y = 116°$, corresponding

b. $z = 38°$, alternate

c. $b = 136°$, supplementary

10. a. 68°, vertically opposite

b. 90°, corresponding



11. c, f

12. b, e, f

13. a. 25° **b.** 57°

14. a. 45° **b.** 55°

15.

Diagram	Type of angle relation	Associated shape	Rule
	Corresponding	F	Are equal
	Alternate	Z	Are equal
	Co-interior	C	Add to 180°

16. a. C **b.** D **c.** A **d.** B

17. a. a and d, c and b, e and h, f and g

b. a and e, c and g, b and f, d and h

c. c and e, d and f

d. c and f, d and e

18. a. 123° **b.** 43° **c.** 45°

19. a. 28° **b.** 50° **c.** 70°

20. No, because $48° + 133° \neq 180°$. For parallel lines, co-interior angles need to add to 180° (or alternate angles must be equal).

21. a. 52°. The three angles forming the straight line add to 180°.

b. Yes. $52° + 128° = 180°$, so lines parallel as co-interior angles add to 180°.

c. 52°, 55°. Exterior angle: 125°

22. a. The vertical lines are parallel, the horizontal lines are parallel and the oblique lines are parallel because they are equally distant from each other.

b. The vertical lines are parallel and the horizontal lines are parallel because they are equally distant from each other.

23. 60°

24. a. 130° **b.** 50°


25. Acute $\angle PQR = 67°$ and reflex $\angle PQR = 293^{\circ}$.

Project

1. a.



b.



c.



2. a.




b.



c.




d.



3. a.



b.




c.



4. a.




b.




Exercise 9.8 Review questions

1. a. Revolution
   b. Right angle
   c. Straight angle
2. a. Obtuse b. Reflex c. Acute
3. B
4. D
5. C
6. A
7. ∠EDF or ∠FDE
8. a. Equilateral triangle
   b. Scalene triangle
   c. Isosceles triangle
9. a. Obtuse-angled triangle
   b. Acute-angled triangle
   c. Right-angled triangle
10. a. $t = 67°$ b. $b = 28°$ c. $x = 75°$
11. a. $p = 56°$ b. $m = 64°$ c. $n = 60°$
12. a. Rectangle b. Parallelogram c. Trapezium
13. a. Kite b. Square c. Rhombus
14. a. 75° b. 55° c. 42°
15. a. 66° b. 112° c. 126°
16. a. $x = 15°$ because vertically opposite angles are equal.
    b. $x = 50°$ because corresponding angles are equal and the angle sum of a straight line is 180°,
    $y = 25°$ because corresponding angles are equal.
    c. $y = 100°$ because co-interior angles add to 180°, $x = 8°$
    The sum of the interior angles of a triangle equals 180°.
    Since $90 + 50 = 140$ and $180 - 140 = 40$, $5x = 40$.
    Therefore $x = 8$.
17. a. i. Alternate angles
    ii. $x = 60°$
    b. i. Vertically opposite angles
    ii. $y = 135°$
    c. i. Vertically opposite angles, then co-interior angles, then vertically opposite angles. Another solution is supplementary angles, followed by corresponding angles.
    ii. $t = 50^{o}$
18. A, B
19. A, E
20. C, E
21. C
22. 67°
23. 115°
24. Because an equilateral triangle has 3 congruent angles, right-equilateral and obtuse-equilateral are not possible.
    Examples of the other triangles:
    i.



Right–scalene

    ii.




Right–isosceles

iii.




Acute–scalene

iv.



Acute–isoceles

v.



Acute–equilateral

vi.



Obtuse–scalene

vii.



Obtuse–isosceles

25. 4
26. ∠BOE, ∠BOD, ∠BOC, ∠COE, ∠COD, ∠DOE
27. 75°
28. 35°

10 Measurement

LEARNING SEQUENCE

10.1 Overview 520
10.2 Units of measurement 523
10.3 Reading scales and measuring length 530
10.4 Perimeter 538
10.5 Area 546
10.6 Area of composite shapes (extending) 559
10.7 Volume of rectangular prisms 564
10.8 Capacity 572
10.9 Drawing solids 576
10.10 Review 587



10.1 Overview

Why learn this?



Measurement, together with geometry, is important in our everyday lives. We are able to describe objects using numbers and units of measurement, such as millimetres, centimetres, grams and kilograms. How far is it from your home to the nearest beach? What is the size of a tennis court or a football ground? How long is a cricket pitch? How much sugar is in your favourite cookie? All of these questions and thousands more are answered using measurement.

When we measure objects we need to understand the units of measurement. Which is longer, a centimetre or a millimetre? Can you change centimetres to millimetres and millimetres to centimetres? From stump to stump, a cricket pitch is 20.12 metres or 2012 centimetres or 20120 millimetres!

Olympic swimming pools need to be 50 metres long and 25 metres wide. Builders must know these dimensions before constructing a pool. Before anything can be made, you need to decide how small or large it will be — that is, its dimensions or measurements. We use measurement to describe length, perimeter, area, volume and capacity every day. Can you imagine trying to build your home without first knowing what its size will be? Many professionals use measurement in their day-to-day work. Among these are property developers, builders, engineers, designers, dressmakers, chefs, architects and construction workers.

DISCUSSION

Why is it important to have an international standard metric system? Which countries don't follow this system?

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 10.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.


1. Convert 0.565 m into cm.

2. If the length of a cricket pitch is 20.12 m, calculate its length in km.

3. If the height of a city building is 36 m and it measures 10 cm in a photo, calculate how tall a building that measured 25 cm in a photo would be in real life.


4. Luca went for a training run that was 1200 strides long. If each of his strides was 1.5 m, calculate the total distance he covered.

5. Determine the perimeter of this figure.




6. A rectangular pool has a perimeter of 34 m. If a concrete border of width 2 m was laid around the pool, calculate the perimeter around the outer section of the concrete border.

7. Determine the area of the triangle at right.



8. A rectangular room with dimensions 3.5 m by 6 m is to be carpeted at a cost of $22.50 per m^2.
Calculate the total cost to carpet the room.

9. Calculate the area of the figure at right.



10. A rectangular wall 6.2 m by 2.4 m is to be painted.
A rectangular cabinet 1.8 m by 1.2 m rests against this wall.
The area to be painted does not include the area of the cabinet.
Calculate the area of the wall to be painted.


11. Calculate the volume of a rectangular prism with a length of 8 m, a width of 3 m and a height of 2 m.

12. A rectangular prism has a volume of 112 cm^3.
If it has a height of 2 cm and a width of 8 cm, determine its length.


13. A rectangular sink has a length of 45 cm, width of 40 cm and a depth of 30 cm. Calculate the sink's capacity, in litres.

14. Match the following three-dimensional shapes to their plan views.


a.




b.




c.



d.




e.




Plan views:


i.



ii.




iii.



iv.



v.



15. Select the correct shape that represents each of the following views.

a. MC The top view of a telephone pole

A. Oval **B.** Circle **C.** Trapezium **D.** Rectangle **E.** Triangle

b. MC The top view of the Sydney Cricket Ground

A. Oval **B.** Circle **C.** Trapezium **D.** Rectangle **E.** Triangle

c. MC The side view of a bucket

A. Oval **B.** Circle **C.** Trapezium **D.** Rectangle **E.** Triangle

d. MC The top view of a car

A. Oval **B.** Circle **C.** Trapezium **D.** Rectangle **E.** Triangle

10.2 Units of measurement

LEARNING INTENTION

At the end of this subtopic you should be able to:

- convert between different units of length.

10.2.1 Metric units of length

eles-4549

- The metric system is based on the number 10.
- The base unit of length of the metric system is the metre.
- The following figures show the most commonly used units of length along with their abbreviations and photos showing approximate examples.

1. Kilometre (km)



One kilometre is the distance travelled in one minute by a car travelling at a speed of 60 kilometres per hour.

2. Metre (m)



The length of an adult's stride

3. Centimetre (cm)



The width of each of your fingers

4. Millimetre (mm)



The width of a wire in this computer chip

DISCUSSION

Where do you use measurement in your everyday life?

WORKED EXAMPLE 1 Identifying the most appropriate unit of length

You have been given the task of measuring the width of an A4 page. State which metric units of length you would use.

THINK

Estimate the length involved. In this case, it will be less than a metre and more than a centimetre. Consider which unit would be easiest to use. If you use metres, the width would be expressed as a decimal. If you use centimetres, the width would be expressed as a whole number. Therefore, centimetres is the best choice of unit.

WRITE

Centimetres (or cm)

eles-4550


10.2.2 Converting units of length

- The main metric units of length are related as follows:

$$1\text{ km} = 1000\text{ m} \quad 1\text{ m} = 100\text{ cm} \quad 1\text{ cm} = 10\text{ mm}$$

Unit conversion

Units of length can be converted as shown in the following diagram. The numbers next to each arrow are called **conversion factors**.



- When converting from a larger unit to a smaller unit, multiply by the conversion factor.
- When converting from a smaller unit to a larger unit, divide by the conversion factor.

WORKED EXAMPLE 2 Converting units of length

Complete each of the following metric conversions.

a. 0.3285 km = _____ m


b. 560 m = _____ mm

c. 480 cm = _____ km

d. $2\frac{3}{5}$ m = _____ cm

THINK


a. To convert kilometres to metres, multiply by 1000. (Move the decimal point 3 places to the right.)




WRITE

a. 0.3285 km = 0.3285 × 1000 m
= 0.3285
= 328.5 m

b. To convert from metres to centimetres, multiply by 100 (since there is no decimal point, place two zeros after the final digit).




To convert from centimetres to millimetres, multiply by 10 (place one zero after the final digit).




Note: Overall, we need to multiply by 100×10 or 1000.

c. To convert from centimetres to metres, divide by 100 (move the decimal point 2 places to the left).




To convert from metres to kilometres, divide by 1000 (move the decimal point 3 places to the left).



d. 1. Convert $2\frac{3}{5}$ m to an improper fraction.

2. Convert metres to centimetres by multiplying by 100.



Note: Remember when multiplying fractions by a whole number, the number multiplies the numerator.

3. Simplify the fraction.

b. $560\text{ m} = 560 \times 100\text{ cm}$
$= 56\,000\text{ cm}$

$= 56\,000 \times 10\text{ mm}$
$= 560\,000\text{ mm}$

c. $480\text{ cm} = 480 \div 100\text{ m}$
$= 4.8\text{ m}$

$= 4.8 \div 1000\text{ km}$
$= 0.0048\text{ km}$

d. $2\frac{3}{5}\text{ m} = \frac{2 \times 5 + 3}{5}\text{ m}$
$= \frac{13}{5}\text{ m}$

$= \frac{13}{5} \times 100\text{ cm}$
$= \frac{1300}{5}\text{ cm}$

$= 260\text{ cm}$

Resources

eWorkbook	Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)
Digital documents	SkillSHEET Metric units of length (doc-6505) SkillSHEET Measuring the length of a line (doc-6507) SkillSHEET Relationship between unit size and the number of units used (doc-6508) SkillSHEET Converting units (doc-6509) SkillSHEET Converting units to compare lengths and distances (doc-6510)
Interactivities	Individual pathway interactivity: Units of measurement and converting units of measurement (int-4355) Metric units of length (int-4010) Converting units of length (int-4011)

Exercise 10.2 Units of measurement

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 4, 6, 9, 14, 16, 18, 20, 25, 28	2, 5, 7, 11, 13, 15, 17, 22, 23, 26, 29, 30	8, 10, 12, 19, 21, 24, 27, 31, 32, 33, 34

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 State which metric units (mm, cm, m or km) would be most suitable for measuring the real lengths marked in each photograph.


a. The length of a large kangaroo




b. Large distances between towns



c. The diameter of a DVD



d. The diameter of a planet



e. The height of a tall building



2. State which metric units of length you would use for measuring the following.

a. The length of a netball court
b. The diameter of a netball
c. The distance between Melbourne and Sydney
d. The thickness of a magazine

3. MC Select which unit you would use to measure and compare the thicknesses of two different brands of chocolate biscuits.

A. millimetres
B. kilometres
C. metres
D. centimetres
E. kilometres or metres

4. WE2 Complete each of the following metric conversions.

a. 2.0 km = _____m
b. 7.0 km = _____m
c. 5.3 km = _____m
d. 0.66 km = _____m

5. Complete each of the following metric conversions.

a. 0.25 m = _____cm
b. 28.0 cm = _____mm
c. 200.0 cm = _____mm
d. 700.0 m = _____cm

6. Convert to the units indicated.

a. 8000 m = _____km
b. 6500 m = _____km
c. 700 m = _____km
d. 50 m = _____km

7. Convert to the units indicated.

a. 6000 cm = _____m
b. 57 cm = _____m
c. 45 mm = _____cm
d. 25 600 mm = _____cm

8. Convert to the units indicated.

a. 8 km = _____cm
b. 101 m = _____mm
c. 72.33 m = _____mm
d. $30\frac{7}{20}$ mm = _____m

9. MC Identify which of these distances is the same as 6.25 km.

A. 625 m
B. 0.006 25 m
C. 625 000 mm
D. 625 000 mm
E. 62.50 cm

10. MC Identify which of these distances is the same as 7 860 000 cm.

A. 78.6 km
B. 786 m
C. 786 km
D. 786 000 mm
E. 7.86 km

11. Convert to the units indicated.

a. $45\frac{1}{5}$ m to km
b. 560 mm to m
c. $8\frac{3}{4}$ cm to mm

12. Convert to the units indicated.

a. 0.0006 km to cm
b. $3\frac{9}{100}$ km to cm
c. 48 mm to cm

Understanding

13. Give an example of a length that each of the following people might measure in their jobs. (For example, a carpet layer would measure the length of a room.)

a. Veterinary surgeon
b. Costume designer
c. Carpenter
d. Landscape gardener
e. Field athlete

14. The longest snake ever held in captivity was a female reticulated python named Colossus. She measured 8.68 m long. The shortest species of snake, the West Indian *Leptotyphlops bilineatus*, only grows to 108 mm. Write, in centimetres:

a. the length of the longest snake
b. the length of the shortest snake.



15. The world's highest mountains are Everest (8848 m) and K2 (8611 m). Convert these heights to kilometres.



16. Arrange the following in order from smallest to largest.

a. 12.5 m, 150 cm, 0.02 km
b. 350 cm, 0.445 m, 3000 mm
c. 50 km, 500 m, 50 000 mm

17. Arrange the following in order from smallest to largest.

a. 1700 cm, 1.7 m, 0.17 km
b. 0.052 cm, 0.0052 mm, 0.000 052 m
c. 990 cm, 0.909 m, 9000 mm

18. Add the following lengths, giving your answer in the specified unit.

a. 75 cm and 3 m: cm
b. 2700 m and 7.5 km: m
c. 1.66 m and 58.2 cm: cm
d. 0.000 675 km and 87.8 cm: cm

19. Calculate the difference between each of the following lengths, giving your answer in the specified unit.

a. 72 km and 5600 m: m
b. 418 000 mm and 7.6 m: m
c. $34\frac{3}{5}$ cm and $\frac{9}{20}$ m: cm
d. $2\frac{4}{5}$ km and 450 000 cm: km

20. The tallest building in Dubai is the Burj Khalifa, which stands 0.828 km high. Convert this height to metres.



21. A builder needs to build a wall 3.5 m high. If each layer of bricks adds 8 cm of height, calculate how many layers of bricks are in the wall.

22. Deanne buys a length of rope and cuts it into three smaller sections, each of length 7200 cm.
Calculate how long the original piece of rope measured.

23. Norbert is 1.53 m tall in bare feet. If he wears shoes with soles that are 6.3 cm thick, calculate how tall he is when wearing these shoes, in metres.

24. Adrian is driving a truck with a rooftop 3.4 m above road level when he approaches an overpass bridge that has a clearance of 376 cm. Determine whether Adrian's truck will fit under the bridge. If so, state the room he has spare, in centimetres.

Reasoning

25. Zvenglo is stacking identical boxes of height 330 mm. Calculate the height of a stack of six boxes, in centimetres.

26. Finita attaches a trellis that is 0.6 m high to the top of her 180 cm high fence. Calculate the height to the top of the new trellis from ground level. Give your answer in metres.

27. Astronomers use light-years as a measure of distance in the universe. A light-year is the distance travelled by light in one year. If light travels approximately 300 000 km in one second, calculate the distance travelled by light in:



a. **i.** one minute **ii.** one hour
iii. one day **iv.** one year (365 days).

b. Explain why astronomers use this measurement for distance rather than kilometres.

Problem solving

28. A pin, 14 mm long, is made of wire. Determine how many whole pins could be made from 1 km of wire.

29. A licorice strap machine takes 3.80 m lengths of licorice and chops them into 10 cm long pieces. Determine how many pieces each 3.80 m length produces.

30. Waldo's noticeboard is 1.5 m long and 1.2 m wide. If he pins a calendar of length 70 cm and width 60 cm exactly in the middle of the board, determine the distance from the top of the calendar to the top of the noticeboard. (*Hint:* Draw a diagram of the situation.)


31. A childcare centre has three large cardboard boxes that the children stack up in various combinations. What stack heights are possible if the boxes' individual heights are 600 mm, 45 cm and 1.1 m? Give your answer in centimetres.

32. A mother and daughter are riding their bikes to the local market. The circumference of the mother's bike wheel is 2 m while the circumference of the daughter's bike wheel is 1 m.

a. Calculate the number of rotations of the wheel there are in 100 m for the:
i. mother **ii.** daughter.

b. Calculate the number of rotations of the wheel there are in 1 km for the:
i. mother **ii.** daughter.

33. In a 'log cabin' quilt, a pattern is created from a series of squares and rectangles. From a centre square, 4 congruent rectangles are placed to build a larger square. This process is repeated a number of times to build larger and larger squares. Laurel starts with a centre square of side length 2 cm. If each rectangle has a width of 2 cm and a length that depends on its position in the block, give the dimensions of the rectangles that will need to be cut if the final block is to be 18 cm square. (Don't worry about seam allowance.)



34. It is said that the average person walks the equivalent of four times around the Earth in a lifetime. The circumference of the Earth is about 40 000 km. If you lived to age 80, approximate the number of kilometres per week you would walk to achieve this distance.

10.3 Reading scales and measuring length

LEARNING INTENTION

At the end of this subtopic you should be able to:

- read and interpret various scales.

eles-4551

10.3.1 Reading scales and measuring length

- A **scale** is a set of levels or numbers used to measure length, mass, temperature or any other quantity.

Reading scales

When reading scales and measuring lengths:

- check that the scale starts with zero
- check the value of each small division by counting along the scale to the next major mark
- always give units (for example, centimetres or kilograms) with your answer.



WORKED EXAMPLE 3 Reading a scale


State the reading indicated by the arrow, giving answers in:

i. decimal form **ii. fractional form where appropriate.**

a.



b.



THINK

a. i. 1. Check that the line starts at 0. It does.

2. Note the units printed on the ruler (cm).

3. Read the last centimetre mark (5).


4. Does the line go past the last centimetre mark? No.

5. Write the answer with units.

ii. There is no need to write in fractional form as the value is a whole number.

WRITE

a. i.



5 cm

b. i. 1. Check that the line starts at 0. It does.

2. Note the units printed on the ruler (cm).


3. Read the last centimetre mark (7).

4. Consider how many smaller intervals (or divisions) there are between each number. There are 10, so each smaller division represents 0.1 of a unit.

5. Count the number of small divisions past the last centimetre mark (3).

6. Write the answer with units.

b. i.



7.3 cm

ii. Express the answer obtained in **b i** as a fraction. Recall the conversion of decimals to fractions.

ii. $7.3 = \frac{73}{10}$ cm

Or, $7\frac{3}{10}$ cm

WORKED EXAMPLE 4 Applying a scale

Use the given length of the climber's lower leg to estimate the labelled length of the rope in the following diagram.



THINK

1. Refer to the 0.5 m lengths indicated on the diagram and determine how many of these lengths correspond to the unknown length of the rope above the climber.
Note: There are approximately $3\frac{1}{2}$ or 3.5 of these lengths in the rope.

2. Multiply the number of lengths by 0.5 m.

3. Write the answer.

WRITE

From the diagram there are approximately $3\frac{1}{2}$ (or 3.5) of these lengths in the rope.




$\text{Length} = 3.5 \times 0.5$
$= 1.75$

The length of the rope is approximately 1.75 m.

COLLABORATIVE TASK: Using your body to estimate lengths

To help improve your ability to estimate lengths, you can use different parts of your body for reference.

1. Use a ruler or a tape measure to measure the following distances and complete the following table.

	Digit width	Handwidth	Fathom	Cubit	Arm length
Picture of measurement					
Your measurement					

2. Complete the following sentences.
   a. One metre is _____.
   b. The bottom of my knee is _____ off the floor.
3. As a class, select a range of objects around the room and:
   a. estimate the dimensions simply by looking at the object
   b. estimate the dimensions using a body part as a reference
   c. measure the dimensions using a ruler or tape measure.
4. Make a table, like the following one, to record your data for each object. A sample is shown.

Object and dimension	First estimate	Number and type of body part unit	Estimate using body parts	Length, using a ruler or tape measure
Height of door	190 cm	$23\frac{1}{2}$ handwidths	$23.5 \times 7.5\text{ cm} = 176.25\text{ cm}$	180 cm
Length of pen				

5. List some other body dimensions that you could use to estimate length: for example, the distance from the tip of your nose to the end of your outstretched arm, or the length of your foot.
6. Use a ruler or tape measure to measure these distances on your own body.
7. As a class, discuss whether the measurements that you made were exact measurements or approximations.

on Resources

eWorkbook Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)
Digital document SkillSHEET Reading scales (doc-6506)
Interactivities Individual pathway interactivity: Reading scales and measuring length (int-4356)
Scales and measuring length (int-4012)

Exercise 10.3 Reading scales and measuring length

learnON


Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 4, 8, 9, 12, 15, 18, 21	2, 5, 10, 13, 16, 19, 22	3, 6, 7, 11, 14, 17, 20


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


1. WE3a State the reading indicated by the arrow.


a.



b.



c.


2. State the reading indicated by the arrow, in decimal form.

a. WE3b



b.


c.



d.


3. State the reading indicated by the arrow, in decimal form.


4. State the values shown on this scale.



5. State the values shown on this scale.



6. State the values shown in the following jugs.

a.




b.



7. State the value shown on this scale.



8. State the values shown on this scale.




9. MC Choose the correct reading for the following scale.



A. 2.2 B. 2.4 C. 2.6 D. 2.8 E. 3.3

10. MC Choose the correct reading for the following scale.




A. $\frac{4}{5}$ B. 4 C. $\frac{2}{5}$ D. $\frac{2}{10}$ E. $\frac{1}{2}$

Understanding

For questions 11 to 17, use the given length to estimate the other length mentioned.

11. MC Approximate the distance from the centre of Earth to the centre of the Sun, using the scale bar provided.




A. 10 million km B. 50 million km C. 100 million km
D. 150 million km E. 200 million km

12. MC If the train pictured has four carriages, identify the length of the train.

A. 15 m
B. 30 m
C. 45 m
D. 60 m
E. 150 m



13. MC If the height of the rhino in the photo is 1.8 m, choose the approximate height of the giraffe.



A. 1.8 m
B. 4.9 m
C. 3.6 m
D. 18 m
E. 7.0 m

14. State the approximate height of the window (to the inside centre of the frame) if the bucket is 30 cm tall.




15. MC On the following map, select the approximate straight-line distance from Geelong to Canberra.



A. 150 km **B.** 320 km **C.** 540 km **D.** 700 km **E.** 1000 km

16. MC If 2 floors are 10 m tall, estimate the height of the building.



A. 136 m **B.** 100 m **C.** 184 m **D.** 350 m **E.** 388 m

17. MC If the orange ute is 180 cm tall, estimate the height (x) of the pole next to the building.



A. 18 m **B.** 12 m **C.** 24 m **D.** 15 m **E.** 8 m

Reasoning

18. List three examples of situations in which you would use each of the following measuring tools in everyday life.

a. A 30 cm ruler that includes millimetre markings
b. A 100 cm ruler that has only centimetre markings
c. A 2 m dressmaker's tape that includes centimetre markings
d. A 100 m measuring tape that has metre and centimetre markings

19. Use the information provided in the following photograph to estimate the height of the lamppost. Explain how you estimated this height.



20. Explain how you could use a normal ruler to determine the thickness of a page in a textbook. Estimate the thickness of a page in your Maths textbook and Science textbook.

Problem solving

21. Your friend is working on the top floor of a very tall office building. She walks up 726 steps from the ground floor to her office. Each step is 23 cm high. Calculate how high she climbs (in km), to 1 decimal place.

22. A gift box has dimensions 30 cm by 22 cm by 15 cm. If a ribbon is wrapped around this box as shown using 25 cm for a bow, determine the total length of ribbon needed.



10.4 Perimeter


LEARNING INTENTION

At the end of this subtopic you should be able to:
- calculate the perimeter of a given shape
- calculate the perimeter of rectangles and squares.

10.4.1 Calculating the perimeter

eles-4552

- A **perimeter** is the distance around the outside (border) of a shape.
- To calculate the perimeter of the shape, convert all lengths to the same unit and then add all the lengths.




Perimeter = 4 + 5 + 3 + 2 + 10 + 10
= 34 cm


WORKED EXAMPLE 5 Calculating the perimeter of shapes

Calculate the perimeter of each shape.


a.



b.



c.



Note: **The dots are 1 unit apart.**

THINK

a. 1. Count the number of unit intervals around the outside of the shape (16).

2. Write the answer.

b. 1. Check that the measurements are in the same unit. All are in centimetres.

2. Add the measurements to determine the perimeter.

3. Write the answer with the correct unit.


c. 1. Notice the measurements are not all the same. Convert to the smaller unit (6 cm = 60 mm).

2. Add the measurements that now have the same unit (mm) to determine the perimeter.

3. Write the answer with the correct unit.

WRITE

a.



The perimeter is 16 units.

b.

$$\begin{array}{r} 12 \\ 13 \\ +\,10 \\ \hline 35 \end{array}$$

The perimeter is 35 cm.

c. 6 cm = 60 mm

$$\begin{array}{r} 60 \\ 30 \\ +\,45 \\ \hline 135 \end{array}$$

The perimeter is 135mm.

WORKED EXAMPLE 6 Calculating perimeters of squares and rectangles

Calculate the perimeter of:

a. a rectangle that is 49.3 cm long and 22.0 cm wide


b. a square whose side length is 28 cm.

THINK

a. 1. Draw a diagram and write its measurements.

WRITE

a.



2. Check that the measurements are in the same unit. All are in centimetres. The perimeter is the distance around the rectangle, so add all the distances together.


$P = 49.3 + 22.0 + 49.3 + 22.0$
$= 142.6$

3. Write the answer with the correct unit.

The perimeter is 142.6 cm.

b. 1. Draw a diagram and write its measurements.

b.



2. Check that the measurements are in the same unit. The perimeter is the distance around the square, so add all the distances together.

$P = 28 + 28 + 28 + 28$
$= 112$

3. Write the answer with the correct unit.

The perimeter is 112 cm.

DISCUSSION

What information does the perimeter give you about a shape? Is it enough to draw the shape?

eles-4553

10.4.2 Calculating the perimeter of a rectangle and a square


- The perimeters of rectangles and squares can be found using the following formulas.

Perimeter of a rectangle

For a rectangle, the perimeter P is:

$$P = 2(l + w)$$

where l is its length and w is its width.




Perimeter of a square

For a square, the perimeter P is:

$$P = 4l$$

where l is its side length.



COLLABORATIVE TASK: Same perimeter, different shape

Equipment: a ball of string, A3 paper, marker pens, glue or sticky tape, ruler

1. Cut a piece of string into four equal lengths.
2. Measure and record the lengths of your pieces of string.
3. Make an enclosed shape with one of your pieces of string and stick it onto an A3 sheet of paper.
4. Write a caption about the perimeter of the shape. For example, you might write, 'It is 25 cm around this shape'.
5. Repeat steps 3 and 4 with your other pieces of string. Each time, make a different shape and write a different caption.
6. As a class, discuss the answer to the following question: What information does the perimeter give you about a shape?

Resources

eWorkbook	Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)
Digital document	SkillSHEET Perimeter (doc-6511)
Video eLesson	Perimeter (eles-1874)
Interactivities	Individual pathway interactivity: Perimeter (int-4357) Perimeter (int-4013) Perimeter of composite shapes (int-4014)

Exercise 10.4 Perimeter

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 4, 7, 10, 13, 16, 19, 22	3, 5, 8, 11, 14, 17, 20, 23	6, 9, 12, 15, 18, 21, 24

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE5a Calculate the perimeter of each shape. The dots are 1 unit apart.


a.




b.




c.



d.



e.




2. WE5b Calculate the perimeter of each of the following.

a.




b.




3. Calculate the perimeter of each of the following.


a.




b.




4. Calculate the perimeter of the shape shown.



5. Calculate the perimeter of the shape shown.




6. Calculate the perimeter of the shape shown.




7. WE5c Calculate the perimeter of each shape, giving answers in the smaller unit in each case.

a.




b.




8. Calculate the perimeter of each shape, giving answers in the smaller unit in each case.

a.




b.




9. Calculate the perimeter of each shape, giving answers in the smaller unit in each case.

a.




b.



10. MC Identify the perimeter of the shape shown.

A. 9 units
B. 18 units
C. 16 units
D. 14 units
E. 12 units

Note: The dots are 1 unit apart.



11. WE6

a. Calculate the perimeter of a rectangle of length 45 cm and width 33 cm.
b. Calculate the perimeter of a rectangle of length 2.8 m and width 52.1 cm.
c. Calculate the perimeter of a square of side length 3.7 cm.

12. a. Calculate the perimeter of a rectangle of length $4\frac{1}{4}$ m and width $2\frac{1}{5}$ m.

b. Calculate the perimeter of a square of side length $8\frac{1}{5}$ mm.

Understanding

13. Calculate the length of party lights needed to decorate the perimeter of a rectangular tent with dimensions 15.5 m by 8.75 m.


14. Allowing an extra 30 cm for waste, calculate the length of picture frame required to frame the artwork shown in the photo.



15. Zedken wishes to install three strands of barbed wire at the top of the fences around a rectangular work site. The length of the site is 34.5 m, and its width is 19.8 m. Calculate the length of wire needed.

16. A new game, Bop-ball, is played on a triangular field, where each side of the triangle measures 46.6 m. A greenkeeper is marking the field's perimeter using a chalk-dispensing trundle wheel. Determine how far the greenkeeper will walk to mark the field.

17. Phang's property boundary dimensions are shown in the diagram.



- **a.** Calculate how many metres of fencing are needed to fence all but the front boundary.
- **b.** If the fencing costs $19 per metre, calculate the total cost.

18. Lucille has received a quote of $37 per metre for new fencing for a tennis court. The tennis court is 23.77 m long and 10.97 m wide. There should be a 3.6 m space between each side of the court and the fence, and a 6.4 m gap between each end of the court and the fence.


- **a.** Draw a diagram showing all given measurements.
- **b.** Determine how many metres of fencing are needed.
- **c.** Based on the quote, calculate the total cost of the fencing.


Reasoning

19. Suggest a type of work where people need to calculate perimeters on a daily basis.

20. A piece of paper is 22 cm long, including a 2.2 cm sticky strip at each end. Five strips of paper are stuck together so that the sticky parts overlap exactly to make a loop of paper. Determine the circumference of (distance around) the loop.

21. Marc and Cathy are seeking quotes for the cost of building a fence on three sides of their property. They want to calculate approximate costs for each item to decide whether the quotes supplied sound reasonable.






The new fence requires three rails, a kickboard, posts and palings.

- **a.** Calculate the length of timber needed for the kickboard.
- **b.** Calculate the cost of the kickboard if the timber required for this costs $1.90 per metre.
- **c.** If the timber for the rails costs $2.25 per metre, determine the total cost of the timber for the railings.

d. Determine how many posts will be needed for the new fence if each post is to be 5 metres apart and there needs to be a post at the end of each straight section of fence.

e. Calculate the cost of the posts if the price of each post is $13.65.

Palings are 9 cm wide and are nailed so they overlap each other by 15 mm on each side.



f. i. Calculate the approximate number of palings needed for the fence.

ii. Palings cost $1.05 each. Determine how much money should be allowed for the total cost of the palings.

g. Write an itemised list of all the costs involved. Include an amount to cover labour charges and miscellaneous items like the cost of nails. This amount is around $1000 (two people for two days at approximately $30.00 per hour for an eight-hour day). Estimate the cost of the new fence. This will provide Marc and Cathy with information to use when comparing builders' quotes.


Problem solving

22. Kelly has a piece of string 32 cm long. He uses it to form rectangular shapes that each have a length and a width that are a whole number of centimetres.


a. Identify how many different rectangular shapes he can form.

b. Predict what the sides of the rectangle will be to give the largest possible area. Check by drawing different rectangles to see if your prediction is correct.

23. Write an equation for the perimeter of the diagram shown in terms of a and b.



24. The rectangle shown is made up of three identical, smaller rectangles that fit inside (as shown). If its length measures 9 cm, work out its width without using a ruler.



10.5 Area

LEARNING INTENTION

At the end of this subtopic you should be able to:

- calculate, or estimate, the area of a given shape
- calculate the area of rectangles, squares, triangles and parallelograms using formulas.

10.5.1 Metric units of area

eles-4554

- The **area** of a shape is the amount of flat surface enclosed by the shape.
- Area is measured in square units such as square centimetres, square metres and square kilometres.
- Commonly used metric units of area, with their abbreviations and examples, are shown in the following figures.

1. Square kilometres (km^2)




The area of a country or a large city like Sydney is given in square kilometres.

2. Square metres (m^2)



Square metres are used to measure the area of an object such as a classroom floor, whiteboard or a window.

3. Square centimetres (cm^2)




Small areas, such as the area of a sheet of A4 paper or a book cover, are measured in square centimetres.

4. Square millimetres (mm^2)




Very small areas, such as the area of a button or a postage stamp, are measured in square millimetres.


- The area of a farm or a large city park is measured in hectares (ha). $1\text{ ha} = 10\,000\text{ m}^2$.
- 1 square metre is the area enclosed by a square with sides that are 1 m long. The same is true for any other unit.
- If a shape is drawn on 1 cm grid paper, its area can be found by counting the number of squares that the shape covers.



WORKED EXAMPLE 7 Determining area by counting squares

The following figures are drawn on centimetre grid paper. Determine the area of each one.

a. 

b. 


THINK

a. Count the squares. Remember to include the correct unit (cm^2) in the answer.


b. Some of the squares are cut in half by the diagonal line. It takes two of these to make up one square centimetre. Count the squares. Remember to include the correct unit (cm^2) in the answer.

WRITE

a. 8 cm^2



b. 8 cm^2




Estimating shaded areas

If a square of the grid paper is not completely covered by the shape, use the following rule to obtain an estimate of the area.

- If more than half the square is covered, count it as a full square.
- If less than half the square is covered, do not count it at all.

WORKED EXAMPLE 8 Estimating the shaded area


Estimate the shaded area of the following diagram drawn on centimetre grid paper.



THINK

1. Tick the squares that are more than half covered and count them.
2. State the answer, with the correct unit.

WRITE



6 cm^2

10.5.2 Calculating the area of a rectangle


eles-4555

- The areas of rectangles and squares can also be calculated by using the following formulas.

Area of a rectangle

For a rectangle, the area A is:

$$A = l \times w$$
$$= lw$$




where l is the length and w is the width of the rectangle.

Area of a square

For a square, the area A is:


$$A = l \times l$$
$$= l^2$$



where l is the length of the square's side.

Digital technology


A quick way to calculate the area of a square on a calculator is to use the 'square' button. The button has the symbol x^2 and will square the number that you type in.




WORKED EXAMPLE 9 Calculating areas of different shapes

Calculate the areas of the following shapes.


a.



b.



c.




THINK

a. 1. Write the formula for the area of a rectangle.

WRITE

a. $A = lw$



2. Substitute the value 4 for l and 3 for w and calculate the area.


$A = 4 \times 3$
$= 12 \text{ cm}^2$

3. State the answer in the correct unit (cm^2).

The area is $12\ cm^2$.

b. 1. Divide the shape into two rectangles.

b.



2. Calculate the area of each rectangle separately by substituting the correct values of l and w into the formula $A = lw$.


$$\text{Area of rectangle 1} = l \times w$$
$$= 4 \times 2$$
$$= 8\ cm^2$$
$$\text{Area of rectangle 2} = l \times w$$
$$= 1 \times 2$$
$$= 2\ cm^2$$

3. Add the two areas. Remember to answer in the correct unit (cm^2).

$$\text{Area of shape} = \text{Area of rectangle 1} + \text{Area of rectangle 2}$$
$$= 8\ cm^2 + 2\ cm^2$$
$$= 10\ cm^2$$

c. 1. Divide the shape into three rectangles.

c.



2. Calculate the area of each rectangle separately by substituting the correct values of l and w into the formula $A = lw$.

$$\text{Area of rectangle 1} = l \times w$$
$$= 10.2 \times 9.7$$
$$= 98.94\ mm^2$$
$$\text{Area of rectangle 2} = l \times w$$
$$= (21.7 - 9.7 - 7.3) \times (18.5 - 15.9)$$
$$= 4.7 \times 2.6$$
$$= 12.22\ mm^2$$
$$\text{Area of rectangle 3} = l \times w$$
$$= 18.5 \times 7.3$$
$$= 135.05\ mm^2$$

3. Add the three areas. Remember to answer in the correct unit (mm^2).

$$\text{Area of shape} = \text{Area 1} + \text{Area 2} + \text{Area 3}$$
$$= 98.94\ mm^2 + 12.22\ mm^2 + 135.05\ mm^2$$
$$= 246.21\ mm^2$$

COLLABORATIVE TASK: Rectangles with the same areas and perimeters

Work in pairs to answer the following questions.


Compare the perimeters of two different rectangles, each with an area of 60 cm^2. Which rectangles have the smallest perimeters and which have the largest perimeters?


Compare the areas of different rectangles, each with a perimeter of 24 cm. Which rectangles have the smallest areas and which have the largest areas?


10.5.3 Calculating the area of a triangle

eles-4556

- Triangles can be formed by cutting rectangles in half.








- The area of a triangle is therefore equal to half the area of a rectangle of the same base length and height.

Area of a triangle


To calculate the area A of a triangle:

$$A = \frac{1}{2}b \times h$$
$$= \frac{1}{2}bh$$




where b is the base and h the perpendicular height.


- To measure the perpendicular height of a triangle, the line must form a right angle with the base of the triangle. Sometimes this line will have to be drown outside the triangle, as shown in the following diagram.



WORKED EXAMPLE 10 Calculating the area of a right-angled triangle

Calculate the area of the following shape.




THINK	WRITE
Method 1: Using the formula for the area of a triangle	
1. Write the formula for the area of a triangle.	$A = \frac{1}{2}bh$
2. Identify the values of b and h.	$b = 8\text{ cm}, h = 6\text{ cm}$
3. Substitute the values of b and h into the formula.	$A = \frac{1}{2} \times 8 \times 6$
4. Evaluate. (Since one of the values is even, halve it first to make calculations easier.) Remember to include the correct unit (cm^2).	$= 4 \times 6$ $= 24\text{ cm}^2$
Method 2: By cutting the rectangle in half	
1. Draw an imaginary rectangle that contains the triangle. The rectangle should have the same base length and height as the triangle. Notice that the triangle forms half of the rectangle.	
2. Use the formula $A = lw$ to calculate the area of this rectangle.	$A = lw$ $= 8\text{ cm} \times 6\text{ cm}$ $= 48\text{ cm}^2$
3. Halve the area of the rectangle to get the area of the triangle. Remember to answer in the correct unit (cm^2).	Area of triangle $= \frac{1}{2}$ of area of rectangle Area of triangle $= \frac{1}{2} \times 48$ $= 24\text{ cm}^2$


WORKED EXAMPLE 11 Calculating the area of a triangle

Calculate the area of each of these triangles.

a.



b.



THINK	WRITE
a. 1. Write the formula for the area of a triangle.	**a.** $A = \frac{1}{2}bh$
2. Identify the values of b and h.	$b = 10, h = 4.5$
3. Substitute the values of b and h into the formula.	$A = \frac{1}{2} \times 10 \times 4.5$
4. Evaluate. (Since one of the values is even, halve it first to make calculations easier.) Remember to include the correct unit (cm^2).	$= 5 \times 4.5$ $= 22.5\text{ cm}^2$

b. **1.** Write the formula for the area of a triangle.

b. $A = \frac{1}{2}bh$

2. Identify the values of b and h.

$b = 15, h = 7$

3. Substitute the values of b and h into the formula.

$A = \frac{1}{2} \times 15 \times 7$

4. Evaluate. (Since neither value is even, multiply 15 and 7 first, and then divide by 2.) Remember to include the correct unit (cm^2).


$= \frac{1}{2} \times 105$

$= 52.5\ cm^2$


10.5.4 Area of a parallelogram

eles-4557

- A **parallelogram** is a quadrilateral having each pair of opposite sides parallel.



- To calculate the area of the parallelogram, first draw a diagonal from B to D to form two triangles, ABD and BDC. Label the base b and the perpendicular height h.



- The area of triangle BCD $= \frac{1}{2}b \times h$ and the area of triangle ABD $= \frac{1}{2}b \times h$.
  So, the area of the parallelogram:

$$\begin{aligned} \text{ABCD} &= \frac{1}{2}b \times h + \frac{1}{2}b \times h \\ &= b \times h \end{aligned}$$


where b is the base and h is the perpendicular height.

Area of a parallelogram

The area of a parallelogram is:


$$\boldsymbol{A = bh}$$

where b is the base and h is the perpendicular height.



- For example, the area of the parallelogram shown is:

$$\begin{aligned} \text{ABCD} &= b \times h \\ &= 6 \times 4 \\ &= 24 \text{ cm}^2 \end{aligned}$$



on Resources

eWorkbook	Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)
Digital documents	SkillSHEET Area units (doc-6512) SkillSHEET Area of figures drawn on one-centimetre grid paper (doc-6513) SkillSHEET Area of rectangles (doc-6514) SkillSHEET Area of triangles (doc-6515)
Interactivities	Individual pathway interactivity: Area (int-4358) Metric units of area 1 (int-4015) Metric units of area 2 (int-4016) Area of a rectangle (int-4017) Area of a triangle (int-4018) Area of a parallelogram (int-4019)

Exercise 10.5 Area

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 5, 8, 9, 13, 14, 18, 21, 24, 26, 29, 31	2, 6, 10, 11, 15, 17, 19, 22, 25, 27, 30, 32, 34, 35	3, 7, 12, 16, 20, 23, 28, 33, 36, 37

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


1. Identify which unit would be most suitable to measure the following areas. Choose from mm^2, cm^2, m^2, ha or km^2.


a. A computer screen
b. The Melbourne Cricket Ground
c. A shirt button
d. The Brisbane metropolitan area


2. Identify which unit would be most suitable to measure the following areas. Choose from mm^2, cm^2, m^2, ha or km^2.


a. A house block
b. The state of Queensland
c. A basketball court
d. A dairy farm


3. WE7a The following figures are drawn on centimetre grid paper. Determine the area of each one.

a. 


b. 


c. 


d. 


e. 


4. Estimate the areas of the following figures, which are drawn on centimetre grid paper.

a. 

b. 


c. 

d. 

e. 


5. MC Select from the following an estimate for the area of the shape drawn on centimetre grid paper.

A. 18 cm^2
B. 21 cm^2
C. 16 cm^2
D. 23 cm^2
E. 28 cm^2




6. MC Select from the following an estimate for the area of the shape drawn on centimetre grid paper.

A. 16 cm^2
B. 20 cm^2
C. 25 cm^2
D. 28 cm^2
E. 30 cm^2



7. MC Select from the following an estimate for the area of the shape drawn on centimetre grid paper.

A. 15 cm^2
B. 17 cm^2
C. 19 cm^2
D. 21 cm^2
E. 25 cm^2




8. WE9a Determine the areas of the following rectangles. (*Hint:* Use the formula $A = lw$.)


a.



b.




c.




WE9b, c For questions **9** to **12**, calculate the areas of the following shapes. (*Hint:* Divide the shapes into rectangles and squares before using the formula $A = lw$)


9. a.




b.




10. a.




b.




11. a.




b.



12. a.




b.




13. WE10 Calculate the areas of the following triangles.


a.




b.



c.




d.




14. MC Identify the height of the triangle shown.

A. 60 mm **B.** 30 mm **C.** 27 mm
D. 53 mm **E.** 49 mm




15. MC Identify the height of the triangle shown.

A. 2.6 cm **B.** 4.0 cm **C.** 3.0 cm
D. 4.2 cm **E.** 3.8 cm




16. MC Identify the base length of the triangle shown.

A. 39 cm **B.** 58 cm **C.** 29 cm
D. 25 cm **E.** 43 cm




17. WE11 Calculate the area of each of these triangles.


a.




b.



c.




d.




18. Calculate the area of each of these triangles.


a.




b.




c.



d.




19. Calculate the area of the following parallelogram.



Understanding

20. MC Select the closest estimate of the area of this butterfly if a centimetre grid is placed over it as shown.



A. 10 cm^2
B. 18 cm^2
C. 27 cm^2
D. 38 cm^2
E. 51 cm^2

21. One of the largest open-air shopping centres is the Ala Moana centre in Honolulu, Hawaii, USA with more than 200 shops covering an area of 20 hectares. Convert this area to square metres.

22. The Taupo volcanic eruption that occurred in New Zealand nearly 2000 years ago is estimated to have flattened an area of 16 000 km^2.



a. Convert this area to square metres.
b. Convert this area to hectares.

23. Calculate how many square metres of carpet are needed to cover a rectangular room of length 5 m and width 3.5 m.

24. Determine the area of material needed to make a rectangular rug that is 4.2 m long and 230 cm wide. (Give your answer in square metres.) (*Hint:* Convert the width measurement into metres first.)

25. Toby is tiling his bathroom with ceramic tiles that cost $35.20 per box.

a. Calculate how many square metres of tiles he will need if the rectangular room has a width of 2.5 m and a length of 3 m.
b. Calculate how many boxes of tiles he should order if each box contains enough tiles to cover 0.5 m^2.
c. Determine the cost of the tiles.

Reasoning

26. Alana, who works for Fast Glass Replacements, has been asked for a quote to replace three windows. Each window is 1.8 m long and 0.8 m wide. Determine the price Alana should quote if the glass costs $27 per square metre. (Include a delivery cost of $25 in the quote.)

27. A floor tiler charged $640.00 to tile a rectangular room. Her next job is to tile the floor of a rectangular room twice as long and twice as wide. Determine how much she should charge for the larger room. (The answer is not $1280.00.) Justify your answer.

28. Glen wants to pave his back courtyard. His courtyard is 12 m × 12 m. He has a choice of 10 cm × 25 cm clay pavers that cost $2.30 each, or concrete pavers that are 70 cm × 70 cm and cost $42 each. Compare the costs of each to determine the cheaper option.


Problem solving

29. For the sailboat shown, calculate the approximate area of the triangular mainsail when the sail is flat. Use the dimensions shown.




30. Jane is a landscape gardener who is laying a new lawn. The rectangular lawn is 13 m long and 8 m wide. Calculate how many square metres of turf Jane should order.
Calculate the total cost of the turf if it costs $12.50 per square metre.


31. Calculate the total area of the cattle station shown in the diagram, which has 3 large paddocks. (Give your answer in square kilometres.)




32. Determine the area of cloth required to make the kite shown, given that the length BD is 80 cm and the length AC is 1.5 m.




33. Calculate the total floor area of a concrete slab for a house as shown in the following diagram.



34. A church spire has six identical triangular faces that have the dimensions shown. Determine the area of copper roofing required to cover all six faces of the spire.



35. Calculate the total wing area of the following delta-winged jet aircraft.



36. A rectangle has an area of 36 cm^2 and a perimeter of 26 cm. Each side of the rectangle is a whole number of centimetres. Determine the length and width of this rectangle. Show your working.

37. Geoff wants to establish a rectangular vegetable garden bed on his farm. His work shed is 20 m long, and it will act as one of the boundaries for the garden bed. (*Note:* The garden will not necessarily be this long.) He has 24 metres of fencing, which he plans to use to fence the other three sides. Describe how Geoff could use this fencing to enclose the largest possible area.

10.6 Area of composite shapes

LEARNING INTENTION

At the end of this subtopic you should be able to:


- separate composite shapes into simple shapes
- calculate the areas of composite shapes by adding or subtracting areas of simple shapes.

10.6.1 Calculating the area of composite shapes

eles-4558


- **Composite shapes** can be separated into parts, each of which is a simple shape (such as, for example, a rectangle or a triangle).
- The area of a composite shape can be found by adding the areas of each of the separate parts.
- For example, the area of the following pentagon can be found by adding the areas of the triangle and rectangle.






WORKED EXAMPLE 12 Calculating the area of a composite shape using addition

Calculate the area of the following shape.




THINK	WRITE
1. Divide the shape into a rectangle and a triangle.	
2. Calculate the area of shape 1 using the formula $A = lw$. The value of $l = 7$ cm and $w = 4$ cm.	Area 1 $= lw$ $\quad l = 7$ cm, $w = 4$ cm
3. Substitute the values of l and w in the formula to calculate the area of the rectangle.	$= 7 \times 4$ $= 28\ \text{cm}^2$
4. Calculate the area of shape 2 using the formula $A = \frac{1}{2}bh$. The value of $b = 5$ cm and $h = 4$ cm.	Area 2 $= \frac{1}{2}bh$ $\quad b = 5$ cm, $h = 4$ cm
5. Substitute the values of b and h in the formula to calculate the area of the triangle.	$= \frac{1}{2} \times 5 \times 4$ $= 10\ \text{cm}^2$
6. Add the two areas to get the total area.	Total area $= A_1 + A_2$ $= 28 + 10$ $= 38\ \text{cm}^2$
7. Write the answer with the correct units.	The area of the composite shape is $38\ \text{cm}^2$.

- In many situations the area of a given shape can be found by subtracting individual areas from each other.

WORKED EXAMPLE 13 Calculating the area of a composite shape using subtraction

Calculate the shaded area in the following figure.



THINK	WRITE
1. The figure shows a large square with the blue shaded area and a small square.	Area of a square $= l^2$
2. Calculate the area of the large square.	Area of the large square: $A = 5^2$ $= 5 \times 5$ $= 25\ \text{m}^2$
3. Calculate the area of the small square.	Area of the small square: $A = 2^2$ $= 2 \times 2$ $= 4\ \text{m}^2$
4. To calculate the area of the shaded region, subtract the area of the small square from that of the large one.	Shaded area $= 25 - 4$ $= 21\ \text{m}^2$
5. Write the answer with the correct unit.	The shaded area is $21\ \text{m}^2$.

Resources

- **eWorkbook** Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)
- **Video eLesson** Composite area (eles-1886)
- **Interactivities** Individual pathway interactivity: Area of composite shapes, using addition and subtraction (int-4359)
  Area of composite shapes (int-4020)

Exercise 10.6 Area of composite shapes

learnON

Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 5, 7, 9, 11, 14	2, 6, 10, 12, 15	3, 4, 8, 13, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE12 Calculate the area of the following composite shapes.


a.



b.




c.




2. Calculate the area of the following composite shapes.


a.



b.




c.




3. **WE13** Calculate the shaded area of the following shapes.


a.




b.



4. Calculate the area of the following garage wall.




5. Determine the area of bricks needed to cover the following courtyard.




Understanding

6. Determine the area of the hotel lobby in the following diagram.




7. **a.** Calculate the area of carpet needed for the floor plan shown.

b. Determine the cost of carpeting the room if the carpet costs $25 per square metre.




8. Michael is paving a rectangular yard that is 15.5 m long and 8.7 m wide. A square fishpond with side lengths of 3.4 m is in the centre of the yard. Calculate the cost of paving Michael's yard if the paving material costs $17.50 per square metre.

9. Members of the Lee family want to pave the area around their new swimming pool. The pool is set into the corner of the yard as shown in the diagram. Calculate the area of paving (in square metres) required to cover the yard around the pool (shaded in the diagram).




10. In order to construct an advertising sign, the following letters are cut from plastic sheets. Calculate the total area of plastic required to make all 3 letters.



Reasoning


11. **a.** Calculate the area of the diagram. Show all your working.
b. Calculate the area of the figure using an alternative method. Show all your working.
c. Explain the differences between the two methods.



12. When determining the area of a composite shape, explain how you would decide whether to use addition or subtraction.


13. The stylised diagram of a set of traffic lights has been constructed using basic shapes, as shown.

a. State the shapes used to draw the diagram and their dimensions in cm.
b. Explain the steps required in calculating the black area surrounding the traffic lights shown.
c. If the area of one of the large semicircles is closest to 353 cm^2, and the area of one of the small coloured circles is closest to 177 cm^2, calculate the area of the black surface. State the answer in cm^2.
d. Explain why it is more appropriate to express the area in cm^2 rather than mm^2.




Problem solving

14. Ellen wants to frame her cross-stitch work. Her cross-stitch work is 90 cm long and 75 cm wide. The frame's border, shown in the diagram, measures 2.5 cm wide. One company charges $120 for the frame. Determine the cost of the frame per square centimetre. Round your answer to 2 decimal places.




15. A square of side length 1 metre is made up of smaller internal squares that are formed by joining the midpoints of the outer square as shown in the diagram. Determine how much of the square the shaded area represents.



16. The diagram of the letter M shown has been constructed using basic shapes.

a. Explain two methods of calculating the area of the letter using:
i. addition **ii.** subtraction.

b. Using your preferred method, calculate the area of the letter.



10.7 Volume of rectangular prisms

LEARNING INTENTION

At the end of this subtopic you should be able to:
- calculate the volume of a rectangular prism.

eles-4559


10.7.1 Volume

- The **volume** of a **3-dimensional object** is the amount of space it occupies.
- Volume is measured in cubic units such as mm^3, cm^3 and m^3.
- A cubic centimetre (cm^3) is the space occupied by a cube with sides of 1 cm.

A sugar cube has a volume of about 1 cm^3.




A cubic metre (m^3) is the space occupied by a cube with sides of 1 m.




WORKED EXAMPLE 14 Counting cubes in solid shapes

Calculate how many cubic centimetres are in each solid shape. (Each small cube represents 1 cm^3.)

a.



b.




THINK	WRITE
a. 1. Count the cubes. There are 10 cubes in each layer. There are three layers altogether.	**a.** Volume $= 10\,cm^3 \times 3$
2. Give the answer in cubic centimetres.	$= 30\,cm^3$
b. 1. Count the cubes. There are 12 cubes in the first layer. There are 6 cubes in the second layer. There are 3 cubes in the third layer.	**b.** Volume $= 12\,cm^3 + 6\,cm^3 + 3\,cm^3$
2. Give the answer in cubic centimetres.	$= 21\,cm^3$

COLLABORATIVE TASK: The blue cube

Work in pairs to answer the following questions.


1. The outside of a cube with 3 cm sides is painted blue. The cube is then cut into smaller cubes, each with sides 1 cm long. How many of the 1 cm cubes will have paint on:
   - **a.** 1 side only
   - **b.** 2 sides only
   - **c.** 3 sides only
   - **d.** no sides?
2. For a cube with 4 cm sides, made from 1 cm cube blocks and painted blue on the outside, determine the number of cubes painted on:
   - **a.** 1 side only
   - **b.** 2 sides only
   - **c.** 3 sides only
   - **d.** no sides.
3. Repeat question **2** for a cube with sides of 5 cm.
4. Is there a pattern that you can use to predict the numbers of cubes with paint on one, two, three or no sides if you know the number of cubes along the side of the large cube?



eles-4560

10.7.2 Calculating the volume of a rectangular prism

- A cube is a 6-sided 3-dimensional shape in which all sides are squares.
- A cuboid is a 6-sided 3-dimensional shape in which all sides are rectangles or squares.
- Cuboids are also known as rectangular **prisms**.




Volume of a rectangular prism

For a rectangular prism, the volume V is:


$$V = l \times w \times h$$
$$= lwh$$

where l is its length, w its width and h its height.



WORKED EXAMPLE 15 Calculating the volume of a rectangular prism


Use the formula $V = lwh$ to calculate the volume of the following rectangular prism.



THINK	WRITE
1. State the formula for the volume of a rectangular prism.	$V = lwh$
2. Identify the length ($l = 7$ cm), width ($w = 4$ cm), and height ($h = 2$ cm) of the prism and substitute the values into the formula.	$= 7\text{ cm} \times 4\text{ cm} \times 2\text{ cm}$
3. Calculate the volume, stating the answer in the appropriate units (cm^3).	$= 56\text{ cm}^3$


WORKED EXAMPLE 16 Calculating the volume of a composite rectangular prism

Use the information given in the diagram to calculate the volume of the composite rectangular prism.



THINK	WRITE
1. To calculate the volume, first write the formula for the volume of a rectangular prism.	$V = lwh$

2. Split the shape into 2 rectangular prisms and calculate the volume of each rectangular prism.



Volume of rectangular prism 1 $= 3 \times 2 \times 3$
$= 18\ \text{cm}^3$
Volume of rectangular prism 2 $= 2 \times 1 \times 3$
$= 6\ \text{cm}^3$

3. Add the volumes to determine the volume of the composite rectangular prism.

$V = 18\ \text{cm}^3 + 6\ \text{cm}^3$
$= 24\ \text{cm}^3$

on Resources

eWorkbook	Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)
Digital documents	SkillSHEET Volume units (doc-6516)
	SkillSHEET Volume of a solid constructed from cubic-centimetre blocks (doc-6517)
Interactivities	Individual pathway interactivity: Volume of rectangular prisms (int-8470)
	Volume (int-4021)
	Volume of a rectangular prism (int-4022)

Exercise 10.7 Volume of rectangular prisms

learnON

Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 2, 6, 9, 13, 16, 21, 24	3, 5, 7, 10, 11, 14, 17, 19, 22, 25	4, 8, 12, 15, 18, 20, 23, 26

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE14a Calculate how many cubic centimetres are in each solid shape. (Each small cube represents 1 cm^3.)


a.




b.




c.



d.



2. MC Select the volume of the prism shown.




A. 4 cm^3
B. 12 cm^3
C. 1 cm^3
D. 8 cm^3
E. 19 cm^3


Note: Each cube has a volume of 1 cm^3.

3. WE14b Calculate the volumes of the following solids. (Each small cube represents 1 cm^3)


a.




b.



c.




d.




4. Calculate the volumes of the following solids. (Each small cube represents 1 cm^3)


a.




b.



c.




d.



5. MC Select the volume of the prism shown.


A. 20 cm^3
B. 16 cm^3
C. 10 cm^3
D. 22 cm^3
E. 3 cm^3

Note: Each cube has a volume of 1 cm^3.




6. WE15 Use the formula $V = lwh$ to calculate the volumes of the following rectangular prisms.


a.



b.




c.




7. Determine the volume of each of the following. (Each cube has a volume of 1 cm^3.)


a.



b.




c.




8. Use the formula $V = lwh$ to calculate the volumes of the following rectangular prisms.


a.



b.




c.




9. MC Select the volume of the prism shown.

A. 10 cm^3
B. 20 cm^3
C. 30 cm^3
D. 40 cm^3
E. 80 cm^3

Note: Each cube has a volume of 1 cm^3.



10. MC Select the volume of the prism shown.




A. 16 cm^3
B. 48 cm^3
C. 32 cm^3
D. 40 cm^3
E. 160 cm^3


Note: Each cube has a volume of 1 cm^3.

11. WE16 Calculate the volumes of the following composite prisms.

a.




b.




12. Calculate the volumes of the following composite prisms.

a.



b.



Understanding

13. Calculate the volume of the shoe box shown. (Give your answer in cm^3.)



14. The inside dimensions of a refrigerator are shown. Calculate the volume available for food storage inside the refrigerator.



15. **a.** A rectangular prism has a length of 30 cm and a width of 15 cm. If its volume is 9000 cm^3, determine its height.

b. A rectangular prism has a length of 13 cm and a width of 17 cm. If its volume is 1989 cm^3, determine its height.

c. A rectangular prism has a length of 10 cm and a width of 15 cm. If its volume is 1800 cm^3, determine its height.

16. The lunch box shown is a rectangular prism.

a. Calculate the volume of the lunch box in cubic centimetres.

b. Change each measurement to millimetres and hence calculate the volume of the lunch box in cubic millimetres.





17. Determine the volume of concrete (in cubic metres) that would be needed to make the base for a garage that is 6.5 m wide and 3 m long. The concrete base is 0.25 m deep.

18. **a.** Calculate the volume (in cubic centimetres) of the matchbox shown.

b. Change each measurement to millimetres and hence determine the volume of the matchbox in cubic millimetres.

c. Matches are rectangular prisms of length 44 mm, width 2 mm and height 2 mm. Calculate the volume of a match (in cubic millimetres). (Ignore the red substance on the end of each match.)






d. If a matchbox contains 50 matches, determine how much space is left in a full box.

19. Calculate how many cubic metres of water would be needed to fill a diving pool that has a length of 16 m, a width of 12 m and a depth of 4 m.

20. Heather wishes to cover a rectangular lawn with topsoil to a depth of 0.1 m. If the lawn is 24 m long and 17 m wide, calculate the volume of soil (in cubic metres) she needs to order.

Reasoning




21. The fruitcake shown in the photo is to be divided equally among 100 people at a wedding reception. Determine the volume of cake (in cubic centimetres) each guest will receive.

22. A swimming pool is rectangular and its width is exactly half its length. Determine the volume of water needed to fill it if the swimming pool is 50 metres long and has a constant depth of 2 metres.

23. A new rectangular patio has been built on the end of your house. It measures 3.8 m by 1.9 m. You want to plant a garden that is 1.5 m wide around the patio on three sides. The garden beds are to be 0.5 metres deep. If you order 7.3 cubic metres, explain with a diagram whether enough soil has been ordered.

Problem solving



24. Calculate the volume of clay in a house brick that has a length of 23 cm, a width of 11 cm and a height of 9 cm.

25. The areas of the three sides of a rectangular box are shown in the diagram. Determine the volume of the box, showing all your working.

26. A big cargo box measures 12 m by 6 m by 5 m. Determine how many small boxes of 40 cm by 25 cm by 10 cm can fit in the cargo box.

10.8 Capacity

LEARNING INTENTION


At the end of this subtopic you should be able to:
- calculate the capacity of a container
- convert between units of volume and capacity.

10.8.1 Capacity


eles-4561


- The **capacity** of a container is the volume of liquid that it can hold.
- Capacity is commonly measured in millilitres (mL), litres (L), kilolitres (kL) and megalitres (ML).
- The following chart can be used to convert between megalitres, kilolitres, litres and millilitres.

Capacity conversion



- Capacity can be measured in the same units as volume (e.g. cm^3 or m^3).
- The metric volume unit 1 cm^3 has a capacity of 1 mL. The metric capacity unit 1 L is equivalent to 1000 cm^3.





WORKED EXAMPLE 17 Converting between different units of capacity

Complete the following unit conversions.

a. **6 L = _____mL** **b.** **700 mL = _____L** **c.** **0.45 L = _____cm^3**

THINK

a. Check the conversion chart. To convert litres to millilitres, multiply by 1000. Since 6 is a whole number, do this by adding three zeros to the end of the number.

b. Check the conversion chart. To convert millilitres to litres, divide by 1000. To do this, move the decimal point 3 places to the left.

c. Check the conversion chart. To convert litres to millilitres, multiply by 1000. To do this, move the decimal point 3 places to the right. Note that 1 mL = 1 cm^3.

WRITE

a. $6\text{ L} = 6 \times 1000\text{ mL}$
$= 6000\text{ mL}$

b. $700\text{ mL} = 700 \div 1000\text{ L}$
$= 0.7\text{ L}$

c. $0.45\text{ L} = 0.45 \times 1000\text{ mL}$
$= 450\text{ mL}$
$= 450\text{ cm}^3$

DISCUSSION

How would you explain the difference between volume and capacity?

on Resources

eWorkbook Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)

Interactivities Individual pathway interactivity: Capacity (int-4361)
Capacity (int-4024)

Exercise 10.8 Capacity

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 13, 15, 17, 20	2, 5, 8, 11, 14, 18, 21, 22	3, 6, 9, 12, 16, 19, 23, 24, 25

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE17a, b Complete the following unit conversions.
   a. 2 L = _____ mL
   b. 3000 mL = _____ L
   c. 7000 mL = _____ L
   d. 5500 mL = _____ L

2. Complete the following unit conversions.
   a. $2\frac{1}{2}$ L = _____ mL
   b. 32 000 mL = _____ L
   c. 0.035 L = _____ mL
   d. 420 L = _____ mL

3. Complete the following unit conversions.
   a. $1\frac{87}{100}$ L = _____ mL
   b. 22 500 mL = _____ L
   c. $\frac{1}{10}$ L = _____ mL
   d. 25 L = _____ kL

4. WE17c Complete the following unit conversions.
   a. 750 cm^3 = _____ mL
   b. 2500 m^3 = _____ kL
   c. 2.45 L = _____ m^3
   d. 78 000 cm^3 = _____ L

5. Complete the following unit conversions.
   a. 40 000 cm^3 = _____ mL = _____ L
   b. 6 L = _____ mL = _____ cm^3
   c. 5200 L = _____ kL = _____ m^3

6. MC A capacity of 25 L is equal to:
   A. 0.025 mL B. 250 mL C. 0.25 mL D. 25 000 mL E. 2500 mL

7. MC A capacity of 35 400 mL is equal to:
   A. 35 400 000 L B. 0.354 L C. 3.5400 L D. 35.4 L E. 35 L

8. Arrange in order from smallest to largest:
   a. $2\frac{1}{2}$ L, 25 000 mL, $\frac{1}{4}$ L, 2.45 L
   b. 760 mL, 0.765 L, 7.65 mL, 7.60 L
   c. 110 mL, 0.1 L, 0.011 L, 1.1 L

Understanding

9. A water bottle has a capacity of 2 litres. Calculate how many 125 mL bottlefuls are required to fill it.

10. A bottle contains 250 mL of orange juice concentrate. Calculate how much water should be added to make up 2 L of juice from the concentrate.

11. A scientist dilutes (waters down) an acid solution by adding 120 mL of acid to 1.5 L of water. Calculate how much of the diluted solution this will make.

12. Most sports drinks are sold in 500 mL bottles. Calculate how many litres of sports drink are in one dozen (12) bottles.

13. A medicine bottle contains 125 mL of cough syrup. Calculate how many 2.5 mL doses could be administered from this bottle, assuming that none is spilt.

14. Anthea runs a market stall selling detergent. Calculate how many 200 mL bottles of detergent she could fill from a 45 L bulk container.

15. A milk bar sells 55 small bottles of lemon drinks in one week. If each bottle contains 180 mL, calculate how many litres are sold each week.

16. Petrov is working as a school laboratory technician. If there are 12 groups of students and each group requires 400 mL of salt solution for an experiment, calculate how many litres of solution should be prepared.

Reasoning

17. a. Claire has made her favourite green cordial with 0.25 L of water and 30 mL of cordial. Determine whether a glass with a capacity of 250 mL will hold this volume.

b. Sharmila has made fresh juice with 0.3 L of apple juice and 40 mL of carrot juice. Determine whether a glass with a capacity of 350 mL will hold this volume.

18. A 185 mL container of hair conditioner is sold at the special price of $3.70. A 0.5 L container of the same conditioner costs $11.00. Compare them to identify the better buy. (*Hint:* Calculate the cost of 1 mL of hair conditioner in each case.)

19. Laurie connected a water tank to his 5 m × 3 m roof in order to collect rain water. In four hours, 2 cm of rain fell. The water tank holds 280 litres. Determine whether the tank overflowed. *Hint:* $1000\text{ L} = 1\text{ m}^3$.




Problem solving

20. Determine the number of millilitres of milk the container in the picture holds.



21. Water is to be poured into this fish tank. How many litres of water are needed to fill the tank to a depth of 28 cm?



22. Using the measurements shown in the photo of the sinks, estimate how many litres of water each sink will hold if filled to the top. Both sinks have the same dimensions. (*Hint:* First convert the measurements to centimetres.)



23. One litre of paint covers an area of 20 square metres. Calculate how many millilitres of paint are required to cover an area of 6 square metres. Show your working.

24. A tap drips water at a rate of one drop every three seconds. If it takes 750 drops of water to fill a 100 mL container, determine how many litres of water are lost in one year (365 days).

25. To achieve a world record, a 16.4 kL strawberry milkshake was made in the UK in 1996. To understand how large this is, consider the size of a rectangular prism that would have this capacity. Suggest three possible sets of measurements for this container.

10.9 Drawing solids


LEARNING INTENTION

At the end of this subtopic you should be able to:
- draw the cross-section of a given prism
- draw the views, or elevations, of a given solid
- construct a solid given its views or elevations.

eles-4562


10.9.1 Prisms


- A prism is a 3-dimensional figure that can be cut into parallel slices or cross-sections that have the same size and shape.



WORKED EXAMPLE 18 Drawing the cross-section of a prism

Draw the cross-section of the following prisms.

a. 

b. 

THINK


a. 1. Identify the cross-section of the prism that is uniform along the length.


2. Draw the cross-section as a 2-dimensional shape.


b. 1. Identify the cross-section of the prism that is uniform along the length.


2. Draw the cross-section as a 2-dimensional shape.

DRAW

a. 



b. 



eles-4563

10.9.2 Plans and views

- An object can be viewed from different angles.
- Architects and draftspersons draw plans of buildings viewed from the front, the side or the top.
- The **front view**, or **front elevation**, is what you see if you are standing directly in front of an object.
- The **side view**, or **side elevation**, is what you see if you are standing directly to one side of the object. You can draw the left view or the right view of an object.
- The **top view**, or **bird's eye view**, is what you see if you are hovering directly over the top of the object looking down on it.




- The **back view**, or **back elevation**, is what you see if you are standing directly behind an object.

WORKED EXAMPLE 19 Drawing elevations or views

The following object is made from 4 cubes.
Draw plans of it showing:

a. the front view
b. the right view
c. the top view
d. the back view.



THINK

a. Make this shape using cubes. Place the shape at a considerable distance and look at it from the front (this way you can see only the front face of each cube). Draw what you see. (Or simply imagine looking at the shape from the front and draw what you see.)


b. Look at your model from the right, or imagine that you can see only the right face of each cube and draw what you see.

c. Look at your model from the top, or imagine that you can see only the top face of each cube. Draw what you see.

d. Imagine that you can only see the shape from behind. Draw what you would see.


DRAW

a.




Front view

b.



Right view


c.



Top view



Front




Back view

- As you can see from Worked example 19, the back view is a mirror image of the front view. In fact, for any solid, the back view will always be the mirror image of the front view.
- Figures such as the one in Worked example 19 can be drawn using isometric dot paper. This will help to give the 3-dimensional perspective of the object.

WORKED EXAMPLE 20 Drawing a view of a solid


Draw plans of this solid showing:
a. **the front view**
b. **the right view**
c. **the top view.**



THINK

1. Determine an object of similar shape, or visualise the object in your head.
2. Whether viewed from the front, or from the right of the object, the rectangular shaft will appear as a long thin rectangle. The square prisms will also be seen as a pair of identical rectangles. So the front view and the right view are the same.
3. When the object is viewed from above, all we can see is the flat surface of the top square prism: that is, a large and a small square with the same centre.

DRAW



eles-4564

10.9.3 Isometric drawing

- When working with 3-dimensional models and designs, it is often useful to have the design or model drawn on paper (that is, in 2 dimensions).
- An **isometric drawing** is a 2-dimensional drawing of a 3-dimensional object.
- Isometric dot paper can be used to help with these drawings.

WORKED EXAMPLE 21 Completing an isometric drawing of an object

First copy the incomplete figure (Figure 1) onto isometric dot paper. Complete the isometric drawing of the object (Figure 2).

Figure 1



Figure 2



THINK

Study the object and identify the lines that have already been drawn. Fill in the missing lines on your isometric drawing to match the object.

DRAW



WORKED EXAMPLE 22 Drawing an object on isometric dot paper


Draw the following object on isometric dot paper. (You could construct it from a set of cubes.)



THINK


1. Use cubes to make the object shown (optional). Draw the front face of the object. The vertical edges of the 3-dimensional object are shown with vertical lines on the isometric drawing; the horizontal edges are shown with the lines at an angle (by following the dots on the grid paper).
2. Draw the left face of the object.
3. Add the top face to complete the isometric drawing of the object.

DRAW



WORKED EXAMPLE 23 Constructing a solid from given information


The front, right and top views of a solid are shown. Use cubes to construct the solid, then sketch the solid.



THINK

1. Use cubes to construct the solid.
2. Check carefully that your solid matches each of the 3 views you are given. Make adjustments if necessary.

CONSTRUCT



COLLABORATIVE TASK: Build it!

Equipment: building blocks

For this activity, you will work in groups of three or four as directed by your teacher.

1. Stack ten building blocks in any formation. An example is shown.
2. Draw diagrams of the formations you have assembled to show:
   a. the top view
   b. the front view
   c. the side view.
3. Dismantle your formation. Swap your drawings with another group and ask them to build your formation by using your diagrams.



DISCUSSION

In your small groups from the previous activity, discuss some of the uses of these types of drawings. In which professions might these types of drawings be used?

Resources

eWorkbook Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)

Interactivities Individual pathway interactivity: Plans and views (int-4392)
Prisms (int-4148)
Plans and views (int-4149)

Exercise 10.9 Drawing solids

learnON

Individual pathways


PRACTISE	CONSOLIDATE	MASTER
1, 3, 7, 8, 10, 12, 16, 19, 20	2, 4, 5, 9, 11, 14, 17, 21	6, 13, 15, 18, 22, 23

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE18 Draw the cross-sections of the following prisms.

a.




b.




2. Draw the cross-sections of the following prisms.

a.




b.




3. WE19 The following objects are made from cubes. For each object draw the plans, showing the front view, the right view, the top view and the back view. (You may wish to use a set of cubes or building blocks to help you.)


a.



b.




c.




4. The following objects are made from cubes. For each object draw the plans, showing the front view, the right view, the top view and the back view. (You may wish to use a set of cubes or building blocks to help you.)


a.



b.




c.




5. Draw the front, right and top views of these objects.


a.




b.



c.



6. Draw the top, front and side views of the object shown in the following isometric drawing.




7. **WE20** Draw the front, right and top views of each solid shown.

a.




b.




8. **WE21** Copy the following figures onto isometric dot paper and complete the isometric drawing of the objects shown.


a.




b.



c.



d.



9. **WE22** Draw each of the following objects on isometric dot paper. (You might wish to make them first from a set of cubes.)


a.




b.



c.



d.




Understanding


10. WE23 The front, right and top views of a solid are shown. In each case, use cubes to construct the solid, then sketch the solid.

a.


Front view



Right view




Top view





b.

Front view



Right view



Top view






11. The front, right and top views of a solid are shown. In each case, use cubes to construct the solid, then sketch the solid.

a.

Front view



Right view



Top view





b.

Front view



Right view



Top view





12. MC The front, right and top views of a solid are shown. Select the correct solid represented by these views.


Front view



Right view




Top view







A.




B.




C.



D.



E.



13. Construct the following letters using cubes, and then draw the solids on isometric dot paper:

a. the letter T with 5 cubes
b. the letter L with 7 cubes
c. the letter E with 10 cubes
d. the letter H with 7 cubes.

14. Draw the following figure on isometric dot paper.





15. Draw a selection of buildings from this photograph of a city skyline on isometric dot paper.




Reasoning


16. Consider the shapes with the following front and right views.
Determine the minimum number of cubes that could be used to construct the shape with the following views.
Determine the maximum number of cubes that could be used. Explain your reasoning.


Front view 

Right view 

17. A shape is made using only 4 cubes. Its front view, right view and top view are shown.

Front view 

Right view 

Top view 



a. Explain whether it is possible to construct this solid.
b. Describe or draw what this solid would look like.


18. How many objects can you construct using the top view shown? Explain your answer with the use of diagrams.




Problem solving

19. On the same isometric dot paper, draw the two wooden boxes shown.






20. Draw the plans of the following diagram, showing the front view, right view and top view.



21. Jonah is building a brick wall as shown in the photograph. Draw this part of the wall on isometric dot paper.



22. Draw top, front and side views for the 3D objects shown.







23. Sam has a set of wooden cube blocks he uses to build different shapes. His sister Chris challenged him to see how many different ways he could stack 4 cubes. He can only stack them on top of each other or side by side — not one behind the other. The arrangements must be different and not simply be a mirror image or rotation of another shape. Draw the different arrangements possible.

10.10 Review

10.10.1 Topic summary

Area


- The area of a shape is the amount of 2-dimensional space within it.
- Area is measured in square units: mm^2, cm^2 m^2 and km^2
- The area formulas for some common shapes are listed below.

Shape	Area formula
Square 	$A = l \times l$ $= l^2$
Rectangle 	$A = l \times w$
Parallelogram 	$A = b \times h$
Triangle 	$A = \frac{1}{2} \times b \times h$

- The hectare, ha, is a non-SI metric unit of area equal to a square with sides of 100 m.
  1 ha = 10 000 m^2

Capacity


- The amount of liquid an object can hold is known as its *capacity*.
- Capacity can be measured in cubic units (cm^3 or m^3); however, it is more commonly measured in millilitres (mL), litres (L), kilolitres (kL) or megalitres (ML).
- You can convert between these units by using the diagram below.



1000 mL = 1 L
1000 L = 1 kL
1 cm^3 = 1 mL
1000 cm^3 = 1 L

Units of length

- The modern metric system in Australia is defined by the International System of Units (SI).
- The most common units of length are millimetres (mm), centimetres (cm), metres (m) and kilometres (km).
- You can convert between these units by using the diagram below.




e.g.
3.4 m = 3.4 × 100 × 10 mm = 3400 mm



Perimeter

- The perimeter, *P*, is the distance around a closed shape.
- When calculating the perimeter of a shape, make sure all lengths are in the same units before adding them together.




$P = 4 + 3.2 + 3 + 4.3 = 14.5$ cm

MEASUREMENT

Volume

- Volume is the amount of 3-dimensional space an object takes up.
- Volume is measured in cubic units: mm^3, cm^3, m^3 and km^3.
- A prism is a solid object with identical ends, flat faces and the same cross-section along its length.
- The volume of a rectangular prism is given by:

$V = l \times w \times h$



10.10.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
10.2	I can convert between different units of length.			
10.3	I can read and interpret various scales.			
10.4	I can calculate the perimeter of a given shape.			
	I can calculate the perimeter of rectangles and squares.			
10.5	I can calculate, or estimate, the area of a given shape.			
	I can calculate the area of rectangles, squares, triangles and parallelograms using formulas.			
10.6	I can separate composite shapes into simple shapes.			
	I can calculate the area of composite shapes by adding or subtracting areas of simple shapes.			
10.7	I can calculate the volume of a rectangular prism.			
10.8	I can calculate the capacity of a container.			
	I can convert between units of volume and capacity.			
10.9	I can draw the cross-section of a given prism.			
	I can draw the views, or elevations, of a given solid.			
	I can construct a solid given its views or elevations.			

10.10.3 Project


Old units of length

When studying length and perimeter, you learned about the common metric units of length: millimetre, centimetre, metre and kilometre. It's only in the last few decades that these units have been commonly used in Australia. Prior to this, the units of length were based on the imperial system. Most countries in the world use units based on the metric system, but a few continue to use imperial units.



The origins of the imperial units are far and wide. Many have been adapted from ancient times or translated into English from other languages. Other units, as strange as it may seem, are based on parts of the body.

The ancient Egyptians built the Great Pyramid of Giza over four and a half thousand years ago. It was constructed with side lengths of 440 cubits and was 280 cubits high.



The *cubit* was a unit equal to the 'length of the forearm of the bent elbow to the tip of the extended middle finger'.

1. The metric height of the Great Pyramid of Giza is 146.5 metres; its base length is 230 metres. Use these to determine the value of the cubit to 3 decimal places.
2. Below are some units of length from the imperial system. Select five units, and calculate their equivalent in the metric system. Find out where and how they were used (what sorts of objects they measured, in what situations they were used — for example, for small or large distances, for racetracks, for the depth of water or in land surveying).

league	hand	line	mile
furlong	chain	inch	link
rod	foot	yard	fathom



Although Australians have used units of length from the metric system for over 3 decades, many institutions have stuck with units common to the imperial system. For example, a cricket pitch is still 22 yards long.

3. Find another sport that still uses lengths associated with the imperial system and state the unit(s) involved.



Resources

eWorkbook Topic 10 Workbook (worksheets, code puzzle and project) (ewbk-1911)

Interactivities Crossword (int-2600)
Sudoku puzzle (int-3170)

Exercise 10.10 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Identify which metric unit would be most suitable for measuring:
   a. the distance walked by a teacher at school during a week
   b. the length of a piece of spaghetti
   c. the width of a pencil.


2. Complete the following conversions.
   a. 560 mm = _____ m
   b. 2300 cm = _____ km
   c. 17 m = _____ cm
   d. $\frac{3}{4}$ km = _____ mm
   e. 2.09 m = _____mm

3. Complete the following conversions.
   a. $6\frac{4}{5}$ cm = _____ m
   b. 22.5 mm = _____ cm
   c. $\frac{63}{10\,000}$ km = _____ m
   d. 82 000 000 m = _____ km
   e. $5\frac{9}{10}$ mm = _____ cm

4. Arrange from smallest to largest: 44.5 m, 455 cm, 455 000 mm, 0.004 45 km.

5. a. Add 45.6 km to 5600 m.
   b. Calculate the difference between 80 m and 4300 cm.

6. Identify the reading in kilograms on this bathroom scale. *Note:* The scale for kilograms is the inner circle.




7. Estimate the height of the front tree in the photograph, given that the person standing is 1.7 m tall.




8. Identify which unit of area would be the most appropriate for measuring the following. (Choose from mm^2, cm^2, m^2, ha and km^2.)


a. The floor area of your classroom
b. The area of the city of Brisbane
c. A pin head
d. A market garden
e. The area of the continent of Antarctica

9. Determine the areas of the following figures, which are drawn on centimetre grid paper.

a.



b.


c.



d.


e.



10. Estimate the shaded area in the figure.
Note: Each square on the grid has an area of 1 cm^2



11. Use the formula $A = lw$ to calculate the areas of the following rectangles.


a.


b.



c.


12. Calculate the areas of the following shapes by first dividing them into rectangles.


a.



b.




c.




13. Calculate the areas of the following shapes by first dividing them into rectangles.


a.



b.




c.




14. Calculate the areas of the following triangles.


a.



b.




c.




15. Calculate the areas of the following shapes.

a.




b.




16. Calculate the areas of the following shapes.

a.




b.




17. Calculate the volume of each shape in cubic centimetres (cm^3). Each cube has a volume of 1 cm^3.


a.




b.



c.




d.




18. Draw the front, right and top views of these objects.

a.




b.




19. Draw isometric views of the objects, whose front (F), right (R) and top (T) views are given here.


a.




b.



20. Use the information given in the diagram to calculate the volume of the shape.



21. Use the information given in the diagram to determine the volume of the shape.



22. Complete the following conversions.

a. 8 L = _____ mL

b. $\frac{21}{50}$ L = _____ mL

c. 3300 mL = _____ L

d. $1\frac{3}{250}$ L = _____ mL

23. Complete the following conversions.

a. $4\frac{3}{10}$ kL = _____ L

b. 0.0034 kL = _____ L

c. 4755 L = _____ kL


d. 432 mL = _____ L

Problem solving


24. During a rescue operation in calm seas, a 16.5 m rope is dangled from a helicopter hovering 20 m above sea level. A man who is 175 cm tall is standing on the deck of a boat when he reaches 50 cm above his head for the rope. By how much does he fail to reach the rope if the deck is 1 m above sea level?

25. Calculate the perimeter of each shape.

a.




b.




Note: The dots are 1 cm apart.


c.



d.




26. Michelle rides three laps of the following dirt-bike track. Calculate how far she rides altogether.




27. Determine the length of satin ribbon required to edge a rectangular blanket on all four sides if the blanket is 240 cm long and 195 cm wide. (Assume there is no overlap.)

28. Determine the cost of paving a rectangular courtyard that is 6.5 m long and 3.2 m wide. The courtyard is to be paved with concrete paving blocks, which cost $28 per square metre.

29. Calculate the area of card needed to make the triangular display sign shown.



30. When making a box kite, Katie cuts a square piece of material diagonally, as shown by the dotted line in the diagram. What is the area of each triangular piece of material?



31. **a.** A rectangular prism has a length of 40 cm and a width of 26 cm. If its volume is 29 120 cm^3, calculate the height of the rectangular prism.

b. A rectangular prism has a length of 30 cm and a width of 15 cm. If its volume is 3825 cm^3, calculate its height.


32. In a food technology class, each of the 14 groups of students uses 350 mL of fresh milk to make pancakes. Calculate how many litres of milk should be ordered for the whole class.

33. Mario makes up raspberry cordial by pouring 275 mL of concentrate into a 2-litre container and filling the container with cold water.


a. Calculate how much cold water Mario needs to add.

b. Calculate how many 250 mL glasses of cordial Mario can pour from the large container.

34. A 6×16 rectangle is cut into two pieces as indicated. The two pieces are rearranged to form a right triangle. Calculate the perimeter of the resulting triangle.



35. Each small square in the following diagram measures 1 cm $\times$ 1 cm. Calculate the area of triangle ABC (in square cm).



36. Stewart is having a swimming pool built in his back yard. The hole for the pool is 6 metres long, 4 metres wide and 1.5 metres deep. The excavated soil becomes aerated as it is dug out, and its volume is increased by $\frac{1}{10}$. Determine the volume of the excavated soil.

37. A rectangular cake is three times as long as it is wide. A layer of icing that is 1 cm thick is spread on top of the cake. If the total volume of icing used is 300 cm^3, determine the dimensions of the top of the cake.


38. A gardener is employed to pave a path that is 2 metre wide around a 10 m $\times$ 5.5 m rectangular swimming pool.

a. Determine the area of the paved path.

b. Determine the minimum number of bricks that should be ordered if there are 60 bricks per square metre.


39. The perimeter of a rectangle is 20 cm. Investigate the shape of all such rectangles if the sides are whole numbers. Identify the dimensions of the rectangle with the largest area.

40. The following rectangle is divided into three identical smaller rectangles. The length of the large rectangle is 12 cm.
Determine the width of the large rectangle.




41. The front, side and top views of a solid are shown. Construct this solid using blocks, then sketch the solid.

a.



b.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1911) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0699) ☐

Digital documents

10.2 SkillSHEET Metric units of length (doc-6505) ☐
SkillSHEET Measuring the length of a line (doc-6507) ☐
SkillSHEET Relationship between unit size and the number of units used (doc-6508) ☐
SkillSHEET Converting units (doc-6509) ☐
SkillSHEET Converting units to compare lengths and distances (doc-6510) ☐
10.3 SkillSHEET Reading scales (doc-6506) ☐
10.4 SkillSHEET Perimeter (doc-6511) ☐
10.5 SkillSHEET Area units (doc-6512) ☐
SkillSHEET Area of figures drawn on one-centimetre grid paper (doc-6513) ☐
SkillSHEET Area of rectangles (doc-6514) ☐
SkillSHEET Area of triangles (doc-6515) ☐
10.6 SkillSHEET Volume units (doc-6516) ☐
SkillSHEET Volume of a solid constructed from cubic-centimetre blocks (doc-6517) ☐

Video eLessons

10.2 Metric units of length (eles-4549) ☐
Converting units of length (eles-4550) ☐
10.3 Reading scales and measuring length (eles-4551) ☐
10.4 Calculating the perimeter (eles-4552) ☐
Calculating the perimeter of a rectangle and a square (eles-4553) ☐
Perimeter (eles-1874) ☐
10.5 Metric units of area (eles-4554) ☐
Calculating the area of a rectangle (eles-4555) ☐
Calculating the area of a triangle (eles-4556) ☐
Area of a parallelogram (eles-4557) ☐
10.6 Calculating the area of composite shapes (eles-4558) ☐
Composite area (eles-1886) ☐
10.7 Volume (eles-4559) ☐
Calculating the volume of a rectangular prism (eles-4560) ☐
10.8 Capacity (eles-4561) ☐
10.9 Prisms (eles-4562) ☐
Plans and views (eles-4563) ☐
Isometric drawing (eles-4564) ☐

Interactivities

10.2 Individual pathway interactivity: Units of measurement and converting units of measurement (int-4355) ☐
Metric units of length (int-4010) ☐
Converting units of length (int-4011) ☐
10.3 Individual pathway interactivity: Reading scales and measuring length (int-4356) ☐
Scales and measuring length (int-4012) ☐
10.4 Individual pathway interactivity: Perimeter (int-4357) ☐
Perimeter (int-4013) ☐
Perimeter of composite shapes (int-4014) ☐
10.5 Individual pathway interactivity: Area (int-4358) ☐
Metric units of area 1 (int-4015) ☐
Metric units of area 2 (int-4016) ☐
Area of a rectangle (int-4017) ☐
Area of a triangle (int-4018) ☐
Area of a parallelogram (int-4019) ☐
10.6 Individual pathway interactivity: Area of composite shapes, using addition and subtraction (int-4359) ☐
Area of composite shapes (int-4020) ☐
10.7 Individual pathway interactivity: Volume of rectangular prisms (int-8470) ☐
Volume (int-4021) ☐
Volume of a rectangular prism (int-4022) ☐
10.8 Individual pathway interactivity: Capacity (int-4361) ☐
Capacity (int-4024) ☐
10.9 Individual pathway interactivity: Plans and views (int-4392) ☐
Prisms (int-4148) ☐
Plans and views (int-4149) ☐
10.10 Crossword (int-2600) ☐
Sudoku puzzle (int-3170) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers

Topic 10 Measurement

Exercise 10.1 Pre-test

1. 56.5 cm
2. 0.020 12 km
3. 90 m
4. 1.8 km
5. 46.8 cm
6. 50 m
7. 27 m^2
8. $472.50
9. 112 cm^2
10. 12.72 m^2
11. 48 m^3
12. 7 cm
13. 54 L
14. **a.** ii **b.** iii **c.** v **d.** i **e.** iv
15. **a.** B **b.** A **c.** C **d.** D

Exercise 10.2 Units of measurement

1. **a.** m **b.** km **c.** cm **d.** km **e.** m
2. **a.** m **b.** cm **c.** km **d.** mm
3. A
4. **a.** 2000 m **b.** 7000 m
   c. 5300 m **d.** 660 m
5. **a.** 25 cm **b.** 280 mm
   c. 2000 mm **d.** 70 000 cm
6. **a.** 8 km **b.** 6.5 km
   c. 0.7 km **d.** 0.05 km
7. **a.** 60 m **b.** 0.57 m
   c. 4.5 cm **d.** 2560 cm
8. **a.** 800 000 cm **b.** 101 000 mm
   c. 72 330 mm **d.** 0.030 35 mm
9. D
10. A
11. **a.** 0.0452 km **b.** 0.56 m **c.** 87.5 mm
12. **a.** 60 cm **b.** 309 000 cm **c.** 4.8 cm
13. Sample responses are given here:
    a. the length of tube required to allow a cat to breathe through while in surgery
    b. the circumference of an actor's head so that an old-fashioned hat of the correct size can be made
    c. the length of a piece of milled hardwood required for the tabletop of a new table for a large family
    d. the height of a hill that requires terracing
    e. the length, in paces, of the runway leading to a long jump pit
14. **a.** 868 cm **b.** 10.8 cm
15. Everest: 8.848 km, K2: 8.611 km
16. **a.** 150 cm, 12.5 m, 0.02 km
    b. 0.445 m, 3000 mm, 350 cm
    c. 50 000 mm, 500 m, 50 km
17. **a.** 1.7 m, 1700 cm, 0.17 km
    b. 0.0052 mm, 0.000 052 m, 0.052 cm
    c. 0.909 m, 9000 mm, 990 cm
18. **a.** 375 cm **b.** 10 200 m
    c. 224.2 cm **d.** 155.3 cm
19. **a.** 66 400 m **b.** 410.4 m
    c. 10.4 cm **d.** 1.7 km
20. 828 m
21. 44
22. 216 m
23. 1.593 m
24. Yes, 36 cm
25. 198 cm
26. 2.4 m
27. **a.** **i.** 18 000 000 km
    ii. 1 080 000 000 km
    iii. 25 920 000 000 km
    iv. 9 460 800 000 000 km
    b. Distances in the universe are very big and it would be inconvenient to use kilometres to measure them. The numbers in kilometres would be too large and would make interpreting and even reading distances difficult.
28. 71 428 pins
29. 38
30. 40 cm
31. 215 cm, 105 cm, 155 cm, 170 cm
32. **a.** **i.** 50 rotations
    ii. 100 rotations
    b. **i.** 500 rotations
    ii. 1000 rotations
33. 2 cm × 4 cm, 2 cm × 8 cm, 2 cm × 12 cm, 2 cm × 16 cm
34. 38.5 km


Exercise 10.3 Reading scales and measuring length

1. **a.** 4 cm **b.** 7 cm **c.** 2 cm
2. **a.** 9.5 cm **b.** 6.4 cm **c.** 10.1 cm **d.** 5.8 cm
3. 2.3 units
4. **a.** 45 °F **b.** 34 °C **c.** 26 °C **d.** 10 °C
5. **a.** 45 km/h **b.** 80 km/h **c.** 100 km/h
6. **a.** 1280 mL **b.** 1800 mL
7. 30 °C
8. **a.** 130 °C **b.** 220 °C **c.** 360 °F
9. B
10. C
11. D
12. D
13. B
14. 1.74 m

15. C
16. A
17. B
18. Sample answers include the following:
    a. Measuring a piece of wood
    b. Drawing straight lines
    c. Determining waist size
    d. Measuring garden dimensions
19. The lamppost is about 4 times the height of the car, so it is about 7.2 m high.
20. Measure the thickness of the book using a ruler, then divide the thickness of the book by the number of pages (two sided) in the book to calculate the thickness of each page.
21. 0.2 km
22. 293 cm

Exercise 10.4 Perimeter

1. a. 8 units b. 18 units c. 18 units
   d. 22 units e. 12 units
2. a. 40 cm b. 92 mm
3. a. 30 m b. 44 cm
4. 74 cm
5. 68 cm
6. 28 cm
7. a. 173 mm b. 2995 cm
8. a. 408 mm b. 180 mm
9. a. 14 433 m b. 17 579 m
10. B
11. a. 156 cm b. 664.2 cm c. 14.8 cm
12. a. $12\frac{9}{10}$ m or 12.9 m
    b. $32\frac{4}{5}$ mm or 32.8 mm
13. 48.5 m
14. 252 cm
15. 325.8 m
16. 139.8 m
17. a. 193 m b. $3667
18. a.



    b. 109.48 m
    c. $4050.76
19. For example, fence construction companies would need to calculate perimeters on a daily basis.
20. 99 cm
21. a. 120 m b. $228 c. $810
    d. 25 posts e. $341.25
    f. i. 1600
       ii. $1680
    g. $4059.25
22. a. 8 different rectangles
    b. Square sides 8 cm
23. $P = 6a - 2b$
24. 6 cm

Exercise 10.5 Area

1. a. cm^2 b. m^2 c. mm^2 d. km^2
2. a. m^2 b. km^2 c. m^2 d. ha
3. a. $14\,cm^2$ b. $10\,cm^2$ c. $10\,cm^2$
   d. $16\,cm^2$ e. $8\,cm^2$
4. a. $9\,cm^2$ b. $6\,cm^2$ c. $9\frac{1}{2}\,cm^2$
   d. $12\,cm^2$ e. $10\,cm^2$
5. A
6. C
7. C
8. a. $15\,cm^2$ b. $14\,km^2$ c. $10\,m^2$
9. a. $20\,cm^2$ b. $48\,m^2$
10. a. $56\,m^2$ b. $400\,mm^2$
11. a. $72\,cm^2$ b. $76\,m^2$
12. a. $135\,mm^2$ b. $686\,mm^2$
13. a. $4\,cm^2$ b. $3\,cm^2$ c. $40.5\,cm^2$ d. $50\,cm^2$
14. C
15. A
16. A
17. a. $416\,cm^2$ b. $3.125\,m^2$ c. $2.4\,m^2$ d. $493\,mm^2$
18. a. $583\,cm^2$ b. $600\,km^2$
    c. $337.5\,cm^2$ d. $152\,cm^2$
19. $28.14\,mm^2$
20. C
21. $200\,000\,m^2$
22. a. $16\,000\,000\,000\,m^2$
    b. 1 600 000 hectares
23. $17.5\,m^2$
24. $9.66\,m^2$
25. a. $7.5\,m^2$ b. 15 boxes c. $528
26. $141.64
27. $2560
28. It would be cheaper to use the 70 cm × 70 cm concrete pavers.
29. $88.8\,m^2$
30. $104\,m^2$, $1300
31. $4920\,km^2$
32. $6000\,cm^2$ ($0.6\,m^2$)
33. $135\,m^2$
34. $12.6\,m^2$

35. 126 m^2
36. Length 9 cm, width 4 cm
37. Two sides of the fencing are 6 m long and the other side is 12 m, providing an area of 72 cm^2.

Exercise 10.6 Area of composite shapes

1. a. 81 cm^2 b. 5 m^2 c. 16 cm^2
2. a. 56 cm^2 b. 588 cm^2 c. 13.5 m^2
3. a. 48 m^2 b. 325 m^2
4. 13.05 m^2
5. 39.28 m^2
6. 14.25 m^2
7. a. 27 m^2 b. $675
8. $2157.60 (rounded to the nearest 5 cents)
9. 75 m^2
10. 39 m^2
11. a. 22 cm^2
    b. 22 cm^2
    c. Sample responses can be found in the worked solutions in the online resources.
12. If your composite shape is made up of two or more simple shapes, it is best to determine the area by addition. If the area of a shape has a section not required (a shaded area), it is best to calculate the total area and then subtract the area not required.
13. a. Square of side length 30 cm
    Three circles of diameter 15 cm
    Two semicircles of diameter 30 cm
    b. Using addition of areas: square + circle of diameter 30 cm (the two equal semicircles form one circle).
    Using subtraction of areas: area calculated in previous step $-3\times$ area of the smaller (coloured) circle.
    c. 1075 cm^2
    d. The area in mm^2 would be 107 500 mm^2. This is more inconvenient to use because it is a larger number, which is harder to interpret and use in further calculations if needed.
14. \$0.15/cm^2
15. The shaded area is $\frac{7}{32}$ of the square.
16. a. i. Two rectangles with length 4 cm and width 1 cm and two parallelograms with length 3 cm and width 0.5 cm
    ii. One square of side length 4 cm, one rectangle with length 2 cm and width 1 cm, one triangle with height 3 cm and base 1 cm and two right-angled triangles with height 3 cm and base 0.5 cm. The last two triangles form a triangle with base 1 cm and height 3 cm.
    b. 11 cm^2

Exercise 10.7 Volume of rectangular prisms

1. a. 8 cm^3 b. 6 cm^3 c. 12 cm^3 d. 48 cm^3
2. B
3. a. 4 cm^3 b. 24 cm^3 c. 15 cm^3 d. 13 cm^3
4. a. 7 cm^3 b. 35 cm^3 c. 14 cm^3 d. 17 cm^3
5. A
6. a. 12 cm^3 b. 12 m^3 c. 6144 cm^3
7. a. 12 cm^3 b. 10 cm^3 c. 10 cm^3
8. a. 192 m^3 b. 270 cm^3 c. 101.25 cm^3
9. D
10. B
11. a. 186 cm^3 b. 136 cm^3
12. a. 189 cm^3 b. 180 cm^3
13. 9690 cm^3
14. 477 750 cm^3
15. a. 20 cm b. 9 cm c. 12 cm
16. a. 2700 cm^3 b. 2 700 000 mm^3
17. 4.875 m^3
18. a. 28.875 cm^3 b. 28 875 mm^3
    c. 176 mm^3 d. 20 075 mm^3
19. 768 m^3
20. 40.8 m^3
21. Each guest receives 267 cm^3 of cake.
22. 2500 m^3
23. 0.65 m^3 more soil is needed (or 2.075 m^3).
24. 2277 cm^3
25. Length 18 cm, width 15 cm and height 10 cm. Volume is 2700 cm^3.
26. 36 000

Exercise 10.8 Capacity


1. a. 2000 mL b. 3 L c. 7 L d. 5.5 L
2. a. 2500 mL b. 32 L c. 35 mL d. 420 000 mL
3. a. 1870 mL b. 22.5 L c. 100 mL d. 0.025 kL
4. a. 750 mL b. 0.0025 kL
    c. 2450 cm^3 d. 78 L
5. a. 40 000 mL = 40 L b. 6000 mL = 6000 cm^3
    c. 5.2 kL = 5.2 m^3
6. D
7. D
8. a. 0.25 L, 2.45 L, 2.5 L, 25 000 mL
    b. 7.65 mL, 760 mL, 0.765 L, 7.60 L
    c. 0.011 L, 0.1 L, 110 mL, 1.1 L
9. 16 bottles
10. 1750 mL (1.75 L)
11. 1620 mL (1.62 L)
12. 6 L
13. 50 doses
14. 225 bottles
15. 9.9 L
16. 4.8 L
17. a. No b. Yes
18. The 185 mL container is the better buy.


19. The tank overflowed.
20. 616 mL
21. 50.4 L
22. Approximately 27 L (27.09 L)
23. 300 mL
24. 1401.6 L
25. 16.4 kL = 16.4 m^3. An example could be length 2 m, width 2 m, height 4.1 m.


Exercise 10.9 Drawing solids


1. a. 
b. 


2. a. 
b. 


3 a. 


b. 


c. 


4. a. 



b. 


c. 


5. a. 

b. 

c. 

6. Top view 
Front and side views 


7. a. 

b. 


8. a. 
b. 
c. 
d. 

9. a. 
b. 
c. 
d. 


10. a.




b.



11. a.



b.



12. D

13. a.



b.



c.




d.



14.



15. A sample response is shown below.




16. The minimum number of cubes that could be used is 8, as shown in blue in the figure. There are two spaces that could be filled with cubes without changing the front or right views (shown in pink); therefore, the maximum number of cubes that could be used is 10.




17. a. It would be difficult to construct this solid.

b.




The solid would look like the one shown. The fourth cube is behind the front bottom cube, resting on the surface. The two top cubes have no cubes supporting them.


18. An infinite number of shapes because there are no restrictions on the other two views




19.




20.



21.




22. Top view | Front view | Side view



Top view | Front view | Side view



23. The arrangements are shown below.



Project

1. 1 cubit = 0.523 metres

2. A sample response is given here.
Inch — a unit of length used as a measure for display screens, the height of a person or sometimes the thickness of an object
Mile — a unit of length or distance used to measure the distance usually seen on road signs in the US
Furlong — a unit of distance used to measure dimensions of farmland and distance in horse racing
Foot — a unit of length used to measure the height of a person or an object
Fathom — a unit of length used to measure the depth of the water, or the length of a fisher's setline

3. A sample response is given here.

Basketball:

Baskets:	Inches Rings are 18 inches in inside diameter, with white cord 12-mesh nets, 15 to 18 inches in length.
Height of basket:	Feet 10 feet (upper edge)
Circumference of ball:	Inches Not greater than 30 inches and not less than $29\frac{1}{2}$ inches.

Soccer:

Goals:	Yards/feet/inches Distance between posts is 8 yards. Distance from crossbar to the ground is 8 feet.
Penalty area:	Yards Two lines drawn at right angles to the goal line, 18 yards from the inside of each goalpost. Lines extend into playing field for 18 yards and are joined by a line drawn parallel with the goal line.

Exercise 10.10 Review questions

1. a. Kilometres or metres
b. Centimetres
c. Millimetres

2. a. 0.56 m **b.** 0.023 km **c.** 1700 cm
d. 750 000 mm **e.** 2090 mm

3. a. 0.068 m **b.** 2.25 cm **c.** 6.3 m
d. 82 000 km **e.** 0.59 cm

4. 0.004 45 km, 455 cm, 44.5 m, 455 000 mm

5. a. 51 200 m (51.2 km)
b. 3700 cm (37 m)

6. 80 kg

7. 7 m

8. a. m^2 **b.** km^2 **c.** mm^2
d. ha **e.** km^2

9. a. $12\ cm^2$ **b.** $13\ cm^2$ **c.** $2\ cm^2$
d. $5\ cm^2$ **e.** $6\frac{1}{2}\ cm^2$

10. $15\ cm^2$

11. a. $150\ m^2$ **b.** $6\ cm^2$ **c.** $2914\ mm^2$

12. a. $9\ cm^2$ **b.** $19\ cm^2$ **c.** $52\ cm^2$

13. a. $9\ cm^2$ **b.** $380\ cm^2$ **c.** $11\ cm^2$

14. a. $627\ cm^2$ **b.** $96\ m^2$ **c.** $1344\ cm^2$

15. a. $16\ m^2$ **b.** $432\ mm^2$

16. a. $87.5\ cm^2$ **b.** $41\ cm^2$

17. a. $18\ cm^3$ **b.** $30\ cm^3$
c. $20\ cm^3$ **d.** $28\ cm^3$

18. a.



F R T

b.



F R T

19. a.



b.



20. $72\ cm^3$

21. $112\ cm^3$

22. a. 8000 mL **b.** 420 mL
c. 3.3 L **d.** 1012 mL

23. a. 4300 L **b.** 3.4 L
c. 4.755 kL **d.** 0.432 L

24. 25 cm

25. **a.** 46 cm **b.** 20 cm
c. 191 mm (19.1 cm) **d.** 21 cm (210 mm)

26. 243 m

27. 870 cm

28. $582.40

29. 3.6 m^2

30. 0.72 m^2

31. **a.** 28 cm **b.** 8.5 cm

32. 4.9 L

33. **a.** 1725 mL (1.725 L)
b. 8 glasses

34. The perimeter is 46.

35. 32 cm^2

36. 39.6 cubic metres

37. 10 cm by 30 cm


38. **a.** Area of path is 78 m^2.
b. 4680 bricks are needed.

39. Possible side dimensions: $9 \times 1; 8 \times 2; 7 \times 3; 6 \times 4; 5 \times 5$.
Largest area is 25 square units.

40. 8 cm

41. **a.**  **b.** 

11 Coordinates and the Cartesian plane



LEARNING SEQUENCE

11.1 Overview 608
11.2 The Cartesian plane 611
11.3 Linear number patterns 619
11.4 Plotting simple linear relationships 627
11.5 Interpreting graphs 633
11.6 Review 645

11.1 Overview

Why learn this?

Using a coordinate system enables us to pinpoint locations in different settings. When you go to the movies, a musical, a concert or a sporting grand final, your ticket shows where you will be seated. For example, a ticket to a concert may give the location of your seat as Section 47, Row G, Seat 5. A boarding pass on a flight always shows where you will be sitting. For example, a boarding pass that shows seat 30A means you will be seated in row 30, seat A, by the window.



Have you ever wondered where you are on a map, or globe, of the world? Melbourne is 37.81°S, 144.96°E, which means it is in the southern hemisphere, 37.81° south of the equator and 144.96° east of the Royal Observatory in Greenwich, England. New York is 40.71°N, 74.01°W, so it is in the northern hemisphere and west of Greenwich. In coordinate geometry, we define a point by how far it is horizontally and vertically from the centre point. Scientists and geographers often use coordinates when they analyse data. Reading and interpreting maps involves knowing about coordinates. Computer programmers use coordinates when creating artwork. A computer screen is made up of tiny points of light called pixels. Programmers use coordinates to identify which pixels to light up when creating art. Understanding coordinates, and maps, assists you in many of your everyday activities.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 11.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.


Use the following map to answer questions 1 and 2.




1. Use the grid map to give the grid references for:
   a. Mt Kosciuszko b. Port Campbell c. The Grampians.

2. Using the grid map, name a town that is located within each of the following grid references.
   a. C1 b. B2 c. D3

3. Consider the chessboard shown.
   a. One of the black rooks (in chess, rook is another name for castle) is on a8. State the location of the white rooks.
   b. One of the white bishops is on c1. State the position of the second white bishop.
   c. A bishop can move diagonally any number of (unoccupied) squares at a time. With its next move, the bishop at b3 could capture the pawn at what position?



4. Identify the coordinates of point X on the Cartesian plane.



5. Calculate the area of the rectangle formed by connecting the points $(-2, 3), (3, 3), (3, -4)$ and $(-2, -4)$ on a Cartesian plane.

6. **MC** Identify which of the following points is located in the second quadrant.
A. (5, 1) **B.** (1, 5) **C.** (1, –5) **D.** (–1, –5) **E.** (–5, 1)

7. Determine the coordinates of the midpoint between (–2, 6) and (0, 2).

8. **MC** Identify the point that sits on the x-axis.
A. (1, 1) **B.** (1, 0) **C.** (3, 3) **D.** (–3, 3) **E.** (0, 1)

9. Determine the value of point P if the points (2, 5), (4, 11) and (6, P) are to be linear.

10. If the values in the following table are linear, determine the missing value.

x	2	3	5	7
y	5	9		25

11. **MC** Select which of the following points form a linear pattern when plotted.
A. (0, 2), (2, 4), (3, 6) **B.** (–1, 0), (–3, 4), (–4, 6) **C.** (–1, 1), (1, 1), (2, 2)
D. (3, 3), (4, –4), (5, 5) **E.** (0, 0), (–1, –2), (3, 4)


Use the following information to answer questions **12** and **13**.

Teo plants a fast-growing hedge. The plant starts at a height of 45 cm, and for each of the next three weeks he measures the height to be 51 cm, 57 cm and 63 cm.


12. Explain whether the hedge is following a linear growth pattern.

13. If H represents the height of the hedge after x weeks, determine the equation that models the height of the plants.

14. **MC** Select which of the statements is true about the graph shown.
A. Claire is the oldest.
B. Heidi is the tallest.
C. Jodie is the tallest.
D. Claire is the tallest.
E. Sharon is the shortest.



15. The graph shows the distance Frankie is from his school.
Identify which section shows the period when Frankie is travelling fastest towards school.



11.2 The Cartesian plane

LEARNING INTENTION


At the end of this subtopic you should be able to:


- plot points on a Cartesian plane
- identify the coordinates of points on a Cartesian plane.

11.2.1 The Cartesian plane

eles-4635

- The **Cartesian plane** is formed from two straight, perpendicular lines called **axes**.
- The horizontal axis is referred to as the ***x*-axis**.
- The vertical axis is referred to as the ***y*-axis**.
- The point where the two axes intersect is called the **origin** and can be labelled with the letter O. The origin has the coordinate (0, 0).
- Both axes must be marked with evenly spaced ticks and numbered with an appropriate scale (usually the distance between each tick is one unit).
- The x-axis must be labelled with an x at the far right of the horizontal axis and the y-axis must be labelled with a y at the top of the vertical axis.
- A **Cartesian coordinate** is a pair of numbers, written in brackets and separated by a comma, which gives the position of a point on the plane.
- In a coordinate, the first number is the x-coordinate and shows how far right (or left) from the origin a point is located. The second number is the y-coordinate and shows how far up (or down) from the origin a point is located.





Cartesian coordinates

A Cartesian coordinate is written in the form: (x, y).

The Cartesian coordinate (2, 3) can be located by moving two units right from the origin and then three units up.

WORKED EXAMPLE 1 Creating a Cartesian plane and plotting points

Draw a Cartesian plane with axes extending from 0 to 6 units. Mark the following points with a dot, and label them.

a. (2, 4) **b.** (5, 0) **c.** (0, 2) **d.** $\left(3\frac{1}{2}, 2\right)$

THINK

First rule and label the axes.

a. (2, 4) means starting at the origin, go across 2 units, and then up 4 units.


b. (5, 0) means go across 5 units and up 0 units. It lies on the x-axis.

c. (0, 2) means go across 0 units and up 2 units. It lies on the y-axis.

d. $\left(3\frac{1}{2}, 1\right)$ means go across $3\frac{1}{2}$ units and up 1 unit.


Label each point.

DRAW



WORKED EXAMPLE 2 Determining the coordinates of points on the Cartesian plane

Identify the Cartesian coordinates for each of the points A, B, C and D.




THINK	WRITE
Point A is 3 units across and 1 unit up.	A is at (3, 1)
Point B is 1 unit across and 3 units up.	B is at (1, 3)
Point C is 0 units across and 4 units up.	C is at (0, 4)
Point D is 1 unit across and $1\frac{1}{2}$ units up.	D is at $\left(1, 1\frac{1}{2}\right)$

eles-4636

11.2.2 The four quadrants of the Cartesian plane

- The axes on the Cartesian plane can extend infinitely in both directions.
- On the x-axis, the values to the left of the origin are negative.
- On the y-axis, the values below the origin are negative.
- By extending the axes in both directions, the Cartesian plane is divided into four sections called **quadrants**.
- The quadrants are numbered one to four, starting with the top right as quadrant one, then numbering in an anti-clockwise direction.



Quadrants of the Cartesian plane

- In the first quadrant, the x and y values are both **positive**.
- In the second quadrant, the x value is **negative** and the y value is **positive**.
- In the third quadrant, both the x and y values are **negative**.
- In the fourth quadrant, the x value is **positive** and the y value is **negative**.
- A point located on the y-axis has an x-coordinate of 0.
- A point located on the x-axis has a y-coordinate of 0.

WORKED EXAMPLE 3 Locating the quadrant of points on the Cartesian plane

a. Plot the following points on the Cartesian plane.

$$A(-1, 2),\ B(2, -4),\ C(0, -3),\ D(4, 0),\ E(-5, -2)$$


b. State the location of each point on the plane (that is, the quadrant, or the axis on which it sits).

THINK

a. 1. Draw a set of axes, ensuring that they are long enough to fit all the values.

2. Plot the points. The first point is one unit to the left and two units up from the origin. The second point is two units to the right and four units down from the origin (and so on).

WRITE



b. Look at the plane and state the location of each point. Remember that the quadrants are numbered in an anti-clockwise direction, starting at the top right. If the point is on the axis, specify which axis it is.

Point A is in the second quadrant.
Point B is in the fourth quadrant.
Point C is on the *y*-axis.
Point D is on the *x*-axis.
Point E is in the third quadrant.

COLLABORATIVE TASK: Alphanumeric grid references on a map

- Similar to a Cartesian plane, areas of land can be displayed by using a grid reference map, where the map is divided into squares.
- Because grid references refer to a square region rather than a point on a map, they are often called area references.
- The reference for each square on a map is given by two coordinates — a letter and a number (hence the name alphanumeric).
- Alphanumeric grid references are usually found in tourist maps, street directories or atlases.
- A map of central London with an alphanumeric grid is shown.



1. Using the map provided, give the grid reference for each of the following locations.
   a. The British Museum **b.** Westminster Abbey **c.** Cleopatra's Needle
2. Name the major feature located at each of the following grid references.
   a. D3 **b.** F4 **c.** H10
3. Suggest a disadvantage to using a map with alphanumeric grid references.
4. Investigate other ways that locations are given on maps. How do pilots navigate to specific runways in large cities around the world?
5. Discuss with your classmates other uses for alphanumeric grid references.

Resources

eWorkbook	Topic 11 Workbook (worksheets, code puzzle and project) (ewbk-1912)
Digital document	SkillSHEET Marking points on the line (doc-6588)
Interactivities	Individual pathway interactivity: The Cartesian plane (int-4384)
	The Cartesian plane (int-4136)
	Extending the axes (int-4137)

Exercise 11.2 The Cartesian plane

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 5, 8, 11, 14, 16, 19, 23	2, 6, 9, 12, 13, 17, 20, 24, 25	3, 7, 10, 15, 18, 21, 22, 26, 27

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 Draw a Cartesian plane with axes extending from 0 to 5 units. Mark the following points with a dot, and label them.

   a. (4, 3) **b.** (1, 4) **c.** (3, 3) **d.** (2, 0) **e.** (0, 4) **f.** (0, 0)


2. Draw a Cartesian plane with axes extending from 0 to 10 units. Mark the following points with a dot and label them.

   a. (4, 2) **b.** (3, 8) **c.** (9, 9) **d.** (5, 0) **e.** (7, 2) **f.** (0, 10)

3. Draw a Cartesian plane with axes extending from 0 to 20 units using a scale of 2 units for both axes. Mark the following points with a dot and label them.

   a. (12, 16) **b.** (2, 8) **c.** (18, 4) **d.** (10, 10) **e.** (6, 0) **f.** (14, 20)

4. WE2 Identify the Cartesian coordinates for each of the points A to L.



5. WE3 **a.** Plot the following points on the Cartesian plane.
   A(−1, −3), B(−2, 5), C(3, −3), D(0, −4), E(−2, −2), F(−5, 0), G(3, 1), H(3, 0), I(−4, −2), J(4, −5)
   b. State the location of each point on the plane (that is, the quadrant, or the axis it sits on).


6. a. Plot the following points on the Cartesian plane.
A $(-4, 3)$, B $(5, -7)$, C $(-5, -5)$, D $(0, -7)$, E $(-9, 0)$, F $(-2, 8)$, G $(-3, -6)$, H $(-1, 6)$, I $(2, 8)$, J $(-7, 7)$

b. State the location of each point on the plane (that is, the quadrant or the axis it sits on).


7. a. Plot the following points on the Cartesian plane.
A $(-12, 7)$, B $(-7, 1)$, C $(-10, -10)$, D $(0, 7)$, E $(-3, 0)$, F $(-13, 5)$, G $(-9, -11)$, H $(1, -9)$, I $(2, 8)$, J $(3, -3)$

b. State the location of each point on the plane (that is, the quadrant or the axis it sits on).


8. Identify the Cartesian coordinates for each of the points A to F.



9. Identify the Cartesian coordinates for each of the points A to F.



10. Identify the Cartesian coordinates for each of the points A to F.




Understanding


11. Each of the following sets of Cartesian axes (except one) has something wrong with it. From the list below, match the mistake in each diagram with one of the sentences.

A. The units are not marked evenly.
B. The *y*-axis is not vertical.
C. The axes are labelled incorrectly.
D. The units are not marked on the axes.
E. There is nothing wrong.


a.




b.




c.




d.



e.




f.



12. From the graph, write down the coordinates of 2 points that:

a. have the same x-coordinate

b. have the same y-coordinate.




13. Messages can be sent in code using a grid like the one shown in the following graph, where the letter B is represented by the coordinates (2, 1).

Use the graph to decode the answer to the following riddle:

Q: Where did they put the man who was run over by a steamroller?

A: (4, 2) (4, 3), (3, 2) (5, 3) (4, 4) (1, 4) (4, 2) (5, 4) (1, 1) (2, 3), (4, 2) (4, 3), (3, 5) (1, 1) (3, 4) (4, 1) (4, 4) (4, 4) (4, 2) (4, 5), (4, 4) (5, 1) (2, 5) (5, 1) (4, 3), (5, 1) (4, 2) (2, 2) (3, 2) (5, 4), (1, 1) (4, 3) (4, 1), (4, 3) (4, 2) (4, 3) (5, 1)

The commas outside the brackets in the above indicate separate words. Do not use the commas in your answer; use spaces between your decoded words.



14. Rule a Cartesian plane with both axes extending from 0 to 10 units. Plot the following points and join them in the order given to make a geometric figure. Name each shape.

a. $(2, 2) - (5, 2) - (2, 6) - (2, 2)$

b. $(4, 4) - (8, 4) - (6, 8) - (4, 4)$

c. $(1, 1) - (10, 1) - (8, 9) - (2, 9) - (1, 1)$

d. $(0, 0) - (8, 0) - (10, 10) - (2, 10) - (0, 0)$

15. Here is an exercise that may require extra care and concentration. On graph paper or in your exercise book rule a pair of Cartesian axes. The x-axis must go from 0 to 26 and the y-axis from 0 to 24. Plot the following points and join them in the order given.

$(0, 15) - (4, 17) - (9, 22) - (10, 21) - (12, 24) - (16, 22) - (15, 21) - (18, 19) - (20, 24) - (22, 18) - (26, 12)$

$-(26, 10) - (23, 4) - (20, 3) - (18, 4) - (14, 7) - (11, 7) - (4, 6) - (2, 7) - \left(2\frac{1}{2}, 8\right) - (0, 15)$

Complete the picture by joining $(19, 2) - (21, 2) - (20, 0) - (19, 2)$.

16. Consider a rectangle formed by connecting the points (3, 2), (9, 2), (9, 5) and (3, 5) on a Cartesian plane. Calculate:

a. the area of the rectangle

b. the perimeter of the rectangle.

17. Consider the following set of points:

$A(2, 5), B(-4, -12), C(3, -7), D(0, -2), E(-10, 0), F(0, 0), G(-8, 15), H(-9, -24), I(18, -18), J(24, 0)$.

Identify which of the following statements are true.

a. Points A and J are in the first quadrant.

b. Points B and H are in the third quadrant.

c. Only point I is in the fourth quadrant.


d. Only one point is in the second quadrant.

e. Point F is at the origin.

f. Point J is not on the same axis as point E.

g. Point D is two units to the left of point F.


18. Consider the following triangle ABC.



- **a.** State the coordinates of the vertices of the triangle ABC.
- **b.** Calculate the area of the triangle.
- **c.** Reflect the triangle in the x-axis. (You need to copy it into your workbook first.) What are the new coordinates of the vertices?
- **d.** Now reflect the triangle you have obtained in part **c** in the y-axis, and state the new coordinates of the vertices.

Reasoning

19. Consider the square ABCD shown.



- **a.** State the coordinates of the vertices of the square ABCD.
- **b.** Calculate the area of the square ABCD.
- **c.** Extend sides AB and CD three squares to the right and three squares to the left.
- **d.** Calculate the area of the new shape.
- **e.** Extend sides AD and BC three squares up and three squares down.
- **f.** Calculate the area of the new shape.
- **g.** Compare the three areas calculated in parts **b**, **d** and **f**. Explain the changes of area in relation to the change in side length.

20. a. Explain what would happen to a shape in quadrant 3 if it was reflected in:

i. the x-axis **ii.** the y-axis.

b. Explain what would happen to a shape in quadrant 4 if it was reflected in:

i. the x-axis **ii.** the y-axis.

c. Write a rule about reflections:

i. in the x-axis **ii.** in the y-axis.

21. a. Determine the coordinate of the point that lies in the middle of the following pairs of points:

i. (2, 6) and (4, 10) **ii.** (9, 3) and (3, 1)
iii. (−7, 4) and (−1, −6) **iv.** (−2, −3) and (8, −7)

b. Write a rule that could be used to find the middle of the points (a, b) and (m, n).

22. (x, y) is a point that lies somewhere on the Cartesian plane. State which quadrant/s the point could be located in, given the following conditions:

a. $x < 0$ **b.** $y > 0$ **c.** $x < 0$ and $y < 0$ **d.** $x > 0$ and $y < 0$

Problem solving

23. A line AB passes through points A(−5, 6) and B(3, 6).

- **a.** Draw line AB on a number plane.
- **b.** Determine the length of AB.
- **c.** Determine the coordinates of the middle point of the line interval AB.
- **d.** Draw another horizontal line and determine the coordinates of the middle point.
- **e.** Is there a formula to calculate the x-coordinate of the middle point of a horizontal line?

24. A line CD passes through points C(1, 7) and D(1, −5).

- **a.** Draw line CD on a number plane.
- **b.** Determine the length of CD.
- **c.** Determine the coordinates of the middle point of the line interval CD.
- **d.** Draw another vertical line and determine the coordinates of the middle point.
- **e.** Explain whether there is a formula to calculate the *y*-coordinate of the middle point of a vertical line.

25. Consider the die shown. If we consider the centre dot to be the origin, give a possible set of coordinates for the other four dots.



26. Consider the following set of points:
(0, 3), (2, 7), (4, 11), (6, 15), (8, 19)

- **a.** Describe the pattern that connects these points to one another.
- **b.** Write the next three points in the sequence.
- **c.** Write a rule that connects the *x*-coordinate to the *y*-coordinate for each point in this sequence.

27. Consider a circle with a radius of 5 units that has its centre as the origin.

- **a.** Identify the coordinates of the four points where the circle cuts each axis.
- **b.** By drawing this circle on the Cartesian plane, explain whether you can identify any other points with integer coordinates that lie on this circle.

11.3 Linear number patterns

LEARNING INTENTION

At the end of this subtopic you should be able to:

- construct a number pattern from a rule
- identify a rule from a number pattern
- identify a number pattern that can be used to describe a geometric sequence
- express a number pattern algebraically.

11.3.1 Describing relationships and patterns

eles-4637

- Mathematicians aim to describe relationships in the world around us. The relationships and rules they find can often be described using number patterns.
- Each number in a number pattern is called a **term**.
- Linear relationships are number patterns that increase or decrease by the same amount from one term to the next. For example, the sequence 1, 4, 7, 10, . . . increases by 3 from one term to the next, so it is a linear relationship.
- Number patterns can be described by rules. For example, the number pattern above can be described by the rule ‘start with 1 and add 3 each time’.

WORKED EXAMPLE 4 Creating a sequence from a rule

Using the rule 'start with 32 and subtract 3 each time', write the first 5 terms of the number pattern.

THINK	WRITE
1. Start with 32 and subtract 3.	$32 - 3 = 29$
2. Keep subtracting 3 from the previous answer until five numbers have been calculated.	$29 - 3 = 26$ $26 - 3 = 23$ $23 - 3 = 20$
3. Write the answer.	The first five numbers are 32, 29, 26, 23 and 20.

WORKED EXAMPLE 5 Identifying a rule from a number pattern

Consider the number pattern: 4, 8, 12, . . .
a. Describe the pattern in words.
b. Write down the next 3 terms in the pattern.

THINK	WRITE
a. 1. The next number is found by adding 4 to the previous number.	a. Next number = previous number + 4
b. 1. Add 4 each time to get the next three numbers.	b. $12 + 4 = 16$ $16 + 4 = 20$ $20 + 4 = 24$
2. Write down the next three numbers.	The next three numbers are 16, 20 and 24.

- We can also describe a number pattern in words by looking at the value of any particular term and relating it to its position in the number pattern.
- For example, we could use a table of values to show the relationship from the previous worked example.

Position in pattern	1	2	3	4	5	6
Value of term	4	8	12	16	20	24

- This number pattern can be described as 'value of term = position in pattern $\times 4$'.
- After a rule in the format for a number pattern has been identified, you can use it to find any future value in the pattern.

WORKED EXAMPLE 6 Determining the rule of a number pattern

Consider the number pattern 6, 13, 20, . . .
a. Determine the rule for the number pattern by relating the value of a term to its position in the pattern.
b. Determine the 15th term in the pattern.

THINK	WRITE
a. 1. Draw a table relating the position in the pattern to the value of the term.	
2. The value of the term is found by multiplying the position in the pattern by 7 and subtracting 1.	Value of term = position in pattern $\times$ 7 − 1

Position in pattern	1	2	3
Value of term	6	13	20

b. 1.	Substitute the position in the pattern into the formula and evaluate.	Value of term $= 15 \times 7 - 1$ $= 104$
2.	Write the answer.	The 15th term in the pattern is 104.

- When the terms in a number pattern are decreasing, the rule can be described by subtracting a multiple of the position in the pattern from a fixed number. For example, the number pattern 31, 25, 19, ... can be described by 'value of term = 37 – position in pattern × 6'.
- If you are given an algebraic expression, you can generate a number pattern by substituting values into the expression.

WORKED EXAMPLE 7 Calculating terms in a number pattern


The algebraic expression $x - 3$ can be used to generate a number pattern, where x represents the position in the pattern. Using the expression, calculate:
a. the first five terms of the number pattern
b. the 10th term of the number pattern
c. the 100th term of the number pattern.

THINK		WRITE
a. 1.	Write the expression.	**a.** $x - 3$
2.	Substitute $x = 1$, 2, 3, 4 and 5 into the expression for the first five tems.	When $x = 1$ $x - 3 = 1 - 3$ $= 2$ When $x = 2$ $x - 3 = 2 - 3$ $= -1$ When $x = 3$ $x - 3 = 3 - 3$ $= 0$ When $x = 4$ $x - 3 = 4 - 3$ $= 1$ When $x = 5$ $x - 3 = 5 - 3$ $= 2$
3.	Write the answer.	The first five terms of the number pattern are -2, -1, 0, 1 and 2.
b. 1.	Write the expression.	**b.** $x - 3$
2.	Substitute $x = 10$ into the expression.	When $x = 10$ $x - 3 = 10 - 3$ $= 7$
3.	Write the answer.	The 10th term of the number pattern is 7.
c. 1.	Write the expression.	**c.** $x - 3$
2.	Substitute $x = 100$ into the expression.	When $x = 100$ $x - 3 = 100 - 3$ $= 97$
3.	Write the answer.	The 100th term of the number pattern is 97.

eles-4638

11.3.2 Geometric patterns


- We can often find number patterns when we look at geometric shapes.
- For example, looking at the number of matchsticks in each set of triangles, we can see patterns by investigating the changes from one shape to the next.
- By using a table of values, we can see a number pattern developing.
- The pattern in the final column is 3, 6, 9, . . . and we can see that the rule here is 'next number = previous number + 3'.
- We can also look for a relationship between the number of triangles and the number of matchsticks in each shape. If you examine the table, you will see that a relationship can be found. The relationship can be described by the rule: number of matchsticks = 3 × numbers of triangles.



Number of triangles	Number of matchsticks
1	3
2	6
3	9
4	12
5	15
6	18

WORKED EXAMPLE 8 Geometric number patterns

Consider a set of hexagons constructed according to the following pattern.



a. Using matches, pencils or similar objects, construct these figures, then draw the next two figures in the series.
b. Draw a table showing the relationship between the number of hexagons in the figure and the number of matches used to construct the figure.
c. Devise a rule to describe the number of matches required for each figure in terms of the number of hexagons in the figure.
d. Use your rule to determine the number of matches required to make a figure consisting of 15 hexagons.

THINK

a. Construct the given figures with matches, then draw the next two figures.


b. Draw a table showing the number of matches needed for each figure in terms of the number of hexagons. Fill it in by looking at the figures.

c. 1. Look at the pattern in the number of matches going from one figure to the next. It is increasing by 5 each time.

2. If we take the number of hexagons and multiply this number by 5, it does not give us the number of matches. However, if we add 1 to this number, it does give us the number of matches in each shape.

WRITE

a. The next two figures are:



b.

Number of hexagons	1	2	3	4	5
Number of matches	6	11	16	21	26

c. The number of matches increased by 5 in going from one figure to the next.

Number of matches = number of hexagons × 5 + 1

d. 1. Use the rule to find the number of matches to make a figure with 15 hexagons.

2. Write the answer.

d. Number of matches for 15 hexagons $= 15 \times 5 + 1$
$= 76$

76 matches would be required to construct a figure consisting of 15 hexagons.


eles-4639

11.3.3 Using algebra to describe patterns

- Once a pattern has been identified, we can use algebra to describe it.
- If we let $n =$ the number of matches and $h =$ the number of hexagons from the pattern in the previous worked example, the equation $n = 5h + 1$ would describe this pattern.

WORKED EXAMPLE 9 Using algebra to describe patterns

Consider the set of shapes constructed according to the following pattern.



a. Draw a table of values showing the number of matches needed for each figure in the pattern.
b. Express the relationship between the number of matches (n) and the number of squares (s) in the pattern as an algebraic equation.

THINK

a. Look at the figures in the pattern to complete a table of values.

b. 1. Look at the pattern in the number of matches going from one figure to the next. It is increasing by 3 each time.

2. If we take the number of squares and multiply this number by 3, it does not give us the number of matches. However, if we add 1 to this number, it does give us the number of matches in each shape.

3. Replace 'number of matches' with 'n' and 'number of squares' with 's' to create your algebraic equation, then simplify by removing the multiplication sign.

WRITE

a.

Number of squares	1	2	3
Number of matches	4	7	10

b. The number of matches increased by 3 in going from one figure to the next.

Number of matches = number of squares $\times$ 3 + 1

$n = s \times 3 + 1$
$n = 3s + 1$

on Resources

eWorkbook	Topic 11 Workbook (worksheets, code puzzle and project) (ewbk-1912)
Digital documents	SkillSHEET Number patterns (doc-6978) SkillSHEET Using tables to show number patterns (doc-6979) SkillSHEET Describing a number pattern from a table (doc-6980)
Interactivities	Individual pathway interactivity: Identifying patterns (int-4446) Identifying patterns (int-3801) Geometric patterns (int-3802)

Exercise 11.3 Linear number patterns

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 8, 12, 14, 17	2, 4, 7, 9, 13, 15, 18, 19	5, 10, 11, 16, 20, 21, 22

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE4 Using the following rules, write down the first five terms of the number patterns.
   a. Start with 1 and add 4 each time.
   b. Start with 5 and add 9 each time.
2. Using the following rules, write down the first five terms of the number patterns.
   a. Start with 50 and subtract 8 each time.
   b. Start with 64 and subtract 11 each time.
3. Write down the next three terms for the following number patterns.
   a. 2, 4, 6, 8, ...
   b. 3, 8, 13, 18, ...
4. WE5 Consider the number pattern 27, 24, 21, 18, ...
   a. Describe the pattern in words.
   b. Write down the next three terms in the pattern.
5. Consider the number pattern 48, 41, 34, 27, ...
   a. Describe the pattern in words.
   b. Write down the next three terms in the pattern.
6. Fill in the missing numbers in the following number patterns.
   a. 3, ___, 9, 12, ___, ___
   b. 8, ___, ___, 14, ___
   c. 4, 8, ___, 32, ___
7. Fill in the missing numbers in the following number patterns.
   a. ___, ___, 13, 15, ___
   b. 66, 77, ___, 99, ___, 121
   c. 100, ___, ___, 85, 80, ___
8. WE6 Consider the number pattern 5, 15, 25, ...
   a. Determine the rule for the number pattern by relating the value of a term to its position in the number pattern.
   b. Calculate the 15th term in the pattern.
9. Consider the number pattern 44, 41, 38, ...
   a. Determine the rule for the number pattern by relating the value of a term to its position in the number pattern.
   b. Calculate the 15th term in the pattern.
10. Consider the number pattern 102, 108, 114, ...
    a. Determine the rule for the number pattern by relating the value of a term to its position in the number pattern.
    b. Calculate the 35th term in the pattern.
11. Consider the number pattern 212, 199, 186, ...
    a. Determine the rule for the number pattern by relating the value of a term to its position in the number pattern.
    b. Calculate the 23rd term in the pattern.

Understanding

12. WE7 The algebraic expression $x + 4$ is used to generate a number pattern, where x represents the position in the pattern.

- **a.** Generate the first five terms of the number pattern.
- **b.** Determine the 10th term of the number pattern.
- **c.** Determine the 100th term of the number pattern.

13. A number pattern is given by the algebraic expression $2x - 2$, where x represents the position in the pattern.

- **a.** Generate the first five terms of the number pattern.
- **b.** Generate the 20th term of the number pattern.
- **c.** Generate the 77th term of the number pattern.

Reasoning

14. Explain why it is more useful to describe a number pattern in terms of relating the value of a term to its position in the pattern than to describe a number pattern by the rule between terms.

15. Are all patterns that you can describe by written descriptions also describable using algebraic symbols? Explain your answer.

16. Explain why it is useful to describe the rule for a pattern by drawing a table and looking for the connection between the top row and the bottom row of the table.


Problem solving

17. WE8 **a.** Construct the following figures using matches, then draw the next two figures in the pattern.




- **b.** Draw a table showing the relationship between the number of shapes in each figure and the number of matchsticks used to construct it.
- **c.** Devise a rule that describes the pattern relating the number of shapes in each figure and the number of matchsticks required to construct it.
- **d.** Use your rule to calculate the number of matchsticks required to construct a figure made up of 7 such shapes.

18. **a.** Construct the following figures using matches, then draw the next two figures in the pattern.



- **b.** Draw a table showing the relationship between the number of shapes in each figure and the number of matchsticks used to construct it.
- **c.** Devise a rule that describes the pattern relating the number of shapes in each figure and the number of matchsticks required to construct it.
- **d.** Use your rule to calculate the number of matchsticks required to construct a figure made up of 7 such shapes.

19. WE9 **a.** For the geometric pattern shown, draw a table of values showing the relationship between the number of shapes in each figure and the number of matchsticks used to construct it.



b. Express the relationship between the number of matches (m) and the number of shapes (n) in the pattern as an algebraic equation.

20. a. Construct the following figures using matches, then draw the next two figures in the pattern.



b. Draw a table showing the relationship between the number of shapes in each figure and the number of matchsticks used to construct it.

c. Devise a rule that describes the pattern relating the number of shapes in each figure and the number of matchsticks required to construct it.

d. Use your rule to calculate the number of matchsticks required to construct a figure made up of 7 such shapes.

21. a. For the geometric pattern shown, draw a table of values showing the relationship between the number of shapes in each figure and the number of matchsticks used to construct it.



b. Express the relationship between the number of matches (m) and the number of shapes (n) in the pattern as an algebraic equation.

22. Create a matchstick pattern that can be represented by the rule $m = 5n + 3$.

11.4 Plotting simple linear relationships

LEARNING INTENTION

At the end of this subtopic you should be able to:

- plot a simple linear relationship from a table of values
- identify whether a series of points forms a linear relationship.

11.4.1 Plotting simple linear relationships

eles-4640

- When a set of points is plotted on the Cartesian plane, a pattern may be formed. If a pattern forms a straight line, we call it a *linear pattern*. If the pattern forms a curve, we call it a *non-linear pattern*.
- The coordinates of the points that form a pattern can be presented in a table of values or as a set of points (as shown in the following table).

- If shown in a table, the coordinates of each point should be read 'in columns'; the top number in each column gives the x-coordinate and the bottom number gives the corresponding y-coordinate of the point.

x	0	1	2	3
y	8	6	4	2

(0, 8), (1, 6), (2, 4), (3, 2)

- The Cartesian coordinates of the points are ordered pairs. That is, the first number always represents the x-coordinate of a point and the second always represents the y-coordinate. A set of ordered pairs forms a relationship between x and y.
- If the points form a linear pattern when plotted, we say that the relation between x and y is linear.


WORKED EXAMPLE 10 Plotting a set of points to observe a pattern

Plot the following set of points on the Cartesian plane, and comment on any pattern formed.
(1, 3), (2, 4), (3, 5), (4, 6), (5, 7)

THINK

1. Look at the coordinates of the points in the set: the x-values range between 1 and 5, while the y-values range between 3 and 7. Draw a set of axes, ensuring they are long enough to fit all the values.
2. Plot the points.
3. Comment on the pattern that the points form.

WRITE



The points form a linear pattern.

WORKED EXAMPLE 11 Plotting points presented in a table of values


Plot the following points on a Cartesian plane and decide whether the relationship is linear.

x	0	1	2	3	4
y	8	7	6	5	4

THINK

1. The x-values range from 0 to 4; the y-values range from 4 to 8. Draw a set of axes that will include all these values. (The axes need not be the same length. In this case you can extend the y-axis a bit more than the x-axis, as the y-values are higher.)
2. The entries in the table can be rewritten as a set of points. The top number in each column gives the x-coordinate of the point and the bottom number gives the corresponding y-coordinate. Thus the first column gives the point (0, 8), the second (1, 7), and so on. Plot all points.

WRITE



3. Consider the pattern formed by the points. It is a straight line. Draw a suitable conclusion about the relationship between x and y.

The relationship between x and y is linear.

WORKED EXAMPLE 12 Constructing a table of values from a rule

Consider the relationship between x and y given by the rule $y = 3x - 4$.
a. Describe the set of points produced by this relationship between x and y.
b. Construct a table of values for the integers $-2 \leq x \leq 2$

THINK

a. When a rule is written in this form, it means that each y-coordinate must be found from a corresponding x-coordinate. In this case the y-value is four less than three times the x-value.

b. 1. The interval $-2 \leq x \leq 2$ represents the following x-coordinates:
$x = -2, -1, 0, 1, 2$

For each x-coordinate, calculate the corresponding y-coordinate.

2. Place this information into a table of values.

WRITE

a. The rule describes a set of points such that the y-coordinate of each point is four less than three times the value of the x-coordinate.

b. $y = 3 \times -2 - 4 = -10$
$y = 3 \times -1 - 4 = -7$
$y = 3 \times 0 - 4 = -4$
$y = 3 \times 1 - 4 = -1$
$y = 3 \times 2 - 4 = 2$

x	–2	–1	0	1	2
y	–10	–7	–4	–1	2

Digital technology

Scientific calculators have the ability to create a table of values.


Start by typing the rule for the relationship between x and y by pressing the table button then the x button for the equation itself.








Once the rule is typed in, press Enter. You will be able to change some settings.




Start = 0 means the first value of x is 0.

Step = 1 means that the table counts up in single units (ones).



Selecting **Auto** will generate the table.



Selecting **Ask-*x*** will let you choose your own values of x and allow you to generate your own unique table.



on Resources

eWorkbook	Topic 11 Workbook (worksheets, code puzzle and project) (ewbk-1912)
Digital documents	SkillSHEET Drawing scales (doc-6589) SkillSHEET Substituting values into the rule (doc-6590) SkillSHEET Finding patterns (doc-6591) SkillSHEET Establishing patterns connecting two numbers (doc-6592)
Interactivities	Individual pathway interactivity: Plotting simple linear relationships (int-4385) Plotting simple linear relationships (int-4138)

Exercise 11.4 Plotting simple linear relationships

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 12, 15	2, 5, 8, 9, 13, 16	3, 6, 11, 14, 17, 18

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE10 Plot the following sets of points on the Cartesian plane, and comment on any pattern formed.

a. $(0, 1), (1, 2), (2, 3), (3, 4), (4, 5)$
b. $(0, 3), (1, 4), (2, 5), (3, 6), (4, 7)$
c. $(2, 2), (3, 3), (4, 4), (5, 5), (6, 6)$
d. $(0, 2), (1, 3), (2, 1), (3, 0), (4, 5)$
e. $(1, 10), (2, 8), (3, 6), (4, 4), (5, 2)$
f. $(2, 3), (3, 3), (4, 3), (5, 3), (6, 3)$

2. Plot the following sets of points on the Cartesian plane. (Note that some coordinates are negative, so you will need to use all four quadrants.) Comment on any pattern formed.

a. $(-2, 0), (-1, 2), (0, 4), (1, 6), (2, 8)$
b. $(-3, -3), (-2, 0), (-1, 3), (0, 6), (1, 9)$
c. $(-2, 7), (-1, 6), (0, 4), (1, 3), (2, 1)$
d. $(-6, 8), (-5, 6), (-4, 4), (-3, 2), (-2, 0)$

3. Plot the following sets of points on the Cartesian plane. Comment on any pattern formed.

a. $(-3, 8), (-1, 5), (1, 2), (3, -1), (5, -4)$
b. $(-5, 0), (-5, 5), (-5, 3), (-5, -2), (-5, -4)$
c. $(-4, 4), (-1, 3), (2, 1), (5, -3), (8, -11)$
d. $(7, 8), (1, -2), (-2, -7), (4, 3), (10, 13)$

4. WE11 Plot the points in each table on a Cartesian plane, and decide whether or not the relationship is linear.

a.

x	0	1	2	3	4
y	3	4	5	6	7

b.

x	0	1	2	3	4
y	0	1	4	9	16

c.

x	1	2	3	4	5
y	7	6	5	4	3

d.

x	1	2	3	4	6
y	12	6	4	3	2

e.

x	0	1	2	3	4
y	0	3	6	9	12

f.

x	2	3	4	5	6
y	0	−2	−4	−6	−8

5. Plot the points in each table on a Cartesian plane and decide whether the relationship is linear or not.

a.

x	0	1	2	3	4
y	1	4	7	10	13

b.

x	−2	−1	0	1	2
y	10	5	0	−5	−10

c.

x	0	1	2	3	4
y	−1	0	2	6	14

d.

x	−3	−2	−1	0	1
y	10	−8	6	−4	2

6. Plot the points in each table on a Cartesian plane, and decide whether or not the relationship is linear.

a.

x	0	1	2	3	4
y	8	5	2	−1	−4

b.

x	−2	−1	0	1	2
y	5	3	1	−1	−3

c.

x	0	1	2	3	4
y	−2	4	−6	8	−10

d.

x	−2	−1	0	1	2
y	8	7	4	−1	−8

Understanding

7. **a.** Plot the following points on the set of axes: (0, 10), (1, 8), (2, 6), (3, 4).
b. Describe the pattern formed by the points.
c. Extend the pattern by plotting the next two points.
d. State the coordinates of the two points you have plotted.

8. The points in the following table form a linear pattern. The y-coordinate of the middle point is missing.


x	1	2	3	4	5
y	0	3		9	12

a. Plot the four points (whose x- and y-coordinates are both known) on the Cartesian plane.
b. Use your graph to predict the missing y-coordinate of the middle point.
c. Add the middle point to your graph and check whether it fits the pattern.

9. Which of the following sets of points, when plotted, will form a linear pattern?

a. (0, 3), (1, 5), (2, 7), (3, 9), (4, 11)
b. (−1, 8), (−2, 7), (−3, 6), (−4, 5), (−5, 4)
c. (1, 6), (2, 5), (3, 7), (4, 8), (5, 9)
d. (2, 3), (3, 5), (4, 7), (5, 9), (6, 11)
e. (0, 2), (1, 4), (2, 4), (3, 5), (4, 6)
f. (10, 7), (9, 4), (8, 3), (7, 1), (6, 0)

10. Consider the linear pattern shown.



- **a.** If the pattern is continued to the right, identify the coordinates of the next point.
- **b.** If the pattern is extended to the left, identify the coordinates of the previous point.

11. Rachel planted a cherry tomato plant in her vegetable patch. She measured the height of her plant every week for four consecutive weeks, obtaining the following data: 20 mm, 24 mm, 28 mm, 32 mm. Rachel forgot to measure her plant in week 5, but the following week she found the height of the cherry tomato to be 40 mm.



- **a.** Fill in the table of values below.

Week						
Height (mm)						

- **b.** Plot the heights of the cherry tomato plant on a set of axes.
- **c.** Explain whether the relationship between the number of the week and the height of the plant is linear.
- **d.** Assuming the pattern was the same for the first 6 weeks, determine the height of the tomato plant in week 5.
- **e.** If the pattern continues, predict the height of the cherry tomato plant in week 8.

Reasoning

12. WE12 The relationship between the two variables x and y is described by the rule $y = x + 3$.

- **a.** Complete the following statement: 'The rule describes a set of points such that the y-coordinate of each point is …'
- **b.** Construct a table of values for whole numbers $-2 \leq x \leq 2$ using the given rule.
- **c.** Plot the points on a set of axes.
- **d.** Is the relationship linear? Justify your answer.

13. The relationship between the two variables x and y is described by the rule $y = 2x - 3$.

- **a.** Complete the following statement: 'The rule describes a set of points such that the y-coordinate of each point is three less than …'
- **b.** Construct a table of values for whole numbers $-2 \leq x \leq 2$ using the given rule.
- **c.** Plot the points from the table on a set of axes.
- **d.** Is the relationship linear? Justify your answer.
- **e.** The x-values of the relationship form the *domain* of that relationship, while the y-values form its *range*. The domain of the given relationship is $-2 \leq x \leq 2$. Identify the range.

14.
- **a.** On the same set of axes, plot the following linear relationships: $y = x$, $y = 3x + 1$ and $y = 5x - 2$.
- **b.** On the same set of axes, plot the following linear relationships: $y = -x$, $y = -3x + 1$ and $y = -5x - 2$.
- **c.** Explain the differences and similarities between the two sets of graphs.

Problem solving

15. a. Use the following information to complete the table of coordinates.
Point A is two units to the left of the origin and five units below the origin.
Point B is one unit to the left of the origin and two units above point A.
Point C is one unit below the origin on the vertical axis.
Point D is one unit to the right of C and two units above point C.
Point E is two units to the right of the *y*-axis and three points above the *x*-axis.

x					
y					
	A	B	C	D	E

b. Plot these points on a Cartesian plane.
c. Determine the value of the horizontal step between two adjacent points.
d. Is the relationship linear? Explain your answer.

16. The table of values shown displays the relationship between time, in minutes, and parking fee, in dollars.

Time, minutes	30	60	90	120	
Parking fee, $	1.20	2.40		4.80	6.00

a. Write a rule for this relationship.
b. Use the rule found in part **a** to calculate the missing values.

17. The following table of values gives the relationship between the weight of coffee beans (in kg) and the cost per kg from a wholesale distributor.

Weight (kg)	1	5		20	25
Cost per kg ($)	49.00	46.00	42.25	34.75	

a. Write a rule for this relationship.
b. Use the rule found in part **a** to calculate the missing values.
c. Joel orders a 22 kg bag of beans each week for his coffee shop. Calculate how much he has to pay the wholesaler for his coffee.
d. The biggest bag that the wholesaler produces is a 30 kg bag of coffee beans. A chain coffee store orders a number of these bags each week. If the total cost of their order was $5722.50, determine the weight of coffee beans that was ordered.



18. Each row in my classroom has the same number of desks, and the rows are straight. My desk is fourth from the front and fourth from the back. It has one desk to its left and two desks to its right. Determine how many desks are in the classroom.

11.5 Interpreting graphs

LEARNING INTENTION


At the end of this subtopic you should be able to:

- interpret information present on a Cartesian plane
- identify the domain of a set of points or line graph
- identify the range of a set of points or line graph
- read a travel graph and calculate average speed.


11.5.1 Interpreting graphs

eles-4641

- As graphs are found in many areas of daily life, it is important to be able to interpret graphs by considering the following points:
  - Look at the overall picture. Where are the points situated? Does the line go up from left to right (an increasing trend) or go down from left to right (a decreasing trend)?
  - Look at what the horizontal and vertical axes represent, the values shown on the scale (if any) and their units of measurement.
  - Note that the values increase as you move up the vertical axis and move to the right along the horizontal axis.
- A scatter plot graph shows individual points of information only. A line graph can show how the information changes.



Scatter plot




Line graph

WORKED EXAMPLE 13 Interpreting a scatter plot

Use the graph shown to answer the following questions about Brendan and Kelly.

a. Identify who is taller, Brendan or Kelly.

b. Identify who is younger.



THINK

a. Height is on the vertical axis. Kelly is above Brendan, so Kelly is taller.

b. The horizontal axis shows age. Brendan is to the left of Kelly, so Brendan is younger.


WRITE

a. Kelly is taller.

b. Brendan is younger.

WORKED EXAMPLE 14 Interpreting a line graph

This graph shows the distance Conchita is from home when she is out hiking. Describe what each straight line section of the graph shows.



THINK

1. As you move along section A, the distance is increasing and time is increasing, so Conchita is moving further away from home.
2. As you move along section B, the distance is staying the same but time is still increasing.
3. As you move along section C, the distance from home is decreasing and time is increasing.

WRITE

Section A : Conchita is walking away from home.

Section B : Conchita could be resting.

Section C : Conchita is walking towards home.


WORKED EXAMPLE 15 Comparing line graphs

This graph shows the average maximum and minimum monthly temperatures for Sydney. Use the graph to answer the following questions.

a. Identify which month was the hottest and its average maximum temperature.

b. Identify which month was the coldest and its average minimum temperature.

c. Identify which months had an average minimum temperature of 12 °C.



THINK

a. Temperature is on the vertical axis and months are on the horizontal axis. We can read the hottest month and highest temperature from the graph.

b. We can read the coldest month and lowest temperature from the graph.

c. We can read the average minimum temperature of 12 °C from the vertical axis.

WRITE

a. Hottest month is January and the average maximum temperature is 26 °C.

b. Coldest month is July and the average minimum temperature is 7 °C.

c. Average minimum temperature of 12 °C was in May and October.

eles-4642

11.5.2 Domain and range

- For any relationship between x and y, the **domain** is the set of all x-coordinates and the **range** is the set of all y-coordinates.
- For a collection of points, domain and range can be represented as a set of numbers.
- For a line segment, the domain and range can be represented as an interval between two values.
- Domain and range are always given in ascending order (lowest value to highest value).

Set of points

$(1, 2), (3, 6), (-4, -8), (0, 0), (-5, -10)$

Domain: $\{-5, -4, 0, 1, 3\}$
Range: $\{-10, -8, 0, 2, 6\}$

Table of values

x	-2	-1	0	1	2	3
y	-5	-2	1	4	7	10

Domain: $\{-2, -1, 0, 1, 2, 3\}$
Range: $\{-5, -2, 1, 4, 7, 10\}$

WORKED EXAMPLE 16 Finding domain and range


State the domain and range for the following:

a. $(1, 2), (5, -6), (7, 4), (-3, 3), (0, -5), (2, 4)$

b.

x	-3	-1	0	2	4
y	6	2	0	-4	-8

c.



THINK

a. The domain is a list of all x-coordinates in the set of points and the range is a list of all y-coordinates in the set. The domain and range must be listed from lowest values to highest.

The range has one less value as the number 4 appears twice as a y-coordinate and we only need to list it once when stating the range.

b. We can get the domain and range directly from the table. Remember to order the range in ascending order

c. Since this is a continuous line, the domain and range include every possible value between the lowest and highest value. This means we need to use an interval to represent domain and range.

WRITE

a. Domain $= \{-3, 0, 1, 2, 5, 7\}$
Range $= \{-6, -5, 2, 3, 4\}$

b. Domain $= \{-3, 1, 0, 2, 4\}$
Range $= \{-8, -4, 0, 2, 6\}$

c. Domain $= 2 \leq x \leq 13$
Range $= 20 \leq y \leq 50$

11.5.3 Travel graphs


eles-4643

- A **travel graph** is a special type of line graph.
- A travel graph is used to represent a journey. Time is shown on the horizontal axis and distance is shown on the vertical axis. The following graph is an example of a travel graph, including all of the information this type of graph can show.
- This graph shows information about Enrico's trip on his scooter. Some of the information we can find out from the graph is already shown.

Calculating average speed

The average speed of a journey can be calculated using the formula:

$$\text{average speed} = \frac{\text{total distance travelled}}{\text{total time taken}}$$




WORKED EXAMPLE 17 Interpreting a travel graph

The following travel graph shows Todd's afternoon out.

a. Identify how far Todd was from home when he stopped for one hour.

b. Calculate how far Todd travelled overall.

c. Calculate Todd's average speed for the return journey.



THINK	WRITE
a. The line on the travel graph is horizontal for one hour from 3 pm indicating that no distance was covered in that time. On the y-axis the distance from home at 3 pm was 60 km.	**a.** Todd was 60 km from home when he stopped for one hour.
b. The outward journey and return journey are both 100 km.	**b.** Overall, Todd travelled $100 + 100$ km $= 200$ km
c. Todd's 200 km trip took from 2 pm to 6 pm, which is 4 hours overall. Divide the distance travelled by the time taken to calculate Todd's average speed.	**c.** Speed $= \frac{\text{Distance}}{\text{Time}}$ $= \frac{200}{4}$ $= 50$ Todd's average speed was 50 km/h.

Resources

eWorkbook Topic 11 Workbook (worksheets, code puzzle and project) (ewbk-1912)

Interactivities Individual pathway interactivity: Interpreting graphs (int-4386)
Interpreting graphs (int-4139)

Exercise 11.5 Interpreting graphs

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 7, 10, 14, 17, 22, 25, 28	3, 6, 8, 11, 13, 15, 18, 20, 23, 27, 29	4, 9, 12, 16, 19, 21, 24, 26, 30

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE13 Use the following graph to answer the questions about Lucas and Selina.

a. Identify who is taller.


b. Identify who is younger.






2. Use the graph to answer the following questions.

a. Identify whether Yelena has a larger shoe size than Andrea.
b. Identify whether Yelena is older than Andrea.




3. Use the graph to answer the following questions.

a. Identify who is the youngest.
b. Identify who weighs the most.
c. Decide whether the oldest person is also the heaviest.




4. Use the graph to answer the following questions.

a. Identify who is given the most pocket money.
b. Decide whether the youngest person is given the least amount of pocket money.
c. Decide whether the oldest person is given the most pocket money.



5. **WE14** The following graph shows the distance Claire is from home when she is out rockclimbing. Describe what each straight line section of the graph is showing.




Understanding

6. **a.** Use the graph to answer these questions.


i. Identify who weighs the most.
ii. Identify who is the tallest.
iii. Decide whether the shortest person weighs the least.

b. Copy this graph and plot the height and weight of Georgia, who is taller than Linh and weighs less than Hannah but more than James.




7. **MC** Select which of the following is shown by this graph.

A. Myfanwy is the lightest and youngest.
B. Tania is the oldest.
C. Myfanwy is older than Louise and younger than Tania.
D. Tania and Louise are the same age.
E. Louise weighs the least.




8. MC Select which of the following is shown by this graph.



A. Jack is the tallest.
B. Chris is the oldest.
C. Darren and Chris are the same age.
D. Tim is the tallest.
E. Darren is the same height as Chris.

9. The graph below shows Thomas's head circumference for the first 12 weeks after birth.


a. Explain why the graph doesn't start at zero.
b. Describe the change in Thomas's head circumference during the first 12 weeks.
c. Suggest what the graph would look like beyond the first 12 weeks.






10. The graph shows Monique's journey as she walks to school.

a. Identify the section of the graph that shows when Monique is not moving.
b. The line in section C is steeper than the line in section A. Describe what this tells us about section C.
c. Identify where Monique is at the end of section C.




11. Yupa owns an ice-cream shop. The following graph shows his profit for the first 4 months of the year.

a. Identify the month when Yupa made the most profit.
b. Identify the month when Yupa made the least profit.
c. Describe what has happened to Yupa's profit over the 4 months.



12. Copy the following axes and draw a line graph that you think would show rainfall over one year.






13. Cathy has been training hard for the 100 m sprint. She has kept a record of the fastest time she has run each week. Draw a graph that shows the following sections:
Section A: Cathy increased her speed for the 100 m sprint each week for the first 4 weeks.
Section B: After 4 weeks Cathy's speed stayed the same for the next 2 weeks.
Section C: Cathy had a cold and her speed decreased for 2 weeks.
Section D: Having recovered from her cold, Cathy trained hard and increased her speed again.




14. **WE15** The following graph shows the average rainfall and average maximum and minimum temperatures for Muswellbrook and the Upper Hunter Valley.




a. Identify which two months had the lowest average rainfall.
b. Identify the lowest average rainfall.
c. Identify which month had the lowest average minimum temperature.

15. Looking at the following graph, comment about the future for wind power in Australia and the world.



16. The following graph shows the percentage of visitors to Parks and Wildlife Group–managed parks in New South Wales for 3 years.



a. For the 25–34 age group, identify which year had the lowest percentage of visits.
b. Identify which age group visited the parks more frequently than any other group.
c. Suggest a reason why this age group visited the parks more often.

17. **WE 16** State the domain and range of each of the following:

a. $(3, 4),\ (5, 6),\ (7, 8), (9, 10),\ (11, 12)$

b. $(8, 8),\ (7, 6),\ (6, 4), (5, 2),\ (4, 0)$

c.

x	1	2	3	4	5
y	6	2	0	−4	−8

d.

x	−4	−2	0	2	4
y	8	4	0	−4	−8

18. State the domain and range of each of the following:

a. $(1, 2),\ (2, 4),\ (3, 6), (4, 8),\ (5, 10)$

b. $(7, 2),\ (3, 5),\ (-6, 9), (-5, -2),\ (0, 1)$

c.

x	−1	−2	−3	−4	−5
y	3	6	9	12	15

d.

x	−4	−2	0	2	4
y	3	1	0	1	3

19. State the domain and range of each of the following:

a. $(1, -2),\ (-2, 4),\ (-3, 6), (4, -8),\ (-5, 10)$

b. $(2, 2),\ (3, 2),\ (-6, 4), (5, -2),\ (0, 0)$


c.

x	0	3	4	7	9
y	5	5	5	5	5

d.

x	1	2	0	2	3
y	4	6	8	1	3

20. The line graph shown compares the heights of Yasha and Yolande over a 20-year period.



a. State how tall Yasha was at age:
i. 3 **ii.** 5 **iii.** 14.

b. State how tall Yolande was at age:
i. 4 **ii.** 10 **iii.** 14.

c. State the age (or ages) at which they were the same height.

d. State Yasha's age when she was:
i. 140 cm tall **ii.** 176 cm tall.

e. Identify the range of ages when Yolande was taller than Yasha.


f. Between which two birthdays did each person grow the fastest?

21. Weekly sales of song downloads for the pop group The Mathemagics are shown in the following table.

Week	1	2	3	4	5	6	7	8
Sales	1500	2800	3750	4000	3600	3000	2400	1900


a. Construct a line graph of the data. **b.** Estimate the sales for week 9.

22. WE17 The graph shows the bike trips made by Svetlana and Sam.




a. State who left first.
b. Calculate how far Sam travelled.
c. Calculate how far Svetlana travelled.
d. State who got home first.
e. Identify who stopped, when, and for how long.
f. Calculate Sam's and Svetlana's average speeds for the full trips, correct to two decimals places where appropriate.

23. The graph at the right shows Steven's return trip from home to the Victoria Market.



- **a.** Calculate how far he travelled.
- **b.** Calculate the average speed of his trip.
- **c.** State how long he was at the market for.
- **d.** Was he driving faster on his way to the market or on his way home? Justify your answer.


24. Tom and Sarah's journey to school is shown on the graph.



- **a.** State who lives further from school.
- **b.** Identify who takes the train to school. Justify your answer.
- **c.** Calculate the average speed of each of their journeys.
- **d.** Identify the time at which they were the same distance from school.

Reasoning

25. Lisa created a line graph to illustrate the number of glass pendants she has sold for each of the last ten years. She intends to use the graph for a presentation at her bank, in order to obtain a loan.




- **a.** Identify in what year of operation she sold the most pendants. State how many she sold.
- **b.** Identify in what year of operation she sold the fewest pendants. State how many she sold.
- **c.** Describe any trend in the sales of the pendants.
- **d.** Will this trend help Lisa obtain the loan?
- **e.** State the domain and range of the graph of glass pendant sales.

26. Peter and Sonja are walking home from school. A dog started chasing them and Peter started running away from the dog. Sonja noticed that this was her neighbour's dog so she stopped to pat the dog and then started to walk towards Peter who was now waiting for her.
Draw a graph to represent the relationship between distance travelled and time for both Peter and Sonja.



27. The cost in cents of a phone call is displayed in the following graph.
Using the graph, explain the relationship between the cost and the time of a call.



Problem solving

28.

x	−4	−3	−2	−1	0	1	2	3	4
y	16	9	4	1	0	1	4	9	16

a. On a number plane plot the relationship shown in the table and connect all points with a smooth line.
b. Complete the statement: 'As the value of x increases, the value of y …'

29.

x	−3	−2	−1	0	1	2	3
y	−27	−8	−1	0	1	8	27

a. On a number plane plot the relationship shown in the table above and connect all points with a smooth line.
b. Complete the statement: 'As the value of x increases, the value of y …'

30. John competed in a long-distance endurance cycling race. The race was divided into two sections with a break in the middle. John's average speed for the first section was 44 km/hour for 3.5 hours. His break in the middle was 45 minutes and he then completed the second section in 4.25 hours at an average speed of 36 km/hour. Calculate John's average speed for the whole race. Give your answer to 2 decimal places.




11.6 Review

11.6.1 Topic summary

COORDINATES AND THE CARTESIAN PLANE


The Cartesian plane

- The Cartesian plane is made up of two straight, perpendicular lines called axes.
- The horizontal axis is called the *x*-axis.
- The vertical axis is called the *y*-axis.



Extending the axis

- Each of the axes can continue infinitely in both directions.
- On the *x*-axis, values to the left of the origin are negative.
- On the *y*-axis, values below the origin are negative.
- The Cartesian plane can be split into four quadrants:




Cartesian coordinates

- A coordinate is a pair of numbers, separated by a comma and in brackets, that specifies the location of a point: for example, (4, 2).
- The first number is the *x*-coordinate and the second is the *y*-coordinate.
- The coordinate (4, 2) represents the point found by moving 4 units to the right of the origin and then 2 units up.



Number patterns

- Geometric pattern:




- Number pattern: 6, 11, 16
- Table:


Number of shapes (*s*)	1	2	3
Number of matches (*m*)	6	11	16

- Rule: $m = 5 \times s + 1$

Linear relationships


- If a sequence of points forms a straight line when plotted, we call this a *linear relationship*.
- If the points form a line that is curved, we call this a *non-linear relationship*.


Linear relationship


Non-linear relationship

Domain and range

- The domain is the set of all *x*-coordinates covered by a series of points or a section of a line graph.
- The range is the set of all *y*-coordinates covered by a series of points or a section of a line graph.
- For the graph below, the domain is $2 \leq x \leq 13\,°C$ and the range is $20 \leq y \leq 50$ mm.



11.6.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
11.2	I can plot coordinates on a Cartesian plane.			
	I can identify the coordinates of points on a Cartesian plane.			
11.3	I can construct a number pattern from a rule.			
	I can identify a rule from a number pattern.			
	I can identify a number pattern that can be used to describe a geometric sequence.			
	I can express a number pattern algebraically.			
11.4	I can plot a simple linear relationship from a table of values.			
	I can identify whether a series of points forms a linear relationship.			
11.5	I can interpret the information presented on a Cartesian plane.			
	I can identify the domain of a set of points or line graph.			
	I can identify the range of a set of points or line graph.			
	I can read a travel graph and calculate average speed.			

11.6.3 Project

Battleships game

The goal of this two-person game is to sink all of your opponent's ships before they do the same to you.

Equipment: Each player has two 10×10 grids. The grids are labelled with letters across the top (A to J) and numbers down the side (1 to 10). One of the grids is labelled 'My grid' and the other is labelled 'Opponent's grid'.

Set-up: Each player decides where to place four ships on their 'My grid': a five-square battleship, a four-square cruiser, a three-square submarine and a two-square destroyer. All ships must be placed in straight lines either horizontally or vertically, but not diagonally. It is fine (but not required) for two or more ships to be adjacent to each other.

How to play: Players take turns taking shots at each other. A shot is taken by calling out the coordinates of a square on the 10×10 grid, such as A1 or H4. Each player takes one shot at a time. If the player calls the coordinates of a square where one of the opponent's ships is located, the opponent calls out 'Hit' and says which ship was hit; if the shot misses, the opponent says 'Miss'.

Players should mark the shots they take on their 'Opponent's grid' and whether each shot was a hit or a miss, so that they don't call any square more than once. Players should also mark their 'My grid' with shots taken by their opponent.









A ship is sunk when all of its squares have been hit. When this happens, the player whose ship was sunk says, for example, 'You sank my battleship.'

The first player to sink all of their opponent's ships wins the game.

My grid										
	A	B	C	D	E	F	G	H	I	J
1										
2										
3										
4										
5										
6										
7										
8										
9										
10										

Opponent's grid										
	A	B	C	D	E	F	G	H	I	J
1										
2										
3										
4										
5										
6										
7										
8										
9										
10										

Resources

eWorkbook Topic 11 Workbook (worksheets, code puzzle and project) (ewbk-1912)

Interactivities Crossword (int-2610)

Sudoku puzzle (int-3175)

Exercise 11.6 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. The following grid shows a simplified map that uses alphanumeric grid references.

a. Fill in the blank cells in the table.

Location	Grid reference
	B3
Alex's house	
	D1
Lena's house	

b. A playground is to be built at A3. Mark its location on the grid with an X.



2. Study the graph to answer these questions.


a. Identify the letter that represents the point (−3, 4).

b. Identify the points on the *x*–axis.

c. Name all points whose *x*–coordinate is zero.

d. Identify the points in the second quadrant. Give their coordinates.

e. State the coordinates of C and F.




3. Use the graph to answer these questions.

a. Fill in the blanks in the table.

Coordinates	Point
(0, 2)	
	C
	D

b. Mark E (4, 6) on the graph. Join all the points with a straight line.




4. The following table gives the *x* and *y* coordinates of some points.

x	0	1	2	3
y	0	2	4	6

a. Using the axes shown, plot the points given in the table and join them.

b. Explain whether the relationship between *x* and *y* is linear.



Problem solving

5. A game consists of a grid, and a dart that is thrown to land on a square of the grid.


A	B	C	D	E
F	G	H	I	J
K	L	M	N	O
P	Q	R	S	T
U	V	W	X	Y

The dart is thrown and lands on a letter that:

- has horizontal symmetry
- also has vertical symmetry
- and is not a vowel.

What are the possibilities for the landing position of the dart? Give instructions for locating any possibilities on the grid.

6. Rachel and Nathan are playing a battleship game. Rachel's grid (in progress, up to this moment) is shown below.



a. For each of the following attempts, state whether Nathan will miss (M), sink (S) or hit (H) one of Rachel's ships.

i. A7 **ii.** F9 **iii.** I10 **iv.** C3

b. Specify the location of all of Rachel's one-berth ships.


c. State the set of grid references that Nathan needs if he is to sink Rachel's largest ship.

7. Answer the following questions, then translate each letter of your answer into an ordered pair by using the grid.


a. In which Australian state is the Great Barrier Reef?

b. Which Australian state is known as the Garden State?

c. The Opera House is in which city?




8. The following diagram gives the key to a code by matching letters to coordinates. Use the key to write in code this famous statement by Descartes: 'I think, therefore I am.'



9. On a carefully ruled pair of Cartesian axes, join the following points in the order given. It reveals a symbol used by an ancient mathematical secret society.

$$(1, 0) - (6, 4) - (0, 4) - (5, 0) - (3, 6) - (1, 0)$$

10. ABCD is a square drawn in the first quadrant as shown.
Given A(0, 3) and B(4, 0) and C(7, 4), find the coordinates of D.



11. **a.** Plot the points A(3, 0), B(6, 7), C(10, 7), D(7, 0).
i. What type of quadrilateral is ABCD?
ii. Calculate its area.
b. Draw a set of axes and on them plot points so that the encompassing triangle has an area of 20 square units. List the points and show why the area is 20 square units.

12. Four points — A, B, C and D — are drawn on a Cartesian plane and are joined in order to form a square. A is the point (−4, 0), B is (1, 5) and C is (6, 0). State the coordinates of point D.


13. **a.** State the domain and range of this table.
b. Does this table represent a relationship between x and y that is linear?

x	1	2	3	4
y	1	4	9	16

Explain why or why not.


14. Consider the following statement: 'A linear relation, when plotted on a Cartesian plane, produces a straight line that cuts the x-axis at one point, and the y-axis at one point.'
Discuss whether or not this statement is true.

15. The following graph shows Anton's distance from the shore during a surf life-saving drill.



a. Describe what each section of the graph is showing.
b. The line in section A is steeper than the line in section C. Describe what this tells you about Anton's swimming speed in section A compared to his speed in section C.

16. A Year 8 student doing an exercise program recorded her pulse rate at one-minute intervals, as shown in the graph.



a. State her pulse rate after:

i. 2 minutes
ii. 4 minutes.


b. After how many minutes did her pulse rate reach its maximum?

c. After how many minutes was her pulse rate 80beats/min? Explain why there are two answers to this question.

d. State her pulse rate after $3\frac{1}{2}$ minutes.

e. Calculate for how long her pulse rate was above 80 beats/min.

17. The following line graph shows the traffic flow on a particular road on a certain day.



a. State when the traffic flow hit its peak.

b. During the period studied, state when the number of vehicles was lowest.

c. State how many cars used the road at:

i. 11.00 am
ii. 9.30 am.


d. State the times of the day when:

i. 300 cars were on the road
ii. 225 cars were on the road.

e. Discuss why a line graph is used for this information rather than a column or a sector graph.

18. The following graph shows Wilma's bike trip for an afternoon. Write a report on Wilma's trip, including the following:

- when she left home
- when she stopped and for how long
- when she arrived at Mt Cranson
- when she left to go home
- how fast she was going and why
- when she got home again.





To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1912) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0700) ☐

Digital documents

11.2 SkillSHEET Marking points on the line (doc-6588) ☐
11.3 SkillSHEET Number patterns (doc-6978) ☐
SkillSHEET Using tables to show number patterns (doc-6979) ☐
SkillSHEET Describing a number pattern from a table (doc-6980) ☐
11.4 SkillSHEET Drawing scales (doc-6589) ☐
SkillSHEET Substituting values into the rule (doc-6590) ☐
SkillSHEET Finding patterns (doc-6591) ☐
SkillSHEET Establishing patterns connecting two numbers (doc-6592) ☐

Video eLessons

11.2 The Cartesian plane (eles-4635) ☐
The four quadrants of the Cartesian plane (eles-4636) ☐
11.3 Describing relationships and patterns (eles-4637) ☐
Geometric patterns (eles-4638) ☐
Using algebra to describe patterns (eles-4639) ☐
11.4 Plotting simple linear relationships (eles-4640) ☐
11.5 Interpreting graphs (eles-4641) ☐
Domain and range (eles-4642) ☐
Travel graphs (eles-4643) ☐

Interactivities

11.2 Individual pathway interactivity: The Cartesian plane (int-4384) ☐
The Cartesian plane (int-4136) ☐
Extending the axes (int-4137) ☐
11.3 Individual pathway interactivity: Identifying patterns (int-4446) ☐
Identifying patterns (int-3801) ☐
Geometric patterns (int-3802) ☐
11.4 Individual pathway interactivity: Plotting simple linear relationships (int-4385) ☐
Plotting simple linear relationships (int-4138) ☐
11.5 Individual pathway interactivity: Interpreting graphs (int-4386) ☐
Interpreting graphs (int-4139) ☐
11.6 Crossword (int-2610) ☐
Sudoku puzzle (int-3175) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers


Topic 11 Coordinates and the Cartesian plane

Exercise 11.1 Pre-test


1. a. E2
   b. B1
   c. B2
2. a. Any of the following: Torquay, Geelong, Queenscliff, Sorrento, Wonthaggi, Berwick
   b. Any of the following: Warracknebeal, Dimboola, Wycheproof, Inglewood, Murtoa, Horsham, Navarre, Stawell, Avoca, Ararat, Clunes, Dunkeld, Penshurst, Derrinallum, Skipton, Clunes, Ballarat
   c. Any of the following: Griffith, Narrandera, Wagga Wagga
3. a. a1 and f1 b. b3 c. f7
4. (5, 3)
5. 35 units^2
6. E
7. $(-1, 4)$
8. B
9. 17
10. 17
11. B
12. True
13. $H = 6x + 45$
14. D
15. Section C

Exercise 11.2 The Cartesian plane


1.



2.




3.




4. A(6, 1) B(2, 5) C(7, 9) D(12, 10) E(10, 0) F $\left(4\frac{1}{2}, 0\right)$ G(0, 6) H(0, 0) I $\left(7\frac{1}{2}, 5\right)$ J $\left(10, 7\frac{1}{2}\right)$ K$\left(3\frac{1}{2}, 2\frac{1}{2}\right)$ L$\left(\frac{1}{2}, 9\frac{1}{2}\right)$

5. a.




   b. Quadrant I: point G; Quadrant II: point B; Quadrant III: points A, E, I; Quadrant IV: points C, J; x–axis: points F, H; y–axis: point D.

6. a.



   b. Quadrant I: point I; Quadrant II: points A, F, H, J; Quadrant III: point C, G; Quadrant IV: point B; x–axis: point E; y–axis: point D.

7. a.



b. Quadrant I: point I; Quadrant II: point A, B, F; Quadrant III: points C, G; Quadrant IV: points H, J; *x*–axis: points E; *y*–axis: point D.

8. A(–4, 2), B(–1, 4), C(2, –2), D(4, 1), E(–3, –4), F(0, –5)

9. A(6, –9), B(–7, –8), C(–3, −2), D (–7, 4) , E (–3, 9), F (8, 6)


10. A(–9, –6), B(–3, 3), C(9, –3), D(2, –6), E(–9, 8), F(3, 9)

11. a. B **b.** C **c.** D
d. A **e.** E **f.** A

12. a. E, C **b.** B, D

13. In hospital; in wards six, seven, eight and nine

14.



a. Right-angled triangle

b. Isosceles triangle

c. Trapezium

d. Parallelogram

15.



16. a. Area is 18 square units

b. Perimeter is 18 units

17. b, d, e

18. a. A(0, 1) B(2, 3) C(5, 1)

b. 5 square units


c. A(0, −1) B(2, −3) C(5, −1)

d. A(0, −1) B(−2, −3) C(−5, −1)

19. a. A(−3, 3), B(3, 3), C(3, −3), D(−3, −3)


b. 36 square units.

c.



d. 72 square units.

e.



f. 144 square units.


g. The length doubled, so the area doubled.
When both the length and the width doubled, the area became four times bigger.

20. a. i. It would move in quadrant 2.
ii. It would move in quadrant 4.
b. i It would move in quadrant 1.
ii It would move in quadrant 3.
c. i. Vertical reflection.
ii. Horizontal reflection.

21. a. i. $(3, 8)$
ii. $(6, 2)$
iii. $(-4, -1)$
iv. $(3, -5)$
b. $\left(\frac{a+m}{2}, \frac{b+n}{2}\right)$


22. a. Quadrant 2 or 3 **b.** Quadrant 1 or 2
c. Quadrant 3 **d.** Quadrant 4

23. a.



b. 8 units
c. $(-1, 6)$
d. Take care when determining the middle point of your second horizontal line.
e. $\frac{x_1 + x_2}{2}$

24. a.



b. 12 units
c. $(1, 1)$
d. Take care when determining the middle point of your second vertical line.
e. $\frac{y_1 + y_2}{2}$

25. One possible answer is: $(2, 2)$ $(-2, 2)$ $(-2, -2)$ $(2, -2)$.

26. a. The x-coordinate increases by 2 and the y-coordinate increases by 4. The y-coordinate is always 3 more than double the x-coordinate.
b. $(10, 23)$ $(12, 27)$ $(14, 31)$
c. $y = 2x + 3$

27. a. $(0, 5)$ $(5, 0)$ $(-5, 0)$ $(0, -5)$
b. $(3, 4)$ $(4, 3)$ $(-3, 4)$ $(-4, 3)$ $(-3, -4)$ $(-4, -3)$ $(3, -4)$ $(4, -3)$ all lie on a circle of radius 5 units with centre at the origin.

Exercise 11.3 Linear number patterns

1. a. 1, 5, 9, 13, 17
b. 5, 14, 23, 32, 41

2. a. 50, 42, 34, 26, 18
b. 64, 53, 42, 31, 20

3. a. 10, 12, 14 **b.** 23, 28, 33

4. a. Value of term = 30 – position in pattern × 3
b. 15, 12, 9

5. a. Value of term = 55 – position in pattern × 7
b. 20, 13, 6

6. a. 6, 15, 18 **b.** 10, 12, 16 **c.** 16, 64

7. a. 9, 11, 17 **b.** 88, 110 **c.** 95, 90, 75

8. a. Value of term = position in pattern × 10 − 5
b. 145

9. a. Value of term = 47 − position in pattern × 3
b. 2

10. a. Value of term = position in pattern × 6 + 96
b. 306

11. a. Value of term = 225 − position in pattern × 13
b. −74

12. a. 5, 6, 7, 8 and 9
b. 14
c. 104

13. a. 0, 2, 4, 6 and 8
b. 38
c. 152

14. When relating the value of a term to its position in the pattern, you can use that description to find any other future term in the number pattern.

15. Yes, you can substitute appropriate algebraic symbols for parts of the written descriptions to create an algebraic statement. For example, let the number of matches = m and the number of shapes = n.

16. Once you have identified the connection between the top row and the bottom row in a table of values, you have identified the rule for the pattern.

17. a.



b.

Number of triangles	1	2	3	4	5
Number of matches	3	5	7	9	11

c. Number of matches = number of triangles × 2 + 1

d. 15

18. a. 

b.

Number of houses	1	2	3	4	5
Number of matches	6	11	16	21	26

c. Number of matches = number of houses × 5 + 1

d. 36

19. a.

Number of shapes	1	2	3
Number of matches	5	10	15

b. $m = 5n$

20. a. 

b.

Number of fence units	1	2	3	4	5
Number of matches	4	7	10	13	16

c. Number of matches = number of fence units × 3 + 1

d. 22

21. a.


Number of shapes	1	2	3
Number of matches	6	14	22

b. $m = 8n - 2$


22. See a sample pattern below. Other sample responses can be found in the worked solutions in the online resources.




Exercise 11.4 Plotting simple linear relationships

1. a. 


Linear pattern

b. 


Linear pattern

c. 


Linear pattern

d. 


Non-linear pattern

e. 


Linear pattern

f. 


Linear pattern

2. a. 


Linear pattern

b. 

Linear pattern


c. 

Non-linear pattern

d. 


Linear pattern

3. a.




Linear pattern

b.




Vertical line

c.




Non-linear pattern

d.




Linear pattern

4. a.




Linear relationship

b.




Non-linear relationship

c.




Linear relationship

d.




Non-linear relationship

e.




Linear relationship

f.




Linear relationship

c.




Non-linear pattern

d.




Non-linear pattern

5. a.




Linear pattern

b.




Linear pattern

6. a.




Linear pattern

b.




Linear pattern

c.




Non-linear pattern

d.



Non-linear pattern


7. a, c.



b. Linear pattern

d. (4, 2), (5, 0)

8. a, c.



b. $y = 6$


9. **a**, **b**, **d**

10. a. (8, 7) **b.** (3, 2)

11. a.

Week	1	2	3	4	5	6
Height (mm)	20	24	28	32		40

b.



c. Yes, the points form a straight line.

d. 36 mm


e. 48 mm

12. a. The rule describes a set of points such that the y-coordinate of each point is 3 more than the x-coordinate.

b.

x	−2	−1	0	1	2
y	1	2	3	4	5

c.




d. Yes, the relationship is linear as it produces a straight line.

13. a. The rule describes a set of points such that the y-coordinate of each point is three less than twice the x-coordinate.

b.

x	−2	−1	0	1	2
y	−7	−5	−3	−1	1


c.




d. Yes; the points form a straight line.

e. $-7 \leq y \leq 1$

14. a.



b.




c. *Differences*: The coefficient of x is positive in the first set and negative in the second set. In the first set, the graphs are sloping up, while in the second set the graphs are sloping down. *Similarities*: They are all straight lines.

15. a.

x	−2	−1	0	1	2
y	−5	−3	−1	1	3

b.



c. 1 unit

d. Yes, the points form a straight line.

16. a. Parking fee = 0.04 × time

b.

Time, minutes	30	60	90	120	150
Parking fee, $	1.20	2.40	3.60	4.80	6.00

17. a. Cost per kg = 49.75 − 0.75 × weight in kg

b. 10 and 31

c. $731.50

d. Seven 30 kg bags, so the total weight ordered is 210 kg.

18. 28 desks

Exercise 11.5 Interpreting graphs

1. a. Lucas **b.** Selina

2. a. Yes **b.** No


3. a. Talia **b.** Amy **c.** No

4. a. Karl **b.** No **c.** Yes

5. A: Claire is moving away from home.
B: Claire could be resting as she has stopped.
C: Claire is moving further away from home.
D: Claire could be resting again as she has stopped.
E: Claire is travelling home.

6. a. i. Linh ii. Linh iii. No

b.



7. E

8. C

9. a. A baby is not born with a zero head circumference.

b. The head circumference has increased steadily over the 12 weeks.

c. You would expect the graph to continue to show some increase in head circumference, but this would eventually slow down.

10. a. B

b. Monique is walking faster in section C; therefore, the distance from school is decreasing more quickly.


c. At school

11. a. January


b. April

c. Yupa's profit has gone down each month.

12. The following graph is an example answer.



13.



14. a. April and August b. 40 mm

c. July

15. Windpower is increasing in Australia and worldwide.

16. a. 2009

b. 50 + years

c. Retired people have more time available and want to increase fitness levels as they are getting older.

17. a. Domain: {3, 5, 7, 9, 11} and range: {4, 6, 8, 10, 12}

b. Domain: {4, 5, 6, 7, 8} and range: {0, 2, 4, 6, 8}

c. Domain: {1, 2, 3, 4, 5} and range: {−8, −4, 0, 2, 6}

d. Domain: {−4, −2, 0, 2, 4} and range: {−8, −4, 0, 4, 8}

18. a. Domain: {1, 2, 3, 4, 5} and range: {2, 4, 6, 8, 10}

b. Domain: {−6, −5, 0, 3, 7} and range: {−2, 1, 2, 5, 9}

c. Domain: {−1, −2, −3, −4, −5} and range: {3, 6, 9, 12, 15}

d. Domain: {−4, −2, 0, 2, 4} and range: {0, 1, 3}

19. a. Domain: {−5, −3, −2, 1, 4} and range: {−8, −2, 4, 6, 10}

b. Domain: {−6, 0, 2, 3, 5} and range: {−2, 0, 2, 4}

c. Domain: {0, 3, 4, 7, 9} and range: {5}

d. Domain: {0, 1, 2, 3} and range: {1, 3, 4, 6, 8}

20. a. i. 110 cm ii. 122 cm iii. 158 cm

b. i. 110 cm ii. 146 cm iii. 170 cm


c. 7 and 16

d. i. 10 ii. 17

e. 7 and 16

f. 0 and 1

21. a.



b. If the downward trend continues, there would be approximately 1300 to 1400 sales.

22. a. Svetlana b. 80 km c. 60 km d. Sam

e. Svetlana rested at 1 pm for 1 hour

f. Sam: $80 \div 2\frac{1}{4} = 35.56$ km/h, Svetlana: $60 \div 4 = 15$ km/h

23. a. 120 km

b. 30 km per hour

c. 1.5 hours

d. On the way to the market, as the line is steeper.

24. a. Sarah

b. Tom, as his journey stops and starts a number of times

c. Sarah: 1.5 km per minute, Tom: $\frac{2}{3}$ km per minute

d. They were the same distance from school at 8:35 am.

25. a. In year 6 she sold 300.


b. In year 10 she sold 50.

c. There are two trends. The sales of the glass pendants gradually increase from year 1 to year 6. However, after year 6 the sales decrease quickly.

d. No, the second trend is down and will not help Lisa obtain the loan because the lowest sales are her most recent ones.


e. Domain: $1 \leq x \leq 10$ and range: $50 \leq y \leq 300$

26.




27. It cost 25 cents to make a phone call and then 2 cents for every second of the call.

28. a.



b. As the value of x increases, the value of y decreases to zero and then increases.

29. a.



b. As the value of x increases, the value of y increases.

30. 36.12 km per hour


Project

Players should apply their knowledge of coordinates and the Cartesian plane and play the game to be the first to sink all their opponent's ships.

Exercise 11.6 Review questions

1. a. Joseph's house: B1; Post office: B4

b.



2. a. A

b. K, I, L, J


c. M, N, O, P

d. A(−3, 4) B(−4, 3)


e. C(−4, −3) F(4, −3)

3. a. A(2, 4) (3, 5)

b.



4. a.



b. Yes, the points form a straight line.

5. H or X
H lies in column 3 and row 2.
X lies in column 4 and row 5.

6. a. i. H **ii.** H **iii.** S **iv.** M

b. B9, C2, H6, I10

c. A5 and A6 are already hit, so he needs A4 and A7 to sink it.


7. a. QUEENSLAND (6, 6), (4, 4), (12, 8), (12, 8), (14, 14), (16, 16), (8, 14), (10, 10), (14, 14), (12, 12)

b. VICTORIA (4, 18), (8, 8), (10, 12), (16, 4), (14, 6), (6, 16), (8, 8), (10, 10)

c. SYDNEY (16, 16), (18, 18), (12, 12), (14, 14), (12, 8), (18, 18)


8. (3, 1) (2, 3) (2, 1) (3, 1) (2, 2) (5, 1) (2, 3) (2, 1) (5, 0) (0, 3) (5, 0) (0, 1) (3, 2) (0, 3) (5, 0) (3, 1) (1, 0) (1, 2)

9.



10. D is (3, 7)


11. a.



i. Parallelogram

ii. 28 square units

b.



One example could be Triangle ABC where A is (1, 1), B is (1, 6) and C is (9, 1).

The area of this triangle is $\frac{1}{2} \times \text{base} \times \text{height} = \frac{1}{2} \times 8 \times 5 = 20$ square units as required.

12. D$(1, -5)$

13. a. Domain: {1, 2, 3, 4} and Range {1, 4, 9, 16}

b. No; the relation is $y = x^2$, which is not in the form $y = mx + c$.

14. Not true, as a straight line could:
- be parallel to the y-axis and only cut the x-axis once
- be parallel to the x-axis and only cut the y-axis once
- pass through the origin, cutting the axes at only that point.

15. a. A: Anton is swimming out from the shore.
B: Anton is staying the same distance from the shore.
C: Anton is swimming back to the shore.

b. Anton is swimming faster in section A than in section C.

16. a. i. 100 beats/min

ii. 90 beats/min

b. 3 min

c. 1, 5 min. Pulse rate increases and exceeds 80 beats/min while exercising and then begins to decrease and comes back down to 80 beats/min after exercising.

d. 100 beats/min

e. 4 minutes

17. a. 9:00 am

b. 6:00 am

c. i. 200 **ii.** 450

d. i. 7:00 am, 10:15 am, 12:15 pm

ii. 6:30 am, 10:45 am, 11:30 am


e. The line graph displays how traffic changes over time and we can estimate traffic flow at in-between times.

18. Wilma left home at 1 pm and rode for 16 km (this took 1 hour) before she rested for 15 minutes. She continued for $1\frac{1}{2}$ hours, travelling 8 km, then rested again for 15 minutes. She rode on for 8 km, which took 30 minutes. She reached Mt Cranson at 4:30 pm. She stopped for 30 minutes, then rode home at 5 pm non-stop (32 km) in 1 hour, getting back home at 6 pm. Her speeds between stops were 16 km/h, $5\frac{1}{3}$ km/h, 16 km/h and 32 km/h. These speeds suggest that she rode uphill to Mt Cranson and downhill home. Her average speed for the entire day was 12.8 km/h.

12 Transformations

LEARNING SEQUENCE

12.1 Overview 666
12.2 Line and rotational symmetry 668
12.3 Translations 674
12.4 Reflections 680
12.5 Rotations and combined transformations 687
12.6 Review 698



12.1 Overview

Why learn this?



Geometry is not only the study of figures and shapes; it is the study of their movement. *Transformation* is a term used to describe a change to a shape or its position. Shapes can be rotated, reflected or translated (moved to another position). Some shapes, such as isosceles and equilateral triangles, have symmetrical properties. Symmetry is found in nature; some examples are honeycombs, starfish and orchids.

Transformations can be found in many different places from ancient times to the present day. Tiling a floor or wall uses the concept of transformation, where the same shape or shapes are moved to cover the surface. For example, Ancient Roman mosaics and Islamic tilings often feature intricate geometric patterns.

During the twentieth century, the graphic artist Escher used transformations in his paintings and drawings. The verandahs of period homes in Australia are often tessellated or tiled in traditional English patterns involving just a few different tiles that are repeated to cover the space.

The concept of transformation is still used in architecture and building today. It can also be seen in design. If you look carefully, you will find symmetry and geometric patterns in the world around you, all of which are examples of how transformations can be applied in everyday life.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 12.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. State the number of axes of symmetry a square has.

2. MC Select which of these times on an analogue clock has a vertical axis of symmetry.
   A. 3:00 B. 3:45 C. 9:15 D. 12:00 E. 6:30

3. MC Select which of the following capital letters does not have an axis of symmetry.
   A. A B. B C. E D. F E. H

4. State which regular polygon has 6 axes of symmetry.

5. State the final position of an object, from its original position, if it undergoes translations of: 2U, 4D, 6L, 4R, 7U and 3R.

6. MC If, relative to its original position, the final position of a point is 2U and 3L, the translations that it could have undergone are:
   A. 3U, 5R, 5D, 2L B. 3U, 5L, 5D, 2R C. 6L, 4U, 5U, 3R, 7D
   D. 7U, 2D, 4R, 6L, 2D E. 4D, 2R, 7L, 2U, 2R

7. State the final position of the point $(-3, 5)$ after it undergoes the following translations: 3R, 4L, 3U, 1L, 5D.


8. State the coordinates of the point $(-2, 3)$ after it undergoes a reflection in the x-axis.

9. MC An analogue clock is showing a time of 3:30. If the little hand is reflected about the line from the 12 to the 6, the new time on the clock is:
   A. 3:30 B. 4:30 C. 8:30 D. 9:30 E. 9:00


10. MC Select which of the following letters does not remain the same if reflected either horizontally or vertically.
    A. A B. B C. O D. L E. M

11. State the coordinates of the point $(-4, -7)$ after it is reflected in the y-axis.


12. MC In the diagram shown, select which two transformations the shape on the left has undergone to become the shape on the right.
    A. A reflection and then a rotation
    B. A reflection and then a translation
    C. A rotation and then a translation
    D. A rotation and then a reflection
    E. A translation and then a reflection



13. MC In the diagram, point A is located at the origin and each square represents one unit.
    If the shape is rotated at point A, 90° in the anticlockwise direction, identify the new coordinates of point B.
    A. $(0, 0)$ B. $(6, 0)$ C. $(0, -6)$ D. $(-6, 0)$ E. $(-6, -6)$



14. In the diagram, point C is $(2, 4)$ and each square represents a unit. The shape is rotated 180° in a clockwise direction about C. State the new coordinates of point C.



15. The point $(-2, 6)$ is reflected about the y-axis and then translated 2U and 3R. State the coordinates of its new position.

12.2 Line and rotational symmetry

LEARNING INTENTION


At the end of this subtopic you should be able to:

- identify line symmetry and rotational symmetry in shapes.


12.2.1 Line symmetry

eles-4680


- A shape is symmetrical along a line if it can be folded along that line to create two identical parts that overlap perfectly.
- A line that has this property is called a **line** (or **axis**) **of symmetry**.
- A line of symmetry can be thought of as a mirror, where each side of the shape reflects the other.
- Shapes can have one, many or no lines of symmetry.



One line (axis) of symmetry





4 lines (axes) of symmetry



No lines of symmetry

- Lines of symmetry can be seen in nature. The following photographs show Tasmania's Cradle Mountain reflected in a lake and Washington DC's Memorial Bridge reflected in a river.





- Many buildings and bridges have a line of symmetry. Can you identify the line of symmetry in the following photographs?








DISCUSSION

What objects that are part of everyday life have line symmetry?

WORKED EXAMPLE 1 Identifying lines of symmetry


Identify how many lines of symmetry this shape has.




THINK

1. An axis of symmetry is a line that acts like a mirror line. A vertical line through the top and bottom vertices of this shape would divide it into halves that are mirror images of each other. This vertical line is the axis of symmetry.
2. Look for other axes of symmetry. Indicate all the lines of symmetry with dashed lines. Write down the number of lines.

WRITE/DRAW





There are 4 lines of symmetry.

12.2.2 Rotational symmetry


eles-4681

- A shape has rotational symmetry if rotating it less than 360° matches the original figure.
- The number of times a match occurs within a 360° turn is known as the **order** (or degree) **of rotational symmetry**.
- A shape that has no rotational symmetry still has rotational symmetry of order 1, because the shape will match the original figure after a rotation of 360°.
- Rotational symmetry can be seen in nature and in design, as shown in the following images.

Flower: Rotational symmetry of order 5



Hexagonal frame: Rotational symmetry of order 6




Mercedes Benz logo: Rotational symmetry of order 3




WORKED EXAMPLE 2 Identifying rotational symmetry

Identify whether the following shapes have rotational symmetry. State the order of rotational symmetry for each shape.


a.



b.



c.



THINK	WRITE
a. 1. An equilateral triangle can be rotated less than 360° to match the original shape, so it has rotational symmetry.	**a.** Yes, this shape has rotational symmetry.
2. A match occurs three times throughout the rotation (each of the three sides can sit horizontally).	The shape has a rotational symmetry of order 3.
b. 1. An isosceles triangle must be rotated 360° to match the original shape, so it does not have rotational symmetry.	**b.** This shape does not have rotational symmetry. This shape has rotational symmetry of order 1.
c. 1. A rectangle can be rotated less than 360° to match the original shape, so it has rotational symmetry.	**c.** Yes, this shape has rotational symmetry.
2. A match occurs two times throughout the rotation (each of the two long sides can sit horizontally).	The shape has a rotational symmetry of order 2.

DISCUSSION

The flags of many countries contain lines of symmetry. For example, the Canadian flag has one line of symmetry. Look at some other countries' flags and identify lines of symmetry or rotational symmetry you find in them.



on Resources

eWorkbook Topic 12 Workbook (worksheets, code puzzle and project) (ewbk-1913)

Interactivities Individual pathway interactivity: Line and rotational symmetry (int-4387)

Axes of symmetry (int-4140)

Exercise 12.2 Line and rotational symmetry

learnON






Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 8, 9, 12, 15, 18	2, 5, 7, 10, 13, 16, 19	3, 6, 11, 14, 17, 20






To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency



1. WE1 Identify the number of axes of symmetry for each shape. (Some shapes will have more than one axis of symmetry.) *Hint*: Copy each of the following shapes onto grid or squared paper. Carefully cut out each shape. Fold it to find the axes of symmetry.

a. 
b. 
c. 
d. 
e. 

2. Identify the number of axes of symmetry for each shape.

a. 
b. 
c. 
d. 
e. 

3. Identify how many axes of symmetry each of the following shapes has.

a. 
b. 
c. 
d. 


4. WE2 Identify which of the shapes in question 1 have rotational symmetry. For each shape, state the order of rotational symmetry.

5. Identify which of the shapes in question 2 have rotational symmetry. For each shape, state the order of rotational symmetry.

6. For each figure in question 3, state the order of rotational symmetry.


7. MC Identify the number of axes of symmetry in the shape shown.

A. 0 B. 1 C. 2 D. 3 E. 4




8. a. For each of the following diagrams, use the dotted line as an axis of symmetry to complete the picture.

i.



ii.



b. State the order of rotational symmetry of the completed shapes in part a.

Understanding

9. a. Determine how many axes of symmetry an equilateral triangle has.
   b. Determine how many axes of symmetry an isosceles triangle has.
   c. Determine how many axes of symmetry a scalene triangle has.

10. a. State how many lines of symmetry a square has.
    b. State how many lines of symmetry a rectangle has.
    c. State how many lines of symmetry a parallelogram has.

11. a. Determine how many lines of symmetry a rhombus has.
    b. Determine how many lines of symmetry a trapezium has.
    c. Determine how many lines of symmetry a kite has.

12. a. State the order of rotational symmetry of an equilateral triangle.
    b. State the order of rotational symmetry of an isosceles triangle.
    c. State the order of rotational symmetry of a scalene triangle.

13. a. State the order of rotational symmetry of a square.
    b. State the order of rotational symmetry of a rectangle.
    c. State the order of rotational symmetry of a parallelogram.

14. a. State the order of rotational symmetry of a rhombus.
    b. State the order of rotational symmetry of a trapezium.
    c. State the order of rotational symmetry of a kite.

Reasoning


15. **a.** Determine how many axes of symmetry a circle has. Justify your answer.
b. Determine the order of rotational symmetry of a circle. Justify your answer.

16. The following shapes are regular polygons.



a. Show how many axes of symmetry each shape has.
b. Determine the order of rotational symmetry of each shape.
c. Is there a relationship between the number of vertices in each of these shapes and the number of axes of symmetry? Explain your answer.

17. **a.** Complete the pattern knowing that the horizontal and the vertical dashed lines are both axes of symmetry for this pattern.
b. How did you know where to draw the pattern? Explain your answer using the concept of symmetry and its meaning.
c. Determine the order of rotational symmetry of the completed pattern.



Problem solving


18. The shape given is a sector of a circle.

a. Determine how many axes of symmetry this shape has.
b. Determine the order of rotational symmetry of the shape.




19. The shape given is a circle with a marked chord.

a. Determine how many axes of symmetry this shape has.
b. Determine the order of rotational symmetry of the shape.



20. Answer the following questions for the given shape.

a. Copy the following shape and draw in its axes of symmetry.
b. Determine the order of rotational symmetry of this shape.



12.3 Translations

LEARNING INTENTION

At the end of this subtopic you should be able to:

- translate points and objects in the Cartesian plane
- identify translations in the Cartesian plane.


12.3.1 Transformations

eles-4682

- Transformations are operations that move a point P from one position to another.
- The position of the point, P, after a transformation is called the **image** of the point and is denoted P′.
- Shapes can also undergo transformations. In this case, the transformations are applied to all points of the shape. For example, the image of the rectangle ABCD after a transformation is A′B′C′D′.
- There are different types of transformations. In this topic we will cover **translations**, **reflections** and **rotations**.


Translations

- A translation is the movement of a point or an object up, down, left or right (U, D, L or R) without flipping, turning or changing size.
- After a translation, the object has the same shape and size but is in a different position. For this reason translations are also known as 'slides'.
- The Cartesian plane in the diagram shows some examples of translations.
- The point P has been translated 3 units to the right.
- The triangle ABC has been translated 3 units to the left and 4 units down.



WORKED EXAMPLE 3 Identifying a translation


State the translation of shape *a* to *a′*.



THINK

1. Select any point on the boundaries of the original object, *a* (any vertex is good to choose), and name it A. Locate the corresponding point on the image and name it A′. From point A, draw a horizontal line until it is directly above A′; then draw a vertical line so that it meets A′.
2. Count the number of units that the object has moved across (to the right) and down and, hence, record the translation that took place.

WRITE/DRAW



Translation: 8R 6D

Translating points

- To translate a point horizontally, add or subtract the appropriate number from the x-coordinate of the point.
  - Right is the positive direction.
  - Left is the negative direction.
- To translate a point vertically, add or subtract the appropriate number from the y-coordinate of the point.
  - Up is the positive direction.
  - Down is the negative direction.

WORKED EXAMPLE 4 Translating points

State the coordinates and sketch the image of the point $P(2, -1)$ after:
a. it is translated 3 units to the left
b. it is translated 5 units up
c. it is translated 1 unit to the right and 2 units down.


THINK

a. 1. To translate 3 units to the left, subtract 3 from the x-coordinate.

2. Sketch the image P′.

WRITE


a. $P' = (2 - 3, -1)$
$= (-1, -1)$



b. 1. To translate 5 units up, add 5 to the y-coordinate.

2. Sketch the image P′.


b. $P' = (2, -1 + 5)$
$= (2, 4)$



c. 1. To translate 1 unit to the right and 2 units down, add 1 to the x-coordinate and subtract 2 from the y-coordinate.

2. Sketch the image P′.

c. $P' = (2 + 1, -1 - 2)$
$= (3, -3)$



eles-4684

12.3.2 Combining translations

- If a point or a shape has been translated several times in both horizontal and vertical directions, its final position (relative to the original one) can be described by the total horizontal and total vertical translations.

WORKED EXAMPLE 5 Combining translations

State the final position of an object (relative to its original position) after the translation: 4U 2L, 2D 5L, 6U 2R and 3D 2L.

THINK

1. Find the total vertical translation.
Note: Think of upward movements as positive and downward movements as negative.

2. Find the total horizontal translation.
Note: Treat movements to the right as positive and movements to the left as negative.

3. State the final position of the object relative to its position prior to translation.

WRITE

$4U + 2D + 6U + 3D$
$= 4 - 2 + 6 - 3$
$= 5$
So, the vertical translation is 5U.

$2L + 5L + 2R + 2L$
$= -2 - 5 + 2 - 2$
$= -7$
So, the horizontal translation is 7L.

The position after translation, relative to the original position, is 5U 7L.

on Resources

eWorkbook Topic 12 Workbook (worksheets, code puzzle and project) (ewbk-1913)
Digital document SkillSHEET Translation of a point (doc-6596)
Interactivities Individual pathway interactivity: Translations (int-4388)
Translations (int-4142)

Exercise 12.3 Translations

learnON


Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 14, 17	2, 5, 8, 11, 13, 15, 18	3, 6, 9, 12, 16, 19


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


1. WE3 State the translation that has occurred to each of the shapes labelled a to d in the following figure.



2. State the translation that has occurred to each of the shapes labelled e to h in the following figure.



3. State the translation that has occurred to each of the shapes labelled i to l in the following figure.



4. WE4 State the coordinates and sketch the image of the point $P(1, 3)$ after:

- **a.** it is translated 2 units to the left
- **b.** it is translated 4 units up
- **c.** it is translated 1 unit to the right and 2 units down.

5. State the coordinates and sketch the image of the point $P(4, -1)$ after:

- **a.** it is translated 5 units to the right
- **b.** it is translated 2 units down
- **c.** it is translated 4 units to the left and 3 units up.

6. State the coordinates and sketch the image of the point $P(-3, -5)$ after:

- **a.** it is translated 7 units to the right
- **b.** it is translated 3 units up
- **c.** it is translated 4 unit to the right and 4 units down.


7. WE5 State the final position of an object (relative to its original position) after the translation: 1R 7U, 2R 3D, 5L 2D and 2L 4U.

8. State the final position of an object (relative to its original position) after the translation: 5L 2U, 6L 4U, 8R 3U and 7L 11D.

9. State the final position of an object (relative to its original position) after the translation: 8R 6D, 1R 5U, 3L 9U and 7R 7D.


Understanding

10. Translate the square ABCD, shown in the diagram, 3 units right and 1 unit up, then translate the resulting image 2 units left and 6 units up.



11. Determine each of the following translations of the labelled arrows in the diagram.

- **a.** A to C
- **b.** A to F
- **c.** F to E
- **d.** E to F
- **e.** D to B
- **f.** E to A



12. Using the diagram in question **11**, state which arrow is the object and which arrow is the image in the following translations.

- **a.** 2U 5R
- **b.** 2D 5L
- **c.** 2U 9L
- **d.** 2L 8U
- **e.** 4U 10L
- **f.** 14L

13.

- **a.** Translate the point P (3, 1) 3 units up and 2 units to the left. Label the new point P′ and give the coordinates of this point.
- **b.** Translate P′ 2 units down and 3 units to the left. Label the new point P″ and give the coordinates of this point.
- **c.** Determine what single translation would move P to P″.

Reasoning


14. A city road map can be thought of using Cartesian coordinates with the north being the positive direction of the y-axis. Lucia's home is located at $(3, 11)$ and her work is located at $(-6, -2)$.

a. Describe the translation that describes Lucia's trip home from work.

b. Lucia does not always take the same route home from work. Sometimes she drives past the supermarket to buy groceries on her way home. If the supermarket is located at $(1, 5)$ describe the transformations that describe Lucia's trip home.


c. Show that the transformations in parts **a** and **b** are equivalent.

15. In a game of draughts, a counter is removed from the board when another counter jumps over it. Four counters are arranged on the corner of a draughts board as shown. Use three horizontal or vertical jumps to remove all three red counters, leaving the single black counter. Copy and complete the table to show your working.



Jump	From	To
1		
2		
3		


16. In another game, any counter can jump any other counter. Use seven horizontal or vertical jumps to remove all seven red counters, leaving the single black counter. Copy and complete the table to show your working.



Jump	From	To
1		
2		
3		
4		
5		
6		
7		

Problem solving

17. A crane is moving a girder needed in the construction of a building 5 m up from an initial position of 3 m above the ground. Determine how far above ground level the girder will be at the end of the translation.




18. Alja likes to skip around her backyard.

a. If her starting position on a number plane is at point A (1, 1) and she skips two steps forward and one step to the right, draw her next four locations (on the following graph) after every set of three steps.

b. Do the five points form a pattern?

c. From her last location, Alja decides to skip one step backwards and two steps to the left. She skips in this pattern four times.

d. Do these five points form a pattern?



19. Sketch the quadrilateral ABCD that is formed by the vertices that are described by the following translations from the origin.
A: 3R 2D
B: 5R 1U
C: 1R 5U
D: 4L 3D

12.4 Reflections

LEARNING INTENTION

At the end of this subtopic you should be able to:
- reflect points and shapes in mirror lines
- reflect points and shapes in the Cartesian plane.

12.4.1 Reflections in mirror lines

eles-4685

- A reflection is the image of a point or an object, as seen in the mirror.
- Reflections are often called 'mirror images' and the lines in which the objects are reflected are called 'mirror' lines.
- Mirror images always have reverse orientation; that is, left appears to be right and vice versa.
- Reflected points always lie on the line that is perpendicular to the mirror line that passes through the original point.
- Reflected points are the same distance from the mirror line as the original point on the other side of the mirror.
- Reflections are also known as 'flips'.



- When reflecting shapes in a given line, the following steps can be of assistance:

  Step 1: Select some key points on the original object (the vertices are usually a good choice).


  Step 2: From each point, draw a line perpendicular (at a right angle) to the mirror line. Extend each line beyond the mirror line.

  Step 3: For each selected point, measure its distance along the line from the mirror. The image of the point will be the same distance from the mirror line, on the other side of it.

  Step 4: Complete the image using the reflections of the key points.

WORKED EXAMPLE 6 Reflections in a mirror line


Sketch the image of the triangle after it is reflected in the mirror line.



THINK


1. From each vertex of the given triangle, draw the lines perpendicular to and extending beyond the mirror line.

WRITE




2. Points A and B are both 2 units to the left of the mirror line. Therefore their images A′ and B′ will be 2 units to the right of the mirror line.

   Point C is 8 units to the left of the mirror line. Therefore C′ will be 8 units to the right of the mirror line.



3. Join the vertices A′, B′ and C′ to complete the image.



eles-4686

12.4.2 Reflections in the Cartesian plane


- Points and objects in the Cartesian plane can be reflected in lines and axes.

Reflecting points in an axis

If a point $P = (x, y)$ is reflected in the x-axis, the x-coordinate stays the same and the y-coordinate switches sign. Therefore $P' = (x, -y)$.

If a point $P = (x, y)$ is reflected in the y-axis, the y-coordinate stays the same and the x-coordinate switches sign. Therefore $P' = (-x, y)$.

- The Cartesian plane in the following diagram shows some examples of reflections. The point P has been reflected in the x-axis, the triangle ABC has been reflected in the y-axis and the point S has been reflected in the line $x = -4$.



WORKED EXAMPLE 7 Reflecting points

State the coordinates and sketch the image of the point P(3, 2) after:

a. it is reflected in the x-axis

b. it is reflected in the y-axis

c. it is reflected in the line $y = -1$.

THINK


a. 1. A point (x, y) reflected in the x-axis becomes $(x, -y)$. Therefore the image of P(3, 2) becomes $P'(3, -2)$.

2. To reflect in the x-axis, draw the line $y = 0$. This is the mirror line.

3. Flip the point P over the mirror line (the x-axis) and label it as P'.

WRITE

a. $P' = (3, -2)$




(continued)

b. 1. A point (x, y) reflected in the y-axis becomes $(-x, y)$. Therefore the image of P(3, 2) becomes P′(−3, 2).

2. To reflect in the y-axis, draw the line $x = 0$. This is the mirror line.

3. Flip the point P over the mirror line (the y-axis) and label as P′.


b. P′ = (−3, 2)




c. 1. Draw the line $y = -1$. This is the mirror line.

2. Draw a second line that is perpendicular to $y = -1$ and passes through P.

c.



3. Place the image P′ on the dashed line so that the distance from the line $y = -1$ is equal for P and P′.



4. State the coordinates of P′.

P′ = (3, −4)

on Resources

eWorkbook	Topic 12 Workbook (worksheets, code puzzle and project) (ewbk-1913)
Digital documents	SkillSHEET Reflection of a point (doc-6597) SkillSHEET Reflection of an object (doc-6598)
Interactivities	Individual pathway interactivity: Reflections (int-4389) Reflections (int-4141)

Exercise 12.4 Reflections

learnON


Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 7, 9, 12, 15	3, 4, 8, 10, 13, 16	5, 6, 11, 14, 17


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


1. WE6 Sketch the image of the following shape after it is reflected in the mirror line.




2. Sketch the image of the following shape after it is reflected in the mirror line.




3. Sketch the image of the following shape after it is reflected in the mirror line.




4. Sketch the image of the following shape after it is reflected in the mirror line.



5. Sketch the image of the following shape after it is reflected in the mirror line.



6. Sketch the image of the following shape after it is reflected in the mirror line.




7. **WE7** State the coordinates and sketch the image of the point P(1, 6) after:
   - **a.** it is reflected in the x-axis
   - **b.** it is reflected in the y-axis
   - **c.** it is reflected in the line $y = 3$.

8. State the coordinates and sketch the image of the point P(−2, 4) after:
   - **a.** it is reflected in the x-axis
   - **b.** it is reflected in the y-axis
   - **c.** it is reflected in the line $x = -1$.


Understanding

9. Consider the following shape.




   - **a.** Draw the image reflected in the mirror.
   - **b.** Determine the coordinates of the vertices of the image.

10. Consider the following shape.



   - **a.** Draw the image reflected in the mirror.
   - **b.** Determine the coordinates of the vertices of the image.

11. Consider the following shape.




a. Draw the image reflected in the mirror.
b. Determine the coordinates of the vertices of the image.

Reasoning

12. Explain the statement: In a reflection, the axis of reflection becomes the axis of symmetry if the object and its image are next to each other.

13. Explain the difference between reflection in a horizontal axis and reflection in a vertical axis.


14. Explain which one of the four strawberries is a reflection in the dotted line of the strawberry marked as the original.




Problem solving

15. Reflections in mirrors transform objects. Complete each of the patterns by determining images of the objects reflected in a single mirror, as shown in the following.

a.



b.




16. This is a backward clock. It has the numbers in reverse order, and the hands sweep anticlockwise. Determine the time shown by the clock.




17. A kaleidoscope uses more than one mirror to create wonderful patterns. To help design a kaleidoscope, reflect each object in each of the mirrors to complete the pattern in each of these figures.

a.



b.



12.5 Rotations and combined transformations

LEARNING INTENTION

At the end of this subtopic you should be able to:

- rotate a point or object in the Cartesian plane about the origin
- determine the image of a point or object after it has undergone multiple transformations.

12.5.1 Rotations

eles-4687


- A rotation is simply a turn. By turning your phone from portrait to landscape you have performed a rotation.
- A point or a shape can be rotated about a point called the **centre of rotation**. To specify the rotation, we need to give the angle through which the object is to be turned and the direction of the rotation (clockwise or anticlockwise).
- Consider a centre of rotation at the origin (0, 0). Any point may be rotated about the origin in either direction, clockwise or anticlockwise.




Rotation by 90° about the origin

- To understand what happens when a point is rotated by 90° about the origin, consider the following graphs.

Anticlockwise turn




Clockwise turn




- Rotating a point 90° about the origin simply means that the angle at the origin between a point and its image must be 90°.
- By applying your knowledge of rotating one point, you can rotate multiple points at once. Consider the following graphs.

Anticlockwise turn



Clockwise turn



- By analysing these graphs we can see the rules that hold true for rotations by 90° about the origin.

Rotating points by 90° about the origin


Anticlockwise: The image of a point P(x, y) that is rotated by 90° anticlockwise about the origin is P′$(-y, x)$.

Clockwise: The image of a point P(x, y) that is rotated by 90° clockwise about the origin is P′$(y, -x)$.


Rotation by 180° about the origin

- A similar method can be used to understand what happens when a point is rotated by 180° about the origin.


Anticlockwise turn



Clockwise turn



- An alternate method is to draw a straight line through the point and the centre of rotation. The image will be on the line, at the same distance from the centre of rotation.



Rotating points by 180° about the origin

Regardless of the direction of rotation, the image of a point P(x, y) that is rotated by 180° about the origin is P′$(-x, -y)$.

WORKED EXAMPLE 8 Rotating points

State the coordinates and sketch the image of the point P$(-4, -2)$ after:
a. it is rotated by 90° anticlockwise about the origin
b. it is rotated by 90° clockwise about the origin
c. it is rotated by 180° anticlockwise about the origin.

THINK

a. 1. To rotate by 90° anticlockwise about the origin, the point (x, y) becomes $(-y, x)$.


WRITE

a. $(x, y) \rightarrow (-y, x)$

2. To determine the image of P, swap the x-coordinate with the y-coordinate then change the sign of the new x-coordinate.

$P' = (-(-2), -4)$
$= (2, -4)$

3. Sketch the image P′.




b. 1. To rotate by 90° clockwise about the origin, the point (x, y) becomes $(y, -x)$.

b. $(x, y) \rightarrow (y, -x)$

2. To determine the image of P, swap the x-coordinate with the y-coordinate then change the sign of the new y-coordinate.

$P' = (-2, -(-4))$
$= (-2, 4)$


3. Sketch the image P′.



c. 1. To rotate by 180° anticlockwise about the origin, the point (x, y) becomes $(-x, -y)$. We can simply change the signs of the x- and y-coordinates.


c. $P' = (-(-4), -(-2))$
$= (4, 2)$

2. Sketch the image P′.



WORKED EXAMPLE 9 Rotating shapes

State the coordinates and sketch the image of the following shape after it is rotated by 180° clockwise about the origin.



THINK

1. Write the coordinates of the original shape.


WRITE

The vertices of the original image are:
A(0, 0), B(8, 0), C(8, 2), D(5, 2), E(5, 5), F(3, 5), G(3, 2) and H(0, 2)

2. A rotation of 180° clockwise about the origin changes the signs of the x- and y-coordinates. That is $(x, y) \rightarrow (-x, -y)$.


The vertices of the image are:
A′(0, 0), B′(−8, 0), C′(−8, −2), D′(−5, −2), E′(−5, −5), F′(−3, −5), G′(−3, −2) and H′(0, −2)

3. Sketch the image using the coordinates of the image that were determined in step 2.



Digital technology

Desmos is a free, interactive web application that contains a graphing calculator and a geometry tool. The geometry tool can be used to draw points, circles, polygons, angles, rays and lines. It can also be used to perform and visualise all types of transformations.




12.5.2 Combined transformations in the Cartesian plane

eles-4688

- Transformations can be combined by performing separate transformations, one after the other.
- When combining transformations, keep track of the coordinates of the point/points as each transformation is applied.

WORKED EXAMPLE 10 Combining transformations


Reflect the V-shape in the line $y = 0$, then rotate the image 90° anticlockwise about the origin, then translate the second image 5 units right and 3 units down.




THINK

1. Reflect the V-shape in the line $y = 0$ by changing the signs of the y-coordinates.
   Recall: $(x, y) \rightarrow (x, -y)$
   $A' = (1, -3)$
   $B' = (3, -1)$
   $C' = (5, -3)$


WRITE



2. Rotate the image by 90° anticlockwise about the origin by swapping the x-coordinates with the y-coordinates then changing the signs of the new x-coordinates.
   Recall: $(x, y) \rightarrow (-y, x)$
   $A'' = (3, 1)$
   $B'' = (1, 3)$
   $C'' = (3, 5)$



3. Translate the second image 5 units right and 3 units down by adding 5 to the x-coordinates and subtracting 3 from the y-coordinates.
$A''' = (8, -2)$
$B''' = (6, 0)$
$C''' = (8, 2)$



on Resources

eWorkbook	Topic 12 Workbook (worksheets, code puzzle and project) (ewbk-1913)
Digital documents	SkillSHEET Rotation of a point (doc-6599) SkillSHEET Rotation of an object through 180° (doc-6600)
Interactivities	Individual pathway interactivity: Rotations and combined transformations (int-4390) Rotations (int-4144) Combined transformations (int-4145)

Exercise 12.5 Rotations and combined transformations

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 10, 14, 18, 19	2, 5, 8, 11, 13, 15, 16, 20	3, 6, 9, 12, 17, 21

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE8 State the coordinates and sketch the image of the point P(1, 5) after:
   a. it is rotated by 90° anticlockwise about the origin
   b. it is rotated by 90° clockwise about the origin
   c. it is rotated by 180° anticlockwise about the origin.


2. State the coordinates and sketch the image of the point Q(−2, 4) after:
   a. it is rotated 90° anticlockwise about the origin
   b. it is rotated 90° clockwise about the origin
   c. it is rotated 180° anticlockwise about the origin.

3. State the coordinates and sketch the image of the point R(−3, −1) after:
   a. it is rotated 90° anticlockwise about the origin
   b. it is rotated 90° clockwise about the origin
   c. it is rotated 180° clockwise about the origin.


4. WE9 State the coordinates and sketch the image of the following shape after it has been rotated by 180° anticlockwise about the origin.




5. State the coordinates and sketch the image of the following shape after it has been rotated by 90° clockwise about the origin.




6. State the coordinates and sketch the image of the following shape after it has been rotated by 90° anticlockwise about the origin.




7. State the coordinates and sketch the image of the following shape after it has been rotated by 90° anticlockwise about the origin.



8. State the coordinates and sketch the image of the following shape after it has been rotated by 90° clockwise about the origin.




9. State the coordinates and sketch the image of the following shape after it has been rotated by 90° clockwise about the origin.




Understanding


10. WE10 Reflect the triangle ABC in the x-axis, then rotate the image 90° clockwise about the origin and then translate the second image 4 units right and 6 units down.



11. Translate the V-shape 3 units left and 2 units up, then rotate the image 90° anticlockwise about the origin and then reflect the second image in the y-axis.




12. Rotate the tick ABC 90° clockwise about the origin, then translate the image 7 units right and 1 unit down and then reflect the second image in the x-axis.




13. MC The following diagram shows an object and its image after a certain set of transformations. The object was:

A. reflected in the y-axis, then translated 3R 2D.
B. reflected in the x-axis, then translated 4R 2D.
C. translated 3R 2D, then reflected in the x-axis.
D. translated 4R 2D, then reflected in the x-axis.
E. translated 3R 2U, then reflected in the y-axis.



Reasoning

14. The following object has been rotated 180° about point A. Is there another transformation that would produce the same image? Explain your response.



15. Using the point $(x, -y)$, prove that a rotation of 180° anticlockwise gives an identical result to a rotation of 180° clockwise.

16. The point A (a, b) is rotated anticlockwise through 90° about the origin, then reflected in the x-axis, translated by 4 units in the negative x direction and finally reflected in the y-axis. Determine the final coordinates of A.

17. Using the point R $(-r, -q)$ and showing all working, prove that a rotation of 180° followed by a reflection in the y-axis is equivalent to a reflection in the x-axis.

Problem solving

18. Earth completes a full rotation around the Sun in approximately one year. Determine the approximate angle of rotation of a point on Earth in one day.



19. The point P $(a, -b)$ is reflected in the y-axis and then rotated through 180° about the origin. Determine the coordinates of the new point. Show your working.

20. **a.** Translate the point P (3, 1) 3 units up and 2 units to the left. Label the new point P′ and give the coordinates of this point.
b. Translate P′ 2 units down and 3 units to the left. Label the new point P″ and give the coordinates of this point.
c. Identify the single translation that would move P to P″.

21. A point is translated seven units to the right and four units down, rotated 180° clockwise about the initial position, then reflected in a vertical line passing through the initial position, and then translated seven units to the left and four units down. What are the coordinates of the point at the end of these transformations? Draw a diagram to represent the transformations.

12.6 Review

12.6.1 Topic summary

Rotational symmetry

- A shape has rotational symmetry if rotating it less than 360° matches the original figure.
- The number of times a match occurs in a 360° rotation is the order (or degree) of rotational symmetry.
- The flower below has rotational symmetry of order 5, and the Mercedes-Benz logo has rotational symmetry of order 3.






- All shapes have rotational symmetry of at least order 1, since a rotation of 360° always creates a match.

Line symmetry

- A shape is symmetrical along a line if it can be folded along that line to create two identical parts that overlap perfectly.
- Shapes can have zero, one or multiple lines of symmetry.




Images

- The position of a point or object after transformation is called the image of that point or object.
- The notation for the image is to place an apostrophe after the name of the point or object.
  - The image of a point P is denoted as P'.
  - The image of an image P' is denoted as P''.

TRANSFORMATIONS


Translations

- Translations move points up, down, left or right.
- The directions are often abbreviated by their first letter. For example, a translation 1 unit down and 5 units right is often expressed as D1 5R.



Rotations


- A point or object in the Cartesian plane can be rotated about the origin.
- If a point $P(x, y)$ is rotated 90° clockwise about the origin, $P' = (y, -x)$.
- If a point $P(x, y)$ is rotated 90° anticlockwise about the origin, $P' = (-y, x)$.
- If a point $P(x, y)$ is rotated 180° in either direction about the origin, $P' = (-x, -y)$.



Reflections



- Reflections are images of a point or object as seen in a mirror.
- If a point $P(x, y)$ is reflected in the x-axis, $P' = (x, -y)$.
- If a point $P(x, y)$ is reflected in the y-axis, $P' = (-x, y)$.



Combined transformations

- Multiple transformations can be combined by performing them one after the other.
- It is a good idea to keep track of the coordinates of the point(s) as each transformation is performed.

12.6.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
12.2	I can identify line symmetry and rotational symmetry in shapes.			
12.3	I can translate points and objects in the Cartesian plane.			
	I can identify translations in the Cartesian plane.			
12.4	I can reflect points and shapes in mirror lines.			
	I can reflect points and shapes in the Cartesian plane.			
12.5	I can rotate a point or object in the Cartesian plane about the origin.			
	I can determine the image of a point or object after it has undergone multiple transformations.			


12.6.3 Project

Designing a paved outdoor area

Many paths and entertaining areas are paved with bricks of the same size and shape laid in an interesting design. One such pattern is shown in the following image.

To design this pattern, the basic shape of the brick undergoes one or more transformations to different positions.





1. Using the diagram, what transformation has occurred to brick 1 to obtain the position of brick 2?
2. Identify the transformation that has occurred to brick 2 to obtain the position of brick 3.
3. Describe how the position of brick 3 can be obtained in relation to brick 1.
4. For each of the other numbered bricks in the pattern, describe what transformations to brick 1 are needed to obtain the position of that brick.
5. Explain why this pattern is an example of a **tessellation**.

6. Design your own paved entertaining area. You may like to use one or more shapes that tessellate to form your pattern. Describe what transformations are involved.



Resources

eWorkbook Topic 12 Workbook (worksheets, code puzzle and project) (ewbk-1913)

Interactivities Crossword (int-2612)
Sudoku puzzle (int-3176)


Exercise 12.6 Review questions

learnON


To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency


1. a. State how many axes of symmetry this shape has.
   b. State the order of rotational symmetry of this shape.



2. a. Copy the following shape and draw in its axes of symmetry.
   b. State the order of rotational symmetry of this shape.




3. **a.** Copy the following shape and draw in its axes of symmetry.
b. Determine the order of rotational symmetry of this shape.



4. Show the following translations by copying the shapes and producing an image on a grid.

a.




7R 2U

b.



2L 3D

c.




5R 2D

5. State the final position after each set of the following translations.


a. 3U 2R, 4D 6R, 2U 3L
b. 2D 3L, 4U 5R, 2D 6L, 3D 2R
c. 3L 2U, 9R 5D, 2L 3D, 4R 7U
d. 12L 3U, 4R 2D, 6L 5U, 2R 2D

6. For each of the following shapes, sketch the reflected image in the mirror line shown.


a.



b.




c.




7. **a.** Sketch the image after the sets of transformations shown in these objects.

i.



Translated 3L 4U; then reflected in the mirror

ii.




Reflected in the mirror; then translated 3U 5L

b. Determine the coordinates of the vertices of the object and its image.


8. For each of the following shapes, show the image after the rotation about the origin as specified in the following figures.

a.




90° clockwise

b.



180° anticlockwise


c.




270° clockwise

Problem solving


9. Braille is a code of raised dots that can be read by touch. It was developed by a 15-year-old blind French student named Louis Braille. The braille alphabet is based on a cell three dots high and two dots wide.



a. Compare the first 10 letters of the braille alphabet with the second 10 letters. Describe any patterns that you see.
b. Determine which braille letters are reflections of each other.
c. Determine which braille letters are rotations of each other.
d. There are no braille letters that are translations of each other. Explain this statement.
e. A word like MUM has reflection symmetry. Identify two words that have reflection symmetry when written in braille.



f. A word like SWIMS has rotational symmetry. Identify a two-letter combination that has rotational symmetry when written in braille.



10. Design an image on grid paper. Perform three successive transformations on this image.

on To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1913) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0701) ☐

Digital documents

12.3 SkillSHEET Translation of a point (doc-6596) ☐
12.4 SkillSHEET Reflection of a point (doc-6597) ☐
SkillSHEET Reflection of an object (doc-6598) ☐
12.5 SkillSHEET Rotation of a point (doc-6599)
SkillSHEET Rotation of an object through 180° (doc-6600) ☐

Video eLessons

12.2 Line symmetry (eles-4680) ☐
Rotational symmetry (eles-4681) ☐
12.3 Transformations (eles-4682) ☐
Combining translations (eles-4684) ☐
12.4 Reflections in mirror lines (eles-4685) ☐
Reflections in the Cartesian plane (eles-4686) ☐
12.5 Rotations (eles-4687) ☐
Combined transformations in the Cartesian plane (eles-4688) ☐

Interactivities

12.2 Individual pathway interactivity: Line and rotational symmetry (int-4387) ☐
Axes of symmetry (int-4140) ☐
12.3 Individual pathway interactivity: Translations (int-4388) ☐
Translations (int-4142) ☐
12.4 Individual pathway interactivity: Reflections (int-4389) ☐
Reflections (int-4141) ☐
12.5 Individual pathway interactivity: Rotations and combined transformations (int-4390) ☐
Rotations (int-4144) ☐
Combined transformations (int-4145) ☐
12.6 Crossword (int-2612) ☐
Sudoku puzzle (int-3176) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers


Topic 12 Transformations

Exercise 12.1 Pre-test


1. 4
2. D
3. C
4. Hexagon
5. 1R 5U
6. C
7. $(-5, 3)$
8. $(-2, -3)$
9. C
10. D
11. $(4, -7)$
12. C
13. D
14. $(2, 4)$
15. $(5, 8)$

Exercise 12.2 Line and rotational symmetry

1. a. 3 b. 0 c. 1 d. 1 e. 0
2. a. 0 b. 1 c. 4 d. 2 e. 2
3. a. 6 b. 8 c. 5 d. 0
4. a. 3 b. 1 c. 1 d. 1 e. 1
5. a. 2 b. 1 c. 4 d. 2 e. 2
6. a. 6 b. 8 c. 5 d. 3
7. A
8. a. i.




ii.




b. i. 2
ii. 1

9. a. 3 b. 1 c. 0
10. a. 4 b. 2 c. 0
11. a. 2 b. 0 or 1 c. 1
12. a. 3 b. 1 c. 1
13. a. 4 b. 2 c. 2
14. a. 2 b. 1 c. 1
15. a. An infinite amount
    b. An infinite amount
16. a. 4, 5, 6, 7
    b. 4, 5, 6, 7
    c. Yes, the number of vertices is double the number of axes of symmetry, because each axis of symmetry goes through two vertices.
17. a.




    b. Every point on the pattern has to be equally distant from the axis of symmetry on either side of the axis.
    c. 4
18. a. 1 b. 1
19. a. 1 b. 1
20. a.




    b. 4

Exercise 12.3 Translations


1. a. 1R 2U b. 19R 2D c. 4L 5D d. 10L
2. e. 2R 4U f. 2R g. 2R 9U h. 11L 8D
3. i. 4L 1D j. 6R k. 7L 5D l. 2L 8U
4. a. $P' = (-1, 3)$




b. $P' = (1, 7)$




c. $P' = (2, 1)$




5. a. $P' = (9, -1)$




b. $P' = (4, -3)$




c. $P' = (0, 2)$




6. a. $P' = (4, -5)$



b. $P' = (-3, -2)$



c. $P' = (1, -9)$




7. 4L 6U

8. 10L 2D

9. 13R 1U

10.



11. a. 5R 6D **b.** 21R 5D **c.** 2L 1D
d. 2R 1U **e.** 7R 6U **f.** 19L 6U

12. a. C to D **b.** D to C **c.** E to D
d. E to B **e.** D to A **f.** E to C

13. a. P′ (1, 4)
b. P″ (–2, 2)
c. A translation of 1 unit up and 5 units to the left.

14. a. 9R 13U **b.** 7R 7U then 2R 6U
c. $7R + 2R = 9R$
$7U + 6U = 13U$

15.


Jump	From	To
1	A2	C2
2	A1	C1
3	C1	C3

16.

Jump	From	To
1	A4	C4
2	A3	C3
3	C4	C2
4	A1	A3
5	B1	B3
6	A3	C3
7	C3	C1


17. 8 m

18. a.




b. Form a straight line.

c.




d. Form a straight line.

19.




Exercise 12.4 Reflections


1.




2.




3.




4.




5.




6.




7. a. $P' = (1, -6)$




b. $P' = (-1, 6)$




c. $P' = (1, 0)$




8. a. $P' = (-2, -4)$




b. $P' = (2, 4)$



c. $P' = (0, 4)$




9. a.




b. $A'(7, 2), B'(7, -2), C'(0, -2)$

10. a.



b. A′(4, 2), B′(4, −1), C′(0, −1), D′(0, −5), E′(−3, −5), F′(−3, 2)

11. a.




b. A′(1, 7), B′(6, 7), C′(6, 5), D′(3, 5), E′(3, −1), F′(1, −1)

12. When reflected in an axis, the image is the mirror representation of the original object. If the object and its image are next to each other, they touch each other so they could form one object together. As they are both identical, the axis of reflection becomes the axis of symmetry of the newly formed object.


13. A reflection in a horizontal axis requires the object to be reflected in a vertical direction: up or down.

14. Image 2. It is equally distant from the reflection line as the original strawberry, it is the mirror image of the original strawberry and it is placed on the line perpendicular to the reflection line passing through the original strawberry.

15. a.




b.




16. 10:15

17. a.




b.




Exercise 12.5 Rotations and combined transformations


1. a. $P' = (-5, 1)$




b. $P' = (5, -1)$




c. $P' = (-1, -5)$




2. a. $Q' = (-4, -2)$




b. $Q' = (4, 2)$




c. $Q' = (2, -4)$




3. a. $R' = (1, -3)$




b. $R' = (-1, 3)$




c. $R' = (3, 1)$




4. $A' = (-6, 0)$, $B' = (0, -4)$, $C' = (0, 0)$




5. $A' = (6, 0)$, $B' = (4, 6)$, $C' = (0, 0)$




6. $A' = (0, -8)$, $B' = (-4, -8)$, $C' = (0, -2)$




7. $A' = (2, 2)$, $B' = (-2, 2)$, $C' = (2, 7)$




8. $A' = (-2, 0)$, $B' = (2, 0)$, $C' = (-2, -5)$




9. $A' = (-1, 4)$, $B' = (3, 4)$, $C' = (-1, -1)$




10.



11.




12.




13. C

14. A reflection in the dashed line shown.



15. A full circle is 360°. 180° is half of a circle. It does not matter which direction you move along a circle; if you travel 180°, you will reach the opposite side. This can be seen in the following diagram.




16. $(4 - b, -a)$

17. $(-r, -q) \Rightarrow (r, q) \Rightarrow (-r, q)$; $(-r, -q) \Rightarrow (-r, q)$

18. Approximately 1°.


19. $P(a, -b) \Rightarrow P'(-a, -b) \Rightarrow P''(a, b)$

20. a., b.



c. A translation of 1 unit up and 5 units to the left.

21. The coordinates of the point remain unchanged.




Project

1. 90° clockwise rotation around the bottom right corner of brick 1
2. Translation of one brick-width to the right
3. 90°clockwise rotation around a point halfway between the bases of bricks 1 and 3
4. Brick 4: translate one brick-width up
   Brick 5 : rotate 180° around the point halfway between the closest points connecting bricks 1 and 5
   Brick 6: rotate 90° clockwise around the bottom right corner of brick 3
   Brick 7: rotate 90° clockwise around the bottom right corner of brick 1 and then translate it four brick-widths to the right
   Brick 8: rotate 90° clockwise around the point at the bottom left corner of brick 7
5. This is an example of a tessellation because the pattern repeats itself and there are no gaps.
6. Students could use one or more shapes that look like a tessellation for their entertaining area. After creating the pattern, students should describe what transformations are involved.

Exercise 12.6 Review questions


1. a. 3 **b.** 3

2. a.




b. 4

3. a.




b. 2


4. a.



b.




c.




5. a. 1U 5R **b.** 3D 2L **c.** 8R 1U **d.** 12L 4U


6. a.




b.




c.



7. a. i.




ii.




b. i. $A(-7, -5) \rightarrow A'(6, -1)$,
$B(-7, 0) \rightarrow B'(6, 4)$,
$C(-5, -3) \rightarrow C'(4, 1)$,
$D(-3, -3) \rightarrow D'(2, 1)$,
$E(-3, -5) \rightarrow E'(2, -1)$,

ii. $A(-3, -7) \rightarrow A'(-8, 6)$,
$B(-4, -5) \rightarrow B'(-9, 4)$,
$C(-2, -3) \rightarrow C'(-7, 2)$,
$D(1, -3) \rightarrow D'(-4, 2)$,
$E(3, -5) \rightarrow E'(-2, 4)$,
$F(1, -7) \rightarrow F'(-4, 6)$


8. a.



b.



c.




9. a. Each of the second group of 10 letters has the same pattern as the corresponding letter but with an extra dot underneath.

b. D and F, E and I, H and J, M and U, N and Z, P and V, R and W


c. B, C, E and I

d. Braille is read by touch and translations would not be determined by touch.

e. The word *fixed* has rotational symmetry when written in braille:



f. The letters W and R form a rotational symmetrical pair in braille:



10. Sample responses can be found in the worked solutions in the online resources.

13 Introduction to probability

LEARNING SEQUENCE

13.1 Overview 716
13.2 The language of chance 718
13.3 The sample space 723
13.4 Simple probability 728
13.5 Experimental probability (extending) 734
13.6 Review 742



13.1 Overview

Why learn this?

Probability describes the chances of different events occurring. As with many different areas of mathematics, probability has its own terminology or language. To understand the chances of an event happening, it is important to understand the language of probability.



Whether you realise it or not, you use and consider probabilities every single day. For example, the weather report may say that there is a high chance of rain tomorrow. When you decide what to wear each day, you are taking into account the likelihood of it raining, or the likelihood of the sun shining all day.

Many board games depend on probability. Have you ever played a board game with 2 dice where you wanted to throw a double 6? The chance, or probability, of that occurring is 1 in 36. Lotteries use probability to determine the likelihood of a winning ticket being bought, and set the prize money based on these calculations. To win first prize in TattsLotto, you need to have selected the correct 6 balls from the 45 balls in the barrel. The chance of this happening is 1 in 8 145 060. This means that you would be likely to win TattsLotto approximately once per 8 million tickets you buy! In Oz Lotto you need to select 7 balls from a 45 ball barrel, with the chance of winning division 1 dropping lower, to 1 in 45 379 620!

Probability is also widely used in the finance industry. Insurance brokers look at the chance, or likelihood, of an event occurring, and set their rates accordingly. Many different professions require knowledge of probability, including science, market research analysis, meteorology, financial analysis, statistics and many others.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 13.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Select the option that best describes the probability of rolling an odd number with a die.
   A. Impossible B. Unlikely C. Even D. Likely E. Certain

2. MC Select the probability that is best linked to a likely probability.
   A. 0 B. 0.1 C. 0.3 D. 0.5 E. 0.7

3. A bag contains 3 blue balls, 5 red balls and 2 yellow balls. Determine the probability of randomly selecting a yellow ball from the bag.

4. MC A ball is selected from a bag. Determine the sample space of the bag that contains 5 blue balls, 8 red balls and 2 yellow balls. (B = blue, R = red, Y = yellow)
   A. S = {5B, 8R, 2Y} B. S = {B, R, Y}
   C. S = {B, R, W, Y} D. S = {BBBBB, RRRRRRRR, YY}
   E. S = {B, G, R, Y}

5. A card is selected from a standard deck of cards and the suit is noted. Determine the number of elements in the sample space.

6. Two dice are rolled and the sum of the two dice is 5. Determine the number of ways the sum of 5 can be obtained.

7. MC If a fair die is rolled, the probability of rolling a number less than 5 is:
   A. $\frac{2}{3}$ B. $\frac{1}{6}$ C. $\frac{1}{3}$ D. $\frac{2}{5}$ E. $\frac{1}{2}$

8. MC If a 12-sided die is rolled, the probability of rolling a multiple of 4 is:
   A. $\frac{1}{2}$ B. $\frac{1}{4}$ C. $\frac{1}{3}$ D. $\frac{5}{12}$ E. $\frac{7}{12}$

9. MC A card is chosen at random from a standard deck of cards. The probability of selecting a red picture card is:
   A. $\frac{2}{13}$ B. $\frac{3}{26}$ C. $\frac{3}{28}$ D. $\frac{3}{13}$ E. $\frac{1}{4}$

10. A bag contains 5 blue balls, 7 red balls and 3 green balls. If a ball is selected at random, calculate the probability that neither a red or blue ball was selected.

11. MC Lauren does not know when Emily's birthday is. Determine which of the following months it is most likely to be in.
    A. April B. June C. September
    D. November E. All options are equally likely.

12. Australia Post delivers parcels during business hours (9 am to 5 pm). Sally has ordered a parcel that will arrive next week. Determine the probability that the parcel arrives before midday on Tuesday.

13. MC Identify which of the following options best describes the probability of randomly choosing a prime number out of the first 100 whole numbers.
    A. Impossible B. Unlikely C. Even chance D. Likely E. Certain

14. MC Identify which of the following options would best simulate selecting a ball from a bag of 6 differently coloured balls.
   - **A.** Tossing a coin
   - **B.** Spinning a 4-sector circular spinner
   - **C.** Spinning a 5-sector circular spinner
   - **D.** Rolling a standard die
   - **E.** Spinning a square spinner

15. A box contains 3 red dice and 4 blue dice. Determine the smallest number of dice needed to be taken from the box to be *sure* you have a die of each colour.

13.2 The language of chance

LEARNING INTENTION

At the end of this subtopic you should be able to:
- understand that a probability is a number between 0 and 1 that describes the possibility of an event
- classify the chance of an event occurring using words such as *certain, likely, unlikely, even chance* or *impossible*.


13.2.1 The language of chance

eles-4710

- An **event** is a result that may occur.
  - When classifying the chance of an event occurring, we use words such as *certain, likely, even chance, unlikely* and *impossible*.
  - Probabilities can be written as decimals, fractions and percentages. For example, $0.5 = \frac{1}{2} = 50\%$.



  - The following **probability** scale associates important words used to describe probability with their approximate corresponding numerical values.



- An **outcome** in a chance experiment refers to any possible result.
- An event can describe either one outcome (for example, rolling a 1 on a die) or a collection of outcomes (for example, rolling an even number on a die).

DISCUSSION

Discuss other examples of events that have a probability of 0, 0.5 or 1.

WORKED EXAMPLE 1 Classifying an event occurring

For each of the given statements, specify whether the chance of the following events occurring is *certain, likely, even chance, unlikely* or *impossible*.

a. You will compete in the next Olympics.
b. Every student in Year 7 will obtain 100% in their next mathematics test.
c. Each person in your class has been to the zoo.
d. You flip a coin and Tails comes up.
e. March is followed by April.



THINK	WRITE
a. The chance of a person competing in the next Olympics is very small; however, it could happen.	a. It is *unlikely* that this event will occur.
b. Due to each student having different capabilities and the number of students involved, this situation will almost never happen.	b. The chance of this event occurring is *impossible.*
c. The chance that each student in your class has been to the zoo, either with their family or primary school, is probable.	c. It is *likely* this event has occurred.
d. When you flip a coin in a chance experiment, there are only two possibilities, a Head or a Tail. So there is a 50% chance of Tails coming up.	d. There is an *even chance* this event will occur.
e. April always follows the month of March. This is a true statement.	e. It is *certain* this event will occur.

WORKED EXAMPLE 2 Estimating the probability of an event occurring

Assign a number between and including 0 and 1 to represent the estimated probability of the following events, depending on how likely they are.

a. One of two evenly matched tennis players will win the next game.

b. You will guess the correct answer on a multiple choice question with four options.

c. Rolling a fair die and obtaining a number less than 6.



THINK	WRITE
a. 1. Determine the likelihood of an event occurring, with reasoning.	a. Since the two players are evenly matched, one does not have an advantage over the other. Therefore, they each have an equal chance of winning the next game.
2. Express the answer as a decimal.	The probability that one player wins the game is $\frac{1}{2}$ or 0.5.
b. 1. Determine the likelihood of an event occurring, with reasoning.	b. When guessing an answer on a multiple choice question with 4 options, 1 out of the 4 possibilities will be correct. One out of 4 may be expressed as a fraction.
2. Express the answer as a decimal.	The probability of guessing the correct answer is $\frac{1}{4}$ or 0.25.
c. 1. Determine the likelihood of an event occurring, with reasoning.	c. In the chance experiment of rolling a die, there are six possibilities. They are 1, 2, 3, 4, 5, 6. A number less than 6 includes 1, 2, 3, 4, 5. Therefore, five out of the six possibilities may be rolled. Five out of six may be expressed as a fraction.
2. Express the answer as a decimal, correct to 2 decimal places.	The probability of obtaining a number less than six is $\frac{5}{6}$ or approximately 0.83.

COLLABORATIVE TASK: Draw a spinner

Create spinners with the following probabilities.

a. $P(\text{blue}) = \frac{1}{3}$ and $P(\text{white}) = \frac{2}{3}$

b. $P(\text{blue}) = \frac{1}{2}$, $P(\text{white}) = \frac{1}{4}$, $P(\text{green}) = \frac{1}{8}$ and $P(\text{red}) = \frac{1}{8}$

c. $P(\text{blue}) = 0.75$ and $P(\text{white}) = 0.25$

Once you have created your spinners, test them out with your classmates. How accurately do your results match the probabilities for which the spinners were designed?



Resources

eWorkbook	Topic 13 Workbook (worksheets, code puzzle and project) (ewbk-1914)
Digital documents	SkillSHEET Understanding 'chance' words (doc-6522) SkillSHEET Comparing the likelihood of different events occurring (doc-6523) SkillSHEET Describing the chance of an event occurring as more or less than half (doc-6524)
Interactivities	Individual pathway interactivity: The language of chance (int-4362) Chance (int-4026)

Exercise 13.2 The language of chance

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 5, 9, 12, 15	2, 6, 7, 10, 13, 16	4, 8, 11, 14, 17

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency



1. WE1 For each of the given statements, specify whether the chance of the following events occurring is certain, likely, even chance, unlikely or impossible.
   a. New Year's Day will be on 1 January next year.
   b. You roll a fair die and obtain a number less than 5.
   c. Water will boil in the fridge.
   d. There will be snow on the ski fields this winter.
   e. You will grow 18 cm taller this year.

2. For each of the given statements, specify whether the chance of the following events occurring is certain, likely, even chance, unlikely or impossible.
   a. You will win first prize in Tattslotto.
   b. You roll a fair die and obtain an odd number.
   c. The year 2024 will be a leap year.
   d. You choose a white ball from a bag that contains only white balls.
   e. You choose a yellow ball from a bag containing 4 red balls and 4 yellow balls.

3. WE2 Assign a number between and including 0 and 1 to represent the estimated probability of the following events, depending on how likely they are.
   a. You flip a coin and obtain a Tail.
   b. You choose a red ball from a bag containing only 8 white balls.
   c. You guess the correct answer in a multiple choice question with 5 options.
   d. You roll a die and obtain a number greater than 4 on a fair die.

4. Assign a number between and including 0 and 1 to represent the estimated probability of the following events, depending on how likely they are.



   a. You flip a coin and obtain a Head.
   b. You choose a green ball from a bag containing only four green balls.
   c. You have science classes this year.
   d. Australia will win the Boxing Day cricket test.

5. MC The word that has the same meaning as *improbable* is the word:

   A. unlikely B. impossible C. uncertain D. certain E. likely

6. MC The word that has the same meaning as *certain* is the word:

   A. definite B. possible C. likely D. probable E. unlikely

Understanding

7. Compare the given events A, B, C, D and order them from least to most likely.



   a. It will be sunny in Queensland most of the time when you visit.
   b. Melbourne Cup Day will be on the first Tuesday in November next year.
   c. You will be the next Australian Eurovision contestant.
   d. Saturn will be populated next year.

8. List five events that are:
   a. impossible
   b. unlikely to happen
   c. likely to happen
   d. sure to happen.

For questions 9 to 11, match the word with the number that best represents the probability associated with the word. Use only the following numbers: 0, 0.25, 0.5, 0.75, 1.

9. a. Certain b. Likely c. Unlikely d. Probable e. Improbable

10. a. Slim chance b. Sure c. Doubtful
    d. Not able to occur e. More than likely

11. a. Definite b. Impossible c. Fifty-fifty d. Fair chance

Reasoning

12. Explain your answers to the following questions using the language learned in this subtopic.





   a. If today is Monday, what is the chance that tomorrow is Thursday?
   b. If today is the 28th of the month, what is the chance for tomorrow to be the 29th?
   c. If you toss a coin, what is the chance it will land Heads up?


13. 'Fifty-fifty' is an expression commonly used in probability. Explain the meaning of this expression, giving its fractional value and its decimal number form, as well as expressing it as a percentage.

14. Five balls numbered 1, 2, 3, 4 and 5 are placed in a bag. You draw a ball out of the bag at random and check whether it is odd or even. Explain why the probability of drawing an odd ball from the bag is not 0.5.

Problem solving

15. Anthony has 10 scrabble pieces, as shown. His friend Lian is blindfolded and is asked to pick a piece at random during a chance experiment. Determine the chance she will pick:

a. an I **b.** an A **c.** a U **d.** an E.



16. On 1 January, two friends, Sharmela and Marcela, were chatting with each other. Sharmela commented, 'It is very likely that tomorrow the temperature will be around 35 °C.' Marcela replied, 'It is very likely that tomorrow it is going to snow.' They were both correct.

a. Explain how this is possible.
b. Think and discuss any other situations like the one described in this question.

17. You roll a regular 6-sided die. Identify an event that could be described by the following words:

a. Impossible **b.** Very unlikely **c.** Even chance **d.** Very likely **e.** Certain

13.3 The sample space


LEARNING INTENTION

At the end of this subtopic you should be able to:
- determine the outcomes and sample space of a chance experiment
- identify the sample space of a two-step chance experiment using a two-way table.

13.3.1 The sample space

eles-4711

- The **sample space** refers to the list of all possible outcomes of a chance experiment. It is represented by the letter S.
- For example, the sample space for the spinner shown is $S = \{\text{blue, pink, green, orange}\}$.
  Note: Each outcome is only listed once in the sample space (for example, even if there are multiple sectors with red on the spinner, red is only listed once).
- Each outcome in the sample space is called an element of the sample space.
- For example, green is an outcome of the chance experiment and an element of the sample space.
- The number of elements in the sample space is denoted $n(S)$.
- The number of elements in the sample space of the spinner shown is 4: $n(S) = 4$.



WORKED EXAMPLE 3 Listing the sample space

A card is drawn from a standard deck. The suit of the card is then noted. List the sample space for this chance experiment.

THINK	WRITE
Although there are 52 cards in the deck, we are concerned only with the suit. List each of the four suits as the sample space for this chance experiment.	$S = \{\text{clubs, spades, diamonds, hearts}\}$

WORKED EXAMPLE 4 Identifying the number of elements in a sample space

A die is rolled and the number on the uppermost face is noted. Identify the number of elements in the sample space.




THINK	WRITE
A die has six outcomes: 1, 2, 3, 4, 5 or 6.	$n(S) = 6$

eles-4712

13.3.2 Two-way tables

- **Two-way tables** are used to show the sample space of two consecutive chance experiments.
- Suppose we want to spin a spinner and then toss a coin. The outcomes of each experiment are listed in the first column and the first row of the following table.





Second set of outcomes

First set of outcomes

	Heads	Tails
Pink		
Blue		
Green		
Orange		

- The sample space for the **two-step experiment** is then listed in the remaining cells.

	Heads	Tails
Pink	Pink, Heads	Pink, Tails
Blue	Blue, Heads	Blue, Tails
Green	Green, Heads	Green, Tails
Orange	Orange, Heads	Orange, Tails

Sample space

$$S = \{(\text{Pink, Heads}), (\text{Pink, Tails}), (\text{Blue, Heads}), (\text{Blue, Tails}), (\text{Green, Heads}), (\text{Green, Tails}), (\text{Orange, Heads}), (\text{Orange, Tails})\}$$

WORKED EXAMPLE 5 Creating a two-way table and listing the sample space

a. Draw a two-way table and list the sample space for the experiment 'tossing a coin and rolling a die'.
b. State how many different outcomes or results are possible.

THINK

a. 1. Rule a table consisting of 7 rows and 3 columns. Leave the first cell blank.
2. Label the second and third cells of the first row as H and T respectively.
3. Label cells 2 to 7 of the first column as 1, 2, 3, 4, 5, 6 respectively.
4. Answer the question by combining the outcome pairs in the order in which they occur in each of the remaining cells, that is, the first event result followed by the second event result.

b. Count the number of different outcomes and answer the question.

WRITE

a.

	H	T
1	H1	T1
2	H2	T2
3	H3	T3
4	H4	T4
5	H5	T5
6	H6	T6

The sample space for the experiment 'tossing a coin and rolling a die' is:
$\{(H, 1), (H, 2), (H, 3), (H, 4), (H, 5), (H, 6), (T, 1), (T, 2), (T, 3), (T, 4), (T, 5), (T, 6)\}$.

b. There are 12 different outcomes.

on Resources

eWorkbook Topic 13 Workbook (worksheets, code puzzle and project) (ewbk-1914)
Interactivities Individual pathway interactivity: The sample space (int-4363)
The sample space (int-4027)
Tables and sample spaces (int-4029)

Exercise 13.3 The sample space

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 3, 9, 10, 13, 16, 19	4, 6, 7, 11, 14, 17, 20	5, 8, 12, 15, 18, 21, 22

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

WE3 For each of the chance experiments in questions 1 to 6, list the sample space.

1. A spinner with equal sectors labelled 1 to 10 is spun.
2. A coin is tossed.
3. A multiple choice question has five alternative answers: A, B, C, D and E.
4. A soccer team plays a match and the result is noted.
5. A card is selected from the four aces in a deck.
6. An exam paper is given the grade *A* to *F*.
7. A card is selected from a standard deck. List the sample space if we are interested in:
   a. the suit of the card chosen
   b. the colour of the card chosen.
8. A bag contains 8 red marbles, 9 green marbles and 2 orange marbles. A marble is selected from the bag. List the sample space.



Understanding

9. WE4 A coin is tossed. Identify the number of elements in the sample space.
10. In each of the following, state the number of elements in the sample space.
    a. A card selected from a standard deck.
    b. The first ball drawn in the Tattslotto draw. (Balls are numbered from 1 to 45.)
    c. The winner of the AFL premiership. (There are 18 teams.)
    d. A day of the year is selected.




11. In each of the following, state the number of elements in the sample space.
    a. A letter from the alphabet is selected at random.
    b. The first prize in the lottery is chosen from tickets numbered 1 to 180 000.
    c. A term is selected from a school year.
    d. You win a medal at your chosen event at the world swimming championships.

12. MC From the following list, select the event that has the most elements in the sample space.

- **A.** Selecting a card from a standard deck
- **B.** Selecting a page at random from this book
- **C.** Selecting an exercise book from your school bag
- **D.** Selecting a student at random from your class
- **E.** Selecting a page at random from the phone directory

13. WE5 The spinner shown is spun and a coin is tossed.



- **a.** Construct a two-way table to list the sample space of this two-step experiment.
- **b.** State how many different outcomes or results are possible.

14.
- **a.** Draw a two-way table and list the sample space for the experiment 'spinning a circular spinner divided into 3 equal sectors labelled A, B, C and rolling a die'.
- **b.** State the number of different outcomes or results.

15. A five-sided die and a 3-sided die are rolled simultaneously.

- **a.** Use a two-way table to list the sample space of this two-step experiment.
- **b.** Use your two-way table to help you construct a sample space for 'the sum of the two dice rolled'.

Reasoning

16. Explain the difference between a chance experiment, an outcome, an event and the sample space.

17. Are all elements in a sample space equally likely to occur? Justify your answer.

18. Determine the number of different ways in which change can be given for a 50 cent coin using only 20 cent, 10 cent and 5 cent coins. Justify your answer.



Problem solving

19. Michelle studies elective music. Her assignment this term is to compose a piece of music using as many instruments as she chooses, but only those that she can play. Michelle plays the acoustic guitar, the piano, the double bass and the electric bass. Determine the different combinations Michelle could choose.



20. Alex has one brother, one sister, a mother and a father. The family owns a 5-seat car. When the family goes out, the parents always sit in the front two seats. There are three seats behind that. Determine the different seating arrangements that are there.

21. If you had any number of ordinary six-sided dice, determine the number of different ways you could roll the dice and obtain a total of 6.

22. Four students, Aimee, Ben, Carla and Donald, are standing in a line waiting to enter the classroom. Determine the number of possible ways these 4 students can be arranged if Ben refuses to stand at the front of the line.



13.4 Simple probability

LEARNING INTENTION

At the end of this subtopic you should be able to:

- calculate theoretical probabilities.

13.4.1 Simple probability

eles-4713


- An outcome is a particular result of a chance experiment.
- A **favourable outcome** is one that we are looking for.

Theoretical probability

- The **theoretical probability** of a particular result or event is defined as:

$$\textbf{Pr(event)} = \frac{\textbf{number of favourable outcomes}}{\textbf{total number of outcomes}}$$

- **Equally likely outcomes** have an equal chance of occurring.
- For the spinner shown:
  - there are three blue sectors out of eight possible outcomes (sectors), so $\text{Pr(blue)} = \frac{3}{8}$
  - pink and green are equally likely outcomes as they both are two out of the eight sectors: $\text{Pr(pink)} = \frac{2}{8} = \frac{1}{4}$ and $\text{Pr(green)} = \frac{2}{8} = \frac{1}{4}$
  - orange is the least likely outcome as it is one sector out of the eight, so $\text{Pr(orange)} = \frac{1}{8}$.



DISCUSSION

Design a spinner that has four colours: red, green, blue and yellow.

Red should be twice as likely to occur as green and three times as likely to occur as blue. Yellow should be half as likely to occur as green.

Are there multiple designs that meet the description above?

Discuss with your classmates and try to come up with multiple designs.



WORKED EXAMPLE 6 Determining outcomes of chance experiments

State how many possible outcomes there are for each of the following chance experiments and specify what they are. Discuss whether the outcomes are equally likely or not equally likely to occur.

a. Tossing a coin

b. Spinning a circular spinner with 9 equal sectors labelled from *a* to *i*

c. Drawing a picture card (jack, queen, king) from a standard pack of cards

THINK	WRITE
a. 1. Make a note of how many sides the coin has and what each side represents.	**a.** The coin has 2 sides, a Head and a Tail.
2. State the outcomes and specify whether they are equally likely or not equally likely to occur.	When tossing a coin, there are two possible outcomes: Head or Tail. These outcomes are equally likely to occur.
b. 1. Make a note of how many sectors are in the circular spinner and what each one represents.	**b.** The circular spinner has 9 sectors labelled *a* to *i*.
2. State the outcomes and specify whether they are equally likely or not equally likely to occur.	When spinning the circular spinner, there are 9 possible outcomes; they are *a*, *b*, *c*, *d*, *e*, *f*, *g*, *h* or *i*. These outcomes are equally likely to occur.
c. 1. State the possible outcomes.	**c.** There are 2 possible outcomes, drawing a picture card or drawing a non-picture card.
2. Consider the possibility of the outcomes and specify whether they are equally likely or not equally likely to occur.	There are 52 cards in a standard pack. There are 3 picture cards in each of the four suits: $3 \times 4 = 12$ picture cards in a pack. Therefore the probabilities are: $\Pr(\text{picture card}) = \frac{12}{52}$ $\Pr(\text{non-picture card}) = \frac{52-12}{52} = \frac{40}{52}$ The probability of drawing a picture card is less than the probability of drawing a non-picture card.

WORKED EXAMPLE 7 Calculating probability

Christopher rolls a fair 6-sided die.


a. State all the possible results that could be obtained.

b. Calculate the probability of obtaining:

i. a 4

ii. a number greater than 2

iii. an odd number.



THINK	WRITE
a. Write all the possible outcomes.	**a.** There are six possible outcomes: $1, 2, 3, 4, 5, 6$.
b. i. 1. The number 4 occurs once.	**b. i.** Number of favourable outcomes $= 1$ Total number of outcomes $= 6$
2. Write the rule for probability.	$\Pr(\text{event}) = \dfrac{\text{number of favourable outcomes}}{\text{Total number of outcomes}}$
3. Substitute the known values into the probability formula and evaluate the probability of obtaining a 4.	$\Pr(4) = \dfrac{1}{6}$
4. Write the answer.	The probability of obtaining a 4 is $\dfrac{1}{6}$.
ii. 1. 'A number greater than 2' implies: $3, 4, 5, 6$.	**ii.** Number of favourable outcomes $= 4$ Total number of outcomes $= 6$
2. Write the rule for probability.	
3. Substitute the known values into the probability formula and evaluate the probability of obtaining a number greater than 2.	$\Pr(\text{greater than } 2) = \dfrac{4}{6}$
4. Simplify the fraction.	$= \dfrac{2}{3}$
5. Write the answer.	The probability of obtaining a number greater than two is $\dfrac{2}{3}$.
iii. 1. 'An odd number' implies $1, 3, 5$.	**iii.** Number of favourable outcomes $= 3$ Total number of outcomes $= 6$
2. Write the rule for probability.	
3. Substitute the known values into the probability formula and evaluate the probability of obtaining an odd number.	$\Pr(\text{an odd number}) = \dfrac{3}{6}$
4. Simplify the fraction.	$= \dfrac{1}{2}$
5. Write the answer.	The probability of obtaining an odd number is $\dfrac{1}{2}$.

COLLABORATIVE TASK: Experimental versus theoretical probability!

1. Roll a die 20 times and record how many even numbers you roll.
2. Calculate the number of even numbers you should have rolled. How does your number compare to the theoretical number you would expect from 20 rolls?
3. Compare your results with your classmates' results. How do your classmates' results compare to the expected number?
4. Collate all of your classmates' results together. How does the total number of evens compare to the theoretical expected number? Are the class results closer to the expected results than each student's individual results?



Resources

eWorkbook	Topic 13 Workbook (worksheets, code puzzle and project) (ewbk-1914)
Digital documents	SkillSHEET Listing all possible outcomes for an event (doc-6525) SkillSHEET Understanding a standard deck of playing cards (doc-6526) SkillSHEET Writing a simple probability as a fraction (doc-6527)
Interactivities	Individual pathway interactivity: Simple probability (int-4364) Simple probability (int-4028)

Exercise 13.4 Simple probability

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 7, 11, 14, 18, 21	2, 5, 8, 10, 13, 16, 19, 22	3, 6, 9, 12, 15, 17, 20, 23

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

For each of the chance experiments in questions **1** to **5**, state the number of possible outcomes and specify what they are.



1. Rolling a 12-sided die, numbered 1 to 12 inclusively
2. Spinning a spinner for a game that has 5 equal-sized sections, numbered 1 to 5 inclusively
3. Choosing a consonant from the word *cool*
4. Rolling an even number greater than 2 on a fair 6-sided die
5. Choosing an odd number from the first 20 counting numbers

WE6 For each of the chance experiments in questions **6** to **10**, state the possible outcomes and specify whether each outcome is equally likely to occur or not.

6. Rolling a fair 6-sided die

7. Spinning a spinner where half is white and half is black

8. Spinning a spinner where half is white, a quarter is blue and a quarter is red

9. Rolling a 6-sided die that has the numbers 1, 2, 3, 4, 5, 5 on it

10. Choosing a vowel in the word *mathematics*



Understanding

11. **WE7** Christina rolls a fair 10-sided die with faces numbered from 1 to 10.

- **a.** State all the possible results that could be obtained.
- **b.** Calculate the probability of obtaining:
  - **i.** a 9
  - **ii.** a number less than 7
  - **iii.** a prime number
  - **iv.** a number greater than 3
  - **v.** a multiple of 3.

12. Leo has been given a bag of marbles to play with. Inside the bag, there are 3 blue, 6 red, 4 green and 7 black marbles. If Leo takes out one marble from the bag, calculate:


- **a.** Pr(getting a red marble)
- **b.** Pr(getting a green marble)
- **c.** Pr(getting a black marble)
- **d.** Pr(getting a blue or black marble)
- **e.** Pr(getting a green, red or blue marble)
- **f.** Pr(getting a green, red, blue or black marble).



13. There is a valuable prize behind 2 of the 5 doors in a TV game show. Determine the probability that a player choosing any door will win a valuable prize.

14. **MC** A circular spinner is shown. Select the probability of obtaining an orange sector.

A. $\frac{4}{7}$ **B.** $\frac{1}{7}$ **C.** 75% **D.** $\frac{1}{2}$ **E.** $\frac{3}{7}$



15. **MC** For an octagonal spinner with equal sectors numbered 1 to 8, select the chance of getting a number *between* 2 and 7.

A. $\frac{5}{8}$ **B.** $\frac{3}{8}$ **C.** $\frac{3}{4}$ **D.** 0.5 **E.** 25%

16. A pack of playing cards is shuffled and a card is chosen at random (in no particular order or pattern). Calculate the probability that the card chosen is:

- **a.** a black card (that is, spades or clubs)
- **b.** an ace
- **c.** a diamond
- **d.** a picture card (that is, jack, queen or king)
- **e.** the queen of hearts.



17. A pack of playing cards is shuffled and a card is chosen at random (in no particular order or pattern). Calculate the probability that the card chosen is:

a. a diamond or a black card **b.** not a king **c.** a club, diamond, heart or spade
d. not a spade **e.** red and a ten.

Reasoning

18. If we know the probability of an event occurring, explain how we can work out the probability of it not occurring.

19. In a raffle where there is only 1 prize (a car), 100 000 tickets have been sold, at a cost of $5.00 each.



a. Determine the chance of winning the prize for a buyer who:
- **i.** purchases only 1 ticket
- **ii.** purchases 20 tickets
- **iii.** purchases 50 tickets
- **iv.** purchases all the tickets.

b. If someone bought all the tickets in the raffle, explain whether they had made a wise purchase.

20. Answer the following questions with full working.

a. If you had only one pair of shoes, determine what the probability would be that you would wear that pair of shoes on any given day.
b. If you had two pairs of shoes, determine what the probability would be that you would wear a certain pair of shoes on any given day.
c. If you had seven pairs of shoes, determine what the probability would be that you would wear a certain pair of shoes on any given day.
d. If you had seven pairs of shoes but two pairs were identical, state what the probability would be that you would wear one of the two identical pairs of shoes on any given day.
e. Explain what happens to the probability when the number of pairs of shoes increases.
f. Explain what happens to the probability when the number of identical pairs of shoes increases.

Problem solving

21. Melbourne City FC is a soccer team in the Australian A-league. Over its history the team has won 60% of its matches, and lost half as many as it has won. If one of the team's past matches is selected at random, determine the probability that the match was a draw.

22. At Jaca college there are 220 Year 7 students, with a gender split of 55% girls and 45% boys. Every morning, 59 Year 7 students catch a bus to school. If one third of Year 7 boys catch a bus to school every morning, determine the probability that a randomly selected Year 7 student is a girl who does not catch a bus to school.

23. An apple, a banana, an orange, a peach and a bunch of grapes are in May's fruit basket. If she chooses two fruits to take to school with her lunch, determine the probability that one of the fruits is a banana.



13.5 Experimental probability

LEARNING INTENTION

At the end of this subtopic you should be able to:

- calculate experimental probabilities from data and by performing repeated trials of a chance experiment.

13.5.1 Experimental probability

eles-4714

- In real life, the chance of something occurring may be based on factors other than the number of favourable and possible outcomes.

  For example, the chances of you beating your friend in a game of tennis could theoretically be $\frac{1}{2}$, as you are one of 2 possible winners. In practice, however, there are other factors (such as experience and skill) that would influence your chance of winning.
- A **trial** is one performance of an experiment to collect a result.
- An **experiment** is a process that allows us to collect data by performing trials. In experiments with repeated trials, it is important to keep the conditions for each trial the same.
- A **successful trial** is one that results in the desired outcome.
- The **experimental probability** of an event is found by conducting an experiment and counting the number of times the event occurs.

Experimental probability

- The experimental probability of a particular result or event is defined as:

$$\textbf{Pr(event)} = \frac{\textbf{number of successful trials}}{\textbf{total number of trials}}$$

WORKED EXAMPLE 8 Calculating experimental probability

A coin is flipped 10 times and the results are seven Heads and three Tails. Calculate the experimental probability of obtaining a Tail.



THINK	WRITE
1. Obtaining a Tail is considered a success. Each flip of the coin is a trial.	$\text{Pr(sucess)} = \frac{\text{number of successful trials}}{\text{total number of trials}}$
2. Tails was flipped three times, so there were three successful trials out of a total of 10 trials.	$\text{Pr(Tail)} = \frac{3}{10}$ $= 0.3$

13.5.2 Long-term trends

eles-4715

- The more times an experiment is performed, the more accurate the experimental probability becomes.
- In fair experiments, the **long-term trend** (that is, the trend observed for results from a very large number of trials) shows that the results obtained through experimental probability will match those of theoretical probability.

WORKED EXAMPLE 9 Investigating experimental probability

a. Copy the following table. Toss a coin 10 times and record the result in row 1 of the table.

Experiment	Heads		Tails	
number	Tally	Count	Tally	Count
1				
2				
3				
4				
5				
6				
	Total		Total	

b. Calculate the probability of obtaining a Head from your experiment.
c. Calculate the probability of obtaining a Tail from your experiment.
d. Discuss how these values compare with the theoretical results.
e. Repeat step a another 5 times and combine all of your results.
f. Explain how the combined result compare with the theoretical results.

THINK

a. Toss a coin 10 times and record the results in the first row of the table.
Notes: (a) Place a stroke in the appropriate tally column each time an outcome is obtained. Five is denoted by a 'gatepost': that is, 4 vertical strokes and 1 diagonal stroke (𝍸). (b) The same coin must be used throughout the experiment. The style of the toss and the surface the coin lands on must be the same.

b. 1. For experiment 1, calculate the probability of obtaining a Head using the rule.

2. Substitute the given values into the rule.

3. Evaluate and simplify.

WRITE

a.

	Heads		Tails	
Exp. No.	Tally	Count	Tally	Count
1	𝍸	4	𝍸 |	6
2	𝍸	4	𝍸 |	6
3	𝍸 ||	7	|||	3
4	|||	3	𝍸 ||	7
5	𝍸	4	𝍸 |	6
6	𝍸 |||	8	||	2
	Total	30	Total	30

b. $\Pr(\text{event}) = \dfrac{\text{number of favourable outcomes}}{\text{number of possible outcomes}}$

$\Pr(\text{Heads}) = \dfrac{\text{number of Heads obtained}}{\text{total number of tosses}}$

$\Pr(\text{Heads}) = \dfrac{4}{10}$

$= \dfrac{2}{5}$

4. Convert the fraction to a percentage by multiplying by 100%.

As a percentage $\frac{2}{5} = \frac{2}{5} \times 100\%$
$= \frac{200}{5}\%$
$= 40\%$

5. Answer the question.

The probability of obtaining a Head in this experiment is $\frac{2}{5}$ or 40%

c. 1. For experiment 1, calculate the probability of obtaining a Tail for this experiment.

c. $\text{Pr(Tails)} = \frac{\text{number of Tails obtained}}{\text{total number of tosses}}$

2. Substitute the given values into the rule and simplify.

$\text{Pr(Tails)} = \frac{6}{10}$
$= \frac{3}{5}$

3. Convert the fraction to a percentage by multiplying by 100%.

As a percentage $\frac{3}{5} = \frac{3}{5} \times 100\%$
$= \frac{300}{5}\%$
$= 60\%$

The probability of obtaining a Tail in this experiment is $\frac{3}{5}$ or 60%.

d. Compare the results obtained in parts **b** and **c** with the theoretical results.

d. The experimental value obtained for the Pr(Heads) is $\frac{2}{5}$ (or 40%) and Pr(Tails) is $\frac{3}{5}$ (or 60%). The theoretical value of these probabilities is $\frac{1}{2}$ (or 50%). Therefore, the experimental probabilities differ from the theoretical probabilities by 10%.

e. 1. Repeat the procedure of part **a** 5 times.

2. Calculate the total number of Heads and Tails obtained and enter the results in the table.

e. Refer to the results in the table in part a.

f. 1. Calculate the probability of obtaining a Head for all 10 experiments combined.

f. $\text{Pr(Heads)} = \frac{\text{number of Heads obtained}}{\text{total number of tosses}}$

2. Substitute the given values into the rule and simplify.

$\text{Pr(Heads)} = \frac{30}{60}$
$= \frac{1}{2}$

3. Convert the fraction to a percentage by multiplying by 100%.

As a percentage $\frac{1}{2} = \frac{1}{2} \times 100\%$
$= \frac{100}{2}\%$
$= 50\%$

The probability of obtaining a Head in all 10 experiments is $\frac{1}{2}$ or 50%.

4. Calculate the probability of obtaining a Tail for all 10 experiments combined.

$$\Pr(\text{Tails}) = \frac{\text{number of Tails obtained}}{\text{total number of tosses}}$$

$$\Pr(\text{Tails}) = \frac{30}{60}$$

$$= \frac{1}{2}$$

$$\text{As a percentage } \frac{1}{2} = \frac{1}{2} \times 100\%$$

$$= \frac{100}{2}\%$$

$$= 50\%$$

The probability of obtaining a Tail in all 10 experiments is $\frac{1}{2}$ or 50%.


5. Compare the combined result obtained with the theoretical results.

The combined results in this experiment produced probability values that were equal to the theoretical probability values.

Therefore, the long-term trend of obtaining a Head or Tail when tossing a coin is equal to $\frac{1}{2}$.

Digital technology

Chance experiments can be simulated using simple devices (such as coins or dice) or by using technology. Examples include random number generators in Excel spreadsheets or online adjustable spinner simulators, as shown. These simulators allow you to select the number of sectors and the number of spins (trials) and let the simulation run. You will notice that the experimental probabilities get closer to the theoretical probabilities as you increase the number of spins.



Resources

eWorkbook Topic 13 Workbook (worksheets, code puzzle and project) (ewbk-1914)

Interactivities Individual pathway interactivity: Experimenting with chance (int-4366)
Experimenting with chance (int-4030)
Experimental probability versus theoretical probability (int-4031)
Generating random numbers on an Excel spreadsheet (int-4032)
Simulations (int-5352)

Exercise 13.5 Experimental probability

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 4, 9, 10, 13	2, 5, 7, 11, 14	6, 8, 12, 15

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE8 Teagan was playing the game Trouble and recorded the number of times she rolled a 6. During the game, she was successful 5 times out of the 25 times she tried. Calculate the experimental probability of rolling a 6 in the game.
2. In the 2020 AFL season, the Brisbane Lions won 14 out of 17 games. Determine the experimental probability of the Lions winning a game in 2020.
3. WE9

Experiment number	Heads		Tails	
	Tally	Count	Tally	Count
1				
2				
3				
4				
5				
6				
	Total		Total	

   a. Copy the table provided. Toss a coin 10 times and record the results in the first row of the table.
   b. Calculate the experimental probability of obtaining a Head.
   c. Calculate the experimental probability of obtaining a Tail.
   d. Discuss how these values compare with the theoretical results.
   e. Repeat step a another 5 times and combine all your results.
   f. Explain how the combined result compare with the theoretical results.

4. If you wanted to create a device that would give a theoretical probability of achieving a particular result as $\frac{1}{4}$, state how many sections a spinner such as this would need to be divided into.
5. Determine how you would divide or colour a spinner if you wanted to achieve the probability of a success equal to $\frac{3}{10}$.

6. Two students conducted a chance experiment using a standard 6-sided die. The results were recorded in the following table.

Experiment number	Even number		Odd number	
	Tally	Count	Tally	Count
1	|||	3	||	2
2	||||	4	|	1
3	||	2	|||	3

a. Describe in words the experiment that was conducted by the two students.
b. State the number of times they conducted the experiment.
c. Calculate the theoretical probability of rolling an even number.
d. Compare the experimental probability with the theoretical probability of rolling an even number.
e. Compare the experimental probability with the theoretical probability of rolling an odd number.

Understanding

7. Toss a coin 60 times, tallying up the number of Heads and Tails that you toss in trials of 10 tosses at a time. (If you have already completed question 3, you may use the results you obtained from that experiment).

a. The long-term trend of the probability of obtaining a Head on the toss of a coin is the Pr(Heads) from your experiment.
Determine the long-term trend of the probability after:

i. 10 tosses of the coin
ii. 20 tosses of the coin
iii. 30 tosses of the coin
iv. 60 tosses of the coin.

b. Obtain a classmate's 60 results. Combine these with yours. State the long-term trend of Pr(Heads) obtained.
c. Combine your pair's 120 results with those of another pair. State the long-term trend of Pr(Heads) obtained.
d. Finally, count the results obtained by the whole class for this experiment. (Make sure nobody's results are counted twice.) You should have 60 tosses per person. State the long-term trend of Pr(Heads) obtained.
e. Copy and complete the following table.

Number of tosses	Heads		Tails	
	Pr(Heads)	Pr(Heads) as percentage	Pr(Tails)	Pr(Tails) as percentage
10				
20				
30				
60				
120				
240				
Whole class (specify number of tosses)				

f. Comment on the changes of the long-term trend value of Pr(Heads) as you toss the coin more times.

8. Use a random number generator to simulate a 5-colour spinner.
   a. Determine the chance of getting any one of the five colours when you spin the spinner (theoretically).
   b. Spin the spinner 10 times and, using a table such as the following one, record your results.

Colour	1	2	3	4	5
Number of times it occurs					

   c. From your results, list the probabilities of obtaining each colour. For example, divide the number of times a particular colour was obtained by the total number of spins (that is, 10).
   d. Explain why these probabilities might not be the same as the theoretical probability would suggest.
   e. Spin your spinner and record the results for another 10 spins.
   f. Spin your spinner so that you have 100 results. Is the experimental probability closer to the pure probability? Why might this be? Discuss.

Reasoning

9. Cory records the fact that it has rained on 65 out of 365 days in a year.
   a. Write the number of days that it has rained as a simple fraction.
   b. Karen says that since any day can be wet or dry, the probability of rain on any day is $\frac{1}{2}$. Explain whether Karen is correct.
   c. Determine the experimental probability of rain on any given day, expressed as a decimal, correct to 2 decimal places.

10. a. Conduct the following experiments:
      i. Toss a coin 10 times and record the number of Heads and Tails that occur.
      ii. Toss a coin 25 times and record the number of Heads and Tails that occur.
      iii. Toss a coin 50 times and record the number of Heads and Tails that occur.
      iv. Toss a coin 100 times and record the number of Heads and Tails that occur.
   b. Calculate the experimental probability for each experiment.
   c. Compare these values and explain your findings.

11. A die is rolled 30 times, giving the following results.



4	3	5	4	3	5	2	1	1	5
3	2	2	4	1	3	1	6	1	3
2	1	6	6	3	5	1	3	5	3

   a. Display these results in a frequency table.
   b. Calculate the probability of obtaining a 6 when you roll a die.
   c. Calculate how many times you would expect to obtain a 6 in 30 rolls of a die.
   d. Explain the difference between your expected results and the actual results shown in this question.

12. You have calculated previously that the chance of getting any particular number on a 6-sided die is $\frac{1}{6}$. You have 2 different coloured dice. Explain whether there is any difference in your dice apart from colour and whether one could be biased (more likely to give a particular result than theory says it should).
   a. Design a test to determine whether the dice you have are fair. Write down what you are going to do.
   b. Perform your test and record results.
   c. Determine the probability of getting each of the numbers on each of your dice, based on your tests and on the long-term trend you have observed.
   d. State what your test says about your two dice. Explain whether there are any things that need to be considered before giving your answer. (Perhaps your dice have slightly uneven shapes or something that might cause them to lean towards one result more than others.)




Problem solving

13. Inside a bag are 36 shapes that are either squares or triangles. One shape is taken out at random, its shape noted and put back in the bag. After this is repeated 72 times, it is found that a triangle was taken out 24 times. Estimate how many triangles and how many squares there are in the bag.

14. In your desk drawer, there are 5 identical red pens and 6 identical black pens. Determine the smallest number of pens you have to remove from the drawer in the dark so that you will be absolutely sure of having:

a. 2 black pens
b. 2 red pens
c. 1 black pen and 1 red pen.
d. Explain your answers to parts **a**, **b** and **c**.

15. Jim operates a parachute school. Being a man who is interested in statistics, he keeps a record of the landing position of each jump from first-time parachutists. With experience, parachutists are able to land on a particular spot with great accuracy. However, first-time parachutists do not possess this ability.
Jim has marked out his landing field with squares, as shown here.





We are going to look at the areas of each of the regions A, B and C. To do this, we will determine each of the areas in terms of one of the small squares in region A. We will say that each small square has an area of 1 square unit.

a. Determine the area of Jim's whole landing field (in square units).
b. Determine the areas of regions A, B and C (in square units).
c. Assuming that the parachutist lands in the field, calculate the probability that the landing will occur in:

i. region A
ii. region B
iii. region C.

These represent theoretical probabilities.

d. Jim's records indicate that, from 5616 jumps of first-time parachutists, the landing positions were:

i. 592 in region C
ii. 1893 in region B
iii. 3131 in region A.

Comment on these results in comparison with the probabilities you calculated in part **c**.

13.6 Review


13.6.1 Topic summary

Understanding probability

- Probability looks at how **likely** something is to happen.
- Probabilities are stated as a number between 0 and 1 inclusive, where 0 corresponds to *impossible* and 1 corresponds to *certain*. That is,

0 ≤Probability ≤1

- Different words or phrases in the English language can be associated with different probabilities, as indicated on the probability scale below.





INTRODUCTION TO PROBABILITY

The language of chance

- A **chance experiment** is an experiment in which there are several different possible outcomes, each having a defined chance of occurring.
  e.g. Rolling a die is a chance experiment.
- An **outcome** is a possible result of a chance experiment, such as rolling a 2.
- An **event** is either a single outcome (e.g. rolling a 4) or a collection of outcomes (e.g. rolling a 1, 2 or 3).
- The **sample space**, S, is the set of *all* possible outcomes of a chance experiment.
  e.g. The sample space of rolling a fair six-sided die is $S = \{1, 2, 3, 4, 5, 6\}$.
- The number of elements in the sample space is often important in probability. It is denoted by the symbol $n(S)$.

Calculating probability

- A *favourable outcome* is one that we are looking for.
- *Equally likely outcomes* have an equal chance of occurring.
- The **theoretical probability** of an event occurring is defined as:

$$\textbf{Pr(event)} = \frac{\textbf{number of favourable outcomes}}{\textbf{total number of outcomes}}.$$

e.g. Consider the following chance experiments.

Rolling a die: $\Pr(\text{rolling a 1}) = \frac{1}{6}$

Flipping a coin: $\Pr(\text{Tail}) = \frac{1}{2}$ (or 0.5)

Picking a card from a deck of cards:
$\Pr(\text{diamond}) = \frac{13}{52} = \frac{1}{4}$ (or 0.25)

Experimental probability

- The **experimental probability** of an event is determined by the results of repeated trials of the experiment.
- $$\textbf{Pr(event)} = \frac{\textbf{number of successful trials}}{\textbf{total number of trials}}$$

  e.g. If a team has won 42 out of their last 70 matches, the experimental probability that they will win a match is $\frac{42}{70} = \frac{3}{5} = 60\%$.
- The experimental probability of an event becomes more accurate as the number of trials increases, and approaches the theoretical probability.

13.6.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)


Subtopic	Success criteria			
13.2	I understand that a probability is a number between 0 and 1 that describes the possibility of an event.			
	I can classify the chance of an event occurring using words such as *certain*, *likely*, *unlikely*, *even chance* or *impossible*.			
13.3	I can determine the outcomes and sample space of a chance experiment.			
	I can identify the sample space of a two-step chance experiment using a two-way table.			
13.4	I can calculate theoretical probabilities.			
13.5	I can calculate experimental probabilities from data and by performing repeated trials of a chance experiment.			

13.6.3 Project

Snakes, ladders and probability!

In the game of snakes and ladders, you roll 2 dice, add the 2 numbers that appear on the uppermost faces to get a total, and move a marker the total number around a 100-square board. If you are lucky and your marker lands on the base of a ladder, you can advance more quickly in the game by 'climbing' to the top of the ladder. However, if your marker lands on the head of a snake, you must 'slide down' the length of the snake.

1. Complete the following table to show the possible totals when 2 dice are rolled. Some of the values have been included for you.
2. List the sample space for the possible totals when 2 dice are rolled.
3. Determine which total appears the most.
4. Determine which total appears the least.
5. Calculate the probability of getting a total of 3 when 2 dice are rolled.



Die 2 \ Die 1	1	2	3	4	5	6
1	2	3	4			
2	3	4	5			
3	4					
4						
5						
6						

Using the table that shows the frequency of the totals, we can investigate the probabilities involved in moving around the snakes and ladders board. The following situations will enable you to investigate some of the possibilities that occur in snakes and ladders.

6. Imagine you landed on square 95 and slid down the snake to square 75. What total would you need to get to go up the ladder at square 80 on your next move? Determine the number of ways in which this total can be achieved in one turn.
7. If you slid down the snake at square 87, is it possible to move up the next ladder with your next turn? Explain.
8. Explain what would happen if you were on square 89 and rolled two 1s and rolled two 1s again with your next turn. Discuss what would be the likelihood of this happening in a game.
9. Describe how you could get from square 71 to square 78 in one turn. Work out the probability of this happening.
10. Imagine you had a streak of luck and had just climbed a ladder to square 91. Your opponent is on square 89. Explain which player has the greater chance of sliding down the snake at square 95 during the next turn.
11. Investigate the different paths that are possible in getting from start to finish in the fewest turns. For each case, explain the totals required at each turn and discuss the probability of obtaining these totals.

Play a game of snakes and ladders with a partner. Examine your possibilities after each turn, and discuss with each other the likelihood of moving up ladders and keeping away from the snakes' heads as you both move around the board.

Resources

eWorkbook Topic 13 Workbook (worksheets, code puzzle and project) (ewbk-1914)

Interactivities Crossword (int-2596)
Sudoku puzzle (int-3171)

Exercise 13.6 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. For each of the given statements, specify whether the chance of the following events occurring is certain, likely, even chance, unlikely or impossible.
   a. Australia is in the Southern Hemisphere.
   b. You will still be alive in the next century.
   c. You obtain an even number on a circular spinner numbered from 1 to 16.

2. For each of the given statements, specify whether the chance of the following events occurring is certain, likely, even chance, unlikely or impossible.
   a. England is in the Southern Hemisphere.
   b. You roll a fair die and obtain a number less than or equal to 4.
   c. Humans can survive without water indefinitely.

3. List one event for which the chance of it occurring would be:
   a. impossible b. certain c. unlikely

4. Copy the number line and place the following words on it to indicate what sort of chance each number would represent: *certain*, *very unlikely*, *unlikely*, *likely*, *highly likely*, *highly unlikely*, *even chance*, *impossible*, *very likely*



5. List the sample space for the following chance experiments.
   a. Tossing a coin
   b. Drawing a marble out of a bag containing red, green and blue marbles
   c. Answering a true/false question in a test

6. List the sample space for the following chance experiments.
   a. Rolling a 6-sided die
   b. Spinning a circular spinner numbered from 1 to 10
   c. Competing in a race in which there are 9 runners

7. For each of the following, state the number of elements in the sample space, $n(S)$.
   a. The first prize in a raffle is chosen from tickets numbered from 1 to 5000.
   b. A card is selected from the red cards in a standard deck.
   c. A circular spinner numbered 1 to 5 is spun.
   d. A day is selected in the month of July.



8. A six-sided die labelled 1, 2, 3, 3, 4, 5 is rolled.
State:
a. Pr(getting a 5)
b. Pr(getting a 3)
c. Pr(getting an even number)
d. Pr(getting an odd number).

9. A six-sided die labelled 1, 2, 3, 3, 4, 5 is rolled.
State:
a. Pr(getting a number greater than or equal to 3)
b. Pr(getting a number less than 3)
c. Pr(getting a 0)
d. Pr(getting a 6).

10. A person has a normal pack of cards and draws one out.
Calculate:
a. Pr(picking a heart)
b. Pr(picking a spade)
c. Pr(picking a picture card)
d. Pr(picking a card with a number less than 5 on it). Do not count an ace as a number.

11. Ten cards are numbered from 1 to 10, shuffled and placed face down on a table. If a card is selected at random, calculate the probability that the card selected is:
a. 4
b. an even number
c. divisible by 3
d. an even number and divisible by 3.

12. Ten cards are numbered from 1 to 10, shuffled and placed face down on a table. If a card is selected at random, calculate the probability that the card selected is:
a. an even number or divisible by 3
b. not divisible by 3
c. greater than 8
d. 12.

13. A sample of 250 students at a particular school found that 225 of them had access to the internet at home. Given this sample is a good representation for the entire school, calculate the probability that a student selected at random in the school will have internet access at home.




14. Use a table to show the sample space for the experiment 'tossing a coin and rolling a die'.
Calculate:
a. Pr(a Tail and a number less than 3)
b. Pr(a Head and a number greater than 3)
c. Pr(a Tail and an even number)
d. Pr(a Head and a prime number).

15. Use a table to show the sample space for the experiment 'spinning a spinner with 10 sectors and rolling a die'.
Determine:
a. Pr(the sum totals to an even number)
b. Pr(odd number on the spinner and an even number on the die)
c. Pr(both digits having a value less than 5)
d. Pr(the sum totals to a value between 7 and 10)
e. Pr(the sum totals to a value greater than or equal to 13 but less than 16)
f. Pr(the sum totals to a prime number).

Problem solving

16. In your sock drawer there are 4 identical blue socks and 5 identical black socks. Determine the smallest number of socks you can take from the drawer in the dark so that you will be absolutely sure of having:
- **a.** a pair of black socks
- **b.** a pair of blue socks
- **c.** a black pair and a blue pair of socks.

17. The arrows on Spinner A and Spinner B are spun. (If an arrow lands on a line, the spinner is spun again.) The two numbers are added to get a score. For example, in the diagram the score is 10.



Spinner A Spinner B

- **a.** Determine the highest total score possible.
- **b.** Determine the possible total scores.
- **c.** List all the ways to get a total score of 8.
- **d.** Determine the probability of getting a total of 9.
- **e.** Determine the probability of getting a total score of 10.
- **f.** Draw a grid showing the probabilities of getting all possible totals.

18. Charlotte and Rhianna have a flower garden. They have 17 red flowers, 12 pink flowers and 13 yellow flowers. Charlotte picks some flowers for her vase. She selects 6 red flowers, 3 pink and 3 yellow flowers. If Rhianna picks a flower at random for her hair, determine the probability that it is yellow.



19. A bowl contains blue marbles and white marbles. If there are twice as many blue marbles as white marbles, determine the probability that a blue marble is selected.

20. Chloë is a contestant on a game show. There are five sealed cases on the podium and each of the cases contains one of the following amounts: $1, $50, $500, $1000 and $5000. The game show host offers her a deal of $400, or she can choose a case and keep the amount of money in it, instead. Determine the probability she will win more than the $400 the host is offering.



21. Rebecca plays a sideshow game where she puts four balls into a clown's mouth, and the balls then fall into slots numbered 1 to 6. To win, one of her balls must go into slot 6.
She has noticed that the numbers 2 and 5 come up 4 times as often as 1 and 6, and the numbers 3 and 4 come up 5 times as often as 1 and 6. Determine the probability that she will get a 6.



22. You have a spinner. Draw a pie or circle graph to represent the following list of colours and their associated sectors of the circle, in degrees.
Discuss the chances of landing on each of the colours. List the likelihoods from smallest to largest.

Colour	Degree
Yellow	25°
Orange	40°
Green	60°
Pink	100°
Purple	15°
Blue	120°

on To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1914) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0702) ☐

Digital documents

13.2 SkillSHEET Understanding 'chance' words (doc-6522) ☐
SkillSHEET Comparing the likelihood of different events occurring (doc-6523) ☐
SkillSHEET Describing the chance of an event occurring as more or less than half (doc-6524) ☐
13.4 SkillSHEET Listing all possible outcomes for an event (doc-6525) ☐
SkillSHEET Understanding a standard deck of playing cards (doc-6526) ☐
SkillSHEET Writing a simple probability as a fraction (doc-6527) ☐

Video eLessons

13.2 The language of chance (eles-4710) ☐
13.3 The sample space (eles-4711) ☐
Two-way tables (eles-4712) ☐
13.4 Simple probability (eles-4713) ☐
13.5 Experimental probability (eles-4714) ☐
Long-term trends (eles-4715) ☐

Interactivities

13.2 Individual pathway interactivity: The language of chance (int-4362) ☐
Chance (int-4026) ☐
13.3 Individual pathway interactivity: The sample space (int-4363) ☐
The sample space (int-4027) ☐
Tables and sample spaces (int-4029) ☐
13.4 Individual pathway interactivity: Simple probability (int-4364) ☐
Simple probability (int-4028) ☐
13.5 Individual pathway interactivity: Experimenting with chance (int-4366) ☐
Experimenting with chance (int-4030) ☐
Experimental probability versus theoretical probability (int-4031) ☐
Generating random numbers on an Excel spreadsheet (int-4032) ☐
Simulations (int-5352) ☐
13.6 Crossword (int-2596) ☐
Sudoku puzzle (int-3171) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers

Topic 13 Introduction to Probability

Exercise 13.1 Pre-test

1. C
2. E
3. $\frac{1}{5}$
4. B
5. 4
6. 4
7. A
8. B
9. B
10. $\frac{1}{5}$
11. E
12. $\frac{11}{40}$
13. B
14. D
15. 5

Exercise 13.2 The language of chance

1. a. Certain
   b. Likely
   c. Impossible
   d. Likely
   e. Unlikely
2. a. Unlikely
   b. Even chance
   c. Certain
   d. Certain
   e. Even chance
3. a. $\frac{1}{2}$ (or 0.5)
   b. 0
   c. $\frac{1}{5}$ (or 0.2)
   d. $\frac{1}{3}$
4. a. $\frac{1}{2}$ (or 0.5)
   b. 1
   c. 1
   d. 0.3–0.7. Any value within this range is reasonable.
5. A
6. A
7. D, C, A, B
8. Sample responses can be found in the worked solutions in the online resources.
9. a. 1
   b. 0.75
   c. 0.25
   d. 0.75
   e. 0.25
10. a. 0.25
    b. 1
    c. 0.25
    d. 0
    e. 0.75
11. a. 1
    b. 0
    c. 0.5
    d. 0.5
12. a. It is impossible because Tuesday always follows Monday.
    b. It is certain because the 29th always follows the 28th day of the month. However, if the month is February, depending on whether the year is a leap year or not, the chance is either impossible or certain.
    c. It has an equal chance or a fifty-fifty chance if it is a coin with a Head on one side and a Tail on the other side.
13. Equal chance: 50% or $\frac{1}{2}$ or 0.5.
14. There are 3 odd-numbered balls (1, 3, 5) and only 2 even-numbered balls (2, 4). Therefore you are more likely to draw an odd-numbered ball from the bag than an even-numbered ball.
15. a. Highly unlikely because there is only one piece with the letter I. The chance is $\frac{1}{10}$ or 0.1.
    b. Equal chance because there are five pieces with the letter A and five pieces with other vowels.
    c. Impossible because there are no pieces with the letter U.
    d. Unlikely because the chance is $\frac{3}{10}$ or 0.3.
16. a. The two girls are living in two different countries.
    b. Time zones in different places, night-time and daytime in different places in the world.
17. a. Rolling a 7
    b. Rolling a 1
    c. Rolling an even number
    d. Rolling a number that is greater than 1
    e. Rolling a number that is less than 10

Exercise 13.3 The sample space

1. $S = \{1, 2, 3, 4, 5, 6, 7, 8, 9, 10\}$
2. $S = \{\text{Heads, Tails}\}$
3. $S = \{A, B, C, D, E\}$
4. $S = \{\text{win, loss, draw}\}$
5. $S = \{\text{ace of clubs, ace of spades, ace of hearts, ace of diamonds}\}$
6. $S = \{A, B, C, D, E, F\}$
7. a. $S = \{\text{clubs, spades, diamonds, hearts}\}$
   b. $S = \{\text{red, black}\}$
8. $S = \{\text{red, green, orange}\}$
9. 2
10. a. 52
    b. 45
    c. 18
    d. 365 (or 366 in a leap year)
11. a. 26
    b. 180 000
    c. 4
    d. 3
12. E
13. a.

	Heads	Tails
Blue	Blue, H	Blue, T
Green	Green, H	Green, T
Orange	Orange, H	Orange, T

    $S = \{(\text{Blue, H}), (\text{Blue, T}), (\text{Green, H}), (\text{Green, T}), (\text{Orange, H}), (\text{Orange, T})\}$
    b. $n(S) = 6$

14. a.

Die \ Spinner	A	B	C
1	A1	B1	C1
2	A2	B2	C2
3	A3	B3	C3
4	A4	B4	C4
5	A5	B5	C5
6	A6	B6	C6

{(A, 1), (A, 2), (A, 3), (A, 4), (A, 5), (A, 6),
(B, 1), (B, 2), (B, 3), (B, 4), (B, 5), (B, 6),
(C, 1), (C, 2), (C, 3), (C, 4), (C, 5), (C, 6)}

b. 18

15. a.

	1	2	3
1	(1, 1)	(1, 2)	(1, 3)
2	(2, 1)	(2, 2)	(2, 3)
3	(3, 1)	(3, 2)	(3, 3)
4	(4, 1)	(4, 2)	(4, 3)
5	(5, 1)	(5, 2)	(5, 3)

$S = \{(1, 1),\ (2, 1),\ (3, 1),\ (4, 1),\ (5, 1),\ (1, 2),$
$(2, 2), (3, 2),\ (4, 2),\ (5, 2),\ (1, 3),\ (2, 3),\ (3, 3),$
$(4, 3),\ (5, 3)\}$

b. $S = \{2,\ 3,\ 4,\ 5,\ 6,\ 7,\ 8\}$

16. A chance experiment is an experiment in which the outcome is left to chance. An outcome is any possible result of the chance experiment. An event can describe either one outcome or a collection of outcomes. The sample space is a list of all possible outcomes.

17. It depends on whether each element has an equal chance of occurring. In the sample space for rolling a die, each element is equally likely to occur. In more complex experiments, each event may not be likely to occur.

18. 12 different ways:
20, 20, 10; 20, 20, 5, 5; 20, 10, 10, 10;
20, 10, 10, 5, 5; 20, 10, 5, 5, 5, 5; 20, 5, 5, 5, 5, 5, 5;
10, 10, 10, 10, 10; 10, 10, 10, 10, 5, 5;
10, 10, 10, 5, 5, 5, 5; 10, 10, 5, 5, 5, 5, 5, 5;
10, 5, 5, 5, 5, 5, 5, 5, 5; 5, 5, 5, 5, 5, 5, 5, 5, 5, 5;

19. 15 choices

20. 12

21. 11

22. 18 ways

Exercise 13.4 Simple probability

1. 12 : 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12

2. 5 : 1, 2, 3, 4, 5

3. 2 : C, L

4. 2 : 4, 6

5. 10 : 1, 3, 5, 7, 9, 11, 13, 15, 17, 19

6. 1, 2, 3, 4, 5, 6. All equally likely.

7. White, black. Each is equally likely.

8. White, blue, red. It is more likely you will get white rather than red or blue, because white takes up a bigger area.

9. 1, 2, 3, 4, 5. It is more likely that a five will be rolled because it appears twice on the die.

10. a, e, i. It is more likely that a consonant would be obtained as there are 7 consonants and 4 vowels.

11. a. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10

b. i. $\frac{1}{10}$ **ii.** $\frac{3}{5}$ **iii.** $\frac{2}{5}$ **iv.** $\frac{7}{10}$ **v.** $\frac{3}{10}$

12. a. $\frac{3}{10}$ **b.** $\frac{1}{5}$ **c.** $\frac{7}{20}$
d. $\frac{1}{2}$ **e.** $\frac{13}{20}$ **f.** 1

13. $\frac{2}{5}$

14. E

15. D

16. a. $\frac{1}{2}$ **b.** $\frac{1}{13}$ **c.** $\frac{1}{4}$ **d.** $\frac{3}{13}$ **e.** $\frac{1}{52}$

17. a. $\frac{3}{4}$ **b.** $\frac{12}{13}$ **c.** 1 **d.** $\frac{3}{4}$ **e.** $\frac{1}{26}$

18. An event must either occur or not occur — there is no other option. If we know the probability of an event occurring, the probability it will not occur is 1 − P (event).

19. a. i. $\frac{1}{100\,000}$
ii. $\frac{1}{5000}$
iii. $\frac{1}{2000}$
iv. 1

b. It would not be a very wise purchase because the total cost would be \$500 000 unless of course the car was worth more than \$500 000.

20. a. 100% **b.** 50%
c. $\frac{1}{7}$ **d.** $\frac{2}{7}$
e. Decrease **f.** Increase

21. $0.1 = 10\%$

22. $\frac{95}{220} = \frac{19}{44} \approx 43\%$

23. The probability of taking a banana is $\frac{2}{5}$.

Exercise 13.5 Experimental probability

1. $\frac{1}{5}$

2. $\frac{14}{17} \approx 82\%$

3. a.

Exp. No.	Heads		Tails	
	Tally	Count	Tally	Count
1	𝍸	4	𝍸 |	6
2	|	1	𝍸 𝍸	9
3	𝍸 |	6	𝍸	4
4	𝍸 |||	8	||	2
5	𝍸	4	𝍸 |	6
6	𝍸 ||	7	|||	3
	Total	30	Total	30

Note: This is only one possible solution. Answers will differ each time.

b. $\frac{2}{5}(40\%)$

c. $\frac{3}{5}(60\%)$

d. The theoretical value for both results is $\frac{1}{2}(50\%)$. They differ by 10%.

e. Refer to table.

f. The combined result equals the theoretical value.

4. 4

5. Divide the spinner into 10 sections; 3 of these sections will be shaded in 1 colour and 7 sections will be shaded in another colour.

6. a. The students rolled a die 5 times and recorded whether the result was an odd number or an even number.

b. 3 times

c. 0.5

d. The experimental probability was 0.6; this is 0.1 higher than the theoretical probability.

e. The experimental probability was 0.4, this is 0.1 lower than the theoretical probability.

7. Values will differ for each group. As you complete more trials, you will probably notice the values you get experimentally are closer to those you would expect from theoretical probability $\left(\frac{1}{2} \text{ or } 50\%\right)$. If this is not occurring, you will probably need more trials.

8. a. $\frac{1}{5}$

b.

Colour	1	2	3	4	5
Number of times it occurs		||	||	||||	||

c. $P(1) = 0,\ P(2) = \frac{1}{5},\ P(3) = \frac{1}{5},\ P(4) = \frac{2}{5},\ P(5) = \frac{1}{5}$

Note: This is only one possible solution. Answers will differ each time.

d. Your spinner may not be evenly balanced and this may lead to an increased likelihood of getting one result or another.

e-f. Values will differ for each group. As you complete more trials, you will probably notice the values you get experimentally are closer to those you would expect from theoretical probability $\left(\frac{1}{5} \text{ or } 20\%\right)$. If this is not occurring, you will probably need more trials.

9. a. $\frac{13}{73}$

b. Karen is not correct, as a wet day (65 out of 365) and a dry day (300 out of 365) are not equally likely.

c. 0.18

10. The general trend as the number of trials increases should show that the probability of getting a Head or a Tail gets closer to 50%.

11. a.

Score	Frequency
1	7
2	4
3	8
4	3
5	5
6	3

b. $P(6) = \frac{1}{6}$

c. 5

d. The result differs by pure chance. The more often we roll the die, the closer we can expect the results to match the expected number of sixes.

12. a. Each die would need to be thrown about 120 times for us to get some impression of whether it is biased or not. The same person would need to roll the die each time in the same manner and onto the same surface.

b.

Number on die	Black	White
1	20	19
2	19	21
3	20	20
4	21	20
5	19	20
6	21	20
Total	120	120

Note: These values will differ each time the experiment is conducted.

c.

Number on die	Probability of black	Probability of white
1	$\frac{20}{120} = \frac{1}{6}$	$\frac{19}{120}$
2	$\frac{19}{120}$	$\frac{21}{120} = \frac{7}{40}$
3	$\frac{20}{120} = \frac{1}{6}$	$\frac{20}{120} = \frac{1}{6}$
4	$\frac{21}{120} = \frac{7}{40}$	$\frac{20}{120} = \frac{1}{6}$
5	$\frac{19}{120}$	$\frac{20}{120} = \frac{1}{6}$
6	$\frac{21}{120} = \frac{7}{40}$	$\frac{20}{120} = \frac{1}{6}$
Total	1	1

The long-term trend suggests that the probability of obtaining each value on either die will be $\frac{1}{6}$.

d. The 2 dice appear to be fair as each value occurred approximately 20 times, which is what we would expect in 120 throws. More trials however could be conducted. It is very important when conducting an experiment such as this that the devices used are even in shape and size and that one doesn't have an advantage over the other.

13. 12 triangles, 24 squares

14. a. 7

b. 8

c. 7

d. In part **a** there are 5 red pens, so, to make sure that you pick 2 black pens, you have to pick $5 + 2 = 7$.
In part **b** there are 6 black pens, so, to make sure that you pick 2 red pens, you have to pick $6 + 2 = 8$.
In part **c** there are 5 red pens and 6 black pens, so, to make sure that you pick 1 black pen and 1 red pen, you have to pick $6 + 1 = 7$.

15. a. 36 square units

b. A = 20 square units, B = 12 square units, C = 4 square units

c. i. $\frac{5}{9}$

ii. $\frac{1}{3}$

iii. $\frac{1}{9}$

d. i. $\frac{37}{351}$, which is approximately 0.11. This is very close to the theoretical probability.

ii. $\frac{631}{1872}$, which is approximately 0.34. This is very close to the theoretical probability.

iii. $\frac{3131}{5616}$, which is approximately 0.56. This is very close to the theoretical probability.

Project

1.

		Die 1					
		1	**2**	**3**	**4**	**5**	**6**
Die 2	**1**	2	3	4	5	6	7
	2	3	4	5	6	7	8
	3	4	5	6	7	8	9
	4	5	6	7	8	9	10
	5	6	7	8	9	10	11
	6	7	8	9	10	11	12

2. {2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12}

3. 7

4. 2, 12

5. $\frac{1}{18}$

6. 5, four different ways.

7. You end up at square 36. The next ladder is at square 51. It is not possible to obtain a 15 when you roll 2 dice.

8. At the end of these two turns, you would end up at square 73. P(two ones in a row) $= \frac{1}{36} \times \frac{1}{36} = \frac{1}{1296}$.

9. You need to roll a total of 7. P(7) $= \frac{1}{6}$.

10. Your opponent has a better chance, because the chance of scoring a 6 is higher than that of scoring a 4.

11. There are many different paths that get from start to finish in 5 turns.

Exercise 13.6 Review questions

1. a. Certain **b.** Unlikely **c.** Even chance


2. a. Impossible **b.** Likely **c.** Impossible

3. a. The month of January having 29 days

b. Tuesday coming after Monday

c. Rolling a 3 on a regular die

4.



5. a. {Head, Tail}

b. {red marble, green marble, blue marble}.

c. {true, false}

6. a. {1, 2, 3, 4, 5, 6}

b. {1, 2, 3, 4, 5, 6, 7, 8, 9, 10}

c. {1, 2, 3, 4, 5, 6, 7, 8, 9}

7. a. 5000 **b.** 26 **c.** 5 **d.** 31

8. a. $\frac{1}{6}$ **b.** $\frac{1}{3}$ **c.** $\frac{1}{3}$ **d.** $\frac{2}{3}$

9. a. $\frac{2}{3}$ **b.** $\frac{1}{3}$ **c.** 0 **d.** 0

10. a $\frac{1}{4}$ **b** $\frac{1}{4}$ **c** $\frac{3}{13}$ **d** $\frac{3}{13}$

11. a. $\frac{1}{10}$ b. $\frac{1}{2}$ c. $\frac{3}{10}$ d. $\frac{1}{10}$

12. a. $\frac{7}{10}$ b. $\frac{7}{10}$ c. $\frac{1}{5}$ d. 0

13. $\frac{9}{10}$

14.

Die \ Coin	Head	Tail
1	H 1	T 1
2	H 2	T 2
3	H 3	T 3
4	H 4	T 4
5	H 5	T 5
6	H 6	T 6

a. $\frac{1}{6}$ b. $\frac{1}{4}$ c. $\frac{1}{4}$ d. $\frac{1}{4}$

15. See the table at the foot of the page.*

a. $\frac{1}{2}$ b. $\frac{1}{4}$ c. $\frac{4}{15}$

d. $\frac{1}{5}$ e. $\frac{3}{20}$ f. $\frac{23}{60}$

16. a. 6 socks. Worst case scenario is first picking 4 blue socks, then 2 black socks.

b. 7 socks. Worst case scenario is first picking 5 black socks then 2 blue socks.

c. 7 socks. Minimum needed to guarantee a pair of black socks is 6 (from part a). Picking one more guarantees a pair of blue socks will be included (from part b).

17. a. 12

b. 4, 6, 8, 10, 12

c. 2 + 6, 6 + 2, 4 + 4

d. 0

e. $\frac{2}{9}$

f.

Spinner B \ Spinner A	2	4	6
2	4	6	8
4	6	8	10
6	8	10	12

Total				
4	6	8	10	12
$\frac{1}{9}$	$\frac{2}{9}$	$\frac{3}{9} = \frac{1}{3}$	$\frac{2}{9}$	$\frac{1}{9}$


18. $\frac{1}{3}$

19. $\frac{2}{3}$

20. $\frac{3}{5}$

21. $\frac{29\,679}{160\,000}$

22. Likelihood smallest to largest: purple, yellow, orange, green, pink, blue



---

*15.

Die \ Spinner	1	2	3	4	5	6	7	8	9	10
1	11	21	31	41	51	61	71	81	91	101
2	12	22	32	42	52	62	72	82	92	102
3	13	23	33	43	53	63	73	83	93	103
4	14	24	34	44	54	64	74	84	94	104
5	15	25	35	45	55	65	75	85	95	105
6	16	26	36	46	56	66	76	86	96	106

14 Representing and interpreting data



LEARNING SEQUENCE

14.1 Overview 756
14.2 Collecting and classifying data 759
14.3 Displaying data in tables 766
14.4 Measures of centre and spread 772
14.5 Column graphs and dot plots 783
14.6 Stem-and-leaf plots 789
14.7 Pie charts and divided bar graphs (extending) 795
14.8 Comparing data 806
14.9 Review 812

14.1 Overview

Why learn this?



Every day we see graphs, charts and statistics in the media. These graphs, charts and statistics all serve to condense massive amounts of information into a few simple numerical facts. This is the beauty of statistics. It turns complicated data into simpler forms that, with the knowledge gained throughout this topic, you will be able to interpret and understand.

You may have seen graphs or charts of housing prices in the news or online. One house price report stated that in September 2020 the median house price was $1 154 406 in Sydney, $875 980 in Melbourne and $596 316 in Brisbane. What is the median house price? Why are house prices discussed in terms of the median and not the mean? This topic will help you to understand the answers to these questions, and apply your understanding to other contexts.

In every business it is vital to keep a close eye on finances. Statistics can be used to determine the economic health of a business by looking at changes in revenue, costs, customer satisfaction, market share and many other factors over time. Line graphs are often used to show changes over time, and pie charts are often used to display market share or customer satisfaction.

Data is also extremely important in the medical field. Statistics are used to collate data from around the world to better understand the rates of disease, effectiveness of different medicines or treatments, and many other things. In 2020, when the Covid-19 pandemic hit the world, graphs and charts started appearing in the news and on social media displaying the case numbers for different states and countries. The data collected by each state and country was displayed graphically, enabling residents to be informed and educated on the latest developments.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 14.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Select the data category that suits the number of players in a netball team.
   - A. Categorical and discrete
   - B. Numerical and discrete
   - C. Numerical and continuous
   - D. Categorical and continuous
   - E. Categorical and numerical

2. MC Select the data category that suits the amount of rainfall.
   - A. Numerical and continuous
   - B. Categorical and discrete
   - C. Numerical and discrete
   - D. Categorical and continuous
   - E. Numerical and categorical

Use the following information to answer questions 3 and 4.

The following frequency table represents the heights of 20 students in a Mathematics class.

Height group (cm)	Frequency
120–129	2
130–139	8
140–149	7
150–159	

3. Determine the number of students in the 150–159 cm group.

4. MC Choose the most common height group in the class.
   - A. 120–129 cm
   - B. 130–139 cm
   - C. 140–149 cm
   - D. 150–159 cm
   - E. 160–169 cm

5. A book store sold the following number of books each day for the last week. Calculate the daily average number of books sold.

   Book sales: 23, 34, 18, 28, 36, 45, 33



6. Calculate the median of the following data set.


   3, 3, 7, 8, 9, 9, 9, 11, 12, 13, 13, 17, 18, 21

7. Buddy kicks a ball 7 times. His kicks are 49, 52, 57, 43, 55, 62 and 59 metres in distance. Calculate the range of Buddy's 7 kicks.

8. The following data represents the sizes of Nike runners sold over a week. State the most common shoe size.

   Nike shoe sizes: 7, 7, 8, 9, 9, 9, 9, 10, 10, 11, 11, 11, 12, 12

9. The following graph shows the preferred sports of a group of students.



To the nearest per cent, determine the percentage of students who preferred swimming.

10. Determine the median value in the following dot plot.



11. The following stem-and-leaf plot represents the ages of a group of golfers. Determine the number of golfers that are older than 20 years of age.

Key: 2|4 = 24

Stem	*Leaf*
1	7 8 8 9 9
2	2 4 7 9
3	1 3 3 8
4	0 2 2 2 6 6
5	5 7
6	4

12. The following back-to-back stem-and-leaf plot shows the heights of Year 7 students. Determine the difference between the height of the tallest boy and the shortest girl.

Key: 13|7 = 137 cm


Leaf (boys)	*Stem*	*Leaf (girls)*
9 8	13	7 8
9 8 8 7 6	14	3 5 6
9 8 8	15	1 2 3 7
7 6 6 5	16	3 5 6
8 7 6	17	1

13. A survey asked people for their favourite brand of car. The following results were found:

Toyota = 34, Ford = 28, Holden = 30, Mazda = 18


If a sector graph was constructed using these results, determine the angle used for Toyota. Give your answer to the nearest degree.

14. The data presented in a divided bar graph shows the preferred Australian holiday destinations.



a. Based on this graph, calculate the number of people who were interviewed about their favourite Australian holiday destination.
b. Identify the number of people who preferred the Sunshine Coast.
c. Calculate the percentage of the total number of people who preferred Canberra.
d. Calculate the percentage of the total number of people who preferred Uluru.

15. The following sector graph is based on the way students travel to school. Determine the percentage, to the nearest whole per cent, of students who get to school by bus.



14.2 Collecting and classifying data

LEARNING INTENTION

At the end of this subtopic you should be able to:
- describe types of data using the key words 'categorical' (discrete) or 'numerical' (continuous)
- understand the difference between primary and secondary data
- explain why some data is more reliable that other data.

14.2.1 How to classify data

eles-4716

- Statistics is the study of collecting, organising, presenting, analysing and interpreting data.
- **Data** is information that is collected about a certain group.
- A **variable** is a particular characteristic that can be observed, counted or measured, such as eye colour or height. A variable can change over time or between individual observations.
- Data can be classified as **categorical data** or **numerical data**.

Categorical data

- Categorical data provides information about variables that can be *grouped into categories*.
- Take, for example, recycling bins. The different categories for recycling can include organic, paper, plastic, glass and metal.




- Categorical data can take many forms (some of which are numbers). These numbers generally represent a group or category, such as a rating scale (for example, 1 = dislike, 2 = don't care, 3 = like).
- Other common examples of categorical data include hair colour, gender, brand of vehicle, pizza size (small, medium, large, family) and rating scales (low, medium, high).



Numerical data

- Numerical data provides information about variables that can be *counted or measured*.
  For example, the number of text messages you send in a day, the number of puppies in a litter, the height of a tree at your school, and the daily pollution levels on a particular highway are all examples of data that can be counted or measured.
- Numerical data can be further classified as **discrete** (able to be counted), or **continuous** (able to be measured).
  For example, *number of goals scored* is a discrete variable, while *height of tree* is a continuous variable.





Numerical or categorical?

Deciding whether data is numerical or categorical is not always easy. Two things that can help your decision-making are the following.

1. Numerical data can always be used to perform arithmetic computations. This is not the case with categorical data. This is a good test to apply when in doubt.
   For example, it makes sense to calculate the average weight of a group of individuals, but not the average hair colour of a class of students.
2. It is not the variable alone that determines whether data is numerical or categorical — it is also the way the data is recorded.
   For example, if the data for the variable *weight* is recorded in kilograms, it is numerical. However, if the data is recorded using labels such as 'underweight', 'normal weight' and 'overweight', it is categorical.

WORKED EXAMPLE 1 Classifying data

Classify the following data using the following descriptive words: 'categorical' or 'numerical' (discrete or continuous).

a. The number of students absent from school
b. The types of vehicle using a certain road
c. The eye colour of each student in your class
d. The room temperature at various times during a particular day

THINK

a. 1. Determine whether the data is categorical or numerical.
   2. Determine whether the data is discrete (countable) or continuous (measurable).

WRITE

a. The data is *numerical* because the number of students can be counted or measured.
   The data is *discrete* because the number of absences can be counted rather than measured.

b. Determine whether the data is categorical or numerical.	**b.** The data is *categorical* because the types of vehicles can be placed into groups or categories (for example, car, truck, motorbike).
c. Determine whether the data is categorical or numerical.	**c.** The data is *categorical* because the colour of a person's eyes fits into groups (for example, brown, blue, green).
d. 1. Determine whether the data is categorical or numerical.	**d.** The data is *numerical* because the room temperature can be counted or measured.
2. Determine whether the data is discrete (countable) or continuous (measurable).	The data is *continuous* because temperature can be measured rather than counted.

14.2.2 Primary and secondary data

eles-4717

- When data is collected it is either **primary data** or **secondary data**. Both primary and secondary data can be either categorical data or numerical data.
- **Primary data** is data that you have collected yourself.
- Various methods of collecting primary data are available. These include observation, measurement, survey, experiment or simulation.
- **Secondary data** is data that has already been collected by someone else.
- The data can come from a variety of sources:
  - books, journals, magazines, company reports
  - online databases, broadcasts, videos
  - government sources — the Australian Bureau of Statistics (ABS) provides a wealth of statistical data
  - general business sources — academic institutions, stockbroking firms, sporting clubs
  - media — newspapers, TV reports.
- Secondary data sources often provide data that it would not be possible for an individual to collect.

WORKED EXAMPLE 2 Classifying primary and secondary data

Classify the following as primary data or secondary data.
a. The results of a class survey that you ran about favourite football teams
b. The Bureau of Meteorology's rainfall data from the last 10 years

THINK	WRITE
a. 1. Identify the person/people who collected the data.	**a.** I collected the data.
2. I collected the data; therefore, it is primary data.	It is primary data.
b. 1. Identify the person/people who collected the data.	**b.** The Bureau of Meteorology collected the data.
2. Someone else collected the data; therefore, it is secondary data.	It is secondary data.

Reliability of data

- When using data it is important to identify whether or not the data is reliable.

Determining the reliability of data

To determine the reliability of data, consider the following factors:

- Data source
  - Was the data collected by a reputable organisation or individual?
  - Did the people who collected the data have a motivation to find certain results? That is, does the data contain bias? (For example, a cigarette company might wish to fund a survey that finds no link between cigarettes and lung cancer.)
- Sample size
  - Was the sample of data collected small? This is not very reliable.
  - Was the sample of data collected large? This is generally more reliable.

DISCUSSION

How are graphs and statistics used to summarise data?

Resources

eWorkbook	Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)
Digital document	SkillSHEET Distinguishing discrete from continuous data (doc-6579)
Interactivity	Individual pathway interactivity: Classifying data (int-7045)

Exercise 14.2 Collecting and classifying data

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 5, 6, 10, 13	3, 7, 8, 11, 14	4, 9, 12, 15, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Match each word with its correct meaning.

a. discrete
b. categorical
c. continuous
d. numerical
e. primary data
f. secondary data

i. placed in categories or classes
ii. data collected by someone else
iii. data in the form of numbers
iv. used for measurements
v. counted in exact values
vi. data collected by me

2. WE1 Classify each of the following data as 'categorical' or 'numerical' (discrete or continuous).



   a. The population of your town or city
   b. The types of motorbikes in a car park
   c. The heights of people in an identification line-up
   d. The weights of babies in a group
   e. The languages spoken at home by students in your class
   f. The time spent watching TV

3. Classify each of the following numerical data as either 'discrete' or 'continuous'.



   a. The number of children in the families in your suburb
   b. The air pressure in your car's tyres
   c. The number of puppies in a litter
   d. The times for swimming 50 metres
   e. The quantity of fish caught in a net

4. Classify each of the following data as 'categorical' or 'numerical' (discrete or continuous).
   a. The types of shops in a shopping centre
   b. The football competition ladder at the end of each round
   c. The lifetime of torch batteries
   d. The number of people attending the Big Day Out
   e. Final Year 12 exam grades
   f. Hotel accommodation ratings

5. WE2 Classify the following as primary data or secondary data.
   a. The number of cars you counted going past your house in the last hour
   b. The Australian government's data about the number of students enrolled in Australian schools

Understanding

6. Data representing shoe (or rollerblade) sizes can be classified as categorical. Identify whether this statement is true or false.



7. Data representing the points scored in a basketball game can best be described as discrete. Identify whether this statement is true or false.

8. MC Select an example of categorical data.
   A. Heights of buildings in Sydney
   B. Number of pets in households
   C. Types of pets in households
   D. Birthday year of students in Year 7
   E. Number of hours spent playing sport

9. a. Write a sentence explaining the difference between discrete and continuous data. Give an example of each.
   b. Write a sentence explaining the difference between primary and secondary data. Give an example of each.

Reasoning

10. A Likert scale is used to represent people's attitudes to a topic. A five-level Likert scale could be as follows:

1. Strongly disagree
2. Disagree
3. Neither agree nor disagree
4. Agree
5. Strongly agree

The data collected from a Likert scale is recorded as a numerical value. Explain why this data is categorical instead of numerical.

11. Explain why data such as postal codes, phone numbers and drivers' licence numbers is not numerical data.

12. The Fizzy Drink company surveyed 50 people about the health benefits of soft drinks. The results showed that soft drink is healthy. Explain why this data is unreliable giving at least two reasons.

Problem solving

13. The following questions would collect categorical data. Rewrite the questions so that you could collect numerical data.

- **a.** Do you read every day?
- **b.** Do you play sport every day?
- **c.** Do you play computer games every day?

14. The following questions would collect numerical data. Rewrite the questions so that you could collect categorical data.

- **a.** On average, how many minutes per week do you spend on Maths homework?
- **b.** How many books have you read this year?
- **c.** How long does it take you to travel to school?

15. A fisheries and wildlife officer released 200 tagged trout into a lake. A week later, the officer took a sample of 50 trout and found that 8 of them were tagged. The officer can use this information to estimate the population of trout in the lake. Calculate the number of trout that are in the lake. Explain how you got this answer.



16. Bill is a soccer coach who trains 150 players. Bill surveys 5 players and the results say that Bill is the best soccer coach in Australia.

- **a.** Discuss whether Bill has collected primary or secondary data.
- **b.** Explain whether this data is reliable.
- **c.** Bill wants people to think he is the best soccer coach. Explain how this affect the reliability of the data.
- **d.** If the survey was done by the Australian Institute of Soccer, explain whether the data would be more or less reliable.

14.3 Displaying data in tables

LEARNING INTENTION

At the end of this subtopic you should be able to:

- construct a frequency distribution table for a set of data
- analyse and report on the information in a frequency distribution table.

14.3.1 Frequency distribution tables

eles-4718

- Data can be displayed in a variety of forms.
- In general, data is first organised into a table, and then a suitable graph is chosen as a visual representation.
- One way of presenting data is by using a frequency distribution table.
- **Frequency** is the number of times a result or piece of data occurs.
- A **frequency distribution table** consists of three columns: score, tally and frequency.
- The following frequency table is the result of a survey of 30 students, and it shows the number of family members who live at home with them.

Score (number of family members living at home)	Tally	Frequency
2	|||	3
3	𝍸	5
4	𝍸 ||||	9
5	𝍸 ||	7
6	||||	4
7	|	1
8	|	1
	Total	30

WORKED EXAMPLE 3 Constructing and interpreting a frequency table

A particular class was surveyed to determine the number of pets per household, and the data was recorded. The raw data was:
0, 3, 1, 2, 0, 1, 0, 1, 2, 4, 0, 6, 1, 1, 0, 2, 2, 0, 1, 3, 0, 1, 2, 1, 1, 2

a. Organise the data into a frequency distribution table.
b. Calculate the number of households that were included in the survey.
c. Determine the number of households that have fewer than 2 pets.
d. State the most common number of pets.
e. Determine the number of households that have 3 or more pets.
f. Determine the fraction of households surveyed that had no pets.



THINK

a. 1. Draw a frequency distribution table comprising three columns, headed Number of pets, Tally and Frequency.
2. In the first column list the possible number of pets per household (from 0 to 6).
3. Place a stroke in the tally column each time a particular score is noted.
Hint: A score of 5 is shown as a 'gate post' (four vertical strokes and one diagonal stroke: 𝍸).
4. Write the total number of tally strokes for each pet in the frequency column.
5. Calculate the total of the frequency column.

WRITE

a.

Number of pets	Tally	Frequency
0	𝍸 ||	7
1	𝍸 ||||	9
2	𝍸 |	6
3	||	2
4	|	1
5		0
6	|	1
	Total	26

b. The total of the frequency column gives the number of households surveyed.	**b.** 26 households were surveyed.
c. 1. Calculate the number of households that have fewer than two pets. *Hint:* Fewer than two means zero pets or one pet.	**c.** Fewer than two pets $= 7 + 9$ $= 16$
2. Write the answer.	16 households have fewer than two pets.
d. 1. Make a note of the highest value in the frequency column and check which score it corresponds to.	**d.** The score with the highest frequency (9) corresponds to one pet.
2. Write the answer.	The most common number of pets is one.
e. 1. Calculate the number of households that have 3 or more pets. *Hint:* 3 or more means 3, 4, 5 or 6.	**e.** 3 or more pets $= 2 + 1 + 0 + 1$ $= 4$
2. Write the answer.	Four households have 3 or more pets.
f. 1. Write the number of households with no pets.	**f.** Households with no pets $= 7$
2. Write the total number of households surveyed.	Total number of households surveyed $= 26$
3. Define the fraction and substitute the known values into the rule.	$\frac{\text{Households with no pets}}{\text{Total number of households surveyed}} = \frac{7}{26}$
4. Write the answer.	Of the households surveyed, $\frac{7}{26}$ have no pets.

Class intervals

- Sometimes data may contain too many numerical values to list them all individually in the 'score' column. In this case, we use a range of values, called a *class interval*, as our category. For example, the range 100–104 may be used to cater for all the values that lie within the range, including 100 and 104.

WORKED EXAMPLE 4 Using class intervals in a frequency table

The data below shows the ages of a number of mobile phone owners.

12, 11, 21, 12, 30, 26, 13, 15, 29, 16, 17, 17, 17, 21, 19, 12, 14, 16, 43, 18, 51, 25, 30, 28, 33, 62, 39, 40, 30, 18, 19, 41, 22, 21, 48, 31, 33, 33, 34, 41, 18, 17, 31, 43, 42, 17, 46, 23, 24, 33, 27, 31, 53, 52, 25

a. Construct a frequency table to classify the given data. Use a class interval of 10, that is, ages 11–20, 21–30 and so on, as each category.
b. Calculate the number of people who were surveyed.
c. State the age group that had the most people with mobile phones.
d. State the age group that had the fewest people with mobile phones.
e. Determine the number of people in the 21–30 age group who own a mobile phone.

THINK

a. 1. Draw a frequency distribution table.

2. In the first column, list the possible age groups (11–20, 21–30 and so on).

3. Systematically go through the results and place a stroke in the tally column each time a particular age group is noted.

4. Write the total tally of strokes for each age group in the frequency column.

5. Calculate the total of the frequency column.

b. The total of the frequency column gives us the number of people surveyed.

c. 1. Make note of the highest value in the frequency column and check which age group it corresponds to.

2. Write the answer.

d. 1. Make note of the lowest value in the frequency column and check which age group it corresponds to.
Note: There may be more than one answer.

2. Write the answer.

e. 1. Check the 21–30 age group in the table to see which frequency value corresponds to this age group.

2. Write the answer.

WRITE

a.

Age group	Tally	Frequency
11–20	𝍸 𝍸 𝍸 ||||	19
21–30	𝍸 𝍸 𝍸	15
31–40	𝍸 𝍸	10
41–50	𝍸 ||	7
51–60	|||	3
over 60	|	1
	Total	55

b. A total of 55 people were surveyed.

c. The 11–20 age group has the highest frequency: that is, a value of 19.

The 11–20 age group has the highest number of people with mobile phones.

d. The over-60 age group has the lowest frequency: that is, a value of 1.

The over-60 age group has the lowest number of people with mobile phones.

e. The 21–30 age group has a corresponding frequency of 15.

15 people in the 21–30 age group own a mobile phone.

Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)

Interactivities Individual pathway interactivity: Displaying data in tables (int-4379)

Frequency distribution tables (int-4051)

Exercise 14.3 Displaying data in tables

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 6, 7, 10, 13	2, 4, 8, 11, 14	5, 9, 12, 15

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE3 The number of children per household in a particular street is surveyed and the data recorded as follows.

   0, 8, 6, 4, 0, 0, 0, 2, 1, 3, 3, 3, 1, 2, 3,
   2, 3, 2, 1, 2, 1, 3, 0, 2, 2, 4, 2, 3, 5, 2



   a. Organise the data into a frequency distribution table.
   b. Calculate the number of households that are included in the survey.
   c. Determine the number of households that have no children.
   d. Determine the number of households that have at least 3 children.
   e. State the most common number of children.
   f. Determine the fraction of households surveyed that have 4 children.

2. WE4 The following data shows the incomes of a sample of doctors.

   $100 000, $105 000, $110 000, $150 000, $155 000, $106 000, $165 000, $148 000, $165 000,
   $200 000, $195 000, $138 000, $142 000, $153 000, $173 000, $149 000, $182 000, $186 000

   a. Construct a frequency table to classify the given data. Use a class interval of 10 000 to organise incomes into brackets of $100 000 to $109 999, $110 000 to $119 999, and so on.
   b. Calculate the number of people who were surveyed.
   c. State the income bracket that was most common.
   d. State the income bracket that was least common.
   e. Determine the number of doctors who earned $140 000 to $149 999.

3. Use this frequency distribution table to answer the following questions.

Score	Tally	Frequency
0	||	2
1	𝍸	5
2	|||	3
3	𝍸 𝍸 |	11
4	𝍸 |||	8
5	||||	4
	Total	

   a. Calculate the number of people who participated in the survey.
   b. State the most frequent score.
   c. Determine the number of people who scored less than 3.
   d. Determine the number of people who scored 3 or more.
   e. Calculate the fraction of the people surveyed who scored 3.

4. Draw a frequency distribution table for each of the following data sets.

a. Andrew's scores in Mathematics tests this semester are:

6, 9, 7, 9, 10, 7, 6, 5, 8, 9.

b. The number of children in each household of a particular street are:

2, 0, 6, 1, 1, 2, 1, 3, 0, 4, 3, 2, 4, 1, 0, 2, 1, 0, 2, 0.

c. The weights (in kilograms) of students in a Year 7 class are:

46, 60, 48, 52, 49, 51, 60, 45, 54, 54, 52, 58, 53, 51,
54, 50, 50, 56, 53, 57, 55, 48, 56, 53, 58, 53, 59, 57.

d. The heights of students in a Year 7 class are:

145, 147, 150, 150, 148, 145, 144, 144, 147, 149, 144, 150, 150, 152,
145, 149, 144, 145, 147, 143, 144, 145, 148, 144, 149, 146, 148, 143.

5. Rosemary decided to survey the participants of her local gym about their preferred sport. She asked each participant to name one preferred sport. Her results are below:

hockey, cricket, cricket, tennis, scuba diving, netball, tennis, netball, swimming, netball, tennis, hockey, cricket, lacrosse, lawn bowls, hockey, swimming, netball, tennis, netball, cricket, tennis, hockey, lacrosse, swimming, lawn bowls, swimming, swimming, netball, netball, tennis, golf, hockey, hockey, lacrosse, swimming, golf, hockey, netball, swimming, scuba diving, scuba diving, golf, tennis, cricket, cricket, hockey, lacrosse, netball, golf

a. State any problems with the way Rosemary has displayed the data.

b. Organise Rosemary's results into a frequency table to show the participants' preferred sports.

c. From the frequency table, determine:

i. the most preferred sport

ii. the least preferred sport.

d. State whether any sport(s) have the same frequency.

Understanding

6. A random sample of 30 families was surveyed to determine the number of children in high school in each family. The following is the raw data collected.

2, 1, 1, 0, 2, 0, 1, 0, 2, 0, 3, 1, 1, 0, 0,
0, 1, 4, 1, 0, 0, 1, 2, 1, 2, 0, 3, 2, 0, 1



a. Organise the data into a frequency distribution table.

b. Determine the number of families that have no children of high school age.

c. Determine the number of families that have 2 or more children of high school age.

d. State the score that has the highest frequency.

e. From the 30 families surveyed, state the highest number of children in high school from one family.

f. Calculate the fraction of families that had 2 children of high school age.

7. Draw a frequency table to classify the following data on students' heights. Use a range of values (for example, 140–144, 145–149, and so on) as each category. The values are listed below.

168 cm, 143 cm, 145 cm, 151 cm, 153 cm, 148 cm, 166 cm, 147 cm, 160 cm, 162 cm,
175 cm, 168 cm, 143 cm, 150 cm, 160 cm, 180 cm, 146 cm, 158 cm, 149 cm, 169 cm,
167 cm, 167 cm, 163 cm, 172 cm, 148 cm, 151 cm, 170 cm, 160 cm

8. A real estate agent has listed all the properties sold in the area in the last month. She wants to know what has been the most popular type of property from the list of sold properties:

2-bedroom house, 4-bedroom house, 3-bedroom house, 2-bedroom unit, 4-bedroom house, 1-bedroom unit, 3-bedroom house, 2-bedroom unit, 3-bedroom house, 1-bedroom unit, 2-bedroom unit, 3-bedroom house, 3-bedroom house, 3-bedroom house, 2-bedroom unit, 1-bedroom unit



a. Complete a frequency table for the list of properties and work out which type of property was most popular.

b. MC Select the least popular type of property.

A. 1-bedroom unit
B. 2-bedroom unit
C. 2-bedroom house
D. 3-bedroom house
E. 4-bedroom house

c. MC Choose the type of property that is half as popular as a 2 bedroom unit.

A. 4-bedroom house
B. 3-bedroom house
C. 2-bedroom house
D. 1-bedroom unit
E. none of these

9. MC Select the statement(s) about the frequency column of a frequency table that are true.

A. It adds up to the total number of categories.
B. It adds up to the total number of results given.
C. It adds up to the total of the category values.
D. It displays the tally.
E. None of these statements are true.

Reasoning

10. Explain why tallies are drawn in batches of four vertical lines crossed by a fifth one.

11. Discuss what you need to consider when selecting a class interval for a frequency distribution table.

12. Explain the reasoning behind using class intervals and state the circumstances in which they should be used.

Problem solving

13. The following frequency distribution table displays the number of pets in the families of the students of a class.

Number of pets	Frequency	% Frequency
0	8	
1	11	
2	3	
3	2	
4	0	
5	1	

a. Determine the number of students in the class.
b. Calculate the percentage frequency for each row of the table.

Another class containing 25 students creates their own version of this frequency distribution table. When the data in both tables is combined, the percentage frequency of having 1 pet is 34%.

c. Determine the number of students in the other class with one pet in their family.

14. This frequency table shows the percentage occurrence of the vowels in a piece of writing. Two pieces of data are missing — the percentage occurrence of the letters O and U. The occurrence of O is 2.6 times that of U. Determine the two missing values in this table. Show your working.

Vowel	Percentage frequency
A	22.7
E	27.6
I	19.9
O	
U	

15. A survey was conducted on 45 households to identify the number of children living in each household. Use the following information to determine the results and complete the table.

- The number of households with no children is equal to the number of households with 3 children.
- The number of households with 1 child was 4 times the number of households with no children.
- The number of households with 2 children was 5 times the number of households with no children.
- There was one household with 4 children.

Score	Frequency
0	
1	
2	
3	
4	
Total	



14.4 Measures of centre and spread

LEARNING INTENTION

At the end of this subtopic you should be able to:

- calculate the mean, median and mode of a set of data
- calculate the range of a set of data.

14.4.1 Measures of centre

eles-4719

- Measures of centre are statistical values that give us an idea about the centre of a data set. The measures of centre are **mean**, **median** and **mode**.

The mean

- The mean of a set of data is the average of the values.
- The mean is denoted by the symbol $\bar{x}$ (a lower-case x with a bar on top).
- The average is found by adding up all of the values in the data set, then dividing by the number of values in the set.
- The mean is not necessarily a whole number, or a number that was in the original set of data.

Calculating the mean

- The formula for the mean is:

$$\bar{x} = \frac{\text{sum of data values}}{\text{total number of data values}}$$

- In most cases the mean is thought of as the centre of a set of data.

WORKED EXAMPLE 5 Calculating the mean

For each of the following sets of data, calculate the mean, $\bar{x}$.
Give your answers correct to two decimal places where appropriate.

a. **5, 5, 6, 4, 8, 3, 4**

b. **0, 0, 0, 1, 1, 1, 1, 1, 4, 4, 4, 4, 5, 5, 5, 7, 7**

THINK

a. 1. Calculate the sum of the given values.

2. Count the number of values.

3. Define the rule for the mean.

4. Substitute the known values into the rule and evaluate.

5. Write the answer.

b. 1. Calculate the sum of the given values. Take note of the number of times each value occurs.
0 occurs 3 times (3×0),
1 occurs 5 times (1×5),
4 occurs 4 times (4×4),
5 occurs 3 times (5×3),
7 occurs 2 times (7×2)

2. Count the number of values.

3. Define the rule for the mean.

4. Substitute the known values into the rule and evaluate.

5. Round the answer to 2 decimal places.

6. State the answer.

WRITE

a. Sum of data values $= 5 + 5 + 6 + 4 + 8 + 3 + 4$
$= 35$

Number of data values $= 7$

$$\bar{x} = \frac{\text{sum of data values}}{\text{total number of data values}}$$

$$= \frac{35}{7}$$
$$= 5$$

The mean (or average) of the set of data is 5.

b. Sum of data values
$= 3 \times 0 + 5 \times 1 + 4 \times 4 + 3 \times 5 + 2 \times 7$
$= 0 + 5 + 16 + 15 + 14$
$= 50$

Number of data values $= 17$

$$\bar{x} = \frac{\text{sum of data values}}{\text{total number of data values}}$$


$$= \frac{50}{17}$$
$$= 2.94117647...$$

$$= 2.94$$

The mean (or average) of the set of data is 2.94.

The median

- The median represents the middle score when the data values are ordered from **smallest** to **largest** (also known as 'numerical order' or 'ascending order').



- An equal number of data values can be found below the median and above it.

Calculating the median

When determining the median, follow these steps.

1. Arrange the data values in ascending order (smallest to largest).
2. Locate the middle value (ensure that there are as many values above the median as there are below it).
3. If the data set contains an even number of data values there will be two 'middle' numbers. The median is the average of these numbers.

Alternatively:

The *position* of the median is the $\left(\frac{n+1}{2}\right)$ th data value, where n is the total number of data values.

WORKED EXAMPLE 6 Determining the median

Determine the middle value (median) for the following sets of data.

a. **5, 4, 2, 6, 3, 4, 5, 7, 4, 8, 5, 5, 6, 7, 5**

b. **8, 2, 5, 4, 9, 9, 7, 3, 2, 9, 3, 7, 6, 8**

THINK	WRITE
a. 1. Arrange the data values in ascending order (smallest to largest).	**a.** 2, 3, 4, 4, 4, 5, 5, 5, 5, 5, 6, 6, 7, 7, 8
2. Locate the middle value by inserting a vertical line that splits the data into two equal sections. The pink line inserted through the third number 5 splits the data into two equal sections that each have 7 data values.	2, 3, 4, 4, 4, 5, 5, 5, 5, 6, 6, 7, 7, 8
3. Write the answer.	The median of the data set is 5.
b. 1. Arrange the data values in ascending order (smallest to largest).	**b.** 2, 2, 3, 3, 4, 5, 6, 7, 7, 8, 8, 9, 9, 9
2. Locate the middle value by inserting a vertical line that splits the data into two equal sections. The pink line inserted in between the 6 and 7 splits the data into two equal sections that each have 6 data values.	2, 2, 3, 3, 4, 5, 6, | 7, 7, 8, 8, 9, 9, 9

3. Since the median (or middle position) occurs between 6 and 7, we need to determine the average of these two numbers. The median of the data lies directly between 6 and 7.

$$\text{Median} = \frac{6+7}{2} = \frac{13}{2} = 6.5$$

4. The number directly between 6 and 7 is 6.5. Write the answer.

The median of the data set is 6.5.

Alternative method:

a. 1. Arrange the data values in ascending order (smallest to largest).

a. 2, 3, 4, 4, 4, 5, 5, 5, 5, 5, 6, 6, 7, 7, 8

2. Count the number of data values in the set.

$n = 15$

3. Determine the $\left(\frac{n+1}{2}\right)^{\text{th}}$ data value.

$\left(\frac{n+1}{2}\right) = \frac{15+1}{2} = 8$

4. The median is located at the $\left(\frac{n+1}{2}\right)^{\text{th}}$ data value.

The median is the 8th value in the set of data.
The 8th number in the set of data is 5.

5. Write the answer.

The median of the data set is 5.

b. 1. Arrange the data values in ascending order (smallest to largest).

b. 2, 2, 3, 3, 4, 5, 6, 7, 7, 8, 8, 9, 9, 9

2. Count the number of data values in the set.

$n = 14$

3. Determine the $\left(\frac{n+1}{2}\right)^{\text{th}}$ data value.

$\left(\frac{n+1}{2}\right) = \frac{14+1}{2} = 7.5$

4. The two middle values are the 7th and 8th values.

The middle values are 6 and 7

5. Calculate the average of the middle values.

$\frac{6+7}{2} = \frac{13}{2} = 6.5$

6. Write the answer.

The median of the data set is 6.5.

- As the median is the middle value, it is a common measure of centre, especially for large data sets or data sets where the average is skewed by a small number of extreme (outlier) values.

The mode

- The mode is the most common value in a set of data. It is the value that occurs most frequently.
- Some sets of data have more than one mode.
- Some sets of data have no mode at all.

Calculating the mode

When determining the mode:

1. arrange the data values in ascending order (smallest to largest) — this step is optional but does help
2. look for the value that occurs most often (the one that has the highest frequency).

Important notes about the mode

- If a set of data has no mode, your answer should be the words 'no mode', not '0'. This is what would happen when no value occurs more than once in a set of data.
  For example, in the set of data 1, 2, 3, 4, 6, 7, 10, 12, 13, no value is repeated, so there is no mode.
- If a set of data has one mode, write this value as your answer.
  For example, for the set of data 15, 31, 12, 47, 21, 65, 12, the mode is 12 because it appears twice — each other value only appears once.
- If a set of data has more than one mode, write all of the values that occur the most as your answer.
  For example, for the set of data 1, 1, 2, 2, 2, 4, 5, 6, 6, 6, 9, 9, 12, 12, 12, the modes are 2, 6 and 12.

WORKED EXAMPLE 7 Identifying the mode

Identify the mode of the following scores.
a. 2, 3, 4, 5, 5, 6, 6, 7, 8, 8, 8, 9
b. 12, 18, 5, 17, 3, 5, 2, 10, 12
c. 42, 29, 11, 28, 21

THINK	WRITE
a. 1. Look at the set of data and highlight any values that have been repeated.	**a.** 2, 3, 4, 5, 5, 6, 6, 7, 8, 8, 8, 9
2. Choose the value that has been repeated the most.	The numbers 5 and 6 occur twice. However, the number 8 occurs three times.
3. Write the answer.	The mode for the given set of values is 8.
b. 1. Look at the set of data and highlight any values that have been repeated.	**b.** 12, 18, 5, 17, 3, 5, 2, 10, 12
2. Choose the value(s) that have been repeated the most.	The number 5 occurs twice. The number 12 occurs twice.
3. Write the answer.	The modes for the given set of values are 5 and 12.
c. 1. Look at the set of data and highlight any value(s) that have been repeated.	**c.** 42, 29, 11, 28, 21
2. Write the answer.	No values have been repeated. The set of data has no mode, since each of the numbers occurs once only.

- The mode is generally not used as a measure of centre, rather as a measure of the most common, or popular, value.

COLLABORATIVE TASK: Which average?

In this activity you will investigate how the mean, the median and the mode are affected by the size of a data set. You will also determine which of these is the most useful value.

1. Working in groups of 4 or more, list the number of pets each student has. This will be the data set for your group.
2. Calculate the mean, the median and the mode of your data set. Explain which measure of centre best describes the number of pets that people in your group own.

3. Compare your results with the results found by another group.
4. If you were to combine your data set with the other group's data set, predict what would happen to the mean, the median and the mode.
5. Combine the two sets of data and find the mean, the median and the mode of this new data set.
   a. Did the new values you calculated agree with your prediction? Discuss your findings.
   b. Explain which of the new measures of centre best describes the number of pets that people in the combined group own.
6. Combine your latest set of data with another group's data and repeat your calculations for the mean, the median and the mode.





7. Your teacher will now record the data for the whole class on the board. Calculate the mean, the median and the mode for the whole class.
8. Discuss the results. Compare the values you found for the mean of each different-sized data set. Do the same for the median and the mode.
9. If you were to rely on just one of these measures of centre to describe the number of pets that people in your class own, determine which one you would choose. Discuss your reasons.

14.4.2 Measures of spread

eles-4720

- A measure of spread indicates how far data values are spread from the centre, or from each other.
- Looking at the following two graphical displays, the pink graph on the left is more 'spread out' compared to the green graph on the right. That is, the pink graph has a larger spread (from 0 to 22) compared to the green graph (from 6 to 18).
- There are several measures of spread, but at this stage we will only discuss the **range**.
- The range of a set of values is the difference between the largest and smallest values.





Calculating the range

The range of a set of data is the difference between the largest and smallest values in that set.

Range = (largest data value) – (smallest data value)

WORKED EXAMPLE 8 Determining the range

Determine the range of the following data.

12, 76, 35, 29, 16, 45, 56

THINK	WRITE
1. Identify the largest and smallest values.	Largest value = 76 Smallest value = 12
2. State the formula for the range and substitute the values in to evaluate it.	Range = largest value – smallest value = 76 – 12 = 64
3. Write the answer.	The range of the data set is 64.

on Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)

Digital documents SkillSHEET Finding the mean of ungrouped data (doc-6580)
SkillSHEET Finding the median (doc-6581)

Interactivities Individual pathway interactivity: Measures of centre and spread (int-4380)
Measures of centre (int-4052)
Mean (int-4053)
Median (int-4054)
Mode (int-4055)
Range (int-4056)

Exercise 14.4 Measures of centre and spread

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 8, 10, 11, 15, 16, 21, 22, 27, 28, 29	2, 5, 6, 9, 12, 17, 18, 23, 24, 28, 30, 31, 32	3, 7, 13, 14, 19, 20, 25, 26, 33, 34, 35

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE5 For each of the following sets of data, calculate the mean.
   a. 3, 4, 5, 5, 6, 7
   b. 5, 6, 7, 5, 5, 8
   c. 4, 6, 5, 4, 2, 3
   d. 3, 5, 6, 8, 7, 7
   e. 5, 4, 4, 6, 2, 3
2. For each of the following sets of data, calculate the mean.
   a. 2, 2, 2, 4, 3, 5
   b. 12, 10, 13, 12, 11, 14
   c. 11, 12, 15, 17, 18, 11
   d. 12, 15, 16, 17, 15, 15
   e. 10, 14, 12, 12, 16, 14
3. For each of the following sets of data, calculate the mean.
   Hint: Use the grouping of values to help you.
   a. 2, 2, 2, 4, 4, 4
   b. 1, 2, 2, 4, 4, 5
   c. 1, 2, 2, 5, 5, 6, 7
   d. 9, 9, 8, 8, 7, 1, 1, 1, 1
   e. 3, 3, 3, 1, 1, 1, 2, 2, 2
   f. 2, 2, 2, 3, 3, 3, 3, 6

4. WE6a Determine the median (middle value) for the following sets of data.

   a. 3, 3, 4, 5, 5, 6, 7
   b. 1, 2, 2, 3, 4, 8, 9
   c. 2, 2, 2, 3, 3, 4, 5
   d. 5, 5, 6, 6, 7, 7, 8, 9, 9

5. Determine the median (middle value) for the following sets of data.

   a. 7, 7, 7, 10, 11, 12, 15, 15, 16
   b. 4, 3, 5, 3, 4, 4, 3, 5, 4
   c. 1, 2.5, 5, 3.4, 1, 2.4, 5
   d. 1.2, 1.5, 1.4, 1.8, 1.9

6. WE6b Determine the median (middle value) for the following sets of data.

   a. 1, 1, 2, 2, 4, 4
   b. 4, 5, 5, 5, 6, 7
   c. 4, 5, 7, 7, 8, 9
   d. 1, 2, 2, 3, 3, 4

7. Determine the median (middle value) for the following sets of data.

   a. 2, 4, 4, 6, 8, 9
   b. 1, 5, 7, 8
   c. 2, 4, 5, 7, 8, 8, 9, 9
   d. 1, 5, 7, 8, 10, 15

8. WE7 Identify the mode for each of the following sets of data.

   a. 3, 3, 4, 4, 4, 5, 6
   b. 2, 9, 8, 8, 4, 5
   c. 1, 1, 2, 2, 2, 3
   d. 4, 6, 4, 2, 7, 3
   e. 2, 4, 3, 6, 2, 4, 2

9. Identify the mode for each of the following sets of data.

   a. 4, 8, 8, 3, 3, 4, 3, 3
   b. 6, 2, 12, 10, 14, 14, 10, 12, 10, 12, 10, 12, 10, 12
   c. 7, 9, 4, 6, 26, 71, 3, 3, 3, 2, 4, 6, 4, 25, 4
   d. 2, 2, 3, 4, 4, 9, 9, 9, 6
   e. 3, 7, 4, 5, 22

10. WE8 Determine the range of the following sets of data:

    a. 15, 26, 6, 38, 10, 17
    b. 12.8, 21.5, 1.9, 12.0, 25.4, 2.8, 1.3

Understanding

11. MC Select the method(s) that can be used to calculate the mean for the data 5, 5, 6, 7, 2.

    A. Adding all the results and multiplying by the number of results
    B. Adding all the results and dividing by the number of results
    C. Adding all the results
    D. Choosing the middle result
    E. Ordering the results, then choosing the middle result

12. MC Select statement(s) that are true about calculating the mean of a set of data.

    A. Zeroes do not matter at all.
    B. Zeroes must be counted in the number of results.
    C. Zeroes must be added to the total as they will change it.
    D. Zeroes will make the mean zero.
    E. None of these are true.

13. MC Choose the statement that is true about the set of data 2.6, 2.8, 3.1, 3.7, 4.0, 4.2.

    A. The mean value for the data will be above 4.2.
    B. The mean value for the data will be below 2.6.
    C. The mean value for the data will be between 2.6 and 3.0.
    D. The mean value for the data will be between 3.0 and 4.0.
    E. The mean value for the data will be between 4.0 and 4.2.

14. MC Choose the correct statement.

A. The mean, median and mode for any set of data will always be the same value.
B. The mean, median and mode for any set of data will never be the same value.
C. The mean, median and mode for any set of data must always be close in value.
D. The mean, median and mode for any set of data are sometimes close in value.
E. None of these statements are true.

15. MC Select the range of the set of numbers: 16, 33, 24, 48, 11, 30, 15

A. 48 **B.** 59 **C.** 37 **D.** 20 **E.** 11

16. Eleanor wanted to know what her Mathematics test average was. Eleanor's teacher told her that she had used the mean of Eleanor's test results to calculate the end-of-year mark. Eleanor's test results (written as percentages) are:

89, 87, 78, 75, 89, 94, 82, 93, 78

Calculate Eleanor's mean Mathematics test score.

17. A cricketer had scores of 14, 52, 35, 42 and 47 in her last 5 innings. Determine her mean score.

18. Eliza works in a shoe factory as a shoe inspector. The number of shoes Eliza inspected in an hour was counted over a number of days' work. The following list contains the results.



105, 102, 105, 106, 103, 105, 105,
102, 108, 110, 102, 103, 106, 107,
108, 102, 105, 106, 105, 104, 102,
99, 98, 105, 102, 101, 97, 100

Calculate the mean number of shoes checked by Eliza in one hour. Round your answer to the nearest whole number.

19. The number of students in the canteen each lunchtime was surveyed for 2 weeks. The following are the results.

52, 45, 41, 42, 53, 45, 47, 32, 52, 56

Calculate the mean number of students in the canteen at lunchtime in that fortnight. Round your answer to the nearest whole number.

20. Answer the following questions.

a. Explain what 'the mean number of goals scored in a soccer match' means.
b. Explain what 'the median house price' means.
c. Explain what 'the mode of shoe-size data' means.

Reasoning

21. Suggest why we summarise data by calculating measures of centre and spread.

22. The local football team has been doing very well. They want to advertise their average score to attract new club members. You suggest that they use the mean of their past season's game scores. They ask you to find it out for them. Their results are listed below (scores are given as total points for each game).

110, 112, 141, 114, 112, 114, 95, 75, 58, 115, 116, 115, 75,
114, 78, 96, 78, 115, 112, 115, 102, 75, 79, 154, 117, 62

a. Calculate the team's mean score. Show your working.
b. Identify whether the mode or median is the 'better' value to use to attract new club members. Justify your answer.

23. A clothing company wanted to know the size of jeans that should be manufactured in the largest quantities. A number of shoppers were surveyed and asked their jeans size. The results are given below.



13, 12, 14, 12, 15, 16, 14, 12, 15, 14, 12,
14, 13, 14, 11, 10, 12, 13, 14, 14, 10, 12,
14, 12, 12, 10, 8, 16, 17, 12, 11, 13, 12,
15, 14, 12, 17, 8, 16, 11, 12, 13, 12, 12

a. Determine the mode of the data.
b. Explain why the company would be more interested in the mode than the mean or median values.

24. Explain whether we are able to calculate the mean, median, mode and range of categorical data.

25. Tom thinks that the petrol station where he buys his petrol is cheaper than the one where his friend Sarah buys her petrol. They begin to keep a daily watch on the prices for 4 weeks and record the following prices (in dollars per litre).

Tom: 1.32, 1.37, 1.39, 1.39, 1.40, 1.42, 1.41, 1.38, 1.34, 1.30,
1.29, 1.28, 1.27, 1.26, 1.25, 1.25, 1.24, 1.25, 1.24, 1.24,
1.25, 1.25, 1.26, 1.27, 1.28, 1.28, 1.30, 1.32

Sarah: 1.41, 1.37, 1.32, 1.31, 1.29, 1.27, 1.24, 1.22, 1.21, 1.21,
1.20, 1.19, 1.20, 1.21, 1.22, 1.23, 1.24, 1.24, 1.25, 1.26,
1.27, 1.28, 1.28, 1.28, 1.29, 1.30, 1.32, 1.31



a. Calculate the mean petrol prices for Tom and Sarah.
b. Identify the petrol station that sells cheaper petrol on average. Justify your answer.
c. Explain why Tom might have been wrong about thinking his petrol station was cheaper.

26. Jennifer wants to make sure the mean height of her jump in the high jump for 10 jumps is over 1.80 metres.

a. Calculate her current mean if her jumps so far have been (in metres) 1.53, 1.78, 1.89, 1.82, 1.53, 1.81, 1.75, 1.86, 1.82. Show your working.
b. Determine what height she needs to jump on the tenth jump to achieve a mean of 1.80. Show your working.
c. Discuss whether this is likely, given her past results.

Problem solving

27. Kim has an average (mean) score of 72 in Scrabble. He has played 6 games. Determine what he must score in the next game to keep the same average.

28. Peter has calculated his mean score for history to be 89%, based on 5 tests. If he scores 92% in the sixth test, calculate his new mean score.

29. The club coach at a local cycling track was overheard saying that he thought at least half of the cyclists using the track were cycling at speeds of 30 km/h or more. The speeds (in km/h) of the club cyclists are listed as follows.

31, 22, 40, 12, 26, 39, 49, 23, 24, 38, 27, 16, 25, 37, 19, 25, 45, 23, 17, 20, 34, 19, 24, 15, 40, 39, 11, 29, 33, 44, 29, 50, 18, 22, 51, 24, 19, 20, 30, 40, 49, 29, 17, 25, 37, 25, 18, 34, 21, 20, 18

Discuss whether the coach's statement is correct.



30. Identify five whole numbers that have a mean of 10 and a median of 12.

31. The mean of five different test scores is 15. All test scores are whole numbers. Determine the largest and smallest possible test scores, given that the median test score is 12.

32. Gavin records the amount of rainfall in millimetres each day over a two-week period. Gavin's results are:

11, 24, 0, 6, 15, 0, 0, 0, 12, 0, 0, 127, 15, 0.

a. Determine the mean rainfall for the two-week period.
b. Determine the median rainfall.
c. Identify the mode of the rainfall.
d. State which of the mean, median and mode is the best measure of the typical rainfall. Explain your choice.

33. A group of 3 children have a mean height of 142 cm. The middle height is the same as the mean. The tallest child leaves the group, and is replaced by a child with the same height as the shortest child.
The mean height of this group of three children is now 136 cm. Calculate the heights of the 4 children. Explain how you got your answer.



34. The mean of 5 different test scores is 10. All test scores are whole numbers. Determine the largest and smallest possible values for the median.

35. The mean of 9 different test scores ranging from 0 to 100 is 85. The median is 80. All test scores are whole numbers. Determine the greatest possible range between the highest and lowest possible test scores.

14.5 Column graphs and dot plots

LEARNING INTENTION


At the end of this subtopic you should be able to:
- display data as a column or bar graph
- display data as a dot plot
- analyse and interpret column and bar graphs and dot plots.

14.5.1 Column and bar graphs

eles-4721

Features of graphs

- Graphs are a useful way of displaying data, or numerical information. TV, websites, newspapers and magazines frequently display data as graphs.
- All graphs should have the following features:
  - a *title* — to tell us what the graph is about
  - clear *labels* for the axes — to explain what is being shown
  - *evenly scaled axes* — if the graph has numerical axes, they must have a scale that is constant for the length of the axes, with a clear indication of the units being used
  - **legends** — these are not always necessary, but they are necessary when any symbols or colours are used to illustrate some element of the graph.
- Different graphical displays are used depending whether the data is categorical or numerical.




Using column graphs and bar graphs

- Column and bar graphs can be used to represent categorical data.
- The frequency for each category determines the length of the bar or the height of the column.
- It is easiest to graph the data from a frequency table.
- The advantage of column and bar graphs is that they are usually easy to prepare and interpret.
- The disadvantages of column and bar graphs are:
  - if they are displaying a large number of categories they become difficult to understand
  - they don't provide a visualisation of what proportion each category is of the whole.

Column graphs

- **Column graphs** should be presented on graph paper and have:
  - a title
  - labelled axes that are clearly and evenly scaled
  - columns of the same width
  - an even gap between each column
  - a space between the vertical axis and the first column.



WORKED EXAMPLE 9 Constructing a column graph from a frequency table


Beth surveyed the students in her class to find out their preferences for the school uniform. Her results are shown in the following table. Construct a column graph to display the results.

Type of uniform	Tally	Frequency
White shirt and black skirt/trousers	𝍸 |||	8
Blue shirt and black skirt/trousers	||||	4
Blue shirt and navy skirt/trousers	𝍸 𝍸 ||	12
White shirt and navy skirt/trousers	𝍸	5
	Total	29

THINK


1. Rule a set of axes on graph paper. Give the graph a title. Label the horizontal and vertical axes.
2. Scale the horizontal and vertical axes.
   Hint: Leave an interval at the beginning and end of the graph by placing the first column a half or one unit from the vertical axis, and making sure the horizontal axis is a half or one unit longer than needed to fit all of the columns.
3. Draw the first column so that it reaches a vertical height corresponding to 8 people. Label the section of the axis below the column as 'White shirt and black skirt/trousers'.
4. Leave a gap (measuring one column width) between the first column and the second column.
5. Repeat steps 3 and 4 for each of the remaining uniform types.

DRAW



Bar graphs


- Column graphs that are drawn horizontally are known as **bar graphs**. Bar graphs can be used when category names are too long to fit at the bottom of a column.
- Bar graphs should have the same features as a column graph; that is:
  - a title
  - labelled and evenly scaled axes
  - bars of the same width
  - even gaps between bars.



14.5.2 Dot plots

eles-4723

- **Dot plots** are usually used to represent numerical data. They use dots on a number line to show individual data values.
- If a data value appears more than once, the dots are stacked vertically.
- Dot plots give a quick overview of distribution. They show **clustering** (groups of dots) and **outliers** (values that are extremely small or large compared to the majority of values).
- The dot plot shown here displays the number of hours of screen time each day for a group of people. Each dot represents the number of hours of screen time per day for each person. Two people had 6 hours of screen time on a particular day.



WORKED EXAMPLE 10 Constructing a dot plot

Over a 2-week period, the number of packets of potato chips sold from a vending machine each day was recorded. The results are listed below.

10, 8, 12, 11, 12, 18, 13, 11, 12, 11, 12, 12, 13, 14

a. **Draw a dot plot of the data.**
b. **Comment on the distribution.**


THINK

a. 1. Use a number line to include the full range of data recorded.
   2. Place a dot above the number for each value recorded.

b. Comment on interesting features of the dot plot, for example the range, clustering, extreme values or any practical information about the situation.

WRITE

a.



b. The scores on this dot plot extend from 8 to 18. That gives a range of 10. On most days between 11 to 13 packets of chips were sold. There were very few days on which 8 and 18 packets of chips were sold. Making sure that there are enough chips to sell 20 packets per day should cover even the most extreme demand for chips from this machine.

Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)

Interactivities Individual pathway interactivity: Column graphs and dot plots (int-8471)
Representing data graphically (int-4057)
Column and bar graphs 1 (int-4058)
Column and bar graphs 2 (int-4059)

Exercise 14.5 Column graphs and dot plots

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 9, 12	2, 5, 7, 10, 11, 13	3, 8, 11, 14

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE9 Beth surveyed the students in her class to find out their method of travelling to school. Her results are shown in the following table. Construct a column graph to display the data.

Transport	Tally	Frequency
Car	𝍸 𝍸 𝍸	15
Tram	𝍸 ||||	9
Train	𝍸 𝍸 𝍸 |||	18
Bus	𝍸 |||	8
Bicycle	|||	3
	Total	53

2. Construct a column graph to display the data in the table shown, displaying the mean daily maximum temperatures for each month in Cairns, Queensland.

Month	Mean daily maximum temperature (°C)
January	31.8
February	31.5
March	30.7
April	29.3
May	27.6
June	25.9
July	25.6
August	26.4
September	27.9
October	29.7
November	30.8
December	31.8

3. The data in the table displays the number of students absent from school each day in a fortnight. Construct a bar graph to display the data.

Day	Number of students absent
Monday	15
Tuesday	17
Wednesday	20
Thursday	10
Friday	14
Monday	16
Tuesday	14
Wednesday	12
Thursday	5
Friday	14

4. WE10 Over a 2-week period, the number of packets of potato chips sold from a vending machine each day was recorded as follows: 15, 17, 18, 18, 14, 16, 17, 6, 16, 18, 16, 16, 20, 18.


a. Draw a dot plot of the data.
b. Comment on the distribution.

5. Draw a dot plot for each of the following sets of data.

a. 2, 0, 5, 1, 3, 3, 2, 1, 2, 3
b. 18, 22, 20, 19, 20, 21, 19, 20, 21
c. 5.2, 5.5, 5.0, 5.8, 5.3, 5.2, 5.6, 5.3, 6.0, 5.5, 5.6
d. 49, 52, 60, 55, 57, 60, 52, 66, 49, 53, 61, 57, 66, 62, 64, 48, 51, 60


Understanding

6. Phone bills often include a graph showing your previous bill totals. Use the phone bills column graph shown to answer the following questions.



a. State the horizontal axis label.
b. State the vertical axis label.
c. Determine how often this person receives a phone bill.
d. State in which month their phone bill was the highest.
e. Explain why it would be useful to receive a graph like this with your phone bill.
f. If the next bill was for $240.09, explain whether this would be expected.

7. An apple grower records his sales for a 12-week period.




a. Determine the number of boxes sold:

i. in the first week **ii.** in the fifth week **iii.** in the eighth week.

b. The values for some weeks might be unusual. Determine which values these ones are.

c. Does the graph indicate that apple sales are improving? Explain your answer.

8. The students in a Year 7 physical education class were asked to sprint for 10 seconds. The teacher recorded their results on 2 different days. The graph shown displays the results collected.



a. State who was the fastest student on each day.

b. Identify how far the fastest student ran on each day.

c. Determine who improved the most.

d. Determine which students did not improve, if any.

e. Explain whether this graph could be misleading in any way.

f. Why might the graph's vertical axis start at 30 m?

Reasoning

9. Explain why it is important for the data points in a dot plot to be neatly aligned above the value they are representing.

10. Explain why column and bar graphs are more often used to represent categorical data rather than numerical data.

11. Explain and give an example of the effect that outliers in a set of data have on the:

a. mean
b. median
c. mode
d. range.

Problem solving

12. Loic surveys his class to determine which eye colour is most common and obtains the following results.
Blue, Brown, Brown, Green, Brown, Blue, Hazel, Brown, Brown, Hazel, Brown, Brown,
Blue, Brown,Brown, Brown, Hazel, Brown, Brown, Blue, Brown, Blue, Blue

a. Represent this data as a bar graph.
b. Determine the median of this sample.
c. Identify the mode of this sample.
d. If a student is selected at random from the class, calculate the probability that they don't have brown eyes.


13. Ten randomly chosen students from Class A and Class B each sit for a test in which the highest possible mark is 10. The results of the ten students from the two classes are:

Class A	1	2	3	4	5	6	7	8	9	10
Class B	1	2	2	3	3	4	4	5	9	10

a. Display the data on a dot plot.
b. Calculate measures of centre and spread.
c. Explain any similarities or differences between the results of the two classes.

14. A new whitegoods store opened up in town five weeks ago. The column graph at the right shows the number of fridges they have sold over their first five weeks.

a. Identify the number of fridges they sold in week 2.
b. Describe how the number of fridges sold changed from week to week.
c. Write a formula to describe the number of fridges sold each week over the first five weeks. Let F = the number of fridges sold, and w = the week number.
d. Using your answer to part **b** or **c**, predict the number of fridges they will sell in week 10.



14.6 Stem-and-leaf plots

LEARNING INTENTION

At the end of this subtopic you should be able to:
- display data as a stem-and-leaf plot
- analyse and interpret stem-and-leaf plots.

eles-4724

14.6.1 Stem-and-leaf plots

- A **stem-and-leaf plot** may be used as an alternative to a frequency distribution table.
- Stem-and-leaf plots are used to display numerical data.
- Sometimes the term 'stem-and-leaf plot' is shortened to 'stem plot'.
- Each piece of data in a stem plot is made up of two components: a stem and a leaf.
  For example, the value 28 is made up of 20, a tens component (the stem), and 8, the units component (the leaf).
  In a stem plot, 28 would be written as:
  Key: 2|8 = 28

Stem	*Leaf*
2	8

- It is important to provide a key when drawing up stem plots to make sure the data can be read and interpreted correctly.
- **Ordered stem plots** have the leaf part written in ascending order from left to right.

WORKED EXAMPLE 11 Constructing an ordered stem-and-leaf plot

Prepare an ordered stem-and-leaf plot for each of the following sets of data.
a. 129, 148, 137, 125, 148, 163, 152, 158, 172, 139, 162, 121, 134
b. 1.6, 0.8, 0.7, 1.2, 1.9, 2.3, 2.8, 2.1, 1.6, 3.1, 2.9, 0.1, 4.3, 3.7, 2.6

THINK

a. 1. Rule two columns with the headings 'Stem' and 'Leaf'.
2. Include a key to the plot that tells the reader the meaning of each entry.
3. Make a note of the smallest and largest values of the data (that is, 121 and 172 respectively). List the stems in ascending order in the first column (that is, 12, 13, 14, 15, 16, 17). *Note:* The hundreds and tens components of the number represent the stem.
4. Systematically work through the given data and enter the leaf (unit component) of each value in a row beside the appropriate stem. *Note:* The first row represents the interval 120–129, the second row represents the interval 130–139 and so on.
5. Redraw the stem plot so that the numbers in each row of the leaf column are in ascending order.

WRITE

a. Key: 12|1 = 121

Stem	*Leaf*
12	9 5 1
13	7 9 4
14	8 8
15	2 8
16	3 2
17	2

Key: 12|1 = 121

Stem	*Leaf*
12	1 5 9
13	4 7 9
14	8 8
15	2 8
16	2 3
17	2

b. **1.** Rule the stem and leaf columns and include a key.

2. Include a key to the plot that tells the reader the meaning of each entry.

3. Make a note of the smallest and largest values of the data (that is, 0.1 and 4.3 respectively). List the stems in ascending order in the first column (that is, 0, 1, 2, 3, 4). *Note:* The units components of the decimal represent the stem.

4. Systematically work through the given data and enter the leaf (tenth component) of each decimal in a row beside the appropriate stem. *Note:* The first row represents the interval 0.1–0.9, the second row represents the interval 1.0–1.9 and so on.

5. Redraw the stem plot so that the numbers in each row of the leaf column are in ascending order.

b. Key: 0|1 = 0.1

Stem	*Leaf*
0	8 7 1
1	6 2 9 6
2	3 8 1 9 6
3	1 7
4	3

Key: 0|1 = 0.1

Stem	*Leaf*
0	1 7 8
1	2 6 6 9
2	1 3 6 8 9
3	1 7
4	3

- The advantage of using a stem plot instead of a grouped frequency distribution table is that all the original pieces of data are retained. This means it is possible to identify the smallest and largest values. It is also possible to identify any repeated values. This makes it possible to calculate measures of centre (such as mean, median and mode) and spread (range). These identifications and calculations cannot be done when values are grouped in class intervals.
- The disadvantages of stem plots are:
  - they are not very informative for small sets of data or data that is tightly clustered together
  - they are not very manageable for data that has a large range.

Back-to-back stem-and-leaf plots

- Two sets of data can be displayed using just one stem, by placing the leaf parts for each set on either side of the stem. This is called a **back-to-back stem-and-leaf plot**.
- Back-to-back stem-and-leaf plots are used to display numerical data for two different groups. For example, test scores for two classes, Class A and Class B, can be displayed as shown here:

Key: 5|6 = 56%

Leaf (Class A)	*Stem*	*Leaf (Class B)*
4 3 2	5	6
8 5 3 4 1	6	0 0 2 4
9 6 4 4 3 1 0	7	3 5 6 7 8 8 8 9
8 8 7 5 3	8	0 1 4 6
8 6 3	9	2 3 5 6 7 8

- In a back-to-back stem-and-leaf plot, the values in the leaf are written in ascending order, working outwards from the stem.

WORKED EXAMPLE 12 Constructing a back-to-back stem-and-leaf plot

The ages of male and female groups using a ten-pin bowling centre are listed.

Males: 65, 15, 50, 15, 54, 16, 57, 16, 16, 21, 17, 28, 17, 27, 17, 22, 35, 18, 19, 22, 30, 34, 22, 31, 43, 23, 48, 23, 46, 25, 30, 21

Females: 16, 60, 16, 52, 17, 38, 38, 43, 20, 17, 45, 18, 45, 36, 21, 34, 19, 32, 29, 21, 23, 32, 23, 22, 23, 31, 25, 28

Display the data as a back-to-back stem plot and comment on the distribution.

THINK

1. Rule three columns, headed 'Leaf (female)', 'Stem' and 'Leaf (male)'.
2. Make a note of the smallest and largest values across both sets of data (15 and 65). List the stems in ascending order in the middle column.
3. Beginning with the males, work through the given data and enter the leaf (unit component) of each value in a row beside the appropriate stem.
4. Repeat step 3 for the females' set of data.
5. Include a key that tells the reader the meaning of each entry.
6. Redraw the stem plot so that the numbers in each row of the leaf columns are in ascending order.
   Note: The smallest values are closest to the stem column and increase as they move away from the stem.
7. Comment on any interesting features.

WRITE

Key: 1|5 = 15

Leaf (female)	*Stem*	*Leaf (male)*
987766	1	5566677789
8532331910	2	1872223351
1224688	3	50410
553	4	386
2	5	047
0	6	5

Key: 1 | 5 = 15

Leaf (female)	*Stem*	*Leaf (male)*
987766	1	5566677789
9853332110	2	1122233578
8864221	3	00145
553	4	368
2	5	047
0	6	5

The youngest male attending the ten-pin bowling centre is 15 and the oldest is 65. The youngest female attending the centre is 16 and the oldest is 60. Ten-pin bowling is most popular for men in their teens and 20s, and for females in their 20s and 30s.

COLLABORATIVE TASK: Secret numbers

As a class, construct a stem-and-leaf plot using data supplied by each student.

1. Write a whole number between 210 and 290 on a piece of paper.
2. As a class, decide what the stems will be for this data and come up with a key that matches this.
3. One student should volunteer to draw two columns headed 'Stem' and 'Leaf' on the left-hand side of the board and list the stems in ascending order in the first column. Remember to also include the key that you came up with in step 2.

4. Each student should then come to the board one at a time to write the leaf part of their own number in the appropriate row of the stem-and-leaf plot. Show a classmate your number and have them check that you have written your piece of data in the correct row.
5. Is the stem-and-leaf plot drawn on the board an ordered stem-and-leaf plot? How can you tell? If it is not, how can it be redrawn to make it ordered?
6. Several students should volunteer to use the answers from step 5 to draw the final version of the stem-and-leaf plot on the right-hand side of the board.
7. As a class, make some observations about the distribution of the data. Did any students have the same secret number?
8. Explain whether there is a type of graph that looks similar to a stem-and-leaf plot? Discuss the advantages and disadvantages of using this kind of graph compared with using a stem-and-leaf plot for displaying data.

on Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)
Interactivities Individual pathway interactivity: Stem-and-leaf plots (int-8472)
Stem-and-leaf plots (int-4060)

Exercise 14.6 Stem-and-leaf plots

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 5, 6, 9, 12	2, 3, 7, 10, 13	4, 8, 11, 14

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE11 The following data gives the number of fruit that have formed on each of 40 trees in an orchard.



29, 37, 25, 62, 73, 41, 58, 62, 73, 67, 47, 21, 33, 71,
92, 41, 62, 54, 31, 82, 93, 28, 31, 67, 29, 53, 62, 21,
78, 81, 51, 25, 93, 68, 72, 46, 53, 39, 28, 40

Prepare an ordered stem plot that displays the data.

2. The number of mistakes made each week by 30 machine operators is recorded below.

12, 2, 0, 10, 8, 16, 27, 12, 6, 1, 40, 16, 25, 3, 3 12,
31, 19, 22, 15, 7, 17, 21, 18, 32, 33, 12, 28, 31, 32, 14

Prepare an ordered stem plot that displays the data.

3. Prepare an ordered stem plot for each of the following sets of data.
   a. 132, 117, 108, 129, 165, 172, 145, 189, 137, 116, 152, 164, 118
   b. 131, 173, 152, 146, 150, 171, 130, 124, 114
   c. 207, 205, 255, 190, 248, 248, 248, 237, 225, 239, 208, 244
   d. 748, 662, 685, 675, 645, 647, 647, 708, 736, 691, 641, 735

4. Prepare an ordered stem plot for each of the following sets of data.
   a. 1.2, 3.9, 5.8, 4.6, 4.1, 2.2, 2.8, 1.7, 5.4, 2.3, 1.9
   b. 7.7, 6.0, 9.3, 8.3, 6.5, 9.2, 7.4, 6.9, 8.8, 8.4, 7.5, 9.8
   c. 14.8, 15.2, 13.8, 13.0, 14.5, 16.2, 15.7, 14.7, 14.3, 15.6, 14.6, 13.9, 14.7, 15.1, 15.9, 13.9, 14.5
   d. 0.18, 0.51, 0.15, 0.02, 0.37, 0.44, 0.67, 0.07

5. **WE12** The number of goals scored in football matches by Mitch and Yani were recorded as follows.

Mitch	0	3	1	0	1	2	1	0	0	1
Yani	1	2	0	1	0	1	2	2	1	1

Display the data as a back-to-back stem plot and comment on the distribution.

Understanding

6. Answer the following questions for the back-to-back stem plot in question 5.
   a. Determine the number of times each player scored more than 1 goal.
   b. State who scored the greatest number of goals in a match.
   c. State who scored the greatest number of goals overall.
   d. State who is the more consistent performer.

7. The stem plot shown gives the ages of members of a theatrical group.
   a. Determine the number of people that are in the theatrical group.
   b. Identify the age of the youngest member of the group.
   c. Identify the age of the oldest member of the group.
   d. Determine the number of people who are over 30 years of age.
   e. State the most common age in the group.
   f. Determine the number of people who are over 65 years of age.

Key: 2 | 4 = 24

Stem	*Leaf*
1	7 8 8 9 9
2	2 4 7 9
3	1 3 3 8
4	0 2 2 2 6 6
5	5 7
6	4

8. Sprint times, in seconds, over 100 metres were recorded for a random sample of 20 runners as follows.

10.8, 11.0, 12.0, 13.2, 12.4, 13.9, 11.8, 12.8, 14.0, 15.0,
11.2, 12.6, 12.5, 12.8, 13.6, 11.5, 13.6, 10.9, 14.1, 13.9

   a. Show the data as a stem-and-leaf plot.
   b. Comment on the range of performance and other interesting points.
   c. Draw conclusions about the runners' performances.

Reasoning

9. Explain why it is important to use a key with all stem-and-leaf plots. Give an example to illustrate your answer.

10. Explain why it is important to order and align data values when constructing a stem-and-leaf plot.

11. The scores in a Mathematics test for two classes are shown in the following table.

7F	91	77	85	82	43	84	77	79	78	92	81	80	41	88
7G	76	85	82	74	89	83	68	66	78	82	80	78	75	76

   a. Display the data as a back-to-back stem-and-leaf plot.
   b. Calculate the mean and median for each class.
   c. Explain which of these measures of centre is the most appropriate in this situation.

Problem solving

12. The following stem-and-leaf plot displays the ages of a sample of people who were in a grocery store on a particular day.

Key: 2 | 1 = 21

Stem	*Leaf*
1	8
2	2 4
3	0 9
4	1 3 3 5 8
5	7
6	5
7	1 3

a. Determine the range of their ages.
b. Determine the mode of their ages.
c. One more person in the store is added to the sample. The mean is now equal to the mode. Determine the age of this additional person. Show your working.

13. The following data shows the maximum temperature for 7 straight days in two different cities. The temperatures were recorded in the month of Feburary.

City A	25	23	21	24	29	36	30
City B	20	17	13	13	12	12	13

a. Display the data as a back-to-back stem-and-leaf plot.
b. Calculate the range, median, mean and mode for each city.
c. One of the cities is in the northern hemisphere and the other is in the southern hemisphere. Use your answers to part **b** to determine which city is in the northern hemisphere and which is in the southern hemisphere.

14. Percentages in a Mathematics exam for two classes were as follows:

9A	32	65	60	54	85	73	67	65	49	96	57	68
9B	46	74	62	78	55	73	60	75	73	77	68	81

a. Construct a back-to-back stem plot of the data.
b. Determine the percentage of each group who scored above 50.
c. State which group had more scores over 80.
d. Compare the clustering for each group and comment on any extreme values.
e. Parallel dot plots are obtained by constructing individual dot plots for each set of data and positioning them on a common scale. Construct a parallel dot plot of the data (use colour).
f. Compare class performances by reference to both graphs.

14.7 Pie charts and divided bar graphs


LEARNING INTENTION

At the end of this subtopic you should be able to:
- display data as a sector graph (pie chart)
- display data as a divided bar graph
- analyse and interpret sector and divided bar graphs.


14.7.1 Sector graphs and divided bar graphs

eles-4725

- **Sector graphs** or pie charts, are made up of sectors of a circle. **Divided bar graphs** are made up of a rectangle divided into bars.
- Both of these types of graphs are used to represent categorical data — they are not suitable for numerical data.
- The sector graph and divided bar graph shown have six different sectors.



- In a sector graph the sectors should be ordered from largest to smallest in a clockwise direction (starting at 12 o'clock).
- In a divided bar graph the bars should be ordered largest to smallest from left to right.



- Each sector or bar must be labelled appropriately either on the graph or using a legend.


Drawing sector graphs and divided bar graphs by hand

- To draw sector graphs and divided bar graphs you must determine the fraction (or percentage) of the total that is represented by each category.
- The fraction of the whole that each category represents should correspond to the fraction/percentage of the sector/divided bar graph.
- The following table shows how to draw a sector graph and a divided bar graph from data.


Category	Frequency	Fraction of total	Angle at centre of circle	Length of bar
A	3	$\frac{3}{12} = \frac{1}{4}$	$\frac{1}{4} \times 360° = 90°$	$\frac{1}{4} \times 12 = 3\text{ cm}$
B	4	$\frac{4}{12} = \frac{1}{3}$	$\frac{1}{3} \times 360° = 120°$	$\frac{1}{3} \times 12 = 4\text{ cm}$
C	5	$\frac{5}{12}$	$\frac{5}{12} \times 360° = 150°$	$\frac{5}{12} \times 12 = 5\text{ cm}$
Total	12			

- A protractor and a ruler are required to draw these graphs by hand.

A sector graph



A divided bar graph



Drawing sector graphs and bar graphs using technology

- The quickest and easiest way to create sector graphs and divided bar graphs is to use a spreadsheet such as Microsoft Excel.
- The following worked examples provide a detailed explanation of how to create sector graphs and divided bar graphs in Microsoft Excel.


WORKED EXAMPLE 13 Constructing a sector graph

Of 120 people surveyed about where they would prefer to spend their holidays this year, 54 preferred to holiday in Australia, 41 preferred to travel overseas and 25 preferred to stay at home. Use a spreadsheet program such as Microsoft Excel to represent the data as a sector graph.


THINK

1. Input the data into a spreadsheet in order from largest category to smallest category. Put labels along the top row and numbers along the second row.


WRITE




2. Select the data.




3. Click **insert**, select the **Insert Pie or Doughnut Chart** icon then click **Pie.**




4. The chart will appear.



5. Rename the chart by clicking **Chart Title** and writing a name for your chart.



6. Click on the **Chart Elements** in the top right corner and select **Data Labels**.



WORKED EXAMPLE 14 Constructing a divided bar graph

From a community group, 90 people were surveyed about their favourite weekend activities. Of these, 43 people preferred to go to the beach, 25 preferred to watch sports and 22 preferred to go shopping. Use a spreadsheet program such as Microsoft Excel to represent the data as a divided bar graph.

THINK

WRITE

1. Input the data into a spreadsheet in order from largest category to smallest category. Put labels along the top row and numbers along the second row.




2. Select the data.




3. Click **insert**, select the **Insert Column or Bar Chart** icon then click **More Column Charts**.




4. From the **Bar** options, select the second option at the top then click the second graph and click **OK**.




5. The chart will appear.



6. Rename the chart by clicking **Chart Title** and writing a name for your chart.



7. Click on the **Chart Elements** in the top right corner and select **Data Labels**.



Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)

Interactivities Individual pathway interactivity: Pie charts and divided bar graphs (int-8473)
Pie graphs (int-4061)

Exercise 14.7 Pie charts and divided bar graphs

learnON


Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 6, 9, 12, 13, 16	4, 5, 7, 10, 14, 17	3, 8, 11, 15, 18

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. A survey was conducted of a group of students to determine their method of transport to school each day. The following sector graph displays the survey's results.




a. State the number of students surveyed.
b. State the most common method of transport to school.

2. **WE13** The following table shows the different sports played by a group of Year 7 students.

a. Complete the table.
b. Draw a sector graph to display the data.
c. Use technology to represent the data as a sector graph.


Sport	Number of students	Fraction of students	Angle at centre of circle
Basketball	55	$\frac{55}{180}$	$\frac{55}{\cancel{180}^{1}} \times \frac{\cancel{360°}^{2}}{1} = 110°$
Netball	35	$\frac{35}{180}$	
Soccer	30		
Football	60		
Total	180		

3. The sector graph shown displays the candidates and the percentage of votes received in a community organisation's recent election.



a. State who received the highest number of votes.
b. State the percentage of votes Paula received.
c. Can this sector graph tell us how many people voted in the election? Explain your answer.
d. Calculate the size of the angle for the sector representing Brigid's votes. Give your answer to 2 decimal places.

4. The sector graph shown displays the results of a student election.




a. Identify the percentage of votes that went to Danielle.
b. Identify the percentage of votes that went to Andrew.
c. Calculate the percentage of votes that went to Christiana.
d. Evaluate the total of the percentages.
e. Using calculations, determine the size of the angle of each sectors showing the votes for each of the 3 candidates.

5. For the following table of values showing the type of roofing material used in 36 houses, answer the following questions.

a. Complete the fraction and angle size columns in the table.
b. Draw a sector graph to display the data.
c. Use technology to represent the data as a sector graph.

Roofing material	Number of houses	Fraction	Angle size (°)
Concrete tiles	12		
Terracotta tiles	9		
Galvanised iron	6		
Colourbond	3		
Slate	2		
Shingles	4		
Total	36		

6. The following divided bar graph displays the types of dogs in a dog rescue centre.



a. Based on this graph, calculate the total number of dogs in the rescue centre.
b. Identify the number of Labradors that are in the centre.
c. Identify the number of Rottweilers that are in the centre.
d. Calculate the percentage of the total number of dogs that are terriers.
e. State which type of dog there are the fewest of.

7. **WE14** The following table of values shows the number of kilograms of meat of various types that a butcher sold in a day.

   a. Copy and complete the table of values.
   b. Construct a divided bar graph to display the data.
   c. Use technology to represent the data as a divided bar graph.

Type of meat	Amount sold (kg)	Fraction
Lamb	10	
Beef	45	
Pork	5	
Chicken	15	
Turkey	10	
Rabbit	5	
Total	90	

8. The students at Mount Birdie Secondary College counted the number of birds that landed on their school oval on one day. The results are in the following table.

Type of bird	Number of birds	Fraction
Magpie	24	
Crow	12	
Cockatoo	12	
Wattlebird	6	
Rosella	6	
Total	60	

   a. Copy and complete this table.
   b. Use technology to represent the data as:
      i. a sector graph
      ii. a divided bar graph.


Understanding

9. The following table shows the different forms of transport that 100 students use to get to school.

   a. Copy the table and complete the *Fraction* column (the first one has been done for you).
   b. Using a total bar length of 10 cm, complete the *Length of bar* column (the first one has been done for you).
   c. Represent the data as a divided bar graph.
   d. If the total bar length was 5 cm (instead of 10 cm) calculate how long the *Walk* section would be.


Transport	Number of students	Fraction	Length of bar
Walk	50	$\frac{50}{100} = \frac{1}{2}$	$\frac{1}{2} \times 10 = 5$ cm
Car	20		
Bus	15		
Bike	15		
Total	100		

10. The sector graph shown represents the favourite colours of 200 students. The angle of each section is shown.



a. Calculate the number of students who said their favourite colour was blue.
b. Calculate the number of students who said their favourite colour was orange.
c. Calculate the number of students who said their favourite colour was purple.

11. The sector graph shown represents the furniture sold at Devin's Furniture Land over the period of one week. The total number of sales was 90 items. Calculate the number of pieces of each furniture item that were sold. Use a protractor to measure the angles in the sector graph.



12. State which type of data is represented by the following graphs: column and bar graphs, dot plots, stem-and-leaf plots and sector graphs.

Reasoning

13. Discuss the advantage of using a divided bar graph to display categorical data, rather than a column graph.

14. The following two sector graphs represent the sales at Charlie's Kiosk. One sector graph is from summer and one sector graph is from winter.

Graph 1



Graph 2



a. State which graph represents the sales from summer.
b. Explain your answer to part **a**.

15. For the table of values showing the sports played by a group of students, answer the following questions.

a. Complete the angle size column before drawing a sector graph to display the data.
b. In this data we are not told how many students were surveyed.
i. Explain why the data could not represent ten students.
ii. Explain why the data could represent twenty students.

Sport	Percentage of total	Angle size (°)
Cricket	20	
Hockey	25	
Netball	40	
Soccer	10	
Tennis	5	
Total	100	

Problem solving

16. Omar is working on his budget. His income is $2000 per month and the following divided bar graph shows how he is currently spending his money. Omar needs your help to increase the amount he saves.



a. Omar does not want to move house and he cannot change his utility bills. Determine the sections of the bar graph that must stay the same.

b. Determine the much Omar is currently spending on food and entertainment in total.

c. If Omar halves the amount he spends on food and entertainment and puts that money into savings, determine how much he would:


i. spend on food

ii. spend on entertainment

iii. put into savings in total each month.

d. Use technology to draw a new divided bar graph showing the changes to Omar's budget you made in part **c**.

17. Beach Brellas Inc. is designing a new beach umbrella using the design shown.




a. Determine the percentage of the umbrella that is blue.

b. Determine the angle for one section of the umbrella.

c. If it takes 1.5 m^2 of fabric to make the whole design, determine how much of each colour fabric is needed to make the design. Give your answer to three decimal places and include units.

18. The sector graph shown has four sectors representing different amounts. Starting at the smallest sector, each new sector is double the size of the previous one. Without using a protractor, calculate the third sector as a percentage. Show your working.



14.8 Comparing data

LEARNING INTENTION

At the end of this subtopic you should be able to:

- calculate measures of centre and spread from a graphical display
- identify the most appropriate measure of centre for a graphical display.

14.8.1 Determining measures of centre and spread from graphs

eles-4726

- We have considered the calculation of measures of centre and spread from lists of data.
- We also need to know how to calculate these measures from graphs of individual pieces of data.
- We can then make comparisons between data presented in listed form and data presented in graphical form.
- When data is displayed graphically, the spread may be obvious, but we often need to calculate the data's measures of centre so that we can understand it better.
- We also need to be able to determine which measure of centre best represents the data.

Determining the most appropriate measure of centre

- If a set of data contains outliers, the median is the most appropriate measure of centre because outliers do not affect it, whereas outliers can significantly affect the value of the mean.
- If a set of data does not contain outliers, the mean or median could be used as the measure of centre. Since the concept of the mean (or average) is more familiar to most people, it is generally used in preference to the median.
- The mode is not normally considered a good measure of centre because it tells us only about the most common score.

WORKED EXAMPLE 15 Determining measures of centre and spread from a dot plot

a. Use the dot plot shown to determine the following statistical measures.
i. Mean **ii. Median** **iii. Mode** **iv. Range**
b. Comment on the most suitable measure of centre for the data.



THINK

a. i. 1. Determine the sum of the values.

2. Count the number of values.

3. Calculate the mean by dividing the sum by the total number of values.

WRITE

a. Sum of values $= 16 + 3 \times 18 + 4 \times 19 + 2 \times 20 + 21 + 24$
$= 231$

There are 12 values.

$$\text{Mean} = \frac{\text{sum of data values}}{\text{total number of data values}}$$
$$= \frac{231}{12}$$
$$= 19.25$$

ii. 1. The values are already in order. The median is the middle value. There are 12 values, so the middle one is the average of the 6th and 7th values.

The 6th and 7th values are both 19.

2. Calculate the average of these.

The median value is 19.

iii. The mode is the most common value. Look for the one that occurs most frequently.

The mode is 19.

iv. The range is the difference between the largest value and the smallest value.

$$\text{Range} = 24 - 16 = 8$$

b. The scores 16 and 24 are possible outliers. When a set of data contains outliers the best measure of centre is the median, as it is not affected by outliers as much as the mean.

b. Since there may be outliers in the data, the median is the most suitable measure of centre in this case.

WORKED EXAMPLE 16 Determining measures of centre and spread from a stem plot

a. Use the stem plot to determine the following measures of the data.
- **i. Mean**
- **ii. Median**
- **iii. Mode**
- **iv. Range**

b. Comment on the most suitable measure of centre for the data.

Key: 1|8 = 18

Stem	*Leaf*
1	8 9
2	2 2 5 7 7 8
3	0 1 4 6 7
4	0 5

THINK

WRITE

a. i. 1. Determine the sum of the values.

a. i. $\text{Sum of values} = 18 + 19 + 22 + 22 + 25 + 27 + 27 + 28 + 30 + 31 + 34 + 36 + 37 + 40 + 45 = 441$

2. Count the number of values.

There are 15 values.

3. Calculate the mean by dividing the sum by the total number of values.

$$\text{Mean} = \frac{\text{sum of data values}}{\text{total number of data values}} = \frac{441}{15} = 29.4$$

ii. The values are already in order. The median is the middle value. There are 15 values, so the middle one is the 8th value. Locate this.

The middle position of the 15 values is the 8th value. This is 28. The median value is 28.

iii. The mode is the most common value. Look for the one that occurs most frequently.

There are two modes (the data set is bimodal): 22 and 27.

iv. The range is the difference between the largest value and the smallest value.

$$\text{Range} = 45 - 18 = 27$$

b. Look at the measures of mean, median and mode to see which best represents the values in terms of their closeness to the centre.

b. Because there does not appear to be any outliers, the mean or median could be used to represent the centre of this set of data.

Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)

Interactivities Individual pathway interactivity: Comparing data (int-4382)

Determining measures of centre and spread from graphs (int-4062)

Exercise 14.8 Comparing data

learnON


Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 7, 13, 16	2, 5, 8, 9, 10, 14, 17	3, 11, 12, 15, 18

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.


Fluency

1. WE15 Consider the dot plot shown.




   a. Use the dot plot to determine the following measures of the data.
   i. mean **ii.** median **iii.** mode **iv.** range
   b. Comment on the most suitable measure of centre for the data.

2. Consider the dot plot shown.



   a. Use the dot plot to determine the following measures of the data.
   i. mean **ii.** median **iii.** mode **iv.** range
   b. Comment on the most suitable measure of centre for the data.

3. Consider the dot plot shown.



   a. Use the dot plot to determine the following measures of the data.
   i. mean **ii.** median **iii.** mode **iv.** range
   b. Disregard the score of 10 and recalculate each of these values.
   c. Discuss the differences/similarities in your two sets of results.

4. WE16 Consider the stem-and-leaf plot shown.

Key: 6.1|8 = 6.18

Stem	*Leaf*
6.1	8 8 9
6.2	0 5 6 8
6.3	0 1 2 4 4

   a. Use the stem plot to determine the following measures of the data.
   i. mean
   ii. median
   iii. mode
   iv. range
   b. Comment on the most suitable measure of centre for the data.

5. Consider the stem-and-leaf plot shown.

Key: 1|10 = 10

Stem	*Leaf*
1	0 2
2	1 3 3 5
3	
4	4

a. Use the stem plot to determine the following measures of the data.
- **i.** mean
- **ii.** median
- **iii.** mode
- **iv.** range

b. Disregard the score of 44 and recalculate each of these values.
c. Discuss the differences/similarities in your two sets of results.

Understanding

6. MC Select the score that shows up most often.
A. median **B.** mean **C.** mode **D.** average **E.** frequency

7. MC Select the best term for *average* in everyday use.
A. the mean **B.** the mode **C.** the median **D.** the total **E.** none of these

8. MC Choose the measure affected by outliers (extreme values).
A. the middle
B. the mode
C. the median
D. the mean
E. none of these

The back-to-back stem plot shown displays the heights of a group of Year 7 students. Use this plot to answer questions **9** and **10**.

Key: 13 | 7 = 137cm

Leaf (boys)	*Stem*	*Leaf (girls)*
9 8	13	7 8
9 8 8 7 6	14	3 5 6
9 8 8	15	1 2 3 7
7 6 6 5	16	3 5 6
8 7 6	17	1

9. MC Select the total number of Year 7 students.
A. 13 **B.** 17 **C.** 30 **D.** 36 **E.** 27

10. MC Choose the tallest male and shortest female heights.
A. 186 cm and 137 cm
B. 171 cm and 148 cm
C. 137 cm and 188 cm
D. 178 cm and 137 cm
E. None of these

11. A survey of the number of people in each house in a street produced the following data:



2, 5, 1, 6, 2, 3, 2, 1, 4, 3, 4, 3, 1, 2, 2, 0, 2, 4

- **a.** Prepare a frequency distribution table with an $f \times x$ column and use it to calculate the average (mean) number of people per household.
- **b.** Draw a dot plot of the data and use it to find the median number per household.
- **c.** Calculate the modal number per household.
- **d.** State which measure of centre (mean, median or mode) would be most useful to:
  - **i.** real estate agents renting out houses
  - **ii.** a government population survey
  - **iii.** an ice-cream truck owner.

12. The mean of 12 scores is 6.3. Calculate the total of the scores.

Reasoning

13. A class of 26 students had a median mark of 54 in Mathematics, even though no-one actually scored this result.

- **a.** Explain how this is possible.
- **b.** Explain how many students must have scored below 54.

14. A clothing store records the dress sizes sold during one day in order to work out the most popular sizes. The results for a particular day are given below.

12, 14, 10, 12, 8, 12, 16, 10, 8, 12, 10, 12, 18, 10, 12, 14
16, 10, 12, 12, 12, 14, 18, 10, 14, 12, 12, 14, 14, 10

Rebecca is in charge of marketing and sales. She uses these figures when ordering future stock. From these figures she decides on the following ordering strategy. She will order:

- the same number of size 8, 16 and 18 dresses
- three times this number of size 10 and size 14 dresses
- five times as many size 12 dresses as size 8, 16 and 18.

Comment on Rebecca's strategy.

15. A small business pays these salaries listed below (in thousands of dollars) to its employees.

18, 18, 18, 18, 26, 26, 26, 35

The business owner's salary is 80 thousand dollars.

- **a.** Determine the wage earned by most workers. Make sure to include the business owner's salary in this calculation.
- **b.** Calculate the average wage. Show your working.
- **c.** Calculate the median of the distribution.
- **d.** Explain which measure of centre might be used in salary negotiations by:
  - **i.** the union that represents the business's employees
  - **ii.** the business owner.

Problem solving

16. Five scores have an average of 8.2. Four of those scores are 10, 9, 8 and 7. Determine the fifth score.

17. A tyre manufacturer selects 48 tyres at random from their production line for testing. The total distance travelled during the safe life of each tyre is shown in the following table.

Distance in km ('000)	46	50	52	56	78	82
Number of tyres	4	12	16	10	4	2



a. Calculate the mean, median and mode.
b. Explain which measure best describes the average safe life of these tyres.
c. Recalculate the mean with the 6 longest-lasting tyres removed. Determine how much it is lowered by.
d. If you selected a tyre at random, determine how long it would most likely last.
e. In a production run of 10 000 tyres, determine how many could be expected to last for a maximum of 50 000 km.
f. If you were the tyre manufacturer, explain what kind of distance guarantee you would be prepared to offer on your tyres.

18. A soccer team had averaged 2.6 goals per match after 5 matches. After their 6th match the average dropped to 2.5 goals per match. Determine the number of goals they scored in their 6th match. Show your working.



14.9 Review

14.9.1 Topic summary



Types of data

- There are two main types of data: *categorical* data and *numerical* data.

Categorical data	Numerical data
Data that can be placed into a group or category e.g. Eye colour, gender, shoe size, rating scale (high, medium, low)	Data that can be counted or measured • **Discrete** numerical data can be counted. e.g. The number of people in a room • **Continuous** numerical data can be measured. e.g. A person's height

REPRESENTING AND INTERPRETING DATA

Frequency distribution tables

- Frequency is the number of times a result or piece of data occurs.
- A frequency table shows the score, tally and frequency in a tabular form.

e.g.

Age group (score)	Tally	Frequency
11–20	IIII	4
21–30	II	2
31–40	I	1
	Total	7

Representing data graphically

- There are many types of graphical displays to represent data.
- For *categorical* data the most appropriate graphical displays are:
  - frequency table
  - column or bar graph
  - sector graph (pie chart)
  - divided bar graph.
- For *numerical* data the most appropriate graphical displays are:
  - frequency table
  - dot plot
  - stem-and-leaf plot.

Measures of centre

- A measure of centre gives us some idea about the location of the centre of the data.
- The three measures of centre are *mean*, *median* and *mode*.
- The **mean** is commonly referred to as the *average*.
  The symbol used to represent the mean is $\bar{x}$.
  The formula used to calculate the mean is:

$$\bar{x} = \frac{\text{sum of data values}}{\text{total number of data values}}.$$

- The **median** represents the middle score when the data is ordered from smallest to largest.

  e.g. 1, 1, 3, 4, **4**, 10, 12, 25, 41
  Median = 4

- The **mode** is the most commonly occurring value in a data set. Data sets might have one mode, no mode or more than one mode.

Comparing data

- By calculating measures of centre, we can make comparisons between data sets.
  e.g. Mean battery life is higher for brand A batteries than for brand B so, on average, brand A batteries last longer.
- When extreme values (outliers) are present in a data set, the best measure of centre is the median as it is least affected by outliers.

Measures of spread

- A measure of spread tells us how spread out the data is.
- The **range** is one measure of spread; it is the difference between the largest and smallest values in that set.

  Range = largest value − smallest value

14.9.2 Success criteria

Tick the column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)


Subtopic	Success criteria			
14.2	I can describe types of data using the key words 'categorical' (discrete) or 'numerical' (continuous).			
	I understand the difference between primary and secondary data.			
	I can explain why some data is more reliable than other data.			
14.3	I can construct a frequency distribution table for a set of data.			
	I can analyse and report on the information in a frequency distribution table.			
14.4	I can calculate the mean, median and mode of a set of data.			
	I can calculate the range of a set of data.			
14.5	I can display data as a column or bar graph.			
	I can display data as a dot plot.			
	I can analyse and interpret column and bar graphs and dot plots.			
14.6	I can display data as a stem-and-leaf plot.			
	I can analyse and interpret stem-and-leaf plots.			
14.7	I can display data as a sector graph (pie chart).			
	I can display data as a divided bar graph.			
	I can analyse and interpret sector and divided bar graphs.			
14.8	I can calculate measures of centre and spread from a graphical display.			
	I can identify the most appropriate measure of centre for a graphical display of data.			

14.9.3 Project

Families with children

Surveys help us to find out about lots of different things. They can be conducted by collecting information from an entire population or smaller groups. The information collected in a survey, known as data, can be examined and presented in many different ways. Graphs are commonly used to present the results of a survey.

The graph shown displays the percentage of families in Australia with children under the age of 15. This data is taken from the 2011 census.



1. State the type of graph that has been used to display the information.
2. State the most common category of Australian families with children under 15.
3. Give an example of another type of graph that could be used to present this information.

Conduct your own survey of the number of children under 15 in your classmates' families. Compare your results with the results of the 2011 census.

4. Record your survey results in the following frequency distribution table.

Number of children	Tally	Frequency	Percentage
1			
2			
3			
4 or more			
	Total		

5. Is the survey you conducted an example of a *census* (contains the entire population) or a *sample* (contains only a portion of the entire population)? Explain your answer.
6. Explain whether the data you collected is classified as categorical data or numerical data.
7. Present the information from your survey as a column graph. Use the percentage values on the vertical axis and number of children on the horizontal axis.
8. Explain how the results of your class compare with the results obtained in the 2011 census. Discuss the major difference between these two sets of results.
9. Design and conduct a new survey on a topic of interest (choose the topic as a class). You can survey members of your class on this topic or expand it to include a larger target audience. Present your data as a poster that displays the findings of your survey using an appropriate style of graph.

on Resources

eWorkbook Topic 14 Workbook (worksheets, code puzzle and project) (ewbk-1915)

Interactivities Crossword (int-2608)
Sudoku puzzle (int-3174)

Exercise 14.9 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Identify whether the following statement is true or false.
   The classification of data describing the number of iPhones sold during the year is continuous.

2. State whether the data that describes a person's mass (in kilograms) is categorical, discrete or continuous.

3. State whether the data that describes sandwich types at a takeaway outlet is categorical, discrete or continuous.

4. Eighty students in a school of 800 participated in a survey to find their favourite drinks. The results were: Coke 20, Pepsi 14, other soft drink 10, milk/milk-based 16, coffee 9, tea 4 and fruit juice 7.
   a. Identify the most popular beverage.
   b. Identify the least popular beverage.

5. Use the frequency distribution table shown to answer the following questions.

Score	Frequency
13	2
14	9
15	3
16	5
17	6
18	1

   a. Calculate the number of students in the class.
   b. State the most frequent score.
   c. State the least frequent score.
   d. Determine the number of students who scored 15 or less.
   e. Determine the number of students who scored at least 16.

6. A random sample of 24 families was surveyed to determine the number of vehicles in each household. The following list is the raw data.

   2, 0, 3, 2, 1, 0, 2, 3, 4, 2, 2, 1, 0, 1, 3, 2, 1, 0, 0, 0, 2, 2, 3, 3

   a. Organise the data into a frequency distribution table.
   b. Identify the number of families who have no vehicles in their household.
   c. Determine the number of families who have two or more vehicles in their household.
   d. Identify the score that has the highest frequency.
   e. State the highest score.
   f. Calculate the fraction of families who had two vehicles in their household.


7. For the following sets of data, determine the following.

i. the mean **ii.** the mode **iii.** the median

a. 4, 4, 4, 3, 2, 2, 3 **b.** 2, 4, 2, 4, 3, 7, 4 **c.** 4, 5, 6, 6, 5, 5, 3

d. 1, 2, 1, 4, 1, 5, 1 **e.** 5, 8, 1, 7, 7, 5, 2, 7, 5, 5 **f.** 1, 5, 8, 7, 4, 8, 5, 6, 8

8. The graph shown displays the test marks of a group of students.



a. State the label on the horizontal axis.

b. State the scale used on the vertical axis.


c. State the name of the student with the highest mark.

d. Determine which student(s) would have failed if the pass mark was 50%.

e. Identify Paul's mark.

f. Identify George's mark.

9. Look at the following graph, showing air quality.



a. State what the horizontal axis represents.

b. State what the vertical axis represents.

c. Identify the region with a rating that ranged from very good to good every day.

d. Determine the day when the Western region had a fair to poor air quality rating.

e. Determine the region with a rating that ranged from good to fair every day.

10. **a.** The following data gives the speed of 30 cars recorded by a roadside speed camera along a stretch of road where the speed limit is 80 km/h.

75, 90, 83, 92, 103, 96, 110, 92, 102, 93, 78, 94, 104, 85, 88,
82, 81, 115, 94, 84, 87, 86, 96, 71, 91, 91, 92, 104, 88, 97

Present the data as an ordered stem-and-leaf plot.

b. Comment on the data recorded by the roadside speed camera.

11. Complete the specified tasks for the given sets of data.

Set A	64	30	59	1	57	13	45	28
Set B	3	41	38	68	29	32	30	31

a. Construct a back-to-back stem plot of the two sets of data.

b. For each data set, determine the:

i. lowest score **ii.** highest score **iii.** mean **iv.** median **v.** range.

c. Compare the two data sets.

12. Consider the dot plot shown, which represents the number of soft drinks sold at lunchtime over a 20-day period from a vending machine in a school cafeteria in the USA.



a. Use the dot plot to determine the following.

i. mean **ii.** median **iii.** mode **iv.** range

b. Comment on the distribution of the data.

13. Consider the stem plot shown, which represents the ages of participants in an aerobics class at a gym.

Key: 1|7 = 17

Stem	*Leaf*
1	4 7 8 8 9
2	0 1 3 5 6 7 9
3	2 4 5 6 7 8
4	2 5
5	3



a. Use the graph to determine the:

i. mean age

ii. median age

iii. modal age

iv. range of ages.

b. Comment on the distribution of the data.

14. A group of 150 people were surveyed about what they had for breakfast that morning. Of the people surveyed, 62 had cereal, 70 had toast, 12 had a cooked breakfast and 6 had no breakfast. Use technology to represent the data as a sector graph.

15. Use technology to draw a divided bar chart to display the following data.

Hobby	Percentage of total
Stamp collecting	20
Photography	15
Sailboarding	20
Skateboarding	30
Model making	15
Total	100

Problem solving

16. This table shows the maximum and minimum daily temperatures in a city over a one-week period.

Day	1	2	3	4	5	6	7
Maximum (°C)	12	13	10	11	9	10	8
Minimum (°C)	3	3	2	1	0	4	2

Use the table to answer the following questions.

a. State the maximum temperature on day 3.
b. State the day that had the lowest minimum temperature.
c. Determine the coldest day.
d. Identify the day that had the warmest overnight temperature.
e. Calculate the temperature range (variation) on day 2.
f. Determine the day that had the smallest range of temperatures.

The table shown is part of a teacher's mark book. Use it to answer questions **17** and **18**.

Name	Test 1	Test 2
John	85	94
Peter	85	63
Mark	95	58
James	82	67
David	76	95
Rachel	62	85
Mary	87	75
Eve	94	63
Esther	68	68

17. **a.** Calculate the class mean for test 1.
b. Calculate the class mean for test 2.
c. Identify the test in which the class received better marks.
d. Determine the number of students who scored above the mean in test 1.
e. Determine the number of students who scored above the mean in test 2.

18. **a.** Determine the mode score for test 1.
b. Determine the mode score for test 2.
c. Determine the median score for test 1.
d. Determine the median score for test 2.
e. Calculate the mean score for the two tests for each student and list them.
f. Determine the range of values for these means.

19. The results of height measurements (in cm) for the students in class 9A are given below.

145, 152, 148, 152, 163, 148, 165, 158, 159, 162, 145, 153, 156, 158, 157,
159, 169, 156, 156, 156, 152, 154, 128, 141, 154, 153, 156, 156, 165, 168

a. Calculate the range of heights.
b. Calculate the mean height of the class.
c. Determine the mode for the heights.
d. Determine the median height of the class.
e. Explain whether these three values (mean, mode, median) are similar.



20. Use the table of values shown to answer the following questions.

Month	Number of files (thousands)
January	24
February	28
March	26
April	20
May	18
June	15
July	12
August	10
September	11
October	12
November	15
December	19

a. State what would be on the horizontal axis in drawing a column graph using this data.
b. State what would be on the vertical axis in drawing a column graph.
c. Identify the minimum value required on the vertical axis.
d. Identify the maximum value required on the vertical axis.
e. Determine the scale that should be used for the vertical axis.
f. Draw a column graph to display the data.

21. The number of pets cared for by each of 20 families was surveyed, giving the following data.



1, 2, 3, 2, 0, 1, 0, 2, 5, 3, 2, 1, 2, 0, 2, 0, 1, 3, 2, 1

a. Organise the data into a frequency distribution table.
b. Draw a dot plot of the data and comment on the distribution.
c. Calculate the mode, median and mean.

22. a. For the given set of scores 9, 3, 8, 5, 6, 9, 4, 5, 5, 25, determine the following.
i. mode
ii. median
iii. mean
iv. outliers (if any)
v. mean when outliers are omitted
vi. mean and median when 10 is added to *each* of the given scores
b. Comment on any discoveries from part **a**.

23. This back-to-back stem-and-leaf plot shows the heights of a group of boys and girls.



Key: 13 | 7 = 137 cm

Leaf (boys)	*Stem*	*Leaf (girls)*
9 8	13	7 8
9 8 8 7 6	14	3 5 6
9 8 8	15	1 2 3 7
7 6 6 5	16	3 5 6
8 7 6	17	1

Give a full description of the heights of the boys and the girls.

To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

eWorkbook

Download the workbook for this topic, which includes worksheets, a code puzzle and a project (ewbk-1915) ☐

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0703) ☐

Digital documents

14.2 SkillSHEET Distinguishing discrete from continuous data (doc-6579) ☐
14.4 SkillSHEET Finding the mean of ungrouped data (doc-6580) ☐
SkillSHEET Finding the median (doc-6581) ☐

Video eLessons

14.2 How to classify data (eles-4716) ☐
Primary and secondary data (eles-4717) ☐
14.3 Frequency distribution tables (eles-4718) ☐
14.4 Measures of centre (eles-4719) ☐
Measures of spread (eles-4720) ☐
14.5 Column and bar graphs (eles-4721) ☐
Dot plots (eles-4723) ☐
14.6 Stem-and-leaf plots (eles-4724) ☐
14.7 Sector graphs and divided bar graphs (eles-4725) ☐
14.8 Determining measures of centre and spread from graphs (eles-4726) ☐

Interactivities

14.2 Individual pathway interactivity: Classifying data (int-7045) ☐
14.3 Individual pathway interactivity: Displaying data in tables (int-4379) ☐
Frequency distribution tables (int-4051) ☐
14.4 Individual pathway interactivity: Measures of centre and spread (int-4380) ☐
Measures of centre (int-4052) ☐
Mean (int-4053) ☐
Median (int-4054) ☐
Mode (int-4055) ☐
Range (int-4056) ☐
14.5 Individual pathway interactivity: Column graphs and dot plots (int-8471) ☐
Representing data graphically (int-4057) ☐
Column and bar graphs 1 (int-4058) ☐
Column and bar graphs 2 (int-4059) ☐
14.6 Individual pathway interactivity: Stem-and-leaf plots (int-8472) ☐
Stem-and-leaf plots (int-4060) ☐
14.7 Individual pathway interactivity: Pie charts and divided bar graphs (int-8473) ☐
Pie graphs (int-4061) ☐
14.8 Individual pathway interactivity: Comparing data (int-4382) ☐
Determining measures of centre and spread from graphs (int-4062) ☐
14.9 Crossword (int-2608) ☐
Sudoku puzzle (int-3174) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers

Topic 14 Representing and interpreting data

Exercise 14.1 Pre-test

1. B
2. A
3. 3
4. B
5. 31
6. 10
7. 19 m
8. 9
9. 20%
10. 2.55
11. 17
12. 41 cm
13. 111
14. a. 150 b. 45
    c. 8% d. 50%
15. 24%

Exercise 14.2 Collecting and classifying data

1. a. v b. i
    c. iv d. iii
    e. vi f. ii
2. a. Numerical (discrete)
    b. Categorical
    c. Numerical (continuous)
    d. Numerical (continuous)
    e. Categorical
    f. Numerical (continuous)
3. a. Discrete b. Continuous c. Discrete
    d. Continuous e. Discrete
4. a. Categorical
    b. Categorical
    c. Numerical (continuous)
    d. Numerical (discrete)
    e. Categorical
    f. Categorical
5. a. primary data b. secondary data
6. True
7. True
8. C
9. a. Discrete data deals with values that are exact and must be counted, for example the number of people at a football match. Continuous data deals with values that are measured and may be written in decimal form, for example the length of each football quarter.
    b. Primary data is data collected by me, for example a survey I conduct, and secondary data is data collected by someone else, for example AFL/NRL data.
10. In a Likert scale the data is split into categories, so even though these categories can be represented by numbers, the data is still categorical.
11. Although represented by digits, these types of data are categorical because they do not represent numerical ordered values.
12. Many possible answers. Some ideas: small amount of data; the company is motivated to find that soft drink is healthy.
13. Possible answers:
    a. How many minutes, on average, do you read per day?
    b. How many times a week do you play sport?
    c. How many times a week do you play computer games?
14. Possible answers:
    a. Do you do Maths homework every night?
    b. What books have you read this year?
    c. What suburb do you live in?
15. 1250
16. a. Primary data
    b. 5 is a small amount of data
    c. Data unreliable because Bill is motivated to get a certain result.
    d. More reliable because there is more data and there is no motivation to get a certain result.

Exercise 14.3 Displaying data in tables

1. a.

Score	Tally	Frequency
0	𝍸	5
1	IIII	4
2	𝍸 IIIII	9
3	𝍸 II	7
4	II	2
5	I	1
6	I	1
7		0
8	I	1
	Total	30

    b. 30
    c. 5
    d. 12
    e. 2
    f. $\frac{2}{30} = \frac{1}{15}$

2. a.

Value (thousand dollars)	Tally	Frequency
100–109	III	3
110–119	I	1
120–129		0
130–139	I	1
140–149	III	3
150–159	III	3
160–169	II	2
170–179	I	1
180–189	II	2
190–199	I	1
200–209	I	1
	Total	18

b. 18

c. \$100 000 – \$109 999, \$140 000 – \$149 999 and \$150 000 – \$159 999

d. \$120 000 – \$129 999

e. 3

3. a. 33 **b.** 3 **c.** 10

d. 23 **e.** $\frac{1}{3}$

4. a.

Score	Tally	Frequency
5	I	1
6	II	2
7	II	2
8	I	1
9	III	3
10	I	1
	Total	10

b.

Score	Tally	Frequency
0	𝍸	5
1	𝍸	5
2	𝍸	5
3	II	2
4	II	2
5		0
6	I	1
	Total	20

c.

Score	Tally	Frequency
45	I	1
46	I	1
47		0
48	II	2
49	I	1
50	II	2
51	II	2
52	II	2
53	IIII	4
54	III	3
55	I	1
56	II	2
57	II	2
58	II	2
59	I	1
60	II	2
	Total	28

d.

Score	Tally	Frequency
143	II	2
144	𝍸I	6
145	𝍸	5
146	I	1
147	III	3
148	III	3
149	III	3
150	IIII	4
151		0
152	I	1
	Total	28

5. a. The list is messy. It is difficult to see how many different sports there are or to tell how many people prefer a particular sport.

b.

Score	Tally	Frequency
Hockey	𝍸 |||	8
Cricket	𝍸 |	6
Tennis	𝍸 ||	7
Netball	𝍸 ||||	9
Swimming	𝍸 ||	7
Golf	||||	4
Scuba diving	|||	3
Lacrosse	||||	4
Lawn bowls	||	2
	Total	50

c. **i.** Netball

ii. Lawn bowls

d. Yes, Tennis and swimming had a frequency of 7, and golf and lacrosse had a frequency of 4.

6. a.

Score	Tally	Frequency
0	𝍸 𝍸 |	11
1	𝍸 𝍸	10
2	𝍸 |	6
3	||	2
4	|	1
	Total	30

b. 11

c. 9

d. 0

e. 4

f. $\frac{1}{5}$

7.

Height	Tally	Frequency
140–144	||	2
145–149	𝍸 |	6
150–154	||||	4
155–159	|	1
160–164	𝍸	5
165–169	𝍸 |	6
170–174	||	2
175–179	|	1
180–184	|	1
	Total	28

8. a.

Type	Tally	Frequency
1-bedroom unit	|||	3
2-bedroom unit	||||	4
2-bedroom house	|	1
3-bedroom house	𝍸 |	6
4-bedroom house	||	2
	Total	16

A 3-bedroom house was the most popular.

b. C

c. A

9. B

10. Because it makes it easier to collect and read the data.

11. When selecting a class interval we need to select ranges that are narrow enough to highlight variations in the data, and that are also wide enough to ensure the amount of data we are looking at is manageable.

12. Class intervals can be used to group continuous numerical data so that it can be represented in tables and other graphical forms.

13. a. 25

b.

Number of pets	Frequency	% Frequency
0	8	32
1	11	44
2	3	12
3	2	8
4	0	0
5	1	4

c. 6

14. O: 21.5%, U: 8.3%

15.

Score	Frequency
0	4
1	16
2	20
3	4
4	1
Total	45

Exercise 14.4 Measures of centre and spread

1. **a.** 5 **b.** 6 **c.** 4
d. 6 **e.** 4

2. **a.** 3 **b.** 12 **c.** 14
d. 15 **e.** 13

3. **a.** 3 **b.** 3 **c.** 4
d. 5 **e.** 2 **f.** 3

4. **a.** 5 **b.** 3 **c.** 3 **d.** 7

5. **a.** 11 **b.** 4 **c.** 2.5 **d.** 1.5

6. **a.** 2 **b.** 5 **c.** 7 **d.** 2.5

7. **a.** 5 **b.** 6 **c.** 7.5 **d.** 7.5

8. **a.** 4 **b.** 8 **c.** 2
d. 4 **e.** 2

9. **a.** 3 **b.** 10 and 12 **c.** 4
d. 9 **e.** no mode

10. **a.** 32 **b.** 24.1

11. B

12. B

13. D

14. D

15. C

16. 85%

17. 38

18. 104 shoes

19. 47 students

20. **a.** The average number of goals scored in each match, calculated by summing the total number of goals scored and dividing by the number of matches played.

b. The average house price, calculated by listing all of the house prices and finding the value that has the same number of houses being more expensive and less expensive than it.

c. The most popular shoe size.

21. By calculating measures of centre and spread we can see how data is grouped around a central point. This allows us to see any patterns in the data and interpret those patterns.

22. **a.** 101.9

b. Both the mode (115) and median (112) give a better impression of how the team has performed, even though they could give a 'misleading' impression of the team's performance.

23. **a.** Mode = 12

b. The mode shows which size to order more of. The mean and median would not show the more common sizes and would give only an indication of the middle of the range.

24. We cannot calculate the mean, median and range of categorical data, because these values are all calculated using the numerical values of the variables. We can calculate the mode of categorical data, which is the most popular or frequency category.

25. **a.** Tom: \$1.30, Sarah: \$1.27

b. Sarah's sells cheaper petrol.

c. Tom may have seen the price on a very expensive day. There's a greater range of values at Sarah's petrol station.

26. **a.** 1.75 m

b. 2.21 m

c. Based on her past performances and her past range of values, she cannot jump this high.

27. 72

28. 89.5%

29. The coach's statement was not correct.

30. One possible answer is 5, 6, 12, 13, 14. If the 5 numbers are in ascending order, the 3rd number must be 12 and the other 4 numbers must add up to 38.

31. The highest score is 49 and the lowest score is 0. The scores would be 0, 1, 12, 13, 49

32. **a.** 15

b. 3

c. 0

d. The median is the best measure because the mode is the lowest of all scores and the mean is inflated by one much larger figure.


33. 133 cm, 133 cm, 142 cm, 151 cm

34. Largest value for the median is 15. Scores would be 0, 2, 15, 16, 17 or 0, 1, 15, 16, 18. Smallest value for the median is 2. Scores would be 0, 1, 2, a, b, where $a + b = 47$


35. 43; highest score: 100; lowest score: 57. The scores would be 57, 77, 78, 79, 80, 97, 98, 99, 100

Exercise 14.5 Column graphs and dot plots


1.




2.



3.




4. a.




b. The scores lie between and include 6 to 20; that is, a range of fourteen.
Mostly 16 to 18 packets were sold. Sales of 6 and 20 packets of chips were extremely low. A provision of 20 packets of chips each day should cover the most extreme demands.


5. a.




b.



c.



d.



6. a. Months

b. Bill total

c. Every 3 months (quarterly)

d. January 2021

e. A graph like this is useful to monitor the spending pattern over time and to decide whether there have been any unusual increases.

f. It would not be normal, but there might be reasons to explain why it was so much higher, for example making a lot of overseas phone calls.

7. a. i. 45

ii. 42

iii. 61

b. 5 and 11

c. It does indicate an improvement, despite these two low weeks, because there is an overall upward trend throughout the time period.

8. a. Betty

b. 1 April: 70 m, 29 April: 73 m

c. Rachel

d. Yes. Sarah remained the same. Sumira and Paula sprinted at a slower pace.

e. Yes, the graph could be misleading because the vertical scale begins at 30 m and not at 0 m. If the vertical scale was not read properly, it might appear that the students covered a greater distance in a shorter period of time.


f. The graph's vertical axis starts at 30 m because no-one ran less than that distance and the teacher wanted to use all the space to show small differences in the distances.

9. By aligning the data points neatly above the value they are representing, these data points cannot be mistakenly seen as representing any other value. A dot plot is also neater and easier to interpret.

10. Column and bar graphs have discrete columns and bars, which are perfect for representing categorical data. There are often better graphs for displaying numerical data.

11. a–d. Generally, outliers affect the mean and range, have little effect on the median, and have no effect on the mode.

12. a.




b. The data is categorical, not numerical. Therefore there is no median.

c. Brown

d. $\frac{10}{23} \approx 43\%$

13. a.



b. Class A: Mean 5.5, median 5.5, no mode, range 9; Class B: Mean 4.3, median 3.5, modes 2, 3 and 4, range 9

c. Class A has a higher mean and median than Class B, while the range is the same for both classes. The results for Class A are scattered throughout the whole range, while those for Class B are concentrated more towards the lower end of the range.

14. a. 35

b. Each week the number of fridges sold increases by 5.

c. $F = 25 + 5w$

d. $F = 25 + 5(10)$
$= 25 + 50$
$= 75$

Exercise 14.6 Stem-and-leaf plots

1. Key: 2|7 = 27

Stem	*Leaf*
2	1 1 5 5 8 8 9 9
3	1 1 3 7 9
4	0 1 1 6 7
5	1 3 3 4 8
6	2 2 2 2 7 7 8
7	1 2 3 3 8
8	1 2
9	2 3 3

2. Key: 3|6 = 36

Stem	*Leaf*
0	0 1 2 3 6 7 8
1	0 2 2 2 2 4 5 6 6 7 8 9
2	1 2 5 7 8
3	1 1 2 2 3
4	0

3. a. Key: 12|7 = 127

Stem	*Leaf*
10	8
11	6 7 8
12	9
13	2 7
14	5
15	2
16	4 5
17	2
18	9

b. Key: 13|2 = 132

Stem	*Leaf*
11	4
12	4
13	0 1
14	6
15	0 2
16	
17	1 3

c. Key: 23|7 = 237

Stem	*Leaf*
19	0
20	5 7 8
21	
22	5
23	7 9
24	4 8 8 8
25	5

d. Key: 65|2 = 652

Stem	*Leaf*
64	1 5 7 7
65	
66	2
67	5
68	5
69	1
70	8
71	
72	
73	5 6
74	8

4. a. Key: 1|7 = 1.7

Stem	*Leaf*
1	2 7 9
2	2 3 8
3	9
4	1 6
5	4 8

b. Key: 6|7 = 6.7

Stem	*Leaf*
6	0 5 9
7	4 5 7
8	3 4 8
9	2 3 8

c. Key: 13|7 = 13.7

Stem	*Leaf*
13	0 8 9 9
14	3 5 5 6 7 7 8
15	1 2 6 7 9
16	2

d. Key: 1|5 = 0.15

Stem	*Leaf*
0	2 7
1	5 8
2	
3	7
4	4
5	1
6	7

5.

Key: 0|2 = 2

Leaf (Mitch)	*Stem*	*Leaf (Yani)*
3 2 1 1 1 1 0 0 0 0	0	0 0 1 1 1 1 1 2 2 2

Mitch scored between 0 and 3 goals inclusive.
Yani scored between 0 and 2 goals inclusive.

6. a. Mitch: 2, Yani: 3

b. Mitch

c. Yani: 11

d. Yani, as he scored goals in more games.

7. a. 22 **b.** 17

c. 64 **d.** 13

e. 42 **f.** 0

8. a. Key: 10|8 = 10.8

Stem	*Leaf*
10	8 9
11	0 2 5 8
12	0 4 5 6 8 8
13	2 6 6 9 9
14	0 1
15	0

b. Range = 4.2 There is a reasonably large range of sprint times in this sample.

c. The majority of these runners completed the 100 m sprint between 11 and 13.9 seconds. The average sprint time was 12.68 s and the distribution is approximately evenly spread around the middle.

9. Stem plots need a key because these plots can show a variety of data, ranging from whole numbers to decimals. A key helps to show what the data represents. For example, a stem plot key showing data could be 15|1 = 151 while a stem plot key showing decimals could be 11|1 = 11.1. In these examples, the number on the leaf represents units (in the first example) and decimal values (in the second example).

10. By ordering a dot plot it is easy to identify key values, for example the median, the lowest value and the highest value. By aligning the data values we can easily see how many values lie in each class interval. We can also see the shape of the data.

11. a.

Test scores (%)

Key: 5|6 = 56%

Leaf (Class 7F)	*Stem*	*Leaf (Class 7G)*
3 1	4	
	5	
	6	6 8
9 8 7 7	7	4 5 6 6 8 8
8 5 4 2 1 0	8	0 2 2 3 5 9
2 1	9	

b. 7F: mean = 77, median = 80.5
7G: mean = 78, median = 78

c. Since class 7F has two outliers, the best measure of centre is the median, not the mean.

12. a. 55 **b.** 43 **c.** 26

13. a.

Temperatures (ºC)

Key: 2 | 1 = 21ºC

Leaf (City A)	*Stem*	*Leaf (City B)*
	1	2 2 3 3 3 7
9 5 4 3 1	2	0
6 0	3	

b. City A: range = 15, median = 25, mean = 26.9, there is no mode.
City B: range = 8, median = 13, mean = 14.3, mode = 13.

c. In February the northern hemisphere is in winter and the southern hemisphere is in summer. Looking at the answers to part **b** City A has a higher mean and median temperature, so is most likely in the southern hemisphere. City B has a lower mean and median, so is in the northern hemisphere.

14. a.

Key: 3|2 = 32

Leaf (**9***A*)	*Stem*	*Leaf* (**9***B*)
2	3	
9	4	6
7 4	5	5
8 7 5 5 0	6	0 2 8
3	7	3 3 4 5 7 8
5	8	1
6	9	

b. 9A: 83%; 9B: 92%


c. 9A: 2

d. For class 9A, exam marks are quite spread out overall, but there is a cluster of students scoring in the 60% range. For class 9B, the spread of exam marks is smaller — they are generally clustered in the 70% range.

e. See the dot plot at the foot of the page.*

f. The dot plot tells a slightly different story than the stem-and-leaf plot. For class 9A there appears to be 3 outliers (32%, 85% and 96%). This was not apparent in the stem-and-leaf plot. The results do not seem clustered around any particular percentage range. For class 9B there is one clear outlier (there are possibly more) at 46%. The results still appear clustered in the 70% range.

*14. e.




Exercise 14.7 Pie charts and divided bar graphs

1. a. 356 **b.** Bus

2. a.

Sport	Number of students	Fraction of students	Angle at centre of circle
Basketball	55	$\frac{55}{180}$	$\frac{55}{\cancel{180}^{1}} \times \frac{\cancel{360}^{2}}{1} = 110°$
Netball	35	$\frac{35}{180}$	$\frac{\cancel{35}}{\cancel{180}} \times \frac{\cancel{360}^{2}}{1} = 70°$
Soccer	30	$\frac{30}{180}$	$\frac{\cancel{30}}{\cancel{180}} \times \frac{\cancel{360}^{2}}{1} = 60°$
Football	60	$\frac{60}{180}$	$\frac{\cancel{60}}{\cancel{180}} \times \frac{\cancel{360}^{2}}{1} = 120°$
Total	180		

b, c



3. a. Ian

b. 17%

c. No, this sector graph gives percentages only, not actual values or numbers of people who voted.

d. 78.48°

4. a. 50%

b. 35%

c. 15%


d. 100%

e. i. 180° **ii.** 126° **iii.** 54°

5. a.

Roofing material	Number of houses	Fraction	Angle size (°)
Concrete tiles	12	$\frac{1}{3}$	120
Terracotta tiles	9	$\frac{1}{4}$	90
Galvanised iron	6	$\frac{1}{6}$	60
Colourbond	3	$\frac{1}{12}$	30
Slate	2	$\frac{1}{18}$	20
Shingles	4	$\frac{1}{9}$	40
Total	36	1	360

b.



6. a. 45

b. 6

c. 12

d. 40%


e. German Shepherd

7. a.

Type of meat	Amount sold (kg)	Fraction
Lamb	10	$\frac{1}{9}$
Beef	45	$\frac{1}{2}$
Pork	5	$\frac{1}{18}$
Chicken	15	$\frac{1}{6}$
Turkey	10	$\frac{1}{9}$
Rabbit	5	$\frac{1}{18}$
Total	90	1

b, c See the figure at the foot of the page.*


*7b, c.




8. a.

Type of bird	Number of birds	Fraction
Magpie	24	$\frac{2}{5}$
Crow	12	$\frac{1}{5}$
Cockatoo	12	$\frac{1}{5}$
Wattlebird	6	$\frac{1}{10}$
Rosella	6	$\frac{1}{10}$
Total	60	

b. i.




ii.



9. a, b

Transport	Number of students	Fraction	Length of bar
Walk	50	$\frac{50}{100} = \frac{1}{2}$	$\frac{1}{2} \times 10 = 5$ cm
Car	20	$\frac{20}{100} = \frac{1}{5}$	$\frac{1}{5} \times 10 = 2$ cm
Bus	15	$\frac{15}{100} = \frac{3}{20}$	$\frac{3}{20} \times 10 =$ 1.5 cm
Bike	15	$\frac{15}{100} = \frac{3}{20}$	$\frac{3}{20} \times 10 =$ 1.5 cm
Total	100		

c.



d. 2.5 cm

10. a. 100 **b.** 50 **c.** 25

11. Chair: 40; Table: 28; Couch: 12; Desk: 10.

12. Categorical data: column and bar graphs and sector graphs
Numerical data: dot plots, stem-and-leaf plots


13. A divided bar graph gives a graphical representation of the proportion of each category as a percentage of the whole.

14. a. Graph 1

b. In graph 1 there was a much greater proportion of ice creams and cold drinks sold than pies and hot drinks. Ice creams and cold drinks would be much more popular in summer than pies and hot drinks.

15. a.

Sport	Percentage of total	Angle size (°)
Cricket	20	72
Hockey	25	90
Netball	40	144
Soccer	10	36
Tennis	5	18
Total	100	360



b. i. If there were only 10 students in the class, each student would represent 10% of the class total. It would therefore be impossible for only 5% of the class to play tennis.


ii. If there were 20 students in the class, each student would represent 5% of the class total. Since all of the percentages for the sports are multiples of 5% , this is a plausible scenario.

16. a. Rent and utilities

b. $800

c. i. $200 **ii.** $200 **iii.** $500

d.



17. a. 25% **b.** 45° **c.** $0.375\ m^2$

18. $26\frac{2}{3}\%$

Exercise 14.8 Comparing data

1. a. i. 82.4
ii. 82
iii. 81
iv. 9

b. The mean, median and mode are all quite close, so any could be used as a measure of centre.

2. a. i. 2.63
ii. 2.55
iii. 2.4
iv. 0.7

b. This distribution is quite spread out, with a significant number at the lower end and towards the top. For this reason the mode is probably the best measure of centre.

3. a. i. 4.5 **ii.** 5 **iii.** 5 **iv.** 10

b. i. 4.1 **ii.** 5 **iii.** 5 **iv.** 7

c. The mean and range are affected by the outlier. The median and mode have not been affected.

4. a. i. 6.26 **ii.** 6.27
iii. 6.18 and 6.34 **iv.** 0.16

b. The mean or median would probably be the best measures of centre in this case.

5. a. i. 22.6 **ii.** 23 **iii.** 23 **iv.** 34

b. i. 19 **ii.** 22 **iii.** 23 **iv.** 15

c. The mean and range are most affected by the outlier. The median is affected slightly, while the mode is not affected.

6. C

7. A

8. D

9. C


10. D

11. a.

Score x	Frequency f	Freq. × score $f \times x$
0	1	0
1	3	3
2	6	12
3	3	9
4	3	12
5	1	5
6	1	6
	$n = 18$	$\sum fx = 47$

Mean ≈ 2.6

b.



c. 2

d. i. Median **ii.** Mean **iii.** Mode

12. 75.6

13. a. The median was calculated by taking the average of the 2 middle scores.

b. 13

14. Rebecca's strategy seems reasonable. Sample responses can be found in the worked solutions in your online resources.

15. a. \$18 000

b. \$29 444

c. \$26 000

d. i. Mode **ii.** Mean

16. 7

17. a. 55 250 km, 52 000 km, 52 000 km

b. The median would be a better measure of centre because it will be less affected by the outliers in the data than the mean.

c. 51 810 km; It is reduced by 3440 km

d. 52 000 km

e. 3333

f. 50 000 km; 92% last that distance or more.

18. 2

Project

1. Sector graph


2. Families with no children in this age range is the most common category.

3. Column or bar graph

4. Responses will vary depending on the students surveyed. Here is a sample response.

Number of children	Tally	Frequency	Percentage
1	|||||	6	24%
2	||||||||||	11	44%
2	|||||	5	20%
4 or more	|||	3	12%
	Total	25	

5. Sample (the entire population was not surveyed)
6. Numerical data
7. Responses will vary depending on the students surveyed. The following is a sample response.



8. Responses will vary depending on the students surveyed. One major difference will be that none of the households surveyed have 0 children under 15 years as they all contain at least 1 Year 7 student. This is a major variation from the census data.
9. Responses will vary depending on the survey undertaken by the student.

Exercise 14.9 Review questions

1. False
2. Continuous
3. Categorical
4. a. Coke b. Tea
5. a. 26 b. 14 c. 18 d. 14 e. 12
6. a.

Cars	Frequency
0	6
1	4
2	8
3	5
4	1
Total	24

   b. 6
   c. 14
   d. 2
   e. 4
   f. $\frac{1}{3}$
7. a. i. 3.14 ii. 4 iii. 3
   b. i. 3.71 ii. 4 iii. 4
   c. i. 4.86 ii. 5 iii. 5
   d. i. 2.14 ii. 1 iii. 1
   e. i. 5.2 ii. 5 iii. 5
   f. i. 5.78 ii. 8 iii. 6
8. a. Names b. 1 unit = 10%
   c. John d. Peter
   e. 58% f. 77%
9. a. Days of week b. Air quality rating
   c. Northern region d. Wednesday
   e. Eastern region
10. a. Key: 3|6 = 36

Stem	*Leaf*
7	1 5 8
8	1 2 3 4 5 6 7 8 8
9	0 1 1 2 2 2 3 4 4 6 6 7
10	2 3 4 4
11	0 5


    b. Only 3 cars were travelling under the 80 km/h speed limit. The slowest speed recorded was 71 km/h, while the fastest speed recorded was 115 km/h. Most of the recorded speeds were in the 90–99 km/h class interval. The most common (modal) speed recorded was 92 km/h.
11. a. Key: 3|1 = 31

Leaf Set A	**Stem**	***Leaf Set B***
1	0	3
3	1	
8	2	9
0	3	0 1 2 8
5	4	1
9	5	
4	6	8

    b. Set A
       i. 1
       ii. 64
       iii. 37.1
       iv. 37.5
       v. 63

       Set B
       i. 3
       ii. 68
       iii. 34
       iv. 31.5
       v. 65
    c. The two sets have similar minimum and maximum values, giving them a similar range. The mean of Set A is slightly higher than that of Set B. The scores of Set A are spread out more evenly than those in Set B, which tend to be clustered towards the middle.
12. a. i. 6.55 ii. 6 iii. 6 iv. 9
    b. There appear to be two outliers (11 and 12). The mean, median and mode values are quite close, indicating that it is common for 6 soft drinks to be sold quite frequently. The minimum number sold over the period is 3, while the maximum is 12.
13. a. i. 29 years ii. 27 years
    iii. 18 years iv. 39 years
    b. The ages of the group range from 14 years to 53 years, with most of the group being under 40. The mean or median values would be a good representation of the age of the group.

14. **People who ate different types of breakfast**



15. See the figure at the foot of the page.*


16. **a.** 10 °C **b.** Day 5 **c.** Day 7
d. Day 6 **e.** 10 °C **f.** Days 6 and 7

17. **a.** 81.56 **b.** 74.22 **c.** Test 1
d. 6 **e.** 4

18. **a.** 85
b. 63
c. 85
d. 68
e. John 89.5, Peter 74, Mark 76.5, James 74.5, David 85.5, Rachel 73.5, Mary 81, Eve 78.5, Esther 68
f. 21.5

19. **a.** 41 cm
b. 154.8 cm
c. 156 cm
d. 156 cm
e. Yes


20. **a.** Months
b. Number of flies
c. 10 000
d. 28 000
e. 1 cm = 5000 flies (if beginning from 0 flies) or
1 cm = 2000 flies (if beginning from 10 000 flies)
f.



21. **a.**

x	f
0	4
1	5
2	7
3	3
4	0
5	1
Total	20

b.




c. 2, 2, 1.65

22. **a.** **i.** 5
ii. 5.5
iii. 7.9
iv. 25
v. 6
vi. 17.9, 15.5
b. When 10 was added to each score, both the mean and median increased by exactly 10.

23. The boys have a mean height of 158 cm, with a median height of 158 cm and three modes (148 cm, 158 cm, and 166 cm) They range in height from 138 cm to 178 cm.
The girls have a mean height of 153 cm, with a median height of 152 cm and no mode. They range in height from 137 cm to 171 cm.
The shortest person is a girl, while the tallest person is a boy. On the whole, the boys are taller than the girls.

*15




Semester review 2

The learnON platform is a powerful tool that enables students to complete revision independently and allows teachers to set mixed and spaced practice with ease.

Student self-study

Review the **Course Content** to determine which topics and subtopics you studied throughout the year. Notice the green bubbles showing which elements were covered.



Review your results in **My Reports** and highlight the areas where you may need additional practice.





Use these and other tools to help identify areas of strengths and weakness and target those areas for improvement.

Teachers


It is possible to set questions that span multiple topics. These assignments can be given to individual students, to groups or to the whole class in a few easy steps.

Go to **Menu** and select **Assignments** and then **Create Assignment**. You can select questions from one or many topics simply by ticking the boxes as shown below.





Once your selections are made, you can assign to your whole class or subsets of your class, with individualised start and finish times. You can also share with other teachers.



More instructions and helpful hints are available at www.jacplus.com.au.

15 Algorithmic thinking

LEARNING SEQUENCE

online only

15.1 Overview
15.2 Variables
15.3 Expressions
15.4 Sequences
15.5 Algorithms
15.6 Review



15.1 Overview

Why learn this?



Algorithms are sets of step-by-step instructions that help optimise processes and allow you to complete tasks in a very short amount of time. Instagram uses an algorithm that shows a post at the top of your feed, depending on your browsing history. This minimises your time by making posts quickly available to you that might be of interest. Similarly, Google uses algorithms to sort through billions of websites to find the most relevant information for you.

Algorithmic thinking is the process of creating instructions that, when followed, enable tasks to be performed effectively, with minimum cost. This approach automates the problem-solving process by developing logical and sequential steps that produce reliable output for a given set of inputs. Algorithms are used in the many different languages that can be used to program computers. These languages have specific purposes. For example, JavaScript is used in web pages to create interactive experiences such as games; C is a computer language often embedded in programs in electronic devices such as TVs and digital cameras.

This topic applies the computer language JavaScript in most of the examples and questions. JavaScript was chosen for its popularity and availability on nearly all web browsers.

According to Steve Jobs, the co-founder of Apple and Pixar, 'everybody in this country [the USA] should learn how to program a computer because it teaches you how to think'.

Where to get help

Go to your learnON title at **www.jacplus.com.au** to access the following digital resources. The Online Resources Summary at the end of this topic provides a full list of what's available to help you learn the concepts covered in this topic.



Exercise 15.1 Pre-test

learnON

Complete this pre-test in your learnON title at www.jacplus.com.au and receive **automatic marks**, **immediate corrective feedback** and **fully worked solutions**.

1. MC Choose which of the following is NOT classified as a number.
   A. `"102"` B. `101` C. `1.01` D. `0.001` E. `100`

2. MC Select which of the following is a valid variable name.
   A. `2_BALL` B. `3_Place` C. `Ball-2` D. `Foot_12` E. `FOOT 12`

3. MC Choose which of the following is the correct JavaScript statement to assign the value 12 to the variable twelve.
   A. `var twelve = 12;` B. `var twelve = 12` C. `var 12 = 12;`
   D. `var twelve = 12:` E. `var_twelve = 12;`

4. MC Select which of the following is NOT a JavaScript keyword and can be used as a variable name.
   A. `array` B. `false` C. `width`
   D. `length` E. `var`

5. Evaluate the following expression written in JavaScript.

$$7+6^{*}2-(8-3)$$

6. MC The expression $\frac{12\times(5-2)}{7-3}$ written as a JavaScript expression is:
   A. $\frac{12^{*}(5-2)}{(7-3)}$ B. `12*(5-2)/(7-3)`
   C. $\frac{12\times(5-2)}{7-3}$ $\frac{12\times(5-2)}{7-3}$ D. `12*(5-2)/7-3`
   E. `12(5-2)/7-3`

7. MC The string `"I like doing maths"` as an expression of single words and spaces is:
   A. `Ilikedoingmaths`
   B. `"I" + " " + "like" + " " + "doing" + " " + "maths"`
   C. `"I" + " " + "like" + " " + "maths"`
   D. `I + like + doing + maths`
   E. `"I" + "like" + "doing" + "maths"`

8. MC The JavaScript expression `"Good work". substr (5, 2)` is:
   A. `"od"` B. `"or"` C. `"oo"` D. `"wo"` E. `" w"`

9. Determine the length of the JavaScript expression 'Well done'.

10. Determine the output to the console after running the following.
```
console.log ((23 – 7)/(13 – 9));
```

11. For the following programs, identify the value assigned to the variable `c`.
```
var a = 3*4;
var b = 13 + a;
var c = 2*a + b;
```

12. Manually simulate running the following program. Determine the output to the console.

```
var x = 12;
var y = 15;
var z = 3*x + 2*y;
console.log(z);
```

13. Determine the number of inputs for the following function.

```
function output(dog, x, cat) {
  console.log(dog + cat);
  console.log(x);
}
```

14. MC The output to the console for the following is:

```
function area(x, y) {
  console.log(x*y);
}
area(12, 3);
```

A. 12 **B.** 36 **C.** 48 **D.** 15 **E.** 3

15. MC Select which of the following programs calculates the mean of the three input numbers.

A.
```
function mean(x1, x2, x3) {
   total = x1 + x2 + x3;
   return total/2;
  {
  var x = mean(6, 8, 10);
```

B.
```
function mean(x1, x2, x3) {
   total = x1 + x2 + x3;
   return total/3;
  {
  var x = mean(6, 8, 10);
```

C.
```
function mean(x1, x2, x3) {
   total = x1 + x2 + x3
   return total/3
  {
  var x = mean(6, 8, 10)
```

D.
```
function mean(x1, x2) {
   total = x1 + x2 + x3;
   return total/3;
  {
  var x = mean(6, 8, 10);
```

E.
```
function mean(x1, x2, x3) {
   total = x2 + x3;
   return total/3;
  {
  var x = mean(6, 8, 10);
```

15.2 Variables

LEARNING INTENTION

At the end of this subtopic you should be able to:

- recognise three types of values in computer programming
- identify valid variable names
- assign values to variables.

15.2.1 Values

- Variables in computer programs are similar to variables used in algebra. Variables are used to store values.
- In algebra, the value of a variable is fixed once it's defined. For example, the two equations $x = 2$ and $x = 3$ cannot be simultaneously true. Once x has been defined to be 2 ($x = 2$) it cannot be changed to be 3 ($x \neq 3$).
- In a computer program, the value of a variable can be changed at any point in the sequence. For example, the variable `x` is first assigned the value `2`, and then changed to the value `3`.
- Three of the most common types of values used in computer programming are:
  - **number** (a numerical value): `1, 2, -3, 1.5, 4.15359`
  - **string** (any text in quotation marks `"..."`): `"Some text", "123", "A string"`
  - **Boolean** (used for logic; this type only has two possible values): `true, false`

WORKED EXAMPLE 1 Classifying values in computer programming

Classify the following values as number, string or Boolean.

a. `"Aidan"` b. `1.2` c. `"This is text"`
d. `true` e. `"23"` f. `"true"`
g. `""` h. `-101`

THINK

a. `"Aidan"` is in quotation marks, so this value is a string.
b. `1.2` is a numerical value not in quotation marks, so this value is a number.
c. `"This is text"` is in quotation marks, so this value is a string.
d. `true` is a Boolean value.
e. `"23"` is in quotation marks, so it is a string.
f. `"true"` is in quotation marks, so it is a string.
g. `" "` is an empty pair of quotation marks, so it is a string.
h. `-101` is a numerical value, so it is a number.

WRITE

a. String
b. Number
c. String
d. Boolean
e. String
f. String
g. String
h. Number

15.2.2 Variable names

- A powerful feature of computers is their ability to store vast amounts of information accurately for any required amount of time. Computer languages use memory locations to store values. These named storage containers are called **variables**.
- Variables can have long or short names. Often longer names are used to remind the programmer the meaning of the information to be stored. The following are all valid variable names: `x, y, i, age, name, first_name, number_of_people, bankBalance`
- There are complex rules that determine what can be used for a valid variable name. For simplicity, this topic restricts the variable names to three simple rules.

- Variable names:
  1. must not start with a number
  2. can only contain upper-case and lower-case letters, numbers and the underscore character (`_`), and cannot contain spaces
  3. cannot be JavaScript keywords.

  Note: The following are JavaScript keywords, which should not be used as variable names.

```
abstract, arguments, Array, boolean, break, byte,
case, catch, char, class, const, continue, Date,
debugger, default, delete, do, double, else, enum,
eval, export, extends, final, finally, float, for,
function, goto, hasOwnProperty, if, implements, import,
in, Infinity, instanceof, int, interface, isFinite,
isNaN, isPrototypeOf, length, let, long, Math, name,
NaN, native, new, null, Number, Object, package, private,
protected, prototype, public, return, short, static,
String, super, switch, synchronized, this, throw, throws,
toString, transient, true, try, typeof, undefined,
valueOf, var, void, volatile, while, with, yield, false
```

WORKED EXAMPLE 2 Identifying valid variable names


Identify whether each of the following is a valid variable name. (Answer either true or false for each name.)

a. `a_variable` **b.** `1_first` **c.** `a%percentage`
d. `camelCase_12` **e.** `this` **f.** `function`

THINK	WRITE
a. `a_variable` is valid because it only uses letters and the underscore character.	**a.** True
b. `1_first` is invalid because it uses a number as the first character.	**b.** False
c. `a%percentage` is invalid because it uses a `%` character.	**c.** False
d. `camelCase_12` is valid as it only uses letters, numbers and the underscore character. It also does not start with a number.	**d.** True
e. `this` is invalid because `this` is a JavaScript keyword.	**e.** False
f. `function` is invalid because `function` is a JavaScript keyword.	**f.** False

15.2.3 Assigning values to variables

- Values are assigned to variables differently depending on the computer language used. When using JavaScript, the first time a value is assigned to a variable the instruction should begin with the JavaScript keyword `var`. JavaScript uses the following structure to assign a value to a variable.



WORKED EXAMPLE 3 Assigning values to variables

Write a JavaScript statement to make the following variable assignments.
a. Assign the value `10` to the variable `ten`.
b. Assign `true` to the Boolean variable `I_can_write_code`.
c. Assign `"JavaScript"` to the variable `language`.

THINK	WRITE
a. 1. Identify the variable name, which in this case is `ten`.	a.
2. Identify the value, which in this case is `10`.	
3. Apply the JavaScript structure to write the statement.	`var ten = 10;`
b. 1. Identify the variable name, which in this case is `I_can_write_code`.	b.
2. Identify the value, which in this case is `true`.	
3. Apply the JavaScript structure to write the statement.	`var I_can_write_code = true;`
c. 1. Identify the variable name, which in this case is `language`.	c.
2. Identify the value, which in this case is `"JavaScript"`.	
3. Apply the JavaScript structure to write the statement.	`var language = "JavaScript";`

on Resources

Interactivity CodeBlocks Activity 1 (int-6573)

Exercise 15.2 Variables

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 4, 6, 8, 10, 13, 14, 19, 21	2, 5, 7, 11, 15, 16, 22, 23	3, 9, 12, 17, 18, 20, 24

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE1 Classify the following values as number, string or Boolean.

   a. `123`
   b. `-12`
   c. `3.6`
   d. `"A string"`
   e. `"Is this a string?"`
   f. `"10"`

2. Classify the following values as number, string or Boolean.

   a. `true`
   b. `"true"`
   c. `false`
   d. `"-10"`
   e. `917`
   f. `-10000000`

3. Classify the following values as number, string or Boolean.



a. `"false"` b. `"9999"` c. `""`
d. `0` e. `"Yes"`

4. Use True or False to state whether each of the following is a number value.

a. `"12"` b. `"-13.22342"`
c. `3.14159265359` d. `1237123`
e. `"1237123"` f. `true`
g. `false`

5. Use True or False to state whether each of the following is a number value.

a. `Three` b. `"0"` c. `Nine` d. `Number12`
e. `-80` f. `4` g. `0.0000001`

6. Use True or False to state whether each of the following is a string value.

a. `"A string value"` b. `Another string value`
c. `2` d. `"12"`
e. `Four` f. `"Four"`
g. `"true"` h. `true`

7. Use True or False to state whether each of the following is a string value.

a. `"false"` b. `This is a string`
c. `"This is not a string"` d. `false`
e. `Five` f. `"Five"`
g. `18276`

8. Use True or False to state whether each of the following is a Boolean value.

a. `true` b. `false` c. `"true"` d. `12` e. `Yes`

9. Use True or False to state whether each of the following is a Boolean value.



a. `No` b. `"Yes"` c. `"No"` d. `21344`

10. **WE2** Variable names:

1. must not start with a number
2. can only contain upper-case and lower-case letters, numbers and the underscore character `(_)`, and cannot contain spaces
3. cannot be JavaScript keywords. The following are some JavaScript keywords, which should not be used as variable names: `true, var, false`.

Given these rules, use True or False to state whether each of the following is a valid variable name.

a. `variable` b. `value` c. `x1` d. `x2`
e. `1x` f. `2x` g. `ten` h. `10`

11. Given the rules listed in question **10**, use True or False to state whether each of the following is a valid variable name.

a. `percentage%variable`
b. `percentage_variable`
c. `fourteen`
d. `14variable`
e. `ThisIsAVariableName`
f. `this_is_also_a_variable_name`
g. `100_variable_names_sitting_in_a_row`
h. `Variable name`

12. Given the rules listed in question **10**, use True or False to state whether each of the following is a valid variable name.

a. `a` **b.** `i` **c.** `j` **d.** `_`
e. `_cats` **f.** `true` **g.** `false`

Understanding

13. Fill in the variable, value and type for the following JavaScript assignment statements.

	Variable	Value	Type	JavaScript statement
e.g.	`a_variable`	`"text"`	`String`	`var a_variable = "text";`
a.				`var x = 10;`
b.				`var nine = 9;`
c.				`var aBoolean = true;`
d.				`var _ = "A string";`
e.				`var _long_var = true;`
f.				`var areYouTall = false;`
g.				`var about_e = 2.718281828459;`
h.				`var sin_90 = 1;`
i.				`var isThis = "false";`
j.				`var a_Boolean = true;`

14. State the two possible JavaScript Boolean values.

15. Explain whether a value assigned to a variable in a computer program can be changed.

16. WE3 Write a JavaScript statement to make the following variable assignments.




a. The value `10` assigned to the variable named `count`.
b. The value `"Data"` assigned to the variable called `information`.
c. The value `9` assigned to the variable `threeSquared`.

17. Write a JavaScript statement to make the following variable assignments.

a. `true` assigned to the variable `isThisJavaScript`.
b. The variable `meaningOfLife` storing the value `42`.
c. `classSize` holding the value `25`.

18. The computer language R has a different structure to assign values to variables, which is shown to the right.
Rewrite the following JavaScript assignment statements in the computer language R.



a. `var timeInSeconds = 120;`
b. `var distanceInMiles = 40;`
c. `var firstName = "Ben";`
d. `var middleName = "Violet";`
e. `var numberLeft = 19;`
f. `var littleOverThree = 3.1;`

19. Use True or False to state whether each of the following is a valid JavaScript assignment statement.

a. `var someVariable = 10;`
b. `var thisIsBoolean = "A string";`
c. `var time <- 10;`

d. `time <- 100`
e. `var aString = 10;`
f. `var thisLooksValid == 10;`
g. `var isThisBoolean = false;`

20. The Python computer language uses slightly different Boolean values: `True` and `False`. Note that JavaScript's Boolean values are `true` and `false` (the case of the first letter is different). Python uses the assignment structure:

```
variableName = "some value"
```

Rewrite the JavaScript assignment statements shown in the table below as Python assignment statements.

	JavaScript assignment statement	Python assignment statement
a.	`var x = 10;`	
b.	`var nine = 9;`	
c.	`var aBoolean = true;`	
d.	`var _ = "A string";`	
e.	`var _longer_variable = true;`	
f.	`var areYouTall = false;`	
g.	`var nearly4 = 3.99;`	
h.	`var about_e = 2.718281828459;`	
i.	`var sin_90 = 1;`	
j.	`var isThisABoolean = "false";`	
k.	`var is_this_a_Boolean = true;`	

Reasoning

21. Explain why it is important to have rules for the structure of variable names.

22. Variable names:

1. must not start with a number
2. can only contain upper-case and lower-case letters, numbers and the character `_`
3. cannot be JavaScript keywords like `var, true and false`.

i. Determine which of the rules listed are violated by the following variable names.
ii. In each case explain why the rule is important.

a. `true` b. `false` c. `1w`
d. `2` e. `-value` f. `variable name`
g. `"variableName"`

Problem solving

23. Using only the characters `"a", "B", "_" and "1"`, list all the valid variable names:

a. of length 1
b. of length 2 without repeating characters
c. of length 2, where characters can be repeated.



24. Variable names:

1. must not start with a number
2. can only contain upper and lower case letters, numbers and the underscore character `(_)`, and cannot contain spaces

3. cannot be JavaScript keywords. The following are JavaScript keywords that should not be used as variable names:

```
do, if, in, for, int, let,
NaN, new, try, var, byte,
case, char, Date, else, enum, eval, goto, long,
Math, name, null, this, true, void, with, false
```

Given these rules, determine how many possible valid variables names there are:

a. of length 1 **b.** of length 2 **c.** of length 3 **d.** of length 4.

15.3 Expressions

LEARNING INTENTION

At the end of this subtopic you should be able to:

- evaluate numerical expressions in JavaScript
- evaluate string expressions in JavaScript
- apply the index, substring and length methods to extract specific parts of a string.

15.3.1 Numerical expressions

- Expressions are used to perform calculations on existing values to generate new values.
- Computer programs use similar symbols and rules as standard mathematics to create numerical expressions.
- Numerical expressions involving numbers, brackets, plus and minus in JavaScript evaluate as you would expect in any mathematical expression.

WORKED EXAMPLE 4 Evaluating the JavaScript for the expression

Evaluate the JavaScript for the following expressions.

a. `10 + 2` **b.** `5 - 3`

c. `1.2 + 3.4` **d.** `3 + 6 - (5 - 4)`

THINK

a. Add `10` and `2`.

b. Subtract `3` from `5`.

c. Add `1.2` and `3.4`.

d. Write out the expression. Calculate the sub-expression `(5 - 4)`. Calculate the final expression.

WRITE

a. `10 + 2 = 12`

b. `5 - 3 = 2`

c. `1.2 + 3.4 = 4.6`

d.
```
3 + 6 - (5 - 4) = 3 + 6 - (1)
                = 8
```

Characters for multiplication and division

- In JavaScript, for multiplication, use the character `*`; for division, use the character `/`.
- Fractions can be evaluated using the division character, but the numerator and denominator expressions need to be put into brackets.

$$\frac{2+3+1}{1+1} = \texttt{(2 + 3 + 1) / (1 + 1)}$$

Note: The characters `*` and `/` are only acceptable for use in programs and are not acceptable conventions for writing mathematics generally.

WORKED EXAMPLE 5 Writing expressions as JavaScript

Write the following mathematical expressions as JavaScript expressions.

a. 8×6 **b.** $2 \times (5 - 3)$ **c.** $12 \div (2 \times 2)$ **d.** $\frac{12 + 3}{6 - 1}$

THINK	WRITE
a. Replace the × with a `*`.	a. `8 * 6`
b. Replace the × with a `*`.	b. `2 * (5 - 3)`
c. Replace the × with a `*` and the ÷ with a `/`.	c. `12/(2 * 2)`
d. The fraction is a division. The numerator and denominator require brackets.	d. `(12 + 3)/(6 - 1)`

15.3.2 String expressions

- Expressions are not restricted to numerical expressions. Strings can also belong to expressions.
- Two or more strings can be concatenated (joined together) using the `+` symbol. For example, `"Hello" + " " + "World"` evaluates to `"Hello World"`.

WORKED EXAMPLE 6 Writing the string expression

a. Write a JavaScript expression to concatenate the strings `"Strings"," ","can"," have express", "ions".`
b. Write the expression.
c. Write the string `"I can write expressions"` as an expression of single words and spaces.

THINK	WRITE
a. Replace the commas with `+`.	a. `"Strings" + " " + "can" + "have express" + "ions"`
b. Write the expression.	b. `"Strings can have expressions"`
c. Replace the spaces with `" + " " + "`.	c. `"I" + " " + "can" + " " + "write" + " " + "expressions"`

Character

- A **character** is a string of length `1`. A string is a list of characters. Each character position has an incrementing index starting at `0`.


The string `"a fox"`	
Character	**Index**
`"a"`	0
`" "`	1
`"f"`	2
`"o"`	3
`"x"`	4

15.3.3 String methods

- JavaScript has several **methods** reserved for string expressions. These methods are used to manipulate a string.


String index of method

- The JavaScript method `indexOf` is used to find the first occurrence of a substring inside a larger string. The value returned is an index (starting at `0`) of the first occurrence. The `indexOf` method uses the structure shown in the following figure to define an expression.




String substr method

- The JavaScript method `substr` extracts a substring from a larger string. The method requires the substring's starting index and length. The `substr` method uses the following structure to define an expression.




String substring method

- The JavaScript method `substring` also extracts a substring from a larger string. The method also requires the substring's starting index, but is different from the `substr` method because it requires the final index plus 1. The `substring` method uses the following structure to define an expression.



String length method

- The JavaScript method `length` measures the length of a string. The `length` method uses the following structure to define an expression.



WORKED EXAMPLE 7 Evaluating JavaScript expressions manually

Evaluate the following JavaScript expressions manually.

a. `"Some text".indexOf("ex")` **b.** `"Some other".substr(6,3)`
c. `"Some more".substring(6,8)` **d.** `"Final text".length`

THINK

a. Think about the index of each character. Remember that indexing starts from zero.

S	o	m	e		t	e	x	t
0	1	2	3	4	5	6	7	8

In `"Some text"` the first occurrence of `"ex"` starts at index `6`.

S	o	m	e		t	e	x	t
0	1	2	3	4	5	6	7	8

b. Think about the index of each character.

S	o	m	e		o	t	h	e	r
0	1	2	3	4	5	6	7	8	9

WRITE

a.

6

b.

Look at the first three characters starting at index 6. `"the"`

S	o	m	e		o	t	h	e	r
0	1	2	3	4	5	6	7	8	9

c. Think about the index of each character. **c.**

S	o	m	e		m	o	r	e
0	1	2	3	4	5	6	7	8

Look at the characters starting at index 6 and ending at index 8 - 1 = 7. `"or"`

S	o	m	e		m	o	r	e
0	1	2	3	4	5	6	7	8

d. The number of characters in the string `"Final text"` is 10. **d.** 10

	F	i	n	a	l		t	e	x	t
Index	0	1	2	3	4	5	6	7	8	9
Length	1	2	3	4	5	6	7	8	9	10

15.3.4 Assigning expressions

- Results of expressions can be stored as a variable.

WORKED EXAMPLE 8 Writing a JavaScript statement to assign expression

Write a JavaScript statement to assign the following JavaScript expressions to the variable `store`.
a. `27 / (12 - 3)` **b.** `(6 + 4) * (1 + 12)` **c.** `"Store lat" + "er"`

THINK

Think about the assigning structure `var store = "value";` required for JavaScript.

a. Replace `"value"` with the expression `27 / (12 - 3)`.

b. Replace `"value"` with the expression `(6 + 4) * (1 + 12)`.

c. Replace `"value"` with the expression `"Store lat" + "er"`.

WRITE

a. `var store = 27 / (12 - 3);`

b. `var store = (6 + 4) * (1 + 12);`

c. `var store = "Store lat" + "er";`

Resources

Interactivity CodeBlocks Activity 2 (int-6574)

Exercise 15.3 Expressions

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 3, 5, 7, 11, 17	2, 6, 8, 12, 13, 15, 18, 20	4, 9, 10, 14, 16, 19, 21

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE4 Evaluate the following JavaScript expressions manually.

   a. `2 + 13` b. `52 - 3` c. `-21 + 34` d. `-12 – 13`

2. Evaluate the following JavaScript expressions manually.



   a. `12 + (3 - 2)`
   b. `57 - (6 + 3)`
   c. `57 - (6 - 3)`
   d. `43 - 16 - (12 - (13 - 6)) + 2`

3. Evaluate the following JavaScript expressions manually.

   a. `20 / 5`
   b. `5 * 3`
   c. `8 * 2`
   d. `(2 + 13) / 5`
   e. `(7 + 12) / (2 + 3)`

4. Evaluate the following JavaScript expressions manually.

   a. `100 / 25 - 9 / 3`
   b. `5 * 3 + 16 / 4`
   c. `8 + 6 * 2 / 3`
   d. `((12 - 3) / (5 - 2) + 16 / 8 - 4) / 2`
   e. `(-48 / 8 - 4) / 2 + (22 - 13) / (15 / 5)`

5. WE7 Evaluate the following JavaScript expressions manually.

   a. `"Four".length`
   b. `("Java" + "Script").length`
   c. `"Java".length + "Script".length`
   d. `"The quick brown fox jumps over the lazy dog".length`

6. Evaluate the following JavaScript expressions manually.

   a. `"Moving forward".indexOf("i")`
   b. `"The quick brown fox".length`
   c. `"Find the e".indexOf("e")`

Understanding

7. Evaluate the following JavaScript expressions manually.

a. `"Quotation marks" + " at " + "the start" + " and end"`
b. `"This " + "is a" + " string"`
c. `"Hello " + "World" + "!"`
d. `"Express" + "ions ma" + "ke strings f" + "un"`
e. `"Happy:" + ")"`
f. `"Java" + "Script"`
g. `("String " + "expressions") + (" using" + " brackets")`
h. `"Remember" + " the two " + " spaces"`

8. Evaluate the following JavaScript expressions manually.

a. `"Own this gown".indexOf("own")`
b. `"The quick brown fox".substr(4,5)`
c. `"The quick brown fox".substr(12,3)`

9. Evaluate the following JavaScript expressions manually.

a. `"The quick brown fox".substring(4,5)`
b. `("The sub" + "string is the answer").substring(4,13)`
c. `"The quick brown fox".substr(4,8).length`

10. Evaluate the following JavaScript expressions manually.

a. `"Find the four".substr(4 + 1 + 3 + 1,4)`
b. `"Find five wait find four".substr(4 * 5, "four".length)`
c. `"Take apart put together".substr(0,22 / 2) + "put together"`
d. `"Stop here".indexOf("e")`
e. `("The sub" + "string is the answer").substring(4,39 / 3)`

11. **WE5** Write the following mathematical expressions as JavaScript expressions.

a. 6×11 **b.** $54 \div 3$ **c.** $\frac{12}{5}$

d. $6(2+3)$ **e.** $(2+4)(-3+5)$ **f.** $\frac{7+2}{4-1}$

12. Write the following mathematical expressions as JavaScript expressions.

a. $3 \times 7 + 3$ **b.** $100 \div 25 + 4 + 4 \times 3$

c. $\frac{12 + 2(4-2)}{5}$ **d.** $6(2+5)(4-1)-3$

e. $\frac{(2+4)(-2+6)}{3}$ **f.** $\frac{2+2}{3-2} \times \frac{1+2}{4-1}$



13. Write the expression to extract the string `"and"` from the string below with the method:

i. `substr`
ii. `substring`.

a. `"This fox and sheep"` **b.** `"Find and back there"`
c. `"Use hands"` **d.** `"Search the land"`
e. `"ksanbjhandasdkjh"` **f.** `"Earth and Mars"`

14. `charAt(index)` is the same as `substr(index,1)`.
`charAt` returns one character at the specified index. For example, `"Find the letter h".charAt(6)` evaluates to `"h"`.

Evaluate the following JavaScript expressions.

a. `"The letter x is at index 23".charAt(23)`
b. `"Where is z hiding?".charAt(9)`
c. `"Pick 5 today".charAt(5)`
d. `"Find the last character.".charAt(`
`"Find the last character.".length-1)`

15. There are many more string methods that can be used in expressions.
`toUpperCase` converts all lower-case letters to upper-case letters.
`toLowerCase` converts all the upper-case letters to lower-case letters.
`"To upper case".toUpperCase()` evaluates to `"TO UPPER CASE"`.
`"To Lower Case".toLowerCase()` evaluates to `"to lower case"`.
Evaluate the following JavaScript expressions manually.

a. `"Make all upper case".toUpperCase()`
b. `"Make ALL lower case".toLowerCase()`
c. `"A title".toUpperCase()`
d. `"STOP SHOUTING".toLowerCase()`

16. The `%` symbol is used to find the remainder after an integer division. `7%3` evaluates to `1`, as `3` divides into `7` twice with a `1` remainder.
Evaluate the following JavaScript expressions manually

a. `20%3` b. `19%5` c. `200%8` d. `12%5` e. `6%5` f. `3%120`

17. WE8 Write a JavaScript statement to assign the following JavaScript expressions to the variable `finalResult`.

a. `27 - (16 - 3)`
b. `(3 + 23) / (10 + 3)`
c. `"Assign" + "ed to finalResult"`
d. `"Len".length + "gth".length`
e. `18%5`

Reasoning

18. Write a JavaScript expression and assign to the stated variable for the following situations.

a. Tom has 12 toy cars and 2 friends. Write a numerical expression to divide the cars between the three of them and assign it to the variable `numberOfCarsEach`.
b. Kate has saved $20 and earned $15 today. Write an expression to evaluate how much money she has now in dollars and assign it to the variable `totalCash`.
c. Vanessa wrote the text “My Trip” and she would like to change all the letters to upper case using the string method `toUpperCase`. Write an expression to convert the letters to upper case and assign it to the variable `myTitle`.



19. Write a JavaScript expression and assign it to the variable `questionResult` for the following questions.

a. Calculate $10 \times 9 \times 8 \times 7 \times 6 \times 5 \times 4 \times 3 \times 2 \times 1$.
b. Add the even numbers between 1 to 19.
c. Join the strings `"Th","e"," f","in","al re","sult is 2","2"` and then calculate the length.

Problem solving

20. Rearrange all the characters `123456789*` to form a valid expression:

- **a.** that evaluates to the smallest possible number.
- **b.** that evaluates to the largest possible number.

21. Given an English word, write a JavaScript program to translate the word into Pig Latin.
Output the translated Pig Latin to the console.
To translate a word into Pig Latin, move the first letter to the end of the word and then add `"ay"`. For example, `"javascript"` becomes `"avascriptjay"`.
The program has been started below.

```
var englishWord = "program";
```

15.4 Sequences

LEARNING INTENTION

At the end of this subtopic you should be able to:

- add comments to code and read comments in code
- view results of expressions or values using the console.log function
- store a result and then use it in the next line of code
- determine the output of programs that have the same statements in different orders.

15.4.1 Comments

- Computer programs are usually made up of more than one statement. This list of statements is run in order as a sequence.
- Knowing a computer language is often not enough for people to understand the code of a program easily.
- Comments are added to the code to give hints about the function of the program. The comments are completely ignored by the computer, so are only for the benefit of the reader.
- JavaScript comments start with `//` and the rest of the text on that line is ignored by the computer. For example

```
var x = 2; // The smallest prime number.
```

  - The first part of the line '`var x = 2;`' is the actual JavaScript code to be run.
  - The second part '`// The smallest prime number`' is ignored by the computer and is only there for the reader's reference. The text could be changed and it would make no difference to the running of the program.

WORKED EXAMPLE 9 Adding JavaScript comments

Add a comment to each statement of the form `// variable = value` where `variable` is the variable name and `value` is the evaluated value.

a.
```
var a = 2 + 1 / 10;
```
b.
```
var time = 30 + 15;
```
c.
```
var F5 = 1 * 2 * 3 * 4 * 5;
```

THINK

a. 1. The variable name is `a`.
2. The calculated value is $2 + 1/10 = 2.1$.
3. Add the comment to the statement.

WRITE

a.
```
var a = 2 + 1 / 10; // a = 2.1
```

b. 1. The variable name is `time`.
2. The calculated value is $30 + 15 = 45$.
3. Add the comment to the statement.


c. 1. The variable name is `F5`.
2. The calculated value is $1 \times 2 \times 3 \times 4 \times 5 = 120$.
3. Add the comment to the statement.

b.
```
var time = 30 + 15; // time = 45
```

c.
```
var F5 = 1 * 2 * 3 * 4 * 5;
// F5 = 120
```

15.4.2 Output

- The **console** is a special region in a web browser for monitoring the running of JavaScript programs. Most web browsers, including Chrome, Firefox, Safari, Internet Explorer, Microsoft Edge and Opera, allow you activate the console through the menu options.
- The JavaScript console.log function can be used to see the result of an expression or value. This function outputs results to the console. The following diagram uses the given statement and shows the output.



- Statement: `console.log("This is output.");`
- Output: `This is the output.`

Note: The quotation marks in strings are not shown in the output.

WORKED EXAMPLE 10 Using the console output

Determine the output to the console after running the following statements.

a. `console.log((16 + 4)/(11 - 1));`
b. `console.log(("Test" + " " + "this").length);`
c. `console.log("Con" + "sole out" + "put");`

THINK

a. 1. The expression `(16 + 4) / (11 - 1)` equals `2`.
2. The statement simplifies to `console.log(2)`.

b. 1. The expression `"Test" + " " + "this"` equals `"Test this"`.
`"Test this"` has a length of 9.
2. The statement simplifies to `console.log(9)`.

WRITE

a.
```
2
```

b.
```
9
```

c. 1. The expression `"Con" + "sole out" + "put"` equals `"Console output"`.
2. The statement simplifies to `console.log("Console output");`.
3. The `console.log` output does not show the quotation marks.

c.
```
Console output
```

WORKED EXAMPLE 11 Writing console.log statements

i. Write a JavaScript statement to output the following expressions to the console.
ii. Write the output.
a. `(2 + 12) / (9 - 2)` **b.** `"putter".substr(0,3)`

THINK	WRITE
Think about the structure of the `console.log();` statement.	
a. i. Put the expression inside the brackets.	**a. i.** `console.log((2 + 12) / (9 - 2));`
ii. Write the output.	**ii.** `2`
b. i. Put the expression inside the brackets.	**b. i.** `console.log("putter".substr(0,3));`
ii. Write the output.	**ii.** `put`

15.4.3 Store and use a result

- A common sequence of statements is to:
  1. calculate an expression and store the result in a variable
  2. use the stored result in a new expression.

Store the result

```
var storedForLater = "An" + "expression";
var newString = storedForLater + "with more";
// Output "An expression with more"console.log(newString);
```

WORKED EXAMPLE 12 Storing and using results

For each statement in the following programs:
i. determine the `variable` name between `var` and =
ii. calculate the `value` assigned to this `variable`.
Append a comment to each statement indicating the progress. The comment should be of the form `//` `variable` = `value`.

a.
```
var r = 10 / 2;
var area = r * r;
```

b.
```
var a = 2 * 5;
var b = 20 + a;
var c = 30 + b;
var d = 4 * a * c - b * b;
```

c.
```
var y = 2 + 8;
var y = 3 + 4;
var x = 3 * y;
```

THINK

a. i. The variable is `r`. `10 / 2` is `5`.

ii. The variable is `area`. `5 * 5` is `25`.

b. i. 1. The variable is `a`. `2 * 5` is `10`.

2. The variable is `b`. `20 + 10` is `30`.

3. The variable is `c`. `30 + 30` is `60`.

ii. The variable is `d`. `4 * 10 * 60 - 30 * 30` is `1500`.

c. i. 1. The variable is `y`. `2 + 8` is `10`.

2. The variable is `y`. `3 + 4` is `7`. `y` now has a new value and the old value is lost from memory.

ii. The variable is `x`. `3 * 7` is `21`.

WRITE

a. i.
```
var r = 10 / 2; // r = 5
```

ii.
```
var area = r * r; // area = 25
```

b. i.
```
var a = 2 * 5; // a = 10
var b = 20 + a; // b = 30
var c = 30 + b; // c = 60
```

ii.
```
var d = 4 * a * c - b * b; // d = 1500
```

c. i.
```
var y = 2 + 8; // y = 10
var y = 3 + 4; // y = 7
```

ii.
```
var x = 3 * y; // x = 21
```

WORKED EXAMPLE 13 Simulating programs manually

Manually simulate running the programs shown below. Determine the final value stored in the variable `x`.

a.
```
var a = 10 + 2;
var x = a * a;
```

b.
```
var x1 = "one";
var x2 = "two";
var s = " ";
var x = x1 + s + x2;
```

c.
```
var r = 4;
var r = 6;
var x = r + r;
```

THINK

a. 1. Write the equation.

2. Perform the addition.

3. Write the equation (use `* not x`)

4. Substitute `12` for `a`.

5. Perform the multiplication.

b. 1. Write the first assignment.

2. Write the second assignment.

3. Write the third assignment.

4. Write the fourth equation.

5. Substitute values into `x1`, `x2` and `s`.

6. Evaluate the expression.

c. 1. Write the assignment.

2. Write the reassignment.

3. Write the equation.

WRITE

a.
```
a = 10 + 2
a = 12
x = a * a
x = 12 * 12
x = 144
```

b.
```
x1 = "one"
x2 = "two"
s = " "
x = x1 + s + x2
x = "one" + " " + "two"
x = "one two"
```

c.
```
r = 4
r = 6
x = r + r
```

4. Substitute 6 for r. `x = 6 + 6`
5. Evaluate the expression. `x = 12`

15.4.4 Sequence

- The sequence of statements in a program is very important. Rearranging statements in a program can change the end result and/or cause an error.

WORKED EXAMPLE 14 Running programs with statements in different orders

a. Determine all the different programs that can be created from rearranging the three statements in the following table.

Reference	Statement
A	`var a = 2;`
B	`a = a + 3;`
C	`a = a * a;`

b. Add `console.log(a);` to the end of each program.
c. Determine the end result for each of the programs.

THINK

a. There six possible ways to arrange three statements.

ABC	ACB
BAC	BCA
CAB	CBA

WRITE

a.

A	`var a = 2;`	A	`var a = 2;`
B	`a = a + 3;`	C	`a = a * a;`
C	`a = a * a;`	B	`a = a + 3;`
B	`a = a + 3;`	B	`a = a + 3;`
A	`var a = 2;`	C	`a = a * a;`
C	`a = a * a;`	A	`var a = 2;`
C	`a = a * a;`	C	`a = a * a;`
A	`var a = 2;`	B	`a = a + 3;`
B	`a = a + 3;`	A	`var a = 2;`

b. Add the `console.log(a)` statement to the end of each program.

b.

A	`var a = 2;`	A	`var a = 2;`
B	`a = a + 3;`	C	`a = a * a;`
C	`a = a * a;`	B	`a = a + 3;`
	`console.log(a);`		`console.log(a);`
B	`a = a + 3;`	B	`a = a + 3;`
A	`var a = 2;`	C	`a = a * a;`
C	`a = a * a;`	A	`var a = 2;`
	`console.log(a);`		`console.log(a);`
C	`a = a * a;`	C	`a = a * a;`
A	`var a = 2;`	B	`a = a + 3;`
B	`a = a + 3;`	A	`var a = 2;`
	`console.log(a);`		`console.log(a);`

c. For each program, take the value of `a` through each step.

c.

A	`var a = 2;`	**A**	`var a = 2;`
B	`a = 2 + 3;`	**C**	`a = 2 * 2;`
C	`a = 5 * 5;`	**B**	`a = 4 + 3;`
	The final result is `25`.		The final result is `7`.
B	`a = a + 3;`	**B**	`a = a + 3;`
A	`var a = 2;`	**C**	`a = a * a;`
C	`a = 2 * 2;`	**A**	`var a = 2;`
	The final result is `4`.		The final result is `2`.
C	`a = a * a;`	**C**	`a = a * a;`
A	`var a = 2;`	**B**	`a = a + 3;`
B	`a = 2 + 3;`	**A**	`var a = 2;`
	The final result is `5`.		The final result is `2`.

15.4.5 Computer languages

- Computers follow instructions called computer programs, which are written in a computer language.
- Each computer language has its own clear set of rules and structure called a syntax.
- There are many different computer languages. Some examples include JavaScript, TypeScript, Python, Ruby, C#, C, C++, R and PHP.
- Below are sections of programs using different computer languages. All these programs perform the same key tasks:
  - Assign the value `10` to the variable `x`.
  - Calculate `2 + x` (`x` is currently storing the value `10`).
  - Evaluate this to get the value `12`.
  - Assign the evaluated value `12` to the variable `y`.

JavaScript
```
var x = 10;
var y = 2 + x;
```

TypeScript
```
var x:number = 10;
var y:number = 2 + x;
```

Python and Ruby
```
x = 10
y = 2 + x
```

C#, C and C++
```
int x = 10;
int y = 2 + x;
```

R
```
x <- 10
y <- 2 + x
```

PHP
```
$x = 10;
$y = 2 + $x;
```

WORKED EXAMPLE 15 Translating code from R to JavaScript

Consider the following R program.
```
p <- 4
r <- p + 3
```
Rewrite the program in JavaScript.

THINK

Compare the two example programs.

R	JavaScript
`x <- 10`	`var x = 10;`
`y <- 2 + x`	`var y = 2 + x;`

WRITE

R	JavaScript
`p <- 4`	`var p = 4;`
`r <-p + 3`	`var y = p + 3;`

Note the changes required to go from `R` to JavaScript statements.

- Add `"var"` to the start.
- Change `"<-"` to `"="`.
- Append `";"` to each statement.

Resources

Interactivity CodeBlocks Activity 3 (int-6575)

Exercise 15.4 Sequences

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 5, 6, 9, 11	2, 3, 10, 13, 15	4, 7, 8, 12, 14, 16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. The program statements in the following table relate to a rectangle.

Program	Comment
`var width = 10;`	
`var height = 15;`	
`var halfAround = width + height;`	
`var allAround = 2 * halfAround;`	
`var area = width*height;`	

Match the following JavaScript comments with the appropriate statements.

```
// set the height to 15
// set the width to 10
// calculate half the perimeter
// calculate the area
// calculate the perimeter
```

2. WE10 Determine the output to the console after running the following statements.

a. `console.log((18 + 2)/(6 - 1));`
b. `console.log(("How long is" + " " + "this").length);`
c. `console.log(("This is d").substring(8,9));`
d. `console.log(("Measure the length").length);`
e. `console.log(("The length is 16").substr(14,2));`

3. WE13 Manually simulate running the following programs. Determine the final value stored in the variable `z`.

a.
```
var y = 14 + 16;
var z = y / 3;
```

b.
```
var x1 = "cat";
var x2 = "jumped";
var x3 = "slept";
var s = " ";
var z = x1 + s + x3;
```

c.
```
var radius = 1;
var radius = 22;
var z = radius + radius;
```



4. Manually simulate running the following programs. Determine the output to the console.

a.
```
var a = 10;
console.log(a * a + 5);
```

b.
```
var aString = "Ten";
console.log(aString.length * 3 + 1);
```

c.
```
var a = 3;
var b = 4;
var c = 5;
console.log(a * a + b * b - c * c);
```

d.
```
var single = "One";
var double = "two";
var three = single + " plus " + double;
console.log(three);
```

e.
```
var x = "10";
var y = "20";
console.log(x + y);
```

f.
```
var x = 10;
var y = 20;
var z = x + y;
console.log(y);
```

5. Match the JavaScript statements below with the equivalent C++ statements in the table.

```
var aVariable = 6 * 8 * 7 * 9;
var x = 10 + 3;
var y = 3 + 10;
var x = 10 + 4;
var x = 10 * 4;
```

C++ statements	JavaScript statements
`int y = 10 + 3;`	
`int x = 10 + 4;`	
`int x = 3 + 10;`	
`int x = 10 * 4;`	
`int a Variable = 9 * 8 * 7 * 6;`	

Understanding

6. WE9 To each statement, add a comment of the form `// variable = value`, where `variable` is the variable name and `value` is the evaluated value.

   a. `var nearly_e = 2 + 7 / 10 + 1 / 100 + 8 / 1000;`
   b. `var marathonKm = 26 * 1.6;`
   c. `var secondsPerDay = 60 * 60 * 24;`

7. WE11 Write a JavaScript statement to output the following expressions to the console.

   a. `(3 + 41) / (9 + 2)`
   b. `"putter".substr(1,5)`
   c. `2 + 3 - 5`
   d. `(2 * 12)/(8 - 2)`
   e. `"life".substring(1,3)`

8. WE12 For each statement in the programs below:

   i. determine the `variable` name between `var` and `=`
   ii. calculate the `value` assigned to this `variable`.

   Append a comment of the form `// variable=value` to each statement indicating the progress.

   a.
   ```
   var side1 = 3 * 4;
   var side2 = side1 / 2;
   var area = side1 * side2;
   ```
   b.
   ```
   var a = 5 + 2;
   var b = a + a;
   var c = b + b;
   var delta = 4 * a * c - b * b;
   ```
   c.
   ```
   var reassign = 12 + 18;
   var reassign = 1 + 41;
   var result = 3 * reassign;
   ```

9. WE15 Rewrite the following R program in JavaScript.
   ```
   r <- 8
   r_less_5 <- r - 5
   ```

10. a. Rewrite the following JavaScript program in C.
    ```
    var minutes = 34;
    var seconds = minutes * 60;
    ```
    b. Write a JavaScript program to convert 3 hours into minutes.



11. Determine the most likely programing language of the following statements.

    a. `var thisIsTyped:number = 101;`
    b. `storeMeHere <- 19`
    c. `$dollars = 10 + 13;`
    d. `var webLanguage = "JavaSc" + "ript";`
    e. `var newType:string = "Another type of " + "script";`
    f. `console.log("Nothing new here");`

12. WE14

a. Determine all the different programs that can be created from rearranging the following three statements.

Reference	Statement
A	`var e = 5;`
B	`e = (e + 7) * 2;`
C	`e = e / e;`


b. Add `console.log(e);` to the end of each program.

c. Determine the end result for each of the programs.

Reasoning

13. Write a JavaScript program to calculate the `perimeter` of a rectangle with a `width` of `30` units and `length` of `20` units.

14. Fill in the gaps for the following JavaScript program to calculate the area of a composite shape. The shape is made up of a square of `width 12` units and a triangle of `height 9` units.




```
var ______ = 12;
var _______ = 9;
var triangleArea = height * ______ / 2;
var squareArea = ______ * width;
var totalArea = squareArea + _______________;
```

Problem solving

15. Rearrange the following program so that it starts with `x = 3` and finishes with `x = 100`.
Hint: Assume `x` is always a positive whole number through the entire program sequence.

```
var x = 3;
x = x / 24;
x = x - 96;
x = x + 9;
x = 10 * x; (Hint: This step is in the correct position.)
x = 110 - x;
x = x - 10;
x = x * x;
x = 100
```

16. Fill in the single character gaps below using the nine digits `123456789` so the program finishes with `x = 1`. The `8` has already been filled in.
Hint: Assume `x` is always a positive whole number through the entire program sequence.

```
var x = _;
x = x / _;
x = x + _;
x = x / _;
x = x + 8;
x = x / _;
x = x + _;
x = x - _;
x = _ - x;
x = 1
```

15.5 Algorithms

LEARNING INTENTION

At the end of this subtopic you should be able to:

- define and call a function in JavaScript
- identify the inputs of a function in javaScript
- manually simulate a JavaScript program containing functions
- design and implement an algorithm in JavaScript.

15.5.1 Define a function

- In JavaScript a function is used to give a `name` to a section of code. The following code shows an example of the structure used to do this.

Defining a function

```
function name() {
  statement 1
  statement 2
  statement n
}
```

Note: All functions start and end with curly braces `{}` as shown in the example above.

WORKED EXAMPLE 16 Naming and determining outputs of functions

i. Identify the name of each of the following functions.
ii. Determine the output to the console if the code inside the function was run.

a.
```
function triangleArea() {
  var base = 10;
  var height = 3;
  console.log(base * height / 2);
}
```

b.
```
function outputVolume() {
  var width = 3;
  var height = 4;
  var depth = 5;
  console.log(width * height * depth);
}
```

c.
```
function complexFormula() {
  var w = 6;
  var h = 7;
  var d = 8;
  console.log(2 * w * h + 2 * w * d + 2 * h * d);
}
```

THINK	WRITE
a. i. Identify the `name` after the function keyword.	**a. i.** `triangleArea`
ii. 1. Write the first assignment.	**ii.** `base = 10`
2. Write the second assignment.	`height = 3`
3. Write the output expression.	`base * height / 2`
4. Substitute `10` for `base` and `3` for `height`.	`= 10 * 3 / 2`
5. Evaluate the output expression.	`= 15`
b. i. Identify the `name` after the function keyword.	**b. i.** `outputVolume`
ii. **1.** Write the first assignment.	**ii.** `width = 3`
2. Write the second assignment.	`height = 4`
3. Write the third assignment.	`depth = 5`
4 Write the output expression.	`width * height * depth`
5. Substitute `3` for `width`, `4` for `height` and `5` for `depth`.	`= 3 * 4 * 5`
6. Evaluate the output expression.	`= 60`
c. i. Identify the `name` after the function keyword.	**c. i.** `complexFormula`
ii. 1. Write the first assignment.	**ii.** `w = 6`
2. Write the second assignment.	`h = 7`
3. Write the third assignment.	`d = 8`
4. Write the output expression.	`2 * w * h + 2 * w * d + 2 * h * d`
5. Substitute `6` for `w`, `7` for `h` and `8` for `d`.	`= 2 * 6 * 7 + 2 * 6 * 8 + 2 * 7 * 8`
6. Evaluate the output expression.	`= 292`

15.5.2 Calling a function

- Defining a function only tells the computer what to do if the function is **called**. In order for a function to run, it needs to be called with a separate statement.
- Once a function with the `name` has been defined, it can be called with the statement `name();`.

WORKED EXAMPLE 17 Calling a function

Given the following function names, write the statement to call the function.

a. `outputTime` **b.** `updateResults` **c.** `createNew`

THINK	WRITE
a. Identify the function `name` and join with `();`.	**a.** `outputTime();`
b. Identify the function `name` and join with `();`.	**b.** `updateResults();`
c. Identify the function `name` and join with `();`.	**c.** `createNew();`

- To be a valid program, a function must be defined before it can be called.

Calling functions multiple times

A function can be called many times once defined, as shown in the following example code.

```
function name() {
  statement 1
  statement 2
  statement n
}
name();
name();
name();
```

WORKED EXAMPLE 18 Identifying valid and invalid programs

Identify whether the following programs are valid. (Answer either true or false.)

a.
```
function something() {
  console.log("Output");
}
something();
something();
```

b.
```
function doesNothing() {
}
doesNothing();
```

c.
```
wrongOrder();
function wrongOrder() {
  console.log("Does not work");
}
```

d.
```
function function1() {
  console.log("Function 1");
}
console.log("In the middle");
function1();
```

THINK

a. This program is valid as `something` is defined before being called.

b. This program is valid as `doesNothing` is defined before being called.

c. This program is invalid as `wrongOrder` is called before being defined.

d. This program is valid as `function1` is defined before being called. A program is still valid if it has a statement between the definition and calling statement.

WRITE

a. True

b. True

c. False

d. True

WORKED EXAMPLE 19 Writing a simple function program

a. **Write a function named `outputResults` to output `"Some results"` to the console.**
b. **Write a statement to call the function.**
c. **Combine the function definition and statement into one program.**
d. **Write the output.**

THINK	WRITE
a. Identify the `name` of the function.	a. `function outputResults() {`
Write the output statement.	`  console.log("Some results");`
Finalise the function definition.	`}`
b. Write the calling statement by adding `();` to the end of the function.	b. `outputResults();`
c. Write the function definition.	c. `function outputResults() {` `  console.log("Some results");` `}`
Write the calling statement.	`outputResults();`
d. Write the output.	d. `Some results`

15.5.3 Input

- In JavaScript a function can be given an input to vary the function's behaviour as shown below.

Function given an input

```
function name(input) {
  statement 1
  statement 2
  statement n
}
```

WORKED EXAMPLE 20 Identifying the name of a function and input

i. Identify the name of each of the following functions.
ii. Identify the name of the input.
iii. Determine the output to the console if the functions were called with the input value 10.

a.
```
function outputDouble(inputValue) {
  console.log(2 * inputValue);
}
```
b.
```
function outputVolume(side) {
  console.log(side * side * side);
}
```
c.
```
function sixTimesSquared(x) {
  var squared = x * x;
  console.log(6 * squared);
}
```

THINK	WRITE
a. i. Identify the `name` after the `function` keyword.	a. i. `outputDouble`
ii. Identify the `input` inside the function brackets ().	ii. `inputValue`
iii. 1. Write the output statement.	iii. `console.log(2 * inputValue)`
2. Substitute `10` for `inputValue`.	`console.log(2 * 10)`

	3. Evaluate the expression.	`console.log(20)`
	4. Write the output to console.	`20`
b. i.	Identify the `name` after the `function` keyword.	b. i. `outputVolume`
ii.	Identify the `input` inside the function brackets ().	ii. `side`
iii.	1. Write the output statement.	iii. `console.log(side * side * side)`
	2. Substitute `10` for `side`.	`console.log(10 * 10 * 10)`
	3. Evaluate the expression.	`console.log(1000)`
	4. Write the output to console.	`1000`
c. i.	Identify the `name` after the `function` keyword.	c. i. `sixTimesSquared`
ii.	Identify the `input` inside the function brackets ().	ii. `x`
iii.	1. Write the assignment expression	iii. `squared = x * x`
	2. Substitute `10` for `x`.	`squared = 10 * 10`
	3. Evaluate the assignment.	`squared = 100`
	4. Write the output statement.	`console.log(6 * squared)`
	5. Substitute `100` for `squared`.	`console.log(6 * 100)`
	6. Evaluate the expression.	`console.log(600)`
	7. Write the output to console.	`600`

- In JavaScript a function can be given zero, one or more inputs; for example, the inputs could be `x1,x2,...` as shown in the following code. The inputs are given as a list, separated by commas.

Multiple inputs

```
function name(x1,x2,…) {
  statement 1
  statement 2
  statement n
}
```

WORKED EXAMPLE 21 Determining the number and name of an input of a function

i. Determine the number of inputs each of the following functions has.
ii. Identify the names of the inputs. (Write these in order, with no spaces and separated with commas.)

a.
```
function outputSquared(ignore,x) {
  console.log(x * x);
}
```

b.
```
function outputVolume(w,h,d) {
  console.log(w * h * d);
}
```

c.
```
function requiresNothing() {
  console.log("Always the same");
}
```

THINK			WRITE		
a.	i.	Count the inputs inside the function brackets ().	a.	i.	2
	ii.	Identify the inputs inside the function brackets ().		ii.	`ignore, x`
b.	i.	Count the inputs inside the function brackets ().	b.	i.	3
	ii.	Identify the inputs inside the function brackets ().		ii.	`w, h, d`
c.	i.	Count the inputs inside the function brackets ().	c.	i.	0
	ii.	Identify that there are no inputs inside the function brackets ().		ii.	There are no inputs.

- A function with inputs `x1,x2,...` can be called with the corresponding values `v1,v2,...` The value `v1` is assigned to the input `x1`, the value `v2` is assigned to the input `x2`, etc.

Multiple inputs assigned with corresponding values

```
function name(x1,x2,…) {
  statement 1
  statement 2
  statement n
}
name(v1,v2,…);
```

WORKED EXAMPLE 22 Determining the output of a function

Determine the output to the console of each of the following programs.

a.
```
function outputCubed(x) {
  console.log(x * x * x);
}
outputCubed(3);
```

b.
```
function rectangleArea(w,h) {
  console.log(w * h);
}
rectangleArea(11,2);
```

c.
```
function noInputs() {
  console.log("Never changes");
}
noInputs();
```

THINK		WRITE
a. 1.	The input `x` equals 3.	a. `x = 3`
2.	Write the output statement.	`console.log(x * x * x)`
3.	Substitute 3 for `x`.	`console.log(3 * 3 * 3)`
4.	Evaluate the expression	`console.log(27)`
5.	Write the output to console.	`27`

b. 1. The input `w` equals `11`.
2. The input `h` equals `2`.
3. Write the output statement.
4. Substitute `11` for `w` and `2` for `h`.
5. Evaluate the expression.
6. Write the output to console.

c. 1. The function has no inputs.
2. Write the output statement.
3. Write the output to console.

b.
```
w = 11
h = 2
console.log(w * h)
console.log(11 * 2)
console.log(22)
22
```

c.
```
console.log("Never changes")
Never changes
```

15.5.4 Return value

- A JavaScript function will execute until a return statement is reached, at which point the function stops running the section of code and output is returned to the 'caller'. The output can then be stored in a variable `stored`.

Structure of return value

The structure of the function and storing the result is shown below.

```
function name(x1,x2,…) {
  statement 1
  statement 2
  statement n
return output;
}
var stored = name(v1,v2,…);
```

WORKED EXAMPLE 23 Manually simulating programs containing functions

Manually simulate running each of the following programs. Determine the final value stored in the variable x.

a.
```
function volumePrism(height,area) {
  return height * area;
}
var x = volumePrism(10,40);
```

b.
```
function mean(x1,x2,x3,x4) {
  total = x1 + x2 + x3 + x4;
  return total / 4;
}
var x = mean(2,4,6,8);
```

THINK	WRITE
a. 1. Write the assignment.	a. `x = volumePrism(10, 40)`
2. The input `h` equals `10`.	`height = 10`
3. The input `area` equals `40`.	`area = 40`
4. Write the return expression.	`volumePrism(10, 40) = height * area`
5. Substitute `10` for `h` and `40` for `area`.	`volumePrism(10, 40) = 10 * 40`
6. Evaluate the return expression.	`volumePrism(10, 40) = 400`
7. Write the assignment.	`x = volumePrism(10, 40)`
8. Substitute `400` for `volumePrism(10,40)`	`x = 400`
b. 1. Write the assignment.	b. `x = mean(2, 4, 6, 8)`
2. The input `x1` equals `2`.	`x1 = 2`
3. The input `x2` equals `4`.	`x2 = 4`
4. The input `x3` equals `6`.	`x3 = 6`
5. The input `x4` equals `8`.	`x4 = 8`
6. Write the first assignment inside the function.	`total = x1 + x2 + x3 + x4`
7. Substitute `2` for `x1`, `4` for `x2`, `6` for `x3` and `8` for `x4`.	`total = 2 + 4 + 6 + 8`
8. Evaluate the expression.	`total = 20`
9. Write the return expression.	`mean(2, 4, 6, 8) = total / 4`
10. Substitute `20` for `total`.	`mean(2, 4, 6, 8) = 20 / 4`
11. Evaluate the return expression.	`mean(2, 4, 6, 8) = 5`
12. Write the assignment.	`x = mean(2, 4, 6, 8)`
13. Substitute `5` for `mean(2,4,6,8)`.	`x = 5`

15.5.5 Design an algorithm

- An **algorithm** is a step-by-step set of tasks to solve a particular problem. A program is the implementation of the algorithm.
- Designing an algorithm to solve a problem involves:
  - determining the inputs
  - determining the output required
  - breaking the problem into simple steps.

These steps are not code, but an explanation of what the program is required to do at this point.

WORKED EXAMPLE 24 Designing algorithms

Design an algorithm to solve each of the problems below.

i. **Determine the inputs.**
ii. **Determine the output required.**
iii. **Break the problem into simple steps.**
   a. **Convert from a decimal to a percentage.**
   b. **Calculate the total area of a number of squares with the same side length.**
   c. **Calculate the probability of a picking a red marble from a bag of red marbles and blue marbles.**

THINK

a. i. Write the input.
ii. Write the output required.
iii. Write step 1.

b. i. Write the inputs.
ii. Write the output required.
iii. 1. Write step 1.
2. Write step 2.

c. i. Write the inputs.
ii. Write the output required.
iii. 1. Write step 1.
2. Write step 2.

WRITE

a. i. `decimal`
ii. `percentage`
iii. Find the percentage from a decimal.

b. i. `squares, length`
ii `area`
iii. Calculate area of each square.
Calculate total area.

c. i. `red, blue`
ii. `probability`
iii. Find the total number of marbles.
Find the probability of a red marble.

15.5.6 Implementing an algorithm

- Implementing an algorithm in JavaScript involves:
  - designing an algorithm
  - writing function inputs
  - writing JavaScript statements for each step
  - returning the required result (output).

WORKED EXAMPLE 25 Implementing algorithms

Implement an algorithm in JavaScript to solve each of the following problems.
a. Convert from a decimal to a percentage.
b. Calculate the total area of a number of squares with the same side length.
c. Calculate the probability of a picking a red marble from a bag of red marbles and blue marbles.

THINK

a. 1. Design an algorithm.
2. Write the function input.
3. Write step 1.
4. Return the required result.

b. 1. Design an algorithm.
2. Write the function inputs.
3. Write step 1.
4. Write step 2.
5. Return the required result.

WRITE

a. See Worked example 24a.

```
function toPercentage(decimal) {
  // Find percentage from decimal
  var percentage = 100 * decimal;
  return percentage;
}
```

b. See Worked example 24b.

```
function area(number,length) {
  // Calculate area of each square
  var squareArea = length * length;
  // Calculate total area
  var totalArea = number * squareArea;
  return totalArea;
}
```

c. 1. Design an algorithm.

2. Write the function inputs.

3. Write step 1.

4. Write step 2.

5. Return the required result.

c. See Worked example 24c.

```
function prob(red,blue) {
  // Find total number of marbles
  var marbles = red + blue;
  // Probability of a red marble
  var probability = red / marbles;
  return probability;
}
```

Exercise 15.5 Algorithms

learnON

Individual pathways

PRACTISE	CONSOLIDATE	MASTER
1, 2, 6, 8, 10	3, 4, 7, 11, 13, 15	5, 9, 12, 14,16

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. WE16

i. Identify the name of each of the following functions.

ii. Determine the output to the console if each function was called.



a.
```
function rectangleArea() {
  var width = 30;
  var height = 56;
  console.log(width * height);
}
```

b.
```
function outputResults() {
  var result1 = 1;
  var result2 = 5;
  var result3 = 15;
  var sum = result1 + result2 + result3;
  console.log(sum / 3);
}
```

c.
```
function totalTimeMinutes() {
  var timeHours1 = 16;
  var timeHours2 = 71;
  console.log(60 * (timeHours1 + timeHours2) / 2);
}
```

2. WE17 Given the following function names, write the statement to call each function.

a. `callThis`

b. `outputMeanValue`

c. `outputCircleArea`

3. **WE18** Using True or False, identify whether the following programs are valid.

a.
```
function defineFirst() {
  console.log("Output");
}
defineFirst();
```

b.
```
function whyCallMe() {
}
whyCallMe();
```

c.
```
callLater();
function callLater() {
  console.log("Too late now");
}
```

d.
```
function definedFunction() {
  console.log("Output second and third");
}
console.log("Output first");
definedFunction();
definedFunction();
```

WE20 For questions 4 and 5, answer the following questions.

i. Identify the name of the function.

ii. Identify the name of the input.

iii. Determine the output to the console if the function was called with the input value 6.



4. a.
```
function outputTriple(input) {
  console.log(input + input + input);
}
```

b.
```
function outputArea(s) {
  console.log(s * s);
}
```

5. a.
```
function cubeVolume(length) {
  var area = length * length;
  console.log(length * area);
}
```

b.
```
function twoTimesSquare(a) {
  console.log(2 * a * a);
}
```

WE21 For questions 6 and 7, answer the following questions.

i. Determine the number of inputs of the following functions.

ii. Identify the names of the inputs for each function. (Write the inputs in order with no spaces and separated with commas.)

6. a.
```
function threeInputs(x,y,z) {
  console.log(x * x + y * y + z * z);
}
```

b.
```
function ignoreInputs(ignore1,ignore2) {
  console.log(10);
}
```

7. a.
```
function constantOuput(input) {
  console.log("Never changing");
}
```
b.
```
function sumMany(a0,a1,a2,a3,a4,a5,a6,a7) {
  console.log(a0 + a2 + a3 + a4 + a5 + a6 + a7);
}
```

Understanding

8. WE19
   a. Write a function named `outputBedTime` to output to the console `"9:00PM"`.
   b. Write a statement to call the function.
   c. Combine the function definition and statement into one program.

9. WE22 Determine the output to the console of each of the following programs.
   a.
```
function outputPower5(x) {
  console.log(x * x * x * x * x);
}
outputPower5(3);
```
   b.
```
function squareArea(side) {
  console.log(side * side);
}
squareArea(40);
```
   c.
```
function oneInput(butIgnored) {
  console.log("No input required");
}
oneInput(23847324);
```

10. WE23 Manually simulate running the following program. Determine the final value stored in the variable `x`.
```
function findArea(width,height) {
  return width * height;
}
var x = findArea(12,5);
```


11. Manually simulate running the following program. Determine the final value stored in the variable `x`.
```
function multiply(x1,x2) {
  return x1 * x2;
}
function multiplyAddCombinations(a,b,c) {
  var combination1 = multiply(a,b);
  var combination2 = multiply(b,c);
  var combination3 = multiply(c,a);
  return combination1 + combination2 + combination3;
}
var x = multiplyAddCombinations(2,3,4);
```

12. Manually simulate running the following program. Determine the final value stored in the variable `x`.

```
function f1() { return 1; }
function f2() { return 1; }
function f3() { return f1() + f2(); }
function f4() { return f2() + f3(); }
function f5() { return f3() + f4(); }
function f6() { return f4() + f5(); }
function f7() { return f5() + f6(); }
function f8() { return f6() + f7(); }
var x = f8();
```

Reasoning

13. WE24 Design an algorithm to solve each of the problems below.



i. Determine the inputs.
ii. Determine the output required.
iii. Break the problem into simple steps.

a. Convert from a percentage to a decimal.
b. Calculate the probability of picking a red marble from a bag of red, purple, green and pink marbles.

14. WE25 Implement an algorithm in JavaScript to solve each of the following problems.

a. Convert from a percentage to a decimal.
b. Calculate the probability of picking a red marble from a bag of red, purple, green and pink marbles.

Problem solving

15. Write a function named `someFunction` that returns the following results when called.

Statement	y
`var y = someFunction(1);`	2
`var y = someFunction(12);`	156
`var y = someFunction(6);`	42
`var y = someFunction(7);`	56

16. Design and implement a program that accepts the inputs a, b and c. The program returns the value x, which solves the mathematical equation. $ax + b = c$.

15.6 Review

15.6.1 Success criteria

Tick a column to indicate that you have completed the subtopic and how well you think you have understood it using the traffic light system.

(**Green:** I understand; **Yellow:** I can do it with help; **Red:** I do not understand)

Subtopic	Success criteria			
15.2	I can recognise three types of values in computer programming.			
	I can identify valid variable names.			
	I can assign values to variables.			
15.3	I can evaluate numerical expressions in JavaScript.			
	I can evaluate string expressions in JavaScript.			
	I can apply the index, substring and length methods to extract specific parts of a string.			
15.4	I can add comments to code and read comments in code.			
	I can view results of expressions or values using the console.log function.			
	I can store a result and then use it in the next line of code.			
	I can determine the output of programs that have the same statements in different orders.			
15.5	I can define and call a function in JavaScript.			
	I can identify the inputs of a function in JavaScript.			
	I can manually simulate a JavaScript program containing functions.			
	I can design and implement an algorithm in JavaScript.			

on Resources

Digital document How to write your own program (doc-18769)

Exercise 15.6 Review questions

learnON

To answer questions online and to receive **immediate corrective feedback** and **fully worked solutions** for all questions, go to your learnON title at www.jacplus.com.au.

Fluency

1. Classify the following values as number, string or Boolean.
   a. `64` b. `-2` c. `2.34` d. `"-22"` e. `true` f. `1222.3`

2. Classify the following values as number, string or Boolean.
   a. `"Some random text"` b. `86`
   c. `"true"` d. `"999"`
   e. `false`

3. Using True or False, state whether each of the following is a string value.
   a. `"A string value"` b. `This is a string`
   c. `true` d. `374`
   e. `" 1234"` f. `"1234"`

4. Using True or False, state whether each of the following is a string value.
   a. `false` b. `value1 + value2`
   c. `1.234` d. `1.1.1.1.1`
   e. `"3464812.9879879"`

5. Using True or False, state whether each of the following is a number value.
   a. `"Forty"` b. `"40"` c. `2653` d. `"0"` e. `0`

6. Using True or False, state whether each of the following is a number value.
   a. `true` b. `Eighteen` c. `false` d. `"238476"` e. `-6.22`

7. Using True or False, state whether each of the following is a Boolean value.
   a. `false` b. `true` c. `"true"`
   d. `"false"` e. `False` f. `True`
   g. `1`

8. Using True or False, state whether each of the following is a valid variable name.
   a. `thisIs0k` b. `output_results`
   c. `output results` d. `outputResults`
   e. `1stResult`

9. Using True or False, state whether each of the following is a valid variable name.
   a. `secondResult` b. `3rdResult`
   c. `four%two` d. `no good`

10. Evaluate each of the following JavaScript expressions manually.
    a. `2 + 31` b. `84 - 34`
    c. `-14 + 101` d. `"Length ten".length`

11. Evaluate each of the following JavaScript expressions manually.
    a. `(17 + 3 * (14 - 6) / 2 - 2) / 9`
    b. `11 * 7`
    c. `18 * 2`

12. Evaluate each of the following JavaScript expressions manually.

a.
```
(2 + 31) * 4 / 12
```
b.
```
16 + (6 - 5) * 12
```
c.
```
(7 - 5) / 2 + (12 + 16) / 14
```
d.
```
("Join" + "This").length
```

13. Evaluate each of the following JavaScript expressions manually.

a.
```
(12 + 13) / 5 + (4 + 16) / 4
```
b.
```
200 / 40
```
c.
```
"Join".length + "This".length
```

14. Match the JavaScript comments below with the appropriate statements in the programs in the table.

```
// calculate the area of triangle 1
// calculate the area of triangle 2
// triangle 2 has half the height of triangle 1
// set the base of triangle 1 to 16
// triangle 2 has double the base of triangle 1
// set the height of triangle 1 to 10
```

Program	Comment
`var height1 = 10;`	
`var base1 = 16;`	
`var height2 = height1/2;`	
`var base2 = 2*base1;`	
`var area1 = height1*base1/2;`	
`var area2 = height2*base2/2;`	

15. Determine the output to the console after running each of the following statements.

a.
```
console.log((38 + 12) / (16 - 6));
```
b.
```
console.log(("Measure the " + " " + "length").length);
```
c.
```
console.log("Console output has no " + "quotation
marks");
```
d.
```
console.log(("This is g").substring(8,9));
```
e.
```
console.log(("Length is 12").substr(10,2));
```

16. Manually simulate running the following programs. Determine the final value stored in the variable `p`.

a.
```
var v = 4 + 96;
var p = v / 4;
```
b.
```
var y1 = "heals";
var y2 = "all";
var y3 = "time";
var s = " ";
var p = y3 + s + y1 + s + y2;
```
c.
```
var changing = 12;
var changing = 11;
var changing = 1;
var p = changing + changing + changing;
var changing = 2;
var x = changing;
```

17. Manually simulate running the following programs. Determine the output to the console.

a.
```
var b = 11;
console.log(b * b + b);
```

b.
```
var fourteen = "14";
console.log(fourteen.length * 5 + 4);
```

c.
```
var x = 9;
var y = 12;
var z = 15;
console.log(x * x + y * y – z * z);
```

d.
```
var single = "One";
var double = "two";
var triple = "three";
var three = single + " plus " + double + " equals " +
triple;
console.log(three);
```

e.
```
var x = "Java";
var y = "Script";
console.log(x + y);
```

18. Match the JavaScript statements below with the equivalent R statements in the table.

```
var y = 15;
var t = 10;
var y = 4 + 10;
var t = "10";
```

R statements	JavaScript statements
`t <- 10`	
`t <- "10"`	
`y <- 10 + 4`	
`y <- 4 + 11`	

19. **i.** Identify the name of each of the following functions.
ii. Determine the output to the console if each function was called.

a.
```
function averageWidthScaled() {
    var width1 = 30;
    var width2 = 50;
    var averageWidth = (width1 + width2) / 2;
    var scale = 40;
    console.log(averageWidth * scale);
  }
```

b.
```
function averageResults() {
    var x1 = 31;
    var x2 = 335;
    var x3 = 1335;
    var x4 = 13;
    var Sum = x1 + x2 + x3 + x4;
    var Average = Sum / 4;
    console.log("Average");
  }
```

20. Given the following function names, determine the statement to call each function.

a. `interestingName`

b. `outputTime`

c. `meanValue`

21. Using True or False, state whether each of the following is a valid program.

a.
```
function correctOrder() {
  console.log("Working");
}
correctOrder();
```

b.
```
function I_do_nothing() {
}
I_do_nothing();
```

c.
```
jumpTheGun();
function jumpTheGun() {
  console.log("False start");
}
```

d.
```
function callMeAgain() {
  console.log("Do it again");
}
console.log("First time");
callMeAgain();
callMeAgain();
callMeAgain();
```

22. i. Determine the number of inputs each of the following functions has.

ii. Identify the names of the inputs in each case. (Write the inputs in order with no spaces and separated with commas.)

a.
```
function countThem(x,y) {
  console.log(x / x + y / y);
}
```

b.
```
function useInputs(use1,use2,use3) {
  var total = use1 + use2 + use3;
  console.log("Maybe ignore them");
}
```

23. i. Identify the name of each of the following functions.

ii. Identify the name of the input in each case.

iii. Determine the output to the console if each function was called with the input value 7.

a.
```
function doubleIt(doubleThis) {
  console.log(doubleThis + 2 * doubleThis -
doubleThis);
}
```

b.
```
function outputCubeVolume(side) {
  console.log(side * side * side);
}
```

24. Determine the output to the console of the following program.

```
function power3(y) {
   console.log(y * y * y);
}
function power6(x) {
  console.log(power3(x) * power3(x));
}
power6(2);
```

25. Manually simulate running the program below. Determine the final value stored in the variable `volume`.

```
function findVolume (width,height,depth) {
  return width * height * depth;
}
var volume = findVolume (3,6,8);
```

Problem solving

26. Manually simulate running the following program. Determine the final value stored in the variable `x`.

```
function dice1(a,b,c,d,e,f) {
  return d;
}
function dice2(y1,y2,y3,y4,y5,y6) {
  return y5;
}
function twoDice(z1,z2,z3,z4,z5,z6) {
  var role1 = dice1(z1,z2,z3,z4,z5,z6);
  var role2 = dice2(z1,z2,z3,z4,z5,z6);
  var total = role1 + role2;
  return total;
}
var x = twoDice(6,5,4,3,2,1);
```

27. Manually simulate running the following program. Determine the final value stored in the variable `x`.

```
function f1() { return 1; }
function f2() { return 1; }
function f3() { return 1; }
function f4() { return f1() + f2() + f3(); }
function f5() { return f2() + f3() + f4(); }
function f6() { return f3() + f4() + f5(); }
function f7() { return f4() + f5() + f6(); }
var x = f7();
```

28. Design an algorithm to solve each of the following problems.

- **i.** Determine the inputs.
- **ii.** Determine the output required.
- **iii.** Break the problem into simple steps.
  - **a.** Take the base to the power of 4 and return the value.
  - **b.** Calculate the mean of five numbers.
  - **c.** Calculate the missing angle of a triangle given the other two angles.

29. Implement an algorithm in JavaScript to solve each of the following problems.

a. Take the base to the power of 4 and return the value.

b. Calculate the mean of 5 numbers.

c. Calculate the missing angle of a triangle given the other two angles.



To test your understanding and knowledge of this topic, go to your learnON title at www.jacplus.com.au and complete the **post-test**.

Online Resources

on Resources

Below is a full list of **rich resources** available online for this topic. These resources are designed to bring ideas to life, to promote deep and lasting learning and to support the different learning needs of each individual.

Solutions

Download a copy of the fully worked solutions to every question in this topic (sol-0704) ☐

Digital document

15.6 How to write your own program (doc-18769) ☐

Interactivities

15.2 CodeBlocks Activity 1 (int-6573) ☐
15.3 CodeBlocks Activity 2 (int-6574) ☐
15.4 CodeBlocks Activity 3 (int-6575) ☐

Teacher resources

There are many resources available exclusively for teachers online.

To access these online resources, log on to **www.jacplus.com.au**.

Answers

Topic 15 Algorithmic thinking

Exercise 15.1 Pre-test

1. A
2. D
3. A
4. C
5. 14
6. B
7. B
8. D
9. 9
10. 4
11. 49
12. 66
13. 3
14. B
15. B

Exercise 15.2 Variables

1. a. Number b. Number c. Number
   d. String e. String f. String
2. a. Boolean b. String c. Boolean
   d. String e. Number f. Number
3. a. String b. String c. String
   d. Number e. String
4. a. False b. False c. True
   d. True e. False f. False
   g. False
5. a. False b. False c. False
   d. False e. True f. True
   g. True
6. a. True b. False c. False
   d. True e. False f. True
   g. True h. False
7. a. True b. False c. True
   d. False e. False f. True
   g. False
8. a. True b. True c. False
   d. False e. False
9. a. False b. False c. False
   d. False
10. a. True b. True c. True
    d. True e. False f. False
    g. True h. False
11. a. False b. True c. True
    d. False e. True f. True
    g. False h. False
12. a. True b. True c. True
    d. True e. True f. False
    g. False
13.

	Variable	Value	Type	JavaScript statement
e.g	`a_variable`	`"text"`	String	`var a_variable = "text";`
a.	`x`	`10`	Number	`var x = 10;`
b.	`nine`	`9`	Number	`var nine = 9;`
c.	`aBoolean`	`true`	Boolean	`var aBoolean = true;`
d.	`_`	`"A string"`	String	`var _ = "A string";`
e.	`_long_var`	`true`	Boolean	`var _long_var = true;`
f.	`areYouTall`	`false`	Boolean	`var areYouTall = false;`
g.	`about_e`	`2.718281828459`	Number	`var about_e = 2.718281828459;`
h.	`sin_90`	`1`	Number	`var sin_90 = 1;`
i.	`isThis`	`"false"`	String	`var isThis = "false";`
j.	`a_Boolean`	`true`	Boolean	`var a_Boolean = true;`

14. true, false
15. Yes
16. a. `var count = 10;`
    b. `var information = "Data";`
    c. `var threeSquared = 9;`
17. a. `var isThisJavaScript = true;`
    b. `var meaningOfLife = 42;`
    c. `var classSize = 25;`
18. a. `timeInSeconds <- 120`
    b. `distanceInMiles <- 40`
    c. `firstName <- "Ben"`
    d. `middleName <- "Violet"`
    e. `numberLeft <- 19`
    f. `littleOverThree <- 3.1`
19. a. True b. True c. False d. False
    e. True f. False g. True

20.

	JavaScript assignment statement	Python assignment statement
a.	`var x = 10;`	`x = 10`
b.	`var nine = 9;`	`nine = 9`
c.	`var aBoolean = true;`	`aBoolean = True`
d.	`var _ = "A string";`	`_ = "A string"`
e.	`var _longer_variable = true;`	`_longer_variable = True`
f.	`var areYouTall = false;`	`areYouTall = False`
g.	`var nearly4 = 3.99;`	`nearly4 = 3.99`
h.	`var about_e = 2.718281828459;`	`about_e = 2.718281828459`
i.	`var sin_90 = 1;`	`sin_90 = 1`
j.	`var isThisABoolean = "false";`	`isThisABoolean = "false"`
k.	`var is_this_a_Boolean = true;`	`is_this_a_Boolean = True`

21.
- Avoid confusion with values and keywords.
- Keep the variable names readable.
- Avoid confusion with mathematical and other symbols used by the computer language.

22. a. i. violates rule 3
ii. Avoid confusion with the Boolean value `true`.
b. i. violates rule 3
ii. Avoid confusion with the Boolean value `false`.
c. i. violates rule 1
ii. Avoid confusion with the numerical value 1.
d. i. violates rule 1
ii. Avoid confusion with the numerical value 2.
e. i. violates rule 2
ii. Avoid confusion with the mathematical symbol negative.
f. i. violates rule 2
ii. The space indicates two different variable names.
g. i. violates rule 2
ii. The quotation marks indicate that is a string value.

23. a. `a, B, _`
b. `aB, a_, a1, Ba, B_, B1, _a, _B, _1`
c. `aa, aB, a_, a1, Ba, BB, B_, B1, _a, _B, __, _1`

24. a. $26 + 26 + 1 = 53$ (26 upper-case letters and 26 lower-case letters; plus 1 symbol _)
b. $53 \times 63 - 3 = 3336$ (53 characters in the first position; 63 characters in the second position as the 10 digits can be included in this position; minus the 3 JavaScript keywords of length 2)
c. $53 \times 63 \times 63 - 7 = 210\,350$ (53 characters in the first position; 63 characters in the second and third position; minus the 7 JavaScript keywords of length 3)
d. $53 \times 63 \times 63 \times 63 - 16 = 13\,252\,475$ (53 characters in the first position; 63 characters in the second, third and fourth position; minus the 16 JavaScript keywords of length 4)

Exercise 15.3 Expressions

1. a. `15` b. `49` c. `13` d. `-25`
2. a. `13` b. `48` c. `54` d. `24`
3. a. `4` b. `15` c. `16` d. `3` e. `3.8`
4. a. `1` b. `19` c. `12` d. `0.5` e. `-2`
5. a. `4` b. `10` c. `10` d. `43`
6. a. `3` b. `19` c. `7`
7. a. `"Quotation marks at the start and end"`
b. `"This is a string"`
c. `"Hello World!"`
d. `"Expressions make strings fun"`
e. `"Happy:)"`
f. `"JavaScript"`
g. `"String expressions using brackets"`
h. `"Remember the two spaces"`
8. a. `10` b. `"quick"` c. `"own"`
9. a. `"q"` b. `"substring"` c. `8`
10. a. `"four"`
b. `"four"`
c. `"Take apart put together"`
d. `6`
e. `"substring"`
11. a. `6 * 11`
b. `54 / 3`
c. `12 / 5`
d. `6 * (2 + 3)`
e. `(2 + 4) * (-3 + 5)`
f. `(7 + 2) / (4 - 1)`
12. a. `3 * 7 + 3`
b. `100 / 25 + 4 + 4 * 3`
c. `(12 + 2 * (4 - 2)) / 5`
d. `6 * (2 + 5) * (4 - 1) - 3`
e. `(2 + 4) * (-2 + 6) / 3`
f. `(2 + 2) / (3 - 2) * (1 + 2)/ (4 - 1)`
13. a. i. `"This fox and sheep".substr(9,3)`
ii. `"This fox and sheep".substring(9,12)`

b. i. `"Find and back there".substr(5,3)`
ii. `"Find and back there".substring(5,8)`
c. i. `"Use hands".substr(5,3)`
ii. `"Use hands".substring(5,8)`
d. i. `"Search the land".substr(12,3)`
ii. `"Search the land".substring(12,15)`
e. i. `"ksanbjhandasdkjh".substr(7,3)`
ii. `"ksanbjhandasdkjh".substring(7,10)`
f. i. `"Earth and Mars".substr(6,3)`
ii. `"Earth and Mars".substring(6,9)`

14. a. `"x"` b. `"z"`
c. `"5"` d. `"."`

15. a. `"MAKE ALL UPPER CASE"`
b. `"make all lower case"`
c. `"A TITLE"`
d. `"stop shouting"`

16. a. 2 b. 4 c. 0
d. 2 e. 1 f. 3

17. a.
```
var finalResult = 27 - (16 - 3);
```
b.
```
var finalResult = (3 + 23) / (10 + 3);
```
c.
```
var finalResult = "Assign" + "ed to finalResult";
```
d.
```
var finalResult = "Len".length + "gth".length;
```
e.
```
var finalResult = 18%5;
```

18. a.
```
var numberOfCarsEach = 12 / 3;
```
b.
```
var totalCash = 20 + 15;
```
c.
```
var myTitle = "My Trip".toUpperCase();
```

19. a.
```
var questionResult = 10 * 9 * 8 * 7 * 6 * 5 * 4 * 3 * 2 * 1;
```
b.
```
var questionResult = 2 + 4 + 6 + 8 + 10 + 12 + 14 + 16 + 18;
```
c.
```
var questionResult = ("Th" + "e" + " f" + "in" + "al re" + "sult is 2" + "2").length;
```

20. a. `1*23456789` or `23456789*1`
b. `9642*87531` or `87531*9642`

21. Students' answers will vary. A sample answer is shown.
```
var englishWord = "program";
var wordLength = englishWord.length;
var firstLetter = englishWord.substr(0, 1);
var restOfWord = englishWord.substring(1, wordLength);
var pigLatin = restOfWord + firstLetter + "ay";
console.log(pigLatin);
```

Exercise 15.4 Sequences

1.

Program	Comment
`var width = 10;`	`// set the width to 10`
`var height = 15;`	`// set the height to 15`
`var halfAround = width + height;`	`// calculate half the perimeter`
`var allAround = 2 * halfAround;`	`// calculate the perimeter`
`var area = width * height;`	`// calculate the area`

2. a. 4 b. 16 c. d d. 18 e. 16

3. a. 10
b. `"cat slept"`
c. 44

4. a. 105 b. 10
c. 0 d. One plus two
e. 1020 f. 20

5.

C++ statements	JavaScript statements
`int y = 10 + 3;`	`var y = 3 + 10;`
`int x = 10 + 4;`	`var x = 10 + 4;`
`int x = 3 + 10;`	`var x = 10 + 3;`
`int x = 10 * 4;`	`var x = 10 * 4;`
`int aVariable = 9 * 8 * 7 * 6;`	`var aVariable = 6 * 8 * 7 * 9;`

6. a.
```
var nearly_e = 2 + 7 / 10 + 1 / 100 + 8 / 1000; // nearly_e = 2.718
```
b.
```
var marathonKm = 26 * 1.6; // marathonKm = 41.6;
```
c.
```
var secondsPerDay = 60 * 60 * 24; // secondsPerDay = 86400
```

7. a.
```
console.log((3 + 41) / (9 + 2));
```
b.
```
console.log("putter".substr(1,5));
```
c.
```
console.log(2 + 3 - 5);
```
d.
```
console.log((2 * 12)/(8 - 2));
```
e.
```
console.log("life".substring(1,3));
```

8. a. i.
```
var side1 = 3 * 4; // side1 = 12
var side2 = side1 / 2; // side2 = 6
```
ii.
```
var area = side1 * side2; // area = 72
```
b. i.
```
var a = 5 + 2; // a = 7
var b = a + a; // b = 14
var c = b + b; // c = 28
```
ii.
```
var delta = 4 * a* c - b * b; // delta = 588
```
c. i.
```
var reassign = 12 + 18; // reassign = 30
var reassign = 1 + 41; // reassign = 42
```
ii.
```
var result = 3 * reassign; // result = 126
```

9.
```
var r = 8;
var r_less_5 = r - 5;
```

10. a.
```
int minutes = 34;
int seconds = minutes * 60;
```
b.
```
var hours = 3;
var minutes = hours * 60;
```

11. a. TypeScript **b.** R
c. PHP **d.** JavaScript
e. TypeScript **f.** JavaScript

12. **a** and **b**

A
B
C
	`var e = 5;`
	`e = (e + 7) * 2;`
	`e = e / e; console.log(e);`
		A
		C
		B
			`var e = 5;`
			`e = e / e;`
			`e = (e + 7) * 2;`
			`console.log(e);`

B
A
C
	`e = (e + 7) * 2;`
	`var e = 5;`
	`e = e / e; console.log(e);`
		B
		C
		A
			`e = (e + 7) * 2;`
			`e = e / e;`
			`var e = 5; console.log(e);`

C
A
B
	`e = e / e;`
	`var e = 5;`
	`e = (e + 7) * 2;`
	`console.log(e);`
		C
		B
		A
			`e = e / e;`
			`e = (e + 7) * 2;`
			`var e = 5; console.log(e);`

c

A B C	1	A C B	16
B A C	1	B C A	5
C A B	24	C B A	5

13.
```
var width = 30;
var length = 20;
var perimeter = 2 * width + 2 * length;
```

14.
```
var width = 12;
var height = 9;
var triangleArea = height * width / 2;
var squareArea = width * width;
var totalArea = squareArea + triangleArea;
```

15.
```
var x = 3;
x = x + 9;
x = x * x;
x = x - 96;
x = 10 * x;
x = x / 24;
x = x - 10;
x = 110 - x;
```

16.
```
var x = 9;
x = x / 3;
x = x + 1;
x = x / 2;
x = x + 8;
x = x / 5;
x = x + 7;
x = x - 6;
x = 4 - x;
```

Exercise 15.5 Algorithms

1. a i. `rectangleArea`
   ii. 1680
   b i. `outputResults`
   ii. 7
   c i. `totalTimeMinutes`
   ii. 2610
2. a. `callThis();`
   b. `outputMeanValue();`
   c. `outputCircleArea();`
3. a. True b. True
   c. False d. True
4. a. i. `outputTriple`
   ii. `input`
   iii. 18
   b. i. `outputArea`
   ii. `s`
   iii. 36
5. a. i. `cubeVolume`
   ii. `length`
   iii. 216
   b. i. `twoTimesSquare`
   ii. `a`
   iii. 72
6. a. i. 3
   ii. `x,y,z`
   b. i. 2
   ii. `ignore1,ignore2`
7. a. i. 1
   ii. `input`
   b. i. 8
   ii. `a0,a1,a2,a3,a4,a5,a6,a7`
8. a.
```
function outputBedTime() {
console.log("9:00PM");
}
```
   b. `outputBedTime();`
   c.
```
function outputBedTime() {
console.log("9:00PM");
}
outputBedTime();
```
9. a. 243
   b. 1600
   c. `No input required`
10. 60
11. 26
12. 21
13. a. i. `percentage`
   ii. `decimal`
   iii. Find percentage from decimal.
   b. i. `red,purple,green,pink`
   ii. `probability`
   iii. 1. Find total number of marbles
   2. Find probability of picking a red marble
14. a.
```
function toDecimal(percentage)
{
var decimal = percentage / 100;
return decimal;
}
```
   b.
```
function calculateProbability
(red,purple,green,pink) {
// Find total number of marbles
var marbles =
red+purple+green+pink;
// Probability of a red marble
var probability = red /
marbles;
return probability;
}
```
15.
```
function someFunction(x) {
return x * x + x;
}
```
16.
```
function xSolve(a,b,c) {
// Algebraically solve for x
// a * x + b = c
// a * x + b - b = c - b
// a * x = c - b
// a * x / a = (c - b) / a
// x = (c - b) / a
// Calculate x given a, b and c
return (c - b) / a;
}
```

Exercise 15.6 Review questions

1. a. Number b. Number
   c. Number d. String
   e. Boolean f. Number
2. a. String b. Number
   c. String d. String
   e. Boolean
3. a. True b. False c. False
   d. False e. True f. True
4. a. False b. False c. False
   d. False e. True
5. a. False b. False c. True
   d. False e. True
6. a. False b. False c. False
   d. False e. True
7. a. True b. True c. False
   d. False e. False f. False
   g. False
8. a. True b. True c. False
   d. True e. False
9. a. True b. False
   c. False d. False
10. a. 33 b. 50
    c. 87 d. 10
11. a. 3 b. 77 c. 36
12. a. 11 b. 28 c. 3 d. 8
13. a. 10 b. 5 c. 8

14.

Program	Comment
`var height1 = 10;`	`// set the height of triangle 1 to 10`
`var base1 = 16;`	`// set the base of triangle 1 to 16`
`var height2 = height1 / 2;`	`// triangle 2 has half the height`
`var base2 = 2 * base1;`	`// triangle 2 has double the base`
`var area1 = height1 * base1 / 2;`	`// calculate the area of triangle 1`
`var area2 = height2 * base2 / 2;`	`// calculate the area of triangle 2`

15. a. `5`
    b. `18`
    c. `Console output has no quotation marks`
    d. `g`
    e. `12`

16. a. `25`
    b. `"time heals all"`
    c. `3`

17. a. `132`
    b. `14`
    c. `0`
    d. `One plus two equals three`
    e. `JavaScript`

18.

R statements	JavaScript statements
`t <- 10`	`var t = 10;`
`t <- "10"`	`var t = "10";`
`y <- 10 + 4`	`var y = 4 + 10;`
`y <- 4 + 11`	`var y = 15;`

19. a. i. `averageWidthScaled`
        ii. `1600`
    b. i. `averageResults`
        ii. `Average`

20. a. `interestingName();`
    b. `outputTime();`
    c. `meanValue();`

21. a. True
    b. True
    c. False
    d. True

22. a. i. `2`
        ii. `x,y`
    b. i. `3`
        ii. `use1,use2,use3`

23. a. i. `doubleIt`
        ii. `doubleThis`
        iii. `14`
    b. i. `outputCubeVolume`
        ii. `side`
        iii. `343`

24. `64`

25. `144`

26. `5`

27. `17`

28. a. i. `base`
        ii. `value`
        iii. 1) Multiple base by base by base by base.
    b. i. `x1,x2,x3,x4,x5`
        ii. `mean`
        iii. 1. Determine the total of `x1,x2,x3,x4,x5`.
            2. Divide the total by 5.
    c. i. `angle1,angle2`
        ii. `angle3`
        iii. 1. Determine the total of known angles.
            2. Subtract the above total from 180.

29. a.
```
function toPower4(base) {
// Multiple base by base by
base by base
var value = base * base * base
* base;
return value;
}
```
    b.
```
function findMean(x1,x2,x3,x4,x5)
{
// Find the total of
x1,x2,x3,x4,x5
var total = x1 + x2 + x3 + x4 +
x5;
// Divide the total by 5
var mean = total / 5;
return mean;
}
```
    c.
```
function findMissingAngle(angle1,
angle2) {
// Find the total of known
angles
var knownTotal = angle1 +
angle2;
// Subtract the above total
from 180
var angle3 = 180 - knownTotal;
return angle3;
}
```

GLOSSARY

3-dimensional object shape that has depth, as well as length and width; also called a polyhedron
acute angle angle greater than 0° but less than 90°
acute-angled triangle triangle where each angle is acute; that is, less than 90°
adjacent angles angles lying next to another angle
algorithm a step-by-step set of tasks to solve a particular problem. A program is an implementation of an algorithm.
allied angles *see* **co-interior angles**
alternate angles angles 'inside' the parallel lines, on alternate sides of a transversal; think of them as Z-shaped
area amount of surface enclosed by a shape; measured in square units, such as square metres, m^2, and square kilometres, km^2
arithmagon triangular figure in which the two numbers at the ends of each line add to the number along the line
ascending order in order from smallest to largest
Associative Law a number law that refers to the order in which three numbers may be added, subtracted, multiplied or divided, taking two at a time
Associative Law for addition a number law that refers to the order in which three numbers may be added or subtracted
axis of symmetry *see* **line of symmetry**
back elevation the view observed from standing directly behind an object
back view *see* **back elevation**
back-to-back stem-and-leaf plot a type of table used to organise, display and compare two sets of data
backtracking process of working backwards through a flow chart. Each step is the inverse operation of the corresponding step in the flow chart. It can be used to solve equations.
bar graph graph drawn in a similar way to a column graph, with horizontal bars instead of vertical columns. Categories are graphed on the vertical axis and frequencies (numbers) on the horizontal axis.
base the number being repeatedly multiplied in a power term. The power is the number of times the base is written.
BIDMAS the order in which calculations are performed. The order is: brackets; index (or power); division; multiplication from left to right; addition; and subtraction from left to right.
bird's eye view view observed from the top of the object looking down on it
Boolean a JavaScript data type with two possible values: `true` or `false`. JavaScript Booleans are used to make logical decisions.
called in programming, a defined function is called from another part of the program. Calling a function will run the statements defined inside the function. If a function has a name it is called with the statement `name();`.
capacity maximum amount of fluid that can be contained in an object. The units may be the same as for volume or litres and millilitres may be used.
Cartesian plane area formed by a horizontal line with a scale (x-axis) joined to a vertical line with a scale (y-axis). The point of intersection of the lines is called the origin.
categorical data data that involves grouping or classifying things, not numbers; for example, grouping hair colour
centre of rotation a specific point around which an object is rotated
character in programming, a string of length `1`. A JavaScript character is used to represent a letter, digit or symbol.
clustering a grouping of values around a particular value
coefficient the number written in front of a term
co-interior angles angles on the same side of the transversal positioned between the parallel lines. These angles are supplementary.

column graph graph in which equal width columns are used to represent the frequencies (numbers) of different categories
common factor a factor common to more than one number
common multiple a number that is a multiple of two or more numbers
Commutative Law a rule for a particular operation showing that the result is the same regardless of the order of the numbers
Commutative Law for addition a number law that refers to the order in which two numbers may be added or subtracted
complementary angles angles that sum (add) to 90°
complete revolution an angle of 360° (a full circle)
composite number number with more than two factors
composite shape figure made up of more than one basic shape
console a special region in a web browser for monitoring the running of JavaScript programs
constant a value that is not a variable
continuous describes data that take on any value that is measurable; for example, the heights of people in a class
conversion factor used to convert one unit of measurement to another
convert to change a measurement or value to different units
convex a shape with all its interior angles less than 180°
coordinate a pair of numbers that gives the position of a point on the Cartesian plane. The first number is the x-coordinate and the second number is the y-coordinate.
corresponding angles angles on the same side of the transversal that are both either above or below the parallel lines. The angles are equal in size.
cross-section the two-dimensional shape we can see when we cut straight through a three-dimensional object
cube number a number that can be arranged in a cube
cube root number that multiplies by itself three times to equal the original number. Finding a cube root is the opposite of cubing a number.
data information collected from surveys
decimal places digits after the decimal point
decimal point a dot, placed after a whole number, used to represent parts of a decimal fraction
decomposition method method of subtraction. The larger number is decomposed by taking 10 from the tens column and adding it to the units column. It may also involve taking 100 from the hundreds column and adding it to the tens column.
denominator bottom term of a fraction. It shows the total number of parts into which the whole has been divided.
descending order numbers in order from largest to smallest
difference the answer obtained when two numbers are subtracted
directed number a number with a positive or negative sign indicating that it is a certain direction from the origin along a number line
discrete describes data that takes on exact values that may be counted; for example, the number of televisions sold each week
Distributive Law a rule stating that each term inside a pair of brackets is to be multiplied by the term outside the brackets
divided bar graph a representation of data whereby the different sectors of a bar represent different groups of data
dividend the quantity in a division that is to be divided
divisibility test a series of rules that tests for factors of a number
division the sharing of a number into equal parts; the opposite of multiplication
divisor the quantity in a division by which the dividend is divided
domain the set of all x-values in a relationship between x and y
dot plot consists of a horizontal axis labelled and evenly scaled, with each data value represented by a dot
equally likely outcomes two or more outcomes that have an identical chance of occurring

equation mathematical statement containing a left-hand side, a right-hand side and an equals sign between them

equilateral triangle triangle with all sides equal in length. All angles will be equal too.

equivalent expressions two or more expressions that are identical but displayed in different ways

equivalent fractions two or more fractions that are equal in value but have different numerators and denominators; for example, $\frac{1}{2} = \frac{2}{4}$

event a possible outcome of a trial in a probability experiment

experiment the process in probability of performing repeated trials of an activity for obtaining data in order to be able to predict the chances of certain things happening

experimental probability the probability determined by conducting an experiment and gathering data

exponent *see* **power**

expression mathematical statement made up of pronumerals (letters) and numbers. An expression does not contain an equals sign.

exterior angle angle formed when any side of a closed shape is extended outwards. The exterior angle and the interior angle adjacent to it are supplementary (add up to 180°).

factor a whole number that divides exactly into another whole number, without any remainder

factor tree diagram that displays the prime factors of a composite number. Each branch shows a factor of all numbers above it. The last numbers at the bottom of the tree are the prime factors of the original number.

favourable outcome the outcome we are looking for

fraction used to describe a part of a whole number

frequency number of times a result or piece of data occurs.

frequency distribution table table used to organise data by recording the number of times each data value occurs

front elevation view observed from directly in front of an object

front view *see* **front elevation**

highest common factor (HCF) largest factor that is common to all the numbers given

image a point or shape after it has been transformed

improper fraction fraction whose numerator is larger than its denominator; for example, $\frac{7}{4}$

index *see* **power**

input number the first number in a flow chart

integers positive whole numbers, negative whole numbers and zero

interior angle an angle on the inside edges of a shape

inverse operation an operation that 'undoes' a previous operation. Addition and subtraction are inverse operations; and multiplication and division are inverse operations.

is greater than more or higher in value, expressed by the symbol >

is less than less or lower in value, expressed by the symbol <

isometric drawing a 2-dimensional drawing of a 3-dimensional object

isosceles triangle triangle that has two sides of equal length. The two angles opposite the equal sides will also be equal.

legend lists definitions of different symbols or colours used in a graph

like terms terms that contain exactly the same pronumeral (letter) part; for example, $5a$ and $33a$ are like terms but $4ab$ is not

line of symmetry line that divides a shape into two identical parts

long-term trend in probability, the trend observed for results from a very large number of trials. This tends to match the theoretical probability.

lowest common multiple (LCM) lowest multiple that two or more numbers have in common

magnitude the size of a number, relative to its distance from zero; also called absolute value

mean a measure of the centre of a set of data. If the total value of all the observations is shared equally among all of the values in the data set, the mean is the amount that each observation would receive.

median the middle value of a set of data when the data is arranged in order from smallest to largest

method in JavaScript, a defined function applied to an object. For example, the method indexOf can be applied to a string, `"string".indexOf("in")`, to find the index of the substring `"in"`.

mixed number number that is made up of a whole number and a fraction; for example, $2\frac{3}{4}$

mode the most common value in a set of data

multiple the result of multiplying a number by another whole number

multiplication a quick, shortened process of adding a number to itself a specific number of times

negative integers whole numbers less than zero

number in programming, a JavaScript data type that represents a numerical value

number plane *see* **Cartesian plane**

numerator top term of a fraction. It shows how many parts there are.

numerical data data that can be measured with a numerical value

obtuse angle angle greater than 90° but less than 180°

obtuse-angled triangle triangle that has one angle greater than 90°

opposite integers numbers equidistant from zero, but one is positive and one is negative

opposite operations *see* **inverse operations**

order of operations set of rules that determines the order in which mathematical operations are performed

order of rotational symmetry the number of times that a shape matches the original figure when being rotated through 360°

ordered stem plot a type of table used to organise and display data, with the leaf part written in ascending order from left to right

outcome result of an experiment

outlier an extreme value in a data set

output number the last number in a flow chart

parallel lines lines that run in the same direction and never meet

parallelogram quadrilateral with both pairs of opposite sides parallel to each other. Rectangles, squares and rhombuses are parallelograms.

per used to indicate 'for each' or 'for every' in a rate; for example, 20 km per hour or 20 km/h. It indicates that you are dividing the first quantity by the second quantity.

per cent out of 100

perfect square a number that can be arranged in a square; a number that is the square of another number

perigon an angle of 360° (a full circle)

perimeter distance around the outside (border) of a shape

perpendicular describes two objects with a right angle (90°) between them

place value the position of a digit in a number

positive integers whole numbers greater than zero

power the number of times that the base is written in the expanded form of a power term; also known as an exponent or index

primary data data that has been collected first-hand (by you)

prime factors factors that are only prime numbers

prime number counting number that has exactly two factors, itself and 1

prism a solid object with identical parallel ends, and with the same cross-section along its length

probability likelihood or chance of a particular event (result) occurring

product result of a multiplication

pronumeral letter used in place of a number

proper fraction fraction whose numerator is smaller than its denominator; for example, $\frac{3}{4}$

protractor instrument used to measure angles in degrees

quadrant one of four regions of the Cartesian plane produced by the intersection of the x- and y-axes

quadrilateral 2-dimensional, closed shape formed by four straight lines

quotient result of a division

range the set of all y-values in a relationship between x and y (algebra); the difference between the largest and smallest data value (measure of spread)

rate a ratio that compares two measurements with different units; for example, km/h or $/g

ratio a comparison of two or more quantities of the same kind

reciprocal the reciprocal of a number is obtained by first expressing it as a fraction then tipping the fraction upside down; for example, $\frac{4}{3}$ is the reciprocal of $\frac{3}{4}$. A mixed number must be converted to an improper fraction first and then tipped.

recurring decimal decimals that have one or more digits repeated continuously; for example, 0.999… They can be expressed exactly by placing a dot or horizontal line over the repeating digits, as in this example: $8.343\,434\ldots = 8.\dot{3}\dot{4}$ or $8.\overline{34}$.

reflection exact image of an object, as seen in a mirror, as far behind the mirror as the object is in front of it. Reflections always have reversed orientations; right appears left and left appears right.

reflex angle an angle greater than 180° but less than 360°

remainder number left over after numbers have been divided

right angle angle that equals 90°

right-angled triangle triangle that has one of its angles equal to 90° (a right angle). A small square is placed in that angle to mark the right angle.

rotation the turning of an object about a certain point — the centre of rotation

sample space in probability, the complete set of outcomes or results obtained from an experiment. It is shown as a list enclosed in a pair of braces (curled brackets) { }.

scale a series of marks indicating measurement increasing in equal quantities

scalene triangle triangle that has no equal sides. The angles will all be unequal too.

secondary data data that has been collected second-hand (by someone else)

sector graph a representation of data whereby the different sectors of a circle represent different groups of data; also known as a pie graph

side elevation view observed when standing directly to one side of an object. The left view or the right view of the object can be drawn.

side view *see* **side elevation**

square number a numbers that can be arranged in a square

square root number that multiplies by itself to equal the original number. Finding a square root is the opposite of squaring a number; for example, $\sqrt{49} = 7$.

squaring a number multiplying a number by itself; for example, $2 \times 2 = 2^2 = 4$

stem-and-leaf plot a type of table used to organise and display data

straight angle an angle that equals exactly 180°

string a JavaScript data type that represents text

substitution process by which a number replaces a pronumeral in a formula

successful trial a trial that results in the outcome you wanted

sum answer obtained when numbers are added together

supplementary angles angles that sum (add) to 180°

term part of an equation or expression. A term can be expressed as one or more than one pronumeral, or a number only. Examples include $5x$, $3ab$, xyz, 8 and so on.

terminating decimal a decimal number that has a fixed number of decimal places; for example, 0.6 and 2.54

tessellation a repeated pattern that covers a flat surface without any gaps

theoretical probability probability determined by predicting outcomes rather than by gathering data

top view *see* **bird's eye view**

translation horizontal (left/right) or vertical (up/down) movement

transversal a line that intersects a pair (a set) of parallel lines

travel graph a line graph that represents a journey. The horizontal axis represents time and the vertical axis represents distance.

trial number of times a probability experiment is conducted

triangle 2-dimensional closed shape formed by three straight lines

two-step experiment in probability, the process of performing repeated trials of two consecutive chance experiments to predict the chances of two events occurring; this data is recorded in a two-way table

two-way table a diagram that represents the relationship between two non-mutually exclusive attributes

unit price the price for a single unit of the item in question. This can be the price of a specified quantity (e.g. 1 kg or 100 mL) or of a single unit (e.g. 1 banana).

unitary method a method comparing the unit cost of varying quantities of items to help determine the best buy

unlike terms terms that do not contain exactly the same pronumeral (letter) part; for example, $5a$ and $33a$ are like terms but $4ab$ is an unlike term

value the worth of a number

variable another word for a pronumeral (algebra); a symbol in an equation or expression that may take many different values (data)

vertex the point at which two line s meet

vertically opposite angles special angles formed when two straight lines intersect. The two non-adjacent angles are called vertically opposite angles. These angles are equal in size.

vinculum horizontal bar separating the numerator from the denominator

volume amount of space that a 3-dimensional object occupies. The units used are cubic units, such as cubic metres, m^3, and cubic centimetres, cm^3. A volume of 1 m^3 is the space occupied by a cube of side length 1 m.

whole numbers counting numbers: 0, 1, 2, 3, 4, …

INDEX

A

acute angle 461
acute-angled
  triangle 468
addition
  decimals 313
  fractions 194–8
  integers 81–3
  mixed numbers 215–7
  positive integers
    algorithms 16–17
    compensation strategy 11
    jump strategy 10
    rearrange strategy 11–12
    split strategy 10–11
adjacent angles 489
algebra
  dividing terms 370–1
  evaluation 360–2
  expanding brackets 377–9
  expressions 353–4
    simplifying, like terms 364–6
  multiplying terms 369–70
  number laws 373–5
  pronumerals and constants 352
  substitution 360–2
algorithmic thinking 2
  algorithms 29–42
  expressions 11–19
allied angles 492
alternate angles 492
ancient number systems 53
angles 447–8
  classification 461
  drawing 462
  estimating 447–8
  measuring 448–50
  naming 462
  protractor 455–8
  quadrilateral 481–3
  triangle 470–2
  types of 461–2
area
  composite shapes 559–64
  metric units 546–8
  parallelogram 552–9
  rectangle 548–50
  triangle 550–2
arithmagon 23
ascending order 5
Associative Law 374–5
Associative Law for addition 17
axes 611
axis of symmetry 668–9

B

back elevation, drawing solids 578
back view, drawing solids 578
back-to-back stem-and-leaf plots 791–3
backtracking 405–7
  inverse operations 417–23
  solving equations 410–13
bar graphs 785
base 128
battleships game 646
best buys, unitary method 278–80
BIDMAS, positive and negative integers 98–9
bird's eye view, drawing solids 578

C

capacity 572–3
Cartesian coordinates 611
Cartesian plane 611–13
  combined transformations in 692–3
  creating 611
  determining coordinates of points on 612
  four quadrants 612–13
  reflections in 682–3
categorical data 759
centre of rotation 687
chance 718–20
clustering 785
coefficient 353
co-interior angles 492
column graphs 784–5
common factors 123
common multiples 123
common percentages, short cuts 238–40
Commutative Law 373–4
  addition 17
comparing numbers 5–6
compensation strategy
  addition 11
  subtraction 14
complementary angles 490
complete revolution 461
composite numbers 133
  factor trees 135–7
composite rectangular prism 566
composite shapes 559–61
constructing angles
  greater than 180°, semicircular protractor 456–8
  protractor 455–8
continuous numerical data 760
conversion
  decimals to fractions 302–3
  fractions to decimals 303–4
conversion factors 524
convert 274
convex quadrilaterals 479
coordinate 611
coordinate geometry 608
coordinate system 608
corresponding angles 492
Covid-19 pandemic and data 756
cube numbers 150–1
cube roots 151–2

D

data
  categorical 760
  collecting and classifying 759–63
  column graphs and dot plots 783–5
  comparing 806–8
  displaying data, in tables 766–8
  frequency distribution tables 766–8
  measures of centre 772–7
  measures of spread 777–8
  numerical 759
  pie charts and divided bar graphs 795–800
  primary and secondary data 762–3
  reliability 763
  stem-and-leaf plots 789–93
decimals
  adding and subtracting 313–14
  checking by estimation 314
  comparing 296–8
  converting to fractions 302–3
  decimal parts 294–6
  dividing by another decimal number 327–9
  division
    multiple of 10 326–7
    whole number 325–6
  multiplication 319–20

multiples of 10 321–2
multiplying by another decimal number 327–9
short cuts 322
squaring 320–1
percentages 332
place value 294–8
places 294
repeating 309–10
rounding 307–9
decomposition method 19
denominator 173
descending order 5
dice fractions 198
difference result 18
directed numbers 72
discount 282–4
discrete numerical data 760
distributive law 29, 377–9
divided bar graphs 795–800
dividend (numerator) 37
divisibility tests 147–8
division
algebra terms 370–1
decimals 325
dividing by another decimal number 327–9
multiple of 10 326–7
whole number 325–6
fraction 210–12
integers 93–5
positive integers 34
numbers, multiples of 10 37
short division algorithm 35–7
using expanded form 35
divisor (denominator) 37
domain and range 635
dot plots 785
drawing solids
isometric drawing 579–81
plans and views 578–9
prisms 576–8

E

Egyptian numbers 53–4
elastic percentages 227
equally likely outcomes 728
equations
backtracking 405–7
balanced 417–18
checking solutions 426–7
expressions 404–7
flowcharts 404–5
guess, check and improve 400–1
inspection 400
inverse operations 417–23
making pronumerals positive 422–3
writing, from words 398–9
equilateral triangle 468
equivalent expressions, algebra 366
equivalent fractions 174–5
equivalent ratios 268
equivalent repeating fractions 310
Eratosthenes 134
estimating angles 447–8
estimating by rounding 41–2
event 718
experimental probability of 734
expanding brackets, algebra
Distributive Law 377–9
experiment 734
experimental probability 734
defining 734–5
long-term trends 735–7
vs. theoretical probability 731
exponent 128
expressions, algebra 353–4
exterior angle 472

F

factors 119–20
factor tree 135
favourable outcome 728
fractions 172
adding and subtracting 194–8
comparing 177–80
converting to decimals 303
dice 198
division 210–12
equivalent 174–5
mixed numbers 188–90
multiplication 202–5
number line 176–7
percentages 222–4
simplifying 184–6
frequency 766
frequency distribution tables 766–8
front elevation, drawing solids 578
front view, drawing solids 578

G

geometry
angles 447–50, 461–2
constructing angles, protractor 455–58
parallel and perpendicular lines 489–95
quadrilaterals 479–83
triangles 467–73
Goldbach's conjecture 138
graphs
column and bar graphs 783–5
features of 783
interpretation of 633–4
domain and range 635–6
travel graphs 636–7
measures of centre and spread determination from 806
Greek numbers 54–5

H

highest common factor (HCF) 123–4

I

image 674
improper fractions 173
to mixed numbers 188–9
index 128
index notation
indices 128–9
place values 130–1
indices 128–9
place values 130–1
input number, flowchart 404
inspection equations 400
integers 70–1
adding integers 81–3
division of 93–5
magnitude 71
multiplication 92–3
number line 70–3
number plane 76–7
order of operations 98–99
subtraction 86–8
interior angles 472
inverse operations, equations 405–6, 417–23
is greater than 6
is less than 6
isometric drawing 579–81
isosceles triangle 468

J

jump strategy
addition 10
subtraction 12–13

L

language of chance 718–20
legends 783
like terms, algebra 364–6
line graph, interpretation 634
line of symmetry 668–9

linear number
patterns 619–23
geometric patterns 612–13
relationships and patterns, description of 619–22
linear pattern 626
long-term trends 735–7
lowest common denominator (LCD) 195–8
lowest common multiple (LCM) 123–4, 195

M

magnitude, integers 71
mean 772–3
measurement
area 546–53, 559–61
capacity 572–3
drawing solids 576–81
old units of length 588–9
perimeter 538–41
reading scales and measuring length 530–2
units of 523–6
volume of rectangular prisms 564–7
measures of centre 772–7
determination from graphs 806–8
measures of spread 777–8
determination from graphs 806–8
median 774–5
memory game 246
metric units, area 546–8
mirror lines, reflections in 680–2
mixed numbers 173
adding and subtracting 215–17
improper fractions 189–90
multiplying 217–18
simplifying fractions 184–5
working with 215–18
mode 775–7
multiples 30, 118–19
multiplication
algebra terms 369–70
decimals 319–20
multiples of 10 321–2
short cuts 322
squaring 320–1
fractions 202–5
word *of* 205–7
integers 92–3
mixed numbers 217–18
positive integers 25
algorithm 27–8
area mode 26
long multiplication algorithm 28–9
mental strategies 29–30
using diagrams 25–6
using expanded form 26

N

naming angles 462
naming quadrilaterals 480
naming triangles 467–70
negative integers 70
negative integers, BIDMAS 98–9
negative numbers 72–3
non-linear pattern 626
number laws, algebra
Associative Law 374–5
Commutative Law 373–4
number line 71–2
fractions 176–7
integers 70–1
number plane
integers 77
positive integers and zero 76–7
numerator 173
numerical data 759

O

obtuse angle 461
obtuse-angled triangle 468
opposite integers 71
opposite operations 405–6
order of operations 45, 144–5
BIDMAS 45–8, 98–9
cube 150
integers 98–99
order of rotational symmetry 669
ordered stem plots 790
ordering numbers 5–6
origin 611
outcome 719, 728
outliers 785
output number, flowchart 404

P

parallel lines 491–2
calculating angles 492–4
testing 494
parallelograms 479
parallelograms, area 552–3
per, rates 273
per cent 222
percentages
amount using fractions 227–9
decimal 332
definition 222–4
fractions 222–4
short cuts 238–40
unitary method 279–80
whole number 238
perfect squares 141
perigon 461
perimeter 538–46
rectangle and square 540–1
perpendicular lines 494
pie charts 795–8
place values
decimals 294–8
indices 130–1
place-holding zeros 4–5
reading numbers 5
plotting simple linear relationships 626–29
positive integers 70
addition 10–12
BIDMAS 98–9
division 34–5
multiplication 25–6
number plane 76–7
order of operations 45–8
ordering and comparing numbers 5–6
place value 4–5
rounding and estimating 41
subtraction 12–14
positive numbers 72–3
power 128
primary data 762
prime factors 135
prime numbers 133–5
prisms 576–8
probability 716, 718
experimental probability 734–7
language of chance 718–20
sample space 723–5
simple probability 728–31
product 25
pronumerals 352–3
proper fractions 173
protractor 448
constructing angles 455–6
greater than 180°, angles 456–8

Q

quadrants 612
of Cartesian plane 612–13
quadrilaterals 479
angles 481–3
properties 479–83
types of 479–81
quotient 37

R

range 635, 777
rates 273
  applications of 275–6
  identifying 273–4
  simplifying 274–5
ratios 267
  simplification 268–9
reading scales 530–2
rearrange strategy, addition 11–12
reciprocal, fractions 210
rectangle, area 548–50
recurring decimal 309
reflections 674, 680–3
  Cartesian plane 682–3
  mirror lines 680–2
reflex angle 461
reliability, of data 763
remainder 35
repeating decimals 309–10
right angle 461
right-angled triangle 468
rotating points 621
rotational symmetry 669–70
rotations 674, 687–91
rounding decimals 307–8
rounding integers
  first or leading digit 41–2
  nearest 10 41
  nearest 100 41
rule
  creating sequence from 620
  identifying 620
  number pattern, determination of 620

S

sample space 723–4
scale, measuring length 530–2
scalene triangle 468
scatter plot, interpretation 633
secondary data 762–3
secret numbers 407
sector graphs 795
  drawing by hand 796
  drawing using technology 797–800
short division algorithm 35–7
side elevation, drawing solids 578
side view, drawing solids 578
simple probability 728–31
simplifying fractions 184–5
  mixed numbers 188–90
sketching quadrilaterals 483
solving equations
  backtracking 410–13
  balancing 418–20
  guess, check and improve 400–1
  inverse operations 417–22, 426
  making pronumerals positive 422
sorting, multiples and factors 120
split strategy, addition 10–11
square numbers 141–2
square roots 142–5
squaring decimals 320–1
stem-and-leaf plots 789–93
straight angle 461
substitution
  algebra 360
  equations 426–7
subtraction
  decimals 314
  fractions 194–8
  integers 86–8
  mixed numbers 215–18
  positive integers
    algorithms 18–21
    compensation strategy 14
    decomposition 19–21
    find the difference 13–14
    jump strategy 12–13
    with borrowing 19
    with no borrowing 18
successful trial 734
successive discounts 284
sum 16
supplementary angles 490
> symbol 6
< symbol 6

T

tangrams 501
term 619
terminating decimal 309
theoretical probability 728
  vs. experimental probability 731
top view, drawing solids 578
transformations 674–6
  combined transformations, in Cartesian plane 692–3
  line and rotational symmetry 668–70
  reflections 680–3
  rotations 687–91
  translations 674–6
translations 674–6, 680
  combining 676
transversal parallel lines 491
travel graphs 636–7
trial 734
  successful 734
triangles 467
  area 550–2
  classification 468–70
  interior and exterior angles 472–3
  naming triangles 467–70
two-step experiment 725
two-way tables 724–5

U

unit price 278–9
unitary method 278
  best buys 278–80
  percentages 279–80
units of length
  converting 524–5
  metric 523–4
units of measurement
  converting units of length 524–5
  metric units of length 523–4
unlike terms, algebra 364

V

value 274
variables 759
vertically opposite angles 489, 492
vinculum 173
volume 564–5
  rectangular prisms 564–7

W

whole numbers 70
  decimals 294–8
  dividing a decimal 325–6
  multiplying fractions 202–3
  short cut, percentages 238
  subtracting fractions 197
writing number sentences 6

X

x-axis 611

Y

y-axis 611