


7

ESSENTIAL MATHEMATICS

FOR THE AUSTRALIAN CURRICULUM

SECOND EDITION

DAVID GREENWOOD | BRYN HUMBERSTONE
JUSTIN ROBINSON | JENNY GOODMAN
JENNIFER VAUGHAN | STUART PALMER

CAMBRIDGE UNIVERSITY PRESS

Essential Mathematics for the Australian Curriculum Year 7 2ed

ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

CAMBRIDGE
UNIVERSITY PRESS

University Printing House, Cambridge CB2 8BS, United Kingdom

One Liberty Plaza, 20th Floor, New York, NY 10006, USA

477 Williamstown Road, Port Melbourne, VIC 3207, Australia

4843/24, 2nd Floor, Ansari Road, Daryaganj, Delhi – 110002, India

79 Anson Road, #06–04/06, Singapore 079906

Cambridge University Press is part of the University of Cambridge.

It furthers the University's mission by disseminating knowledge in the pursuit of education, learning and research at the highest international levels of excellence.

www.cambridge.org
Information on this title: www.cambridge.org/9781107568822

First Edition © David Greenwood, Franca Frank, Jenny Goodman, Bryn Humberstone, Justin Robinson, Jennifer Vaughan 2010
Second Edition © David Greenwood, Bryn Humberstone, Justin Robinson, Jenny Goodman, Jennifer Vaughan 2015

This publication is in copyright. Subject to statutory exception and to the provisions of relevant collective licensing agreements, no reproduction of any part may take place without the written permission of Cambridge University Press.

First published 2010
Second Edition 2015
20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5

Cover designed by Sardine Design
Typeset by diacriTech
Printed in China by C & C Offset Printing Co. Ltd.

A Cataloguing-in-Publication entry is available from the catalogue of the National Library of Australia at www.nla.gov.au

ISBN 978-1-107-56882-2 Paperback

Additional resources for this publication at www.cambridge.edu.au/hotmaths

Reproduction and communication for educational purposes
The Australian *Copyright Act 1968* (the Act) allows a maximum of one chapter or 10% of the pages of this publication, whichever is the greater, to be reproduced and/or communicated by any educational institution for its educational purposes provided that the educational institution (or the body that administers it) has given a remuneration notice to Copyright Agency Limited (CAL) under the Act.

For details of the CAL licence for educational institutions contact:

Copyright Agency Limited
Level 15, 233 Castlereagh Street
Sydney NSW 2000
Telephone: (02) 9394 7600
Facsimile: (02) 9394 7601
Email: info@copyright.com.au

Reproduction and communication for other purposes
Except as permitted under the Act (for example a fair dealing for the purposes of study, research, criticism or review) no part of this publication may be reproduced, stored in a retrieval system, communicated or transmitted in any form or by any means without prior written permission. All inquiries should be made to the publisher at the address above.

Cambridge University Press has no responsibility for the persistence or accuracy of URLS for external or third-party internet websites referred to in this publication, and does not guarantee that any content on such websites is, or will remain, accurate or appropriate. Information regarding prices, travel timetables and other factual information given in this work is correct at the time of first printing but Cambridge University Press does not guarantee the accuracy of such information thereafter.

Disclaimer
All material identified by  is material subject to copyright under the Copyright Act 1968 (Cth) and is owned by the Australia Curriculum, Assessment and Reporting Authority 2015.

Table of contents

About the authors *ix*
Introduction and overview of this series *x*
Working with unfamiliar problems *xiv*

1 Whole numbers **2**

Number and Algebra

Number and place value

1A	Numbers systems EXTENDING	4
1B	Place value CONSOLIDATING	9
1C	Addition and subtraction	13
1D	Addition and subtraction algorithms	18
1E	Multiplication	23
1F	Multiplying larger numbers	28
	Progress quiz	32
1G	Division	33
1H	Estimating and rounding CONSOLIDATING	38
1I	Order of operations	42
	Investigation	46
	Problems and challenges	48
	Chapter summary	49
	Review: Multiple-choice questions	50
	Short-answer questions	50
	Extended-response questions	52

2 Geometry **54**

Measurement and Geometry

Geometric reasoning

2A	Points, lines and angles CONSOLIDATING	56
2B	Measuring angles CONSOLIDATING	62
2C	Angles at a point	68
	Progress quiz	74
2D	Transversal lines and parallel lines	75
2E	Problems with parallel lines EXTENDING	83
2F	Circles and constructions	88
2G	Dynamic geometry	92
	Investigation	95
	Problems and challenges	96
	Chapter summary	97
	Review: Multiple-choice questions	98
	Short-answer questions	99
	Extended-response questions	102

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



3 Number properties and patterns 104

Number and Algebra

Number and place value

Linear and non-linear relationships

3A	Factors and multiples CONSOLIDATING	106
3B	Highest common factor and lowest common multiple CONSOLIDATING	111
3C	Divisibility EXTENDING	115
3D	Prime numbers	120
3E	Powers	123
3F	Prime decomposition	129
	Progress quiz	133
3G	Squares and square roots	134
3H	Number patterns CONSOLIDATING	139
3I	Spatial patterns	145
3J	Tables and rules	153
3K	The number plane and graphs	158
	Investigation	164
	Problems and challenges	165
	Chapter summary	167
	Review: Multiple-choice questions	169
	Short-answer questions	170
	Extended-response questions	172

4 Fractions and percentages 174

Number and Algebra

Real numbers

Money and financial mathematics

4A	What are fractions? CONSOLIDATING	176
4B	Equivalent fractions and simplified fractions	182
4C	Mixed numbers CONSOLIDATING	188
4D	Ordering fractions	194
4E	Adding fractions	199
4F	Subtracting fractions	206
4G	Multiplying fractions	212
4H	Dividing fractions	220
	Progress quiz	226
4I	Fractions and percentages	227
4J	Percentage of a number	232
4K	Expressing a quantity as a proportion	237
	Investigation	242
	Problems and challenges	244
	Chapter summary	245
	Review: Multiple-choice questions	246
	Short-answer questions	247
	Extended-response questions	249

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 Algebra 250

Number and Algebra

Patterns and algebra

5A	Introduction to algebra	252
5B	Substituting and evaluating	257
5C	Equivalent expressions	262
5D	Like terms	266
	Progress quiz	270
5E	Multiplying and dividing expressions	271
5F	Expanding brackets EXTENDING	276
5G	Algebraic modelling EXTENDING	282
	Investigation	287
	Problems and challenges	289
	Chapter summary	290
	Review: Multiple-choice questions	291
	Short-answer questions	291
	Extended-response questions	293

6 Decimals 294

Number and Algebra

Real numbers

Money and financial mathematics

6A	Decimals and place value CONSOLIDATING	296
6B	Rounding decimals	301
6C	Addition and subtraction of decimals CONSOLIDATING	306
6D	Multiplying and dividing by powers of 10	310
6E	Multiplication of decimals	316
6F	Division of decimals	320
	Progress quiz	325
6G	Decimals and fractions	326
6H	Decimals and percentages	331
	Investigation	336
	Problems and challenges	339
	Chapter summary	340
	Review: Multiple-choice questions	341
	Short-answer questions	341
	Extended-response questions	343

Semester review 1 344

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 Negative numbers 354

Number and Algebra

Number and place value

Linear and non-linear relationships

7A	Integers CONSOLIDATING	356
7B	Adding and subtracting positive integers	360
7C	Adding and subtracting negative integers	364
7D	Multiplication and division of integers EXTENDING	369
	Progress quiz	373
7E	Order of operations EXTENDING	374
7F	Substituting integers EXTENDING	378
7G	The number plane	381
	Investigation	386
	Problems and challenges	387
	Chapter summary	388
	Review: Multiple-choice questions	389
	Short-answer questions	390
	Extended-response questions	391

8 Statistics and probability 392

Statistics and Probability

Chance

Data representation and interpretation

Number and Algebra

Linear and non-linear relationships

8A	Collecting and classifying data	394
8B	Summarising data numerically	401
8C	Dot plots and column graphs	406
8D	Line graphs	416
8E	Stem-and-leaf plots	423
8F	Pie charts and divided bar graphs EXTENDING	431
	Progress quiz	437
8G	Describing chance CONSOLIDATING	439
8H	Theoretical probability	445
8I	Experimental probability EXTENDING	451
	Investigation	456
	Problems and challenges	457
	Chapter summary	458
	Review: Multiple-choice questions	459
	Short-answer questions	460
	Extended-response questions	463

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 Polygons, solids and transformations 464

Measurement and Geometry

Location and transformation
Geomentric reasoning
Shape

9A	Polygons	466
9B	Triangles	471
9C	Constructing triangles EXTENDING	475
9D	Triangle angle sum	480
9E	Quadrilaterals	486
9F	Quadrilateral angle sum	490
	Progress quiz	494
9G	Symmetry	496
9H	Reflection and rotation	501
9I	Translation	509
9J	Drawing solids	514
9K	Nets and the Platonic solids EXTENDING	519
	Investigation	525
	Problems and challenges	526
	Chapter summary	527
	Review: Multiple-choice questions	528
	Short-answer questions	529
	Extended-response questions	531

10 Equations 532

Number and Algebra

Linear and non-linear relationships

10A	Introduction to equations	534
10B	Solving equations by inspection CONSOLIDATING	539
10C	Equivalent equations	543
10D	Solving equations algebraically	548
10E	Equations with fractions EXTENDING	556
	Progress quiz	561
10F	Equations with brackets EXTENDING	562
10G	Formulas	566
10H	Applications	570
	Investigation	575
	Problems and challenges	576
	Chapter summary	578
	Review: Multiple-choice questions	579
	Short-answer questions	580
	Extended-response questions	581

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 Measurement 582

11A	Measurement systems EXTENDING	584
11B	Using and converting metric lengths CONSOLIDATING	590
11C	Perimeter CONSOLIDATING	594
11D	Areas and rectangles	599
11E	Area of a triangle	605
11F	Area of a parallelogram	611
11G	Area of composite shapes EXTENDING	616
	Progress quiz	621
11H	Volume of rectangular prisms	623
11I	Capacity CONSOLIDATING	629
11J	Mass and temperature CONSOLIDATING	634
	Investigation	640
	Problems and challenges	642
	Chapter summary	643
	Review: Multiple-choice questions	644
	Short-answer questions	645
	Extended-response questions	647

Semester review 2 648

Answers *657*

Measurement and Geometry

Using units of measurements

Shape

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

About the Authors



David Greenwood is the Head of Mathematics at Trinity Grammar School in Melbourne and has 21 years' experience teaching mathematics from Years 7 to 12. He has run numerous workshops within Australia and overseas regarding the implementation of the Australian Curriculum and the use of technology for the teaching of mathematics. He has written more than 20 mathematics titles and has a particular interest in the sequencing of curriculum content and working with the Australian Curriculum proficiency strands.



Bryn Humberstone graduated from University of Melbourne with an Honours degree in Pure Mathematics, is currently teaching both junior and senior mathematics in Victoria and is the Head of Mathematics (Senior School) at Caulfield Grammar School Wheelers Hill. Bryn is particularly passionate about writing engaging mathematical investigations and effective assessment tasks for students with a variety of backgrounds and ability levels.




Justin Robinson is the inaugural Director of the Institute of Positive Education, based at Geelong Grammar School, where he leads a team of staff dedicated to promoting the theory and practice of Positive Education. Prior to this, he spent 20 years teaching mathematics, covering all levels of secondary education and with significant experience teaching VCE, IB and A-Levels. Justin is passionate about challenging students within a safe learning environment and instils in his students a growth mindset. He has a keen interest in promoting student engagement through a wide variety of effective teaching methods and materials.



Jenny Goodman has worked for 20 years in comprehensive state and selective high schools in New South Wales and has a keen interest in teaching students of differing ability levels. She was awarded the Jones Medal for education at Sydney University and the Bourke prize for Mathematics. She has written for Cambridge NSW and was involved in the Spectrum and Spectrum Gold series.



Jennifer Vaughan has taught secondary mathematics for over 30 years in New South Wales, Western Australia, Queensland and New Zealand and has tutored and lectured in mathematics at Queensland University of Technology. She is passionate about providing students of all ability levels with opportunities to understand and to have success in using mathematics. She has taught special needs students and has had extensive experience in developing resources that make mathematical concepts more accessible; hence, facilitating student confidence, achievement and an enjoyment of maths.



Stuart Palmer has been a head of department in two schools and is now an educational consultant who conducts professional development workshops for teachers all over New South Wales and beyond. He is a Project Officer with the Mathematical Association of New South Wales, and also works with pre-service teachers at The University of Sydney and The University of Western Sydney.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Introduction

This second edition of *Essential Mathematics for the Australian Curriculum* has been developed into a complete resources pack comprising a revised and updated print textbook, a new interactive textbook with a host of cutting-edge features, and an online teaching suite.

The successful elements of the first edition have been retained and improved upon. These include:

- logical sequencing of chapters and development of topics
- careful structuring of exercises according to the four Australian Curriculum proficiency strands (Understanding, Fluency, Problem-solving, Reasoning) plus Enrichment
- graduated difficulty of exercise questions within the overall exercise and within proficiency groups
- *Let's Start* and *Key Ideas* to help introduce concepts and key skills.

Additions and revisions to the text include:

- new topics reflecting updates to the Australian Curriculum and state syllabuses
- Revision and Extension topics marked as 'Consolidating' or 'Extending' to help customise the course to the needs of each classroom
- working programs embedded in each exercise to differentiate three student pathways: Foundation, Standard and Advanced
- 'Progress quiz' placed approximately two-thirds of the way into each chapter, allowing students to check and consolidate their learning – in time to address misunderstandings or weaknesses prior to completing the chapter
- pre-tests revised and moved to the interactive textbook.

Features of the all-new interactive textbook:

- seamlessly blended with Cambridge *HOTmaths*, allowing enhanced learning opportunities in blended classrooms, revision of previous years' work, and access to *Scorcher*
- all worked examples linked to a high-quality video demonstration, supporting both in-class learning and the 'flipped classroom'
- searchable dictionary of mathematical terms and pop-up definitions in the text
- hundreds of interactive widgets, walkthroughs and games
- automatically-marked quizzes and assessment tests, with saved scores
- printable worksheets (HOTsheets) suitable for homework or class group work.

Features of the online teaching suite, also powered by Cambridge *HOTmaths*:

- test generator, with ready-made tests
- printable worked solutions for all questions
- powerful learning management system with task-setting, progress-tracking and reporting functions.

The information on the next pages shows how the components of this resource are integrated.


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Guide to the working programs

The working programs that were previously available in separate supporting documents have been updated, refined and subtly embedded in the exercises for this second edition of *Essential Mathematics for the Australian Curriculum*. The suggested working programs provide three pathways through the course to allow differentiation for Foundation, Standard and Advanced students.

As with the first edition, each exercise is structured in subsections that match the four Australian Curriculum proficiency strands (Understanding, Fluency, Problem-solving and Reasoning) as well as Enrichment (challenge). The questions* suggested for each pathway are listed in three columns at the top of each subsection.

- The left column (lightest shaded colour) is the Foundation pathway
- The middle column (medium shaded colour) is the Standard pathway
- The right column (darkest shaded colour) is the Advanced pathway.



Gradients within exercises and proficiency strands

The working programs make use of the gradients that have been carefully and considerately written into the exercises.

A gradient runs through the overall structure of each exercise – where there is an increasing level of mathematical sophistication required from Understanding through to Reasoning and Enrichment – but also within each proficiency strand; the first few questions in Fluency, for example, are easier than the last few, and the last Problem-solving question is more challenging than the first Problem-solving question.

The right mix of questions

Questions in the working programs are selected to give the most appropriate mix of types of questions for each learning pathway. Students going through the Foundation pathway will likely need more practice at Understanding and Fluency, but should also attempt the easier Problem-solving and Reasoning questions. An Advanced student will likely be able to skip the Understanding questions, proceed through the Fluency questions (often half of each question), focus on the Problem-solving and Reasoning questions, and have a go at the Enrichment question. A Standard student would do a mix of everything.

Choosing a pathway

There are a variety of ways of determining the appropriate pathway for students through the course, including using the chapter Pre-tests (now found online). Schools and individual teachers should follow the method that works for them.

For schools that have ability grouping of classes, teachers may wish to set one of the Foundation, Standard or Advanced pathways as their default setting for their entire class and then make individual alterations depending on student need. For schools that have mixed-ability classes, teachers may wish to set a number of pathways within the one class depending on previous performance and other factors.

* The nomenclature used to list questions is as follows:

- 3, 4: complete all parts of questions 3 and 4
- 1-4: complete all parts of questions 1, 2, 3 and 4
- 10(½): complete half of the parts from question 10 (a, c, e, ... or b, d, f, ...)
- 2-4(½): complete half of the parts of questions 2, 3 and 4
- 4(½), 5: complete half of the parts of question 4 and all parts of question 5
- — : complete none of the questions in this section.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


An overview of the *Essential Mathematics for the Australian Curriculum* complete learning suite

For more detail, see the guide in the online Interactive Textbook

All non-core topics are marked Consolidating or Extending to assist with course planning

Examples with fully worked solutions and explanations show the thinking behind each step

PRINT TEXTBOOK



- Investigations
- Problems and challenges
- Chapter summaries
- Chapter reviews
- Answers
- 'Working with unfamiliar problems' poster


Each topic in the print book comes with interactive *HOTmaths* widgets, walkthroughs and HOTsheets in the interactive textbook

Key ideas summarise key knowledge and skills for each lesson

Let's start activities get students thinking critically and creatively about the topic

Working programs subtly embedded in each Proficiency Strand to provide three learning pathways through the book

PDF TEXTBOOK



Downloadable

Included with print textbook and interactive textbook

Note-taking

Search functions

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Easy navigation within sections without scrolling


Walkthroughs, Scorcher and levelled question sets in every section

Interactive navigation and searching

Tasks sent by teacher

Access to interactive resources at any time without leaving the page

Hundreds of interactive widgets



INTERACTIVE TEXTBOOK POWERED BY *HOTmaths*


Online tests sent by teacher

Video demonstration for every worked example

Student reporting

Class reporting

Access to all *HOTmaths* Australian Curriculum courses



Teacher's copy of interactive textbook

Test generator and ready-made tests

Student results

Printable chapter tests and worksheets

ONLINE TEACHING SUITE POWERED BY *HOTmaths*

Plus:
- worked solutions
- teaching program
- curriculum grids

and more


Essential Mathematics for the Australian Curriculum Year 7 2ed

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Working with unfamiliar problems: Part 1

The questions on the next four pages are designed to provide practice in solving unfamiliar problems. Use the 'Working with unfamiliar problems' poster at the back of this book to help you if you get stuck.

In Part 1, apply the suggested strategy to solve these problems, which are in no particular order. Clearly communicate your solution and final answer.



1 How many diagonals exist for a 7-sided regular polygon? How many diagonals can be drawn from one vertex of a 30-sided regular polygon?


2 Find the value of 11111111 squared.

3 Find the sum of the first 25 odd numbers.



4 Five students have entered a race. How many different arrangements are there for first, second and third place, given that nobody ties?


5 Arrange all the digits 1, 2, 3, 4 and 5 into the form $\square\square\square \times \square\square$ so that the 3-digit number multiplied by the 2-digit number gives the largest possible answer.



6 A tree surgeon charges $15 to cut a log into 4 pieces. How much would he charge, at the same rate, to cut a log into 99 pieces?

7 How many 2-digit numbers can be written using only the digits 0, 1, 2, 3 or 4 with no repetition?

8 An 8-sided star is formed by drawing an equilateral triangle on each side of a square. Find the obtuse angle formed by adjacent sides of the star.



9 Approximately how many planes are needed to carry 76 819 people if each plane holds 289 people? Give your answer to the nearest 10 planes.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press



10 How many times does the word 'the' appear in this book?


11 Approximately how far would you have walked, in km, after walking 10 000 steps?

12 Insert operation signs between the digits 1 2 3 4 5 6 7 8 9 to make an answer of 100. The digits must be kept in ascending order.

- **a** Use any of the four operations and keep the digits separate.
- **b** Use only + or – and digits may be combined to form a 2- or 3-digit number.



13 A glass fish tank is a rectangular prism of width 40 cm and length 1 m. A scale is to be marked on the side of the tank showing 10-litre increases in volume. How far apart should the scale markings be? If the tank is to hold 280 litres of water and 5 cm height is allowed above the water level, what is the height of the fish tank?



14 Divide $410 between Bob, Zara and Ahmed so that Bob gets $40 more than Zara and Zara has $20 more than Ahmed.

15 A sailor has a cat, a mouse and a chunk of cheese that he needs to get across the lake in his boat. The boat is very small and it can only hold the sailor and one passenger, or the cheese, at a time. The other problem the sailor faces is that if he leaves the mouse and the cat alone, the cat will eat the mouse and if he leaves the cheese with the mouse alone, the cheese will get eaten. How many trips are needed for the sailor, the cat, the mouse and the cheese to arrive safely on the other side of the lake?



16 Ethan takes 6 days to paint a house, Jack takes 8 days to paint a house and Noah takes 12 days to paint a house. Exactly how many days would it take to paint a house if all three of them worked together?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Working with unfamiliar problems: Part 2

For the questions in Part 2, again use the 'Working with unfamiliar problems' poster at the back of this book, but this time choose your own strategy (or strategies) to solve each problem. Clearly communicate your solution and final answer.

1 Maddie remembered her friend's house number has two digits and that they added to 8. In ascending order, list the possible house numbers that fit this description given that there are less than 100 houses in this street.



2 Find the smaller angle between the big hand and little hand of a clock at 2 pm and also at 7:10 am.

3 Find each 2-digit number, from 12 to 40, that has the sum of its factors greater than double the number.

4 Using grid paper, draw all the possible different arrangements of 5 equally sized connecting squares. Rotations and reflections don't count as separate arrangements. Which of your arrangements would fold up to make an open box? Mark the base square for these arrangements.

5 How many prime numbers are less than 100?

6 At the end of a soccer match, each member of the two teams of 11 players wishes to shake hands with everyone else who played. How many handshakes are needed?



7 What is the smallest number that has each of the digits 1 to 9 as a factor?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 A game involves rolling two 8-sided dice. The numbers shown on both dice are 1 to 8 inclusive. How many different totals are possible in this game?



9 What is the 2014th digit in the number $\frac{4}{7}$?

10 Approximately how many 20 cent coins are needed so when placed next to each other they cover a 1-metre square? Give your answer to the nearest 100. What is their value in $?

11 A triangle has one angle double the smallest angle and the other angle 25° less than double the smallest angle. Find the size of the smallest angle in this triangle.

12 What is the last digit in the number 3^{203}?

13 Find the interior angle sum of a 42-sided regular polygon.

14 How many palindromic numbers are there that are more than 100 and less than 1000. (A palindrome is the same when written forwards and backwards.)




15 In a message that is written in secret code, what letter of the alphabet would likely be represented by the most common symbol in the message?

16 How many squares of any size are on a chess board?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 1

Whole numbers

What you will learn

1A Number systems (Extending)
1B Place value (Consolidating)
1C Addition and subtraction
1D Addition and subtraction algorithms
1E Multiplication
1F Multiplying larger numbers
1G Division
1H Estimating and rounding (Consolidating)
1I Order of operations

Australian curriculum

NUMBER AND ALGEBRA

Number and place value

Apply the associative, commutative and distributive laws to aid mental and written computation (ACMNA151) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Whole numbers in the ancient world and now

Whole numbers and number systems have been used for thousands of years to help count objects and record information.

In ancient Egypt in about 3000 BCE if one hundred and twenty-four blocks of stone were needed to build a monument, this number would have been represented as

Today we use whole numbers to help deal with all sorts of situations.

Here are some examples:

- Recording the number of points in a game
- Calculating the number of pavers required for a terrace
- Counting the number of items purchased at a shop
- Tallying the number of votes in an election
- Calculating the approximate distance between two towns.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1A Number systems EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Throughout the ages and in different countries, number systems were developed and used to help people count and communicate with numbers. From the ancient Egyptians to the modern day, different systems have used pictures and symbols to represent whole numbers. Some of the well-known number systems are the Egyptian, Babylonian, Roman, modern Chinese and the Hindu-Arabic or decimal system.



The Roman numerals on this stone show the distance to the next village.

Let's start: Count like a Roman

Here are the letters used in the Roman number system for some numbers that you know.

Number	1	2	3	4	5	6	7	8	9	10	50	100
Roman numerals	I	II	III	IV	V	VI	VII	VIII	IX	X	L	C

- What numbers do you think XVII and XIX represent?
- Can you write the numbers 261 and 139 using Roman numerals?

Key ideas

Egyptian number system

- Records show that this number system was used from about 3000 BCE.
- **Hieroglyphics** were used to represent numbers.
- From about 1600 BCE hieroglyphics were used to represent groups of 10, 100, 1000 etc.
- Symbols of the same type were grouped in twos or threes and arranged vertically.

Number	1	10	100	1000	10 000	100 000	1 000 000
Hieroglyphic							
Description	Stick or staff	Arch or heel bone	Coil of rope	Lotus flower	Bent finger or reed	Tadpole or frog	Genie

- Examples:

3 5 21 342

- Note that the hieroglyphics with the larger value are written in front (i.e. on the left).
- There was no symbol for the number zero.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

Babylonian number system

- From about 1750 BCE the ancient Babylonians used a very sophisticated number system and its origins have been traced to about 3000 BCE.
- Symbols called **cuneiform** (wedge shapes) were used to represent numbers.
- The symbols were written into clay tablets, which were then allowed to dry in the Sun.
- The number system is based on the number 60, but a different wedge shape was used to represent groups of 10.



The Hanging Gardens of Babylon, built for his wife by King Nebuchadnezzar II around 600 BCE, were one of the seven wonders of the ancient world.

- The system is positional in that the position of each wedge shape helps determine its value. So ▼▼ means 2 but ▼ ◀▼ means 62.

Number	1	10	60
Symbol	▼	◀	▼
Description	Upright wedge shape	Sideways wedge	Upright wedge shape

- To represent zero, they used a blank space or sometimes a small slanted wedge shape for zeros inside a number.
- Examples:

5 ▼▼▼ 11 ◀▼ 72 ▼ ◀▼▼ 121 ▼▼ ▼

Roman number system

- Some capital letters are used and are called Roman numerals.
- The Roman number system was developed in about the third century BCE and remained the dominant system in many parts of the world until about the Middle Ages. It is still used today in many situations.
- A smaller letter value to the left of a larger letter value indicates subtraction. For example, IV means 5 – 1 = 4 and XC means 100 – 10 = 90. Only one letter can be placed to the left for subtraction. Is, Xs and Cs are the numerals that can be used to reduce the next two larger numerals. So X, for example, can be used to reduce L and C but not D.

Number	1	5	10	50	100	500	1000
Symbol	I	V	X	L	C	D	M

- Examples:

2	4	21	59	90
II	IV	XXI	LIX	XC

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Using ancient number systems

Write each of the numbers 3, 15 and 144 using the given number systems.

a Egyptian **b** Babylonian **c** Roman

SOLUTION

a 3 

15 

144 

b 3 

15 

144 

c 3 III

15 XV

144 CXLIV

EXPLANATION

 means 1

 means 10

 means 100

 means 1

 means 10

 means 60

I means 1

V means 5
X means 10

C means 100
XL means 40
IV means 4

Exercise 1A

1–3 | 3 | —

UNDERSTANDING

1 Which number system uses these symbols?

a cuneiform (wedge shapes), e.g. 

b capital letters, e.g. V and L

c hieroglyphics (pictures), e.g.  and 

2 Draw the symbols used in these number systems for the given numbers.

a Egyptian

i 1 **ii** 10 **iii** 100 **iv** 1000

b Babylonian

i 1 **ii** 10 **iii** 60

c Roman

i 1 **ii** 5 **iii** 10 **iv** 50 **v** 100

3 In the Roman system, IV does not mean 1 + 5 to give 6. What do you think it means?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1A

4, 5 | 4–6 | 4–6(½)

FLUENCY

Example 1

4 Write these numbers using the given number systems.

a Egyptian

i 3 **ii** 21 **iii** 114 **iv** 352

b Babylonian

i 4 **ii** 32 **iii** 61 **iv** 132

c Roman

i 2 **ii** 9 **iii** 24 **iv** 156

5 What number do these groups of symbols represent?

a Egyptian

i  **ii**  **iii**  **iv** 

b Babylonian

i  **ii**  **iii**  **iv** 

c Roman

i IV **ii** VIII **iii** XVI **iv** XL

6 Work out the answer to each of these problems. Write your answer using the same number system that is given in the question.

a XIV + XXII

b 

c 

d DCLXIX + IX

7, 8 | 8–10 | 8–10

PROBLEM-SOLVING

7 In ancient Babylon, a person adds goats to another group of  .
How many goats are there in total? Write your answer using the Babylonian number system.

8 An ancient Roman counts the number of people in three queues. The first queue has XI, the second has LXII and the third has CXV. How many people are there in total? Write your answer using the Roman number system.



9 One Egyptian house is made from  stones and a second house is made from stones.
How many more stones does the first house have? Write your answer using the Egyptian number system.

10 Which number system (Egyptian, Babylonian or Roman) uses the least number of symbols to represent these numbers?

a 55 **b** 60 **c** 3104

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

1A

11(½) | 11(½), 12 | 11(½), 12, 13

REASONING

11 In the Roman system Is, Xs and Cs are used to reduce either of the next two larger numerals. So 9 is IX, not VIIII; and 49 is XLIX, not IL.
Also, only one numeral can be used to reduce another number. So 8 is VIII, not IIX.
Write these numbers using Roman numerals.

a 4	**b** 9	**c** 14	**d** 19
e 29	**f** 41	**g** 49	**h** 89
i 99	**j** 449	**k** 922	**l** 3401

12 The Egyptian system generally uses more symbols than the other systems described here. Can you explain why? How many symbols are used for the number 999?

13 In the Babylonian system ▼ stands for 1, but because they did not use a symbol for zero at the end of a number, it also represents 60. People would know what it meant, depending on the situation it was used. Here is how it worked for large numbers. The dots represent empty spaces.

1	60	3600
▼	▼ ……	▼ …… ……

a Write these numbers using the Babylonian system.

i 12 **ii** 72 **iii** 120 **iv** 191 **v** 3661 **vi** 7224

b Can you explain why ▼ …… …… represents 3600?

c What would ▼ …… …… …… represent?

Other number systems

— | — | 14

ENRICHMENT

14 Other well-known number systems include:

i Mayan
ii modern Chinese
iii ancient Greek.

Look up these number systems on the internet or in other books. Write a brief sentence covering the points below.

a When and where the number systems were used.
b What symbols were used?
c Examples of numbers using these symbols.



An ancient Mayan carving.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1B Place value CONSOLIDATING


Interactive

Widgets

HOTsheets

Walkthroughs

The commonly used number system today, called the decimal system or base 10, is also called the Hindu-Arabic number system. Like the Babylonian system, the value of the digit depends on its place in the number, but only one digit is used in each position. A digit for zero is also used. The decimal system originated in ancient India about 3000 BCE and spread throughout Europe through Arabic texts over the next 4000 years.



The famous 'Histoire de la Mathematique', a French document showing the history of the Hindu-Arabic number system over thousands of years.

Let's start: Largest and smallest

Without using decimal points, repeated digits or a zero (0) at the start of a number, see if you can use all the digits 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 to write down:

- the largest possible number
- the smallest possible number.

Can you explain why your numbers are, in fact, the largest or smallest possible?

Key ideas

- The Hindu-Arabic or **decimal system** uses base 10. This means powers of 10 (1, 10 or 10^1, 100 or 10^2, 1000 or 10^3, ...) are used to determine the place value of a digit in a number.
- The symbols 0, 1, 2, 3, 4, 5, 6, 7, 8 and 9 are called **digits**.
- The value of each digit depends on its place in the number. The **place value** of the digit 2 in the number 126, for example, is 20.
- $3 \times 1000 + 2 \times 100 + 5 \times 10 + 4 \times 1$ (or $3 \times 10^3 + 2 \times 10^2 + 5 \times 10^1 + 4 \times 1$) is said to be the **expanded form** of the **basic numeral** 3254.

thousands hundreds tens ones

$3\ 2\ 5\ 4 = 3 \times 1000 + 2 \times 100 + 5 \times 10 + 4 \times 1$

expanded form

- Symbols used to compare numbers include the following.

= (is equal to)	$1 + 3 = 4$	or	$10 - 7 = 3$
≠ (is not equal to)	$1 + 3 \neq 5$	or	$11 + 38 \neq 50$
> (is greater than)	$5 > 4$	or	$100 > 37$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

≥ (is greater than or equal to)	$5 \geq 4$	or	$4 \geq 4$
< (is less than)	$4 < 5$	or	$13 < 26$
≤ (is less than or equal to)	$4 \leq 5$	or	$4 \leq 4$
≈ or ≒ (is approximately equal to)	$4.02 \approx 4$	or	$8997 \fallingdotseq 9000$

Example 2 Finding place value

Write down the place value of the digit 4 in these numbers.

a 437 **b** 543 910

SOLUTION	EXPLANATION
a $4 \times 100 = 400$	4 is worth 4×100 3 is worth 3×10 7 is worth 7×1
b $4 \times 10\,000 = 40\,000$	5 is worth $5 \times 100\,000$ 4 is worth $4 \times 10\,000$ 3 is worth 3×1000 9 is worth 9×100 1 is worth 1×10

Example 3 Writing in expanded form

Write 517 in expanded form.

SOLUTION	EXPLANATION
$517 = 5 \times 100 + 1 \times 10 + 7 \times 1$	Write each digit separately and multiply by the appropriate power of 10.



Place value is very important, such as in a bank cheque.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 1B

1–3 | 3 | —

UNDERSTANDING

1 Choose one of the words 'ones', 'tens', 'hundreds' or 'thousands' to describe each number.

a 100 **b** 1000 **c** 10 **d** 1

2 Write down these numbers using digits.

a two hundred and sixty-three
b seven thousand four hundred and twenty-one
c thirty-six thousand and fifteen
d one hundred thousand and one

3 Which symbol (next to the capital letters) matches the given words?

A = **B** ≠ **C** > **D** ≥
E < **F** ≤ **G** ≈

a is not equal to **b** is less than **c** is greater than or equal to
d is equal to **e** is greater than **f** is less than or equal to
g is approximately equal to

4–7(½) | 4–7(½), 8 | 4–8(½)

FLUENCY

Example 2

4 Write down the place value of the digit 7 in these numbers.

a 37 **b** 71 **c** 379 **d** 704
e 1712 **f** 7001 **g** 45 720 **h** 170 966

5 Write down the place value of the digit 2 in these numbers.

a 126 **b** 2143 **c** 91 214 **d** 1 268 804

6 State whether each of these statements is true or false.

a $5 > 4$ **b** $6 = 10$ **c** $9 \neq 99$ **d** $1 < 12$
e $22 \leq 11$ **f** $126 \leq 126$ **g** $19 \geq 20$ **h** $138 > 137$

Example 3

7 Write these numbers in expanded form.

a 17 **b** 281 **c** 935 **d** 20
e 4491 **f** 2003 **g** 10 001 **h** 55 555

8 Write these numbers, given in expanded form, as a basic numeral.

a $3 \times 100 + 4 \times 10 + 7 \times 1$
b $9 \times 1000 + 4 \times 100 + 1 \times 10 + 6 \times 1$
c $7 \times 1000 + 2 \times 10$
d $6 \times 100\,000 + 3 \times 1$
e $4 \times 1\,000\,000 + 3 \times 10\,000 + 7 \times 100$
f $9 \times 10\,000\,000 + 3 \times 1000 + 2 \times 10$

9 | 9(½), 10 | 10, 11

PROBLEM-SOLVING

9 Arrange these numbers from smallest to largest.

a 55, 45, 54, 44
b 729, 29, 92, 927, 279
c 23, 951, 136, 4
d 435, 453, 534, 345, 543, 354
e 12 345, 54 321, 34 512, 31 254
f 1010, 1001, 10 001, 1100, 10 100

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1B

PROBLEM-SOLVING

10 How many numbers can be made using the given digits? Digits are not allowed to be used more than once and all digits must be used.

a 2, 8 and 9 **b** 1, 6 and 7 **c** 2, 5, 6 and 7

11 You are given three different non-zero digits, for example; 2, 5 and 8. How many three digit numbers can be formed from your three given digits if digits can be used more than once?

REASONING

12 | 12 | 12, 13

12 The letters used here represent the digits of a number. Write each one in expanded form.

a *ab* **b** *abcd* **c** *a*0000*a*

13 By considering some of the other number systems (Egyptian, Babylonian or Roman) explained in the previous section, describe the main advantages of the Hindu-Arabic system.

ENRICHMENT

Large numbers and expanded form — | — | 14

14 It is convenient to write very large numbers in expanded form with index notation.
Here is an example.
$50\,000\,000 = 5 \times 10\,000\,000 = 5 \times 10^7$

a Explain why it is convenient to write large numbers in this type of expanded form.

b 3200 can also be written in the form 32×10^2. All the non-zero digits are written down and then multiplied by a power of 10. Similarly, write each of these numbers in the same way.

i 4100 **ii** 370 000 **iii** 21 770 000

c Write each of these numbers as basic numerals.

i 381×10^2 **ii** 7204×10^3 **iii** 1028×10^6

d Write these numbers in expanded form, just as you did in the examples above. Research them if you do not know what they are.

i 1 million **ii** 1 billion **iii** 1 trillion

iv 1 googol **v** 1 googolplex



In 2008 in Zimbabwe, bank notes were issued in trillions of dollars, but soon became worthless due to inflation.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1C Addition and subtraction









The process of finding the total value of two or more numbers is called addition. The words 'plus', 'add' and 'sum' are also used to describe addition.

The process for finding the difference between two numbers is called subtraction. The words 'minus', 'subtract' and 'take away' are also used to describe subtraction.



What's the difference in our heights?

Let's start: Your mental strategy


Many problems that involve addition and subtraction can be solved mentally without the use of a calculator or complicated written working.

Consider $98 + 22 - 31 + 29$


How would you work this out? What are the different ways it could be done mentally? Explain your method.

Key ideas

- The symbol + is used to show addition or find a sum.
  e.g. $4 + 3 = 7$



- $a + b = b + a$ e.g. $4 + 3 = 3 + 4$
  - This is the **commutative law** for addition, meaning that the order does not matter.
- $a + (b + c) = (a + b) + c$ e.g. $4 + (11 + 3) = (4 + 11) + 3$
  - This is called the associative law for addition, meaning that it does not matter which pair is added first.



- The symbol – is used to show subtraction or find a difference.
  e.g. $7 - 2 = 5$
- $a - b \neq b - a$ (in general ...) e.g. $4 - 3 \neq 3 - 4$
- $a - (b - c) \neq (a - b) - c$ e.g. $8 - (4 - 2) \neq (8 - 4) - 2$
- Mental addition and subtraction can be done using different strategies.
  - **Partitioning** (grouping digits in the same position)

$$171 + 23 = 100 + (70 + 20) + (1 + 3)$$
$$= 194$$

  - **Compensating** (making a 10, 100 etc. and then adjusting or compensating by adding or subtracting)

$$46 + 9 = 46 + 10 - 1$$
$$= 55$$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Doubling or halving** (making a double or half and then adjusting with addition or subtraction)

$$75 + 78 = 75 + 75 + 3 = 150 + 3 = 153 \qquad 124 - 61 = 124 - 62 + 1 = 62 + 1 = 63$$

Example 4 Mental addition and subtraction

Use the suggested strategy to mentally work out the answer.

a 132 + 156 (partitioning)
b 25 + 19 (compensating)
c 56 – 18 (compensating)
d 35 + 36 (doubling or halving)

SOLUTION	EXPLANATION
a 132 + 156 = 288	100 + 30 + 2 100 + 50 + 6 200 + 80 + 8
b 25 + 19 = 44	25 + 19 = 25 + 20 – 1 = 45 – 1 = 44
c 56 – 18 = 38	56 – 18 = 56 – 20 + 2 = 36 + 2 = 38
d 35 + 36 = 71	35 + 36 = 35 + 35 + 1 = 70 + 1 = 71

Exercise 1C

1–5 | 5 | — | UNDERSTANDING

1 **a** List three words that mean *addition*.
b List three words that mean *subtraction*.

2 Write the number which is:
a 3 more than 7
b 58 more than 11
c 7 less than 19
d 137 less than 157

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1C

UNDERSTANDING

3 **a** Find the sum of these pairs of numbers.
- **i** 2 and 6
- **ii** 19 and 8
- **iii** 62 and 70

b Find the difference between these pairs of numbers.
- **i** 11 and 5
- **ii** 29 and 13
- **iii** 101 and 93

4 State whether each of these statements is true or false.

a $4 + 3 > 6$ **b** $11 + 19 \geq 30$ **c** $13 - 9 < 8$

d $26 - 15 \leq 10$ **e** $1 + 7 - 4 \geq 4$ **f** $50 - 21 + 6 < 35$

5 Give the result for each of the following.

a 7 plus 11 **b** 22 minus 3

c the sum of 11 and 21 **d** 128 add 12

e 36 take away 15 **f** the difference between 13 and 4

6(½), 7–10 | 6–11(½) | 6–11(½)

FLUENCY

Example 4a

6 Mentally find the answers to these sums. Hint: Use the partitioning strategy.

a $23 + 41$ **b** $71 + 26$ **c** $138 + 441$

d $246 + 502$ **e** $937 + 11$ **f** $1304 + 4293$

g $140\,273 + 238\,410$ **h** $390\,447 + 201\,132$ **i** $100\,001 + 101\,010$

7 Mentally find the answers to these differences. Hint: Use the partitioning strategy.

a $29 - 18$ **b** $57 - 21$ **c** $249 - 137$

d $1045 - 1041$ **e** $4396 - 1285$ **f** $10101 - 100$

Example 4b

8 Mentally find the answers to these sums. Hint: Use the compensating strategy.

a $15 + 9$ **b** $64 + 11$ **c** $19 + 76$

d $18 + 115$ **e** $31 + 136$ **f** $245 + 52$

Example 4c

9 Mentally find the answers to these differences. Hint: Use the compensating strategy.

a $35 - 11$ **b** $45 - 19$ **c** $156 - 48$

d $244 - 22$ **e** $376 - 59$ **f** $5216 - 199$

Example 4d

10 Mentally find the answers to these sums and differences. Hint: Use the doubling or halving strategy.

a $25 + 26$ **b** $65 + 63$ **c** $121 + 123$

d $240 - 121$ **e** $482 - 240$ **f** $1006 - 504$

11 Mentally find the answers to these mixed problems.

a $11 + 18 - 17$ **b** $37 - 19 + 9$ **c** $101 - 15 + 21$

d $136 + 12 - 15$ **e** $28 - 10 - 9 + 5$ **f** $39 + 71 - 10 - 10$

g $1010 - 11 + 21 - 1$ **h** $5 - 7 + 2$ **i** $10 - 25 + 18$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1C

12–14 | 13–15 | 15–17

PROBLEM-SOLVING

12 Gary worked 7 hours on Monday, 5 hours on Tuesday, 13 hours on Wednesday, 11 hours on Thursday and 2 hours on Friday. What is the total number of hours that Gary worked during the week?

13 In a batting innings, Phil hit 126 runs and Mario hit 19 runs. How many more runs did Phil hit compared to Mario?




14 A farmer reduced his cattle numbers from 86 to 54. How many cows were taken away?



15 Bag A has 18 marbles and bag B has 7 fewer marbles than bag A. What is the total number of marbles?

16 Matt has 36 cards and Andy has 35 more cards than Matt. If they combine their cards, how many do they have in total?

17 Each side on a magic triangle adds up to the same number, as shown in this example with a sum of 12 on each side.




a Place each of the digits from 1 to 6 in a magic triangle with three digits along each side so that each side adds up to the given number.

i 9 **ii** 10

b Place each of the digits from 1 to 9 in a magic triangle with four digits along each side so that each side adds up to the given number.

i 20 **ii** 23



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

18 | 18, 19 | 19, 20

1C

REASONING


18 **a** The mental strategy of partitioning is easy to apply for 23 + 54 but harder for 23 + 59. Explain why.

b The mental strategy of partitioning is easy to apply for 158 – 46 but harder for 151 – 46. Explain why.

19 Complete these number sentences if the letters a, b and c represent numbers.

a $a + b = c$ so $c - __ = a$ **b** $a + c = b$ so $b - a = __$

20 This magic triangle uses the digits 1 to 6, and has each side adding to the same total. This example shows a side total of 9.



a How many different side totals are possible using the same digits?


b Explain your method.

Magic squares

— | — | 21, 22

ENRICHMENT

21 A magic square has every row, column and main diagonal adding to the same number, called the magic sum. For example, this magic square has a magic sum of 15.
Find the magic sums for these squares, then fill in the missing numbers.



a

6		
7	5	
2		

b

10		
	11	13
		12


c

15	20	
14		
19		

d

1	15		4
	6		9
		11	
13		2	16

22 The sum of two numbers is 87 and their difference is 29. What are the two numbers?



This magic square was known in ancient China as a 'Lo Shu' square and uses only the numbers 1 to 9. It is shown in the middle of this ancient design as symbols on a turtle shell, surrounded by the animals which represent the traditional Chinese names for the years.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

1D Addition and subtraction algorithms

Interactive

Widgets

HOTsheets

Walkthroughs

It is not always practical to solve problems involving addition and subtraction mentally. For more complex problems a procedure involving a number of steps can be used and this helps to give the answer. Such a procedure is called an algorithm.

For the addition algorithm, if two digits add to more than 9, then the higher place value digit in the sum can be carried to the next column.

For the subtraction algorithm, if two digits subtract to be less than 0, then a 1 can be borrowed from the next column to form an extra 10.

Let's start: The missing digits

Discuss what numbers should go in the empty boxes.
Give reasons for your answers.

$$\begin{array}{r} 1\,\square\,4 \\ +\,9\;5\;\square \\ \hline 1\,\square\,2\;5 \end{array} \qquad \begin{array}{r} \square\,5\,\square \\ -\,1\,\square\,4 \\ \hline 9\;4 \end{array}$$



Key ideas

- An **algorithm** is a procedure involving a number of steps that eventually leads to the answer to a problem.
- **Addition algorithm**
  - Arrange the numbers vertically so that the digits with similar place value are in the same column.
  - Add digits in the same column, starting on the right.
  - If the digits add to more than 9, carry the 10 to the next column.

$$\begin{array}{r} {}^{1}234 \\ 192 \\ \hline 426 \end{array} \qquad \begin{array}{l} 4+2=6 \\ 3+9=12 \\ 1+2+1=4 \end{array}$$

- **Subtraction algorithm**
  - Arrange the numbers vertically so that the digits with similar place value are in the same column.
  - Subtract digits in the same column top-down and starting on the right.
  - If the digits subtract to less than 0, borrow a 1 from the next column to form an extra 10.

$$\begin{array}{r} {}^{1}2\,{}^{1}59 \\ 1\;82 \\ \hline 77 \end{array} \qquad \begin{array}{l} 9-2=7 \\ 15-8=7 \\ 1-1=0 \end{array}$$

- Calculators may be used to check your answers.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 5 Using the addition algorithm

Give the result for each of these sums.

a
$$\begin{array}{r} 26 \\ +\,66 \\ \hline \end{array}$$

b
$$\begin{array}{r} 439 \\ +\,172 \\ \hline \end{array}$$

SOLUTION

a
$$\begin{array}{r} {}^{1}26 \\ +\,66 \\ \hline 92 \end{array}$$

b
$$\begin{array}{r} {}^{1}4{}^{1}39 \\ +\;1\;7\;2 \\ \hline 6\;1\;1 \end{array}$$

EXPLANATION

Add the digits vertically.

$6 + 6 = 12$, so carry the 1 to the tens column.

$9 + 2 = 11$, carry a 1 to the tens column.

$1 + 3 + 7 = 11$, so carry a 1 to the hundreds column.

Example 6 Using the subtraction algorithm

Give the result for each of these differences.

a
$$\begin{array}{r} 74 \\ -\,15 \\ \hline \end{array}$$

b
$$\begin{array}{r} 3240 \\ -\,2721 \\ \hline \end{array}$$

SOLUTION

a
$$\begin{array}{r} {}^{6}\not{7}{}^{1}4 \\ -\;1\;5 \\ \hline 5\;9 \end{array}$$

b
$$\begin{array}{r} {}^{2}\not{3}{}^{1}2\,{}^{3}\not{4}{}^{1}0 \\ -\;2\;7\;2\;1 \\ \hline 5\;1\;9 \end{array}$$

EXPLANATION

Borrow 1 from 7 to make $14 - 5 = 9$.

Then subtract 1 from 6 (not 7).

Borrow 1 from 4 to make $10 - 1 = 9$.

Subtract 2 from 3 (not 4).

Borrow 1 from 3 to make $12 - 7 = 5$.

Note that $2 - 2 = 0$ and you do not need to show a 0 before the 5.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 1D

1–3(½) | 3(½) | —

UNDERSTANDING

1 Mentally find the results to these simple sums.

a 8 + 9 **b** 87 + 14 **c** 138 + 6 **d** 99 + 11

e 998 + 7 **f** 19 + 124 **g** 102 + 99 **h** 52 + 1053

2 Mentally find the results to these simple differences.

a 13 – 5 **b** 36 – 9 **c** 75 – 8 **d** 100 – 16

e 37 – 22 **f** 104 – 12 **g** 46 – 17 **h** 1001 – 22

3 What is the missing number in these problems?

a
$$\begin{array}{r} 2\ 7 \\ +\ 3\ 1 \\ \hline 5\square \end{array}$$

b
$$\begin{array}{r} 3\ 6 \\ +\ 1\ 5 \\ \hline 5\square \end{array}$$

c
$$\begin{array}{r} 1\ 2\ 3 \\ +\ \ 9\ 1 \\ \hline 2\square 4 \end{array}$$

d
$$\begin{array}{r} 4\ 6 \\ +\ \square 4 \\ \hline 1\ 1\ 0 \end{array}$$

e
$$\begin{array}{r} 2\ 4 \\ -\ 1\square \\ \hline 1\ 2 \end{array}$$

f
$$\begin{array}{r} 6\ 7 \\ -\ 4\ 8 \\ \hline \square 9 \end{array}$$

g
$$\begin{array}{r} 1\ 6\ 2 \\ -\ \square 1 \\ \hline 8\ 1 \end{array}$$

h
$$\begin{array}{r} 1\ 4\square 2 \\ -\ 6\ 2\ 3 \\ \hline 8\ 0\ 9 \end{array}$$

4–5(½), 7–8(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 5

4 Give the answer to each of these sums. Check your answer with a calculator.

a
$$\begin{array}{r} 36 \\ +\ 51 \\ \hline \end{array}$$

b
$$\begin{array}{r} 74 \\ +\ 25 \\ \hline \end{array}$$

c
$$\begin{array}{r} 17 \\ +\ 24 \\ \hline \end{array}$$

d
$$\begin{array}{r} 47 \\ +\ 39 \\ \hline \end{array}$$

e
$$\begin{array}{r} 129 \\ +\ 97 \\ \hline \end{array}$$

f
$$\begin{array}{r} 458 \\ +\ 287 \\ \hline \end{array}$$

g
$$\begin{array}{r} 1041 \\ +\ 882 \\ \hline \end{array}$$

h
$$\begin{array}{r} 3092 \\ +\ 1988 \\ \hline \end{array}$$

5 Show your working to find the result for each of these sums.

a 85 + 76 **b** 131 + 94 **c** 1732 + 497 **d** 988 + 987

6 Give the result for each of these sums.

a
$$\begin{array}{r} 17 \\ 26 \\ +\ 34 \\ \hline \end{array}$$

b
$$\begin{array}{r} 126 \\ +\ 47 \\ +\ 19 \\ \hline \end{array}$$

c
$$\begin{array}{r} 152 \\ 247 \\ +\ 19 \\ \hline \end{array}$$

d
$$\begin{array}{r} 2197 \\ 1204 \\ +\ 807 \\ \hline \end{array}$$

e 946 + 241 + 27 + 9 **f** 1052 + 839 + 7 + 84

Example 6

7 Find the answers to these differences. Check your answer with a calculator.

a
$$\begin{array}{r} 54 \\ -\ 23 \\ \hline \end{array}$$

b
$$\begin{array}{r} 85 \\ -\ 65 \\ \hline \end{array}$$

c
$$\begin{array}{r} 46 \\ -\ 27 \\ \hline \end{array}$$

d
$$\begin{array}{r} 94 \\ -\ 36 \\ \hline \end{array}$$

e
$$\begin{array}{r} 125 \\ -\ 89 \\ \hline \end{array}$$

f
$$\begin{array}{r} 241 \\ -\ 129 \\ \hline \end{array}$$

g
$$\begin{array}{r} 358 \\ -\ 279 \\ \hline \end{array}$$

h
$$\begin{array}{r} 491 \\ -\ 419 \\ \hline \end{array}$$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

FLUENCY

8 Show your working to find the answer to each of these differences.

a 32 – 16 **b** 124 – 77 **c** 613 – 128 **d** 1004 – 838

9, 10 | 10–12 | 11–13

PROBLEM-SOLVING

9 Farmer Green owns 287 sheep, farmer Brown owns 526 sheep and farmer Grey owns 1041 sheep. How many sheep are there in total?



10 A car's odometer shows 12 138 kilometres at the start of a journey and 12 714 kilometres at the end of the journey. How far was the journey?



11 Two different schools have 871 and 950 students enrolled.

a How many students are there in total?

b Find the difference in the number of students between the schools.

12 Find the missing numbers in these sums.

a
$$\begin{array}{r} 3\,\square \\ +\,5\;3 \\ \hline \square\;1 \end{array}$$

b
$$\begin{array}{r} 1\,\square\;4 \\ +\quad 7\,\square \\ \hline \square\;9\;1 \end{array}$$

c
$$\begin{array}{r} \square\,\square \\ +\square\;4\;7 \\ \hline 9\;1\;4 \end{array}$$

13 Find the missing numbers in these differences.

a
$$\begin{array}{r} 6\,\square \\ -\,2\;8 \\ \hline \square\;4 \end{array}$$

b
$$\begin{array}{r} 2\,\square\;5 \\ -\square\;8\,\square \\ \hline 8\;1 \end{array}$$

c
$$\begin{array}{r} 3\,\square\,\square\;2 \\ -\quad 9\;2\,\square \\ \hline \square\;1\;6\;5 \end{array}$$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1D

14 | 14, 15 | 14, 15

REASONING

14 **a** First work out the answer to these simple problems before doing part **b**.

i 28 + 18 – 17 **ii** 36 – 19 + 20

b For part **i** above, is it possible to work out 18 – 17 and then add this total to 28?

c For part **ii** above, is it possible to work out 19 + 20 and then subtract this total from 36?

d Can you suggest a good mental strategy for part **ii** above that gives the correct answer?

15 **a** What are the missing digits in this sum?

b Explain why there is more than one possible set of missing numbers in the sum given opposite. Give some examples.

$$\begin{array}{r} 2\ \square\ 3 \\ +\ \square\ \square\ \square \\ \hline 4\ 2\ 1 \end{array}$$

More magic squares

— | — | 16–18

ENRICHMENT

16 Complete these magic squares.

a


62	67	60
		65

b

101		114	
	106		109
	110		
113	103	102	116

17 The sum of two numbers is 978 and their difference is 74. What are the two numbers?

18 Make up some of your own problems like Question **17** and test them on a friend.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


1E Multiplication

Interactive

The multiplication of two numbers represents a repeated addition.

For example, 4×2 could be thought of as 4 groups of 2 or $2 + 2 + 2 + 2$.

Similarly, 4×2 could be thought of as 2 groups of 4 or 2×4 or $4 + 4$.



Widgets

HOTsheets

Walkthroughs

Let's start: Which is the correct mental strategy?

Three students explain their method for finding the answer to 124×8.

- Billy says that you can do 124×10 to get 1240, then subtract 2 to get 1238.
- Lea says that you halve 124 and 8 twice each to give $31 \times 2 = 62$.
- Surai says that you multiply 8 by 4 to give 32, 8 by 2 to give 16 and 8 by 1 to give 8. She says the total is therefore $32 + 16 + 8 = 56$.

Are any of the students correct and can you explain any errors in their thinking?

Key ideas

- Finding the **product** of two numbers involves multiplication. We say 'the product of 2 and 3 is 6'.
- $a \times b = b \times a$ e.g. $2 \times 3 = 3 \times 2$
  - This is the **commutative law** for multiplication, meaning that the order does not matter.
- $(a \times b) \times c = a \times (b \times c)$ e.g. $(3 \times 5) \times 4 = 3 \times (5 \times 4)$
  - This is the **associative law** for multiplication, meaning it does not matter which pair is multiplied first.
- The multiplication algorithm for multiplying by a single digit involves:
  - Multiplying the single digit by each digit in the other number, starting from the right.
  - Carrying and adding any digits with a higher place value to the total in the next column.

$$\begin{array}{r} {}^{1}23 \\ \times \quad 4 \\ \hline 92 \end{array} \qquad \begin{array}{l} 4 \times 3 = 12 \\ 4 \times 2 + 1 = 9 \end{array}$$

- Mental strategies for multiplication include:
  - Knowing your multiplication tables off by heart.
  - Using the commutative law by changing the order. For example, 43×2 might be thought of more easily as 2 groups of 43 or 2×43.
  - Using the commutative and associative law by altering the order if more than one number is being multiplied.

$9 \times 7 = 63$ $\quad 12 \times 3 = 36$

$$\begin{aligned} 5 \times 11 \times 2 &= 5 \times 2 \times 11 \\ &= 10 \times 11 \\ &= 110 \end{aligned}$$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Using the **distributive law** by making a 10, 100 etc. and then adjusting by adding or subtracting. The distributive law is $a \times (b + c) = (a \times b) + (a \times c)$ or $a \times (b - c) = (a \times b) - (b \times c)$. This will be used more extensively in the algebra chapters.

$6 \times 21 = (6 \times 20) + (6 \times 1)$
$= 120 + 6$
$= 126$

$7 \times 18 = (7 \times 20) - (7 \times 2)$
$= 140 - 14$
$= 126$

- Using the doubling and halving strategy by doubling one number and halving the other.

$5 \times 7 \times 4 = 10 \times 7 \times 2$
$= 70 \times 2$
$= 140$

- Using factors to split a number.

$11 \times 12 = 11 \times 6 \times 2$
$= 66 \times 2$
$= 132$

Example 7 Using mental strategies for multiplication

Use a mental strategy to find the answer to each of these products.

a 7×6 **b** 3×13 **c** 4×29 **d** 5×24 **e** 7×14

SOLUTION	EXPLANATION
a $7 \times 6 = 42$	7×6 or 6×7 should be memorised (from multiplication tables).
b $3 \times 13 = 39$	$3 \times 13 = (3 \times 10) + (3 \times 3) = 30 + 9 = 39$ (The distributive law is being used.)
c $4 \times 29 = 116$	$4 \times 29 = (4 \times 30) - (4 \times 1) = 120 - 4 = 116$ (The distributive law is being used.)
d $5 \times 24 = 120$	$5 \times 24 = 10 \times 12 = 120$ (The doubling and halving strategy is being used.)
e $7 \times 14 = 98$	$7 \times 14 = 7 \times 7 \times 2 = 49 \times 2 = 98$ (Factors of 14 are used.)

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 8 Using the multiplication algorithm

Give the result for each of these products.

a 31×4 **b** 197×7

SOLUTION	EXPLANATION
a $\begin{array}{r} 31 \\ \times\ 4 \\ \hline 124 \end{array}$	$4 \times 1 = 4$ $4 \times 3 = 12$
b $\begin{array}{r} {}^{6}1\ {}^{4}9\ \ 7 \\ \times\ \ \ \ \ 7 \\ \hline 1\ 3\ 7\ 9 \end{array}$	$7 \times 7 = 49$ (carry the 4) $7 \times 9 + 4 = 67$ (carry the 6) $7 \times 1 + 6 = 13$

Exercise 1E

1, 2(½), 3 | 3 | —

UNDERSTANDING

1 Write the next three numbers in these patterns.

a 4, 8, 12, 16, __ **b** 11, 22, 33, __ **c** 17, 34, 51, __

2 Are these statements true or false?

a $4 \times 3 = 3 \times 4$ **b** $2 \times 5 \times 6 = 6 \times 5 \times 2$ **c** $11 \times 5 = 10 \times 5$

d $3 \times 32 = 3 \times 30 + 3 \times 2$ **e** $5 \times 18 = 10 \times 9$ **f** $21 \times 4 = 2 \times 42$

g $19 \times 7 = 20 \times 7 - 19$ **h** $39 \times 4 = 40 \times 4 - 1 \times 4$ **i** $64 \times 4 = 128 \times 8$

3 What is the missing digit in these products?

a $\begin{array}{r} 2\ 1 \\ \times\ \ 3 \\ \hline 6\ \square \end{array}$ **b** $\begin{array}{r} 3\ 6 \\ \times\ \ 5 \\ \hline 18\ \square \end{array}$ **c** $\begin{array}{r} 7\ 6 \\ \times\ \ 2 \\ \hline 1\ \square\ 2 \end{array}$ **d** $\begin{array}{r} 4\ 0\ 2 \\ \times\ \ \ \ 3 \\ \hline 1\ \square\ 0\ 6 \end{array}$

4–7 | 4–5(½), 6, 7(½), 8 | 4–8(½)

FLUENCY

Example 7a

4 Using your knowledge of multiplication tables, give the answer to these products.

a 8×7 **b** 6×9 **c** 12×4 **d** 11×11

e 6×12 **f** 7×5 **g** 12×9 **h** 13×3

Example 7b, c

5 Find the results to these products mentally. Hint: Use the distributive law strategy – subtraction for **a** to **d** and addition for **e** to **h**.

a 3×19 **b** 6×29 **c** 4×28 **d** 38×7

e 5×21 **f** 4×31 **g** 6×42 **h** 53×3

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1E

FLUENCY

Example 7d, e

6 Find the answer to these products mentally. Hint: Use the double and halve strategy or split a number using its factors.

a 4×24 **b** 3×18 **c** 6×16 **d** 24×3

Example 8

7 Give the result of each of these products, using the multiplication algorithm. Check your results using a calculator.

a 33×2 **b** 43×3 **c** 72×6 **d** 55×3

e 129×2 **f** 407×7 **g** 526×5 **h** 3509×9

8 Find the answer to these products, showing your working.

a 47×5 **b** 1391×3 **c** 9×425 **d** 7×4170

PROBLEM-SOLVING

9, 10 | 10–12 | 11–13

9 Eight tickets costing $33 each are purchased for a concert. What is the total cost of the tickets?



10 A circular race track is 240 metres long and Rory runs seven laps. How far does Rory run in total?

11 Reggie and Angelo combine their packs of cards. Reggie has five sets of 13 cards and Angelo has three sets of 17 cards. How many cards are there in total?

12 Sala purchases some goods for a party at an outlet store and has $100 to spend. She selects eight bottles of drink for $2 each, 13 food packs at $6 each and 18 party hats at 50 cents each. Does she have enough money to pay for all the items?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1E

PROBLEM-SOLVING

13 Find the missing digits in these products.

a
$$\begin{array}{r} 3\,9 \\ \times\quad 7 \\ \hline 2\square 3 \end{array}$$

b
$$\begin{array}{r} 2\,5 \\ \times\quad \square \\ \hline 1\,2\,5 \end{array}$$

c
$$\begin{array}{r} 7\,9 \\ \times\quad \square \\ \hline \square\,3\,7 \end{array}$$

d
$$\begin{array}{r} 1\,3\,2 \\ \times\quad \square \\ \hline 10\square\,6 \end{array}$$

e
$$\begin{array}{r} 2\square \\ \times\quad 7 \\ \hline \square\,8\,9 \end{array}$$

f
$$\begin{array}{r} \square\square \\ \times\quad 9 \\ \hline 3\,5\,1 \end{array}$$

g
$$\begin{array}{r} 2\,3\square \\ \times\quad 5 \\ \hline 1\square\,6\,0 \end{array}$$

h
$$\begin{array}{r} \square\square\,4 \\ \times\quad \square \\ \hline \square\,1\,9\,8 \end{array}$$

14 | 14, 15 | 15, 16

REASONING

14 The commutative and associative laws for multiplication mean that numbers can be multiplied in any order. So $(a \times b) \times c = (b \times a) \times c = b \times (a \times c) =$ _____, where the brackets show which numbers are multiplied first. In how many ways can $2 \times 3 \times 5$ be calculated?

15 The distributive law can help to work out products mentally.
e.g. $7 \times 31 = (7 \times 30) + (7 \times 1) = 210 + 7 = 217$
Write each of the following as single products. Do not find the answer.

a $3 \times 20 + 3 \times 1$ **b** $9 \times 50 + 9 \times 2$ **c** $7 \times 30 + 7 \times 2$
d $5 \times 100 - 5 \times 3$ **e** $a \times 40 - a \times 2$ **f** $a \times 200 + a \times 3$

16 How many different ways can the two spaces be filled in this problem? Explain why.

$$\begin{array}{r} 2\square 3 \\ \times\quad 4 \\ \hline 8\square 2 \end{array}$$

Missing digits — | — | 17, 18

ENRICHMENT

17 Find all the missing digits in these products.

a
$$\begin{array}{r} \square\,1\,\square \\ \times\quad 7 \\ \hline \square\,5\,1\,\square \end{array}$$

b
$$\begin{array}{r} 2\,9\,\square \\ \times\quad 3 \\ \hline 8\square\square \end{array}$$



18 The product of two numbers is 132 and their sum is 28.
What are the two numbers?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

1F Multiplying larger numbers

Interactive

Widgets

HOTsheets

Walkthroughs

There are many situations that require the multiplication of large numbers – for example, the total revenue from selling 40 000 tickets at $23 each, or the area of a rectangular park with length and width dimensions of 65 metres by 122 metres. To complete such calculations by hand requires the use of a suitable algorithm.



How much revenue came from selling tickets to this game?

Let's start: Spot the errors

There are three types of errors in the working shown for this problem. Find the errors and describe them.

$$\begin{array}{r} 271 \\ \times\ 13 \\ \hline 613 \\ 271 \\ \hline 1273 \end{array}$$

Key ideas

- When multiplying by 10, 100, 1000, 10 000 etc. each digit moves to the left by the number of zeros, e.g. $45 \times 1000 = 45\,000$.
- A strategy for multiplying by multiples of 10, 100 etc. is to first multiply by the number without the zeros then add the zeros to the answer later.
  For example, $21 \times 3000 = 21 \times 3 \times 1000 = 63 \times 1000 = 63\,000$
- The algorithm for multiplying large numbers involves dividing the problem into smaller products and then adding the totals.

$$\begin{array}{rcl} 143 & & \\ \times\ 14 & & \\ \hline {}^{1}572 & \leftarrow & 143 \times 4 \\ 1430 & \leftarrow & 143 \times 10 \\ \hline 2002 & \leftarrow & 1430 + 572 \end{array}$$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Multiplying large numbers

Give the result for each of these products.

a 37×100 **b** 45×70 **c** 614×14

SOLUTION	EXPLANATION
a $37 \times 100 = 3700$	Move the 3 and the 7 two places to the left and add two zeros.
b $45 \times 70 = 45 \times 7 \times 10$ $= 315 \times 10$ $= 3150$	First multiply by 7, then multiply by 10 later. 45 × 7 315
c 614 × 14 2456 6140 8596	First multiply 614×4. Then multiply 614×10. Add the totals to give the answer.

Exercise 1F

1–3 | 3 | —

UNDERSTANDING

1 What is the missing digit in these products?

a $72 \times 10 = 7\square 0$ **b** $13 \times 100 = 130\square$ **c** $49 \times 100 = 49\square 0$ **d** $924 \times 10 = 92\square 0$

2 What is the missing number in these products?

a $15 \times __ = 1500$ **b** $329 \times __ = 3290$ **c** $92 \times __ = 920\,000$


3 State if the following calculations are correct. If they are incorrect, find the correct answer.

a
26
× 4
84

b
39
× 14
156
39
195

c
92
× 24
368
1840
2208

d
102
× 24
408
240
648



How could you calculate the number of pieces of fruit on this stall without counting them all?

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1F

4–6(½) | 4–7(½) | 4–7(½)

FLUENCY

Example 9a

4 Give the result of each of these products.

a 4×100 **b** 29×10 **c** 183×10 **d** 46×100

e 50×1000 **f** 630×100 **g** 1441×10 **h** $2910 \times 10\,000$

Example 9b

5 Use the suggested strategy in Example 9b to find these products.

a 17×20 **b** 36×40 **c** 92×70 **d** 45×500

e 138×300 **f** 92×5000 **g** 317×200 **h** 1043×9000

Example 9c

6 Use the multiplication algorithm to find these products.

a 37×11 **b** 72×19 **c** 126×15 **d** 428×22

e 396×46 **f** 416×98 **g** 380×49 **h** 1026×33

7 First estimate the answers to these products, then use a calculator to check.

a 19×11 **b** 26×21 **c** 37×15 **d** 121×18

8, 9 | 9–11 | 10–12

PROBLEM-SOLVING

8 A pool area includes 68 square metres of paving at $32 per square metre. What is the total cost of paving?

9 Waldo buys 215 metres of pipe at $28 per metre. What is the total cost of piping?

10 How many seconds are there in one day?

11 Find the missing digits in these products.

a
$$\begin{array}{r} 2\square \\ \times\ 1\ 7 \\ \hline 1\square\ 1 \\ 2\square\ 0 \\ \hline \square\square\ 1 \end{array}$$

b
$$\begin{array}{r} 1\square\ 3 \\ \times\ \ 1\square \\ \hline \ \square\ 2\ 9 \\ 1\square\ 3\square \\ \hline \square\square\ 5\square \end{array}$$

c
$$\begin{array}{r} \square\square \\ \times\ \ 3\ 7 \\ \hline \ 3\ 4\ 3 \\ \square\ 4\square\square \\ \hline \square\square\square\square \end{array}$$

d
$$\begin{array}{r} \square\ 2\square \\ \times\ \ \ 2\square \\ \hline \ 1\ 2\ 6 \\ \square\ 5\ 2\square \\ \hline \square\ 6\square\square \end{array}$$

12 There are 360 degrees in a full turn. How many degrees does the minute hand on a clock turn in one week?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1F

13 | 13, 14 | 14, 15

REASONING

13 The product of two whole numbers is less than their sum. Neither number is zero or less. What must be true about one of the numbers?

14 If both numbers in a multiplication problem have at least three digits, then the algorithm needs to be expanded. Use the algorithm to find these products.

a $\begin{array}{r} 294 \\ \times\ 136 \\ \hline \end{array}$ **b** $\begin{array}{r} 1013 \\ \times\ 916 \\ \hline \end{array}$ **c** $\begin{array}{r} 3947 \\ \times\ 1204 \\ \hline \end{array}$ **d** $\begin{array}{r} 47126 \\ \times\ 3107 \\ \hline \end{array}$

15 Can you work out these computations using an effective mental strategy? Look to see if you can first simplify each question.

a $98 \times 16 + 2 \times 16$

b $33 \times 26 - 3 \times 26$

c $19 \times 15 + 34 \times 17 - 4 \times 17 + 1 \times 15$

d $22 \times 19 - 3 \times 17 + 51 \times 9 - 1 \times 9 + 13 \times 17 - 2 \times 19$

Multiplication puzzle

— | — | 16, 17

ENRICHMENT

16 **a** What is the largest number you can make by choosing five digits from the list 1, 2, 3, 4, 5, 6, 7, 8, 9 and placing them into the product shown at right?

b What is the smallest number you can make by choosing five digits from the list 1, 2, 3, 4, 5, 6, 7, 8, 9 and placing them into the product shown at right?

$\square\square\square \times \square\square$

17 The product of two whole numbers is 14 391 and their difference is 6. What are the two numbers?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

1A **1** Write the number 134 using the given number systems.

Ext

a Egyptian **b** Roman

1B **2** Write the number 50862 in expanded form.

1C **3** Use the suggested strategy to mentally work out the answer.

a 143 + 232 (partitioning) **b** 35 + 29 (compensating)

c 74 – 17 (compensating) **d** 35 + 36 (doubling)

1D **4** Give the result for each of these problems.

a Addition

$$\begin{array}{r} 18 \\ +\ 44 \\ \hline \end{array}$$

b Subtraction

$$\begin{array}{r} 124 \\ -\ 46 \\ \hline \end{array}$$

1E **5** Using your knowledge of multiplication tables, give the answer to these products.

a 7×4 **b** 9×8 **c** 12×9 **d** 5×9

1E **6** Use the distributive law strategy to find the answer to each of these products. Show your working.

a 6×14 **b** 5×39

1E **7** Give the result of each of these products, using the multiplication algorithm. Show your working.

a
$$\begin{array}{r} 84 \\ \times\ 3 \\ \hline \end{array}$$

b
$$\begin{array}{r} 237 \\ \times\ 4 \\ \hline \end{array}$$

c 2146×7

1F **8** Give the result of each of these products. Show your working.

a 38×100 **b** 24×70 **c** 513×200

1F **9** Use the multiplication algorithm to find these products.

a
$$\begin{array}{r} 26 \\ \times\ 12 \\ \hline \end{array}$$

b
$$\begin{array}{r} 317 \\ \times\ 16 \\ \hline \end{array}$$

1D **10** Two different schools have 948 and 1025 students enrolled.

a How many students are there in total?

b Find the difference in the number of students between the schools.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1G Division

Interactive

Division involves finding the number of equal groups into which a particular number can be divided. This can be achieved both with and without a remainder or 'left over'. Dividing 20 apples among five people and $10 000 between three bank accounts are examples of when division can be used.

Widgets

Multiplication and division are reverse operations, and this is shown in this simple example:

$7 \times 3 = 21$ So, $21 \div 3 = 7$ or $21 \div 7 = 3$

HOTsheets

Let's start: Arranging counters

Walkthroughs

A total of 24 counters sit on a table. Using whole numbers, in how many ways can the counters be divided into equal-sized groups with no counters remaining?

- Is it also possible to divide the counters into equal-sized groups but with two counters remaining?
- If five counters are to remain, how many equal-sized groups can be formed and why?



Key ideas

- The number of equal-sized groups formed from the division operation is called the **quotient**.
- The total being divided is called the **dividend** and the size of the equal groups is called the **divisor**.
- Any amount remaining after division into equal-sized groups is called the **remainder**.

  $7 \div 3 = 2$ and 1 remainder means $7 = 2 \times 3 + 1$

  $37 \div 5 = 7$ and 2 remainder means $37 = 7 \times 5 + 2$

$7 \div 3 = 2$ and 1 remainder $= 2\frac{1}{3}$

total being divided (dividend) — size of equal groups (divisor) — quotient

- $a \div b \neq b \div a$ (in general)
  - The commutative law does not hold for division, e.g. $8 \div 2 \neq 2 \div 8$
- $(a \div b) \div c \neq a \div (b \div c)$
  - The associative law does not hold for division, e.g. $(8 \div 4) \div 2 \neq (4 \div 2)$
- The short division algorithm involves first dividing into the digit with the highest place value and then carrying any remainder to the next digit, working from left to right.

  $413 \div 3 = 137$ and 2 remainder

  $= 137\frac{2}{3}$

$4 \div 3 = 1$ and 1 rem.

$11 \div 3 = 3$ and 2 rem.

$23 \div 3 = 7$ and 2 rem.

$$3\overline{)4^{1}1^{2}3}\quad 137$$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Mental division can be done using different strategies.
  - Knowing your multiplication tables off by heart.
  - $63 \div 9 = ?$ is the same as asking $9 \times ? = 63$.
  - Making a convenient multiple of the divisor and then adjusting by adding or subtracting. Below is an application of the distributive law.

$$\begin{aligned} 84 \div 3 &= (60 + 24) \div 3 \\ &= (60 \div 3) + (24 \div 3) \\ &= 20 + 8 \\ &= 28 \end{aligned} \qquad \begin{aligned} 84 \div 3 &= (90 - 6) \div 3 \\ &= (90 \div 3) - (6 \div 3) \\ &= 30 - 2 \\ &= 28 \end{aligned}$$

  - Halving both numbers. If both numbers in the division are even, then halve both numbers.

$$\begin{aligned} 70 \div 14 &= 35 \div 7 \\ &= 5 \end{aligned}$$

Example 10 Using mental strategies for division

Use a mental strategy to find the quotient.

a $84 \div 7$ **b** $93 \div 3$ **c** $128 \div 8$

SOLUTION	EXPLANATION
a $84 \div 7 = 12$	$7 \times ? = 84$ (Use your knowledge from multiplication tables.)
b $93 \div 3 = 31$	$93 \div 3 = (90 \div 3) + (3 \div 3) = 30 + 1$ (This uses the distributive law.)
c $128 \div 8 = 16$	$128 \div 8 = 64 \div 4 = 32 \div 2 = 16$ (Halve both numbers repeatedly.)

Example 11 Using the short division algorithm

Use the short division algorithm to find the quotient and remainder.

a $3\overline{)37}$ **b** $7\overline{)195}$

SOLUTION	EXPLANATION
a $3\overline{)37}^{\,12}$ $37 \div 3 = 12$ and 1 remainder.	$3 \div 3 = 1$ with no remainder. $7 \div 3 = 2$ with 1 remainder.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $7\overline{)19^{5}5}$ $\quad$ $2\ 7$

195 ÷ 7 = 27 and 6 remainder.

7 does not divide into 1.

19 ÷ 7 = 2 with 5 remainder.

55 ÷ 7 = 7 with 6 remainder.

Exercise 1G

1–3 | 3 | —

UNDERSTANDING

1 Write the number that is missing in these statements.

a 8 ÷ 2 = 4 is the same as 4 × ? = 8.

b 36 ÷ 12 = 3 is the same as ? × 12 = 36.

c 42 ÷ ? = 6 is the same as 6 × 7 = 42.

d 72 ÷ 6 = ? is the same as 12 × 6 = 72.

2 What is the remainder when:

a 2 is divided into 7?

b 5 is divided into 37?

c 42 is divided by 8?

d 50 is divided by 9?

3 Write the missing digit in each of these divisions.

a $3\overline{)5\ 1}$ $\quad$ $\square 7$

b $7\overline{)8\ 4}$ $\quad$ $\square 2$

c $5\overline{)1\ 2\ 5}$ $\quad$ $2\square$

d $9\overline{)1\ 3\ 5}$ $\quad$ $1\square$

4–5(½), 6–8 | 4–5(½), 6–9 | 4–9(½)

FLUENCY

Example 10a **4** Use your knowledge of multiplication tables to find the quotient.

a 28 ÷ 7 **b** 36 ÷ 12 **c** 48 ÷ 8 **d** 45 ÷ 9

e 56 ÷ 8 **f** 63 ÷ 7 **g** 96 ÷ 12 **h** 121 ÷ 11

Example 10b **5** Find the answer to these using a mental strategy. Hint: Use the distributive law strategy.

a 63 ÷ 3 **b** 76 ÷ 4 **c** 57 ÷ 3 **d** 205 ÷ 5

e 203 ÷ 7 **f** 189 ÷ 9 **g** 906 ÷ 3 **h** 490 ÷ 5

Example 10c **6** Find the answers to these using a mental strategy. Hint: Use the halving strategy by halving both numbers.

a 88 ÷ 4 **b** 124 ÷ 4 **c** 136 ÷ 8 **d** 112 ÷ 16

7 Write the answers to these divisions, which involve 0s and 1s.

a 26 ÷ 1 **b** 1094 ÷ 1 **c** 0 ÷ 7 **d** 0 ÷ 458

Example 11 **8** Use the short division algorithm to find the quotient and remainder.

a $3\overline{)71}$ **b** $7\overline{)92}$ **c** $2\overline{)139}$ **d** $6\overline{)247}$

e $4\overline{)2173}$ **f** $3\overline{)61\,001}$ **g** $5\overline{)4093}$ **h** $9\overline{)90\,009}$

9 Use the short division algorithm to find the quotient and remainder.

a 526 ÷ 4 **b** 1691 ÷ 7 **c** 2345 ÷ 6 **d** 92 337 ÷ 8

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1G

10–12 | 11–14 | 14–16

PROBLEM-SOLVING

10 If 117 food packs are divided equally among nine families, how many packs does each family receive?

11 Spring Fresh Company sells mineral water in packs of six bottles. How many packs are there in a truck containing 744 bottles?

12 A bricklayer earns $1215 in a week.

a How much does he earn per day if he works Monday to Friday?

b How much does he earn per hour if he works 9 hours per day?

13 A straight fence has two end posts as well as other posts that are divided evenly along the fence 4 metres apart. If the fence is to be 264 metres long, how many posts are needed, including the end posts?

14 Friendly Taxis can take up to four passengers each. How many taxis are required to transport 59 people?

15 A truck can carry up to 7 tonnes of rock. What is the minimum number of trips needed to transport 130 tonnes of rock?

16 All the rows, columns and main diagonals in the magic square multiply to give 216. Can you find the missing numbers?

	9	12
		1

17, 18 | 17–19 | 20–22

REASONING

17 Write down the missing numbers.

a $37 \div 3 = 12$ and $\square$ remainder means $37 = \square \times 3 + 1$

b $96 \div 7 = \square$ and 5 remainder means $96 = 13 \times \square + 5$

c $104 \div 20 = 5$ and $\square$ remainder means $104 = \square \times 20 + 4$

18 Pies are purchased wholesale at 9 for $4. How much will it cost to purchase 153 pies?

19 Give the results to these problems, if a represents any number.

a $a \div 1$

b $0 \div a$

c $a \div a$

20 A number less than 30 leaves a remainder of 3 when divided by 5 and a remainder of 2 when divided by 3. What two numbers meet the given conditions?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1G

REASONING

21 As you know $a \div b$ is not generally equal to $b \div a$. However, can you find a situation where $a \div b = b \div a$?

22 The short division algorithm can also be used to divide by numbers with more than one digit.

e.g. $215 \div 12 = 17$ and 11 remainder.

$21 \div 12 = 1$ and 9 remainder.

$95 \div 12 = 7$ and 11 remainder.

$$12\overline{)21^{9}5}\quad 1\ 7$$

Use the short division algorithm to find the quotient and remainder.

a $371 \div 11$ **b** $926 \div 17$ **c** $404 \div 13$

d $1621 \div 15$ **e** $2109 \div 23$ **f** $6914 \div 56$

Long, short division — — 23–25

ENRICHMENT

23 Use the short division algorithm to find the quotient and remainder.

a $1247 \div 326$ **b** $1094 \div 99$ **c** $26\,401 \div 1432$

24 The magic product for this square is 6720. Find the missing numbers.

1	6		56
40		2	3
14			
			10

25 Instead of carrying out a complex division algorithm, you could convert the divisor into a smaller pair of factors and complete two simpler division questions to arrive at the correct answer.

For example: $1458 \div 18 = (1458 \div 2) \div 9$

$= 729 \div 9$

$= 81$

Use factors to help you calculate the following.

a $555 \div 15$ **b** $860 \div 20$ **c** $3600 \div 48$

d $1456 \div 16$ **e** $6006 \div 42$ **f** $2024 \div 22$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1H Estimating and rounding CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Many theoretical and practical problems do not need precise or exact answers. In such situations reasonable estimations can provide enough information to solve the problem.

The total revenue from the Australian Open tennis tournament depends on crowd numbers. Estimates would be used before the tournament begins to predict these numbers. An estimate for the total revenue might be $8 million.

Let's start: The tennis crowd

Here is a photo of a crowd at a tennis match. Describe how you might estimate the number of people in the photo. What is your answer? How does your answer differ from those of others in your class?



How can you estimate the number of spectators?

Key ideas

- Estimates or approximations to the answers of problems can be found by **rounding** numbers to the nearest 10, 100, 1000 etc.
- If the next digit is 0, 1, 2, 3 or 4, then round down.
- If the next digit is 5, 6, 7, 8 or 9, then round up.
- **Leading digit approximation** rounds the first digit to the nearest 10 or 100 or 1000 etc.
  e.g. For 932 use 900 For 968 use 1000
- The symbol $\approx$ means '**approximately equal to**'. The symbol $\fallingdotseq$ can also be used.

Example 12 Rounding

Round these numbers as indicated.

a 86 (to the nearest 10)

b 4142 (to the nearest 100)

SOLUTION	EXPLANATION
a $86 \approx 90$	The digit after the 8 is greater than or equal to 5, so round up.
b $4142 \approx 4100$	The digit after the 1 is less than or equal to 4, so round down.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Using leading digit approximation

Estimate the answers to these problems by rounding each number to the leading digit.

a 42×7 **b** 95×326

SOLUTION	EXPLANATION
a $42 \times 7 \approx 40 \times 7$ $= 280$	The leading digit in 42 is the 4 in the 'tens' column.
b $95 \times 326 \approx 100 \times 300$ $= 30\,000$	The nearest 'ten' to 95 is 100, and the leading digit in 326 is in the 'hundreds' column.

Example 14 Estimating with operations

Estimate the answers to these problems by rounding both numbers as indicated.

a 115×92 (to the nearest 100) **b** $2266 \div 9$ (to the nearest 10)

SOLUTION	EXPLANATION
a $115 \times 92 \approx 100 \times 100$ $= 10\,000$	115 rounds to 100 and 92 rounds to 100.
b $2266 \div 9 \approx 2270 \div 10$ $= 227$	2266 rounds to 2270 and 9 rounds to 10.

Exercise 1H

1, 2 | 2 | —

UNDERSTANDING

1 State whether these numbers have been rounded up or down.

a $59 \approx 60$ **b** $14 \approx 10$ **c** $137 \approx 140$

d $255 \approx 260$ **e** $924 \approx 900$ **f** $1413 \approx 1000$

2 For the given estimates, decide if the approximate answer is going to give a larger or smaller result compared to the true answer.

a $58 + 97 \approx 60 + 100$ **b** $24 \times 31 \approx 20 \times 30$

c $130 - 79 \approx 130 - 80$ **d** $267 - 110 \approx 270 - 110$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1H

3–7(½) | 3–7(½) | 3–7(½)

FLUENCY

Example 12

3 Round these numbers as indicated.

a 59 (nearest 10) b 32 (nearest 10) c 124 (nearest 10)
d 185 (nearest 10) e 231 (nearest 100) f 894 (nearest 100)
g 96 (nearest 10) h 584 (nearest 100) i 1512 (nearest 1000)

4 Round these numbers using leading digit approximation; i.e. round to the first digit.

a 21 b 29 c 136 d 857
e 5600 f 92 104 g 9999 h 14

5 Estimate the answers to these problems by first rounding both numbers as indicated.

a 72 + 59 (nearest 10) b 138 – 61 (nearest 10)
c 275 – 134 (nearest 10) d 841 + 99 (nearest 10)
e 203 – 104 (nearest 100) f 815 + 183 (nearest 100)
g 990 + 125 (nearest 100) h 96 + 2473 (nearest 100)
i 1555 – 555 (nearest 1000)

Example 13

6 Use leading digit approximation to estimate the answer.

a 29×4 b $124 + 58$ c $232 - 106$ d $61 \div 5$
e $394 \div 10$ f 97×21 g $1390 + 3244$ h $999 - 888$

Example 14

7 Estimate the answers to these problems by rounding both numbers as indicated.

a 29×41 (nearest 10) b 92×67 (nearest 10)
c 124×173 (nearest 100) d 2402×3817 (nearest 1000)
e $48 \div 11$ (nearest 10) f $159 \div 12$ (nearest 10)
g $104 \div 11$ (nearest 10) h $2493 \div 103$ (nearest 100)

8, 9 | 9–11 | 10–12

PROBLEM-SOLVING

8 Many examples of Aboriginal art include dot paintings. Here is one example. Estimate the number of dots it contains.



9 A digger can dig 29 scoops per hour and work 7 hours per day. Approximately how many scoops can be dug over 10 days?

10 Most of the pens at a stockyard are full of sheep. There are 55 pens and one of the pens has 22 sheep. Give an estimate for the total number of sheep at the stockyard.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1H

PROBLEM-SOLVING

11 A whole year group of 159 students is roughly divided into 19 groups. Estimate the number in each group.

12 It is sensible sometimes to round one number up if the other number is going to be rounded down. Use leading digit approximation to estimate the answers to these problems.

a 11×19 **b** 129×954 **c** 25×36 **d** 1500×2500

13a, b	13	13

REASONING

13 The letters a and b represent numbers. Which of the words 'smaller' or 'larger' completes these sentences?

a If a and b are both rounded up, then compared to the true answer the approximate answer to:

i $a + b$ will be _____.

ii $a \times b$ will be _____.

b If only a is rounded up, but b is left as it is, then compared to the true answer the approximate answer to:

i $a - b$ will be _____.

ii $a \div b$ will be _____.

c If only b is rounded up, but a is left as it is, then compared to the true answer the approximate answer to:

i $a - b$ will be _____.

ii $a \div b$ will be _____.

d If only b is rounded down, but a is left as it is, then compared to the true answer the approximate answer to:

i $a - b$ will be _____.

ii $a \div b$ will be _____.

Maximum error	—	—	14

ENRICHMENT

14 When rounding numbers before a calculation is completed, it is most likely that there will be an error. This error can be large or small, depending on the type of rounding involved.
For example, when rounding to the nearest 10, $71 \times 11 \approx 70 \times 10 = 700$.
But $71 \times 11 = 781$, so the error is 81.

a Calculate the error if these numbers are rounded to the nearest 10 before the multiplication is calculated.

i 23×17 **ii** 23×24 **iii** 65×54 **iv** 67×56

b Explain why the error in parts **i** and **iii** is much less than the error in parts **ii** and **iv**.

c Calculate the error if these numbers are rounded to the nearest 10 before the division is calculated.

i $261 \div 9$ **ii** $323 \div 17$ **iii** $99 \div 11$ **iv** $396 \div 22$

d Explain why the approximate answers in parts **i** and **ii** are less than the correct answer, and why the approximate answers in parts **iii** and **iv** are more than the correct answer.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

1I Order of operations

Interactive

When combining the operations of addition, subtraction, multiplication and division, a particular order needs to be followed. Multiplication and division sit higher in the order than addition and subtraction, and this relates to how we might logically interpret simple mathematical problems put into words.



Widgets

HOTsheets

Walkthroughs

Consider these two statements.

- 2 groups of 3 chairs plus 5 chairs.
- 5 chairs plus 2 groups of 3 chairs.

In both cases, there are $2 \times 3 + 5 = 11$ chairs. This means that $2 \times 3 + 5 = 5 + 2 \times 3$.

This also suggests that for $5 + 2 \times 3$ the multiplication should be done first.

Let's start: Minimum brackets

- How might you use brackets to make this statement true?


$$2 + 3 \times 5 - 3 \div 6 + 1 = 2$$

- What is the minimum number of pairs of brackets needed to make it true?

Key ideas

- When working with more than one operation:
  - Deal with **brackets** (also known as parentheses) first.
  - Do **multiplication** and **division** next, working from left to right.
  - Do **addition** and **subtraction** last, working from left to right.
- Recall $(a + b) + c = a + (b + c)$ but $(a - b) - c \neq a - (b - c)$

  $(a \times b) \times c = a \times (b \times c)$ but $(a \div b) \div c \neq a \div (b \div c)$
- Brackets can sit inside other brackets.
  - Square brackets can also be used. e.g. $[2 \times (3 + 4) - 1] \times 3$
  - Always deal with the inner brackets first.
- Note that some calculators apply the order of operations and some do not.



Example 15 Using order of operations

Use order of operations to answer the following.

a $5 + 10 \div 2$ b $18 - 2 \times (4 + 6) \div 5$

SOLUTION	EXPLANATION
a $5 + 10 \div 2 = 5 + 5$ $= 10$	Do the division before the addition.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $18 - 2 \times (4 + 6) \div 5 = 18 - 2 \times 10 \div 5$
$= 18 - 20 \div 5$
$= 18 - 4$
$= 14$

Deal with brackets first.

Do the multiplication and division next, working from left to right.

Do the subtraction last.



Example 16 Using order of operations in worded problems

Find the difference between 76 and 43, triple this result and, finally, subtract the quotient of 35 and 7.

SOLUTION

a $3 \times (76 - 43) - 35 \div 7 = 3 \times 33 - 5$
$= 99 - 5$
$= 94$

EXPLANATION

First, write the problem using symbols and numbers.
Use brackets for the difference since this operation is to be completed first.

Exercise 1I

1(½), 2 | 2 | —

UNDERSTANDING

1 Which operation (addition, subtraction, multiplication or division) is done first in the following?

a $2 + 5 - 3$ **b** $5 \div 5 \times 2$ **c** $2 \times 3 \div 6$
d $5 \times 2 + 3$ **e** $7 \div 7 - 1$ **f** $(6 + 2) \times 3$
g $(8 \div 4) - 1$ **h** $4 + 7 \times 2$ **i** $8 - 10 \div 5$
j $10 - 2 + 3$ **k** $6 + 2 \times 3 - 1$ **l** $5 \times (2 + 3 \div 3) - 1$

2 Classify these statements as true or false.

a $5 \times 2 + 1 = (5 \times 2) + 1$ **b** $10 \times (3 + 4) = 10 \times 3 + 4$
c $21 - 7 \div 7 = (21 - 7) \div 7$ **d** $9 - 3 \times 2 = 9 - (3 \times 2)$

3–4(½), 5, 6 | 3–4(½), 5, 6 | 3–6(½)

FLUENCY

Example 15a



3 Use order of operations to find the answers to the following. Check your answers using a calculator and see if it applies the order of operations.

a $2 + 3 \times 7$ **b** $5 + 8 \times 2$ **c** $10 - 20 \div 2$
d $22 - 16 \div 4$ **e** $6 \times 3 + 2 \times 7$ **f** $1 \times 8 - 2 \times 3$
g $18 \div 9 + 60 \div 3$ **h** $2 + 3 \times 7 - 1$ **i** $40 - 25 \div 5 + 3$
j $63 \div 3 \times 7 + 2 \times 3$ **k** $78 - 14 \times 4 + 6$ **l** $300 - 100 \times 4 \div 4$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11

FLUENCY

Example 15b

4 Use order of operations to find the answer to the following problems. Check your answers using a calculator and see if it applies the order of operations.

a $2 \times (3 + 2)$
b $18 \div (10 - 4)$
c $(19 - 9) \div 5$
d $(100 + 5) \div 5 + 1$
e $2 \times (9 - 4) \div 5$
f $50 \div (13 - 3) + 4$
g $16 - 2 \times (7 - 5) + 6$
h $(7 + 2) \div (53 - 50)$
i $14 - (7 \div 7 + 1) \times 2$
j $(20 - 10) \times (5 + 7) + 1$
k $3 \times (72 \div 12 + 1) - 1$
l $48 \div (4 + 4) \div (3 \times 2)$

5 These computations involve brackets within brackets. Ensure you work with the inner brackets first.

a $2 \times [(2 + 3) \times 5 - 1]$
b $[10 \div (2 + 3) + 1] \times 6$
c $26 \div [10 - (17 - 9)]$
d $[6 - (5 - 3)] \times 7$
e $2 + [103 - (21 + 52)] - (9 + 11) \times 6 \div 12$

Example 16

6 Find the answer to these worded problems by first writing the sentence using numbers and symbols.

a Triple the sum of 3 and 6.
b Double the quotient of 20 and 4.
c The quotient of 44 and 11 plus 4.
d 5 more than the product of 6 and 12.
e The quotient of 60 and 12 is subtracted from the product of 5 and 7.
f 15 less than the difference of 48 and 12.
g The product of 9 and 12 is subtracted from double the product of 10 and 15.

7, 8 | 8, 9 | 8–10

PROBLEM-SOLVING

7 A delivery of 15 boxes of books arrives, each box containing eight books. The bookstore owner removes three books from each box. How many books still remain in total?



8 In a class, eight students have three TV sets at home, four have two TV sets, 13 have one TV set and two students have no TV sets. How many TV sets are there in total?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11

PROBLEM-SOLVING

9 Insert brackets into these statements to make them true.

a $4 + 2 \times 3 = 18$ **b** $9 \div 12 - 9 = 3$ **c** $2 \times 3 + 4 - 5 = 9$

d $3 + 2 \times 7 - 3 = 20$ **e** $10 - 7 \div 21 - 18 = 1$ **f** $4 + 10 \div 21 \div 3 = 2$

g $20 - 31 - 19 \times 2 = 16$ **h** $50 \div 2 \times 5 - 4 = 1$ **i** $25 - 19 \times 3 + 7 \div 12 + 1 = 6$

10 The amount of $100 is divided into two first prizes of equal value and three second prizes of equal value. Each prize is a whole number of dollars and first prize is at least four times the value of second prize. If second prize is more than $6, find the amount of each prize.

11 | 11, 12 | 12, 13

REASONING

11 Decide if the brackets given in each statement are actually necessary; that is, do they make any difference to the problem?

a $2 + (3 \times 6) = 20$ **b** $(2 + 3) \times 6 = 30$ **c** $(20 \times 2) \times 3 = 120$

d $10 - (5 + 2) = 3$ **e** $22 - (11 - 7) = 18$ **f** $19 - (10 \div 2) = 14$

g $(40 \div 10) \div 4 = 1$ **h** $100 \div (20 \div 5) = 25$ **i** $2 \times (3 + 2) \div 5 = 2$

12 The letters a, b and c represent numbers. Decide if the brackets are necessary in these expressions.

a $a + (b + c)$ **b** $a - (b - c)$ **c** $a \times (b \times c)$ **d** $a \div (b \div c)$

13 Simplify the following. Assume $b \neq 0$, and $a \neq 0$.

a $a + b - a$ **b** $(a - a) \times b$ **c** $a + b \div b$ **d** $a \times b \div a$

Operation in rules — | — | 14

ENRICHMENT

14 Using whole numbers and any of the four operations ($+, -, \times, \div$), describe how you would obtain the 'Finish' number from the 'Start' number in each of these tables. Your rule must work for every pair of numbers in its table.

a

Start	Finish
1	3
2	5
3	7
4	9

b

Start	Finish
1	0
2	3
3	6
4	9

c

Start	Finish
3	10
4	17
5	26
6	37

Make up your own table with a 'secret' rule and test it on a friend.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

The abacus

The abacus is a counting device that has been used for thousands of years. Abacuses were used extensively by merchants, traders, tax collectors and clerks before modern-day numerals systems were developed. Counting boards called Abax date back to 500 BCE. These were wood or stone tablets with grooves, which would hold beans or pebbles.

The modern abacus is said to have originated in China in about the thirteenth century and includes beads on wires held in a wooden frame.



A German woodcut from 1508 showing an abacus in use by the gentleman on the right, while a mathematician (at left) writes algorithms.




A modern abacus with 13 wires.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

There are 5 beads on one side of a modern abacus worth 1 each and 2 beads on the opposite side worth 5 each.


- Each wire represents a different unit, e.g. ones, tens, hundreds etc.
- Beads are counted only when they are pushed towards the centre.




Here is a diagram showing the number 5716.

a What numbers are showing on the abacus diagrams below? Only the first six wires are showing.


i




ii



iii



iv



b Draw abacus diagrams showing these numbers.

i 57 **ii** 392 **iii** 6804 **iv** 290 316

c Imagine adding two numbers using an abacus by sliding beads along their wires. Clearly explain the steps taken to add these numbers.

i $11 + 7$ **ii** $2394 + 536$

d Imagine subtracting two numbers using an abacus by sliding beads along their wires. Clearly explain the steps taken to subtract these numbers.

i $23 - 14$ **ii** $329 - 243$

e Multiplication is calculated as a repeated addition.
e.g. $3 \times 21 = 21 + 21 + 21$
Clearly explain the steps involved when using an abacus to multiply these numbers.

i 3×42 **ii** 5×156

f Division is calculated as a repeated subtraction.
e.g. $63 \div 21 = 3$, since $63 - 21 - 21 - 21 = 0$
Clearly explain the steps involved when using an abacus to divide these numbers.

i $28 \div 7$ **ii** $405 \div 135$

g See if you can find a real abacus or computer abacus with which to work. Use the abacus to show how you can do the problems in Questions **c** to **f** above.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 The extra dollar. The cost of dinner for two people is $45 and they both give the waiter $25 each. Of the extra $5 the waiter is allowed to keep $3 as a tip and returns $1 to each person. So the two people paid $24 each, making a total of $48, and the waiter has $3. The total is therefore $48 + $3 = $51. Where did the extra $1 come from?

2 The sum along each line is 15. Can you place each of the digits 1, 2, 3, 4, 5, 6, 7, 8 and 9 to make this true?



3 Ethan starts at 2637 and counts backwards by eights. He stops counting when he reaches a number less than 10. What is this final number?


4 Make the total of 100 out of all the numbers 2, 3, 4, 7 and 11, using each number only once. You can use any of the operations (+, –, ×, ÷), as well as brackets.

5 A leaking tap loses 1 drop of water per second. If 40 of these drops of water make a volume of 10 mL, how many litres of water are wasted from this tap in mL:

a in 1 day? (round answer to the nearest unit)


b in 1 year? (round answer to the nearest 100)

6 When this shape is folded to make a cube, three of the sides will meet at every vertex (corner) of the cube. The numbers on these three sides can be multiplied together.
Find the smallest and largest of these products.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

1A Ext **1** The correct Roman numerals for the number 24 are:

A XXIII **B** XXIV **C** XXXLIV **D** IVXX **E** IXXV

1B **2** $3 \times 1000 + 9 \times 10 + 2 \times 1$ is the expanded form of:

A 3920 **B** 392 **C** 3092 **D** 3902 **E** 329

1C/E **3** Which of the following is not true?

A $2 + 3 = 3 + 2$ **B** $2 \times 3 = 3 \times 2$ **C** $(2 \times 3) \times 4 = 2 \times (3 \times 4)$

D $5 \div 2 \neq 2 \div 5$ **E** $7 - 2 = 2 - 7$

1C **4** The sum of 198 and 103 is:

A 301 **B** 304 **C** 299 **D** 199 **E** 95

1C **5** The difference between 378 and 81 is:

A 459 **B** 297 **C** 303 **D** 317 **E** 299

1E **6** The product of 7 and 21 is:

A 147 **B** 141 **C** 21 **D** 140 **E** 207

1G **7** The missing digit in this division

$$\begin{array}{r} 1\ \ 1\ \ 8 \\ 7\overline{)\ \square\ {}^{1}2\ {}^{5}6} \end{array}$$

is:

A 6 **B** 1 **C** 9 **D** 8 **E** 7

1G **8** The remainder when 317 is divided by 9 is:


A 7 **B** 5 **C** 2 **D** 1 **E** 0

1G **9** 458 rounded to the nearest 100 is:

A 400 **B** 500 **C** 460 **D** 450 **E** 1000

1I **10** The answer to $[2 + 3 \times (7 - 4)] \div 11$ is:

A 1 **B** 5 **C** 11 **D** 121 **E** 0



Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1A **1** Write these numbers using the given number systems.

Ext

a Egyptian

i 3 **ii** 31 **iii** 326

b Babylonian

i 12 **ii** 60 **iii** 132

c Roman

i 14 **ii** 40 **iii** 146

1B **2** Write down the place value of the digit 5 in these numbers.

a 357 **b** 5249 **c** 356 612

1C **3** Use a mental strategy to find these sums and differences.

a $124 + 335$ **b** $687 - 324$ **c** $59 + 36$ **d** $256 - 39$

1D **4** Use an algorithm and show your working for these sums and differences.

a $76 + 52$ **b** $1528 + 796$ **c** $329 - 138$ **d** $2109 - 1814$

1E/G **5** Use a mental strategy to answer the following.

a 5×19 **b** 22×6 **c** 5×44 **d** $123 \div 3$

e $264 \div 8$ **f** $96 \div 4$ **g** 29×1000 **h** 36×300

i $14\,678 \div 1$

1F/G **6** Use an algorithm and show your working for the following.

a 157×9 **b** 27×13 **c** $7\overline{)327}$ **d** $4\overline{)30162}$

1D/F/G **7** Find the missing digits in the following.

a
$$\begin{array}{r} 2\square 3 \\ +\,7\,3\,\square \\ \hline 9\,6\,1 \end{array}$$

b
$$\begin{array}{r} \square\,2\,\square \\ -\,4\,\square\,3 \\ \hline 2\,5\,6 \end{array}$$

c
$$\begin{array}{r} \quad\quad\square\,3 \\ \times\quad 2\,\square \\ \hline \quad\square\,7\,1 \\ \square\,0\,6\,0 \\ \hline \square\square\,3\,1 \end{array}$$

d $5\overline{)\square\,4\,\square\,1\,\square}$ with no remainder

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

1H **8** Round these numbers as indicated.

a 72 (nearest 10) **b** 3268 (nearest 100) **c** 951 (nearest 100)

1H **9** Use leading digit approximation to estimate the answers to the following.

a $289 + 532$ **b** 22×19 **c** 452×11 **d** $99 \div 11$

1I **10** Use order of operations to find the answers to the following.

a $3 \times (2 + 6)$ **b** $6 - 8 \div 4$ **c** $2 \times 8 - 12 \div 6$

d $(5 + 2) \times 3 - (8 - 7)$ **e** $0 \times (988\,234 \div 3)$ **f** $1 \times (3 + 2 \times 5)$

Extended-response questions

1 A city tower construction uses 4520 tonnes of cement trucked from a factory that is 7 kilometres from the construction site. Each cement mixer can carry 7 tonnes of cement, and the cement costs $85 per truck load for the first 30 loads and $55 per load after that.

a How many loads of cement are needed? Add a full load for any remainder.

b Find the total distance travelled by the cement mixers to deliver all loads, assuming they need to return to the factory after each load.

c Find the total cost of cement needed to make concrete for the tower construction.

d A different cement supplier offers a price of $65 per 8-tonne truck, no matter how many loads are needed. Find the difference in the cost of cement for the tower by this supplier compared to the original supplier.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 One night Ricky and her brother Micky decide to have some fun at their father's sweet shop. In the shop they find 7 tins of 135 jelly beans each, 9 packets of 121 choc buds, 12 jars of 70 smarties and 32 packets of 5 liquorice sticks.

- **a** Find the total number of sweets that Ricky and Micky find that night.
- **b** Find the difference between the number of choc buds and the number of smarties.
- **c** Ricky and Micky decide to divide each type of sweet into groups of 7 and then eat any remainder. Which type of sweet will they eat the most of and how many?
- **d** After eating the remainders, they round the total of each sweet using leading digit approximation. If they round down they put the spare sweets in their pockets. If they round up they borrow any spare sweets from their pockets. Any leftover in their pockets they can eat. Do Ricky and Micky get to eat any more sweets?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter 2 Geometry

What you will learn

2A Points, lines and angles (Consolidating)
2B Measuring angles (Consolidating)
2C Angles at a point
2D Transversal lines and parallel lines
2E Problems with parallel lines (Extending)
2F Circles and constructions
2G Dynamic geometry

Australian curriculum


MEASUREMENT AND GEOMETRY

Geometric reasoning

Identify corresponding, alternate and cointerior angles when two parallel straight lines are crossed by a transversal (ACMMG163)
Investigate conditions for two lines to be parallel and solve simple numerical problems using reasoning (ACMMG164) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Thales, pyramids and the solar eclipse

From the Egyptian pyramids to modern architecture, points, lines and angles are everywhere. Geometry is a very visual element of mathematics where the designs of buildings and the orbits of planets can be studied using basic objects like points, lines and circles.

Thales (624–546 BCE) is known to be the founder of Greek geometry. He was an astronomer and philosopher, and records show he was the first person to use mathematical geometry to calculate the height of an Egyptian pyramid using the sun's rays and to accurately predict the timing of a solar eclipse.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2A Points, lines and angles CONSOLIDATING









The fundamental building blocks of geometry are the point, line and plane. They are the basic objects used to construct angles, triangles and other more complex shapes and objects. Points and lines do not actually occupy any area but can be represented on a page using drawing equipment.


Lines don't take up any area, but they still exist in nature.

Let's start: Geometry around you

Take a look around the room you are in or consider any solid object near where you are seated (e.g. a book). Discuss what parts of the room or object could be described using:

- single points
- straight lines
- flat planes.

Key ideas


- A **point** is usually labelled with a capital letter.




- A **line** passing through two points, A and B, can be called line AB or line BA and extends indefinitely in both directions.




- A **plane** is a flat surface and extends indefinitely.



- Points that all lie on a single line are **collinear**.



- If two lines meet, an **intersection point** is formed.
- Three or more lines that intersect at the same point are **concurrent**.




- A line **segment** (or **interval**) is part of a line with a fixed length and end points. If the end points are A and B then it would be named segment AB or segment BA (or interval AB or interval BA).




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas


- A **ray** AB is a part of a line with one end point A and passing through point B. It extends indefinitely in one direction.




- When two rays (or lines) meet, an angle is formed at the intersection point called the **vertex**. The two rays are called **arms** of the angle.



- An **angle** is named using three points, with the vertex as the middle point. A common type of notation is $\angle ABC$ or $\angle CBA$. The measure of the angle is $a°$.



or






This mosaic around a fountain in Morocco is made up entirely of straight lines, even though it looks circular.


Example 1 Naming objects

Name this line segment and angle.

a



b



SOLUTION	EXPLANATION
a segment AB	Segment BA, interval AB or interval BA are also acceptable.
b $\angle PQR$	Point Q is the vertex and sits in between P and R. $\angle RQP$ is also correct.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 2A

1–4 | 4 | —

UNDERSTANDING

1 Draw the following objects.

a a point P **b** a line AN **c** an angle $\angle ABC$

d a ray ST **e** a plane **f** three collinear points A, B and C

2 Explain what it means to say:

a three points D, E and F are collinear **b** three lines are concurrent

3 Match the words *line*, *segment* or *ray* to the correct description.

a Starts from a point and extends indefinitely in one direction.

b Extends indefinitely in both directions, passing through two points.

c Starts and ends at two points.

4 Match the words *point*, *line* or *plane* with the following descriptions.

a the edge of a sheet of paper

b a flat wall

c the surface of a pool of water on a calm day

d where two walls and a floor meet in a room

e where two walls meet in a room

f one side of a cereal packet

g where two sides meet on a box

h where three sides meet on a box

5–9 | 5–9 | 5–6(½), 7–9


FLUENCY


Example 1


5 Name the following objects.


a 

b 

c 

d 


e 

f 


Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 Name the angle marked by the arc in these diagrams.


a




b



c




d




7 In each of these diagrams name the five line segments and the four marked angles using the given labels.

a




b




8 Name the set of three labelled points that are collinear in these diagrams.

a




b




9 State whether the following sets of lines are concurrent.

a



b



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


2A

10 | 10, 11 | 11, 12


PROBLEM-SOLVING

10 Count the number of angles formed inside these shapes. Count all angles, including ones that may be the same size and those angles that are divided by another segment.

a



b



11 How many line segments are there on this line? Do not count *AB* and *BA* as separate segments since they represent the same segment.



12 A line contains a certain number of labelled points. For example, this line has three points.

a Complete this table by counting the total number of segments for the given number of labelled points.




Number of points	1	2	3	4	5	6
Number of segments						

b Explain any patterns you see in the table. Is there a quick way of finding the next number in the table?

13 | 13 | 13, 14

REASONING

13 The lines joining each vertex (corner) of a triangle with the midpoint (middle point) of the opposite side are drawn here.



a Draw any triangle and use a ruler to measure and mark the midpoints of each side.

b Join each vertex with the midpoint of the opposite side.

c Are your segments from part **b** concurrent?

d Do you think your answer to part **c** will always be true for any triangle? Try one other triangle of a different size to check.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2A

REASONING

14 **a** If points A, B and C are collinear and points A, B and D are collinear, does this mean that points B, C and D are also collinear?

b If points A, B and C are collinear and points C, D and E are collinear, does this mean that points B, C and D are also collinear?

The general rule — — 15

ENRICHMENT

15 In Question **12** you may have determined a quick method of finding the number of segments for the given number of points. If n is the number of points on the line, can you find a rule (in terms of n) for the number of segments? Test your rule to see if it works for at least three cases.



Number of segments
$= (2n + 1) \times n$?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2B Measuring angles CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Angles are usually described using the unit of measurement called the degree, where 360 degrees (360°) describes one full turn. The idea to divide a circle into 360° dates back to the Babylonians, who used a sexagesimal number system based on the number 60. Because both 60 and 360 are numbers that have a large number of factors, many fractions of these numbers are very easy to calculate.



What angle is between each spoke on this Ferris wheel?

Let's start: Estimating angles



How good are you at estimating the size of angles? Estimate the size of these angles and then check with a protractor.

Alternatively, construct an angle using computer geometry. Estimate and then check your angle using the angle-measuring tool.



Key ideas

- Angles are classified according to their size.

Angle type	Size	Examples
acute	between 0° and 90°	
right	90°	
obtuse	between 90° and 180°	
straight	180°	
reflex	between 180° and 360°	
revolution	360°	

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Key ideas

- A **protractor** can be used to measure angles to within an accuracy of about half a degree. Some protractors have increasing scales marked both clockwise and anticlockwise from zero. To use a protractor:
  1. Place the centre of the protractor on the vertex of the angle.
  2. Align the base line of the protractor along one arm of the angle.
  3. Measure the angle using the other arm and the scale on the protractor.
  4. A reflex angle can be measured by subtracting a measured angle from 360°.


Example 2 Measuring with a protractor

For the angles shown, state the type of angle and measure its size.


a



b




c



SOLUTION


a acute

$\angle AOB = 60°$



b obtuse

$\angle EFG = 125°$




c reflex

obtuse $\angle DOE = 130°$

reflex $\angle DOE = 360° - 130°$

$= 230°$






Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Drawing angles

Use a protractor to draw each of the following angles.

a $\angle AOB = 65°$ **b** $\angle WXY = 130°$ **c** $\angle MNO = 260°$

SOLUTION	EXPLANATION
a 	Step 1: Draw a base line OB. Step 2: Align the protractor along the base line with the centre at point O. Step 3: Measure 65° and mark a point, A. Step 4: Draw the arm OA.
b 	Step 1: Draw a base line XW. Step 2: Align the protractor along the base line with the centre at point X. Step 3: Measure 130° and mark a point, Y. Step 4: Draw the arm XY.
c 	Step 1: Draw an angle of $360° - 260° = 100°$. Step 2: Mark the reflex angle on the opposite side to the obtuse angle of 100°. Alternatively, draw a 180° angle and measure an 80° angle to add to the 180° angle.

Exercise 2B

1–3 | 3 | —

UNDERSTANDING

1 Without using a protractor, draw an example of the following types of angles.

a acute **b** right **c** obtuse
d straight **e** reflex **f** revolution

2 How many right angles (i.e. angles of 90°) make up:

a a straight angle? **b** 270°? **c** a revolution?


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2B


UNDERSTANDING

3 What is the size of the angle measured with these protractors?


a




b



c



d




4–6	4(½), 5, 6(½), 7, 8	4(½), 5, 6(½), 7, 8

FLUENCY


Example 2

4 For the angles shown, state the type of angle and measure its size.


a




b




c




d




e




f




g



h



i




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

2B

FLUENCY

5 **a** Write down the size of the angles shown on this protractor.



i $\angle AOB$ **ii** $\angle BOC$
iii $\angle COD$ **iv** $\angle DOE$
v $\angle EOF$

b Find the sum of all the angles from part **a**. Name a single angle in the diagram that equals this sum.


Example 3

6 Use a protractor to draw each of the following angles.


a 40° **b** 75° **c** 90° **d** 135° **e** 175°
f 205° **g** 260° **h** 270° **i** 295° **j** 352°

7 For each of the angles marked in the situations shown, measure:


a the angle that this ramp makes with the ground




b the angle the Sun's rays make with the ground




c the angle or pitch of this roof



d the angle between this laptop screen and the keyboard



8 In the diagram shown at right, there are two marked angles, $\angle AOB$ and $\angle BOC$. Measure $\angle AOB$, $\angle BOC$ and $\angle AOC$.
Does $\angle AOB + \angle BOC = \angle AOC$? Why or why not?



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2B

PROBLEM-SOLVING | 9 | 9(½), 10 | 9(½), 10

9 A clock face is numbered 1 to 12. Find the angle the minute hand turns in:

a 30 minutes **b** 1 hour **c** 15 minutes **d** 45 minutes
e 5 minutes **f** 20 minutes **g** 55 minutes **h** 1 minute
i 9 minutes **j** 10.5 minutes **k** 42.5 minutes **l** 21.5 minutes


10 A clock face is numbered 1 to 12. Find the angle between the hour hand and the minute hand at:

a 6:00 pm **b** 3:00 pm **c** 4:00 pm **d** 11:00 am

REASONING | 11 | 11 | 11, 12

11 The arrow on this dial starts in an upright position. It then turns by a given number of degrees clockwise or anticlockwise.

a Find the angle between the arrow in its final position with the arrow in its original position, as shown in the diagram opposite, which illustrates part **i**. Answer with an acute or obtuse angle.




i 290° clockwise **ii** 290° anticlockwise
iii 450° clockwise **iv** 450° anticlockwise
v 1000° clockwise **vi** 1000° anticlockwise

b Did it matter to the answer if the dial was turning clockwise or anticlockwise?

c Explain how you calculated your answer for turns larger than 360°.

12 An acute angle $\angle AOB$ is equal to 60°. Why is it unnecessary to use a protractor to work out the size of the reflex angle $\angle AOB$?



ENRICHMENT | Time challenge | — | — | 13

13 Find the angle between the hour hand and the minute hand of a clock at these times.

a 10:10 am **b** 4:45 am
c 11:10 pm **d** 2:25 am
e 7:16 pm **f** 9:17 pm



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

2C Angles at a point

Interactive

Not all angles in a diagram or construction need to be measured directly. Special relationships exist between pairs of angles at a point and this allows some angles to be calculated exactly without measurement, even if diagrams are not drawn to scale.


Widgets


HOTsheets


Walkthroughs

Let's start: Special pairs of angles

By making a drawing or using computer geometry, construct the diagrams below. Measure the two marked angles. What do you notice about the two marked angles?









Key ideas

- **Adjacent** angles are side by side and share a vertex and an arm. $\angle AOB$ and $\angle BOC$ in this diagram at right are adjacent angles.




- **Complementary adjacent** angles sum to 90°.




$a + b = 90$

- **Supplementary adjacent** angles sum to 180°.




$a + b = 180$

- Angles in a **revolution** sum to 360°.




$a + b = 360$

- **Vertically opposite** angles are formed when two lines intersect. The opposite angles are equal. The name comes from the fact that the pair of angles has a common vertex and they sit in opposite positions across the vertex.



- **Perpendicular** lines meet at a right angle (90°). We write $AB \perp CD$.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 4 Finding angles at a point

Without using a protractor, find the size of each angle marked with the letter a.


a



b



c



SOLUTION	EXPLANATION
a $a + 35 = 90$	Angles in a right angle add to 90°.
$a = 55$	$90 - 35 = 55$
b $a + 55 = 180$	Angles on a straight line add to 180°.
$a = 125$	$180 - 55 = 125$
c $a + 90 + 120 = 360$	The sum of angles in a revolution is 360°.
$a + 210 = 360$	Simplify by adding 90 and 120.
$a = 150$	a is the difference between 210 and 360°.

Exercise 2C


1–4 | 4 | —

UNDERSTANDING

1 **a** Measure the angles $a°$ and $b°$ in this diagram.

b Calculate $a + b$. Is your answer 90? If not, check your measurements.


c Write the missing word: $a°$ and $b°$ are _____ angles.



2 **a** Measure the angles $a°$ and $b°$ in this diagram.

b Calculate $a + b$. Is your answer 180? If not, check your measurements.

c Write the missing word: $a°$ and $b°$ are _____ angles.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


2C

UNDERSTANDING


3 **a** Measure the angles $a°$, $b°$, $c°$ and $d°$ in this diagram.

b What do you notice about the sum of the four angles?


c Write the missing words: $b°$ and $d°$ are _____ angles.




4 **a** Name the angle that is complementary to $\angle AOB$ in this diagram.



b Name the two angles that are supplementary to $\angle AOB$ in this diagram.



c Name the angle that is vertically opposite to $\angle AOB$ in this diagram.




FLUENCY

5, 6 | 5–6(½), 7, 8(½) | 5–8(½)


Example 4

5 Without using a protractor, find the value of the pronumeral a. (The diagrams shown may not be drawn to scale.)


a




b




c




d




e




f




g



h



i



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2C


FLUENCY

6 For each of the given pairs of angles, write C if they are complementary, S if they are supplementary or N if they are neither.


a 21°, 79° **b** 130°, 60° **c** 98°, 82° **d** 180°, 90°
e 17°, 73° **f** 31°, 59° **g** 68°, 22° **h** 93°, 87°

7 Write a statement like $AB \perp CD$ for these pairs of perpendicular line segments.


a



b




c




8 Without using a protractor, find the value of a in these diagrams.


a




b




c




d



e



f




9 | 9, 10(½) | 10, 11


PROBLEM-SOLVING

9 Do these diagrams have the correct information? Give reasons.


a




b




c




d



e



f




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2C


PROBLEM-SOLVING

10 Find the value of a in these diagrams.


a




b




c




d



e



f



11 A pizza is divided between four people. Bella is to get twice as much as Bobo, who gets twice as much as Rick, who gets twice as much as Marie. Assuming the pizza is cut into triangular pieces, find the angle at the centre of the pizza for Marie's piece.




12 | 12 | 12, 13


REASONING

12 Write down a rule connecting the letters in these diagrams, e.g. $a + b = 180$.


a



b



c



13 What is the minimum number of angles needed in this diagram to determine all other angles? Explain your answer.




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Pentagon turns — — 14

2C

ENRICHMENT

14 Consider walking around a path represented by this regular pentagon. All sides have the same length and all internal angles are equal. At each corner (vertex) you turn an angle of a, as marked.



a How many degrees would you turn in total after walking around the entire shape? Assume that you face the same direction at the end as you did at the start.

b Find the value of a.

c Find the value of b.

d Explore the outside and inside angles of other regular polygons using the same idea. Complete this table to summarise your results.


Regular shape	*a*	*b*
Triangle		
Square		
Pentagon		
Hexagon		
Heptagon		
Octagon		



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz


2A/B **1** Consider the diagram opposite and answer the following.




- **a** Name the point where the line EH intersects KF.
- **b** Name an angle which has its vertex at G.
- **c** Name an angle adjacent to $\angle FGH$.
- **d** Name a set of three concurrent lines.
- **e** Name an obtuse angle with its vertex at B and use your protractor to measure the size of this angle.

2C **2** Find the value of each pronumeral below and give a reason for each answer.


a




b




c




d




e




f




g




h




i




j




k



l



2B/C **3** Consider the following diagram and answer these questions.



- **a** Explain why $\angle ACB$ equals 56°.
- **b** What is the supplement of 146°?
- **c** Write down the value of $x + y + z$.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

2D Transversal lines and parallel lines

Interactive

Widgets

HOTsheets

Walkthroughs

When a line, called a transversal, cuts two or more other lines a number of angles are formed. Pairs of these angles are corresponding, alternate or cointerior angles, depending on their relative position. If the transversal cuts parallel lines, then there is a relationship between the sizes of the special pairs of angles that are formed.




Multiple angles are formed when this transversal road intersects with the freeway.

Let's start: What's formed by a transversal?

Draw a pair of parallel lines using either:

- two sides of a ruler; or
- computer geometry (parallel line tool).




Then cross the two lines with a third line (transversal) at any angle.


Measure each of the eight angles formed and discuss what you find. If computer geometry is used, drag the transversal and see if your observations apply to all the cases that you observe.

Key ideas


- A **transversal** is a line passing through two or more other lines that are usually, but not necessarily, parallel.




- A transversal crossing two lines will form special pairs of angles. These are:
  - **corresponding** (in corresponding positions)



  - **alternate** (on opposite sides of the transversal and inside the other two lines)




  - **cointerior** (on the same side of the transversal and inside the other two lines).



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Key ideas

- **Parallel lines** are marked with the same arrow set.
  - **Skew** lines are not parallel.
  - If AB is parallel to CD, then we write $AB \parallel CD$.




- If a transversal crosses two **parallel** lines then:
  - corresponding angles are equal
  - alternate angles are equal
  - cointerior angles are supplementary (i.e. sum to 180°).


corresponding



alternate



cointerior




$a + b = 180$ $a + b = 180$





Example 5 Naming pairs of angles

Name the angle that is:

a corresponding to $\angle ABF$ **b** alternate to $\angle ABF$

c cointerior to $\angle ABF$ **d** vertically opposite to $\angle ABF$




SOLUTION	EXPLANATION
a $\angle HFG$	
b $\angle EFB$	
c $\angle HFB$	
d $\angle CBD$	

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 6 Finding angles in parallel lines

Find the value of a in these diagrams and give a reason for each answer.


a



b



c




SOLUTION	EXPLANATION
a $a = 115$ alternate angles in parallel lines	Alternate angles in parallel lines are equal.
b $a = 55$ corresponding angles in parallel lines	Corresponding angles in parallel lines are equal.
c $a = 180 - 110$ $= 70$ cointerior angles in parallel lines	Cointerior angles in parallel lines sum to 180°.


Example 7 Proving lines are parallel

Giving reasons, state whether the two lines cut by the transversal are parallel.

a



b



SOLUTION	EXPLANATION
a not parallel Alternate angles are not equal.	Parallel lines have equal alternate angles.
b parallel The cointerior angles sum to 180°.	$122° + 58° = 180°$ Cointerior angles inside parallel lines are supplementary (i.e. sum to 180°).


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 2D

1–3	3	—


UNDERSTANDING

1 Use a protractor to measure each of the eight angles in this diagram.



- **a** How many *different* angle measurements did you find?
- **b** Do you think that the two lines cut by the transversal are parallel?

2 Use a protractor to measure each of the eight angles in this diagram.



- **a** How many *different* angle measurements did you find?
- **b** Do you think that the two lines cut by the transversal are parallel?

3 Choose the word *equal* or *supplementary* to complete these sentences.
If a transversal cuts two parallel lines, then:


- **a** alternate angles are _____.
- **b** cointerior angles are _____.
- **c** corresponding angles are _____.
- **d** vertically opposite angles are _____.

4–8	4, 6, 7(½), 8, 9	4, 7–9(½)

FLUENCY


Example 5

4 Name the angle that is:



- **a** corresponding to $\angle ABE$
- **b** alternate to $\angle ABE$
- **c** cointerior to $\angle ABE$
- **d** vertically opposite to $\angle ABE$

5 Name the angle that is:




- **a** corresponding to $\angle EBH$
- **b** alternate to $\angle EBH$
- **c** cointerior to $\angle EBH$
- **d** vertically opposite to $\angle EBH$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

6 Name an angle that is:

a corresponding to $\angle ACD$


b vertically opposite to $\angle ACD$




Example 6

7 Find the value of a in these diagrams, giving a reason.


a




b




c




d




e




f




g




h




i




j



k




l




8 Find the value of each unknown pronumeral in the following diagrams.


a




b




c




d



e



f



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


2D

Example 7


FLUENCY

9 Giving reasons, state whether the two lines cut by the transversal are parallel.


a




b




c




d



e



f




10–11(½) | 10–11(½), 12 | 11(½), 12, 13


PROBLEM-SOLVING

10 Find the value of a in these diagrams.


a




b




c




d



e




f




11 Find the value of a in these diagrams.


a




b




c




d



e



f




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


2D

PROBLEM-SOLVING


g



h



i




12 A transversal cuts a set of three parallel lines.

a How many angles are formed?

b How many angles of different sizes are formed if the transversal is *not* perpendicular to the three lines?

13 Two roads merge into a freeway at the same angle, as shown. Find the obtuse angle, a, between the parallel roads and the freeway.




14 | 14, 15 | 14–16

REASONING

14 This diagram includes two triangles with two sides that are parallel.


a Give a reason why:

i $a = 20$ **ii** $b = 45$




b Now find the values of a and b in the diagrams below.


i



ii



iii




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2D

REASONING


15 This shape is a parallelogram with two pairs of parallel sides.




- **a** Use the 60° angle to find the value of a and b.
- **b** Find the value of c.
- **c** What do you notice about the angles inside a parallelogram?

16 Explain why these diagrams do not contain a pair of parallel lines.


a



b




c



Adding parallel lines	—	—	17, 18


ENRICHMENT

17 Consider this triangle and parallel lines.



- **a** Giving a reason for your answer, name an angle equal to:
  - **i** $\angle ABD$
  - **ii** $\angle CBE$
- **b** What do you know about the three angles $\angle ABD$, $\angle DBE$ and $\angle CBE$?
- **c** What do these results tell you about the three inside angles of the triangle BDE. Is this true for any triangle? Try a new diagram to check.

18 Use the ideas explored in Question **17** to show that the angles inside a quadrilateral (i.e. a four-sided shape) must sum to 360°. Use this diagram to help.





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2E Problems with parallel lines

EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Parallel lines are at the foundation of construction in all its forms. Imagine the sorts of problems engineers and builders would face if drawings and constructions could not accurately use and apply parallel lines. Angles formed by intersecting beams would be difficult to calculate and could not be transferred to other parts of the building.




Parallel support beams in the foyer of Parliament House in Canberra

Let's start: Not so obvious

Some geometrical problems require a combination of two or more ideas before a solution can be found. This diagram includes the unknown angle $a°$.

- Discuss if it is possible to find the value of a.
- Describe the steps you would take to find the value of a. Discuss your reasons for each step.




Key ideas

■ Some geometrical problems involve more than one step.

Step 1: $\angle ABC = 75°$ (corresponding angles on parallel lines)

Step 2: $a = 360 - 75$ (angles in a revolution sum to 360°)


$= 285$




Example 8 Finding angles with two steps

Find the value of a in these diagrams.

a



b



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $\angle BDE = 360^\circ - 90^\circ - 170^\circ$ $= 100^\circ$ $\therefore\ a = 100$	Angles in a revolution add to 360°. $\angle ABC$ corresponds with $\angle BDE$, and BC and DE are parallel.
b $\angle ABC = 180^\circ - 70^\circ$ $= 110^\circ$ $\therefore\ a = 110 - 60$ $= 50$	$\angle ABC$ and $\angle BCD$ are cointerior angles, with AB and DC parallel. $\angle ABC = 110^\circ$ and $a^\circ + 60^\circ = 110^\circ$


Exercise 2E

1, 2 | 2 | —


UNDERSTANDING

1 In these diagrams, first find the value of a and then find the value of b.


a



b




c




2 Name the angle in these diagrams (e.g. $\angle ABC$) that you would need to find first before finding the value of a. Then find the value of a.


a



b



c





ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

3(½) 3(½) 3(½)


2E

FLUENCY


Example 8

3 Find the value of a in these diagrams.


a




b




c




d




e




f




g




h




i




j



k



l



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press


2E

4 | 4, 5 | 4, 5


PROBLEM-SOLVING

4 Find the size of $\angle ABC$ in these diagrams.


a




b




c




d



e




f




5 Find the value of x in each of these diagrams.


a



b



c




6 | 6, 7 | 7, 8


REASONING

6 What is the minimum number of angles you need to know to find all the angles marked in these diagrams?


a



b



c




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2E


REASONING

7 In these diagrams, the letter x represents a number and $2x$ means $2 \times x$. Find the value of x.


a




b




c




d



e




f




8 Find the value of a in these diagrams.


a



b



c




Adding parallel lines — — 9


ENRICHMENT

9 Find the value of a in these diagrams. You may wish to add one or more parallel lines to each diagram.


a




b




c




d



e



f



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F Circles and constructions

Interactive

Widgets

HOTsheets

Walkthroughs

One of the most important characteristics of a circle is that the distance from the centre to the circle, called the radius, is always the same. This fact is critical in the construction of geometrical diagrams and other objects that contain circular parts like gears and wheels.



Gears in a car's gearbox must be circular.


Let's start: Features of a circle

Here is a circle with some common features.

Which of the features (radius, diameter, chord or arc) would change in length if:


- point A is moved around the circle?
- point B is moved away from O so that the size of the circle changes?

If possible, try constructing this diagram using computer geometry. Measure lengths and drag the points to explore other possibilities.




Key ideas

- Common circle features include:
  - **centre** (point at an equal distance from all points on the circle)
  - **radius** (line interval joining the centre to a point on the circle. Plural: radii)
  - **chord** (line interval joining two points on the circle)
  - **diameter** (longest chord passing through the centre)
  - **arc** (part of a circle). It is possible for a circle to have either a minor or major arc.



- A pair of **compasses** (sometimes called a compass) and a **ruler** can be used to construct geometrical figures precisely.
- The word **bisect** means to cut in half.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Constructing an angle bisector

Use a pair of compasses and a ruler to bisect an angle $\angle AOB$ by following steps **a** to **e**.



a Draw and label an angle $\angle AOB$.

b Construct an arc with centre O so that it cuts OA at point C and OB at point D.

c With the same radius construct an arc with centre C and another with centre D. Ensure these arcs intersect at a point E.

d Mark in the ray OE.

e Measure $\angle AOE$ and $\angle DOE$. What do you notice?

SOLUTION	EXPLANATION
a, b 	First, draw an angle $\angle AOB$. The size of the angle is not important. Construct an arc using O as the centre to produce points C and D.
c, d 	Construct E so that the intersecting arcs have the same radius. Ray OE completes the construction.
e $\angle AOE = \angle BOE$	The angles are equal, so ray OE bisects $\angle AOB$.

Exercise 2F

1–3 | 3 | —

UNDERSTANDING

1 Use a pair of compasses and a ruler to draw a circle with a radius of about 3 cm. Then mark and label these features.

a centre O **b** two points, A and B, at any place on the circle

c radius OA **d** chord AB **e** minor arc AB

2 Use a ruler to draw a segment AB of length 6 cm and then complete the following.

a Construct a circle with radius 3 cm with centre A. (Use a ruler to help set the pair of compasses.)

b Construct a circle with radius 3 cm with centre B.


c Do your two circles miss, touch or overlap? Is this what you expected?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F

UNDERSTANDING

3 Use a ruler to draw a line segment, AB, of about 5 cm in length.




- **a** Using a pair of compasses, construct arcs with radius 4 cm, as shown, using:
  - **i** centre A **ii** centre B
- **b** Mark point C as shown and use a ruler to draw the segments:
  - **i** AC **ii** BC
- **c** Measure the angles $\angle BAC$ and $\angle ABC$. What do you notice?

4, 5 | 4–6 | 4–6

FLUENCY


Example 9

4 Follow steps **a** to **e** to construct a perpendicular line.




- **a** Draw a line segment, AB, of about 5 cm in length.
- **b** Construct overlapping circles of different sizes using the two centres A and B.
- **c** Mark the intersecting points of the circles and label these points C and D.
- **d** Draw the line CD and mark the intersection of line CD and segment AB with the point E.
- **e** Measure $\angle AEC$ with a protractor. What do you notice?

5 Follow steps **a** to **d** to construct a 60° angle.



- **a** Draw a line segment, AB, of about 5 cm in length.
- **b** Construct an arc with centre A and intersecting the segment AB at C.
- **c** With the same radius construct an arc with centre C and intersecting the first arc at D.
- **d** Draw the ray AD and measure $\angle BAD$. What do you notice?

6 Follow steps **a** to **e** to construct an angle bisector.



- **a** Draw any angle and label $\angle AOB$.
- **b** Construct an arc with centre O so that it cuts OA and OB at points C and D.
- **c** With the same radius, construct an arc with centre C and another with centre D. Ensure these arcs intersect at a point, E.
- **d** Mark in the ray OE.
- **e** Measure $\angle AOE$ and $\angle BOE$. What do you notice?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2F

PROBLEM-SOLVING

7, 7, 8, 8, 9

7 Consider the construction of the perpendicular line. (See the diagram in Question **4**.)

a Explain how to alter the construction so that the point E is the exact midpoint of the segment AB.

b If point E is at the centre of segment AB, then the line CD will be called the perpendicular bisector of segment AB. Complete the full construction to produce a perpendicular bisector.

8 Using the results from Questions **5** and **6**, explain how you could construct the angles below. Try each construction and then check each angle with a protractor.

a 30° **b** 15°

9 Show how you could construct these angles. After each construction, measure the angle using a protractor. (You may wish to use the results from Questions **4** and **6** for help.)

a 45° **b** 22.5°

REASONING

10, 10, 10, 11

10 Consider the construction of a perpendicular line. (See the diagram in Question **4**.) Do you think it is possible to construct a perpendicular line using circles with radii of any size? Explain.

11 The diagram in Question **6** shows an acute angle, $\angle AOB$.

a Do you think it is possible to bisect an obtuse angle? If so, show how.


b Do you think it is possible to bisect a reflex angle? If so, show how.

ENRICHMENT


No measurement allowed — — 12

12 Using only a pair of compasses and a ruler's edge, see if you can construct these objects. No measurement is allowed.

a Perpendicular line at the end point of a segment. Start with segment AB.




b Two parallel lines. Start with line AB.





c A square. Start with segment AB.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2G Dynamic geometry

Interactive

Widgets


HOTsheets

Walkthroughs

Dynamic computer geometry is an ideal tool for constructing geometrical figures. Constructing with dynamic geometry is like constructing with a ruler and a pair of compasses, but there is the added freedom to drag objects and explore different variations of the same construction. With dynamic geometry the focus is on 'construction' as opposed to 'drawing'. Although this is more of a challenge initially, the results are more precise and allow for greater exploration.

Let's start: The disappearing line

Use computer geometry to construct this figure starting with segment AB.




Add the line CD and check that it makes a right angle.

Drag the points A and B or increase the size of the circles.


Can you drag point A or B to make the line CD disappear? Why would this happen?

Key ideas

- Using dynamic geometry is like using a pair of compasses and a ruler.
- Objects can be dragged to explore different cases.



- Upon dragging, the geometrical construction should retain the desired properties.
- The same segment can be used to ensure two circles have exactly the same radius.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Constructing a 60° angle

Construct an angle of 60° using computer geometry. Then drag one of the starting points to check the construction.

SOLUTION



EXPLANATION

Step 1: Construct and label a segment AB.

Step 2: Construct two circles with radius AB and centres A and B.

Step 3: Mark the intersection C and draw the ray AC.

Step 4: Measure $\angle BAC$ to check.

Exercise 2G


1, 2 | 2 | —

UNDERSTANDING

1 **a** Use computer geometry to construct an angle $\angle ABC$. Any size will do.

b Mark and measure the angle using computer geometry. Drag the point A around B to enlarge the angle. See whether you can form all these types of angles.

i acute **ii** right **iii** straight
iv reflex **v** revolution



2 Look at the 60° angle construction in **Example 10**.

a Why do the two circles have exactly the same radius?

b What other common geometrical object could be easily constructed simply by adding one more segment?

3 | 3 | 3

FLUENCY

Example 10

3 Construct each of the following using dynamic geometry. If necessary, refer back to **Section 2F** and **Exercise 2F** to assist you. Check each construction by dragging one of the starting points. All desired properties should be retained.

a perpendicular line **b** perpendicular bisector
c 60° angle **d** angle bisector

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2G


4 | 4, 5 | 5, 6

PROBLEM-SOLVING

4 **a** Use the 'parallel line' tool to construct a pair of parallel lines and a transversal.
b Measure the eight angles formed.
c Drag the transversal to change the size of the angles. Check that:
i alternate angles are equal
ii corresponding angles are equal
iii cointerior angles are always supplementary

5 Use computer geometry to construct these angles. You may wish to use the 'angle bisector' shortcut tool.
a 30° **b** 15° **c** 45°

6 Use computer geometry to construct a six-pointed flower. Then drag one of the starting points to increase or decrease its size.



7 | 7, 8 | 7, 8

REASONING

7 **a** When using computer geometry it may be necessary to use a full circle instead of an arc. Explain why.
b When constructing a perpendicular bisector the starting segment *AB* is used as the radius of the circles. This is instead of two circles with different radii. Explain why.


8 Explain why geometrical construction is a precise process, whereas drawing using measurement is not.

Intricate designs

— | — | 9

ENRICHMENT

9 Sketch your own intricate design or use the internet to find a design that uses circles and lines. Use dynamic geometry to see if it is possible to precisely construct the design. Use colour to enhance your design.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation


The perfect billiard ball path

When a billiard ball bounces off a straight wall (with no side spin) we can assume that the angle at which it hits the wall (incoming angle) is the same as the angle at which it leaves the wall (outgoing angle). This is similar to how light reflects off a mirror.



Single bounce

Use a ruler and protractor to draw a diagram for each part and then answer the questions.




a Find the outgoing angle if:
- **i** the incoming angle is 30°
- **ii** the centre angle is 104°

b What geometrical reason did you use to calculate the answer to part **a ii** above?

Two bounces

Two bounces of a billiard ball on a rectangular table are shown here.



a Find the values of angles a, b, c, d and e, in that order. Give a reason for each.

b What can be said about the incoming angle on the first bounce and the outgoing angle on the second bounce? Give reasons for your answer.

c Accurately draw the path of two bounces using:
- **i** an initial incoming bounce of 20°
- **ii** an initial incoming bounce of 55°

More than two bounces

a Draw paths of billiard balls for more than two bounces starting at the midpoint of one side of a rectangular shape, using the starting incoming angles below.



- **i** 45°
- **ii** 30°

b Repeat part **a** but use different starting positions. Show accurate diagrams, using the same starting incoming angle but different starting positions.

c Summarise your findings of this investigation in a report that clearly explains what you have found. Show clear diagrams for each part of your report.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges




Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 What is the angle between the hour hand and minute hand of a clock at 9:35 am?




2 Two circles are the same size. The shaded circle rolls around the other circle. How many degrees will it turn before returning to its starting position?



3 Move three matchsticks to turn the fish to face the opposite direction.



4 A cube is shown with diagonals *BD* and *DG* marked. What is the size of angle *BDG*?



5 How many angles of different sizes can you form from joining dots in this 2 by 3 grid? One possible angle is shown for you. Do not count the 0° or 180° angle or reflex angles outside the grid.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Geometry


Measuring angles



Angles


acute $0° - 90°$
right $90°$
obtuse $90° - 180°$
straight $180°$
reflex $180° - 360°$
revolution $360°$

Angles at a point




Complementary
$a + b = 90$
Supplementary
$c + d = 180$
Vertically opposite
$a = c$
Revolution
$a + b + 90 + c + d = 360$

Geometrical objects




$\angle ABC$
ray BD
line EF
segment AB
collinear points B, C, D
vertex B

Circle features



Parallel lines




$a = b$ (corresponding)
$a = d$ (alternate)
$a + c = 180$ (cointerior)


If $a = 120$, $b = 120$, $d = 120$ and $c = 60$.

Constructions


angle bisector



perpendicular line



triangle



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review


Multiple-choice questions

2A **1** Three points are collinear if:

A they are at right angles
B they form a 60° angle
C they all lie in a straight line
D they are all at the same point
E they form an arc on a circle

2A **2** The angle shown here can be named:

A $\angle QRP$ **B** $\angle PQR$ **C** $\angle QPR$
D $\angle QRR$ **E** $\angle PQP$



2C **3** Complementary angles:


A sum to 180°
B sum to 270°
C sum to 360°
D sum to 90°
E sum to 45°

2B **4** A reflex angle is:

A 90°
B 180°
C between 180° and 360°
D between 0° and 90°
E between 90° and 180°

2B **5** What is the reading on this protractor?

A 15° **B** 30°
C 105° **D** 165°
E 195°



2B **6** The angle a minute hand on a clock turns in 20 minutes is:

A 72° **B** 36° **C** 18° **D** 144° **E** 120°

2D **7** If a transversal cuts two parallel lines, then:

A cointerior angles are equal
B alternate angles are supplementary
C corresponding angles are equal
D vertically opposite angles are supplementary
E supplementary angles add to 90°


2F **8** An angle bisector:

A cuts an angle in half
B cuts a segment in half
C cuts a line in half
D makes a 90° angle
E makes a 180° angle

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


2E **9** The value of a in this diagram is

A 115 **B** 75 **C** 60 **D** 55 **E** 65



2F **10** In this diagram, if line CD is to cut segment AB in half then:

A segment AB has to be 5 cm
B the radii of the arcs must be the same
C the radii of the arcs must not be the same
D line CD should be 10 cm
E AB should be a line not a segment




Short-answer questions

2A **1** Name each of these objects.

a




b



c



d



e




f




2B **2** For the angles shown, state the type of angle and measure its size using a protractor.


a



b



c



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Chapter review

2B **3** Find the angle between the hour and minute hands on a clock at the following times.


a 6:00 am **b** 9:00 pm **c** 3:00 pm **d** 5:00 am

2C **4** Without using a protractor, find the value of a in these diagrams.


a




b




c




d




e




f




g



h




i




2D **5** Using the pronumerals a, b, c or d given in the diagram, write down a pair of angles that are:

a vertically opposite
b cointerior
c alternate
d corresponding
e supplementary but not cointerior




2D **6** For each of the following, state whether the two lines cut by the transversal are parallel. Give reasons for each answer.


a



b




c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2D **7** Find the value of a in these diagrams.


a




b




c




d



e




f




2E **8** Find the size of $\angle ABC$ in these diagrams.


a



b




c




2F **9** Use the diagrams to help draw your own construction. You will need a pair of compasses and a ruler.

a angle bisector (start with any angle size).




b perpendicular line (start with a segment of about 6 cm in length).



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 A factory roof is made up of three sloping sections. The sloping sections are all parallel and the upright supports are at 90° to the horizontal, as shown. Each roof section makes a 32° angle (or pitch) with the horizontal.



a State the size of each of these angles.

i $\angle EAB$ **ii** $\angle GCD$ **iii** $\angle ABF$ **iv** $\angle EBF$

b Complete these sentences.

i $\angle BAE$ is _____ to $\angle CBF$.

ii $\angle FBC$ is _____ to $\angle GCB$.

iii $\angle BCG$ is _____ to $\angle GCD$.

c Solar panels are to be placed on the sloping roofs and it is decided that the angle to the horizontal is to be reduced by 11°. Find the size of these new angles.

i $\angle FBC$ **ii** $\angle FBA$ **iii** $\angle FCG$



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2 A circular birthday cake is cut into pieces of equal size, cutting from the centre outwards. Each cut has an angle of $a°$ at the centre.
Tanya's family takes four pieces. George's family takes three pieces.
Sienna's family takes two pieces. Anita's family takes two pieces.
Marcus takes one piece.

a How many pieces were taken all together?

b If there is no cake left after all the pieces are taken, find the value of a.

c Find the value of a if:

i half of the cake still remains

ii one-quarter of the cake still remains

iii one-third of the cake still remains

iv one-fifth of the cake still remains



ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

Chapter 3

Number properties and patterns

What you will learn

3A Factors and multiples (Consolidating)
3B Highest common factor and lowest common multiple (Consolidating)
3C Divisibility (Extending)
3D Prime numbers
3E Powers
3F Prime decomposition
3G Squares and square roots
3H Number patterns (Consolidating)
3I Spatial patterns
3J Tables and rules
3K The number plane and graphs

Australian curriculum

NUMBER AND ALGEBRA

Number and place value

Investigate index notation and represent whole numbers as products of powers of prime numbers (ACMNA149)

Investigate and use square roots of perfect square numbers (ACMNA150)

Linear and non-linear relationships

Given coordinates, plot points on the Cartesian plane, and find coordinates for a given point (ACMNA178)

Investigate, interpret and analyse graphs from authentic data (ACMNA180) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses



Number patterns around us: Architecture

The Louvre Palace in Paris is the world's largest museum and is visited by over 8 million people a year. Visitors enter the museum through a giant glass pyramid that has a square base of length 35.4 metres and is 21.6 metres in height. It is said that the pyramid contains 666 glass panels.

To carefully count the number of glass panels, we can observe how the sides of the pyramid are constructed. Each triangular side of the pyramid has 17 rows of rhombus-shaped glass panels. The base row is joined to the ground by triangular-shaped glass panels. The trapezium-shaped entry has a height of one rhombus and a width of six triangles. The number of glass panels used in the Louvre Pyramid can be determined using these facts and the related properties and patterns.

Each rhombus panel is supported by four segments of steel. Adjacent rhombuses share the ame steel segment for support. The number of steel segments per row can be calculated, as well as the total number of steel segments used.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

3A Factors and multiples CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Number patterns are fascinating. Factors and multiples are key building blocks for a broad field known as Number Theory. Many famous mathematicians have studied number patterns in an attempt to better understand our world and to assist with new scientific discoveries. Around 600 BCE, the Greeks built on the early work of the Egyptians and Babylonians. Thales of Miletus, the 'father of Greek mathematics', is credited for significant advances in Number Theory. One of his students, Pythagoras of Samos, went on to become one of the most well-known mathematicians to have lived. Pythagoras was primarily a religious leader, but he believed that the understanding of the world could be enhanced through the understanding of numbers. We start this chapter on Number Patterns by explaining the concepts of factors and multiples.



How many factors are there in a set of 12?

One dozen doughnuts are generally packed into bags with 3 rows of 4 doughnuts each. Since $3 \times 4 = 12$, we can say that 3 and 4 are **factors** of 12.

Purchasing 'multiple' packs of one dozen doughnuts could result in buying 24, 36, 48 or 60 doughnuts, depending on the number of packs. These numbers are known as **multiples** of 12.

Let's start: The most factors, the most multiples

Which number that is less than 100 has the most factors?

Which number that is less than 100 has the most multiples less than 100?

Key ideas

- **Factors** of a particular number are numbers that divide exactly into that number.
  - For example: The factors of 20 are pairs of numbers that multiply to give 20 which are 1×20, 2×10 and 4×5.
    Therefore, written in **ascending** order, the factors of 20 are 1, 2, 4, 5, 10, 20.
  - Every whole number is a factor of itself and also 1 is a factor of every whole number.
- **Multiples** of a particular number are numbers created by multiplying the particular number by any whole number.
  - For example: The multiples of 20 are 20, 40, 60, 80, 100, 120, …
    Multiples of 20 are also 480, 2000, 68 600. There is an infinite number of multiples!
- Given the statements above, it follows that factors are less than or equal to the particular number being considered and multiples are greater than or equal to the number being considered.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Finding factors

Find the complete set of factors for each of these numbers.

a 15 **b** 40

SOLUTION	EXPLANATION
a Factors of 15 are 1, 3, 5, 15.	$1 \times 15 = 15$, $3 \times 5 = 15$
b Factors of 40 are: 1, 2, 4, 5, 8, 10, 20, 40.	$1 \times 40 = 40$, $2 \times 20 = 40$ $4 \times 10 = 40$, $5 \times 8 = 40$ The last number you need to check is 7.

Example 2 Listing multiples

Write down the first six multiples for each of these numbers.

a 11 **b** 35

SOLUTION	EXPLANATION
a 11, 22, 33, 44, 55, 66	The first multiple is always the given number. Add on the given number to find the next multiple. Repeat this process to get more multiples.
b 35, 70, 105, 140, 175, 210	Start at 35, the given number, and repeatedly add 35 to continue producing multiples.

Example 3 Finding factor pairs

Express 195 as a product of two factors, both of which are greater than 10.

SOLUTION	EXPLANATION
$195 = 13 \times 15$	Systematically divide 195 by numbers greater than 10 in an attempt to find a large factor.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 3A

1–2 | 2 | —

UNDERSTANDING

1 For each of the following numbers, state whether they are factors (F), multiples (M) or neither (N) of the number 60.

a 120	**b** 14	**c** 15	**d** 40
e 6	**f** 5	**g** 240	**h** 2
i 22	**j** 600	**k** 70	**l** 1

2 For each of the following numbers, state whether they are factors (F), multiples (M) or neither (N) of the number 26.

a 2	**b** 54	**c** 52	**d** 4
e 210	**f** 27	**g** 3	**h** 182
i 1	**j** 26 000	**k** 13	**l** 39

3–5(½) | 3–6(½) | 3–6(½)

FLUENCY

Example 1

3 List the complete set of factors for each of the following numbers.

a 10	**b** 24	**c** 17
d 36	**e** 60	**f** 42
g 80	**h** 12	**i** 28

Example 2

4 Write down the first six multiples for each of the following numbers.

a 5	**b** 8	**c** 12
d 7	**e** 20	**f** 75
g 15	**h** 100	**i** 37

5 Fill in the gaps to complete the set of factors for each of the following numbers.

a 18 1, 2, __, 6, 9, __
b 25 1, __, 25
c 72 __, 2, 3, __, __, 8, __, __, 18, __, 36, 72
d 120 1, 2, __, __, __, 6, __, 10, __, __, 20, __, 30, __, 60, __

6 Which number is the incorrect multiple for each of the following sequences.

a 3, 6, 9, 12, 15, 18, 22, 24, 27, 30
b 43, 86, 129, 162, 215, 258, 301, 344
c 11, 21, 33, 44, 55, 66, 77, 88, 99, 110
d 17, 34, 51, 68, 85, 102, 117, 136, 153, 170

7–8 | 8–10 | 8–10

PROBLEM-SOLVING

7 Consider the set of whole numbers from 1 to 25 inclusive.

a Which number has the most factors?
b Which number has the fewest factors?
c Which numbers have an odd number of factors?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3

8 Express each of the following numbers as a product of two factors, both of which are greater than 10.

a 192 **b** 315 **c** 180
d 121 **e** 336 **f** 494

9 Zane and Matt are both keen runners. Zane takes 4 minutes to jog around a running track and Matt takes 5 minutes. They start at the same time and keep running until they both cross the finish line at the same time.

a How long do they run for?
b How many laps did Zane run?
c How many laps did Matt run?

10 Anson is preparing for his 12th birthday party. He has invited 12 friends and is making each of them a 'lolly bag' to take home after the party. To be fair, he wants to make sure that each friend has the same number of lollies. Anson has a total of 300 lollies to share among the lolly bags.



a How many lollies does Anson put in each of his friends' lolly bags?
b How many lollies does Anson have left over to eat himself?

Anson then decides that he wants a lolly bag for himself also.

c How many lollies will now go into each of the 13 lolly bags?

After much pleading from his siblings, Anson prepares lolly bags for them also. His sister Monique notices that the total number of lolly bags is now a factor of the total number of lollies.

d What are the different possible number of sibling(s) that Anson could have?
e How many siblings do you expect Anson has?

11 11–13 13–15

11 Are the following statements true or false?

a A multiple of a particular number is always smaller than that number.
b 2 is a factor of every even number.
c 3 is a factor of every odd number.
d A factor is always greater than or equal to the given number.
e When considering a particular number, that number is both a factor and a multiple of itself.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

3A

REASONING

12 60 is a number with many factors. It has a total of 12 factors and, interestingly, it has each of the numbers 1, 2, 3, 4, 5, 6 as a factor.

- **a** What would be the smallest number that could boast having 1, 2, 3, 4, 5, 6, 7 and 8 as factors?
- **b** What would be the smallest number that could boast having 1, 2, 3, 4, 5, 6, 7, 8, 9 and 10 as factors?

13 **a** What numbers can claim the number 100 to be a multiple?

- **b** What are the factors of 100?

14 All Australian AM radio stations have frequencies that are multiples of 9. For example, a particular radio station has a frequency of 774 (kilohertz or kHz). Find three other AM radio stations and show their frequencies are, indeed, multiples of 9.

15 Two numbers are chatting with one another when one number asks the other, 'Are you a multiple of mine?' The reply comes back, 'Well, I have always considered you to be one of my factors'. Explain why this response is enough to help the first number answer her question. Which number is the larger number?

ENRICHMENT

Factors and multiples with computers — — 16

16 **a** Design a spreadsheet that will enable a user to enter any number between 1 and 100 and it will automatically list the first 30 multiples of that number.

- **b** Design a spreadsheet that will enable a user to enter any particular number between 1 and 100 and it will automatically list the number's factors.
- **c** Improve your factor program so that it finds the sum of the factors and also states the total number of factors for the particular number.
- **d** Use your spreadsheet program to help you find a pair of **amicable numbers**. A pair of numbers is said to be amicable if the sum of the factors for each number, excluding the number itself, is equal to the other number. Each number that makes up the first such pair of amicable numbers falls between 200 and 300.
  An example of a non-amicable pair of numbers:
  12 – factor sum = 1 + 2 + 3 + 4 + 6 = 16
  16 – factor sum = 1 + 2 + 4 + 8 = 15
  The factor sum for 16 would need to be 12 for the pair to be amicable numbers.

  Helpful Excel formulas
  INT(number) – Rounds a number down to the nearest integer (whole number).
  MOD(number, divisor) – Returns the remainder after a number is divided by its divisor.
  IF(logical test, value if true, value if false) – Checks whether a condition is met and returns one value if true and another value if false.
  COUNTIF(range, criteria) – Counts the number of cells within a range that meet the given condition.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3B Highest common factor and lowest common multiple

CONSOLIDATING










In the previous exercise, factors and muliples of a number were explained. Remember that factors are less than or equal to a given number and that multiples are greater than or equal to a given number.



There are many applications in Mathematics for which the highest common factor (HCF) of two or more numbers must be determined. In particular, the skill of finding the HCF is required for the future topic of factorisation, which is an important aspect of Algebra.

Similarly, there are many occasions for which the lowest common multiple (LCM) of two or more numbers must be determined. Adding and subtracting fractions with different denominators requires the skill of finding the LCM.

Let's start: You provide the starting numbers!

For each of the following answers, you must determine possible starting numbers. On all occasions, the numbers involved are less than 100.

1 The HCF of two numbers is 12. Suggest two possible starting numbers.
2 The HCF of three numbers is 11. Suggest three possible starting numbers.
3 The LCM of two numbers is 30. Suggest two possible starting numbers.
4 The LCM of three numbers is 75. Suggest three possible starting numbers.
5 The HCF of four numbers is 1. Suggest four possible numbers.
6 The LCM of four numbers is 24. Suggest four possible numbers.



- **HCF** stands for **highest common factor**.
- As the name suggests, it refers to the highest (i.e. largest) factor that is common to the numbers provided in the question.
  - For example: Find the HCF of 24 and 40.
    Factors of 24 are 1, 2, 3, 4, 6, 8, 12 and 24.
    Factors of 40 are 1, 2, 4, 5, 8, 10, 20 and 40.
    Therefore, common factors of 24 and 40 are 1, 2, 4 and 8.
    Therefore, the highest common factor of 24 and 40 is 8.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **LCM** stands for **lowest common multiple**.
- As the name suggests, it refers to the lowest (i.e. smallest) multiple that is common to the numbers provided in the question.
  - For example: Find the LCM of 20 and 12.
    Multiples of 20 are 20, 40, 60, 80, 100, 120, 140, …
    Multiples of 12 are 12, 24, 36, 48, 60, 72, 84, 96, 108, 120, 132, …
    Therefore, common multiples of 20 and 12 are 60, 120, 180, …
    Therefore, the lowest common multiple of 20 and 12 is 60.
- The LCM of two numbers can always be found by multiplying the two numbers together and dividing by their HCF.
  - For example: Find the LCM of 20 and 12.
    The HCF of 20 and 12 is 4.
    Therefore, the LCM of 20 and 12 is $20 \times 12 \div 4 = 60$.

Example 4 Finding the highest common factor (HCF)

Find the highest common factor (HCF) of 36 and 48.

SOLUTION	EXPLANATION
Factors of 36 are: 1, 2, 3, 4, 6, 9, 12, 18 and 36.	$1 \times 36 = 36, 2 \times 18 = 36, 3 \times 12 = 36,$ $4 \times 9 = 36, 6 \times 6 = 36$
Factors of 48 are: 1, 2, 3, 4, 6, 8, 12, 16, 24 and 48.	$1 \times 48 = 48, 2 \times 24 = 48, 3 \times 16 = 48,$ $4 \times 12 = 48, 6 \times 8 = 48$
The HCF of 36 and 48 is 12.	Common factors are 1, 2, 3, 4, 6 and 12, of which 12 is the highest.

Example 5 Finding the lowest common multiple (LCM)

Find the lowest common multiple (LCM) of the following pairs of numbers.

a 5 and 11 **b** 6 and 10

SOLUTION	EXPLANATION
a The LCM of 5 and 11 is 55.	Note that the HCF of 5 and 11 is 1. $5 \times 11 \div 1 = 55$
b The LCM of 6 and 10 is 30.	Note that the HCF of 6 and 10 is 2. The LCM of 6 and 10 is $6 \times 10 \div 2 = 30$. Multiples of 6 are 6, 12, 18, 24, 30, 36, … Multiples of 10 are 10, 20, 30, 40, …

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 3B

1–4 | 4 | —

UNDERSTANDING

1 The factors of 12 are 1, 2, 3, 4, 6 and 12, and the factors of 16 are 1, 2, 4, 8 and 16.
- **a** What are the common factors of 12 and 16?
- **b** What is the HCF of 12 and 16?

2 Fill in the missing numbers to find out the HCF of 18 and 30.
Factors of 18 are 1, __, 3, __, __ and 18.
Factors of __ are 1, __, __, 5, __, 10, __ and 30.
Therefore, the HCF of 18 and 30 is __.

3 The first 10 multiples of 8 are 8, 16, 24, 32, 40, 48, 56, 64, 72 and 80.
The first 10 multiples of 6 are 6, 12, 18, 24, 30, 36, 42, 48, 54 and 60.
- **a** What are two common multiples of 8 and 6?
- **b** What is the LCM of 8 and 6?

4 Fill in the missing numbers to find out the LCM of 9 and 15.
Multiples of 9 are 9, 18, __, 36, __, __, __, __, 81 and __.
Multiples of 15 are __, 30, __, 60, 75, __, __ and 120.
Therefore, the LCM of 9 and 15 is __.

5–8(½) | 5–9(½) | 5–9(½)

FLUENCY

Example 4

5 Find the HCF of the following pairs of numbers.

a 4 and 5	**b** 8 and 13	**c** 2 and 12	**d** 3 and 15
e 16 and 20	**f** 15 and 60	**g** 50 and 150	**h** 48 and 72
i 80 and 120	**j** 75 and 125	**k** 42 and 63	**l** 28 and 42

6 Find the HCF of the following groups of numbers.

a 20, 40, 50	**b** 6, 15, 42	**c** 50, 100, 81
d 18, 13, 21	**e** 24, 72, 16	**f** 120, 84, 144

Example 5

7 Find the LCM of the following pairs of numbers.

a 4 and 9	**b** 3 and 7	**c** 12 and 5
d 10 and 11	**e** 4 and 6	**f** 5 and 10
g 12 and 18	**h** 6 and 9	**i** 20 and 30
j 12 and 16	**k** 44 and 12	**l** 21 and 35

8 Find the LCM of the following groups of numbers.

a 2, 3, 5	**b** 3, 4, 7	**c** 2, 3, 4
d 3, 5, 9	**e** 4, 5, 8, 10	**f** 6, 12, 18, 3

9 Find the HCF of the following pairs of numbers and then use this information to help calculate the LCM of the same pair of numbers.

a 15 and 20	**b** 12 and 24	**c** 14 and 21	**d** 45 and 27

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3B

PROBLEM-SOLVING

10, 11 | 11, 12 | 11–13

10 Find the LCM of 13 and 24.

11 Find the HCF of 45 and 72.

12 Find the LCM and HCF of 260 and 390.

13 Andrew runs laps of 'the circuit' in 4 minutes. Bryan runs laps of the same circuit in 3 minutes. Chris can run laps of the same circuit in 6 minutes. They all start together on the starting line and run a 'race' that goes for 36 minutes.

- **a** What is the first time, after the start, that they will all cross over the starting line together?
- **b** How many laps will each boy complete in the race?
- **c** How many times does Bryan overtake Andrew during this race?



REASONING

14 | 14, 15 | 15, 16

14 Given that the HCF of a pair of different numbers is 8, find the two numbers:

- **a** if both numbers are less than 20
- **b** when one number is in the 20s and the other in the 30s

15 Given that the LCM of a pair of different numbers is 20, find the seven possible pairs of numbers.

16 The rule for finding the LCM of two numbers x and y is $\frac{x \times y}{\text{HCF}\ (x, y)}$. Is the rule for the LCM of three numbers x, y and z $\frac{x \times y \times z}{\text{HCF}\ (x, y, z)}$?

ENRICHMENT

LCM of large groups of numbers

— | — | 17

17 **a** Find the LCM of these single-digit numbers: 1, 2, 3, 4, 5, 6, 7, 8, 9.

- **b** Find the LCM of these first 10 natural numbers: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10.
- **c** Compare your answers to parts **a** and **b**. What do you notice? Explain.
- **d** Find the LCM of the first 11 natural numbers.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3C Divisibility EXTENDING









It is useful to know whether a large number is exactly divisible by another number. Although we can always carry out the division algorithm, this can be a difficult and tedious process for large numbers. There are simple divisibility tests for each of the single-digit numbers, with the exception of 7. These divisibility tests determine whether or not the number is divisible by the chosen divisor.

Let's start: Five questions in 5 minutes


In small groups, attempt to solve the following five questions in 5 minutes.

1. Some numbers are only divisible by 1 and themselves. What are these numbers called?
2. Is 21 541 837 divisible by 3?
3. What two-digit number is the 'most divisible' (i.e. has the most factors)?
4. Find the smallest number that is divisible by 1, 2, 3, 4, 5 and 6.
5. Find a number that is divisible by 1, 2, 3, 4, 5, 6, 7 and 8.

Key ideas

- A number is said to be **divisible** by another number if there is **no remainder** after the division has occurred.
- If the **divisor** divides into the **dividend** exactly, then the divisor is said to be a **factor** of that number.
- **Division notation**

  Example: $27 \div 4 = 6$ remainder 3

  Another way of representing this information is $27 = 4 \times 6 + 3$.
- **Key terms**

Dividend	The starting number; the total; the amount you have
Divisor	The number doing the dividing; the number of groups
Quotient	The number of times the divisor went into the dividend, also known as 'the answer'
Remainder	The number left over; the number remaining (sometimes written as 'rem.')

- **Divisibility tests**
  1. All numbers are divisible by 1.
  2. All even numbers are divisible by 2. Last digit must be a 0, 2, 4, 6 or 8.
  3. The sum of the digits must be divisible by 3.
  4. The number formed from the last two digits must be divisible by 4.
  5. The last digit must be a 0 or 5.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas

6 Must pass the divisibility tests for 2 and 3.
7 There is no easy divisibility test for the numeral 7.
8 The number formed from the last three digits must be divisible by 8.
9 The sum of the digits must be divisible by 9.
10 The last digit must be 0.

Example 6 Applying divisibility tests

Determine whether or not the following calculations are possible without leaving a remainder.

a $54\,327 \div 3$

b $765\,146 \div 8$

SOLUTION

a Digit sum = 21
Yes, 54 327 is divisible by 3.

b $8\overline{)146}$ rem. 2 (18)
No, 765 146 is not divisible by 8.

EXPLANATION

$5 + 4 + 3 + 2 + 7 = 21$
21 is divisible by 3.

Check whether the last three digits are divisible by 8.

Example 7 Testing divisibility

Carry out divisibility tests on the given number and fill in the table with ticks or crosses.

Number	Divisible by 2	Divisible by 3	Divisible by 4	Divisible by 5	Divisible by 6	Divisible by 8	Divisible by 9	Divisible by 10
48 569 412								

SOLUTION

Number	Divisible by 2	Divisible by 3	Divisible by 4	Divisible by 5	Divisible by 6	Divisible by 8	Divisible by 9	Divisible by 10
48 569 412	☑	☑	☑	✗	☑	✗	✗	✗

EXPLANATION

48 569 412 is an even number and therefore is divisible by 2.
48 569 412 has a digit sum of 39 and therefore is divisible by 3, but not by 9.
48 569 412 is divisible by 2 and 3, therefore it is divisible by 6.
The last two digits are 12, which is divisible by 4.
The last three digits are 412, which is not divisible by 8.
The last digit is a 2 and therefore is not divisible by 5 or 10.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 3C

1–4 | 4 | —

UNDERSTANDING

1 Give a reason why:

a 8631 is not divisible by 2
b 31 313 is not divisible by 3
c 426 is not divisible by 4
d 5044 is not divisible by 5
e 87 548 is not divisible by 6
f 214 125 is not divisible by 8
g 3 333 333 is not divisible by 9
h 56 405 is not divisible by 10

2 Give the remainder when:

a 326 is divided by 3
b 21 154 is divided into groups of four
c 72 is divided into six groups
d 45 675 is shared into five groups

3 Which three divisibility tests involve calculating the sum of the digits?

4 If you saw only the last digit of a 10-digit number, which three divisibility tests (apart from 1) could you still apply?

5–7 | 5–6(½), 7 | 5–6(½), 7

FLUENCY

Example 6

5 **a** Determine whether the following calculations are possible without leaving a remainder.

i 23 562 ÷ 3
ii 39 245 678 ÷ 4
iii 1 295 676 ÷ 9
iv 213 456 ÷ 8
v 3 193 457 ÷ 6
vi 2 000 340 ÷ 10
vii 51 345 678 ÷ 5
viii 215 364 ÷ 6
ix 9543 ÷ 6
x 25 756 ÷ 2
xi 56 789 ÷ 9
xii 324 534 565 ÷ 5
xiii 2 345 176 ÷ 8
xiv 329 541 ÷ 10
xv 225 329 ÷ 3
xvi 356 781 276 ÷ 9
xvii 164 567 ÷ 8
xviii 2 002 002 002 ÷ 4

b Repeat the process using a calculator. Which way is quicker?

6 Write down five two-digit numbers that are divisible by:

a 5
b 3
c 2
d 6
e 8
f 9
g 10
h 4

Example 7

7 Carry out divisibility tests on the given numbers and fill in the table with ticks or crosses.

Number	Divisible by 2	Divisible by 3	Divisible by 4	Divisible by 5	Divisible by 6	Divisible by 8	Divisible by 9	Divisible by 10
243 567								
28 080								
189 000								
1 308 150								
1 062 347								

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3C

8, 9 | 9–11 | 11–13

PROBLEM-SOLVING

8 **a** Can Julie share $41.75 equally among her three children?

b Julie finds one more dollar on the floor and realises that she can now share the money equally among her three children. How much do they each receive?



9 The game of 'clusters' involves a group getting into smaller-sized groups as quickly as possible once a particular cluster size has been called out. If a year level consists of 88 students, which 'cluster' sizes would ensure no students are left out of a group?

10 How many of the whole numbers between 1 and 250 inclusive are not divisible by 5?

11 How many two-digit numbers are divisible by 2 and 3?

12 Find the largest three-digit number that is divisible by both 4 and 5.

13 Find the largest three-digit number that is divisible by both 6 and 7.

14 | 14, 15 | 15–17

REASONING

14 **a** Is the number 968 362 396 392 139 963 359 divisible by 3?

b Many of the digits in the number above can actually be ignored when calculating the digit sum. Which numbers can be ignored and why?

c To determine if the number above is divisible by 3, only five of the 21 digits actually need to be added together. Find this 'reduced' digit sum.

15 The divisibility test for the numeral 4 is to consider whether the number formed by the last two digits is a multiple of 4. Complete the following sentences to make a more detailed divisibility rule.

a If the second-last digit is even, the last digit must be either a ___, ___or ___.

b If the second-last digit is odd, the last digit must be either a ___or ___.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3C

REASONING

16 Blake's age is a two-digit number. It is divisible by 2, 3, 6 and 9. How old is Blake if you know that he is older than 20 but younger than 50?



17 Find the smallest number that satisfies each of the conditions below. The number must be larger than the divisor and leave:

- **a** a remainder of 5 when divided by 6
- **b** a remainder of 4 when divided by 5
- **c** a remainder of 3 when divided by 4
- **d** a remainder of 2 when divided by 3
- **e** a remainder of 1 when divided by 2

ENRICHMENT

Divisible by 11? — — 18

18 **a** Write down the first nine multiples of the numeral 11.

- **b** What is the difference between the two digits for each of these multiples?
- **c** Write down some three-digit multiples of 11.
- **d** What do you notice about the sum of the first digit and the last digit?

The following four-digit numbers are all divisible by 11:
1606, 2717, 6457, 9251, 9306

- **e** Find the sum of the odd-placed digits and the sum of the even-placed digits. Then subtract the smaller sum from the larger. What do you notice?
- **f** Write down a divisibility rule for the number 11.
- **g** Which of the following numbers are divisible by 11?

i 2 594 669 **ii** 45 384 559 **iii** 488 220
iv 14 641 **v** 1 358 024 679 **vi** 123 456 789 987 654 321

An alternative method is to alternate adding and subtracting each of the digits.
For example: 4 134 509 742 is divisible by 11.
Alternately adding and subtracting the digits will give the following result:

$$4 - 1 + 3 - 4 + 5 - 0 + 9 - 7 + 4 - 2 = 11$$

- **h** Try this technique on some of your earlier numbers.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3D Prime numbers









It is believed that prime numbers (i.e. positive whole numbers with two factors) were first studied by the ancient Greeks. More recently, the introduction of computers has allowed for huge developments in this field. Computers have allowed mathematicians to determine which large numbers are primes. Programs have also been written to automatically generate huge prime numbers that could not be calculated previously by hand.

There continues to be much debate as to whether or not 1 is a prime number. The current thinking is that 1 should not be considered a prime number, the basic reason being that it does not have two distinct factors.


Computers allow mathematicians to examine and work with extremely large numbers.

Remarkable fact: There are some interesting prime numbers that have patterns in their digits; for example, 12 345 678 901 234 567 891. This is known as an ascending prime.

You can also get palindromic primes, such as 111 191 111 and 123 494 321.

Below is a palindromic prime number that reads the same upside down or when viewed in a mirror.

$$|88808|80888|$$

Let's start: How many primes?

How many numbers from 1 to 100 are prime?

You and a classmate have 4 minutes to come up with your answer.

Key ideas

- A **prime number** is a positive whole number that has only two factors: 1 and itself.
- A number that has more than two factors is called a **composite number**.
- 0 and 1 are neither prime nor composite numbers.



Example 8 Determining whether a number is a prime or composite

State whether each of these numbers is a prime or composite: 22, 35, 17, 11, 9, 5.

SOLUTION	EXPLANATION
Prime: 5, 11, 17	5, 11, 17 have only two factors (1 and itself).
Composite: 9, 22, 35	$9 = 3 \times 3, 22 = 2 \times 11, 35 = 5 \times 7$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Finding prime factors

Find the prime numbers that are factors of 30.

SOLUTION	EXPLANATION
Factors of 30 are: 1, 2, 3, 5, 6, 10, 15, 30	Find the entire set of factors first.
Prime numbers from this list of factors are 2, 3 and 5.	Determine which factors are prime according to the given definition.

Exercise 3D

1–6 | 4, 6 | —

UNDERSTANDING

1 The factors of 12 are 1, 2, 3, 4, 6 and 12. Is 12 a prime number?

2 The factors of 13 are 1 and 13. Is 13 a prime number?

3 List the first 10 prime numbers.

4 List the first 10 composite numbers.

5 What is the first prime number greater than 100?

6 What is the first prime number greater than 200?

7(½), 8 | 7(½), 8, 9 | 7–8(½), 9

FLUENCY

Example 8

7 State whether each of the following is a prime (P) or composite (C) number.

a 14	b 23	c 70	d 37
e 51	f 27	g 29	h 3
i 8	j 49	k 99	l 59
m 2	n 31	o 39	p 89

Example 9

8 Find the prime numbers that are factors of:

a 42	b 39	c 60
d 25	e 28	f 36

9 List the composite numbers between:

a 30 and 50	b 50 and 70	c 80 and 100

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3D

10	11, 12	11–13

PROBLEM-SOLVING

10 The following are not prime numbers, yet they are the product (×) of two primes. Find the two primes for each of the following numbers.

a 55 **b** 91 **c** 143
d 187 **e** 365 **f** 133

11 Which one of these numbers has factors that are only prime numbers, itself and 1?
12, 14, 16, 18, 20

12 Twin primes are pairs of primes that are separated from each other by only one even number; for example, 3 and 5 are twin primes. Find three more pairs of twin primes.

13 13 and 31 are known as a pair of 'reverse numbers'. They are also both prime numbers. Find any other two-digit pairs of prime reverse numbers.

14	14, 15	15, 16

REASONING

14 Find three different prime numbers that are less than 100 and which sum to a fourth different prime number. Can you find more than five sets of such numbers?

15 Many mathematicians believe that every even number greater than 2 is the sum of two prime numbers. Show this is true for even numbers between 30 and 50.

16 Give two examples of a pair of primes that add to a prime number. Explain why all possible pairs of primes that add to a prime must contain the number 2.

Prime or not prime?

—	—	17

ENRICHMENT

17 Design a spreadsheet that will check whether or not any number entered between 1 and 1000 is a prime number.
If your spreadsheet is successful, someone should be able to enter the number 773 and very quickly be informed whether or not this is a prime number.
You may choose to adapt your factor program (Enrichment activity **Exercise 3A**, Question **16**).



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3E Powers



When repeated multiplication of the same factor occurs, the expression can look quite cumbersome. Mathematicians have a method for simplifying such expressions by writing them as **powers**. This involves writing the repeated factor as the base number and then including an index number to indicate how many times this factor must be multiplied by itself. This is also known as writing a number in **index form**.

Powers are also used to represent very large and very small numbers. For example, 400 000 000 000 000 would be written as 4×10^{14}. This way of writing a number is called standard form or scientific notation, and you will come across this concept in future years.


Let's start: A better way…

- What is a better way of writing $2 + 2 + 2 + 2 + 2 + 2 + 2 + 2 + 2 + 2 + 2 + 2$ (that is not the answer, 20)?
- What is a better way of writing $2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2 \times 2$ (that is not the answer, 1024)?

You may need to access the internet to find out some of the following answers.

Computers have the capacity to store a lot of information. As you most likely know, computer memory is given in bytes.

- How many bytes (B) are in a kilobyte (kB)?
- How many kilobytes are in a megabyte (MB)?
- How many megabytes are in a gigabyte (GB)?
- How many gigabytes are in a terabyte (TB)?
- How many bytes are in a gigabyte?
  Hint: It is over 1 billion and it is far easier to write this number as a power!
- Why do computers frequently use base 2 (binary numbers)?



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Powers** are used to help write expressions involving repeated multiplication in a simplified form using indices
  For example: $8 \times 8 \times 8 \times 8 \times 8$ can be written as 8^5
- When writing a **basic numeral** as a power, you need a base number and an index number. This is also known as writing an expression in **index form**.

index number

$8^5 = 32\,768$

base number — basic numeral

- a^b reads as 'a to the power of b'. In expanded form it would look like:

$$\underbrace{a \times a \times a \times a \times a \ldots\ldots \times a}_{a \text{ is repeated } b \text{ times}}$$

- Powers take priority in the order of operations.
  For example: $3 + 2 \times 4^2 = 3 + 2 \times 16$
  $= 3 + 32$
  $= 35$
- Note: $2^3 \neq 2 \times 3$, therefore $2^3 \neq 6$. This is a common mistake that must be avoided.
  Instead: $2^3 = 2 \times 2 \times 2 = 8$.

Example 10 Converting to index form

Simplify the following expressions by writing them in index form.

a $5 \times 5 \times 5 \times 5 \times 5 \times 5$ **b** $3 \times 3 \times 2 \times 3 \times 2 \times 3$

SOLUTION	EXPLANATION
a $5 \times 5 \times 5 \times 5 \times 5 \times 5 = 5^6$	The number 5 is the repeated factor and it appears six times.
b $3 \times 3 \times 2 \times 3 \times 2 \times 3 = 2^2 \times 3^4$	2 is written two times. 3 is written four times.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Expanding a power

Expand and evaluate the following terms.

a 2^4 **b** $2^3 \times 5^2$

SOLUTION	EXPLANATION
a $2^4 = 2 \times 2 \times 2 \times 2$ $= 16$	Write 2 down four times and multiply.
b $2^3 \times 5^2 = 2 \times 2 \times 2 \times 5 \times 5$ $= 8 \times 25$ $= 200$	Write the number 2 three times, and the number 5, two times.

Example 12 Evaluating expressions with powers

Evaluate:

a $7^2 - 6^2$ **b** $2 \times 3^3 + 10^2 + 1^7$

SOLUTION	EXPLANATION
a $7^2 - 6^2 = 7 \times 7 - 6 \times 6$ $= 49 - 36$ $= 13$	Write in expanded form (optional). Powers are evaluated before the subtraction occurs.
b $2 \times 3^3 + 10^2 + 1^7$ $= 2 \times 3 \times 3 \times 3 + 10 \times 10 + 1 \times 1 \times 1$ $\times 1 \times 1 \times 1 \times 1$ $= 54 + 100 + 1$ $= 155$	Write in expanded form (optional). Follow order of operation rules. Carry out the multiplication first, then carry out the addition.

Exercise 3E

1–3 | 3 | —

UNDERSTANDING

1 Select the correct answer from the following alternatives.
3^7 means:

A 3×7 **B** $3 \times 3 \times 3$ **C** $7 \times 7 \times 7$
D $3 \times 7 \times 3 \times 7 \times 3 \times 7 \times 3$ **E** $3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3$ **F** 37

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

3E

UNDERSTANDING

2 Select the correct answer from the following alternatives.
$9 \times 9 \times 9 \times 9 \times 9$ can be simplified to:

A 9×5 **B** 5×9 **C** 5^9
D 9^5 **E** 99 999 **F** 95

3 Copy and complete the table.

Index form	Base number	Index number	Basic numeral
2^3	2	3	8
5^2			
10^4			
2^7			
1^{12}			
12^1			
0^5			

FLUENCY

4–5(½), 6, 7–10(½) 4–5(½), 6, 7–10(½) 4–5(½), 6, 7–10(½)

Example 10a **4** Simplify the following expressions by writing them as powers.

a $3 \times 3 \times 3$ **b** $2 \times 2 \times 2 \times 2 \times 2$ **c** $15 \times 15 \times 15 \times 15$
d $10 \times 10 \times 10 \times 10$ **e** 6×6 **f** $20 \times 20 \times 20$
g $1 \times 1 \times 1 \times 1 \times 1 \times 1$ **h** $4 \times 4 \times 4$ **i** 100×100

Example 10b **5** Simplify the following expressions by writing them as powers.

a $3 \times 3 \times 5 \times 5$ **b** $7 \times 7 \times 2 \times 2 \times 7$ **c** $12 \times 9 \times 9 \times 12$
d $8 \times 8 \times 5 \times 5 \times 5$ **e** $6 \times 3 \times 6 \times 3 \times 6 \times 3$ **f** $13 \times 7 \times 13 \times 7 \times 7 \times 7$
g $4 \times 13 \times 4 \times 4 \times 7$ **h** $10 \times 9 \times 10 \times 9 \times 9$ **i** $2 \times 3 \times 5 \times 5 \times 3 \times 2 \times 2$

6 Simplify by writing using powers.
$2 \times 3 \times 5 \times 5 \times 3 \times 3 \times 2 \times 2 \times 2 \times 5 \times 3 \times 2 \times 2 \times 5 \times 3$

Example 11a **7** Expand these terms. (Do not evaluate.)

a 2^4 **b** 17^2 **c** 9^3 **d** 3^7
e 14^4 **f** 8^8 **g** 10^5 **h** 54^3

Example 11b **8** Expand these terms. (Do not evaluate.)

a $3^5 \times 2^3$ **b** $4^3 \times 3^4$ **c** $7^2 \times 5^3$ **d** $4^6 \times 9^3$
e 5×7^4 **f** $2^2 \times 3^3 \times 4^1$ **g** $11^5 \times 9^2$ **h** $20^3 \times 30^2$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3E

FLUENCY

9 Evaluate:

a 2^5 **b** 8^2 **c** 10^3 **d** $3^2 \times 2^3$

e 10^4 **f** $2^3 \times 5^3$ **g** $1^6 \times 2^6$ **h** $11^2 \times 1^8$

Example 12

10 Evaluate:

a $3^2 + 4^2$ **b** $2 \times 5^2 - 7^2$ **c** $8^2 - 2 \times 3^3$

d $(9-5)^3$ **e** $2^4 \times 2^3$ **f** $2^7 - 1 \times 2 \times 3 \times 4 \times 5$

g $1^4 + 2^3 + 3^2 + 4^1$ **h** $10^3 - 10^2$ **i** $(1^{27} + 1^{23}) \times 2^2$

11, 12 12, 13 12–14

PROBLEM-SOLVING

11 Determine the index number for the following basic numerals.

a $16 = 2^?$ **b** $16 = 4^?$ **c** $64 = 4^?$ **d** $64 = 2^?$

e $27 = 3^?$ **f** $100 = 10^?$ **g** $49 = 7^?$ **h** $625 = 5^?$

12 Write one of the symbols <, = or > in the box to make the following statements true.

a $2^6 \square 2^9$ **b** $8^3 \square 8^2$ **c** $2^4 \square 4^2$ **d** $3^2 \square 4^2$

e $6^4 \square 5^3$ **f** $12^2 \square 3^4$ **g** $11^2 \square 2^7$ **h** $1^8 \square 2^3$

13 A text message is sent to five friends. Each of the five friends then forwards it to five other friends and each of these people also sends it to five other friends. How many people does the text message reach, not including those who forwarded the message?

14 Jane writes a chain email and sends it to five friends. If each person who receives the email reads it within 5 minutes of the email arriving and then sends it to five other people:

a How many people, including Jane, will have read the email 15 minutes after Jane first sent it?

b If the email always goes to a new person, and assuming every person in Australia has an email address and access to email, how long would it take until everyone in Australia has read the message? (Australian population is approx. 25 million people.)

c How many people will read the email within 1 hour?

d Using the same assumptions as above, how long would it take until everyone in the world has read the message? (World population is approx. 7 billion people.)

e How many people will have read the email in 2 hours?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3E

15 | 15, 16 | 16, 17

REASONING

15 Write the correct operation (+, −, ×, ÷) in the box to make the following equations true.

a $3^2 \square 4^2 = 5^2$ **b** $2^4 \square 4^2 = 4^4$ **c** $2^7 \square 5^3 = 3^1$

d $9^2 \square 3^4 = 1^{20}$ **e** $10^2 \square 10^2 = 10^4$ **f** $10^2 \square 8^2 = 6^2$

16 A chain email is initiated by an individual and sent to x number of recipients. This process is repeated (i.e. is forwarded to x new recipients) y times including the first sending. How many people receive the email, not including those who forwarded the message?



17 Find a value for a and for b such that $a \neq b$ and $a^b = b^a$.

Investigating factorials

— | — | 18

ENRICHMENT

18 In mathematics, the exclamation mark (!) is the symbol for factorials.

$4! = 4 \times 3 \times 2 \times 1 = 24$

$n! = n \times (n-1) \times (n-2) \times (n-3) \times (n-4) \times \ldots \times 6 \times 5 \times 4 \times 3 \times 2 \times 1$

a Evaluate 1!, 2!, 3!, 4!, 5! and 6!

Factorials can be written in prime factor form, which involves powers.

For example: $6! = 6 \times 5 \times 4 \times 3 \times 2 \times 1$

$= (2 \times 3) \times 5 \times (2 \times 2) \times 3 \times 2 \times 1$

$= 2^4 \times 3^2 \times 5$

b Write these numbers in prime factor form.

i 7! **ii** 8! **iii** 9! **iv** 10!

c Write down the last digit of 12!

d Write down the last digit of 99!

e Find a method of working out how many consecutive zeros would occur on the right-hand end of each of the following factorials if they were evaluated. Hint: Consider prime factor form.

i 5! **ii** 6! **iii** 15! **iv** 25!

f $10! = 3! \times 5! \times 7!$ is an example of one factorial equal to the product of three factorials. Express 24! as the product of two or more factorials.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F Prime decomposition

Interactive

Widgets

HOTsheets

Walkthroughs

All composite numbers can be broken down (i.e. decomposed) into a unique set of prime factors. A common way of performing the decomposition into prime factors is using a factor tree. Starting with the given number, 'branches' come down in pairs, representing a pair of factors that multiply to give the number above it.This process continues until prime factors are reached.

Let's start: Composition of numbers from prime factors


'Compose' composite numbers from the following sets of prime factors. The first one has been done for you.

a $2 \times 3 \times 5 = 30$
b $2 \times 3 \times 7 \times 3 \times 2$
c $3^2 \times 2^3$
d $5 \times 11 \times 2^2$
e $13 \times 17 \times 2$
f $2^2 \times 5^2 \times 7^2$
g $2^5 \times 3^4 \times 7$
h $11 \times 13 \times 17$

Note that this process is the reverse of **decomposition**.

Key ideas

- Every **composite number** can be expressed as a product of its **prime factors**.
- A **factor tree** can be used to show the prime factors of a composite number.
- Each 'branch' of a factor tree eventually terminates in a prime factor.
- Powers are often used to efficiently represent composite numbers in prime factor form.
  For example:



$\therefore 48 = 2 \times 2 \times 2 \times 2 \times 3$
$= 2^4 \times 3$ ← expressed with powers


- It does not matter with which pair of factors you start a factor tree. The final result of prime factors will always be the same.
- It is conventional to write the prime factors in **ascending** (i.e. increasing) order.
  For example: $600 = 2^3 \times 3 \times 5^2$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 13 Expressing composites in prime factor form

Express the number 60 in prime factor form.

SOLUTION



$\therefore\ 60 = 2 \times 2 \times 3 \times 5$

$60 = 2^2 \times 3 \times 5$

EXPLANATION

A pair of factors for 60 are 5×12.

The 5 branch terminates since 5 is a prime factor.

A pair of factors for 12 are 3×4.

The 3 branch terminates since 3 is a prime factor.

A pair of factors for 4 are 2×2.

Both these branches are now terminated.

Hence, the composite number, 60, can be written as a product of each terminating branch.

Exercise 3F


1–4 | 4 | —

UNDERSTANDING


1 Sort the following list of numbers into two groups: composite numbers and prime numbers.
15, 13, 7, 5, 8, 9, 27, 23, 11, 4, 12, 2

2 Fill in the gaps to complete the following factor trees.


a



b




c




3 Complete each of the following factor trees.


a



b



c



4 Write the following prime factors, using powers.

a $2 \times 3 \times 3 \times 2 \times 2$

b $5 \times 3 \times 3 \times 3 \times 3 \times 5$

c $7 \times 2 \times 3 \times 7 \times 2$

d $3 \times 3 \times 2 \times 11 \times 11 \times 2$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F

5(½) 5–6(½) 5–6(½)

FLUENCY

Example 13

5 Express the following numbers in prime factor form.

a 72	**b** 24	**c** 38	**d** 44
e 124	**f** 80	**g** 96	**h** 16
i 75	**j** 111	**k** 64	**l** 56

6 Express these numbers in prime factor form.

a 600	**b** 800	**c** 5000	**d** 2400
e 1 000 000	**f** 45 000	**g** 820	**h** 690

7, 8 7–9 8–10

PROBLEM-SOLVING

7 Match the correct composite number (**a** to **d**) to its set of prime factors (**A** to **D**).

a 120	**A** $2 \times 3 \times 5^2$
b 150	**B** $2^2 \times 3^2 \times 5$
c 144	**C** $2^4 \times 3^2$
d 180	**D** $2 \times 3 \times 2 \times 5 \times 2$

8 Find the smallest composite number that has the five smallest prime numbers as factors.

9 **a** Express 144 and 96 in prime factor form.
b By considering the prime factor form, determine the HCF of 144 and 96.

10 **a** Express 25 200 and 77 000 in prime factor form.
b By considering the prime factor form, determine the HCF of 25 200 and 77 000.

11 11, 12 12–14

REASONING

11 Represent the number 24 with four different factor trees, each resulting in the same set of prime factors. Note that simply swapping the order of a pair of factors does not qualify it as a different form of the factor tree.



12 Only one of the following is the correct set of prime factors for 424.

A $2^2 \times 3^2 \times 5$	**B** $2 \times 3^2 \times 5^2$	**C** 53×8	**D** $2^3 \times 53$

i Justify why you can eliminate alternatives **A** and **B** straight away.
ii Why can option **C** be discarded as an option?
iii Show that option **D** is the correct answer.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3F

REASONING


13 a State the error in each of the following prime factor trees.

i




$60 = 2 \times 5^2$

ii



$60 = 2 \times 5 \times 6$

iii



$60 = 2 \times 3 \times 5$


b What is the correct way to express 60 in prime factor form?

14 Write 15 different (i.e. distinct) factor trees for the number 72.

ENRICHMENT

Four distinct prime factors — — 15–17

15 There are 16 composite numbers that are smaller than 1000 which have four distinct (i.e. different) prime factors. For example: $546 = 2 \times 3 \times 7 \times 13$.
By considering the prime factor possibilities, find all 16 composite numbers and express each of them in prime factor form.



Supercomputers like this have been used to search for prime numbers with millions of digits.

16 A conjecture is a statement that may appear to be true but has not been proved conclusively. Goldbach's conjecture states: 'Every even number greater than 2 is the sum of two prime numbers.' For example, $52 = 47 + 5$
Challenge: Try this for every even number from 4 to 50.

17 Use the internet to find the largest-known prime number.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

3A **1** Find the complete set of factors for each of these numbers.

a 16 **b** 70

3A **2** Write down the first four multiples for each of these numbers.

a 7 **b** 20

3B **3** Find the HCF of the following groups of numbers.

a 15 and 10 **b** 36, 54 and 72

3B **4** Find the LCM of the following groups of numbers.

a 8 and 12 **b** 3, 5 and 9

3C Ext **5** Use the divisibility rules to determine whether the following calculations are possible without leaving a remainder. Give a reason for each answer.

a $34\,481 \div 4$ **b** $40\,827 \div 3$ **c** $824\,730 \div 6$ **d** $5\,247\,621 \div 9$

3C Ext **6** The game of 'clusters' involves a group getting into smaller-sized groups as quickly as possible once a particular cluster size has been called out. If a year level consists of 120 students, which 'cluster' sizes (of more than one person) would ensure no students are left out of a group?

3D **7** State whether each of the following is a prime (P) or composite (C) number or neither (N). Give reasons.

a 60 **b** 1 **c** 13 **d** 0

3D **8** Find the prime numbers that are factors of:

a 35 **b** 36

3E **9** Simplify the following expressions by writing them as powers.

a $5 \times 5 \times 5 \times 5$ **b** $7 \times 3 \times 7 \times 7 \times 3 \times 7 \times 7$

3E **10** Expand and evaluate the following terms.

a 3^4 **b** $1^4 \times 3^2$ **c** $5^1 \times 10^4$ **d** $(12 - 8)^2$ **e** $9^2 - 3^3 \times 2$

3F **11** Express the following numbers in prime factor form, writing them in ascending order.

a 24 **b** 180


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G Squares and square roots



A square number can be illustrated by considering the area of a square with a whole number as its side length.

For example:



Area of square = 4 cm × 4 cm = 16 cm^2

Therefore, 16 is a square number.







Another way of representing square numbers is through a square array of dots.

For example:



Number of dots = 3 rows of 3 dots

= 3 × 3 dots

= 3^2 dots

= 9 dots

Therefore, 9 is a square number.

To produce a square number you must multiply the number by itself. All square numbers written in index form will have a power of 2.

Finding a square root of a number is the opposite of squaring a number.

For example: $4^2 = 16$ and therefore $\sqrt{16} = 4$.

To find square roots we use our knowledge of square numbers. A calculator is also frequently used to find square roots. Geometrically, the square root of a number is the side length of a square whose area is that number.



Old Town Square in Prague. The square root of its area is the length of one of its sides.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Let's start: Speed squaring tests

In pairs, test one another's knowledge of square numbers.

- Ask 10 quick questions, such as '3 squared', '5 squared' etc.
- Have two turns each. Time how long it takes each of you to answer the 10 questions.
- Aim to be quicker on your second attempt.

Write down the first 10 square numbers.

- Begin to memorise these important numbers.
- Time how quickly you can recall the first 10 square numbers without looking at a list of numbers.
- Can you go under 5 seconds?



Key ideas

- Any whole number multiplied by itself produces a **square number**.
  For example: $5^2 = 5 \times 5 = 25$. Therefore, 25 is a square number.
  - Square numbers are also known as **perfect squares**.
  - The first 12 square numbers are:

Index form	1^2	2^2	3^2	4^2	5^2	6^2	7^2	8^2	9^2	10^2	11^2	12^2
Basic numeral	1	4	9	16	25	36	49	64	81	100	121	144

  - All square numbers have an odd number of factors.
  - The symbol for squaring is $(\ )^2$. The brackets are optional, but can be very useful when simplifying more difficult expressions.
- The **square root** of a given number is the 'non-negative' number that, when multiplied by itself, produces the given number.
  - The symbol for square rooting is $\sqrt{\ }$.
  - Finding a square root of a number is the opposite of squaring a number.
    For example: $4^2 = 16$; hence, $\sqrt{16} = 4$
    We read this as: '4 squared equals 16, therefore, the square root of 16 equals 4.'
  - Squaring and square rooting are 'opposite' operations.
    $(\sqrt{x})^2 = x$ also $\sqrt{(x)^2} = x$
  - A list of common square roots are:

Square root form	$\sqrt{1}$	$\sqrt{4}$	$\sqrt{9}$	$\sqrt{16}$	$\sqrt{25}$	$\sqrt{36}$	$\sqrt{49}$	$\sqrt{64}$	$\sqrt{81}$	$\sqrt{100}$	$\sqrt{121}$	$\sqrt{144}$
Basic numeral	1	2	3	4	5	6	7	8	9	10	11	12

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 14 Evaluating squares and square roots

Evaluate:

a 6^2 b $\sqrt{64}$ c $\sqrt{1600}$

SOLUTION	EXPLANATION
a $6^2 = 36$	$6^2 = 6 \times 6$
b $\sqrt{64} = 8$	$8 \times 8 = 64$ $\therefore \sqrt{64} = 8$
c $\sqrt{1600} = 40$	$40 \times 40 = 1600$ $\therefore \sqrt{1600} = 40$

Example 15 Evaluating expressions involving squares and square roots

Evaluate:

a $3^2 - \sqrt{9} + 1^2$ b $\sqrt{8^2 + 6^2}$

SOLUTION	EXPLANATION
a $3^2 - \sqrt{9} + 1^2 = 9 - 3 + 1$ $= 7$	$3^2 = 3 \times 3, \sqrt{9} = 3, 1^2 = 1 \times 1$
b $\sqrt{8^2 + 6^2} = \sqrt{64 + 36}$ $= \sqrt{100}$ $= 10$	$8^2 = 8 \times 8, 6^2 = 6 \times 6$ $\sqrt{100} = 10$

Exercise 3G

1–5 | 5 | —

UNDERSTANDING

1 Draw a square of side length 6 cm. What would be the area of this shape? What special type of number is your answer?

2 Write down the first 15 square numbers in index form and as basic numerals.

3 We can confirm that 9 is a square number by drawing the diagram shown at right.



a Show, using dots, why 6 is not a square number.

b Show, using dots, why 16 is a square number.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G

UNDERSTANDING

4 Evaluate:

a 6^2 **b** 5 squared **c** $(11)^2$

d 10 to the power of 2 **e** 7^2 **f** 12×12

5 Evaluate:

a $\sqrt{25}$ **b** square root of 16 **c** $\sqrt{100}$

d the length of a square that has an area of 49 cm^2

FLUENCY

6–9(½) 6–9(½) 6–9(½)

Example 14a

6 Evaluate:

a 8^2 **b** 7^2 **c** 1^2 **d** 12^2

e 3^2 **f** 15^2 **g** 5^2 **h** 0^2

i 11^2 **j** 100^2 **k** 17^2 **l** 33^2

Example 14b

7 Evaluate:

a $\sqrt{25}$ **b** $\sqrt{9}$ **c** $\sqrt{1}$ **d** $\sqrt{121}$

e $\sqrt{0}$ **f** $\sqrt{81}$ **g** $\sqrt{49}$ **h** $\sqrt{16}$

i $\sqrt{4}$ **j** $\sqrt{144}$ **k** $\sqrt{400}$ **l** $\sqrt{169}$

Example 14c

8 Evaluate:

a $\sqrt{2500}$ **b** $\sqrt{6400}$ **c** $\sqrt{8100}$ **d** $\sqrt{729}$

Example 15

9 Evaluate:

a $3^2 + 5^2 - \sqrt{16}$ **b** 4×4^2 **c** $8^2 - 0^2 + 1^2$

d $1^2 \times 2^2 \times 3^2$ **e** $\sqrt{5^2 - 3^2}$ **f** $\sqrt{81} - 3^2$

g $6^2 \div 2^2 \times 3^2$ **h** $\sqrt{9} \times \sqrt{64} \div \sqrt{36}$ **i** $\sqrt{12^2 + 5^2}$

PROBLEM-SOLVING

10, 11 11, 12 11–13

10 List all the square numbers between 50 and 101.

11 List all the square numbers between 101 and 200. Hint: There are only four.

12 **a** Find two square numbers that add to 85.

b Find two square numbers that have a difference of 85.

13 Find three different square numbers that sum to 59.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G

14 | 14, 15 | 15–17

REASONING

14 **a** Evaluate $3^2 \times 4^2$.

b Evaluate 12^2.

c The rule $a^2 \times b^2 = (a \times b)^2$ can be used to link $3^2 \times 4^2$ and 12^2. What are the values of a and b if $3^2 \times 4^2 = 12^2$?

d Check this formula using other numbers.

15 **a** Show that $3^2 + 4^2 = 5^2$.

b What does $6^2 + 8^2$ equal? Write the answer using a power of 2.

c What does $9^2 + 12^2$ equal?

d What does $30^2 + 40^2$ equal?

16 **a** Evaluate 11^2 and 111^2.

b Predict an answer for 1111^2.

c Evaluate 1111^2 and test your prediction.

17 Stuart decides there are no odd square numbers. His justification is that 'because an even number multiplied by an even number produces an even number, and that an odd number multiplied by an odd number also produces an even number, then there are no odd square numbers'. Do you agree with Stuart's claim? If not, give an example to explain your answer.

Properties of square roots

— | — | 18

ENRICHMENT

18 Trial different numbers in the following formulas to determine whether these algebraic statements involving square roots are true or false.

a $\sqrt{a} + \sqrt{b} = \sqrt{a+b}$

b $\sqrt{a} - \sqrt{b} = \sqrt{a-b}$

c $\sqrt{a} \times \sqrt{b} = \sqrt{a \times b}$


d $\sqrt{\frac{a}{b}} = \frac{\sqrt{a}}{\sqrt{b}}$

e $\sqrt{a^2} = a$

f $a^3 = a\sqrt{a}$

g $\sqrt{a^2 + b^2} = a + b$

h $\sqrt{a^2 - b^2} = a - b$



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3H Number patterns CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Mathematicians commonly look at lists of numbers in an attempt to discover a pattern. They also aim to find a rule that describes the number pattern to allow them to predict future numbers in the sequence.

Here is a list of professional careers that all involve a high degree of mathematics and, in particular, involve looking at data so that comments can be made about past, current or future trends:

Statistician, economist, accountant, market researcher, financial analyst, cost estimator, actuary, stock broker, data analyst, research scientist, financial advisor, medical scientist, budget analyst, insurance underwriter and mathematics teacher!



There are many careers that involve using mathematics and data.

Let's start: What's next?

A number sequence consisting of five terms is placed on the board. Four gaps are placed after the last number.

20, 12, 16, 8, 12, ___, ___, ___, ___,

- Can you work out and describe the number pattern?
  This number pattern involves a repeated process of subtracting 8 and then adding 4.
- Make up your own number pattern and test it on a class member.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Number patterns are also known as **sequences**, and each number in a sequence is called a **term**.
  - Each number pattern has a particular starting number and terms are generated by following a particular rule.
- Strategies to determine the pattern involved in a number sequence include:
  - Looking for a common difference
    Are terms increasing or decreasing by a constant amount?
    For example: 2, 6, 10, 14, 18, … Each term is increasing by 4.
  - Looking for a common ratio
    Is each term being multiplied or divided by a constant amount?
    For example: 2, 4, 8, 16, 32, … Each term is being multiplied by 2.
  - Looking for an increasing/decreasing difference
    Is there a pattern in the difference between pairs of terms?
    For example: 1, 3, 6, 10, 15, … The difference increases by 1 each term.
  - Looking for two interlinked patterns
    Is there a pattern in the odd-numbered terms, and another pattern in the even-numbered terms?
    For example: 2, 8, 4, 7, 6, 6, … The odd-numbered terms increase by 2, the even-numbered terms decrease by 1.
  - Looking for a special type of pattern
    Could it be a list of square numbers, prime numbers, Fibonacci numbers etc.?
    For example: 1, 8, 27, 64, 125, … This is the pattern of cube numbers: 1^3, 2^3, 3^3, . . .

Example 16 Identifying patterns with a common difference

Find the next three terms for these number patterns that have a common difference.

a 6, 18, 30, 42, ___, ___, ___

b 99, 92, 85, 78, ___, ___, ___

SOLUTION	EXPLANATION
a 54, 66, 78	The common difference is 12. Continue adding 12 to generate the next three terms.
b 71, 64, 57	The pattern indicates the common difference is 7. Continue subtracting 7 to generate the next three terms.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 17 Identifying patterns with a common ratio

Find the next three terms for the following number patterns that have a common ratio.

a 2, 6, 18, 54, ___, ___, ___

b 256, 128, 64, 32, ___, ___, ___

SOLUTION	EXPLANATION
a 162, 486, 1458	The common ratio is 3. Continue multiplying by 3 to generate the next three terms.
b 16, 8, 4	The common ratio is $\frac{1}{2}$. Continue dividing by 2 to generate the next three terms.

Exercise 3H

1–3 | 3 | —

UNDERSTANDING

1 Generate the first five terms of the following number patterns.

a starting number of 8, common difference of adding 3

b starting number of 32, common difference of subtracting 1

c starting number of 52, common difference of subtracting 4

d starting number of 123, common difference of adding 7

2 Generate the first five terms of the following number patterns.

a starting number of 3, common ratio of 2 (multiply by 2 each time)

b starting number of 5, common ratio of 4

c starting number of 240, common ratio of $\frac{1}{2}$ (divide by 2 each time)

d starting number of 625, common ratio of $\frac{1}{5}$

3 State whether the following number patterns have a common difference (+ or –), a common ratio (× or ÷) or neither.

a 4, 12, 36, 108, 324, …

b 19, 17, 15, 13, 11, …

c 212, 223, 234, 245, 256, …

d 8, 10, 13, 17, 22, …

e 64, 32, 16, 8, 4, …

f 5, 15, 5, 15, 5, …

g 2, 3, 5, 7, 11, …

h 75, 72, 69, 66, 63, …

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3H

4–7(½) | 4–8(½) | 4–8(½)

FLUENCY

Example 16

4 Find the next three terms for the following number patterns that have a common difference.

a 3, 8, 13, 18, __, __, __
b 4, 14, 24, 34, __, __, __
c 26, 23, 20, 17, __, __, __,
d 106, 108, 110, 112, __, __, __
e 63, 54, 45, 36, __, __, __
f 9, 8, 7, 6, __, __, __
g 101, 202, 303, 404, __, __, __
h 75, 69, 63, 57, __, __, __

Example 17

5 Find the next three terms for the following number patterns that have a common ratio.

a 2, 4, 8, 16, __, __, __
b 5, 10, 20, 40, __, __, __
c 96, 48, 24, __, __, __
d 1215, 405, 135, __, __, __
e 11, 22, 44, 88, __, __, __
f 7, 70, 700, 7000, __, __, __
g 256, 128, 64, 32, __, __, __
h 1216, 608, 304, 152, __, __, __

6 Find the missing numbers in each of the following number patterns.

a 62, 56, __, 44, 38, __, __
b 15, __, 35, __, __, 65, 75
c 4, 8, 16, __, __, 128, __
d 3, 6, __, 12, __, 18, __
e 88, 77, 66, __, __, __, 22
f 2997, 999, __, __, 37
g 14, 42, __, __, 126, __, 182
h 14, 42, __, __, 1134, __, 10 206

7 Write the next three terms in each of the following sequences.

a 3, 5, 8, 12, __, __, __
b 1, 2, 4, 7, 11, __, __, __
c 1, 4, 9, 16, 25, __, __, __
d 27, 27, 26, 24, 21, __, __, __
e 2, 3, 5, 7, 11, 13, __, __, __
f 2, 5, 11, 23, __, __, __
g 2, 10, 3, 9, 4, 8, __, __, __
h 14, 100, 20, 80, 26, 60, __, __, __

8 Generate the next three terms for the following number sequences and give an appropriate name to the sequence.

a 1, 4, 9, 16, 25, 36, __, __, __
b 1, 1, 2, 3, 5, 8, 13, __, __, __
c 1, 8, 27, 64, 125, __, __, __
d 2, 3, 5, 7, 11, 13, 17, __, __, __
e 4, 6, 8, 9, 10, 12, 14, 15, __, __, __
f 121, 131, 141, 151, __, __, __

9, 10 | 10, 11 | 10–12


PROBLEM-SOLVING

9 Complete the next three terms for the following challenging number patterns.

a 101, 103, 106, 110, __, __, __
b 162, 54, 108, 36, 72, __, __, __
c 3, 2, 6, 5, 15, 14, __, __, __
d 0, 3, 0, 4, 1, 6, 3, __, __, __

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

10 When making human pyramids, there is one less person on each row above, and it is complete when there is a row of only one person on the top.
Write down a number pattern for a human pyramid with 10 students on the bottom row. How many people are needed to make this pyramid?



11 The table below represents a seating plan with specific seat number for a section of a grandstand at a soccer ground. It continues upwards for another 20 rows.

Row 4	25	26	27	28	29	30	31	32
Row 3	17	18	19	20	21	22	23	24
Row 2	9	10	11	12	13	14	15	16
Row 1	1	2	3	4	5	6	7	8

a What is the number of the seat directly above seat number 31?
b What is the number of the seat on the left-hand edge of row 8?
c What is the third seat from the right in row 14?
d How many seats are in the grandstand?

12 Find the next five numbers in the following number pattern.
1, 4, 9, 1, 6, 2, 5, 3, 6, 4, 9, 6, 4, 8, 1, __, __, __, __, __

ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

3H

13 | 13, 14 | 14, 15

REASONING

13 Jemima writes down the following number sequence: 7, 7, 7, 7, 7, 7, 7, …
Her friend Peta declares that this is not really a number pattern. Jemima defends her number pattern, stating that it is most definitely a number pattern as it has a common difference and also has a common ratio. What are the common difference and the common ratio for the number sequence above? Do you agree with Jemima or Peta?

14 Find the sum of the following number sequences.

a $1 + 2 + 3 + 4 + 5 + 6 + 7 + 8 + 9 + 10$

b $1 + 3 + 5 + 7 + 9 + 11 + 13 + 15 + 17 + 19$

c $1 + 2 + 3 + 4 + 5 + \cdots + 67 + 68 + 69 + 70$

d $5 + 8 + 11 + 14 + 17 + 20 + 23 + 26 + 29 + 32 + 35 + 38$

15 The great handshake problem. There are a certain number of people in a room and they must all shake one another's hand. How many handshakes will there be if there are:

a 3 people in the room?

b 5 people in the room?

c 10 people in the room?

d 24 people in a classroom?

e n people in the room?

What number am I?

— | — | 16

ENRICHMENT

16 Read the following clues to work out the mystery number.

a I have three digits.
I am divisible by 5.
I am odd.
The product of my digits is 15.
The sum of my digits is less than 10.
I am less than 12×12.

b I have three digits.
The sum of my digits is 12.
My digits are all even.
My digits are all different.
I am divisible by 4.
The sum of my units and tens digits equals my hundreds digit.

c I have three digits.
I am odd and divisible by 5 and 9.
The product of my digits is 180.
The sum of my digits is less than 20.
I am greater than 30^2.

d Make up two of your own mystery number puzzles and submit your clues to your teacher.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3I Spatial patterns

Interactive

Widgets

HOTsheets

Walkthroughs

Patterns can also be found in geometric shapes. Mathematicians examine patterns carefully to determine how the next term in the sequence is created. Ideally, a rule is formed that shows the relationship between the geometric shape and the number of objects (e.g. tiles, sticks, counters) required to make such a shape. Once a rule is established it can be used to make predictions about future terms in the sequence.



A pattern rule can be created to show how these shapes can be constructed.

Let's start: Stick patterns

Materials required: One box of toothpicks/matches per student.

- Generate a spatial pattern using your sticks.
- You must be able to make at least three terms in your pattern.
  For example:




- Ask your partner how many sticks would be required to make the next term in the pattern.
- Repeat the process with a different spatial design.

Key ideas


- A **spatial pattern** is a sequence of geometrical shapes that can be described by a **number pattern**.
  For example:

spatial pattern



number pattern 4 8 12

- A spatial pattern starts with a simple geometric design. Future terms are created by adding on repeated shapes of the same design. If designs connect with an edge, the repetitive shape added on will be a subset of the original design, as the connecting edge does not need to be repeated.
  For example:




- To help describe a spatial pattern, it is generally converted to a number pattern and a common difference is observed.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas


- The common difference is the number of objects (e.g. sticks) that need to be added on to create the next term.
- Rules can be found that connect the number of objects (e.g. sticks) required to produce the number of designs.
  For example: hexagon design



Rule is: Number of sticks used = 6 × number of hexagons formed



Example 18 Drawing and describing spatial patterns

a Draw the next two shapes in the spatial pattern shown.



b Write the spatial pattern above as a number pattern in regard to the number of sticks required to make each shape.

c Describe the pattern by stating how many sticks are required to make the first term, and how many sticks are required to make the next term in the pattern.

SOLUTION	EXPLANATION
a 	Follow the pattern.
b 5, 8, 11, 14, 17	Count the number of sticks in each term. Look for a pattern.
c 5 matches are required to start the pattern, and an additional 3 matches are required to make the next term in the pattern.	

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 19 Finding a general rule for a spatial pattern

a Draw the next two shapes in this spatial pattern.



b Complete the table.


Number of triangles	1	2	3	4	5
Number of sticks required	3				

c Describe a rule connecting the number of sticks required to the number of triangles produced.

d Use your rule to predict how many sticks would be required to make 20 triangles.

SOLUTION

a



b

No. of triangles	1	2	3	4	5
No. of sticks	3	6	9	12	15

c Number of sticks = 3 × number of triangles

d Number of sticks = 3 × 20 triangles
= 60 sticks

EXPLANATION

Follow the pattern by adding one triangle each time.

An extra 3 sticks are required to make each new triangle.

3 sticks are required per triangle.

20 triangles × 3 sticks each


Exercise 3I

1–3 | 3 | —

UNDERSTANDING

1 Draw the next two terms for each of these spatial patterns.


a



b




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

c 


d 

e 

2 Draw the following geometrical designs in sequential ascending (i.e. increasing) order and draw the next term in the sequence.





3 For each of the following spatial patterns, draw the starting geometrical design and also the geometrical design added on repetitively to create new terms. (For some patterns the repetitive design is the same as the starting design.)


a 

b 

c 

d 

e 

f 

ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

Example 18

4 For each of the spatial patterns below:

i Draw the next two shapes.

ii Write the spatial pattern as a number pattern.

iii Describe the pattern by stating how many sticks are required to make the first term and how many more sticks are required to make the next term in the pattern.


a




b



c




d



e




f



Example 19

5 **a** Draw the next two shapes in this spatial pattern.



b Copy and complete the table.

Number of crosses	1	2	3	4	5
Number of sticks required					

c Describe a rule connecting the number of sticks required to the number of crosses produced.


d Use your rule to predict how many sticks would be required to make 20 crosses.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

3I

FLUENCY

6 **a** Draw the next two shapes in this spatial pattern.



b Copy and complete the table. Planks are vertical and horizontal.

Number of fence sections	1	2	3	4	5
Number of planks required					

c Describe a rule connecting the number of planks required to the number of fence sections produced.

d Use your rule to predict how many planks would be required to make 20 fence sections.

7, 8 | 8, 9 | 8–10

PROBLEM-SOLVING

7 At North Park Primary School, the classrooms have trapezium-shaped tables. Mrs Greene arranges her classroom's tables in straight lines, as shown.




a Draw a table of results showing the relationship between the number of tables in a row and the number of students that can sit at the tables. Include results for up to five tables in a row.

b Describe a rule that connects the number of tables placed in a straight row to the number of students that can sit around the tables.

c The room allows seven tables to be arranged in a straight line. How many students can sit around the tables?

d There are 65 students in Grade 6 at North Park Primary School. Mrs Greene would like to arrange the tables in one straight line for an outside picnic lunch. How many tables will she need?

8 The number of tiles required to pave around a spa is related to the size of the spa. The approach is to use large tiles that are the same size as that of a small spa.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

A spa of length 1 unit requires 8 tiles to pave around its perimeter, whereas a spa of length 4 units requires 14 tiles to pave around its perimeter.


- **a** Complete a table of values relating length of spa and number of tiles required, for values up to and including a spa of length 6 units.
- **b** Describe a rule that connects the number of tiles required for the length of the spa.
- **c** The largest size spa manufactured is 15 units long. How many tiles would be required to pave around its perimeter?
- **d** A paving company has only 30 tiles left. What is the largest spa they would be able to tile around?

9 Which rule correctly describes this spatial pattern?



- **A** Number of sticks = 7 × number of 'hats'
- **B** Number of sticks = 7 × number of 'hats' + 1
- **C** Number of sticks = 6 × number of 'hats' + 2
- **D** Number of sticks = 6 × number of 'hats'

10 Which rule correctly describes this spatial pattern?



- **A** Number of sticks = 5 × number of houses + 1
- **B** Number of sticks = 6 × number of houses + 1
- **C** Number of sticks = 6 × number of houses
- **D** Number of sticks = 5 × number of houses

11 | 11, 12 | 12, 13

11 Design a spatial pattern to fit the following number patterns.

- **a** 4, 7, 10, 13, …
- **b** 4, 8, 12, 16, …
- **c** 3, 5, 7, 9, …
- **d** 3, 6, 9, 12, …
- **e** 5, 8, 11, 14, …
- **f** 6, 11, 16, 21, …

12 A rule to describe a special window spatial pattern is written as $y = 4 \times x + 1$, where y represents the number of 'sticks' required and x is the number of windows created.

- **a** How many sticks are required to make one window?
- **b** How many sticks are required to make 10 windows?
- **c** How many sticks are required to make g windows?
- **d** How many windows can be made from 65 sticks?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3I

REASONING

13 A rule to describe a special fence spatial pattern is written as $y = m \times x + n$, where y represents the number of pieces of timber required and x represents the number of fencing panels created.



a How many pieces of timber are required to make one panel?

b What does m represent?

c Draw the first three terms of the fence spatial pattern for $m = 4$ and $n = 1$.


ENRICHMENT

Cutting up a circle — — 14


14 What is the *greatest* number of sections into which you can divide a circle, using only a particular number of straight line cuts?

a Explore the problem above.

Note: The greatest number of sections is required and, hence, only one of the two diagrams below is correct for three straight line cuts.



Incorrect. Not the maximum number of sections.



Correct. The maximum number of sections.

b Copy and complete this table of values.

Number of straight cuts	1	2	3	4	5	6	7
Number of sections created			7				

c Can you discover a pattern for the maximum number of sections created? What is the maximum number of sections that could be created with 10 straight line cuts?

d The formula for determining the maximum number of cuts is quite complex:

$$\text{sections} = \frac{1}{2}\,\text{cuts}^2 + \frac{1}{2}\,\text{cuts} + 1$$

Verify that this formula works for the values you listed in the table above.

Using the formula, how many sections could be created with 20 straight cuts?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3J Tables and rules




In the previous section on spatial patterns, it was observed that rules can be used to connect the number of objects (e.g. sticks) required to make particular designs.

A table of values can be created for any spatial pattern. Consider this spatial pattern and the corresponding table of values.








Number of diamonds (*input*)	Number of sticks (*output*)
1	4
2	8
3	12

What values would go in the next row of the table?
A rule that produces this table of values is:

Number of sticks = 4 × number of diamonds

Alternatively, if we consider the number of diamonds as the *input variable* and the number of sticks as the *output variable*, then the rule could be written as:

output = 4 × *input*



If a rule is provided, a table of values can be created.

If a table of values is provided, often a rule can be found.

Let's start: Guess the output

- A table of values is drawn on the board with three completed rows of data.
- Additional values are placed in the *input* column. What *output* values should be in the *output* column?
- After adding *output* values, decide which rule fits (models) the values in the table and check that it works for each *input* and *output* pair.
  Four sample tables are listed below.

input	*output*
2	6
5	9
6	10
1	?
8	?

input	*output*
12	36
5	15
8	24
0	?
23	?

input	*output*
2	3
3	5
9	17
7	?
12	?

input	*output*
6	1
20	8
12	4
42	?
4	?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- A **rule** shows the relation between two varying quantities.
  For example: *output* = *input* + 3 is a rule connecting the two quantities *input* and *output*.
  The values of the *input* and the *output* can vary, but we know from the rule that the value of the *output* will always be 3 more than the value of the *input*.
- A **table of values** can be created from any given rule. To complete a table of values, the *input* (one of the quantities) is replaced by a number. This is known as **substitution**. After substitution the value of the other quantity, the *output*, is calculated.
  For example: If *input* = 4, then
  output = *input* + 3
  = 4 + 3
  = 7
- Often, a rule can be determined from a table of values. On close inspection of the values, a relationship may be observed. Each of the four operations should be considered when looking for a connection.

input	1	2	3	4	5	6
output	6	7	8	9	10	11

By inspection, it can be observed that every *output* value is 5 more than the corresponding *input* value. The rule can be written as: *output* = *input* + 5.

Example 20 Completing a table of values

Complete each table for the given rule.

a *output* = *input* – 2

input	3	5	7	12	20
output					

b *output* = (3 × *input*) + 1

input	4	2	9	12	0
output					

SOLUTION

a *output* = *input* – 2

input	3	5	7	12	20
output	1	3	5	10	18

b *output* = (3 × *input*) + 1

input	4	2	9	12	0
output	13	7	28	37	1

EXPLANATION

Replace each *input* value in turn into the rule.
e.g. When *input is* 3:
output = 3 – 2 = 1

Replace each *input* value in turn into the rule.
e.g. When *input* is 4:
output = (3 × 4) + 1 = 13

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 21 Finding a rule from a table of values

Find the rule for each of these tables of values.

a

input	3	4	5	6	7
output	12	13	14	15	16

b

input	1	2	3	4	5
output	7	14	21	28	35

SOLUTION

a $output = input + 9$

b $output = input \times 7$ or $output = 7 \times input$

EXPLANATION

Each *output* value is 9 more than the *input* value.

By inspection, it can be observed that each *output* value is 7 times bigger than the *input* value.

Exercise 3J

1–4 | 4 | —

UNDERSTANDING

1 State whether each of the following statements is true or false.

a If $output = input \times 2$, then when $input = 7$, $output = 14$.

b If $output = input - 2$, then when $input = 5$, $output = 7$.

c If $output = input + 2$, then when $input = 0$, $output = 2$.

d If $output = input \div 2$, then when $input = 20$, $output = 10$.

2 Which table of values matches the rule $output = input - 3$?

A

input	10	11	12
output	13	14	15

B

input	5	6	7
output	15	18	21

C

input	8	9	10
output	5	6	7

D

input	4	3	2
output	1	1	1

3 Which table of values matches the rule $output = input \div 2$?

A

input	20	14	6
output	18	12	4

B

input	8	10	12
output	4	5	6

C

input	4	5	6
output	8	10	12

D

input	4	3	2
output	6	5	4

4 Match each rule (A to D) with the correct table of values (**a** to **d**).

Rule A: $output = input - 5$

Rule B: $output = input + 1$

Rule C: $output = 4 \times input$

Rule D: $output = 5 + input$

a

input	20	14	6
output	15	9	1

b

input	8	10	12
output	13	15	17

c

input	4	5	6
output	5	6	7

d

input	4	3	2
output	16	12	8

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3J

5–7 | 5–7 | 5–7(½)

FLUENCY

Example 20a

5 Copy and complete each table for the given rule.

a *output* = *input* + 3

input	4	5	6	7	10
output					

b *output* = *input* × 2

input	5	1	3	21	0
output					

c *output* = *input* – 8

input	11	18	9	44	100
output					

d *output* = *input* ÷ 5

input	5	15	55	0	100
output					

Example 20b

6 Copy and complete each table for the given rule.

a *output* = (10 × *input*) – 3

input	1	2	3	4	5
output					

b *output* = (*input* ÷ 2) + 4

input	6	8	10	12	14
output					

c *output* = (3 × *input*) + 1

input	5	12	2	9	0
output					

d *output* = (2 × *input*) – 4

input	3	10	11	7	50
output					

Example 21

7 State the rule for each of these tables of values.

a

input	4	5	6	7	8
output	5	6	7	8	9

b

input	1	2	3	4	5
output	4	8	12	16	20

c

input	10	8	3	1	14
output	21	19	14	12	25

d

input	6	18	30	24	66
output	1	3	5	4	11

8, 9 | 8, 9 | 9, 10

PROBLEM-SOLVING

8 Copy and complete the missing values in the table and state the rule.

input	4	10	13	24			5	11	2
output			39		42	9	15		6

9 Copy and complete the missing values in the table and state the rule.

input	12	93	14	17		10			
output	3			8	12	1	34	0	200

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3J

PROBLEM-SOLVING

10 Copy and complete each table for the given rule.

a $output = input \times input - 2$

input	3	6	8	12	2
output					

b $output = (24 \div input) + 1$

input	6	12	1	3	8
output					

c $output = input^2 + input$

input	5	12	2	9	0
output					

d $output = 2 \times input \times input - input$

input	3	10	11	7	50
output					

11 | 11, 12 | 12, 13

REASONING

11 Copy and complete each table for the given rule.

a $output = input + 6$

input	c	d	$2p$	b^2	www
output					

b $output = 3 \times input - 2$

input	t	k	p^2	$2f$	ab
output					

12 Copy and complete the missing values in the table and state the rule.

input	b		e	g^2		x	c		1
output		cd			cmn	xc		0	c

13 It is known that for an *input* value of 3 the *output* value is 7.

a State two different rules that work for these values.

b How many different rules are possible? Explain.

ENRICHMENT

Finding harder rules — | — | 14

14 a The following rules all involve two operations. Find the rule for each of these tables of values.

i

input	4	5	6	7	8
output	5	7	9	11	13

ii

input	1	2	3	4	5
output	5	9	13	17	21

iii

input	10	8	3	1	14
output	49	39	14	4	69

iv

input	6	18	30	24	66
output	3	5	7	6	13

v

input	4	5	6	7	8
output	43	53	63	73	83

vi

input	1	2	3	4	5
output	0	4	8	12	16

b Write three of your own two-operation rules and produce a table of values for each rule.

c Swap your tables of values with those of a classmate and attempt to find one another's rules.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

3K The number plane and graphs










We are already familiar with number lines.

A number line is used to locate a position in one dimension (i.e. along the line).

A number plane is used to locate a position in two dimensions (i.e. within the plane). A number plane uses two number lines to form a grid system, so that points can be located precisely. A rule can then be illustrated visually using a number plane by forming a graph.



What is the position of this point on the number plane?

Let's start: Estimate your location

Consider the door as 'the origin' of your classroom.

- Describe the position you are sitting in within the classroom in reference to the door.
- Can you think of different ways of describing your position? Which is the best way? Submit a copy of your location description to your teacher.

Can you locate a classmate correctly when location descriptions are read out by your teacher?




Key ideas

- A **number plane** is used to represent position in two dimensions, therefore it requires two coordinates.
- In mathematics, a number plane is generally referred to as a **Cartesian plane**, named after the famous French mathematician, René Descartes (1596–1650).
- A number plane consists of two straight perpendicular number lines, called axes.
  - The horizontal number line is known as the x-axis.
  - The vertical number line is known as the y-axis.
- For a rule describing a pattern with *input* and *output*, the x value is the *input* and the y value is the *output*.
- The point at which the two axes intersect is called the **origin**, and is often labelled O.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas


- The position of a point on a number plane is given as a pair of numbers, known as the **coordinates** of the point. Coordinates are always written in brackets and the numbers are separated by a comma.
  For example: (2, 4).
  - The x-coordinate (*input*) is always written first. The x-coordinate indicates how far to go from the origin in the horizontal direction.
  - The y-coordinate (*output*) is always written second. The y-coordinate indicates how far to go from the origin in the vertical direction.



Example 22 Plotting points on a number plane

Plot these points on a number plane.
$A(2, 5)$ $B(4, 3)$ $C(0, 2)$

SOLUTION



EXPLANATION

Draw a Cartesian plane, with both axes labelled from 0 to 5.
The first coordinate is the x-coordinate.
The second coordinate is the y-coordinate.
To plot point A, go along the horizontal axis to the number 2, then move vertically up 5 units. Place a dot at this point, which is the intersection of the line passing through the point 2 on the horizontal axis and the line passing through the point 5 on the vertical axis.

Example 23 Drawing a graph

For the given rule *output* = *input* + 1:

a Complete the given table of values.

b Plot each pair of points in the table to form a graph.

input (x)	*output* (y)
0	1
1	
2	
3	


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION

a

input (x)	output (y)
0	1
1	2
2	3
3	4

b



EXPLANATION

Use the given rule to find each *output* value for each *input* value. The rule is:
output = *input* + 1, so add 1 to each *input* value.

Plot each (x, y) pair.
The pairs are (0, 1), (1, 2), (2, 3) and (3, 4).

Exercise 3K


1–5 | 5 | —

UNDERSTANDING

1 Draw a number plane, with the numbers 0 to 6 marked on each axis.


2 Draw a Cartesian plane, with the numbers 0 to 4 marked on both axes.

3 Which of the following is the correct way to describe point *A*?



A 2, 1 **B** 1, 2 **C** (2, 1)
D ($x2$, $y1$) **E** (2_x, 1_y)

4 Which of the following is the correct set of coordinates for point *B*?



A (2, 4) **B** 4, 2 **C** (4, 2)
D (24) **E** $x = 4, y = 2$

5 Copy and complete the following sentences.

a The horizontal axis is known as the_____.
b The_____is the vertical axis.
c The point at which the axes intersect is called the_____.
d The *x*-coordinate is always written_____.
e The second coordinate is always the _____.
f _____ comes before _____ in the dictionary, and the _____ coordinate comes before the _____ coordinate on the Cartesian plane.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 22


6 Plot the following points on a number plane.

a $A(4, 2)$ **b** $B(1, 1)$ **c** $C(5, 3)$ **d** $D(0, 2)$


e $E(3, 1)$ **f** $F(5, 4)$ **g** $G(5, 0)$ **h** $H(0, 0)$

7 Write down the coordinates of each of these labelled points.

a



b




Example 23

8 For the given rule *output* = *input* + 2:

a Copy and complete the given table of values.

b Plot each pair of points in the table to form a graph.

input (*x*)	*output* (*y*)
0	2
1	
2	
3	




9 For the given rule *output* = *input* – 1:

a Copy and complete the given table of values.

b Plot each pair of points in the table to form a graph.

input (*x*)	*output* (*y*)
1	
2	
3	
4	




10 For the given rule *output* = *input* × 2:

a Copy and complete the given table of values.

b Plot each pair of points in the table to form a graph.

input (*x*)	*output* (*y*)
0	
1	
2	
3	



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3K

FLUENCY

11 Draw a Cartesian plane from 0 to 5 on both axes. Place a cross on each pair of coordinates that have the same x and y value.

12 Draw a Cartesian plane from 0 to 8 on both axes. Plot the following points on the grid and join them in the order they are given.
(2, 7), (6, 7), (5, 5), (7, 5), (6, 2), (5, 2), (4, 1), (3, 2), (2, 2), (1, 5), (3, 5), (2, 7)


PROBLEM-SOLVING

13, 14 | 14, 15 | 14–16

13 **a** Plot the following points on a Cartesian plane and join the points in the order given, to draw the basic shape of a house.
(1, 5), (0, 5), (5, 10), (10, 5), (1, 5), (1, 0), (9, 0), (9, 5)
b Describe a set of four points to draw a door.
c Describe two sets of four points to draw two windows.
d Describe a set of four points to draw a chimney.

14 Point $A(1, 1)$ is the bottom left-hand corner of a square of side length 3.
a State the other three coordinates of the square.
b Draw the square on a Cartesian plane and shade in half of the square where the x-coordinates are greater than the y-coordinates.

15 A grid system can be used to make secret messages. Jake decides to arrange the letters of the alphabet on a Cartesian plane in the following manner.



a Decode Jake's following message:
(3, 2), (5, 1), (2, 3), (1, 4)
b Code the word 'secret'.
c To increase the difficulty of the code, Jake does not include brackets or commas and he uses the origin to indicate the end of a word. What do the following numbers mean?
13515500154341513400145354001423114354.
d Code the phrase: 'Be here at seven'.

16 $ABCD$ is a rectangle. The coordinates of A, B and C are given below. Draw each rectangle on a Cartesian plane and state the coordinates of the missing corner, D.
a $A(0, 5)$ $B(0, 3)$ $C(4, 3)$ $D(?, ?)$
b $A(4, 4)$ $B(1, 4)$ $C(1, 1)$ $D(?, ?)$
c $A(0, 2)$ $B(3, 2)$ $C(3, 0)$ $D(?, ?)$
d $A(4, 1)$ $B(8, 4)$ $C(5, 8)$ $D(?, ?)$


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

17 17 17, 18 **3K**


REASONING

17 Write a rule (e.g. *output* = *input* × 2) that would give these graphs.


a



b



c



18 $A(1, 0)$ and $B(5, 0)$ are the base points of an isosceles triangle.

a Find the coordinates of a possible third vertex.

b Show on a Cartesian plane that there are infinite answers for this third vertex.

c The area of the isosceles triangle is 10 square units. State the coordinates of the third vertex.

Locating midpoints

— — 19

ENRICHMENT

19 a Plot the points $A(1, 4)$ and $B(5, 0)$ on a Cartesian plane. Draw the line segment AB. Find the coordinates of M, the midpoint of AB, and mark it on the grid.

b Find the midpoint, M, of the line segment AB, which has coordinates $A(2, 4)$ and $B(0, 0)$.


c Determine a method for locating the midpoint of a line segment without having to draw the points on a Cartesian plane.

d Find the midpoint, M, of the line segment AB, which has coordinates $A(6, 3)$ and $B(2, 1)$.

e Find the midpoint, M, of the line segment AB, which has coordinates $A(1, 4)$ and $B(4, 3)$.

f Find the midpoint, M, of the line segment AB, which has coordinates $A(-3, 2)$ and $B(2, -3)$.

g $M(3, 4)$ is the midpoint of AB and the coordinates of A are $(1, 5)$. What are the coordinates of B?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Fibonacci sequences

Leonardo Fibonacci was a famous thirteenth century mathematician who discovered some very interesting patterns of numbers that are found in nature.

Fibonacci's rabbits

These rules determine how fast rabbits can breed in ideal circumstances.

- Generation 1: One pair of newborn rabbits is in a paddock. A pair is one female and one male.
- Generation 2: When it is 2 months old, the female produces another pair of rabbits.
- Generation 3: When it is 3 months old, this same female produces another pair of rabbits.
- Every female rabbit always produces one new pair *every month* from age 2 months.

a Using the 'rabbit breeding rules', complete a drawing of the first five generations of rabbit pairs. Use it to complete the table opposite.

Month	1	2	3	4	5
Number of rabbits	2				
Number of pairs					

b Write down the numbers of pairs of rabbits at the end of each month for 12 months. This is the Fibonacci sequence.

c How many rabbits will there be after 1 year?

d Explain the rule for the Fibonacci sequence.

Fibonacci sequence in plants

a Count the clockwise and anticlockwise spiralling 'lumps' of some pineapples and show how these numbers relate to the Fibonacci sequence.

b Find three examples of flowers that have two terms of the Fibonacci sequence as the ratio of the numbers of clockwise and anticlockwise spirals of petals.

c On many plants, the number of petals is a Fibonacci number. Research the names and images of some of these 'Fibonacci' flowers.

Fibonacci sequence and the golden ratio

a Write down the next 10 terms of the Fibonacci sequence: 1, 1, 2, 3, 5, …

Fibonacci sequence	1	1	2	3	5	…
Ratio	1	1	2	1.5	…	…

1 ÷ 1 2 ÷ 1 3 ÷ 2

b Write down a new set of numbers that is one Fibonacci number divided by its previous Fibonacci number. Copy and complete this table.

c What do you notice about the new sequence (ratio)?

d Research the *golden ratio* and explain how it links to your new sequence.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Matches are arranged by a student such that the first three diagrams in the pattern are:



How many matches are in the 50th diagram of the pattern?

2 A number is said to be a 'perfect number' if the sum of its factors equals the number. For this exercise, we must exclude the number itself as one of the factors.
The number 6 is the first perfect number.
Factors of 6 (excluding the numeral 6) are 1, 2 and 3.
The sum of these three factors is $1 + 2 + 3 = 6$. Hence, we have a perfect number.

a Find the next perfect number. Hint: It is less than 50.

b The third perfect number is 496. Find all the factors for this number and show that it is a perfect number.



3 Anya is a florist who is making up bunches of tulips with every bunch having the same number of tulips. Anya uses only one colour in each bunch. She has 126 red tulips, 108 pink tulips and 144 yellow tulips. Anya wants to use all the tulips.

a What is the largest number of tulips Anya can put in each bunch?

b How many bunches of each colour would Anya make with this number in each bunch ?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 Mr and Mrs Adams have two teenage children. If the teenagers' ages multiply together to give 252, find the sum of their ages.

5 Complete this sequence.

$2^2 = 1^2 + 3$

$3^2 = 2^2 + 5$

$4^2 = 3^2 + 7$

$5^2 =$ _____


$6^2 =$ _____

6 Use the digits 1, 9, 7 and 2, in any order, and any operations and brackets you like, to make as your answers the whole numbers 0 to 10. For example:

$1 \times 9 - 7 - 2 = 0$

$(9 - 7) \div 2 - 1 = 0$

7 The first three shapes in a pattern made with matchsticks are:




How many matchsticks make up 100th shape?

8 Two numbers have a highest common factor of 1. If one of the numbers is 36 and the other number is a positive integer less than 36, find all possible values for the number that is less than 36.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Number patterns

Sequence
2, 4, 6, 8, ...
↑ ↑ ↑ ↑
terms

Common difference of minus 3
100, 97, 94, ...

Common ratio of times 2
3, 6, 12, 24, ...

Pair differences increase by 3
6, 7, 11, 18, 28, ...

Rules, graphs and tables show a relation between two quantities that can vary.

Common difference of an increase of 4

Spatial pattern:  ...

Number pattern: 4 8 12 ...

Rule: Number of sticks
= 4 times the number of diamonds


input	20	10	5
output	37	17	7


$output = 2 \times input - 3$

Sam is 5 years older than his sister Mikaela

Mikaela's age	0	3	7	13
Sam's age	5	8	12	18

Sam = Mikaela + 5





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

3A **1** Which number is the incorrect multiple for the following sequence?
3, 6, 9, 12, 15, 18, 22, 24, 27, 30
A 18 **B** 22 **C** 30 **D** 6 **E** 3

3A **2** Which group of numbers contains every factor of 60?
A 2, 3, 4, 5, 10, 12, 15, 60
B 2, 3, 4, 5, 10, 12, 15, 20, 30
C 1, 2, 3, 4, 5, 10, 12, 15, 20, 30
D 2, 3, 4, 5, 10, 15, 20, 30, 60
E 1, 2, 3, 4, 5, 6, 10, 12, 15, 20, 30, 60

3C Ext **3** Which of the following numbers is *not* divisible only by prime numbers, itself and 1?
A 21 **B** 77 **C** 110 **D** 221 **E** 65

3D **4** Which of the following groups of numbers include one prime and two composite numbers?
A 2, 10, 7 **B** 54, 7, 11 **C** 9, 32, 44 **D** 5, 17, 23 **E** 18, 3, 12

3E **5** $7 \times 7 \times 7 \times 7 \times 7$ can be simplified to:
A 5^7 **B** 7^5 **C** 7×5 **D** 75 **E** 77 777

3G **6** Evaluate $\sqrt{3^2 + 4^2}$.
A 7 **B** 5 **C** 14 **D** 25 **E** 6

3B **7** The HCF and LCM of 12 and 18 are:
A 6 and 18 **B** 3 and 12 **C** 2 and 54 **D** 6 and 36 **E** 3 and 18

3F **8** The prime factor form of 48 is:
A $2^4 \times 3$ **B** $2^2 \times 3^2$ **C** 2×3^3 **D** 3×4^2 **E** $2^3 \times 6$

3E **9** Evaluate $4^3 - 3 \times (2^4 - 3^2)$.
A 427 **B** 18 **C** 43 **D** 320 **E** 68

3A **10** Factors of 189 are:
A 3, 7, 9, 18, 21, 27
B 3, 9, 18, 21
C 3, 9, 18
D 3, 7, 9, 17, 21
E 3, 7, 9, 21, 27, 63

3C Ext **11** Which number is *not* divisible by 3?
A 25 697 403
B 31 975
C 7 297 008
D 28 650 180
E 38 629 634 073

3K **12** Which set of points is in a horizontal line?
A (5, 5), (6, 6), (7, 7)
B (3, 2), (3, 4), (3, 11)
C (2, 4), (3, 6), (4, 8)
D (5, 4), (6, 4), (8, 4), (12, 4)
E (1, 5), (5, 1), (1, 1), (5, 5)

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Short-answer questions

3A/D **1** **a** Find the complete set of factors of 120 and circle those that are composite numbers.
b Determine three numbers between 1000 and 2000 that each have factors 1, 2, 3, 4, 5 and itself.

3A/D **2** **a** Write down the first 12 multiples for each of 8 and 7 and circle the odd numbers.
b Which two prime numbers less than 20 have multiples that include both 1365 and 1274?

3B **3** **a** Find the HCF of the following pairs of numbers.
i 15 and 40 **ii** 18 and 26 **iii** 72 and 96
b Find the LCM of the following pairs of numbers.
i 5 and 13 **ii** 6 and 9 **iii** 44 and 8

3D **4** **a** State whether each of these numbers is a prime or composite number.
21, 30, 11, 16, 7, 3, 2
b How many prime multiples are there of 13?

3D/F **5** **a** State the prime factors of 770.
b Determine three composite numbers less than 100, each with only three factors that are all prime numbers less than 10.

3E **6** Simplify these expressions by writing them in index form.
a $6\times6\times6\times6\times6\times6\times6\times6$
b $5\times5\times5\times5\times2\times2\times2\times2\times2$

3F **7** Write these numbers as a product of prime numbers. Use a factor tree and then index form.
a 32 **b** 200 **c** 225

3F **8** Determine which number to the power of 5 equals each of the following.
a 100 000 **b** 243 **c** 1024

3F **9** Evaluate each of the following.
a $5^2 - 3^2$ **b** $2\times4^2 - 5^2$
c $5\times3^4 - 3^2 + 1^6$ **d** $12^2 - (7^2 - 6^2)$

3C Ext **10** Determine whether the following calculations are possible without leaving a remainder.
a $32\,766 \div 4$ **b** $1136 \div 8$ **c** $2417 \div 3$

3C Ext **11** **a** Carry out divisibility tests on the given number and fill in the table with ticks or crosses. State the explanation for each result.

Number	Divisible by 2	Divisible by 3	Divisible by 4	Divisible by 5	Divisible by 6	Divisible by 8	Divisible by 9	Divisible by 10
84 539 424								

b Use divisibility rules to determine a 10-digit number that is divisible by 3, 5, 6 and 9.
c Determine a six-digit number that is divisible by 2, 3, 5, 6, 9 and 10.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3G **12** Evaluate:

a $\sqrt{25}$ **b** $\sqrt{2500}$ **c** $\sqrt{5^2 + 12^2}$

d $4^2 - \sqrt{25} + \sqrt{7^2}$ **e** $\sqrt{16 \times 49} \div \sqrt{4}$ **f** $10^2 \div \sqrt{3^2 + 4^2}$

3H **13** Find the next three terms for the following number patterns that have a common difference.

a 27, 30, 33, … **b** 67, 59, 51, … **c** 238, 196, 154, …


3H **14** Find the next three terms for the following number patterns that have a common ratio.

a 35, 70, 140, … **b** 24 300, 8100, 2700, … **c** 64, 160, 400, …

3H **15** Find the next six terms for each of these number patterns.

a 21, 66, 42, 61, 84, 56, … **b** 22, 41, 79, 136, …

3I **16** **a** Draw the next two shapes in this spatial pattern of sticks.



b Copy and complete this table.

Number of rhombuses	1	2	3	4	5
Number of sticks required					

c Describe the pattern by stating how many sticks are required to make the first rhombus and how many sticks must be added to make the next rhombus in the pattern.

3I **17** A rule to describe a special window spatial pattern is:

Number of sticks = 3 × number of windows + 2

a How many sticks are required to make one window?

b How many sticks are required to make 10 windows?

c How many sticks are required to make g windows?

d How many windows can be made from 65 sticks?

3J **18** Copy and complete each table for the given rule.

a $output = input + 5$

input	3	5	7	12	20
output					

b $output = 2 \times input + 7$

input	4	2	9	12	0
output					

3J **19** Find the rule for each of these tables of values.

a

input	3	4	5	6	7
output	12	13	14	15	16

b

input	1	2	3	4	5
output	20	32	44	56	68

c


input	0	1	2	3	4
output	1	3	5	7	9

d

input	3	4	5	6	7
output	7	6	5	4	3

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

3K **20 a** State the coordinates of each point plotted on this number plane.



b State the coordinates on this grid of a point C so that $ABCD$ is a square.

c State the coordinates on this grid of a point E on the x-axis so that $ABED$ is a trapezium (i.e. has only one pair of parallel sides).

Extended-response questions

1 For the following questions, write the answers in index notation (i.e. b^x) and simplify where possible.

a A rectangle has width 27 cm and length 125 cm. Determine power expressions for its area
and perimeter.


b A square's side length is equal to 4^3. Determine three power expressions for each of the area and perimeter of this square.

c $a \times a \times a \times a \times c \times c$

d $4^3 + 4^3 + 4^3 + 4^3$

e $\dfrac{3^x + 3^x + 3^x}{3}$

2 A class arranges its square desks so that the space between their desks creates rhombuses of identical size, as shown in this diagram.



a How many rhombuses are contained between:

i four desks that are in two rows (as shown in the diagram above)?

ii six desks in two rows?

b Draw 12 desks in three rows arranged this way.

c Rule up a table with columns for the number of:

- rows
- desks per row
- total number of desks
- total number of rhombuses

If there are four desks per row, complete your table for up to 24 desks.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d If there are four desks per row, write a rule for the number of rhombuses in n rows of square desks.

e Using a computer spreadsheet, complete several more tables, varying the number of desks per row.

f Explain how the rule for the number of rhombuses changes when the number of desks, d, per row varies and also the number of rows, n, varies.

g If the number of rows of desks equals the number of desks per row, how many desks would be required to make 10 000 rhombuses?

3 Determine the next three terms in each of these sequences and explain how each is generated.

a 1, 4, 9, 16, 25, …


b 1, 8, 27, 64, …

c (1, 3), (2, 4), (3, 5), …

d 31, 29, 31, 30, 31, 30, …

e $1, \sqrt{2}, \sqrt{3}, 2$, …

f 1, 1, 2, 2, 3, 4, 4, 8, 5, 16, 6, 32, …



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 4

Fractions and percentages

What you will learn

4A What are fractions? (Consolidating)
4B Equivalent fractions and simplified fractions
4C Mixed numbers (Consolidating)
4D Ordering fractions
4E Adding fractions
4F Subtracting fractions
4G Multiplying fractions
4H Dividing fractions
4I Fractions and percentages
4J Percentage of a number
4K Expressing a quantity as a proportion

Australian curriculum

NUMBER AND ALGEBRA

Real numbers

Compare fractions using equivalence. Locate and represent fractions and mixed numerals on a number line (ACMNA152)

Solve problems involving addition and subtraction of fractions, including those with unrelated denominators (ACMNA153)

Multiply and divide fractions and decimals using efficient written strategies and digital technologies (ACMNA154)

Express one quantity as a fraction of another with and without the use of digital technologies (ACMNA155)

Connect fractions, decimals and percentages and carry out simple conversions (ACMNA157)

Find percentages of quantities and express one quantity as a percentage of another, with and without digital technologies. (ACMNA158)

Recognise and solve problems involving simple ratios. (ACMNA173)

Money and financial mathematics

Investigate and calculate 'best buys', with and without digital technologies (ACMNA174)

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Cambridge University Press



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Ancient Egyptian fractions

The ancient Egyptians used fractions over 4000 years ago. The Egyptian sky god Horus was a falcon-headed man whose eyes were believed to have magical healing powers. Egyptian jewellery, ornaments or clothing decorated with the Eye of Horus design were regarded as good luck charms for health and magical protection from evil.


The six parts in the Eye of Horus design represent the six ways that information enters the brain. These six different parts or symbols represented the six fractions used by ancient Egyptian mathematics. For example, instead of writing $\frac{1}{2}$, Egyptians would write  , and instead of writing $\frac{1}{8}$ they would write  .


Eye of Horus fraction symbols are found in ancient Egyptian medical prescriptions for mixing 'magical' medicine. Amazingly, modern doctors still use the eye of Horus () symbolism when they write (Rx) at the start of a prescription.


 $\frac{1}{8}$ thought (eyebrow closest to brain)

 $\frac{1}{16}$ hearing (pointing to ear)

 $\frac{1}{2}$ smell (pointing to nose)

 $\frac{1}{4}$ sight (pupil of the eye)

 $\frac{1}{64}$ touch (leg touching the ground)

 $\frac{1}{32}$ taste (curled top of wheat plant)

A proportion or fraction can be written using a combination of these symbols. For example:

$\frac{3}{4} =$  and

$\frac{3}{16} =$  .

Which symbols would represent $\frac{7}{8}$? Can $\frac{1}{3}$ be written using the Eye of Horus symbols?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4A What are fractions? CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

The word 'fraction' comes from the Latin word 'frangere', which means 'to break into pieces'.

Although the following sentences are not directly related to the mathematical use of fractions, they all contain words that are related to the orginal Latin term 'frangere' and they help us gain an understanding of exactly what a fraction is.

- *The fragile vase smashed into a hundred pieces when it landed on the ground.*
- *After the window was broken, several fragments were found on the floor.*
- *She fractured her leg in two places.*
- *The computer was running slowly and needed to be defragmented.*
- *The elderly gentleman was becoming very frail in his old age.*



Fragments of a broken object are all fractions of the whole.

Can you think of any other related sentences?

Brainstorm specific common uses of fractions in everyday life. The list could include cooking, shopping, sporting, building examples and more.

Let's start: What strength do you like your cordial?

- Imagine preparing several jugs of different strength cordial. Samples could include $\frac{1}{4}$ strength cordial, $\frac{1}{5}$ strength cordial, $\frac{1}{6}$ strength cordial, $\frac{1}{8}$ strength cordial.
- In each case, describe how much water and how much cordial is needed to make a 1 litre mixture. Note: 1 litre (L) = 1000 millilitres (mL).
- On the label of a Cottee's cordial container, it suggests 'To make up by glass or jug: add five parts water to one part Cottee's Fruit Juice Cordial, according to taste'. What fraction of cordial do Cottee's suggest is the best?

Key ideas

- A fraction is made up of a numerator (**u**p) and a denominator (**d**own).

  For example: $\frac{3}{5}$ ← numerator, ← denominator


  - The **denominator** tells you how many parts the whole is divided up into.
  - The **numerator** tells you how many of the divided parts you have selected.
  - The horizontal line separating the numerator and the denominator is called the **vinculum**.
- A **proper fraction** or **common fraction** is less than a whole, and therefore the numerator must be smaller than the denominator.

  For example: $\frac{2}{7}$ is a proper fraction.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Key ideas

- An **improper fraction** is greater than a whole, and therefore the numerator must be larger than the denominator.
  For example: $\frac{5}{3}$ is an improper fraction.
- We can represent fractions on a number line.
  This number line shows the whole numbers 0, 1 and 2. Each unit has then been divided equally into four segments, therefore creating 'quarters'.



- Whole numbers can be represented as fractions.
  On the number line above we see that 1 is the same as $\frac{4}{4}$ and 2 is the same as $\frac{8}{4}$.
- We can represent fractions using area. If a shape is divided into regions of equal areas, then shading a certain number of these regions will create a fraction of the whole shape.
  For example:  Fraction shaded = $\frac{3}{4}$

Example 1 Understanding the numerator and the denominator



a Into how many pieces has the whole pizza been divided?
b How many pieces have been selected (shaded)?
c In representing the shaded fraction of the pizza:
  i What must the denominator equal?
  ii What must the numerator equal?
  iii Write the amount of pizza selected (shaded) as a fraction.


SOLUTION	EXPLANATION
a 8	Pizza cut into 8 equal pieces.
b 3	3 of the 8 pieces are shaded in blue.
c i 8	Denominator shows the number of parts the whole has been divided into.
ii 3	Numerator tells how many of the divided parts you have selected.
iii $\frac{3}{8}$	Shaded fraction is the numerator over the denominator; i.e. 3 out of 8 divided pieces.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 2 Representing fractions on a number line

Represent the fractions $\frac{3}{5}$ and $\frac{9}{5}$ on a number line.

SOLUTION



EXPLANATION


Draw a number line starting at 0 and mark on it the whole numbers 0, 1 and 2.

Divide each whole unit into five segments of equal length. Each of these segments has a length of one-fifth.

Example 3 Shading areas

Represent the fraction $\frac{3}{4}$ in three different ways, using a square divided into four equal regions.

SOLUTION



EXPLANATION

Ensure division of square creates four equal areas. Shade in three of the four regions.

Exercise 4A

1–4 | 4 | —

UNDERSTANDING

1 **a** State the denominator of this proper fraction: $\frac{2}{9}$.

b State the numerator of this improper fraction: $\frac{7}{5}$.

2 Group the following list of fractions into proper fractions, improper fractions and whole numbers.

a $\frac{7}{6}$ **b** $\frac{2}{7}$ **c** $\frac{50}{7}$ **d** $\frac{3}{3}$

e $\frac{3}{4}$ **f** $\frac{5}{11}$ **g** $\frac{1}{99}$ **h** $\frac{9}{4}$

i $\frac{11}{8}$ **j** $\frac{10}{10}$ **k** $\frac{5}{1}$ **l** $\frac{121}{5}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4A

UNDERSTANDING

Example 1

3 Answer the following questions for each of the pizzas (**A** to **D**) drawn below.

a Into how many pieces has the whole pizza been divided?

b How many pieces have been selected (shaded)?


c In representing the shaded fraction of the pizza:

i What must the denominator equal?


ii What must the numerator equal?

iii Write the amount of pizza selected (shaded) as a fraction.


A




B



C



D



4 Find the whole numbers amongst the following list of fractions. Hint: There are five whole numbers to find.

a $\frac{15}{4}$ **b** $\frac{14}{8}$ **c** $\frac{12}{5}$ **d** $\frac{30}{15}$

e $\frac{17}{3}$ **f** $\frac{30}{12}$ **g** $\frac{12}{12}$ **h** $\frac{33}{10}$

i $\frac{53}{3}$ **j** $\frac{9}{3}$ **k** $\frac{50}{20}$ **l** $\frac{28}{7}$

m $\frac{96}{8}$ **n** $\frac{24}{5}$ **o** $\frac{62}{4}$ **p** $\frac{1031}{2}$

5(½), 6 | 5(½), 6, 7(½) | 5(½), 6, 7(½)

FLUENCY

Example 2

5 Represent the following fractions on a number line.

a $\frac{3}{7}$ and $\frac{6}{7}$ **b** $\frac{2}{3}$ and $\frac{5}{3}$ **c** $\frac{1}{6}$ and $\frac{5}{6}$

d $\frac{2}{4}$ and $\frac{11}{4}$ **e** $\frac{11}{5}$ and $\frac{8}{5}$ **f** $\frac{5}{4}$, $\frac{9}{4}$ and $\frac{3}{2}$

Example 3

6 Represent each of these fractions in three different ways, using a rectangle divided into equal regions.

a $\frac{1}{4}$ **b** $\frac{3}{8}$ **c** $\frac{2}{6}$

7 Write the next three fractions for each of the following fraction sequences.

a $\frac{3}{5}, \frac{4}{5}, \frac{5}{5}, \frac{6}{5}$, ___, ___, ___

b $\frac{5}{8}, \frac{6}{8}, \frac{7}{8}, \frac{8}{8}$, ___, ___, ___

c $\frac{1}{3}, \frac{2}{3}, \frac{3}{3}, \frac{4}{3}$, ___, ___, ___

d $\frac{11}{7}, \frac{10}{7}, \frac{9}{7}, \frac{8}{7}$, ___, ___, ___

e $\frac{13}{2}, \frac{11}{2}, \frac{9}{2}, \frac{7}{2}$, ___, ___, ___

f $\frac{3}{4}, \frac{8}{4}, \frac{13}{4}, \frac{18}{4}$, ___, ___, ___

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4A

8 | 8, 9 | 9, 10


PROBLEM-SOLVING

8 What fractions correspond to each of the different shapes positioned on these number lines?

a




b



c




d



9 What operation (i.e. +, –, × or ÷) does the vinculum relate to?

10 For each of the following, state what fraction of the diagram is shaded.


a



b



c




d



e



f



11 | 11, 12 | 12, 13

REASONING

11 For each of the following, write the fraction that is describing part of the total.

- **a** After one day of a 43-kilometre hike, they had completed 12 kilometres.
- **b** From 15 starters, 13 went on and finished the race.
- **c** Rainfall for 11 months of the year was below average.
- **d** One egg is broken in a carton that contains a dozen eggs.
- **e** Two players in the soccer team scored a goal.
- **f** The lunch stop was 144 kilometres into the 475-kilometre trip.
- **g** Seven members in the class of 20 have visited Australia Zoo.
- **h** One of the car tyres is worn and needs replacing.
- **i** It rained three days this week.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press


4A

REASONING


12 Explain the logic behind the terms 'proper fraction' and 'improper fraction'.

13 Which diagram has one-quarter shaded?


a




b



c



d



Adjusting concentration — — 14

ENRICHMENT

14 a A 250-millilitre glass of cordial is made by mixing four parts water to one part cordial.

- **i** What fraction of the glass is cordial?
- **ii** What amount of cordial is required?

b Fairuz drinks 50 millilitres of the glass and thinks it's 'too strong'. So he fills the glass back up with 50 millilitres of pure water.

- **i** How much cordial is in the glass now?
- **ii** What fraction of the glass is cordial?

c Fairuz drinks 50 millilitres of the drink but he still thinks it is 'too strong'. So, once again, he fills the glass back up with 50 millilitres of pure water.

- **i** How much cordial is in the glass now?
- **ii** What fraction of the glass is cordial?

d Lynn prefers her cordial much stronger compared with Fairuz. When she is given a glass of the cordial that is mixed at four parts to one, she drinks 50 millilitres and decides it is 'too weak'. So she fills the glass back up with 50 millilitres of straight cordial.

- **i** How much cordial is in Lynn's glass after doing this once?
- **ii** What fraction of the glass is cordial?

e Like Fairuz, Lynn needs to repeat the process to make her cordial even stronger. So, once again, she drinks 50 millilitres and then tops the glass back up with 50 millilitres of straight cordial.

- **i** How much cordial is in Lynn's glass now?
- **ii** What fraction of the glass is cordial?

f If Fairuz continues diluting his cordial concentration in this manner and Lynn continues strengthening her cordial concentration in this manner, will either of them ever reach pure water or pure cordial? Explain your reasoning.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4B Equivalent fractions and simplified fractions

Interactive

Widgets

HOTsheets

Walkthroughs

Often fractions may look very different when in fact they have the same value.


For example, in an AFL football match, 'half-time' is the same as 'the end of the second quarter'. We can say that $\frac{1}{2}$ and $\frac{2}{4}$ are equivalent fractions. In both situations, the equivalent fraction of the game has been completed.



There are four quarters played out in a game of AFL football.

Consider a group of friends eating pizzas during a sleepover. The pizzas are homemade and each person cuts up their pizza as they like.

Trevor cuts his pizza into only two pieces, Jackie cuts hers into four pieces, Tahlia into six pieces and Jared into eight pieces. The shaded pieces are the amount that they have eaten before it is time to start the second movie.



By looking at the pizzas, it is clear to see that Trevor, Jackie, Tahlia and Jared have all eaten the same amount of pizza. We can therefore conclude that $\frac{1}{2}$, $\frac{2}{4}$, $\frac{3}{6}$ and $\frac{4}{8}$ are equivalent fractions.

This is written as $\frac{1}{2} = \frac{2}{4} = \frac{3}{6} = \frac{4}{8}$.

Let's start: Fraction clumps

- Prepare a class set of fraction cards. (Two example sets are provided below.)
- Hand out one fraction card to each student.
- Students then arrange themselves into groups of equivalent fractions.
- Set an appropriate time goal by which this task must be completed.
- Repeat the process with a second set of equivalent fraction cards.

Sample sets of fraction cards

Class set 1

$\frac{1}{2}, \frac{3}{12}, \frac{3}{24}, \frac{10}{80}, \frac{1}{3}, \frac{8}{40}, \frac{1}{5}, \frac{3}{6}, \frac{1}{8}, \frac{5}{40}, \frac{3}{9}, \frac{1}{4}, \frac{1000}{4000}, \frac{100}{200}, \frac{10}{50}, \frac{2}{16}, \frac{10}{30}, \frac{13}{39}, \frac{5}{10}, \frac{7}{14}, \frac{2}{6}, \frac{7}{28}, \frac{2}{10}, \frac{4}{20}, \frac{2}{8}$

Class set 2

$\frac{2}{3}, \frac{6}{14}, \frac{3}{18}, \frac{4}{10}, \frac{2}{12}, \frac{24}{64}, \frac{11}{66}, \frac{4}{6}, \frac{3}{7}, \frac{30}{70}, \frac{12}{32}, \frac{3}{8}, \frac{10}{15}, \frac{5}{30}, \frac{1}{6}, \frac{2000}{5000}, \frac{21}{49}, \frac{300}{800}, \frac{6}{9}, \frac{9}{21}, \frac{2}{5}, \frac{14}{35}, \frac{20}{30}, \frac{6}{16}, \frac{22}{55}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- **Equivalent fractions** are fractions that mark the same place on a number line.
  For example: $\frac{1}{2}$ and $\frac{2}{4}$ are equivalent fractions.
- Equivalent fractions are produced by multiplying the numerator and denominator by the same number. This number can be any whole number greater than 1.
- Equivalent fractions can also be produced by dividing the numerator and denominator by the same number.
- **Simplifying fractions** involves writing a fraction in its 'simplest form' or 'easiest form' or 'most convenient form'. To do this, the numerator and the denominator must be divided by their **highest common factor (HCF)**.
- It is a mathematical convention to write all answers involving fractions in their simplest form.

Example 4 Producing equivalent fractions

Write four equivalent fractions for $\frac{2}{3}$.

SOLUTION

$\frac{2}{4} = \frac{4}{6} = \frac{6}{9} = \frac{8}{12} = \frac{10}{15}$

Many other fractions are also possible.

Other common choices include:

$\frac{20}{30}, \frac{200}{300}, \frac{2000}{3000}, \frac{40}{60}$

EXPLANATION

$\frac{2}{3} \overset{\times 2}{=} \frac{4}{6} \overset{\times 3}{=} \frac{6}{9} \overset{\times 4}{=} \frac{8}{12} \overset{\times 5}{=} \frac{10}{15}$

Example 5 Checking for equivalence

By writing either = or ≠ between the fractions, state whether the following pairs of fractions are equivalent or not equivalent.

a $\frac{1}{3} \quad \frac{3}{7}$

b $\frac{4}{5} \quad \frac{20}{25}$

SOLUTION

a $\frac{1}{3} \neq \frac{3}{7}$

b $\frac{4}{5} = \frac{20}{25}$

EXPLANATION

Convert to a common denominator.

$\frac{1}{3} = \frac{1 \times 7}{3 \times 7} = \frac{7}{21}$ and $\frac{3}{7} = \frac{3 \times 3}{7 \times 3} = \frac{9}{21}$, $\frac{7}{21} \neq \frac{9}{21}$

$\frac{4}{5} = \frac{4 \times 5}{5 \times 5} = \frac{20}{25}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 6 Converting to simplest form

Write these fractions in simplest form.

a $\frac{12}{20}$ **b** $\frac{7}{42}$

SOLUTION

a $\frac{12}{20} = \frac{3 \times \cancel{4}}{5 \times \cancel{4}} = \frac{3}{5}$

b $\frac{7}{42} = \frac{\cancel{7} \times 1}{\cancel{7} \times 6} = \frac{1}{6}$

EXPLANATION

The HCF of 12 and 20 is 4.

Both the numerator and the denominator are divided by the HCF of 4.

The HCF of 7 and 42 is 7.

The 7 is 'cancelled' from the numerator and the denominator.

Exercise 4B

1–5 | 5 | —

UNDERSTANDING

1 Which of the following fractions are equivalent to $\frac{1}{2}$?

$\frac{3}{5}, \frac{3}{6}, \frac{3}{10}, \frac{2}{4}, \frac{11}{22}, \frac{7}{15}, \frac{8}{12}, \frac{2}{1}, \frac{5}{10}, \frac{6}{10}$

2 Which of the following fractions are equivalent to $\frac{8}{20}$?

$\frac{4}{10}, \frac{1}{5}, \frac{6}{20}, \frac{8}{10}, \frac{16}{40}, \frac{2}{5}, \frac{4}{12}, \frac{12}{40}, \frac{80}{200}, \frac{1}{4}$

3 Fill in the missing numbers to complete the following strings of equivalent fractions.

a $\frac{1}{3} = \frac{\square}{6} = \frac{4}{\square} = \frac{\square}{30} = \frac{\square}{60} = \frac{100}{\square}$

b $\frac{2}{8} = \frac{\square}{4} = \frac{\square}{12} = \frac{6}{\square} = \frac{\square}{80} = \frac{10}{\square}$

4 In the following lists of equivalent fractions, circle the fraction that is in its simplest form.

a $\frac{3}{15}, \frac{10}{50}, \frac{2}{10}, \frac{1}{5}$ **b** $\frac{100}{600}, \frac{3}{18}, \frac{1}{6}, \frac{7}{42}$

c $\frac{4}{6}, \frac{2}{3}, \frac{16}{24}, \frac{20}{30}$ **d** $\frac{9}{12}, \frac{15}{20}, \frac{6}{8}, \frac{3}{4}$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4B

UNDERSTANDING

5 Fill in the gaps to reduce these fractions to their simplest form.

a $\frac{10}{30}$ **i** HCF = ☐ **ii** $\frac{10}{30} = \frac{1 \times \square}{3 \times \square}$. Therefore, simplest form is $\frac{\square}{3}$.

b $\frac{4}{18}$ **i** HCF = ☐ **ii** $\frac{4}{18} = \frac{2 \times \square}{9 \times \square}$. Therefore, simplest form is $\frac{\square}{9}$.

c $\frac{4}{28}$ **i** HCF = ☐ **ii** $\frac{4}{28} = \frac{1 \times \square}{7 \times \square}$. Therefore, simplest form is $\frac{1}{\square}$.

d $\frac{9}{15}$ **i** HCF = ☐ **ii** $\frac{9}{15} = \frac{3 \times \square}{5 \times \square}$. Therefore, simplest form is $\frac{\square}{\square}$.

6–9(½) 6–10(½) 6–10(½)

FLUENCY

Example 4

6 Write four equivalent fractions for each of the fractions listed.

a $\frac{1}{2}$ **b** $\frac{1}{4}$ **c** $\frac{2}{5}$ **d** $\frac{3}{5}$

e $\frac{2}{9}$ **f** $\frac{3}{7}$ **g** $\frac{5}{12}$ **h** $\frac{3}{11}$

7 Find the unknown value to make the equation true.

a $\frac{3}{4} = \frac{?}{12}$ **b** $\frac{5}{8} = \frac{?}{80}$ **c** $\frac{6}{11} = \frac{18}{?}$ **d** $\frac{2}{7} = \frac{16}{?}$

e $\frac{3}{?} = \frac{15}{40}$ **f** $\frac{?}{1} = \frac{14}{7}$ **g** $\frac{?}{10} = \frac{24}{20}$ **h** $\frac{13}{14} = \frac{?}{42}$

i $\frac{2}{7} = \frac{10}{?}$ **j** $\frac{19}{20} = \frac{190}{?}$ **k** $\frac{11}{21} = \frac{55}{?}$ **l** $\frac{11}{?} = \frac{44}{8}$

Example 5

8 Write either = or ≠ between the fractions, to state whether the following pairs of fractions are equivalent or not equivalent.

a $\frac{1}{2}$ $\frac{5}{8}$ **b** $\frac{4}{8}$ $\frac{2}{4}$ **c** $\frac{3}{7}$ $\frac{30}{60}$

d $\frac{5}{9}$ $\frac{15}{18}$ **e** $\frac{11}{15}$ $\frac{33}{45}$ **f** $\frac{1}{2}$ $\frac{402}{804}$

g $\frac{12}{36}$ $\frac{1}{3}$ **h** $\frac{18}{24}$ $\frac{21}{28}$ **i** $\frac{6}{18}$ $\frac{11}{33}$

Example 6

9 Write the following fractions in simplest form.

a $\frac{15}{20}$ **b** $\frac{12}{18}$ **c** $\frac{10}{30}$ **d** $\frac{8}{22}$

e $\frac{14}{35}$ **f** $\frac{2}{22}$ **g** $\frac{8}{56}$ **h** $\frac{9}{27}$

i $\frac{35}{45}$ **j** $\frac{36}{96}$ **k** $\frac{120}{144}$ **l** $\frac{700}{140}$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4B

FLUENCY

10 These lists of fractions are meant to contain only fractions in their simplest form; however, there is one mistake in each list. Find the fraction that is not in simplest form and rewrite it in its simplest form.

a $\frac{1}{3}, \frac{3}{8}, \frac{5}{9}, \frac{7}{14}$

b $\frac{2}{5}, \frac{12}{16}, \frac{16}{9}, \frac{13}{37}$

c $\frac{12}{19}, \frac{4}{42}, \frac{5}{24}, \frac{6}{61}$

d $\frac{7}{63}, \frac{9}{62}, \frac{11}{81}, \frac{13}{72}$

11 | 11, 12 | 12

PROBLEM-SOLVING

11 A family block of chocolate consists of 12 rows of 6 individual squares. Tania eats 16 individual squares. What fraction of the block, in simplest terms, has Tania eaten?



12 Four people win a competition that allows them to receive $\frac{1}{2}$ a tank of free petrol. Find how many litres of petrol the drivers of these cars receive.

a Ford Territory with a 70-litre tank

b Nissan Patrol with a 90-litre tank

c Holden Commodore with a 60-litre tank

d Mazda 323 with a 48-litre tank



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4B

13 | 13, 14 | 14, 15

REASONING

13 Justin, Joanna and Jack are sharing a large pizza for dinner. The pizza has been cut into 12 equal pieces. Justin would like $\frac{1}{3}$ of the pizza, Joanna would like $\frac{1}{4}$ of the pizza and Jack will eat whatever is remaining. By considering equivalent fractions, determine how many slices each person gets served.

14 J.K. Rowling's first book, *Harry Potter and the Philosopher's Stone*, is 225 pages long. Sam plans to read the book in three days, reading the same number of pages each day.

a How many pages should Sam read each day?

b The fraction $\frac{75}{225}$ of the book is equivalent to what fraction in simplest form?

By the end of the second day, Sam is on track and has read $\frac{2}{3}$ of the book.

c How many pages of the book is $\frac{2}{3}$ equivalent to?

15 A fraction when simplified is written as $\frac{3}{5}$. What could the fraction have been before it was simplified?

Equivalent bars of music

— | — | 16

ENRICHMENT

16 Each piece of music has a time signature. A common time signature is called $\frac{4}{4}$ time, and is actually referred to as Common time!

Common time, or $\frac{4}{4}$ time, means that there are four 'quarter notes' (or crotchets) in each bar.

Listed below are the five most commonly used musical notes.

 – whole note (fills the whole bar) – semibreve

 – half note (fills half the bar) – minim

 – quarter note (four of these to a bar) – crotchet

 – eighth note (eight to a bar) – quaver

 – sixteenth note (sixteen to a bar) – semi-quaver

a Write six different 'bars' of music in $\frac{4}{4}$ time.

Carry out some research on other types of musical time signatures.

b Do you know what the time signature $\frac{12}{8}$ means?

c Write three different bars of music for a $\frac{12}{8}$ time signature.

d What are the musical symbols for different length rests?

e How does a dot (or dots) written after a note affect the length of the note?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4C Mixed numbers CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

As we have seen in this chapter, a fraction is a common way of representing part of a whole number. For example, a particular car trip may require $\frac{2}{3}$ of a tank of petrol.

On many occasions, you may need whole numbers plus a part of a whole number. For example, a long interstate car trip may require $2\frac{1}{4}$ tanks of petrol.

When you have a combination of a whole number and a fraction this number is known as a **mixed number**.



A long car trip may require a full tank of petrol and another fraction of a tank as well.

Let's start: Pizza frenzy

With a partner, attempt to solve the following pizza problem. There is more than one answer.

At Pete's pizza shop, small pizzas are cut into four equal slices, medium pizzas are cut into six equal slices and large pizzas are cut into eight equal slices.

For a class party, the teacher ordered 13 pizzas, which the students ate with ease. After the last slice was eaten, a total of 82 slices of pizza had been eaten by the students. How many pizzas of each size did the teacher order?

Key ideas

- A number is said to be a **mixed number** when it is a mix of a whole number plus a proper fraction.

$2\frac{3}{5}$ is a mixed number

whole number: 2 — proper fraction: $\frac{3}{5}$

- **Improper fractions** (fractions greater than a whole, where the numerator is greater than the denominator) can be converted to mixed numbers or whole numbers.


$\frac{15}{4} = 3\frac{3}{4}$ (improper fraction → mixed number)

$\frac{16}{4} = 4$ (improper fraction → whole number)

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Mixed numbers can be converted to improper fractions.
- In general, improper fractions should be written as mixed numbers, with the fraction part written in simplest form.
- A number line helps show the different types of fractions.



Example 7 Converting mixed numbers to improper fractions

Convert $3\frac{1}{5}$ to an improper fraction.

SOLUTION

$3\frac{1}{5} = 1 + 1 + 1 + \frac{1}{5}$

$= \frac{5}{5} + \frac{5}{5} + \frac{5}{5} + \frac{1}{5}$

$= \frac{16}{5}$


or

$3\frac{1}{5} = \frac{15}{5} + \frac{1}{5}$

$= \frac{16}{5}$

EXPLANATION

$3\frac{1}{5}$ = 3 wholes + $\frac{1}{5}$ of a whole



Short-cut method:

Multiply the whole number part by the denominator and then add the numerator.

$3 \times 5 + 1 = 16$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 8 Converting improper fractions to mixed numbers

Convert $\frac{11}{4}$ to a mixed number.

SOLUTION

Method 1

$$\frac{11}{4} = \frac{8+3}{4} = \frac{8}{4} + \frac{3}{4} = 2 + \frac{3}{4} = 2\frac{3}{4}$$


Method 2

$$4\overline{)11} \quad 2 \text{ rem } 3$$

So $\frac{11}{4} = 2\frac{3}{4}$

EXPLANATION

$\frac{11}{4}$ = 11 quarters



$= 2\frac{3}{4}$

Example 9 Writing mixed numbers in simplest form

Convert $\frac{20}{6}$ to a mixed number in simplest form.

SOLUTION

$$\frac{20}{6} = 3\frac{2}{6} = 3\frac{1 \times \cancel{2}}{3 \times \cancel{2}} = 3\frac{1}{3}$$

or

$$\frac{20}{6} = \frac{10 \times \cancel{2}}{3 \times \cancel{2}} = \frac{10}{3} = 3\frac{1}{3}$$

EXPLANATION

Method 1: Convert to mixed number and then simplify the fraction part.

Method 2: Simplify the improper fraction first and then convert to a mixed number.



Each pane of glass is $\frac{1}{12}$ of the whole window.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4C

1–5 | 5 | —

UNDERSTANDING

1 Between which two whole numbers do the following mixed numbers lie?

a $2\frac{1}{2}$ **b** $11\frac{1}{7}$ **c** $36\frac{8}{9}$

2 Work out the total number of pieces in each of these situations.


a four pizzas cut into six pieces each

b 10 Lego trucks, where each truck is made from 36 Lego pieces

c five jigsaw puzzles with 12 pieces in each puzzle

d three cakes cut into eight pieces each


3 The mixed number $2\frac{3}{4}$ can be represented in 'window shapes' as

$2\frac{3}{4} =$  $+ \quad +$

Represent the following mixed numbers using 'window shapes'.

a $1\frac{1}{4}$ **b** $1\frac{3}{4}$ **c** $3\frac{2}{4}$ **d** $5\frac{2}{4}$

4 A 'window shape' consists of four panes of glass. How many panes of glass are there in the following number of 'window shapes'?




a 2 **b** 3 **c** 7 **d** 11

e $4\frac{1}{4}$ **f** $1\frac{3}{4}$ **g** $2\frac{2}{4}$ **h** $5\frac{4}{4}$

5 What mixed numbers correspond to the letters written on each number line?

a



b



c



6–8(½) | 6–8(½) | 6–8(½)

FLUENCY

Example 7

6 Convert these mixed numbers to improper fractions.

a $2\frac{1}{5}$ **b** $1\frac{3}{5}$ **c** $3\frac{1}{3}$ **d** $5\frac{2}{3}$ **e** $4\frac{1}{7}$ **f** $3\frac{3}{7}$

g $2\frac{1}{2}$ **h** $6\frac{1}{2}$ **i** $4\frac{2}{3}$ **j** $11\frac{1}{3}$ **k** $8\frac{2}{5}$ **l** $10\frac{3}{10}$

m $6\frac{1}{9}$ **n** $2\frac{7}{9}$ **o** $5\frac{2}{8}$ **p** $2\frac{5}{8}$ **q** $1\frac{11}{12}$ **r** $3\frac{5}{11}$

s $4\frac{5}{12}$ **t** $9\frac{7}{12}$ **u** $5\frac{15}{20}$ **v** $8\frac{3}{100}$ **w** $64\frac{3}{10}$ **x** $20\frac{4}{5}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4C

FLUENCY

Example 8

7 Convert these improper fractions to mixed numbers.

a $\frac{7}{5}$ **b** $\frac{4}{3}$ **c** $\frac{5}{3}$ **d** $\frac{7}{4}$

e $\frac{11}{3}$ **f** $\frac{21}{5}$ **g** $\frac{16}{7}$ **h** $\frac{10}{4}$

i $\frac{12}{7}$ **j** $\frac{19}{6}$ **k** $\frac{20}{3}$ **l** $\frac{41}{4}$

m $\frac{35}{8}$ **n** $\frac{26}{5}$ **o** $\frac{48}{7}$ **p** $\frac{41}{3}$

q $\frac{37}{12}$ **r** $\frac{81}{11}$ **s** $\frac{93}{10}$ **t** $\frac{78}{7}$

u $\frac{231}{100}$ **v** $\frac{333}{10}$ **w** $\frac{135}{11}$ **x** $\frac{149}{12}$

Example 9

8 Convert these improper fractions to mixed numbers in their simplest form.

a $\frac{10}{4}$ **b** $\frac{28}{10}$ **c** $\frac{16}{12}$ **d** $\frac{8}{6}$

e $\frac{18}{16}$ **f** $\frac{30}{9}$ **g** $\frac{40}{15}$ **h** $\frac{60}{25}$

9 | 9, 10 | 10, 11

PROBLEM-SOLVING

9 Draw a number line from 0 to 5 and mark on it the following fractions.

a $\frac{2}{3}, 2, \frac{5}{3}, 3\frac{1}{3}$ **b** $\frac{3}{4}, \frac{12}{4}, 2\frac{1}{4}, 3\frac{1}{2}$ **c** $\frac{4}{5}, \frac{14}{5}, 3\frac{1}{5}, \frac{10}{5}, \frac{19}{5}$

10 Fill in the gaps for the following number patterns.

a $1\frac{1}{3}, 1\frac{2}{3}, 2, ___, 2\frac{2}{3}, 3, 3\frac{1}{3}, ___, ___, 4\frac{1}{3}, 4\frac{2}{3}, 5$

b $\frac{3}{7}, \frac{5}{7}, 1, 1\frac{2}{7}, ___, 1\frac{6}{7}, ___, 2\frac{3}{7}, 2\frac{5}{7}, ___, 3\frac{2}{7}, ___, ___$

c $\frac{3}{5}, 1\frac{1}{5}, 1\frac{4}{5}, ___, 3, 3\frac{3}{5}, ___, ___, 5\frac{2}{5}, ___, 6\frac{3}{5}, ___$

11 Four friends order three large pizzas for their dinner. Each pizza is cut into eight equal slices. Simone has three slices, Izabella has four slices, Mark has five slices and Alex has three slices.

a How many pizza slices do they eat in total?

b How many pizzas do they eat in total? Give your answer as a mixed number.

c How many pizza slices are left uneaten?

d How many pizzas are left uneaten? Give your answer as a mixed number.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4C

12 12 12

REASONING

12 **a** Patricia has three sandwiches that are cut into quarters and she eats all but one-quarter. How many quarters does she eat?

b Phillip has five sandwiches that are cut into halves and he eats all but one-half. How many halves does he eat?

c Crystal has x sandwiches that are cut into quarters and she eats them all but one-quarter. How many quarters does she eat?

d Byron has y sandwiches that are cut into thirds and he eats all but one-third. How many thirds does he eat?

e Felicity has m sandwiches that are cut into n pieces and she eats them all. How many pieces does she eat?



Mixed number swap meet

— — 13

ENRICHMENT

13 **a** Using the digits 1, 2 and 3 only once, three different mixed numbers can be written.

i Write down the three possible mixed numbers.

ii Find the difference between the smallest and highest mixed numbers.

b Repeat part **a** using the digits 2, 3 and 4.

c Repeat part **a** using the digits 3, 4 and 5.

d Predict the difference between the largest and smallest mixed number when using only the digits 4, 5 and 6. Check to see if your prediction is correct.

e Write down a rule for the difference between the largest and smallest mixed numbers when using any three consecutive integers.

f Extend your investigation to allow mixed numbers where the fraction part is an improper fraction.

g Extend your investigation to produce mixed numbers from four consecutive digits.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4D Ordering fractions

Interactive

Widgets

HOTsheets

Walkthroughs

You already know how to order a set of whole numbers.

For example: 3, 7, 15, 6, 2, 10 are a set of six different whole numbers that you could place in ascending or descending order.


In ascending order, the correct order is: 2, 3, 6, 7, 10, 15.

In descending order, the correct order is: 15, 10, 7, 6, 3, 2.

In this section you will learn how to write different fractions in ascending and descending order. To be able to do this we need to compare different fractions and we do this through our knowledge of equivalent fractions (see Section 4B).

Remember a fraction is greater than another fraction if it lies to the right of that fraction on a number line.

$\frac{3}{4} > \frac{1}{2}$



Let's start: The order of five

- As a warm-up activity, ask five volunteer students to arrange themselves in alphabetical order, then in height order and, finally, in birthday order.
- Each of the five students receives a large fraction card and displays it to the class.
- The rest of the class must then attempt to order the students in ascending order, according to their fraction card. It is a group decision and none of the five students should move until the class agrees on a decision.
- Repeat the activity with a set of more challenging fraction cards.



Key ideas

- To **order** (or arrange) fractions we must know how to compare different fractions. This is often done by considering equivalent fractions.
- If the numerators are the same, the smallest fraction is the one with the biggest denominator, as it has been divided up into the most pieces.

  For example: $\frac{1}{7} < \frac{1}{2}$
- If the denominators are the same, the smallest fraction is the one with the smallest numerator.

  For example: $\frac{3}{10} < \frac{7}{10}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- To order two fractions with different numerators and denominators, we can use our knowledge of equivalent fractions to produce fractions with a common denominator and then compare the numerators.
- The **lowest common denominator (LCD)** is the lowest common multiple of the different denominators.
- **Ascending** order is when numbers are ordered going *up*, from smallest to largest.
- **Descending** order is when numbers are ordered going *down*, from largest to smallest.

Example 10 Comparing fractions

Place the correct mathematical symbol <, = or >, in between the following pairs of fractions to make true mathematical statements.

a $\frac{2}{5} \square \frac{4}{5}$

b $\frac{1}{3} \square \frac{1}{5}$

c $\frac{2}{3} \square \frac{3}{5}$

d $2\frac{3}{7} \square \frac{16}{7}$

SOLUTION	EXPLANATION
a $\frac{2}{5} \boxed{<} \frac{4}{5}$	Denominators are the same, therefore compare numerators.
b $\frac{1}{3} \boxed{>} \frac{1}{5}$	Numerators are the same. Smallest fraction has the biggest denominator.
c $\frac{2}{3} \square \frac{3}{5}$ $\frac{10}{15} \boxed{>} \frac{9}{15}$. Hence, $\frac{2}{3} \boxed{>} \frac{3}{5}$.	LCD of 3 and 5 is 15. Produce equivalent fractions. Denominators now the same, therefore compare numerators.
d $2\frac{3}{7} \square \frac{16}{7}$ $\frac{17}{7} \boxed{>} \frac{16}{7}$. Hence, $2\frac{3}{7} \boxed{>} \frac{16}{7}$.	Convert mixed number to an improper fraction. Denominators are the same, therefore compare numerators.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Ordering fractions

Place the following fractions in ascending order.

a $\frac{3}{4}, \frac{4}{5}, \frac{2}{3}$

b $1\frac{3}{5}, \frac{7}{4}, \frac{3}{2}, 2\frac{1}{4}, \frac{11}{5}$

SOLUTION	EXPLANATION
a $\frac{45}{60}, \frac{48}{60}, \frac{40}{60}$	LCD of 3, 4 and 5 is 60. Produce equivalent fractions with denominator of 60.
$\frac{40}{60}, \frac{45}{60}, \frac{48}{60}$	Order fractions in ascending order.
$\frac{2}{3}, \frac{3}{4}, \frac{4}{5}$	Rewrite fractions back in original form.
b $\frac{8}{5}, \frac{7}{4}, \frac{3}{2}, \frac{9}{4}, \frac{11}{5}$	Express all fractions as improper fractions.
$\frac{32}{20}, \frac{35}{20}, \frac{30}{20}, \frac{45}{20}, \frac{44}{20}$	LCD of 2, 4 and 5 is 20. Produce equivalent fractions with a denominator of 20.
$\frac{30}{20}, \frac{32}{20}, \frac{35}{20}, \frac{44}{20}, \frac{45}{20}$	Order fractions in ascending order.
$\frac{3}{2}, 1\frac{3}{5}, \frac{7}{4}, \frac{11}{5}, 2\frac{1}{4}$	Rewrite fractions back in original form.

Exercise 4D

1–4(½) | 3–4(½) | —

UNDERSTANDING

1 Circle the largest fraction in each of the following lists.

a $\frac{3}{7}, \frac{2}{7}, \frac{5}{7}, \frac{1}{7}$

b $\frac{4}{3}, \frac{2}{3}, \frac{7}{3}, \frac{5}{3}$

c $\frac{5}{11}, \frac{9}{11}, \frac{3}{11}, \frac{4}{11}$

d $\frac{8}{5}, \frac{4}{5}, \frac{6}{5}, \frac{7}{5}$

2 State the lowest common multiple of the following sets of numbers.

a 2, 5 **b** 3, 7 **c** 5, 4 **d** 6, 5

e 3, 6 **f** 2, 10 **g** 4, 6 **h** 8, 6

i 2, 3, 5 **j** 3, 4, 6 **k** 3, 8, 4 **l** 2, 6, 5

3 State the lowest common denominator of the following sets of fractions.

a $\frac{1}{3}, \frac{3}{5}$ **b** $\frac{2}{4}, \frac{3}{5}$ **c** $\frac{4}{7}, \frac{2}{3}$ **d** $\frac{2}{10}, \frac{1}{5}$

e $\frac{4}{6}, \frac{3}{8}$ **f** $\frac{5}{12}, \frac{2}{5}$ **g** $\frac{1}{2}, \frac{2}{3}, \frac{3}{4}$ **h** $\frac{4}{3}, \frac{3}{4}$

4 Fill in the gaps to produce equivalent fractions.

a $\frac{2}{5} = \frac{\square}{15}$ **b** $\frac{2}{3} = \frac{\square}{12}$ **c** $\frac{1}{4} = \frac{\square}{16}$

d $\frac{3}{7} = \frac{\square}{14}$ **e** $\frac{3}{8} = \frac{\square}{40}$ **f** $\frac{5}{6} = \frac{\square}{18}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4D

5–7(½) | 5–7(½) | 5–7(½)

FLUENCY

Example 10

5 Place the correct mathematical symbol <, = or >, in between the following pairs of fractions to make true mathematical statements.

a $\frac{3}{5} \square \frac{1}{5}$ **b** $\frac{7}{9} \square \frac{2}{9}$ **c** $\frac{2}{2} \square \frac{3}{3}$ **d** $\frac{13}{18} \square \frac{17}{18}$

e $\frac{1}{4} \square \frac{1}{3}$ **f** $\frac{1}{10} \square \frac{1}{20}$ **g** $\frac{1}{7} \square \frac{1}{5}$ **h** $\frac{3}{5} \square \frac{18}{30}$

i $\frac{2}{3} \square \frac{1}{3}$ **j** $\frac{4}{5} \square \frac{3}{4}$ **k** $\frac{5}{6} \square \frac{9}{10}$ **l** $\frac{5}{7} \square \frac{15}{21}$

m $\frac{7}{11} \square \frac{3}{5}$ **n** $1\frac{2}{3} \square 1\frac{1}{2}$ **o** $3\frac{3}{7} \square \frac{15}{4}$ **p** $\frac{12}{5} \square \frac{19}{8}$

Example 11

6 Place the following fractions in ascending order.

a $\frac{3}{5}, \frac{8}{5}, 1\frac{2}{5}$ **b** $\frac{5}{9}, \frac{1}{3}, \frac{2}{9}$

c $\frac{2}{5}, \frac{3}{4}, \frac{4}{5}$ **d** $\frac{5}{6}, \frac{3}{5}, \frac{2}{3}$

e $2\frac{1}{4}, \frac{11}{4}, \frac{5}{2}, 3\frac{1}{3}$ **f** $\frac{15}{8}, \frac{11}{6}, \frac{7}{4}, \frac{5}{3}$

g $2\frac{7}{10}, \frac{9}{4}, \frac{11}{5}, 2\frac{1}{2}, 2\frac{3}{5}$ **h** $4\frac{4}{9}, \frac{15}{3}, 4\frac{10}{27}, 4\frac{2}{3}, 4\frac{1}{6}$

7 Place the following fractions in descending order, without finding common denominators.

a $\frac{1}{3}, \frac{1}{5}, \frac{1}{4}, \frac{1}{2}$ **b** $\frac{3}{5}, \frac{3}{7}, \frac{3}{6}, \frac{3}{8}$

c $\frac{7}{2}, \frac{7}{5}, \frac{7}{8}, \frac{7}{7}$ **d** $\frac{1}{15}, \frac{1}{10}, \frac{1}{50}, \frac{1}{100}$

e $7\frac{1}{11}, 8\frac{3}{5}, 5\frac{4}{9}, 10\frac{2}{3}$ **f** $2\frac{1}{3}, 2\frac{1}{9}, 2\frac{1}{6}, 2\frac{1}{5}$

8 | 8, 9 | 9, 10

PROBLEM-SOLVING

8 Place the following cake fractions in decreasing order of size.

A sponge cake shared equally by four people = $\frac{1}{4}$ cake

B chocolate cake shared equally by eleven people = $\frac{1}{11}$ cake

C carrot and walnut cake shared equally by eight people = $\frac{1}{8}$ cake

9 Four friends, Dean, David, Andrea and Rob, all competed in the Great Ocean Road marathon. Their respective finishing times were $3\frac{1}{3}$ hours, $3\frac{5}{12}$ hours, $3\frac{1}{4}$ hours and $3\frac{4}{15}$ hours. Write down the correct finishing order of the four friends.

10 Rewrite the fractions in each set with their lowest common denominator and then write the next two fractions that would continue the pattern.

a $\frac{2}{9}, \frac{1}{3}, \frac{4}{9}, _, _$ **b** $\frac{1}{2}, \frac{5}{4}, 2, _, _$

c $\frac{11}{6}, \frac{3}{2}, \frac{7}{6}, _, _$ **d** $\frac{1}{2}, \frac{4}{7}, \frac{9}{14}, _, _$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4D

11 | 11, 12 | 12, 13

REASONING

11 Write a fraction that lies between the following pairs of fractions.

a $\frac{3}{5}, \frac{3}{4}$ **b** $\frac{1}{4}, \frac{1}{2}$ **c** $\frac{2}{7}, \frac{1}{6}$

d $\frac{17}{20}, \frac{7}{10}$ **e** $2\frac{1}{3}, 2\frac{1}{5}$ **f** $8\frac{7}{10}, 8\frac{3}{4}$

12 Write the whole number values that ? can take so that $\frac{?}{3}$ lies between:

a 2 and 3 **b** 5 and $5\frac{1}{2}$

13 Thomas and Nathan had a doughnut eating race to see who could eat the most doughnuts in 1 minute. Before the race started Thomas cut each of his doughnuts into fifths to make them just the right bite-size. Nathan decided to cut each of his doughnuts into quarters before the race. After 1 minute of frenzied eating, the stop whistle blew. Thomas had devoured 28 fifths of doughnut and Nathan had munched his way through 22 quarters of doughnut.

a Who won the doughnut eating race?

b What was the winning doughnut margin? Express your answer in simplest form.



Shady designs

— | — | 14


ENRICHMENT

14 a For each of the diagrams shown, work out what fraction of the rectangle is coloured purple. Explain how you arrived at each of your answers.


b Redraw the shapes in order from the largest amount of purple to the smallest.

c Design and shade two more rectangle designs.


i




ii



iii



iv



Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4E Adding fractions


Interactive

Widgets

HOTsheets


Walkthroughs

Fractions with the same denominator can be easily added together.



$\frac{3}{8} + \frac{2}{8} = \frac{5}{8}$

Fractions with different denominators cannot be added together so easily.




$\frac{1}{3} + \frac{1}{4} = ?$

Note:

$\frac{1}{3} + \frac{1}{4} \neq \frac{1}{7}$

$\frac{1}{3} + \frac{1}{4} \neq \frac{2}{7}$

But with a common denominator it is possible.



$\frac{1}{3} + \frac{1}{4} = ?$

$\frac{4}{12} + \frac{3}{12} = \frac{7}{12}$

Let's start: 'Like' addition

Pair up with a classmate and discuss the following.

1 Which of the following pairs of numbers can be simply added together without having to carry out any form of conversion?

a 6 goals, 2 goals	**b** 11 goals, 5 behinds	**c** 56 runs, 3 wickets
d 6 hours, 5 minutes	**e** 21 seconds, 15 seconds	**f** 47 minutes, 13 seconds
g 15 cm, 3 m	**h** 2.2 km, 4.1 km	**i** 5 kg, 1680 g
j $\frac{2}{7}, \frac{3}{7}$	**k** $\frac{1}{4}, \frac{1}{2}$	**l** $2\frac{5}{12}, 1\frac{1}{3}$

Does it become clear that we can only add pairs of numbers that have the *same* unit? In terms of fractions, we need to have the same _____?

2 By choosing your preferred unit (when necessary), work out the answer to each of the problems above.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Fractions can be simplified using addition *only* if they are 'like' fractions; that is, they must have the **same denominator**. This means they have been divided up into the same number of pieces.

Same denominators

- If two or more fractions have the same denominator, to add them together simply add the numerators and keep the denominator. This allows you to find the total number of divided pieces.

Different denominators

- If the denominators are different, we must use our knowledge of equivalent fractions to convert them to fractions with the same **lowest common denominator (LCD)**.
- To do this, carry out these steps.
  1. Find the LCD (often, but not always, found by multiplying denominators).
  2. Convert fractions to their equivalent fractions with the LCD.
  3. Add the numerators and write this total above the LCD.
- After adding fractions, always look to see if your answer needs to be simplified.

Example 12 Adding 'like' fractions

Add the following fractions together.

a $\frac{1}{5}+\frac{3}{5}$ b $\frac{3}{11}+\frac{5}{11}+\frac{6}{11}$

SOLUTION	EXPLANATION
a $\frac{1}{5}+\frac{3}{5}=\frac{4}{5}$	The denominators are the same; i.e. 'like', therefore simply add the numerators.
b $\frac{3}{11}+\frac{5}{11}+\frac{6}{11}=\frac{14}{11}$	Denominators are the same, so add numerators.
$=1\frac{3}{11}$	Simplify answer by converting to a mixed number.

Example 13 Adding 'unlike' fractions

Add the following fractions together.

a $\frac{1}{5}+\frac{1}{2}$ b $\frac{3}{4}+\frac{5}{6}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $\frac{1}{5}+\frac{1}{2}=\frac{2}{10}+\frac{5}{10}$	LCD is 10. Write equivalent fractions with the LCD.
$=\frac{7}{10}$	Denominators are the same, so add numerators.
b $\frac{3}{4}+\frac{5}{6}=\frac{9}{12}+\frac{10}{12}$	LCD is 12. Write equivalent fractions with the LCD.
$=\frac{19}{12}$	Denominators are the same, so add numerators.
$=1\frac{7}{12}$	Simplify answer to a mixed number.

Example 14 Adding mixed numbers

Simplify:

a $3\frac{2}{3}+4\frac{2}{3}$ **b** $2\frac{5}{6}+3\frac{3}{4}$

SOLUTION	EXPLANATION
a **Method 1**	
$3+4+\frac{2}{3}+\frac{2}{3}=7+\frac{4}{3}$	Add the whole number parts together. Add the fraction parts together.
$=8\frac{1}{3}$	Noting that $\frac{4}{3}=1\frac{1}{3}$, simplify the answer.
Method 2	
$\frac{11}{3}+\frac{14}{3}=\frac{25}{3}$	Convert mixed numbers to improper fractions. Have the same denominators, so add numerators.
$=8\frac{1}{3}$	Convert improper fraction back to a mixed number.
b **Method 1**	
$2+3+\frac{5}{6}+\frac{3}{4}$	Add the whole number parts together. LCD of 6 and 4 is 12. Write equivalent fractions with LCD.
$=5+\frac{10}{12}+\frac{9}{12}$	
$=5+\frac{19}{12}$	Add the fraction parts together.
$=6\frac{7}{12}$	Noting that $\frac{19}{12}=1\frac{7}{12}$, simplify the answer.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Method 2

$\frac{17}{6} + \frac{15}{4} = \frac{34}{12} + \frac{45}{12}$

$= \frac{79}{12}$

$= 6\frac{7}{12}$

Convert mixed numbers to improper fractions.
Write equivalent fractions with LCD.
Add the numerators together.

Simplify answer back to a mixed number.

Exercise 4E

1–4 | 4 | —

UNDERSTANDING

1 Copy the following sentences into your workbook and fill in the gaps.

a To add two fractions together, they must have the same _____.

b When adding fractions together, if they have the same _____, you simply add the _____.

c When adding two or more fractions where the _____ are different, you must find the _____ _____ _____.

d After carrying out the addition of fractions, you should always _____ your answer to see if it can be _____.

2 Copy the following sums into your workbook and fill in the empty boxes.

a $\frac{3}{8} + \frac{2}{8} = \frac{\square}{8}$

b $\frac{4}{7} + \frac{1}{7} = \frac{\square}{7}$

c $\frac{1}{3} + \frac{1}{4}$

$= \frac{\square}{12} + \frac{\square}{12}$

$= \frac{\square}{12}$

d $\frac{2}{5} + \frac{3}{4}$

$= \frac{\square}{20} + \frac{\square}{20}$

$= \frac{\square}{20} = 1\frac{\square}{20}$

3 State the LCD for the following pairs of 'incomplete' fractions.

a $\frac{}{5} + \frac{}{3}$ **b** $\frac{}{4} + \frac{}{5}$ **c** $\frac{}{2} + \frac{}{3}$ **d** $\frac{}{6} + \frac{}{3}$

e $\frac{}{2} + \frac{}{8}$ **f** $\frac{}{5} + \frac{}{10}$ **g** $\frac{}{7} + \frac{}{11}$ **h** $\frac{}{3} + \frac{}{9}$

i $\frac{}{12} + \frac{}{8}$ **j** $\frac{}{2} + \frac{}{18}$ **k** $\frac{}{15} + \frac{}{10}$ **l** $\frac{}{12} + \frac{}{16}$

4 The following sums have been completed, but only six of them are correct. Copy them into your workbook, then place a tick beside the six correct answers and a cross beside the six incorrect answers.

a $\frac{1}{6} + \frac{3}{6} = \frac{4}{6}$ **b** $\frac{1}{3} + \frac{1}{4} = \frac{2}{7}$ **c** $\frac{2}{5} + \frac{4}{5} = \frac{6}{10}$ **d** $\frac{1}{11} + \frac{3}{11} = \frac{4}{11}$

e $\frac{3}{5} + \frac{4}{5} = 1\frac{2}{5}$ **f** $\frac{2}{7} + \frac{2}{7} = \frac{2}{7}$ **g** $\frac{7}{12} + \frac{4}{12} = \frac{11}{12}$ **h** $\frac{4}{9} + \frac{4}{5} = \frac{4}{14}$

i $\frac{3}{10} + \frac{4}{10} = \frac{7}{10}$ **j** $\frac{1}{2} + \frac{2}{5} = \frac{3}{7}$ **k** $2\frac{2}{7} + 3\frac{1}{7} = 5\frac{3}{7}$ **l** $1\frac{2}{3} + 2\frac{1}{5} = 3\frac{3}{8}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4E

5–8(½) | 5–8(½) | 6(½), 8(½)

FLUENCY

Example 12a **5** Add the following fractions.

a $\frac{1}{8}+\frac{4}{8}$ b $\frac{2}{7}+\frac{3}{7}$ c $\frac{1}{5}+\frac{3}{5}$ d $\frac{3}{11}+\frac{6}{11}$

e $\frac{5}{8}+\frac{2}{8}$ f $\frac{1}{12}+\frac{6}{12}$ g $\frac{3}{15}+\frac{4}{15}$ h $\frac{3}{9}+\frac{2}{9}$

Example 12b i $\frac{6}{7}+\frac{3}{7}$ j $\frac{7}{10}+\frac{6}{10}$ k $\frac{2}{5}+\frac{3}{5}+\frac{4}{5}$ l $\frac{12}{19}+\frac{3}{19}+\frac{8}{19}$

Example 13a **6** Add the following fractions.

a $\frac{1}{2}+\frac{1}{4}$ b $\frac{1}{3}+\frac{3}{5}$ c $\frac{1}{2}+\frac{1}{6}$ d $\frac{1}{4}+\frac{1}{3}$

e $\frac{2}{5}+\frac{1}{4}$ f $\frac{1}{5}+\frac{3}{4}$ g $\frac{2}{7}+\frac{1}{3}$ h $\frac{3}{8}+\frac{1}{5}$

Example 13b i $\frac{3}{5}+\frac{5}{6}$ j $\frac{4}{7}+\frac{3}{4}$ k $\frac{8}{11}+\frac{2}{3}$ l $\frac{2}{3}+\frac{3}{4}$

Example 14a **7** Simplify:

a $1\frac{1}{5}+2\frac{3}{5}$ b $3\frac{2}{7}+4\frac{1}{7}$ c $11\frac{1}{4}+1\frac{2}{4}$ d $1\frac{3}{9}+4\frac{2}{9}$

e $5\frac{2}{3}+4\frac{2}{3}$ f $8\frac{3}{6}+12\frac{4}{6}$ g $9\frac{7}{11}+9\frac{7}{11}$ h $4\frac{3}{5}+7\frac{4}{5}$

Example 14b **8** Simplify:

a $2\frac{2}{3}+1\frac{3}{4}$ b $5\frac{2}{5}+1\frac{5}{6}$ c $3\frac{1}{2}+8\frac{2}{3}$ d $5\frac{4}{7}+7\frac{3}{4}$

e $8\frac{1}{2}+6\frac{3}{5}$ f $12\frac{2}{3}+6\frac{4}{9}$ g $17\frac{8}{11}+7\frac{3}{4}$ h $9\frac{7}{12}+5\frac{5}{8}$

9, 10 | 10, 11 | 11, 12

PROBLEM-SOLVING

9 Myles, Liza and Camillus work at a busy cinema complex. For a particular movie, Myles sells $\frac{3}{5}$ of all the tickets and Liza sells $\frac{1}{3}$.

a What fraction of movie tickets are sold by Myles and Liza, together?

b If all of the movie's tickets are sold, what is the fraction sold by Camillus?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

4E

PROBLEM-SOLVING

10 Martine loves to run and play. Yesterday, she ran for $2\frac{1}{4}$ kilometres, walked for $5\frac{2}{5}$ kilometres and skipped for $\frac{1}{2}$ a kilometre. What was the total distance that Martine ran, walked and skipped?

11 Jackson is working on a 1000-piece jigsaw puzzle. After 1 week, he has completed $\frac{1}{10}$ of the puzzle. After 2 weeks he has completed another $\frac{2}{5}$ of the puzzle. In the third week, Jackson completed another $\frac{1}{4}$ of the puzzle.

- **a** By the end of the third week, what fraction of the puzzle has Jackson completed?
- **b** How many pieces of the puzzle does Jackson place in the second week?
- **c** What fraction of the puzzle is still unfinished by the end of the third week? How many pieces is this?



12 A survey of Year 7 students' favourite sport is carried out. A total of 180 students participate in the survey. One-fifth of students reply that netball is their favourite, one-quarter reply rugby and one-third reply soccer. The remainder of students leave the question unanswered.

- **a** What fraction of the Year 7 students answered the survey question?
- **b** What fraction of the Year 7 students left the question unanswered?
- **c** How many students did not answer the survey question?

13 | 13, 14 | 13, 14

REASONING

13 Fill in the empty boxes to make the following fraction sums correct.

- **a** $\frac{1}{\square} + \frac{1}{\square} = \frac{7}{10}$
- **b** $\frac{1}{\square} + \frac{1}{\square} + \frac{1}{\square} = \frac{7}{8}$
- **c** $\frac{3}{\square} + \frac{\square}{4} = \frac{17}{20}$
- **d** $\frac{2}{\square} + \frac{\square}{3} + \frac{4}{\square} = 1$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4E

REASONING

14 Four students each read the same English novel over two nights, for homework. The table shows what fraction of the book was read on each of the two nights.

Student	First night	Second night
Mikhail	$\frac{2}{5}$	$\frac{1}{4}$
Jim	$\frac{1}{2}$	$\frac{1}{10}$
Vesna*	$\frac{1}{4}$	$\frac{1}{5}$
Juliet	$\frac{7}{12}$	$\frac{1}{20}$



*Vesna woke up early on the third morning and read another $\frac{1}{6}$ of the novel before leaving for school.

Place the students in order, from least to most, according to what fraction of the book they had read by their next English lesson.

ENRICHMENT

Raise it to the max — — 15

15 a Using the numbers 1, 2, 3, 4, 5 and 6 only once, arrange them in the boxes below to, first, produce the maximum possible answer, and then the minimum possible answer. Work out the maximum and minimum possible answers.

$$\frac{\square}{\square} + \frac{\square}{\square} + \frac{\square}{\square}$$

b Repeat the process for four fractions using the digits 1 to 8 only once each. Again, state the maximum and minimum possible answers.

c Investigate maximum and minimum fraction statements for other sets of numbers and explain your findings.

d Explain how you would arrange the numbers 1 to 100 for 50 different fractions if you were trying to achieve the maximum or minimum sum.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4F Subtracting fractions

Interactive

Widgets


HOTsheets

Walkthroughs

Subtracting fractions is very similar to adding fractions. You must establish the **lowest common denominator** (**LCD**) if one does not exist and this is done through producing equivalent fractions. Then, instead of adding numerators at the final step, you simply carry out the correct subtraction.

Complications can arise when subtracting mixed numbers and **Example 16** shows the available methods that can be used to overcome such problems.

Let's start: Alphabet subtraction



- Copy into your workbook the number line above.
- Place the following letters in the correct position on the number line.

$A = \frac{2}{3}$ $B = \frac{5}{12}$ $C = \frac{1}{2}$ $D = \frac{11}{12}$ $E = \frac{1}{12}$ $F = \frac{1}{4}$ $G = \frac{0}{12}$

$H = \frac{1}{3}$ $I = \frac{7}{12}$ $J = \frac{5}{6}$ $K = \frac{12}{12}$ $L = \frac{3}{4}$ $M = \frac{1}{6}$

- Complete the following alphabet subtractions, giving your answer as a fraction and also the corresponding alphabet letter.

a J – F **b** A – G **c** D – F – M **d** C – B

e K – C **f** L – H – E **g** K – J – E **h** L – I – M

- What does A + B + C + D + E + F + G + H + I – J – K – L – M equal?

Key ideas

- Fractions can be simplified using subtraction *only* if they are 'like' fractions.
- The process for subtracting fractions is the same as adding fractions, until the final step. At the final step you follow the operation and subtract the second numerator from the first numerator.
- When subtracting mixed numbers, you must have a fraction part that is large enough to allow the other proper fraction to be subtracted from it. If this is not the case at the start of the problem, you may choose to borrow a whole.
  For example:

  $7\frac{1}{2} - 2\frac{3}{4}$ $\frac{1}{2}$ is not big enough to have $\frac{3}{4}$ subtracted from it.

  $6\frac{3}{2} - 2\frac{3}{4}$ Therefore, we choose to borrow a whole from the 7.
- A fail-safe method for subtracting mixed numbers is to convert to improper fractions right from the start.
  For example: $7\frac{1}{2} - 2\frac{3}{4} = \frac{15}{2} - \frac{11}{4}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 15 Subtracting 'like' and 'unlike' fractions

Simplify:

a $\frac{7}{9}-\frac{2}{9}$ **b** $\frac{5}{6}-\frac{1}{4}$

SOLUTION	EXPLANATION
a $\frac{7}{9}-\frac{2}{9}=\frac{5}{9}$	Denominators are the same, therefore we are ready to subtract the second numerator from the first.
b $\frac{5}{6}-\frac{1}{4}=\frac{10}{12}-\frac{3}{12}$	Need to find the LCD, which is 12. Write equivalent fractions with the LCD.
$=\frac{7}{12}$	We have the same denominators now, so subtract second numerator from the first.

Example 16 Subtracting mixed numbers

Simplify:

a $5\frac{2}{3}-3\frac{1}{4}$ **b** $8\frac{1}{5}-4\frac{3}{4}$

SOLUTION	EXPLANATION
Method 1: Converting to an improper fraction	
a $5\frac{2}{3}-3\frac{1}{4}=\frac{17}{3}-\frac{13}{4}$	Convert mixed numbers to improper fractions. Need to find the LCD, which is 12. Write equivalent fractions with the LCD.
$=\frac{68}{12}-\frac{39}{12}$	
$=\frac{29}{12}$	We have the same denominators now, so subtract second numerator from the first and convert back to improper fraction.
$=2\frac{5}{12}$	
b $8\frac{1}{5}-4\frac{3}{4}=\frac{41}{5}-\frac{19}{4}$	Convert mixed numbers to improper fractions. Need to find the LCD, which is 20. Write equivalent fractions with the LCD.
$=\frac{164}{20}-\frac{95}{20}$	
$=\frac{69}{20}$	We have the same denominators now, so subtract second numerator from the first and convert back to improper fraction.
$=3\frac{9}{20}$	

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Method 2: Borrowing a whole number

a $5\frac{2}{3} - 3\frac{1}{4} = \left(5 + \frac{2}{3}\right) - \left(3 + \frac{1}{4}\right)$

$= (5 - 3) + \left(\frac{2}{3} - \frac{1}{4}\right)$

$= 2 + \left(\frac{8}{12} - \frac{3}{12}\right)$

$= 2\frac{5}{12}$

Understand that a mixed number is the addition of a whole number and a proper fraction.
Group whole numbers and group proper fractions.

Simplify whole numbers; simplify proper fractions.

Borrowing a whole was not required.

b $8\frac{1}{5} - 4\frac{3}{4} = \left(8 + \frac{1}{5}\right) - \left(4 + \frac{3}{4}\right)$

$= \left(7 + \frac{6}{5}\right) - \left(4 + \frac{3}{4}\right)$

$= (7 - 4) + \left(\frac{6}{5} - \frac{3}{4}\right)$

$= 3 + \left(\frac{24}{20} - \frac{15}{20}\right)$

$= 3\frac{9}{20}$

$\frac{3}{4}$ cannot be taken away from $\frac{1}{5}$ easily.

Therefore, we must borrow a whole.

Group whole numbers and group proper fractions.
Simplify whole numbers; simplify proper fractions.
Borrowing a whole was required.

Exercise 4F

1–4 | 4 | —

UNDERSTANDING

1 Copy the following sentences into your workbook and fill in the blanks.

a To subtract one fraction from another, you must have a common _____.

b One fail-safe method of producing a common denominator is to simply _____ the two denominators.

c The problem with finding a common denominator that is not the lowest common denominator is that you have to deal with larger numbers and you also need to _____ your answer at the final step.

d To find the LCD you can _____ the denominators and then divide by the HCF of the denominators.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

4F

UNDERSTANDING

2 State the LCD for the following pairs of 'incomplete' fractions.

a $\frac{}{4}-\frac{}{6}$ **b** $\frac{}{2}-\frac{}{10}$ **c** $\frac{}{15}-\frac{}{5}$ **d** $\frac{}{6}-\frac{}{9}$

e $\frac{}{8}-\frac{}{12}$ **f** $\frac{}{12}-\frac{}{20}$ **g** $\frac{}{14}-\frac{}{8}$ **h** $\frac{}{9}-\frac{}{21}$

3 Copy these equations into your workbook, and fill in the empty boxes.

a $\frac{3}{7}-\frac{2}{7}=\frac{\square}{7}$ **b** $\frac{8}{13}-\frac{5}{13}=\frac{\square}{13}$

c $\frac{1}{3}-\frac{1}{4}=\frac{\square}{12}-\frac{\square}{12}$
$=\frac{\square}{12}$

d $\frac{4}{5}-\frac{2}{3}=\frac{\square}{15}-\frac{\square}{15}$
$=\frac{\square}{15}$

4 The following equations have been completed, but only six of them are correct. Copy them into your workbook, then place a tick beside the six correct answers and a cross beside the six incorrect answers.

a $\frac{8}{10}-\frac{5}{10}=\frac{3}{10}$ **b** $\frac{3}{5}-\frac{2}{3}=\frac{1}{2}$ **c** $\frac{5}{12}-\frac{5}{10}=\frac{5}{2}$ **d** $\frac{3}{4}-\frac{1}{4}=\frac{2}{4}$

e $\frac{8}{11}-\frac{8}{10}=\frac{0}{1}=0$ **f** $\frac{12}{15}-\frac{3}{15}=\frac{9}{15}$ **g** $\frac{2}{3}-\frac{2}{3}=0$ **h** $\frac{5}{7}-\frac{2}{7}=\frac{2}{7}$

i $\frac{3}{20}-\frac{2}{20}=\frac{1}{20}$ **j** $2\frac{5}{9}-1\frac{4}{9}=1\frac{1}{9}$ **k** $2\frac{8}{14}-\frac{5}{14}=2\frac{3}{0}$ **l** $\frac{12}{21}-\frac{7}{11}=\frac{5}{10}=\frac{1}{2}$

5–8(½) 5–8(½) 6–8(½)

FLUENCY

Example 15a

5 Simplify:

a $\frac{5}{7}-\frac{3}{7}$ **b** $\frac{4}{11}-\frac{1}{11}$ **c** $\frac{12}{18}-\frac{5}{18}$ **d** $\frac{2}{3}-\frac{1}{3}$

e $\frac{3}{5}-\frac{3}{5}$ **f** $\frac{6}{9}-\frac{2}{9}$ **g** $\frac{5}{19}-\frac{2}{19}$ **h** $\frac{17}{23}-\frac{9}{23}$

i $\frac{84}{100}-\frac{53}{100}$ **j** $\frac{41}{50}-\frac{17}{50}$ **k** $\frac{23}{25}-\frac{7}{25}$ **l** $\frac{7}{10}-\frac{3}{10}$

Example 15b

6 Simplify:

a $\frac{2}{3}-\frac{1}{4}$ **b** $\frac{3}{5}-\frac{1}{2}$ **c** $\frac{3}{5}-\frac{3}{6}$ **d** $\frac{4}{7}-\frac{1}{4}$

e $\frac{1}{2}-\frac{1}{3}$ **f** $\frac{3}{4}-\frac{1}{9}$ **g** $\frac{8}{11}-\frac{1}{3}$ **h** $\frac{4}{5}-\frac{2}{3}$

i $\frac{3}{4}-\frac{5}{8}$ **j** $\frac{11}{20}-\frac{2}{5}$ **k** $\frac{5}{12}-\frac{7}{18}$ **l** $\frac{7}{9}-\frac{2}{3}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4F

FLUENCY

Example 16a

7 Simplify:

a $3\frac{4}{5} - 2\frac{1}{5}$ **b** $23\frac{5}{7} - 15\frac{2}{7}$ **c** $8\frac{11}{14} - 7\frac{9}{14}$ **d** $3\frac{5}{9} - \frac{3}{9}$

e $6\frac{2}{3} - 4\frac{1}{4}$ **f** $5\frac{3}{7} - 2\frac{1}{4}$ **g** $9\frac{5}{6} - 5\frac{4}{9}$ **h** $14\frac{3}{4} - 7\frac{7}{10}$

Example 16b

8 Simplify:

a $5\frac{1}{3} - 2\frac{2}{3}$ **b** $8\frac{2}{5} - 3\frac{4}{5}$ **c** $13\frac{1}{2} - 8\frac{5}{6}$ **d** $12\frac{2}{9} - 7\frac{1}{3}$

e $8\frac{5}{12} - 3\frac{3}{4}$ **f** $1\frac{3}{5} - \frac{7}{9}$ **g** $11\frac{1}{11} - 1\frac{1}{4}$ **h** $6\frac{3}{20} - 3\frac{2}{3}$

PROBLEM-SOLVING

9, 10 | 10–12 | 11–13

9 Tiffany poured herself a large glass of cordial. She noticed that the cordial jug has $\frac{3}{4}$ of a litre in it before she poured her glass and only $\frac{1}{5}$ of a litre in it after she filled her glass. How much cordial did Tiffany pour into her glass?

10 A family block of chocolate is made up of 60 small squares of chocolate. Marcia eats 10 blocks, Jon eats 9 blocks and Holly eats 5 blocks. What fraction of the block of chocolate is left?

11 Three friends split a restaurant bill. One pays $\frac{1}{2}$ of the bill and one pays $\frac{1}{3}$ of the bill. What fraction of the bill must the third friend pay?

12 Patty has $23\frac{1}{4}$ dollars, but owes her parents $15\frac{1}{2}$ dollars. How much money does Patty have left after she pays back her parents? Repeat this question using decimals and dollars and cents. Do you get the same answer?

13 Three cakes were served at a birthday party: an ice-cream cake, a chocolate cake and a sponge cake. $\frac{3}{4}$ of the ice-cream cake was eaten. The chocolate cake was cut into 12 equal pieces, of which 9 were eaten. The sponge cake was divided into 8 equal pieces, with only 1 piece remaining.



a What fraction of each cake was eaten?
b What fraction of each cake was left over?
c What was the total amount of cake eaten during the party?
d What was the total amount of cake left over after the party?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4F

14 | 14, 15 | 15, 16

REASONING

14 Fill in the empty boxes to make the following fraction sums correct.

a $\frac{1}{\square} - \frac{1}{\square} = \frac{1}{12}$

b $\frac{\square}{5} - \frac{\square}{2} = \frac{1}{10}$

c $2\frac{\square}{3} - 1\frac{\square}{3} = \frac{2}{3}$

d $8\frac{1}{\square} - 6\frac{\square}{4} = 1\frac{1}{2}$

15 Today David's age is one-seventh of Felicity's age. Felicity is a teenager.

a In 1 year's time David will be one-fifth of Felicity's age. What fraction of her age will he be in 2 years' time?

b How many years must pass until David is one-third of Felicity's age?

c How many years must pass until David is half Felicity's age?



16 Simplify:

a **Example 16** shows two possible methods for subtracting mixed numbers: 'Borrowing a whole number' and 'Converting to an improper fraction'. Simplify the following two expressions and discuss which method is the most appropriate for each question.

i $2\frac{1}{5} - 1\frac{2}{3}$ **ii** $27\frac{5}{11} - 23\frac{4}{5}$

b If you have an appropriate calculator, work out how to enter fractions and check your answers to parts **i** and **ii** above.

Letter to an absent friend

— | — | 17

ENRICHMENT

17 Imagine that a friend in your class is absent for this lesson on the subtraction of fractions. They were present yesterday and understood the process involved when adding fractions. Your task is to write a letter to your friend, explaining how to subtract mixed numbers. Include some examples, discuss both possible methods but also justify your favourite method. Finish off with three questions for your friend to attempt and include the answers to these questions on the back of the letter.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4G Multiplying fractions









What does it mean to multiply two fractions together?

Do you end up with a smaller amount or a larger amount when you multiply two proper fractions together?

What does $\frac{1}{3} \times \frac{2}{3}$ equal?


- **'Strip' method**

  Imagine you have a strip of paper.

  You are told to shade $\frac{2}{3}$ of the strip.

  You are now told to shade in a darker colour $\frac{1}{3}$ of your $\frac{2}{3}$ strip.

  The final amount shaded is your answer.



- **'Number line' method**

  Consider the number line from 0 to 1 (shown opposite).


  It is divided into ninths.

  Locate $\frac{2}{3}$.

  Divide this position into three equal pieces (shown as ⟷).


  To locate $\frac{1}{3} \times \frac{2}{3}$ you have only one of the three pieces.

  The final location is your answer (shown as ⟷); i.e. $\frac{2}{9}$.



- **'Shading' method**

  Consider $\frac{1}{3}$ of a square multiplied by $\frac{2}{3}$ of a square.



- **'The rule' method**

  When multiplying fractions, multiply the numerators together and mutiply the denominators together.

$$\frac{1}{3} \times \frac{2}{3} = \frac{1 \times 2}{3 \times 3} = \frac{2}{9}$$





Cutting materials to fit a purpose may involve multiplying a fraction by a fraction.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Let's start: 'Clock face' multiplication

Explain and discuss the concept of fractions of an hour on the clock face.
In pairs, students match up the following 10 'clock face' multiplication questions with their correct answer. You may like to place a time limit of 5 minutes on the activity.

Discuss answers at the end of the activity.

Questions		Answers	
1	$\frac{1}{2}$ of 4 hours	**A**	25 minutes
2	$\frac{1}{3}$ of 2 hours	**B**	$1\frac{1}{2}$ hours
3	$\frac{1}{4}$ of 6 hours	**C**	5 minutes
4	$\frac{1}{3}$ of $\frac{1}{4}$ hour	**D**	$\frac{1}{4}$ hour
5	$\frac{1}{4}$ of $\frac{1}{3}$ hour	**E**	2 hours
6	$\frac{1}{3}$ of $\frac{3}{4}$ hour	**F**	2 hours 40 minutes
7	$\frac{1}{10}$ of $\frac{1}{2}$ hour	**G**	$\frac{1}{12}$th hour
8	$\frac{1}{5}$ of $\frac{1}{2}$ hour	**H**	40 minutes
9	$\frac{2}{3}$ of 4 hours	**I**	$\frac{1}{10}$th hour
10	$\frac{5}{6}$ of $\frac{1}{2}$ hour	**J**	3 minutes





Key ideas

- Fractions do *not* need to have the same denominator to be multiplied together.
- To multiply fractions, multiply the numerators together and multiply the denominators together.
  - In symbols: $\frac{a}{b} \times \frac{c}{d} = \frac{a \times c}{b \times d}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- If possible, 'simplify', 'divide' or 'cancel' fractions before multiplying.
  - Cancelling can be done *vertically* or *diagonally*.
  - Cancelling can never be done *horizontally*.

$\frac{3}{5} \times \frac{\cancel{4}^{1}}{\cancel{8}^{2}}$ cancelling vertically ✓

$\frac{\cancel{3}^{1}}{5} \times \frac{4}{\cancel{6}^{2}}$ cancelling diagonally ✓

Never do this! → $\frac{\cancel{3}^{1}}{5} \times \frac{\cancel{6}^{2}}{7}$ cancelling horizontally ✗

- A whole number can be written as a fraction with a denominator of 1.
- 'of', '×', 'times', 'lots of' and 'product' all refer to the same mathematical operation of multiplying.
- Mixed numbers must be changed to improper fractions before multiplying.
- Final answers should be written in simplest form.

Example 17 Finding a simple fraction of a quantity

Find:

a $\frac{2}{3}$ of 15 bananas

b $\frac{3}{10}$ of 50 lollies


SOLUTION

a $\frac{2}{3}$ of 15 bananas

$\left(\frac{1}{3} \text{ of } 15\right) \times 2 = 10$

EXPLANATION

Divide 15 bananas into 3 equal groups.
Therefore, 5 in each group.
Take 2 of the groups.



Answer is 10 bananas.

b $\frac{3}{10}$ of 50 lollies

$\left(\frac{1}{10} \text{ of } 50\right) \times 3 = 15$

Divide 50 into 10 equal groups.
Therefore, 5 in each group.
Take 3 of the groups.
Therefore, answer is 15 lollies.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 18 Multiplying proper fractions

Find:

a $\frac{2}{3} \times \frac{1}{5}$ **b** $\frac{3}{4} \times \frac{8}{9}$ **c** $\frac{4}{8}$ of $\frac{3}{6}$

SOLUTION	EXPLANATION
a $\frac{2}{3} \times \frac{1}{5} = \frac{2 \times 1}{3 \times 5}$	Multiply the numerators together.
$= \frac{2}{15}$	Multiply the denominators together. The answer is in simplest form.
b $\frac{3}{4} \times \frac{8}{9} = \frac{{}^{1}\cancel{3} \times 8^{2}}{{}_{1}\cancel{4} \times 9^{3}}$	Cancel first.
$= \frac{2}{3}$	Then multiply numerators together and denominators together.
c $\frac{4}{8}$ of $\frac{3}{6} = \frac{4}{8} \times \frac{3}{6}$	Change 'of' to multiplication sign.
$= \frac{{}^{1}\cancel{4} \times 3^{1}}{{}_{2}\cancel{8} \times 6^{2}}$	Cancel and then multiply the numerators and the denominators.
$= \frac{1}{4}$	The answer is in simplest form.

Example 19 Multiplying proper fractions by whole numbers

Find:

a $\frac{1}{3} \times 21$ **b** $\frac{2}{5}$ of 32

SOLUTION	EXPLANATION
a $\frac{1}{3} \times 21 = \frac{1}{{}_{1}\cancel{3}} \times \frac{\cancel{21}^{7}}{1}$	Rewrite 21 as a fraction with a denominator equal to 1. Cancel and then multiply numerators and denominators.
$= \frac{7}{1}$	$7 \div 1 = 7$
$= 7$	
b $\frac{2}{5}$ of $32 = \frac{2}{5} \times \frac{32}{1}$	Rewrite 'of' as a multiplication sign. Write 32 as a fraction.
$= \frac{64}{5}$	Multiply numerators and denominators.
$= 12\frac{4}{5}$	Convert answer to a mixed number.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Example 20 Multiplying improper fractions

Find:

a $\frac{5}{3} \times \frac{7}{2}$ **b** $\frac{8}{5} \times \frac{15}{4}$

SOLUTION	EXPLANATION
a $\frac{5}{3} \times \frac{7}{2} = \frac{5 \times 7}{3 \times 2}$	Multiply the numerators together.
$= \frac{35}{6} = 5\frac{5}{6}$	Multiply the denominators together. Convert the answer to a mixed number.
b $\frac{8}{5} \times \frac{15}{4} = \frac{{}^{2}\cancel{8} \times \cancel{15}^{3}}{{}_{1}\cancel{5} \times \cancel{4}^{1}}$	Cancel first.
$= \frac{6}{1} = 6$	Multiply 'cancelled' numerators together and 'cancelled' denominators together. Write the answer in simplest form.

Example 21 Multiplying mixed numbers

Find:

a $2\frac{1}{3} \times 1\frac{2}{5}$ **b** $6\frac{1}{4} \times 2\frac{2}{5}$

SOLUTION	EXPLANATION
a $2\frac{1}{3} \times 1\frac{2}{5} = \frac{7}{3} \times \frac{7}{5}$	Convert mixed numbers to improper fractions.
$= \frac{49}{15}$	Multiply numerators together. Multiply denominators together.
$= 3\frac{4}{15}$	Write the answer in simplest form.
b $6\frac{1}{4} \times 2\frac{2}{5} = \frac{{}^{5}\cancel{25}}{{}_{1}\cancel{4}} \times \frac{\cancel{12}^{3}}{\cancel{5}^{1}}$	Convert to improper fractions. Simplify fractions by cancelling.
$= \frac{15}{1}$	Multiply numerators and denominators together.
$= 15$	Write the answer in simplest form.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4G

1–5 | 5 | —


UNDERSTANDING

1 Copy these sentences into your workbook and fill in the blanks.

- **a** A proper fraction has a value that is between _____ and _____.
- **b** An improper fraction is always greater than _____.
- **c** A mixed number consists of two parts, a _____ _____ part and a _____ _____ part.

2 When multiplying a whole number by a proper fraction, do you get a smaller or larger answer when compared with the whole number? Explain your answer.

3 Copy into your workbook the grid shown opposite.



- **a** On your diagram, shade in blue $\frac{1}{3}$ of the grid.
- **b** Now shade in red $\frac{1}{4}$ of the shaded blue.
- **c** You have now shaded $\frac{1}{4}$ of $\frac{1}{3}$. What fraction is this of the original grid?

Example 17

4 Use drawings to show the answer to these problems.

- **a** $\frac{1}{3}$ of 12 1ollies
- **b** $\frac{1}{5}$ of 10 pencils
- **c** $\frac{2}{3}$ of 18 donuts
- **d** $\frac{3}{4}$ of 16 boxes
- **e** $\frac{3}{8}$ of 32 dots
- **f** $\frac{3}{7}$ of 21 triangles

5 One of the following four methods is the correct solution to the problem $\frac{1}{2} \times \frac{1}{5}$. Find the correct solution and copy it into your workbook.

A
$\frac{1}{2} \times \frac{1}{5}$
$= \frac{1+1}{2+5}$
$= \frac{2}{7}$

B
$\frac{1}{2} \times \frac{1}{5}$
$= \frac{1 \times 1}{2 \times 5}$
$= \frac{2}{10}$

C
$\frac{1}{2} \times \frac{1}{5}$
$= \frac{5}{10} \times \frac{2}{10}$
$= \frac{7}{20}$

D
$\frac{1}{2} \times \frac{1}{5}$
$= \frac{1 \times 1}{2 \times 5}$
$= \frac{1}{10}$

6–9(½) | 6–10(½) | 6–10(½)

FLUENCY

Example 18

6 Evaluate:

- **a** $\frac{3}{4} \times \frac{1}{5}$
- **b** $\frac{2}{7} \times \frac{1}{3}$
- **c** $\frac{2}{3} \times \frac{5}{7}$
- **d** $\frac{4}{9} \times \frac{2}{5}$
- **e** $\frac{2}{3} \times \frac{3}{5}$
- **f** $\frac{4}{7} \times \frac{1}{4}$
- **g** $\frac{3}{4} \times \frac{1}{3}$
- **h** $\frac{5}{9} \times \frac{9}{11}$
- **i** $\frac{3}{6} \times \frac{5}{11}$
- **j** $\frac{2}{3} \times \frac{4}{8}$
- **k** $\frac{8}{11} \times \frac{3}{4}$
- **l** $\frac{2}{5} \times \frac{10}{11}$
- **m** $\frac{2}{7}$ of $\frac{3}{5}$
- **n** $\frac{3}{4}$ of $\frac{2}{5}$
- **o** $\frac{5}{10}$ of $\frac{4}{7}$
- **p** $\frac{6}{9}$ of $\frac{3}{12}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

4G

FLUENCY

Example 19

7 Find:

a $\frac{1}{3}$ of 18 **b** $\frac{1}{5}$ of 45 **c** $\frac{2}{3}$ of 24 **d** $\frac{3}{5}$ of 25

e $\frac{2}{7}$ of 42 **f** $\frac{1}{4}$ of 16 **g** $\frac{4}{5}$ of 100 **h** $\frac{3}{7}$ of 77

Example 20

8 Find:

a $\frac{5}{2} \times \frac{7}{3}$ **b** $\frac{6}{5} \times \frac{11}{7}$ **c** $\frac{6}{4} \times \frac{11}{5}$ **d** $\frac{9}{6} \times \frac{13}{4}$

e $\frac{8}{5} \times \frac{10}{3}$ **f** $\frac{21}{4} \times \frac{8}{6}$ **g** $\frac{10}{7} \times \frac{21}{5}$ **h** $\frac{14}{9} \times \frac{15}{7}$

Example 21

9 Find:

a $1\frac{3}{5} \times 2\frac{1}{3}$ **b** $1\frac{1}{7} \times 1\frac{2}{9}$ **c** $3\frac{1}{4} \times 2\frac{2}{5}$ **d** $4\frac{2}{3} \times 5\frac{1}{7}$

10 Find:

a $\frac{6}{5} \times \frac{8}{3}$ **b** $\frac{1}{2} \times \frac{3}{8}$ **c** $\frac{3}{4}$ of $5\frac{1}{3}$ **d** $7\frac{1}{2} \times 4\frac{2}{5}$

e $\frac{3}{7}$ of $\frac{2}{3}$ **f** $1\frac{1}{2} \times 2\frac{1}{4}$ **g** $\frac{8}{9} \times \frac{6}{20}$ **h** $\frac{15}{4} \times \frac{8}{5}$

PROBLEM-SOLVING


11, 12 | 12, 13 | 12–14

11 At a particular secondary college, $\frac{2}{5}$ of the Year 7 students are boys.

a What fraction of the Year 7 students are girls?

b If there are 120 Year 7 students, how many boys and girls are there?

12 To paint one classroom, $2\frac{1}{3}$ litres of paint are required.
How many litres of paint are required to paint five identical classrooms?



13 A scone recipe requires $1\frac{3}{4}$ cups of self-raising flour and $\frac{3}{4}$ of a cup of cream. James is catering for a large group and needs to quadruple the recipe. How much self-raising flour and how much cream will he need?

14 Julie has finished an injury-plagued netball season during which she was able to play only $\frac{2}{3}$ of the matches. The season consisted of 21 matches. How many games did Julie miss as a result of injury?

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4G

15 | 15, 16 | 16, 17

REASONING

15 Not all of the following fraction equations are correct. Copy them into your workbook, then place a tick beside those that are correct and a cross beside those that are wrong. Provide the correct solution for those you marked as incorrect.

a $\frac{1}{3}+\frac{1}{4}=\frac{1}{7}$ **b** $\frac{1}{3}+\frac{1}{4}=\frac{1}{12}$ **c** $\frac{1}{3}\times\frac{1}{4}=\frac{2}{7}$

d $\frac{1}{3}\times\frac{1}{4}=\frac{1}{12}$ **e** $\frac{1}{3}-\frac{1}{4}=\frac{1}{12}$ **f** $\frac{1}{3}-\frac{1}{4}=\frac{0}{-1}$

16 Circle the correct alternative for the following statement and justify your answer. Using an example, explain why the other alternatives are incorrect.

When multiplying a proper fraction by another proper fraction the answer is:

A a whole number **B** a mixed numeral

C an improper fraction **D** a proper fraction

17 Write two fractions that:

a multiply to $\frac{3}{5}$ **b** multiply to $\frac{3}{4}$ **c** multiply to $\frac{1}{7}$

Who are we? | — | — | 18

ENRICHMENT

18 a Using the clues provided, work out which two fractions are being discussed.

- We are two proper fractions.
- Altogether we consist of four different digits.
- When added together our answer will still be a proper fraction.
- When multiplied together you could carry out some cancelling.
- The result of our product, when simplified, contains no new digits from our original four.
- Three of our digits are prime numbers and the fourth digit is a cube number.

b Design your own similar question and develop a set of appropriate clues. Have a classmate try and solve your question.

c Design the ultimate challenging 'Who are we?' question. Make sure there is only one possible answer.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

4H Dividing fractions









Remember that division used to be referred to as 'how many'.

Thinking of division as 'how many' helps us to understand dividing fractions.

For example, to find $\frac{1}{2} \div \frac{1}{4}$, think of $\frac{1}{2}$ how many $\frac{1}{4}$s, or how many $\frac{1}{4}$s are in a $\frac{1}{2}$?

Consider this strip of paper that is divided into four equal sections.



In our example of $\frac{1}{2} \div \frac{1}{4}$, we have only $\frac{1}{2}$ a strip, so we will shade in half the strip.



By thinking of the $\div$ sign as 'how many', the question is asking how many quarters are in half the strip. From our diagram, we can see that the answer is 2. Therefore, $\frac{1}{2} \div \frac{1}{4} = 2$.

In a game of football, when it is half-time, you have played two quarters. This is another way of confirming that $\frac{1}{2} \div \frac{1}{4} = 2$.

Let's start: 'Divvy up' the lolly bag

To 'divvy up' means to divide up, or divide out, or share equally.

Consider a lolly bag containing 24 lollies.
In pairs, students answer the following questions.

- How many lollies would each person get if you 'divvy up' the lollies between three people?
- If you got $\frac{1}{3}$ of the lollies in the bag, how many did you get?



How many ways can these 24 lollies be divided?

Can you see that 'divvying up' by 3 is the same as getting $\frac{1}{3}$? Therefore, $\div 3$ is the same as $\times \frac{1}{3}$.

- How many lollies would each person get if you 'divvy up' the lollies between eight people?
- If you got $\frac{1}{8}$ of the lollies in the bag, how many did you get?

Can you see that 'divvying up' by 8 is the same as getting $\frac{1}{8}$? Therefore, $\div 8$ is the same as $\times \frac{1}{8}$.

- What do you think is the same as dividing by n?
- What do you think is the same as dividing by $\frac{a}{b}$?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- To find the **reciprocal** of a fraction, you must **invert** the fraction. This is done by swapping the numerator and the denominator. 'Inverting' is sometimes known as turning the fraction upside down, or flipping the fraction.
  - The reciprocal of $\frac{a}{b}$ is $\frac{b}{a}$.

  For example: The reciprocal of $\frac{3}{5}$ is $\frac{5}{3}$.
- Dividing by a number is the same as multiplying by its reciprocal.

  For example: $15 \div 3 = 5$ and $15 \times \frac{1}{3} = 5$.
  - Dividing by 2 is the same as multiplying by $\frac{1}{2}$.
- When asked to divide by a fraction, instead choose to multiply by the fraction's reciprocal.

  Therefore, to divide by $\frac{a}{b}$ we multiply by $\frac{b}{a}$.
- When dividing, mixed numbers must be changed to improper fractions.

Example 22 Finding reciprocals

State the reciprocal of the following.

a $\frac{2}{3}$ **b** 5 **c** $1\frac{3}{7}$

SOLUTION	EXPLANATION
a Reciprocal of $\frac{2}{3}$ is $\frac{3}{2}$.	The numerator and denominator are swapped.
b Reciprocal of 5 is $\frac{1}{5}$.	Think of 5 as $\frac{5}{1}$ and then invert.
c Reciprocal of $1\frac{3}{7}$ is $\frac{7}{10}$.	Convert $1\frac{3}{7}$ to an improper fraction; i.e. $\frac{10}{7}$, and then invert.

Example 23 Dividing a fraction by a whole number

Find:

a $\frac{5}{8} \div 3$ **b** $2\frac{3}{11} \div 5$

SOLUTION	EXPLANATION
a $\frac{5}{8} \div 3 = \frac{5}{8} \times \frac{1}{3}$	Change the $\div$ sign to a $\times$ sign and invert the 3 $\left(\text{or } \frac{3}{1}\right)$.
$= \frac{5}{24}$	Multiply the numerators and denominators.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $2\frac{3}{11} \div 5 = \frac{25}{11} \div \frac{5}{1}$ — Convert the mixed number to an improper fraction. Write 5 as an improper fraction.

$= \frac{{}^{5}\cancel{25}}{11} \times \frac{1}{\cancel{5}^{1}}$ — Change the ÷ sign to a × sign and invert the divisor. Simplify by cancelling.

$= \frac{5}{11}$ — Multiply numerators and denominators.

Example 24 Dividing a whole number by a fraction

Find:

a $6 \div \frac{1}{3}$ **b** $24 \div \frac{3}{4}$

SOLUTION **EXPLANATION**

a $6 \div \frac{1}{3} = \frac{6}{1} \times \frac{3}{1}$ — Instead of ÷ $\frac{1}{3}$, change to × $\frac{3}{1}$.

$= \frac{18}{1} = 18$ — Simplify.

b $24 \div \frac{3}{4} = \frac{{}^{8}\cancel{24}}{1} \times \frac{4}{\cancel{3}^{1}}$ — Instead of ÷ $\frac{3}{4}$, change to × $\frac{4}{3}$.

$= 32$ — Cancel and simplify.

Example 25 Dividing fractions by fractions

Find:

a $\frac{3}{5} \div \frac{3}{8}$ **b** $2\frac{2}{5} \div 1\frac{3}{5}$

SOLUTION **EXPLANATION**

a $\frac{3}{5} \div \frac{3}{8} = \frac{3}{5} \times \frac{8}{3}$ — Change the ÷ sign to a × sign and invert the divisor. (Note: The divisor is the second fraction.)

$= \frac{8}{5} = 1\frac{3}{5}$ — Cancel and simplify.

b $2\frac{2}{5} \div 1\frac{3}{5} = \frac{12}{5} \div \frac{8}{5}$ — Convert mixed numbers to improper fractions.

$= \frac{{}^{3}\cancel{12}}{\cancel{5}^{1}} \times \frac{{}^{1}\cancel{5}}{\cancel{8}^{2}}$ — Change the ÷ sign to a × sign and invert the divisor.

$= \frac{3}{2} = 1\frac{1}{2}$ — Cancel, multiply and simplify.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4H

1–4 | 4 | —

UNDERSTANDING

1 Which of the following is the correct first step for finding $\frac{3}{5} \div \frac{4}{7}$?

A $\frac{3}{5} \times \frac{7}{4}$ **B** $\frac{5}{3} \times \frac{4}{7}$ **C** $\frac{5}{3} \times \frac{7}{4}$

2 Write the correct first step for each of these division questions. (Do not go on and find the final answer.)

a $\frac{5}{11} \div \frac{3}{5}$ **b** $\frac{1}{3} \div \frac{1}{5}$ **c** $\frac{7}{10} \div \frac{12}{5}$ **d** $\frac{8}{3} \div 3$

3 When dividing mixed numbers, the first step is to convert to improper fractions and the second step is to multiply by the reciprocal of the divisor. Write the correct first and second steps for each of the following mixed number division questions. (Do not go on and find the final answer.)

a $2\frac{1}{2} \div 1\frac{1}{3}$ **b** $24 \div 3\frac{1}{5}$ **c** $4\frac{3}{11} \div 5\frac{1}{4}$ **d** $\frac{8}{3} \div 11\frac{3}{7}$

4 Make each sentence correct, by inserting the word *more* or *less* in the gap.

a $10 \div 2$ gives an answer that is _____ than 10.

b $10 \div \frac{1}{2}$ gives an answer that is _____ than 10.

c $\frac{3}{4} \div \frac{2}{3}$ gives an answer that is _____ than $\frac{3}{4}$.

d $\frac{3}{4} \times \frac{3}{2}$ gives an answer that is _____ than $\frac{3}{4}$.

e $\frac{5}{7} \div \frac{8}{5}$ gives an answer that is _____ than $\frac{5}{7}$.

f $\frac{5}{7} \times \frac{5}{8}$ gives an answer that is _____ than $\frac{5}{7}$.

5–8(½) | 5–9(½) | 5–9(½)

FLUENCY

Example 22

5 State the reciprocal of each of the following.

a $\frac{5}{7}$ **b** $\frac{3}{5}$ **c** $\frac{2}{9}$ **d** $\frac{1}{8}$

e $2\frac{1}{3}$ **f** $4\frac{3}{5}$ **g** $1\frac{5}{6}$ **h** $8\frac{2}{3}$

i 12 **j** 101 **k** $\frac{1}{9}$ **l** 1

Example 23

6 Find:

a $\frac{3}{4} \div 2$ **b** $\frac{5}{11} \div 3$ **c** $\frac{8}{5} \div 4$ **d** $\frac{15}{7} \div 3$

e $2\frac{1}{4} \div 3$ **f** $5\frac{1}{3} \div 4$ **g** $12\frac{4}{5} \div 8$ **h** $1\frac{13}{14} \div 9$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4H

FLUENCY

Example 24

7 Find:

a $5 \div \frac{1}{4}$ **b** $7 \div \frac{1}{3}$ **c** $10 \div \frac{1}{10}$ **d** $24 \div \frac{1}{5}$

e $12 \div \frac{2}{5}$ **f** $15 \div \frac{3}{8}$ **g** $14 \div \frac{7}{2}$ **h** $10 \div \frac{3}{2}$

Example 25

8 Find:

a $\frac{2}{7} \div \frac{2}{5}$ **b** $\frac{1}{5} \div \frac{1}{4}$ **c** $\frac{3}{7} \div \frac{6}{11}$ **d** $\frac{2}{3} \div \frac{8}{9}$

e $2\frac{1}{4} \div 1\frac{1}{3}$ **f** $4\frac{1}{5} \div 3\frac{3}{10}$ **g** $12\frac{1}{2} \div 3\frac{3}{4}$ **h** $9\frac{3}{7} \div 12\frac{4}{7}$

9 Find:

a $\frac{3}{8} \div 5$ **b** $22 \div \frac{11}{15}$ **c** $2\frac{2}{5} \div 1\frac{3}{4}$ **d** $\frac{3}{4} \div \frac{9}{4}$

e $7 \div \frac{1}{4}$ **f** $2\frac{6}{15} \div 9$ **g** $7\frac{2}{3} \div 1\frac{1}{6}$ **h** $\frac{3}{5} \div \frac{2}{7}$

PROBLEM-SOLVING

10, 11 | 11–13 | 12–14

10 If $2\frac{1}{4}$ leftover pizzas are to be shared between three friends, what fraction of pizza will each friend receive?

11 A property developer plans to subdivide $7\frac{1}{2}$ acres of land into blocks of at least $\frac{3}{5}$ of an acre. Through some of the land runs a creek, where a protected species of frog lives. How many of the blocks can the developer sell if two blocks must be reserved for the creek and its surroundings?

12 Miriam cuts a 10-millimetre thick sisal rope into four equal pieces. If the rope is $3\frac{3}{5}$ metres long before it is cut, how long is each piece?

13 A carpenter takes $\frac{3}{4}$ of an hour to make a chair. How many chairs can he make in 6 hours?

14 Justin is a keen runner and regularly runs at a pace of $3\frac{1}{2}$ minutes per kilometre. Justin finished a Sunday morning run in 77 minutes. How far did he run?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4H

	15	15, 16	16, 17

REASONING

15 Pair up the equivalent expressions and state the simplified answer.

$\frac{1}{2}$ of 8 | $12 \div 4$ | $10 \times \frac{1}{2}$ | $10 \div 2$

$3 \div \frac{1}{2}$ | $12 \times \frac{1}{4}$ | $\frac{1}{2} \div \frac{1}{8}$ | 3×2

16 Find:

a $\frac{3}{8} \times \frac{4}{5} \div \frac{2}{3}$ **b** $\frac{3}{8} \div \frac{4}{5} \div \frac{2}{3}$ **c** $\frac{3}{8} \div \frac{4}{5} \times \frac{2}{3}$ **d** $\frac{3}{8} \times \frac{4}{5} \times \frac{2}{3}$

17 a A car travels 180 kilometres in $1\frac{1}{2}$ hours. How far will it travel in 2 hours if it travels at the same speed?

b A different car took $2\frac{1}{4}$ hours to travel 180 kilometres. How far did it travel in 2 hours, if it maintained the same speed?



You provide the question	—	—	18

ENRICHMENT

18 Listed below are six different answers.
You are required to make up six questions that will result in the following six answers.
All questions must involve a division sign. Your questions should increase in order of difficulty by adding extra operation signs and extra fractions.

a Answer 1: $\frac{3}{5}$ **b** Answer 2: $2\frac{1}{3}$ **c** Answer 3: $\frac{7}{1}$

d Answer 4: 0 **e** Answer 5: $\frac{1}{100}$ **f** Answer 6: $4\frac{4}{5}$


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

4A **1** Consider the fraction $\frac{3}{4}$.

- **a** Represent this fraction on a diagram.
- **b** State the denominator of this fraction.
- **c** State the numerator of this fraction.
- **d** Represent this fraction on a number line.
- **e** Is this a proper fraction, an improper fraction or a mixed numeral?

4A **2** What fraction is represented on the number line shown?



Write it as an improper fraction and as a mixed number.

4B **3** Write three equivalent fractions for $\frac{2}{5}$.

4B/C **4** Write these fractions in simplest form.

- **a** $\frac{4}{10}$
- **b** $\frac{15}{30}$
- **c** $\frac{14}{6}$
- **d** $\frac{24}{8}$

4C **5** Convert $1\frac{3}{5}$ to an improper fraction.

4C **6** Convert $\frac{13}{4}$ to a mixed number.

4D **7** Place the correct mathematical symbol $<, =$ or $>$ between the following pairs of fractions to make true mathematical statements.

- **a** $\frac{2}{3} \quad \frac{5}{9}$
- **b** $\frac{4}{5} \quad \frac{24}{30}$
- **c** $1\frac{1}{5} \quad \frac{12}{10}$
- **d** $\frac{5}{9} \quad \frac{18}{20}$

4D **8** Write the following fractions in ascending order: $\frac{1}{2}, \frac{2}{3}, \frac{9}{4}, \frac{4}{9}$.

4E **9** Add the following fractions together.

- **a** $\frac{4}{7} + \frac{2}{7}$
- **b** $\frac{2}{5} + \frac{3}{10}$
- **c** $\frac{3}{4} + \frac{2}{5}$
- **d** $1\frac{3}{4} + 3\frac{1}{2}$

4F **10** Simplify:

- **a** $\frac{5}{12} - \frac{1}{3}$
- **b** $\frac{5}{6} - \frac{1}{4}$
- **c** $5\frac{1}{2} - 3\frac{1}{5}$

4G **11** Find:

- **a** $\frac{3}{5}$ of \$560
- **b** $\frac{2}{3} \times \frac{7}{11}$
- **c** $\frac{2}{3} \times \frac{9}{10}$
- **d** $1\frac{1}{3} \times \frac{9}{16}$

4H **12** State the reciprocal of:

- **a** $\frac{4}{5}$
- **b** 6
- **c** $2\frac{1}{2}$
- **d** $\frac{1}{12}$

4H **13** Find:

- **a** $\frac{7}{8} \div 4$
- **b** $8 \div \frac{3}{4}$
- **c** $\frac{3}{5} \div \frac{7}{15}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4I Fractions and percentages

Interactive

Widgets

HOTsheets

Walkthroughs

We come across percentages in many everyday situations. Interest rates, discounts, test results and statistics are just some of the common ways in which we deal with percentages. Percentages are closely related to fractions. A percentage is another way of writing a fraction with a denominator of 100. Therefore, 87% means that if something is divided into 100 pieces you would have 87 of them.



A fraction can be interpreted as a percentage of the total.

Let's start: Student ranking

Five students completed five different Mathematics tests. Each of the tests was out of a different number of marks. The results are shown below. Your task is to rank the five students in descending order, according to their test result.

- Matthew scored 15 out of a possible 20 marks.
- Mengna scored 36 out of a possible 50 marks.
- Maria scored 33 out of a possible 40 marks.
- Marcus scored 7 out of a possible 10 marks.
- Melissa scored 64 out of a possible 80 marks.

Change these test results to equivalent scores out of 100, and therefore state the percentage test score for each student.

Key ideas

- The symbol, **%**, means 'per cent'. This comes from the Latin words *per centum*, which means out of 100. Therefore, 75% means 75 out of 100.
- We can write percentages as fractions by changing the % sign to a denominator of 100 (meaning out of 100).
  For example: $37\% = \frac{37}{100}$
- We can convert fractions to percentages through our knowledge of equivalent fractions.
  For example: $\frac{1}{4} = \frac{25}{100} = 25\%$
- To convert any fraction to a percentage, multiply by 100.
  For example: $\frac{3}{8} \times 100 = \frac{3}{8} \times \frac{100}{1} = \frac{75}{2} = 37\frac{1}{2}$. Therefore $\frac{3}{8} = 37\frac{1}{2}\%$
- Common percentages and their equivalent fractions are shown in the table below. It is useful to know these.

Fraction	$\frac{1}{2}$	$\frac{1}{3}$	$\frac{1}{4}$	$\frac{1}{5}$	$\frac{1}{8}$	$\frac{2}{3}$	$\frac{3}{4}$
Percentage	50%	$33\frac{1}{3}\%$	25%	20%	$12\frac{1}{2}\%$	$66\frac{2}{3}\%$	75%

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Example 26 Converting percentages to fractions

Express these percentages as fractions or mixed numbers in their simplest form.

a 17% **b** 36% **c** 140%

SOLUTION	EXPLANATION
a $17\% = \frac{17}{100}$	Change % sign to a denominator of 100.
b $36\% = \frac{36}{100}$	Change % sign to a denominator of 100.
$= \frac{9 \times 4}{25 \times 4}$	Cancel HCF.
$= \frac{9}{25}$	Answer is now in simplest form.
c $140\% = \frac{140}{100}$	Change % sign to a denominator of 100.
$= \frac{7 \times 20}{5 \times 20}$	Cancel HCF.
$= \frac{7}{5} = 1\frac{2}{5}$	Convert answer to a mixed number.

Example 27 Converting to percentages through equivalent fractions

Convert the following fractions to percentages.

a $\frac{5}{100}$ **b** $\frac{11}{25}$

SOLUTION	EXPLANATION
a $\frac{5}{100} = 5\%$	Denominator is already 100, therefore simply write number as a percentage.
b $\frac{11}{25} \overset{\times 4}{=} \frac{44}{100}$	Require denominator to be 100. Therefore, multiply numerator and denominator by 4 to get an equivalent fraction.
$= 44\%$	

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 28 Converting to percentages by multiplying by 100%

Convert the following fractions to percentages.

a $\frac{3}{8}$ **b** $3\frac{3}{5}$

SOLUTION | **EXPLANATION**

a $\frac{3}{8} \times 100 = \frac{3}{\cancel{8}_{2}} \times \frac{\cancel{100}^{25}}{1}$

$= \frac{75}{2} = 37\frac{1}{2}$

$\therefore \frac{3}{8} = 37\frac{1}{2}\%$

Multiply by 100%.
Simplify by cancelling HCF.
Write your answer as a mixed number.

b $3\frac{3}{5} \times 100 = \frac{18}{\cancel{15}_{1}} \times \frac{\cancel{100}^{20}}{1}$

$= 360$

$\therefore 3\frac{3}{5} = 360\%$

Convert mixed number to improper fraction.
Cancel and simplify.

Exercise 4I

1–3 | 3 | —

UNDERSTANDING

1 Change these test results to equivalent scores out of 100, and therefore state the percentage.

a 7 out of 10 = _____ out of 100 = _____%
b 24 out of 50 = _____ out of 100 = _____%
c 12 out of 20 = _____ out of 100 = _____%
d 1 out of 5 = _____ out of 100 = _____%
e 80 out of 200 = _____ out of 100 = _____%
f 630 out of 1000 = _____ out of 100 = _____%

2 Write these fraction sequences into your workbook and write beside each fraction the equivalent percentage value.

a $\frac{1}{4}, \frac{2}{4}, \frac{3}{4}, \frac{4}{4}$ **b** $\frac{1}{5}, \frac{2}{5}, \frac{3}{5}, \frac{4}{5}, \frac{5}{5}$ **c** $\frac{1}{3}, \frac{2}{3}, \frac{3}{3}$

3 **a** If 14% of students in Year 7 are absent due to illness, what percentage of Year 7 students are at school?
b If 80% of the Geography project has been completed, what percentage still needs to be finished?

4–7(½) | 4–7(½) | 4–7(½)

FLUENCY

Example 26a,b

4 Express these percentages as fractions in their simplest form.

a 11% **b** 71% **c** 43% **d** 49%
e 25% **f** 30% **g** 15% **h** 88%

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4I

FLUENCY

Example 26c

5 Express these percentages as mixed numbers in their simplest form.

a 120%	**b** 180%	**c** 237%	**d** 401%
e 175%	**f** 110%	**g** 316%	**h** 840%

Example 27

6 Convert these fractions to percentages, using equivalent fractions.

a $\frac{8}{100}$	**b** $\frac{15}{100}$	**c** $\frac{97}{100}$	**d** $\frac{50}{100}$
e $\frac{7}{20}$	**f** $\frac{8}{25}$	**g** $\frac{43}{50}$	**h** $\frac{18}{20}$
i $\frac{56}{50}$	**j** $\frac{27}{20}$	**k** $\frac{20}{5}$	**l** $\frac{16}{10}$

Example 28

7 Convert these fractions to percentages by multiplying by 100%.

a $\frac{1}{8}$	**b** $\frac{1}{3}$	**c** $\frac{4}{15}$	**d** $\frac{10}{12}$
e $1\frac{3}{20}$	**f** $4\frac{1}{5}$	**g** $2\frac{36}{40}$	**h** $\frac{13}{40}$

8, 9 | 9, 10 | 9–11

PROBLEM-SOLVING

8 A bottle of lemonade is only 25% full.
- **a** What fraction of the bottle has been consumed?
- **b** What percentage of the bottle has been consumed?
- **c** What fraction of the bottle is left?
- **d** What percentage of the bottle is left?

9 A lemon tart is cut into eight equal pieces. What percentage of the tart does each piece represent?

10 Petrina scores 28 out of 40 on her Fractions test. What is her score as a percentage?

11 The Heathmont Hornets basketball team have won 14 out of 18 games. They still have two games to play. What is the smallest and the largest percentage of games the Hornets could win for the season?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

41

12 | 12, 13 | 13, 14

REASONING

12 Lee won his tennis match with the score 6–4, 6–2, 6–1.

a What fraction of games did he win?

b What percentage of games did he win?



13 Scott and Penny have just taken out a home loan, with an interest rate of $5\frac{1}{2}\%$. Write this interest rate as a fraction.

14 Write each of the following percentages as fractions.

a $2\frac{1}{2}\%$ **b** $8\frac{1}{4}\%$ **c** $12\frac{1}{2}\%$ **d** $33\frac{1}{3}\%$

Lottery research

— | — | 15

ENRICHMENT

15 Conduct research on a major lottery competition. If possible:

a Find out, on average, how many tickets are sold each week.

b Find out, on average, how many tickets win a prize each week.

c Determine the percentage chance of winning a prize.

d Determine the percentage chance of winning the various divisions.

e Work out the average profit the lottery competition makes each week.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4J Percentage of a number

Interactive

Widgets

HOTsheets

Walkthroughs

A common application of percentages is to find a certain percentage of a given number. Throughout life you will come across many examples where you need to calculate percentages of a quantity. Examples include retail discounts, interest rates, personal improvements, salary increases, commission rates and more.

In this exercise we will focus on the mental calculation of percentages.



Retail sales may involve a percentage of the original price being taken away.

Let's start: Percentages in your head

It is a useful skill to be able to quickly calculate percentages mentally.
Calculating 10% or 1% is often a good starting point. You can then multiply or divide these values to arrive at other percentage values.

- In pairs, using mental arithmetic only, calculate these 12 percentages.

a 10% of $120	**b** 10% of $35	**c** 20% of $160	**d** 20% of $90
e 30% of $300	**f** 30% of $40	**g** 5% of $80	**h** 5% of $420
i 2% of $1400	**j** 2% of $550	**k** 12% of $200	**l** 15% of $60

- Check your answers with a classmate or your teacher.
- Design a quick set of 12 questions for a classmate.
- Discuss helpful mental arithmetic skills to increase your speed at calculating percentages.

Key ideas

■ To find the percentage of a number we:
1. Express the required percentage as a fraction.
2. Change the 'of' to a multiplication sign.
3. Express the number as a fraction.
4. Follow the rules for multiplication of fractions.

$$25\% \text{ of } 60 = \frac{25}{100} \times \frac{60}{1}$$
$$= 15$$

■ Percentage of a number $= \frac{\text{percentage}}{100} \times \text{number}$

Example 29 Finding the percentage of a number

Find:

a 30% of 50 **b** 15% of 400

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $30\% \text{ of } 50 = \frac{30}{100} \times \frac{50}{1}$	Write % as a fraction.
$= \frac{30}{2} = 15$	Cancel and simplify.
Mental arithmetic:	
10% of 50 = 5	
Hence, 30% of 50 = 15.	Multiply by 3 to get 30%.
b $15\% \text{ of } 400 = \frac{15}{100} \times \frac{400}{1}$	Write % as a fraction.
$= \frac{15 \times 4}{1} = 60$	Cancel and simplify.
Mental arithmetic:	
10% of 400 = 40, 5% of 400 = 20	Halve to get 5%.
Hence, 15% of 400 = 60.	Multiply by 3 to get 15%.



Example 30 Solving a worded percentage problem

Jacqueline has saved up $50 to purchase a new pair of jeans. She tries on many different pairs but only likes two styles, Evie and Next. The Evie jeans are normally $70 and are on sale with a 25% discount. The Next jeans retail for $80 and have a 40% discount for the next 24 hours. Can Jacqueline afford either pair of jeans?

SOLUTION	EXPLANATION
Evie jeans	
Discount = 25% of $70	Calculate the discount on the Evie jeans.
$= \frac{25}{100} \times \frac{70}{1} = \$17.50$	Find 25% of $70.
Sale price = $70 – $17.50	Find the sale price by subtracting the discount.
= $52.50	
Next jeans	
Discount = 40% of $80	Calculate the discount on the Next jeans.
$= \frac{40}{100} \times \frac{80}{1} = \$32$	Find 40% of $80.
Sale price = $80 – $32	Find the sale price by subtracting the discount.
= $48	
Jacqueline can afford the Next jeans.	

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4J

1–2 | 2 | —

UNDERSTANDING

1 Copy and complete the following sentences.

a Finding 10% of a quantity is the same as dividing the quantity by _____.
b Finding 1% of a quantity is the same as dividing the quantity by _____.
c Finding 50% of a quantity is the same as dividing the quantity by _____.
d Finding 100% of a quantity is the same as dividing the quantity by _____.
e Finding 20% of a quantity is the same as dividing the quantity by _____.
f Finding 25% of a quantity is the same as dividing the quantity by _____.

2 Without calculating the exact values, determine which alternative (**i** or **ii**) has the highest value.

a **i** 20% of $400 **ii** 25% of $500
b **i** 15% of $3335 **ii** 20% of $4345
c **i** 3% of $10 000 **ii** 2% of $900
d **i** 88% of $45 **ii** 87% of $35

3–4(½), 5 | 3–4(½), 5, 6(½) | 3–4(½), 5, 6(½)

FLUENCY

Example 29

3 Find:

a 50% of 140	**b** 10% of 360	**c** 20% of 50	**d** 30% of 90
e 25% of 40	**f** 25% of 28	**g** 75% of 200	**h** 80% of 250
i 5% of 80	**j** 4% of 1200	**k** 5% of 880	**l** 2% of 9500
m 11% of 200	**n** 21% of 400	**o** 12% of 300	**p** 9% of 700

4 Find:

a 120% of 80	**b** 150% of 400	**c** 110% of 60	**d** 400% of 25
e 125% of 12	**f** 225% of 32	**g** 146% of 50	**h** 3000% of 20

5 Match the questions with their correct answer.

Questions	Answers
10% of $200	$8
20% of $120	$16
10% of $80	$20
50% of $60	$24
20% of $200	$25
5% of $500	$30
30% of $310	$40
10% of $160	$44
1% of $6000	$60
50% of $88	$93

6 Find:

a 30% of $140	**b** 10% of 240 millimetres	**c** 15% of 60 kilograms
d 2% of 4500 tonnes	**e** 20% of 40 minutes	**f** 80% of 500 centimetres
g 5% of 30 grams	**h** 25% of 12 hectares	**i** 120% of 120 seconds

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4J

PROBLEM-SOLVING

7, 8 | 8–10 | 10–12

7 Harry scored 70% on his Percentages test. If the test is out of 50 marks, how many marks did Harry score?

Example 30

8 Grace wants to purchase a new top and has $40 to spend. She really likes a red top that was originally priced at $75 and has a 40% discount ticket on it. At another shop, she also likes a striped hoody, which costs $55. There is 20% off all items in the store on this day. Can Grace afford either of the tops?

9 In a student survey, 80% of students said they received too much homework. If 300 students were surveyed, how many students felt they get too much homework?

10 25% of teenagers say their favourite fruit is watermelon. In a survey of 48 teenagers, how many students would you expect to write watermelon as their favourite fruit?

11 At Gladesbrook College, 10% of students walk to school, 35% of students catch public transport and the remainder of students are driven to school. If there are 1200 students at the school, find how many students:

- **a** walk to school
- **b** catch public transport
- **c** are driven to school

12 Anthea has just received a 4% salary increase. Her wage before the increase was $2000 per week.

- **a** How much extra money does Anthea receive due to her salary rise?
- **b** What is Anthea's new salary per week?
- **c** How much extra money does Anthea receive per year?

REASONING

13 | 13, 14 | 15–18

13 Sam has 2 hours of 'free time' before dinner is ready. He spends 25% of that time playing computer games, 20% playing his drums, 40% playing outside and 10% reading a book.

- **a** How long does Sam spend doing each of the four different activities?
- **b** What percentage of time does Sam have remaining at the end of his four activities?
- **c** Sam must set the table for dinner, which takes 5 minutes. Does he still have time to get this done?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4J

REASONING

14 Gavin mows 60% of the lawn in 48 minutes. How long will it take him to mow the entire lawn if he mows at a constant rate?

15 Find:

a 20% of (50% of 200)
b 10% of (30% of 3000)
c 5% of (5% of 8000)
d 80% of (20% of 400)

16 Which is larger: 60% of 80 or 80% of 60?

17 Tom did the following calculation: $120 \div 4 \div 2 \times 3$. What percentage of 120 did Tom find?

18 **a** If 5% of an amount is \$7, what is 100% of the amount?

b If 25% of an amount is \$3, what is $12\frac{1}{2}$% of the amount?

ENRICHMENT

Waning interest — — 19

19 When someone loses interest or motivation in a task, they can be described as having a 'waning interest'. Jill and Louise are enthusiastic puzzle makers, but they gradually lose interest when tackling very large puzzles.

a Jill is attempting to complete a 5000-piece jigsaw puzzle in 5 weeks. Her interest drops off, completing 100 fewer pieces each week.

i How many pieces must Jill complete in the first week to ensure that she finishes the puzzle in the 5-week period?
ii What percentage of the puzzle does Jill complete during each of the 5 weeks?
iii What is the percentage that Jill's interest wanes each week?

b Louise is attempting to complete an 8000-piece jigsaw puzzle in 5 weeks. Her interest drops off at a constant rate of 5% per week.



i What percentage of the puzzle must Louise complete in the first week to ensure she finishes the puzzle in the 5-week period?
ii Record how many pieces of the puzzle Louise completes each week and the corresponding percentage of the puzzle.
iii Produce a table showing the cumulative number of pieces completed and the cumulative percentage of the puzzle completed over the 5-week period.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4K Expressing a quantity as a proportion

Interactive

Widgets

HOTsheets

Walkthroughs

Sometimes we want to know the proportion of a certain quantity compared to a given total or another quantity. This may be done using a fraction, percentage or ratio. The Earth's surface, for example, is about 70% ocean. So, the proportion of land could be written as 30% (as a percentage) or $\frac{3}{10}$ (as a fraction). The ratio of land to ocean could be described as 30 parts of land to 70 parts of ocean. Alternatively, the ratio could be expressed as 3 parts of land to 7 parts of ocean.



The proportion of land to sea in this photo of the Whitsunday Islands, Queensland, could be expressed as a fraction, percentage or ratio.

Let's start: Tadpole proportion

Scientists Hugh and Jack take separate samples of tadpoles, which include green and brown tadpoles, from their local water channels. Hugh's sample contains 3 green tadpoles and 15 brown tadpoles, whereas Jack's sample contains 27 green tadpoles and 108 brown tadpoles.

- Find the proportion of green tadpoles in each of Hugh and Jack's samples.
- Use both fractions and percentages to compare the proportions.
- Which sample might be used to convince the local council that there are too many brown tadpoles in the water channels?

Key ideas


- To express one quantity as a fraction of another:

$$\text{fraction} = \frac{\text{amount}}{\text{total}}$$

- To express one quantity as a percentage of another:

$$\text{percentage} = \frac{\text{amount}}{\text{total}} \times \frac{100}{1}$$

- A ratio compares parts of a total.



$$\text{Red fraction} = \frac{2}{5}$$

$$\text{Red percentage} = \frac{2}{5} \times \frac{100}{1} = 40\%$$

Ratio = 2 parts red to 3 parts yellow

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 31 Expressing as a proportion

Express the following as both a fraction and percentage of the total.

a $40 out of a total of $200

b 24 green ducks out of a total of 30 ducks


SOLUTION	EXPLANATION
a Fraction $= \frac{40}{200}$	Write the given amount and divide by the total. Then simplify the fraction.
$= \frac{1}{5}$	
Percentage $= \frac{40}{200} \times \frac{100}{1}$	Multiply the fraction by 100 to convert to a percentage.
$= 20\%$	
b Fraction $= \frac{24}{30}$	There is a total of 24 brown ducks out of a total of 30.
$= \frac{4}{5}$	
Percentage $= \frac{24}{30} \times \frac{100}{1}$	Use the same fraction and multiply by 100.
$= 80\%$	

Example 32 Using ratios

A glass of cordial is 1 part syrup to 9 parts water.

a Express the amount of syrup as a fraction of the total.

b Express the amount of water as a percentage of the total.



SOLUTION	EXPLANATION
a Fraction $= \frac{1}{10}$	There is a total of 10 parts, including 1 part syrup.
b Percentage $= \frac{9}{10} \times \frac{100}{1}$	There is a total 9 parts water in a total of 10 parts.
$= 90\%$	


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 4K

1, 2 | 2 | —

UNDERSTANDING

1 This square shows some coloured triangles and some white triangles.



- **a** How many triangles are coloured?
- **b** How many triangles are white?
- **c** What fraction of the total is coloured?
- **d** What percentage of the total is coloured?
- **e** What fraction of the total is white?
- **f** What percentage of the total is white?

2 A farmer's pen has 2 black sheep and 8 white sheep.

- **a** How many sheep are there in total?
- **b** What fraction of the sheep are black?
- **c** What fraction of the sheep are white?
- **d** What percentage of the sheep are black?
- **e** What percentage of the sheep are white?

3(½), 4–6 | 3(½), 4–7 | 3–4(½), 5–7

FLUENCY

Example 31

3 Express the following as both a fraction and a percentage of the total.


- **a** 30 out of a total of 100
- **b** 3 out of a total of 5
- **c** \$10 out of a total of \$50
- **d** \$60 out of a total of \$80
- **e** 2 kg out of a total of 40 kg
- **f** 14 g out of a total of 28 g
- **g** 3 L out of a total of 12 L
- **h** 30 mL out of a total of 200 mL

4 Write each coloured area as both a fraction and percentage of the total area.


a




b




c




d



e



f



Example 32

5 A jug of lemonade is made up of 2 parts of lemon juice to 18 parts of water.

- **a** Express the amount of lemon juice as a fraction of the total.
- **b** Express the amount of lemon juice as a percentage of the total.

6 A mix of concrete is made up of 1 part of cement to 4 parts of sand.

- **a** Express the amount of cement as a fraction of the total.
- **b** Express the amount of cement as a percentage of the total.
- **c** Express the amount of sand as a fraction of the total.
- **d** Express the amount of sand as a percentage of the total.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4K

FLUENCY

7 A pair of socks is made up of 3 parts of wool to 1 part of nylon.
- **a** Express the amount of wool as a fraction of the total.
- **b** Express the amount of wool as a percentage of the total.
- **c** Express the amount of nylon as a fraction of the total.
- **d** Express the amount of nylon as a percentage of the total.

PROBLEM-SOLVING


8, 9 | 9–11 | 10–12

8 Gillian pays $80 tax out of her income of $1600. What percentage of her income does she keep?

9 Over summer, a dam's water volume reduces from 20 megalitres to 4 megalitres. What fraction of the water in the dam has been lost?

10 Express the following as a fraction and percentage of the total.
- **a** 20 cents of $5
- **b** 14 days out of 5 weeks
- **c** 15 centimetres removed from a total length of 3 metres
- **d** 3 seconds taken from a world record time of 5 minutes
- **e** 180 grams of a total of 9 kilograms
- **f** 1500 centimetres from a total of 0.6 kilometres

11 Of 20 students, 10 play sport and 12 play a musical instrument, with some of these students playing both sport and music. Two students do not play any sport or musical instrument.



- **a** What fraction of the students play both sport and a musical instrument?
- **b** What percentage of the students play a musical instrument but not a sport?

12 An orchard of 80 apple trees is tested for diseases. 20 of the trees have blight disease, 16 have brown rot disease and some trees have both. A total of 48 trees have neither blight nor brown rot.
- **a** What percentage of the trees has both diseases?
- **b** What fraction of the trees has blight but does not have brown rot?

REASONING

13 | 13, 14 | 15–17

13 For a recent class test, Ross scored 45 out of 60 and Maleisha scored 72 out of 100. Use percentages to show that Ross obtained the higher mark.

14 The prices of two cars are reduced for sale. A hatch priced at $20 000 is now reduced by $3000 and a 4WD priced at $80 000 is now reduced by $12 800. Determine which car has the largest percentage reduction, giving reasons.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4K

REASONING

15 A yellow sports drink has 50 g of sugar dissolved in fluid that weighs 250 g, including the weight of the sugar. A blue sports drink has 57 g of sugar dissolved in fluid that weighs 300 g, including the weight of the sugar. Which sports drink has the least percentage of sugar? Give reasons.

16 A room contains a girls and b boys.

a Write an expression using the pronumerals a and b for the fraction of:

i boys in the room **ii** girls in the room

b Write an expression using the pronumerals a and b for the percentage of:

i boys in the room **ii** girls in the room

17 A mixture of dough has a parts of flour to b parts of water.

a Write an expression for the fraction of flour.

b Write an expression for the percentage of water.




ENRICHMENT

Transport turmoil — — 18

18 A class survey of 30 students reveals that the students use three modes of transport to get to school: bike, public transport and car. All of the students used at least one of these three modes of transport in the past week.

Twelve students used a car to get to school and did not use any of the other modes of transport. One student used all three modes of transport and one student used only a bike for the week. There were no students who used both a bike and a car but no public transport. Five students used both a car and public transport but not a bike. Eight students used only public transport.

Use this diagram to help answer the following.



a How many students used both a bike and public transport but not a car?

b What fraction of the students used all three modes of transport?

c What fraction of the students used at least one mode of transport, including a bike?

d What fraction of the students used at least one mode of transport, including public transport?

e What percentage of students used public transport and a car during the week?


f What percentage of students used either public transport or a car or both during the week?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Egyptian fractions

The fractions in the ancient Egyptian Eye of Horus were used for dividing up food and land, as well as portions of medicine. They are called **unitary** fractions because all the numerators are 1.



Clearly, the ancient Egyptians had no calculators or precise measuring instruments; nevertheless, by repeatedly dividing a quantity in half, the fractions $\frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{1}{16}$ or $\frac{1}{32}$ were combined to estimate any other fraction.


Imagine that you are an ancient Egyptian baker and wish to share your last three loaves of bread equally between four people.



First, you cut two loaves in half and give half a loaf to each of your four customers.



You have one loaf remaining and you can cut that into quarters (i.e. half and then half again).




So each of your four customers now receives half a loaf and one-quarter of a loaf, which is $\frac{3}{4}$ ( ) of a loaf.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Using ancient Egyptian fractions, how could three loaves be divided equally between five people?

First, cut the loaves in half and give each customer $\frac{1}{2}$ ( ) a loaf. The remaining half loaf can be cut into eight parts and each person is given $\frac{1}{8}$ of $\frac{1}{2} = \frac{1}{16}$th ( ) of a loaf. There is a small portion left $\left(3 \text{ portions of } \frac{1}{16}\right)$, so these portions can be divided in half and each customer given $\frac{1}{2}$ of $\frac{1}{16} = \frac{1}{32}$ ( ) of a loaf.



Each customer has an equal share $\frac{1}{2} + \frac{1}{16} + \frac{1}{32}$ ( ) of the loaf and the baker will have the small $\frac{1}{32}$ ( ) of a loaf left over.



If each loaf is divided *exactly* into five parts, the three loaves would have 15 equal parts altogether and each customer could have three parts of the 15; $\frac{3}{15} = \frac{1}{5}$th of the total or $\frac{3}{5}$th of one loaf.

$\frac{3}{5} = 0.6$ and $\frac{1}{2} + \frac{1}{16} + \frac{1}{32} = 0.59375 \approx 0.6$ ($\approx$ means approximately equal).

So even without calculators or sophisticated measuring instruments, the ancient Egyptian method of repeated halving gives quite close approximations to the exact answers.

Task

Using diagrams, explain how the following portions can be divided equally using only the ancient Egyptian unitary fractions of $\frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{1}{16}$ and $\frac{1}{32}$

a three loaves of bread shared between eight people
b one loaf of bread shared between five people
c two loaves of bread shared between three people

Include the Egyptian Eye of Horus symbols for each answer, and determine the difference between the exact answer and the approximate answer found using the ancient Egyptian method.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Find the sum of all fractions in the form $\frac{a}{b}$ where the numerator a is less than the denominator b, and b is an integer from 2 to 10 inclusive.

2 At the end of each practice session, Coach Andy rewards his swim team by distributing 30 pieces of chocolate according to effort. Each swimmer receives a *different* number of whole pieces of chocolate. Suggest possible numbers (all different) of chocolate pieces for each swimmer attending practice when the chocolate is shared between:

a 4 swimmers
b 5 swimmers
c 6 swimmers
d 7 swimmers



3 In this magic square the sum of the fractions in each row, column and diagonal is the same. Find the value of each letter in this magic square.

$\frac{2}{5}$	A	$\frac{4}{5}$
B	C	D
E	$\frac{1}{2}$	1

4 You are given four fractions: $\frac{1}{3}, \frac{1}{4}, \frac{1}{5}$ and $\frac{1}{6}$. Using any three of these fractions, complete each number sentence below.

a $____ + ____ \times ____ = \frac{7}{30}$


b $____ \div ____ - ____ = \frac{7}{6}$

c $____ + ____ - ____ = \frac{13}{60}$

5 When a \$50 item is increased by 20%, the final price is \$60. Yet when a \$60 item is reduced by 20%, the final price is not \$50. Explain.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

4A **1** Which set of fractions corresponds to each of the different shapes positioned on the number line?



A $\frac{3}{8}, \frac{6}{8}, 1\frac{3}{8}, \frac{12}{8}$ **B** $\frac{3}{8}, \frac{3}{4}, 1\frac{1}{4}, \frac{12}{8}$ **C** $\frac{1}{2}, \frac{3}{4}, \frac{9}{8}, 1\frac{5}{8}$


D $\frac{2}{8}, \frac{3}{4}, 1\frac{3}{8}, 1\frac{1}{2}$ **E** $\frac{3}{8}, \frac{3}{4}, 1\frac{1}{2}, \frac{14}{8}$

4B **2** Which of the following statements is not true?

A $\frac{3}{4} = \frac{9}{12}$ **B** $\frac{6}{11} = \frac{18}{33}$ **C** $\frac{3}{10} = \frac{15}{40}$

D $\frac{13}{14} = \frac{39}{42}$ **E** $\frac{2}{7} = \frac{16}{56}$

4C **3** Which set of mixed numbers corresponds to the letters written on the number line?



A $1\frac{1}{5}, 1\frac{3}{5}, 2\frac{2}{5}, 3\frac{1}{5}$ **B** $1\frac{2}{5}, 1\frac{3}{5}, 2\frac{3}{5}, 3\frac{1}{5}$ **C** $1\frac{1}{5}, 1\frac{2}{5}, 2\frac{2}{5}, 3\frac{2}{5}$

D $1\frac{2}{5}, 1\frac{4}{5}, 2\frac{2}{5}, 3\frac{2}{5}$ **E** $1\frac{1}{5}, 1\frac{3}{5}, 2\frac{3}{5}, 3\frac{1}{5}$

4D **4** Which is the lowest common denominator for this set of fractions? $\frac{7}{12}, \frac{11}{15}, \frac{13}{18}$

A 60 **B** 120 **C** 180 **D** 3240 **E** 90

4D **5** Which of the following fraction groups is in correct descending order?

A $\frac{1}{5}, \frac{1}{3}, \frac{2}{2}$ **B** $\frac{3}{4}, \frac{3}{5}, \frac{3}{8}, \frac{3}{7}$ **C** $\frac{5}{8}, \frac{4}{5}, \frac{3}{8}, \frac{2}{3}$

D $\frac{1}{10}, \frac{1}{20}, \frac{1}{50}, \frac{1}{100}$ **E** $2\frac{1}{5}, 2\frac{8}{15}, 2\frac{2}{3}, 2\frac{3}{4}$

4E **6** Which problem has an incorrect answer?

A $\frac{1}{6} + \frac{3}{6} = \frac{4}{6}$ **B** $\frac{3}{4} + \frac{5}{12} = \frac{5}{16}$ **C** $\frac{3}{4} \times \frac{5}{12} = \frac{5}{16}$

D $5\frac{2}{3} - 3\frac{1}{4} = 2\frac{5}{12}$ **E** $\frac{3}{4} \times \frac{4}{5} = \frac{3}{5}$

4E **7** Three friends share a pizza. Kate eats $\frac{1}{5}$ of the pizza, Archie eats $\frac{1}{3}$ of the pizza and Luke eats the rest. What fraction of the pizza does Luke eat?

A $\frac{4}{12}$ **B** $\frac{2}{3}$ **C** $\frac{14}{15}$ **D** $\frac{7}{15}$ **E** $\frac{8}{15}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4D/I **8** Which list is in correct ascending order?

A 0.68, $\frac{3}{4}$, 0.76, 77%, $\frac{13}{40}$

B $\frac{7}{8}$, 82%, 0.87, $\frac{12}{15}$, 88%

C 21%, 0.02, 0.2, 0.22, $\frac{22}{10}$

D $\frac{14}{40}$, 0.3666, $0.3\dot{6}$, 37%, $\frac{93}{250}$

E 0.76, 72%, $\frac{3}{4}$, 0.68, $\frac{13}{40}$

4C **9** $\frac{60}{14}$ can be written as:


A $4\frac{2}{7}$ **B** $2\frac{4}{7}$ **C** $4\frac{2}{14}$ **D** $7\frac{4}{7}$ **E** $5\frac{1}{7}$

4G **10** $\frac{17}{25}$ of a metre of material is needed for a school project. How many centimetres is this?

A 65 cm **B** 70 cm **C** 68 cm **D** 60 cm **E** 75 cm

Short-answer questions

4A **1** List the shaded fractions in correct ascending order.



4B **2** Write four fractions equivalent to $\frac{3}{5}$ and write a sentence to explain why they are equal in value.

4B **3** Write the following fractions in simplest form.

a $\frac{18}{30}$ **b** $\frac{8}{28}$ **c** $\frac{35}{49}$

4C **4** Convert each of the following to a mixed number in simplest form.

a $\frac{15}{10}$ **b** $\frac{63}{36}$ **c** $\frac{45}{27}$ **d** $\frac{56}{16}$

4D **5** Place the correct mathematical symbol $<, =$ or $>$, in between the following pairs of fractions to make true mathematical statements.

a $\frac{2}{7} \square \frac{4}{7}$ **b** $\frac{3}{8} \square \frac{1}{8}$

c $1\frac{2}{3} \square 1\frac{3}{5}$ **d** $3\frac{1}{9} \square \frac{29}{9}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

4D **6** State the largest fraction in each list.

a $\frac{3}{7}, \frac{2}{7}, \frac{5}{7}, \frac{1}{7}$ b $\frac{3}{8}, \frac{2}{8}, \frac{5}{8}, \frac{1}{8}$

4D **7** State the lowest common multiple for each pair of numbers.

a 2, 5 b 3, 7 c 8, 12

4D **8** State the lowest common denominator for each set of fractions.

a $\frac{1}{2}, \frac{3}{5}$ b $\frac{2}{3}, \frac{3}{7}$ c $\frac{3}{8}, \frac{5}{12}$

4D **9** Rearrange each set of fractions in descending order.

a $1\frac{3}{5}, \frac{9}{5}, 2\frac{1}{5}$ b $\frac{14}{8}, \frac{11}{6}, \frac{9}{4}, \frac{5}{3}$ c $5\frac{2}{3}, \frac{47}{9}, 5\frac{7}{18}, 5\frac{1}{9}, 5\frac{1}{3}$

4E/F **10** Determine the simplest answer for each of the following.

a $\frac{3}{8}+\frac{1}{8}$ b $\frac{1}{3}+\frac{1}{2}$ c $\frac{3}{8}+\frac{5}{6}$

d $2\frac{7}{15}+3\frac{3}{10}$ e $\frac{7}{8}-\frac{3}{8}$ f $5\frac{1}{4}-2\frac{3}{4}$

g $\frac{3}{4}-\frac{2}{5}+\frac{7}{8}$ h $8\frac{7}{12}-4\frac{7}{9}+2\frac{1}{3}$ i $13\frac{1}{2}+5\frac{7}{10}-6\frac{3}{5}$

4G **11** Find:

a $\frac{1}{3}\times 21$ b $\frac{4}{5}$ of 100 c $\frac{3}{4}$ of 16

d $\frac{8}{10}\times\frac{25}{4}$ e $\frac{2}{3}$ of $\frac{1}{4}$ f $3\frac{1}{8}\times 2\frac{2}{5}$

4H **12** Determine the reciprocal of each of the following.

a $\frac{3}{4}$ b $\frac{7}{12}$ c $2\frac{3}{4}$ d $5\frac{1}{3}$

4H **13** Perform these divisions.

a $\frac{6}{10}\div 3$ b $64\div 3\frac{1}{5}$

c $6\frac{2}{5}\div 1\frac{6}{10}$ d $\frac{3}{8}\div 1\frac{1}{4}\div 1\frac{1}{2}$

4I **14** Copy the table into your workbook and complete.

Percentage form	36%			140%		18%
Fraction		$2\frac{1}{5}$	$\frac{5}{100}$		$\frac{11}{25}$	

4J **15** Determine which alternative (**i** or **ii**) is the better value discount.

a **i** 25% of \$200 **ii** 20% of \$260

b **i** 5% of \$1200 **ii** 3% of \$1900

4K **16** Express the following as both a fraction and percentage of the total.

a 6 out of 10 b \$4 out of 20

c 50 cents out of \$8 d 600 mL out of 2 L

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 Evaluate each of the following.

a $3\frac{1}{4}+1\frac{3}{4}\times 2\frac{1}{2}$

b $5\div 3\frac{1}{3}+4\frac{3}{8}-\frac{5}{12}$

c $7\frac{2}{5}+2\frac{1}{10}\div 2\frac{4}{5}\times 3\frac{3}{4}$

d $3\frac{5}{7}+6\frac{1}{4}\div\left(3\frac{3}{8}-\frac{3}{4}\right)$

2 The length of one side of a triangle is $\frac{5}{12}$ of the perimeter and a second side has length $\frac{5}{28}$ of the perimeter. If these two sides have a total length of 77 centimetres, determine the triangle's perimeter as a mixed number.

3 **a** A sale on digital cameras offers 20% discount. Determine the sale price of a camera that was originally priced at $220.

b The sale price of a DVD is $18. This is 25% less than the original marked price. Determine the original price of this DVD.

4 Perform the following calculations.

a Increase $440 by 25%.

b Decrease 300 litres by 12%.

c Increase $100 by 10% and then decrease that amount by 10%. Explain the reason for the answer.

d When $\$A$ is increased by 20%, the result is $300. Calculate the result if $\$A$ is decreased by 20%.

5 When a Ripstick is sold for $200 the shop makes 25% profit on the price paid for it.
If this $200 Ripstick is now sold at a discount of 10%, what is the percentage profit of the price at which the shop bought the Ripstick?
At what price should the Ripstick be sold to make 30% profit?

6 At Sunshine School there are 640 primary school students and 860 secondary students.
For their Christmas family holiday, 70% of primary school students go to the beach and 45% of secondary students go to the beach.
Determine the overall percentage of students in the whole school that has a beach holiday for Christmas. Write this percentage as a mixed number.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 5 Algebra

What you will learn

5A Introduction to algebra
5B Substituting and evaluating
5C Equivalent expressions
5D Like terms
5E Multiplying and dividing expressions
5F Expanding brackets (Extending)
5G Algebraic modelling (Extending)

Australian curriculum

NUMBER AND ALGEBRA

Patterns and algebra


Introduce the concept of variables as a way of representing numbers using letters (ACMNA175)

Create algebraic expressions and evaluate them by substituting a given value for each variable (ACMNA176)

Extend and apply the laws and properties of arithmetic to algebraic terms and expressions (ACMNA177)

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Designing robots

Algebra provides a way to describe everyday activities using mathematics alone. By allowing letters like x or y to stand for unknown numbers, different concepts and relationships can be described easily.

Engineers apply their knowledge of algebra and geometry to design buildings, roads, bridges, robots, cars, satellites, planes, ships and hundreds of other structures and devices that we take for granted in our world today.

To design a robot, engineers use algebraic rules to express the relationship between the position of the robot's 'elbow' and the possible positions of a robot's 'hand'. Although they cannot think for themselves, electronically programmed robots can perform tasks cheaply, accurately and consistently, without ever getting tired or sick or injured, or the need for sleep or food! Robots can have multiple arms, reach much farther than a human arm and can safely lift heavy, awkward objects.

Robots are used extensively in car manufacturing. At one plant that uses robots and humans, a finished car comes off the assembly line every 76 seconds.

Understanding and applying mathematics has made car manufacturing safer and also extremely efficient.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5A Introduction to algebra









A pronumeral is a letter that can represent a number. The choice of letter used is not significant mathematically, but can be used as an aid to memory. For instance, h might stand for someone's height and w might stand for someone's weight.

The table shows the salary Petra earns for various hours of work if she is paid \$12 an hour.

Numbers of hours	Salary earned (\$)
1	$12 \times 1 = 12$
2	$12 \times 2 = 24$
3	$12 \times 3 = 36$
n	$12 \times n = 12n$

Rather than writing $12 \times n$, we write $12n$ because multiplying a pronumeral by a number is common and this notation saves space. We can also write $18 \div n$ as $\frac{18}{n}$.



Using pronumerals we can work out a total salary for any number of hours of work.

Let's start: Pronumeral stories

Ahmed has a jar with b biscuits. He eats 3 biscuits and then shares the rest equally among 8 friends. Each friend receives $\frac{b-3}{8}$ biscuits. This is a short story for the expression $\frac{b-3}{8}$.

- Try to create another story for $\frac{b-3}{8}$, and share it with others in the class.
- Can you construct a story for $2t + 12$? What about $4(k + 6)$?

Key ideas

- In algebra, letters can be used to stand for numbers. A **pronumeral** is a letter that stands for a number. If a pronumeral could represent *any* number rather than just one, it is also called a **variable**.
- $a \times b$ is written as ab and $a \div b$ is written as $\frac{a}{b}$.
- A **term** consists of numbers and pronumerals combined with multiplication or division. For example, 5 is a term, x is a term, $9a$ is a term, abc is a term, $\frac{4xyz}{3}$ is a term.
- A term that does not contain any pronumerals is called a **constant term**. All numbers by themselves are constant terms.
- An (**algebraic**) **expression** consists of numbers and pronumerals combined with any mathematical operations. For example, $3x + 2yz$ is an expression and $8 \div (3a - 2b) + 41$ is also an expression. Any term is also an expression.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- A **coefficient** is the number in front of a pronumeral. For example, the coefficient of y in the expression $8x + 2y + z$ is 2. If there is no number in front, then the coefficient is 1, since $1z$ and z are equal.

Example 1 The terminology of algebra

a List the individual terms in the expression $3a + b + 13c$.

b State the coefficient of each pronumeral in the expression $3a + b + 13c$.

c Give an example of an expression with exactly two terms, one of which is a constant term.

SOLUTION	EXPLANATION
a There are three terms: $3a$, b and $13c$.	Each part of an expression is a term. Terms get added (or subtracted) to make an expression.
b The coefficient of a is 3, the coefficient of b is 1 and the coefficient of c is 13.	The coefficient is the number in front of a pronumeral. For b the coefficient is 1 because b is the same as $1 \times b$.
c $27a + 19$ (There are many other possible expressions.)	This expression has two terms, $27a$ and 19, and 19 is a constant term because it is a number without any pronumerals.

Example 2 Writing expressions from word descriptions

Write an expression for each of the following.

a 5 more than k **b** 3 less than m **c** the sum of a and b

d double the value of x **e** the product of c and d

SOLUTION	EXPLANATION
a $k + 5$	5 must be added to k to get 5 more than k.
b $m - 3$	3 is subtracted from m.
c $a + b$	a and b are added to obtain their sum.
d $2 \times x$ or $2x$	x is multiplied by 2. The multiplication sign is optional.
e $c \times d$ or cd	c and d are multiplied to obtain their product.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Expressions involving more than one operation

Write an expression for each of the following without using the × or ÷ symbols.

a p is halved, then 4 is added

b the sum of x and y is taken and then divided by 7

c the sum of x and one-seventh of y

d 5 is subtracted from k and the result is tripled

SOLUTION	EXPLANATION
a $\frac{p}{2} + 4$	p is divided by 2, then 4 is added.
b $(x + y) \div 7 = \frac{x + y}{7}$	x and y are added. This whole expression is divided by 7. By writing the result as a fraction, the brackets are no longer needed.
c $x + \frac{y}{7}$ or $x + \frac{1}{7}y$	x is added to one-seventh of y, which is $\frac{y}{7}$.
d $(k - 5) \times 3 = 3(k - 5)$	5 subtracted from k gives the expression $k - 5$. Brackets must be used to multiply the whole expression by 3.

Exercise 5A

1, 2 | 1, 2 | —

UNDERSTANDING

Example 1

1 The expression $4x + 3y + 24z + 7$ has four terms.

a List the terms.

b What is the constant term?

c What is the coefficient of x?

d Which letter has a coefficient of 24?

Example 2

2 Match each of the word descriptions on the left with the correct mathematical expression on the right.

a the sum of x and 4

b 4 less than x

c the product of 4 and x

d one-quarter of x

e the result from subtracting x from 4

f 4 divided by x

A $x - 4$

B $\frac{x}{4}$

C $4 - x$

D $4x$

E $\frac{4}{x}$

F $x + 4$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5A

FLUENCY

3, 4–5(½) | 3, 4–5(½), 6 | 3–6(½)

3 For each of the following expressions, state:

i the number of terms; and

ii the coefficient of n.

a $17n + 24$

b $31 - 27a + 15n$

c $15nw + 21n + 15$

d $15a - 32b + 2n + \frac{4}{3}xy$

e $n + 51$

f $5bn - 12 + \frac{d}{5} + 12n$

4 Write an expression for each of the following without using the × or ÷ symbols.

a 1 more than x

b the sum of k and 5

c double the value of u

d 4 lots of y

e half of p

f one-third of q

g 12 less than r

h the product of n and 9

i t is subtracted from 10

j y is divided by 8

Example 3

5 Write an expression for each of the following without using the × or ÷ symbols.

a 5 is added to x, then the result is doubled.

b a is tripled, then 4 is added.

c k is multiplied by 8, then 3 is subtracted.

d 3 is subtracted from k, then the result is multiplied by 8.

e The sum of x and y is multiplied by 6.

f x is multiplied by 7 and the result is halved.

g p is halved and then 2 is added.

h The product of x and y is subtracted from 12.

6 Describe each of these expressions in words.

a $7x$

b $a + b$

c $(x + 4) \times 2$

d $5 - 3a$

PROBLEM-SOLVING

7, 8 | 8–10 | 8–11

7 Nicholas buys 10 lolly bags from a supermarket.

a If there are 7 lollies in each bag, how many lollies does he buy in total?

b If there are n lollies in each bag, how many lollies does he buy in total?
Hint: Write an expression involving n.

8 Mikayla is paid $\$x$ per hour at her job. Write an expression for each of the following amounts (in $).

a How much does Mikayla earn if she works 8 hours?

b If Mikayla gets a pay rise of $3 per hour, what is her new hourly wage?

c If Mikayla works for 8 hours at the increased hourly rate, how much does she earn?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5A

PROBLEM-SOLVING

9 Recall that there are 100 centimetres in 1 metre and 1000 metres in 1 kilometre. Write expressions for each of the following.

- **a** How many metres are there in x km?
- **b** How many centimetres are there in x metres?
- **c** How many centimetres are there in x km?

10 A group of people go out to a restaurant, and the total amount they must pay is $\$A$. They decide to split the bill equally. Write expressions to answer the following questions.

- **a** If there are 4 people in the group, how much do they each pay?
- **b** If there are n people in the group, how much do they each pay?
- **c** One of the n people has a voucher that reduces the total bill by \$20. How much does each person pay now?

11 There are many different ways of describing the expression $\frac{a+b}{4}$ in words. One way is: 'The sum of a and b is divided by 4.' What is another way?

REASONING

12 | 12, 14 | 13, 14

12 If x is a whole number between 10 and 99, classify each of these statements as true or false.

- **a** x must be smaller than $2 \times x$.
- **b** x must be smaller than $x + 2$.
- **c** $x - 3$ must be greater than 10.
- **d** $4 \times x$ must be an even number.
- **e** $3 \times x$ must be an odd number.

13 If b is an even number greater than 3, classify each of these statements as true or false.

- **a** $b + 1$ must be even.
- **b** $b + 2$ could be odd.
- **c** $5 + b$ could be greater than 10.
- **d** $5b$ must be greater than b.

14 If c is a number between 10 and 99, sort the following in ascending order (i.e. smallest to largest): $3c$, $2c$, $c - 4$, $c \div 2$, $3c + 5$, $4c - 2$, $c + 1$, $c \times c$.

ENRICHMENT

Many words compressed — | — | 15

15 One advantage of writing expressions in symbols rather than words is that it takes up less space. For instance, 'twice the value of the sum of x and 5' uses eight words and can be written as $2(x + 5)$. Give an example of a worded expression that uses more than 10 words and then write it as a mathematical expression.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5B Substituting and evaluating

Interactive

Widgets

HOTsheets

Walkthroughs

Evaluation of expressions involves replacing pronumerals (like x and y) with numbers and obtaining a single number as a result. For example, we can evaluate $4 + x$ when x is 11, to get 15.

Let's start: Sum to 10

The pronumerals x and y could stand for any number.

- What numbers could x and y stand for if you know that $x + y$ must equal 10? Try to list as many pairs as possible.
- If $x + y$ must equal 10, what values could $3x + y$ equal? Find the largest and smallest values.



Key ideas

- To **evaluate** an expression or to **substitute** values means to replace each pronumeral in an expression with a number to obtain a final value. For example, if $x = 3$ and $y = 8$, then $x + 2y$ evaluated gives $3 + 2 \times 8 = 19$.
- A term like $4a$ means $4 \times a$. When substituting a number we must include the multiplication sign, since two numbers written as 42 is very different from the product 4×2.
- Once an expression contains no pronumerals, evaluate using the normal order of operations seen in Chapter 1:
  - brackets
  - multiplication and division from left to right
  - addition and subtraction from left to right.

  For example: $(4 + 3) \times 2 - 20 \div 4 + 2 = 7 \times 2 - 20 \div 4 + 2$
  $= 14 - 5 + 2$
  $= 9 + 2$
  $= 11$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4 Substituting a pronumeral

Given that $t = 5$, evaluate:

a $t + 7$ **b** $8t$ **c** $\frac{10}{t} + 4 - t$

SOLUTION	EXPLANATION
a $t + 7 = 5 + 7$ $= 12$	Replace t with 5 and then evaluate the expression, which now contains no pronumerals.
b $8t = 8 \times t$ $= 8 \times 5$ $= 40$	Insert $\times$ where it was previously implied, then substitute in 5. If the multiplication sign is not included, we might get a completely incorrect answer of 85.
c $\frac{10}{t} + 4 - t = \frac{10}{5} + 4 - 5$ $= 2 + 4 - 5$ $= 1$	Replace all occurrences of t with 5 before evaluating. Note that the division $(10 \div 5)$ is calculated before the addition and subtraction.

Example 5 Substituting multiple pronumerals

Substitute $x = 4$ and $y = 7$ to evaluate these expressions.

a $5x + y + 8$ **b** $80 - (2xy + y)$

SOLUTION	EXPLANATION
a $5x + y + 8 = 5 \times x + y + 8$ $= 5 \times 4 + 7 + 8$ $= 20 + 7 + 8$ $= 35$	Insert the implied multiplication sign between 5 and x before substituting the values for x and y.
b $80 - (2xy + y) = 80 - (2 \times x \times y + y)$ $= 80 - (2 \times 4 \times 7 + 7)$ $= 80 - (56 + 7)$ $= 80 - 63$ $= 17$	Insert the multiplication signs, and remember the order in which to evaluate. Note that both occurrences of y are replaced with 7.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 6 Substituting with powers and roots

If $p = 4$ and $t = 5$, find the value of:

a $3p^2$ **b** $t^2 + p^3$ **c** $\sqrt{p^2 + 3^2}$

SOLUTION	EXPLANATION
a $3p^2 = 3 \times p \times p$ $= 3 \times 4 \times 4$ $= 48$	Note that $3p^2$ means $3 \times p \times p$ not $(3 \times p)^2$.
b $t^2 + p^3 = 5^2 + 4^3$ $= 5 \times 5 + 4 \times 4 \times 4$ $= 25 + 64$ $= 89$	t is replaced with 5, and p is replaced with 4. Remember that 4^3 means $4 \times 4 \times 4$.
c $\sqrt{p^2 + 3^2} = \sqrt{4^2 + 3^2}$ $= \sqrt{25}$ $= 5$	Recall that the square root of 25 must be 5 because $5 \times 5 = 25$.

Exercise 5B

1–5 | 2, 3 | —

UNDERSTANDING

1 Use the correct order of operations to evaluate the following.

a $4 + 2 \times 5$ **b** $7 - 3 \times 2$

c $3 \times 6 - 2 \times 4$ **d** $(7 - 3) \times 2$

Example 4a

2 What number would you get if you replaced b with 5 in the expression $8 + b$?

3 What number is obtained when $x = 3$ is substituted into the expression $5 \times x$?

4 What is the result of evaluating $10 - u$ if u is 7?

5 Calculate the value of $12 + b$ if:

a $b = 5$ **b** $b = 8$

c $b = 60$ **d** $b = 0$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5B

6–8(½), 9 | 6–7(½), 8, 9, 10(½) | 6–10(½)

FLUENCY

Example 4b,c

6 If $x = 5$, evaluate each of the following. Set out your solution in a manner similar to that shown in **Example 4**.

a $x + 3$
b $x \times 2$
c $14 - x$
d $2x + 4$
e $3x + 2 - x$
f $13 - 2x$
g $2(x + 2) + x$
h $30 - (4x + 1)$
i $\frac{20}{x} + 3$
j $(x + 5) \times \frac{10}{x}$
k $\frac{x + 7}{4}$
l $\frac{10 - x}{x}$
m $7x + 3(x - 1)$
n $40 - 3x - x$
o $x + x(x + 1)$
p $\frac{30}{x} + 2x(x + 3)$
q $100 - 4(3 + 4x)$
r $\frac{6(3x - 8)}{x + 2}$

Example 5

7 Substitute $a = 2$ and $b = 3$ into each of these expressions and evaluate.

a $2a + 4$
b $3a - 2$
c $a + b$
d $3a + b$
e $5a - 2b$
f $7ab + b$
g $ab - 4 + b$
h $2 \times (3a + 2b)$
i $100 - (10a + 10b)$
j $\frac{12}{a} + \frac{6}{b}$
k $\frac{ab}{3} + b$
l $\frac{100}{a + b}$

8 Evaluate the expression $5x + 2y$ when:

a $x = 3$ and $y = 6$
b $x = 4$ and $y = 1$
c $x = 7$ and $y = 3$
d $x = 0$ and $y = 4$
e $x = 2$ and $y = 0$
f $x = 10$ and $y = 10$

9 Copy and complete each of these tables.

a

n	1	2	3	4	5	6
$n + 4$	5			8		

b

x	1	2	3	4	5	6
$12 - x$			9			

c

b	1	2	3	4	5	6
$2(b - 1)$						

d

q	1	2	3	4	5	6
$10q - q$						

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5B

FLUENCY

Example 6

10 Evaluate each of the following, given that $a = 9, b = 3$ and $c = 5$.

a $3c^2$ **b** $5b^2$ **c** $a^2 - 3^3$ **d** $2b^2 + \frac{a}{3} - 2c$

e $\sqrt{a} + \sqrt{3ab}$ **f** $\sqrt{b^2 + 4^2}$ **g** $24 + \frac{2b^3}{6}$ **h** $(2c)^2 - a^2$

PROBLEM-SOLVING

11 | 11, 13 | 12, 13

11 A number is substituted for b in the expression $7 + b$ and gives the result 12. What is the value of b?

12 A number is substituted for x in the expression $3x - 1$. If the result is a two-digit number, what value might x have? Try to describe all the possible answers.

13 Copy and complete the table.

x	5	9	12			
$x + 6$	11			7		
$4x$	20				24	28

REASONING

14 | 14 | 14, 15

14 Assume x and y are two numbers, where $xy = 24$.

a What values could x and y equal if they are whole numbers? Try to list as many as possible.

b What values could x and y equal if they can be decimals, fractions or whole numbers?

15 Dugald substitutes different whole numbers into the expression $5 \times (a + a)$. He notices that the result always ends in the digit 0. Try a few values and explain why this pattern occurs.

ENRICHMENT

Missing numbers — | — | 16

16 a Copy and complete the following table. Note: x and y are whole numbers $(0, 1, 2, 3, \ldots)$ for this table.

x	5	10	7			
y	3	4		5		
$x + y$			9	14	7	
$x - y$	2				3	8
xy		40			10	0

b If x and y are two numbers where $x + y$ and $x \times y$ are equal, what values might x and y have? Try to find at least three (they do not have to be whole numbers).

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5C Equivalent expressions

Interactive

Widgets

HOTsheets

Walkthroughs

In algebra, as when using words, there are often many ways to express the same thing. For example, we can write 'the sum of x and 4' as $x + 4$ or $4 + x$, or even $x + 1 + 1 + 1 + 1$.

No matter what number x is, $x + 4$ and $4 + x$ will always be equal. We say that the expressions $x + 4$ and $4 + x$ are equivalent because of this.

By substituting different numbers for the pronumerals it is possible to see whether two expressions are equivalent. Consider the four expressions in this table.

	$3a + 5$	$2a + 6$	$7a + 5 - 4a$	$a + a + 6$
$a = 0$	5	6	5	6
$a = 1$	8	8	8	8
$a = 2$	11	10	11	10
$a = 3$	14	12	14	12
$a = 4$	17	14	17	14

From this table it becomes apparent that $3a + 5$ and $7a + 5 - 4a$ are equivalent, and that $2a + 6$ and $a + a + 6$ are equivalent.

Let's start: Equivalent expressions

Consider the expression $2a + 4$.

- Write as many different expressions as possible that are equivalent to $2a + 4$.
- How many equivalent expressions are there?
- Try to give a logical explanation for why $2a + 4$ is equivalent to $4 + a \times 2$.



This collection of pronumerals and numbers can be arranged into many different equivalent expressions.

Key ideas

- Two expressions are called **equivalent** when they are always equal, regardless of what numbers are substituted for the pronumerals.
  For example:
  - $x + 12$ is equivalent to $12 + x$, because the order in which numbers are added is not important.
  - $3k$ is equivalent to $k + k + k$, because multiplying by a whole number is the same as adding repeatedly.
- The rules of algebra are used to prove that two expressions are equivalent, but a table of values can be helpful to test whether expressions are likely to be equivalent.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 7 Equivalent expressions

Which two of these expressions are equivalent: $3x + 4$, $8 - x$, $2x + 4 + x$?

SOLUTION

$3x + 4$ and $2x + 4 + x$ are equivalent.

EXPLANATION

By drawing a table of values, we can see straight away that $3x + 4$ and $8 - x$ are not equivalent, since they differ for $x = 2$.

	$x = 1$	$x = 2$	$x = 3$
$3x + 4$	7	10	13
$8 - x$	7	6	5
$2x + 4 + x$	7	10	13

$3x + 4$ and $2x + 4 + x$ are equal for all values, so they are equivalent.

Exercise 5C

1, 2 | 2 | —

UNDERSTANDING

1 a Copy the following table into your workbook and complete.

	$x = 0$	$x = 1$	$x = 2$	$x = 3$
$2x + 2$				
$(x + 1) \times 2$				

b Fill in the gap: $2x + 2$ and $(x + 1) \times 2$ are _____ expressions.

2 a Copy the following table into your workbook and complete.

	$x = 0$	$x = 1$	$x = 2$	$x = 3$
$5x + 3$				
$6x + 3$				

b Are $5x + 3$ and $6x + 3$ equivalent expressions?

3, 4 | 3–5 | 3–5

FLUENCY

3 Demonstrate that $6x + 5$ and $4x + 5 + 2x$ are equivalent by completing the table.

	$6x + 5$	$4x + 5 + 2x$
$x = 1$		
$x = 2$		
$x = 3$		
$x = 4$		

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5C

Example 7

FLUENCY

4 For each of the following, choose a pair of equivalent expressions.

a $4x, 2x + 4, x + 4 + x$

b $5a, 4a + a, 3 + a$

c $2k + 2, 3 + 2k, 2(k + 1)$

d $b + b, 3b, 4b - 2b$

5 Match up the equivalent expressions below.


a $3x + 2x$	**A** $6 - 3x$
b $4 - 3x + 2$	**B** $2x + 4x + x$
c $2x + 5 + x$	**C** $5x$
d $x + x - 5 + x$	**D** $4 - x$
e $7x$	**E** $3x + 5$
f $4 - 3x + 2x$	**F** $3x - 5$

PROBLEM-SOLVING

6 | 6, 7 | 7, 8

6 Write two different expressions that are equivalent to $4x + 2$.

7 The rectangle shown below has a perimeter given by $w + l + w + l$. Write an equivalent expression for the perimeter.



8 There are many expressions that are equivalent to $3a + 5b + 2a - b + 4a$.
Write an equivalent expression with as few terms as possible.

REASONING

9 | 10, 11 | 10–12

9 The expressions $a + b$ and $b + a$ are equivalent and only contain two terms. How many expressions are equivalent to $a + b + c$ and contain only three terms?
Hint: Rearrange the pronumerals.

10 Prove that no two of these three expressions are equivalent: $4 + x, 4x, x - 4, x \div 4$.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5C

REASONING

11 Generalise each of the following patterns in numbers to give two equivalent expressions. The first one has been done for you.

- **a** Observation: $3 + 5 = 5 + 3$ and $2 + 7 = 7 + 2$ and $4 + 11 = 11 + 4$.
  Generalised: The two expressions $x + y$ and $y + x$ are equivalent.
- **b** Observation: $2 \times 5 = 5 \times 2$ and $11 \times 5 = 5 \times 11$ and $3 \times 12 = 12 \times 3$.
- **c** Observation: $4 \times (10 + 3) = 4 \times 10 + 4 \times 3$ and $8 \times (100 + 5) = 8 \times 100 + 8 \times 5$.
- **d** Observation: $100 - (4 + 6) = 100 - 4 - 6$ and $70 - (10 + 5) = 70 - 10 - 5$.
- **e** Observation: $20 - (4 - 2) = 20 - 4 + 2$ and $15 - (10 - 3) = 15 - 10 + 3$.
- **f** Observation: $100 \div 5 \div 10 = 100 \div (5 \times 10)$ and $30 \div 2 \div 3 = 30 \div (2 \times 3)$.

12 **a** Show that the expression $4 \times (a + 2)$ is equivalent to $8 + 4a$ using a table of values for a between 1 and 4.

- **b** Write an expression using brackets that is equivalent to $10 + 5a$.
- **c** Write an expression without brackets that is equivalent to $6 \times (4 + a)$.


Thinking about equivalence — — 13–14

ENRICHMENT

13 $3a + 5b$ is an expression containing two terms. List two expressions containing three terms that are equivalent to $3a + 5b$.

14 Three expressions are given: expression A, expression B and expression C.

- **a** If expressions A and B are equivalent, and expressions B and C are equivalent, does this mean that expressions A and C are equivalent? Try to prove your answer.
- **b** If expressions A and B are not equivalent, and expressions B and C are not equivalent, does this mean that expressions A and C are not equivalent? Try to prove your answer.



Each shape above is made from three identically-sized tiles of width w and length l. Which of the shapes have the same perimeter?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5D Like terms



Whenever we have terms with exactly the same pronumerals, they are called 'like terms' and can be collected and combined. For example, $3x + 5x$ can be simplified to $8x$. If the two terms do not have exactly the same pronumerals, they must be kept separate; for example, $3x + 5y$ cannot be simplified – it must be left as it is.



Recall from arithmetic that numbers can be multiplied in any order (e.g. $5 \times 3 = 3 \times 5$). This means pronumerals can appear in a different order within a term and give equivalent expressions (e.g. ab and ba are equivalent).





Let's start: Simplifying expressions

- Try to find a simpler expression that is equivalent to

$$1a + 2b + 3a + 4b + 5a + 6b + \ldots + 19a + 20b$$

- What is the longest possible expression that is equivalent to $10a + 20b + 30c$? Assume that all coefficients must be whole numbers greater than zero.
- Compare your expressions to see who has the longest one.

Key ideas

- **Like terms** are terms containing exactly the same pronumerals, although not necessarily in the same order.
  - $5ab$ and $3ab$ are like terms.
  - $4a$ and $7b$ are not like terms.
  - $2acb$ and $4bac$ are like terms.
- Like terms can be combined within an expression to create a simpler expression that is equivalent. For example, $5ab + 3ab$ can be simplified to $8ab$.
- If two terms are not like terms (such as $4x$ and $5y$), they can still be added to get an expression like $4x + 5y$, but this expression cannot be simplified further.



Example 8 Identifying like terms

Which of the following pairs are like terms?

a $3x$ and $2x$ **b** $3a$ and $3b$ **c** $2ab$ and $5ba$

d $4k$ and k **e** $2a$ and $4ab$ **f** $7ab$ and $9aba$

SOLUTION	EXPLANATION
a $3x$ and $2x$ are like terms.	The pronumerals are the same.
b $3a$ and $3b$ are not like terms.	The pronumerals are different.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c	$2ab$ and $5ba$ are like terms.	The pronumerals are the same, even though they are written in a different order (one a and one b).
d	$4k$ and k are like terms.	The pronumerals are the same.
e	$2a$ and $4ab$ are not like terms.	The pronumerals are not exactly the same (the first term contains only a and the second term has a and b).
f	$7ab$ and $9aba$ are not like terms.	The pronumerals are not exactly the same (the first term contains one a and one b, but the second term contains two copies of a and one b).



Example 9 Simplifying using like terms

Simplify the following by collecting like terms.

a $7b + 2 + 3b$

b $12d - 4d + d$

c $5 + 12a + 4b - 2 - 3a$

d $13a + 8b + 2a - 5b - 4a$

e $12uv + 7v - 3vu + 3v$

SOLUTION	EXPLANATION
a $7b + 2 + 3b = 10b + 2$	$7b$ and $3b$ are like terms, so they are added. They cannot be combined with the term 2 because it is not 'like' $7b$ or $3b$.
b $12d - 4d + d = 9d$	All the terms here are like terms. Remember that d means $1d$ when combining them.
c $5 + 12a + 4b - 2 - 3a$ $= 12a - 3a + 4b + 5 - 2$ $= 9a + 4b + 3$	$12a$ and $3a$ are like terms. We subtract $3a$ because it has a minus sign in front of it. We can also combine the 5 and the 2 because they are like terms.
d $13a + 8b + 2a - 5b - 4a$ $= 13a + 2a - 4a + 8b - 5b$ $= 11a + 3b$	Combine like terms, remembering to subtract any term that has a minus sign in front of it.
e $12uv + 7v - 3vu + 3v$ $= 12uv - 3vu + 7v + 3v$ $= 9uv + 10v$	Combine like terms. Remember that $12uv$ and $3vu$ are like terms (i.e. they have the same pronumerals), so $12uv - 3uv = 9uv$.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 5D

1, 2 | 2 | —

UNDERSTANDING

1 For each of the following terms, state all the pronumerals that occur in it.

a $4xy$ **b** $3abc$ **c** $2k$ **d** pq

2 Copy the following sentences into your workbook and fill in the gaps to make the sentences true. More than one answer might be possible.

a $3x$ and $5x$ are _____ terms.

b $4x$ and $3y$ are not _____ _____.

c $4xy$ and $4yx$ are like _____.

d $4a$ and _____ are like terms.

e $x + x + 7$ and $2x + 7$ are _____ expressions.

f $3x + 2x + 4$ can be written in an equivalent way as _____.

3–5(½) | 3–5(½) | 3–5(½)

FLUENCY

Example 8

3 Classify the following pairs as like terms (L) or not like terms (N).

a $7a$ and $4b$ **b** $3a$ and $10a$ **c** $18x$ and $32x$ **d** $4a$ and $4b$

e 7 and $10b$ **f** x and $4x$ **g** $5x$ and 5 **h** $12ab$ and $4ab$

i $7cd$ and $12cd$ **j** $3abc$ and $12abc$ **k** $3ab$ and $2ba$ **l** $4cd$ and $3dce$

4 Simplify the following by collecting like terms.

a $a + a$ **b** $3x + 2x$ **c** $4b + 3b$ **d** $12d - 4d$

e $15u - 3u$ **f** $14ab - 2ab$ **g** $8ab + 3ab$ **h** $4xy - 3xy$

Example 9

5 Simplify the following by collecting like terms.

a $2a + a + 4b + b$ **b** $5a + 2a + b + 8b$ **c** $3x - 2x + 2y + 4y$

d $4a + 2 + 3a$ **e** $7 + 2b + 5b$ **f** $3k - 2 + 3k$

g $7f + 4 - 2f + 8$ **h** $4a - 4 + 5b + b$ **i** $3x + 7x + 3y - 4x + y$

j $10a + 3 + 4b - 2a$ **k** $4 + 10h - 3h$ **l** $10x + 4x + 31y - y$

m $10 + 7y - 3x + 5x + 2y$ **n** $11a + 4 - 3a + 9$ **o** $3b + 4b + c + 5b - c$

p $7ab + 4 + 2ab$ **q** $9xy + 2x - 3xy + 3x$ **r** $2cd + 5dc - 3d + 2c$

s $5uv + 12v + 4uv - 5v$ **t** $7pq + 2p + 4qp - q$ **u** $7ab + 32 - ab + 4$

6, 7 | 7, 8 | 7, 8, 9(½)

PROBLEM-SOLVING

6 Ravi and Marissa each work for n hours per week. Ravi earns \$27 per hour and Marissa earns \$31 per hour.

a Write an expression for the amount Ravi earns in one week (in dollars).

b Write an expression for the amount Marissa earns in one week (in dollars).

c Write a simplified expression for the total amount Ravi and Marissa earn in one week (in dollars).

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5D

PROBLEM-SOLVING

7 The length of the line segment shown could be expressed as $a + a + 3 + a + 1$.



a Write the length in the simplest form.
b What is the length of the segment if a is equal to 5?

8 Let x represent the number of marbles in a standard-sized bag. Xavier bought 4 bags and Cameron bought 7 bags. Write simplified expressions for:



a the number of marbles Xavier has
b the number of marbles Cameron has
c the total number of marbles that Xavier and Cameron have
d the number of *extra* marbles that Cameron has compared to Xavier

9 Simplify the following by collecting like terms.

a $3xy + 4xy + 5xy$	**b** $4ab + 5 + 2ab$	**c** $5ab + 3ba + 2ab$
d $10xy - 4yx + 3$	**e** $10 - 3xy + 8xy + 4$	**f** $3cde + 5ecd + 2ced$
g $4 + x + 4xy + 2xy + 5x$	**h** $12ab + 7 - 3ab + 2$	**i** $3xy - 2y + 4yx$

	10	10	11

REASONING

10 **a** Test, using a table of values, that $3x + 2x$ is equivalent to $5x$.
b Prove that $3x + 2y$ is not equivalent to $5xy$.

11 **a** Test that $5x + 4 - 2x$ is equivalent to $3x + 4$.
b Prove that $5x + 4 - 2x$ is not equivalent to $7x + 4$.
c Prove that $5x + 4 - 2x$ is not equivalent to $7x - 4$.

How many rearrangements?	—	—	12

ENRICHMENT

12 The expression $a + 3b + 2a$ is equivalent to $3a + 3b$.

a List two other expressions with three terms that are equivalent to $3a + 3b$.
b How many expressions, consisting of exactly three terms added together, are equivalent to $3a + 3b$? All coefficients must be whole numbers greater than 0.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

5A **1** For the expression $7a + 4b + c + 9$, answer the following.

- **a** State the number of terms.
- **b** List the individual terms.
- **c** State the coefficient of b.
- **d** What is the constant term?

5A **2** Write an expression for each of the following.

- **a** the product of m and p
- **b** the sum of a and k
- **c** 8 more than t
- **d** 4 less than w

5A **3** Write an expression for each of the following without using the $\div$ or $\times$ symbols.

- **a** m is halved, then 7 is added.
- **b** 7 is added to m and then the result is halved.
- **c** The sum of a and k is taken and then divided by 3.
- **d** The sum of a and one-third of k.
- **e** 12 is subtracted from d and the result is tripled.
- **f** d is tripled and 12 is subtracted from the result.

5B **4** If $x = 4$, evaluate each of the following.

- **a** $3x + 7$
- **b** $\frac{20}{x} + 2 - x$
- **c** $18 - (2x + 1)$

5B **5** Substitute $a = 5$ and $b = 2$ into each of these expressions and evaluate.

- **a** $3a + b + 7$
- **b** $20 - (a + 2b)$
- **c** $\frac{35}{a + b}$
- **d** $5 + a^2 - 2b^2$
- **e** $\sqrt{a^2 - 16}$

5C **6** Which two of the following expressions are equivalent?
$3a + 4$, $4a + 3$, $4 + 3a$, $7a$

5D **7** Classify the following pairs as like terms (L) or not like terms (N).

- **a** $3a$ and $8a$
- **b** $3x$ and $3xy$
- **c** 6 and $6a$
- **d** $4mp$ and $5pm$

5D **8** Simplify the following by collecting like terms.

- **a** $7a + 2b + 5 + a + 3b$
- **b** $2cd + 4c + 8d + 5dc - c + 4$

5C **9** Archie has two part-time jobs each paying \$8 per hour. He works x hours at one job and y hours at the other. Write two equivalent expressions for the total amount of money, in dollars, that he earns.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5E Multiplying and dividing expressions



To multiply a number by a pronumeral, we have already seen we can write them next to each other. For example, $7a$ means $7 \times a$, and $5abc$ means $5 \times a \times b \times c$. The order in which numbers or pronumerals are multiplied is unimportant, so $5 \times a \times b \times c = a \times 5 \times c \times b = c \times a \times 5 \times b$. When writing a product without $\times$ signs, the numbers are written first.



We write $\frac{7xy}{3xz}$ as shorthand for $(7xy) \div (3xz)$.



We can simplify fractions like $\frac{10}{15}$ by dividing by common factors such as $\frac{10}{15} = \frac{\cancel{5} \times 2}{\cancel{5} \times 3} = \frac{2}{3}$.



Similarly, common pronumerals can be cancelled in a division like $\frac{7xy}{3xz}$, giving $\frac{7\cancel{x}y}{3\cancel{x}\cancel{z}} = \frac{7y}{3z}$.

Let's start: Rearranging terms

$5abc$ is equivalent to $5bac$ because the order of multiplication does not matter. In what other ways could $5abc$ be written?

$5 \times a \times b \times c = ?$



- $a \times b$ is written as ab.
- $a \div b$ is written as $\frac{a}{b}$.
- $a \times a$ is written as a^2.
- Because of the commutative property of multiplication (e.g. $2 \times 7 = 7 \times 2$), the order in which values are multiplied is not important. So $3 \times a$ and $a \times 3$ are equivalent.
- Because of the associative property of multiplication (e.g. $3 \times (5 \times 2)$ and $(3 \times 5) \times 2$ are equal), brackets are not required when only multiplication is used. So $3 \times (a \times b)$ and $(3 \times a) \times b$ are both written as $3ab$.
- Numbers should be written first in a term and pronumerals are generally written in alphabetical order. For example, $b \times 2 \times a$ is written as $2ab$.
- When dividing, any common factor in the numerator and denominator can be cancelled.
  For example: $\frac{{}^{2}\cancel{4}a^{1}\cancel{b}}{{}_{1}\cancel{2}^{1}\cancel{b}c} = \frac{2a}{c}$



Example 10 Simplifying expressions with multiplication

a Write $4 \times a \times b \times c$ without multiplication signs.

b Simplify $4a \times 2b \times 3c$, giving your final answer without multiplication signs.

c Simplify $3w \times 4w$.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
a $4 \times a \times b \times c = 4abc$	When pronumerals are written next to each other they are being multiplied.
b $4a \times 2b \times 3c = 4 \times a \times 2 \times b \times 3 \times c$ $= 4 \times 2 \times 3 \times a \times b \times c$ $= 24abc$	First insert the missing multiplication signs. Rearrange to bring the numbers to the front. $4 \times 2 \times 3 = 24$ and $a \times b \times c = abc$, giving the final answer.
c $3w \times 4w = 3 \times w \times 4 \times w$ $= 3 \times 4 \times w \times w$ $= 12w^2$	First insert the missing multiplication signs. Rearrange to bring the numbers to the front. $3 \times 4 = 12$ and $w \times w$ is written as w^2.



Example 11 Simplifying expressions with division

a Write $(3x + 1) \div 5$ without a division sign.

b Simplify the expression $\frac{8ab}{12b}$.

SOLUTION	EXPLANATION
a $(3x + 1) \div 5 = \frac{3x + 1}{5}$	The brackets are no longer required as it becomes clear that all of $3x + 1$ is being divided by 5.
b $\frac{8ab}{12b} = \frac{8 \times a \times b}{12 \times b}$ $= \frac{2 \times \cancel{4} \times a \times \cancel{b}}{3 \times \cancel{4} \times \cancel{b}}$ $= \frac{2a}{3}$	Insert multiplication signs to help spot common factors. 8 and 12 have a common factor of 4. Cancel out the common factors of 4 and b.

Exercise 5E

1–4 | 3, 4 | —

UNDERSTANDING

1 Chen claims that $7 \times d$ is equivalent to $d \times 7$.

a If $d = 3$, find the values of $7 \times d$ and $d \times 7$.

b If $d = 5$, find the values of $7 \times d$ and $d \times 7$.

c If $d = 8$, find the values of $7 \times d$ and $d \times 7$.

d Is Chen correct in his claim?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5E

UNDERSTANDING

2 Classify each of the following statements as true or false.

a $4 \times n$ can be written as $4n$.
b $n \times 3$ can be written as $3n$.
c $4 \times b$ can be written as $b + 4$.
d $a \times b$ can be written as ab.
e $a \times 5$ can be written as $50a$.
f $a \times a$ can be written as $2a$.

3 **a** Simplify the fraction $\frac{12}{18}$. (Note: This is the same as $\frac{2 \times 6}{3 \times 6}$.)

b Simplify the fraction $\frac{2000}{3000}$. (Note: This is the same as $\frac{2 \times 1000}{3 \times 1000}$.)

c Simplify $\frac{2a}{3a}$. (Note: This is the same as $\frac{2 \times a}{3 \times a}$.)

4 Match up these expressions with the correct way to write them.

a $2 \times u$	**A** $3u$
b $7 \times u$	**B** $\frac{5}{u}$
c $5 \div u$	**C** $2u$
d $u \times 3$	**D** $\frac{u}{5}$
e $u \div 5$	**E** $7u$

5–8(½) 5–8(½) 5–8(½)

FLUENCY

Example 10a

5 Write each of these expressions without any multiplication signs.

a $2 \times x$	**b** $5 \times p$	**c** $8 \times a \times b$
d $3 \times 2 \times a$	**e** $7 \times 4 \times f$	**f** $5 \times 2 \times a \times b$
g $2 \times 8 \times x \times y$	**h** $2 \times b \times 5$	**i** $x \times 7 \times z \times 4$

Example 10b,c

6 Simplify these expressions.

a $3a \times 12$	**b** $7d \times 9$	**c** $2 \times 4e$
d $3 \times 5a$	**e** $4a \times 3b$	**f** $7e \times 9g$
g $8a \times bc$	**h** $4d \times 7af$	**i** $a \times 3b \times 4c$
j $2a \times 4b \times c$	**k** $4d \times 3e \times 5fg$	**l** $2cb \times 3a \times 4d$
m $w \times w$	**n** $a \times a$	**o** $3d \times d$
p $2k \times k$	**q** $p \times 7p$	**r** $q \times 3q$
s $6x \times 2x$	**t** $3z \times 5z$	**u** $9r \times 4r$

Example 11a

7 Write each expression without a division sign.

a $x \div 5$	**b** $z \div 2$	**c** $a \div 12$
d $b \div 5$	**e** $2 \div x$	**f** $5 \div d$
g $x \div y$	**h** $a \div b$	**i** $(4x + 1) \div 5$
j $(2x + y) \div 5$	**k** $(2 + x) \div (1 + y)$	**l** $(x - 5) \div (3 + b)$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5E

Example 11b

FLUENCY

8 Simplify the following expressions by dividing by any common factors. Remember that $\frac{a}{1} = a$.

a $\frac{2x}{5x}$ **b** $\frac{5a}{9a}$ **c** $\frac{9ab}{4b}$ **d** $\frac{2ab}{5a}$

e $\frac{2x}{4}$ **f** $\frac{9x}{12}$ **g** $\frac{10a}{15a}$ **h** $\frac{30y}{40y}$


i $\frac{4a}{2}$ **j** $\frac{21x}{7x}$ **k** $\frac{4xy}{2x}$ **l** $\frac{9x}{3xy}$

9, 10 | 10, 12 | 10–12


PROBLEM-SOLVING

9 Write a simplified expression for the area of the following rectangles. Recall that for rectangles, *Area* = *width* × *length*.


a



b



c



10 The weight of a single muesli bar is x grams.



a What is the weight of 4 bars? Write an expression.

b If Jamila buys n bars, what is the total weight of her purchase?

c Jamila's cousin Roland buys twice as many bars as Jamila. What is the total weight of Roland's purchase?

11 Five friends go to a restaurant. They split the bill evenly, so each spends the same amount.

a If the total cost is \$100, how much do they each spend?

b If the total cost is \$$C$, how much do they each spend? Write an expression.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

5E

PROBLEM-SOLVING

12 Replace the question marks with algebraic terms to make these equivalence statements true.

a $4c \times ? \times b = 12abc$

b $2a \times 2b \times ? = 28abc$

c $\frac{14ab}{?} = 2a$

d $\frac{12xy}{?} = x$

e $\frac{50x}{?} \times y = 5y$

13 | 13, 14 | 13, 14


REASONING

13 The expression $3 \times 2p$ is the same as the expression $\underset{(1)}{2p} + \underset{(2)}{2p} + \underset{(3)}{2p}$.

a What is a simpler expression for $2p + 2p + 2p$? Hint: Combine like terms.

b $3 \times 2p$ is shorthand for $3 \times 2 \times p$. How does this relate to your answer in part **a**?

14 The area of the rectangle shown is $3a$. The length and width of this rectangle are now doubled.



a Draw the new rectangle, showing its dimensions.

b Write a simplified expression for the area of the new rectangle.

c Divide the area of the new rectangle by the area of the old rectangle. What do you notice?

d What happens to the area of the original rectangle if you triple both the length and the width?

Managing powers | — | — | 15

ENRICHMENT

15 The expression $a \times a$ can be written as a^2 and the expression $a \times a \times a$ can be written as a^3.

a What is $3a^2b^2$ when written in full with multiplication signs?

b Write $7 \times x \times x \times y \times y \times y$ without any multiplication signs.

c Simplify $2a \times 3b \times 4c \times 5a \times b \times 10c \times a$.

d Simplify $4a^2 \times 3ab^2 \times 2c^2$.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

5F Expanding brackets EXTENDING

Interactive

We have already seen that there are different ways of writing two equivalent expressions. For example, $4a + 2a$ is equivalent to $2 \times 3a$, even though they look different.

Note that $3(7 + a) = 3 \times (7 + a)$, which is equivalent to 3 lots of $7 + a$.

Widgets

So, $3(7 + a) = 7 + a + 7 + a + 7 + a$

$= 21 + 3a$


HOTsheets

It is sometimes useful to have an expression that is written with brackets, like $3 \times (7 + a)$, and sometimes it is useful to have an expression that is written without brackets, like $21 + 3a$.

Walkthroughs

Let's start: Total area

What is the total area of the rectangle shown at right? Try to write two expressions, only one of which includes brackets.



Key ideas

- **Expanding** (or **eliminating**) brackets involves writing an equivalent expression without brackets. This can be done by writing the bracketed portion a number of times or by multiplying each term.

  $2(a + b) = a + b + a + b$ or $2(a + b) = 2 \times a + 2 \times b$

  $= 2a + 2b$ $= 2a + 2b$

- To eliminate brackets, you can use the **distributive law**, which states that:

  $a(b + c) = ab + ac$ and $a(b - c) = ab - ac$

- The distributive law is used in arithmetic. For example:

$$\begin{aligned} 5 \times 27 &= 5(20 + 7) \\ &= 5 \times 20 + 5 \times 7 \\ &= 100 + 35 \\ &= 135 \end{aligned}$$

- The process of removing brackets using the distributive law is called **expansion**.
- When expanding, every term inside the brackets must be multiplied by the term outside the brackets.



Many of the simpler expressions in algebra can be thought of in terms of the areas of rectangles.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Expanding brackets by simplifying repeated terms

Repeat the expression that is inside the brackets and then collect like terms. The number outside the brackets is the number of copies required.


a $2(a + k)$ **b** $3(2m + 5)$

SOLUTION	EXPLANATION
a $2(a + k) = a + k + a + k$ $= 2a + 2k$	Two copies of the expression $a + k$. Simplify by collecting the like terms.
b $3(2m + 5) = 2m + 5 + 2m + 5 + 2m + 5$ $= 6m + 15$	Three copies of the expression $2m + 5$. Simplify by collecting the like terms.


Example 13 Expanding brackets using rectangle areas

Write two equivalent expressions for the area of each rectangle shown, only one of which includes brackets.


a



b



c



SOLUTION	EXPLANATION
a Using brackets: $2(5 + x)$	The whole rectangle has height 2 and width $5 + x$.
Without brackets: $10 + 2x$	The smaller rectangles have area $2 \times 5 = 10$ and $2 \times x = 2x$, so they are added.
b Using brackets: $12(a + 3)$	The dimensions of the whole rectangle are 12 and $a + 3$. Note that, by convention, we do not write $(a + 3)12$.
Without brackets: $12a + 36$	The smaller rectangles have area $12 \times a = 12a$ and $12 \times 3 = 36$.
c Using brackets: $(a + 7)(b + 2)$	The whole rectangle has height $a + 7$ and width $b + 2$. Note that brackets are used to ensure we are multiplying the entire height by the entire width.
Without brackets: $ab + 2a + 7b + 14$	The diagram can be split into four rectangles, with areas ab, $2a$, $7b$ and 14.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 14 Expanding using the distributive law

Expand the following expressions.

a $5(x + 3)$ **b** $8(a - 4)$

c $3(a + 2b)$ **d** $5a(3p - 7q)$

SOLUTION	EXPLANATION
a $5(x + 3) = 5 \times x + 5 \times 3$	Use the distributive law: $5(x + 3) = 5x + 5 \times 3$
$= 5x + 15$	Simplify the result.
b $8(a - 4) = 8 \times a - 8 \times 4$	Use the distributive law with subtraction:
$= 8a - 32$	$8(a - 4) = 8a - 8 \times 4$
	Simplify the result.
c $3(a + 2b) = 3 \times a + 3 \times 2b$	Use the distributive law:
$= 3a + 6b$	$3(a + 2b) = 3a + 3 \times 2b$
	Simplify the result, remembering that $3 \times 2b = 6b$.
d $5a(3p - 7q) = 5a \times 3p - 5a \times 7q$	Expanding: $5a(3p - 7q) = 5a \times 3p - 5a \times 7q$
$= 15ap - 35aq$	Simplify the result, remembering that $5a \times 3p = 15ap$ and $5a \times 7q = 35aq$.

Exercise 5F

1–4 | 2, 3 | —

UNDERSTANDING

Example 12

1 The expression $3(a + 2)$ can be written as $(a + 2) + (a + 2) + (a + 2)$.


a Simplify this expression by collecting like terms.

b Write $2(x + y)$ in full without brackets and simplify the result.

c Write $4(p + 1)$ in full without brackets and simplify the result.

d Write $3(4a + 2b)$ in full without brackets and simplify the result.

2 The area of the rectangle shown can be written as $4(x + 3)$.



a What is the area of the green rectangle?

b What is the area of the red rectangle?

c Write the total area as an expression, without using brackets.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5F

UNDERSTANDING

3 Copy and complete the following calculation using the distributive law.

a $3 \times 21 = 3 \times (20 + 1)$
$= 3 \times 20 + 3 \times 1$
$= ____ + ____$
$= ____$

b $7 \times 34 = 7 \times (30 + 4)$
$= 7 \times __ + 7 \times __$
$= ____ + ____$
$= ____$

c $5 \times 19 = 5 \times (20 - 1)$
$= 5 \times __ - 5 \times __$
$= ____ - ____$
$= ____$

4 a Copy and complete the following table. Remember to follow the rules for correct order of operations.

	$4(x + 3)$	$4x + 12$
$x = 1$	$= 4(1 + 3)$ $= 4(4)$ $= 16$	$= 4(1) + 12$ $= 4 + 12$ $= 16$
$x = 2$		
$x = 3$		
$x = 4$		

b Fill in the gap: The expressions $4(x + 3)$ and $4x + 12$ are _____.


5, 6–8(½) 5, 6–8(½) 5, 6–8(½)

FLUENCY


Example 13

5 For the following rectangles, write two equivalent expressions for the area.


a



b



c



Example 14a,b

6 Use the distributive law to expand the following.

a $6(y + 8)$	**b** $7(l + 4)$	**c** $8(s + 7)$	**d** $4(2 + a)$
e $7(x + 5)$	**f** $3(6 + a)$	**g** $9(9 - x)$	**h** $5(j - 4)$
i $8(y - 8)$	**j** $8(e - 7)$	**k** $6(e - 3)$	**l** $10(8 - y)$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5F

FLUENCY

Example 14c

7 Use the distributive law to expand the following.

a $10(6g - 7)$	**b** $5(3e + 8)$	**c** $5(7w + 10)$	**d** $5(2u + 5)$
e $7(8x - 2)$	**f** $3(9v - 4)$	**g** $7(q - 7)$	**h** $4(5c - v)$
i $2(2u + 6)$	**j** $6(8l + 8)$	**k** $5(k - 10)$	**l** $9(o + 7)$

Example 14d

8 Use the distributive law to expand the following.

a $6i(t - v)$	**b** $2d(v + m)$	**c** $5c(2w - t)$	**d** $6e(s + p)$
e $d(x + 9s)$	**f** $5a(2x + 3v)$	**g** $5j(r + 7p)$	**h** $i(n + 4w)$
i $8d(s - 3t)$	**j** $f(2u + v)$	**k** $7k(2v + 5y)$	**l** $4e(m + 10y)$

9, 10 | 10, 11 | 10–12

PROBLEM-SOLVING

9 Write an expression for each of the following and then expand it.

a A number, x, has 3 added to it and the result is multiplied by 5.

b A number, b, has 6 added to it and the result is doubled.

c A number, z, has 4 subtracted from it and the result is multiplied by 3.

d A number, y, is subtracted from 10 and the result is multiplied by 7.

10 In a school classroom there is one teacher as well as an unknown number of boys and girls.

a If the number of boys is b and the number of girls is g, write an expression for the total number of people in the classroom, including the teacher.

b The teacher and all the students are each wearing two socks. Write two different expressions for the total number of socks being worn, one with brackets and one without.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5F

PROBLEM-SOLVING

11 When expanded, $4(3x + 6y)$ gives $12x + 24y$. Find two other expressions that expand to $12x + 24y$.

12 The distance around a rectangle is given by the expression $2(l + w)$, where l is the length and w is the width. What is an equivalent expression for this distance?

	13	13, 14	14, 15

REASONING

13 Use a diagram of a rectangle like that in Question **2** to demonstrate that $5(x + 3) = 5x + 15$.

14 Use a diagram of a rectangle to prove that $(a + 2)(b + 3) = ab + 2b + 3a + 6$.

15 When expanded, $5(2x + 4y)$ gives $10x + 20y$.

a How many different ways can the missing numbers be filled with whole numbers for the equivalence $\square(\square x + \square y) = 10x + 20y$?

b How many different expressions expand to give $10x + 20y$ if fractions or decimals are included?

Expanding sentences	—	—	16

ENRICHMENT

16 Using words, people do a form of expansion. Consider these two statements:

Statement A: 'John likes tennis and football.'

Statement B: 'John likes tennis and John likes football.'

Statement B is an 'expanded form' of statement A, which is equivalent in its meaning but more clearly shows that two facts are being communicated. Write an 'expanded form' of the following sentences.

a Rosemary likes Maths and English.

b Priscilla eats fruit and vegetables.

c Bailey and Lucia like the opera.

d Frank and Igor play video games.

e Pyodir and Astrid like fruit and vegetables.

(Note: There are four facts being communicated here.)



Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5G Algebraic modelling EXTENDING


Interactive

Widgets

HOTsheets

Walkthroughs


An algebraic expression can be used to describe problems relating to many different areas, including costs, speeds and sporting results. Much of modern science relies on the application of algebraic rules and formulas. It is important to be able to convert word descriptions of problems to mathematical expressions in order to solve these problems mathematically.



In many sports, results and details can be expressed using algebra.

Let's start: Garden bed area

The garden shown at right has an area of 34 m^2, but the width and length are unknown.



- What are some possible values that w and l could equal?
- Try to find the dimensions of the garden that make the fencing around the outside as small as possible.

Key ideas

- Many different situations can be modelled with algebraic expressions.
- To apply an expression, the pronumerals should be defined clearly. Then known values should be substituted for the pronumerals.

Example 15 Applying an expression

The perimeter of a rectangle is given by the expression $2w + 2l$, where w is the width and l is the height.

a Find the perimeter of a rectangle if $w = 5$ and $l = 7$.

b Find the perimeter of a rectangle with width 8 cm and length 3 cm.

SOLUTION	EXPLANATION
a $2w + 2l = 2(5) + 2(7)$ $= 10 + 14$ $= 24$	To apply the rule, we substitute $w = 5$ and $l = 7$ into the expression. Evaluate using the normal rules of arithmetic (i.e. multiplication before addition).
b $2w + 2h = 2(8) + 2(3)$ $= 16 + 6$ $= 22$ cm	Substitute $w = 8$ and $h = 3$ into the expression. Evaluate using the normal rules of arithmetic, remembering to include appropriate units (cm) in the answer.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 16 Constructing expressions from problem descriptions

Write expressions for each of the following.

a The total cost, in dollars, of 10 bottles, if each bottle costs $\$x$.

b The total cost, in dollars, of hiring a plumber for n hours. The plumber charges a \$30 call-out fee plus \$60 per hour.

c A plumber charges a \$60 call-out fee plus \$50 per hour. Use an expression to find how much an 8-hour job would cost.

SOLUTION	EXPLANATION
a $10x$	Each of the 10 bottles costs $\$x$, so the total cost is $10 \times x = 10x$.
b $30 + 60n$	For each hour, the plumber charges \$60, so must pay $60 \times n = 60n$. The \$30 call-out fee is added to the total bill.
c Expression for cost: $60 + 50n$ If $n = 8$, then cost is $60 + 50 \times 8 = \$460$	Substitute $n = 8$ to find the cost for an 8-hour job. Cost will be \$460.

Exercise 5G

1–3 | 3 | —

UNDERSTANDING

1 The area of a rectangle is given by the expression $w \times l$, where w is its width and l is its length.

a Find the area if $w = 5$ and $l = 7$.

b Find the area if $w = 2$ and $l = 10$.

2 The perimeter of a square with width w is given by the expression $4w$.


a Find the perimeter of a square with width 6 cm (i.e. $w = 6$).

b Find the perimeter of a square with width 10 m (i.e. $w = 10$).

3 Consider the equilateral triangle shown.

a Write an expression that gives the perimeter of this triangle.

b Use your expression to find the perimeter if $x = 12$.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5G

4–7 4–8 5–8

FLUENCY

Example 16a

4 If pens cost \$2 each, write an expression for the cost, in dollars, of n pens.

5 If pencils cost \$$x$ each, write an expression for the cost, in dollars, of:

a 10 pencils

b 3 packets of pencils, if each packet contains 5 pencils

c k pencils



6 A car travels at 60 km/h, so in n hours it has travelled $60n$ kilometres.

a How far does the car travel in 3 hours (i.e. $n = 3$)?

b How far does the car travel in 30 minutes?

c Write an expression for the total distance (in km) travelled in n hours for a motorbike with speed 70 km/h.



7 A carpenter charges a \$40 call-out fee and then \$80 per hour. This means the total cost, in dollars, for x hours of work is $40 + 80x$.

a How much would it cost for a 2-hour job (i.e. $x = 2$)?

b How much would it cost for a job that takes 8 hours?

c The call-out fee is increased to \$50. What is the new expression for the total cost, in dollars, of x hours?

Example 16b

8 Match up the word problems with the expressions (**A** to **E**) below.

a The area of a rectangle with height 5 and width x.

b The perimeter of a rectangle with height 5 and width x.

c The total cost, in dollars, of hiring a DVD for x days if the price is \$1 per day.

d The total cost, in dollars, of hiring a builder for 5 hours if the builder charges a \$10 call-out fee and then \$$x$ per hour.

e The total cost, in dollars, of buying a \$5 magazine and a book that costs \$$x$.

A $10 + 2x$

B $5x$

C $5 + x$

D x

E $10 + 5x$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9, 10 | 10–12 | 11–13

5G

PROBLEM-SOLVING

9 A plumber charges a $50 call-out fee and $100 per hour.



a Copy and complete the table below.

Number of hours	1	2	3	4	5
Total costs ($)					

b Find the total cost if the plumber works for t hours. Give an expression.

c Substitute $t = 30$ into your expression to find how much it will cost for the plumber to work 30 hours.

10 To hire a tennis court, you must pay a $5 booking fee plus $10 per hour.

a What is the cost of booking a court for 2 hours?

b What is the cost of booking a court for x hours? Write an expression.

c A tennis coach hires a court for 7 hours. Substitute $x = 7$ into your expression to find the total cost.

11 Adrian's mobile phone costs 30 cents to make a connection, plus 60 cents per minute of talking. This means that a t-minute call costs $30 + 60t$ cents.

a What is the cost of a 1-minute call?

b What is the cost of a 10-minute call? Give your answer in dollars.

c Write an expression for the cost of a t-minute call in dollars.

12 In Australian Rules football a goal is worth 6 points and a 'behind' is worth 1 point. This means the total score for a team is $6g + b$, if g goals and b behinds are scored.



a What is the score for a team that has scored 5 goals and 3 behinds?

b What are the values of g and b for a team that has scored 8 goals and 5 behinds?

c If a team has a score of 20, this could be because $g = 2$ and $b = 8$. What are the other possible values of g and b?

13 In a closing-down sale, a shop sells all CDs for $\$c$ each, books cost $\$b$ each and DVDs cost $\$d$ each. Claudia buys 5 books, 2 CDs and 6 DVDs.

a What is the cost of Claudia's order? Give your answer as an expression involving b, c and d.

b Write an expression for the cost of Claudia's order if CDs doubled in price and DVDs halved in price.

c As it happens, the total price Claudia ends up paying is the same in both situations. Given that CDs cost $12 and books cost $20 (so $c = 12$ and $b = 20$), how much do DVDs cost?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5G

14 | 14 | 14, 15

REASONING

14 A shop charges $\$c$ for a box of tissues.

- **a** Write an expression for the total cost, in dollars, of buying n boxes of tissues.
- **b** If the original price is tripled, write an expression for the total cost, in dollars, of buying n boxes of tissues.
- **c** If the original price is tripled and twice as many boxes are bought, write an expression for the total cost in dollars.

15 Hiring a basketball court costs $10 for a booking fee, plus $30 per hour.

- **a** Write an expression for the total cost in dollars to hire the court for x hours.
- **b** For the cost of $40, you could hire the court for 1 hour. How long could you hire the court for the cost of $80?
- **c** Explain why it is *not* the case that hiring the court for twice as long costs twice as much.
- **d** Find the average cost per hour if the court is hired for a 5 hour basketball tournament.
- **e** Describe what would happen to the *average* cost per hour if the court is hired for many hours (e.g. more than 50 hours).

Mobile phone mayhem

— | — | 16

ENRICHMENT

16 Rochelle and Emma are on different mobile phone plans, as shown below.

	Connection	Cost of minute
Rochelle	20 cents	60 cents
Emma	80 cents	40 cents

- **a** Write an expression for the cost of making a t-minute call using Rochelle's phone.
- **b** Write an expression for the cost of making a t-minute call using Emma's phone.
- **c** Whose phone plan would be cheaper for a 7-minute call?
- **d** What is the length of call for which it would cost exactly the same for both phones?
- **e** Investigate current mobile phone plans and describe how they compare to those of Rochelle's and Emma's plans.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Fencing paddocks

A farmer is interested in fencing off a large number of 1 m × 1 m foraging regions for the chickens. Consider the pattern below.



a For $n = 2$, the outside perimeter is 8 m, the area is 4 m^2 and the total length of fencing required is 12 m. Copy and complete the following table.

n	1	2	3	4	5	6
Outside perimeter (m)		8				
Area (m^2)		4				
Fencing required		12				

b Write an expression for:

i the total outside perimeter of the fenced section

ii the total area of the fenced section.

c The farmer knows that the expression for the total amount of fencing is one of the following. Which one is correct? Prove to the farmer that the others are incorrect.

i $6n$ **ii** $(n+1)^2$ **iii** $n \times 2 \times (n+1)$

d Use the correct formula to work out the total amount of fencing required if the farmer wants to have a total area of 100 m^2 fenced off.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

In a spreadsheet application these calculations can be made automatically. Set up a spreadsheet as follows.

	A	B	C	D
1	n	Perimeter	Area	Total fencing
2	0	0	0	0
3	=A2+1	=A3*4	=A3*A3	=A3*2*(A3+1)

Drag down the cells until you have all the rows from $n = 0$ to $n = 30$.

e Find the amount of fencing needed if the farmer wants the total area to be at least:

i 25 m^2 **ii** 121 m^2

iii 400 m^2 **iv** 500 m^2

f If the farmer has 144 m of fencing, what is the maximum area his grid could have?

g For each of the following lengths of fencing, give the maximum area, in m^2, that the farmer could contain in the grid.

i 50 m **ii** 200 m **iii** 1 km **iv** 40 km

h In the end, the farmer decides that the overall grid does not need to be a square, but could be any rectangular shape. Design rectangular paddocks with the following properties.

a perimeter = 20 m and area = 21 m^2

b perimeter = 16 m and fencing required = 38 m^2

c area = 1200 m^2 and fencing required = 148 m

d perimeter = 1 km and fencing required is less than 1.5 km



Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 If $x + y = 8$ and $y + m = 17$ find the value of $x + 2y + m$.


2 A square is cut in half and the two identical rectangles are joined to form a rectangle as shown in this diagram.



Find an expression for the perimeter of the rectangle if the square has a side length of:

a $2m$ **b** $4(x + 3)$ **c** $w + y$

3 These two identical 'L' shapes are to be joined along identical (matching) sides without any overlap. Find a simplified algebraic expression for the largest and smallest possible perimeters of the joined shapes and also for the difference between these two perimeters.



Calculate this difference when $x = 10$ cm. The diagrams are not drawn to scale.

4 In a list of five consecutive integers, the middle integer is $3a + 2$. Find two equivalent expressions for the sum of these five integers: one expanded and simplified, and one factorised.

5 Find the values of the pronumerals below in the following sum/product tables.

a

			Sum
	a	b	c
	d	24	32
Sum	12	e	48

b

			Product
	a	b	18
	2	c	d
Product	12	e	180

6 What is the coefficient of x once the expression $x + 2(x + 1) + 3(x + 2) + 4(x + 3) + \ldots + 100(x + 99)$ is simplified completely?

7 Think of any number and then perform the following operations. Add 5, then double the result, then subtract 12, then subtract the original number, then add 2. Use algebra to explain why you now have the original number again. Then design a puzzle like this yourself and try it on friends.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Creating expressions

6 more than k: $k + 6$
Product of 4 and x: $4x$
10 less than b: $b - 10$
Half of q: $\frac{q}{2}$
The sum of a and b is tripled: $3(a + b)$

Pronumerals

are letters used to represent numbers
g: number of grapes in a bunch
d: distance travelled (in metres)

Terms are pronumerals and numbers combined with $\times$, $\div$
e.g. $4x$, $10y$, $\frac{a}{3}$, 12
3a means $3 \times a$
$\frac{b}{10}$ means $b \div 10$

Like terms have exactly the same pronumerals.
$5a$ and $3a$ ✓
$2ab$ and $12ba$ ✓
$7ab$ and $2a$ ×

Algebraic expressions

Combination of numbers, pronumerals and operations, e.g. $2xy + 3yz$, $\frac{12}{x} - 3$

Algebra

Equivalent expressions

Always equal when pronumerals are substituted.
e.g. $2x + 3$ and $3 + 2x$ are equivalent.
$4(3x)$ and $12x$ are equivalent.

Substitution


Replacing pronumerals with values.
e.g. $5x + 2y$ when $x = 10$ & $y = 3$ becomes $5(10) + 2(3) = 50 + 6 = 56$
e.g. q^2 when $q = 7$ becomes $7^2 = 49$

Combining like terms gives a way to simplify.
e.g. $4a + 2 + 3a = 7a + 2$
$3b + 5c + 2b - c = 5b + 4c$
$12xy + 3x - 5yx = 7xy + 3x$

To **simplify** an expression, find a simpler expression that is equivalent.

Applications (Ext)

Commonly used expressions
$A = l \times w$
$P = 2l + 2w$



Cost is $50 + 90x$
call-out fee
hourly rate

Expanding brackets (Ext)

$3(a + 4) = 3a + 12$
$5k(10 - 2j) = 50k - 10kj$
Using the distributive law gives an equivalent expression.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Multiple-choice questions

5A **1** In the expression $3x + 2y + 4xy + 7yz$ the coefficient of y is:
A 3 **B** 2 **C** 4 **D** 7 **E** 16

5B **2** If $t = 5$ and $u = 7$, then $2t + u$ is equal to:
A 17 **B** 32 **C** 24 **D** 257 **E** 70

5B **3** If $x = 2$, then $3x^2$ is equal to:
A 32 **B** 34 **C** 12 **D** 25 **E** 36

5D **4** Which of the following pairs does *not* consist of two like terms?
A $3x$ and $5x$ **B** $3y$ and $12y$ **C** $3ab$ and $2ab$
D $3cd$ and $5c$ **E** $3xy$ and yx

5D **5** A fully simplified expression equivalent to $2a + 4 + 3b + 5a$ is:
A 4 **B** $5a + 5b + 4$ **C** $10ab + 4$
D $7a + 3b + 4$ **E** $11ab$

5E **6** The simplified form of $4x \times 3yz$ is:
A $43xyz$ **B** $12xy$ **C** $12xyz$ **D** $12yz$ **E** $4x3yz$

5E **7** The simplified form of $\frac{21ab}{3ac}$ is:
A $\frac{7b}{c}$ **B** $\frac{7ab}{ac}$ **C** $\frac{21b}{3c}$ **D** 7 **E** $\frac{b}{7c}$

5F Ext **8** When brackets are expanded, $4(2x + 3y)$ becomes:
A $8x + 3y$ **B** $2x + 12y$ **C** $8x + 8y$ **D** $24x$ **E** $8x + 12y$

5F Ext **9** The fully simplified form of $2(a + 7b) - 4b$ is:
A $2a + 10b$ **B** $2a + 3b$ **C** $a + 3b$
D $2a + 14b - 4b$ **E** $2a + 18b$

5A **10** A number is doubled and then 5 is added. The result is then tripled. If the number is represented by k, then an expression for this description is:
A $3(2k + 5)$ **B** $6(k + 5)$ **C** $2k + 5$
D $2k + 15$ **E** $30k$

Short-answer questions

5A **1** **a** List the four individual terms in the expression $5a + 3b + 7c + 12$.
b What is the constant term in the expression above?

5A **2** Write an expression for each of the following.
a 7 is added to u **b** k is tripled **c** 7 is added to half of r
d 10 is subtracted from h **e** the product of x and y **f** x is subtracted from 12

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

5B **3** If $u = 12$, find the value of:

a $u + 3$ **b** $2u$ **c** $\frac{24}{u}$ **d** $3u - 4$

5B **4** If $p = 3$ and $q = 5$, find the value of:

a pq **b** $p + q$ **c** $2(q - p)$ **d** $4p + 3q$

5B **5** If $t = 4$ and $u = 10$, find the value of:

a t^2 **b** $2u^2$ **c** $3 + \sqrt{t}$ **d** $\sqrt{10tu}$

5C **6** For each of the following pairs of expressions, state whether they are equivalent (E) or not equivalent (N).

a $5x$ and $2x + 3x$ **b** $7a + 2b$ and $9ab$

c $3c - c$ and $2c$ **d** $3(x + 2y)$ and $3x + 2y$

5D **7** Classify the following pairs as like terms (L) or not like terms (N).

a $2x$ and $5x$ **b** $7ab$ and $2a$ **c** $3p$ and p

d $9xy$ and $2yx$ **e** $4ab$ and $4aba$ **f** $8t$ and $2t$

g $3p$ and 3 **h** $12k$ and $120k$

5D **8** Simplify the following by collecting like terms.

a $2x + 3 + 5x$ **b** $12p - 3p + 2p$ **c** $12b + 4a + 2b + 3a + 4$

d $12mn + 3m + 2n + 5nm$ **e** $1 + 2c + 4h - 3o + 5c$ **f** $7u + 3v + 2uv - 3u$

5E **9** Simplify the following expressions involving products.

a $3a \times 4b$ **b** $2xy \times 3z$ **c** $12f \times g \times 3h$ **d** $8k \times 2 \times 4lm$

5E **10** Simplify the following expressions involving quotients.

a $\frac{3u}{2u}$ **b** $\frac{12y}{20y}$ **c** $\frac{2ab}{6b}$ **d** $\frac{12xy}{9yz}$

5F Ext **11** Expand the following expressions using the distributive law.

a $3(x + 2)$ **b** $4(p - 3)$ **c** $7(2a + 3)$ **d** $12(2k + 3l)$

5F Ext **12** Give two examples of expressions that expand to give $12b + 18c$.

5G Ext **13** If tins of paints weigh 9 kg, write an expression for the weight in kg of t tins of paint.

5G Ext **14** If there are g girls and b boys in a room, write an expression for the total number of children in the room.

5G Ext **15** Write an expression for the total number of books that Analena owns if she has x fiction books and twice as many non-fiction books.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 A taxi driver charges $3.50 to pick up passengers and then $2.10 per kilometre travelled.



a State the total cost if the trip length is:

i 10 km

ii 20 km

iii 100 km


b Write an expression for the total cost, in dollars, of travelling a distance of d kilometres.

c Use your expression to find the total cost of travelling 40 km.

d Prove that your expression is not equivalent to $2.1 + 3.5d$ by substituting in a value for d.

e Another taxi driver charges $6 to pick up passengers and then $1.20 per kilometre. Write an expression for the total cost (in dollars) of travelling d kilometres in this taxi.

2 An architect has designed a room, shown opposite, for which x and y are unknown. (All measurements are in metres.)



a Find the perimeter of this room if $x = 3$ and $y = 2$.

b It costs $3 per metre to install skirting boards around the perimeter of the room. Find the total cost of installing skirting boards if the room's perimeter is $x = 3$ and $y = 2$.

c Write an expression for the perimeter (in metres) of the room and simplify it completely.


d Write an expanded expression for the total cost, in dollars, of installing skirting boards along the room's perimeter.

e Write an expression for the total floor area in m^2.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 6

Decimals

What you will learn

6A Decimals and place value (Consolidating)
6B Rounding decimals
6C Addition and subtraction of decimals (Consolidating)
6D Multiplying and dividing by powers of 10
6E Multiplication of decimals
6F Division of decimals
6G Decimals and fractions
6H Decimals and percentages

Australian curriculum

NUMBER AND ALGEBRA

Real numbers

Multiply and divide fractions and decimals using efficient written strategies and digital technologies (ACMNA154)

Round decimals to a specified number of decimal places (ACMNA156)

Connect fractions, decimals and percentages and carry out simple conversions (ACMNA157)

Find percentages of quantities and express one quantity as a percentage of another, with and without digital technologies. (ACMNA158)

Money and financial mathematics

Investigate and calculate 'best buys', with and without digital technologies (ACMNA174) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Swimming records and decimal places

Swimming times are electronically measured and recorded with the seconds given to 2 decimal places. Accuracy is very important so that the right decision is made for placegetters and records.

Sometimes winners are separated by as little as one-hundredth of a second. Ian Thorpe, who set 13 world records, had his 400 m freestyle record (3:40.06) broken in 2009 by German swimmer Paul Biedermann, who swam only 0.01 of a second faster than Thorpe.

The decimal system allows us to express quantities with great accuracy. There are many instances in our everyday lives in which accuracy of measurement is highly important. For example, bicycle, car and aeroplane parts must be manufactured to precise measurements; medicine production requires measurement of chemicals in precise quantities; and investment rates, stock market prices and values are measured to many decimal places (8% per year equals 0.153 846% per week).

Can you think of any other quantities that require decimal measurement?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6A Decimals and place value

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Some quantities change by whole number amounts, such as the number of people in a room, but there are many quantities that increase or decrease continuously, such as your height, weight and age. Often we talk about age as a whole number (e.g. Mike is 12 years old) but, in reality, our age is an ever-increasing (continuous) quantity. For example, if Mike is 12 years, 4 months, 2 weeks, 3 days, 5 hours, 6 minutes and 33 seconds old, then Mike is actually 12.380 621 47 years old!



If a chocolate bar costs $2, would the price still be a decimal number?

There are many numbers in today's society that are not whole numbers. For example, it is unusual to buy an item in a supermarket that is simply a whole number of dollars. The price of almost all shopping items involves both dollars and cents. A chocolate bar may cost $1.95, which is an example of a decimal number.

Let's start: Split-second timing

Organise students into pairs and use a digital stopwatch. Many students' watches will have a suitable stopwatch function.

- Try to stop the stopwatch on exactly 10 seconds. Have two attempts each.
  Were you able to stop it exactly on 10.00 seconds? What was the closest time?
- Try these additional challenges with your partner.

a Stop the watch exactly on: **i** $12\frac{1}{2}$ seconds **ii** 8.37 seconds **iii** $9\frac{7}{10}$ seconds **iv** 14.25 seconds

b How quickly can you start and stop the stopwatch?

c How accurately can you time 1 minute without looking at the stopwatch?

Key ideas

- A **decimal point** is used to separate the whole number from the decimal or fraction part.
- When dealing with decimal numbers, the place value table must be extended to involve tenths, hundredths, thousandths etc.
  The number 428.357 means:

Hundreds	Tens	Units	.	Tenths	Hundredths	Thousandths
4	2	8	.	3	5	7
4×100	2×10	8×1	.	$3 \times \frac{1}{10}$	$5 \times \frac{1}{100}$	$7 \times \frac{1}{1000}$
400	20	8	.	$\frac{3}{10}$	$\frac{5}{100}$	$\frac{7}{1000}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Understanding decimal place value

What is the value of the digit 8 in the following numbers?

a 12.85 **b** 6.1287

SOLUTION	EXPLANATION
a The value of 8 is $\frac{8}{10}$.	The 8 is in the first column after the decimal point, which is the tenths column.
b The value of 8 is $\frac{8}{1000}$.	The 8 is in the third column after the decimal point, which is the thousandths column.

Example 2 Changing to decimals

Express each of the following proper fractions and mixed numerals as decimals.

a $\frac{7}{10}$ **b** $\frac{5}{100}$ **c** $3\frac{17}{100}$

SOLUTION	EXPLANATION
a $\frac{7}{10} = 0.7$	$\frac{7}{10}$ means seven-tenths, so put the 7 in the tenths column.
b $\frac{5}{100} = 0.05$	$\frac{5}{100}$ means five-hundredths, so put the 5 in the hundredths column.
c $3\frac{17}{100} = 3.17$	$3\frac{17}{100}$ means 3 units and 17 one-hundredths. 17 hundredths is one-tenth and seven-hundredths.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Arranging decimal numbers in order

Arrange the following decimal numbers in ascending order (i.e. smallest to largest).
3.72, 7.23, 2.73, 2.37, 7.32, 3.27

SOLUTION	EXPLANATION
2.37, 2.73, 3.27, 3.72, 7.23, 7.32	The units column has a higher value than the tenths column, and the tenths column has a higher value than the hundredths column. 2.73 is bigger than 2.37 because it has seven-tenths, which is bigger than three-tenths.

Exercise 6A

1–3 | 3 | —

UNDERSTANDING

1 For the number 58.237, give the value of the digit:
- **a** 2
- **b** 3
- **c** 7

2 A stopwatch is stopped at 36.57 seconds.
- **a** What is the digit displayed in the tenths column?
- **b** What is the digit displayed in the units column?
- **c** What is the digit displayed in the hundredths column?
- **d** Is this number closer to 36 or 37 seconds?

Example 1

3 What is the value of the digit 6 in the following numbers?
- **a** 23.612
- **b** 17.46
- **c** 80.016
- **d** 0.693
- **e** 16.4
- **f** 8.568 13
- **g** 2.3641
- **h** 11.926

4–7(½) | 4–7(½) | 4–7(½)

FLUENCY

4 State whether each of the following is true or false.
- **a** $7.24 < 7.18$
- **b** $21.32 < 20.89$
- **c** $4.61 > 4.57$
- **d** $8.09 > 8.41$
- **e** $25.8 \leq 28.5$
- **f** $2.1118 \leq 2.8001$
- **g** $7.93 \geq 8.42$
- **h** $11.11 \geq 11.109$
- **i** $\frac{3}{10} = \frac{30}{100}$
- **j** $\frac{7}{10} = \frac{70}{100}$
- **k** $\frac{5}{10} \neq 5$
- **l** $\frac{2}{10} \neq \frac{20}{100}$

Example 2a,b

5 Express each of the following proper fractions as a decimal.
- **a** $\frac{3}{10}$
- **b** $\frac{8}{10}$
- **c** $\frac{15}{100}$
- **d** $\frac{23}{100}$
- **e** $\frac{9}{10}$
- **f** $\frac{2}{100}$
- **g** $\frac{121}{1000}$
- **h** $\frac{74}{1000}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6A

FLUENCY

Example 2c

6 Express each of the following mixed numerals as a decimal.

a $6\frac{4}{10}$ **b** $5\frac{7}{10}$ **c** $212\frac{3}{10}$ **d** $1\frac{16}{100}$

e $14\frac{83}{100}$ **f** $7\frac{51}{100}$ **g** $5\frac{7}{100}$ **h** $18\frac{612}{1000}$

7 Write the following number phrases as decimals.

a seven and six-tenths
b twelve and nine-tenths
c thirty-three and four-hundredths
d twenty-six and fifteen-hundredths
e eight and forty-two hundredths
f ninety-nine and twelve-thousandths

8, 9 | 9, 10 | 9–11

PROBLEM-SOLVING

8 How close are the following decimal numbers to their nearest whole number?

a 6.9 **b** 7.03 **c** 18.98
d 16.5 **e** 17.999 **f** 4.99
g 0.85 **h** 99.11


Example 3

9 Arrange these groups of numbers in ascending order (i.e. smallest to largest).

a 3.52, 3.05, 3.25, 3.55
b 30.6, 3.06, 3.6, 30.3
c 17.81, 1.718, 1.871, 11.87
d 26.92, 29.26, 29.62, 22.96, 22.69

10 The batting averages for five retired Australian Cricket test captains are: Adam Gilchrist 47.60, Steve Waugh 51.06, Mark Taylor 43.49, Allan Border 50.56 and Kim Hughes 37.41.

a List the five players in descending order of batting averages (i.e. largest to smallest).
b Ricky Ponting's test batting average is 56.72. Where does this rank him in terms of the retired Australian test captains listed above?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

6A

PROBLEM-SOLVING

11 The depth of a river at 9:00 am on six consecutive days was:

Day 1: 1.53 m Day 2: 1.58 m Day 3: 1.49 m
Day 4: 1.47 m Day 5: 1.52 m Day 6: 1.61 m

a On which day was the river level highest?
b On which day was the river level lowest?
c On which days was the river level higher than the previous day?



12 | 12 | 12, 13

REASONING

12 a, b and c are digits and $a > b > c$. Write these numbers from smallest to largest. Note that the dot represents the decimal point.

a $a.b$, $b.c$, $a.c$, $c.c$, $c.a$, $b.a$
b $a.bc$, $b.ca$, $b.bb$, $c.ab$, $c.bc$, $ba.ca$, $ab.ab$, $a.aa$, $a.ca$

13 Write as decimals, if a is a digit.

a $\frac{a}{10}$ **b** $\frac{a}{100}$ **c** $\frac{a}{10} + \frac{a}{100}$ **d** $a + \frac{a}{10} + \frac{a}{1000}$

Different decimal combinations — | — | 14

ENRICHMENT

14 a Write as many different decimal numbers as you can and place them in ascending order using:
i the digits 0, 1 and a decimal point. Each digit can be used only once.
ii the digits 0, 1, 2 and a decimal point. Each digit can be used only once.
iii the digits 0, 1, 2, 3 and a decimal point. Each digit can be used only once.

b Calculate the number of different decimal numbers that could be produced using the digits 0, 1, 2, 3, 4 and a decimal point.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6B Rounding decimals

Interactive

Widgets

HOTsheets

Walkthroughs

Decimal numbers sometimes contain more decimal places than we need. It is important that we are able to round decimal numbers when working with money, measuring quantities, including time and distance, or writing answers to some division calculations.

For example, the distance around the school oval might be 0.39647 km, which rounded to 1 decimal place is 0.4 km or 400 m. The rounded figure, although not precise, is accurate enough for most applications.

Running events are electronically measured and rounded to 2 decimal places. Usain Bolt has repeatedly broken his own world records. In August 2009 he set a new world record of 9.58 seconds over 100 m at the World Championships in Germany, which was 11-hundredths (0.11) of a second faster than his Beijing Olympic Games (August 2008) record of 9.69 seconds.



Usain Bolt's 100-metre sprint world record is measured to 2 decimal places.

Let's start: Rounding brainstorm

1. In a group of four, brainstorm occasions when it may be useful to round or estimate decimal numbers. Aim to get more than 10 common applications.
2. In pairs one person states a decimal number and the partner needs to state another decimal number that would allow the two numbers to add up to a whole number. Use mental arithmetic only. Start with 1 decimal place and try to build up to 3 or 4 decimal places.

Key ideas

- **Rounding** involves approximating a decimal number to fewer decimal places.
- To round a decimal:
  - Cut the number after the required decimal place; e.g. round to 2 decimal places.
  - To determine whether you should round your answer up or down, consider only the digit *immediately* to the right of the specified place. For rounding purposes this can be referred to as the **critical digit**.

'cut'

2 is the critical digit in this example

15.63 | 27

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- If the critical digit is *less than* 5 (i.e. 0, 1, 2, 3 or 4), then you *round down*. This means write the original number to the place required, leaving off all other digits. This can be referred to as simply leaving the number as it is.
- If the critical digit is *5 or more* (i.e. 5, 6, 7, 8 or 9), then you *round up*. This means write the original number to the place required, but increase this digit by 1. Leave off all other digits.

Example 4 Determining the critical digit

The following decimal numbers need to be rounded to 2 decimal places. Draw a line where the number must be cut and then circle the critical digit.

a 23.5398 **b** 1.75137

SOLUTION	EXPLANATION
a 23.53 | (9) 8	A line is drawn directly after the specified number of decimal places, in this case, 2.
b 1.75 | (1) 37	The critical digit is always the number straight after the specified number of decimal places.

Example 5 Rounding decimals to 1 decimal place

Round each of the following to 1 decimal place.

a 25.682 **b** 13.5458

SOLUTION	EXPLANATION
a 25.7	The critical digit is 8 and therefore the tenths column must be rounded up from a 6 to a 7.
b 13.5	The critical digit is 4 and therefore the tenths column remains the same, in effect rounding the original number down to 13.5.

Example 6 Rounding decimals to different decimal places

Round each of the following to the specified number of decimal places.

a Round 18.34728 to 3 decimal places. **b** Round 0.43917 to 2 decimal places.

c Round 7.59967 to 3 decimal places.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a 18.347	The critical digit is 2, therefore round down.
b 0.44	The critical digit is 9, therefore round up.
c 7.600	The critical digit is 6, therefore round up. Rounding up has resulted in digits being carried over. Remember to show the stated number of decimal places; hence, the zeros must be displayed.

Exercise 6B

1–3 | 3 | —

UNDERSTANDING

1 For each of the following, select the closer alternative.
- a Is 5.79 closer to 5.7 or 5.8?
- b Is 2.4 closer to 2 or 3?
- c Is 83 closer to 80 or 90?
- d Is 6.777 closer to 6.77 or 6.78?

Example 4

2 The following decimals need to be rounded, correct to 2 decimal places. Draw a line where the number must be cut and then circle the critical digit that must be checked as to whether to round up or down.

a 12.6453	b 4.81932	c 157.281	d 4 001 565.38471
e 0.06031	f 203.5791	g 66.6666	h 7.995123

3 To round correctly to a specified number of places, you must know which digit is the critical digit. Remember: The critical digit is always the digit immediately to the right of the specified number of places.
- a State the critical digit in each of the following numbers.
  - i 25.8174 rounded to 1 decimal place. Critical digit = ____
  - ii 25.8174 rounded to 2 decimal places. Critical digit = ____
  - iii 25.8174 rounded to 3 decimal place. Critical digit = ____
  - iv 25.8174 rounded to the nearest whole number. Critical digit = ____
- b State the correct rounded numbers for the numbers in parts i to iv above.

4–8(½) | 4–9(½) | 4–9(½)

FLUENCY

Example 5

4 Round each of the following to 1 decimal place.

a 14.82	b 7.38	c 15.62	d 0.87
e 6.85	f 9.94	g 55.55	h 7.98

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6B

FLUENCY

5 Write each of the following correct to 2 decimal places.

a 3.7823	**b** 11.8627	**c** 5.9156	**d** 0.93225
e 123.456	**f** 300.0549	**g** 3.1250	**h** 9.849
i 56.2893	**j** 7.121 999	**k** 29.9913	**l** 0.8971

Example 6a, b

6 Round each of the following to the specified number of decimal places, given as the number in the brackets.

a 15.913 (1)	**b** 7.8923 (2)	**c** 235.62 (0)	**d** 0.5111 (0)
e 231.86 (1)	**f** 9.3951 (1)	**g** 9.3951 (2)	**h** 34.712 89 (3)

Example 6c

7 Round each of the following to the specified number of decimal places.

a 23.983 (1)	**b** 14.8992 (2)	**c** 6.95432 (0)	**d** 29.999731 (3)

8 Round each of the following to the nearest whole number.

a 27.612	**b** 9.458	**c** 12.299	**d** 123.72
e 22.26	**f** 117.555	**g** 2.6132	**h** 10.7532

9 Round each of the following amounts to the nearest dollar.

a $12.85	**b** $30.50	**c** $7.10	**d** $1566.80
e $120.45	**f** $9.55	**g** $1.39	**h** $36.19

PROBLEM-SOLVING

10 | 10, 11 | 10, 11

10 Some wise shoppers have the habit of rounding all items to the nearest dollar as they place them in their shopping basket. They can then keep a running total and have a close approximation as to how much their final bill will cost. Use this technique to estimate the cost of the following.

a Jeanette purchases 10 items:
$3.25, $0.85, $4.65, $8.99, $12.30, $7.10, $2.90, $1.95, $4.85, $3.99

b Adam purchases 12 items:
$0.55, $3.00, $5.40, $8.90, $6.90, $2.19, $3.20, $5.10, $3.15, $0.30, $4.95, $1.11

c Jeanette's actual shopping total is $50.83 and Adam's is $44.75. How accurate were Jeanette's and Adam's estimations?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

6B

PROBLEM-SOLVING

11 Electronic timing pads are standard in National Swimming competitions. In a recent National Under 15 100-m freestyle race, Edwina receives a rounded time of 52.83 seconds and Jasmine a time of 53.17 seconds.



a If the timing pads can calculate times only to the nearest second, what will be the time difference between the two swimmers?

b If the timing pads can calculate times only to the nearest tenth of a second, what will be the time difference between the two swimmers?

c What is the time difference between the two swimmers, correct to 2 decimal places?

d If the timing pads can measure to 3 decimal places, what would be the quickest time that Edwina could have swum the race in?

REASONING

	12	12	12, 13

12 Without using a calculator, evaluate $15.735\,629 \div 7$, correct to 2 decimal places. What is the least number of decimal places you need to find in the quotient to ensure that you have rounded correctly to 2 decimal places?

13 Samara believes 0.449 999 should be rounded up to 0.5, but Cassandra believes it should be rounded down to 0.4. Make an argument to support each of their statements, but then show the flaw in one girl's logic and clearly indicate which girl you think is correct.

ENRICHMENT

Rounding with technology	—	—	14, 15

14 Most calculators are able to round numbers correct to a specified number of places. Find out how to do this on your calculator and check your answers to Questions **5** and **6**.

15 Spreadsheet software packages can also round numbers correct to a specified number of places. Find out the correct syntax for rounding cells in a spreadsheet program, such as Microsoft Excel, and then check your answers to Questions **7** and **8**.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6C Addition and subtraction of decimals

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Addition and subtraction of decimals follows the same procedures as those for whole numbers. To add or subtract whole numbers you must line up the units, tens, hundreds and so on, and then you add or subtract each column. When dealing with the addition or subtraction of decimals the routine is the same.

Consider how similar the following two sums are:

$$\begin{array}{r} {}^{1}5\,1\,4 \\ 2\,7\,2 \\ 1\,0\,6 \\ \hline 8\,9\,2 \end{array} \qquad \begin{array}{r} {}^{1}5\,1\,.\,4 \\ 2\,7\,.\,2 \\ 1\,0\,.\,6 \\ \hline 8\,9\,.\,2 \end{array}$$

Let's start: What's the total?

Each student thinks of three coins (gold or silver) and writes their total value on a sheet of paper. Each student in the class then estimates the total value of the amounts written down in the classroom. Record each student's estimated total.

- Each student then writes the value of the three coins they thought of on the board (e.g. $2.70, $0.80 etc.).
- Students copy down the values into their workbooks and add the decimal numbers to determine the total value of the coins in the classroom.
- Which student has the closest estimation?



Accounting involves the addition and subtraction of decimal numbers.

Key ideas

- When adding or subtracting decimals, the decimal points and each of the decimal places must be aligned under one another.
- The location of the decimal point in the answer is directly in line with the location of each of the decimal points in the question.
- Once the numbers are correctly aligned, proceed as if completing whole number addition or subtraction.
- If the numbers of decimal places in the numbers being added or subtracted are different, it can be helpful to place additional zeros in the 'shorter' number(s) to prevent calculation errors.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 7 Adding decimals

Find:

a 8.31 + 5.93

b 64.8 + 3.012 + 5.94

SOLUTION

a
$$\begin{array}{r} {}^{1}8.31 \\ +\,5.93 \\ \hline 14.24 \end{array}$$

b
$$\begin{array}{r} {}^{1}6{}^{1}4.800 \\ 3.012 \\ +\ 5.940 \\ \hline 73.752 \end{array}$$

EXPLANATION

Make sure all decimal points and decimal places are correctly aligned directly under one another.

Align decimal points directly under one another. Fill in missing decimal places with additional zeros.
Carry out addition, following the same procedure as that for addition of whole numbers.

Example 8 Subtracting decimals

Find:

a 5.83 – 3.12

b 146.35 – 79.5

SOLUTION

a
$$\begin{array}{r} 5.83 \\ -\,3.12 \\ \hline 2.71 \end{array}$$

b
$$\begin{array}{r} {}^{13}{}^{15}\,{}^{1} \\ 1\not{4}\not{6}.35 \\ -\quad 79.50 \\ \hline 66.85 \end{array}$$

EXPLANATION

Make sure all decimal points and decimal places are correctly aligned directly under one another.

Align decimal points directly under one another and fill in missing decimal places with additional zeros.
Carry out subtraction, following the same procedure as that for subtraction of whole numbers.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 6C

1, 2 | 2 | —

UNDERSTANDING

1 7.12, 8.5 and 13.032 must be added together. Which of the following is the best way to prepare these numbers ready for addition?

A
$$\begin{array}{r} 7.12 \\ 8.5 \\ +\ 13.032 \\ \hline \\ \hline \end{array}$$

B
$$\begin{array}{r} 7.12 \\ 8.5 \\ +\ 13.032 \\ \hline \\ \hline \end{array}$$

C
$$\begin{array}{r} 7.120 \\ 8.500 \\ +\ 13.032 \\ \hline \\ \hline \end{array}$$

D
$$\begin{array}{r} 7.12 \\ 8.5 \\ +\ 13.032 \\ \hline \\ \hline \end{array}$$

2 Which of the following is the correct way to present and solve the subtraction problem 77.81 – 6.3?

A
$$\begin{array}{r} 77.81 \\ -\ 6.3 \\ \hline 84.11 \\ \hline \end{array}$$

B
$$\begin{array}{r} 77.81 \\ -\ 6.30 \\ \hline 71.51 \\ \hline \end{array}$$

C
$$\begin{array}{r} 7\ 7.81 \\ -\ 6.3 \\ \hline 14.81 \\ \hline \end{array}$$

D
$$\begin{array}{r} 77.8\ 1 \\ -\ 6.3 \\ \hline 77.18 \\ \hline \end{array}$$

3–6(½) | 3–6(½) | 3–6(½)

FLUENCY

3 Find each of the following.

a
$$\begin{array}{r} 13.25 \\ +\ 14.72 \\ \hline \\ \hline \end{array}$$

b
$$\begin{array}{r} 7.23 \\ 16.31 \\ +\ 2.40 \\ \hline \\ \hline \end{array}$$

c
$$\begin{array}{r} 210.0 \\ 22.3 \\ +\ 15.1 \\ \hline \\ \hline \end{array}$$

d
$$\begin{array}{r} 47.81 \\ 6.98 \\ +\ 3.52 \\ \hline \\ \hline \end{array}$$

Example 7

4 Find each of the following.

a 12.45 + 3.61
b 5.37 + 13.81 + 2.15
c 312.5 + 31.25
d 1.567 + 3.4 + 32.6
e 5.882 + 3.01 + 12.7
f 323.71 + 3.4506 + 12.9

5 Find:

a
$$\begin{array}{r} 17.2 \\ -\ 5.1 \\ \hline \\ \hline \end{array}$$

b
$$\begin{array}{r} 128.63 \\ -\ 14.50 \\ \hline \\ \hline \end{array}$$

c
$$\begin{array}{r} 23.94 \\ -\ 17.61 \\ \hline \\ \hline \end{array}$$

d
$$\begin{array}{r} 158.32 \\ -\ 87.53 \\ \hline \\ \hline \end{array}$$

Example 8

6 Find:

a 14.8 – 2.5
b 234.6 – 103.2
c 25.9 – 3.67
d 31.657 – 18.2
e 412.1 – 368.83
f 5312.271 – 364.93

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6C

PROBLEM-SOLVING

7, 8 | 7–10 | 10–12

7 Find the missing numbers in the following sums.

a
$$\begin{array}{r} 3.\square \\ +\ 4.\ 6 \\ \hline \square.\ 3 \end{array}$$

b
$$\begin{array}{r} 8.\square\ 9 \\ +\ \square.\ 7\ 5 \\ \hline \square 4.\ 4\ \square \end{array}$$

c
$$\begin{array}{r} 1.\square\ 1 \\ +\ \square\square.\ 1\ 1 \\ \hline 1\ 1.1\ \square \end{array}$$

d
$$\begin{array}{r} \square.\ 3\ \square\ 6 \\ 2.\ \square\ 4\ 3 \\ +\ \ 1.\ 8\ 9\ \square \\ \hline \square\ 1.\ 3\ 9\ 5 \end{array}$$

8 How much greater is 262.5 than 76.31?

9 Stuart wants to raise $100 for the Rainbow Club charity. He already has three donations of $30.20, $10.50 and $5.00. How much does Stuart still need to raise?

10 Daily rainfalls for 4 days over Easter were 12.5 mm, 3.25 mm, 0.6 mm and 32.76 mm. What was the total rainfall over the 4-day Easter holiday?

11 Complete the addition table below.

+	0.01	0.05	0.38	1.42
0.3				1.72
0.75			1.13	
1.20	1.21		1.58	
1.61				3.03

12 Michelle earned $3758.65 working part-time over a 1-year period. However, she was required to pay her parents $20 per week for board for 52 weeks. Michelle also spent $425.65 on clothing and $256.90 on presents for her family and friends during the year. She placed the rest of her money in the bank. How much did Michelle bank for the year?

REASONING

13 | 13 | 13, 14

13 If $a = 2.8$, $b = 1.31$ and $c = 3.928$, find:

a $a + b + c$ **b** $a + b - c$ **c** $c + b - a$ **d** $c - (b + b)$

14 **a** Write down three numbers between 1 and 10, each with 2 decimal places, that would add to 11.16.

b Can you find a solution to part **a** that uses each digit from 1 to 9 exactly once each?

ENRICHMENT

Money, money, money … — | — | 15

15 Investigate the following procedures and share your findings with a friend.

a Choose an amount of money that is less than $10.00 (e.g. $3.25).

b Reverse the order of the digits and subtract the smaller number from the larger number (e.g. $5.23 – $3.25 = $1.98).

c Reverse the order of the digits in your new answer and now add this number to your most recent total (e.g. $1.98 + $8.91 = $10.89).

Did you also get $10.89? Repeat the procedure using different starting values.

Try to discover a pattern or a rule. Justify your findings.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6D Multiplying and dividing by powers of 10

Interactive

Powers of 10 include $10^1, 10^2, 10^3, 10^4, \ldots$, which correspond to the numbers 10, 100, 1000, 10 000, ... Note that the number of zeros in the number is the same as the power of 10 for that number. For example, $10^4 = 10\,000$, the number ten thousand has four zeros and it is equal to ten to the power of four.

Widgets

HOTsheets

Walkthroughs

Let's start: Dynamic leap frog

A set of large number cards, enough for one card per student in the class, is required.

The set of cards should include the following digits, numbers and symbols:

0, 1, 2, 3, 4, 5, 6, 7, 8, 9, . , ×, ÷, 1, 10, 100, 1000, 10 000, 100 000, 1 000 000

The decimal place card is vital! Cards should be big enough to be read from the back of the classroom. Any of the digits can be doubled up to increase the total number of cards. Each student receives one card.

- Four students with one of the 0 to 9 digit cards stand up at the front and make a 4-digit number.
- The student with the decimal place card then positions themselves somewhere within this number or on either end.
- Now a student with the × or ÷ operation comes up the front.
- Finally, a student with a power of 10 card comes up and performs the actual calculation by gently moving the decimal place!
- Repeat a number of times with students swapping cards on several occasions.



Key ideas

- Every number contains a decimal point but it is usually not shown in integers.
  For example: 345 is 345.0 and 2500 is 2500.0
- Extra zeros can be added in the column to the right of the decimal point without changing the value of the decimal.
  For example: 12.5 = 12.50 = 12.500 = 12.5000 etc.
- When multiplying by powers of 10:
  - Move the decimal point to the *right* the same number of places as there are zeros in the multiplier.
    For example, if multiplying by 1000, move the decimal point 3 places to the right.
    $5.7839 \times 1000 = 5783.9$
    Note: The decimal point actually stays still and all the digits move three places to the left, but this is harder to visualise.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

■ When dividing by powers of 10:
- Move the decimal point to the *left* the same number of places as there are zeros in the multiplier.
  For example, if dividing by 100, move the decimal point 2 places to the left.
  $2975.6 \div 100 = 29.756$
  Note: The decimal point actually stays still and all the digits move two places to the right, but this is harder to visualise.

Example 9 Multiplying by powers of 10

Evaluate:

a 36.532×100 **b** $4.31 \times 10\,000$

SOLUTION	EXPLANATION
a $36.532 \times 100 = 3653.2$	100 has two zeros, therefore decimal point appears to move 2 places to the right. 36.532
b $4.31 \times 10\,000 = 43\,100$	Decimal point appears to move 4 places to the right and additional zeros are inserted as necessary. 4.3100

Example 10 Dividing by powers of 10

Evaluate:

a $268.15 \div 10$ **b** $7.82 \div 1000$

SOLUTION	EXPLANATION
a $268.15 \div 10 = 26.815$	10 has one zero, therefore decimal point is moved 1 place to the left. 268.15
b $7.82 \div 1000 = 0.00782$	Decimal point is moved 3 places to the left and additional zeros are inserted as necessary. .00782

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Working with 'the missing' decimal point

Evaluate:

a $567 \times 10\,000$ **b** $23 \div 1000$

SOLUTION	EXPLANATION
a $567 \times 10\,000 = 5\,670\,000$	If no decimal point is shown in the question, it must be at the very end of the number. Four additional zeros must be inserted to move the invisible decimal point 4 places to the right. $5670000.$
b $23 \div 1000 = 0.023$	Decimal point is moved 3 places to the left. 0.023

Example 12 Evaluating using order of operations

Calculate this expression, using the order of operations:
$426 \div 100 + 10(0.43 \times 10 - 1.6)$

SOLUTION	EXPLANATION
$426 \div 100 + 10(0.43 \times 10 - 1.6)$ $= 4.26 + 10(4.3 - 1.6)$ $= 4.26 + 10 \times 2.7$ $= 4.26 + 27$ $= 31.26$	First, we must calculate the brackets. The division by 100 can also be done in the first step. $10(4.3 - 2.6)$ means $10 \times (4.3 - 2.6)$.

Exercise 6D

1–3 | 3 | —

UNDERSTANDING

1 Fill in the correct number of zeros in the multiplier to make the following product statements correct. The first one has been done for you.

a $56.321 \times 1\,[00] = 5632.1$
b $27.9234 \times 1\,[\quad] = 27\,923.4$
c $0.035\,72 \times 1\,[\quad] = 3.572$
d $3200 \times 1\,[\quad] = 320\,000\,000$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6D

UNDERSTANDING

2 Fill in the correct number of zeros in the divisor to make the following division statements correct. The first one has been done for you.

a $2345.1 \div 1$ [000] $= 2.3451$ **b** $7238.4 \div 1$ [ ] $= 72.384$

c $0.003\,67 \div 1$ [ ] $= 0.000\,367$ **d** $890 \div 1$ [ ] $= 0.0089$

3 **a** How many places and in what direction does the decimal point in the number appear to move if the following operations occur?

i $\times 100$ **ii** $\div 10$ **iii** $\times 1\,000\,000$ **iv** $\div 1$

v $\div 1000$ **vi** $\times 1000$ **vii** $\times 10$ **viii** $\div 10\,000\,000$

b If all of the operations above had taken place on a number, one after the other, what would be the final position of the decimal place relative to its starting position?

4–7(½) | 4–7(½) | 4–7(½)

FLUENCY

Example 9

4 Calculate:

a 4.87×10 **b** 35.283×10 **c** 422.27×10

d 14.304×100 **e** $5.699\,23 \times 1000$ **f** $1.259\,63 \times 100$

g 12.7×1000 **h** 154.23×1000 **i** $0.34 \times 10\,000$

j 213.2×10 **k** $867.1 \times 100\,000$ **l** $0.005\,16 \times 100\,000\,000$

Example 10

5 Calculate:

a $42.7 \div 10$ **b** $353.1 \div 10$ **c** $24.422 \div 10$

d $5689.3 \div 100$ **e** $12\,135.18 \div 1000$ **f** $93\,261.1 \div 10\,000$

g $2.9 \div 100$ **h** $13.62 \div 10\,000$ **i** $0.54 \div 1000$

j $36.7 \div 100$ **k** $0.02 \div 10\,000$ **l** $1000.04 \div 100\,000$

6 Calculate:

a 22.913×100 **b** $0.031\,67 \times 1000$ **c** $4.9 \div 10$

d $22.2 \div 100$ **e** $6348.9 \times 10\,000$ **f** $1.0032 \div 1000$

Example 11

7 Calculate:

a 156×100 **b** 43×1000 **c** $2251 \div 10$

d $16 \div 1000$ **e** 2134×100 **f** $2134 \div 100$

g $7 \div 1000$ **h** $99 \times 100\,000$ **i** $34 \div 10\,000$

8(½), 9 | 8(½), 9, 10 | 10–12

PROBLEM-SOLVING

Example 12

8 Calculate the following, using the order of operations.

a $1.56 \times 100 + 24 \div 10$ **b** $16 \div 100 + 32 \div 10$

c $3 + 10(24 \div 100 + 8)$ **d** $10(6.734 \times 100 + 32)$

e $35.4 + 4.2 \times 10 - 63.4 \div 10$ **f** $4.7 - 24 \div 10 + 0.52 \times 10$

g $14 \div 100 + 1897 \div 1000$ **h** $78.1 - 10(64 \div 100 + 5)$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6D

PROBLEM-SOLVING

9 A service station charges $1.37 per litre of petrol. How much will it cost Tanisha to fill her car with 100 litres of petrol?

10 A large bee farm produces 1200 litres of honey per day.

- **a** If there are 1000 millilitres in 1 litre, how many millilitres of honey can the farm's bees produce in one day?
- **b** The farm's honey is sold in 100 millilitre jars. How many jars of honey can the farm's bees fill in one day?

11 Wendy is on a mobile phone plan that charges her 3 cents per text message. On average, Wendy sends 10 text messages per day. What will it cost Wendy for 100 days of sending text messages at this rate? Give your answer in cents and then convert your answer to dollars.



12 Darren wishes to purchase 10 000 shares at $2.12 per share. Given that there is also an additional $200 brokerage fee, how much will it cost Darren to purchase the shares?

13 | 13, 14 | 14, 15

REASONING

13 The weight of a matchstick is 0.000 15 kg. Find the weight of 10 000 boxes of matches, with each box containing 100 matches. The weight of one empty match box is 0.0075 kg.

14 Complete the table below, listing at least one possible combination of operations that would produce the stated answer from the given starting number.

Starting number	Answer	Possible two-step operations
12.357	1235.7	$\times 1000, \div 10$
34.0045	0.0340045	
0.003 601	360.1	
bac.dfg	*ba.cdfg*	$\div 100, \times 10$
d.swkk	*dswkk*	
fwy	*f.wy*	

15 The number 12 345.6789 undergoes a series of multiplication and division operations by different powers of 10. The first four operations are: $\div$ 1000, $\times$ 100, $\times$ 10 000 and $\div$ 10. What is the fifth and final operation if the final number is 1.234 567 89?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

ENRICHMENT

16 Extremely large numbers and extremely small numbers are often written in a more practical way, known as standard form or scientific notation.

For example, the distance from the Earth to the Sun is 150 000 000 kilometres! The distance of 150 million kilometres can be written in standard form as 1.5×10^8 kilometres.

On a calculator, 150 000 000 can be represented as 1.5E8.

1.5×10^8 and 1.5E8 represent the same large number and indicate that the decimal place needs to be moved 8 places to the right.

$$1.5E8 = 1.5 \times 10^8 = 1.5 \times 100\,000\,000$$
$$= 150000000.$$

a Represent these numbers in standard form.

i 50 000 000 000 000 **ii** 42 000 000 **iii** 12 300 000 000 000 000

b Use a calculator to evaluate the following.

i $40\,000\,000\,000 \times 500\,000\,000$ **ii** $9\,000\,000 \times 120\,000\,000\,000\,000$

c The distance from the Earth to the Sun is stated above as 150 million kilometres. The more precise figure is 149 597 892 kilometres. Research how astronomers can calculate the distance so accurately. Hint: It is linked to the speed of light.

d Carry out further research on very large numbers. Create a list of 10 very large numbers (e.g. distance from Earth to Pluto, the number of grains in 1 kg of sand, the number of stars in the galaxy, the number of memory bytes in a terabyte. . .). Rank your 10 large numbers in ascending order.

e How are very small numbers, such as 0.000000000035, represented in standard form?

f Represent the following numbers in standard form.

i 0.000001 **ii** 0.0000000009 **iii** 0.000000000007653



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

6E Multiplication of decimals









There are countless real-life applications that involve the multiplication of decimal numbers. For example, finding the area of a block of land that is 34.5 m long and 5.2 m wide, or pricing a 4.5-hour job at a rate of $21.75 per hour. In general, the procedure for multiplying decimal numbers is the same as multiplying whole numbers. There is, however, one extra final step, which involves placing the decimal point in the correct position in the answer.



Finding the area of a block of land usually involves multiplying decimals.

Let's start: Multiplication musings

Consider the following questions within your group.

- What happens when you multiply by a number that is less than 1?
- Consider the product of 15×0.75. Will the answer be more or less than 15? Why?
- Estimate an answer to 15×0.75.
- What is the total number of decimal places in the numbers 15 and 0.75?
- Calculate 15×0.75. How many decimal places are there in the answer?

Key ideas

- When multiplying decimals, start by ignoring any decimal points and perform the multiplication as you would normally. On arriving at your answer, now place the decimal point in the correct position.
- The correct position of the decimal point in the answer is found by following the rule that the total number of decimal places in the question must equal the number of decimal places in the answer.

  For example: 5.34×1.2 ← 3 decimal places in the question

$$\begin{array}{r} 534 \\ \times\ 12 \\ \hline 1068 \\ 5340 \\ \hline 6408 \end{array}$$

decimal points ignored here

$5.34 \times 1.2 = 6.408$ 3 decimal places in the answer

- It is always worthwhile estimating your answer. This allows you to check that your decimal point is in the correct place and that your answer makes sense.
- When multiplying by multiples of 10, initially ignore the zeros in the multiplier and any decimal points and perform routine multiplication. On arriving at your answer, position your decimal point, remembering to move your decimal point according to the rules of multiplying by powers of 10.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Multiplying decimals

Calculate:

a 12.31×7 **b** 3.63×6.9

SOLUTION	EXPLANATION
a 1231 × 7 = 8617	Perform multiplication, ignoring decimal point. There are 2 decimal places in the question, so there will be 2 decimal places in the answer.
$12.31 \times 7 = 86.17$	Estimation is less than 100 ($\approx 12 \times 7 = 84$).
b 363 × 69 = 3267 + 21780 = 25047	Ignore both decimal points. Perform routine multiplication. Total of 3 decimal places in the question, so there must be 3 decimal places in the answer.
$3.63 \times 6.9 = 25.047$	Estimation is less than 28 ($\approx 4 \times 7 = 28$).

Example 14 Multiplying decimals by multiples of 10

Calculate:

a $2.65 \times 40\,000$ **b** 0.032×600

SOLUTION	EXPLANATION
a $2.65 \times 40\,000 = 106\,000$ 265 × 4 = 1060 $\therefore 10.60 \times 10\,000 = 106000.$	Ignore the decimal point and zeros. Multiply 265×4. Position the decimal place in your answer. There are 2 decimal places in the question, so must have 2 decimal places in the answer. Move the decimal point 4 places to the right.
b $0.032 \times 600 = 19.2$ 32 × 6 = 192 $\therefore 0.192 \times 100 = 19.2$	Ignore the decimal point and zeros. Multiply 32×6. Position decimal place in the answer. Shift decimal place 2 places to the right because there are two zeros in the question.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 6E

1–5 | 5 | —

UNDERSTANDING

1 Work out the total number of decimal places in each of the following product statements.

a 4×6.3	**b** 3.52×76	**c** 42×5.123
d 8.71×11.2	**e** 5.283×6.02	**f** 2.7×10.3
g 4.87×3241.21	**h** 0.003×3	**i** 0.00103×0.0045

2 Insert the decimal point into each of the following answers so that the multiplication is true.

a $6.4 \times 3 = 192$ **b** $6.4 \times 0.3 = 192$ **c** $0.64 \times 0.3 = 192$

3 Why is it worthwhile to estimate an answer to a multiplication question involving decimals?

4 **a** What is the difference between a decimal point and a decimal place?

b How many decimal points and how many decimal places are in the number 423.1567?

5 Copy and complete the rule for multiplying decimal numbers (see the **Key ideas** in this section).
The total number of decimal places _____ must equal the number of _____ in the answer.

6–8(½) | 6–8(½) | 6–8(½)

FLUENCY

Example 13

6 Calculate:

a 5.21×4	**b** 3.8×7	**c** 22.93×8
d 14×7.2	**e** 3×72.82	**f** 1.293×12
g 3.4×6.8	**h** 5.4×2.3	**i** 0.34×16
j 43.21×7.2	**k** 0.023×0.042	**l** 18.61×0.071

Example 14

7 Calculate:

a 2.52×40	**b** 6.9×70	**c** 31.75×800
d 1.4×7000	**e** 3000×4.8	**f** $7.291 \times 50\,000$
g 0.0034×200	**h** $0.0053 \times 70\,000$	**i** 3.004×30

8 Calculate and then round your answer to the nearest dollar.

a $5 \times \$6.30$	**b** $3 \times \$7.55$	**c** $4 \times \$18.70$
d $\$1.45 \times 12$	**e** $\$30.25 \times 4.8$	**f** $7.2 \times \$5200$
g $34.2 \times \$2.60$	**h** $0.063 \times \$70.00$	**i** $0.085 \times \$212.50$

9, 10 | 10–12 | 11–13

PROBLEM-SOLVING

9 Anita requires 4.21 m of material for each dress she is making. She is planning to make a total of seven dresses. How much material does she need?

10 The net weight of a can of spaghetti is 0.445 kg. Find the net weight of eight cans of spaghetti.

11 Jimbo ran 5.35 km each day for the month of March. How many kilometres did he run for the month?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6E

PROBLEM-SOLVING

12 Bernard is making a cubby house for his children. He needs 32 lengths of timber, each 2.1 m long.

- **a** What is the total length of timber needed to build the cubby house?
- **b** What is the cost of the timber if the price is $2.95 per metre?

13 A lawyer charges $125.00 per hour to assist her client. How much does the lawyer charge the client if she works on the job for 12.25 hours?

	14	14, 15	15–17

REASONING

14 According to its manufacturer, a particular car can travel 14.2 km on 1 litre of petrol.

- **a** How far could the car travel on 52 litres of petrol?
- **b** The car has 23.4 litres of fuel in the tank and must complete a journey of 310 km. Will it make the journey without refuelling?
- **c** If the car does make the journey, how much petrol is left in the tank at the end of the trip? If the car doesn't make the journey, how many extra litres of fuel is needed?

15 Write down two numbers, each with 2 decimal places, that when multiplied by 1.83 will give an answer between 0.4 and 0.5.

16 Write down one number with 4 decimal places that when multiplied by 345.62 will give an answer between 1 and 2.

17 **a** If $68 \times 57 = 3876$, what is the answer to 6.8×5.7? Why?

- **b** If $23 \times 32 = 736$, what is the answer to 2.3×32? Why?
- **c** If $250 \times 300 = 75\,000$, what is the answer to 2.5×0.3? Why?
- **d** What is 7×6? What is the answer to 0.7×0.6? Why?

Creating a simple cash register	—	—	18

ENRICHMENT

18 Using a spreadsheet program, such as Excel, design a user-friendly cash register interface. You must be able to enter up to 10 different items into your spreadsheet. You will need a quantity column and a cost per item column.

Using appropriate formulas, the total cost of the bill should be displayed, and there should then be room to enter the amount of money paid and, if necessary, what change should be given.

When your spreadsheet is set up, enter the following items.

4 chocolate bars @ $1.85 each
3 loaves of bread @ $3.19 each
newspaper @ $1.40
2×2 litres of milk @ $3.70 each
2 packets of Tim Tams @ $3.55 each
Money paid = $80.00
toothpaste @ $4.95
2 kg sausages @ $5.99 per kg
tomato sauce @ $3.20
washing powder @ $8.95
5×1.25 litres of soft drink @ $0.99 each

If your program is working correctly, the amount of change given should be $13.10.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

6F Division of decimals









Similar to multiplication of decimal numbers, there are countless real-life applications that involve the division of decimal numbers. However, unlike multiplying decimal numbers, where we basically ignore the decimal points until the very end of the question, with division we try to manipulate the question in such a way as to prevent dividing by a decimal number.

Terminology reminders

Example: $24 \div 4 = 6$ or $\frac{24}{4} = 6$ or $4\overline{)24}$ with quotient 6

24 is known as the **dividend** (the amount you have, or the number being divided), 4 is known as the **divisor** (the number doing the dividing) and 6 is known as the **quotient** (or the answer).

Let's start: Division decisions

Consider the following questions within your group.

- What happens when you divide by a number that is less than 1?
- Consider the answer of $10 \div 0.2$. Will the answer be more or less than 10? Why?
- Estimate an answer to $10 \div 0.2$.
- Calculate the answer of $100 \div 2$. How does this compare to the answer of $10 \div 0.2$?
- Can you think of an easier way to calculate $21.464 \div 0.02$?

Key ideas

Division of decimal numbers by whole numbers

- Complete as you would normally with any other division question.
- The decimal point in the quotient (answer) goes directly above the decimal point in the dividend.

For example: $60.524 \div 4$

$$4\overline{)60.524} \quad \text{(quotient: } 15.131\text{)}$$

Division of decimal numbers by other decimals

- Change the divisor into a whole number.
- Whatever change is made to the divisor must also be made to the dividend.

For example: $24.562 \div 0.02$

$$24.562 \div 0.02 = 2456.2 \div 2$$

- When dividing by multiples of 10, initially ignore the zeros in the divisor and perform routine division. On arriving at your answer, you must then re-position your decimal point according to the rules of dividing by powers of 10. For each zero in the question that you ignored initially, the decimal point must move 1 place to the left.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 15 Dividing decimals by whole numbers

Calculate:

a $42.837 \div 3$ **b** $0.0234 \div 4$

SOLUTION

a 14.279

$$3\overline{)42.837}$$

b 0.005 85

$$4\overline{)0.0234}$$

EXPLANATION

Carry out division, remembering that the decimal point in the answer is placed directly above the decimal point in the dividend.

Remember to place zeros in the answer every time the divisor 'doesn't go'.
Again, align the decimal place in the answer directly above the decimal place in the question.
An additional zero is required at the end of the dividend to terminate the decimal answer.

Example 16 Dividing decimals by decimals

Calculate:

a $62.316 \div 0.03$ **b** $0.03152 \div 0.002$

SOLUTION

a $62.316 \div 0.03$
$= 6231.6 \div 3 = 2077.2$

$$3\overline{)62.316}$$

b $0.031\,52 \div 0.002$
$= 31.52 \div 2 = 15.76$

$$2\overline{)31.52}$$

EXPLANATION

Need to divide by a whole number.
$62.316 \div 0.03$

Move each decimal point 2 places to the right.
Carry out the division question $6231.6 \div 3$.

Multiply divisor and dividend by 1000.
$0.03152 \div 0.002$

Move each decimal point 3 places to the right.
Carry out the division question $31.52 \div 2$.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 17 Dividing decimals by multiples of 10

Calculate $67.04 \div 8000$.

SOLUTION	EXPLANATION
$8\overline{)67.04}$ gives 08.38 $8.38 \div 1000 = 0.00838$ $67.04 \div 8000 = 0.008\,38$	Ignore the three zeros in the 8000. Divide 67.04 by 8. Now divide by 1000, resulting in moving the decimal point 3 places to the left.

Example 18 Evaluating using order of operations

Calculate using the order of operations:
$3.8 - 1.6 \times 0.45 + 5 \div 0.4$

SOLUTION	EXPLANATION
$3.8 - 1.6 \times 0.45 + 5 \div 0.4$ $= 3.8 - 0.72 + 12.5$ $= 3.08 + 12.5$ $= 15.58$	First carry out $\times$ and $\div$, working from left to right. Then carry out + and –, working from left to right.

Exercise 6F

1–4 | 4 | —

UNDERSTANDING

1 For the question $36.52 \div 0.4 = 91.3$, which of the following options uses the correct terminology?

- **A** 36.52 is the divisor, 0.4 is the dividend and 91.3 is the quotient.
- **B** 36.52 is the dividend, 0.4 is the divisor and 91.3 is the quotient.
- **C** 36.52 is the quotient, 0.4 is the dividend and 91.3 is the divisor.
- **D** 36.52 is the divisor, 0.4 is the quotient and 91.3 is the dividend.

2 Explain where you place the decimal point in the quotient (i.e. answer), when dividing a decimal by a whole number.

3 Calculate:

a $1200 \div 20$ **b** $120 \div 2$ **c** $12 \div 0.2$ **d** $1.2 \div 0.02$

e Explain why these questions all give the same answer.

4 For each of the following pairs of numbers, move the decimal points the same number of places so that the second number becomes a whole number.

a 3.2456, 0.3 **b** 120.432, 0.12

c 0.003 45, 0.0001 **d** 1234.12, 0.004

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F

5–6(½), 7, 8(½) | 5–6(½), 8–9(½) | 5–6(½), 7, 8–9(½)

FLUENCY

Example 15

5 Calculate:

a $8.4 \div 2$ **b** $30.5 \div 5$ **c** $64.02 \div 3$

d $2.822 \div 4$ **e** $4.713 \div 3$ **f** $2.156 \div 7$

g $38.786 \div 11$ **h** $1491.6 \div 12$ **i** $0.0144 \div 6$

j $234.21 \div 2$ **k** $3.417 \div 5$ **l** $0.010\,25 \div 4$

Example 16

6 Calculate:

a $6.14 \div 0.2$ **b** $23.25 \div 0.3$ **c** $2.144 \div 0.08$

d $5.1 \div 0.6$ **e** $0.3996 \div 0.009$ **f** $45.171 \div 0.07$

g $0.0032 \div 0.04$ **h** $0.040\,34 \div 0.8$ **i** $10.78 \div 0.011$

j $4.003 \div 0.005$ **k** $0.948 \div 1.2$ **l** $432.2 \div 0.0002$

7 Design three decimal division questions for your partner. Make sure you calculate the answer to each question. Swap questions with your partner. Go to work solving your partner's questions. Pass your answers back for your partner to correct. Discuss any mistakes made by either person.

Example 17

8 Calculate:

a $236.14 \div 200$ **b** $413.35 \div 50$ **c** $3.712\,44 \div 300$

d $0.846 \div 200$ **e** $482.435 \div 5000$ **f** $0.0313 \div 40$

9 Calculate the following, rounding your answers to 2 decimal places.

a $35.5 \text{ kg} \div 3$ **b** $\$213.25 \div 7$ **c** $182.6 \text{ m} \div 0.6 \text{ m}$

d $287 \text{ g} \div 1.2$ **e** $482.523 \text{ L} \div 0.5$ **f** $\$5235.50 \div 9$

10(½), 11 | 10(½), 11–13 | 13–15

PROBLEM-SOLVING

Example 18

10 Calculate the following, using the order of operations.

a $3.68 \div 2 + 5.7 \div 0.3$ **b** $6(3.7 \times 2.8 + 5.2)$

c $17.83 - 1.2(8.1 - 2.35)$ **d** $9.81 \div 0.9 + 75.9 \div 10$

e $(56.7 - 2.4) \div (0.85 \div 2 + 0.375)$ **f** $34.5 \times 2.3 + 15.8 \div (0.96 - 0.76)$

11 Find the missing digits in these division questions.

a $3\overline{)2.\ 6\ 7}$ gives $0.\square\square$

b $3\overline{)1.\square\ 2}$ gives $0.\ 6\ 4$

c $\square\overline{)10.7\square}$ gives $2.\square 5$

d $\square\overline{)15.\square\ 2\ 9}$ gives $2.\ 1\ 4\square$

12 Charlie paid \$12.72 to fill his ride-on lawnmower with 8 L of fuel. What was the price per litre of the fuel that he purchased?

13 Dibden is a picture framer and has recently purchased 214.6 m of timber. The average-sized picture frame requires 90 cm (0.9 m) of timber. How many average picture frames could Dibden make with his new timber?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F

PROBLEM-SOLVING

14 A water bottle can hold 600 mL of water. How many water bottles can be filled from a large drink container that can hold 16 L?

15 Six friends go out for dinner. At the end of the evening, the restaurant's bill is $398.10.
- **a** As the bill is split equally among the six friends, how much does each person pay?
- **b** Given that they are happy with the food and the service, they decide to round the amount they each pay to $70. What is the waiter's tip?

	16	16, 17	17, 18

REASONING

16 Clara purchases 1.2 kg of apples for $3.90. Her friend Sophia buys 900 g of bananas for $2.79 at the same shop. Find the cost per kilogram of each fruit. Which type of fruit is the best value in terms of price per kilogram?

17 A police radar gun measures a car to be 231.5 m away. At 0.6 seconds later, the radar gun measures the same car to be 216.8 m away.
- **a** Determine the speed of the car in metres per second (m/s).
- **b** Multiply your answer to part **a** by 3.6 to convert your answer to km/h.
- **c** The car is travelling along an 80 km/h stretch of road. Is the car speeding?



18 Given that $24.53 \times 1.97 = 48.3241$, write down the value of each of the following questions, without using a calculator.

a $48.3241 \div 1.97$	**b** $48.3241 \div 2.453$	**c** $4832.41 \div 1.97$
d $483.241 \div 245.3$	**e** $0.483\,241 \div 0.197$	**f** $483\,241 \div 2453$

What number am I?	—	—	19

ENRICHMENT

19 I am thinking of a number. Given the following clues for each, find the number.
- **a** When I add 4.5 and then multiply by 6, the answer is 30.
- **b** When I divide it by 3 and then add 2.9, the answer is 3.
- **c** When I multiply it by 100 and then add 9, the answer is 10.
- **d** When I multiply it by 5 and then add a half, the answer is 6.
- **e** When I subtract 0.8, then divide by 0.2 and then divide by 0.1, the answer is 200.
- **f** Make up three of your own number puzzles to share with the class.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

6A **1** What is the place value of the digit 6 in the following numbers?

a 3.5678 **b** 126.872

6A **2** Express each of the following fractions as a decimal.

a $\frac{9}{10}$ **b** $\frac{19}{1000}$ **c** $3\frac{1}{4}$

6A **3** Arrange the following decimal numbers in ascending order.

3.4, 4.3, 0.43, 0.34, 0.043

6B **4** Round each of the following to the specified number of decimal places.

a 16.8765 to 2 decimal places **b** 2.34999 to 3 decimal places

c $0.6\dot{6}$ to 1 decimal place

6C **5** Find:

a $0.9 + 4.5$ **b** $12.56 + 3.671 + 0.8$

c $12.89 - 9.37$ **d** $8.06 - 2.28$

6D **6** Evaluate:

a 3.45×1000 **b** $65.345 \div 100$

6E/F **7** Calculate:

a 45×2000 **b** 23.8×5 **c** 4.78×0.4 **d** $4.56 \times 30\,000$

e $56.4 \div 4$ **f** $0.065 \div 5$ **g** $3.864 \div 0.02$ **h** $88.4 \div 400$

i $9 \div 0.001$ **j** $3.4 - 3.2 \times 0.4 + 1.2 \div 3$

6C/E **8** Insert the decimal point in the answer so that each mathematical sentence is true.

a $12 - 3.989 = 8011$ **b** $1.234 \times 0.08 \times 2000 = 19744$

6C–F **9** It costs \$59.85 for 15 kilograms of dog shampoo. Find:

a the change from paying with one \$50 note and one \$20 note

b the cost of the shampoo per kilogram

c the number of kilograms that can be purchased with a \$100 note

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6G Decimals and fractions

Interactive

Widgets

HOTsheets

Walkthroughs

Decimals and fractions are both commonly used to represent numbers that are not simply whole numbers. It is important that we know how to convert a decimal number to a fraction, and how to convert a fraction to a decimal number.

In the photo opposite, we can see that

$\frac{1}{4}$ or 0.25 of the cake has been cut and

$\frac{3}{4}$ or 0.75 of the cake remains.



Let's start: Match my call

- In pairs, nominate one student to be 'Fraction kid' and the other to be 'Decimal expert'. 'Fraction kid' starts naming some common fractions and 'Decimal expert' tries to give the equivalent decimal value. Start with easy questions and build up to harder ones.
- After 10 turns, swap around. This time 'Decimal expert' will name some decimal numbers and 'Fraction kid' will attempt to call out the equivalent fraction.
- Discuss the following question in pairs:
  Which is easier, converting fractions to decimals or decimals to fractions?

Key ideas

Converting decimals to fractions

- Using your knowledge of place value, express the decimal places as a fraction whose denominator is a power of 10. Remember to simplify the fraction whenever possible.

e.g. $0.25 = \frac{25}{100} = \frac{1}{4}$

Converting fractions to decimals

- When the denominator is a power of 10, we can simply change the fraction to a decimal through knowledge of place value.

e.g. $\frac{37}{100} = 0.37$

- When the denominator is *not* a power of 10, try to find an equivalent fraction whose denominator has a power of 10 and then convert to a decimal.

e.g. $\frac{2}{5} = \frac{4}{10} = 0.4$

- A method that will always work for converting fractions to decimals is to divide the numerator by the denominator.

e.g. $\frac{5}{8} = 8\overline{)5.000}\ \begin{matrix}0.625\\ 5\,2\,4\end{matrix} = 0.625$

Recurring decimals are decimals with a repeated pattern.

- A dot, dots or a bar above a number or numbers indicates a repeated pattern.

e.g. $\frac{1}{3} = 0.333\,33\ldots = 0.\dot{3}$ $\qquad \frac{13}{11} = 1.181\,818\ldots = 1.\dot{1}\dot{8}$ or $1.\overline{18}$

$\frac{12}{7} = 1.714\,285\,714\,285\ldots = 1.\dot{7}14\,285\dot{}$ or $1.\overline{714\,285}$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 19 Converting decimals to fractions

Convert the following decimals to fractions in their simplest form.

a 0.239 **b** 10.35

SOLUTION	EXPLANATION
a $\frac{239}{1000}$	0.239 = 239 thousandths
b $10\frac{35}{100} = 10\frac{7}{20}$.	0.35 = 35 hundredths, which can be simplified further by dividing the numerator and denominator by the highest common factor of 5.



Example 20 Converting fractions to decimals

Convert the following fractions to decimals.

a $\frac{17}{100}$ **b** $5\frac{3}{5}$ **c** $\frac{7}{12}$

SOLUTION	EXPLANATION
a $\frac{17}{100} = 0.17$	17 hundredths
b $5\frac{3}{5} = 5\frac{6}{10} = 5.6$	$\frac{6}{10}$ is an equivalent fraction of $\frac{3}{5}$, whose denominator is a power of 10.
c $\frac{7}{12} = 0.583\,33\ldots$ or $0.58\dot{3}$	$12\overline{)7.00\,000}$ $0.58333\ldots$, $70\,40\,40\,40$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 6G

1, 2 | 2 | —

UNDERSTANDING

1 Complete each of these statements, which convert common fractions to decimals.

a $\frac{1}{2} = \frac{\square}{10} = 0.5$

b $\frac{1}{4} = \frac{25}{\square} = 0.25$

c $\frac{3}{4} = \frac{\square}{100} = 0.\square 5$

d $\frac{2}{\square} = \frac{4}{10} = 0.\square$

2 Complete each of these statements, which convert decimals to fractions, in simplest form.

a $0.2 = \frac{\square}{10} = \frac{1}{5}$

b $0.15 = \frac{\square}{100} = \frac{3}{\square}$

c $0.8 = \frac{8}{\square} = \frac{\square}{5}$

d $0.64 = \frac{64}{100} = \frac{\square}{25}$

3–7(½) | 3–8(½) | 3–8(½)

FLUENCY

Example 19a **3** State whether each of the following is true or false. Use the examples in the **Key ideas** to help.

a $0.333\ldots = 0.3$ **b** $0.1111\ldots = 0.\dot{1}$ **c** $3.2222\ldots = 3.\dot{2}$

d $1.727\,2\ldots = 1.7\dot{2}$ **e** $3.161\,616\ldots = 3.1\dot{6}$ **f** $4.216\,216\ldots = 4.\overline{216}$

Example 19b **4** Convert the following decimals to fractions in their simplest form.

a 0.5 **b** 6.4 **c** 10.15 **d** 18.12

e 3.25 **f** 0.05 **g** 9.075 **h** 5.192

Example 20a **5** Convert each of these fractions to decimals.

a $\frac{7}{10}$ **b** $\frac{9}{10}$ **c** $\frac{31}{100}$ **d** $\frac{79}{100}$

e $\frac{121}{100}$ **f** $3\frac{29}{100}$ **g** $\frac{123}{1000}$ **h** $\frac{3}{100}$

Example 20b **6** Convert the following fractions to decimals, by first changing the fraction to an equivalent fraction whose denominator is a power of 10.

a $\frac{4}{5}$ **b** $\frac{1}{2}$ **c** $\frac{7}{20}$ **d** $\frac{23}{50}$

e $\frac{19}{20}$ **f** $3\frac{1}{4}$ **g** $\frac{5}{2}$ **h** $\frac{3}{8}$

Example 20c **7** Convert the following fractions to decimals, by dividing the numerator by the denominator.

a $\frac{1}{2}$ **b** $\frac{3}{6}$ **c** $\frac{3}{4}$ **d** $\frac{2}{5}$

e $\frac{1}{3}$ **f** $\frac{3}{8}$ **g** $\frac{5}{12}$ **h** $\frac{3}{7}$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6G

FLUENCY

8 Copy and complete the following fraction/decimal tables. The quarters table (part **c**) has already been done for you. It's well worth trying to memorise these fractions and their equivalent decimal values.

a halves

Fraction	$\frac{0}{2}$	$\frac{1}{2}$	$\frac{2}{2}$
Decimal			

b thirds

Fraction	$\frac{0}{3}$	$\frac{1}{3}$	$\frac{2}{3}$	$\frac{3}{3}$
Decimal				

c quarters

Fraction	$\frac{0}{4}$	$\frac{1}{4}$	$\frac{2}{4}$	$\frac{3}{4}$	$\frac{4}{4}$
Decimal	0	0.25	0.5	0.75	1

d fifths

Fraction	$\frac{0}{5}$	$\frac{1}{5}$	$\frac{2}{5}$	$\frac{3}{5}$	$\frac{4}{5}$	$\frac{5}{5}$
Decimal						

9–10 9–10 10–11

PROBLEM-SOLVING

9 Arrange the following from smallest to largest.

a $\frac{1}{2}, 0.75, \frac{5}{8}, 0.4, 0.99, \frac{1}{4}$

b $\frac{3}{7}, 0.13, \frac{1}{9}, 0.58, 0.84, \frac{4}{5}$

10 Tan and Lillian are trying to work out who is the better chess player. They have both been playing chess games against their computers. Tan has played 37 games and beaten the computer 11 times. Lillian has played only 21 games and has beaten the computer 6 times.

a Using a calculator and converting the appropriate fractions to decimals, determine who is the better chess player.

b Lillian has time to play another four games of chess against her computer. To be classified as a better player than Tan, how many of these four games must she win?



11 To estimate the thickness of one sheet of A4 paper, Christopher measures a ream of paper, which consists of 500 sheets of A4 paper. He determines that the pile is 55 mm thick. How thick is one sheet of A4 paper? Express your answer as a decimal number and also as a fraction.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6G

12 | 12–13 | 13–15

REASONING

12 a Copy and complete the following fraction/decimal table.

Fraction	$\frac{1}{2}$	$\frac{1}{3}$	$\frac{1}{4}$	$\frac{1}{5}$	$\frac{1}{6}$	$\frac{1}{7}$	$\frac{1}{8}$	$\frac{1}{9}$	$\frac{1}{10}$
Decimal									

b Comment on the trend in the decimal values as the *denominator* increases.

c Try to explain why this makes sense.

13 a Copy and complete the following decimal/fraction table.

Decimal	0.1	0.2	0.25	0.4	0.5	0.6	0.75	0.8	0.9
Fraction									

b Comment on the trend in the fractions as the *decimal value* increases.

c Try to explain why this makes sense.

14 Write three different fractions with different denominators that are between the decimal value of 2.4 and 2.5.

15 When $\frac{4}{7}$ is expressed in decimal form, find the digit in the 23rd decimal place. Give a reason for your answer.

Design a decimal game for the class — | — | 16

ENRICHMENT

16 Using the skill of converting decimals to fractions and vice versa, design an appropriate game that students in your class could play. Ideas may include variations of Bingo, Memory, Dominoes etc. Try creating a challenging set of question cards.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6H Decimals and percentages

Interactive

Widgets

HOTsheets

Walkthroughs

Percentages are commonly used in today's society. **Per cent** is derived from the Latin words *per centum*, meaning 'out of 100'.




We see percentages used around us in many different situations.

Percentages give an idea of proportion. For example, if a newspaper states that 2000 people want a council swimming pool constructed, then we know how many want a pool but we don't know what proportion of the community that is. However, if there are 2500 people in this community, the newspaper can state that 80% want a swimming pool. This informs us that a majority of the community (i.e. 80 out of every 100 people) want a swimming pool constructed.

Let's start: Creative shading

- Draw a square of side length 10 cm and shade exactly 20% or 0.2 of this figure.
- Draw a square of side length 5 cm and shade exactly 60% or 0.6 of this figure.
- Draw another square of side length 10 cm and creatively shade an exact percentage of the figure. Ask your partner to work out the percentage you shaded.


What percentage is shaded?

Key ideas

- The symbol, **%**, means **per cent**. It comes from the Latin words *per centum*, which translates to 'out of 100'.
  For example: 23% means 23 out of 100 $\frac{23}{100} = 0.23$
- To convert a percentage to a decimal, divide by 100. This is done by moving the decimal point 2 places to the left.
  For example: $42\% = 42 \div 100 = 0.42$.
- To convert a decimal to a percentage, multiply by 100. This is done by moving the decimal point 2 places to the right.
  For example: $0.654 \times 100 = 65.4$. Therefore $0.654 = 65.4\%$
  Note: As in Section 6D, it is not actually the decimal point that moves; rather, it is the digits that move around the stationary decimal point.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 21 Converting percentages to decimals

Express the following percentages as decimals.

a 30% **b** 240% **c** 12.5% **d** 0.4%

SOLUTION	EXPLANATION
a 30% = 0.3	30 ÷ 100
b 240% = 2.4	240 ÷ 100 = 2.4
c 12.5% = 0.125	Decimal point moves 2 places to the left.
d 0.4% = 0.004	Decimal point moves 2 places to the left.

Example 22 Converting decimals to percentages

Express the following decimals as percentages.

a 0.045 **b** 7.2

SOLUTION	EXPLANATION
a 0.045 = 4.5%	Multiplying by 100 moves the decimal point 2 places to the right.
b 7.2 = 720%	Multiply 7.2 by 100.


Exercise 6H

1–6 | 5, 6 | —


UNDERSTANDING

1 What percentage of each square has been shaded?

a




b




Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c



d



2 72.5% is equivalent to which of the following decimals?

A 72.5 **B** 7.25 **C** 0.725 **D** 725.0

3 1452% is equivalent to which of the following decimals?

A 0.1452 **B** 14.52 **C** 145 200 **D** 145.20

4 0.39 is equivalent to which of the following percentages?

A 39% **B** 3.9% **C** 0.39% **D** 0.0039%

5 Prue answered half the questions correctly for a test marked out of 100.

a What score did Prue get on the test?

b What percentage did Prue get on the test?

c Find the score you would expect Prue to get if the test was out of:

i 10 **ii** 200

iii 40 **iv** 2

d Find the percentage you would expect Prue to get if the test was out of:

i 10 **ii** 200

iii 40 **iv** 2

6 Fill in the empty boxes.

a 58% = 58 out of $\square$ = 58 $\square$ 100 = $\frac{58}{\square}$ = 0 $\square$ 58

b 35% = $\square$ out of 100 = 35 ÷ $\square$ = $\frac{\square}{100}$ = $\square$.35

c 126% = 126 __ __ 100 = $\square$ ÷ 100 = $\frac{126}{\square}$ = 1.$\square$ $\square$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

6H

7–9(½) | 7–9(½) | 7–9(½)

FLUENCY

Example 21a, b

7 Express the following percentages as decimals.

a 32%	**b** 27%	**c** 68%	**d** 54%
e 6%	**f** 9%	**g** 100%	**h** 1%
i 218%	**j** 142%	**k** 75%	**l** 199%

Example 21c, d

8 Express the following percentages as decimals.

a 22.5%	**b** 17.5%	**c** 33.33%	**d** 8.25%
e 112.35%	**f** 188.8%	**g** 150%	**h** 520%
i 0.79%	**j** 0.025%	**k** 1.04%	**l** 0.95%

Example 22

9 Express the following decimals as percentages.

a 0.8	**b** 0.3	**c** 0.45	**d** 0.71
e 0.416	**f** 0.375	**g** 2.5	**h** 2.314
i 0.025	**j** 0.0014	**k** 12.7	**l** 1.004

10, 11 | 11,12 | 12,13

PROBLEM-SOLVING

10 Place the following values in order from highest to lowest.

a 86%, 0.5%, 0.6, 0.125, 22%, 75%, 2%, 0.78

b 124%, 2.45, 1.99%, 0.02%, 1.8, 55%, 7.2, 50

11 At a hockey match, 65% of the crowd supports the home team. What percentage of the crowd supports the visiting team?

12 Last Saturday, Phil spent the 24 hours of the day in the following way: 0.42 of the time was spent sleeping, 0.22 was spent playing sport and 0.11 was spent eating. The only other activity Phil did for the day was watch TV.

a What percentage of the day did Phil spend watching TV?

b What percentage of the day did Phil spend either sitting down or lying down?

13 Sugarloaf Reservoir has a capacity of 96 gigalitres. However, as a result of the drought it is only 25% full. How many gigalitres of water are in the reservoir?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6H

14 | 14, 15 | 15, 16

REASONING

14 a, b, c and d are digits. Write the following decimal numbers as percentages.

a $0.abcd$ **b** $a.ac$ **c** $ab.dc$

d $0.0dd$ **e** $c.dba$ **f** $0.cccddd$

15 a, b, c and d are digits. Write the following percentages as decimal numbers.

a $a.b\%$ **b** $bcd\%$ **c** $ac\%$

d $0.da\%$ **e** $abbb\%$ **f** $dd.d\%$

16 Trudy says that it is impossible to have more than 100%. She supports her statement by saying that if you get every question correct in a test, then you get 100% and you cannot get any more.

a Do you agree with Trudy's statement?

b Provide four examples of when it makes sense that you cannot get more than 100%.

c Provide four examples of when it is perfectly logical to have more than 100%.

ENRICHMENT

AFL ladder — | — | 17, 18

17 The Australian Rules football ladder has the following column headings.

Pos	Team	P	W	L	D	F	A	%	Pts
6	Brisbane Lions	22	13	8	1	2017	1890	106.72	54
7	Carlton	22	13	9	0	2270	2055	110.46	52
8	Essendon	22	10	11	1	2080	2127	97.79	42
9	Hawthorn	22	9	13	0	1962	2120	92.55	36
10	Port Adelaide	22	9	13	0	1990	2244	88.68	36

a Using a calculator, can you determine how the percentage column is calculated?

b What do you think the 'F' and the 'A' column stand for?

c In their next match, Essendon scores 123 points for their team and has 76 points scored against them. What will be their new percentage?

d By how much do Hawthorn need to win their next game to have a percentage of 100?

e If Port Adelaide plays Hawthorn in the next round and the final score is Port Adelaide 124 beats Hawthorn 71, will Port Adelaide's percentage become higher than Hawthorn's?

18 Create your own AFL-style ladder using a spreadsheet program. After inputting the results, the program should automatically update the points column and the percentage column.
When carrying out a sort on the data, ensure that your program will automatically change any team's position on the ladder, if necessary.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Best buy

The concept 'best buy' relates to purchasing a product that is the best value for money.
To determine the 'best buy' you need to compare the prices of similar products for the same weight.



STRAWBERRY JAM jar 375 g
$3.95
$10.53 per kg



STRAWBERRY JAM jar 250 g
$2.95
$11.80 per kg

Converting units

a Convert the following to a price per kg.
- **i** 2 kg of apples for $3.40
- **ii** 5 kg of sugar for $6.00
- **iii** 1.5 kg of cereal for $4.50
- **iv** 500 g of butter for $3.25

b Convert the following to a price per 100 g.
- **i** 300 g of grapes for $2.10
- **ii** 1 kg of cheese for $9.60
- **iii** 700 g of yogurt for $7.49
- **iv** 160 g of dip for $3.20

Finding 'best buys'

a By converting to a price per kg, determine which is the best buy.
- **i** 2 kg of sauce A for $5.20 or 1 kg of sauce B for $2.90
- **ii** 4 kg of pumpkin A for $3.20 or 3 kg of pumpkin B for $2.70
- **iii** 500 g of honey A for $5.15 or 2 kg of honey B for $19.90
- **iv** 300 g of milk A for $0.88 or 1.5 kg of milk B for $4.00

b By converting to a price per 100 g, determine which is the best buy.
- **i** 500 g of paper A for $3.26 or 200 g of paper B for $1.25
- **ii** 250 g of salami A for $4.50 or 150 g of salami B for $3.10
- **iii** 720 g of powder A for $3.29 or 350 g of powder B for $1.90
- **iv** 1.1 kg of shampoo A for $12.36 or 570 g of shampoo B for $6.85

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Problem solving

a Star Washing Liquid is priced at $3.85 for 600 g, while Best Wash Liquid is priced at $5.20 for 1 kg. Find the difference in the price per 100 g, correct to the nearest cent.

b Budget apples cost $6.20 per 5 kg bag. How much would a 500 g bag of Sunny apples have to be if it was the same price per 100 g?

c 1.5 kg of cheddar cheese costs $11.55, and 800 g of feta cheese costs $7.25. Sally works out the best value cheese, then buys $5 worth of it. How much and what type of cheese did Sally buy?

Investigate

Go to a local supermarket and choose a type of product where there are many brands to choose from.

a Record the following information for each brand of the same type of product:
- **i** price
- **ii** weight
- **iii** brand name

b Calculate the price of each brand per:
- **i** kg
- **ii** 100 g

c Compare the prices of each brand. Comment on:
- **i** which brand is the 'best buy'
- **ii** the differences between the cheapest and most expensive brands
- **iii** reasons why some brands might be more expensive

d Most supermarkets now display an additional price for most items: the cost of the item per set amount. In effect, this allows the customer to see the best value. Take a photo of an item at a supermarket which displays this value and explain the prices.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Decimal vs percentage

Draw two horizontal lines on a long sheet of graph paper that is 100 small squares wide. On line 1, make a number line from 0 to 1, labelling every tenth and marking hundredths. On line 2, mark percentages from 0% to 100%, labelling every 10% and marking every %.

Example of the number lines



Answer the following questions, using your number lines to help you.

a Which is larger, 73% or 0.74?

b Which is smaller, 26% or 0.3?

c List in ascending order: 45%, 0.72, 49%, 37%, 0.58, 0.7, 51%, 0.64, 60%, 0.5.

d List in descending order: 37%, 0.03, 82%, 0.37, 0.8, 77%, 0.23, 38%, 2%, 0.4.

e List in ascending order: 78%, 0.683, 77.5%, 79.9%, 0.78452, 0.76, 0.784, 69.9%, 0.6885.

f Write three decimal numbers between 0.47 and 0.57.

g In decimal form, list all the whole tenths that are greater than 0.34 and less than 0.78.

h In decimal form, list all the decimal hundredths that are greater than 0.32 and less than 0.41.

i Write down three pairs of decimals so that each pair has a difference of 0.02. Now write each of your number pairs as percentages. What is the difference between these percentage values?

j Play some decimal/percentage games in pairs.

- Person A gives a decimal (between 0 and 1) and person B states the percentage that is equivalent to two-tenths less than person A's decimal.
- Person A states a percentage and person B gives the decimal that is equivalent to 5% more than person A's percentage.
- Use your decimal and percentage number lines to make up your own games.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 **a** When $\frac{3}{7}$ is written as a decimal, state the digit in the 20th decimal place.

b Given that $A \times 2.75 = 10.56$, write an expression for $1.056 \div 0.00275$.


c Find this product:

$$(1 - 0.5)(1 - 0.\dot{3})(1 - 0.25)(1 - 0.2)$$

d Write the recurring decimal $1.4\overline{51}$ as an improper fraction.

e Callum pays $4.10 for his coffee using eight coins. They are made up of $1 coins and 50 and 20 cent pieces. How many of each coin did Callum use?

2 Consider the ladder in the diagram. The heights of each rung on the ladder are separated by an equal amount. Determine the heights for each rung of the ladder.



3 Find the digits represented by the letters in these decimal problems.

a
$$\begin{array}{r} \text{A}.2\text{B} \\ +\ 9.\text{C}5 \\ \hline 11.12 \end{array}$$

b
$$\begin{array}{r} 2\text{A}.43 \\ -\ 9.\text{B}4 \\ \hline \text{C}7.8\text{D} \end{array}$$

c $3.\text{A} \times \text{B}.4 = 8.16$

d $\text{A}\overline{)2.2\text{B}1}$ $\quad 0.757$

4 We know that $\sqrt{9}$ is 3 since $3^2 = 9$, but what about $\sqrt{2}$?

a Find the value of:

i 1.4^2 **ii** 1.5^2 **iii** 1.45^2


b Now try to find the value of $\sqrt{2}$ correct to:

i two decimal places

ii three decimal places

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter summary



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

6A **1** The next number in the pattern 0.023, 0.025, 0.027, 0.029 is:
A 0.0003 **B** 0.030 **C** 0.0031 **D** 0.031 **E** 0.033

6G **2** 0.05 is equivalent to:
A $\frac{5}{10}$ **B** $\frac{5}{100}$ **C** $\frac{5}{1000}$ **D** $\frac{5}{500}$ **E** 5

6A **3** The smallest number out of 0.012, 10.2, 0.102, 0.0012 and 1.02 is:
A 0.012 **B** 0.102 **C** 0.0012 **D** 1.02 **E** 10.2

6F **4** $0.36 \div 1000$ is equal to:
A 3.6 **B** 360 **C** 0.036 **D** 0.0036 **E** 0.000 36

6E **5** 6.2×0.2 is equal to:
A 1.24 **B** 12.4 **C** 0.124 **D** 124 **E** 0.0124

6E **6** What is the answer to 0.08×0.6?
A 0.48 **B** 4.8 **C** 0.0048 **D** 0.048 **E** 48

6B **7** When rounded to 1 decimal place, 84.553 becomes:
A 80 **B** 84 **C** 84.5 **D** 84.6 **E** 84.55

6G **8** As a decimal, $\frac{23}{90}$ is equal to:
A 0.2 **B** $0.2\dot{5}$ **C** 0.26 **D** $0.\dot{2}\dot{5}$ **E** $0.25\dot{6}$

6A/B **9** $7 + 0.7 + 0.07 + 0.007$, to 2 decimal places, is:
A 7.78 **B** 7.77 **C** 7 **D** 7.7 **E** 7.777

6G **10** $5.\overline{624}$ means:
A 5.62444… **B** 6.6242424… **C** 5.624624624…
D 5.6246464… **E** 5.62456245624…

Short-answer questions

6A **1** Arrange each group in descending order, from largest to smallest.
a 0.4, 0.04, 0.44 **b** 2.16, 2.016, 2.026 **c** 0.932, 0.98, 0.895

6G **2** Write each fraction as a decimal.
a $\frac{81}{10}$ **b** $\frac{81}{100}$ **c** $\frac{801}{100}$ **d** $\frac{801}{1000}$

6A **3** What is the place value of the digit 3 in the following numbers?
a 12.835 **b** 6.1237 **c** 13.5104

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

6A **4** State whether each of the following is true or false.

a $8.34 < 8.28$ **b** $4.668 > 4.67$ **c** $8.2 > 8.182$

d $3.08 \leq \frac{308}{100}$ **e** $\frac{62}{100} \geq 6.20$ **f** $\frac{7}{10} = \frac{70}{100}$

6B **5** List all possible numbers with 3 decimal places that, when rounded to 2 decimal places, always result in 45.27.

6B **6** Round each of the following to the specified number of decimal places (which is given in brackets).

a 423.46 (1) **b** 15.8892 (2) **c** 7.25432 (1)

d 69.999531 (3) **e** $2\frac{3}{4}$ (1) **f** $\frac{2}{3}$(2)

g $\frac{5}{11}$ (3) **h** $\frac{1}{81}$ (44) (Hint: Look for the short method!)

6C **7** Evaluate:

a $13.85 - 4.32$ **b** $19.12 - 14.983$

c $27.6 + 15.75$ **d** $204.708\,37 + 35.7902$

e $472.427 - 388.93$ **f** $210.8 - (26.3 - 20.72)$

6A/B/D **8** State whether each of the following is true or false.

a $10.34 \div 100 = 0.1034$ **b** $3.125 \times 0.1 = 31.25$

c $115.23 \div 10 = 1.1523 \times 1000$ **d** 115.23 has 3 decimal places

e 24.673 = 24.7 when rounded to 1 decimal place

6E **9** State the number of decimal places in each answer to these calculations.

a A number with 2 decimal places × a number with 3 decimal places.

b A number with 1 decimal place × a number with 4 decimal places.

c A number with 2 decimal places × a number with 2 decimal places.

d A number with 2 decimal places × a number with 0 decimal places.

6D **10** Solve each of the following, using the order of operations.

a 1.37×100 **b** 0.79×1000

c $225.1 \div 10$ **d** $96.208 \div 1000$

e $75.68 + 6.276 \times 100 - 63.24 \div 10$ **f** $3.56 \times 100 + 45 \div 10$

g $100 \times (56.34 \times 100 + 0.893)$

6E/F **11** Calculate the following.

a 2.4×8 **b** 9×7.11 **c** 2.3×8.4

d $3.8 \div 4$ **e** $12.16 \div 8$ **f** $3 \div 0.5$

g $4 \div 0.25$ **h** $1.2 \div 0.4$ **i** $3.42 \div 1.1$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6F/G/H **12** Copy and complete this table, stating fractions both with the denominator 100 and in their simplest form.

Decimal	Fraction	Percentage
0.45		
	$\frac{?}{100} = \frac{7}{10}$	
		32%
0.06		
	$\frac{79}{100}$	
1.05		
	$\frac{?}{100} = \frac{7}{20}$	
		65%
	$\frac{?}{1000} = \frac{1}{8}$	

Extended-response questions

1 Find the answer in these practical situations.

- **a** Jessica is paid $125.70 for 10 hours of work and Jaczinda is paid $79.86 for 6 hours of work. Who receives the higher rate of pay per hour, and by how much?
- **b** Petrol is sold for 124.9 cents per litre. Jacob buys 30 L of petrol for his car. Find the total price he pays, to the nearest 5 cents.
- **c** The Green family are preparing to go to the Great Barrier Reef for a holiday. For each of the four family members, they purchase a goggles and snorkel set at $37.39 each, fins at $18.99 each and rash tops at $58.48 each. How much change is there from $500?
- **d** For her school, a physical education teacher buys 5 each of basketballs, rugby union and soccer balls. The total bill is $711.65. If the rugby balls cost $38.50 each and the basketballs cost $55.49 each, what is the price of a soccer ball?

2 A car can use 25% less fuel per km when travelling at 90 km/h than it would when travelling at 110 km/h. Janelle's car uses 7.8 litres of fuel per 100 km when travelling at 110 km/h, and fuel costs 155.9 cents per litre.

- **a** How much money could Janelle save on a 1000-km trip from Sydney to Brisbane if she travels at a constant speed of 90 km/h instead of 110 km/h?
- **b** During a 24-hour period, 2000 cars travel the 1000-km trip between Sydney and Brisbane. How much money could be saved if 30% of these cars travel at 90 km/h instead of 110 km/h?

3 Siobhan is on a 6-week holiday in the United Kingdom, and is using her phone to keep in contact with her friends and family in Australia. The phone charge for voice calls is $0.40 'flagfall' and $0.65 per 45 seconds; text messages are $0.38 each.
During her holiday, Siobhan makes 27 voice calls and sends 165 text messages to Australia. If her phone bill is $832.30, determine the average length of Siobhan's voice calls.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Semester review 1

Whole numbers

Multiple-choice questions

1 Using numerals, thirty-five thousand, two hundred and six is:

A 350 260 **B** 35 260 **C** 35 000 206 **D** 3526 **E** 35 206

2 The place value of 8 in 2 581 093 is:

A 8 thousand **B** 80 thousand **C** 8 hundred **D** 8 tens **E** 8 ones

3 The remainder when 23 650 is divided by 4 is:

A 0 **B** 4 **C** 1 **D** 2 **E** 3

4 $18 - 3 \times 4 + 5$ simplifies to:

A 65 **B** 135 **C** 11 **D** 1 **E** 20

5 $800 \div 5 \times 4$ is the same as:

A 160×4 **B** $800 \div 20$ **C** $800 \div 4 \times 5$ **D** 40 **E** $4 \times 5 \div 800$

Short-answer questions

1 Write the number seventy-four in:

a Babylonian numerals

b Roman numerals

c Egyptian numerals

2 Write the numeral for:

a $6 \times 10\,000 + 7 \times 1000 + 8 \times 100 + 4 \times 10 + 9 \times 1$

b $7 \times 100\,000 + 8 \times 100 + 5 \times 10$

3 Calculate:

a $96\,481 + 2760 + 82$ **b** $10\,963 - 4096$ **c** 147×3

d 980×200 **e** $4932 \div 3$ **f** $9177 \div 12$

4 State whether each of the following is true or false.

a $18 < 20 - 2 \times 3$ **b** $9 \times 6 > 45$ **c** $23 = 40 \div 2 + 3$

5 How much more than 17×18 is 18×19?

6 Calculate:

a $7 \times 6 - 4 \times 3$ **b** $8 \times 8 - 16 \div 2$ **c** $12 \times (6 - 2)$

d $16 \times [14 - (6 - 2)]$ **e** $24 \div 6 \times 4$ **f** $56 - (7 - 5) \times 7$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 State whether each of the following is true or false.

a $4 \times 25 \times 0 = 1000$ **b** $0 \div 10 = 0$ **c** $8 \div 0 = 0$

d $8 \times 7 = 7 \times 8$ **e** $20 \div 4 = 20 \div 2 \div 2$ **f** $8 + 5 + 4 = 8 + 9$

8 Insert brackets to make $18 \times 7 + 3 = 18 \times 7 + 18 \times 3$ true.

9 How many times can 15 be subtracted from 135 before an answer of zero occurs?

10 Write 3 859 643 correct to the nearest:

a 10 **b** thousand **c** million

Extended response question

1 Tom works as a labourer, earning $25 an hour on weekdays and $60 an hour on weekends.

a During a particular week, Tom works 7:00 am to 2:00 pm Monday to Thursday. How many hours does he work that week?

b How much does Tom earn for this work?

c If Tom works 5 hours on Saturday in the same week, what is his total income for the week?

d How many more hours on a Friday must Tom work to earn the same amount as working 5 hours on a Saturday?

Geometry

Multiple-choice questions

1 Which statement is correct?


A Line m is perpendicular to line l.

B Line m bisects line l.

C Line m is parallel to line l.

D Line m is shorter than line l.

E Line m is longer than line l.



2 An angle of 181° is classified as:

A acute **B** reflex **C** straight **D** obtuse **E** sharp

3 Which two angles represent alternate angles?


A $a°$ and $e°$

B $d°$ and $f°$

C $a°$ and $f°$

D $g°$ and $b°$


E $c°$ and $f°$




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 Which of the following shows a pair of supplementary angles?


A




B




C



D




E




5 The value of $x + y$ is:

A 70
B 220
C 35
D 140
E 110




Short-answer question

1 **a** Name two pairs of parallel lines.
b Name a pair of perpendicular lines.
c List any three lines that are concurrent. At what point do they cross?
d Name two points that are collinear with point C.
e Name the point at which line BE and line FD intersect.




2 Measure these angles.

a




b



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c




3 What is the complement of 65°?


4 What is the supplement of 102°?

5 Find the value of a in each of the following angles.


a




b




c




d




e




f



6 Find the value of each angle formed when these two parallel lines are crossed by the transversal, as shown.



7 Explain why AB is *not* parallel to CD.



8 Use your ruler and pair of compasses to draw a 60° angle. Bisect it to form two 30° angles.

Extended-response question

1 Consider the diagram shown.


a Find the value of:

i x

ii y

iii z

b What is the value of $x + y + z$?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Number properties and patterns

Multiple-choice questions

1 The first prime number after 90 is:

A 91 **B** 92 **C** 97 **D** 95 **E** 93

2 The highest common factor (HCF) of 12 and 18 is:

A 6 **B** 12 **C** 4 **D** 2 **E** 9

3 $2 \times 2 \times 2 \times 3$ is the same as:

A 6×3 **B** $2^3 \times 3$ **C** 8^3 **D** 6^3 **E** 4^3

4 Evaluating $3^2 - \sqrt{25} + 3$ gives:

A 8 **B** 5 **C** 4 **D** 17 **E** 7

5 The number 48 in prime factor form is:

A $2^4 \times 5$ **B** $2 \times 3 \times 5$ **C** $2^3 \times 3^2$ **D** $2^4 \times 3$ **E** $2^3 \times 3$

Short-answer questions

1 List the factors of:

a 15 **b** 30 **c** 100

2 List the first five multiples of:

a 3 **b** 7 **c** 11

3 List all factors common to 30 and 36.

4 What is the highest factor common to 36 and 40?

5 Find the value of:

a 11^2 **b** $6^2 \times 2^2$ **c** $33 - 2^3$


6 What is the square root of 14 400?

7 Is the expression $\sqrt{3^2 + 4^2} = 3 + 4$ true or false?

8 Find the smallest number that must be added to 36 791 so that it becomes divisible by:

a 2 **b** 3 **c** 4

9 A pattern is shown using matchsticks.



a How many matchsticks are needed to build the 12th term in this pattern?


b Which term in this pattern uses exactly 86 matchsticks?

10 Find the missing values in the table.


input	4	5	6			
output	19	23		39	47	403

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 Write down the coordinates of each point.



Extended-response question



term 1 term 2 term 3

1 The diagrams above show the tile pattern being used around the border of an inground swimming pool.

- **a** Draw the fourth term in the pattern.
- **b** How many coloured tiles are used in term 4 of the pattern?
- **c** Which term uses 41 coloured tiles in its construction?
- **d** If each coloured tile costs $1 and each white tile costs 50 cents, what is the cost of completing the pattern using 41 coloured tiles?

Fractions

Multiple-choice questions

1 Which of the following is equivalent to $\frac{12}{7}$?

A $\frac{24}{7}$ **B** $1\frac{5}{7}$ **C** $1\frac{5}{12}$ **D** $\frac{112}{17}$ **E** $\frac{7}{12}$

2 $\frac{1}{2}+\frac{1}{3}$ is equal to:

A $\frac{2}{5}$ **B** $\frac{2}{6}$ **C** $\frac{5}{6}$ **D** $\frac{1}{5}$ **E** $\frac{7}{6}$

3 $\frac{350}{450}$ in simplest form is:

A $\frac{35}{45}$ **B** $\frac{4}{5}$ **C** $\frac{3}{4}$ **D** $\frac{3.5}{4.5}$ **E** $\frac{7}{9}$

4 What fraction of $2 is 40 cents?

A $\frac{1}{20}$ **B** $\frac{20}{1}$ **C** $\frac{5}{1}$ **D** $\frac{1}{5}$ **E** $\frac{1}{40}$

5 $2\frac{1}{2}\div\frac{3}{4}$ is the same as:

A $\frac{5}{2}\times\frac{4}{3}$ **B** $\frac{5}{2}\times\frac{3}{4}$ **C** $\frac{2}{5}\div\frac{3}{4}$ **D** $\frac{2}{5}\times\frac{4}{3}$ **E** $\frac{3}{2}\times\frac{3}{4}$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 Arrange $\frac{1}{2}, \frac{1}{3}, \frac{2}{5}$ and $\frac{3}{10}$ in *ascending* order.

2 Express $5\frac{2}{3}$ as an improper fraction.

3 Find each of the following.

a $\frac{2}{3}+\frac{1}{4}$ b $4-1\frac{1}{3}$ c $2\frac{1}{2}+3\frac{3}{4}$

d $\frac{2}{5}\times\frac{1}{2}$ e $\frac{2}{3}\div\frac{1}{6}$ f $1\frac{1}{5}\times\frac{5}{12}$

4 Write 15% as a simple fraction.

5 Find 25% of \$480.

6 Find $12\frac{1}{2}$% of \$480.

7 State whether each of the following is true or false.

a 25% of $x = x \div 4$ b 10% of $w = \frac{w}{10}$

c 20% of 50 = 50% of 20 d 1% of $x = 100x$

8 Which is larger, $\frac{2}{3}$ or 67%?

Extended-response question

1 Caleb's cold and flu prescription states: 'Take two pills three times a day with food.' The bottle contains 54 pills:

a How many pills does Caleb take each day?

b What fraction of the bottle remains after Day 1?

c How many days will it take for the pills to run out?

d If Caleb takes his first dose Friday night before going to bed, on what day will he take his last dose?

Algebra

Multiple-choice questions

1 $12 - x$ means:

A 12 less than x B x less than 12 C x has the value of 12

D x is less than 12 E x is more than 12

2 Double the sum of x and y is:

A $2(x+y)$ B $2x+y$ C $x+2y$ D $(x+y)^2$ E $x+y+2$

3 Half the product of a and b is:

A $2ab$ B $\frac{a+b}{2}$ C $\frac{ab}{2}$ D $\frac{1}{2}a+\frac{1}{2}b$ E $\frac{a}{2}+b$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 $4a + 3b + c + 5b - c$ is the same as:

A $32ab$ **B** $4a + 8b + 2c$ **C** $8a + 4b$ **D** $64abc$ **E** $4a + 8b$

5 If $a = 3$ and $b = 7$, then $3a^2 + 2b$ is equal to:

A 66 **B** 95 **C** 23 **D** 41 **E** 20

Short-answer questions

1 Consider the expression $5x + 7y + 3x + 9$.

a How many terms are in this expression?

b Can the expression be simplified?

c What is the value of the constant term?

d What is the coefficient of y?

2 Write an algebraic expression for each of the following.

a the sum of x and 3

b the product of a and 12

c the sum of double x and triple y

d w divided by 6

e double x taken from y

3 Find how many:

a cents are in $\$m$ **b** hours are in x days

c millimetres are in p kilometres **d** days are in y hours

4 If $m = 6$, find the value of each of the following.

a $m + 7$ **b** $2m - 1$ **c** $6m + 3$

d $2(m - 3)$ **e** $\frac{m + 6}{2}$ **f** $\frac{m}{2} + 4m - 3$

5 Evaluate the expression $3(2x + y)$ when $x = 5$ and $y = 2$.


6 Simplify each of the following.

a $6a + 4a$ **b** $7x - 3x$ **c** $9a + 2a + a$

d $m + m - m$ **e** $6 + 2a + 3a$ **f** $x + y + 3x + y$

7 **a** Write an expression for the perimeter of rectangle $ABCD$.

b Write an expression for the area of rectangle $ABCD$.



8 Find the missing term.

a $3a \times ___ = 18abc$ **b** $10ab \div ___ = 2a$


c $2p + 2p + 2p = 6___$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 Expand:

a $2(a + 3)$ **b** $12(a - b)$ **c** $8(3m + 4)$

10 Write the simplest expression for the perimeter of this figure.



Extended-response question

1 A bottle of soft drink costs \$3 and a pie costs \$2.

a Find the cost of:

i 2 bottles of soft drink and 3 pies

ii x bottles of soft drink and 3 pies

iii x bottles of soft drink and y pies

b If Anh has \$50, find his change if he buys x bottles of soft drink and y pies.

Decimals

Multiple-choice questions

1 $80 + \frac{6}{10} + \frac{7}{1000}$ is the same as:

A 8067 **B** 867 **C** 80.67 **D** 80.067 **E** 80.607

2 Select the incorrect statement.

A $0.707 > 0.7$ **B** $0.770 = \frac{77}{100}$ **C** $0.07 \times 0.7 = 0.49$

D $0.7 \times \frac{1}{10} = 0.07$ **E** $0.7 \times 10 = 7$

3 The best estimate for 23.4×0.96 is:

A 234 **B** 230 **C** 0.234 **D** 23 **E** 20

4 $\frac{3}{8}$ is the same as:

A 0.375 **B** 3.8 **C** 0.38 **D** $2.\dot{6}$ **E** 38%

5 $6.8 \div 0.04$ is the same as:

A $68 \div 4$ **B** $680 \div 4$ **C** 17 **D** $\frac{4}{68}$ **E** $7 \div 0.05$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 Write each of the following as a decimal.

a two-tenths **b** $\frac{13}{100}$ **c** $\frac{17}{10}$

2 In the decimal 136.094:

a What is the value of the 6?

b What is the value of the 4?

c What is the decimal, correct to the nearest tenth?

3 Round 18.398 741 correct to:

a the nearest whole **b** 1 decimal place **c** 2 decimal places

4 Evaluate:

a $15 - 10.93$ **b** $19.7 + 240.6 + 9.03$ **c** $20 - 0.99$

d 0.6×0.4 **e** $(0.3)^2$ **f** $\frac{12}{0.2}$

5 Find:

a $1.24 - 0.407$ **b** $1.2 + 0.6 \times 3$ **c** $1.8 \times 0.2 \div 0.01$

6 If $369 \times 123 = 45\,387$, write down the value of:

a 3.69×1.23 **b** 0.369×0.123 **c** $45.387 \div 36.9$

7 Find:

a 36.49×1000 **b** $1.8 \div 100$ **c** 19.43×200

8 For each of the following, circle the larger of each pair.

a $\frac{4}{5}$, 0.79 **b** 1.1, 11% **c** $\frac{2}{3}$, 0.6

9 State if each of the following is true or false.

a $0.5 = 50\%$ **b** $0.15 = \frac{2}{20}$ **c** $38\% = 0.19$

d $126\% = 1.26$ **e** $\frac{4}{5} = 0.08$ **f** $1\frac{3}{4} = 1.75$

Extended-response question

1 The cost of petrol is 116.5 cents per litre.

a Find the cost of 55 L of petrol, correct to the nearest cent.

b Mahir pays cash for his 55 L of petrol. What is the amount that he pays, correct to the nearest 5 cents?

c If the price of petrol is rounded to the nearest cent before the cost is calculated, how much would 55 L of petrol cost now?

d By how much is Mahir better off if the rounding occurs at the end rather than the beginning?

e If the price drops to 116.2 cents per litre, is the comparison between rounding at the end versus rounding at the beginning the same as it was above?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 7

Negative numbers

What you will learn

- 7A Integers (Consolidating)
- 7B Adding and subtracting positive integers
- 7C Adding and subtracting negative integers
- 7D Multiplication and division of integers (Extending)
- 7E Order of operations (Extending)
- 7F Substituting integers (Extending)
- 7G The number plane

Australian curriculum

NUMBER AND ALGEBRA

Number and place value

Compare, order, add and subtract integers (ACMNA280)

Linear and non-linear relationships

Given coordinates, plot points on the Cartesian plane, and find coordinates for a given point (ACMNA178) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

The coldest place on Earth

The coldest place on Earth is Antarctica, where maximum daily temperatures below 0° Celsius are commonplace. The coldest temperature ever recorded on Earth was about –89°C in 1983 at the Russian Vostok Station in Antarctica. Temperatures on the coast of Antarctica can reach 15°C in summer but average temperatures are generally below 0°C. A layer of ice surrounds and covers almost all of the continent.

The surrounding ice sits both above and below sea level, making it very difficult for ships to reach their destinations. Like the temperature scale, heights above and below sea level can be recorded using both positive and negative numbers.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A Integers CONSOLIDATING









The numbers 1, 2, 3, . . . are considered to be positive because they are greater than zero (0). Negative numbers extend the number system to include numbers less than zero. All the whole numbers less than zero, zero itself and the whole numbers greater than zero are called integers.

The use of negative numbers dates back to 100 BCE when the Chinese used black rods for positive numbers and red rods for negative numbers in their rod number system. These coloured rods were used for commercial and tax calculations. Later, a great Indian mathematician named Brahmagupta (598–670) set out the rules for the use of negative numbers, using the word *fortune* for positive and *debt* for negative. Negative numbers were used to represent loss in a financial situation.


John Wallis invented the number line.

An English mathematician named John Wallis (1616–1703) invented the number line and the idea that numbers have a direction. This helped define our number system as an infinite set of numbers extending in both the positive and negative directions. Today negative numbers are used in all sorts of mathematical calculations and are considered to be an essential element of our number system.

Let's start: Simple applications of negative numbers


- Try to name as many situations as possible in which negative numbers are used.
- Give examples of the numbers in each case.

Key ideas

- **Negative** numbers are numbers less than zero.
- **Integers** are whole numbers that can be negative, zero or positive.

  . . . , –4, –3, –2, –1, 0, 1, 2, 3, 4, . . .

- A **number line** shows:
  - positive numbers to the right of zero
  - negative numbers to the left of zero.




- Each negative number has a positive **opposite**.
  3 and –3 are examples of opposite numbers.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Drawing a number line

Draw a number line, showing all integers from –4 to 2.

SOLUTION



EXPLANATION

Use equally spaced markings and put –4 on the left and 2 on the right.

Example 2 Less than or greater than

Insert the symbol < (less than) or > (greater than) into these statements to make them true.


a –2 ☐ 3 **b** –1 ☐ –6

SOLUTION

a –2 < 3


EXPLANATION

–2 is to the left of 3 on a number line.



b –1 > –6

–1 is to the right of –6 on a number line.




Exercise 7A

1–3 | 3 | —


UNDERSTANDING

1 What are the missing numbers on these number lines?


a




b



c



d



2 –5 is the opposite number of 5, and 5 is the opposite number of –5. Write down the opposite to these numbers.

a 2 **b** 6 **c** –3 **d** –7
e –15 **f** 21 **g** 132 **h** –1071

3 Fill in the blanks using the words *greater* and *less*.

a 5 is _____ than 0 **b** –3 is _____ than 0
c 0 is _____ than –6 **d** 0 is _____ than 1

4–5, 6(½), 7 | 4–5, 6(½), 7 | 4–7(½)

FLUENCY

Example 1

4 Draw a number line for each description, showing all the given integers.

a from –2 to 2 **b** from –5 to 1 **c** from –10 to –6 **d** from –32 to –25

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A

FLUENCY

5 List all the integers that fit the given description.

a from –2 up to 4
b from –7 up to 0
c greater than –3 and less than 2
d greater than –5 and less than 1
e less than 4 and greater than –4
f less than –3 and greater than –10


Example 2

6 Insert the symbol < (less than) or > (greater than) into these statements to make them true.


a 7 ☐ 9
b 3 ☐ 2
c 0 ☐ –2
d –4 ☐ 0
e –1 ☐ –5
f –7 ☐ –6
g –11 ☐ –2
h –9 ☐ –13
i –3 ☐ 3
j 3 ☐ –3
k –130 ☐ 1
l –2 ☐ –147

7 Give the temperature shown on these thermometers.


a




b



c



d



8, 9 | 9, 10 | 9, 10

PROBLEM-SOLVING

8 Arrange these numbers in *ascending* order.

a –3, –6, 0, 2, –10, 4, –1
b –304, 126, –142, –2, 1, 71, 0

9 Write the next three numbers in these simple patterns.

a 3, 2, 1, _____, _____, _____
b –8, –6, –4, _____, _____, _____
c 10, 5, 0, _____, _____, _____
d –38, –40, –42, _____, _____, _____
e –91, –87, –83, _____, _____, _____
f 199, 99, –1, _____, _____, _____

10 These lists of numbers show deposits (positive numbers) and withdrawals (negative numbers) for a month of bank transactions. Find the balance at the end of the month.

a

Start balance	$200
	–$10
	–$130
	$25
	–$100
	$20
Final balance	_____

b

Start balance	$0
	$50
	–$60
	–$100
	$200
	–$100
Final balance	_____

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7A

11 | 11 | 11, 12


REASONING

11 If the height above sea level for a plane is a positive number, then the height for a submarine could be written as a negative number. What is the height relative to sea level for a submarine at these depths?

a 50 m **b** 212.5 m **c** 0 m



12 The difference between two numbers could be thought of as the distance between the numbers on a number line. For example, the difference between –2 and 1 is 3.



Find the difference between these pairs of numbers.


a –1 and 1 **b** –2 and 2 **c** –3 and 1 **d** –4 and 3
e –3 and 0 **f** –4 and –1 **g** –10 and –4 **h** –30 and 14

The final position

— | — | 13

ENRICHMENT

13 For these sets of numbers, a positive number means to move right and a negative number means to move left. Start at zero each time and find the final position.



a –1, 4, –5 **b** 3, –5, –1, 4
c –5, –1, 3, 1, –2, –1, 4 **d** –10, 20, –7, –14, 8, –4
e –250, 300, –49, –7, 36, –81 **f** –7001, 6214, –132, 1493, –217

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7B Adding and subtracting positive integers

Interactive

Widgets

HOTsheets

Walkthroughs

Adding and subtracting a positive integer can give both positive and negative answers. For example, when the temperature inside a newly installed fridge is 20°C but, after being switched on, the temperature then falls by 25°C, the result is –5°C; i.e. 20 – 25 = –5. If a temperature of –10°C rises by 5°C, the result is –5°C; i.e. –10 + 5 = –5.



When food goes into a fridge its temperature begins to change.

Let's start: Positive and negative possibilities


Decide if it is possible to find an example of the following.
If so, give a specific example.

- A positive number added to a positive number gives a positive number.
- A positive number added to a positive number gives a negative number.
- A positive number added to a negative number gives a positive number.
- A positive number added to a negative number gives a negative number.
- A positive number subtracted from a positive number gives a positive number.
- A positive number subtracted from a positive number gives a negative number.
- A positive number subtracted from a negative number gives a positive number.
- A positive number subtracted from a negative number gives a negative number.


Key ideas

■ If a positive number is added to an integer, you move right on a number line.

2 + 3 = 5 Start at 2 and move right by 3.




–5 + 2 = –3 Start at –5 and move right by 2.




■ If a positive number is subtracted from an integer, you move left on a number line.

2 – 3 = –1 Start at 2 and move left by 3.



–4 – 2 = –6 Start at –4 and move left by 2.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 3 Adding and subtracting positive integers

Calculate the answer to these additions and subtractions.


a $-2 + 3$ **b** $-8 + 1$ **c** $5 - 7$ **d** $-3 - 3$

SOLUTION **EXPLANATION**


a $-2 + 3 = 1$




b $-8 + 1 = -7$



c $5 - 7 = -2$



d $-3 - 3 = -6$



Exercise 7B

1, 2 | 2 | —

UNDERSTANDING

1 In which direction (i.e. right or left) on a number line do you move for the following calculations?


a 2 is added to -5 **b** 6 is added to -4

c 4 is subtracted from 2 **d** 3 is subtracted from -4

2 Match up the problems **a** to **d** with the number lines **A** to **D**.


a $5 - 6 = -1$

A




b $-2 + 4 = 2$

B




c $-1 - 3 = -4$

C



d $-6 + 3 = -3$

D



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7B

3–5(½) | 3–6(½) | 3–6(½)

FLUENCY

Example 3a,b

3 Calculate the answer to these additions. Check your answers using a calculator.

a $-1 + 2$	**b** $-1 + 4$	**c** $-3 + 5$	**d** $-10 + 11$
e $-4 + 3$	**f** $-5 + 2$	**g** $-11 + 9$	**h** $-20 + 18$
i $-4 + 0$	**j** $-8 + 0$	**k** $-30 + 29$	**l** $-39 + 41$
m $-130 + 132$	**n** $-181 + 172$	**o** $-57 + 63$	**p** $-99 + 68$

Example 3c,d

4 Calculate the answer to these subtractions. Check your answers using a calculator.

a $4 - 6$	**b** $7 - 8$	**c** $3 - 11$	**d** $1 - 20$
e $-3 - 1$	**f** $-5 - 5$	**g** $-2 - 13$	**h** $-7 - 0$
i $-37 - 4$	**j** $39 - 51$	**k** $62 - 84$	**l** $-21 - 26$
m $-100 - 200$	**n** $100 - 200$	**o** $328 - 421$	**p** $-496 - 138$

5 Find the missing number.

a $2 + \square = 7$	**b** $-2 + \square = 7$	**c** $-2 + \square = 3$	**d** $-4 + \square = -2$
e $5 - \square = 0$	**f** $3 - \square = -4$	**g** $-9 - \square = -12$	**h** $-20 - \square = -30$
i $-6 + \square = -1$	**j** $-8 - \square = -24$	**k** $\square + 1 = -3$	**l** $\square + 7 = 2$
m $\square - 4 = -10$	**n** $\square - 7 = -20$	**o** $\square + 6 = -24$	**p** $\square - 100 = -213$

6 Evaluate the following. Remember to work from left to right.

a $3 - 4 + 6$	**b** $2 - 7 - 4$	**c** $-1 - 4 + 6$	**d** $-5 - 7 - 1$
e $-3 + 2 - 7 + 9$	**f** $-6 + 1 - 20 + 3$	**g** $0 - 9 + 7 - 30$	**h** $-15 - 20 + 32 - 1$

7, 8 | 8, 9 | 8–10

PROBLEM-SOLVING

7 Determine how much debt remains in these financial situations.

a owes $300 and pays back $155

b owes $20 and borrows another $35

c owes $21 500 and pays back $16 250

8 **a** The reading on a thermometer measuring temperature rises 18°C from –15°C. What is the final temperature?

b The reading on a thermometer measuring temperature falls 7°C from 4°C. What is the final temperature?

c The reading on a thermometer measuring temperature falls 32°C from –14°C. What is the final temperature?

9 For an experiment, a chemical solution starts at a temperature of 25°C, falls to –3°C, rises to 15°C and then falls again to –8°C. What is the total change in temperature? Add all the changes together for each rise and fall.



10 An ocean sensor is raised and lowered to different depths in the sea. Note that –100 m means 100 m below sea level.

a If the sensor is initially at –100 m and then raised to –41 m, how far does the sensor rise?

b If the sensor is initially at –37 m and then lowered to –93 m, how far is the sensor lowered?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

7B

11 | 11 | 11, 12

REASONING

11 Give an example that suits the description.

- **a** A positive number subtract a positive number equals a negative number.
- **b** A negative number subtract a positive number equals a negative number.
- **c** A negative number add a positive number equals a positive number.
- **d** A negative number add a positive number equals a negative number.

12 a a is a positive integer, b is a positive integer and $a > b$. For each of the following, decide if the result will be positive, negative or zero.

i $a + b$ **ii** $a - b$ **iii** $b - a$ **iv** $a - a$

b a is a negative integer and b is a positive integer. Decide if each of the following is *always* true.

i $a + b$ is positive **ii** $a - b$ is negative

+ or – combinations | — | — | 13

ENRICHMENT

13 Insert + or – signs into these statements to make them true.

- **a** $3 \square 4 \square 5 = 4$
- **b** $1 \square 7 \square 9 \square 4 = -5$
- **c** $-4 \square 2 \square 1 \square 3 \square 4 = 0$
- **d** $-20 \square 10 \square 7 \square 36 \square 1 \square 18 = -4$
- **e** $-a \square b \square a \square b = 0$
- **f** $-a \square a \square 3a \square b \square b = a - 2b$

Market Movers Snapshot

Top 20 of ASX 100 Stocks

Rises: 85 Falls: 9 Steadies: 6

Jul 14, 2010 - 03:00 PM

	ASX Code		Price	Movement by price	Movement by %	
1	IPL	INCITEC PIVOT LIMITED	2.992	0.160 ↑	5.65	Chart
2	AQP	AQUARIUS PLATINUM LIMITED	5.481	0.260 ↑	4.98	Chart
3	DOW	DOWNER EDI LIMITED	4.140	0.190 ↑	4.81	Chart
4	ALL	ARISTOCRAT LEISURE LIMITED	3.542	0.130 ↑	3.81	Chart
5	AMC	AMCOR LIMITED	6.715	0.200 ↑	3.07	Chart
6	TSE	TRANSFIELD SERVICES LIMITED	3.357	0.100 ↑	3.07	Chart
7	FMG	FORTESCUE METALS GROUP LTD	4.375	0.120 ↑	2.82	Chart
8	AWE	AWE LIMITED	1.675	0.045 ↑	2.76	Chart
9	BLY	BOART LONGYEAR LIMITED	2.979	0.080 ↑	2.76	Chart
10	ITO	INTOLL GROUP	1.121	0.030 ↑	2.75	Chart
11	MGR	MIRVAC GROUP	1.308	0.035 ↑	2.75	Chart
12	CBA	COMMONWEALTH BANK OF AUSTRALIA.	51.370	1.370 ↑	2.74	Chart
13	NWS	NEWS CORPORATION	16.955	0.420 ↑	2.54	Chart
14	ASX	ASX LIMITED	29.636	0.720 ↑	2.49	Chart
15	FXJ	FAIRFAX MEDIA LIMITED	1.441	0.035 ↑	2.49	Chart
16	DXS	DEXUS PROPERTY GROUP	0.840	0.020 ↑	2.44	Chart
17	GMG	GOODMAN GROUP	0.635	0.015 ↑	2.42	Chart
18	JHX	JAMES HARDIE INDUSTRIES SE	6.453	0.150 ↑	2.38	Chart
19	MQG	MACQUARIE GROUP LIMITED	39.903	0.920 ↑	2.36	Chart
20	ERA	ENERGY RESOURCES OF AUSTRALIA LIMITED	13.713	-0.330 ↓	-2.35	Chart

Postive and negative numbers are used to show stock price changes.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7C Adding and subtracting negative integers

Interactive

Widgets

HOTsheets

Walkthroughs

By observing patterns in number calculations, we can see the effect of adding and subtracting negative integers.

Addition		Subtraction	
$2 + 3 = 5$	-1	$2 - 3 = -1$	$+1$
$2 + 2 = 4$	-1	$2 - 2 = 0$	$+1$
$2 + 1 = 3$	-1	$2 - 1 = 1$	$+1$
$2 + 0 = 2$	-1	$2 - 0 = 2$	$+1$
$2 + (-1) = 1$	-1	$2 - (-1) = 3$	$+1$
$2 + (-2) = 0$	-1	$2 - (-2) = 4$	$+1$
$2 + (-3) = -1$		$2 - (-3) = 5$	

So adding –3 is equivalent to subtracting 3, and subtracting –3 is equivalent to adding 3.



If I have \$100 of debt and subtract \$50 of debt, how do I calculate my final balance?

Let's start: Dealing with debt

Let –\$10 represent \$10 of debt. Can you write a statement (e.g. $5 + (-10) = -5$) to represent the following financial situations?


- \$10 of debt is added to a balance of \$5.
- \$10 of debt is added to a balance of –\$5.
- \$10 of debt is removed from a balance of –\$15.

Key ideas


- Adding a negative number is equivalent to subtracting its opposite.

  $a + (-b) = a - b$

  $2 + (-3) = 2 - 3 = -1$




  $-4 + (-2) = -4 - 2 = -6$




- Subtracting a negative number is equivalent to adding its opposite.

  $a - (-b) = a + b$

  $5 - (-2) = 5 + 2 = 7$



  $-2 - (-3) = -2 + 3 = 1$



- On a number line, the effect of adding or subtracting a negative number is to reverse the direction of the operation.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 4 Adding and subtracting negative integers

Calculate the answer to these additions and subtractions.

a $7 + (-2)$ **b** $-2 + (-3)$ **c** $1 - (-3)$ **d** $-6 - (-2)$

SOLUTION	EXPLANATION
a $7 + (-2) = 7 - 2$ $= 5$	Adding –2 is equivalent to subtracting 2.
b $-2 + (-3) = -2 - 3$ $= -5$	Adding –3 is equivalent to subtracting 3.
c $1 - (-3) = 1 + 3$ $= 4$	Subtracting –3 is equivalent to adding 3.
d $-6 - (-2) = -6 + 2$ $= -4$	Subtracting –2 is equivalent to adding 2.

Exercise 7C

1–3(½) 3(½) —

UNDERSTANDING

1 Write down the missing numbers in these sentences. The first one has been done for you.

a $2 + 5$ means that 5 is added to 2.
b $-3 + 6$ means that ☐ is added to ☐.
c $1 + (-3)$ means that ☐ is added to ☐.
d $-7 + (-11)$ means that ☐ is added to ☐.
e $5 - 3$ means that ☐ is subtracted from ☐.
f $-2 - 6$ means that ☐ is subtracted from ☐.
g $7 - (-3)$ means that ☐ is subtracted from ☐.
h $-7 - (-11)$ means that ☐ is subtracted from ☐.

2 Complete these sentences.

a Adding –4 is equivalent to subtracting ☐.
b Adding –6 is equivalent to _____ 6.
c Adding 5 is equivalent to subtracting ☐.
d Adding –11 is equivalent to _____ 11.
e Subtracting –2 is equivalent to adding ☐.
f Subtracting –7 is equivalent to _____ 7.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7C

UNDERSTANDING

3 State whether each of the following is true or false.

a $2 + (-3) = 5$	**b** $10 + (-1) = 9$	**c** $-5 + (-3) = -8$	**d** $-6 + (-2) = -4$
e $5 - (-1) = 4$	**f** $3 - (-9) = 12$	**g** $2 - (-3) = 1$	**h** $-11 - (-12) = -1$

4–6(½) 4–7(½) 4–7(½)

FLUENCY

Example 4a,b

4 Calculate the answer to these additions. Check your answer using a calculator.

a $3 + (-2)$	**b** $8 + (-3)$	**c** $12 + (-6)$	**d** $9 + (-7)$
e $1 + (-4)$	**f** $6 + (-11)$	**g** $20 + (-22)$	**h** $0 + (-4)$
i $-2 + (-1)$	**j** $-7 + (-15)$	**k** $-5 + (-30)$	**l** $-28 + (-52)$
m $-7 + (-3)$	**n** $-20 + (-9)$	**o** $-31 + (-19)$	**p** $-103 + (-9)$

Example 4c,d

5 Calculate the answer to these subtractions. Check your answer using a calculator.

a $2 - (-3)$	**b** $5 - (-6)$	**c** $20 - (-30)$	**d** $29 - (-61)$
e $-5 - (-1)$	**f** $-7 - (-4)$	**g** $-11 - (-6)$	**h** $-41 - (-7)$
i $-4 - (-6)$	**j** $-9 - (-10)$	**k** $-20 - (-20)$	**l** $-96 - (-104)$
m $5 - (-23)$	**n** $28 - (-6)$	**o** $-31 - (-19)$	**p** $-104 - (-28)$

6 Find the missing number.

a $2 + \square = -1$	**b** $3 + \square = -7$	**c** $-2 + \square = -6$	**d** $\square + (-3) = 1$
e $\square + (-10) = -11$	**f** $\square + (-4) = 0$	**g** $5 - \square = 6$	**h** $2 - \square = 7$
i $-1 - \square = 3$	**j** $\square - (-3) = 7$	**k** $\square - (-10) = 12$	**l** $\square - (-4) = -20$
m $5 - \square = 11$	**n** $\square - (-2) = -3$	**o** $-2 - \square = -4$	**p** $\square + (-5) = -1$

7 Calculate the answer, working from left to right.

a $3 + (-2) + (-1)$	**b** $2 + (-1) + (-6)$	**c** $3 - (-1) - (-4)$	**d** $10 - (-6) + (-4)$
e $-7 - (-1) + (-3)$	**f** $-20 - (-10) - (-15)$	**g** $-9 - (-19) + (-16)$	**h** $-15 - (-20) + (-96)$
i $-13 - (-19) + (-21)$	**j** $-2 - (-3) - (-5)$	**k** $-18 - (-16) - (-19)$	**l** $5 + (-20) - (-26)$

8, 9 9–11 10–12

PROBLEM-SOLVING

8 A diver is at a height of –90 m from the surface of the sea. During a diving exercise, the diver rises 50 m, falls 138 m and then rises once again by 35 m. What is the diver's final height from sea level?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 A small business has a bank balance of –$50 000. An amount of $20 000 of extra debt is added to the balance and, later, $35 000 is paid back. What is the final balance?



10 $100 of debt is added to an existing balance of $50 of debt. Later, $120 of debt is removed from the balance. What is the final balance?


11 Here is a profit graph showing the profit for each month of the first half of the year for a bakery shop.

a What is the profit for:

i February?

ii April?

b What is the overall profit for the 6 months?



12 Complete these magic squares, using addition. The sum of each row, column and diagonal should be the same.

a

–2		5
	1	
		4

b

		–6
–3		–17
		–7

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

7C

13 | 13, 14 | 14, 15

REASONING

13 Write these sentences as mathematical statements, e.g. 2 + (–3).

a The sum of 3 and 4.
b The sum of –2 and –9.
c The difference between 5 and –2.
d The difference between –2 and 1.
e The sum of a and the opposite of b.
f The difference between a and the opposite of b.

14 Simplify these numbers. Hint: In part **a**, –(–4) is the same as 0 – (–4).

a –(–4)
b –(–(–1))
c –(–(–(–(–3))))

15 **a** If a is a positive number and b is a negative number, decide if each of the following statements is *always* true.

i $a + b$ is negative
ii $a - b$ is positive

b If a is a negative number and b is a negative number, decide if each of the following statements is *always* true.

i $a + b$ is negative
ii $a - b$ is positive

c If a and b are both negative numbers and $b < a$, is $a - b$ always positive? Give reasons.

Negative fractions

— | — | 16

ENRICHMENT

16 Negative decimals and fractions can be added and subtracted using the same rules as those for integers. Calculate the answer to these sums and differences of fractions.

a $2 + \left(-\frac{1}{2}\right)$
b $5 + \left(-\frac{4}{3}\right)$
c $-\frac{1}{2} + \left(-\frac{3}{2}\right)$
d $-\frac{2}{3} + \left(-\frac{10}{3}\right)$
e $5 - \left(-\frac{1}{3}\right)$
f $10 - \left(-\frac{3}{2}\right)$
g $-\frac{5}{4} - \left(-\frac{3}{4}\right)$
h $-\frac{4}{7} - \left(-\frac{1}{2}\right)$
i $\frac{9}{2} + \left(-\frac{9}{3}\right)$
j $\frac{9}{2} - \left(-\frac{9}{3}\right)$
k $4\frac{2}{3} + \left(-1\frac{1}{2}\right)$
l $5\frac{5}{7} + \left(-4\frac{4}{5}\right)$
m $-\frac{3}{2} + \left(-\frac{1}{3}\right)$
n $-\frac{7}{4} - \left(-\frac{2}{5}\right)$
o $3\frac{2}{7} - \left(-1\frac{1}{2}\right)$
p $-5\frac{1}{6} - \left(-3\frac{2}{5}\right)$



In the Celsius scale, temperatures below the freezing point of water (zero degrees) are indicated by negative numbers.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7D Multiplication and division of integers EXTENDING



The rules for multiplication and division of integers can be developed by considering repeated addition.

For example: 4 groups of –3 is $-3 + (-3) + (-3) + (-3) = -12$. So, $4 \times (-3) = -12$.

Also, $-3 \times 4 = -12$ since $a \times b = b \times a$.



We also know that if $5 \times 7 = 35$, then $35 \div 7 = 5$, so if $4 \times (-3) = -12$ then $-12 \div (-3) = 4$. This is saying there are 4 groups of –3 in –12, which we know from the repeated addition above.



Also, $-12 \div 4 = -3$.



These examples give rise to the rules governing the multiplication and division of negative numbers.

Let's start: Patterns in tables

Complete this table of values for multiplication by noticing the patterns. What does the table of values tell you about the rules for multiplying negative integers?

×	–3	–2	–1	0	1	2	3
–3				0			
–2				0			
–1				0			
0	0	0	0	0	0	0	
1				0	1		
2				0	2	4	
3				0			



- The product or quotient of two numbers of the same sign (i.e. positive or negative) is a positive number.

So $a \times b = ab$ and $-a \times (-b) = ab$

e.g. $3 \times 4 = 12$ or $-3 \times (-4) = 12$

and $a \div b = \frac{a}{b}$ and $-a \div (-b) = \frac{a}{b}$

e.g. $12 \div 4 = 3$ or $-12 \div (-4) = 3$

- The product or quotient of two numbers of the opposite sign (i.e. positive and negative) is a negative number.

So $-a \times b = -ab$ and $a \times (-b) = -ab$

e.g. $-3 \times 4 = -12$ or $3 \times (-4) = -12$

and $-a \div b = -\frac{a}{b}$ and $a \div (-b) = -\frac{a}{b}$

e.g. $-12 \div 3 = 4$ or $12 \div (-3) = -4$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 5 Multiplying and dividing integers

Calculate these products and quotients.

a $5 \times (-6)$ **b** $-3 \times (-7)$ **c** $-36 \div (-4)$ **d** $-18 \div 9$

SOLUTION	EXPLANATION
a $5 \times (-6) = -30$	The two numbers are of opposite sign, so the answer is negative.
b $-3 \times (-7) = 21$	The two numbers are of the same sign, so the answer is positive.
c $-36 \div (-4) = 9$	Both numbers are negative, so the answer is positive.
d $-18 \div 9 = -2$	The two numbers are of opposite sign, so the answer is negative.

Example 6 Working with multiple operations

Work from left to right to find the answer to $-7 \times 4 \div (-2)$.

SOLUTION	EXPLANATION
$-7 \times 4 \div (-2) = -28 \div (-2)$ $= 14$	First, calculate -7×4. Then calculate $-28 \div (-2)$.

Exercise 7D

1–3 | 3 | —

UNDERSTANDING

1 Complete these product tables.

a

×	–2	–1	0	1	2
–2			0		
–1			0		
0	0	0	0	0	0
1			0	1	2
2			0		

b

×	–4	–2	0	2	4
–4	16				
–2					
0					0
2					
4				8	

2 Write down the missing number.

a $2 \times (-3) = -6$, so $-6 \div (-3) = \square$

b $2 \times (-3) = -6$, so $-6 \div 2 = \square$

c $-16 \div 4 = -4$, so $\square \times 4 = -16$

d $16 \div (-4) = -4$, so $\square \times (-4) = 16$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7D

UNDERSTANDING

3 Complete each sentence by inserting the missing word *positive* or *negative*.

a The product (×) of two positive numbers is _____.

b The product (×) of two negative numbers is _____.

c The product (×) of two numbers with opposite signs is _____.

d The quotient (÷) of two positive numbers is _____.

e The quotient (÷) of two negative numbers is _____.

f The quotient (÷) of two numbers with opposite signs is _____.

FLUENCY

4–8(½) 4–9(½) 4–9(½)

Example 5a,b

4 Calculate the answer to these products.

a $3 \times (-5)$	**b** $1 \times (-10)$	**c** -3×2	**d** -9×6
e $-8 \times (-4)$	**f** $-2 \times (-14)$	**g** $-12 \times (-12)$	**h** -11×9
i -13×3	**j** $7 \times (-12)$	**k** $-19 \times (-2)$	**l** -36×3
m $-6 \times (-11)$	**n** $5 \times (-9)$	**o** $-21 \times (-3)$	**p** $-36 \times (-2)$

Example 5c,d

5 Calculate the answer to these quotients.

a $14 \div (-7)$	**b** $36 \div (-3)$	**c** $-40 \div 20$	**d** $-100 \div 25$
e $-9 \div (-3)$	**f** $-19 \div (-19)$	**g** $-25 \div 5$	**h** $38 \div (-2)$
i $84 \div (-12)$	**j** $-108 \div 9$	**k** $-136 \div 2$	**l** $-1000 \div (-125)$
m $-132 \div (-11)$	**n** $-39 \div (-3)$	**o** $78 \div (-6)$	**p** $-156 \div (-12)$

Example 6

6 Work from left to right to find the answer. Check your answer using a calculator.

a $2 \times (-3) \times (-4)$	**b** $-1 \times 5 \times (-3)$	**c** $-10 \div 5 \times 2$
d $-15 \div (-3) \times 1$	**e** $-2 \times 7 \div (-14)$	**f** $100 \div (-20) \times 2$
g $48 \div (-2) \times (-3)$	**h** $-36 \times 2 \div (-4)$	**i** $-125 \div 25 \div (-5)$
j $-8 \div (-8) \div (-1)$	**k** $46 \div (-2) \times (-3) \times (-1)$	**l** $-108 \div (-12) \div (-3)$

7 Write down the missing number in these calculations.

a $5 \times \square = -35$	**b** $\square \times (-2) = -8$	**c** $16 \div \square = -4$	**d** $-32 \div \square = -4$
e $\square \div (-3) = -9$	**f** $\square \div 7 = -20$	**g** $-5000 \times \square = -10\,000$	**h** $-87 \times \square = 261$
i $243 \div \square = -81$	**j** $50 \div \square = -50$	**k** $-92 \times \square = 184$	**l** $-800 \div \square = -20$

8 Remember that $\frac{9}{3}$ means $9 \div 3$. Use this knowledge to simplify each of the following.

a $\frac{-12}{4}$	**b** $\frac{21}{-7}$	**c** $\frac{-40}{-5}$	**d** $\frac{-124}{-4}$
e $\frac{-15}{-5}$	**f** $\frac{-100}{-20}$	**g** $\frac{-900}{30}$	**h** $\frac{20\,000}{-200}$

9 Remember that $3^2 = 3 \times 3 = 9$, and $(-3)^2 = -3 \times (-3) = 9$. Use this knowledge to simplify each of the following.

a $(-2)^2$	**b** $(-1)^2$	**c** $(-9)^2$	**d** $(-10)^2$
e $(-6)^2$	**f** $(-8)^2$	**g** $(-3)^2$	**h** $(-1.5)^2$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7D

10 | 10, 11 | 11, 12

PROBLEM-SOLVING

10 List the different pairs of integers that multiply to give these numbers.

a 6 **b** 16 **c** –5 **d** –24

11 Insert a multiplication or division sign between the numbers to make a true statement.

a $2 \square -3 \square -6 = 1$ **b** $-25 \square -5 \square 3 = 15$

c $-36 \square 2 \square -3 = 216$ **d** $-19 \square -19 \square 15 = 15$

12 **a** There are two distinct pairs of numbers whose product is –8 and difference is 6. What are the two numbers?

b The quotient of two numbers is –11 and their difference is 36. What are the two numbers? There are two distinct pairs to find.

13 | 13 | 13, 14

REASONING

13 2^4 means $2 \times 2 \times 2 \times 2$, and $(-2)^4 = -2 \times (-2) \times (-2) \times (-2)$.

a Calculate:

i $(-2)^3$ **ii** $(-2)^6$ **iii** $(-3)^3$ **iv** $(-3)^4$

b Which questions from part **a** give positive answers and why?

c Which questions from part **a** give negative answers and why?

14 $a \times b$ is equivalent to ab, and $2 \times (-3)$ is equivalent to $-(2 \times 3)$. Use this information to simplify these expressions.

a $a \times (-b)$ **b** $-a \times b$ **c** $-a \times (-b)$

× and ÷ with negative fractions | — | — | 15

ENRICHMENT

15 Calculate the answer to these problems containing fractions. Simplify where possible.

a $\frac{1}{2} \times \left(-\frac{1}{2}\right)$ **b** $\frac{3}{4} \times \left(-\frac{2}{3}\right)$ **c** $-\frac{5}{7} \times \frac{3}{5}$ **d** $-\frac{3}{4} \times \left(-\frac{4}{3}\right)$

e $\frac{1}{4} \div \left(-\frac{1}{4}\right)$ **f** $-\frac{5}{8} \div \frac{1}{2}$ **g** $-\frac{6}{11} \div \left(-\frac{12}{11}\right)$ **h** $-\frac{3}{2} \div \left(-\frac{1}{4}\right)$

i $\frac{a}{b} \times \left(-\frac{b}{a}\right)$ **j** $-\frac{b}{a} \times \left(-\frac{a}{b}\right)$ **k** $-\frac{a}{b} \div \frac{a}{b}$ **l** $-\frac{b}{a} \div \left(-\frac{b}{a}\right)$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

7A **1** Draw a number line from –2 to +3, showing all the given integers.

7A **2** Copy and insert the symbol < (less than) or > (greater than) into these statements to make them true.

a $-2 \square 1$ **b** $-9 \square -12$ **c** $4 \square -5$

7A **3** Arrange these numbers in *ascending* order: $-6, 8, -4, 0, 7$.

7B **4** Calculate the answer to these additions and subtractions.

a $-10 + 12$ **b** $-4 - 5$ **c** $26 - 34$ **d** $-5 - 8 + 9 - 22$

7C **5** Calculate the answer to these additions and subtractions.

a $9 + (-4)$ **b** $-8 + (-7)$ **c** $0 + (-3)$ **d** $12 - (-8)$

7C **6** Calculate the answer, working from left to right.

a $-20 - (-10) - (-15)$ **b** $10 - (-6) + (-4)$

7D Ext **7** Calculate these products and quotients.

a $4 \times (-3)$ **b** $-5 \times (-12)$ **c** $-56 \div 8$ **d** $-20 \div (-5)$

7D Ext **8** Work from left to right to find the answer.

a $5 \times (-2) \times (-4)$ **b** $25 \div (-5) \times 6$

c $64 \div (-8) \times (-2)$ **d** $-40 \div (-4) \div (-5)$

7D Ext **9** Simplify each of the following.

a $(-5)^2$ **b** $(-2)^3$ **c** $\frac{-72}{-6}$ **d** $\frac{-1260}{4}$

7C **10** Ethan has a debt of $120 on his credit card. He buys another item using his credit card, which adds an extra debt of $90. At the end of the month $140 is paid back. What is the final balance on Ethan's credit card?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

7E Order of operations EXTENDING



We have learnt from our study of positive whole numbers that there is a particular order to follow when dealing with mixed operations and brackets. This order also applies when dealing with negative numbers.

For example: $-2 + 3 \times (-4)$ is different from $(-2 + 3) \times (-4)$.



Let's start: Brackets or not?

During a classroom debate about the statement $3 \times (-4) - 8 \div (-2) = -8$:

- Lil says that the statement needs to have more brackets to make it true.
- Max says that even with brackets it is impossible to make it true.
- Riley says that it is correct as it is and there is no need for more brackets.


Who is correct and why?





Key ideas

- When working with more than one operation and with positive and/or negative numbers:
  - Deal with brackets first.
  - Do multiplication and division next, working from left to right.
  - Do addition and subtraction last, working from left to right.





Example 7 Using order of operations

Use order of operations to evaluate the following.

a $5 + 2 \times (-3)$ b $-6 \times 2 - 10 \div (-5)$

SOLUTION	EXPLANATION
a $5 + 2 \times (-3) = 5 + (-6)$ $= -1$	Do the multiplication before the addition.
b $-6 \times 2 - 10 \div (-5) = -12 - (-2)$ $= -12 + 2$ $= -10$	Do the multiplication and division first. When subtracting -2, add its opposite.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 8 Order of operations with brackets

Use order of operations to evaluate the following.

a $(-2-1)\times 8$ **b** $5\div(-10+5)+5$

SOLUTION	EXPLANATION
a $(-2-1)\times 8 = -3\times 8$ $= -24$	Deal with brackets first.
b $5\div(-10+5)+5 = 5\div(-5)+5$ $= -1+5$ $= 4$	Deal with brackets first. Then do the division before the subtraction.

Exercise 7E

1, 2 | 2 | —

UNDERSTANDING

1 Which operation (i.e. addition, subtraction, multiplication or division) is done first in each of the following problems?

a $-2\div 2+1$ **b** $8\times(-6)-4$ **c** $-3+2\times(-6)$
d $7-(-8)\div 4$ **e** $(-2+3)\div 5$ **f** $-6\div(4-(-2))$
g $-4\times 3\div(-6)$ **h** $(2+3\times(-2))+1$ **i** $-11\div(7-2\times(-2))$

2 Classify each of the following statements as true or false.

a $-4+2\times 3 = -4+(2\times 3)$ **b** $-4+2\times 3 = (-4+2)\times 3$
c $8\times(2-(-2)) = 8\times 4$ **d** $8\times(2-(-2)) = 8\times 0$
e $-40-20\div(-5) = (-40-20)\div(-5)$ **f** $-40-20\div(-5) = -40-(20\div(-5))$

3, 4(½) | 3–4(½) | 3–4(½)

FLUENCY

Example 7

3 Use order of operations to evaluate the following. Check your answer using a calculator.

a $2+3\times(-3)$ **b** $9+10\div(-5)$ **c** $20+(-4)\div 4$
d $18+(-9)\times 1$ **e** $10-2\times(-3)$ **f** $10-1\times(-4)$
g $-8-(-7)\times 2$ **h** $-2\times 4+8\times(-3)$ **i** $-3\times(-1)+4\times(-2)$
j $12\div(-6)+4\div(-2)$ **k** $-30\div 5-6\times 2$ **l** $-2\times 3-4\div(-2)$
m $8\times(-2)-(-3)\times 2$ **n** $-1\times 0-(-4)\times 1$ **o** $0\times(-3)-(-4)\times 0+0$

Example 8

4 Use order of operations to evaluate the following. Check your answer using a calculator.

a $(3+2)\times(-2)$ **b** $(8-4)\div(-2)$ **c** $-3\times(-2+4)$
d $-1\times(7-8)$ **e** $10\div(4-(-1))$ **f** $(2+(-3))\times(-9)$
g $(24-12)\div(16+(-4))$ **h** $(3-7)\div(-1+0)$ **i** $-2\times(8-4)+(-6)$
j $-2-3\times(-1+7)$ **k** $0+(-2)\div(1-2)$ **l** $1-2\times(-3)\div(-3-(-2))$
m $(-3+(-5))\times(-2-(-1))$ **n** $-3\div(-1+4)\times 6$ **o** $-5-(8+(-2))+9\div(-9)$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7E

5, 6 | 6, 7 | 6–8

PROBLEM-SOLVING

5 A shop owner had bought socks at $5 a pair but, during an economic downturn, sold them for $3 a pair. In a particular week, 124 pairs are sold and there are other costs of $280. What is the shop owner's overall loss for the week?



6 A debt of $550 is doubled and then $350 of debt is removed each month for 3 months. What is the final balance?

7 Insert brackets to make each statement true.

a $-2 + 3 \times 8 = 8$ **b** $-10 \div 4 + 1 = -2$ **c** $-1 + 7 \times 2 - 15 = -3$

d $-5 - 1 \div (-6) = 1$ **e** $3 - 8 \div 5 + 1 = 0$ **f** $50 \times 7 - 8 \times (-1) = 50$

g $-2 \times 3 - (-7) - 1 = -21$ **h** $-3 + 9 \div (-7) + 5 = -3$ **i** $32 - (-8) \div (-3) + 7 = 10$

8 By inserting only *one* pair of brackets, how many different answers are possible for this calculation? Also include the answers for which brackets are not used.

$-2 + 8 \times (-4) - (-3)$

9 | 9, 10 | 10, 11

REASONING

9 If brackets are removed from these problems, does the answer change?

a $(2 \times 3) - (-4)$ **b** $(8 \div (-2)) - 1$ **c** $(-2 + 3) \times 4$

d $9 \div (-4 + 1)$ **e** $(9 - (-3) \times 2) + 1$ **f** $(-1 + 8 \div (-2)) \times 2$

10 State if each of the following is generally true or false.

a $(-3 + 1) + (-7) = -3 + (1 + (-7))$ **b** $(-3 + 1) - (-7) = -3 + (1 - (-7))$

c $(a + b) + c = a + (b + c)$ **d** $(a + b) - c = a + (b - c)$

e $(a - b) + c = a - (b + c)$ **f** $(a - b) - c = a - (b - c)$

11 **a** Is the answer to each of the following positive or negative?

i $-6 \times (-4) \times (-8) \times (-108) \times (-96)$ **ii** $-100 \div (-2) \div 2 \div (-5)$

iii $(-3)^3$ **iv** $-1 \times (-2)^3$

v $\dfrac{-6 \times (-3) \times 4 \times 7 \times (-3)}{(-2)^2}$ **vi** $\dfrac{(-1)^2 \times (-1)}{(-1)^3 \times (-1)}$

b Explain the strategy you used to answer the questions in part **a**.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Powers and negative numbers — — 12,13 7E

ENRICHMENT

12 First, note that:

- $2^4 = 2 \times 2 \times 2 \times 2 = 16$
- $(-2)^4 = -2 \times (-2) \times (-2) \times (-2) = 16$
- $-2^4 = -(2 \times 2 \times 2 \times 2) = -16$

When evaluating expressions with powers, the power is dealt with first in the order of operations.
For example: $((-2)^3 - 1) \div (-3) = (-8 - 1) \div (-3) = -9 \div (-3) = 3$
Evaluate each of the following.

a 2^2 **b** $(-2)^2$ **c** -2^2
d $(-2)^5$ **e** -2^5 **f** $(3^2 - 1) \times 4$
g $((-3)^3 - 1) \div (-14)$ **h** $30 \div (1 - 4^2)$ **i** $-10\,000 \div (-10)^4$

13 Kevin wants to raise -3 to the power of 4. He types -3^4 into a calculator and gets -81.
Explain what Kevin has done wrong.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7F Substituting integers EXTENDING









The process known as substitution involves replacing a pronumeral or letter (sometimes called a variable) with a number. As a car accelerates, for example, its speed could be modelled by the rule $10 + 4t$. So, after 8 seconds we can calculate the car's speed by substituting $t = 8$ into $10 + 4t$.

So $10 + 4t = 10 + 4 \times 8 = 42$ metres per second.

We can also look at the car's speed before time $t = 0$. So at 2 seconds before $t = 0$ (i.e. $t = -2$), the speed would be $10 + 4t = 10 + 4 \times (-2) = 2$ metres per second.



We can use substitution to work out this car's speed at a given time.

Let's start: Order matters

Two students substitute the values $a = -2$, $b = 5$ and $c = -7$ into the expression $ac - bc$. Some of the different answers received are 21, –49, –21 and 49.

- Which answer is correct and what errors were made in the calculation of the other three incorrect answers?

Key ideas

- Substitute into an expression by replacing pronumerals (letters representing numbers) with numbers.

If $a = -3$ then

$$\begin{aligned} 3 - 7a &= 3 - 7 \times (-3) \\ &= 3 - (-21) \\ &= 3 + 21 \\ &= 24 \end{aligned}$$

- Brackets can be used around negative numbers to avoid confusion with other symbols.



Example 9 Substituting integers

Evaluate the following expressions using $a = 3$ and $b = -5$.

a $2 + 4a$ **b** $7 - 4b$ **c** $b \div 5 - a$

SOLUTION	EXPLANATION
a $2 + 4a = 2 + 4 \times 3$ $= 2 + 12$ $= 14$	Replace a with 3 and evaluate the multiplication first.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b $7 - 4b = 7 - 4 \times (-5)$
$= 7 - (-20)$
$= 7 + 20$
$= 27$

Replace the b with -5 and evaluate the multiplication before the subtraction.

c $b \div 5 - a = -5 \div 5 - 3$
$= -1 - 3$
$= -4$

Replace b with -5 and a with 3, and then evaluate.

Exercise 7F

1–3 | 3 | —

UNDERSTANDING

1 Which of the following shows the correct substitution of $a = -2$ into the expression $a - 5$?
A $2 - 5$ **B** $-2 + 5$ **C** $-2 - 5$ **D** $2 + 5$

2 Which of the following shows the correct substitution of $x = -3$ into the expression $2 - x$?
A $-2 - (-3)$ **B** $2 - (-3)$ **C** $-2 + 3$ **D** $-3 + 2$

3 Rafe substitutes $c = -10$ into $10 - c$ and gets 0. Is he correct? If not, what is the correct answer?

4–6 | 4–5(½), 6–7 | 4–7(½)

FLUENCY

Example 9a,b

4 Evaluate the following expressions using $a = 6$ and $b = -2$.
a $5 + 2a$ **b** $-7 + 5a$ **c** $b - 6$ **d** $b + 10$
e $4 - b$ **f** $7 - 2b$ **g** $3b - 1$ **h** $-2b + 2$
i $5 - 12 \div a$ **j** $1 - 60 \div a$ **k** $10 \div b - 4$ **l** $3 - 6 \div b$

Example 9c

5 Evaluate the following expressions using $a = -5$ and $b = -3$.
a $a + b$ **b** $a - b$ **c** $b - a$ **d** $2a + b$
e $5b + 2a$ **f** $6b - 7a$ **g** $-7a + b + 4$ **h** $-3b - 2a - 1$

6 Evaluate these expressions for the given pronumeral values.
a $26 - 4x$ $(x = -3)$ **b** $-2 - 7k$ $(k = -1)$
c $10 \div n + 6$ $(n = -5)$ **d** $-3x + 2y$ $(x = 3, y = -2)$
e $18 \div y - x$ $(x = -2, y = -3)$ **f** $-36 \div a - ab$ $(a = -18, b = -1)$

7 These expressions contain brackets. Evaluate them for the given pronumeral values. (Remember that ab means $a \times b$.)
a $2 \times (a + b)$ $(a = -1, b = 6)$ **b** $10 \div (a - b) + 1$ $(a = -6, b = -1)$
c $ab \times (b - 1)$ $(a = -4, b = 3)$ **d** $(a - b) \times bc$ $(a = 1, b = -1, c = 3)$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7F

8, 9	8, 9	9, 10

PROBLEM-SOLVING

8 The area of a triangle for a fixed base of 4 metres is given by the rule Area = $2h$ m^2, where h metres is the height of the triangle. Find the area of such a triangle with these heights.

a 3 m **b** 8 m

9 A motorcycle's speed, in metres per second, after a particular point on a racing track is given by the expression $20 + 3t$, where t is in seconds.

a Find the motorcycle's speed after 4 seconds.

b Find the motorcycle's speed at $t = -2$ seconds (i.e. 2 seconds before passing the $t = 0$ point).

c Find the motorcycle's speed at $t = -6$ seconds.

10 The formula for the perimeter, P, of a rectangle is $P = 2l + 2w$, where l and w are the length and the width, respectively.

a Use the given formula to find the perimeter of a rectangle with:

i $l = 3$ and $w = 5$ **ii** $l = 7$ and $w = -8$

b What problems are there with part **a ii** above?

11	11, 12	12, 13

REASONING

11 Write two different expressions involving x that give an answer of -10 if $x = -5$.

12 Write an expression involving the pronumeral a combined with other integers, so if $a = -4$ the expression would equal these answers.

a -3 **b** 0 **c** 10

13 If a and b are any non-zero integer, explain why these expressions will always give the result of zero.

a $a - b + b - a$ **b** $\frac{a}{a} - 1$ **c** $\frac{(a-a)}{b}$ **d** $\frac{ab}{b} - a$

Celsius/Fahrenheit

—	—	14

ENRICHMENT

14 The Fahrenheit temperature scale (°F) is still used today in some countries, but most countries use the Celsius scale (°C). 32°F is the freezing point for water (0°C). 212°F is the boiling point for water (100°C).


The formula for converting °F to °C is $°C = \frac{5}{9} \times (°F - 32)$.

a Convert these temperatures from °F to °C.

i 41°F **ii** 5°F **iii** -13°F

b Can you work out the formula that converts from °C to °F?

c Use your rule from part **b** to check your answers to part **a**.



The water temperature is 100°C and 212°F.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7G The number plane









During the seventeenth century, two well-known mathematicians, René Descartes and Pierre de Fermat, independently developed the idea of a number plane. The precise positions of points are illustrated using coordinates, and these points can be plotted using the axes as measuring guides. This invention revolutionised the study of mathematics and provided a vital link between geometry and algebra. The number plane or coordinate plane, is also called the Cartesian plane (named after Descartes). It uses two axes at right angles that extend in both the positive and negative directions.



Mathematician and philosopher René Descartes.

Let's start: North, south, east and west

The units for this grid are in metres.

René starts at position O and moves:

- 3 m east
- 2 m south
- 4 m west
- 5 m north.




Pierre starts at position O and moves:

- 1 m west
- 3 m south
- 4 m east
- 5 m north.

Using the number plane, how would you describe René and Pierre's final positions?

Key ideas


- The number plane (or Cartesian plane) uses two axes (x-axis and y-axis) at right angles. Each axis uses a scale that includes both positive and negative numbers.
- A point plotted on the plane has an x- and y-coordinate, which is written as (x, y). The x-coordinate is written before the y coordinate, as in the alphabet.
- The point (0, 0) is called the origin or O.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Finding coordinates

For the number plane shown, write down the coordinates of the points labelled A, B, C and D.



SOLUTION

$A = (1, 1)$

$B = (3, -2)$

$C = (-2, -4)$

$D = (-3, 3)$

EXPLANATION

For each point, write the x-coordinate first (from the horizontal axis) followed by the y-coordinate (from the vertical axis).

Exercise 7G

1, 2 | 2 | —


UNDERSTANDING

1 Match the points A, B, C, D, E, F, G and H with the given coordinates.

a $(-1, 3)$ **b** $(2, -3)$ **c** $(2, 1)$

d $(-2, -2)$ **e** $(3, 3)$ **f** $(-3, 1)$

g $(1, -2)$ **h** $(-1, -1)$



2 Count the number of points, shown as dots, on this plane that have:

a both x and y coordinates as positive numbers

b an x-coordinate as a positive number


c a y-coordinate as a positive number

d an x-coordinate as a negative number

e a y-coordinate as a negative number

f both x and y coordinates as negative numbers


g neither x nor y as positive or negative numbers



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10

3 For the Cartesian plane given, write down the coordinates of the points labelled A, B, C, D, E, F, G and H.




4 **a** Draw a set of axes using 1 cm spacings. Use –4 to 4 on both axes.

b Now plot these points.

i (–3, 2) **ii** (1, 4) **iii** (2, –1) **iv** (–2, –4)

v (2, 2) **vi** (–1, 4) **vii** (–3, –1) **viii** (1, –2)

5 For the number plane given, write down the coordinates of the points labelled A, B, C, D, E, F, G and H.



6 Seven points have the following x and y coordinates.

x	–3	–2	–1	0	1	2	3
y	–2	–1	0	1	2	3	4

a Plot the seven points on a Cartesian plane. Use –3 to 3 on the x-axis and –2 to 4 on the y-axis.

b What do you notice about these seven points on the Cartesian plane?

7 Seven points have the following x and y coordinates.

x	–3	–2	–1	0	1	2	3
y	5	3	1	–1	–3	–5	–7

a Plot the seven points on a number plane. Use –3 to 3 on the x-axis and –7 to 5 on the y-axis.

b What do you notice about these seven points on the number plane?

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7G

8, 9 | 9–11 | 10–12

PROBLEM-SOLVING

8 When plotted on the Cartesian plane, what shape does each set of points form?


a $A(-2, 0), B(0, 3), C(2, 0)$

b $A(-3, -1), B(-3, 2), C(1, 2), D(1, -1)$

c $A(-4, -2), B(3, -2), C(1, 2), D(-1, 2)$

d $A(-3, 1), B(-1, 3), C(4, 1), D(-1, -1)$

9 Using the origin as one corner, the point $A(3, 2)$ as the opposite corner and the axes as two of the sides, a rectangle can be positioned on a set of axes, as shown opposite. Its area is 6 square units. Find the area of the rectangle if the point A is:



a $(2, 2)$

b $(-3, 2)$

c $(-1, -4)$

d $(3, -5)$

10 Karen's bushwalk starts at a point $(2, 2)$ on a grid map. Each square on the map represents 1 km. If Karen walks to the points $(2, -7)$, then $(-4, -7)$, then $(-4, 0)$ and then $(2, 0)$, how far has she walked in total?



11 The points $A(-2, 0), B(-1, ?)$ and $C(0, 4)$ all lie on a straight line. Find the y-coordinate of point B.

12 The points $A(-4, 8), B(-1, ?)$ and $C(2, -2)$ all lie on a straight line. Find the y-coordinate of point B.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7G


13 | 13, 14 | 13, 14

REASONING

13 Consider the points $A(-2, 2)$, $B(0, 2)$ and $C(3, -2)$.

- **a** Which point is closest to $(0, 0)$?
- **b** Which point is farthest from $(0, 0)$?
- **c** List the given points in order from closest to farthest from the origin, O.

14 A point (a, b) sits on the number plane in one of the four regions 1, 2, 3 or 4, as shown. These regions are called **quadrants**.



- **a** Name the quadrant or quadrants that include the points where:
  - **i** $a > 0$
  - **ii** $a > 0$ and $b < 0$
  - **iii** $b < 0$
  - **iv** $a < 0$ and $b < 0$
- **b** Shade the region that includes all points for which $b > a$.

Rules and graphs | — | — | 15

ENRICHMENT

15 Consider the rule $y = 2x - 1$.

- **a** Substitute each given x-coordinate into the rule to find the y-coordinate. Then complete this table.

x	−3	−2	−1	0	1	2	3
y							

- **b** Draw a Cartesian plane, using −3 to 3 on the x-axis and −7 to 5 on the y-axis.
- **c** Plot each pair of coordinates (x, y) onto your Cartesian plane.
- **d** What do you notice about the set of seven points?



The Cartesian plane was the starting point for the development of computer-generated graphics and design.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Account balance with spreadsheets

If you have money saved in a bank account, your account balance should be positive. If you take out or spend too much money, your account balance may become negative.

a Set up a spreadsheet to record and calculate a bank balance. Enter the given information describing one week of deposits and withdrawals, as shown.



b **i** For the given spreadsheet, what is the balance at the end of May 1st?

ii On which day does the balance become negative?

c Enter this formula into cell E5 : = E4+C5–D5
Fill down to reveal the balance after each day.

d Enter another week of deposits and withdrawals so that the balance shows both positive and negative amounts.

e Now alter your opening balance. What opening balance is needed so that the balance never becomes negative? Is there more than one value? What is the least amount?

f Investigate how positive and negative numbers are used on credit card accounts. Give a brief explanation.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Find the next three numbers in these patterns.

a 3, –9, 27, ____, ____, ____

b –32, 16, –8, ____, ____, ____

c 0, –1, –3, –6, ____, ____, ____

d –1, –1, –2, –3, –5, ____, ____, ____

2 Evaluate the following.

a $-100 + (-98) + (-96) + \ldots + 98 + 100$

b $(50 - 53) + (49 - 52) + (48 - 51) + \ldots + (0 - 3)$

c $2 - 3 + 4 - 5 + 6 - 7 + \ldots - 199 + 200$

3 Insert brackets and symbols (+, –, ×, ÷) into these number sentences to make them true.

a $-3 \square 4 \square -2 = -6$

b $-2 \square 5 \square -1 \square 11 = 21$

c $1 \square 30 \square -6 \square -2 = -3$

4 **a** The difference between two numbers is 14 and their sum is 8. What are the two numbers?

b The difference between two numbers is 31 and their sum is 11. What are the two numbers?

5 If x and y are integers less than 10 and greater than –10, how many different integer pairs (x, y) make the equation $x + 2y = 10$ true?

6 In the sequence of numbers $\ldots, e, d, c, b, a, 0, 1, 1, 2, 3, 5, 8, 13, \ldots$ each number is the sum of its two preceding numbers, e.g. $13 = 5 + 8$. What are the values of a, b, c, d and e?

7 Given the rule $x^{-m} = \frac{1}{x^m}$, evaluate $-(-5)^{-2}$.

8 If $p > q > 0$ and $t < 0$, insert > or < to make each of these a true statement for all values of p, q and t.

a $p + t \square q + t$ **b** $t - p \square t - q$ **c** $pt \square qt$


9 Describe the set of all possible numbers for which the square of the number is greater than the cube of the number.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Integers
…, –3, –2, –1, 0, 1, 2, 3, …

Number line



–2 < 3 1 > –1


Adding and subtracting positive integers

–3 + 5 = 2
–4 + 3 = –1
5 – 7 = –2
–1 –10 = –11

Adding and subtracting negative integers

2 + (–3) = 2 – 3 = –1
–5 + (–4) = –5 – 4 = –9
4 – (–3) = 4 + 3 = 7
–10 – (–6) = –10 + 6 = –4

Cartesian plane



Multiplication (Ext)

2 × 3 = 6
2 × (–3) = –6
–2 × 3 = –6
–2 × (–3) = 6

Substitution (Ext)

If $a = -2$ and $b = 4$, then:
$b - a = 4 - (-2) = 6$
$ab + 2a = -2 \times 4 + 2 \times (-2)$
$= -8 + (-4)$
$= -12$

Division (Ext)

10 ÷ 5 = 2
10 ÷ (–5) = –2
–10 ÷ 5 = –2
–10 ÷ (–5) = 2

Order of operations (Ext)

First brackets, then × or ÷ then + or –, from left to right.

$3 \times (5 - (-2)) + 8 \div (-4)$
$= 3 \times 7 + (-2)$
$= 21 + (-2)$
$= 19$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

7A **1** When the numbers –4, 0, –1, 7 and –6 are arranged from lowest to highest, the correct sequence is:
A 0, –1, –4, –6, 7 **B** 0, –4, –6, –1, 7 **C** –6, –4, –1, 0, 7
D –1, –4, –6, 0, 7 **E** –6, –1, 0, –4, 7

7B **2** The difference between –19 and 8 is:
A 152 **B** –11 **C** –27 **D** 11 **E** 27

7C **3** The missing number in $2 - \square = 3$ is:
A 1 **B** –1 **C** 5 **D** –5 **E** 2

7C **4** $5 - (-2) + (-7)$ is equal to:
A –4 **B** 10 **C** 7 **D** 0 **E** 14

7A **5** The temperature inside a mountain hut is initially –5°C. After burning a fire for 2 hours the temperature rises to 17°C. What is the rise in temperature?
A –12°C **B** 12°C **C** 22°C **D** –85°C **E** –22°C

7D Ext **6** The product or quotient of two negative numbers is:
A positive **B** negative **C** zero **D** added **E** different

7D Ext **7** $-2 \times (-5) \div (-10)$ is equal to:
A –5 **B** 10 **C** –20 **D** 1 **E** –1

7E Ext **8** Which operation (i.e. addition, subtraction, multiplication or division) is completed second in the calculation of $(-2 + 5) \times (-2) + 1$?
A addition **B** subtraction **C** multiplication
D division **E** brackets

7F Ext **9** If $a = -2$ and $b = 5$, then $ab - a$ is equal to:
A –12 **B** –8 **C** 8 **D** 12 **E** 9

7G **10** The points $A(-2, 3)$, $B(-3, -1)$, $C(1, -1)$ and $D(0, 3)$ are joined on a number plane. What shape do they make?
A triangle **B** square **C** trapezium
D kite **E** parallelogram

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Short-answer questions

7A **1** Insert the symbol < (less than) or > (greater than) into each of these statements to make it true.

a $0 \square 7$ **b** $-1 \square 4$ **c** $3 \square -7$ **d** $-11 \square -6$

7B/C **2** Evaluate:

a $2 - 7$ **b** $-4 + 2$ **c** $0 - 15$ **d** $-36 + 37$

e $5 + (-7)$ **f** $-1 + (-4)$ **g** $10 - (-2)$ **h** $-21 - (-3)$

i $1 - 5 + (-2)$ **j** $-3 + 7 - (-1)$ **k** $0 + (-1) - 10$ **l** $-2 - (-3) - (-4)$

7C **3** Find the missing number for each of the following.

a $-2 + \square = -3$ **b** $-1 + \square = -10$ **c** $5 - \square = 6$ **d** $-2 - \square = -4$

e $-1 - \square = 20$ **f** $-15 - \square = -13$ **g** $7 + \square = -80$ **h** $-15 + \square = 15$

7D Ext **4** Evaluate:

a $5 \times (-2)$ **b** -3×7 **c** $-2 \times (-15)$ **d** $10 \div (-2)$

e $-36 \div 12$ **f** $-100 \div (-25)$ **g** $-3 \times 2 \div (-6)$ **h** $-38 \div (-19) \times (-4)$

7D Ext **5** Find the missing number.

a $4 \times \square = -8$ **b** $\square \div -5 = 10$ **c** $\square \div 9 = -4$ **d** $-1 \times \square = 1$

7E Ext **6** Use order of operations to find the answers to these expressions.

a $-2 + 5 \times (-7)$ **b** $-1 - 18 \div (-2)$


c $-15 \div (1 + 4)$ **d** $5 - 4 \times (-3) \div (-3)$

e $(-2 - 5) \times (8 \div (-1))$ **f** $-7 \times ((-4) - 7) + 3$

7F Ext **7** Evaluate the following expressions if $a = 7$, $b = -3$ and $c = -1$.

a $a - b$ **b** $2b - 5a$ **c** $ab + c$ **d** $bc - 2a$

7G **8** For the Cartesian plane shown, write down the coordinates of the points labelled A, B, C, D, E and F.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 A scientist, who is camped on the ice in Greenland, records the following details in her notepad regarding the temperature over five days. Note that 'min' stands for minimum and 'max' stands for maximum.

- Monday: min = –18°C, max = –2°C.
- Decreased 29°C from Monday's max to give Tuesday's min.
- Wednesday's min was –23°C.
- Max was only –8°C on Thursday.
- Friday's min is 19°C colder than Thursday's max.

a What is the overall temperature increase on Monday?

b What is Tuesday's minimum temperature?

c What is the difference between the minimum temperatures for Tuesday and Wednesday?

d What is the overall temperature drop from Thursday's maximum to Friday's minimum?

e By how much will the temperature need to rise on Friday if its maximum is 0°C?



2 When joined, these points form a picture on the number plane. What is the picture?
$A(0, 5), B(1, 3), C(1, 1), D(2, 0), E(1, 0), F(1, -2), G(3, -5),$
$H(-3, -5), I(-1, -2), J(-1, 0), K(-2, 0), L(-1, 1), M(-1, 3), N(0, 5)$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

Chapter

8 Statistics and probability

What you will learn

- 8A Collecting and classifying data
- 8B Summarising data numerically
- 8C Dot plots and column graphs
- 8D Line graphs
- 8E Stem-and-leaf plots
- 8F Pie charts and divided bar graphs (Extending)
- 8G Describing chance (Consolidating)
- 8H Theoretical probability
- 8I Experimental probability (Extending)

Australian curriculum

STATISTICS AND PROBABILITY

Chance

Construct sample spaces for single-step experiments with equally likely outcomes (ACMSPA167)

Assign probabilities to the outcomes of events and determine probabilities for events (ACMSPA168)

Data representation and interpretation

Identify and investigate issues involving continuous or large count data collected from primary and secondary sources (ACMSPA169)

Construct and compare a range of data displays including stem-and-leaf plots and dot plots (ACMSPA170)

Calculate mean, median, mode and range for sets of data. Interpret these statistics in the context of data (ACMSPA171)


Describe and interpret data displays and the relationship between the median and mean (ACMSPA172)

NUMBER AND ALGEBRA

Linear and non-linear relationships

Investigate, interpret and analyse graphs from authentic data (ACMNA180) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Codes and ciphers

Cracking codes and deciphering secret messages involves a lot of maths, from simple addition and subtraction to data handling and logical thinking.

One style of code replaces letters with symbols or pictures. This type of code was used in the sixteenth century by Mary Queen of Scots, when she was plotting against Queen Elizabeth I and sending coded messages about her plans to her co-conspirators. Unfortunately for Mary, there was a simple mathematical way of cracking the code. The letter 'E' is the most commonly used letter in the English language. 'T' is the second most common letter and 'A' is the third most commonly used letter.

All that Elizabeth's spymaster had to do to crack the code was to look through the coded message and count the number of times each symbol came up. The symbol that came up the most would probably stand for the letter 'E'. The next letter that occurred most often was probably 'T', and so forth. This method, called 'frequency analysis', gave the spymaster enough information to decode Mary's messages and foil her plans.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-9
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A Collecting and classifying data









People collect or use data almost every day. Athletes and sports teams look at performance data, customers compare prices at different stores, investors look at daily interest rates, and students compare marks with other students in their class. Companies often collect and analyse data to help produce and promote their products to customers and to make predictions about the future.



Let's start: Collecting data

Consider, as a class, the following questions and discuss their implications.

- Have you or your family ever been surveyed by a telemarketer at home? What did they want? What time did they call?
- Do you think that telemarketers get accurate data? Why or why not?
- Why do you think companies collect data this way?
- If you wanted information about the most popular colour of car sold in NSW over the course of a year, how could you find out this information?

Key ideas

- In statistics, a **variable** is something measurable or observable that is expected to change over time or between individual observations. It can be numerical or categorical.
  - **Numerical** (**quantitative**) which can be discrete or continuous:
    - **Discrete numerical** – data that can only be particular numerical values, e.g. the number of TV sets in a house (could be 0, 1, 2, 3 but not values in between like 1.3125).
    - **Continuous numerical** – data that can take any value in a range. Variables such as heights, weights and temperatures are all continuous. For instance, someone could have a height of 172 cm, 172.4 cm, or 172.215 cm (if it can be measured accurately).
  - **Categorical** – data that are not numerical such as colours, gender, brands of cars are all examples of categorical data. In a survey, categorical data comes from answers which are given as words (e.g. 'yellow' or 'female') or ratings (e.g. 1 = dislike, 2 = neutral, 3 = like).
- Data can be collected from primary or secondary sources.
  - Data from a **primary source** are firsthand information collected from the original source by the person or organisation needing the data, e.g. a survey an individual student conducts or census data collected and then used by an organisation like the Bureau of Statistics.
  - Data from a **secondary source** have been collected, published and possibly summarised by someone else before we use it. Data collected from newspaper articles, textbooks or internet blogs represent secondary source data.
- Samples and populations
  - When an entire population (e.g. a maths class, all the cars in a parking lot, a company, or a whole country) is surveyed, it is called a **census**.
  - When a subset of the population is surveyed, it is called a **sample**. Samples should be randomly selected and large enough to represent the views of the overall population.
  - When we cannot choose which members of the population to survey, and can record only those visible to us (e.g. people posting their political views on a news website), this is called an **observation**.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Classifying variables

Classify the following variables as categorical, discrete numerical or continuous numerical.

a the gender of a newborn baby

b the length of a newborn baby

SOLUTION	EXPLANATION
a categorical	As the answer is 'male' or 'female' (a word, not a number) the data are categorical.
b continuous numerical	Length is a measurement, so all numbers are theoretically possible.

Example 2 Collecting data from primary and secondary sources

Decide whether a primary source or a secondary source is suitable for collection of data on each of the following and suggest a method for its collection.

a the average income of Australian households

b the favourite washing powder or liquid for households in Australia

SOLUTION	EXPLANATION
a primary source by looking at the census data	The population census held every 5 years in Australia is an example of a primary data source collection and will have this information.
b secondary data source using the results from a market research agency	A market research agency might collect these results using a random phone survey. Obtaining a primary source would involve conducting the survey yourself but it is unlikely that the sample will be large enough to be suitable.

Exercise 8A

1–3 | 2 | —

UNDERSTANDING

1 Match each word on the left to its meaning on the right.

a sample	i only takes on particular numbers within a range
b categorical	ii a complete set of data
c discrete numerical	iii a smaller group taken from the population
d primary source	iv data grouped in categories like 'male' and 'female'
e continuous numerical	v data collected firsthand
f population	vi can take on any number in a range

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A

Example 1

UNDERSTANDING

2 Classify the following as categorical or numerical.

- **a** the eye colour of each student in your class
- **b** the date of the month each student was born, e.g. the 9th of a month
- **c** the weight of each student when they were born
- **d** the brands of airplanes landing at Sydney's international airport
- **e** the temperature of each classroom
- **f** the number of students in each classroom period one on Tuesday

3 Give an example of:

a discrete numerical data **b** continuous numerical data **c** categorical data

4–5(½), 6 | 4–5(½), 6 | 4–5(½), 6

FLUENCY

4 Classify the following variables as categorical, continuous numerical or discrete numerical data.

- **a** the number of cars per household
- **b** the weights of packages sent by Australia Post of the 20th of December
- **c** the highest temperature of the ocean each day
- **d** the favourite brand of chocolate of the teachers at your school
- **e** the colours of the cars in the school car park
- **f** the brands of cars in the school car park



- **g** the number of letters in different words on a page
- **h** the number of advertisements in a time period over each of the free-to-air channels
- **i** the length of time spent doing this exercise
- **j** the arrival times of planes at JFK airport
- **k** the daily pollutions level in the M5
- **l** the number of text messages sent by an individual yesterday
- **m** the times for the 100 m freestyle event at the world championships over the last 10 years
- **n** the number of Blu-ray discs someone owns
- **o** the brands of cereals available at the supermarket
- **p** marks awarded on a maths test
- **q** the star rating on a hotel or motel
- **r** the censorship rating on a movie showing at the cinema

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 Is observation or a sample or a census the most appropriate way to collect data on each of the following?

- **a** the arrival times of trains at central station during a day
- **b** the arrival times of trains at central station over the year
- **c** the heights of students in your class
- **d** the heights of all Year 7 students in the school
- **e** the heights of all Year 7 students in NSW
- **f** the number of plastic water bottles sold in a year
- **g** the religion of Australian families
- **h** the number of people living in each household in your class
- **i** the number of people living in each household in your school
- **j** the number of people living in each household in Australia
- **k** the number of native Australian birds found in a suburb
- **l** the number of cars travelling past a school between 8 a.m. and 9 a.m. on a school day
- **m** the money spent by students during a week at the canteen
- **n** the ratings of TV shows







ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.

8A

Example 2

FLUENCY

6 Identify whether a primary or secondary source is suitable for the collection of data on the following.

a the number of soft drinks bought by the average Australian family in a week
b the age of school leavers in far North Queensland
c the number of cigarettes consumed by school age students in a day
d the highest level of education by the adults in a household
e the reading level of students in Year 7 in Australia



7, 8 | 7, 9–11 | 10–12

PROBLEM-SOLVING

7 Give a reason why someone might have trouble obtaining reliable and representative data using a primary source to find the following.

a the temperature of the Indian Ocean over the course of a year
b the religions of Australian families
c the average income of someone in India
d drug use by teenagers within a school
e the level of education of different cultural communities within NSW

8 Secondary sources are already published data that are then used by another party in their own research. Why is the use of this type of data not always reliable?

9 When obtaining primary source data you can survey the population or a sample.

a Explain the difference between a 'population' and a 'sample' when collecting data.
b Give an example situation where you should survey a population rather than a sample.
c Give an example situation where you should survey a sample rather than a population.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A

PROBLEM-SOLVING

10 A Likert-type scale is for categorical data where items are assigned a number; for example, the answer to a question could be 1 = dislike, 2 = neutral, 3 = like.

- **a** Explain why the data collected are categorical even though the answers are given as numbers.
- **b** Give examples of a Likert-type scale for the following categorical data. You might need to reorder some of the options.
  - **i** strongly disagree, somewhat disagree, somewhat agree, strongly agree
  - **ii** excellent, satisfactory, poor, strong
  - **iii** never, always, rarely, usually, sometimes
  - **iv** strongly disagree, neutral, strongly agree, disagree, agree

11 A sample should be representative of the population it reports on. For the following surveys, describe who might be left out and how this might introduce a bias.

- **a** a telephone poll with numbers selected from a phone book
- **b** a postal questionnaire
- **c** door-to-door interviews during the weekdays
- **d** a *Dolly* magazine poll
- **e** a Facebook survey

12 Another way to collect primary source data is by direct observation. For example, the colour of cars travelling through an intersection (categorical data) is best obtained in this way rather than through a questionnaire.

- **a** Give another example of a variable for which data could be collected by observation.
- **b** Explain how you could estimate the proportion of black cars parked at a large shopping centre car park without counting every single one.

13 | 14, 15 | 14, 16

REASONING

13 When conducting research on Indigenous Australians, the elders of the community are often involved. Explain why the community is needed to be involved in the research process.

14 Television ratings are determined by surveying a sample of the population

- **a** Explain why a sample is taken rather than conducting a census.
- **b** What would be a limitation of the survey results if the sample included 50 people nationwide?
- **c** If a class census was taken on which (if any) television program students watched from 7.30–8.30 last night, why might the results be different to the official ratings?
- **d** Research how many people are sampled by Nielsen Television Audience Measurement in order to get an accurate idea of viewing habits and stick within practical limitations.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8A

REASONING

15 Australia's census surveys the entire population every five years.

- **a** Why might Australia not conduct a census every year?
- **b** Over 40% of all Australians were born overseas or had at least one of their parents born overseas. How does this impact the need to be culturally sensitive when designing and undertaking a census?
- **c** The census can be filled out on a paper form or using the internet. Given that the data must be collated in a computer eventually, why does the government still allow paper forms to be used?
- **d** Why might a country like India or China conduct their national census every 10 years?

16 Write a sentence explaining why two different samples taken from the same population can produce different results. How can this problem be minimised?

Collecting a sample — — 17


ENRICHMENT

17 a Use a random number generator on your calculator or computer to record the number of times the number 1 to 5 appears (you could even use a die by re-rolling whenever you get a 6) out of 50 trials. Record these data.

- **i** Tabulate your results.
- **ii** Compare the results of the individuals in the class.
- **iii** Explain why differences between different students might occur.

b Choose a page at random from a novel or an internet page and count how many times each vowel (A, E, I, O, U) occurs. Assign each vowel the following value
A = 1, E = 2, I = 3, O = 4, U = 5 and tabulate your results.

- **i** Why are the results different from those in part **a**?
- **ii** How might the results for the vowels vary depending on the webpage or novel chosen?



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8B Summarising data numerically

Interactive

Widgets

HOTsheets

Walkthroughs

Although sometimes it is important to see a complete set of data, either as a list of numbers or as a graph, it is often useful to summarise the data with a few numbers.

For example, instead of listing the height of every Year 7 student in a school, you could summarise this by stating the median height and the difference (in cm) between the tallest and shortest people.



Let's start: Class summary

For each student in the class, find their height (in cm), their age (in years), and how many siblings they have.

- Which of these three sets would you expect to have the largest range?
- Which of these three sets would you expect to have the smallest range?
- What do you think is the mean height of students in the class? Can you calculate it?

Key ideas

- The **range** of a set of data is given by:
  Range = highest number – lowest number.

  1 6 7 1 5 → range = 7 – 1 = 6
  ↑ ↑
  lowest highest

- The **mean** of a set of data is given by:
  Mean = (sum of all the values) ÷ (total number of values)

  $1 + 6 + 7 + 1 + 5 = 20 \rightarrow$ mean = 4

- The **median** is the middle value if the values are sorted from lowest to highest. If there are two middle values, then add them together and divide by 2.

  1 1 (5) 6 7
  ↑
  middle → median = 5

- The **mode** is the most common value. It is the value that occurs most frequently. We also say that it is the value with the highest frequency. There can be more than one mode.

  (1) (1) 5 6 7 → mode = 1

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Finding the range, mean, median and mode

Consider the ages (in years) of seven people who are surveyed in a shop:
15, 31, 12, 47, 21, 65, 12

a Find the range of values.
b Find the mean of this set of data.
c Find the median of this set of data.
d Find the mode of this set of data.
e If another person is surveyed who is 29 years old, what will be the new median?

SOLUTION	EXPLANATION
a range = 65 – 12 = 53	Highest number = 65, lowest number = 12 The range is the difference.
b mean = 203 ÷ 7 = 29	Sum of values = 15 + 31 + 12 + 47 + 21 + 65 + 12 = 203 Number of values = 7
c values: 12, 12, 15, **21**, 31, 47, 65 median = 21	Place the numbers in ascending order and see that the middle value is 21.
d mode = 12	The most common value is 12.
e values: 12, 12, 15, **21**, **29**, 31, 47, 65 new median = 25	Place the numbers in ascending order. Now there are two middle values (21 and 29), so the median is $\frac{21+29}{2} = \frac{50}{2} = 25$.

Exercise 8B

1–3 | 1, 3 | —

UNDERSTANDING

Example 3a

1 Consider the set of numbers 1, 5, 2, 10, 3.
a Write the numbers from smallest to largest.
b State the largest number.
c State the smallest number.
d What is the range?

2 State the range of the following sets of numbers.
a 2, 10, 1, 3, 9
b 6, 8, 13, 7, 1
c 0, 6, 3, 9, 1
d 3, 10, 7, 5, 10

Example 3b–d

3 For the set of numbers 1, 5, 7, 7, 10, find the:
a total of the numbers when added
b mean
c median
d mode

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8B

FLUENCY

4(½), 5 | 4(½), 5, 6 | 4(½), 5, 6

Example 3e

4 For each of the following sets of data, calculate the:

i range ii mean iii median iv mode

a 1, 7, 1, 2, 4
b 2, 2, 10, 8, 13
c 3, 11, 11, 14, 21
d 25, 25, 20, 37, 25, 24
e 1, 22, 10, 20, 33, 10
f 55, 24, 55, 19, 15, 36
g 114, 84, 83, 81, 39, 12, 84
h 97, 31, 18, 54, 18, 63, 6

5 The number of aces that a tennis player serves per match is recorded over eight matches.

Match	1	2	3	4	5	6	7	8
Number of aces	11	18	11	17	19	22	23	12

a What is the mean number of aces the player serves per match? Round your answer to 1 decimal place.
b What is the median number of aces the player serves per match?
c What is the range of this set of data?

6 Brent and Ali organise their test marks for a number of topics in Maths, in a table.

	Test 1	Test 2	Test 3	Test 4	Test 5	Test 6	Test 7	Test 8	Test 9	Test 10
Brent	58	91	91	75	96	60	94	100	96	89
Ali	90	84	82	50	76	67	68	71	85	57

a Which boy has the higher mean?
b Which boy has the higher median?
c Which boy has the smaller range?
d Which boy do you think is better at tests? Explain why.

PROBLEM-SOLVING

7, 8 | 8–10 | 9–11

7 The set 3, 7, 9, 10 has one extra number added to it, and this causes the mean to be doubled. What is the number?

8 Alysha's tennis coach records how many double faults Alysha has served per match over a number of matches. Her coach presents the results in a table.

Number of double faults	0	1	2	3	4
Number of matches with this many double faults	2	3	1	4	2

a In how many matches does Alysha have no double faults?
b In how many matches does Alysha have 3 double faults?
c How many matches are included in the coach's study?
d What is the total number of double faults scored over the study period?
e Calculate the mean of this set of data, correct to 1 decimal place.
f What is the range of the data?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8B

PROBLEM-SOLVING

9 A soccer goalkeeper recorded the number of saves he makes per game during a season. He presents his records in a table.

Number of saves	0	1	2	3	4	5
Number of games	4	3	0	1	2	2

a How many games did he play that season?
b What is the mean number of saves this goalkeeper made per game?
c What is the most common number of saves that the keeper had to make during a game?



10 Give an example of a set of data with:
a a mean of 10 and a range of 2
b a median of 10 and a range of 5
c a range of 100 and a mean of 50
d a mean of 6, a median of 7 and a mode of 5

11 The set 1, 2, 5, 5, 5, 8, 10, 12 has a mode of 5 and a mean of 6.
a If a set of data has a mode of 5 (and no other modes) and a mean of 6, what is the smallest number of values the set could have? Give an example.
b Is it possible to make a dataset for which the mode is 5, the mean is 6 and the range is 20? Explain your answer.

12 | 12, 13 | 14–16

REASONING

12 Evie surveys all the students in her class to find the distance from their homes to school. One of the students is on exchange from Canada and reports a distance of 16 658 km. Would this very large value have a greater effect on the mean or median distance? Explain your answer.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8B

REASONING

13 Consider the set of values 1, 3, 5, 10, 10, 13.

a Find the mean, median, mode and range.

b If each number is increased by 5, state the effect this has on the:

i mean **ii** median **iii** mode **iv** range

c If each of the original numbers is doubled, state the effect this has on the:

i mean **ii** median **iii** mode **iv** range

d Is it possible to include extra numbers and keep the same mean, median, mode and range? Try to expand this set to at least 10 numbers, but keep the same values for the mean, median, mode and range.

14 **a** Two whole numbers are chosen with a mean of 10 and a range of 6. What are the numbers?

b Three whole numbers are chosen with a mean of 10 and a range of 2. What are the numbers?

c Three whole numbers are chosen with a mean of 10 and a range of 4. Can you determine the numbers? Try to find more than one possibility.

15 Prove that for three consecutive numbers, the mean will equal the median.

16 A **frequency table** shows how common an event is. For instance, Magda has presented her weekly spelling test scores as a frequency table.

Score	4	5	6	7	8	9	10
Frequency	1	5	5	11	12	5	1

This is easier than writing out the results as 4, 5, 5, 5, 5, 5, 6, 6, 6, 6, 6, . . . , 9, 10.

a State the range of scores and the mean score, correct to 2 decimal places.

b If the frequency of each score is reduced by 1, describe the effect this will have on the range and the mean of the scores.

Mean challenges — — 17, 18

ENRICHMENT

17 For the set of numbers 1, 2, 3, . . . , 100, find the mean.

18 **a** Give an example of a set of numbers with the following properties.

i mean = median = mode

ii mean > median > mode

iii mode > median > mean

iv median < mode < mean

b If the range of a set of data is 1, is it still possible to find datasets for each of parts **i** to **iv** above?



An important aspect of scientific investigation is collecting data and summarising it numerically.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8C Dot plots and column graphs

Interactive


Widgets

HOTsheets


Walkthroughs

Numerical and categorical data can be shown graphically using **dot plots**, where each value is represented as a filled circle. More commonly, it is represented using **column graphs**, where the height of each column represents a number. Column graphs can be drawn vertically or horizontally.


Consider a survey of students who are asked to choose their favourite colour from five possibilities. The results could be represented as a dot plot or as a column graph.



Represented as a dot plot



As a column graph (vertical)



As a column graph (horizontal)

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Let's start: Favourite colours

Survey the class to determine each student's favourite colour from the possibilities red, green, yellow, blue and pink.


- Each student should draw a column graph or a dot plot to represent the results.
- What are some different ways that the results could be presented into a column graph? (There are more than 200 ways.)

Key ideas

- A **dot plot** can be used to display data, where each dot represents one **datum**.
- A **column graph** is an alternative way to show data in different categories, and is useful when more than a few items of data are present.
- Column graphs can be drawn vertically or horizontally.
- Graphs should have the following features:




- Any numerical axis must be drawn to scale.
- An **outlier** is a value that is noticeably distinct from the main cluster of points.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Example 4 Interpreting a dot plot

The dot plot below represents the results of a survey that asked some children how many pets they have at home.



a Use the graph to state how many children have 2 pets.
b How many children participated in the survey?
c What is the range of values?
d What is the median number of pets?
e What is the outlier?
f What is the mode?

SOLUTION	EXPLANATION
a 4 children	There are 4 dots in the '2 pets' category, so 4 children have 2 pets.
b 22 children	The total number of dots is 22.
c 8 – 0 = 8	Range = highest – lowest In this case, highest = 8, lowest = 0.
d 1 pet	As there are 22 children, the median is the average of the 11th and 12th value. In this case, the 11th and 12th values are both 1.
e the child with 8 pets	The main cluster of children has between 0 and 3 pets, but the person with 8 pets is significantly outside this cluster.
f 1 pet	The most common number of pets is 1.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 5 Constructing a column graph

Draw a column graph to represent the following people's heights.

Name	Tim	Phil	Jess	Don	Nyree
Height (cm)	150	120	140	100	130

SOLUTION



EXPLANATION

First decide which scale goes on the vertical axis.

Maximum height = 150 cm, so axis goes from 0 cm to 160 cm (to allow a bit above the highest value).

Remember to include all the features required, including axes labels and a graph title.


Exercise 8C

1, 2 | 2 | —

UNDERSTANDING

1 The graph opposite shows the height of four boys.
Answer true or false to each of the following statements.

- **a** Mick is 80 cm tall.
- **b** Vince is taller than Tranh.
- **c** Peter is the shortest of the four boys.
- **d** Tranh is 100 cm tall.
- **e** Mick is the tallest of the four boys.






ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8C

Example 4a,b

UNDERSTANDING

2 The favourite after-school activity of a number of Year 7 students is recorded in the dot plot below.






a How many students have chosen television as their favourite activity?
b How many students have chosen social networking as their favourite activity?
c What is the most popular after-school activity for this group of students?
d How many students participated in the survey?

3–7 3–8 4, 6–8

FLUENCY

3 From a choice of pink, blue, yellow, green or red, each student of Year 7B chose their favourite colour. The results are graphed below.



a How many students chose yellow?
b How many students chose blue?
c What is the most popular colour?
d How many students participated in the class survey?
e Represent these results as a dot plot.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4c–f

4 In a Year 4 class, the results of a spelling quiz are presented as a dot plot.


a What is the most common score in the class?

b How many students participated in the quiz?


c What is the range of scores achieved?

d What is the median score?

e Identify the outlier.



5 Joan has graphed her height at each of her past five birthdays.





a How tall was Joan on her 9th birthday?

b How much did she grow between her 8th birthday and 9th birthday?

c How much did Joan grow between her 8th and 12th birthdays?

d How old was Joan when she had her biggest growth spurt?

Example 5

6 Draw a column graph to represent each of these boys' heights at their birthdays.

a Mitchell

Age (years)	Height (cm)
8	120
9	125
10	135
11	140
12	145

b Fatu


Age (years)	Height (cm)
8	125
9	132
10	140
11	147
12	150

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8C

FLUENCY

7 Every five years, a company in the city conducts a transport survey of people's preferred method of getting to work in the mornings. The results are graphed below.



a Copy the following table into your workbook and complete it, using the graph.

	1990	1995	2000	2005	2010	2015
Use public transport	30					
Drive a car	60					
Walk or cycle	10					

b In which year(s) is public transport the most popular option?

c In which year(s) are more people walking or cycling to work than driving?

d Give a reason why the number of people driving to work has decreased.

e What is one other trend that you can see from looking at this graph?





8 **a** Draw a column graph to show the results of the following survey of the number of boys and girls born at a certain hospital. Put time (years) on the horizontal axis.

	2000	2001	2002	2003	2004	2005
Number of boys born	40	42	58	45	30	42
Number of girls born	50	40	53	41	26	35

b During which year(s) were there more girls born than boys?


c Which year had the fewest number of births?

d Which year had the greatest number of births?

e During the entire period of the survey, were there more boys or girls born?


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9 The average (mean) income of adults in a particular town is graphed over a 6-year period.



- **a** Describe in one sentence what has happened to the income over this period of time.
- **b** Estimate what the income in this town might have been in 2009.
- **c** Estimate what the average income might be in 2025 if this trend continues.

10 A survey is conducted of students' favourite subjects from a choice of Art, Maths, English, History and Science. Someone has attempted to depict the results in a column graph.



- **a** What is wrong with the scale on the vertical axis?
- **b** Give at least two other problems with this graph.
- **c** Redraw the graph with an even scale and appropriate labels.
- **d** The original graph makes Maths look twice as popular as Art, based on the column size. According to the survey, how many times more popular is Maths?
- **e** The original graph makes English look three times more popular than Maths. According to the survey, how many times more popular is English?
- **f** Assume that Music is now added to the survey's choice of subjects. Five students who had previously chosen History now choose Music, and 16 students who had previously chosen English now choose Music. What is the most popular subject now?




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8C

PROBLEM-SOLVING

11 Mr Martin and Mrs Stevensson are the two Year 3 teachers at a school. For the latest arithmetic quiz, they have plotted their students' scores on a special dot plot called a parallel dot plot, shown opposite.




- **a** What is the median score for class 3M?
- **b** What is the median score for class 3S?
- **c** State the range of scores for each class.
- **d** Based on this test, which class has a greater spread of arithmetic abilities?
- **e** If the two classes competed in an arithmetic competition, where each class is allowed only one representative, which class is more likely to win? Justify your answer.

12 | 12, 13 | 12, 13

REASONING

12 At a central city train station, three types of services run – local, country and interstate. The average number of passenger departures during each week is shown in the stacked column graph.



- **a** Approximately how many passenger departures per week were there in 2010?
- **b** Approximately how many passenger departures were there *in total* during 2015?
- **c** Does this graph suggest that the total number of passenger departures has increased or decreased during the period 2010–2015?
- **d** Approximately how many passengers departed from this station in the period 2010–2015? Explain your method clearly and try to get your answer within 10 000 of the actual number.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


13 Explain why it is important to align dot points in a dot plot. Illustrate your explanation with two dot plots of the set of data below.

Activity	Netball	Dancing	Tennis	Chess
Number of students	5	3	2	4


How many ways? — — 14

14 As well as being able to draw a graph horizontally or vertically, the order of the categories can be changed. For instance, the following three graphs all represent the same data.





How many different column graphs could be used to represent the results of this survey? (Assume that you can only change the order of the columns, and the horizontal or vertical layout.) Try to list the options systematically to help with your count.





ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D Line graphs

Interactive

Widgets


HOTsheets

Walkthroughs

A **line graph** is a connected set of points joined with straight line segments. The variables on both axes should be continuous numerical data. It is often used when a measurement varies over time, in which case time is conventionally listed on the horizontal axis. One advantage of a line graph over a series of disconnected points is that it can often be used to estimate values that are unknown.

Let's start: Room temperature


As an experiment, the temperature in two rooms is measured hourly over a period of time. The results are graphed below.




- Each room has a heater and an air conditioner to control the temperature. At what point do you think these were switched on and off in each room.
- For each room, what is the approximate temperature 90 minutes after the start of the experiment?
- What is the proportion of time that room A is hotter than room B?

Key ideas

- The variables on both axes should be **continuous** numerical data.
- A **line graph** consists of a series of points joined by straight line segments.
- Time is often shown on the horizontal axis.



- A common type of line graph is a travel graph.
  - Time is shown on the horizontal axis.
  - Distance is shown on the vertical axis.
  - The slope of the line indicates the rate at which the distance is changing over time. This is called **speed**.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 6 Drawing a line graph

The temperature in a room is noted at hourly intervals.


Time	9:00 am	10:00 am	11:00 am	12:00 pm	1:00 pm
Temperature (°C)	10	15	20	23	18

a Present the results as a line graph.

b Use your graph to estimate the room temperature at 12:30 pm.

SOLUTION

a



b About 20°C

EXPLANATION

- The vertical axis is from 0 to 25. The scale is even (i.e. increasing by 5 each time).
- Dots are placed for each measurement and joined with straight line segments.

By looking at the graph halfway between 12 pm and 1 pm an estimate is formed.

Example 7 Interpreting a travel graph

This travel graph shows the distance travelled by a cyclist over 5 hours.


a How far did the cyclist travel in total?

b How far did the cyclist travel in the first hour?

c What is happening in the second hour?

d When is the cyclist travelling the fastest?

e In the fifth hour, how far does the cyclist travel?



SOLUTION

a 30 km

b 15 km

c at rest

d in the first hour

e 5 km

EXPLANATION

The right end point of the graph is at (5, 30).

At time equals 1 hour, the distance covered is 15 km.

The distance travelled does not increase in the second hour.

This is the steepest part of the graph.

In the last 3 hours, the distance travelled is 15 km, so in 1 hour, 5 km is travelled.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Exercise 8D

1, 2 | 1, 2 | —

UNDERSTANDING

1 The line graph shows the weight of a cat over a 3-month period. It is weighed at the start of each month. State the cat's weight at the start of:

- **a** January
- **b** February
- **c** March
- **d** April





Example 6a

2 A dog is weighed over a period of 3 months.
Draw a line graph of its weight.
January: 5 kg, February: 6 kg, March: 8 kg, April: 7 kg.


3–6 | 3–7 | 3, 5–7

FLUENCY

Example 6b

3 The graph shows Lillian's height over a 10-year period from when she was born.

- **a** What was Lillian's height when she was born?
- **b** What was Lillian's height at the age of 7 years?
- **c** At what age did she first reach 130 cm tall?
- **d** How much did Lillian grow in the year when she was 7 years old?
- **e** Use the graph to estimate her height at the age of $9\frac{1}{2}$ years.




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D

FLUENCY

4 Consider the following graph, which shows the outside temperature over a 24-hour period that starts at midnight.

- **a** What was the temperature at midday?
- **b** When was the hottest time of the day?
- **c** When was the coolest time of the day?
- **d** Use the graph to estimate the temperature at these times of the day:
  - **i** 4:00 am
  - **ii** 9:00 am
  - **iii** 1:00 pm
  - **iv** 3:15 pm



5 Oliver measures his pet dog's weight over the course of a year, by weighing it at the start of each month. He obtains the following results.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Weight (kg)	7	7.5	8.5	9	9.5	9	9.2	7.8	7.8	7.5	8.3	8.5


- **a** Draw a line graph showing this information, making sure the vertical axis has an equal scale from 0 kg to 10 kg.
- **b** Describe any trends or patterns that you see.
- **c** Oliver put his dog on a weight loss diet for a period of 3 months. When do you think the dog started the diet? Justify your answer.



Example 7

6 This travel graph shows the distance travelled by a van over 6 hours.

- **a** How far did the van travel in total?
- **b** How far did the van travel in the first hour?
- **c** What is happening in the fourth hour?
- **d** When is the van travelling the fastest?
- **e** In the sixth hour, how far does the van travel?




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8D

FLUENCY

7 This travel graph shows the distance travelled by a bushwalker over 5 hours.




- **a** For how long was the bushwalker at rest?
- **b** How far did the bushwalker walk in the second hour?
- **c** During which hour did the bushwalker walk the fastest?

8 8 8, 9

PROBLEM-SOLVING

8 The water storage levels for a given city are graphed based on the percentage of water available on the first day of each month. For this question, assume that the amount of water used does not change from month to month.



- **a** During which month did it rain the most in this city?
- **b** At what time(s) in the year is the water storage below 40%?
- **c** From August to September, it rained a total of 20 megalitres of water. How much water did the people in the city use during this period?
- **d** Is it more likely that this city is located in the Northern Hemisphere or the Southern Hemisphere? Justify your answer.




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D

PROBLEM-SOLVING

9 The temperature in a lounge room is measured frequently throughout a particular day. The results are presented in a line graph, as shown below. The individual points are not indicated on this graph to reduce clutter.





a Twice during the day the heating was switched on. At what times do you think this happened? Explain your reasoning.

b When was the heating switched off? Explain your reasoning.

c The house has a single occupant, who works during the day. Describe when you think that person is:

i waking up **ii** going to work **iii** coming home **iv** going to bed

d These temperatures were recorded during a cold winter month. Draw a graph that shows what the lounge room temperature might look like during a hot summer month. Assume that the room has an air conditioner, which the person is happy to use when at home.

10a 10 10

REASONING

10 Draw travel graphs to illustrate the following journeys.

a A car travels:

- 120 km in the first 2 hours
- 0 km in the third hour
- 60 km in the fourth hour
- 120 km in the fifth hour

b A jogger runs:

- 12 km in the first hour
- 6 km in the second hour
- 0 km in the third hour
- at a rate of 6 km per hour for 2 hours




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D Which hemisphere? — — 11

ENRICHMENT

11 The following line graph shows the average monthly temperature in a city.




a Is this city in the Northern or Southern Hemisphere? Explain why.

b Is this city close to the equator or far from the equator? Explain why.

c Redraw the graph to start the 12-month period at July and finish in June.

d Describe how the new graph's appearance is different from the one shown above.

e In another city, somebody graphs the temperature over a 12-month period, as shown below. In which hemisphere is this city likely to be? Explain your answer.





ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8E Stem-and-leaf plots

Interactive

Widgets

HOTsheets

Walkthroughs

A stem-and-leaf plot is a useful way of presenting numerical data in a way that allows trends to be spotted easily. Each number is split into a stem (the first digit or digits) and a leaf (the last digit).

	Stem	Leaf
53 is	5	3
78 is	7	8
125 is	12	5

By convention, leaves are shown in increasing order as you work away from the stem, and stems are shown in increasing order going down the page.

The advantage of presenting data like this comes when multiple numbers have the same stem. For example, the list 122, 123, 124, 124, 127, 129 can be represented as shown opposite.



Stem	Leaf						
12	2	3	4	4	7	7	9

Let's start: Test score analysis

In a class, students' most recent test results out of 50 are recorded.

Test 1 results
43, 47, 50, 26, 38, 20, 25, 20, 50, 44,
33, 47, 47, 50, 37, 28, 28, 22, 21, 29

Test 2 results

Stem	Leaf
1	8
2	7 8
3	2 2 4 5 5 7 9
4	0 1 2 3 3 6 8 8
5	0 0

- For each test, try to find how many students:
  - achieved a perfect score (i.e. 50)
  - failed the test (i.e. less than 25)
  - achieved a mark in the 40s.
- If there are 100 test results that you wish to analyse, would you prefer a list or a stem-and-leaf plot?
- What is it that makes a stem-and-leaf plot easier to work with? Discuss.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- A stem-and-leaf plot is a way to display numerical data.
- Each number is usually split into a **stem** (the first digit or digits) and a **leaf** (the last digit). For example:

	Stem	Leaf
The number 7 is	0	7
The number 31 is	3	1
The number 152 is	15	2

- Leaves should be aligned vertically, listed in ascending order as you move away from the stem.
- Any outliers can be identified by looking at the lowest value or highest value to see if they are far away from all the other numbers.

Example 8 Interpreting a stem-and-leaf plot

Average daily temperatures are shown for some different countries.

Stem	Leaf
1	3 6 6
2	0 0 1 2 5 5 6 8 9
3	0 2

a Write out the temperatures as a list.
b How many countries' temperatures are represented?
c What are the minimum and maximum temperatures?
d What is the range of temperatures recorded?
e What is the median temperature recorded?

SOLUTION	EXPLANATION
a 13, 16, 16, 20, 20, 21, 22, 25, 25, 26, 28, 29, 30, 32	Each number is converted from a stem and a leaf to a single number. For example, $1\vert 3$ is converted to 13.
b 14	The easiest way is to count the number of leaves – each leaf corresponds to one country.
c minimum = 13 maximum = 32	The first stem and leaf is $1\vert 3$ and the last stem and leaf is $3\vert 2$.
d range = 19	Range = maximum – minimum = 32 – 13 = 19.
e median = 23.5	The middle value is halfway between the numbers $2\vert 2$ and $2\vert 5$, so median = $\frac{1}{2}(22 + 25) = 23.5$.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Creating a stem-and-leaf plot

Represent this set of data as a stem-and-leaf plot:
23, 10, 36, 25, 31, 34, 34, 27, 36, 37, 16, 33

SOLUTION

Sorted: 10, 16, 23, 25, 27, 31, 33, 34, 34, 36, 36, 37

Stem	Leaf
1	0 6
2	3 5 7
3	1 3 4 4 6 6 7

EXPLANATION

Sort the list in increasing order so that it can be put directly into a stem-and-leaf plot.

Split each number into a stem and a leaf. Stems are listed in increasing order and leaves are aligned vertically, listed in increasing order down the page.

Exercise 8E

1–3 | 1, 3 | —

UNDERSTANDING

1 The number 52 is entered into a stem-and-leaf plot.
- **a** What digit is the stem?
- **b** What digit is the leaf?

2 What number is represented by the following combinations?
- **a** 3|9
- **b** 2|7
- **c** 13|4

3 In this stem-and-leaf plot, the smallest number is 35. What is the largest number?

Stem	Leaf
3	5 7 7 9
4	2 8
5	1 7

4–6 | 4, 5, 6–7(½) | 4, 5, 6–7(½)

FLUENCY

Example 8a–c

4 This stem-and-leaf plot shows the ages of people in a group.

Stem	Leaf
0	8 9
1	0 1 3 5 7 8
2	1 4

- **a** Write out the ages as a list.
- **b** How many ages are shown?
- **c** Answer true or false to each of the following.
  - **i** The youngest person is aged 10.
  - **ii** Someone in the group is 17 years old.
  - **iii** Nobody listed is aged 20.
  - **iv** The oldest person is aged 4.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8E

FLUENCY

Example 8d,e

5 For each of the stem-and-leaf plots below, state the range and the median.

a

Stem	Leaf
0	9
1	3 5 6 7 7 8 9
2	0 1 9

b

Stem	Leaf
1	1 4 8
2	1 2 4 4 6 8
3	0 3 4 7 9
4	2

c

Stem	Leaf
3	1 1 2 3 4 4 8 8 9
4	0 1 1 2 3 5 7 8
5	0 0 0

Example 9

6 Represent each of the following sets of data as a stem-and-leaf plot.

a 11, 12, 13, 14, 14, 15, 17, 20, 24, 28, 29, 31, 32, 33, 35

b 20, 22, 39, 45, 47, 49, 49, 51, 52, 52, 53, 55, 56, 58, 58

c 21, 35, 24, 31, 16, 28, 48, 18, 49, 41, 50, 33, 29, 16, 32

d 32, 27, 38, 60, 29, 78, 87, 60, 37, 81, 38, 11, 73, 12, 14

7 Represent each of the following datasets as a stem-and-leaf plot. (Remember: 101 is represented as 10|1.)

a 80, 84, 85, 86, 90, 96, 101, 104, 105, 110, 113, 114, 114, 115, 119

b 120, 81, 106, 115, 96, 98, 94, 115, 113, 86, 102, 117, 108, 91, 95

c 192, 174, 155, 196, 185, 178, 162, 157, 173, 181, 158, 193, 167, 192, 184, 187, 193, 165, 199, 184

d 401, 420, 406, 415, 416, 406, 412, 402, 409, 418, 404, 405, 391, 411, 413, 413, 408, 395, 396, 417



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8, 9 | 9, 10 | 10–12

8E

PROBLEM-SOLVING

8 This back-to-back stem-and-leaf plot shows the ages of all the people in two shops. The youngest person in shop 1 is 15 (not 51).

Shop 1	Stem	Shop 2
5	1	6 7
7 7 5 3	2	4 5
	3	1
2	4	5

For each statement below, state whether it is true in shop 1 only (1), shop 2 only (2), both shops (B) or neither shop (N).

- **a** This shop has a 31-year-old person in it.
- **b** This shop has six people in it.
- **c** This shop has a 42-year-old person in it.
- **d** This shop has a 25-year-old person in it.
- **e** This shop has two people with the same age.
- **f** This shop has a 52-year-old person in it.
- **g** This shop has a 24-year-old person in it.
- **h** This shop's oldest customer is an outlier.
- **i** This shop's youngest customer is an outlier.



9 A company recorded the duration (in seconds) that visitors spent on its website's home page.

Stem	Leaf
0	2 4 6 8 9
1	0 0 1 2 8
2	2 7 9
3	
4	
5	8

- **a** How many visitors spent less than 20 seconds on the home page?
- **b** How many visitors spent more than half a minute?
- **c** How many visitors spent between 10 and 30 seconds?
- **d** What is the outlier for this stem-and-leaf plot?
- **e** The company wishes to summarise its results with a single number. 'Visitors spend approximately ____ on our home page.' What number could it use?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8E

PROBLEM-SOLVING

10 Two radio stations poll their audience to determine their ages.

a Find the age difference between the oldest and youngest listener polled for:

i station 1

ii station 2

Station 1	Stem	Station 2
0	1	2 3 3 4 5 6 8 9
8 7	2	0 0 1 2 4 5 8 8
9 7 5 4 3 3	3	1 1 2
7 6 5 5 4 4 1	4	8
9 3 2 0	5	

b One of the radio stations plays contemporary music that is designed to appeal to teenagers and the other plays classical music and broadcasts the news. Which radio station is most likely to be the one that plays classical music and news?

c Advertisers wish to know the age of the stations' audiences so that they can target their advertisements more effectively (e.g. to 38 to 58 year olds). Give a 20-year age range for the audience majority who listen to:

i station 1 **ii** station 2



11 A group of boys and girls have their heights recorded in a back-to-back stem-and-leaf plot, shown here.

a State the range of heights for:

i boys **ii** girls

b Which gender has a bigger range?

c State the median height for:

i boys **ii** girls

d Which gender has the larger median height?

e Which year level do you think these boys and girls are in? Justify your answer.

f Describe how you might expect this back-to-back stem-and-leaf plot to change if it recorded the heights of male and female Year 12 students.

Girls	Stem	Boys
	10	
	11	
6 3 1	12	
8 4 3 2	13	8
7 6 5 4 0	14	3 4 7 9
6 4 1	15	0 1 2 4 6
2 0	16	2 3 6 8
3	17	

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8E

PROBLEM-SOLVING

12 A teacher has compiled her students' recent test scores out of 50 as a stem-and-leaf plot. However, some values are missing, as represented by the letters a, b, c and d.

a How many students took the test?

b How many students passed the test (i.e. achieved a mark of 25 or higher)?

c State the possible values for each of the missing digits a to d.

Stem	Leaf
1	5
2	4 5 a 6 7 9
3	b 0 1 5
4	2 8 c
5	d

13 | 13, 14 | 13, 14

REASONING

13 **a** Explain why it is important that leaves are aligned vertically. (Hint: Consider how the overall appearance could be helpful with a large dataset.)

b Why might it be important that data values are sorted in stem-and-leaf plots?

14 A stem-and-leaf plot is constructed showing the ages of all the people who attended a local farmer's market at a certain time of the day. However, the plot's leaves cannot be read.

Stem	Leaf
1	?
2	?
3	? ? ? ? ? ? ? ? ? ?
4	? ? ? ? ? ? ? ? ? ? ? ? ? ? ?
5	? ? ?

a For each of the following, either determine the exact answer or give a range of values the answer could take.

i How many people were at the market?

ii How many people aged in their 30s were at the market?

iii How old is the youngest person?

iv What is the age difference between the youngest and oldest person?

v How many people aged 40 or over were at the market?

vi How many people aged 35 or over were at the market?



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8E

REASONING

b Classify each of the following as true or false.
- **i** The majority of people at the market were aged in their 30s or 40s.
- **ii** There were five teenagers present.
- **iii** Exactly two people were aged 29 years or under.
- **iv** Two people in their 40s must have had the same age.
- **v** Two people in their 30s must have had the same age.
- **vi** Two people in their 20s could have had the same age.

c Explain why it is possible to determine how many people were aged 40 or over, but not the number of people who are aged 40 or under.

d It is discovered that the person under 20 years of age is an outlier for this market. What does that tell you about how old the next oldest person is?

Negative stem-and-leaf plots — — 15

ENRICHMENT

15 Negative numbers can also be displayed in stem-and-leaf plots. This stem-and-leaf plot gives the average winter temperatures in 15 different cities.

Stem	Leaf
–2	9 4 4
–1	7 5 3 2
–0	8 5
0	3 4 6
1	5 8
2	3

a What are the minimum and maximum temperatures listed?

b Find how many cities had average temperatures:
- **i** between –10°C and 10°C
- **ii** between –25°C and 5°C
- **iii** below 5°C

c Why is there a 0 row and a –0 row, even though 0 and –0 are the same number?

d What is the average (or mean) of all the listed temperatures in the 15 cities? Give your answer correct to 1 decimal place.

e What is the median of all the listed temperatures? Compare this to the mean found in part **d**.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8F Pie charts and divided bar graphs EXTENDING











A pie chart (also called sector graph) consists of a circle divided into different sectors or 'slices of pie', where the size of each sector indicates the proportion occupied by any given item. A divided bar graph is a rectangle divided into different rectangles or 'bars', where the size of each rectangle indicates the proportion of each item.

If a student is asked to describe how much time they spend each evening doing different activities, they could present their results as either type of graph:






From both graphs, it is easy to see that most of the student's time is spent playing sport and the least amount of time is spent using the internet.

Let's start: Student hobbies

Rania, Kristina and Ralph are asked to record how they spend their time after school. They draw the following graphs.



- Based on these graphs alone, describe each student in a few sentences.
- Justify your descriptions based on the graphs.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- To calculate the size of each section of the graph, divide the value in a given category by the sum of all category values. This gives the category's proportion or fraction.
- To draw a **pie chart** (also called a **sector graph**), multiply each category's proportion or fraction by 360° and draw a sector of that size.
- To draw a **divided bar graph**, multiply each category's proportion or fraction by the total width of the rectangle and draw a rectangle of that size.

Example 10 Drawing a pie chart and a divided bar graph

On a particular Saturday, Sanjay measures the number of hours he spends on different activities.


Television	Internet	Sport	Homework
1 hour	2 hours	4 hours	3 hours

Represent the table as:


a a pie chart **b** a divided bar graph

SOLUTION

a



b



EXPLANATION

The total amount of time is $1 + 2 + 4 + 3 = 10$ hours. Then we can calculate the proportions and sector sizes:

Category	Proportion	Sector size (°)
Television	$\frac{1}{10}$	$\frac{1}{10} \times 360 = 36$
Internet	$\frac{2}{10} = \frac{1}{5}$	$\frac{1}{5} \times 360 = 72$
Sport	$\frac{4}{10} = \frac{2}{5}$	$\frac{2}{5} \times 360 = 144$
Homework	$\frac{3}{10}$	$\frac{3}{10} \times 360 = 108$

Using the same proportions calculated above, make sure that each rectangle takes up the correct amount of space. For example, if the total width is 15 cm, then sport occupies $\frac{2}{5} \times 15 = 6$ cm.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 8F

1, 2 | 2 | —


UNDERSTANDING

1 Jasna graphs a pie chart of how she spends her leisure time.


a What does Jasna spend the most time doing?

b What does Jasna spend the least time doing?

c Does she spend more or less than half of her time playing sport?



2 Thirty students are surveyed to find out their favourite sport and their results are graphed below.



a What is the most popular sport for this group of students?

b What is the least popular sport for this group of students?

c What fraction of the students has chosen soccer as their favourite sport?

d What fraction of the students has chosen either rugby or AFL?

3, 4 | 3–5 | 3–5

FLUENCY

Example 10a

3 A group of passengers arriving at an airport is surveyed to establish which countries they have come from. The results are presented below.

Country	China	United Kingdom	USA	France
No. of passengers	6	5	7	2

a What is the total number of passengers who participated in the survey?

b What proportion of the passengers surveyed have come from the following countries? Express your answer as a fraction.

i China **ii** United Kingdom **iii** USA **iv** France

c On a pie chart, determine the angle size of the sector representing:

i China **ii** United Kingdom **iii** USA **iv** France

d Draw a pie chart showing the information calculated in part **c**.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8F

Example 10b

FLUENCY

4 A group of students in Years 7 and 8 is polled on their favourite colour, and the results are shown at right.

Colour	Year 7 votes	Year 8 votes
Red	20	10
Green	10	4
Yellow	5	12
Blue	10	6
Pink	15	8

- **a** Draw a pie chart to represent the Year 7 colour preferences.
- **b** Draw a different pie chart to represent the Year 8 colour preferences.
- **c** Describe two differences between the charts.
- **d** Construct a divided bar graph that shows the popularity of each colour across the total number of Years 7 and 8 students combined.

5 Consider the following results of a study on supermarket shopping habits.


Items	Food	Drinks	Household items	Other
Proportion of money spent	50%	25%	20%	5%

- **a** Represent this information in a divided bar graph.
- **b** Graph this information as a sector graph.

6 | 6, 7 | 7, 8

PROBLEM-SOLVING


6 A group of Year 7 students was polled on their favourite foods, and the results are shown in this pie chart.



- **a** If 40 students participated in the survey, find how many of them chose:
  - **i** chocolate
  - **ii** chips
  - **iii** fruit
  - **iv** pies
- **b** Health experts are worried about what these results mean. They would like fruit to appear more prominently in the pie graph, and to not have the chocolate sector next to the chips. Redraw the pie chart so this is the case.
- **c** Another 20 students were surveyed. Ten of these students chose chocolate and the other 10 chose chips. Their results are to be included in the pie graph. Of the four sectors in the graph, state which sector will:
  - **i** increase in size
  - **ii** decrease in size
  - **iii** stay the same size

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 Yakob has asked his friends what is their favourite school subject, and he has created the following divided bar graph from the information.



a If Yakob surveyed 30 friends, state how many of them like:

i Maths best **ii** History best **iii** either English or Science best

b Redraw these results as a pie chart.


8 Friends Krishna and Nikolas have each graphed their leisure habits, as shown below.

a Which of the two friends spends more of their time playing sport?

b Which of the two friends does more intellectual activities in their leisure time?


c Krishna has only 2 hours of leisure time each day because he spends the rest of his time doing homework. Nikolas has 8 hours of leisure time each day. How does this affect your answers to parts **a** and **b** above?

Krishna's leisure time



Nikolas' leisure time








ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8F

9a–c | 9a–d | 9

REASONING

9 In two surveys, people were asked what is their favourite pet animal.



a If 16 people participated in survey 1, how many chose dog?

b If 30 people participated in survey 2, how many chose bird?

c Jason claims that 20 people participated in survey 1. Explain clearly why this cannot be true.

d Jaimee claims that 40 people participated in survey 2. Explain clearly why this cannot be true.




e In actual fact, the same number of people participated for each survey. Given that fewer than 100 people participated, how many participants were there? Give all the possible answers.

Rearranging graphs

— | — | 10

ENRICHMENT

10 Consider the divided bar graph shown below.



a Show how this graph will look if the segments are placed in the order C, D, A, B (from left to right).

b In how many different ways could this divided bar graph be drawn (counting ABCD and CDAB as two different ways)?

c If this bar graph is redrawn as a pie chart, how many ways could the segments be arranged? Try to list them systematically. Do not consider two pie charts to be different if one is just a rotation of another.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

8A **1** Classify the following variables as categorical, discrete numerical or continuous numerical.

a eye colour
b animal weight (kg)
c number of siblings
d time to run 100 metres (sec)


8B **2** For each of the following sets of data, calculate the:

i range ii mean iii median iv mode

a 5, 12, 3, 8, 2, 9, 3
b 15, 24, 22, 28, 16, 15

8C **3** This dot plot represents the number of children in each family of some Year 7 students.

a What is the most common family size in this class? (family size means the number of children)
b How many families are shown by this graph, assuming there are no siblings within the class?
c What is the range of family sizes?
d What is the median family size?
e Identify the outlier.




8D **4** The temperature outside a classroom was recorded four times during one school day. The following results were obtained.

Time	9 am	11 am	1 pm	3 pm
Temperature	15°C	20°C	28°C	25°C

a Draw a line graph showing this information.
b Use your graph to estimate the temperature at noon.

8D **5** This travel graph shows the distance travelled by a cyclist over 5 hours.

a How far did the cyclist travel in total?
b How far had the cyclist travelled after 3 hours?
c What is happening in the fourth hour?
d In the fifth hour, how far did the cyclist travel?
e During what hour was the cyclist travelling the fastest?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8E **6** This stem-and-leaf table shows the noon temperatures (in °C) of different towns around Australia on one particular day.

Stem	Leaf
1	4 7 8
2	0 2 4 5 7 8 8 9
3	0 3 7

a How many towns have their temperatures listed in this stem-and-leaf table?
b What is the maximum and minimum noon temperature recorded?
c What is the range of temperatures recorded?
d What is the median temperature recorded?

8E **7** Represent this set of data as a stem-and-leaf plot: 10, 21, 16, 18, 7, 19, 18, 9, 20, 12

8F **8** Some Year 7 students were asked how they travelled to school. The results are shown in this table.

Ext

Public transport	Bicycle	Car
14	2	4

a Represent the data as a pie chart.
b Represent the data as a divided bar graph of total length 15 cm.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

8G Describing chance

CONSOLIDATING









Often, there are times when you may wish to describe how likely it is that an event will occur. For example, you may want to know how likely it is that it will rain tomorrow, or how likely your sporting team will win this year's premiership, or how likely it is that you will win a lottery. Probability is the study of chance.



The probability of winning first prize in a lottery is very, very low.

Let's start: Likely or unlikely?


Try to rank these events from least likely to most likely. Compare your answers with other students in the class and discuss any differences.

- It will rain tomorrow.
- Australia will win the soccer World Cup.
- Tails landing uppermost when a 20-cent coin is tossed.
- The Sun will rise tomorrow.
- The king of spades is at the top of a shuffled deck of 52 playing cards.
- A diamond card is at the bottom of a shuffled deck of 52 playing cards.



Key ideas

- When using the English language to describe chance, there are a number of phrases that can be used.



- If two events have the same chance of occurring, then you say that it is **equally likely** they will occur.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 11 Describing chance

Classify each of the following statements as either true or false.

a It is likely that children will go to school next year.

b It is an even chance for a fair coin to display tails.

c Rolling a 3 on a 6-sided die and getting heads on a coin are equally likely.

d It is certain that two randomly chosen odd numbers will add to an even number.

SOLUTION	EXPLANATION
a true	Although there is perhaps a small chance that the laws might change, it is (very) likely that children will go to school next year.
b true	There is a 50-50, or an even chance, of a fair coin displaying tails. It will happen, on average, half of the time.
c false	These events are not equally likely. It is more likely to flip heads on a coin than to roll a 3 on a 6-sided die.
d true	No matter what odd numbers are chosen, they will always add to an even number.

Exercise 8G

1, 2 | 1 | —

UNDERSTANDING

1 Match each of the events **a** to **d** with a description of how likely they are to occur (**A** to **D**).

a A tossed coin landing heads up.	**A** unlikely
b Selecting an ace first try from a fair deck of 52 playing cards.	**B** likely
c Obtaining a number other than 6 if a fair 6-sided die is rolled.	**C** impossible
d Obtaining a number greater than 8 if a fair 6-sided die is rolled.	**D** even chance

2 Fill in the blanks, using the appropriate terminology.

a If an event is guaranteed to occur, we say it is _____.

b An event that is equally likely to occur or not occur has an _____ _____.

c A rare event is considered _____.

d An event that will never occur is called _____.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3, 4 | 3–5 | 3–5

8G

FLUENCY

Example 11

3 Consider a fair 6-sided die with the numbers 1 to 6 on it. Answer true or false to each of the following.



- **a** Rolling a 3 is unlikely.
- **b** Rolling a 5 is likely.
- **c** Rolling a 4 and rolling a 5 are equally likely events.
- **d** Rolling an even number is likely.
- **e** There is an even chance of rolling an odd number.
- **f** There is an even chance of rolling a multiple of 3.


4 Match up each of the events **a** to **d** with an equally likely event **A** to **D**.

- **a** Rolling a 2 on a 6-sided die
- **b** Selecting a heart card from a fair deck of 52 playing cards
- **c** Flipping a coin and tails landing face up
- **d** Rolling a 1 or a 5 on a 6-sided die

- **A** Selecting a black card from a fair deck of 52 playing cards
- **B** Rolling a number bigger than 4 on a 6-sided die
- **C** Selecting a diamond card from a fair deck of 52 playing cards
- **D** Rolling a 6 on a 6-sided die



5 Consider the spinner shown, which is spun and could land with the arrow pointing to any of the three colours. (If it lands on a boundary, it is re-spun until it lands on a colour.)



- **a** State whether each of the following is true or false.
  - **i** There is an even chance that the spinner will point to green.
  - **ii** It is likely that the spinner will point to red.
  - **iii** It is certain that the spinner will point to purple.
  - **iv** It is equally likely that the spinner will point to red or blue.
  - **v** Green is twice as likely to occur as blue.
- **b** Use the spinner to give an example of:
  - **i** an impossible event
  - **ii** a likely event
  - **iii** a certain event
  - **iv** two events that are equally likely


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8G

6 6, 7 7, 8

PROBLEM-SOLVING

6 Three spinners are shown below. Match each spinner with the description.




spinner 1 spinner 2 spinner 3

a Has an even chance of red, but blue is unlikely.
b Blue and green are equally likely, but red is unlikely.
c Has an even chance of blue, and green is impossible.


7 Draw spinners to match each of the following descriptions, using blue, red and green as the possible colours.
a Blue is likely, red is unlikely and green is impossible.
b Red is certain.
c Blue has an even chance, red and green are equally likely.
d Blue, red and green are all equally likely.
e Blue is twice as likely as red, but red and green are equally likely.
f Red and green are equally likely and blue is impossible.
g Blue, red and green are all unlikely, but no two colours are equally likely.
h Blue is three times as likely as green, but red is impossible.

8 For each of the following spinners, give a description of the chances involved so that someone could determine which spinner is being described. Use the colour names and the language of chance (i.e. 'likely', 'impossible' etc.) in your descriptions.


a




b




c




d



e




f



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 A coin consists of two sides that are equally likely to occur when tossed. It is matched up with a spinner that has exactly the same chances, as shown below.




Tossing the coin with heads landing uppermost is equally likely to spinning red on the spinner. Tossing the coin with tails landing uppermost is equally likely to spinning blue on the spinner. Hence, we say that the coin and the spinner are **equivalent**.

a Draw a spinner that is equivalent to a fair 6-sided die. (Hint: The spinner should have six sections of different colours.)

b How can you tell from the spinner you drew that it is equivalent to a fair die?

c A die is 'weighted' so that there is an even chance of rolling a 6, but rolling the numbers 1 to 5 are still equally likely. Draw a spinner that is equivalent to such a die.

d How could you make a die equivalent to the spinner shown in the diagram?




e Describe a spinner that is equivalent to selecting a card from a fair deck of 52 playing cards.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


8G Spinner proportions — — 10

ENRICHMENT


10 The language of chance is a bit vague. For example, for each of the following spinners it is 'unlikely' that you will spin red, but in each case the chance of spinning red is different.



spinner 1



spinner 2



spinner 3

Rather than describing this in words we could give the fraction (or decimal or percentage) of the spinner occupied by a colour.

a For each of the spinners above, give the fraction of the spinner occupiedby red.

b What fraction of the spinner would be red if it had an even chance?

c Draw spinners for which the red portion occupies:

i 100% of the spinner **ii** 0% of the spinner

d For the sentences below, fill in the gaps with appropriate fraction or percentage values.

i An event has an even chance of occurring if that portion of the spinner occupies _____ of the total area.


ii An event that is impossible occupies _____ of the total area.

iii An event is unlikely to occur if it occupies more than _____ but less than _____ of the total area.

iv An event is likely if it occupies more than _____ of the total area.

e How can the fractions help determine if two events are equally likely?

f Explain why all the fractions occupied by a colour must be between 0 and 1.



The game of 'Twister' uses a spinner (being held by the girl at the back) to determine the positions to be attempted.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2 © Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8H Theoretical probability










The **probability** of an event occurring is a number between 0 and 1. This number states precisely how likely it is for an event to occur. It is often written as a fraction and can indicate how frequently the event would occur over a large number of trials. For example, if you toss a fair coin many times, you would expect heads to come up half the time, so the probability is $\frac{1}{2}$. If you roll a fair 6-sided die many times, you should roll a 4 about one-sixth of the time, so the probability is $\frac{1}{6}$.

To be more precise, we should list the possible outcomes of rolling the die: 1, 2, 3, 4, 5, 6. Doing this shows us that there is a 1 out of 6 chance that you will roll a 4 and there is a 0 out of 6 (= 0) chance of rolling a 9.

Let's start: Spinner probabilities

Consider the three spinners shown below.



- What is the probability of spinning blue for each of these spinners?
- What is the probability of spinning red for each of these spinners?
- Try to design a spinner for which the probability of spinning green is $\frac{4}{7}$ and the probability of spinning blue is 0.




- An **experiment** or **trial** could be tossing a coin, rolling a die or spinning a spinner.
- An **outcome** is a possible result of the experiment, like rolling a 5 or a coin showing tails.
- An **event** is either a single outcome (e.g. rolling a 3) or a collection of outcomes (e.g. rolling a 3, 4 or 5).
- The **probability** of an event is a number between 0 and 1 inclusive, to represent the chance of the event occurring. The probability of an event occurring, if all the outcomes are equally likely, is:

$$\frac{\text{number of outcomes where the event occurs}}{\text{total number of outcomes}}$$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- Probability is often written as a fraction, but it can be written as a decimal or as a percentage.
- The **sample space** is the set of all possible outcomes of an experiment.
- We write Pr(green) to mean 'the probability that a spinner shows green'.



Example 12 Calculating probability

A fair 6-sided die is rolled.

a List the sample space.

b Find the probability of rolling a 3, giving your answer as a fraction.

c Find the probability of rolling an even number, giving your answer as a decimal.

d Find the probability of rolling a number less than 3, giving your answer as a percentage.

SOLUTION	EXPLANATION
a sample space = {1, 2, 3, 4, 5, 6}	For the sample space, we list all the possible outcomes. Technically, the sample space is {roll a 1, roll a 2, roll a 3, roll a 4, roll a 5, roll a 6}, but we do not usually include the additional words.
b $\Pr(3) = \frac{1}{6}$	The event can occur in one way (rolling a 3) out of six possible outcomes.
c $\Pr(\text{even}) = \frac{1}{2} = 0.5$	The event can occur in three ways (i.e. 2, 4 or 6). So the probability is $\frac{3}{6} = \frac{1}{2}$. As a decimal this is 0.5.
d $\Pr(\text{less than } 3) = \frac{1}{3} = 33.3\%$	The event can occur in two ways (1 or 2). So the probability is $\frac{2}{6} = \frac{1}{3}$. As a percentage this is 33.3%, rounded to 1 decimal place.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 8H

1–3 | 3 | —

UNDERSTANDING

1 Match up each experiment **a** to **d** with the list of possible outcomes **A** to **D**.

a tossing a coin
b rolling a die
c selecting a suit from a fair deck of 52 playing cards
d choosing a colour on the French flag

A 1, 2, 3, 4, 5, 6
B red, white, blue
C heads, tails
D hearts, diamonds, clubs, spades



The French flag is divided into three sections of different colours and equal size.

2 Complete the following sentences.

a The _____ _____ is the set of possible outcomes.
b An impossible event has a probability of _____.
c If an event has a probability of 1, then it is _____.
d The higher its probability, the _____ likely the event will occur.
e An event with a probability of $\frac{1}{2}$ has an ____ ____ of occurring.

Example 12a

3 Consider a fair 6-sided die.

a List the sample space.
b List the odd numbers on the die.
c State the probability of throwing an even number.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


8H

4–6 | 4–7 | 4, 5, 7

FLUENCY

Example 12b–d

4 Consider the spinner shown.



- **a** How many outcomes are there? List them.
- **b** Find Pr(red); i.e. find the probability of the spinner pointing to red.
- **c** Find Pr(red or green).
- **d** Find Pr(not red).
- **e** Find Pr(yellow).

5 A spinner with the numbers 1 to 7 is spun. The numbers are evenly spaced.



- **a** List the sample space.
- **b** Find Pr(6).
- **c** Find Pr(8).
- **d** Find Pr(2 or 4).
- **e** Find Pr(even).
- **f** Find Pr(odd).
- **g** Give an example of an event having the probability of 1.

6 The letters in the word MATHS are written on 5 cards and then one is drawn from a hat.

- **a** List the sample space.
- **b** Find Pr(T), giving your answer as a decimal.
- **c** Find Pr(consonant is chosen), giving your answer as a decimal.
- **d** Find the probability that the letter drawn is also in the word TAME, giving your answer as a percentage.

7 The letters in the word PROBABILITY are written on 11 cards and then one is drawn from a hat.

- **a** Find Pr(P).
- **b** Find Pr(P or L).
- **c** Find Pr(letter chosen is in the word BIT).
- **d** Find Pr(not a B).
- **e** Find Pr(a vowel is chosen).
- **f** Give an example of an event with the probability of $\frac{3}{11}$.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8 | 8, 9 | 9, 10


8H

PROBLEM-SOLVING

8 A bag of marbles contains 3 red marbles, 2 green marbles and 5 blue marbles. They are all equal in size and weight. A marble is chosen at random.

- **a** What is the probability that a red marble is chosen? (Hint: It is not $\frac{1}{3}$ because the colours are not all equally likely.) Give your answer as a percentage.
- **b** What is the probability that a blue marble is chosen? Give your answer as a percentage.
- **c** What is the probability that a green marble is *not* chosen? Give your answer as a percentage.

9 Consider the spinner opposite, numbered 2 to 9.



- **a** List the sample space.
- **b** Find the probability that a prime number will be spun, giving your answer as a decimal. (Remember that 2 is a prime number.)
- **c** Giving your answers as decimals, state the probability of getting a prime number if each number in the spinner opposite is:
  - **i** increased by 1
  - **ii** increased by 2
  - **iii** doubled

  (Hint: It will help if you draw the new spinner.)
- **d** Design a new spinner for which the Pr(prime) = 1.

10 A bag contains various coloured marbles – some are red, some are blue, some are yellow and some are green. You are told that Pr(red) = $\frac{1}{2}$, Pr(blue) = $\frac{1}{4}$ and Pr(yellow) = $\frac{1}{6}$. You are not told the probability of selecting a green marble.

- **a** If there are 24 marbles:
  - **i** Find how many there are of each colour.
  - **ii** What is the probability of getting a green marble?
- **b** If there are 36 marbles:
  - **i** Find how many there are of each colour.
  - **ii** What is the probability of getting a green marble?
- **c** What is the minimum number of marbles in the bag?
- **d** Does the probability of getting a green marble depend on the actual number of marbles in the bag? Justify your answer.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

8H

11 | 11 | 11, 12

REASONING

11 a State the values of the pronumerals in the following table.

Event	Pr(event occurs)	Pr(event does not occur)	Sum of two numbers
Rolling a die, get a 3	$\frac{1}{6}$	$\frac{5}{6}$	a
Tossing a coin, get H	$\frac{1}{2}$	b	c
Rolling a die, get 2 or 5	d	$\frac{2}{3}$	e
Selecting a letter from 'HEART', getting a vowel	f	g	h

b If the probability of selecting a vowel in a particular word is $\frac{3}{13}$, what is the probability of selecting a consonant?

c If the probability of spinning blue with a particular spinner is $\frac{4}{7}$, what is the probability of spinning a colour other than blue?

12 A box contains different coloured counters, with Pr(purple) = 10%, Pr(yellow) = $\frac{2}{3}$ and Pr(orange) = $\frac{1}{7}$.

a Is it possible to obtain a colour other than purple, yellow or orange? If so, state the probability.

b What is the minimum number of counters in the box?

c If the box cannot fit more than 1000 counters, what is the maximum number of counters in the box?

Designing spinners

— | — | 13

ENRICHMENT

13 a For each of the following, design a spinner using only red, green and blue sectors to obtain the desired probabilities. If it cannot be done, then explain why.

i Pr(red) = $\frac{1}{2}$, Pr(green) = $\frac{1}{4}$, Pr(blue) = $\frac{1}{4}$

ii Pr(red) = $\frac{1}{2}$, Pr(green) = $\frac{1}{2}$, Pr(blue) = $\frac{1}{2}$

iii Pr(red) = $\frac{1}{4}$, Pr(green) = $\frac{1}{4}$, Pr(blue) = $\frac{1}{4}$

iv Pr(red) = 0.1, Pr(green) = 0.6, Pr(blue) = 0.3

b If Pr(red) = x and Pr(green) = y, write a formula using x and y to determine what Pr(blue) must equal.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8I Experimental probability EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Although the probability of an event tells us how often an event should happen in theory, we will rarely find this being exactly right in practice. For instance, if you toss a coin 100 times, it might come up heads 53 times out of 100, which is not exactly $\frac{1}{2}$ of the times you tossed it. Sometimes we will not be able to find the exact probability of an event, but we can carry out an experiment to estimate it.



Tossing a coin 100 times does not mean it will come up heads 50 times.

Let's start: Tossing coins

For this experiment, each class member needs a fair coin that they can toss.

- Each student should toss the coin 20 times and count how many times heads occurs.
- Tally the total number of heads obtained by the class.
- How close is this total number to the number you would expect that is based on the probability of $\frac{1}{2}$? Discuss what this means.

Key ideas

- The **experimental probability** of an event occurring based on a particular experiment is defined as:

$$\frac{\text{number of times the event occurs}}{\text{total number of trials in the experiment}}$$

- The **expected number** of occurrences = probability $\times$ number of trials.
- If the number of trials is large, then the experimental probability is likely to be close to the actual probability of an event.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13 Working with experimental probability

When playing with a spinner with the numbers 1 to 4 on it, the following numbers come up:
1, 4, 1, 3, 3, 1, 4, 3, 2, 3.

a What is the experimental probability of getting a 3?

b What is the experimental probability of getting an even number?

c Based on this experiment, how many times would you expect to get a 3 if you spin 1000 times?

SOLUTION	EXPLANATION
a $\frac{2}{5}$ or 0.4 or 40%	$\frac{\text{number of 3s}}{\text{number of trials}} = \frac{4}{10} = \frac{2}{5}$
b $\frac{3}{10}$	$\frac{\text{number of times with even result}}{\text{number of trials}} = \frac{3}{10}$
c 400 times	probability $\times$ number trials $= \frac{2}{5} \times 1000 = 400$

Exercise 8I

1, 2 | 1 | —

UNDERSTANDING

Example 13a,b

1 A 6-sided die is rolled 10 times and the following numbers come up: 2, 4, 6, 4, 5, 1, 6, 4, 4, 3.

a What is the experimental probability of getting a 3?

b What is the experimental probability of getting a 4?

c What is the experimental probability of getting an odd number?

2 When a coin is tossed 100 times, the results are 53 heads and 47 tails.

a What is the experimental probability of getting a head?

b What is the experimental probability of getting a tail?

c What is the theoretical probability of getting a tail if the coin is fair?

3–7 | 3–8 | 4–8

FLUENCY

3 A survey is conducted on people's television viewing habits.

Number of hours per week	0–	5–	10–	20–	30+
Number of people	20	10	15	5	0

a How many people participated in the survey?

b What is the probability that a randomly selected participant watches less than 5 hours of television?

c What is the probability that a randomly selected participant watches 20–30 hours of television?

d What is the probability that a randomly selected participant watches between 5 and 20 hours of television?

e Based on this survey, the experimental probability of watching 30+ hours of television is 0. Does this mean that watching 30+ hours is impossible?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 13c

4 A fair coin is tossed.

- **a** How many times would you expect it to show tails in 1000 trials?
- **b** How many times would you expect it to show heads in 3500 trials?
- **c** Initially, you toss the coin 10 times to find the probability of the coin showing tails.
  - **i** Explain how you could get an experimental probability of 0.7.
  - **ii** If you toss the coin 100 times, are you more or less likely to get an experimental probability close to 0.5?

5 A fair 6-sided die is rolled.

- **a** How many times would you expect to get a 3 in 600 trials?
- **b** How many times would you expect to get an even number in 600 trials?
- **c** If you roll the die 600 times, is it possible that you will get an even number 400 times?
- **d** Are you more likely to obtain an experimental probability of 100% from two throws or to obtain an experimental probability of 100% from 10 throws?

6 Each time a basketball player takes a free throw there is a 4 in 6 chance that the shot will go in. This can be simulated by rolling a 6-sided die and using numbers 1 to 4 to represent 'shot goes in' and numbers 5 and 6 to represent 'shot misses'.

- **a** Use a 6-sided die over 10 trials to find the experimental probability that the shot goes in.
- **b** Use a 6-sided die over 50 trials to find the experimental probability that the shot goes in.
- **c** Working with a group, use a 6-sided die over 100 trials to find the experimental probability that the shot goes in.
- **d** Use a 6-sided die over just one trial to find the experimental probability that the shot goes in. (Your answer should be either 0 or 1.)
- **e** Which of the answers to parts **a** to **d** above is closest to the theoretical probability of 66.67%? Justify your answer.

7 The colour of the cars in a school car park is recorded.

Colour	Red	Black	White	Blue	Purple	Green
Number of cars	21	24	25	20	3	7

Based on this sample:

- **a** What is the probability that a randomly chosen car is white?
- **b** What is the probability that a randomly chosen car is purple?
- **c** What is the probability that a randomly chosen car is green or black?
- **d** How many purple cars would you expect to see in a shopping centre car park with 2000 cars?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8I

FLUENCY

8 The number of children in some families is recorded in the table shown.

Number of children	0	1	2	3	4
Number of families	5	20	32	10	3

a How many families have no children?
b How many families have an even number of children?
c How many families participated in the survey?
d Based on this experiment, what is the probability that a randomly selected family has 1 or 2 children?
e Based on this experiment, what is the probability that a randomly selected family has an even number of children?
f What is the total number of *children* considered in this survey?

9 | 9, 10 | 9, 10

PROBLEM-SOLVING

9 A handful of 10 marbles of different colours is placed into a bag. A marble is selected at random, its colour recorded and then returned to the bag. The results are:


Red marble chosen	Green marble chosen	Blue marble chosen
21	32	47

a Based on this experiment, how many marbles of each colour do you think there are? Justify your answer in a sentence.
b For each of the following, state whether or not they are possible outcomes for the 10 marbles.
i 3 red, 3 green, 4 blue
ii 2 red, 4 green, 4 blue
iii 1 red, 3 green, 6 blue
iv 2 red, 3 green, 4 blue, 1 purple
v 2 red, 0 green, 8 blue


10 Match each of the experiment results **a** to **d** with the most likely spinner that was used (**A** to **D**).

	Red	Green	Blue
a	18	52	30
b	27	23	0
c	20	23	27
d	47	0	53


A




B



C



D



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 | 11 | 11, 12

8I

REASONING

11 Assume that any baby has a 50% chance of being a boy or a girl, and use a coin to simulate a family with four children. Toss the coin four times, using heads to represent boys and tails to represent girls. Count the number of girls in the family. Repeat this experiment 20 times and present your results in a table like the one below.

Number of girls	0	1	2	3	4	Total
Number of families						20

- **a** Based on your simulation, what is the experimental probability that a family will have just one girl?
- **b** Based on your simulation, what is the experimental probability that a family will have four girls?
- **c** Explain why you might need to use simulations and experimental probabilities to find the answer to parts **a** and **b** above.
- **d** If you had repeated the experiment only 5 times instead of 20 times, how might the accuracy of your probabilities be affected?
- **e** If you had repeated the experiment 500 times instead of 20 times, how might the accuracy of your probabilities be affected?

12 Classify the following statements as true or false. Justify each answer in a sentence.

- **a** If the probability of an event is $\frac{1}{2}$, then it must have an experimental probability of $\frac{1}{2}$.
- **b** If the experimental probability of an event is $\frac{1}{2}$, then its theoretical probability must be $\frac{1}{2}$.
- **c** If the experimental probability of an event is 0, then the theoretical probability is 0.
- **d** If the probability of an event is 0, then the experimental probability is also 0.
- **e** If the experimental probability is 1, then the theoretical probability is 1.
- **f** If the probability of an event is 1, then the experimental probability is 1.

Improving estimates

— | — | 13

ENRICHMENT

13 A spinner is spun 500 times. The table opposite shows the tally for every 100 trials.

	Red	Green	Blue
First set of 100 trials	22	41	37
Second set of 100 trials	21	41	38
Third set of 100 trials	27	39	34
Fourth set of 100 trials	25	46	29
Fifth set of 100 trials	30	44	26

- **a** Give the best possible estimate for Pr(red), Pr(green) and Pr(blue) based on these trials.
- **b** If your estimate is based on just one set of trials, which one would cause you to have the most inaccurate results?
- **c** Design a spinner that could give results similar to those in the table. Assume you can use up to 10 sectors of equal size.
- **d** Design a spinner that could give results similar to those in the table if you are allowed to use sectors of different sizes.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Monopoly risk

In the game of Monopoly, two 6-sided dice are rolled to work out how far a player should go forward. For this investigation, you will need two 6-sided dice or a random number simulator that simulates numbers between 1 and 6.

a Roll the two dice and note what they add up to. Repeat this 100 times and complete this table.

Dice sum	2	3	4	5	6	7	8	9	10	11	12	Total
Tally												100

b Represent the results in a column graph. Describe the shape of the graph. Do you notice any patterns?

c Use the results of your experiment to give the experimental probability of two dice adding to:
i 3 **ii** 6 **iii** 8 **iv** 12 **v** 15

d What is the most likely sum for the dice to add to, based on your experiment? Is this the mean, median or mode that you are describing?

e If the average Monopoly game involves 180 rolls, find the expected number of times, based on your experiment, that the dice will add to:
i 3 **ii** 6 **iii** 8 **iv** 12 **v** 15


f Why do you think that certain sums happen more often than others? Explain why this might happen by comparing the number of times the dice add to 2 and the number of times they add to 8.

g What is the mean dice sum of the 100 trials you conducted above?

To conduct many experiments, a spreadsheet can be used. For example, the spreadsheet below can be used to simulate rolling three 6-sided dice. Drag down the cells from the second row to row 1000 to run the experiment 1000 times.

	A	B	C	D
1	Die 1	Die 2	Die 3	=MODE(D2:D1001)
2	=INT(6*RAND())+1	=INT(6*RAND())+1	=INT(6*RAND())+1	=A2+B2+C2

h Investigate what the most likely dice sums are when you roll more than two dice. You should use a spreadsheet like the one above to find the most likely values. (Note: Instead of using the MODE function to help you, you can also use the AVERAGE function.)



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.

1 Six numbers are listed in ascending order and some are removed. The mean and median are both 6, the mode is 2 and the range is 10. Fill in the missing numbers.

?, ?, 5, ?, ?, ?

2 A survey is conducted at a school and the results are presented as a pie chart. Find the minimum number of people who participated in the survey if the smallest sector has an angle of:

a 90° **b** 36° **c** 92° **d** 35°


3 In a class of 20 students, a poll was taken of the number of cars owned by each family. The median number of cars owned is 1.5 and the mean number is 1.4 cars. Complete the table of the results, shown opposite.

Number of cars	0	1	2	3
Number of students	4			

4 Each of the 8 letters of a word is written on a separate card. Given the following probabilities, what is the word?

Pr(letter P) = Pr(letter R) = 12.5%, Pr(letter B)= $\frac{1}{4}$, Pr(vowel) = 0.375

5 Frank the fisherman enjoys beach fishing on Fraser Island, Qld. One year he kept a count of the fish types that he caught and displayed these numbers as a pie chart in his fish shop. Calculate the answers to these questions, showing all steps.



a What angle did Frank use to represent his whiting catch?

b Find the difference between the smallest and largest angles in this pie chart.

c What is the probability of Frank catching a tailor?

d Find the probability that Frank does *not* catch a golden trevally.

e What is the probability of Frank catching a flathead or golden trevally?

6 A circular spinner is made using the colours red, green, purple and yellow in four sectors with two sectors being equal in size. The spinner is spun 120 times and the results obtained are shown in the table below.

Sector colour	Red	Green	Purple	Yellow
Frequency	40	32	19	29

Design a spinner that is likely to give these results, labelling the sector colours and angles. Explain the mathematical reason for your answer and show relevant calculations.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary


Statistics and probability

Data types
- Numerical
  e.g. number of people (discrete), height of trees (continuous)
- Categorical
  e.g. colours, gender


Data collection
- Primary source (firsthand) or secondary source (collected by someone else)
- Census (whole population) or sample (selection)

Graphical representations


Column graphs



Dot plots



Line graphs



Time is often displayed on the horizontal axis.

Pie charts





$$\text{proportion} = \frac{\text{number}}{\text{total}}$$

angle = 360° × proportion

Divided bar graphs

width of bar = proportion × total width





Stem-and-leaf plots

Stem	Leaf
2	3 6 7

⇒ 23, 26, 27

Summarising data numerically

range = 10 − 1 = 9

1, 2, 2, 3, 4, 4, 4, 5, 5, 6, 7, 8, 8, 9, 10

mode = 4 (most common value)


median = 5 (middle value)

$$\text{mean} = \frac{\text{sum of values}}{\text{number of values}} = \frac{78}{15} = 5.2$$

Experimental probability (Ext)

Use an experiment or survey or simulation to estimate probability.
e.g. Spinner lands on blue 47 times out of 120 ⟶
Experimental probability = $\frac{47}{120}$

Probability: how likely an event is




Outcome: possible result of an experiment
Event: either a single outcome or a collection of outcomes

Experiment/trial: e.g. roll a fair die
Sample space: {1, 2, 3, 4, 5, 6}
Pr(roll a 5) = $\frac{1}{6}$
Pr(roll odd number) = $\frac{3}{6} = \frac{1}{2}$

Expected number is
Pr(event) × number of trials
e.g. Flip coin 100 times, expected number of heads
= $\frac{1}{2} \times 100 = 50$
e.g. Roll die 36 times, expected number of 5s
= $\frac{1}{6} \times 36 = 6$

Sample space: e.g. {red, green, blue}
Pr(spin red) = $\frac{1}{3}$
Pr(don't spin blue) = $\frac{2}{3}$




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Multiple-choice questions

8C **1** In the column graph shown, the highest income is earned by:

A Michael **B** Alice **C** Dan **D** Laura **E** Victoria



*Questions **2** and **3** relate to the following information.*

The results of a survey are shown below.

Instrument learned	piano	violin	drums	guitar
Number of students	10	2	5	3

8F **2** If the results above are presented as a pie chart, then the angle occupied by the drums sector is:

A 360° **B** 180° **C** 120° **D** 90° **E** 45°

8I Ext **3** Based on the survey, the experimental probability that a randomly selected person learns the guitar is:

A $\frac{1}{4}$ **B** $\frac{1}{2}$ **C** 3 **D** $\frac{3}{5}$ **E** $\frac{3}{20}$

8A **4** Which one of the following variables is continuous numerical?

A the gender of newborn babies
B the number of babies born in a given years
C the number of hairs on a baby's head
D the weight (in kg) of newborn babies
E the length (in letters) of a baby's first name



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

*Questions **5** and **6** relate to the following information.*

In a class of 20 students, the number of days each student was absent over a 10-week period is recorded.

1, 0, 1, 2, 2, 3, 2, 4, 3, 0, 1, 1, 2, 3, 3, 3, 2, 2, 2, 2

8B **5** The mode is:

A 0 **B** 1 **C** 2 **D** 3 **E** 4

8B **6** The mean number of days a student was absent is:

A 1 **B** 2 **C** 1.95 **D** 3 **E** 39

8B **7** The range of the numbers 1, 5, 3, 9, 12, 41, 12 is:

A 40 **B** 41 **C** 12 **D** 3 **E** 1

8H **8** Which of the following events has the same probability as rolling an odd number on a fair 6-sided die?

A rolling a number greater than 4 on a fair 6-sided die
B choosing a vowel from the word CAT
C tossing a fair coin and getting heads
D choosing the letter T from the word TOE
E spinning an odd number on a spinner numbered 1 to 7

8H **9** Each letter of the word APPLE is written separately on five cards. One card is then chosen at random. Pr(letter P) is:

A 0 **B** 0.2 **C** 0.4 **D** 0.5 **E** 1

8I Ext **10** A fair 6-sided die is rolled 600 times. The expected number of times that the number rolled is either a 1 or a 2 is:

A 100 **B** 200 **C** 300 **D** 400 **E** 600

Short-answer questions

8C **1** Draw a column graph to represent the following people's ages.

Name	Sven	Dane	Kelly	Hugo	Frankie
Age (years)	20	12	15	22	25


8C **2** A Year 7 group was asked how many hours of television they watch in a week. The results are given in the table.

TV Watched (hours)	No. of students
8	5
9	8
10	14
11	8
12	5

a How many students participated in the survey?
b What is the total number of hours of television watched?
c Find the mean number of hours of television watched.
d Show this information in a column graph.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8D **3** The number of students in the library is recorded hourly, as displayed in the graph.



- **a** How many students entered the library when it first opened?
- **b** How many students were in the library at 8 hours after opening?
- **c** If the library opens at 9:00 am, at what time are there the most number of students in the library?
- **d** How many students were in the library at 4:00 pm?

8F Ext **4** 120 people were asked to nominate their favourite take-away food from the list: chicken, pizza, hamburgers, Chinese. The results are given in the table.

Food	Frequency
Chicken	15
Pizza	40
Hamburgers	30
Chinese	35

- **a** If you want to show the data in a pie chart, state the angle needed to represent Chinese food.
- **b** What percentage of people prefer hamburgers?
- **c** Represent the results in a pie chart.



8B **5** Consider the data 1, 4, 2, 7, 3, 2, 9, 12. State the:

a range **b** mean **c** median **d** mode

8B **6** Consider the data 0, 4, 2, 9, 3, 7, 3, 12. State the:

a range **b** mean **c** median **d** mode

8G **7** For each of the following descriptions, choose the probability from the set $0, \frac{1}{8}, \frac{3}{4}, 1, \frac{19}{20}$ that matches best.


a certain **b** highly unlikely **c** highly likely
d likely **e** impossible

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

8H **8** List the sample space for each of the following experiments.

- **a** A fair 6-sided die is rolled.
- **b** A fair coin is tossed.
- **c** A letter is chosen from the word DESIGN.
- **d** Spinning the spinner shown opposite.



8H **9** Vin spins a spinner with nine equal sectors, which are numbered 1 to 9.

- **a** How many outcomes are there?
- **b** Find the probability of spinning:
  - **i** an odd number
  - **ii** a multiple of 3
  - **iii** a number greater than 10
  - **iv** a prime number less than 6
  - **v** a factor of 8
  - **vi** a factor of 100

8H **10** One card is chosen at random from a standard deck of 52 playing cards. Find the probability of drawing:

- **a** a red king
- **b** a king or queen
- **c** a jack of diamonds
- **d** a picture card (i.e. king, queen or jack)




8I Ext **11** A coin is tossed 100 times, resulting in 42 heads and 58 tails.

- **a** What is the experimental probability of getting heads? Give your answer as a percentage.
- **b** What is the actual probability of getting heads if the coin is fair? Give your answer as a percentage.

8H **12** Consider the spinner shown.

- **a** State the probability that the spinner lands in the green section.
- **b** State the probability that the spinner lands in the blue section.
- **c** Tanya spins the spinner 100 times. What is the expected number of times it would land in the red section?
- **d** She spins the spinner 500 times. What is the expected number of times it would land in the green section?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response questions

1 The number of rainy days experienced throughout a year in a certain town is displayed below.

Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
No. of rainy days	10	11	3	7	2	0	1	5	6	9	7	5

a Show this information in a column graph.

b For how many days of the year did it rain in this town?

c What is the probability that it will rain in any day during winter (i.e. during June, July and August)?

d What type of variable (e.g. continuous numerical) is the number of rainy days?

e What type of variable is the month?

2 At a school camp, a survey was conducted to establish each student's favourite dessert.

Ice-cream	Yoghurt	Danish pastry	Jelly	Pudding	Cheesecake
10	5	2	7	4	12

a How many students participated in the survey?

b What is the most popular dessert selected?

c What is the probability that a randomly selected student chooses jelly as their favourite dessert?

d For each of the following methods listed below, state whether it would be a reasonable way of presenting the survey's results.

i column graph

ii line graph

iii pie chart

iv divided bar graph

e If the campers attend a school with 800 students, how many students from the entire school would you expect to choose pudding as their preferred dessert?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015

Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 9

Polygons, solids and transformations

What you will learn

9A Polygons
9B Triangles
9C Constructing triangles (Extending)
9D Triangle angle sum
9E Quadrilaterals
9F Quadrilateral angle sum
9G Symmetry
9H Reflection and rotation
9I Translation
9J Drawing solids
9K Nets and the Platonic solids (Extending)

Australian curriculum

MEASUREMENT AND GEOMETRY

Location and transformation

Describe translations, reflections in an axis, and rotations of multiples of 90° on the Cartesian plane using coordinates. Identify line and rotational symmetries (ACMMG181)

Geometric reasoning

Classify triangles according to their side and angle properties and describe quadrilaterals (ACMMG165)

Demonstrate that the angle sum of a triangle is 180° and use this to find the angle sum of a quadrilateral (ACMMG166)

Shape

Draw different views of prisms and solids formed from combinations of solids (ACMMG161) AC

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Crystals and viruses

The geometry of shapes and solids occurs naturally in many forms. The way in which atoms and molecules are arranged in crystalline solids gives rise to three-dimensional (3D) shapes with flat surfaces and straight edges. These types of solids are called polyhedra. Some common crystal solids are based on the tetrahedron, cube and octahedron. These are examples of a special group of solids that are regular polyhedra, and are called the Platonic solids named after the Greek philosopher and mathematician Plato. They have faces that are identical, regular polygons.

Early in the twentieth century, it was discovered that many viruses take the shape of regular polyhedra. A more modern example is the human immunodeficiency virus (HIV), which is enclosed by a layer of protein cells arranged in the shape of a regular icosahedron (i.e. a 20-sided regular polyhedron and Platonic solid).

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9A Polygons

Interactive

Widgets

HOTsheets

Walkthroughs


Polygons are closed plane shapes with straight sides. Each side is a segment and joins with two other sides at points called vertices. The number of sides, angles and vertices are the same for each type of polygon, and this number determines the name of the polygon. The word *polygon* comes from the Greek words *poly* meaning 'many' and *gonia* meaning 'angle'.



This tower has a base that is shaped like a hexagon, or 6-sided polygon.

Let's start: How hard is it to draw an octagon?


Try to draw an 8-sided shape with no inside angle that is bigger than 180°. This may not be as easy as you think! Remember that you must link the last drawn segment to the point at which you started.




This is not a good example!

Key ideas

- **Polygons** are closed plane figures with straight sides. A side is also called an **edge**.
- A **vertex** is the point at which two sides of a shape meet. (*Vertices* is the plural form of vertex.)




- **Convex** polygons have all vertices pointing outward and all interior (inside) angles smaller than 180°.
- **Non-convex** (or concave) polygons have at least one vertex pointing inward and at least one interior angle bigger than 180°.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Key ideas

- Polygons are classified by the number of sides they have.
- **Regular** polygons have sides of equal length and angles of equal size.
  - In a diagram, sides of equal length are shown using markings (or dashes).




Number of sides	Type
3	Triangle or trigon
4	Quadrilateral or tetragon
5	Pentagon
6	Hexagon
7	Heptagon or septagon
8	Octagon
9	Nonagon
10	Decagon
11	Undecagon
12	Dodecagon

- Polygons are usually named with capital letters for each vertex and in succession, clockwise or anticlockwise.




- A **diagonal** is a segment that joins two vertices, dividing a shape into two parts.



Example 1 Classifying polygons

a State the type of this shape and whether it is convex or non-convex.
b Is the shape regular or irregular?



SOLUTION	EXPLANATION
a convex pentagon	The shape has 5 sides and all the vertices are pointing outward.
b irregular	The sides are not of equal length and the angles are not equal.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Exercise 9A

1, 2 | 2 | —


UNDERSTANDING

1 Consider these three polygons.


i



ii



iii



a The three shapes are an example of what type of polygon?

b Which shape(s) are convex and why?

c Which shape(s) are non-convex and why?

d Complete the sentence. The third shape is called a _____ _____.

2 Draw an example of each of these shapes.

a convex hexagon **b** non-convex pentagon **c** convex nonagon

3–5 | 3(½), 4, 5, 6(½) | 3(½), 4, 5, 6(½)

FLUENCY

3 How many sides do each of these shapes have?

a pentagon **b** triangle **c** decagon **d** heptagon

e undecagon **f** quadrilateral **g** nonagon **h** hexagon


i octagon **j** dodecagon

Example 1


4 **a** Which of the given shapes are convex?

b State the type of polygon by considering its number of sides.


i




ii



iii



iv



v




vi




5 State the type of polygon and name it, using the vertex labels; e.g. triangle *ABC*.


a



b



c



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9A

FLUENCY

6 Which of the following are not polygons?

a circle **b** square **c** rectangle **d** oval
e cylinder **f** cube **g** line **h** segment


7 | 7, 8 | 7, 8

PROBLEM-SOLVING

7 A diagonal between two vertices divides a polygon into two parts.

a What is the maximum (i.e. largest) number of diagonals that can be drawn for the following shapes if the diagonals are *not* allowed to cross?

i convex pentagon **ii** convex decagon



b What is the maximum number of diagonals that can be drawn for the following shapes if the diagonals *are* allowed to cross?

i convex pentagon **ii** convex decagon


8 Draw line segments to show how you would divide the given shapes into the shapes listed below.

a




two triangles

b




one rectangle and two triangles

c



three triangles

d




four triangles and one square

e



two quadrilaterals

f



one pentagon and one heptagon

9 | 9, 10 | 10–12

REASONING

9 State whether each of the following statements is true or false.

a A regular polygon will have equal interior (i.e. inside) angles.
b The size of the angles inside a pentagon are the same as the angles inside a decagon.
c An irregular polygon must always be non-convex.
d Convex polygons are not always regular.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9A


REASONING

10 **a** For each of these pentagons, draw the five diagonals that join the vertices.

i



ii



b What types of polygons have at least one diagonal outside the shape. Why?

11 An equi-angular shape has all of its interior angles of equal size. Are all equi-angular shapes regular polygons? Draw some examples to investigate.

12 An equilateral shape has all of its sides equal. Are all equilateral shapes regular polygons?

ENRICHMENT

Rules for diagonals — — 13


13 **a** Copy the table below into your workbook and complete it.

Number of sides	3	4	5	6	7
Number of diagonals (not allowed to cross)	0	1			
Number of diagonals (allowed to cross)	0	2			

b If a polygon has n sides, find a rule for:

i the number of diagonals (not allowed to cross)

ii the number of diagonals (allowed to cross)



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9B Triangles









The word 'triangle', meaning 'three angles', describes a shape with three sides. The triangle is an important building block in mathematical geometry. Similarly, it is important in the practical world of building and construction owing to the rigidity of its shape.




Interlocking triangles give this bridge's frame strength and stability.

Let's start: Stable shapes

Consider these constructions, which are made from straight pieces of steel and bolts.

Assume that the bolts are not tightened and that there is some looseness at the points where they are joined.




- Which shape(s) do you think could lose their shape if a vertex is pushed?
- Which shape(s) will not lose their shape when pushed? Why?
- For the construction(s) that might lose their shape, what could be done to make them rigid?

Key ideas


■ **Triangles** can be named using the vertex labels.

triangle ABC or ΔABC




■ Triangles are classified by their **side lengths**.

scalene




3 different sides
3 different angles

isosceles



2 equal sides
2 equal angles


equilateral



3 equal sides
3 equal angles (60°)


■ Triangles are also classified by the size of their **interior angles**.

acute




all angles acute

right



one right angle

obtuse




one obtuse angle

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas


- The parts of an **isosceles triangle** are named as shown opposite. The base angles are equal and two sides (called the legs) are of equal length. The two sides of equal length are opposite the equal angles.




- Sides of equal length are indicated by matching markings.

Example 2 Classifying triangles

Classify these triangles by:

a 

b 



i their side lengths (i.e. scalene, isosceles or equilateral)

ii their angles (i.e. acute, right or obtuse)

SOLUTION	EXPLANATION
a i isosceles	Has 2 sides of equal length.
ii acute	All angles are acute.
b i scalene	Has 3 different side lengths.
ii obtuse	Has 1 obtuse angle.

Example 3 Drawing triangles

Draw a triangle ABC with $AB = 5$ cm, $\angle ABC = 30°$ and $\angle BAC = 45°$.

SOLUTION	EXPLANATION
a 	First, measure and draw segment AB. Then use a protractor to form the angle 30° at point B.
b 	Then use a protractor to form the angle 45° at point A. Mark point C and join with A and B.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 9B


1, 2 | 2 | —

UNDERSTANDING

1 Draw an example of each of the triangles given below. Refer back to the **Key ideas** in this section to check that the features of each triangle are correct.

a scalene **b** isosceles **c** equilateral
d acute **e** right **f** obtuse

2 Answer these questions, using the point labels A, B and C for the given isosceles triangle.



a Which point is the apex?
b Which segment is the base?
c Which two segments are of equal length?
d Which two angles are the base angles?


3–5 | 3–5 | 3–5

FLUENCY


Example 2

3 Classify each of these triangles according to their side lengths (i.e. scalene, isosceles or equilateral).


a



b




c




4 Classify each of these triangles according to their angles (i.e. acute, right or obtuse).


a



b



c



Example 3

5 Use a protractor and ruler to draw the following triangles.

a triangle ABC with $AB = 5$ cm, $\angle ABC = 40°$ and $\angle BAC = 30°$
b triangle DEF with $DE = 6$ cm, $\angle DEF = 50°$ and $\angle EDF = 25°$
c triangle ABC with $AB = 5$ cm, $\angle ABC = 35°$ and $BC = 4$ cm

6, 7 | 6, 7 | 7, 8

PROBLEM-SOLVING

6 Is it possible to draw any of the following? If yes, give an example.

a an acute triangle that is also scalene
b a right triangle that is also isosceles
c an equilateral triangle that is also obtuse
d a scalene triangle that is also right angled

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9B

PROBLEM-SOLVING

7 What is the smallest number of identical equilateral triangles needed to form each of these shapes?



a a diamond
b an equilateral triangle made up of more than one other equilateral triangle
c a hexagon
d a 6-pointed star (shown opposite) (Note: Overlapping is not allowed.)

8 Draw an example of a triangle that fits the triangle type in both the row and column. Are there any cells in the table for which it is impossible to draw a triangle?

Triangles	Scalene	Isosceles	Equilateral
Acute			
Right			
Obtuse			

REASONING

9, 10, 10, 11

9 a Is it possible to divide every triangle into two right triangles using one line segment? Explore with diagrams.
b Which type of triangle can always be divided into two *identical* right triangles?

10 Try drawing a triangle with side lengths 4 cm, 5 cm and 10 cm. Explain why this is impossible.

11 a Is the side opposite the largest angle in a triangle always the longest?
b Can you draw a triangle with two obtuse angles? Explain why or why not.

ENRICHMENT

Unique triangles — — 12

12 Investigate whether it is possible to draw more than one triangle with the following information. If not, then the single triangle you have drawn is unique.

a $\angle ABC = 20°$, $\angle BCA = 50°$, $\angle BAC = 110°$
b $AB = 5$ cm, $AC = 4$ cm, $\angle BAC = 70°$
c $AB = 6$ cm, $\angle BAC = 70°$
d $AB = 5$ cm, $BC = 4$ cm, $\angle BAC = 50°$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9C Constructing triangles EXTENDING


Interactive

Widgets

HOTsheets

Walkthroughs

Triangles can be constructed with a high degree of accuracy using a ruler and a pair of compasses. Alternatively, computer geometry can be a useful tool for assisting in the construction process, as well as for exploring general properties of shapes.



Geometry software allows you to draw and manipulate triangles and other shapes.

Let's start: I am not unique

Use a protractor and ruler to draw a triangle ABC with the properties:


$AB = 6$ cm, $\angle BAC = 20^\circ$ and $BC = 5$ cm

- Compare your triangle with those drawn by other students.
- Is your triangle the same shape? If not, can you explain why?
- How many triangles are possible?


Key ideas

- **Arcs** drawn using a pair of compasses can help to construct triangles accurately.
- Computer geometry or a pair of compasses can be used to accurately construct:


right triangles




isosceles triangles




equilateral triangles




- The following information is sufficient to construct a single **unique triangle**.
  - 3 sides (**SSS**)




  - 2 sides and the angle between them (**SAS**). The angle is also known as the included angle.



  - 2 angles and 1 side (**AAS**) (in any order)



  - a right angle, hypotenuse length and another side length (**RHS**)




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 4 Constructing a triangle

Construct a triangle with side lengths 6 cm, 4 cm and 5 cm.

SOLUTION



EXPLANATION

Use a ruler to draw a segment 6 cm in length.

Construct two arcs with radius 4 cm and 5 cm, using each end of the segment as the centres.


Mark the intersection point of the arcs and draw the two remaining segments.

Example 5 Deciding if triangles are unique

Is there enough information given to accurately construct a unique triangle? If yes, write SSS, SAS, AAS or RHS, whichever one suits best.

a triangle ABC with $AB = 5$ cm, $AC = 6$ cm and $\angle BAC = 60°$

b




SOLUTION

a yes; SAS


EXPLANATION

2 sides and the angle between them are given.



b no

Not enough information is provided to suit SSS, SAS, AAS or RHS. More than one triangle can be drawn with the information.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 9C

1 | 1 | —

UNDERSTANDING

Example 4


1 Use a protractor, pair of compasses and a ruler to construct these triangles.

a 3 sides: 3 cm, 5 cm and 6 cm (SSS)

Step 1. Draw a segment, AB, 6 cm long.

Step 2. Draw 2 arcs: one centred at A with radius 3 cm and the other centred at B with radius 5 cm.

Step 3. Mark the point C and join to points A and B.




b 2 sides: 5 cm and 4 cm; and the angle between them, 40° (SAS)

Step 1. Draw a segment 5 cm long.

Step 2. Use a protractor to draw the angle 40° at A and then draw the ray AC.

Step 3. Measure the segment AC at 4 cm and mark point C.

Step 4. Join point C with point B.




c 2 angles: 35° and 70°; and a side of length 5 cm between the angles. (This is an example of AAS.)

Step 1. Draw the segment AB 5 cm long.

Step 2. Use a protractor to draw the angles – one at each end.

Step 3. Mark point C and join it with points A and B.




d a right angle, with hypotenuse of length 5 cm and one other side of length 4 cm (RHS)

Step 1. Draw a segment, AB, 4 cm in length.

Step 2. Measure a 90° angle at A and then draw the ray AC.

Step 3. Construct the arc centred at B, using a radius of 5 cm.

Step 4. Mark the point C and join with points A and B.



2–4 | 2–5 | 2–5

FLUENCY

Example 5

2 Is there enough information given to accurately construct a unique triangle? If yes, write SSS, SAS, AAS or RHS, whichever one suits best. You may wish to draw a diagram to help display the information.

a triangle ABC with $AB = 4$ cm, $AC = 2$ cm and $BC = 3$ cm

b triangle ABC with $AB = 10$ m and $AC = 5$ cm

c triangle ABC with $AB = 4$ km, $\angle BAC = 30°$ and $AC = 5$ km

d triangle DEF with $\angle DEF = 30°$ and $DE = 9$ cm

e triangle DEF with $\angle DEF = 90°$ and $DF = 3$ m and $DE = 2$ m


f triangle MNO with $\angle MNO = 47°$, $\angle NOM = 70°$ and $NO = 7.2$ m

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9C


FLUENCY

3 Construct an isosceles triangle by following these steps.




- **a** Draw a base segment of about 4 cm in length.
- **b** Use a pair of compasses to construct two arcs of equal radius. (Try about 5 cm but there is no need to be exact.)
- **c** Join the intersection point of the arcs (apex) with each end of the base.
- **d** Measure the length of the legs to check they are equal.
- **e** Measure the two base angles to check they are equal.

4 Construct an equilateral triangle by following these steps.



- **a** Draw a segment of about 4 cm in length.
- **b** Use a pair of compasses to construct two arcs of equal radius. Important: Ensure the arc radius is exactly the same as the length of the segment in part **a**.
- **c** Join the intersection point of the arcs with the segment at both ends.
- **d** Measure the length of the three sides to check they are equal.
- **e** Measure the three angles to check they are all equal and 60°.

5 Construct a right triangle by following these steps.



- **a** Draw a segment, AB, of about 4 cm in length.
- **b** Extend the segment AB to form the ray AD. Make AD about 2 cm in length.
- **c** Construct a circle with centre A and radius AD. Also mark point E.
- **d** Draw two arcs with centres at D and E, as shown in the diagram. Any radius will do as long as they are equal for both arcs.
- **e** Mark point C and join with A and B.

6 | 6, 7 | 6, 7

PROBLEM-SOLVING

6 Without using a protractor, accurately construct these triangles. Rulers can be used to set the pair of compasses.

- **a** triangle ABC with $AB = 5.5$ cm, $BC = 4.5$ cm and $AC = 3.5$ cm
- **b** an isosceles triangle with base length 4 cm and legs 5 cm
- **c** an equilateral triangle with side length 3.5 cm
- **d** a right triangle with one side 4 cm and hypotenuse 5 cm

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9C

PROBLEM-SOLVING

7 Use computer geometry to construct these triangles. No measurement is allowed and each triangle does not have to be of a specific size.

- **a** equilateral triangle
- **b** isosceles triangle
- **c** right triangle

8 | 8 | 8, 9


REASONING

8 Explain why the following information is not sufficient to draw a single unique triangle. Show that it is not sufficient by drawing at least two different triangles that fit the criteria.

- **a** 3 angles
- **b** 2 sides

9 **a** Follow these steps to construct this special triangle that has two sides, 5 cm and 4 cm, and one angle of 40° that is not between them.

- **i** Draw AB 5 cm in length.
- **ii** Draw $\angle BAE = 40°$.
- **iii** Draw an arc centred at B with radius 4 cm.




- **b** How many triangles could be formed with the given information? Explain why.
- **c** Can you explain why this situation might be called the 'ambiguous case'?

Gothic arches — | — | 10


ENRICHMENT

10 **a** The Gothic, or equilateral arch, is based on the equilateral triangle. Try to construct one, using this diagram to help.



- **b** The trefoil uses the midpoints of the sides of an equilateral triangle. Try to construct one, using this diagram to help.





ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9D Triangle angle sum

Interactive

Widgets

HOTsheets

Walkthroughs


The three interior angles of a triangle have a very important property. No matter the shape of the triangle, the three angles always add to the same total.



The different triangles formed by the bridge's cables all have the same angle sum.

Let's start: A visual perspective on the angle sum


Use a ruler to draw any triangle. Cut out the triangle and tear off the three corners. Then place the three corners together.



What do you notice and what does this tell you about the three angles in the triangle? Compare your results with those of others. Does this work for other triangles?


Key ideas

- The **angle sum** of the interior angles of a triangle is 180°.



$a + b + c = 180$

- If one side of a triangle is extended, an **exterior** angle is formed. In the diagram shown opposite, $\angle DBC$ is the exterior angle. The angle $\angle DBC$ is supplementary to $\angle ABC$ (i.e. adds to 180°).




The exterior angle theorem will be looked at more closely in Section 9E.


Example 6 Finding an angle in a triangle

Find the value of a in these triangles.

a



b




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
a $a + 60 + 95 = 180$ $a + 155 = 180$ $a = 25$	The sum of angles in a triangle is 180. Add the two known angles. Find the difference between 180 and 155.
b $a + 70 + 70 = 180$	The two angles opposite the sides of equal length (i.e. the base angles) in an isosceles triangle are equal in size.
$a + 140 = 180$ $a = 40$	Add the two equal angles. Find the difference between 140 and 180.

Example 7 Finding an exterior angle

Find the size of the exterior angle $x°$ in this diagram.



SOLUTION	EXPLANATION
$a + 90 + 62 = 180$ $a + 152 = 180$ $a = 28$	The angle sum for a triangle is 180°. Add the two known angles. a is the difference between 180 and 152.
$x + 28 = 180$ $x = 152$	Angles of size $x°$ and $a°$ are supplementary (i.e. they add to 180°). x is the difference between 180 and 28.


Exercise 9D

1–4 | 4 | —

UNDERSTANDING

1 **a** Use a protractor to measure the three angles in this triangle.

b Add up your three angles. What do you notice?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


9D

UNDERSTANDING

2 For the triangle opposite, give reasons why:

a a must equal 20


b b must equal 60



3 What is the size of each angle in an equilateral triangle?

4 For the isosceles triangle opposite, give a reason why:

a $a = 70$ **b** $b = 40$




5–7 5–7 5–7(½)

FLUENCY


Example 6a

5 Find the value of a in each of these triangles.


a




b




c




d



e




f




Example 6b

6 Find the value of a in each of these isosceles triangles.


a




b




c




d



e



f



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


9D

FLUENCY


Example 7

7 The triangles below have exterior angles. Find the value of x. For parts **b** to **f**, you will need to first calculate the value of a.


a




b




c




d



e



f




8(½) 8–9(½) 8–9(½), 10


PROBLEM-SOLVING

8 Find the value of a, in each of these triangles.


a




b




c




d



e



f




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9D


PROBLEM-SOLVING

9 Each of these diagrams has parallel lines. Find the value of a.


a




b




c




d




e



f



10 A plane flies horizontally 200 m above the ground. It detects two beacons on the ground. Some angles are known, and these are shown in the diagram. Find the angle marked $a°$ between the line of sight to the two beacons.





11 11 11–12


REASONING

11 **a** Find the sum 75° + 80°.

b Find the value of a in the diagram opposite.

c What do you notice about the answers to parts **a** and **b**?

d Do you think this would be true for other triangles with different angles? Explore.




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9D

REASONING

12 This diagram includes two parallel lines.




- **a** The angles marked $a°$ are always equal. From the list (corresponding, alternate, cointerior, vertically opposite), give a reason why.
- **b** Give a reason why the angles marked $b°$ are always equal.
- **c** At the top of the diagram, angles $a°$, $b°$ and $c°$ lie on a straight line. What does this tell you about the three angles $a°$, $b°$ and $c°$ in the triangle?

ENRICHMENT

Proof — — 13

13 Complete these proofs. Give reasons for each step where brackets are shown.

- **a** The angle sum in a triangle is 180°.




$\angle DCA = a°$ (Alternate to $\angle BAC$ and DE is parallel to AB.)

$\angle ECB =$ _____ (_____)

$\angle DCA + \angle ACB + \angle ECB =$ _____ (_____)

$\therefore a + b + c =$ _____

- **b** The exterior angle outside a triangle is equal to the sum of the two interior opposite angles.





The Ancient Greek mathematician Euclid of Alexandria is known as the Father of Geometry.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9E Quadrilaterals

Interactive

Widgets

HOTsheets

Walkthroughs

Quadrilaterals are polygons with four sides. There are special types of quadrilaterals and these are identified by the number of equal side lengths and the number of pairs of parallel lines.



Streets in major cities often form quadrilaterals, and many buildings on them have a similar shape.

Let's start: Quadrilaterals that you know


You may already know the names and properties of some of the special quadrilaterals. Which ones do you think have:

- 2 pairs of parallel sides?
- All sides of equal length?
- 2 pairs of sides of equal length?


Are there any types of quadrilaterals that you know which you have not yet listed?

Key ideas


- A **convex quadrilateral** has all four interior angles less than 180°. All vertices point outward.




- A **non-convex quadrilateral** has one interior angle greater than 180°.




- Parallelograms are quadrilaterals with two pairs of parallel sides.
  - **parallelogram**
    - 2 pairs of parallel sides
    - 2 pairs of sides of equal length
    - opposite angles equal



  - **rectangle** (a parallelogram with all angles 90°)
    - 2 pairs of parallel sides
    - 2 pairs of sides of equal length
    - all angles 90°




  - **rhombus** (or diamond) (a parallelogram with all sides equal)
    - 2 pairs of parallel sides
    - all sides of equal length
    - opposite angles equal




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Key ideas

- **square** (a rhombus with all angles 90°)
  - 2 pairs of parallel sides
  - all sides of equal length
  - all angles 90°



- Other special quadrilaterals include:
  - **trapezium**
    - 1 pair of parallel sides (some like to define a trapezium as a quadrilateral with at least 1 pair of parallel sides; this would make all parallelograms also trapeziums)
  - **kite**
    - 2 pairs of sides of equal length
    - 1 pair of opposite angles that are equal in size







Example 8 Classifying quadrilaterals

State the type of each quadrilateral given below.

a



b



SOLUTION	EXPLANATION
a non-convex quadrilateral	One interior angle is greater than 180°.
b trapezium	There is one pair of parallel sides.

Exercise 9E

1, 2 | 2 | —

UNDERSTANDING

1 Draw an example of each of the quadrilaterals listed. Mark any sides of equal length with single or double dashes, mark parallel lines with single or double arrows and mark equal angles using the letters *a* and *b*. (Refer back to the **Key ideas** in this section should you need help.)

a square b rectangle c rhombus
d parallelogram e trapezium f kite

2 a Draw two examples of a non-convex quadrilateral.
b For each of your drawings, state how many interior angles are greater than 180°.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9E


3–5 | 3–6 | 3–6

FLUENCY


Example 8

3 Classify each of these quadrilaterals as either convex or non-convex.


a



b




c




4 State the type of special quadrilateral given below.


a




b




c



d



e



f




5 Name all the quadrilaterals that have:


- **a** 2 different pairs of sides of equal length
- **b** 2 different pairs of opposite angles that are equal in size
- **c** 2 different pairs of parallel lines
- **d** only 1 pair of parallel lines
- **e** only 1 pair of opposite angles that are equal in size

6 Use your knowledge of the properties of quadrilaterals to find the unknown angles and lengths in each of these diagrams.


a



b



c



7 | 7, 8 | 7, 8

PROBLEM-SOLVING

7 Consider this 4 × 4 grid. Using the dots as vertices, how many different shapes of each kind could be drawn? (Do not count shapes that are of the same size.)

- **a** square
- **b** rectangle (that is not a square)
- **c** rhombus (that is not a square)
- **d** parallelogram (that is not a square, a rectangle or a rhombus)




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9E

PROBLEM-SOLVING

8 Using the given measurements, accurately draw this equilateral triangle onto a piece of paper and cut it into 4 pieces, as shown. Can you form a square with the four pieces?




	9	9	9, 10

REASONING

9 The diagonals of a quadrilateral are segments that join opposite vertices.

a List the quadrilaterals that have diagonals of equal length.

b List the quadrilaterals that have diagonals intersecting at 90°.



10 **a** Are squares a type of rectangle or are rectangles a type of square? Give an explanation.

b Are rhombuses a type of parallelogram? Explain.


c Is it possible to draw a non-convex trapezium?

Construction challenge	—	—	11


ENRICHMENT

11 Use a pair of compasses and a ruler to construct these figures. Use the diagrams as a guide, then measure to check the properties of your construction.

a a rhombus with side length 5 cm



b a line parallel to segment AB and passing through point P



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9F Quadrilateral angle sum

Like a triangle, the interior angle sum of a quadrilateral is a fixed number. This is true for both convex and non-convex quadrilaterals.

Interactive

Widgets


HOTsheets

Walkthroughs

Let's start: What do a revolution and a quadrilateral have in common?

Use a ruler to draw any quadrilateral. Cut it out and tear off the corners. Arrange them to meet at a point.


- What does the arrangement tell you about the angles inside a quadrilateral?
- Compare your results with those of others in the class.



Key ideas


- The **interior angle sum** of a quadrilateral is 360°.

$a + b + c + d = 360$



- **Exterior angles** are formed by extending one side.


$a + b = 180$




Example 9 Finding unknown angles in quadrilaterals

Find the value of a in each of these quadrilaterals.

a



b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a $a + 85 + 90 + 80 = 360$	The sum of the interior angles is 360°.
$a + 255 = 360$	Add the known angles to simplify.
$a = 105$	a is the difference between 360 and 255.
b Interior $\angle ABC = 180° - 120° = 60°$	$\angle ABC$ and $\angle CBE$ are supplementary.
Interior $\angle BCD = 360° - 170° = 190°$	Angles at a point sum to 360°.
$a + 70 + 60 + 190 = 360$	The sum of the interior angles is 360°.
$a + 320 = 360$	Simplify.
$a = 40$	a is the difference between 360 and 320.


Exercise 9F

1–3 | 3 | —

UNDERSTANDING


1 **a** Draw any quadrilateral that is convex (i.e. all interior angles are less than 180°), as shown opposite.

b Measure each interior angle and add them to find the total sum. Check that your answer is close to 360°.



2 **a** Draw any quadrilateral that is non-convex (i.e. one interior angle is greater than 180°), as shown opposite.


b Measure each interior angle and them add to find the total sum. Check that your answer is close to 360°.



3 In the quadrilateral shown opposite, give a geometrical reason why:

a a must equal 110

b b must equal 90




4, 5 | 4–6 | 4, 5(½), 6

FLUENCY


Example 9

4 For each of these quadrilaterals, find the value of a.


a



b



c



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press


9F

Example 9


FLUENCY

5 Find the values of a and b in each of the following diagrams.


a




b




c




d



e




f




6 Give the values of a (and b) in these special quadrilaterals.


a



b



c




7 | 7, 8 | 8, 9


PROBLEM-SOLVING

7 For each of these diagrams, find the value of a. You may need to find some other angles first.


a



b




c




8 The diagrams below include parallel lines. Find the value of a.


a



b




c




9 These diagrams include both triangles and quadrilaterals. Find the value of a.


a



b



c



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9F

10 | 10 | 10, 11

REASONING

10 For the quadrilaterals below, state whether each is possible or impossible. Make drawings to explore.

- **a** all interior angles less than 100°
- **b** all interior angles less than 90°
- **c** more than one interior reflex angle
- **d** more than one interior obtuse angle
- **e** more than three interior acute angles

11 Given is a quadrilateral divided into two triangles. Complete the proof to show that the sum of angles in a quadrilateral is 360°.


$a + b + f =$ _____ (sum of angles in a triangle)

$c + d + e =$ _____ (_____)

Total sum $= a + b + f + c + d + e$

$=$ _____ + _____

$=$ _____




Geometry with algebra | — | — | 12


ENRICHMENT

12 Find the value of x for each of these quadrilaterals.


a




b




c




d



e



f





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

9A **1** Name the type of shape stating whether it is concave or convex, regular or irregular.

a 

b 


c 

d 

9B **2** Classify this triangle by:

a its side length

b its angles





9C **3** Construct an equilateral triangle with sides each 6 cm.

Ext


9D **4** What is the angle sum of any triangle?


9D **5** Find the value of x in each triangle below.

a 


b 


9D **6** Find the size of x in each of these triangles.


a 


b 

9E **7** State the special type of quadrilateral given in each diagram below.

a 

b 


c 

d 


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9F **8** Find the value of each pronumeral below.


a



b




c




9D/F **9** The diagrams below include parallel lines. Find the value of a.


a



b




c



9F **10** Use your combined knowledge of triangles, quadrilaterals, polygons and parallel lines to find:

a the value of a
b the value of b
c the value of c
d the value of d



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9G Symmetry









You see many symmetrical geometrical shapes in nature. The starfish and sunflower are two examples. Shapes such as these may have two types of symmetry: line and rotational.




Starfish and sunflowers are both symmetrical, but in different ways.

Let's start: Working with symmetry


On a piece of paper draw a square (with side lengths of about 10 cm) and a rectangle (with length of about 15 cm and width of about 10 cm), then cut them out.

- How many ways can you fold each shape in half so that the two halves match exactly? The number of creases formed will be the number of lines of symmetry.
- Now locate the centre of each shape and place a sharp pencil on this point. Rotate the shape 360°.
  How many times does the shape make an exact copy of itself in its original position? This number describes the rotational symmetry.



Key ideas

- An axis or **line of symmetry** divides a shape into two equal parts. It acts as a mirror line, with each half of the shape being a reflection of the other.
  - The **order of line symmetry** is the number of axes of symmetry.
- The **order of rotation** is the number of times a shape makes an exact copy of itself (in its original position) after rotating 360°.
  - We say that there is no rotational symmetry if the order of **rotational symmetry** is equal to 1.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 10 Finding the symmetry of shapes

Give the order of line symmetry and of rotational symmetry for each of these shapes.

a rectangle




b regular pentagon




SOLUTION **EXPLANATION**


a line symmetry:
order 2




rotational symmetry:
order 2



b line symmetry:
order 5



rotational symmetry:
order 5



Exercise 9G


1, 2 | 2 | —

UNDERSTANDING

1 How many ways could you fold each of these shapes in half so that the two halves match exactly? (To help you solve this problem, try cutting out the shapes and folding them.)

a square **b** rectangle **c** equilateral triangle
d isosceles triangle **e** rhombus **f** parallelogram

2 For the shapes listed in Question **1**, imagine rotating them 360° about their centre. How many times do you make an exact copy of the shape in its original position?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9G


3–7 | 3–8 | 3(½), 4–8

FLUENCY


Example 10

3 Give the order of line symmetry and of rotational symmetry for each shape.

a




b




c




d



e



f



4 Name a type of triangle that has the following properties.

a order of line symmetry 3 and order of rotational symmetry 3

b order of line symmetry 1 and no rotational symmetry

c no line or rotational symmetry

5 List the special quadrilaterals that have these properties.

a line symmetry of order:

i 1 **ii** 2 **iii** 3 **iv** 4

b rotational symmetry of order:


i 1 **ii** 2 **iii** 3 **iv** 4

6 State the order of line symmetry and rotational symmetry for each of the following.

a



b




Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9G

FLUENCY

c



d



7 Of the capital letters of the alphabet shown here, state which have:

a 1 line of symmetry


b 2 lines of symmetry

c rotational symmetry of order 2


A B C D E F G H I J K L M
N O P Q R S T U V W X Y Z

8 Complete the other half of these shapes for the given axis of symmetry.


a



b



c



9 | 9, 10 | 9, 10

PROBLEM-SOLVING

9 Draw the following shapes, if possible.

a a quadrilateral with no lines of symmetry

b a hexagon with one line of symmetry


c a shape with line symmetry of order 7 and rotational symmetry of order 7

d a diagram with no line of symmetry but rotational symmetry of order 3


e a diagram with line of symmetry of order 1 and no rotational symmetry

10 These diagrams are made up of more than one shape. State the order of line and of rotational symmetry.


a



b



c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9G

11 | 11 | 11, 12


REASONING

11 Many people think a rectangle has four lines of symmetry, including the diagonals.




a Complete the other half of this diagram to show that this is not true.

b Using the same method as that used in part **a**, show that the diagonals of a parallelogram are not lines of symmetry.



12 A trapezium has one pair of parallel lines.



a State whether trapeziums always have:

i line symmetry **ii** rotational symmetry


b What type of trapezium will have one line of symmetry?

Symmetry in 3D

— | — | 13


ENRICHMENT

13 Some solid objects also have symmetry. Rather than line symmetry, they have **plane symmetry**. This cube shows one plane of symmetry, but there are more that could be drawn.




State the number of planes of symmetry for each of these solids.


a cube




b rectangular prism




c right square pyramid




d right triangular prism



e cylinder



f sphere



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9H Reflection and rotation

Interactive

Widgets

HOTsheets


Walkthroughs

Reflection and rotation are two types of transformations that involve a change in position of the points on an object. If a shape is reflected in a mirror line or rotated about a point, the size of the shape is unchanged. Hence, the transformations reflection and rotation are said to be isometric.

Let's start: Draw the image

Here is a shape on a grid.


- Draw the image (result) after reflecting the shape in the mirror line A.
- Draw the image (result) after reflecting the shape in the mirror line B.
- Draw the image after rotating the shape about point O by 180°.
- Draw the image after rotating the shape about point O by 90° clockwise.
- Draw the image after rotating the shape about point O by 90° anticlockwise.



Discuss what method you used to draw each image and the relationship between the position of the shape and its image after each transformation.

Key ideas

- **Reflection** and **rotation** are **isometric transformations** that give an **image** of an object or shape without changing its shape and size.
- The **image** of point A is denoted A'.
- A reflection involves a mirror line, as shown in the diagram opposite.






ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas


- A rotation involves a centre point of rotation (C) and an angle of rotation, as shown.
  - A pair of compasses can be used to draw each circle, to help find the position of image points.




rotation 90° clockwise about C

Example 11 Drawing reflections

Draw the reflected image of this shape and give the coordinates of A', B', C' and D'. The y-axis is the mirror line.



SOLUTION



$A' = (1, -1), B' = (1, -2), C' = (3, -3), D' = (3, -1)$

EXPLANATION

Reflect each vertex A, B, C and D about the mirror line. The line segment from each point to its image should be at 90° to the mirror line.


ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Drawing rotations

Draw the image of this shape and give the coordinates of A', B' and D' after carrying out the following rotations.


a 90° anticlockwise about C

b 180° about C




SOLUTION

a



$A' = (0, 1), B' = (0, 2), D' = (-2, 1)$

b



$A' = (-1, 0), B' = (-2, 0), D' = (-1, -2)$

EXPLANATION

Rotate each point on a circular arc around point C by 90° anticlockwise.

Rotate each point on a circular arc around point C by 180° in either direction.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Exercise 9H

1–3 | 3 | —


UNDERSTANDING

1 Use the grid to reflect each shape in the given mirror line.


a




b




c




d



e




f



2 Give the coordinates of the image point A' after the point $A(2, 0)$ is rotated about point $C(0, 0)$ by the following angles.

a 180° clockwise **b** 180° anticlockwise

c 90° clockwise **d** 90° anticlockwise



3 **a** Is the size and shape of an object changed after a reflection?

b Is the size and shape of an object changed after a rotation?


4–6 | 4–5(½), 6, 7 | 4–5(½), 6, 7

FLUENCY


Example 11

4 Draw the image of this shape and give the coordinates of A', B', C' and D'. Note that the y-axis is the mirror line for parts **a** to **c**, whereas the x-axis is the mirror line for parts **d** to **f**.

a




b




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


c




d



e




f



5 Give the new coordinates of the image point A' after point A has been rotated around point $C(0, 0)$ by:


- **a** 180° clockwise
- **b** 90° clockwise
- **c** 90° anticlockwise
- **d** 270° clockwise
- **e** 360° anticlockwise
- **f** 180° anticlockwise



Example 12

6 Draw the image of this shape and give the coordinates of A', B' and D' after the following rotations.

- **a** 90° anticlockwise about C
- **b** 180° about C
- **c** 90° clockwise about C



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9H


FLUENCY

7 Draw the image of this shape and give the coordinates of A', B' and D' after the following rotations.

a 90° anticlockwise about C

b 180° about C

c 90° clockwise about C




8, 9 | 8–10 | 9–11


PROBLEM-SOLVING

8 The mirror lines on these grids are at a 45° angle. Draw the reflected image.


a




b




c




d



e



f




9 On the Cartesian plane, the point $A(-2, 5)$ is reflected in the x-axis and this image point is then reflected in the y-axis. What are the coordinates of the final image?

10 A point, $B(2, 3)$, is rotated about the point $C(1, 1)$. State the coordinates of the image point B' for the following rotations.

a 180°

b 90° clockwise

c 90° anticlockwise




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9H


PROBLEM-SOLVING

11 For each shape given, how many degrees has it been rotated?


a



b



c



12 | 12, 13 | 13, 14

REASONING

12 Write the missing number in these sentences.

a Rotating a point 90° clockwise is the same as rotating a point _____ anticlockwise.

b Rotating a point 38° anticlockwise is the same as rotating a point _____ clockwise.

c A point is rotated 370° clockwise. This is the same as rotating the point _____ clockwise.

13 A point S has coordinates $(-2, 5)$.


a Find the coordinates of the image point S' after a rotation 180° about $C(0, 0)$.

b Find the coordinates of the image point S' after a reflection in the x-axis followed by a reflection in the y-axis.

c What do you notice about the image points in parts **a** and **b**?

d Test your observation on the point $T(-4, -1)$ by repeating parts **a** and **b**.

14 Explain what is wrong with this attempt at a 180° rotation about $C(0, 0)$.






Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9H Dynamic geometry exploration — — 15, 16

ENRICHMENT


15 Explore reflecting shapes dynamically, using computer geometry.

- **a** On a grid, create any shape using the polygon tool.
- **b** Construct a mirror line.
- **c** Use the reflection tool to create the reflected image about your mirror line.
- **d** Drag the vertices of your original shape and observe the changes in the image. Also try dragging the mirror line.



16 Explore rotating shapes dynamically, using computer geometry.

- **a** On a grid, create any shape using the polygon tool.
- **b** Construct a centre of rotation point and a rotating angle (or number). In Cabri, use the Numerical Edit tool to create a dynamic number.
- **c** Use the rotation tool to create the rotated image that has your nominated centre of rotation and angle. You will need to click on the shape, the centre of rotation and your angle.
- **d** Drag the vertices of your original shape and observe the changes in the image. Also try changing the angle of rotation.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9I Translation

Interactive


Widgets

HOTsheets

Walkthroughs

The transformation called translation is another isometric transformation because the size and shape of the image is unchanged. Translation involves a shift in an object left, right, up or down. The orientation of a shape is also unchanged.


In a dragster race along 300 m of straight track, the main body of the car is translated down the track in a single direction.



Let's start: Describing a translation

Consider this shape $ABCD$ and its image $A'B'C'D'$.

- Use the words left, right, up or down to describe how the shape $ABCD$, shown opposite, could be translated (shifted) to its image.
- Can you think of a second combination of translations that give the same image?
- How would you describe the reverse translation?




Key ideas


- **Translation** is an isometric transformation involving a shift left, right, up or down.
- Describing a translation involves saying how many units a shape is shifted left, right, up or down.

Example 13 Translating shapes

Draw the image of the triangle ABC after a translation 2 units to the right and 3 units down.



SOLUTION



EXPLANATION

Shift every vertex 2 units to the right and 3 units down. Then join the vertices to form the image.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 14 Describing translations

A point $B(5, -2)$ is translated to $B'(-1, 2)$. Describe the translation.

SOLUTION

Translation is 6 units left and 4 units up.

EXPLANATION




Exercise 9I

1, 2(½), 3 | 3 | —

UNDERSTANDING

1 Point A has coordinates (3, 2). Write the coordinates of the image point A' when point A is translated in each of the following ways.



- **a** 1 unit right
- **b** 2 units left
- **c** 3 units up
- **d** 1 unit down
- **e** 1 unit left and 2 units up
- **f** 3 units left and 1 unit down
- **g** 2 units right and 1 unit down
- **h** 0 units left and 2 units down

2 A point is translated to its image. Write the missing word (i.e. left, right, up or down) for each sentence.

- **a** (1, 1) is translated _____ to the point (1, 3).
- **b** (5, 4) is translated _____ to the point (1, 4).
- **c** (7, 2) is translated _____ to the point (7, 0).
- **d** (3, 0) is translated _____ to the point (3, 1).
- **e** (5, 1) is translated _____ to the point (4, 1).
- **f** (2, 3) is translated _____ to the point (1, 3).
- **g** (0, 2) is translated _____ to the point (5, 2).
- **h** (7, 6) is translated _____ to the point (11, 6).

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


3 The point (7, 4) is translated to the point (0, 1).

- **a** How far left has the point been translated?
- **b** How far down has the point been translated?
- **c** If the point (0, 1) is translated to (7, 4):
  - **i** How far right has the point been translated?
  - **ii** How far up has the point been translated?


Example 13

4 Draw the image of these shapes after each translation.


a 3 units left and 1 unit up




b 1 unit right and 2 units up




c 3 units right and 2 units down



d 4 units left and 2 units down



5 Point A has coordinates (–2, 3). Write the coordinates of the image point A' when point A is translated in each of the following ways.



- **a** 3 units right
- **b** 2 units left
- **c** 2 units down
- **d** 5 units down
- **e** 2 units up
- **f** 10 units right
- **g** 3 units right and 1 unit up
- **h** 4 units right and 2 units down
- **i** 5 units right and 6 units down
- **j** 1 unit left and 2 units down
- **k** 3 units left and 1 unit up
- **l** 2 units left and 5 units down

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

91

Example 14

FLUENCY

6 Describe the translation when each point is translated to its image. Give your answer similar to these examples: '4 units right' or '2 units left and 3 units up'.

a $A(1, 3)$ is translated to $A'(1, 6)$.
b $B(4, 7)$ is translated to $B'(4, 0)$.
c $C(-1, 3)$ is translated to $C'(-1, -1)$.
d $D(-2, 8)$ is translated to $D'(-2, 10)$.
e $E(4, 3)$ is translated to $E'(-1, 3)$.
f $F(2, -4)$ is translated to $F'(4, -4)$.
g $G(0, 0)$ is translated to $G'(-1, 4)$.
h $H(-1, -1)$ is translated to $H'(2, 5)$.
i $I(-3, 8)$ is translated to $I'(0, 4)$.
j $J(2, -5)$ is translated to $J'(-1, 6)$.
k $K(-10, 2)$ is translated to $K'(2, -1)$.
l $L(6, 10)$ is translated to $L'(-4, -3)$.

7 | 7, 8 | 8, 9


PROBLEM-SOLVING

7 A point, A, is translated to its image, A'. Describe the translation that takes A' to A (i.e. the reverse translation).


a $A(2, 3)$ and $A'(4, 1)$
b $B(0, 4)$ and $B'(4, 0)$
c $C(0, -3)$ and $C'(-1, 2)$
d $D(4, 6)$ and $D'(-2, 8)$

8 If only horizontal or vertical translations of distance 1 are allowed, how many different paths are there from points A to B on each grid below? No point can be visited more than once.

a



b



9 Starting at $(0, 0)$ on the Cartesian plane, how many different points can you move to if a maximum of 3 units in total can be translated in any of the four directions of left, right, up or down? Do not count the point $(0, 0)$.

10 | 10 | 10, 11

REASONING

10 A shape is translated to its image. Explain why the shape's size and orientation is unchanged.

11 A combination of translations can be replaced with one single translation. For example, if $(1, 1)$ is translated 3 units right and 2 units down, followed by a translation of 6 units left and 5 units up, then the final image point $(-2, 4)$ could be obtained with the single translation 3 units left and 3 units up.
Describe the single translation that replaces these combinations of translations.

a $(1, 1)$ is translated 2 units left and 1 unit up, followed by a translation of 5 units right and 2 units down.
b $(6, -2)$ is translated 3 units right and 3 units up, followed by a translation of 2 units left and 1 unit down.
c $(-1, 4)$ is translated 4 units right and 6 units down, followed by a translation of 6 units left and 2 units up.
d $(-3, 4)$ is translated 4 units left and 4 units down, followed by a translation of 10 units right and 11 units up.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

ENRICHMENT

12 Write the coordinates of the image point after each sequence of transformations. For each part, apply the next transformation to the image of the previous transformation.

a (2, 3)
- reflection in the x-axis
- reflection in the y-axis
- translation 2 units left and 2 units up

b (–1, 6)
- translation 5 units right and 3 units down
- reflection in the y-axis
- reflection in the x-axis

c (–4, 2)
- rotation 180° about (0, 0)
- reflection in the y-axis
- translation 3 units left and 4 units up

d (–3, –7)
- rotation 90° clockwise about (0, 0)
- reflection in the x-axis
- translation 6 units left and 2 units down

e (–4, 8)
- rotation 90° anticlockwise about (0, 0)
- translation 4 units right and 6 units up
- reflection in the x and the y axes



The rotation of the windmills can be analysed as a transformation.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9J Drawing solids

Interactive

Widgets

HOTsheets

Walkthroughs


Three-dimensional solids can be represented as a drawing on a two-dimensional surface (e.g. paper or computer screen), provided some basic rules are followed.



Architects create 3D models of building plans by hand or with computer software.

Let's start: Can you draw a cube?

Try to draw a cube. Here are two bad examples.




- What is wrong with these drawings?
- What basic rules do you need to follow when drawing a cube?


Key ideas

- Draw cubes and rectangular prisms by keeping:
  - parallel edges pointing in the same direction
  - parallel edges the same length.
- Draw **pyramids** by joining the apex with the vertices on the base.


triangular pyramid (tetrahedron)



square pyramid



- Draw **cylinders** and **cones** by starting with an oval shape.




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Key ideas

- **Square** and **isometric dot paper** can help to accurately draw solids. Drawings made on isometric dot paper clearly show the cubes that make up the solid.

square dot paper



isometric dot paper




Example 15 Drawing solids

Draw these solids.


a A cone on plain paper

b This solid on isometric dot paper




SOLUTION

a



b



EXPLANATION

Draw an oval shape for the base and the apex point. Dot any line or curve which may be invisible on the solid.
Join the apex to the sides of the base.

Rotate the solid slightly and draw each cube starting at the front and working back.


Exercise 9J

1, 2 | 2 | —


UNDERSTANDING

1 Copy these diagrams and add lines to complete the solid. Use dashed line for invisible edges.


a cube



b cylinder



c square pyramid



2 Cubes are stacked to form these solids. How many cubes are there in each solid?


a



b



c



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9J

3–6 | 3–6, 7(½) | 3(½), 4–6, 7(½)

FLUENCY


Example 15a

3 On plain paper draw an example of these common solids.


a cube **b** tetrahedron **c** cylinder
d cone **e** square based pyramid **f** rectangular prism

4 Copy these solids onto square dot paper.

a



b



Example 15b


5 Make a copy of the solids in Question **2** on isometric dot paper.

6 Draw these solids onto isometric dot paper.


a



b




7 Here is a cylinder with its top view (circle) and side view (rectangle):




Draw the shapes which are the top view and side view of these solids.


a cube




b square prism




c cone




d square pyramid



e octahedron



f sphere




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


9J

FLUENCY


g square pyramid on cube



h hemisphere $\left(\frac{1}{2}\text{ sphere}\right)$ on square prism




i cone on hemisphere




8 | 8, 9 | 9, 10

PROBLEM-SOLVING

8 Here is the top (plan or bird's eye) view of a stack of 5 cubes. How many different stacks of 5 cubes could this represent?



9 Here is the top (plan) view of a stack of 7 cubes. How many different stacks of 7 cubes could this represent?



10 Draw these solids, making sure that:

i each vertex can be seen clearly

ii dashed lines are used for invisible edges.

a tetrahedron (solid with 4 faces)

b octahedron (solid with 8 faces)

c pentagonal pyramid (pyramid with pentagonal base)

11 | 11 | 11, 12

REASONING

11 Andrea draws two solids as shown. Aiden says that they are drawings of exactly the same solid. Is Aiden correct? Give reasons.




and



12 Match the solids **a**, **b**, **c** and **d** with an identical solid chosen from **A**, **B**, **C** and **D**.

a



b



c



d




A



B



C




D



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


ENRICHMENT

13 This diagram shows the front and left sides of a solid.




a Draw the front, left and top views of these solids.

i




ii




b Draw the solid that has these views.


i front




left




top




ii front



left



top





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

9K Nets and the Platonic solids EXTENDING











The ancient Greek philosophers studied the properties of polyhedra and how these could be used to explain the natural world. Plato (427–347 BCE) reasoned that the building blocks of all three-dimensional objects were regular polyhedra which have faces that are identical in size and shape. There are 5 regular polyhedra, called the Platonic solids after Plato, which were thought to represent fire, earth, air, water and the universe or cosmos.



Plato was one of the greatest early philosophers and mathematicians.

Let's start: Net of a cube

Here is one Platonic solid, the regular hexahedron or cube, and its net.




If the faces of the solid are unfolded to form a net, you can clearly see the 6 faces.

Can you draw a different net of a cube? How do you know it will fold to form a cube? Compare this with other nets in your class.


Key ideas

- A **net** of a solid is an unfolded two-dimensional representation of all the faces. Here are two examples.

square pyramid




cylinder




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas


- A **polyhedron** (plural: polyhedra) is a solid with flat faces.
  - They can be named by their number of faces, e.g. tetrahedron (4 faces), hexahedron (6 faces).
- The 5 **Platonic solids** are **regular polyhedra** each with identical regular faces and the same number of faces meeting at each vertex.
  - regular tetrahedron (4 triangular faces)




  - regular hexahedron or cube (6 square faces)




  - regular octahedron (8 triangular faces)



  - regular dodecahedron (12 pentagonal faces)



  - regular icosahedron (20 triangular faces)




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 16 Drawing nets



Draw a net for these solids.

a rectangular prism



b regular tetrahedron



SOLUTION	EXPLANATION
a 	This is one possible net for the rectangular prism, but others are also possible.
b 	Each triangle is equilateral. Each outer triangle folds up to meet centrally above the centre triangle.

Exercise 9K

1–4 | 3, 4 | —

UNDERSTANDING


1 Complete these sentences.


a A regular polygon will have _____ length sides.


b All the faces on regular polyhedra are _____ polygons.

c The _____ solids is the name given to the 5 regular polyhedra.

2 Which of the following nets would not fold up to form a cube?

A 

B 

C 

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

9K

UNDERSTANDING


3 Name the type of shapes that form the faces of these Platonic solids.

a tetrahedron **b** hexahedron **c** octahedron


d dodecahedron **e** icosahedron

4 Name the solids that have the following nets.


a



b



c




5–7 5–8 5(½), 6–8

FLUENCY


Example 16

5 Draw one possible net for these solids.

a




b




c




d



e



f



6 Which Platonic solid(s) fit these descriptions? There may be more than one.

a Its faces are equilateral triangles.

b It has 20 faces.

c It has 6 vertices.

d It is a pyramid.

e It has 12 edges.

f It has edges which meet at right angles (not necessarily all edges).


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9K


FLUENCY

7 Here are nets for the 5 Platonic solids. Name the Platonic solid that matches each one.


a




b




c



d



e



8 How many faces meet at each vertex for these Platonic solids?

a tetrahedron **b** hexahedron **c** octahedron


d dodecahdron **e** icosahedron

9 9 10


PROBLEM-SOLVING

9 Try drawing a net for a cone. Check by drawing a net and cutting it out to see if it works. Here are two cones to try.

a



b



10 How many different nets are there for these solids? Do not count rotations or reflections of the same net.

a regular tetrahedron **b** cube


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9K

11 | 11 | 11

REASONING

11 Imagine gluing two tetrahedrons together by joining two faces as shown, to form a new solid.




- **a** How many faces are there on this new solid?
- **b** Are all the faces identical?
- **c** Why do you think this new solid is not a Platonic solid.
  Hint: Look at the number of faces meeting at each vertex.

Number of cubes

— | — | 12

ENRICHMENT

12 Consider a number of 1 cm cubes stacked together to form a larger cube. This one, for example, contains $3 \times 3 \times 3 = 27$ cubes.



- **a** For the solid shown:
  - **i** how many 1 cm cubes are completely inside the solid with no faces on the outside?
  - **ii** how many 1 cm cubes have at least one face on the outside?
- **b** Complete this table.

n (side length)	1	2	3	4	5
n^3 (number of 1 cm cubes)	1	8			
Number of inside cubes	0				
Number of outside cubes	1				

- **c** For a cube stack of side length n cm, $n \geq 2$ find the rule for:
  - **i** the number of cubes in total
  - **ii** the number of inside cubes
  - **iii** the number of outside cubes




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Exploring triangles with computer geometry

Scalene

a Use the triangle tool to construct a triangle of any size.
b Measure the three interior angles.
c Use the computer geometry Calculate tool to add up the three interior angles. What do you notice?
d Drag one of the triangle vertices. Does the angle sum change?



Equilateral


a Construct a segment, AB, of any length.
b Construct two circles with centres at A and B, both with exactly the same radius. For the first circle, click at A for the centre and then at B for the radius. For the second circle, do the reverse.
c Place a point where the circles meet and label this C. Then join point C with points A and B.
d Measure the three interior angles. What do you notice?
e Drag the point A or B. What do you notice?

Isosceles

a Construct a segment, AB.
b Use the perpendicular bisector tool to construct the perpendicular bisector of segment AB.
c Place a new point, C, anywhere on the perpendicular line.
d Join point C with points A and B.
e Measure $\angle CAB$ and $\angle CBA$. What do you notice?
f Drag point A, B or C. What do you notice?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges




Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.


1 Use six matches to draw four equilateral triangles.



2 How many equilateral triangles of any size are in this diagram?




3 A regular octahedron has its corners cut off. How many edges are there in the new shape?




4 A polygon's vertices are joined by diagonals. Without counting the sides, how many diagonals can be drawn in each of these polygons?

a decagon (10 sides)



b 50-gon

5 This solid is made from stacking 1 cm cubes. How many cubes are used?




6 How many pairs of parallel lines are there in any cube?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary

Polygons and transformations

Polygons
regular convex octagon



irregular non-convex pentagon



Type
scalene



isosceles



equilateral



acute




right



obtuse




Constructing triangles
- SSS
- SAS
- AAS
- RHS

Symmetry


5 lines of symmetry
rotational symmetry of order 5


regular pentagon

Triangles


Angle sum



$a + 30 + 110 = 180$
$a + 140 = 180$
$a = 40$

Solids
cylinder



net




Exterior angle



$a = 70$
$b + 140 = 180$
$b = 40$
$c + 40 = 180$
$c = 140$


Transformations

Quadrilaterals


Special quadrilaterals
- parallelogram
  - rectangle
  - rhombus
  - square
- trapezium
- kite

Reflection


Rotation


Translation


2 units right and
3 units down

Angle sum


$a + 20 + 40 + 30 = 360$
$a + 90 = 360$
$a = 270$
$b + 270 = 360$
$b = 90$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

9A **1** A non-convex polygon has:
- **A** all interior angles of 90°
- **B** six sides
- **C** all interior angles less than 180°
- **D** all interior angles greater than 180°
- **E** at least one interior angle greater than 180°


9B **2** The three types of triangles all classified by their interior angles are:
- **A** acute, isosceles and scalene
- **B** acute, right and obtuse
- **C** scalene, isosceles and equilateral
- **D** right, obtuse and scalene
- **E** acute, equilateral and right

9C Ext **3** Which of the following is *not* sufficient to construct a single triangle?
- **A** three sides (SSS)
- **B** two sides and the angle between them (SAS)
- **C** three angles (AAA)
- **D** two angles and one side (AAS)
- **E** a right angle, hypotenuse and one other side (RHS)

9D **4** The angle sum of a triangle is always:

A 120° **B** 360° **C** 270° **D** 180° **E** 90°

9D **5** For the triangle shown opposite, the exterior angle theorem for a triangle says:



A $y = x + z$ **B** $z = x - y$ **C** $z = x + y$
D $x = z + y$ **E** $z = y - x$

9E **6** The quadrilateral that has 2 pairs of sides of equal length and 1 pair of angles of equal size is called a:

A kite **B** trapezium **C** rhombus **D** triangle **E** square

9F **7** Three angles inside a quadrilateral add to 275°. The fourth angle is:

A 750° **B** 95° **C** 285° **D** 125° **E** 85°

9G **8** A rhombus has line symmetry of order:

A 0 **B** 1 **C** 2 **D** 3 **E** 4

9H **9** The point $T(-3, 4)$ is reflected in the x-axis; hence, the image point T' has coordinates:

A $(3, 4)$ **B** $(-3, 4)$ **C** $(0, 4)$ **D** $(3, -4)$ **E** $(-3, -4)$

9I **10** The translation that takes $A(2, -3)$ to $A'(-1, 1)$ could be described as:
- **A** 3 units left
- **B** 4 units up
- **C** 3 units left and 4 units up
- **D** 1 unit right and 2 units down
- **E** 1 unit left and 2 units down

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Short-answer questions

9A **1** How many sides do these polygons have?

a pentagon **b** heptagon **c** undecagon

9A **2** A diagonal inside a polygon joins two vertices. Find how many diagonals can be drawn inside a quadrilateral if the shape is:

a convex **b** non-convex



9C Ext **3** Use a protractor and ruler to draw these triangles.

a triangle ABC with $AB = 4$ cm, $\angle CAB = 25°$ and $\angle ABC = 45°$

b triangle ABC with $AB = 5$ cm, $\angle BAC = 50°$ and $AC = 5$ cm

9C Ext **4** Use a protractor, pair of compasses and a ruler to construct these triangles.

a triangle ABC with $AB = 5$ cm, $BC = 6$ cm and $AC = 3$ cm

b triangle ABC with $AB = 6$ cm, $\angle BAC = 35°$ and $AC = 5$ cm

9C Ext **5** Is there sufficient information to construct a triangle in each of following cases? If yes, write SSS, SAS, AAS or RHS.


a triangle ABC with $\angle ABC = 20°$, $\angle BAC = 40°$ and $AB = 6$ cm

b triangle DEF with $DE = 9$ cm and $\angle DEF = 72°$


c triangle STU with $\angle STU = 90°$, $SU = 10$ cm and $ST = 6$ cm

9D **6** Find the value of a in each of these shapes.


a




b




c




d




e




f




g



h




i




9E **7** Name each of these quadrilaterals.


a



b



c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


Chapter review

9F **8** Find the value of a, marked in these quadrilaterals.


a




b




c



d



e



f




9G **9** Name the order of line and rotational symmetry for each of these diagrams.

a



b




c



9H **10** Write the coordinates of A', B' and C' when this shape is reflected in the following mirror lines.

a the y-axis **b** the x-axis




9H **11** Points $A(0, 4)$, $B(2, 0)$ and $D(3, 3)$ are shown here. Write down the coordinates of the image points A', B' and D' after each of the following rotations.

a 180° about $C(0, 0)$

b 90° clockwise about $C(0, 0)$


c 90° anticlockwise about $C(0, 0)$



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


9I **12** Write the coordinates of the vertices A', B' and C' after each of these translations.

- **a** 4 units right and 2 units up
- **b** 1 unit left and 4 units up




9J **13** Draw a side view, top view and net for each of these solids.

a




b



Extended-response questions


1 Two cables support a vertical tower, as shown in the diagram opposite, and the angle marked $a°$ is the angle between the two cables.

- **a** Find $\angle BDC$.
- **b** Find $\angle ADC$.
- **c** Find the value of a.
- **d** If $\angle DAB$ is changed to 30° and $\angle DBC$ is changed to 65°, will the value of a stay the same? If not, what will be the new value of a?




2 Shown is a drawing of a simple house on a Cartesian plane. Draw the image of the house after these transformations.

- **a** translation 5 units left and 4 units down
- **b** reflection in the x-axis
- **c** rotation 90° anticlockwise about $C(0, 0)$





ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 10 Equations

What you will learn

10A Introduction to equations
10B Solving equations by inspection (Consolidating)
10C Equivalent equations
10D Solving equations algebraically
10E Equations with fractions (Extending)
10F Equations with brackets (Extending)
10G Formulas
10H Applications

Australian curriculum

NUMBER AND ALGEBRA

Linear and non-linear relationships

Solve simple linear equations (ACMNA179)

Essential Mathematics for the Australian Curriculum Year 7 2ed

ISBN 978-1-107-56882-2

© Greenwood et al. 2015

Cambridge University Press

Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Theme park equations

Equations are used widely in mathematics and in many other fields. Whenever two things are equal, or should be equal, there is the potential to use the study of equations to help deal with such a situation.

Knowledge of mathematics and physics is vitally important when designing theme park rides. Engineers use equations to 'build' model rides on a computer so that safety limits can be determined in a virtual reality in which nobody gets injured.

Algebraic equations are solved to determine the dimensions and strengths of structures required to deal safely with the combined forces of weight, speed and varying movement. Passengers might scream with a mixture of terror and excitement but they must return unharmed to earth!

At Dreamworld on the Gold Coast, Queensland, 'The Claw' swings 32 people upwards at 75 km/h to a maximum height of 27.1 m (9 storeys), simultaneously spinning 360° at 5 r.p.m. (revolutions per minute). 'The Claw' is the most powerful pendulum ride on the planet. It is built to scare!

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10A Introduction to equations










An equation is a mathematical statement used to say that two expressions have the same value. It will always consist of two expressions that are separated by an equals sign (=).

Sample equations include:

$$3 + 3 = 6$$
$$30 = 2 \times 15$$
$$100 - 30 = 60 + 10$$

which are all true equations.

An equation does not have to be true. For instance, $2 + 2 = 17$ and $5 = 3 - 1$ and $10 + 15 = 12 + 3$ are all false equations.



This equation was proposed by the famous scientist Albert Einstein (1879–1955). It explains the special theory of relativity.

If an equation contains pronumerals, one cannot generally tell whether the equation is true or false until values are substituted for the pronumerals. For example, $5 + x = 7$ could be true (if x is 2) or it could be false (if x is 15).

Let's start: Equations – true or false?

Rearrange the following five symbols to make as many different equations as possible.

$$5,\ 2,\ 3,\ +,\ =$$

- Which of them are true? Which are false?
- Is it always possible to rearrange numbers and operations to make true equations?

Key ideas

- An **expression** is a collection of pronumerals, numbers and operators without an equals sign (e.g. $2x + 3$).
- An **equation** is a mathematical statement stating that two things are equal, (e.g. $2x + 3 = 4y - 2$).
- Equations have a left-hand side (LHS), a right-hand side (RHS) and an equals sign in between.

$$\underbrace{2x + 3}_{\text{LHS}} = \underbrace{4y - 2}_{\text{RHS}}$$

- Equations are mathematical statements that can be true (e.g. $2 + 3 = 5$) or false (e.g. $5 + 7 = 21$).
- If a pronumeral is included in an equation, you need to know the value to substitute before deciding whether the equation is true. For example, $3x = 12$ would be true if 4 is substituted for x, but it would be false if 10 is substituted.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 1 Identifying equations

Which of the following are equations?

a $3 + 5 = 8$ **b** $7 + 7 = 18$ **c** $2 + 12$ **d** $4 = 12 - x$ **e** $3 + u$

SOLUTION	EXPLANATION
a $3 + 5 = 8$ is an equation.	There are two expressions (i.e. $3 + 5$ and 8) separated by an equals sign.
b $7 + 7 = 18$ is an equation.	There are two expressions separated by an equals sign. Although this equation is false, it is still an equation.
c $2 + 12$ is not an equation.	This is just a single expression. There is no equals sign.
d $4 = 12 - x$ is an equation.	There are two expressions separated by an equals sign.
e $3 + u$ is not an equation.	There is no equals sign, so this is not an equation.

Example 2 Classifying equations

For each of the following equations, state whether it is true or false.

a $7 + 5 = 12$ **b** $5 + 3 = 2 \times 4$

c $12 \times (2 - 1) = 14 + 5$ **d** $3 + 9x = 60 + 6$, if $x = 7$

e $10 + b = 3b + 1$, if $b = 4$ **f** $3 + 2x = 21 - y$, if $x = 5$ and $y = 8$

SOLUTION	EXPLANATION
a true	The left-hand side (LHS) and right-hand side (RHS) are both equal to 12, so the equation is true.
b true	LHS $= 5 + 3 = 8$ and RHS $= 2 \times 4 = 8$, so both sides are equal.
c false	LHS $= 12$ and RHS $= 19$, so the equation is false.
d true	If x is 7, then: LHS $= 3 + 9 \times 7 = 66$, RHS $= 60 + 6 = 66$
e false	If b is 4, then: LHS $= 10 + 4 = 14$, RHS $= 3(4) + 1 = 13$
f true	If $x = 5$ and $y = 8$, then: LHS $= 3 + 2(5) = 13$, RHS $= 21 - 8 = 13$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Writing equations from a description

Write equations for each of the following scenarios.

a The sum of x and 5 is 22.

b The number of cards in a deck is x. In 7 decks there are 91 cards.

c Priya's age is currently j. In 5 years' time her age will equal 17.

d Corey earns $\$w$ per year. He spends $\frac{1}{12}$ on sport and $\frac{2}{13}$ on food. The total amount Corey spends on sport and food is \$15 000.

SOLUTION	EXPLANATION
a $x + 5 = 22$	The sum of x and 5 is written $x + 5$.
b $7x = 91$	$7x$ means $7 \times x$ and this number must equal the 91 cards.
c $j + 5 = 17$	In 5 years' time Priya's age will be 5 more than her current age, so $j + 5$ must be 17.
d $\frac{1}{12} \times w + \frac{2}{13} \times w = 15000$	$\frac{1}{12}$ of Corey's wage is $\frac{1}{12} \times w$ and $\frac{2}{13}$ of his wage is $\frac{2}{13} \times w$.

Exercise 10A

1–4 | 3, 4 | —

UNDERSTANDING

Example 1

1 Classify each of the following as an equation (E) or not an equation (N).

a $7 + x = 9$ **b** $2 + 2$ **c** $2 \times 5 = t$

d $10 = 5 + x$ **e** $2 = 2$ **f** $7 \times u$

g $10 \div 4 = 3p$ **h** $3 = e + 2$ **i** $x + 5$

Example 2a–c

2 Classify each of these equations as true or false:

a $2 + 3 = 5$ **b** $3 + 2 = 6$ **c** $5 - 1 = 6$

Example 2d

3 If $x = 2$, is $10 + x = 12$ true or false?

Example 2e

4 Consider the equation $4 + 3x = 2x + 9$.

a If $x = 5$, state the value of the left-hand side (LHS).

b If $x = 5$, state the value of the right-hand side (RHS).

c Is the equation $4 + 3x = 2x + 9$ true or false when $x = 5$?

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10A

FLUENCY

5(½), 6, 7, 9(½) | 5(½), 6, 7, 8–9(½) | 5–9(½)

5 For each of the following equations, state whether it is true or false.

a $10 \times 2 = 20$ **b** $12 \times 11 = 144$ **c** $3 \times 2 = 5 + 1$

d $100 - 90 = 2 \times 5$ **e** $30 \times 2 = 32$ **f** $12 - 4 = 4$

g $2(3 - 1) = 4$ **h** $5 - (2 + 1) = 7 - 4$ **i** $3 = 3$

j $2 = 17 - 14 - 1$ **k** $10 + 2 = 12 - 4$ **l** $1 \times 2 \times 3 = 1 + 2 + 3$

m $2 \times 3 \times 4 = 2 + 3 + 4$ **n** $100 - 5 \times 5 = 20 \times 5$ **o** $3 - 1 = 2 + 5 - 5$

6 If $x = 3$, state whether each of these equations is true or false.

a $5 + x = 7$ **b** $x + 1 = 4$ **c** $13 - x = 10 + x$ **d** $6 = 2x$

7 If $b = 4$, state whether each of the following equations is true or false.

a $5b + 2 = 22$ **b** $10 \times (b - 3) = b + b + 2$

c $12 - 3b = 5 - b$ **d** $b \times (b + 1) = 20$

Example 2f

8 If $a = 10$ and $b = 7$, state whether each of these equations is true or false.

a $a + b = 17$ **b** $a \times b = 3$ **c** $a \times (a - b) = 30$

d $b \times b = 59 - a$ **e** $3a = 5b - 5$ **f** $b \times (a - b) = 20$

g $21 - a = b$ **h** $10 - a = 7 - b$ **i** $1 + a - b = 2b - a$

Example 3a

9 Write equations for each of the following.

a The sum of 3 and x is equal to 10.

b When k is multiplied by 5, the result is 1005.

c The sum of a and b is 22.

d When d is doubled, the result is 78.

e The product of 8 and x is 56.

f When p is tripled, the result is 21.

g One-quarter of t is 12.

h The sum of q and p is equal to the product of q and p.

PROBLEM-SOLVING

10, 11 | 10, 12 | 10, 12, 13

Example 3b–d

10 Write true equations for each of these problems. You do not need to solve them.

a Chairs cost $\$c$ at a store. The cost of 6 chairs is \$546.

b Patrick works for x hours each day. In a 5-day working week, he works $37\frac{1}{2}$ hours in total.

c Pens cost $\$a$ each and pencils cost $\$b$. Twelve pens and three pencils cost \$28 in total.

d Amy is f years old. In 10 years' time her age will be 27.

e Andrew's age is j and Hailey's age is m. In 10 years' time their combined age will be 80.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10A

PROBLEM-SOLVING

11 Find a value of m that would make this equation true: $10 = m + 7$.

12 Find two possible values of k that would make this equation true: $k \times (8 - k) = 12$.

13 If the equation $x + y = 6$ is true, and x and y are both whole numbers between 1 and 5, what values could they have?

	14(½)	14(½)	14

REASONING

14 Equations involving pronumerals can be split into three groups:
A: Always true, no matter what values are substituted.
N: Never true, no matter what values are substituted.
S: Sometimes true but sometimes false, depending on the values substituted.
Categorise each of these equations as either A, N or S.

a $x + 5 = 11$	**b** $12 - x = x$	**c** $a = a$	**d** $5 + b = b + 5$
e $a = a + 7$	**f** $5 + b = b - 5$	**g** $0 \times b = 0$	**h** $a \times a = 100$
i $2x + x = 3x$	**j** $2x + x = 4x$	**k** $2x + x = 3x + 1$	**l** $a \times a + 100 = 0$

Equation permutations	—	—	15, 16

ENRICHMENT

15 For each of the following, rearrange the symbols to make a true equation.

a 6, 2, 3, ×, =	**b** 1, 4, 5, –, =
c 2, 2, 7, 10, –, ÷, =	**d** 2, 4, 5, 10, –, ÷, =

16 **a** How many different equations can be produced using the symbols 2, 3, 5, +, =?
b How many of these equations are true?
c Is it possible to change just one of the numbers above and still produce true equations by rearranging the symbols?
d Is it possible to change just the operation above (i.e. +) and still produce true equations?



Many mathematical equations need to be solved to build and launch space stations into orbit.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10B Solving equations by inspection

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

Solving an equation is the process of finding the values that pronumerals must take in order to make the equation true. Pronumerals are also called 'unknowns' when solving equations. For simple equations, it is possible to find a solution by trying a few values for the pronumeral until the equation is true. This method does not guarantee that we have found all the solutions (if there is more than one) and it will not help if there are no solutions, but it can be a useful and quick method for simple equations.

Let's start: Finding the missing value

- Find the missing values to make the following equations true.

  $10 \times \square - 17 = 13$

  $27 = 15 + 3 \times \square$

  $2 \times \square + 4 = 17$

- Can you always find a value to put in the place of $\square$ in any equation?



Key ideas

- **Solving** an equation means finding the values of any pronumerals that make the equation true. These values are called **solutions** to the equation.
- An **unknown** in an equation is a pronumeral whose value needs to be found in order to make the equation true.
- One method of solving equations is by **inspection** (also called **trial and error**), which involves inspecting (or trying) different values and seeing which ones make the equation true.

Example 4 Finding the missing number

For each of these equations, find the value of the missing number that would make it true.

a $\square \times 7 = 35$ b $20 - \square = 14$

SOLUTION	EXPLANATION
a 5	$5 \times 7 = 35$ is a true equation.
b 6	$20 - 6 = 14$ is a true equation.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 5 Solving equations by inspection

Solve each of the following equations by inspection.

a $c + 12 = 30$ **b** $5b = 20$ **c** $2x + 13 = 21$

SOLUTION	EXPLANATION
a $c + 12 = 30$ $c = 18$	The unknown variable here is c. $18 + 12 = 30$ is a true equation.
b $5b = 20$ $b = 4$	The unknown variable here is b. Recall that $5b$ means $5 \times b$, so if $b = 4$, $5b = 5 \times 4 = 20$.
c $2x + 13 = 21$ $x = 4$	The unknown variable here is x. Trying a few values: $x = 10$ makes LHS $= 20 + 13 = 33$, which is too large. $x = 3$ makes LHS $= 6 + 13 = 19$, which is too small. $x = 4$ makes LHS $= 21$.

Exercise 10B

1–4 | 3 | —

UNDERSTANDING

1 If the missing number is 5, classify each of the following equations as true or false.

a $\square + 3 = 8$ **b** $10 \times \square + 2 = 46$

c $10 - \square = 5$ **d** $12 = 6 + \square \times 2$

2 For the equation $\square + 7 = 13$:

a Find the value of the LHS (left-hand side) if $\square = 5$.

b Find the value of the LHS if $\square = 10$.

c Find the value of the LHS if $\square = 6$.

d What value of $\square$ would make the LHS equal to 13?

Example 4

3 Find the value of the missing numbers.

a $4 + \square = 7$ **b** $2 \times \square = 12$ **c** $13 = \square + 3$ **d** $10 = 6 + \square$

e $42 = \square \times 7$ **f** $100 - \square = 30$ **g** $\square \times 4 = 80$ **h** $\square + 12 = 31$

4 State the unknown pronumeral in each of the following equations.

a $4 + x = 12$ **b** $50 - c = 3$

c $4b + 2 = 35$ **d** $5 - 10d = 2$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10B

5–6(½) | 5–6(½), 7 | 5–7(½)

FLUENCY

Example 5a, b

5 Solve the following equations by inspection.

a $8 \times y = 64$	**b** $6 \div l = 3$	**c** $l \times 3 = 18$
d $4 - d = 2$	**e** $l + 2 = 14$	**f** $a - 2 = 4$
g $s + 7 = 19$	**h** $x \div 8 = 1$	**i** $12 = e + 4$
j $r \div 10 = 1$	**k** $13 = 5 + s$	**l** $0 = 3 - z$

Example 5c

6 Solve the following equations by inspection.

a $2p - 1 = 5$	**b** $3p + 2 = 14$	**c** $4q - 4 = 8$
d $4v + 4 = 24$	**e** $2b - 1 = 1$	**f** $5u + 1 = 21$
g $5g + 5 = 20$	**h** $4(e - 2) = 4$	**i** $45 = 5(d + 5)$
j $3d - 5 = 13$	**k** $8 = 3m - 4$	**l** $8 = 3o - 1$

7 Solve the following equations by inspection. (All solutions are whole numbers between 1 and 10.)

a $4 \times (x + 1) - 5 = 11$	**b** $7 + x = 2 \times x$	**c** $(3x + 1) \div 2 = 8$
d $10 - x = x + 2$	**e** $2 \times (x + 3) + 4 = 12$	**f** $15 - 2x = x$

8, 9 | 8–10 | 10–12

PROBLEM-SOLVING

8 Find the value of the number in each of these examples.

a A number is doubled and the result is 22.
b 3 less than a number is 9.
c Half of a number is 8.
d 7 more than a number is 40.
e A number is divided by 10, giving a result of 3.
f 10 is divided by a number, giving a result of 5.

9 Justine is paid \$10 an hour for x hours. During a particular week, she earns \$180.

a Write an equation involving x to describe this situation.
b Solve the equation by inspection to find the value of x.

10 Karim's weight is w kg and his brother is twice as heavy, weighing 70 kg.

a Write an equation involving w to describe this situation.
b Solve the equation by inspection to find the value of w.

11 Taylah buys x kg of apples at \$4.50 per kg. She spends a total of \$13.50.

a Write an equation involving x to describe this situation.
b Solve the equation by inspection to find x.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10B

PROBLEM-SOLVING

12 Yanni's current age is y years. In 12 years' time he will be three times as old.

a Write an equation involving y to describe this situation.

b Solve the equation by inspection to find y.



	13	13	13, 14

REASONING

13 **a** Solve the equation $x + (x + 1) = 19$ by inspection.

b The expression $x + (x + 1)$ can be simplified to $2x + 1$. Use this observation to solve $x + (x + 1) = 181$ by inspection.

14 There are three consecutive whole numbers that add to 45.

a Solve the equation $x + (x + 1) + (x + 2) = 45$ by inspection to find the three numbers.

b An equation of the form $x + (x + 1) + (x + 2) = ?$ has a whole number solution only if the right-hand side is a multiple of 3. Explain why this is the case. (Hint: Simplify the LHS.)

Multiple pronumerals	—	—	15

ENRICHMENT

15 When multiple pronumerals are involved, inspection can still be used to find a solution. For each of the following equations find, by inspection, one pair of values for x and y that make them true.

a $x + y = 8$ **b** $x - y = 2$ **c** $3 = 2x + y$

d $x \times y = 6$ **e** $12 = 2 + x + y$ **f** $x + y = x \times y$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10C Equivalent equations

Interactive


Widgets

HOTsheets

Walkthroughs

Sometimes, two equations essentially express the same thing. For example, the equations $x + 5 = 14$, $x + 6 = 15$ and $x + 7 = 16$ are all made true by the same value of x. Each time, we have added one to both sides of the equation.

We can pretend that true equations are about different objects that have the same weight. For instance, to say that $3 + 5 = 8$ means that a 3 kg block added to a 5 kg block weighs the same as an 8 kg block.




A true equation stays true if we 'do the same thing to both sides', such as adding a number or multiplying by a number. The exception to this rule is that multiplying both sides of any equation by zero will always make the equation true, and dividing both sides of any equation by zero is not permitted because nothing can be divided by zero. If we do the same thing to both sides we will have an equivalent equation.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Let's start: Equations as scales

The scales in the diagram show $2 + 3x = 8$.

- What would the scales look like if two '1 kg' blocks were removed from both sides?
- What would the scales look like if the two '1 kg' blocks were removed just from the left-hand side? (Try to show whether they would be level.)
- Use scales to illustrate why $4x + 3 = 4$ and $4x = 1$ are equivalent equations.



Key ideas

- Two equations are **equivalent** if you can get from one to the other by repeatedly:
  - adding a number to both sides
  - subtracting a number from both sides
  - multiplying both sides by a number other than zero
  - dividing both sides by a number other than zero
  - swapping the left-hand side with the right-hand side of the equation

Example 6 Applying an operation

For each equation, find the result of applying the given operation to both sides and then simplify.

a $2 + x = 5\ [+4]$ **b** $7x = 10\ [\times 2]$

c $30 = 20b\ [\div 10]$ **d** $7q - 4 = 10\ [+4]$

SOLUTION	EXPLANATION
a $2 + x = 5$	The equation is written out, and 4 is added to both sides.
$2 + x + 4 = 5 + 4$	
$x + 6 = 9$	Simplify the expressions on each side.
b $7x = 10$	The equation is written out, and both sides are multiplied by 2.
$7x \times 2 = 10 \times 2$	
$14x = 20$	Simplify the expressions on each side.
c $30 = 20b$	The equation is written out, and both sides are divided by 10.
$\frac{30}{10} = \frac{20b}{10}$	
$3 = 2b$	Simplify the expressions on each side.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d	$7q - 4 = 10$	The equation is written out, and 4 is added to both sides.
	$7q - 4 + 4 = 10 + 4$	
	$7q = 14$	Simplify the expressions on each side.

Example 7 Showing that equations are equivalent

Show that these pairs of equations are equivalent by stating the operation used.

a $2x + 10 = 15$ and $2x = 5$

b $5 = 7 - x$ and $10 = 2(7 - x)$

c $10(b + 3) = 20$ and $b + 3 = 2$

SOLUTION	EXPLANATION
a Both sides have had 10 subtracted. $2x + 10 = 15$ -10 ↓ -10 $2x = 5$	$2x + 10 - 10$ simplifies to $2x$, so we get the second equation by subtracting 10.
b Both sides have been multiplied by 2. $5 = 7 - x$ $\times 2$ ↓ $\times 2$ $10 = 2(7 - x)$	$2(7 - x)$ represents the RHS; i.e. $7 - x$, being multiplied by 2.
c Both sides have been divided by 10. $10(b + 3) = 20$ $\div 10$ ↓ $\div 10$ $b + 3 = 2$	Remember $10(b + 3)$ means $10 \times (b + 3)$. If we have $10(b + 3)$, we get $b + 3$ when dividing by 10.

Exercise 10C

1, 2 | 1 | —

UNDERSTANDING

Example 6a

1 Write an equation that results from adding 10 to both sides of each of these equations.

a $10d + 5 = 20$ **b** $7e = 31$ **c** $2a = 12$ **d** $x = 12$

2 Match up each of these equations (**a** to **e**) with its equivalent equation (i.e. **A** to **E**), where 3 has been added to both sides.

a $10 + x = 14$	**A** $12x + 3 = 123$
b $x + 1 = 13$	**B** $x + 13 = 11x + 3$
c $12 = x + 5$	**C** $13 + x = 17$
d $x + 10 = 11x$	**D** $x + 4 = 16$
e $12x = 120$	**E** $15 = x + 8$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10C

3–4(½) | 3–4(½), 5 | 3–5(½)

FLUENCY

Example 6b–d

3 For each equation, show the result of applying the listed operations to both sides.

a $5 + x = 10$ [+1] **b** $3x = 7$ [×2] **c** $12 = 8q$ [÷4]

d $9 + a = 13$ [–3] **e** $7 + b = 10$ [+5] **f** $5 = 3b + 7$ [–5]

g $2 = 5 + a$ [+2] **h** $12x - 3 = 3$ [+5] **i** $7p - 2 = 10$ [+2]

Example 7

4 Show that these pairs of equations are equivalent by stating the operation used.

a $4x + 2 = 10$ and $4x = 8$ **b** $7 + 3b = 12$ and $9 + 3b = 14$

c $20a = 10$ and $2a = 1$ **d** $4 = 12 - x$ and $8 = 2(12 - x)$

e $18 = 3x$ and $6 = x$ **f** $12 + x = 3$ and $15 + x = 6$

g $4(10 + b) = 80$ and $10 + b = 20$ **h** $12x = 5$ and $12x + 4 = 9$

5 For each of the following equations, find the equivalent equation that is the result of adding 4 to both sides and then multiplying both sides by 3.

a $x = 5$ **b** $2 = a + 1$ **c** $d - 4 = 2$

d $7 + a = 8$ **e** $3y - 2 = 7$ **f** $2x = 6$

6 | 6, 7 | 7, 8

PROBLEM-SOLVING

6 Match up each of these equations (**a** to **e**) with its equivalent equation (i.e. **A** to **E**), stating the operation used.

a $m + 10 = 12$ **A** $7 - m = 6$

b $3 - m = 2$ **B** $5m = 18$

c $12m = 30$ **C** $6m = 10$

d $5m + 2 = 20$ **D** $6m = 15$

e $3m = 5$ **E** $m + 12 = 14$

7 For each of the following pairs of equations, show they are equivalent by listing the two steps required to transform the first equation to the second.

a $x = 5$ and $3x + 2 = 17$ **b** $m = 2$ and $10m - 3 = 17$

c $5(2 + x) = 15$ and $x = 1$ **d** $10 = 3x + 10$ and $0 = x$

8 For each of the following equations, write an equivalent equation that you can get in one operation. Your equation should be simpler (i.e. smaller) than the original.

a $2q + 7 = 9$ **b** $10x + 3 = 10$ **c** $2(3 + x) = 40$ **d** $x \div 12 = 5$


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 | 9, 10 | 9–11 | 10C

REASONING

9 Sometimes two equations that look quite different can be equivalent.

a Show that $3x + 2 = 14$ and $10x + 1 = 41$ are equivalent by copying and completing the following.



b Show that $5x - 3 = 32$ and $x + 2 = 9$ are equivalent. (Hint: Try to go via the equation $x = 7$.)

c Show that $(x \div 2) + 4 = 9$ and $(x + 8) \div 2 = 9$ are equivalent.

10 As stated in the rules for equivalence listed in the **Key ideas**, multiplying both sides by zero is not permitted.

a Write the result of multiplying both sides of the following equations by zero.

i $3 + x = 5$ **ii** $2 + 2 = 4$ **iii** $2 + 2 = 5$

b Explain in a sentence why multiplying by zero does not give a useful equivalent equation.

11 Substituting pronumerals can be thought of as finding equivalent equations. Show how you can start with the equation $x = 3$ and find an equivalent equation with:

a $7x + 2$ on the LHS **b** $8 + 2x$ on the LHS

Equivalence relations

— | — | 12

ENRICHMENT

12 Classify each of the following statements as true or false, justifying your answer.

a Every equation is equivalent to itself.

b If equation 1 and equation 2 are equivalent, then equation 2 and equation 1 are equivalent.

c If equation 1 and equation 2 are equivalent, and equation 2 and equation 3 are equivalent, then equation 1 and equation 3 are equivalent.

d If equation 1 and equation 2 are *not* equivalent, and equation 2 and equation 3 are *not* equivalent, then equation 1 is *not* equivalent to equation 3.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10D Solving equations algebraically

Interactive

Widgets

HOTsheets

Walkthroughs

A soccer player preparing for a game will put on shin pads, then socks and, finally, soccer boots. When the game is over, these items are removed in reverse order: first the boots, then the socks and, finally, the shin pads. Nobody takes their socks off before their shoes. A similar reversal of procedures occurs with equivalent equations.



The order in which things are done matters in both sports and maths.

Here are three equivalent equations.

$x = 3$

$\times 2$ $\quad$ $\times 2$

$2x = 6$

$+4$ $\quad$ $+4$

$2x + 4 = 10$

We can undo the operations around x by doing the opposite operation in the reverse order.

$2x + 4 = 10$

-4 $\quad$ -4

$2x = 6$

$\div 2$ $\quad$ $\div 2$

$x = 3$

Because these equations are equivalent, this means that the solution to $2x + 4 = 10$ is $x = 3$. An advantage with this method is that solving equations by inspection can be very difficult if the solution is not just a small whole number.

Let's start: Attempting solutions

Georgia, Kartik and Lucas try to solve the equation $4x + 8 = 40$. They present their attempted solutions below.

Georgia

$4x + 8 = 40$

$\div 4$ $\quad$ $\div 4$

$x + 8 = 10$

-8 $\quad$ -8

$x = 2$

Kartik

$4x + 8 = 40$

-8 $\quad$ $+8$

$4x = 48$

$\div 4$ $\quad$ $\div 4$

$x = 12$

Lucas

$4x + 8 = 40$

-8 $\quad$ -8

$4x = 32$

$\div 4$ $\quad$ $\div 4$

$x = 8$

- Which of the students has the correct solution to the equation? Justify your answer by substituting each student's final answer.
- For each of the two students with the incorrect answer, explain the mistake they have made in their attempt to have equivalent equations.
- What operations would you do to both sides if the original equation was $7x - 10 = 11$?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- To solve an equation, find a simpler equation that is equivalent. Repeat this until the solution is found.
- A simpler equation can be found by applying the opposite operations in reverse order.
  e.g. for $5x + 2 = 17$, we have:

$$x \xrightarrow{\times 5} 5x \xrightarrow{+2} 5x + 2$$

So we solve the equation by 'undoing' them in reverse order.

$$5x + 2 \xrightarrow{-2} 5x \xrightarrow{\div 5} x$$

This gives the solution:

$$\begin{array}{c} 5x + 2 = 17 \\ -2 \quad\quad\quad -2 \\ 5x = 15 \\ \div 5 \quad\quad\quad \div 5 \\ x = 3 \end{array}$$

- A solution can be checked by substituting the value to see if the equation is true.
  e.g. LHS $= 5(3) + 2 = 17$ and RHS $= 17$.

Example 8 Solving one-step equations

Solve each of the following equations algebraically.

a $5x = 30$ **b** $17 = y - 21$ **c** $10 = \frac{q}{3}$

SOLUTION	EXPLANATION
a $\begin{array}{c} 5x = 30 \\ \div 5 \quad\quad \div 5 \\ x = 6 \end{array}$ So the solution is $x = 6$.	The opposite of $\times 5$ is $\div 5$. By dividing both sides by 5, we get an equivalent equation. Recall that $5x \div 5$ simplifies to x.
b $\begin{array}{c} 17 = y - 21 \\ +21 \quad\quad +21 \\ 38 = y \end{array}$ So the solution is $y = 38$.	The opposite of -21 is $+21$. Write the pronumeral on the LHS.
c $\begin{array}{c} 10 = \frac{q}{3} \\ \times 3 \quad\quad \times 3 \\ 30 = q \end{array}$ So the solution is $q = 30$.	Multiplying both sides by 3 gives an equivalent equation that is simpler. Note that $\frac{q}{3} \times 3 = q$. Write the pronumeral on the LHS.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 9 Solving two-step equations

Solve each of the following equations algebraically and check the solution.

a $7 + 4a = 23$ **b** $\frac{d}{3} - 2 = 4$ **c** $12 = 2(e + 1)$

SOLUTION	EXPLANATION
a $7 + 4a = 23$ -7 ↓ -7 $4a = 16$ $\div 4$ ↓ $\div 4$ $a = 4$	At each step, try to make the equation simpler by applying an operation to both sides.
Check: LHS $= 7 + 4a$ RHS $= 23$ ✓ $= 7 + 4 \times 4$ $= 7 + 16$ $= 23$	Choose the opposite operations based on $7 + 4a$: $a \xrightarrow{\times 4} 4a \xrightarrow{+7} 7 + 4a$ Opposite operations: -7, then $\div 4$. Check that our equation is true by substituting $a = 4$ back into the LHS and RHS. Both sides are equal, so $a = 4$ is a solution.
b $\frac{d}{3} - 2 = 4$ $+2$ ↓ $+2$ $\frac{d}{3} = 6$ $\times 3$ ↓ $\times 3$ $d = 18$	At each step, try to make the equation simpler by applying an operation to both sides. The opposite of -2 is $+2$ and the opposite of $\div 3$ is $\times 3$.
Check: LHS $= \frac{d}{3} - 2$ RHS $= 4$ ✓ $= \frac{18}{3} - 2$ $= 6 - 2$ $= 4$	Check that our equation is true by substituting $d = 18$ back into the LHS and RHS. Both sides are equal, so $d = 18$ is a solution.
c $12 = 2(e + 1)$ $\div 2$ ↓ $\div 2$ $6 = e + 1$ -1 ↓ -1 $5 = e$	At each step, try to make the equation simpler by applying an operation to both sides. The opposite of $\times 2$ is $\div 2$ and the opposite of $+1$ is -1.
So the solution is $e = 5$.	Write the solution on the LHS.
Check: LHS $= 12$ RHS $= 2(e + 1)$ $= 2(5 + 1)$ $= 2 \times 6$ $= 12$ ✓	Check that our equation is true by substituting $e = 5$ back into the equation.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10D

1–4 | 2, 4 | —


UNDERSTANDING

1 State whether each of the following equations is true or false.

a $x + 4 = 7$, if $x = 3$
b $b - 2 = 7$, if $b = 5$
c $7(d - 6) = d$, if $d = 7$
d $g + 5 = 3g$, if $g = 2$
e $f \times 4 = 20$, if $f = 3$

2 Consider the equation $7x = 42$.


a Copy and complete the diagram opposite.
b What is the solution to the equation $7x = 42$?




3 The equations $g = 2$ and $12(g + 3) = 60$ are equivalent. What is the solution to the equation $12(g + 3) = 60$?

4 Copy and complete the following, showing which operation was used. Remember that the same operation must be used for both sides.


a




b



c



d



5(½), 6, 7, 8(½) | 5(½), 6, 7, 8(½), 9, 10 | 6–10(½)

FLUENCY


Example 8

5 Solve the following equations algebraically.


a $6m = 54$
b $g - 9 = 2$
c $s \times 9 = 81$
d $i - 9 = 1$
e $7 + t = 9$
f $8 + q = 11$
g $4y = 48$
h $7 + s = 19$
i $24 = j \times 6$
j $12 = l + 8$
k $1 = v \div 2$
l $19 = 7 + y$
m $k \div 5 = 1$
n $2 = y - 7$
o $8z = 56$
p $13 = 3 + t$
q $b \times 10 = 120$
r $p - 2 = 9$
s $5 + a = 13$
t $n - 2 = 1$

6 Copy and complete the following to solve the given equations algebraically.


a




b



c



d



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

10D

FLUENCY

7 For each of these equations, state the first operation you would apply to both sides to solve it.

a $2x + 3 = 9$
b $4x - 7 = 33$
c $5(a + 3) = 50$
d $22 = 2(b - 17)$

Example 9

8 For each of the following equations:

i Solve the equation algebraically, showing your steps.
ii Check your solution by substituting the value into the LHS and RHS.

a $6f - 2 = 64$
b $\frac{k}{4} + 9 = 10$
c $5x - 4 = 41$
d $3(a - 8) = 3$
e $5k - 9 = 31$
f $\frac{a}{3} + 6 = 8$
g $2n - 8 = 14$
h $\frac{n}{4} + 6 = 8$
i $1 = 2g - 7$
j $30 = 3q - 3$
k $3z - 4 = 26$
l $17 = 9 + 8p$
m $10d + 7 = 47$
n $38 = 6t - 10$
o $9u + 2 = 47$
p $7 = 10c - 3$
q $10 + 8q = 98$
r $80 = 4(y + 8)$
s $4(q + 8) = 40$
t $7 + 6u = 67$

9 Solve the following equations, giving your solution as fractions.

a $4x + 5 = 8$
b $3 + 5k = 27$
c $22 = (3w + 7) \times 2$
d $10 = 3 \times (2 + x)$
e $3 = (8x + 1) \div 2$
f $3(x + 2) = 7$

10 Solve the following equations algebraically. (Note: The solutions for these equations are negative numbers.)

a $4r + 30 = 2$
b $2x + 12 = 6$
c $10 + \frac{t}{2} = 2$
d $\frac{y}{4} + 10 = 4$
e $-3x = 15$
f $4 = 2k + 22$
g $2x = -12$
h $5x + 20 = 0$
i $0 = 2x + 3$


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

11 For each of the following, write an equation and solve it algebraically.

- **a** The sum of x and 5 is 12.
- **b** The product of 2 and y is 10.
- **c** When b is doubled and then 6 is added, the result is 44.
- **d** 7 is subtracted from k. This result is tripled, giving 18.
- **e** 3 is added to one-quarter of b, giving a result of 6.
- **f** 10 is subtracted from half of k, giving a result of 1.

12 Danny gets paid \$12 per hour, plus a bonus of \$50 for each week. In one week he earned \$410.

- **a** Write an equation to describe this, using n for the number of hours worked.
- **b** Solve the equation algebraically and state the number of hours worked.



13 Jenny buys 12 pencils and 5 pens for the new school year. The pencils cost \$1.00 each.

- **a** If pens cost \$$x$ each, write an expression for the total cost.
- **b** The total cost was \$14.50. Write an equation to describe this.
- **c** Solve the equation algebraically, to find the total cost of each pen.
- **d** Check your solution by substituting your value of x into $12 + 5x$.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10D


PROBLEM-SOLVING

14 Write equations and solve them algebraically to find the unknown value in each of the following diagrams.


a




b



c



d



15 Solve the following equations algebraically.

a $7(3 + 5x) - 21 = 210$ **b** $(100x + 13) \div 3 = 271$ **c** $3(12 + 2x) - 4 = 62$

16 | 16, 17 | 16, 17, 18(½)

REASONING


16 Write five different equations that give a solution of $x = 2$.

17 **a** Show that $2x + 5 = 13$ and $5x = 20$ are equivalent by filling in the missing steps.

b Show that $10 + 2x = 20$ and $2(x - 3) = 4$ are equivalent.


c If two equations have the same solution, does this guarantee they are equivalent? Justify your answer.

d If two equations have different solutions, does this guarantee they are not equivalent? Justify your answer.




18 Nicola has attempted to solve four equations. Describe the mistake she has made in each case.


a




b



c



d



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

19 If an equation has a pronumeral on both sides, you can subtract it from one side and then use the same method as before. For example:

$5x + 4 = 3x + 10$

$-3x$ $-3x$

$2x + 4 = 10$

-4 -4

$2x = 6$

$\div 2$ $\div 2$

$x = 3$

Solve the following equations using this method.

a $5x + 2 = 3x + 10$

b $8x - 1 = 4x + 3$

c $5 + 12l = 20 + 7l$


d $2 + 5t = 4t + 3$

e $12s + 4 = 9 + 11s$

f $9b - 10 = 8b + 9$

g $5j + 4 = 10 + 2j$

h $3 + 5d = 6 + 2d$



Just like dance steps, a strict order must be followed when solving equations algebraically.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10E Equations with fractions EXTENDING

Interactive

Widgets

HOTsheets

Walkthroughs

Solving equations that involve fractions is straightforward once we recall that, in algebra, $\frac{a}{b}$ means $a \div b$. This means that if we have a fraction with b on the denominator, we can multiply both sides by b to get a simpler, equivalent equation.

Let's start: Fractional differences

Consider these three equations.

a $\frac{2x+3}{5} = 7$ **b** $\frac{2x}{5} + 3 = 7$ **c** $2\left(\frac{x}{5}\right) + 3 = 7$

- Solve each of them (by inspection or algebraically).
- Compare your solutions with those of your classmates.
- Why do two of the equations have the same solution?

Key ideas

- Recall that $\frac{a}{b}$ means $a \div b$.
- To solve an equation that has a fraction on one side, multiply *both* sides by the denominator.

$$\begin{array}{l} \times 5 \\ \\ \\ \times 5 \end{array} \left(\begin{array}{c} \frac{x}{5} = 4 \\ \downarrow \\ x = 20 \end{array} \right)$$

- If neither side of an equation is a fraction, do not multiply by the denominator.

$$\begin{array}{l} \times 3 \\ \\ \\ \times 3 \end{array} \left(\begin{array}{c} \frac{x}{3} + 5 = 8 \\ \downarrow \\ \cdots \end{array} \right) \quad \text{✗ Do not do this}$$

$$\begin{array}{l} -5 \\ \\ \times 3 \\ \\ \times 3 \end{array} \left(\begin{array}{c} \frac{x}{3} + 5 = 8 \\ \downarrow \\ \frac{x}{3} = 3 \\ \downarrow \\ x = 9 \end{array} \right) \begin{array}{l} -5 \\ \\ \\ \\ \end{array} \quad \text{✓ Do this}$$

- The expressions $\frac{x}{3} + 2$ and $\frac{x+2}{3}$ are different, as demonstrated in these flow charts.

$$x \xrightarrow{\div 3} \frac{x}{3} \xrightarrow{+2} \frac{x}{3} + 2 \quad \text{vs} \quad x \xrightarrow{+2} x + 2 \xrightarrow{\div 3} \frac{x+2}{3}$$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 10 Solving equations with fractions

Solve each of the following equations.

a $\frac{a}{7} = 3$

b $\frac{5y}{3} = 10$

c $\frac{3x}{4} + 7 = 13$

d $\frac{2x-3}{5} = 3$

SOLUTION	EXPLANATION
a $\frac{a}{7} = 3$ $\times 7$ ↓ $\times 7$ $a = 21$	Multiplying both sides by 7 removes the denominator of 7.
b $\frac{5y}{3} = 10$ $\times 3$ ↓ $\times 3$ $5y = 30$ $\div 5$ ↓ $\div 5$ $y = 6$	Multiplying both sides by 3 removes the denominator of 3. The equation $5y = 30$ can be solved normally.
c $\frac{3x}{4} + 7 = 13$ -7 ↓ -7 $\frac{3x}{4} = 6$ $\times 4$ ↓ $\times 4$ $3x = 24$ $\div 3$ ↓ $\div 3$ $x = 8$	First, we subtract 7 because we do not have a fraction by itself on the LHS. Once there is a fraction by itself, multiply by its denominator (in this case, 4) and solve the equation $3x = 24$ as you would normally.
d $\frac{2x-3}{5} = 3$ $\times 5$ ↓ $\times 5$ $2x - 3 = 15$ $+3$ ↓ $+3$ $2x = 18$ $\div 2$ ↓ $\div 2$ $x = 9$	First, multiply both sides by 5 to remove the denominator. Then solve the equation $2x - 3 = 15$ as you would normally.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10E

1–4 | 4 | —

UNDERSTANDING

1 Classify each of the following as true or false.

a $\frac{a}{5}$ means $a \div 5$.

b $\frac{q}{12}$ means $12 \div q$.

c $\frac{4+a}{3}$ means $(4+a) \div 3$.

d $\frac{4+a}{3}$ means $4 + (a \div 3)$.

e $\frac{12+3q}{4}$ means $(12+3q) \div 4$.

f $2 + \frac{x}{5}$ means $(2+x) \div 5$.

2 **a** If $x = 10$, find the value of $\frac{x+4}{2}$.

b If $x = 10$, find the value of $\frac{x}{2} + 4$.

c State whether the following is true or false: $\frac{x+4}{2}$ and $\frac{x}{2} + 4$ are equivalent expressions.

Example 10a

3 Fill in the missing steps to solve each of these equations.

a

$\frac{b}{4} = 11$

$\times 4$ $\times 4$

$b = __$

b

$\frac{d}{5} = 3$

$\times 5$ $\times 5$

$__ = __$

c

$\frac{h}{4} = 7$

$?$ $?$

$__ = __$

d

$\frac{p}{13} = 2$

$?$ $?$

$__ = __$

4 For each of the following equations (**a** to **d**), choose the appropriate first step (i.e. **A** to **D**) needed to solve it.

a $\frac{x}{3} = 10$

b $\frac{x}{3} + 2 = 5$

c $\frac{x-3}{2} = 1$

d $\frac{x}{2} - 3 = 5$

A Multiply both sides by 2.

B Multiply both sides by 3.

C Subtract 2 from both sides.

D Add 3 to both sides.

5–6(½) | 5–7(½) | 5–7(½)

FLUENCY

Example 10b

5 Solve the following equations algebraically.

a $\frac{m}{6} = 2$ **b** $\frac{c}{9} = 2$ **c** $\frac{s}{8} = 2$ **d** $\frac{r}{5} = 2$

e $\frac{3u}{5} = 12$ **f** $\frac{2y}{9} = 4$ **g** $\frac{5x}{2} = 10$ **h** $\frac{3a}{8} = 6$

i $\frac{4h}{5} = 8$ **j** $\frac{3j}{5} = 9$ **k** $\frac{5v}{9} = 5$ **l** $\frac{3q}{4} = 6$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10E

FLUENCY

Example 10c, d

6 Solve the following equations algebraically. Check your solutions using substitution.

a $\frac{h+15}{12}=2$ **b** $\frac{y+5}{11}=1$ **c** $\frac{j+8}{11}=1$ **d** $\frac{b-2}{2}=1$

e $\frac{7u-12}{9}=1$ **f** $14+\frac{4t}{9}=18$ **g** $1=\frac{w+5}{11}$ **h** $1=\frac{4r-13}{3}$

i $\frac{2q}{9}+2=4$ **j** $\frac{s+2}{5}=1$ **k** $\frac{3l}{2}+9=21$ **l** $12=\frac{2z}{7}+10$

m $1=\frac{v-4}{7}$ **n** $\frac{f-2}{7}=1$ **o** $9=4+\frac{5x}{2}$ **p** $3=\frac{7+4d}{9}$

q $\frac{7n}{5}+14=21$ **r** $\frac{7m+7}{4}=21$ **s** $3=\frac{7p}{4}-11$ **t** $\frac{4a-6}{5}=6$

7 Solve the following equations algebraically. (Note: The solutions to these equations are negative numbers.)

a $\frac{y+4}{3}=1$ **b** $\frac{a}{10}+2=1$ **c** $\frac{2x}{5}+10=6$ **d** $\frac{x}{4}+12=0$

e $0=12+\frac{2u}{5}$ **f** $\frac{3y}{5}+8=2$ **g** $1=\frac{-2u-3}{5}$ **h** $-2=\frac{4d}{5}+2$

8 | 8, 9 | 9, 10

PROBLEM-SOLVING

8 In each of the following cases, write an equation and solve it to find the number.

a A number, t, is halved and the result is 9.

b One-third of q is 14.

c A number, r, is doubled and then divided by 5. The result is 6.

d 4 is subtracted from q and this is halved, giving a result of 3.

e 3 is added to x and the result is divided by 4, giving a result of 2.

f A number, y, is divided by 4 and then 3 is added, giving a result of 5.

9 A group of five people go out for dinner and then split the bill evenly. They each pay $31.50.

a If b represents the total cost of the bill, in dollars, write an equation to describe this situation.

b Solve this equation algebraically.

c What is the total cost of the bill?

10 Lee and Theo hired a tennis court for a cost of $\$x$, which they split evenly. Out of his own pocket, Lee also bought some tennis balls for $5.

a Write an *expression* for the total amount of money that Lee paid.

b Given that Lee paid $11 in total, write an equation and solve it to find the total cost of hiring the court.

c State how much money Theo paid for his share of hiring the tennis court.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10E

11 | 11, 12 | 11–13

REASONING

11 **a** Explain, in one sentence, the difference between $\frac{2x+3}{5}$ and $\frac{2x}{5}+3$.

b What is the first operation you would apply to both sides to solve $\frac{2x+3}{5}=7$?

c What is the first operation you would apply to both sides to solve $\frac{2x}{5}+3=7$?

d Are there any values of x for which $\frac{2x+3}{5}$ and $\frac{2x}{5}+3$ are equal to each other?

12 Sometimes an equation's solution will be a fraction. For example, $2x=1$ has the solution $x=\frac{1}{2}$.

a Give another equation that has $x=\frac{1}{2}$ as its solution.

b Find an equation that has the solution $x=\frac{5}{7}$.

c Could an equation have the solution $x=-\frac{1}{2}$? Justify your answer.

13 Dividing by 2 and multiplying by $\frac{1}{2}$ have the same effect.

For example, $6\div 2=3$ and $6\times\frac{1}{2}=3$.

a Show how each of these equations can be solved algebraically.

i $\frac{x}{2}=5$ **ii** $\frac{1}{2}\times x=5$

b Solve the two equations $\frac{x+4}{3}=10$ and $\frac{1}{3}(x+4)=10$ algebraically, showing the steps you would use at each stage clearly.

c How does rewriting divisions as multiplications change the first step when solving equations?

Fractional answers

— | — | 14

ENRICHMENT

14 Solve each of the following equations, giving your answers as a fraction.

a $\frac{2x+5}{4}=3$ **b** $\frac{3x-4}{6}=\frac{3}{4}$

c $\left(\frac{7+2x}{4}\right)\times 3=10$ **d** $\frac{1}{2}=\frac{3x-1}{5}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Progress quiz

10A **1** Classify each of the following as an equation (E) or not an equation (N).

a $4 + w = 9$ **b** $x + 12$ **c** $3 + 10 = 17$ **d** $20 + 6$

10A **2** If $x = 4$, state whether each of these equations is true (T) or false (F).

a $3x - 4 = 8$ **b** $5x + 6 = 25$ **c** $9 - x = x + 1$ **d** $2x = 5x - 8$

10A **3** Write an equation for each of the following. (You do not need to solve the equations you write.)

a The sum of 5 and m is equal to 12.

b When d is doubled, the result is 24.

c The product of 9 and x is 72.

d Canaries cost $\$c$ each and budgies cost $\$b$ each. Three canaries and four budgies cost \$190.

10B **4** Solve the following equations by inspection.

a $a - 5 = 4$ **b** $36 = x \times 9$ **c** $m \div 5 = 6$ **d** $3a + 1 = 7$

10C **5** For each equation, find the result of applying the given operation to both sides. You *do not* need to solve the equation.

a $4x = 7$ (multiply by 5) **b** $2a + 5 = 21$ (subtract 5)

10C **6** State the operation applied to get from the first to the second equation in each of the following.

a $4x - 8 = 12 \rightarrow 4x = 20$ **b** $18 = 6x \rightarrow 3 = x$ **c** $3a = 5 \rightarrow 6a = 10$

10D **7** Solve each of the following equations algebraically.

a $a + 7 = 19$ **b** $w - 4 = 27$ **c** $k \div 9 = 7$ **d** $5m = 40$

10D **8** Solve each of the following equations algebraically and check your solution.

a $12x = 132$ **b** $8 + 3a = 29$ **c** $42 = 8m - 6$ **d** $100 = 5(y + 12)$

10E **Ext** **9** Solve the following equations algebraically.

a $\frac{c}{4} = 6$ **b** $\frac{3a}{4} = 6$ **c** $\frac{h + 16}{4} = 7$ **d** $15 = \frac{2m}{5} - 7$

10E **Ext** **10** Write an equation for each of these situations and solve it to find the number.

a A number, m, is divided by 2 and then 5 is added, giving a result of 11.

b 7 is added to x and the result is halved, giving a result of 9.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10F Equations with brackets EXTENDING

Interactive

Widgets


HOTsheets

Walkthroughs

Recall from Chapter 5 that expressions with brackets can be expanded using the observation shown at right about rectangles' areas.

So $3(x + 5)$ is equivalent to $3x + 15$.

When solving $3(x + 5) = 21$, we could first divide both sides by 3 or we could first expand the brackets, giving $3x + 15 = 21$, and then subtract 15. For some equations, the brackets must be expanded first.



Let's start: Removing brackets

a Draw two rectangles, with areas $4(x + 3)$ and $5(x + 2)$.

b Use these to show that $4(x + 3) + 5(x + 2)$ is equivalent to $9x + 22$.

c Can you solve the equation $4(x + 3) + 5(x + 2) = 130$?

Key ideas

- To expand brackets, use the **distributive law**, which states that:

  $a(b + c) = ab + ac$ e.g. $3(x + 4) = 3x + 12$

  $a(b - c) = ab - ac$ e.g. $4(b - 2) = 4b - 8$
- **Like terms** are terms that contain exactly the same pronumerals and can be collected to simplify expressions. For example, $3x + 4 + 2x$ can be simplified to $5x + 4$.
- Equations involving brackets can be solved by first expanding brackets and collecting like terms.

Example 11 Expanding brackets

Expand each of the following.

a $4(x + 3)$ b $6(q - 4)$ c $5(3a + 4)$

SOLUTION	EXPLANATION
a $4(x + 3) = 4x + 12$	Using the distributive law: $4(x + 3) = 4x + 12$
b $6(q - 4) = 6q - 24$	Using the distributive law: $6(q - 4) = 6q - 24$
c $5(3a + 4) = 15a + 20$	Using the distributive law: $5(3a + 4) = 5 \times 3a + 20$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Simplifying expressions with like terms

Simplify each of these expressions.

a $2x + 5 + x$ **b** $3a + 8a + 2 - 2a + 5$

SOLUTION | **EXPLANATION**

a $2x + 5 + x = 3x + 5$

Like terms are $2x$ and x.
These are combined to give $3x$.

b $3a + 8a + 2 - 2a + 5 = 9a + 7$

Like terms are combined:
$3a + 8a - 2a = 9a$ and $2 + 5 = 7$

Example 13 Solving equations by expanding brackets

Solve each of these equations by expanding brackets first.

a $3(x + 2) = 18$ **b** $7 = 7(4q - 3)$ **c** $3(b + 5) + 4b = 29$

SOLUTION | **EXPLANATION**

a

$3(x + 2) = 18$

$3x + 6 = 18$

-6 -6

$3x = 12$

$\div 3$ $\div 3$

$x = 4$

Use the distributive law to expand the brackets.

Solve the equation by performing the same operations to both sides.

b

$7 = 7(4q - 3)$

$7 = 28q - 21$

$+21$ $+21$

$28 = 28q$

$\div 28$ $\div 28$

$1 = q$

So $q = 1$ is the solution.

Use the distributive law to expand brackets.

Solve the equation by performing the same operations to both sides.

c $3(b + 5) + 4b = 29$

$3b + 15 + 4b = 29$

$7b + 15 = 29$

-15 -15

$7b = 14$

$\div 7$ $\div 7$

$b = 2$

Use the distributive law to expand brackets.
Collect like terms to simplify the expression.
Solve the equation by performing the same operations to both sides.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10F

1–3 | 2, 3 | —

UNDERSTANDING

1 Which of the following is the correct expansion of $5(x + 2)$?

A $5 \times x + 2$ **B** $5x + 2$ **C** $5x + 10$ **D** $10x$

2 Fill in the missing numbers.

a $3(x + 2) = 3x +$ ☐ **b** $4(3a + 1) = 12a +$ ☐

c $2(b + 1) =$ ☐ $b + 2$ **d** $6(2c + 3) =$ ☐ $c + 18$

3 Answer true or false to each of the following.

a $4x + 3x$ can be simplified to $7x$. **b** $2a + 4b$ can be simplified to $6ab$.

c $6p - 4p$ can be simplified to $2p$. **d** $7a + 3 + 2a$ can be simplified to $9a + 3$.

e $2b + 3$ can be simplified to $5b$. **f** $20x - 12x + 3y$ can be simplified to $32x + 3y$.

4–8(½) | 4–9(½) | 4–9(½)

FLUENCY

Example 11

4 Expand each of the following.

a $2(x + 1)$ **b** $5(2b + 3)$ **c** $2(3a - 4)$ **d** $5(7a + 1)$

e $4(3x + 4)$ **f** $3(8 - 3y)$ **g** $12(4a + 3)$ **h** $2(u - 4)$

Example 12

5 Simplify these expressions by collecting like terms.

a $3a + a + 2$ **b** $5 + 2x + x$ **c** $2b - 4 + b$ **d** $5a + 12 - 2a$

e $5x + 3 + x$ **f** $3k + 6 - 2k$ **g** $7 + 2b - 1$ **h** $6k - k + 1$

Example 13a

6 Solve the following equations by expanding the brackets first. Check your solutions by substituting them in.

a $2(10 + s) = 32$ **b** $2(5 + l) = 12$ **c** $3(p - 7) = 6$ **d** $8(y + 9) = 72$

e $8(4 + q) = 40$ **f** $7(p + 7) = 133$ **g** $8(m + 7) = 96$ **h** $22 = 2(b + 5)$

i $25 = 5(2 + p)$ **j** $63 = 7(p + 2)$ **k** $9(y - 6) = 27$ **l** $2(r + 8) = 32$

Example 13b

7 Solve these equations by expanding the brackets first.

a $6(3 + 2d) = 54$ **b** $8(7x - 7) = 56$ **c** $3(2x - 4) = 18$ **d** $27 = 3(3 + 6e)$

e $44 = 4(3a + 8)$ **f** $30 = 6(5r - 10)$ **g** $10 = 5(9u - 7)$ **h** $3(2q - 9) = 39$

Example 13c

8 Solve the following equations by first expanding the brackets. You will need to simplify the expanded expressions by collecting like terms.

a $5(4s + 4) + 4s = 44$ **b** $5i + 5(2 + 2i) = 25$ **c** $3(4c - 5) + c = 50$

d $3(4 + 3v) - 4v = 52$ **e** $5(4k + 2) + k = 31$ **f** $4q + 6(4q - 4) = 60$

g $40 = 4y + 6(2y - 4)$ **h** $44 = 4f + 4(2f + 2)$ **i** $40 = 5t + 6(4t - 3)$

9 Solve the following equations algebraically. (Note: The answers to these equations are negative numbers.)

a $3(u + 7) = 6$ **b** $2(k + 3) = 0$ **c** $6(p - 2) = -18$

d $16 = 8(q + 4)$ **e** $5(2u + 3) = 5$ **f** $3 = 2(x + 4) + 1$

g $4(p - 3) + p = -32$ **h** $3(r + 4) + 2r + 40 = 2$ **i** $2(5 + x) - 3x = 15$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10F

PROBLEM-SOLVING | 10(½) | 10 | 10

10 For each of the following problems:

- **i** Write an equation.
- **ii** Solve your equation by first expanding any brackets.

a 5 is added to x and then this is doubled, giving a result of 14.

b 3 is subtracted from q and the result is tripled, giving a final result of 30.

c A number, x, is doubled and then 3 is added. This number is doubled again to get a result of 46.

d 4 is added to y and this is doubled. Then the original number, y, is subtracted, giving a result of 17.

REASONING | 11 | 11, 12 | 12, 13(½)

11 For each of the following equations, explain why there are no solutions by first simplifying the LHS.

a $2(x + 5) - 2x = 7$

b $3(2x + 1) + 6(2 - x) = 4$

c $4(2x + 1) - 10x + 2(x + 1) = 12$

12 Consider the equation $2(3x + 4) - 6x + 1 = 9$.

a Show that this equation is true if $x = 0$.

b Show that this equation is true if $x = 3$.

c Explain why this equation is always true.

d Give an example of another equation involving brackets that is always true, where one side contains a variable but the other side is just a number.

13 For equations like $4(3x + 2) = 44$, you have been expanding the brackets first. Since $4(3x + 2) = 44$ is the same as $4 \times (3x + 2) = 44$, you can just start by dividing both sides by 4. Without expanding brackets, solve the equations in Question **6** by dividing first.

ENRICHMENT | Expanding multiple brackets | — | — | 14

14 Solve each of the following equations by expanding all sets of brackets.

a $6(2j - 4) + 4(4j - 3) = 20$

b $3(4a + 5) + 5(1 + 3a) = 47$

c $2(5a + 3) + 3(2a + 3) = 63$

d $222 = 3(4a - 3) + 5(3a + 3)$

e $77 = 2(3c - 5) + 3(4c + 5)$

f $240 = 4(3d + 3) + 6(3d - 2)$

g $2(x + 3) + 4(x + 5) = 32$

h $4(x + 5) + 4(x - 5) = 24$

i $2(3x + 4) + 5(6x + 7) + 8(9x + 10) = 123$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G Formulas

Interactive

Often, two or more pronumerals (or variables) represent related quantities. For example, the speed (s) at which a car travels and the time (t) it takes to arrive at its destination are related variable quantities. A formula is an equation that contains two or more pronumerals and shows how they are related.

Widgets

HOTsheets

Walkthroughs

Let's start: Fahrenheit and Celsius

In Australia, we measure temperature in degrees Celsius, whereas in the USA it is measured in degrees Fahrenheit. A formula to convert between them is $F = \frac{9C}{5} + 32$.



- At what temperature in degrees Fahrenheit does water freeze?
- At what temperature in degrees Fahrenheit does water boil?
- What temperature is 100° Fahrenheit in Celsius? Do you know what is significant about this temperature?

Key ideas

- The **subject** of an equation is a pronumeral that occurs by itself on the left-hand side. For example, T is the subject of $T = 4x + 1$.
- A **formula** or **rule** is an equation that contains two or more pronumerals (or variables), one of which is the subject of the equation.
- To use a formula, first substitute all the known values into the equation and then solve it to find the final value.

Example 14 Applying a formula

Consider the rule $k = 3b + 2$. Find the value of:

a k if $b = 5$ **b** k if $b = 10$ **c** b if $k = 23$

SOLUTION	EXPLANATION
a $k = 3 \times 5 + 2$ $= 17$	Substitute $b = 5$ into the equation.
b $k = 3 \times 10 + 2$ $= 32$	Substitute $b = 10$ into the equation.
c $23 = 3b + 2$ -2 -2 $21 = 3b$ $\div 3$ $\div 3$ $7 = b$ Therefore, $b = 7$.	Substitute $k = 23$ into the equation. Now solve the equation to find the value of b.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 15 Applying a formula involving three pronumerals

Consider the rule $Q = w(4 + t)$. Find the value of:

a Q if $w = 10$ and $t = 3$ **b** t if $Q = 42$ and $w = 6$

SOLUTION	EXPLANATION
a $Q = 10(4 + 3)$ $= 10 \times 7$ $= 70$	Substitute $w = 10$ and $t = 3$ to evaluate.
b $42 = 6(4 + t)$ $42 = 24 + 6t$ -24 -24 $18 = 6t$ $\div 6$ $\div 6$ $3 = t$ Therefore $t = 3$.	Substitute $Q = 42$ and $w = 6$. Expand the brackets and then solve the equation.

Exercise 10G

1, 2 | 2 | —

UNDERSTANDING

1 State whether each of the following equations is a rule (R) or not a rule (N).

a $2x + 5 = 10$ **b** $y = 3x + 5$ **c** $F = ma$

d $5 - q = 3$ **e** $w = 12 - v$ **f** $P = I + k - 3$

2 Substitute:

a $x = 3$ into the expression $5x$ **b** $x = 7$ into the expression $4(x + 2)$

c $y = 3$ into the expression $20 - 4y$ **d** $y = 10$ into the expression $\frac{y + 4}{7}$

3–5 | 3–6 | 3, 5, 6

FLUENCY

Example 14

3 Consider the rule $h = 2m + 1$. Find:

a h if $m = 3$

b h if $m = 4$

c m if $h = 17$. Set up an equation and solve it algebraically.

d Find m if $h = 21$. Set up an equation and solve it algebraically.

4 Consider the formula $y = 5 + 3x$. Find:

a y if $x = 6$ **b** x if $y = 17$ **c** x if $y = 26$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G

Example 15

FLUENCY

5 Consider the rule $A = q + t$. Find:

a A if $q = 3$ and $t = 4$ **b** q if $A = 5$ and $t = 1$ **c** t if $A = 3$ and $q = 3$


6 Consider the formula $G = 7x + 2y$. Find:

a G if $x = 3$ and $y = 3$ **b** x if $y = 2$ and $G = 11$ **c** y if $G = 31$ and $x = 3$

7 | 7, 8 | 8, 9

PROBLEM-SOLVING

7 The formula for the area of a rectangle is $A = w \times h$, where w is the rectangle's width and h is the rectangle's height.



a Set up and solve an equation to find the width of a rectangle with $A = 20$ and $h = 4$.

b A rectangle is drawn for which $A = 25$ and $w = 5$.

i Set up and solve an equation to find h. **ii** What type of rectangle is this?

8 The perimeter for a rectangle is given by $P = 2(w + h)$. Find the:

a perimeter when $w = 3$ and $h = 5$ **b** value of h when $P = 10$ and $w = 2$

c area of a rectangle if its perimeter is 20 and width is 4

9 To convert between temperatures in Celsius and Fahrenheit the rule is $F = \frac{9C}{5} + 32$.

a Find F if $C = 20$. **b** Find the value of C if $F = 50$.


c Find the temperature in Celsius if it is 53.6° Fahrenheit.

d Marieko claims that the temperature in her city varies between 68° Fahrenheit and 95° Fahrenheit. What is the difference, in Celsius, between these two temperatures?

10 | 10 | 10, 11

REASONING

10 Rearranging a formula involves finding an equivalent equation that has a different variable on one side by itself. For example, the formula $S = 6g + b$ can be rearranged to make g by itself: Now we have a formula that can be used to find g once S and b are known.



a Rearrange $S = 5d + 3b$ to make a rule where d is by itself.

b Rearrange the formula $F = \frac{9C}{5} + 32$ to make C by itself.

c Rearrange the formula $Q = 3(x + 12) + x$ to make x by itself. (Hint: You will need to expand the brackets first.)

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 A taxi company charges different amounts of money based on how far the taxi travels and how long the passenger is in the car. Although the company has not revealed the formula it uses, some sample costs are shown below.

Distance (D) in km	Time (t) in minutes	Cost (C) in dollars
10	20	30
20	30	50

a Show that the rule $C = D + t$ is consistent with the values above.

b Show that the rule $C = 3D$ is not consistent with the values above.

c Show that the rule $C = 2D + 10$ is consistent with the values above.

d Try to find at least two other formulas that the taxi company could be using, based on the values shown.

AFL equations — — 12

12 In Australian Rules Football (AFL), the score, S, is given by $S = 6g + b$, where g is the number of goals scored and b is the number of 'behinds' (i.e. near misses).

a Which team is winning if the Abbotsford Apes have scored 11 goals ($g = 11$) and 9 behinds ($b = 9$), whereas the Brunswick Baboons have scored 12 goals and 2 behinds?

b The Camberwell Chimpanzees have scored 7 behinds and their current score is $S = 55$. Solve an equation algebraically to find how many goals the team has scored.

c In some AFL competitions, a team can score a 'supergoal', which is worth 9 points. If q is the number of supergoals that a team kicks, write a new formula for the team's score.

d For some rare combinations of goals and behinds, the score equals the product of g and b. For example, 4 goals and 8 behinds gives a score of $6 \times 4 + 8 = 32$, and $4 \times 8 = 32$. Find all the other values of g and b that make the equation $6g + b = gb$ true.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

10H Applications

Our methods for solving equations can be applied to many situations in which equations occur.

Let's start: Stationery shopping

Sylvia bought 10 pencils and 2 erasers for $20.40. Edward bought 5 pencils and 3 erasers for $12.60.



- Use the information above to work out how much Karl will pay for 6 pencils and 5 erasers.
- Describe how you got your answer.
- Is there more than one possible solution?

Key ideas

- To solve a problem, follow these steps.
  - Define pronumerals to stand for unknown numbers. (e.g. let e = cost of an eraser in dollars.)
  - Write an equation to describe the problem.
  - Solve the equation algebraically if possible, or by inspection.
  - Ensure you answer the original question, and include the correct units (e.g. dollars, years, cm).

Example 16 Solving a problem using equations

The sum of Kate's current age and her age next year is 19. How old is Kate?

SOLUTION	EXPLANATION
Let k = Kate's current age in years.	Define a pronumeral to stand for the unknown number.
$k + (k + 1) = 19$	Write an equation to describe the situation. Note that $k + 1$ is Kate's age next year.
$2k + 1 = 19$ -1 -1 $2k = 18$ $\div 2$ $\div 2$ $k = 9$	Simplify the LHS and then solve the equation algebraically.
Kate is currently 9 years old.	Answer the original question.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 10H

1, 2 | 1, 2 | —

UNDERSTANDING

1 For each of the following problems, choose the best pronumeral definition.

a Problem: Monique's age next year is 12. How old is she now?

A Let m = Monique's current age.
B Let m = Monique.
C Let m = 12.
D Let m = Monique's age next year.
E Let m = this year.

b Problem: Callan has 15 boxes, which weigh a total of 300 kg. How much does each box weigh?

A Let w = 15.
B Let w = 300.
C Let w = the weight of one box.
D Let w = the number of boxes.
E Let w = the total weight.

c Problem: Jared's family has a farm with cows and sheep. The total number of animals is 200 and there are 71 cows. How many sheep are there?

A Let x = the size of a sheep.
B Let x = the total number of animals.
C Let x = the number of sheep.
D Let x = the number of cows.
E Let x = Jared's age.

2 Solve the following equations algebraically.

a $5x = 30$ **b** $7a + 2 = 16$ **c** $2k - 3 = 15$

3–5 | 3–6 | 3–6

FLUENCY

Example 16

3 Launz buys a car and a trailer for a combined cost of $40 000. The trailer costs $2000.



a Define a pronumeral for the car's cost.

b Write an equation to describe the problem.
c Solve the equation algebraically.
d Hence, state the cost of the car.

4 Meghan buys 12 pens for a total cost of $15.60.

a Define a pronumeral for the cost of one pen.
b Write an equation to describe the problem.
c Solve the equation algebraically.
d Hence, state the cost of one pen.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10H


FLUENCY

5 Jonas is paid $17 per hour and gets paid a bonus of $65 each week. One particular week he earned $643.

- **a** Define a pronumeral for the number of hours Jonas worked.
- **b** Write an equation to describe the problem.
- **c** Solve the equation algebraically.
- **d** How many hours did Jonas work in that week?

6 This rectangular paddock has an area of 720 m^2.

- **a** Write an equation to describe the problem, using w for the paddock's width.
- **b** Solve the equation algebraically.
- **c** How wide is the paddock?
- **d** What is the paddock's perimeter?




PROBLEM-SOLVING

7, 8 | 8–10 | 11–14

7 A number is doubled, then 3 is added and the result is doubled again. This gives a final result of 34. Set up and solve an equation to find the original number, showing all the steps clearly.

8 The perimeter of the shape shown is 30. Find the value of x.



9 Alexa watches some television on Monday, then twice as many hours on Tuesday, then twice as many hours again on Wednesday. If she watches a total of $10\frac{1}{2}$ hours from Monday to Wednesday, how much television did Alexa watch on Monday?




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10H


PROBLEM-SOLVING

10 Marcus and Sara's combined age is 30. Given that Sara is 2 years older than Marcus, write an equation and find Marcus' age.

11 An isosceles triangle is shown below. Write an equation and solve it to find $x°$, the unknown angle. (Remember: The sum of angles in a triangle is 180°.)




12 Find the value of y in the triangle shown here, by first writing an equation.



13 A rectangle has width w and height h. The perimeter and area of the rectangle are equal. Write an equation and solve it by inspection to find some possible values for w and h. (Note: There are many solutions to this equation. Try to find a few.)

14 Find the values of x and y in the rectangle shown.




15 15 15, 16

REASONING

15 If photocopying costs 35 cents a page and p is the number of pages photocopied, which of the following equations have possible solutions? Justify your answers. (Note: Fraction answers are not possible because you must still pay 35 cents even if you photocopy only part of a page.)

a $0.35p = 4.20$ **b** $0.35p = 2.90$ **c** $0.35p = 2.80$

16 Assume that an isosceles triangle is drawn so that each of its three angles is a whole number of degrees. Prove that the angle a must be an even number of degrees.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10H Strange triangles — — 17

ENRICHMENT

17 Recall that the sum of angles in a triangle is 180°.


a David proposes the following triangle, which is not drawn to scale.



i Find the value of x.

ii Explain what makes this triangle impossible.


b Helena proposes the following triangle, which is also not drawn to scale.



i Explain why the information in the diagram is not enough to find x.

ii What are the possible values that x could take?

c Design a geometric puzzle, like the one in part **a**, for which the solution is impossible.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Theme parks



There are thousands of theme parks all over the world which offer a vast array of rides that are built to thrill. By surfing the internet, you can discover the longest, tallest, fastest and scariest rides. Although prices are kept competitive, theme parks need to make a profit so that they can maintain safety standards and continue to build new and more exciting rides.

Thrill World and Extreme Park are two theme parks. Both charge different prices for entry and for each ride. Their prices are:

- Thrill World: $20 entry and $5 per ride
- Extreme Park: $60 entry and $3 per ride

a Copy and complete the table below for each theme park. The total cost for the day includes the entry cost and cost of the rides.

Number of rides (n)	1	2	3	4	5	6	7	8	. . .	20	21	22	23	24	25
Thrill World total cost $\$T$	$25								. . .						
Extreme Park total cost $\$E$	$63								. . .						

b Write a formula for:

i T, the total cost, in dollars, for n rides at Thrill World

ii E, the total cost, in dollars, for n rides at Extreme Park

c For each of these thrill seekers, use an equation to calculate how many rides they went on.

i Amanda, who spent $105 at Thrill World

ii George, who spent $117 at Extreme Park

d Refer to your completed table to determine the number of rides that will make the total cost for the day the same at each theme park.

e A third theme park, Fun World, decides to charge no entry fee but to charge $10 per ride. Find the minimum number of rides that you could go on at Fun World before it becomes cheaper at:

i Thrill World


ii Extreme Park

f Fun World changes its pricing policy after it decides that it will be unable to compete by pricing its rides so high, so it decides to charge an entry fee and then make all rides free.

Investigate how much Fun World should charge to attract customers while still making profits that are similar to those of Thrill World and Extreme Park. Provide some mathematical calculations to support your conclusions.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Problems and challenges




1 Find the unknown number in the following problems.

- **a** A number is added to half of itself and the result is 39.
- **b** A number is doubled, then tripled, then quadrupled. The result is 696.
- **c** One-quarter of a number is subtracted from 100 and the result is 8.
- **d** Half of a number is added to 47, and the result is the same as the original number doubled.
- **e** A number is increased by 4, the result is doubled and then 4 is added again to give an answer of 84.


2 A triangle has sides $2x + 7$, $3x + 4$ and $4(x - 4)$ measured in cm. If the perimeter of the triangle is 220 cm, find the difference between the longest and shortest sides.



3 For this rectangle, find the values of x and y and determine the perimeter. The sides are measured in cm.



4 A rectangular property has a perimeter of 378 m. It is divided up into five identical rectangular house blocks as shown in this diagram. Determine the area of each house block.




5 Find the values of a, b and c, given the clues:
$5(a + 2) + 3 = 38$ and $2(b + 6) - 2 = 14$ and $3a + 2b + c = 31$


ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 Find the values of a and b for each of these geometric figures.


a




b



c



d




7 James's nanna keeps goats and chickens in her backyard. She says to James, 'There are 41 animals in this yard'. James says to his nanna, 'There are 134 animal legs in this yard'.
How many goats and how many chickens are in the paddock?



8 Five consecutive numbers have the middle number $3x - 1$. If the sum of these five numbers is 670 find the value of x and list the five numbers.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Chapter summary



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

10A **1** If $x = 3$, which one of the following equations is true?

A $4x = 21$ **B** $2x + 4 = 12$ **C** $9 - x = 6$
D $2 = x + 1$ **E** $x - 3 = 4$

10A **2** When 11 is added to the product of 3 and x, the result is 53. This can be written as:

A $3x + 11 = 53$ **B** $3(x + 11) = 53$ **C** $\frac{x}{3} + 11 = 53$
D $\frac{x + 11}{3} = 53$ **E** $3x - 11 = 53$

10B **3** Which of the following values of x make the equation $2(x + 4) = 3x$ true?

A 2 **B** 4 **C** 6
D 8 **E** 10

10C **4** The equivalent equation that results from subtracting 3 from both sides of $12x - 3 = 27$ is:

A $12x = 24$ **B** $12x - 6 = 24$ **C** $12x - 6 = 30$
D $9x - 3 = 24$ **E** $12x = 30$

10D **5** To solve $3a + 5 = 17$, the first step to apply to both sides is to:

A add 5 **B** divide by 3 **C** subtract 17
D divide by 5 **E** subtract 5

10D **6** The solution to $2t - 4 = 6$ is:

A $t = 1$ **B** $t = 3$ **C** $t = 5$
D $t = 7$ **E** $t = 9$

10E Ext **7** The solution of $\frac{2x}{7} = 10$ is:

A $x = 35$ **B** $x = 70$ **C** $x = 20$
D $x = 30$ **E** $x = 5$

10E Ext **8** The solution to the equation $10 = \frac{3p + 5}{2}$ is:

A $p = 5$ **B** $p = 20$ **C** $p = 15$
D $p = 7$ **E** $p = 1$

10F Ext **9** The solution of $3(u + 1) = 15$ is:

A $u = 5$ **B** $u = 4$ **C** $u = 11$
D $u = 6$ **E** $u = 3$

10G **10** A formula relating A, p and t is $A = 3p - t$. If $A = 24$ and $t = 6$, then p equals:

A 18 **B** 4 **C** 30
D 2 **E** 10

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Short-answer questions

10A **1** Classify each of the following equations as true or false.

a $4 + 2 = 10 - 2$ **b** $2(3 + 5) = 4(1 + 3)$ **c** $5w + 1 = 11$, if $w = 2$

d $2x + 5 = 12$, if $x = 4$ **e** $y = 3y - 2$, if $y = 1$ **f** $4 = z + 2$, if $z = 3$

10A **2** Write an equation for each of the following situations. You do not need to solve the equations.

a The sum of 2 and u is 22. **b** The product of k and 5 is 41.

c When z is tripled the result is 36. **d** The sum of a and b is 15.

10B **3** Solve the following equations by inspection.

a $x + 1 = 4$ **b** $x + 8 = 14$ **c** $9 + y = 10$

d $y - 7 = 2$ **e** $5a = 10$ **f** $\frac{a}{5} = 2$

10C **4** For each equation, find the result of applying the given operation to both sides and then simplify.

a $2x + 5 = 13$ $[-5]$ **b** $7a + 4 = 32$ $[-4]$

c $12 = 3r - 3$ $[+3]$ **d** $15 = 8p - 1$ $[+1]$

10D **5** Solve each of the following equations algebraically.

a $5x = 15$ **b** $r + 25 = 70$ **c** $12p + 17 = 125$ **d** $12 = 4b - 12$

e $5 = 2x - 13$ **f** $13 = 2r + 5$ **g** $10 = 4q + 2$ **h** $8u + 2 = 66$

10E Ext **6** Solve the following equations algebraically.

a $\frac{3u}{4} = 6$ **b** $\frac{8p}{3} = 8$ **c** $3 = \frac{2x + 1}{3}$

d $\frac{5y}{2} + 10 = 30$ **e** $4 = \frac{2y + 20}{7}$ **f** $\frac{4x}{3} + 4 = 24$

10F Ext **7** Expand the brackets in each of the following expressions.

a $2(3 + 2p)$ **b** $4(3x + 12)$ **c** $7(a + 5)$ **d** $9(2x + 1)$

10F Ext **8** Solve each of these equations by expanding the brackets first.

a $2(x - 3) = 10$ **b** $27 = 3(x + 1)$ **c** $48 = 8(x - 1)$

d $60 = 3y + 2(y + 5)$ **e** $7(2z + 1) + 3 = 80$ **f** $2(5 + 3q) + 4q = 40$

10F Ext **9** Consider the equation $4(x + 3) + 7x - 9 = 10$.

a Is $x = 2$ a solution?

b Show that the solution to this equation is *not* a whole number.

10F Ext **10** **a** Does $3(2x + 2) - 6x + 4 = 15$ have a solution? Justify your answer.

b State whether the following are solutions to $5(x + 3) - 3(x + 2) = 2x + 9$.

i $x = 2$ **ii** $x = 3$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10G **11** The formula for the area of a trapezium is $A = \frac{1}{2}h(a + b)$, where h is the height of the trapezium,and a and b represent the parallel sides.

- **a** Set up and solve an equation to find the area of a trapezium with height 20 cm and parallel sides of 15 cm and 30 cm.
- **b** Find the height of a trapezium whose area is 55 cm^2 and has parallel sides 6 cm and 5 cm, respectively.

10G **12** Consider the rule $F = 3a + 2b$. Find:


- **a** F if $a = 10$ and $b = 3$
- **b** b if $F = 27$ and $a = 5$
- **c** a if $F = 25$ and $b = 8$

10H **13** For each of the following problems, write an equation and solve it to find the unknown value.


- **a** A number is added to three times itself and the result is 20. What is the number?
- **b** The product of 5 and a number is 30. What is the number?
- **c** Juanita's mother is twice as old as Juanita. The sum of their ages is 60. How old is Juanita?
- **d** A rectangle has a width of 21 cm and a perimeter of 54 cm. What is its length?

10H **14** Find the value of y for each of these figures.

a



b



Extended-response questions

1 Udhav's mobile phone plan charges a 15-cents connection fee and then 2 cents per second for every call.

- **a** How much does a 30-second call cost?
- **b** Write a rule for the total cost, C, in cents, for a call that lasts t seconds.
- **c** Use your rule to find the cost of call that lasts 80 seconds.
- **d** If a call cost 39 cents, how long did it last? Solve an equation to find t.
- **e** If a call cost $1.77, how long did it last?
- **f** On a particular day, Udhav makes two calls – the second one lasting twice as long as the first, with a total cost of $3.30. What was the total amount of time he spent on the phone?

2 Gemma is paid $\$x$ per hour from Monday to Friday, but earns an extra $2 per hour during weekends. During a particular week, she worked 30 hours during the week and then 10 hours on the weekend.

- **a** If $x = 12$, calculate the total wages Gemma was paid that week.
- **b** Explain why her weekly wage is given by the rule $W = 30x + 10(x + 2)$.
- **c** Use the rule to find Gemma's weekly wage if $x = 16$.
- **d** If Gemma earns $620 in one week, find the value of x.
- **e** If Gemma earns $860 in one week, how much did she earn from Monday to Friday?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Chapter 11

Measurement

What you will learn

11A Measurement systems (Extending)
11B Using and converting metric lengths (Consolidating)
11C Perimeter (Consolidating)
11D Areas and rectangles
11E Area of a triangle
11F Area of a parallelogram
11G Area of composite shapes (Extending)
11H Volume of rectangular prisms
11I Capacity (Consolidating)
11J Mass and temperature (Consolidating)

Australian curriculum

MEASUREMENT AND GEOMETRY

Using units of measurement

Establish the formulas for areas of rectangles, triangles and parallelograms and use these in problem solving (ACMMG159)

Calculate volumes of rectangular prisms (ACMMG160)

Shape

Draw different views of prisms and solids formed from combinations of prisms (ACMMG161)

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2

© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.



Online resources

- Chapter pre-test
- Videos of all worked examples
- Interactive widgets
- Interactive walkthroughs
- Downloadable HOTsheets
- Access to HOTmaths Australian Curriculum courses

Measurement everywhere

Imagine trying to describe facts about the world around us without using any form of measurement. We use units of length to describe distance and degrees Celsius (°C) to describe temperature. Other units are used for area, volume, time, capacity and mass.

Here are some examples of facts that use different units of measurement.

- The Eiffel Tower in France is painted with 50 tonnes of paint every 7 years.
- The Great Wall of China is more than 6000 km long.
- The Great Pyramid of Giza was built around 2500 BCE and includes about 2 300 000 blocks of stone, each weighing about 2500 kg.
- The world's smallest country is Vatican City in Rome, with an area of 0.44 km^2.
- The maximum temperature during the day on Mars is about 20°C.
- The distance between the orbits of Mars and the Earth around the Sun is about 78 000 000 km.
- The volume of water in Sydney Harbour is about 500 gigalitres or five hundred thousand million litres or 0.5 km^3.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11A Measurement systems EXTENDING










From about 3000 BCE a unit of measure called the *cubit* was used in ancient Egypt to measure lengths. It is known that the cubit, which is the length of an arm from the elbow to the end of the middle finger, was used to measure the depth of the Nile River in flood. Other unit measures based on the human body were also used. Some include the *digit* (width of a finger), *palm* (width of four fingers) and *span* (distance from the tip of the thumb to the tip of the little finger in an outstretched hand).



Egyptians used their arms and hands to measure different units.

Because each individual's arm length and finger width is different, there was a need to develop a standard unit of length. The Egyptians defined a *standard royal cubit* (about 524 mm), and this was represented as a stone rod. From this cubit the following divisions were made: 28 digits in a cubit, 4 digits in a palm and 14 digits in a span.

Many of these units of measurement were adapted and developed by the Babylonians, Greeks, Romans, English and French over many centuries. The English imperial system, which was adapted from the Roman and Greek systems, is commonly used in the United Kingdom and the United States today, and was used in Australia until the 1970s. Many people today still prefer to describe lengths and other measures using Imperial units, such as the *inch* and *mile*.

The metric system was developed in France in the 1790s and is the universally accepted system today. The word *metric* comes from the Greek word *metron*, meaning 'measure'. It is a decimal system where length measures are based on the unit called the *metre*. The definition of the metre has changed over time. Originally it was proposed to be the length of a pendulum that beats at a rate of one per second. It was later defined as 1/10 000 000 of the distance from the North Pole to the equator on a line on the Earth's surface passing through Paris. In 1960, a metre became 1 650 763.73 wave lengths of the spectrum of the krypton-86 atom in a vacuum. In 1983, the metre was defined as the distance that light travels in 1/299 792 458 seconds inside a vacuum.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Let's start: Egyptian trader

Imagine you are in ancient Egypt and you are trading goods at a market. You use the Egyptian units: *digit* (width of a finger), *palm* (width of four fingers) and *span* (distance from the top of the thumb to the tip of the little finger in an outstretched hand).

- Use a ruler to find the metric equivalent of your *digit*, *palm* and *span*.
- You purchase a wad of papyrus paper that is 1 digit thick. Which students in the class would get the least paper if they used their own finger width?
- You purchase a bowl of grain 1 span deep. Which student in the class gets the most grain?
- You purchase 5 cubits of cloth. Which student gets the most cloth?

Key ideas

- Ancient measurement systems that developed from about 3000 BCE include the Egyptian, Babylonian, Greek and Roman systems. The **metric system** is the commonly used system today.



- **Roman system**
  - 1 foot = 12 inches = 16 digits = 4 palms
  - 1 cubit = 6 palms
  - 1 pace (double step) = 5 feet
  - 1 mile = 1000 paces
- **imperial system**
  - 1 foot = 12 inches (1 inch is about 2.5 cm)
  - 1 yard = 3 feet (1 yard is about 91.5 cm)
  - 1 rod = 16.5 feet
  - 1 chain = 22 yards
  - 1 furlong = 40 rods
  - 1 mile = 8 furlongs = 1760 yards (1 mile is about 1.6 km)
- **metric system**
  - 1 centimetre (cm) = 10 millimetres (mm)
  - 1 metre (m) = 100 centimetres (cm)
  - 1 kilometre (km) = 1000 metres (m)

Example 1 Using measurement systems

a How many feet are there in 1 mile, using the Roman measuring system?

b How many inches are there in 3 yards, using the imperial system?

SOLUTION	EXPLANATION
a 1 mile = 1000 paces = 5000 feet	There are 1000 paces in a Roman mile and 5 feet in a pace.
b 3 yards = 9 feet = 108 inches	There are 3 feet in an imperial yard and 12 inches in a foot.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 2 Choosing metric lengths

Which metric unit would be the most appropriate for measuring these lengths?

a width of a large room

b thickness of glass in a window

SOLUTION	EXPLANATION
a metres (m)	Using mm or cm would give a very large number, and using km would give a number that is very small.
b millimetres (mm)	The thickness of glass is likely to be around 5 mm.

Exercise 11A

1–4 | 4 | —

UNDERSTANDING

1 Complete these number sentences.

a Roman system

i 1 _____ = 12 inches = 16 _____ = _____ palms

ii 1 _____ = 1000 paces

b imperial system

i 1 foot = 12 _____

ii 3 _____ = 1 yard

iii _____ = 1760 yards

c metric system

i 1 m = _____ cm

ii 1 cm = _____ mm

iii _____ km = 1000 m

2 List the units of length (e.g. cubit), from smallest to largest, commonly used in the Roman system.

3 List the units of length (e.g. inch), from smallest to largest, commonly used in the imperial system.

4 List the units of length (e.g. centimetre), from smallest to largest, commonly used in the metric system.

5–8 | 5–9 | 5–9(½)

FLUENCY

Example 1

5 Use the Roman system to state how many:

a feet are in 1 pace

b feet are in 1 mile

c palms are in 1 foot

d palms are in 1 pace

e digits are in 1 foot

f digits are in 1 pace

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

6 Use the imperial system to state how many:

a inches are in 1 foot
b feet are in 1 yard
c inches are in 1 yard
d yards are in 1 mile
e yards are in 1 chain
f rods are in 1 furlong

7 Use the metric system to state how many:

a millimetres are in 1 centimetre
b centimetres are in 1 metre
c metres are in 1 kilometre
d millimetres are in 1 metre
e centimetres are in 1 kilometre
f millimetres are in 1 kilometre

Example 2

8 Which metric unit would be the most appropriate for measuring the following?

a the distance between two towns
b width of a small drill bit
c height of a flag pole
d length of a garden hose
e width of a small desk
f distance across a city



A drill bit

9 Choose which metric unit would be the most suitable for measuring the real-life length indicated in each of these photos.

a




b



c



d




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11A

FLUENCY

e



f



10, 11 | 11–13 | 12–14

PROBLEM-SOLVING

10 A Roman offers you either 12 palms or 1 pace of cloth. Which option gives you the most cloth?

11 The Roman army marches 5 Roman miles to the next post. How many paces is the journey?

12 An English cricketer runs 1 chain for each run made. How many yards will he run if he makes 20 runs?

13 Here is the length of 1 mm and 1 cm. Use these diagrams as a guide to estimate the length of these lines.

_ 1 mm

_____ 1 cm

a _

b ___


c _____

d _____


e _____

14 Estimate the length of each line or curve, in centimetres.


a



b



c



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

15 | 15, 16 | 16, 17 | 11A

REASONING

15 Complete these tables.

a metric

	mm	cm	m	km
mm	1	$\frac{1}{10}$		
cm	10	1		
m	1000		1	
km				1

b imperial

	Inch	Feet	Yard	Mile
Inch	1		$\frac{1}{36}$	
Feet	12	1		
Yard			1	
Mile			1760	1

c Roman

	Digit	Palm	Feet	Pace	Mile
Digit	1		$\frac{1}{16}$		
Palm	4	1			
Feet			1		
Pace				1	
Mile					1

16 Why would it be more difficult to include the imperial units of chains and rods in the table in Question **15b**?

17 Generally speaking, why is the metric system easier to use than either the imperial or Roman systems?

ENRICHMENT

Walking paces — | — | 18

18 The Roman pace involves 2 steps, and 1000 of these paces make up a Roman mile. These units would have been used to estimate distances for the Roman armies that spread throughout much of the world during that time.

a Estimate how many paces (i.e. double steps) you would take in 1 kilometre (1000).

b Calculate how many paces you would take to cover 1 kilometre.

c If each pace takes 1 second, find how long it would take to walk from Sydney to Melbourne (about 900 km) non-stop. Convert your answer to number of hours.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11B Using and converting metric lengths

CONSOLIDATING

Interactive

Widgets

HOTsheets

Walkthroughs

To avoid the use of very large and very small numbers, an appropriate unit is often chosen to measure a length or distance. It may also be necessary to convert units of length. For example, 150 pieces of timber, each measured in centimetres, may need to be communicated as a total length using metres. Another example might be that 5 millimetres is to be cut from a length of timber 1.4 metres long because it is too wide to fit a door opening that is 139.5 centimetres wide.



A carpenter may need to measure lengths of wood in metres, centimetres and millimetres.


Let's start: How good is your estimate?

In less than 3 seconds, guess the length of your desk, in centimetres.


- Now use a ruler to find the actual length in centimetres.
- Convert your answer to millimetres and metres.
- If you lined up all the class desks end to end, how many desks would be needed to reach 1 kilometre? Explain how you got your answer.

Key ideas

- The **metre** (m) is the basic metric unit of length.
  - 1 km = 1000 m
  - 1 m = 100 cm
  - 1 cm = 10 mm



- **Conversion**
  - When converting to a smaller unit, multiply by a power of 10 (i.e. 10, 100, 1000). A smaller unit means you need more of them, so it makes sense that you multiply.
  - When converting to a larger unit, divide by a power of 10 (i.e. 10, 100, 1000). A larger unit means you need less of them, so it makes sense that you divide.
- When reading scales, be sure about what units are showing on the scale. This scale shows 36 mm.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 3 Converting metric units of length

Convert to the units given in brackets.

a 3 m (cm)


b 25 600 cm (km)

SOLUTION	EXPLANATION
a $3\text{ m} = 3 \times 100\text{ cm}$ $= 300\text{ cm}$	1 m = 100 cm Multiply since you are converting to a smaller unit.
b $25\,600\text{ cm} = 25\,600 \div 100\,000$ $= 0.256\text{ km}$	There are 100 cm in 1 m and 1000 m in 1 km and $100 \times 1000 = 100\,000$.


Example 4 Reading length scales

Read the scales on these rulers to measure the marked length.

a



b



SOLUTION	EXPLANATION
a 25 mm	2.5 cm is also accurate.
b 70 cm	Each division is $\frac{1}{10}$ of a metre, which is 10 cm.

Exercise 11B

1–3 | 3 | —

UNDERSTANDING

1 Write down the missing number or word in these sentences.

a When converting from metres to centimetres, you multiply by _____.

b When converting from metres to kilometres, you divide by _____.

c When converting from centimetres to metres, you _____ by 100.

d When converting from kilometres to metres, you _____ by 1000.

e When converting to a smaller unit, you _____.

f When converting to a larger unit, you _____.

2 Calculate each of the following.

a 100×10 **b** 10×100 **c** 100×1000 **d** $10 \times 100 \times 1000$

3 **a** When multiplying by a power of 10, in which direction does the decimal point move – left or right?

b When dividing by a power of 10, in which direction does the decimal point move – left or right?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

11B

4–7(½), 8 | 4–7(½), 8, 9 | 4–7(½), 8, 9

FLUENCY

Example 3a

4 Convert these measurements to the units shown in brackets.

a 5 cm (mm) **b** 2 m (cm) **c** 3.5 km (m) **d** 26.1 m (cm)
e 40 mm (cm) **f** 500 cm (m) **g** 4200 m (km) **h** 472 mm (cm)
i 6.84 m (cm) **j** 0.02 km (m) **k** 9261 mm (cm) **l** 4230 m (km)

5 Add these lengths together and give the result in the units shown in brackets.

a 2 cm and 5 mm (cm) **b** 8 cm and 2 mm (mm) **c** 2 m and 50 cm (m)
d 7 m and 30 cm (cm) **e** 6 km and 200 m (m) **f** 25 km and 732 m (km)

Example 3b


6 Convert to the units shown in the brackets.

a 3 m (mm) **b** 6 km (cm) **c** 2.4 m (mm)
d 0.04 km (cm) **e** 47 000 cm (km) **f** 913 000 mm (m)
g 216 000 mm (km) **h** 0.5 mm (m)


Example 4

7 These rulers show centimetres with millimetre divisions. Read the scale to measure the marked length.


a




b




c




d




e




f



g




h




8 Read the scale on these tape measures. Be careful with the units shown!

a



b



9 Use subtraction to find the difference between the measurements, and give your answer with the units shown in brackets.

a 9 km, 500 m (km) **b** 3.5 m, 40 cm (cm) **c** 0.2 m, 10 mm (cm)

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11B

PROBLEM-SOLVING

10–12 | 12–14 | 15–17

10 Arrange these measurements from smallest to largest.

a 38 cm, 540 mm, 0.5 m
b 0.02 km, 25 m, 160 cm, 2100 mm
c 0.003 km, 20 cm, 3.1 m, 142 mm
d 0.001 km, 0.1 m, 1000 cm, 10 mm

11 Joe widens a 1.2 m doorway by 50 mm. What is the new width of the doorway, in centimetres?

12 Three construction engineers individually have plans to build the world's next tallest tower. The Titan tower is to be 1.12 km tall, the Gigan tower is to be 109 500 cm tall and the Bigan tower is to be 1210 m tall. Which tower will be the tallest?

13 Steel chain costs $8.20 per metre. How much does it cost to buy chain of the following lengths?

a 1 km **b** 80 cm **c** 50 mm

14 A house is 25 metres from a cliff above the sea. The cliff is eroding at a rate of 40 mm per year. How many years will pass before the house starts to fall into the sea?

15 Mount Everest is moving with the Indo-Australian plate at a rate of about 10 cm per year. How many years will it take to move 5 km?


16 A ream of 500 sheets of paper is 4 cm thick. How thick is 1 sheet of paper, in millimetres?

17 A snail slithers 2 mm every 5 seconds. How long will it take to slither 1 m?

REASONING

18 | 18 | 18, 19

18 Copy this chart and fill in the missing information.



19 Many tradespeople measure and communicate with millimetres, even for long measurements like timber beams or pipes. Can you explain why this might be the case?

ENRICHMENT

Very small and large units — | — | 20

20 When 1 metre is divided into 1 million parts, each part is called a **micrometre** (μm). At the other end of the spectrum, a **light year** is used to describe large distances in space.

a State how many micrometres there are in:

i 1 m **ii** 1 cm
iii 1 mm **iv** 1 km

b A virus is 0.000 312 mm wide. How many micrometres is this?

c Research the length called the light year. Explain what it is and give examples of distances using light years, such as to the nearest star other than the Sun.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11C Perimeter CONSOLIDATING

Interactive
Widgets
HOTsheets
Walkthroughs


The distance around the outside of a two-dimensional shape is called the perimeter. The word *perimeter* comes from the Greek words *peri*, meaning 'around', and *metron*, meaning 'measure'. We associate perimeter with the outside of all sorts of regions and objects, like the length of fencing surrounding a block of land or the length of timber required to frame a picture.



This fence marks the perimeter (i.e. the distance around the outside) of a paddock.


Let's start: Is there enough information?

This diagram, which is not drawn to scale, includes only 90° angles and only one side length is given. Discuss if there is enough information given in the diagram to find the perimeter of the shape.
What additional information, if any, is required?



Key ideas

- **Perimeter**, sometimes denoted as P, is the distance around the outside of a two-dimensional shape.
- Sides with the same markings are of equal length.
- The unknown lengths of some sides can sometimes be determined by considering the given lengths of other sides.




$P = 1.6 + 1.6 + 2.8 + 4.1$
$= 10.1$ cm


Example 5 Finding the perimeter

Find the perimeter of each of these shapes.


a



b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a perimeter $= 2 \times 5 + 3$ $= 13$ cm	There are two equal lengths of 5 cm and one length of 3 cm.
b perimeter $= 2 \times 6 + 2 \times 8$ $= 28$ m	


Exercise 11C

1, 2 | 2 | —


UNDERSTANDING

1 These shapes are drawn on 1 cm grids. Give the perimeter of each.

a



b




2 Use a ruler to measure the lengths of the sides of these shapes, and then find the perimeter.


a




b



c



d



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11C


3, 4 | 3–5 | 3(½), 4, 5

FLUENCY


Example 5a

3 Find the perimeter of these shapes. (Diagrams are not drawn to scale.)


a




b




c




d



e




f




Example 5b

4 Find the perimeter of these shapes. All corner angles are 90°.


a



b



c



5 **a** A square has a side length of 2.1 cm. Find its perimeter.

b A rectangle has a length of 4.8 m and a width of 2.2 m. Find its perimeter.

c An equilateral triangle has all sides the same length. If each side is 15.5 mm, find its perimeter.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


6, 7 | 7–9 | 10–12

11C

PROBLEM-SOLVING

6 A grazing paddock is to be fenced on all sides. It is rectangular in shape, with a length of 242 m and a width of 186 m. If fencing costs $25 per metre, find the cost of fencing required.

7 A grass tennis court is lined with chalk. All the measurements are shown in the diagram and given in feet.




a Find the total number of feet of chalk required to do all the lines of the given tennis court.


b There are 0.305 metres in 1 foot. Convert your answer to part **a** to metres.

8 Only some side lengths are shown for these shapes. Find the perimeter.

a




b




9 Find the perimeter of each of these shapes. Give your answers in centimetres.


a



b




c



10 A square paddock has 100 equally-spaced posts that are 4 metres apart, including one in each corner. What is the perimeter of the paddock?


11 The perimeter of each shape is given. Find the missing length of each.

a




$P = 11$ cm

b



$P = 20$ m

c



$P = 38$ km

12 A rectangle has a perimeter of 16 cm. Using only whole numbers for the length and width, how many different rectangles can be drawn? Do not count rotations of the same rectangle.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


11C

13 | 13, 14 | 14, 15


REASONING

13 Write an algebraic rule (e.g. $P = 2a + b$) to describe the perimeter of each shape.


a




b




c




d



e




f




14 Write an algebraic rule for the perimeter of each given shape.

a



b



15 **a** A square has perimeter P. Write an expression for its side length.


b A rectangle has perimeter P and width a. Write an expression for its length.

Picture frames

— | — | 16

ENRICHMENT

16 The amount of timber used to frame a picture depends on the outside lengths of the overall frame. These are then cut at 45° to make the frame.



a A square painting of side length 30 cm is to be framed with timber of width 5 cm. Find the total length of timber required for the job.

b A rectangular photo with dimensions 50 cm by 30 cm is framed with timber of width 7 cm. Find the total length of timber required to complete the job.

c Kimberley uses 2 m of timber of width 5 cm to complete a square picture frame. What is the side length of the picture?

d A square piece of embroidery has side length a cm and is framed by timber of width 4 cm. Write an expression for the total amount of timber used in cm.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11D Areas and rectangles

Interactive

Widgets

HOTsheets

Walkthroughs

Area is measured in square units. It is often referred to as the amount of space contained inside a flat (i.e. plane) shape; however, curved three-dimensional (3D) solids also have surface areas. The amount of paint needed to paint a house and the amount of chemical needed to spray a paddock are examples of when area would be considered.



The greater the area of the paddock, the more chemicals the plane needs to carry.

Let's start: The 12 cm^2 rectangle

A rectangle has an area of 12 square centimetres (12 cm^2).

- Draw examples of rectangles that have this area, showing the length and width measurements.
- How many different rectangles with whole number dimensions are possible?
- How many different rectangles are possible if there is no restriction on the type of numbers allowed to be used for length and width?


Key ideas

■ The metric units of area include:


- 1 square millimetre (1 mm^2)




- 1 square centimetre (1 cm^2)
  1 cm^2 = 100 mm^2




- 1 square metre (1 m^2)
  1 m^2 = 10 000 cm^2



- 1 square kilometre (1 km^2)
  1 km^2 = 1 000 000 m^2




- 1 hectare (1 ha)
  1 ha = 10 000 m^2




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- The area of a rectangle is given by the number of rows multiplied by the number of columns. Written as a formula, this looks like: $A = l \times w$. This also works for numbers that are not whole.




- The area of a square is given by: $A = l \times l = l^2$



Example 6 Counting areas

Count the number of squares to find the area of the shape drawn on this centimetre grid.




SOLUTION

6 cm^2

EXPLANATION


There are 5 full squares and half of 2 squares in the triangle, giving 1 more.




Example 7 Areas of rectangles and squares

Find the area of this rectangle and square.

a



b



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

SOLUTION	EXPLANATION
a Area $= l \times w$ $= 10 \times 4$ $= 40 \text{ mm}^2$	The area of a rectangle is the product of the length and width.
b Area $= l^2$ $= 2.5^2$ $= 6.25 \text{ cm}^2$	The width is the same as the length, so $A = l \times l = l^2$. $(2.5)^2 = 2.5 \times 2.5$

Exercise 11D

1–4 | 4 | —


UNDERSTANDING

1 For this rectangle drawn on a 1 cm grid, find each of the following.



- **a** the number of single 1 cm squares
- **b** the length and the width
- **c** length × width


2 For this square drawn on a centimetre grid, find the following.




- **a** the number of single 1 cm squares
- **b** the length and the width
- **c** length × width

3 Count the number of squares to find the area of these shapes.


a



b



c



4 Which unit of area (mm^2, cm^2, m^2, ha or km^2) would you choose to measure these areas? Note that 1 km^2 is much larger than 1 ha.

- **a** area of an A4 piece of paper
- **b** area of a wall of a house
- **c** area of a small farm
- **d** area of a large desert
- **e** area of a large football oval
- **f** area of a nail head

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11D


5, 6(½), 7–10 | 5, 6(½), 7–11 | 5, 6(½), 7–11

FLUENCY


Example 6

5 Count the number of squares to find the area of these shapes on centimetre grids.


a




b




c




d



e




f




Example 7

6 Find the area of these rectangles and squares. Diagrams are not drawn to scale.


a



b



c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


11D

FLUENCY


d




e




f




g



h



i



7 Find the side length of a square with each of these areas. Use trial and error if you are unsure.

a 4 cm^2 **b** 25 m^2 **c** 144 km^2

8 There are 10 000 m^2 in one hectare (ha). Convert these measurements to hectares.

a 20 000 m^2 **b** 100 000 m^2 **c** 5000 m^2

9 A rectangular soccer field is to be laid with new grass. The field is 100 m long and 50 m wide. Find the area of grass to be laid.

10 Glass is to be cut for a square window of side length 50 cm. Find the area of glass required for the window.

11 Two hundred square tiles, each measuring 10 cm by 10 cm, are used to tile an open floor area. Find the area of flooring that is tiled.

12, 13 | 13, 14 | 13–15

PROBLEM-SOLVING

12 **a** A square has a perimeter of 20 cm. Find its area.

b A square has an area of 9 cm^2. Find its perimeter.

c A square's area and perimeter are the same number. How many units is the side length?

13 The carpet chosen for a room costs $70 per square metre. The room is rectangular and is 6 m long by 5 m wide. What is the cost of carpeting the room?

14 Troy wishes to paint a garden wall that is 11 m long and 3 m high. Two coats of paint are needed. The paint suitable to do the job can be purchased only in whole numbers of litres and covers an area of 15 m^2 per litre. How many litres of paint will Troy need to purchase?

15 A rectangular area of land measures 200 m by 400 m. Find its area in hectares.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


11D

16 | 16, 17 | 17–19


REASONING

16 **a** Find the missing length for each of these rectangles.

i




ii



b Explain the method that you used for finding the missing lengths of the rectangles above.


17 Explain why the area shaded here is exactly 2 cm^2.



18 A square has perimeter P cm.

a If $P = 44$ cm, find the area of the square.

b If P is unknown, write an expression for the area of the square, using P.




19 A square has all its side lengths doubled. How does this change the area? Investigate and justify your answer.

Area conversions

— | — | 20

ENRICHMENT

20 **a** Use this diagram or similar to help answer the following.




i How many mm^2 in 1 cm^2?

ii How many cm^2 in 1 m^2?

iii How many m^2 in 1 km^2?

b Complete the diagram below.



c Convert these units to the units shown in brackets.

i 2 cm^2 (mm^2)

ii 10 m^2 (cm^2)

iii 3.5 km^2 (m^2)

iv 300 mm^2 (cm^2)

v 21 600 cm^2 (m^2)

vi 4 200 000 m^2 (km^2)

vii 0.005 m^2 (mm^2)

viii 1 km^2 (ha)

ix 40 000 000 cm^2 (ha)



Guess the area of the paddock in the foreground in square millimetres.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11E Area of a triangle


Interactive

Widgets

HOTsheets

Walkthroughs

Put simply, a triangle can be considered to be half a rectangle, which is why the formula for the area of a triangle looks very much like the formula for the area of a rectangle but with the added factor of $\frac{1}{2}$. One of the sides of a triangle is called the base (b), and the height (h) is the distance between the base and the opposite vertex. This is illustrated using a line that is perpendicular (i.e. at 90°) to the base.




Any shape with all straight sides (i.e. polygons) can be divided up into a combination of rectangles (or squares) and triangles. This can help to find areas of such shapes.


Any area of floor with straight sides can be filled with square and triangular tiles.


Let's start: Half a rectangle

Look at these triangles. For each one, discuss why the area could be considered as half a rectangle. Give reasons for each case.


1



2




3



Key ideas

- One side of a triangle is called the **base**, b.
- The **perpendicular** distance from the base to the opposite **vertex** is called the height, h. In the third illustration below, the base needs to be extended to help show the height.



- The area of a triangle is given by the formula:

$$A = \frac{1}{2}bh = \frac{1}{2} \times \text{base} \times \text{height}$$


Note that $\frac{1}{2}bh$ is equivalent to $\frac{bh}{2}$.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 8 Finding areas of triangles

Find the area of each given triangle.

a



b



SOLUTION	EXPLANATION
a area $= \frac{1}{2}bh$ $= \frac{1}{2} \times 10 \times 9$ $= 45 \text{ cm}^2$	Use the formula and substitute the values for base length and height.
b area $= \frac{1}{2}bh$ $= \frac{1}{2} \times 6 \times 9$ $= 27 \text{ cm}^2$	The length measure of 9 m is marked at 90° to the side marked 6 m. So 6 m is the length of the base and 9 m is the perpendicular height.


Exercise 11E

1–3 | 3 | —


UNDERSTANDING

1 For each of these triangles, what length would be used as the base?


a




b



c



d




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11E


UNDERSTANDING

2 For each of these triangles, what length would be used as the height?


a




b



c



d



3 Find the value of A in $A = \frac{1}{2}bh$ if:

a $b = 5$ and $h = 4$ **b** $b = 7$ and $h = 16$ **c** $b = 2.5$ and $h = 10$


4(½), 5, 6 | 4(½), 5–7 | 4–5(½), 6–7

FLUENCY


Example 8

4 Find the area of each triangle given.


a




b




c




d




e




f




g



h



i




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11E


FLUENCY

5 Find the area of these triangles, which have been drawn on 1 cm grids. Give your answer in cm^2.


a




b



c




d



6 A rectangular block of land measuring 40 m long by 24 m wide is cut in half along a diagonal. Find the area of each triangular block of land.

7 A square pyramid has a base length of 120 m and a triangular face of height 80 m. Find the area of one triangular face of the pyramid.





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press


8, 9 | 9, 10 | 9–11

11E

PROBLEM-SOLVING

8 Each face of a 4-sided die is triangular, with a base of 2 cm and a height of 1.7 cm. Find the total area of all 4 faces of the die.

9 A farmer uses fencing to divide a triangular piece of land into two smaller triangles, as shown. What is the difference in the two areas?



10 A yacht must have two of its sails replaced as they have been damaged by a recent storm. One sail has a base length of 2.5 m and a height of 8 m and the bigger sail has a base length of 4 m and a height of 16 m. If the cost of sail material is $150 per square metre, find the total cost to replace the yacht's damaged sails.



11 **a** The area of a triangle is 10 cm^2 and its base length is 4 cm. Find its height.

b The area of a triangle is 44 mm^2 and its height is 20 mm. Find its base length.


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11E


12 | 12, 13 | 13, 14

REASONING

12 The midpoint, M, of the base of a triangle joins the opposite vertex. Is the triangle area split in half exactly? Give reasons for your answer.



13 If the vertex C for this triangle moves parallel to the base AB, will the area of the triangle change? Justify your answer.




14 The area of a triangle can be found using the formula $A = \frac{1}{2}bh$. Write down the formula to find the base, b, if you are given the area, A, and height, h.

Estimating areas with curves

— | — | 15


ENRICHMENT

15 This diagram shows a shaded region that is $\frac{1}{2}$ of 3 cm^2 = 1.5 cm^2.




Using triangles like the one shown here, and by counting whole squares also, estimate the areas of these shapes below.


a




b



c



d



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11F Area of a parallelogram


Interactive

Widgets

HOTsheets

Walkthroughs

Recall that a parallelogram is a quadrilateral with two pairs of parallel sides. Opposite sides are of the same length and opposite angles are equal.




Like a triangle, the area of a parallelogram is found by using the length of one side (called the base) and the height (which is perpendicular to the base.)

Lets start: Developing the rule

Start this activity by drawing a large parallelogram on a loose piece of paper. Ensure the opposite sides are parallel and then use scissors to cut it out. Label one side as the base and label the height, as shown in the diagram.

- Cut along the dotted line.
- Now shift the triangle to the other end of the parallelogram to make a rectangle.
- Now explain how to find the area of a parallelogram.





Key ideas

■ The area of a parallelogram is given by:

$$A = bh$$

where b is the base (one of the sides) and h is the height (perpendicular to the base).







Example 9 Finding the area of a parallelogram

Find the area of these parallelograms.

a



b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
a $A = bh$ $= 12 \times 5$ $= 60 \text{ m}^2$	Choose the given side as the base (12 m) and note the perpendicular height is 5 m.
b $A = bh$ $= 2 \times 3$ $= 6 \text{ cm}^2$	Use the given side as the base (2 cm), noting that the height is 3 cm.

Exercise 11F

1, 2 | 2 | —

UNDERSTANDING

1 Copy and complete the following, using the given values of b and h.

a $b = 5, h = 7$

$A = bh$

$= ___ \times ___$

$= 35$

b $b = 20, h = 3$

$A = ___$

$= 20 \times ___$

$= ___$

c $b = 8, h = 2.5$


$A = ___$

$= 8 \times ___$


$= ___$

2 For each of these parallelograms, state the side length of the base and the height that might be used to find the area.


a




b




c




d



e



f






Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Example 9

3 Find the area of these parallelograms.


a




b




c




d




e




f




g



h




i




4 These parallelograms are on 1 cm grids (not to scale). Find their area.


a




b



c



d



5 The floor of an office space is in the shape of a parallelogram. The longest sides are 9 m and the distance between them is 6 m. Find the area of the office floor.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11F

6, 7 | 7, 8 | 7–9

PROBLEM-SOLVING

6 Find the height of a parallelogram when its:

a area = 10 m^2 and base = 5 m

b area = 28 cm^2 and base = 4 cm

c area = 2.5 mm^2 and base = 5 mm

7 Find the base of a parallelogram when its:

a area = 40 cm^2 and height = 4 cm

b area = 150 m^2 and height = 30 m


c area = 2.4 km^2 and height = 1.2 km

8 A large wall in the shape of a parallelogram is to be painted with a special red paint, which costs $20 per litre. Each litre of paint covers 5 m^2. The wall has a base length of 30 m and a height of 10 m. Find the cost of painting the wall.

9 A proposed rectangular flag for a new country is yellow with a red stripe in the shape of a parallelogram, as shown.

a Find the area of the red stripe.


b Find the yellow area.




10 | 10, 11 | 11, 12


REASONING

10 Explain why this parallelogram's area will be less than the given rectangle's area.





11 A parallelogram includes a green triangular area, as shown. What fraction of the total area is the green area? Give reasons for your answer.




12 The area of a parallelogram can be thought of as twice the area of a triangle. Use this idea to complete this proof of the rule for the area of a parallelogram.

Area = twice triangle area

= 2 × _____

= _____



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Glass façade — — 13


11F

ENRICHMENT



13 The Puerta de Europa (Gate of Europe) towers are twin office buildings in Madrid, Spain. They look like normal rectangular glass-covered skyscrapers but they lean towards each other at an angle of 15° to the vertical. Two sides are parallelograms and two sides are rectangles. Each tower has a vertical height of 120 m, a slant height of 130 m and a square base of side 50 m.

All four sides are covered with glass. If the glass costs $180 per square metre, find the cost of covering *one* of the towers with glass. (Assume the glass covers the entire surface, ignoring the beams.)



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11G Area of composite shapes EXTENDING

Interactive
Widgets
HOTsheets
Walkthroughs

The areas of more complicated shapes can be found by dividing them up into more simple shapes, such as the rectangle and triangle. We can see this in an aerial view of any Australian city. Such a view will show that many city streets are not parallel or at right angles to each other. As a result this causes city blocks to form interesting shapes, many of which are composite shapes made up of rectangles and triangles.




Streets, parks and buildings form complex shapes that can be made up of triangles and rectangles.

Let's start: Dividing land to find its area


Working out the area of this piece of land could be done by dividing it into three rectangles, as shown.

- Can you work out the area using this method?
- What is another way of dividing the land to find its area? Can you use triangles?
- What is the easiest method to find the area? Is there a way that uses subtraction instead of addition?




Key ideas

- **Composite shapes** are made up of more than one simple shape.
- The area of composite shapes can be found by adding or subtracting the areas of simple shapes.



A square plus a triangle




A rectangle subtract a triangle


Example 10 Finding the area of composite shapes

Find the area of each of these composite shapes.



a



b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

SOLUTION	EXPLANATION
a $A = l \times w + \frac{1}{2} bh$ $= 9 \times 5 + \frac{1}{2} \times 3 \times 5$ $= 45 + 7.5$ $= 52.5 \text{ m}^2$	Divide the shape into a rectangle and triangle and find the missing lengths. 
b $A = l^2 - \frac{1}{2} bh$ $= 6^2 - \frac{1}{2} \times 6 \times 4$ $= 36 - 12$ $= 24 \text{ cm}^2$	Subtract the triangle ($\frac{1}{2} \times 6 \times 4$) at the top of the shape from the larger square (6×6). 


Exercise 11G

1–3 | 3 | —

UNDERSTANDING

1 Copy these diagrams and draw a dotted line where you might divide these shapes into two more simple shapes.

a



b




c




2 To find the area of each of the following shapes, decide if the easiest method would involve the *addition* of two shapes or the *subtraction* of one shape from another.


a



b



c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11G

UNDERSTANDING

3 Copy and complete the solutions for the areas of these shapes.

a




$A = l^2 +$ _____

$= 1^2 + 3 \times$ _____

$=$ _____ $+$ _____

$=$ _____ cm^2

b



$A = lw -$ _____

$=$ _____ $\times 8 - \frac{1}{2} \times$ _____ $\times$ _____

$=$ _____ $-$ _____

$=$ _____ m^2


4, 5 | 4, 5 | 4–5(½)

FLUENCY


Example 10

4 Find the area of these composite shapes by adding together the area of simpler shapes.


a




b




c




d



e




f




Example 10

5 Use subtraction to find the area of these composite shapes.

a



b




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


11G

FLUENCY


c




d



e



f




6, 7 | 7, 8 | 7–9


PROBLEM-SOLVING

6 Find the areas of these composite shapes.


a



b




c




7 By finding the missing lengths first, calculate the area of these composite shapes.


a




b



c



d




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


11G

PROBLEM-SOLVING

8 A wall has three square holes cut into it to allow for windows, as shown. Find the remaining area of the wall.




9 A factory floor, with dimensions shown opposite, is to be covered with linoleum. Including underlay and installation, the linoleum will cost $25 per square metre. The budget for the job is $3000. Is there enough money in the budget to cover the cost?




REASONING

10 | 10 | 10, 11

10 Explain why using subtraction is sometimes quicker than using addition to find the area of a composite shape. Refer to the diagram as an example.



11 The 4-sided shape called the trapezium has one pair of parallel sides.




- **a** For the trapezium shown opposite, is it possible to find the base length of each triangle on the sides? Justify your answer.
- **b** Can you come up with a method for finding the area of this trapezium using the rectangle and triangles shown in the diagram? Use diagrams to explain your method.

ENRICHMENT

Adding to infinity — | — | 12

12 The square given opposite, which has an area of 1 unit, is divided to show the areas of $\frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \ldots$



- **a** Similar to the one shown opposite, draw your own square, showing as many fractions as you can. Try to follow the spiral pattern shown. Note: The bigger the square you start with, the more squares you will be able to show.
- **b** **i** Write the next 10 numbers in this number pattern.
  $\frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \ldots$
  ii Will the pattern ever stop?
- **c** What is the total area of the starting square?
- **d** What do your answers to parts **b ii** and **c** tell you about the answer to the sum below?
  $\frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \frac{1}{8} + \ldots$ (continues forever)

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

11A **1** Which metric unit would be most appropriate for measuring the lengths of:

Ext


a the height of the classroom?
b the width of your thumb
c the distance from Sydney to Canberra?

11B **2** Convert to the units given in brackets.


a 4 m (cm)
b 2 m (mm)
c 3.5 cm (mm)
d 3 km (m)
e 1.45 km (m)
f 23 000 m (km)

11C **3** Find the perimeter of each of these shapes.


a



b




c




11D **4** Find the area of this rectangle and square.

a




b




11E **5** Find the area of each given triangle.


a




b



c




d




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

11F **6** Find the area of these parallelograms.


a



b




c




11G **7** Find the area of these composite shapes.

a




b



Ext

c



11C/D **8** The perimeter of a square made of thin wire is 60 cm. Find:

a the area of this square

b the area of a rectangle made with this wire, if its length is twice its width

c the number of smaller squares that can be made from this wire if each square has an area of 4 square centimetres

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

11H Volume of rectangular prisms

Interactive

Widgets

HOTsheets

Walkthroughs

The amount of space inside a three-dimensional (3D) object is called volume. Volume is measured in cubic units such as the cubic centimetre, which is 1 cm long, 1 cm wide and 1 cm high. Just like the topics of length and area, different units can be selected, depending on the size of the volume being measured. For example, the volume of water in the sea could be measured in cubic kilometres and the volume of concrete poured from a cement mixing truck could be measured in cubic metres.




The Pacific Ocean contains hundreds of thousands of cubic kilometres of water.

Let's start: Volume

We all know that there are 100 cm in 1 m, but do you know how many cubic centimetres are in 1 cubic metre?


- Try to visualise 1 cubic metre – 1 metre long, 1 metre wide and 1 metre high. Guess how many cubic centimetres would fit into this space.
- Describe a method for working out the exact answer. Explain how your method works.




Key ideas

- **Volume** is measured in cubic units.
- The common metric units for volume include:
  - cubic millimetres (mm^3)

(Not drawn to scale.)



  - cubic centimetre (cm^3)




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Key ideas


- cubic metre (m^3)

(Not drawn to scale.)




- cubic kilometre (km^3)

(Not drawn to scale.)




- The volume of a **rectangular prism** is given by the formula:
  V = length × width × height
  $= lwh$
  - A rectangular prism is also called a **cuboid**.



$V = lwh$


- The volume of a **cube** is given by:
  $V = l \times l \times l$
  $= l^3$



$V = l^3$

Example 11 Finding the volume of a cuboid

Find the volume of this rectangular prism.



SOLUTION	EXPLANATION
$V = lwh$ $= 8 \times 3 \times 4$ $= 96\ cm^3$	Use the formula for the volume of a rectangular prism, then substitute the three lengths into the formula.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Exercise 11H

1, 2 | 2 | —


UNDERSTANDING

1 For each of these solids, count the number of cubic units to find its volume.


a




b




c




d



e




f



2 Copy and complete the working shown for each of these solids.

a




$V = lwh$

$= 4 \times ____ \times ____$

$= ____ \text{ cm}^3$

b




$V = lwh$

$= 1 \times ____ \times ____$

$= ____ ___$

c



$V = lwh$

$= 2 \times ____ \times ____$

$= ____ \text{ km}^3$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

11H


3–6 | 3(½), 4–7 | 3(½), 4–7

FLUENCY


Example 11

3 Find the volume of these rectangular prisms.


a




b




c




d




e




f



g



h



4 A fruit box is 40 cm long, 30 cm wide and 20 cm high. Find its volume.

5 A shipping container is 3 m wide, 4 m high and 8 m long. Find its volume.

6 A short rectangular ruler is 150 mm long, 40 mm wide and 2 mm thick. Find its volume.

7 There is enough ice on Earth to fill a cube of side length 300 km. Find the approximate volume of ice on Earth.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.


11H

8, 9 | 9, 10 | 9–11


PROBLEM-SOLVING

8 These solids are made up of more than one rectangular prism. Use addition or subtraction to find the volume of the composite solid.


a



b



c



9 A box measuring 30 cm long, 20 cm high and 30 cm wide is packed with matchboxes, each measuring 5 cm long, 2 cm high and 3 cm wide. How many matchboxes will fit in the box?

10 The outside dimensions of a closed wooden box are 20 cm by 20 cm by 20 cm. If the box is made from wood that is 2 cm thick, find the volume of air inside the box.


11 **a** The area of one face of a cube is 25 cm^2. Find the cube's volume.

b The perimeter of one face of a cube is 36 m. Find the cube's volume.


12 | 12 | 12, 13

REASONING


12 We can find the area of this shaded triangle by thinking of it as half a rectangle. Use the same idea to find the volume of each of these solids.




a



b



c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11H

REASONING


13 a Find the height of these rectangular prisms with the given volumes. Use trial and error if you prefer.

i




$V = 16\ m^3$

ii




$V = 45\ cm^3$

iii



$V = 56\ cm^3$

iv



$V = 54\ m^3$


b Can you explain a method that always works for finding the height of a rectangular prism?

c Use V, l and w to write a rule for h.

ENRICHMENT

Cubic conversions — — 14

14 a The diagram shows a 1 cm^3 block that is divided into cubic millimetres.



i How many mm^3 are there along one edge of the cube?

ii How many mm^3 are there in one layer of the cube? (Hint: How many cubes sit on the base?)

iii How many layers of mm^3 are there in the cube?


iv Use your answers from parts **i** to **iii** above to now calculate how many mm^3 there are in 1 cm^3.

b Use a similar method to calculate the number of:

i cm^3 in 1 m^3

ii m^3 in 1 km^3

c Complete the diagram shown.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11I Capacity CONSOLIDATING









Capacity relates to the volume of fluid or gas that a container can hold. For example, the capacity of a water tank may be 5000 litres, or a farmer's water allocation might be 300 megalitres (meaning 300 million litres). The basic unit is the litre, which contains 1000 cm^3 of space. Other common metric units for capacity include the millilitre, kilolitre and megalitre. There is a clear link between capacity and volume, as they both relate to the space occupied by a three-dimensional object.



Irrigation channels carry megalitres of water to farms.

Let's start: Water containers

Wil, Tony and Ethan each bring a container to collect some water from a fountain.

- Wil says his container holds 2 litres.
- Tony says his container holds 2000 cm^3.
- Ethan says his container holds 2000 millilitres.


Who can collect the most water? Give reasons for your answer.

Key ideas

- **Capacity** is the volume of fluid or gas that an object can hold.
- Common metric units include:
  - 1 litre (L) = 1000 millilitres (mL)
  - 1 kilolitre (kL) = 1000 litres (L)
  - 1 megalitre (ML) = 1000 kilolitres (kL)

$$\underset{\div 1000}{\overset{\times 1000}{ML}} \quad \underset{\div 1000}{\overset{\times 1000}{kL}} \quad \underset{\div 1000}{\overset{\times 1000}{L}} \quad \underset{\div 1000}{mL}$$

- Relating volume and capacity
  - 1 cm^3 = 1 mL
  - 1 m^3 = 1000 L = 1 kL



1 L (1000 mL) | 1000 cm^3

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Example 12 Converting units for capacity

Convert to the units shown in brackets.

a 500 mL (L)

b 3 ML (L)

SOLUTION

a $500 \text{ mL} = 500 \div 1000$
$= 0.5 \text{ L}$

b $3 \text{ ML} = 3 \times 1000 \text{ kL}$
$= 3 \times 1000 \times 1000 \text{ L}$
$= 3\,000\,000 \text{ L}$


EXPLANATION

When converting to a larger unit, divide.
There are 1000 mL in 1 L.

There are 1000 kL in 1 ML and 1000 L in 1 kL. So 1 ML is 1 million litres.

Example 13 Converting cm^3 to litres

Find the capacity of this container, in litres.



SOLUTION

$V = 20 \times 10 \times 10$
$= 2000 \text{ cm}^3$
$= 2000 \text{ mL}$
$= 2000 \div 1000 \text{ L}$
$= 2 \text{ L}$

EXPLANATION

$V = lwh$

$1 \text{ cm}^3 = 1 \text{ mL}$
There are 1000 mL in 1 litre.

Exercise 11I

1–3 | 3 | —

UNDERSTANDING

1 Complete these sentences.

a 1 mL contains the volume of _____ cm^3.
b 1 L contains _____ mL.
c 1 L contains _____ cm^3.
d 1 kL contains _____ L.
e 1 ML contains _____ kL.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

UNDERSTANDING

111

2 Circle or write down which volumes are the same.

a 1 L, 10 kL, 1000 mL, 1 m^3, 1000 cm^3

b 1 m^3, 100 L, 1000 L, 1000 ML, 1 kL

3 From options **A** to **F**, choose the capacity that best matches the given container.

a teaspoon	**A** 18 L
b cup	**B** 250 mL
c bottle	**C** 10 kL
d kitchen sink	**D** 20 mL
e water tank	**E** 45 ML
f water in a lake	**F** 0.8 L

4(½), 5–9 | 4(½), 5–9 | 4(½), 5, 6, 7(½), 9(½)

FLUENCY


Example 12

4 Convert to the units shown in brackets.


a 2 L (mL)	**b** 0.1 L (mL)	**c** 6 ML (kL)	**d** 24 kL (L)
e 2000 L (kL)	**f** 3500 mL (L)	**g** 70 000 mL (L)	**h** 2500 kL (ML)
i 0.257 L (mL)	**j** 9320 mL (L)	**k** 3.847 ML (kL)	**l** 47 000 L (kL)
m 0.5 kL (L)	**n** 91 000 kL (ML)	**o** 0.42 L (mL)	**p** 170 L (kL)

5 Read these scales to determine the amount of water in each of the containers.


a



b



c



6 A cup of 200 mL of water is added to a jug already containing 1 L of water. Find the total volume in:

a mL **b** L

Example 12

7 Convert to the units shown in brackets.

a 6 ML (L)	**b** 320 000 L (ML)
c 0.004 kL (mL)	**d** 992 700 mL (kL)

8 A farmer purchases 3.3 ML of water for her apple orchard. How many litres is this?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


11I

Example 13


FLUENCY

9 Find the capacity of each of these containers, in litres.


a




b




c




d



e



f



10, 11 | 11, 12 | 12–14

PROBLEM-SOLVING

10 A swimming pool in the shape of a rectangular prism has length 50 m, width 25 m and depth 2 m. Find the swimming pool's:

a volume, in m^3 **b** capacity, in L

11 A dripping tap leaks about 10 mL every minute.

a If there are 50 drips per minute, find the volume of one drip.

b Find the approximate volume of water, in litres, that has leaked from a tap after the following time periods.

i 100 minutes **ii** 1 hour

iii 1 day **iv** 1 year



12 A dose of 12 mL of medicine is to be taken twice each day from a 0.36 L bottle. How many days will it take to finish the medicine?

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

PROBLEM-SOLVING 11I

13 A gas bottle contains 50 L of liquid gas. If the liquid gas is used at a rate of 20 mL per minute, how many hours will the gas bottle last?

14 A city's dams have 2 million megalitres of water and the average daily consumption of the city's people is 400 L per day per person. If the city's population is 5 million people, how long will the dam supply last without further water catchment?

	15	15	15, 16

REASONING

15 If x is any number, then x litres is the same as $1000 \times x = 1000x$ millilitres because there are 1000 mL in 1 L. Write expressions for x L in the following units.

a cm^3 **b** m^3 **c** kL **d** ML

16 a A rectangular prism has length l cm, width w cm and height h cm. Write an expression for the capacity of the container measured in:

i cm^3 **ii** mL **iii** L **iv** kL

b A rectangular prism has length l m, width w m and height h m. Write an expression for the capacity of the container measured in:

i m^3 **ii** L **iii** kL **iv** ML


Added depth	—	—	17

ENRICHMENT

17 A container is 10 cm long, 5 cm wide and 8 cm high.


a Find the depth of water when the following amounts of water are poured in. (Remember: 1 mL = 1 cm^3.)

i 400 mL **ii** 200 mL **iii** 160 mL



b After adding 200 mL, a further 30 mL is added. What is the increase in depth?

c A 1-litre container of milk has a base area of 8 cm by 7 cm. After 250 mL of milk is poured out, what is the depth of the milk remaining in the container? Give your answer to the nearest mm.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11J Mass and temperature

CONSOLIDATING









The scales for both mass and temperature are based on the properties of water. In France in 1795, the gram was defined as being the weight of 1 cm^3 of water at 0°C. Later it was redefined to be the weight at 4°C, as this is considered to be the temperature at which water is the most dense. So, 1 litre of water is very close to 1 kilogram, which is the basic unit for mass. Other units for mass include the tonne, gram and milligram. A small car has a mass of about 1 tonne and a 20-cent coin has a mass of about 11 grams.


A small car has a mass of about 1 tonne.

Temperature tells us how hot or cold something is. Anders Celsius (1701–1744), a Swedish scientist, worked to define a scale for temperature. After his death, temperature was officially defined by:

- 0°C (0 degrees Celsius) – the freezing point of water.
- 100°C (100 degrees Celsius) – the boiling point of water (at one standard degree of pressure).

This is still the common understanding of degrees Celsius. As mentioned in Chapter 10, Fahrenheit is another scale used for temperature. This is investigated further in the Enrichment questions.

Let's start: Choose a unit of mass

Name five objects of which their mass would commonly be measured in:

- tonnes
- kilograms
- grams
- milligrams.


Is it possible for the temperature to drop below 0°C? How is this measured and can you give examples of places or situations where this might be the case?


Ice melts at 0°C.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Key ideas

- The basic unit for mass is the **kilogram** (kg). 1 litre of water has a mass that is very close to 1 kilogram.
- Metric units for mass include:
  - 1 **gram** (g) = 1000 **milligrams** (mg)
  - 1 **kilogram** (kg) = 1000 **grams** (g)
  - 1 **tonne** (t) = 1000 **kilograms** (kg)
- The common unit for temperature is **degrees Celsius** (°C).
  - 0°C is the freezing point of water.
  - 100°C is the boiling point of water.



Example 14 Converting units of mass

Convert to the units shown in brackets.

a 2.47 kg (g)

b 170 000 kg (t)

SOLUTION	EXPLANATION
a 2.47 kg = 2.47 × 1000 g = 2470 g	1 kg = 1000 g Multiply because you are changing to a smaller unit.
a 170 000 kg = 170 000 ÷ 1000 t = 170 t	1 t = 1000 kg Divide because you are changing to a larger unit.

Exercise 11J

1–3 | 3 | —

UNDERSTANDING

1 Circle or write down the pair of equal mass measurements.

a 1 kg, 100 g, 1000 g, 10 t

b 1000 mg, 10 kg, 1 g, 1000 t

2 From options **A** to **F**, choose the mass that best matches the given object.

a human hair

b 10-cent coin

c bottle

d large book

e large bag of sand

f truck

A 300 g

B 40 kg

C 100 mg

D 1.5 kg

E 13 t

F 5 g

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11J

UNDERSTANDING

3 From options **A** to **D**, choose the temperature that best matches the description.

a	temperature of coffee	**A**	15°C
b	temperature of tap water	**B**	50°C
c	temperature of oven	**C**	–20°C
d	temperature in Antarctica	**D**	250°C

4(½), 5–10 | 4(½), 5–11 | 4(½), 5, 6(½), 7–11

FLUENCY


Example 14

4 Convert to the units shown in brackets.


a 2 t (kg)	**b** 70 kg (g)	**c** 2.4 g (mg)	**d** 2300 mg (g)
e 4620 mg (g)	**f** 21 600 kg (t)	**g** 0.47 t (kg)	**h** 312 g (kg)
i 27 mg (g)	**j** $\frac{3}{4}$ t(kg)	**k** $\frac{1}{8}$ kg(g)	**l** 10.5 g (kg)
m 210 000 kg (t)	**n** 0.47 t (kg)	**o** 592 000 mg (g)	**p** 0.08 kg (g)

5 Read these mass scales.


a



b




c




6 Read these temperature scales.


a




b




c




d



e



f



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11J

FLUENCY

7 A small truck delivers 0.06 t of stone for a garden. Write the mass of stones using these units.

a kg **b** g **c** mg

8 A box contains 20 blocks of cheese, each weighing 150 g. What is the approximate mass of the box in the following units?

a g **b** kg

9 The temperature of water in a cup is initially 95°C. After half an hour the temperature is 62°C. What is the drop in temperature?



10 An oven is initially at a room temperature of 25°C. The oven dial is turned to 172°C. What is the expected increase in temperature?

11 Add all the mass measurements and give the result in kg.

a 3 kg, 4000 g, 0.001 t

b 2.7 kg, 430 g, 930 000 mg, 0.0041 t

12, 13 | 13, 14 | 14–16

PROBLEM-SOLVING

12 Arrange these mass measurements from smallest to largest.

a 2.5 kg, 370 g, 0.1 t, 400 mg

b 0.000 32 t, 0.41 kg, 710 g, 290 000 mg

13 The highest and lowest temperatures recorded over a 7-day period are as follows.

Day	1	2	3	4	5	6	7
Lowest temperature (°C)	8	6	10	9	7	8	10
Highest temperature (°C)	24	27	31	32	21	19	29

a Which day had the largest temperature range?

b What is the largest temperature drop from the highest temperature on one day to the lowest temperature on the next day?

c What would have been the final temperature on Day 7 if the temperature increased from the minimum by 16°C?

14 A 10 kg bag of flour is used at a rate of 200 g per day. How many days will the bag of flour last?

15 A boat has a weight limit of 3.5 t carrying capacity. Loaded onto the boat are 1500 tins of coffee at 500 g each, 36 bags of grain at 20 kg each, 190 boxes of tobacco at 5.5 kg each and 15 people, averaging 80 kg each. Is the load too much for the weight limit of the boat?

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11J

PROBLEM-SOLVING

16 A truck tare mass (i.e. mass with no load) is 13.2 t. The truck's gross mass is 58.5 t. This is the total maximum mass allowed, including the load.

a What is the maximum load the truck can carry?

b The truck is loaded with 120 timber beams at 400 kg each. Will it exceed its gross weight limit?



17 | 17, 18 | 18, 19


REASONING

17 Water weighs 1 kg per litre. What is the mass of these volumes of water?


a 1 mL **b** 1 kL **c** 1 ML

18 The containers shown below are filled with water. Calculate the mass of water in each container, in kg.


a



b



c



19 The kelvin (K) is a temperature unit used by many scientists, where 273 K is approximately 0°C. (The kelvin used to be called the 'degree kelvin' or °K.) An increase in 1 K is the same as an increase in 1°C.

a Write the following temperatures in °C.

i 283 K **ii** 300 K **iii** 1000 K

b Write the following temperatures in kelvins.

i 0°C **ii** 40°C **iii** –273°C



Liquid nitrogen freezes at –210°C and boils at –196°C.

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

20 Daniel Fahrenheit (1686–1736) proposed the Fahrenheit temperature scale in 1724. It was commonly used in Australia up until the mid-twentieth century, and is still used today in the United States.
32°F is the freezing point of water.
212°F is the boiling point of water.

a What is the difference between the temperature, in Fahrenheit, for the boiling point of water and the freezing point of water?


b 1°F is what fraction of 1°C?

c 1°C is what fraction of 1°F?

d To convert from °F to °C, we use the formula $C = (F - 32) \times \frac{5}{9}$. Convert these Fahrenheit temperatures to °C.

i 32°F **ii** 68°F **iii** 140°F **iv** 221°F

e Find the rule to convert from °C to °F. Test your rule to see if it works and write it down.




ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Investigation

Opal mining

Greg, Sally and Alston apply for a mining licence to look for opals at Coober Pedy in South Australia. They are required to choose an area and mark it out with special orange tape so that others will know which areas are already taken. Their length of tape is 200 m.



Square mining areas

They first decide to mark out an area as a square.

a Make a drawing of their square area.

b Calculate the side length and area and show this on your diagram. Also show any working.

Rectangular mining areas

They then change the mining area and experiment with different side lengths.

a Show three possible lengths and areas for rectangular mining sites.

b Complete a table similar to the one below. Fill in the missing numbers for the side lengths given, then add your own rectangle measurements from part **a** above.


Length	Width	Perimeter	Area
10		200	
20		200	
35		200	
		200	
		200	
		200	

c Are there any rectangles that give a larger area than the square mining area from above?

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Circular mining areas

They now decide to try to arrange the tape to form a circle. For this section you will need the rule to calculate the distance around a circle (circumference). The circumference C is given by $C = 2 \times \pi \times r$ where r is the length of the radius and $\pi \approx 3.14$.



a Calculate the radius of the circle correct to one decimal place. Use a trial and error (guess and check) technique and remember that the circumference will be 200. Explain and show your method using a table of values.

b Calculate the area of the circular mining area correct to the nearest square metre. Use the special rule for the area of a circle A which is given by $A = \pi \times r^2$.

The largest area

Compare the areas marked out with the 200 m tape by Greg, Sally and Alston. Comment on any differences. Which shape gives the largest area for the given perimeter? Would your answer be the same if any shape were allowed to be used? Explain.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges



Up for a challenge? If you get stuck on a question, check out the 'Working with unfamiliar problems' poster at the end of the book to help you.


1 Without measuring, state which line looks longer: A or B? Then measure to check your answer.




2 You have two sticks of length 3 m and 5 m, both with no scales. How might you mark a length of 1 m?

3 Count squares to estimate the area of these circles if each grid square is 1 cm across.

a




b




4 A house roof has 500 m^2 of area. If there is 1 mm of rainfall, how much water, in litres, can be collected from the roof?

5 Work out the volume of this rectangular prism with the given face areas.



6 Find the area of the shaded region.




7 A cube of side length 20 cm contains 5 L of water.

a What is the depth of water in the cube?


b What is the increase in depth if 1.5 L is added to the cube of water?

8 These two rectangles overlap, as shown. Find the total area of the shaded region.



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter summary



ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review

Multiple-choice questions

11A Ext

1 Which of the following are imperial units?

A cm **B** pace **C** digit **D** yard **E** litre

11B


2 Shonali buys 300 cm of wire that costs $2 per metre. How much does she pay for the wire?

A $150 **B** $600 **C** $1.50 **D** $3 **E** $6

11C

3 The triangle given has a perimeter of 20 cm. What is the missing base length?

A 6 cm **B** 8 cm **C** 4 cm **D** 16 cm **E** 12 cm



11D

4 The area of a rectangle with length 2 m and width 5 m is:

A $10\ m^2$ **B** $5\ m^2$ **C** 5 m **D** $5\ m^3$ **E** 10 m

11E


5 A triangle has base length 3.2 cm and height 4 cm. What is its area?

A $25.6\ cm^2$ **B** 12.8 cm **C** $12.8\ cm^2$ **D** 6 cm **E** $6.4\ cm^2$

11G Ext

6 The total area of this composite shape is:

A $56\ km^2$ **B** $45.5\ km^2$ **C** $35\ km^2$ **D** $10.5\ km^2$ **E** $24.5\ km^2$



11H

7 A cube has a side length of 3 cm. Its volume is:

A $27\ cm^3$ **B** $9\ cm^2$ **C** 3 cm **D** $9\ cm^3$ **E** $36\ cm^3$

11I

8 $2000\ cm^3$ is the same as:

A $2\ m^3$ **B** 2 L **C** 2 kL **D** 2 mL **E** 2 t

11J

9 9 tonnes of iron ore is being loaded onto a ship at a rate of 20 kg per second. How many minutes will it take to load all of the 9 tonnes of ore?

A 0.75 min **B** 45 min **C** 7.3 min **D** 450 min **E** 7.5 min

11F

10 The base length of a parallelogram is 10 cm and its area is $30\ cm^2$. The parallelogram's height is:

A 10 cm **B** 3 cm **C** 30 cm **D** $3\ cm^2$ **E** $10\ m^2$

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

11A Ext

1 **a** Using the Roman system, state how many:
- **i** digits in 1 foot
- **ii** paces in 1 mile

b Using the imperial system, state how many:
- **i** feet in 1 yard
- **ii** inches in 1 foot

c Using the metric system, state how many:
- **i** millimetres in 1 cm
- **ii** centimetres in 1 km

11B


2 Convert to the units shown in brackets.

a 5 cm (mm) **b** 200 cm (m) **c** 3.7 km (m) **d** 421 000 cm (km)
e 7.1 kg (g) **f** 24 900 mg (g) **g** 28 490 kg (t) **h** 0.009 t (g)
i 4000 mL (L) **j** 29 903 L (kL) **k** 0.4 ML (kL) **l** 0.001 kL (mL)
m 1 day (min) **n** 3600 s (min) **o** 84 h (days) **p** 2.5 h (s)


11B

3 Read these scales.


a




b



c




d




11C

4 Find the perimeter of these shapes.


a




b




c




d



e



f




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Chapter review


11D/E/F/G

5 Find the area of each of the following shapes.


a




b




c




d




e




f



g




h




6 Find the area of these composite shapes.


Ext **a**




Ext **b**



Ext **c**




Ext **d**




11H

7 Find the volume contained in each of these solids.


a



b



c



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11I

8 A rectangular fish tank is of length 60 cm, width 40 cm and height 30 cm. Give the tank's capacity in:

a cm^3 **b** mL **c** L

11J

9 Arrange these measurements from smallest to largest.

a 3 t, 4700 kg, 290 000 g, 45 mg

b 50 000 mL, 1 ML, 51 L, 0.5 kL

Extended-response questions

1 A truck carries a large rectangular container of dimensions 6 m long, 3 m wide and 2 m high. The truck weighs 15.4 tonnes without its load.

a Find the area of the base of the container in:

i m^2 **ii** cm^2


b Find the volume of the container in m^3.

c How many litres of water could the truck hold in the container?

d Since 1 L of water weighs 1 kg, give the weight of the truck if the container was filled with water. Give your answer in tonnes.

e The truck completes three journeys, which take, on average, 1 hour, 17 minutes and 38 seconds per trip. What is the total time for the three journeys?

2 Lachlan builds a race track around the outside of his family house block. The block combines rectangular and triangular area, as shown in the diagram.



a How far is one complete circuit of the track?

b Lachlan can jog 10 laps at about 33 seconds each. What is the total time, in minutes and seconds, that it takes him to complete the 10 laps?

c What is the total area of the block?

d The house occupies 100 m^2 and the rest of the block is to have instant turf, costing $12 per square metre. What will be the cost for the instant turf?

e The house sits on a concrete slab that is 50 cm deep. What is the volume of concrete, in m^3?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Semester review 2

Negative numbers

Multiple-choice questions

1 Which of the following statements is incorrect?

A $-2 > -4$ **B** $0 < 5$ **C** $0 < -10$ **D** $-9 < -8$ **E** $-5 < 3$

2 $12 + (-9) - (-3)$ is the same as:

A $12 + 9 + 3$ **B** $12 - 9 + 3$ **C** $12 - 9 - 3$ **D** $12 - 12$ **E** 12

3 If $a = -3$, the value of $-2a^2$ is:

A 36 **B** -36 **C** 18 **D** -18 **E** 12

4 The coordinates of the point that is 3 units below (3, 1) is:

A $(0, 1)$ **B** $(0, -2)$ **C** $(0, -1)$ **D** $(3, 4)$ **E** $(3, -2)$

5 $12 \times (-4 + (-8) \div 2)$ equals:

A -96 **B** 72 **C** -72 **D** 60 **E** 96

Short-answer questions

1 For each of the following, insert $=$, $>$ or $<$.

a -3 ___ 3 **b** $-10 \div 2$ ___ 5 **c** $-20 \times (-1)$ ___ $\frac{-40}{-2}$

2 Calculate:

a $-5 + (-8)$ **b** $12 - 96$ **c** $-12 - 96$

d $-4 - 8 - 9$ **e** $-12 + 96$ **f** $-7 - (-7)$

3 Find:

a -6×4 **b** $-9 \times 8 \times (-1)$ **c** $(-12)^2$

d $\frac{-9 \times (-7)}{3}$ **e** $-150 \div (-2 - 3)$ **f** $-10 + 7 \times (-3)$

4 State whether the answer to each of the following is positive or negative.

a $-3 \times (-3) \times (-3)$ **b** $-109 \times 142 \times (-83)$ **c** $-2 \times (-1 - (-3))$

5 Copy and complete.

a ___ $+ 9 = -6$ **b** ___ $\times (-3) = -6 \times (-4)$ **c** $16 \times$ ___ $= -64$

6 If $a = 6$ and $b = -4$, find the value of:


a $-a + b$ **b** $a - b$ **c** $2(b - a)$

d $-ab^2$ **e** $a^2 + b^2$ **f** $24 \div (ab)$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response question

1 Refer to the given Cartesian plane when answering these questions.



- **a** Name any point that lies in the first quadrant.
- **b** Name any point(s) with a y value of zero. Where does each point lie?
- **c** Which point has coordinates $(-1, -2)$?
- **d** Find the distance between points:
  - **i** A and B **ii** D and E
- **e** What shape is formed by joining the points $IDAG$?
- **f** What is the area of $IDAG$?
- **g** $ABXD$ are the vertices of a square. What are the coordinates of X?
- **h** Decode: $(2, 2), (2, -3), (0, 2), (-1, 2), (2, 2), (2, -3)$

Statistics and probability

Multiple-choice questions

The following information is relevant for Questions 1 and 2.

A survey asked 60 participants their favourite colour. The results are shown below.

Blue	Pink	Green	Purple	Black
12	20	6	12	10

1 If a divided bar graph 10 cm long is constructed to display the data, the length required for purple would be:

A 12 cm **B** 2 cm **C** 1 cm **D** 5 cm **E** 3 cm

2 If the results are shown as a sector graph, the size of the smallest sector would be:

A 36° **B** 6° **C** 10° **D** 60° **E** 30°

3 For the set of numbers 1, 5, 2, 10, 1, 6, the difference between the mode and median is:

A 5.5 **B** 2.5 **C** 3.5 **D** 3.2 **E** 2

4 For the set of numbers 3, 2, 1, 5, 7, 3, 1, 3, the mean is:

A 3 **B** 5 **C** 6 **D** 22.375 **E** 3.125

5 Which of the following sets of numbers has a mode of 3 and a mean of 2?

A 1, 1, 2, 2, 3 **B** 2, 2, 2, 4, 5 **C** 1, 2, 3, 4, 5
D 1, 3, 3, 3, 0 **E** 1, 2, 3, 3, 3

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 For the set of numbers 1, 2, 5, 5, 8, 9, 10, 5, 3, 8:

a List them in ascending order.

b How many numbers are in the set?

c Calculate the:

i mean **ii** mode **iii** median **iv** range

d If each number in the set is doubled, what is the new mean?

2 A spinner is designed with different numbers in each sector. From the spinners **A** to **D** shown below:


A



B



C



D



a Which spinner has the lowest probability of landing on the number 1 in a single spin?

b Which spinner has a 50% probability of landing on the number 1 in a single spin?

c List the spinners in order, from the most likely to land on the number 1 to the least likely.

3 One card is randomly selected from a standard deck of 52 playing cards. Find the probability that the selected card is:

a red **b** black **c** a heart

d an ace **e** a king **f** a red 7

4 This stem-and-leaf plot shows the ages of a group of people in a room.

Stem	Leaf			
0	3	5		
1	1	7	9	
2	0	2	2	3
3	6	9		
4	3	7		

a How many people are in the room?

b What are the ages of the youngest and oldest people?

c For the data presented in this plot, find the:

i range **ii** median **iii** mode

5 A set of six scores is given as 17, 24, 19, 36, 22 and $\square$.

a Find the value of $\square$ if the mean of the scores is 23.

b Find the value of $\square$ if the median of the scores is 22.

c If the value of $\square$ is 14, and the score of 17 is removed from the set, calculate the new mean and median of the group.

Extended-response question

1 A pack of playing cards includes 13 cards for each suit: hearts, diamonds, clubs, and spades. Each suit has an ace, king, queen, jack, 2, 3, 4, 5, 6, 7, 8, 9, and 10. An ace is considered to have a higher value than all other cards. One card is drawn at random for the pack. Find the following probabilities.

a Pr(heart) **b** Pr(club) **c** Pr(diamond or spade)

d Pr(ace of hearts) **e** Pr(number less than 4) **f** Pr(king)

g Pr(ace or heart) **h** Pr(queen or club)

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Polygons and transformations

Multiple-choice questions

1 Which of the following names correctly describes a 6-sided polygon?

A decagon **B** quadrilateral **C** pentagon **D** nonagon **E** hexagon

2 A quadrilateral with 4 equal sides is best described as a:

A rectangle **B** rhombus **C** trapezium **D** kite **E** plane

3 How many axes of symmetry are in an equilateral triangle?

A 0 **B** 1 **C** 2 **D** 3 **E** 4

4 Which of the following statements is true?

A All rectangles are squares.

B A regular triangle is called an isosceles triangle.

C A square is a rhombus with all angles equal.

D A trapezium is also a rectangle.

E An isosceles triangle has three equal angles.


5 The order of rotation of a parallelogram is:

A 2 **B** 4 **C** 3 **D** 0 **E** 1

Short-answer questions

1 Name each of the following shapes.


a




b




c




d



e




f




2 Find the value of a


a



b




c




ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 For each of the following, find the value of each pronumeral.


a




b




c




d



e




f



4 State the coordinates of the vertices of the image triangle (A', B' and C') if triangle ABC is transformed in the following ways.


- **a** reflected in the x-axis
- **b** reflected in the y-axis
- **c** rotated about $O(0, 0)$ by 90° clockwise
- **d** rotated about $O(0, 0)$ by 90° anticlockwise
- **e** rotated about $O(0, 0)$ by 180°
- **f** translated 4 units to the left and 1 unit up
- **g** translated 3 units to the left and 2 units down




Extended-response question

1 **a** Draw any triangle in your workbook and extend each side, as shown opposite.

- **b** Measure the angles a, b and c. What should they add to?
- **c** Find the values of x, y and z (i.e. the exterior angles of the triangle).
- **d** What is the total of angles $x + y + z$?
- **e** Repeat for any quadrilateral, as shown opposite. What is the value of $w + x + y + z$?





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Equations

Multiple-choice questions

1 The solution to the equation $x - 3 = 7$ is:

A 4 **B** 10 **C** 9 **D** 11 **E** 3

2 The solution to the equation $2(x + 3) = 12$ is:

A 4.5 **B** 2 **C** 7 **D** 6 **E** 3

3 $m = 4$ is a solution to:

A $3m + 12 = 0$ **B** $\frac{m}{4} = 16$ **C** $10 - 2m = 2$

D $m + 4 = 0$ **E** $3m - 6 = 2$

4 The solution to $2p - 3 = 7$ is:

A $p = 4$ **B** $p = 5$ **C** $p = 2$ **D** $p = 10$ **E** $p = 3$

5 Ying thinks of a number. If he adds 4 to his number and then multiplies the sum by 5, the result is 35. What equation represents this information?

A $y + 9 = 35$ **B** $5y - 4 = 35$ **C** $5y + 4 = 35$

D $5(y + 4) = 35$ **E** $y + 20 = 35$

Short-answer questions

1 Solve:

a $x + 9 = 12$ **b** $\frac{x}{9} = 12$ **c** $x - 9 = 12$ **d** $9x = 12$

2 Solve:

a $3x + 3 = 9$ **b** $\frac{x}{2} + 6 = 12$ **c** $3(m - 1) = 18$

3 If $y = mx + b$, find:

a y when $m = 3$, $x = 4$ and $b = 8$ **b** b when $y = 20$, $m = 4$ and $x = 4$

c m when $y = 36$, $x = 3$ and $b = 12$


4 If $P = S - C$, find:

a P when $S = 190$ and $C = 87$ **b** S when $P = 47.9$ and $C = 13.1$


c C when $P = 384$ and $S = 709$

5 Use your knowledge of geometry and shapes to find the value of x in each of the following.


a




b



c



6 The perimeter of this triangle is 85 cm. Write an equation and then solve it to find the value of x.



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Extended-response question



1 The cost of hiring a hall for an event is $200 plus $40 per hour.
   a What is the cost of hiring the hall for 3 hours?
   b What is the cost of hiring the hall for 5 hours?
   c What is the cost of hiring the hall for n hours?
   d If the cost of hiring the hall totals $460, for how many hours was it hired?

Measurement


Multiple-choice questions

1 17 mm is the same as:
   A 0.17 m B 0.17 cm C 0.017 m D 170 cm E 1.7 m


2 0.006 L is the same as:
   A 6 mL B 36 mL C 10 mL D 60 mL E 600 mL


3 Which of the following shapes has the largest perimeter?
   A 
   B 
   C 
   D 
   E 


4 The perimeters of the two shapes shown here are equal. The area of the square is:
   A 30 m^2 B 7.5 m^2 C 56.25 m^2
   D 120 m^2 E 60 m^2







5 Which of the following shapes holds exactly 1 litre?
   A 

   B 

   C 

   D 

   E 

ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 Complete these conversions.


a 5 m = ____ cm **b** 6 km = ____ m

c 1800 mm = ____ m **d** 1.7 cm = ____ m


e 180 cm = ____ m **f** $5\frac{1}{2}$ L = ____ mL

2 Find the perimeter of each of the following.


a




b




c




d



e




f




3 Find the area of each of the following.


a




b




c




d



e




f




4 Calculate the volume of these solids.


a



b



c



5 Convert:

a 5 L = ____ mL **b** 7 cm^3 = ____ mL **c** $\frac{1}{4}$ L = ____ mL

d 3 kL = ____ L **e** 8 m^3 = ____ kL **f** 25 000 mL = ____ L

ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


6 How many hours and minutes are there between 2:30 pm Monday and 11:45 am Tuesday?

7 A busy airport operates 18 hours a day. An aircraft lands every 9 minutes. How many aircraft arrive at the airport each day?

8 The local time in Sydney and Melbourne is 2 hours behind Auckland and 10 hours ahead of London. When it is 5:00 pm in Auckland, what time is it in London?

Extended-response question

1 Robert has been given 36 m of fencing with which to build the largest rectangular enclosure that he can, using whole number side lengths.
   a Draw three possible enclosures and calculate the area of each one.
   b What are the dimensions of the rectangle that gives the largest possible area?
   c If Robert chooses the dimensions in part b and puts a post on each corner, and then posts every metre along the boundary, how many posts will he need?
   d If it takes 15 minutes to dig each hole for each post, how many hours will Robert spend digging?



ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Answers

Working with unfamiliar problems: Part 1

1 14, 27
2 123456787654321
3 625
4 60
5 431 x 52
6 $490
7 16
8 150°
9 270
10 discuss: e.g. count how many times 'the' appears on one page and multiply by the number of written pages in the book.
11 varies: e.g. 7.5 km for an average step of 75 cm
12 **a** $1 + 2 + 3 + 4 + 5 + 6 + 7 + 8 \times 9 = 100$
b many solutions e.g. $123 - 45 - 67 + 89 = 100$
13 2.5 cm, 75 cm (answers vary if thickness of glass considered)
14 $110, $130, $170
15 7 trips
16 $2\frac{2}{3}$ days

Working with unfamiliar problems: Part 2

1 17, 26, 35, 44, 53, 62, 71, 80
2 60°, 155°
3 12, 18, 20, 24, 30, 36 and 40
4 12 arrangements possible, 8 open box nets



5 25
6 231
7 2520
8 15
9 4
10 1100 (a square of 9 coins is approximately 80 cm^2); approximately $220
11 41°
12 7
13 7200°
14 99
15 e
16 204

Chapter 1

Exercise 1A

1 **a** Babylonian **b** Roman **c** Egyptian
2 **a i** I **ii** ∩ **iii** 𓆐 **iv** 𓎆
b i 𓃀 **ii** 𓂋 **iii** 𓃀
c i I **ii** V **iii** X **iv** L **v** C
3 5 – 1 = 4
4 **a i** 𓏺𓏺𓏺 **ii** 𓍢𓍢𓏺 **iii** 𓆐𓏼 **iv** 𓆐𓆐𓆐𓍢𓍢𓏼
b i 𓃀𓃀𓃀 **ii** 𓂋𓂋𓂋𓃀𓃀 **iii** 𓃀 𓃀
iv 𓃀𓃀 𓂋𓃀𓃀
c i II **ii** IX **iii** XXIV
iv CLVI
5 **a i** 33 **ii** 111 **iii** 213
iv 241
b i 12 **ii** 24 **iii** 71
iv 205
c i 4 **ii** 8 **iii** 16
iv 40
6 **a** XXXVI **b** 𓆐𓍢𓍢𓍢𓏺 **c** 𓂋𓂋𓃀𓃀 **d** DCLXXVIII
7 𓂋𓂋𓃀 (21)
8 CLXXXVIII (188)
9 𓍢𓍢𓍢𓏼𓏼
𓍢𓍢𓍢𓏼𓏼 (64)

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 **a** Roman **b** Babylonian **c** Roman

11 **a** IV **b** IX **c** XIV **d** XIX
e XXIX **f** XLI **g** XLIX **h** LXXXIX
i XCIX **j** CDXLIX **k** CMXXII **l** MMMCDI

12 A separate picture is to be used for each 1, 10, 100 etc. The number 999 uses 27 pictures.

13 **a** **i**  **ii**  **iii** 
iv  **v**
vi 
b third position $= 60 \times 60 = 3600$
c 216 000

14 Answers may vary.

Exercise 1B

1 **a** hundreds **b** thousands **c** tens **d** ones

2 **a** 263 **b** 7421 **c** 36 015 **d** 100 001

3 **a** B **b** E **c** D **d** A
e C **f** F **g** G

4 **a** 7 **b** 70 **c** 70 **d** 700
e 700 **f** 7000 **g** 700 **h** 70 000

5 **a** 20 **b** 2000 **c** 200 **d** 200 000

6 **a** true **b** false **c** true **d** true
e false **f** true **g** false **h** true

7 **a** $1 \times 10 + 7 \times 1$ **b** $2 \times 100 + 8 \times 10 + 1 \times 1$
c $9 \times 100 + 3 \times 10 + 5 \times 1$ **d** 2×10
e $4 \times 1000 + 4 \times 100 + 9 \times 10 + 1 \times 1$
f $2 \times 1000 + 3 \times 1$ **g** $1 \times 10\,000 + 1 \times 1$
h $5 \times 10\,000 + 5 \times 1000 + 5 \times 100 + 5 \times 10 + 5 \times 1$

8 **a** 347 **b** 9416 **c** 7020
d 600 003 **e** 4 030 700 **f** 90 003 020

9 **a** 44, 45, 54, 55
b 29, 92, 279, 729, 927
c 4, 23, 136, 951
d 345, 354, 435, 453, 534, 543
e 12 345, 31 254, 34 512, 54 321
f 1001, 1010, 1100, 10 001, 10 100

10 **a** 6 **b** 6 **c** 24

11 27

12 **a** $a \times 10 + b \times 1$
b $a \times 1000 + b \times 100 + c \times 10 + d \times 1$
c $a \times 100\,000 + a \times 1$

13 Position gives the place value and only one digit is needed for each place. There is also a digit for zero.

14 **a** You do not need to write the zeros.
b **i** 41×10^2 **ii** 37×10^4 **iii** 2177×10^4
c **i** 38 100 **ii** 7 204 000 **iii** 1 028 000 000
d **i** 1×10^6 **ii** 1×10^9 **iii** 1×10^{12}
iv 1×10^{100} **v** $1 \times 10^{\text{googol}}$

Exercise 1C

1 **a** add, plus, sum
b minus, take away, difference

2 **a** 10 **b** 69
c 12 **d** 20

3 **a** **i** 8 **ii** 27 **iii** 132
b **i** 6 **ii** 16 **iii** 8

4 **a** true **b** true **c** true
d false **e** true **f** false

5 **a** 18 **b** 19 **c** 32
d 140 **e** 21 **f** 9

6 **a** 64 **b** 97 **c** 579
d 748 **e** 948 **f** 5597
g 378 683 **h** 591 579 **i** 201 011

7 **a** 11 **b** 36 **c** 112
d 4 **e** 3111 **f** 10 001

8 **a** 24 **b** 75 **c** 95
d 133 **e** 167 **f** 297

9 **a** 24 **b** 26 **c** 108
d 222 **e** 317 **f** 5017

10 **a** 51 **b** 128 **c** 244
d 119 **e** 242 **f** 502

11 **a** 12 **b** 27 **c** 107
d 133 **e** 14 **f** 90
g 1019 **h** 0 **i** 3





12 38 hours

13 107 runs

14 32 cows

15 29 marbles

16 107 cards

17 **a** **i**  **ii** 
b **i** 
ii 

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

18 **a** Because $3 + 9$ is more than 10, so you have to carry.
b Because $8 - 6$ is easy, but $1 - 6$ means you have to carry.

19 **a** $c - b = a$ **b** $b - a = c$

20 **a** four ways (totals are 9, 10, 11 and 12)
b Answers may vary.

21 **a**

6	1	8
7	5	3
2	9	4

b

10	15	8
9	11	13
14	7	12

c

15	20	13
14	16	18
19	12	17

d

1	15	14	4
12	6	7	9
8	10	11	5
13	3	2	16

22 29 and 58

Exercise 1D

1 **a** 17 **b** 101 **c** 144 **d** 110
e 1005 **f** 143 **g** 201 **h** 1105

2 **a** 8 **b** 27 **c** 67 **d** 84
e 15 **f** 92 **g** 29 **h** 979

3 **a** 8 **b** 1 **c** 1 **d** 6
e 2 **f** 1 **g** 8 **h** 3

4 **a** 87 **b** 99 **c** 41 **d** 86
e 226 **f** 745 **g** 1923 **h** 5080

5 **a** 161 **b** 225 **c** 2229 **d** 1975

6 **a** 77 **b** 192 **c** 418 **d** 4208
e 1223 **f** 1982

7 **a** 31 **b** 20 **c** 19 **d** 58
e 36 **f** 112 **g** 79 **h** 72

8 **a** 16 **b** 47 **c** 485 **d** 166

9 1854 sheep

10 576 kilometres

11 **a** 1821 students **b** 79 students

12 **a**
$$\begin{array}{r} 3\,\boxed{8} \\ +\,5\,3 \\ \hline \boxed{9}\,1 \end{array}$$
b
$$\begin{array}{r} 1\,\boxed{1}\,4 \\ +\quad 7\,\boxed{7} \\ \hline \boxed{1}\,9\,1 \end{array}$$
c
$$\begin{array}{r} \quad\boxed{6}\,\boxed{7} \\ +\boxed{8}\,4\,7 \\ \hline 9\,1\,4 \end{array}$$

13 **a**
$$\begin{array}{r} 6\,\boxed{2} \\ -\,2\,8 \\ \hline \boxed{3}\,4 \end{array}$$
b
$$\begin{array}{r} 2\,\boxed{6}\,5 \\ -\boxed{1}\,8\,\boxed{4} \\ \hline 8\,1 \end{array}$$
c
$$\begin{array}{r} 3\,\boxed{0}\,\boxed{9}\,2 \\ -\quad 9\,2\,\boxed{7} \\ \hline \boxed{2}\,1\,6\,5 \end{array}$$

14 **a** **i** 29 **ii** 37
b yes
c no
d The balance of $-19 + 20$ is $+1$, so add 1 to 36.

15 **a** Answers may vary.
b Different combinations in the middle column can be used to create the sum.

16 **a**

62	67	60
61	63	65
66	59	64

b

101	115	114	104
112	106	107	109
108	110	111	105
113	103	102	116

17 452 and 526

Exercise 1E

1 **a** 20, 24, 28 **b** 44, 55, 66 **c** 68, 85, 102

2 **a** true **b** true
c false **d** true
e true **f** true
g false **h** true
i false

3 **a** 3 **b** 0
c 5 **d** 2

4 **a** 56 **b** 54
c 48 **d** 121
e 72 **f** 35
g 108 **h** 39

5 **a** 57 **b** 174
c 112 **d** 266
e 105 **f** 124
g 252 **h** 159

6 **a** 96 **b** 54
c 96 **d** 72

7 **a** 66 **b** 129
c 432 **d** 165
e 258 **f** 2849
g 2630 **h** 31 581

8 **a** 235 **b** 4173
c 3825 **d** 29 190

9 \$264

10 1680 metres

11 116 cards

12 no

13 **a**
$$\begin{array}{r} 3\,9 \\ \times\quad 7 \\ \hline 2\,\boxed{7}\,3 \end{array}$$
b
$$\begin{array}{r} 2\,5 \\ \times\,\boxed{5} \\ \hline 1\,2\,5 \end{array}$$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c
$$\begin{array}{r} 7\,9 \\ \times\ \boxed{3} \\ \hline \boxed{2}3\,7 \end{array}$$

d
$$\begin{array}{r} 1\,3\,2 \\ \times\ \ \boxed{8} \\ \hline 1\,0\,\boxed{5}\,6 \end{array}$$

e
$$\begin{array}{r} 2\boxed{7} \\ \times\ \ 7 \\ \hline \boxed{1}8\,9 \end{array}$$

f
$$\begin{array}{r} \boxed{3}\boxed{9} \\ \times\ \ \ 9 \\ \hline 3\,5\,1 \end{array}$$

g
$$\begin{array}{r} 2\,3\boxed{2} \\ \times\ \ \ \ 5 \\ \hline 1\,\boxed{1}6\,0 \end{array}$$

h
$$\begin{array}{r} \boxed{3}\boxed{1}\,4 \\ \times\ \ \ \ 7 \\ \hline \boxed{2}1\,9\,8 \end{array}$$

14 12 ways

15 **a** 3×21 **b** 9×52
c 7×32 **d** 5×97
e $a \times 38$ **f** $a \times 203$

16 three ways: (0, 1), (1, 5), (2, 9). You cannot carry a number to the hundreds column.

17 **a** Answers may vary; e.g.
$$\begin{array}{r} \boxed{2}1\boxed{7} \\ \times\ \ \ \ 7 \\ \hline \boxed{1}\,5\,1\boxed{9} \end{array}$$
b Answers may vary; e.g.
$$\begin{array}{r} 2\,9\,\boxed{5} \\ \times\ \ \ 3 \\ \hline 8\,\boxed{8}\boxed{5} \end{array}$$

18 6, 22

Exercise 1F

1 **a** 2 **b** 0 **c** 0 **d** 4

2 **a** 100 **b** 10 **c** 10 000

3 **a** incorrect, 104
b incorrect, 546
c correct
d incorrect, 2448

4 **a** 400 **b** 290 **c** 1830 **d** 4600
e 50 000 **f** 63 000 **g** 14 410 **h** 29 100 000

5 **a** 340 **b** 1440 **c** 6440 **d** 22 500
e 41 400 **f** 460 000 **g** 63 400 **h** 9 387 000

6 **a** 407 **b** 1368 **c** 1890 **d** 9416
e 18 216 **f** 40 768 **g** 18 620 **h** 33 858

7 **a** 209 **b** 546 **c** 555 **d** 2178

8 $2176

9 $6020

10 86 400 seconds

11 **a**
$$\begin{array}{r} 2\boxed{3} \\ \times\ 1\,7 \\ \hline 1\boxed{6}1 \\ 2\boxed{3}0 \\ \hline \boxed{3}\boxed{9}1 \end{array}$$
b
$$\begin{array}{r} 1\boxed{4}3 \\ \times\ \ \ 1\boxed{3} \\ \hline \ \ 4\,2\,9 \\ 1\,\boxed{4}\,3\,0 \\ \hline \boxed{1}\boxed{8}5\,9 \end{array}$$
c
$$\begin{array}{r} \ \ \boxed{4}\boxed{9} \\ \times\ \ 3\,7 \\ \hline \ \ 3\,4\,3 \\ \boxed{1}\,4\,\boxed{7}\,0 \\ \hline \boxed{1}\boxed{8}1\boxed{3} \end{array}$$
d
$$\begin{array}{r} \ \ 1\,2\,6 \\ \times\ \ \ 2\boxed{1} \\ \hline \ \ 1\,2\,6 \\ 2\,5\,2\,0 \\ \hline 2\,6\,\boxed{4}\boxed{6} \end{array}$$

12 60 480 degrees

13 One number is a 1.

14 **a** 39 984 **b** 927 908 **c** 4 752 188 **d** 146 420 482

15 **a** 1600 **b** 780 **c** 810 **d** 1000

16 **a** 84 000 **b** 3185

17 123, 117

Progress quiz

1 **a** ∩ II ∩ II **b** CXXXIV

2 $5 \times 10\,000 + 8 \times 100 + 6 \times 10 + 2 \times 1$

3 **a** 375 **b** 64 **c** 57 **d** 71

4 **a** 62 **b** 78

5 **a** 28 **b** 72 **c** 108 **d** 45

6 **a** 84 **b** 195

7 **a** 252 **b** 948 **c** 15 022

8 **a** 3800 **b** 1680 **c** 102 600

9 **a** 312 **b** 5072

10 **a** 1973 students **b** 77 students

Exercise 1G

1 **a** 2 **b** 3 **c** 7 **d** 12

2 **a** 1 **b** 2 **c** 2 **d** 5

3 **a** 1 **b** 1 **c** 5 **d** 5

4 **a** 4 **b** 3 **c** 6 **d** 5
e 7 **f** 9 **g** 8 **h** 11

5 **a** 21 **b** 19 **c** 19 **d** 41
e 29 **f** 21 **g** 302 **h** 98

6 **a** 22 **b** 31 **c** 17 **d** 7

7 **a** 26 **b** 1094 **c** 0 **d** 0

8 **a** 23 rem. 2 **b** 13 rem. 1 **c** 69 rem. 1
d 41 rem. 1 **e** 543 rem. 1 **f** 20 333 rem. 2
g 818 rem. 3 **h** 10 001 rem. 0

9 **a** 131 rem. 2 **b** 241 rem. 4 **c** 390 rem. 5
d 11 542 rem. 1

10 13 packs

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 124 packs

12 **a** \$243 **b** \$27

13 67 posts

14 15 taxis

15 19 trips; any remainder needs 1 more trip

16

2	9	12
36	6	1
3	4	18

17 **a** 1, 12 **b** 13, 7 **c** 4, 5

18 \$68

19 **a** a **b** 0 **c** 1

20 8 or 23

21 $a = b$ or $a = -b$

22 **a** 33 rem. 8 **b** 54 rem. 8 **c** 31 rem. 1
d 108 rem. 1 **e** 91 rem. 16 **f** 123 rem. 26

23 **a** 3 rem. 269 **b** 11 rem. 5 **c** 18 rem. 625

24

1	6	20	56
40	28	2	3
14	5	24	4
12	8	7	10

25 **a** 37 **b** 43 **c** 75 **d** 91
e 143 **f** 92

Exercise 1H

1 **a** up **b** down **c** up **d** up
e down **f** down

2 **a** larger **b** smaller **c** smaller **d** larger

3 **a** 60 **b** 30 **c** 120 **d** 190
e 200 **f** 900 **g** 100 **h** 600
i 2000

4 **a** 20 **b** 30 **c** 100 **d** 900
e 6000 **f** 90 000 **g** 10 000 **h** 10

5 **a** 130 **b** 80 **c** 150 **d** 940
e 100 **f** 1000 **g** 1100 **h** 2600
i 1000

6 **a** 120 **b** 160 **c** 100 **d** 12
e 40 **f** 2000 **g** 4000 **h** 100

7 **a** 1200 **b** 6300 **c** 20 000 **d** 8 000 000
e 5 **f** 16 **g** 10 **h** 25

8 Answers may vary.

9 $\approx$ 2100 scoops

10 $\approx$ 1200 sheep

11 $\approx$ 8 people

12 **a** 200 **b** 100 000 **c** 800 **d** 3 000 000

13 **a** **i** larger **ii** larger
b **i** larger **ii** larger
c **i** smaller **ii** smaller
d **i** larger **ii** larger

14 **a** **i** 9 **ii** 152 **iii** 10
iv 448
b One number is rounded up and the other is rounded down.
c **i** 3 **ii** 3 **iii** 1 **iv** 2
d If the numerator is decreased, then the approximation will be smaller. If the denominator is increased then the approximation will also be smaller. If the opposite occurs the approximation will be larger.

Exercise 1I

1 **a** addition **b** division
c multiplication **d** multiplication
e division **f** addition
g division **h** multiplication
i division **j** subtraction
k multiplication **l** division

2 **a** true **b** false **c** false **d** true

3 **a** 23 **b** 21 **c** 0 **d** 18
e 32 **f** 2 **g** 22 **h** 22
i 38 **j** 153 **k** 28 **l** 200

4 **a** 10 **b** 3 **c** 2 **d** 22
e 2 **f** 9 **g** 18 **h** 3
i 10 **j** 121 **k** 20 **l** 1

5 **a** 48 **b** 18 **c** 13 **d** 28
e 22

6 **a** 27 **b** 10 **c** 8 **d** 77
e 30 **f** 21 **g** 192

7 75 books

8 45 TV sets

9 **a** $(4 + 2) \times 3 = 18$ **b** $9 \div (12 - 9) = 3$
c $2 \times (3 + 4) - 5 = 9$ **d** $(3 + 2) \times (7 - 3) = 20$
e $(10 - 7) \div (21 - 18) = 1$
f $(4 + 10) \div (21 \div 3) = 2$
g $[20 - (31 - 19)] \times 2 = 16$
h $50 \div (2 \times 5) - 4 = 1$
i $(25 - 19) \times (3 + 7) \div 12 + 1 = 6$

10 first prize \$38, second prize \$8

11 **a** no **b** yes **c** no **d** yes
e yes **f** no **g** no **h** yes
i yes

12 **a** no **b** yes **c** no **d** yes

13 **a** b **b** 0 **c** $a + 1$ **d** b

14 **a** Multiply by 2 and add 1.
b Multiply by 3 and subtract 3, or subtract 1 and then multiply by 3.
c Multiply by itself and add 1.

Problems and challenges

1 The two people pay \$24 each, which is \$48 in total. Of that \$48 the waiter has \$3, leaving a balance of \$45 for the bill.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

2

2	9	4
7	5	3
6	1	8

3 5

4 One way is $(2 + 7) \times 11 + 4 - 3$

5 **a** 22 L/day **b** 7900 L/year

6 21, 495

Multiple-choice questions

1 B **2** C **3** E **4** A **5** B
6 A **7** D **8** C **9** B **10** A

Short-answer questions

1 **a** **i** III **ii** ∩∩∩I **iii** ⊂⊂⊂∩III

b **i** ◀▼▼ **ii** ▼.... **iii** ▼▼ ◀▼▼

c **i** XIV **ii** XL **iii** CXLVI

2 **a** 50 **b** 5000 **c** 50 000

3 **a** 459 **b** 363 **c** 95 **d** 217

4 **a** 128 **b** 2324 **c** 191 **d** 295

5 **a** 95 **b** 132 **c** 220 **d** 41
e 33 **f** 24 **g** 29 000 **h** 10 800
i 14 678

6 **a** 1413 **b** 351 **c** 46 rem 5 **d** 7540 rem 2

7 **a**
$$\begin{array}{r} 2\,\boxed{2}\,3 \\ +7\,3\,\boxed{8} \\ \hline 9\,6\,1 \end{array}$$

b
$$\begin{array}{r} \boxed{7}\,2\,\boxed{9} \\ -\,4\,\boxed{7}\,3 \\ \hline 2\,5\,6 \end{array}$$

c
$$\begin{array}{r} \boxed{5}\,3 \\ \times\ 2\,\boxed{7} \\ \hline \boxed{3}\,7\,1 \\ \boxed{1}\,0\,6\,0 \\ \hline \boxed{1}\,\boxed{4}\,3\,1 \end{array}$$

d
$$5\overline{)\,1\,\boxed{8}\,3}$$
$$\boxed{9}^{4}\,1^{1}\boxed{5}$$

8 **a** 70 **b** 3300 **c** 1000

9 **a** 800 **b** 400 **c** 5000 **d** 10

10 **a** 24 **b** 4 **c** 14 **d** 20
e 0 **f** 13

Extended-response questions

1 **a** 646 loads **b** 9044 kilometres
c \$36 430 **d** \$295

2 **a** 3034 sweets **b** 249
c liquorice sticks, 6 **d** yes (124)


Chapter 2

Exercise 2A


1 **a** $\bullet p$ **b**




c




d



e



f



2 **a** all in a straight line
b all meet at the same point

3 **a** ray **b** line **c** segment

4 **a** line **b** plane **c** plane **d** point
e line **f** plane **g** line **h** point

5 **a** point T **b** line CD **c** angle BAC
d plane **e** ray PQ **f** segment ST

6 **a** $\angle BOC$ **b** $\angle BAC$ **c** $\angle BEA$ **d** $\angle AOC$

7 **a** segments AB, BC, AC, BD, CD; angles ABD, CBD, CDB, BCD
b segments PQ, PR, QR, RS, QS; angles PQS, RQS, QRS, RSQ

8 **a** C, B and D **b** A, C and D

9 **a** no **b** yes

10 **a** 8 **b** 14

11 10

12 Missing numbers are 0, 1, 3, 6, 10, 15. For 5 points, add 4 to the previous total; for 6 points, add 5 to the previous total, and so on.

13 All segments should intersect at the same point; i.e. are concurrent.

14 **a** yes **b** no

15 number of segments $= \frac{n}{2}(n-1)$

Exercise 2B

1 Answers may vary.


2 **a** 2 **b** 3 **c** 4


3 **a** 50° **b** 145° **c** 90°
d 250°


4 **a** acute, 40° **b** acute, 55°
c right, 90° **d** obtuse, 125°
e obtuse, 165° **f** straight, 180°
g reflex, 230° **h** reflex, 270°
i reflex, 325°


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


5 **a** **i** 20° **ii** 25° **iii** 35°
iv 40° **v** 35°
b $\angle AOF$ (155°)


6 **a**



b



c



d



e


f


g


h


i


j


7 **a** 29° **b** 55° **c** 35° **d** 130°

8 Yes, the two smaller angles make up the larger angle.

9 **a** 180° **b** 360° **c** 90° **d** 270°
e 30° **f** 120° **g** 330° **h** 6°
i 54° **j** 63° **k** 255° **l** 129°

10 **a** 180° **b** 90° **c** 120° **d** 30°

11 **a** **i** 70° **ii** 70° **iii** 90°
iv 90° **v** 80° **vi** 80°
b no
c Subtract 360° until you have a number that is less than 180°, then change the sign if it is negative.

12 Use the revolution to get $360° - 60° = 300°$.

13 **a** 115° **b** 127.5° **c** 85° **d** 77.5°
e 122° **f** 176.5°

Exercise 2C

1 **a,b** angles should add to 90° **c** complementary

2 **a,b** angles should add to 180°
c supplementary

3 **a,b** angles should add to 360°
c vertically opposite angles

4 **a** $\angle BOC$ **b** $\angle AOD$ and $\angle BOC$
c $\angle COD$

5 **a** 60 **b** 15 **c** 135 **d** 70
e 40 **f** 115 **g** 37 **h** 240
i 130

6 **a** N **b** N **c** S **d** N
e C **f** C **g** C **h** S

7 **a** $EF \perp GH$ **b** $ST \perp UV$ **c** $WY \perp XY$

8 **a** 30 **b** 75 **c** 60 **d** 135
e 45 **f** 130

9 **a** No, should add to 90°. **b** Yes, they add to 180°.
c Yes, they add to 360°. **d** Yes, they are equal.
e No, they should be equal. **f** No, should add to 360°.

10 **a** 30 **b** 60 **c** 60 **d** 45
e 180 **f** 36

11 24°

12 **a** $a + b = 90$ **b** $a + b + c = 180$ **c** $a + b = 270$

13 Only one angle – the others are either supplementary or vertically opposite.

14 **a** 360° **b** 72 **c** 108
d

Regular shape	*a*	*b*
Triangle	120	60
Square	90	90
Pentagon	72	108
Hexagon	60	120
Heptagon	(360 ÷ 7)	(900 ÷ 7)
Octagon	45	135

Progress quiz

1 **a** G
b angle EGF or FGH or EGK or KGH and other names
c angle EGF or KGH and other names
d AD, IJ and EH
e angle ABF or angle KBD measures 125°

2 **a** $x = 28$ (angles in a right angle add to 90)
b $x = 75$ (angles on a straight line add to 180)
c $x = 64$ (vertically opposite)
d $x = 23$ (angles in a straight line add to 180)
e $x = 43$ (angles in a right angle add to 90)
f $x = 60$ (revolution)
g $x = 150$ (revolution)
h $x = 65$ (vertically opposite)
i $x = 270$ (revolution)
j $x = 50$ (revolution)
k $x = 115$ (angles in a straight line add to 180)
l $x = 34$ (vertically opposite)

3 **a** Vertically opposite angles are equal.
b 34°
c 180°

Exercise 2D

1 **a** 4 **b** no

2 **a** 2 **b** yes

3 **a** equal **b** supplementary
c equal **d** equal

4 **a** $\angle DEH$ **b** $\angle BEF$ **c** $\angle DEB$ **d** $\angle CBG$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

5 **a** $\angle FEG$ **b** $\angle DEB$ **c** $\angle GEB$ **d** $\angle ABC$

6 **a** $\angle CFG$ **b** $\angle BCF$

7 **a** 130, corresponding **b** 70, corresponding
c 110, alternate **d** 120, alternate
e 130, vertically opposite **f** 67, vertically opposite
g 65, cointerior **h** 118, cointerior
i 100, corresponding **j** 117, vertically opposite
k 116, cointerior **l** 116, alternate

8 **a** $a = 70, b = 70, c = 110$
b $a = 120, b = 120, c = 60$
c $a = 98, b = 82, c = 82, d = 82$
d $a = 90, b = 90, c = 90$
e $a = 95, b = 85, c = 95$
f $a = 61, b = 119$

9 **a** No, corresponding angles should be equal.
b Yes, alternate angles are equal.
c Yes, cointerior angles are supplementary.
d Yes, corresponding angles are equal.
e No, alternate angles should be equal.
f No, cointerior angles should be supplementary.

10 **a** 35 **b** 41 **c** 110 **d** 30
e 60 **f** 141

11 **a** 65 **b** 100 **c** 62 **d** 67
e 42 **f** 57 **g** 100 **h** 130
i 59

12 **a** 12 angles **b** two angles

13 120

14 **a** **i** The angle marked a is alternate to the 20° angle.
ii The angle marked b is alternate to the 45° angle.
b **i** $a = 25, b = 50$ **ii** $a = 35, b = 41$
iii $a = 35, b = 25$

15 **a** $a = 120, b = 120$ **b** 60
c opposite angles are equal

16 **a** Both angles do not add to 180°.
b The cointerior angles do not add to 180°.
c Alternate angles are not equal.

17 **a** **i** $\angle BDE$, alternate **ii** $\angle BED$, alternate
b add to 180°
c Three inside angles of a triangle add to 180°, which is always true.

18 Each triangle adds to 180°, so the total is 360°.

Exercise 2E

1 **a** $a = 65, b = 115$ **b** $a = 106, b = 106$
c $a = 55, b = 55$

2 **a** $\angle BED, a = 30$ **b** $\angle EBD, a = 70$
c $\angle ADC$ or $\angle ABD, a = 50$

3 **a** 60 **b** 120 **c** 115 **d** 123
e 50 **f** 80 **g** 60 **h** 65
i 45 **j** 60 **k** 55 **l** 335

4 **a** 130° **b** 120° **c** 55° **d** 75°
e 90° **f** 75°

5 **a** 50 **b** 150 **c** 60

6 **a** 1 **b** 2 **c** 2


7 **a** 30 **b** 60 **c** 40 **d** 30
e 120 **f** 10

8 **a** 60 **b** 45 **c** 12

9 **a** 110 **b** 250 **c** 40 **d** 110
e 40 **f** 300

Exercise 2F

1 **a–e**



2 Your two circles should just touch.

3 $\angle BAC$ and $\angle ABC$ should be equal.

4 $\angle AEC$ should be 90°.

5 $\angle BAD$ should be 60°.

6 $\angle AOE$ and $\angle BOE$ should be equal.

7 **a** Construct the two circles so that they have the same radius.
b Use two circles of the same size. Point E should be the midpoint of AB.


8 **a** Construct a 60° angle (see Question 4) and then bisect this angle by constructing the angle bisector to form two 30° angles (see Question 5).
b Construct an angle bisector of one of the 30°angles from part **a**.

9 **a** First, construct a 90° angle by constructing a perpendicular line and then construct the angle bisector of the 90° angle.
b Construct the angle bisector of one of the 45° angles from part **a**


10 No, the circles must overlap.

11 **a** Yes, follow the procedure as in Question 6.
b Yes, construct as for an acute or obtuse angle and draw the angle bisector on the reverse side of the vertex.

12 **a**




b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c



Exercise 2G


1–9 Answers may vary and can be checked by testing the properties of the constructions.

Problems and challenges

1 77.5°

2 720°

3



4 60°

5 6

Multiple-choice questions

1 C	**2** B	**3** D	**4** C	**5** D
6 E	**7** C	**8** A	**9** E	**10** B

Short-answer questions

1 **a** segment CD **b** $\angle AOB$ **c** point P
d plane **e** ray AC **f** line ST

2 **a** acute, 35° **b** obtuse, 115° **c** reflex, 305°

3 **a** 180° **b** 90° **c** 90° **d** 150°

4 **a** 20 **b** 230 **c** 35 **d** 41
e 15° **f** 38 **g** 60 **h** 120
i 30

5 **a** $a°$ and $b°$ **b** $a°$ and $d°$
c $a°$ and $c°$ **d** $b°$ and $c°$
e $c°$ and $d°$ or $b°$ and $d°$

6 **a** Yes, corresponding angles are equal.
b No, alternate angles should be equal.
c No, cointerior angles should be supplementary.

7 **a** 100 **b** 95 **c** 51 **d** 30
e 130 **f** 78

8 **a** 145° **b** 140° **c** 100°

9 **a** The angle should be divided in half.
b The angle should be 90°.

Extended-response questions

1 **a** **i** 32° **ii** 32° **iii** 148°
iv 58°
b **i** corresponding **ii** cointerior
iii supplementary
c **i** 21° **ii** 159° **iii** 69°

2 **a** 12 pieces
b 30
c **i** 15 **ii** 22.5 **iii** 20
iv 24

Chapter 3

Exercise 3A

1 **a** M **b** N **c** F **d** N
e F **f** F **g** M **h** F
i N **j** M **k** N **l** F

2 **a** F **b** N **c** M **d** N
e N **f** N **g** N **h** M
i F **j** M **k** F **l** N

3 **a** 1, 2, 5, 10
b 1, 2, 3, 4, 6, 8, 12, 24
c 1, 17
d 1, 2, 3, 4, 6, 9, 12, 18, 36
e 1, 2, 3, 4, 5, 6, 10, 12, 15, 20, 30, 60
f 1, 2, 3, 6, 7, 14, 21, 42
g 1, 2, 4, 5, 8, 10, 16, 20, 40, 80
h 1, 2, 3, 4, 6, 12
i 1, 2, 4, 7, 14, 28

4 **a** 5, 10, 15, 20, 25, 30
b 8, 16, 24, 32, 40, 48
c 12, 24, 36, 48, 60, 72
d 7, 14, 21, 28, 35, 42
e 20, 40, 60, 80, 100, 120
f 75, 150, 225, 300, 375, 450
g 15, 30, 45, 60, 75, 90
h 100, 200, 300, 400, 500, 600
i 37, 74, 111, 148, 185, 222

5 **a** 3, 18 **b** 5 **c** 1, 4, 6, 9, 12, 24
d 3, 4, 5, 8, 12, 15, 24, 40, 120

6 **a** 22 **b** 162 **c** 21 **d** 117

7 **a** 24 **b** 1 **c** 1, 4, 9, 16, 25

8 **a** 12×16 **b** 21×15
c 12×15 **d** 11×11
e 12×28 or 24×14 or 21×16
f 19×26 or 38×13

9 **a** 20 min **b** 5 laps **c** 4 laps

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

10 **a** 25 **b** 0 **c** 23
d 2, 7, 12, 17, 37, 47, 62, 87, 137, 287
e 2

11 **a** false **b** true **c** false **d** false
e true

12 **a** 840 **b** 2520

13 **a** 1, 2, 4, 5, 10, 20, 25, 50, 100
b 1, 2, 4, 5, 10, 20, 25, 50, 100

14 Answers may vary, but they should be multiples of 9.

15 The larger number gives the reply. Any number is a multiple of its factors. So the answer is 'yes'.

16 Check the output each time.

Exercise 3B

1 **a** 1, 2, 4 **b** 4

2 Factors of 18 are 1, 2, 3, 6, 9 and 18.
Factors of 30 are 1, 2, 3, 5, 6, 10, 15 and 30.
Therefore, the HCF of 18 and 30 is 6.

3 **a** 24, 48 **b** 24

4 Multiples of 9 are 9, 18, 27, 36, 45, 54, 63, 72, 81 and 90.
Multiples of 15 are 15, 30, 45, 60, 75, 90, 105 and 120.
Therefore, the LCM of 9 and 15 is 45.

5 **a** 1 **b** 1 **c** 2 **d** 3
e 4 **f** 15 **g** 50 **h** 24
i 40 **j** 25 **k** 21 **l** 14

6 **a** 10 **b** 3 **c** 1 **d** 1
e 8 **f** 12

7 **a** 36 **b** 21 **c** 60 **d** 110
e 12 **f** 10 **g** 36 **h** 18
i 60 **j** 48 **k** 132 **l** 105

8 **a** 30 **b** 84 **c** 12 **d** 45
e 40 **f** 36

9 **a** HCF = 5, LCM = 60 **b** HCF = 12, LCM = 24
c HCF = 7, LCM = 42 **d** HCF = 9, LCM = 135

10 312

11 9

12 LCM = 780, HCF = 130

13 **a** 12 min
b Andrew 9 laps, Bryan 12 laps, Chris 6 laps
c 3 times (including the finish)

14 **a** 8, 16 **b** 24, 32

15 1 and 20; 2 and 20; 4 and 20; 5 and 20; 10 and 20; 4 and 5; 4 and 10.

16 no

17 **a** 2520
b 2520
c Identical answers; 2520 is already divisible by 10, so adding 10 to list does not alter LCM.
d 27 720 ($2^3 \times 5 \times 7 \times 9 \times 11$)

Exercise 3C

1 **a** not even
b digits do not sum to a multiple of 3
c 26 is not divisible by 4
d last digit is not 0 or 5
e not divisible by 3 (sum of digits is not divisible by 3)
f 125 is not divisible by 8 and it is not even
g sum of digits is not divisible by 9
h last digit is not 0

2 **a** 2 **b** 2 **c** 0 **d** 0

3 3, 6 and 9

4 2, 5 and 10

5 **a** **i** yes **ii** no **iii** yes
iv yes **v** no **vi** yes
vii no **viii** yes **ix** no
x yes **xi** no **xii** yes
xiii yes **xiv** no **xv** no
xvi yes **xvii** no **xviii** no

6 **a** 10, 15, 20, 25, 30
b 12, 15, 18, 21, 24
c 10, 12, 14, 16, 18
d 12, 18, 24, 30, 36
e 16, 24, 32, 40, 48
f 18, 27, 36, 45, 54
g 10, 20, 30, 40, 50
h 12, 16, 20, 24, 28
(other answers possible)

7

Number	Divisible by 2	Divisible by 3	Divisible by 4	Divisible by 5	Divisible by 6	Divisible by 8	Divisible by 9	Divisible by 10
243 567	✗	✓	✗	✗	✗	✗	✓	✗
28 080	✓	✓	✓	✓	✓	✓	✓	✓
189 000	✓	✓	✓	✓	✓	✓	✓	✓
1 308 150	✓	✓	✗	✓	✓	✗	✓	✓
1 062 347	✗	✗	✗	✗	✗	✗	✗	✗

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

8 a no b $14.25
9 2, 4, 8, 11, 22, 44
10 200
11 15
12 980
13 966
14 a yes
b Multiples of 3; adding a multiple of 3 does not change the result of the divisibility test for 3.
c 18
15 a 0, 4, 8 b 2, 6
16 36
17 a 11 b 9 c 7 d 5 e 3
18 a 11, 22, 33, 44, 55, 66, 77, 88, 99
b 0
c 110, 121, 132, 143, 154, ...
d equals the centre digit or 11 plus the centre digit
e difference is 0 or 11
f Sum the odd- and even-placed digits. If the difference between these two sums is 0 or is divisible by 11, then the number is divisible by 11.
g i yes ii yes iii no
iv yes v yes vi yes

Exercise 3D

1 no
2 yes
3 2, 3, 5, 7, 11, 13, 17, 19, 23, 29
4 4, 6, 8, 9, 10, 12, 14, 15, 16, 18
5 101
6 211
7 a C b P c C d P
e C f C g P h P
i C j C k C l P
m P n P o C p P
8 a 2, 3, 7 b 3, 13 c 2, 3, 5 d 5
e 2, 7 f 2, 3
9 a 32, 33, 34, 35, 36, 38, 39, 40, 42, 44, 45, 46, 48, 49
b 51, 52, 54, 55, 56, 57, 58, 60, 62, 63, 64, 65, 66, 68, 69
c 81, 82, 84, 85, 86, 87, 88, 90, 91, 92, 93, 94, 95, 96, 98, 99
10 a 5, 11 b 7, 13 c 11, 13 d 11, 17
e 5, 73 f 7, 19
11 14
12 5 and 7, 11 and 13, 17 and 19, as well as other pairs
13 17 and 71, as well as other pairs
14 (5, 7, 11), as well as other groups
15 $32 = 29 + 3$, $34 = 29 + 5$, $36 = 29 + 7$, $38 = 31 + 7$, $40 = 37 + 3$, $42 = 31 + 11$, $44 = 41 + 3$, $46 = 41 + 5$, $48 = 41 + 7$
16 $2 + 3 = 5$ and $2 + 5 = 7$. All primes other than 2 are odd and two odds sum to give an even number that is not a prime. So any pair that sums to a prime must contain an even prime, which is 2.
17 Check your spreadsheet using smaller primes.

Exercise 3E

1 E
2 D
3

Value	Base number	Index number	Basic numeral
2^3	2	3	8
5^2	5	2	25
10^4	10	4	10000
2^7	2	7	128
1^{12}	1	12	1
12^1	12	1	12
0^5	0	5	0

4 a 3^3 b 2^5 c 15^4 d 10^4
e 6^2 f 20^3 g 1^6 h 4^3
i 100^2
5 a $3^2 \times 5^2$ b $2^2 \times 7^3$ c $9^2 \times 12^2$
d $5^3 \times 8^2$ e $3^3 \times 6^3$ f $7^4 \times 13^2$
g $4^3 \times 7^1 \times 13^1$ h $9^3 \times 10^2$ i $2^3 \times 3^2 \times 5^2$
6 $2^6 \times 3^5 \times 5^4$
7 a $2 \times 2 \times 2 \times 2$
b 17×17
c $9 \times 9 \times 9$
d $3 \times 3 \times 3 \times 3 \times 3 \times 3 \times 3$
e $14 \times 14 \times 14 \times 14$
f $8 \times 8 \times 8 \times 8 \times 8 \times 8 \times 8 \times 8$
g $10 \times 10 \times 10 \times 10 \times 10$
h $54 \times 54 \times 54$
8 a $3 \times 3 \times 3 \times 3 \times 3 \times 2 \times 2 \times 2$
b $4 \times 4 \times 4 \times 3 \times 3 \times 3 \times 3$
c $7 \times 7 \times 5 \times 5 \times 5$
d $4 \times 4 \times 4 \times 4 \times 4 \times 4 \times 9 \times 9 \times 9$
e $5 \times 7 \times 7 \times 7 \times 7$
f $2 \times 2 \times 3 \times 3 \times 3 \times 4$
g $11 \times 11 \times 11 \times 11 \times 11 \times 9 \times 9$
h $20 \times 20 \times 20 \times 30 \times 30$
9 a 32 b 64 c 1000 d 72
e 10000 f 1000 g 64 h 121
10 a 25 b 1 c 10 d 64
e 128 f 8 g 22 h 900
i 8
11 a 4 b 2 c 3 d 6
e 3 f 2 g 2 h 4
12 a < b > c = d <
e > f > g < h <
13 125

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 **a** 126 **b** 55 min **c** 244, 140, 625
d 75 min **e** Approx. 75 000 000 000 000 000

15 **a** + **b** × **c** − **d** ÷
e × **f** −

16 x^y

17 $a = 2, b = 4$

18 **a** 1, 2, 6, 24, 120, 720
b **i** $2^4 \times 3^2 \times 5 \times 7$ **ii** $2^7 \times 3^2 \times 5 \times 7$
iii $2^7 \times 3^4 \times 5 \times 7$ **iv** $2^8 \times 3^4 \times 5^2 \times 7$
c 0
d 0
e It is the index number on the base 5.
i 1 **ii** 1 **iii** 3 **iv** 6
f e.g. 23! × 4!

Exercise 3F

1 composite: 15, 8, 9, 27, 4, 12; prime: 13, 7, 5, 23, 11, 2

2 **a** 5, 4 **b** 6, 2 **c** 10, 2, 5

3 **a** 3, 3, 2, 5 **b** 2, 2, 2, 7 **c** 5, 11, 2, 2

4 **a** $2^3 \times 3^2$ **b** $3^4 \times 5^2$ **c** $2^2 \times 3 \times 7^2$
d $2^2 \times 3^2 \times 11^2$

5 **a** $2^3 \times 3^2$ **b** $2^3 \times 3$ **c** 2×19 **d** $2^2 \times 11$
e $2^2 \times 31$ **f** $2^4 \times 5$ **g** $2^5 \times 3$ **h** 2^4
i 3×5^2 **j** 3×37 **k** 2^6 **l** $2^3 \times 7$

6 **a** $2^3 \times 3 \times 5^2$ **b** $2^5 \times 5^2$ **c** $2^3 \times 5^4$
d $2^5 \times 3 \times 5^2$ **e** $2^6 \times 5^6$ **f** $2^3 \times 3^2 \times 5^4$
g $2^2 \times 5 \times 41$
h $2 \times 3 \times 5 \times 23$


7 **a** D **b** A **c** C **d** B

8 2310


9 **a** $144 = 2^4 \times 3^2$, $96 = 2^5 \times 3$
b HCF $= 2^4 \times 3 = 48$

10 **a** $25\,200 = 2^4 \times 3^2 \times 5^2 \times 7$, $77\,000 = 2^3 \times 5^3 \times 7 \times 11$
b HCF $= 2^3 \times 5^2 \times 7 = 1400$

11




12 **i** 424 cannot have a factor of 5.
ii 8 is not a prime number.
iii $\therefore 424 = 2^3 \times 53$




13 **a** **i** $5 \times 10 \neq 60$ **ii** 6 is not a prime number.
iii A 2 has been left off.
b $60 = 2^2 \times 3 \times 5$

14



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press



15 $2 \times 3 \times 5 \times 7 = 210$ $2 \times 3 \times 7 \times 11 = 462$
$2 \times 3 \times 5 \times 11 = 330$ $2 \times 3 \times 7 \times 13 = 546$
$2 \times 3 \times 5 \times 13 = 390$ $2 \times 3 \times 7 \times 17 = 714$
$2 \times 3 \times 5 \times 17 = 510$ $2 \times 3 \times 7 \times 19 = 798$
$2 \times 3 \times 5 \times 19 = 570$ $2 \times 3 \times 7 \times 23 = 966$
$2 \times 3 \times 5 \times 23 = 690$ $2 \times 5 \times 7 \times 11 = 770$
$2 \times 3 \times 5 \times 29 = 870$ $2 \times 5 \times 7 \times 13 = 910$
$2 \times 3 \times 5 \times 31 = 930$ $2 \times 3 \times 11 \times 13 = 858$

Progress quiz

1 **a** 16: 1, 2, 4, 8, 16
b 70: 1, 2, 5, 7, 10, 14, 35, 70

2 **a** 7, 14, 21, 28 **b** 20, 40, 60, 80

3 **a** 5 **b** 18

4 **a** 24 **b** 45

5 **a** no, last 2 digits not $\div$ 4
b yes, sum of 21 $\div$ 3
c yes, sum of 24 $\div$ 3, and even $\div$ 2
d yes, sum of 27 $\div$ 9

6 2, 3, 4, 5, 6, 10, 12, 20, 24, 30, 40, 60, 120

7 **a** C: large number of factors
b N: only one factor
c P: only two factors, 1 and itself
d N

8 **a** 5, 7
b 2, 3

9 **a** 5^4
b $3^2 \times 7^5$

10 **a** $3 \times 3 \times 3 \times 3 = 81$
b $1 \times 1 \times 1 \times 1 \times 3 \times 3 = 9$
c $5 \times 10 \times 10 \times 10 \times 10 = 50\,000$
d $4 \times 4 = 16$
e $9 \times 9 - 3 \times 3 \times 3 \times 2 = 81 - 54$
$= 27$

11 **a** $24 = 2 \times 2 \times 2 \times 3$
$= 2^3 \times 3$
b $180 = 2^2 \times 3^2 \times 5$

Exercise 3G

1 36 cm^2, a square number

2 $1^2 = 1$, $2^2 = 4$, $3^2 = 9$, $4^2 = 16$, $5^2 = 25$, $6^2 = 36$, $7^2 = 49$, $8^2 = 64$, $9^2 = 81$, $10^2 = 100$, $11^2 = 121$, $12^2 = 144$, $13^2 = 169$, $14^2 = 196$, $15^2 = 225$

3 **a** A square is not possible.
b draw a 4 by 4 square

4 **a** 36 **b** 25 **c** 121 **d** 100
e 49 **f** 144

5 **a** 5 **b** 4 **c** 10 **d** 7 cm

6 **a** 64 **b** 49 **c** 1 **d** 144
e 9 **f** 225 **g** 25 **h** 0
i 121 **j** 10 000 **k** 289 **l** 1089

7 **a** 5 **b** 3 **c** 1 **d** 11
e 0 **f** 9 **g** 7 **h** 4
i 2 **j** 12 **k** 20 **l** 13

8 **a** 50 **b** 80 **c** 90 **d** 27

9 **a** 30 **b** 64 **c** 65 **d** 36
e 4 **f** 0 **g** 81 **h** 4
i 13

10 64, 81, 100

11 121, 144, 169, 196

12 **a** 4 and 81 **b** 36 and 121; other answers possible

13 1, 9 and 49

14 **a** 144 **b** 144 **c** $a = 3, b = 4$
d Answers may vary; e.g. $4^2 \times 5^2$ and 20^2

15 **a** $3^2 + 4^2 = 9 + 16 = 25$ **b** 10^2
c 15^2 **d** 50^2

16 **a** 121 and 12 321 **b** 1 234 321
c 1 234 321

17 no, $9^2 = 81$

18 **a** false **b** false **c** true
d true **e** true (if $a \geq 0$) **f** false
g false **h** false

Exercise 3H

1 **a** 8, 11, 14, 17, 20 **b** 32, 31, 30, 29, 28
c 52, 48, 44, 40, 36 **d** 123, 130, 137, 144, 151

2 **a** 3, 6, 12, 24, 48 **b** 5, 20, 80, 320, 1280
c 240, 120, 60, 30, 15 **d** 625, 125, 25, 5, 1

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 **a** ratio of 3 **b** difference subtracting 2
c difference adding 11 **d** neither
e ratio of $\frac{1}{2}$ **f** neither
g neither **h** difference subtracting 3

4 **a** 23, 28, 33 **b** 44, 54, 64
c 14, 11, 8 **d** 114, 116, 118
e 27, 18, 9 **f** 5, 4, 3
g 505, 606, 707 **h** 51, 45, 39

5 **a** 32, 64, 128 **b** 80, 160, 320
c 12, 6, 3 **d** 45, 15, 5
e 176, 352, 704
f 70 000, 700 000, 7 000 000
g 16, 8, 4 **h** 76, 38, 19

6 **a** 50, 32, 26 **b** 25, 45, 55
c 32, 64, 256 **d** 9, 15, 21
e 55, 44, 33 **f** 333, 111
g 70, 98, 154 **h** 126, 378, 3402

7 **a** 17, 23, 30 **b** 16, 22, 29
c 36, 49, 64 **d** 17, 12, 6
e 17, 19, 23 **f** 47, 95, 191
g 5, 7, 6 **h** 32, 40, 38

8 **a** 49, 64, 81; square numbers
b 21, 34, 55; Fibonacci
c 216, 343, 512; cubes (i.e. powers of 3)
d 19, 23, 29; primes
e 16, 18, 20; composite
f 161, 171, 181; palindromes

9 **a** 115, 121, 128 **b** 24, 48, 16
c 42, 41, 123 **d** 9, 6, 13

10 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 (total = 55)

11 **a** 39 **b** 57
c 110 **d** 192

12 1, 0, 0, 1, 2

13 difference is 0, ratio is 1, Jemima


14 **a** 55 **b** 100 **c** 2485 **d** 258

15 **a** 3 **b** 10 **c** 45 **d** 276
e $n \times (n - 1) \div 2$


16 **a** 135 **b** 624 **c** 945

Exercise 3I


1 **a**




b



c




d




e




2




3 **a**




b




c





d



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


e 

f 

4 a i 


ii 4, 7, 10, 13, 16

iii 4 sticks are required to start, then 3 are added

b i 


ii 3, 5, 7, 9, 11

iii 3 sticks are required at the start, then 2 are added

c i 


ii 6, 11, 16, 21, 26

iii 6 sticks are required to start, then 5 are added

d i 


ii 7, 12, 17, 22, 27

iii 7 sticks are required to start, then 5 are added

e i 


ii 6, 11, 16, 21, 26

iii 6 sticks are required to start, then 5 are added

f i 

ii 4, 7, 10, 13, 16

iii 4 sticks are required to start, then 3 are added


5 a 

b

No. of crosses	1	2	3	4	5
No. of sticks required	4	8	12	16	20

c Number of sticks $= 4 \times$ number of crosses

d 80 sticks

6 a 

b

No. of fence sections	1	2	3	4	5
No. of planks required	4	7	10	13	16

c Number of planks $= 3 \times$ number of fence sections $+ 1$

d 61 planks

7 a

No. of tables	1	2	3	4	5
No. of students	5	8	11	14	17

b Number of students $= 3 \times$ number of tables $+ 2$

c 23 students

d 21 tables

8 a

Spa length	1	2	3	4	5	6
No. of tiles	8	10	12	14	16	18

b Number of tiles $= 2 \times$ spa length $+ 6$


c 36 tiles


d 12 units

9 A

10 A

11 Answers may vary.

a 

b 


c 

d 

e 

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

f



12 **a** 5 **b** 41 **c** $4g + 1$ **d** 16

13 **a** $m + n$

b number of pieces for each new panel

c



14 **b**

No. of straight cuts	1	2	3	4	5	6	7
No. of sections created	2	4	7	11	16	22	29

c 56

d 211

Exercise 3J

1 **a** true **b** false **c** true **d** true

2 C

3 B

4 **a** A **b** D **c** B **d** C

5 **a**

input	4	5	6	7	10
output	7	8	9	10	13

b

input	5	1	3	21	0
output	10	2	6	42	0

c

input	11	18	9	44	100
output	3	10	1	36	92

d

input	5	15	55	0	100
output	1	3	11	0	20

6 **a**

input	1	2	3	4	5
output	7	17	27	37	47

b

input	6	8	10	12	14
output	7	8	9	10	11

c

input	5	12	2	9	0
output	16	37	7	28	1

d

input	3	10	11	7	50
output	2	16	18	10	96

7 **a** $output = input + 1$ **b** $output = 4 \times input$

c $output = input + 11$ **d** $output = input \div 6$

8 $output = 3 \times input$

9 $output = input - 9$

10 **a**

input	3	6	8	12	2
output	7	34	62	142	2

b

input	6	12	1	3	8
output	5	3	25	9	4

c

input	5	12	2	9	0
output	30	156	6	90	0

d

input	3	10	11	7	50
output	15	190	231	91	4950

11 **a**

input	c	d	$2p$	b^2	www
output	$c + 6$	$d + 6$	$2p + 6$	$b^2 + 6$	$www + 6$

b

input	t	k	p^2	$2f$	ab
output	$3t - 2$	$3k - 2$	$3p^2 - 2$	$6f - 2$	$3ab - 2$

12

input	b	d	e	g^2	mn	x	c	0	1
output	bc	cd	ec	g^2c	cmn	xc	c^2	0	c

$ouput = c \times input$

13 **a** $output = 2 \times input + 1$; $output = 3 \times input - 2$

b infinite

14 **a** **i** $output = 2 \times input - 3$

ii $output = 4 \times input + 1$

iii $output = 5 \times input - 1$


iv $output = input \div 6 + 2$

v $output = 10 \times input + 3$


vi $output = 4 \times input - 4$

Exercise 3K

1



2




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 C

4 C

5 a x-axis
b y-axis
c origin
d first
e y-coordinate
f x, y, x, y

6




7 a $A(1, 4)$, $B(2, 1)$, $C(5, 3)$, $D(2, 6)$, $E(4, 0)$, $F(6, 5)$, $G(0, 3)$, $H(4, 4)$

b $M(1, 2)$, $N(3, 2)$, $P(5, 1)$, $Q(2, 5)$, $R(2, 0)$, $S(6, 6)$, $T(0, 6)$, $U(5, 4)$

8 a

input (x)	*output* (y)
0	2
1	3
2	4
3	5


b



9 a

input (x)	*output* (y)
1	0
2	1
3	2
4	3


b




10 a

input (x)	*output* (y)
0	0
1	2
2	4
3	6


b




11



12



13 a




b (4, 0), (4, 3), (6, 3), (6, 0), but answers may vary.

c Answers may vary.

d Answers may vary.

14 a $B(1, 4)$, $C(4, 4)$, $D(4, 1)$

b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

15 **a** HELP
b (4, 4), (5, 1), (3, 1), (3, 4), (5, 1), (5, 4)
c key under pot plant
d 215100325134510011540044512551 43

16 **a** $D(4, 5)$ **b** $D(4, 1)$ **c** $D(0, 0)$ **d** $D(1, 5)$

17 **a** *output* = *input* + 2
b *output* = *input* × 3
c *output* = *input* ÷ 2

18 **a** (3, 6) or any with $x = 3$
b any point on a vertical line with $x = 3$
c (3, 5)

19 **a** $M(3, 2)$
b (1, 2)
c Find the average of the x values, then the average of the y values.
d (4, 2)
e (2.5, 3.5)
f $(-0.5, -0.5)$
g (5, 3)

Problems and challenges

1 101
2 **a** 28 (1, 2, 4, 7, 14)
b 1, 2, 4, 8, 16, 31, 62, 124, 248
3 **a** 18 tulips per bunch
b 7 red, 6 pink and 8 yellow bunches
4 $14 + 18 = 32$
5 $5^2 = 4^2 + 9, 6^2 = 5^2 + 11$
6 Answers may vary. Check that the answer is the whole number that you are looking for.
7 602
8 1, 5, 7, 11, 13, 17, 19, 23, 25, 29, 31, 35

Multiple-choice questions

1 B **2** E **3** C **4** E **5** B
6 B **7** D **8** A **9** C **10** E
11 B **12** D

Short-answer questions

1 **a** 1, 2, 3, 4, 5, 6, 8, 10, 12, 15, 20, 24, 30, 40, 60, 120
b For example, 1200, 1440, 1800

2 **a** 8, 16, 24, 32, 40, 48, 56, 64, 72, 80, 88, 96 7, 14, 21, 28, 35, 42, 49, 56, 63, 70, 77, 84
b 7, 13

3 **a** **i** 5 **ii** 2 **iii** 24
b **i** 65 **ii** 18 **iii** 88

4 **a** composite 21, 30, 16; prime 11, 7, 3, 2
b only one, 13

5 **a** 2, 5, 7, 11 **b** 30, 42, 70

6 **a** 6^8 **b** $5^4 \times 2^5$

7 **a** 2^5 **b** $2^3 \times 5^2$ **c** $3^2 \times 5^2$

8 **a** 10 **b** 3 **c** 4

9 **a** 16 **b** 7 **c** 397 **d** 131

10 **a** no **b** yes **c** no

11 **a**

Number	Divisible by 2	Divisible by 3	Divisible by 4	Divisible by 5
84 539 424	✓	✓	✓	✗

Number	Divisible by 6	Divisible by 8	Divisible by 9	Divisible by 10
84 539 424	✓	✓	✗	✗

Explanation:
84 539 424 is an even number, therefore is divisible by 2.
84 539 424 has a digit sum of 39, therefore is divisible by 3, but not by 9.
84 539 424 is divisible by 2 and 3, therefore is divisible by 6.
The last two digits are 24, which is divisible by 4.
The last three digits are 424, which is divisible by 8.
The last digit is a 4, therefore not divisible by 5 or 10.
b many possible answers
c Any six-digit number ending in 0 with sum of digits = 243.


12 **a** 5 **b** 50 **c** 13 **d** 18
e 14 **f** 20

13 **a** 36, 39, 42 **b** 43, 35, 27 **c** 112, 70, 28

14 **a** 280, 560, 1120 **b** 900, 300, 100 **c** 100, 2500, 6250

15 **a** 168, 51, 336, 46, 672, 41
b 212, 307, 421, 554, 706, 877

16 **a**



b

No. of rhombuses	1	2	3	4	5
No. of sticks required	4	7	10	13	16

c Four sticks are required to start the pattern, and an additional three sticks are required to make each next term in the pattern.

17 **a** 5 **b** 32 **c** $3g + 2$
d 21 windows

18 **a**

input	3	5	7	12	20
output	8	10	12	17	25

b

input	4	2	9	12	0
output	15	11	25	31	7

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

19 **a** *output* $=$ *input* $+ 9$

b *output* $= 12 \times$ *input* $+ 8$

c *output* $= 2 \times$ *input* $+ 1$

d *output* $= 10 -$ *input*

20 **a** $A(1, 3)$, $B(3, 4)$, $D(2, 1)$

b $C(4, 2)$

c $E(5, 0)$

Extended-response questions

1 **a** area $= 3^3 \times 5^3$ cm^2, perimeter $= 2 \times 3^3 + 2 \times 5^3$ cm

b area $= 16^3$ or 4^6 or 2^{12}, perimeter $= 16^2$ or 4^4 or 2^8


c $a^4 \times c^2$

d 16^2 or 4^4 or 2^8

e 3^x

2 **a** **i** 1 **ii** 2

b



c

Rows	1	2	3	4	5	6
Desks per row	4	4	4	4	4	4
Total no. of desks	4	8	12	16	20	24
Total no. of rhombuses	0	3	6	9	12	15

d Number of rhombuses $= 3 \times$ (number of rows $- 1$)

$= 3(n - 1)$

e

Rows	1	2	3	4	5	6	7	8
Desks per row	5	5	5	5	5	5	5	5
Total desks	5	10	15	20	25	30	35	40
Rhombuses	0	4	8	12	16	20	24	28

Rows	1	2	3	4	5	6	7	8
Desks per row	6	6	6	6	6	6	6	6
Total desks	6	12	18	24	30	36	42	48
Rhombuses	0	5	10	15	20	25	30	35

Rows	1	2	3	4	5	6	7	8
Desks per row	7	7	7	7	7	7	7	7
Total desks	7	14	21	28	35	42	49	56
Rhombuses	0	6	12	18	24	30	36	42

Rows	1	2	3	4	5	6	7	8
Desks per row	8	8	8	8	8	8	8	8
Total desks	8	16	24	32	40	48	56	64
Rhombuses	0	7	14	21	28	35	42	49

f No. of rhombuses $=$ (no. of desks $- 1$) $\times$ (no. of rows $- 1$)

$= (d - 1)(n - 1)$

g 10 201 desks

3 **a** 36, 49, 64; square the counting numbers

b 125, 216, 343; cube of the counting numbers

c (4, 6), (5, 7), (6, 8); each y value is 2 more than the x value

d 31, 31, 30; days of the month in a leap year

e $\sqrt{5}, \sqrt{6}, \sqrt{7}$; square root of the counting numbers

f 7, 64, 8; two sequences: 1, 2, 3, 4, … and 1, 2, 4, 8, 16, …

Chapter 4

Exercise 4A

1 **a** 9 **b** 7

2 proper: b, e, f, g

improper: a, c, h, i, k, l

whole numbers: d, j, k

3 **A** **a** 4 **b** 1 **c** **i** 4 **ii** 1 **iii** $\frac{1}{4}$


B **a** 8 **b** 7 **c** **i** 8 **ii** 7 **iii** $\frac{7}{8}$

C **a** 3 **b** 2 **c** **i** 3 **ii** 2 **iii** $\frac{2}{3}$


D **a** 12 **b** 5 **c** **i** 12 **ii** 5 **iii** $\frac{5}{12}$

4 d, g, j, l, m


5 **a**




b




c




d



e




f




6 Answers may vary.

a




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

b



c



7 **a** $\frac{7}{5}, \frac{8}{5}, \frac{9}{5}$ **b** $\frac{9}{8}, \frac{10}{8}, \frac{11}{8}$

c $\frac{5}{3}, \frac{6}{3}, \frac{7}{3}$ **d** $\frac{7}{7}, \frac{6}{7}, \frac{5}{7}$

e $\frac{5}{2}, \frac{3}{2}, \frac{1}{2}$ **f** $\frac{23}{4}, \frac{28}{4}, \frac{33}{4}$

8 **a** $\bigcirc = 1\frac{1}{2}, \frac{3}{2}; \square = 3\frac{1}{2}, \frac{7}{2}; \triangle = 5, \frac{10}{2}$

b $\bigcirc = \frac{1}{5}; \square = \frac{4}{5}; \triangle = 2\frac{1}{5}, \frac{11}{5}$

c $\triangle = \frac{3}{7}; \square = 1\frac{4}{7}, \frac{11}{7}; \bigcirc = 2\frac{2}{7}, \frac{16}{7}$

d $\square = 3\frac{1}{3}, \frac{10}{3}; \triangle = 3\frac{2}{3}, \frac{11}{3}; \bigcirc = 4\frac{2}{3}, \frac{14}{3}$

9 division

10 **a** $\frac{6}{11}$ **b** $\frac{4}{8} = \frac{1}{2}$ **c** $\frac{7}{12}$ **d** $\frac{5}{6}$

e $\frac{3}{12} = \frac{1}{4}$ **f** $\frac{5}{9}$

11 **a** $\frac{12}{43}$ **b** $\frac{13}{15}$ **c** $\frac{11}{12}$ **d** $\frac{1}{12}$

e $\frac{2}{11}$ **f** $\frac{144}{475}$ **g** $\frac{7}{20}$ **h** $\frac{1}{4}$

i $\frac{3}{7}$

12 Proper fraction: When you have part of a whole, and therefore you have a numerator that is smaller than the denominator. Improper fraction: It is called improper because it is impossible to break a whole into parts and end up with more than a whole. An improper fraction is when the numerator is greater than the denominator.

13 **c**

14 **a** **i** $\frac{1}{5}$ **ii** 50 mL

b **i** 40 mL **ii** $\frac{4}{25}$

c **i** 32 mL **ii** $\frac{16}{125}$

d **i** 90 mL **ii** $\frac{9}{25}$

e **i** 122 mL **ii** $\frac{61}{125}$

f Approximately, yes they will.

Exercise 4B

1 $\frac{3}{6}, \frac{2}{4}, \frac{11}{22}, \frac{5}{10}$

2 $\frac{4}{10}, \frac{16}{40}, \frac{2}{5}, \frac{80}{200}$

3 **a** 2, 12, 10, 20, 300 **b** 1, 3, 24, 20, 40

4 **a** $\frac{1}{5}$ **b** $\frac{1}{6}$ **c** $\frac{2}{3}$ **d** $\frac{3}{4}$

5 **a** 10, 10, 10, 1 **b** 2, 2, 2, 2

c 4, 4, 4, 7 **d** 3, 3, 3, 3, 5

6 Answers may vary.

a $\frac{2}{4}, \frac{3}{6}, \frac{4}{8}, \frac{10}{20}$ **b** $\frac{2}{8}, \frac{3}{12}, \frac{4}{16}, \frac{10}{40}$

c $\frac{4}{10}, \frac{6}{15}, \frac{8}{20}, \frac{10}{25}$ **d** $\frac{6}{10}, \frac{12}{20}, \frac{24}{40}, \frac{48}{80}$

e $\frac{4}{18}, \frac{6}{27}, \frac{8}{36}, \frac{20}{90}$ **f** $\frac{6}{14}, \frac{9}{21}, \frac{12}{28}, \frac{30}{70}$

g $\frac{10}{24}, \frac{50}{120}, \frac{500}{1200}, \frac{5000}{12000}$ **h** $\frac{6}{22}, \frac{9}{33}, \frac{12}{44}, \frac{30}{110}$

7 **a** 9 **b** 50 **c** 33 **d** 56

e 8 **f** 2 **g** 12 **h** 39

i 35 **j** 200 **k** 105 **l** 2

8 **a** $\neq$ **b** $=$ **c** $\neq$ **d** $\neq$

e $=$ **f** $=$ **g** $=$ **h** $=$

i $=$

9 **a** $\frac{3}{4}$ **b** $\frac{2}{3}$ **c** $\frac{1}{3}$ **d** $\frac{4}{11}$

e $\frac{2}{5}$ **f** $\frac{1}{11}$ **g** $\frac{1}{7}$ **h** $\frac{1}{3}$

i $\frac{7}{9}$ **j** $\frac{3}{8}$ **k** $\frac{5}{6}$ **l** $\frac{5}{1} = 5$

10 **a** $\frac{7}{14} = \frac{1}{2}$ **b** $\frac{12}{16} = \frac{3}{4}$ **c** $\frac{4}{42} = \frac{2}{21}$ **d** $\frac{7}{63} = \frac{1}{9}$

11 $\frac{2}{9}$

12 **a** 35 **b** 45 **c** 30 **d** 24


13 Justin 4, Joanna 3, Jack 5

14 **a** 75 **b** $\frac{1}{3}$ **c** 150


Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


15 Answers may vary; $\frac{6}{10}$

16 Answers may vary.

a 

b 12 quavers (eighth notes) to a bar

c 

d 

e Each dot increases the length of the note by another 50%.

e.g. $\text{♩}\bullet = \frac{3}{4}$ note (value = 3 beats)


$=$ half note $+ 50\%$


$=$ half note $+$ quarter note


Exercise 4C


1 a 2 and 3 b 11 and 12 c 36 and 37

2 a 24 b 360 c 60 d 24

3 a 

b 

c 

d 

4 a 8 b 12 c 28 d 44
e 17 f 7 g 10 h 24

5 a A $7\frac{1}{2}$, B $10\frac{1}{2}$


b C $1\frac{2}{3}$, D $2\frac{1}{3}$, E $4\frac{2}{3}$


c F $23\frac{1}{5}$, G $24\frac{2}{5}$, H $25\frac{4}{5}$, I $26\frac{1}{5}$


6 a $\frac{11}{5}$ b $\frac{8}{5}$ c $\frac{10}{3}$ d $\frac{17}{3}$
e $\frac{29}{7}$ f $\frac{24}{7}$ g $\frac{5}{2}$ h $\frac{13}{2}$
i $\frac{14}{3}$ j $\frac{34}{3}$ k $\frac{42}{5}$ l $\frac{103}{10}$
m $\frac{55}{9}$ n $\frac{25}{9}$ o $\frac{42}{8}$ p $\frac{21}{8}$
q $\frac{23}{12}$ r $\frac{38}{11}$ s $\frac{53}{12}$ t $\frac{115}{12}$
u $\frac{115}{20}$ v $\frac{803}{100}$ w $\frac{643}{10}$ x $\frac{104}{5}$

7 a $1\frac{2}{5}$ b $1\frac{1}{3}$ c $1\frac{2}{3}$ d $1\frac{3}{4}$
e $3\frac{2}{3}$ f $4\frac{1}{5}$ g $2\frac{2}{7}$ h $2\frac{1}{2}$
i $1\frac{5}{7}$ j $3\frac{1}{6}$ k $6\frac{2}{3}$ l $10\frac{1}{4}$
m $4\frac{3}{8}$ n $5\frac{1}{5}$ o $6\frac{6}{7}$ p $13\frac{2}{3}$
q $3\frac{1}{12}$ r $7\frac{4}{11}$ s $9\frac{3}{10}$ t $11\frac{1}{7}$
u $2\frac{31}{100}$ v $33\frac{3}{10}$ w $12\frac{3}{11}$ x $12\frac{5}{12}$

8 a $2\frac{1}{2}$ b $2\frac{4}{5}$ c $1\frac{1}{3}$ d $1\frac{1}{3}$
e $1\frac{1}{8}$ f $3\frac{1}{3}$ g $2\frac{2}{3}$ h $2\frac{2}{5}$

9 a 

b 

c 

10 a $2\frac{1}{3}, 3\frac{2}{3}, 4$

b $1\frac{4}{7}, 2\frac{1}{7}, 3, 3\frac{4}{7}, 3\frac{6}{7}$

c $2\frac{2}{5}, 4\frac{1}{5}, 4\frac{4}{5}, 6, 7\frac{1}{5}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

11 **a** 15 **b** $1\frac{7}{8}$ **c** 9 **d** $1\frac{1}{8}$

12 **a** 11 **b** 9 **c** $4x - 1$

d $3y - 1$ **e** mn

13 **a** **i** $1\frac{2}{3}, 2\frac{1}{3}, 3\frac{1}{2}$ **ii** $1\frac{5}{6}$

b **i** $2\frac{3}{4}, 3\frac{2}{4}, 4\frac{2}{3}$ **ii** $1\frac{11}{12}$

c **i** $3\frac{4}{5}, 4\frac{3}{5}, 5\frac{3}{4}$ **ii** $1\frac{19}{20}$

d $1\frac{29}{30}$

e A mixed number with a whole number part equal to 1. Denominator equal to product of two largest numbers, numerator is one less than denominator.

Exercise 4D

1 **a** $\frac{5}{7}$ **b** $\frac{7}{3}$ **c** $\frac{9}{11}$ **d** $\frac{8}{5}$

2 **a** 10 **b** 21 **c** 20 **d** 30

e 6 **f** 10 **g** 12 **h** 24

i 30 **j** 12 **k** 24 **l** 30

3 **a** 15 **b** 20 **c** 21 **d** 10

e 24 **f** 60 **g** 12 **h** 12

4 **a** 6 **b** 8 **c** 4 **d** 6

e 15 **f** 15

5 **a** $>$ **b** $>$ **c** $=$ **d** $<$

e $<$ **f** $>$ **g** $<$ **h** $=$

i $>$ **j** $>$ **k** $<$ **l** $=$

m $>$ **n** $>$ **o** $<$ **p** $>$

6 **a** $\frac{3}{5}, 1\frac{2}{5}, \frac{8}{5}$ **b** $\frac{2}{9}, \frac{1}{3}, \frac{5}{9}$

c $\frac{2}{5}, \frac{3}{4}, \frac{4}{5}$ **d** $\frac{3}{5}, \frac{2}{3}, \frac{5}{6}$

e $2\frac{1}{4}, \frac{5}{2}, \frac{11}{4}, 3\frac{1}{3}$ **f** $\frac{5}{3}, \frac{7}{4}, \frac{11}{6}, \frac{15}{8}$

g $\frac{11}{5}, \frac{9}{4}, 2\frac{1}{2}, 2\frac{3}{5}, 2\frac{7}{10}$ **h** $4\frac{1}{6}, 4\frac{10}{27}, 4\frac{4}{9}, 4\frac{2}{3}, \frac{15}{3}$

7 **a** $\frac{1}{2}, \frac{1}{3}, \frac{1}{4}, \frac{1}{5}$ **b** $\frac{3}{5}, \frac{3}{6}, \frac{3}{7}, \frac{3}{8}$

c $\frac{7}{2}, \frac{7}{5}, \frac{7}{7}, \frac{7}{8}$ **d** $\frac{1}{10}, \frac{1}{15}, \frac{1}{50}, \frac{1}{100}$

e $10\frac{2}{3}, 8\frac{3}{5}, 7\frac{1}{11}, 5\frac{4}{9}$ **f** $2\frac{1}{3}, 2\frac{1}{5}, 2\frac{1}{6}, 2\frac{1}{9}$

8 $\frac{1}{4}, \frac{1}{8}, \frac{1}{11}$

9 Andrea, Rob, Dean, David

10 **a** $\frac{5}{9}, \frac{6}{9}$ **b** $\frac{11}{4}, \frac{14}{4}$ **c** $\frac{5}{6}, \frac{3}{6}$ **d** $\frac{10}{14}, \frac{11}{14}$

11 Answers may vary.

a $\frac{13}{20}$ **b** $\frac{1}{3}$ **c** $\frac{5}{21}$ **d** $\frac{3}{4}$

e $2\frac{1}{4}$ **f** $8\frac{29}{40}$

12 **a** 7, 8 **b** 16

13 **a** Thomas **b** $\frac{1}{10}$th of a donut

14 **a** **i** $\frac{1}{4}$ **ii** $\frac{3}{8}$ **iii** $\frac{1}{2}$

iv $\frac{1}{3}$

Exercise 4E

1 **a** denominator

b denominator, numerators

c denominators, lowest common denominator

d check, simplified

2 **a** 5 **b** 5 **c** 4, 3, 7 **d** 8, 15, 23, 3

3 **a** 15 **b** 20 **c** 6 **d** 6

e 8 **f** 10 **g** 77 **h** 9

i 24 **j** 18 **k** 30 **l** 48

4 **a** ✓ **b** ✗ **c** ✗ **d** ✓

e ✓ **f** ✗ **g** ✓ **h** ✗

i ✓ **j** ✗ **k** ✓ **l** ✗

5 **a** $\frac{5}{8}$ **b** $\frac{5}{7}$ **c** $\frac{4}{5}$ **d** $\frac{9}{11}$

e $\frac{7}{8}$ **f** $\frac{7}{12}$ **g** $\frac{7}{15}$ **h** $\frac{5}{9}$

i $1\frac{2}{7}$ **j** $1\frac{3}{10}$ **k** $1\frac{4}{5}$ **l** $1\frac{4}{19}$

6 **a** $\frac{3}{4}$ **b** $\frac{14}{15}$ **c** $\frac{2}{3}$ **d** $\frac{7}{12}$

e $\frac{13}{20}$ **f** $\frac{19}{20}$ **g** $\frac{13}{21}$ **h** $\frac{23}{40}$

i $1\frac{13}{30}$ **j** $1\frac{9}{28}$ **k** $1\frac{13}{33}$ **l** $1\frac{5}{12}$

7 **a** $3\frac{4}{5}$ **b** $7\frac{3}{7}$ **c** $12\frac{3}{4}$ **d** $5\frac{5}{9}$

e $10\frac{1}{3}$ **f** $21\frac{1}{6}$ **g** $19\frac{3}{11}$ **h** $12\frac{2}{5}$

8 **a** $4\frac{5}{12}$ **b** $7\frac{7}{30}$ **c** $12\frac{1}{6}$ **d** $13\frac{9}{28}$

e $15\frac{1}{10}$ **f** $19\frac{1}{9}$ **g** $25\frac{21}{44}$ **h** $15\frac{5}{24}$

9 **a** $\frac{14}{15}$ **b** $\frac{1}{15}$

10 $8\frac{3}{20}$ km

11 **a** $\frac{3}{4}$ **b** 400

c $\frac{1}{4}$, 250 pieces

12 **a** $\frac{47}{60}$ **b** $\frac{13}{60}$ **c** 39

13 **a** 5, 2 **b** 2, 4, 8 **c** 5, 1

d 5, 1, 15; other answers possible.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 Jim $\left(\frac{36}{60}\right)$, Vesna $\left(\frac{37}{60}\right)$, Juliet $\left(\frac{38}{60}\right)$, Mikhail $\left(\frac{39}{60}\right)$

15 **a** maximum: $\frac{6}{1}+\frac{5}{2}+\frac{4}{3}=9\frac{5}{6}$

minimum: $\frac{1}{4}+\frac{2}{5}+\frac{3}{6}=1\frac{3}{20}$

b maximum: $\frac{8}{1}+\frac{7}{2}+\frac{6}{3}+\frac{5}{4}=14\frac{3}{4}$

minimum: $\frac{1}{5}+\frac{2}{6}+\frac{3}{7}+\frac{4}{8}=1\frac{97}{210}$

c Maximum: Largest numbers as numerators, smallest numbers as denominators; combine largest numerator available with smallest denominator available to produce the fractions.

Minimum: Smallest numbers as numerators, largest numbers as denominators; combine smallest numerator available with smallest denominator available to produce the fractions.

Exercise 4F

1 **a** denominator **b** multiply **c** simplify **d** multiply

2 **a** 12 **b** 10 **c** 15 **d** 18 **e** 24 **f** 60 **g** 56 **h** 63

3 **a** 1 **b** 3 **c** 4, 3, 1 **d** 12, 10, 2

4 **a** ✓ **b** ✗ **c** ✗ **d** ✓ **e** ✗ **f** ✓ **g** ✓ **h** ✗ **i** ✓ **j** ✓ **k** ✗ **l** ✗

5 **a** $\frac{2}{7}$ **b** $\frac{3}{11}$ **c** $\frac{7}{18}$ **d** $\frac{1}{3}$ **e** 0 **f** $\frac{4}{9}$ **g** $\frac{3}{19}$ **h** $\frac{8}{23}$ **i** $\frac{31}{100}$ **j** $\frac{12}{25}$ **k** $\frac{16}{25}$ **l** $\frac{2}{5}$

6 **a** $\frac{5}{12}$ **b** $\frac{1}{10}$ **c** $\frac{1}{10}$ **d** $\frac{9}{28}$ **e** $\frac{1}{6}$ **f** $\frac{23}{36}$ **g** $\frac{13}{33}$ **h** $\frac{2}{15}$ **i** $\frac{1}{8}$ **j** $\frac{3}{20}$ **k** $\frac{1}{36}$ **l** $\frac{1}{9}$

7 **a** $1\frac{3}{5}$ **b** $8\frac{3}{7}$ **c** $1\frac{1}{7}$ **d** $3\frac{2}{9}$ **e** $2\frac{5}{12}$ **f** $3\frac{5}{28}$ **g** $4\frac{7}{18}$ **h** $7\frac{1}{20}$

8 **a** $2\frac{2}{3}$ **b** $4\frac{3}{5}$ **c** $4\frac{2}{3}$ **d** $4\frac{8}{9}$ **e** $4\frac{2}{3}$ **f** $\frac{37}{45}$ **g** $9\frac{37}{44}$ **h** $2\frac{29}{60}$

9 $\frac{11}{20}$ L

10 $\frac{3}{5}$

11 $\frac{1}{6}$

12 $\$7\frac{3}{4}$, \$7.75

13 **a** ice-cream $\frac{3}{4}$, chocolate $\frac{3}{4}$, sponge $\frac{7}{8}$

b ice-cream $\frac{1}{4}$, chocolate $\frac{1}{4}$, sponge $\frac{1}{8}$

c $2\frac{3}{8}$

d $\frac{5}{8}$

14 **a** 3, 4 **b** 3, 1 **c** 1, 2 **d** 4, 3

15 **a** $\frac{1}{4}$ **b** 4 years **c** 10 years

16 **a** $\frac{8}{15}$: 'Converting to an improper fraction' is quick and efficient for this question.


b $3\frac{36}{55}$: 'Borrowing a whole number' keeps the numbers smaller and easier to deal with for this question.

Exercise 4G


1 **a** 0, 1 **b** 1 **c** whole number, proper fraction

2 You get a smaller answer because you are multiplying by a number that is less than 1.

3 **a**




b




c $\frac{1}{12}$


4 **a**




b



c




d




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

e



f



5 D

6 a $\frac{3}{20}$ b $\frac{2}{21}$ c $\frac{10}{21}$ d $\frac{8}{45}$

e $\frac{2}{5}$ f $\frac{1}{7}$ g $\frac{1}{4}$ h $\frac{5}{11}$

i $\frac{5}{22}$ j $\frac{1}{3}$ k $\frac{6}{11}$ l $\frac{4}{11}$

m $\frac{6}{35}$ n $\frac{3}{10}$ o $\frac{2}{7}$ p $\frac{1}{6}$

7 a 6 b 9 c 16 d 15

e 12 f 4 g 80 h 33

8 a $5\frac{5}{6}$ b $1\frac{31}{35}$ c $3\frac{3}{10}$ d $4\frac{7}{8}$

e $5\frac{1}{3}$ f 7 g 6 h $3\frac{1}{3}$

9 a $3\frac{11}{15}$ b $1\frac{25}{63}$ c $7\frac{4}{5}$ d 24

10 a $3\frac{1}{5}$ b $\frac{3}{16}$ c 4 d 33

e $\frac{2}{7}$ f $3\frac{3}{8}$ g $\frac{4}{15}$ h 6

11 a $\frac{3}{5}$ b 48 boys, 72 girls

12 $11\frac{2}{3}$ L

13 7 cups of self-raising flour, 3 cups of cream

14 7 games

15 a $\times \frac{7}{12}$ b $\times \frac{7}{12}$ c $\times \frac{1}{12}$ d ✓

e ✓ f $\times \frac{1}{12}$

16 D; e.g. $\frac{2}{7} \times \frac{3}{5} = \frac{6}{35}$. The two numerators will always multiply to give a smaller number than the two larger denominators. Hence, the product of two proper fractions will always be a proper fraction.

17 Answers may vary.

a $\frac{2}{5} \times \frac{3}{2}$ b $\frac{5}{4} \times \frac{3}{5}$ c $\frac{3}{7} \times \frac{2}{6}$

18 $\frac{2}{7}, \frac{3}{8}$

Exercise 4H

1 A

2 a $\frac{5}{11} \times \frac{5}{3}$ b $\frac{1}{3} \times \frac{5}{1}$ c $\frac{7}{10} \times \frac{5}{12}$ d $\frac{8}{3} \times \frac{1}{3}$

3 a $\frac{5}{2} \div \frac{4}{3}, \frac{5}{2} \times \frac{3}{4}$ b $24 \div \frac{16}{5}, \frac{24}{1} \times \frac{5}{16}$

c $\frac{47}{11} \div \frac{21}{4}, \frac{47}{11} \times \frac{4}{21}$ d $\frac{8}{3} \div \frac{80}{7}, \frac{8}{3} \times \frac{7}{80}$

4 a less b more c more d more

e less f less

5 a $\frac{7}{5}$ b $\frac{5}{3}$ c $\frac{9}{2}$ d $\frac{8}{1}$

e $\frac{3}{7}$ f $\frac{5}{23}$ g $\frac{6}{11}$ h $\frac{3}{26}$

i $\frac{1}{12}$ j $\frac{1}{101}$ k 9 l 1

6 a $\frac{3}{8}$ b $\frac{5}{33}$ c $\frac{2}{5}$ d $\frac{5}{7}$

e $\frac{3}{4}$ f $1\frac{1}{3}$ g $1\frac{3}{5}$ h $\frac{3}{14}$

7 a 20 b 21 c 100 d 120

e 30 f 40 g 4 h $6\frac{2}{3}$

8 a $\frac{5}{7}$ b $\frac{4}{5}$ c $\frac{11}{14}$ d $\frac{3}{4}$

e $1\frac{11}{16}$ f $1\frac{3}{11}$ g $3\frac{1}{3}$ h $\frac{3}{4}$

9 a $\frac{3}{40}$ b 30 c $1\frac{13}{35}$ d $\frac{1}{3}$

e 28 f $\frac{4}{15}$ g $6\frac{4}{7}$ h $2\frac{1}{10}$

10 $\frac{3}{4}$

11 10

12 $\frac{9}{10}$ m

13 8

14 22 km

15 $\frac{1}{2}$ of 8 and $\frac{1}{2} \div \frac{1}{8} = 4$, $12 \div 4$ and $12 \times \frac{1}{4} = 3$, $10 \times \frac{1}{2}$ and $10 \div 2 = 5$, $3 \div \frac{1}{2}$ and $3 \times 2 = 6$


16 a $\frac{9}{20}$ b $\frac{45}{64}$ c $\frac{5}{16}$ d $\frac{1}{5}$

17 a 240 km b 160 km

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


Progress quiz

1 a a square with 4 equal parts, 3 of which are shaded; many other possible answers



b 4

c 3

d 

e proper fraction

2 $1\frac{2}{3}$ or $\frac{5}{3}$ or $1\frac{4}{6}$ or $\frac{10}{6}$

3 $\frac{2}{5} = \frac{4}{10}, \frac{6}{15}, \frac{20}{50}, \frac{10}{25}, \frac{8}{20}$ …; many other possible answers

4 a $\frac{2}{5}$ b $\frac{1}{2}$ c $\frac{7}{3} = 2\frac{1}{3}$ d 3

5 $\frac{8}{5}$

6 $3\frac{1}{4}$

7 a > b = c = d <

8 $\frac{4}{9}, \frac{1}{2}, \frac{2}{3}, \frac{9}{4}$

9 a $\frac{6}{7}$ b $\frac{7}{10}$ c $1\frac{3}{20}$ d $5\frac{1}{4}$

10 a $\frac{1}{12}$ b $\frac{7}{12}$ c $2\frac{3}{10}$

11 a \$336 b $\frac{14}{33}$ c $\frac{3}{5}$ d $\frac{3}{4}$

12 a $\frac{5}{4}$ b $\frac{1}{6}$ c $\frac{2}{5}$ d 12

13 a $\frac{7}{32}$ b $10\frac{2}{3}$ c $1\frac{2}{7}$

Exercise 4I

1 a 70, 70 b 48, 48 c 60, 60
d 20, 20 e 40, 40 f 63, 63

2 a $\frac{1}{4} = 25\%, \frac{2}{4} = 50\%, \frac{3}{4} = 75\%, \frac{4}{4} = 100\%$

b $\frac{1}{5} = 20\%, \frac{2}{5} = 40\%, \frac{3}{5} = 60\%, \frac{4}{5} = 80\%,$ $\frac{5}{5} = 100\%$

c $\frac{1}{3} = 33\frac{1}{3}\%, \frac{2}{3} = 66\frac{2}{3}\%, \frac{3}{3} = 100\%$

3 a 86% b 20%

4 a $\frac{11}{100}$ b $\frac{71}{100}$ c $\frac{43}{100}$ d $\frac{49}{100}$
e $\frac{1}{4}$ f $\frac{3}{10}$ g $\frac{3}{20}$ h $\frac{22}{25}$

5 a $1\frac{1}{5}$ b $1\frac{4}{5}$ c $2\frac{37}{100}$ d $4\frac{1}{100}$
e $1\frac{3}{4}$ f $1\frac{1}{10}$ g $3\frac{4}{25}$ h $8\frac{2}{5}$

6 a 8% b 15% c 97% d 50%
e 35% f 32% g 86% h 90%
i 112% j 135% k 400% l 160%

7 a $12\frac{1}{2}\%$ b $33\frac{1}{3}\%$ c $26\frac{2}{3}\%$ d $83\frac{1}{3}\%$
e 115% f 420% g 290% h $32\frac{1}{2}\%$

8 a $\frac{3}{4}$ b 75% c $\frac{1}{4}$ d 25%

9 $12\frac{1}{2}\%$

10 70%

11 70%, 80%

12 a $\frac{18}{25}$ b 72%

13 $\frac{55}{1000} = \frac{11}{200}$

14 a $\frac{25}{1000} = \frac{1}{40}$ b $\frac{825}{1000} = \frac{33}{40}$
c $\frac{125}{1000} = \frac{1}{8}$ d $\frac{1}{3}$

Exercise 4J

1 a 10 b 100 c 2 d 1
e 5 f 4

2 a ii b ii c i d i

3 a 70 b 36 c 10 d 27
e 10 f 7 g 150 h 200
i 4 j 48 k 44 l 190
m 22 n 84 o 36 p 63

4 a 96 b 600 c 66 d 100
e 15 f 72 g 73 h 600

5 10% of \$200 = \$20
20% of \$120 = \$24
10% of \$80 = \$8
50% of \$60 = \$30
20% of \$200 = \$40
5% of \$500 = \$25
30% of \$310 = \$93
10% of \$160 = \$16
1% of \$6000 = \$60
50% of \$88 = \$44

6 a \$42 b 24 mm c 9 kg
d 90 tonnes e 8 min f 400 cm
g 1.5 g h 3 hectares i 144 seconds

7 35

8 no (red \$45, striped \$44)

9 240

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2 © Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party. Cambridge University Press

10 12

11 **a** 120 **b** 420 **c** 660

12 **a** \$80/week **b** \$2080 **c** \$4160

13 **a** computer games 30 min, drums 24 min, outside 48 min, reading 12 min

b 5% time remaining

c yes, with 1 min to spare

14 80 min

15 **a** 20 **b** 90 **c** 20 **d** 64

16 they are the same

17 $37\frac{1}{2}\%$

18 **a** \$140 **b** \$1.50

19 **a** **i** 1200 **ii** 24%, 22%, 20%, 18%, 16%

iii 2%

b **i** 30%

ii week 1: 30%, 2400 pieces; week 2: 25%, 2000 pieces; week 3: 20%, 1600 pieces; week 4: 15%, 1200 pieces; week 5: 10%, 800 pieces

iii

Week	Cumulative %	Pieces completed
Week 1	30%	2400
Week 2	55%	4400
Week 3	75%	6000
Week 4	90%	7200
Week 5	100%	8000

Exercise 4K

1 **a** 4 **b** 4 **c** $\frac{1}{2}$ **d** 50%

e $\frac{1}{2}$ **f** 50%

2 **a** 10 **b** $\frac{1}{5}$ **c** $\frac{4}{5}$ **d** 20%

e 80%

3 **a** $\frac{3}{10}$, 30% **b** $\frac{3}{5}$, 60% **c** $\frac{1}{5}$, 20% **d** $\frac{3}{4}$, 75%

e $\frac{1}{20}$, 5% **f** $\frac{1}{2}$, 50% **g** $\frac{1}{4}$, 25% **h** $\frac{3}{20}$, 15%

4 **a** $\frac{3}{5}$, 60% **b** $\frac{1}{2}$, 50% **c** $\frac{1}{4}$, 25% **d** $\frac{2}{5}$, 40%

e $\frac{3}{4}$, 75% **f** $\frac{4}{5}$, 80%

5 **a** $\frac{1}{10}$ **b** 10%

6 **a** $\frac{1}{5}$ **b** 20% **c** $\frac{4}{5}$ **d** 80%

7 **a** $\frac{3}{4}$ **b** 75% **c** $\frac{1}{4}$ **d** 25%

8 95%

9 80%

10 **a** $\frac{1}{25}$, 4% **b** $\frac{2}{5}$, 40% **c** $\frac{1}{20}$, 5% **d** $\frac{1}{100}$, 1%

e $\frac{1}{50}$, 2% **f** $\frac{1}{40}$, 2.5%

11 **a** $\frac{1}{5}$ **b** 40%

12 **a** 5% **b** $\frac{1}{5}$

13 Ross 75%, Maleisha 72%

14 hatch 15%, 4WD 16%; hence, 4WD has larger price reduction.

15 yellow 20%, blue 19%; hence, blue has least percentage of sugar.

16 **a** **i** $\frac{b}{a+b}$ **ii** $\frac{a}{a+b}$

b **i** $\frac{100b}{a+b}$ **ii** $\frac{100a}{a+b}$

17 **a** $\frac{a}{a+b}$ **b** $\frac{100b}{a+b}$

18 **a** 3 **b** $\frac{1}{30}$ **c** $\frac{1}{6}$ **d** $\frac{17}{30}$

e 20% **f** 96.67%

Problems and challenges

1 22.5

2 Answers will vary, but a possible answer is:

a 6, 7, 8, 9

b 4, 5, 6, 7, 8

c 2, 3, 4, 6, 7, 8

d 1, 2, 3, 4, 5, 6, 9

3

$\frac{2}{5}$	$A = \frac{9}{10}$	$\frac{4}{5}$
$B = \frac{11}{10}$	$C = \frac{7}{10}$	$D = \frac{3}{10}$
$E = \frac{3}{5}$	$\frac{1}{2}$	1

4 **a** $\frac{1}{6} + \frac{1}{5} \times \frac{1}{3}$ **b** $\frac{1}{3} \div \frac{1}{4} - \frac{1}{6}$ **c** $\frac{1}{6} + \frac{1}{4} - \frac{1}{5}$

5 Because the final 20% reduction is off the original \$50 plus also off the \$10 increase, the 20% reduction will be \$12 overall.

Multiple-choice questions

1 B **2** C **3** A **4** C **5** D

6 B **7** D **8** D **9** A **10** C

Short-answer questions

1 $\frac{1}{14}, \frac{1}{10}, \frac{1}{8}, \frac{1}{6}, \frac{1}{5}, \frac{1}{4}, \frac{1}{3}, \frac{1}{2}$

2 $\frac{3}{5} = \frac{6}{10} = \frac{9}{15} = \frac{12}{20} = \frac{15}{25}$ etc

Multiplying by the same number in the numerator and denominator is equivalent to multiplying by 1, and so does not change the value of the fraction.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 a $\frac{3}{5}$ b $\frac{2}{7}$ c $\frac{5}{7}$

4 a $1\frac{1}{2}$ b $1\frac{3}{4}$ c $1\frac{2}{3}$ d $3\frac{1}{2}$

5 a $\frac{2}{7} < \frac{4}{7}$ b $\frac{3}{8} > \frac{1}{8}$

c $1\frac{2}{3} > 1\frac{3}{5}$ d $3\frac{1}{9} < \frac{29}{9}$

6 a $\frac{5}{7}$ b $\frac{5}{8}$

7 a 10 b 21 c 24

8 a 10 b 21 c 24

9 a $2\frac{1}{5}, \frac{9}{5}, 1\frac{3}{5}$ b $\frac{9}{4}, \frac{11}{6}, \frac{14}{8}\frac{5}{3}$

c $5\frac{2}{3}, 5\frac{7}{18}, 5\frac{1}{3}, \frac{47}{9}, 5\frac{1}{9}$

10 a $\frac{1}{2}$ b $\frac{5}{6}$ c $1\frac{5}{24}$ d $5\frac{23}{30}$

e $\frac{1}{2}$ f $2\frac{1}{2}$ g $1\frac{9}{40}$ h $6\frac{5}{36}$

i $12\frac{3}{5}$

11 a 7 b 80 c 12 d 5

e $\frac{1}{6}$ f $7\frac{1}{2}$

12 a $\frac{4}{3}$ b $\frac{12}{7}$ c $\frac{4}{11}$ d $\frac{3}{16}$

13 a $\frac{1}{5}$ b 20 c 4 d $\frac{1}{5}$

14

Percentage form	Fraction
36%	$\frac{9}{25}$
220%	$2\frac{1}{5}$
5%	$\frac{5}{100}$
140%	$1\frac{2}{5}$
44%	$\frac{11}{25}$
18%	$\frac{9}{50}$

15 a ii b i

16 a $\frac{3}{5}$, 60% b $\frac{1}{5}$, 20%

c $\frac{1}{16}$, 6.25% d $\frac{3}{10}$, 30%

Extended-response questions

1 a $7\frac{5}{8}$ b $5\frac{11}{24}$ c $10\frac{17}{80}$ d $6\frac{2}{21}$

2 $129\frac{9}{25}$

3 a \$176 b \$24

4 a \$550 b 264 L c \$99 d \$200

5 a $12\frac{1}{2}$ b \$208

6 $55\frac{2}{3}\%$

Chapter 5

Exercise 5A

1 a $4x$, $3y$, $24z$, 7 b 7

c 4 d z

2 a F b A c D

d B e C f E

3 a i 2 ii 17

b i 3 ii 15

c i 3 ii 21

d i 4 ii 2

e i 2 ii 1

f i 4 ii 12

4 a $x + 1$ b $5 + k$ c $2u$ d $4y$

e $\frac{p}{2}$ f $\frac{q}{3}$ g $r - 12$ h $9n$

i $10 - t$ j $\frac{y}{8}$

5 a $2(x + 5)$ b $3a + 4$ c $8k - 3$ d $8(k - 3)$

e $6(x + y)$ f $\frac{7x}{2}$ g $\frac{p}{2} + 2$ h $12 - xy$

6 a The product of 7 and x.

b The sum of a and b.

c The sum of x and 4 is doubled.

d a is tripled and subtracted from 5.

7 a 70 b $10n$

8 a $8x$ b $x + 3$ c $8(x + 3)$

9 a $1000x$ b $100x$ c $100\,000x$

10 a $\frac{\$A}{4}$ b $\frac{\$A}{n}$

c $\frac{\$A - 20}{n}$

11 'One-quarter of the sum of a and b.' Other answers possible.

12 a true b true c false d true

e false

13 a false b false c true d true

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

14 $c \div 2$, $c - 4$, $c + 1$, $2c$, $3c$, $3c + 5$, $4c - 2$, $c \times c$

15 'The sum of twice the value of x is taken from 3' becomes $3 - 2x$. Other answers possible.

Exercise 5B

1 **a** 14 **b** 1 **c** 10 **d** 8

2 13

3 15

4 3

5 **a** 17 **b** 20 **c** 72 **d** 12

6 **a** 8 **b** 10 **c** 9 **d** 14
e 12 **f** 3 **g** 19 **h** 9
i 7 **j** 20 **k** 3 **l** 1
m 47 **n** 20 **o** 35 **p** 86
q 8 **r** 6

7 **a** 8 **b** 4 **c** 5 **d** 9
e 4 **f** 45 **g** 5 **h** 24
i 50 **j** 8 **k** 5 **l** 20

8 **a** 27 **b** 22 **c** 41 **d** 8
e 10 **f** 70

9 **a**

n	1	2	3	4	5	6
n + 4	5	6	7	8	9	10

b

x	1	2	3	4	5	6
12 – x	11	10	9	8	7	6

c

b	1	2	3	4	5	6
2(b – 1)	0	2	4	6	8	10

d

q	1	2	3	4	5	6
10q – q	9	18	27	36	45	54

10 **a** 75 **b** 45 **c** 54 **d** 11
e 12 **f** 5 **g** 33 **h** 19

11 5

12 x is between 4 and 33 inclusive.

13

x	5	9	12	1	6	7
x + 6	11	15	18	7	12	13
4x	20	36	48	4	24	28

14 **a** 1 and 24, 2 and 12, 3 and 8, 4 and 6

b Infinitely many answers; e.g. $x = \frac{1}{5}$, $y = 120$.

15 Because $5 \times (a + a)$ is $5 \times 2 \times a$, which is $10a$. Every multiple of 10 ends with 0.

16 **a**

x	5	10	7	9	5	8
y	3	4	2	5	2	0
x + y	8	14	9	14	7	8
x – y	2	6	5	4	3	8
xy	15	40	14	45	10	0

b 2 and 2, 3 and $1\frac{1}{2}$, 6 and $1\frac{1}{5}$; other answers possible.

Exercise 5C

1 **a**

	x = 0	*x* = 1	*x* = 2	*x* = 3
2x + 2	2	4	6	8
(x + 1) × 2	2	4	6	8

b equivalent

2 **a**

	x = 0	*x* = 1	*x* = 2	*x* = 3
5x + 3	3	8	13	18
6x + 3	3	9	15	21

b no

3

	6x + 5	*4x + 5 + 2x*
x = 1	11	11
x = 2	17	17
x = 3	23	23
x = 4	29	29

They are equivalent because they are always equal.

4 **a** $2x + 4$ and $x + 4 + x$ **b** $5a$ and $4a + a$
c $2k + 2$ and $2(k + 1)$ **d** $b + b$ and $4b - 2b$

5 **a** C **b** A **c** E **d** F
e B **f** D

6 $2x + 2 + 2x$, $2(2x + 1)$; other answers possible.

7 $2(w + l)$; other answers possible.

8 $9a + 4b$; other answers possible (must have 2 terms).

9 6

10 If $x = 8$, all four expressions have different values.

11 **b** $x \times y$ and $y \times x$
c $a \times (b + c)$ and $a \times b + a \times c$
d $a - (b + c)$ and $a - b - c$
e $a - (b - c)$ and $a - b + c$
f $a \div b \div c$ and $a \div (b \times c)$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

12 **a**

	$4 \times (a + 2)$	$8 + 4a$
$x = 1$	12	12
$x = 2$	16	16
$x = 3$	20	20
$x = 4$	24	24

b $5(2 + a)$

c $24 + 6a$

13 $2a + a + 5b$, $3a + 12b - 7b$; others answers possible.

14 **a** Yes; for any value of x expressions A and B are equal, and expression B and C are equal, so expressions A and C are equal.

b No; e.g. if expression A is $7x$, expression B is $3x$ and expression C is $5x + 2x$.

Exercise 5D

1 **a** x and y **b** a, b and c

c k **d** p and q

2 **a** like **b** like terms **c** terms

d $15a$; others answers possible.

e equivalent **f** $5x + 4$; others answers possible.

3 **a** N **b** L **c** L **d** N

e N **f** L **g** N **h** L

i L **j** L **k** L **l** N

4 **a** $2a$ **b** $5x$ **c** $7b$ **d** $8d$

e $12u$ **f** $12ab$ **g** $11ab$ **h** xy

5 **a** $3a + 5b$ **b** $7a + 9b$ **c** $x + 6y$

d $7a + 2$ **e** $7 + 7b$ **f** $6k - 2$

g $5f + 12$ **h** $4a + 6b - 4$ **i** $6x + 4y$

j $8a + 4b + 3$ **k** $7h + 4$ **l** $14x + 30y$

m $2x + 9y + 10$ **n** $8a + 13$ **o** $12b$

p $9ab + 4$ **q** $6xy + 5x$ **r** $7cd - 3d + 2c$

s $9uv + 7v$ **t** $11pq + 2p - q$ **u** $6ab + 36$

6 **a** $27n$ **b** $31n$ **c** $58n$

7 **a** $3a + 4$ **b** 19

8 **a** $4x$ **b** $7x$ **c** $11x$ **d** $3x$

9 **a** $12xy$ **b** $6ab + 5$ **c** $10ab$

d $6xy + 3$ **e** $5xy + 14$ **f** $10cde$

g $6xy + 6x + 4$

h $9ab + 9$ **i** $7xy - 2y$

10 **a**

	$3x + 2x$	$5x$
$x = 1$	5	5
$x = 2$	10	10
$x = 3$	15	15

b For example, if $x = 5$ and $y = 10$, then $3x + 2y = 35$ but $5xy = 250$.

11 **a**

	$5x + 4 - 2x$	$3x + 4$
$x = 1$	7	7
$x = 2$	10	10
$x = 3$	13	13

b For example, if $x = 10$, $5x + 4 - 2x = 34$ but $7x + 4 = 74$.

c For example, if $x = 1$, $5x + 4 - 2x = 7$ but $7x - 4 = 3$.

12 **a** $2a + a + 3b$, $b + 3a + 2b$; others answers possible.

b 12

Progress quiz

1 **a** 4 **b** $7a, 4b, c, 9$

c 4 **d** 9

2 **a** $m \times p$ or mp **b** $a + k$

c $t + 8$ **d** $w - 4$

3 **a** $\frac{m}{2} + 7$ **b** $\frac{m + 7}{2}$ **c** $\frac{a + k}{3}$

d $a + \frac{k}{3}$ **e** $3(d - 12)$ **f** $3d - 12$

4 **a** 19 **b** 3 **c** 9

5 **a** 24 **b** 11 **c** 5

d 22 **e** 3

6 $3a + 4$ and $4 + 3a$

7 **a** L **b** N **c** N **d** L

8 **a** $8a + 5b + 5$ **b** $7cd + 3c + 8d + 4$

9 $8x + 8y, 8(x + y)$ (other variations possible)

Exercise 5E

1 **a** both are 21 **b** both are 35

c both are 56 **d** yes

2 **a** true **b** true **c** false **d** true

e false **f** false

3 **a** $\frac{2}{3}$ **b** $\frac{2}{3}$ **c** $\frac{2}{3}$

4 **a** C **b** E **c** B **d** A

e D

5 **a** $2x$ **b** $5p$ **c** $8ab$ **d** $6a$

e $28f$ **f** $10ab$ **g** $16xy$ **h** $10b$

i $28xz$

6 **a** $36a$ **b** $63d$ **c** $8e$ **d** $15a$

e $12ab$ **f** $63eg$ **g** $8abc$ **h** $28adf$

i $12abc$ **j** $8abc$ **k** $60defg$ **l** $24abcd$

m w^2 **n** a^2 **o** $3d^2$ **p** $2k^2$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

q $7p^2$ **r** $3q^2$ **s** $12x^2$ **t** $15z^2$
u $36r^2$

7 **a** $\frac{x}{5}$ **b** $\frac{z}{2}$ **c** $\frac{a}{12}$ **d** $\frac{b}{5}$
e $\frac{2}{x}$ **f** $\frac{5}{d}$ **g** $\frac{x}{y}$ **h** $\frac{a}{b}$
i $\frac{4x+1}{5}$ **j** $\frac{2x+y}{5}$ **k** $\frac{2+x}{1+y}$ **l** $\frac{x-5}{3+b}$

8 **a** $\frac{2}{5}$ **b** $\frac{5}{9}$ **c** $\frac{9a}{4}$ **d** $\frac{2b}{5}$
e $\frac{x}{2}$ **f** $\frac{3x}{4}$ **g** $\frac{2}{3}$ **h** $\frac{3}{4}$
i $2a$ **j** 3 **k** $2y$ **l** $\frac{3}{y}$

9 **a** $3k$ **b** $6x$ **c** $12xy$


10 **a** $4x$ g **b** nx g **c** $2nx$ g

11 **a** \$20 **b** $\frac{\$C}{5}$

12 **a** $3a$ **b** $7c$ **c** $7b$ **d** $12y$
e $10x$

13 **a** $6p$
b $3 \times 2p$ also simplifies to $6p$, so they are equivalent.

14 **a**



b $12a$
c $\frac{12a}{3a}$ simplifies to 4. It has four times the area.
d Area is multiplied by 9.

15 **a** $3 \times a \times a \times b \times b$
b $7x^2y^3$
c $1200a^3b^2c^2$
d $24a^3b^2c^2$

Exercise 5F

1 **a** $3a + 6$
b $x + y + x + y = 2x + 2y$
c $p + 1 + p + 1 + p + 1 + p + 1 = 4p + 4$
d $4a + 2b + 4a + 2b + 4a + 2b = 12a + 6b$

2 **a** $4x$ **b** 12 **c** $4x + 12$

3 **a** 60, 3, 63
b 30, 4, 210, 28, 238
c 20, 1, 100, 5, 95

4 **a**

	$4(x+3)$	$4x+12$
$x=1$	16	16
$x=2$	20	20
$x=3$	24	24
$x=4$	28	28

b equivalent expressions

5 **a** $12(x + 4)$ and $12x + 48$
b $8(z + 9)$ and $8z + 72$
c $(3 + a)(3 + b)$ and $9 + 3a + 3b + ab$

6 **a** $6y + 48$ **b** $7l + 28$
c $8s + 56$ **d** $8 + 4a$
e $7x + 35$ **f** $18 + 3a$
g $81 - 9x$ **h** $5j - 20$
i $8y - 64$ **j** $8e - 56$
k $6e - 18$ **l** $80 - 10y$

7 **a** $60g - 70$ **b** $15e + 40$
c $35w + 50$ **d** $10u + 25$
e $56x - 14$ **f** $27v - 12$
g $7q - 49$ **h** $20c - 4v$
i $4u + 12$ **j** $48l + 48$
k $5k - 50$ **l** $9o + 63$

8 **a** $6it - 6iv$ **b** $2dv + 2dm$
c $10cw - 5ct$ **d** $6es + 6ep$
e $dx + 9ds$ **f** $10ax + 15av$
g $5jr + 35jp$ **h** $in + 4iw$
i $8ds - 24dt$ **j** $2fu + fv$
k $14kv + 35ky$ **l** $4em + 40ey$

9 **a** $5(x + 3) = 5x + 15$ **b** $2(b + 6) = 2b + 12$
c $3(z - 4) = 3z - 12$ **d** $7(10 - y) = 70 - 7y$

10 **a** $b + g + 1$
b $2(b + g + 1) = 2b + 2g + 2$

11 $3(4x + 8y)$ and $2(6x + 12y)$; others answers possible.

12 $2l + 2w$

13



14



15 **a** 4 ways, including $1(10x + 20y)$
b infinitely many ways

16 **a** Rosemary likes Maths and Rosemary likes English.
b Priscilla eats fruit and Priscilla eats vegetables.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c Bailey likes the opera and Lucia likes the opera.
d Frank plays video games and Igor plays video games.
e Pyodir likes fruit and Pyodir likes vegetables and Astrid likes fruit and Astrid likes vegetables.

Exercise 5G

1 a 35 b 20
2 a 24 cm b 40 cm
3 a $3x$ b 36
4 $2n$
5 a $10x$ b $15x$ c kx
6 a 180 km b 30 km c $70n$
7 a \$200 b \$680 c $50 + 80x$
8 a B b A c D
d E e C
9 a

Hours	1	2	3	4	5
Total cost (\$)	150	250	350	450	550

b $100t + 50$
c \$3050
10 a \$25 b $\$(10x + 5)$ c \$75
11 a 90c b \$6.30 c $0.3 + 0.6t$
12 a 33
b $g = 8$, b $= 5$
c $g = 3$ and $b = 2$, $g = 1$ and $b = 14$, $g = 0$ and $b = 20$
13 a $\$(5b + 2c + 6d)$ b $\$(5b + 4c + 3d)$
c \$8
14 a cn b $3cn$ c $6cn$
15 a $10 + 30x$
b 2 h 20 min
c Because you don't pay the booking fee twice.
d \$32
e It will get closer to \$30.
16 a $\$(0.2 + 0.6t)$ b $\$(0.8 + 0.4t)$
c Emma's d 3 min
e Answers will vary.

Problems and challenges

1 25
2 a $P = 10m$ b $P = 20(x + 3)$ c $P = 5(w + y)$
3 Largest $18x + 70$, smallest $12x + 44$,
difference $6x + 26 = 86$ cm
4 $15a + 10$, $5(3a + 2)$
5 a $a = 4$, $b = 12$, $c = 16$, $d = 8$, $e = 36$
b $a = 6$, $b = 3$, $c = 5$, $d = 10$, $e = 15$
6 5050
7 Because $2(x + 3) - 12 - x + 2$ simplifies to x.

Multiple-choice questions

1 B 2 A 3 C 4 D 5 D
6 C 7 A 8 E 9 A 10 A

Short-answer questions

1 a $5a, 3b, 7c, 12$ b 12
2 a $u + 7$ b $3k$ c $7 + \frac{r}{2}$
d $h - 10$ e xy f $12 - x$
3 a 15 b 24 c 2 d 32
4 a 15 b 8 c 4 d 27
5 a 16 b 200 c 5 d 20
6 a E b N c E d N
7 a L b N c L d L
e N f L g N h L
8 a $7x + 3$ b $11p$
c $7a + 14b + 4$ d $3m + 17\,mn + 2n$
e $1 + 7c + 4h - 3o$ f $4u + 3v + 2uv$
9 a $12ab$ b $6xyz$ c $36fgh$ d $64klm$
10 a $\frac{3}{2}$ b $\frac{3}{5}$ c $\frac{a}{3}$ d $\frac{4x}{3z}$
11 a $3x + 6$ b $4p - 12$ c $14a + 21$ d $24k + 36l$
12 $2(6b + 9c)$, $6(2b + 3c)$; other answers possible
13 $9t$
14 $g + b$
15 $3x$

Extended-response questions

1 a i \$24.50 ii \$45.50 iii \$213.50
b $3.5 + 2.1d$
c \$87.50
d If $d = 40$, $2.1 + 3.5d = 142.10$, not 87.50.
e $6 + 1.2d$
2 a 26 b \$78
c $4x + 2y + 10$ d $12x + 6y + 30$
e $x(x + 5) + 3y$; other answers possible.

Chapter 6

Exercise 6A

1 a $\frac{2}{10}$ b $\frac{3}{100}$ c $\frac{7}{1000}$
2 a 5 b 6 c 7 d 37
3 a $\frac{6}{10}$ b $\frac{6}{100}$ c $\frac{6}{1000}$ d $\frac{6}{10}$
e 6 f $\frac{6}{100}$ g $\frac{6}{100}$ h $\frac{6}{1000}$
4 a false b false c true d false
e true f true g false h true
i true j true k true l false

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

5 **a** 0.3 **b** 0.8 **c** 0.15 **d** 0.23
e 0.9 **f** 0.02 **g** 0.121 **h** 0.074

6 **a** 6.4 **b** 5.7 **c** 212.3 **d** 1.16
e 14.83 **f** 7.51 **g** 5.07 **h** 18.612

7 **a** 7.6 **b** 12.9 **c** 33.04
d 26.15 **e** 8.42 **f** 99.012

8 **a** 0.1 **b** 0.03 **c** 0.02 **d** 0.5
e 0.001 **f** 0.01 **g** 0.15 **h** 0.11

9 **a** 3.05, 3.25, 3.52, 3.55 **b** 3.06, 3.6, 30.3, 30.6
c 1.718, 1.871, 11.87, 17.81
d 22.69, 22.96, 26.92, 29.26, 29.62

10 **a** Waugh, Border, Gilchrist, Taylor, Hughes
b first

11 **a** day 6 **b** day 4 **c** days 2, 5 and 6

12 **a** $c.c, c.a, b.c, b.a, a.c, a.b$
b $c.bc, c.ab, b.ca, b.bb, a.ca, a.bc, a.aa, ba.ca, ab.ab$

13 **a** $0.a$ **b** $0.0a$ **c** $0.aa$ **d** $a.a0a$

14 **a** **i** 0.1, 1.0 (2 ways)
ii 0.12, 0.21, 1.02, 1.20, 2.01, 2.10, 10.2, 12.0, 20.1, 21.0 (10 ways)
iii 0.123, 0.132, 0.213, 0.231, 0.312, 0.321, 1.023, 1.032, 1.203, 1.230, 1.302, 1.320, 2.013, 2.031, 2.103, 2.130, 2.301, 2.310, 3.012, 3.021, 3.102, 3.120, 3.201, 3.210, 10.23, 10.32, 12.03, 12.30, 13.02, 13.20, 20.13, 20.31, 21.03, 21.30, 23.01, 23.10, 30.12, 30.21, 31.02, 31.20, 32.01, 32.10, 102.3, 103.2, 120.3, 123.0, 130.2, 132.0, 201.3, 203.1, 210.3, 213.0, 230.1, 231.0, 301.2, 302.1, 310.2, 312.0, 320.1, 321.0 (60 ways)
b 408 ways

Exercise 6B

1 **a** 5.8 **b** 2 **c** 80 **d** 6.78

2 **a** 5 **b** 9 **c** 1 **d** 4
e 0 **f** 9 **g** 6 **h** 5

3 **a** **i** 1 **ii** 7 **iii** 4 **iv** 8
b **i** 25.8 **ii** 25.82 **iii** 25.817 **iv** 26

4 **a** 14.8 **b** 7.4 **c** 15.6 **d** 0.9
e 6.9 **f** 9.9 **g** 55.6 **h** 8.0

5 **a** 3.78 **b** 11.86 **c** 5.92 **d** 0.93
e 123.46 **f** 300.05 **g** 3.13 **h** 9.85
i 56.29 **j** 7.12 **k** 29.99 **l** 0.90

6 **a** 15.9 **b** 7.89 **c** 236 **d** 1
e 231.9 **f** 9.4 **g** 9.40 **h** 34.713

7 **a** 24.0 **b** 14.90 **c** 7 **d** 30.000

8 **a** 28 **b** 9 **c** 12 **d** 124
e 22 **f** 118 **g** 3 **h** 11

9 **a** \$13 **b** \$31 **c** \$7 **d** \$1567
e \$120 **f** \$10 **g** \$1 **h** \$36

10 **a** \$51 **b** \$44 **c** very accurate

11 **a** 0 s **b** 0.4 s **c** 0.34 s **d** 52.825 s

12 2.25, 3 decimal places

13 Samara: Round to 2 decimal places = 0.45, then round this to 1 decimal = 0.5. Cassandra: Rounding to 1 decimal place, critical digit is the second 4, which is less than 5, therefore rounded to 1 decimal place = 0.4.
Samara has a flaw of rounding an already rounded number. Cassandra is correct.

14 depends on your calculator

15 depends on your software package

Exercise 6C

1 C

2 B

3 **a** 27.97 **b** 25.94 **c** 247.4 **d** 58.31

4 **a** 16.06 **b** 21.33 **c** 343.75 **d** 37.567
e 21.592 **f** 340.0606

5 **a** 12.1 **b** 114.13 **c** 6.33 **d** 70.79

6 **a** 12.3 **b** 131.4 **c** 22.23 **d** 13.457
e 43.27 **f** 4947.341

7 **a** 7, 8 **b** 6, 5, 1, 4 **c** 0, 1, 0, 2 **d** 7, 5, 1, 6, 1

8 186.19

9 \$54.30

10 49.11 mm

11

+	0.01	0.05	0.38	1.42
0.3	0.31	0.35	0.68	1.72
0.75	0.76	0.80	1.13	2.17
1.20	1.21	1.25	1.58	2.62
1.61	1.62	1.66	1.99	3.03

12 \$2036.10

13 **a** 8.038 **b** 0.182 **c** 2.438 **d** 1.308

14 **a** Answers will vary; e.g. $3.57 + 4.15 + 3.44$
b Answers may vary; e.g. $1.35 + 2.87 + 6.94 = 11.16$

15 Always end up with \$10.89 unless the starting value has the same first digit, in which case we end up with zero. The 8 forms as it comes from adding two 9s. This produces a 1 to be carried over, which results in the answer being a \$10 answer, rather than a \$9 answer.

Exercise 6D

1 **a** 00 **b** 000 **c** 00 **d** 00000

2 **a** 000 **b** 00 **c** 0 **d** 00000

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

3 **a** **i** right 2 places **ii** left 1 place
iii right 6 places **iv** no change
v left 3 places **vi** right 3 places
vii right 1 place **viii** left 7 places
b right 1 place

4 **a** 48.7 **b** 352.83 **c** 4222.7 **d** 1430.4
e 5699.23 **f** 125.963 **g** 12 700 **h** 154 230
i 3400 **j** 2132 **k** 86 710 000 **l** 516 000

5 **a** 4.27 **b** 35.31 **c** 2.4422 **d** 56.893
e 12.135 18 **f** 9.326 11 **g** 0.029 **h** 0.001 362
i 0.000 54 **j** 0.367 **k** 0.000 002 **l** 0.010 000 4

6 **a** 2291.3 **b** 31.67 **c** 0.49 **d** 0.222
e 63 489 000 **f** 0.001 003 2

7 **a** 15 600 **b** 43 000 **c** 225.1 **d** 0.016
e 213 400 **f** 21.34 **g** 0.007 **h** 9 900 000
i 0.0034

8 **a** 158.4 **b** 3.36 **c** 85.4 **d** 7054
e 71.06 **f** 7.5 **g** 2.037 **h** 21.7

9 $137

10 **a** 1 200 000 mL
b 12 000

11 3000c, $30

12 $21 400

13 225 kg

14 Answers may vary.

Starting number	Answer	Possible two-step operations
12.357	1235.7	× 1000, ÷ 10
34.004 5	0.034 004 5	÷ 100, ÷ 10
0.003 601	360.1	× 100, × 1000
bac.dfg	*ba.cdfg*	÷ 100, × 10
d.swkk	*dswkk*	× 100 000, ÷ 10
fwy	*f.wy*	÷ 1000, × 10

15 ÷ 1 000 000

16 **a** **i** 5×10^{13} **ii** 4.2×10^{7} **iii** 1.23×10^{16}
b **i** 2×10^{19} **ii** 1.08×10^{21}
e 3.5×10^{-11}
f **i** 1×10^{-6} **ii** 9×10^{-10} **iii** 7.653×10^{-12}

Exercise 6E

1 **a** 1 **b** 2 **c** 3 **d** 3 **e** 5
f 2 **g** 4 **h** 3 **i** 9

2 **a** 19.2 **b** 1.92 **c** 0.192

3 It helps you check the position of the decimal point in the answer.

4 **a** The decimal point is the actual 'dot'; decimal places are the numbers after the decimal point.
b 1 decimal point, 4 decimal places

5 in the question; decimal places

6 **a** 20.84 **b** 26.6 **c** 183.44 **d** 100.8
e 218.46 **f** 15.516 **g** 23.12 **h** 12.42
i 5.44 **j** 311.112 **k** 0.000 966 **l** 1.321 31

7 **a** 100.8 **b** 483 **c** 25 400 **d** 9800
e 14 400 **f** 364 550 **g** 0.68 **h** 371
i 90.12

8 **a** $31.50, $32 **b** $22.65, $23
c $74.80, $75 **d** $17.40, $17
e $145.20, $145 **f** $37 440, $37 440
g $88.92, $89 **h** $4.41, $4
i $18.0625, $18

9 29.47 m

10 3.56 kg

11 165.85 km

12 **a** 67.2 m **b** $198.24

13 $1531.25

14 **a** 738.4 km **b** yes
c 1.57 L left in the tank

15 Answers may vary; 0.25, 0.26

16 Answers may vary; 0.0043

17 **a** 38.76 **b** 73.6 **c** 0.75 **d** 42, 0.42

Exercise 6F

1 B

2 directly above the decimal point in the dividend

3 **a** 60 **b** 60 **c** 60 **d** 60
b An identical change has occurred in both the dividend and the divisor.

4 **a** 32.456, 3 **b** 12 043.2, 12
c 34.5, 1 **d** 1 234 120, 4

5 **a** 4.2 **b** 6.1 **c** 21.34 **d** 0.7055
e 1.571 **f** 0.308 **g** 3.526 **h** 124.3
i 0.0024 **j** 117.105 **k** 0.6834 **l** 0.002 562 5

6 **a** 30.7 **b** 77.5 **c** 26.8 **d** 8.5
e 44.4 **f** 645.3 **g** 0.08 **h** 0.050 425
i 980 **j** 800.6 **k** 0.79 **l** 2 161 000

8 **a** 1.1807 **b** 8.267 **c** 0.012 374 8
d 0.004 23 **e** 0.096 487 **f** 0.000 782 5

9 **a** 11.83 kg **b** $30.46 **c** 304.33
d 239.17 g **e** 965.05 L **f** $581.72

10 **a** 20.84 **b** 93.36 **c** 10.93
d 18.49 **e** 67.875 **f** 158.35

11 **a** 8, 9 **b** 9 **c** 1, 5, 5 **d** 7, 7, 0

12 $1.59/L

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

13 238 frames

14 26.67, 26 can be filled

15 **a** \$66.35 **b** \$21.90

16 apples \$3.25/kg; bananas \$3.10/kg; hence, bananas are better value.

17 **a** 24.5 m/s **b** 88.2 km/h **c** yes

18 **a** 24.53 **b** 19.7 **c** 2453
d 1.97 **e** 2.453 **f** 197

19 **a** 0.5 **b** 0.3 **c** 0.01 **d** 1.1 **e** 4.8
f Answers may vary

Progress quiz

1 **a** 6 hundredths **b** 6 units

2 **a** 0.9 **b** 0.019 **c** 3.25

3 0.043, 0.34, 0.43, 3.4, 4.3

4 **a** 16.88 **b** 2.350 **c** 0.7

5 **a** 5.4 **b** 17.031 **c** 3.52 **d** 5.78

6 **a** 3450 **b** 0.653 45

7 **a** 90 000 **b** 119 **c** 1.912 **d** 136 800
e 14.1 **f** 0.013 **g** 193.2 **h** 0.221
i 9000 **j** 2.52

8 **a** 8.011 **b** 197.44

9 **a** \$10.15 **b** \$3.99 per kg **c** 25 kg

Exercise 6G

1 **a** 5 **b** 100 **c** 75, 7 **d** 5, 4

2 **a** 2 **b** 15, 20 **c** 10, 4 **d** 16

3 **a** false **b** true **c** true **d** false
e true **f** true

4 **a** $\frac{1}{2}$ **b** $6\frac{2}{5}$ **c** $10\frac{3}{20}$ **d** $18\frac{3}{25}$
e $3\frac{1}{4}$ **f** $\frac{1}{20}$ **g** $9\frac{3}{40}$ **h** $5\frac{24}{125}$

5 **a** 0.7 **b** 0.9 **c** 0.31 **d** 0.79
e 1.21 **f** 3.29 **g** 0.123 **h** 0.03

6 **a** $\frac{8}{10} = 0.8$ **b** $\frac{5}{10} = 0.5$ **c** $\frac{35}{100} = 0.35$
d $\frac{46}{100} = 0.46$ **e** $5\frac{95}{100} = 5.95$ **f** $3\frac{25}{100} = 3.25$
g $\frac{25}{10} = 2.5$ **h** $\frac{375}{1000} = 0.375$

7 **a** 0.5 **b** 0.5 **c** 0.75 **d** 0.4
e $0.\dot{3}$ **f** 0.375 **g** $0.41\dot{6}$ **h** $0.\overline{428571}$

8 **a** 0, 0.5, 1
b 0, $0.\dot{3}$, $0.\dot{6}$, $0.\dot{9}$ $(0.9999999\ldots = 1)$
c 0, 0.25, 0.5, 0.75, 1
d 0, 0.2, 0.4, 0.6, 0.8, 1.0

9 **a** $\frac{1}{4}, 0.4, \frac{1}{2}, \frac{5}{8}, 0.75, 0.99$
b $\frac{1}{9}, 0.13, \frac{3}{7}, 0.58, \frac{4}{5}, 0.84$

10 **a** Tan: $= \frac{11}{37} = 0.\overline{297}$; Lillian: $= \frac{6}{21} = 0.\overline{285714}$; hence, Tan is the better chess player.
b two or more

11 0.11 mm, $\frac{11}{100}$ mm

12 0.5, 0.3, 0.25, 0.2, $0.16\dot{6}$, $0.\overline{142857}$, 0.125, $0.\dot{1}$, 0.1

13 $\frac{1}{10}, \frac{1}{5}, \frac{1}{4}, \frac{2}{5}, \frac{1}{2}, \frac{3}{5}, \frac{3}{4}, \frac{4}{5}, \frac{9}{10}$

14 Answers may vary; $2\frac{4}{9}, 2\frac{45}{100}, 2\frac{3}{7}$

15 2, $\frac{4}{7}$, $= 0.\overline{571428}$, repeating pattern

Exercise 6H

1 **a** 95% **b** 60% **c** 75% **d** 26%

2 C **3** B **4** A

5 **a** 50 **b** 50%
c **i** 5 **ii** 100 **iii** 20 **iv** 1
d **i** 50% **ii** 50% **iii** 50% **iv** 50%

6 **a** 100, ÷, 100, . **b** 35, 100, 35, 0
c out of, 126, 100, 26

7 **a** 0.32 **b** 0.27 **c** 0.68 **d** 0.54
e 0.06 **f** 0.09 **g** 1 **h** 0.01
i 2.18 **j** 1.42 **k** 0.75 **l** 1.99

8 **a** 0.225 **b** 0.175 **c** 0.3333 **d** 0.0825
e 1.1235 **f** 1.888 **g** 1.50 **h** 5.20
i 0.0079 **j** 0.000 25 **k** 0.0104 **l** 0.0095

9 **a** 80% **b** 30% **c** 45% **d** 71%
e 41.6% **f** 37.5% **g** 250% **h** 231.4%
i 2.5% **j** 0.14% **k** 1270% **l** 100.4%

10 **a** 86%, 0.78, 75%, 0.6, 22%, 0.125, 2%, 0.5%
b 50, 7.2, 2.45, 1.8, 124%, 55%, 1.99%, 0.02%

11 35%

12 **a** 25% **b** 78%

13 24 gigalitres

14 **a** $ab.cd\%$ **b** $aac\%$ **c** $abdc\%$
d $d.d\%$ **e** $cdb.a\%$ **f** $cc.cddd\%$

15 **a** $0.0ab$ **b** $b.cd$ **c** $0.ac$
d $0.00da$ **e** $ab.bb$ **f** $0.ddd$

16 **a** no
b Answers may vary. Examples include: percentage score on a Maths test, percentage of damaged fruit in a crate, percentage of spectators wearing a hat, percentage of the day spent sleeping.
c Answers may vary. Examples include: percentage profit, percentage increase in prices, percentage increase in the price of a house, percentage score on a Maths test with a bonus question.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

17 a $F \div A \times 100$
b F: points scored for the team; A: points scored against the team
c 100%
d 158 points
e yes; Hawthorn 90.60%, Port Adelaide 91.32%

Problems and challenges

1 a 2 b $100A$ c 0.2
d $\frac{479}{330}$ or $\frac{1437}{990}$
e $2 \times \$1$ coins, 3×50-cent pieces and 3×20-cent pieces

2 Height of rungs: 0.18 m, 0.36 m, 0.54 m, 0.72 m, 0.9 m, 1.08 m, 1.26 m, 1.44 m, 1.62 m, 1.8 m

3 a $A = 1, B = 7, C = 8$
b $A = 7, B = 5, C = 1, D = 9$
c $A = 4, B = 2$
d $A = 3, B = 7$

4 a i 1.96 ii 2.25 iii 2.1025
b i 1.41 ii 1.414

Multiple-choice questions

1 D 2 B 3 C 4 E 5 A
6 D 7 D 8 B 9 A 10 C

Short-answer questions

1 a 0.44, 0.4, 0.04 b 2.16, 2.026, 2.016
c 0.98, 0.932, 0.895

2 a 8.1 b 0.81 c 8.01 d 0.801

3 a 3 hundredths $= \frac{3}{100}$ b 3 thousandths $= \frac{3}{1000}$
c 3 ones $= 3$

4 a false b false c true
d true e false f true

5 45.270, 45.271, 45.272, 45.273, 45.274, 45.265, 45.266, 45.267, 45.268, 45.269

6 a 423.5 b 15.89 c 7.3 d 70.000
e 2.8 f 0.67 g 0.455
h 0.012 345 679 012 345 679 012 345 679 012 345 679 012 345 68

7 a 9.53 b 4.137 c 43.35
d 240.49857 e 83.497 f 205.22

8 a true b false c false d false
e true

9 a 5 b 5 c 4 d 2

10 a 137 b 790 c 22.51 d 0.096 208
e 696.956 f 360.5 g 563 489.3

11 a 19.2 b 63.99 c 19.32 d 0.95
e 1.52 f 6 g 16 h 3
i $3.10\dot{9}$

12

Decimal	Fraction	Percentage
0.45	$\frac{45}{100} = \frac{9}{20}$	45%
0.7	$\frac{70}{100} = \frac{7}{10}$	70%
0.32	$\frac{32}{100} = \frac{8}{25}$	32%
0.06	$\frac{6}{100} = \frac{3}{50}$	6%
0.79	$\frac{79}{100}$	79%
1.05	$\frac{105}{100} = \frac{21}{20}$	105%
0.35	$\frac{35}{100} = \frac{7}{20}$	35%
0.65	$\frac{60}{100} = \frac{13}{20}$	65%
0.125	$\frac{125}{1000} = \frac{1}{8}$	12.5%

Extended-response questions

1 a Jessica \$12.57; Jaczinda \$13.31; hence, Jaczinda earns higher pay rate by 74c per hour.
b \$37.47, \$37.45 to the nearest 5 cents
c \$40.56
d \$48.34

2 a \$30.40 b \$18 240.30

3 32 min and 43 seconds, on average

Semester review 1

Whole numbers

Multiple-choice questions

1 E 2 B 3 D 4 C 5 A

Short-answer questions

1 a  b LXXIV c 

2 a 67 849 b 700 850

3 a 99 323 b 6867 c 441
d 196 000 e 1644 f $764\frac{3}{4}$

4 a false b true c true

5 36

6 a 30 b 56 c 48 d 160
e 16 f 42

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

7 a false b true c false d true
e true f true
8 $18 \times (7 + 3)$
9 9 times
10 a 3 859 640 b 3 860 000 c 4 000 000

Extended-response questions

1 a 28 b $700 c $1000 d 12 h

Geometry

Multiple-choice questions

1 A 2 B 3 B 4 B 5 D

Short-answer questions

1 a $AC \parallel FD$ or $EB \parallel DC$
b BF and BD
c CD, ED, BD at D or any three of AC, BD, BE or BF at B
d A and B
e E
2 a 30° b 80° c 150°
3 25°
4 78°
5 a $a = 140$ b $a = 50$ c $a = 140$ d $a = 65$
e $a = 62$ f $a = 56$
6 $a = 100$, $b = 80$, $c = 100$, $d = 80$, $e = 100$, $f = 80$, $g = 100$
7 Because the cointerior angles add to more than 180°.
8 Check with your teacher.

Extended-response questions

1 a i $x = 56$ ii $y = 95$ iii $z = 29$
b $x + y + z = 180$

Number properties and patterns

Multiple-choice questions

1 C 2 A 3 B 4 E 5 D


Short-answer questions

1 a 1, 3, 5, 15
b 1, 2, 3, 5, 6, 10, 15, 30
c 1, 2, 4, 5, 10, 20, 25, 50, 100
2 a 3, 6, 9, 12, 15 b 7, 14, 21, 28, 35
c 11, 22, 33, 44, 55
3 2, 3 and 6
4 4
5 a 121 b 144 c 25
6 120
7 false
8 a 1 b 1 c 1
9 a 61 b 17
10

input	4	5	6	9	11	100
output	19	23	27	39	47	403

11 A (1, 0), B (4, 1), C (3, 2), D (1, 3), E (3, 4)

Extended-response questions

1a 
b 18 c 9th d $61

Fractions

Multiple-choice questions

1 B 2 C 3 E 4 D 5 A

Short-answer questions

1 $\frac{3}{10}, \frac{1}{3}, \frac{2}{5}, \frac{1}{2}$
2 $\frac{17}{3}$
3 a $\frac{11}{12}$ b $2\frac{2}{3}$ c $6\frac{1}{4}$ d $\frac{1}{5}$
e 4 f $\frac{1}{2}$
4 $\frac{3}{20}$
5 $120
6 $60
7 a true b true c true d false
8 67%

Extended-response questions

1 a 6 b $\frac{8}{9}$ c 9
d second dose on Sunday week

Algebra

Multiple-choice questions

1 B 2 A 3 C 4 E 5 D

Short-answer questions

1 a 4 b yes c 9 d 7
2 a $x + 3$ b $12a$ c $2x + 3y$
d $\frac{w}{6}$ e $y - 2x$
3 a $100m$ b $24x$ c $1\,000\,000p$
d $\frac{y}{24}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 **a** 13 **b** 11 **c** 39 **d** 6
e 6 **f** 24

5 36

6 **a** $10a$ **b** $4x$ **c** $12a$
d m **e** $6 + 5a$ **f** $4x + 2y$

7 **a** $2x + 14$ **b** $3(x + 4) = 3x + 12$

8 **a** $6bc$ **b** $5b$ **c** p

9 **a** $2a + 6$ **b** $12a - 12b$ **c** $24m + 32$

10 $12xy$

Extended-response questions

1 **a** **i** \$12 **ii** $\$(3x + 6)$ **iii** $\$(3x + 2y)$
b $\$(50 - 3x - 2y)$

Decimals

Multiple-choice questions

1 E **2** C **3** D **4** A **5** B

Short-answer questions

1 **a** 0.2 **b** 0.13 **c** 1.7

2 **a** 6 units **b** $\frac{4}{1000}$ **c** 136.1

3 **a** 18 **b** 18.4 **c** 18.40

4 **a** 4.07 **b** 269.33 **c** 19.01
d 0.24 **e** 0.09 **f** 60

5 **a** 0.833 **b** 3 **c** 36

6 **a** 4.5387 **b** 0.045 387 **c** 1.23

7 **a** 36 490 **b** 0.018 **c** 3886

8 **a** $\frac{4}{5}$ **b** 1.1 **c** $\frac{2}{3}$

9 **a** true **b** false **c** false
d true **e** false **f** true

Extended-response questions

1 **a** \$64.08 **b** \$64.10 **c** \$64.35 **d** 25c
e It becomes \$63.90 rather than \$63.80.


Chapter 7


Exercise 7A


1 **a** $-2, 2$ **b** $0, 2$ **c** $-7, -5$ **d** $-5, -3, 0$


2 **a** -2 **b** -6 **c** 3 **d** 7
e 15 **f** -21 **g** -132 **h** 1071

3 **a** greater **b** less **c** greater **d** less

4 **a**


b


c


d


5 **a** $-2, -1, 0, 1, 2, 3, 4$
b $-7, -6, -5, -4, -3, -2, -1, 0$
c $-2, -1, 0, 1$ **d** $-4, -3, -2, -1, 0$
e $-3, -2, -1, 0, 1, 2, 3$ **f** $-9, -8, -7, -6, -5, -4$

6 **a** $<$ **b** $>$ **c** $>$ **d** $<$
e $>$ **f** $<$ **g** $<$ **h** $>$
i $<$ **j** $>$ **k** $<$ **l** $>$

7 **a** 4°C **b** -1°C **c** -7°C **d** -25°C

8 **a** $-10, -6, -3, -1, 0, 2, 4$
b $-304, -142, -2, 0, 1, 71, 126$

9 **a** $0, -1, -2$ **b** $-2, 0, 2$
c $-5, -10, -15$ **d** $-44, -46, -48$
e $-79, -75, -71$ **f** $-101, -201, -301$

10 **a** \$5 **b** $-$\$10

11 **a** -50 m **b** -212.5 m **c** 0 m

12 **a** 2 **b** 4 **c** 4 **d** 7
e 3 **f** 3 **g** 6 **h** 44

13 **a** -2 **b** 1 **c** -1
d -7 **e** -51 **f** 357

Exercise 7B

1 **a** right **b** right **c** left **d** left

2 **a** D **b** A **c** B **d** C

3 **a** 1 **b** 3 **c** 2 **d** 1
e -1 **f** -3 **g** -2 **h** -2
i -4 **j** -8 **k** -1 **l** 2
m 2 **n** -9 **o** 6 **p** -31

4 **a** -2 **b** -1 **c** -8 **d** -19
e -4 **f** -10 **g** -15 **h** -7
i -41 **j** -12 **k** -22 **l** -47
m -300 **n** -100 **o** -93 **p** -634

5 **a** 5 **b** 9 **c** 5 **d** 2
e 5 **f** 7 **g** 3 **h** 10
i 5 **j** 16 **k** -4 **l** -5
m -6 **n** -13 **o** -30 **p** -113

6 **a** 5 **b** -9 **c** 1 **d** -13
e 1 **f** -22 **g** -32 **h** -4

7 **a** \$145 **b** \$55 **c** \$5250

8 **a** 3°C **b** -3°C **c** -46°C

9 69°C

10 **a** 59 m **b** 56 m

11 Answers may vary.

12 **a** **i** positive **ii** positive **iii** negative **iv** zero
b **i** no **ii** yes

13 Other combinations may be possible.
a $-, +$ **b** $+, -, -,$ **c** $+, +, -, +$
d $-, +, +, +, -$ **e** $+, +, -$ **f** $-, +, -, -$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Exercise 7C

1 **b** 6, −3 **c** −3, 1 **d** −11, −7 **e** 3, 5
f 6, −2 **g** −3, 7 **h** −11, −7

2 **a** 4 **b** subtracting **c** −5
d subtracting **e** 2 **f** adding

3 **a** false **b** true **c** true **d** false
e false **f** true **g** false **h** false

4 **a** 1 **b** 5 **c** 6 **d** 2
e −3 **f** −5 **g** −2 **h** −4
i −3 **j** −22 **k** −35 **l** −80
m −10 **n** −29 **o** −50 **p** −112

5 **a** 5 **b** 11 **c** 50 **d** 90
e −4 **f** −3 **g** −5 **h** −34
i 2 **j** 1 **k** 0 **l** 8
m 28 **n** 34 **o** −12 **p** −76

6 **a** −3 **b** −10 **c** −4 **d** 4
e −1 **f** 4 **g** −1 **h** −5
i −4 **j** 4 **k** 2 **l** −24
m −6 **n** −5 **o** 2 **p** 4

7 **a** 0 **b** −5 **c** 8 **d** 12
e −9 **f** 5 **g** −6 **h** −91
i −15 **j** 6 **k** 17 **l** 11

8 −143 m

9 −$35 000

10 −$30

11 **a** **i** $8000 **ii** −$6000
b $2000

12 **a**

−2	0	5
8	1	−6
−3	2	4

b

−13	−11	−6
−3	−10	−17
−14	−9	−7

13 **a** $3 + 4$ **b** $-2 + (-9)$ **c** $5 - (-2)$
d $1 - (-2)$ **e** $a + (-b)$ **f** $a - (-b)$

14 **a** 4 **b** −1 **c** −3

15 **a** **i** no **ii** yes
b **i** yes **ii** no
c Yes, if $b < a$ then subtracting b takes the result to a number bigger than zero.

16 **a** $\frac{3}{2}$ **b** $\frac{11}{3}$ **c** −2 **d** −4
e $\frac{16}{3}$ **f** $\frac{23}{2}$ **g** $-\frac{1}{2}$ **h** $-\frac{1}{14}$
i $\frac{3}{2}$ **j** $\frac{15}{2}$ **k** $\frac{37}{6}$ **l** $\frac{32}{35}$
m $-\frac{11}{6}$ **n** $-\frac{27}{20}$ **o** $\frac{67}{14}$ **p** $-\frac{53}{30}$

Exercise 7D

1 **a**

×	−2	−1	0	1	2
−2	4	2	0	−2	−4
−1	2	1	0	−1	−2
0	0	0	0	0	0
1	−2	−1	0	1	2
2	−4	−2	0	2	4

b

×	−4	−2	0	2	4
−4	16	8	0	−8	−16
−2	8	4	0	−4	−8
0	0	0	0	0	0
2	−8	−4	0	4	8
4	−16	−8	0	8	16

2 **a** 2 **b** −3 **c** −4 **d** −4

3 **a** positive **b** positive **c** negative
d positive **e** positive **f** negative

4 **a** −15 **b** −10 **c** −6 **d** −54
e 32 **f** 28 **g** 144 **h** −99
i −39 **j** −84 **k** 38 **l** −108
m 66 **n** −45 **o** 63 **p** 72

5 **a** −2 **b** −12 **c** −2 **d** −4
e 3 **f** 1 **g** −5 **h** −19
i −7 **j** −12 **k** −68 **l** 8
m 12 **n** 13 **o** −13 **p** 13

6 **a** 24 **b** 15 **c** −4 **d** 5
e 1 **f** −10 **g** 72 **h** 18
i 1 **j** −1 **k** −69 **l** −3

7 **a** −7 **b** 4 **c** −4 **d** 8
e 27 **f** −140 **g** 2 **h** −3
i −3 **j** −1 **k** −2 **l** 40

8 **a** −3 **b** −3 **c** 8 **d** 31
e 3 **f** 5 **g** −30 **h** −100

9 **a** 4 **b** 1 **c** 81 **d** 100
e 36 **f** 64 **g** 9 **h** 2.25

10 **a** (1, 6), (2, 3), (−1, −6), (−2, −3)
b (1, 16), (2, 8), (4, 4), (−1, −16), (−2, −8), (−4, −4)
c (−1, 5), (−5, 1)
d (−1, 24), (−24, 1), (−2, 12), (−12, 2), (−3, 8), (−8, 3), (−4, 6), (−6, 4)

11 **a** ×, ÷ **b** ÷, × **c** ×, × **d** ÷, ×

12 **a** (4, −2), (−4, 2) **b** (33, −3), (−33, 3)

13 **a** **i** −8 **ii** 64 **iii** −27
iv 81
b parts **ii** and **iv**, even number of negative factors
c parts **i** and **iii**, odd number of negative factors


14 **a** $-ab$ **b** $-ab$ **c** ab

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

15 **a** $-\frac{1}{4}$ **b** $-\frac{1}{2}$ **c** $-\frac{3}{7}$ **d** 1
e -1 **f** $-\frac{5}{4}$ **g** $\frac{1}{2}$ **h** 6
i -1 **j** 1 **k** -1 **l** 1

Progress quiz

1



2 **a** $-2 < 1$ **b** $-9 > -12$ **c** $4 > -5$
3 $-6, -4, 0, 7, 8$
4 **a** 2 **b** -9 **c** -8 **d** -26
5 **a** 5 **b** -15 **c** -3 **d** 20
6 **a** 5 **b** 12
7 **a** -12 **b** 60 **c** -7 **d** 4
8 **a** 40 **b** -30 **c** 16 **d** -2
9 **a** 25 **b** -8 **c** 12 **d** -315
10 Debt of \$70 or $-$\$70

Exercise 7E

1 **a** division **b** multiplication **c** multiplication
d division **e** addition **f** subtraction
g multiplication **h** multiplication **i** multiplication
2 **a** true **b** false **c** true
d false **e** false **f** true
3 **a** -7 **b** 7 **c** 19 **d** 9
e 16 **f** 14 **g** 6 **h** -32
i -5 **j** -4 **k** -18 **l** -4
m -10 **n** 4 **o** 0
4 **a** -10 **b** -2 **c** -6 **d** 1
e 2 **f** 9 **g** 1 **h** 4
i -14 **j** -20 **k** 2 **l** -5
m 8 **n** -6 **o** -12
5 \$528
6 $-$\$50
7 **a** $(-2+3)\times 8 = 8$ **b** $-10 \div (4+1) = -2$
c $(-1+7)\times 2 - 15 = -3$
d $(-5-1)\div(-6) = 1$
e $(3-8)\div 5 + 1 = 0$
f $50 \times (7-8)\times(-1) = 50$
g $-2\times(3-(-7)) - 1 = -21$
h $(-3+9)\div(-7+5) = -3$
i $(32-(-8))\div(-3+7) = 10$
8 three answers (-10, -21, -31)
9 **a** no **b** no **c** yes
d yes **e** no **f** yes
10 **a** true **b** true **c** true
d true **e** false **f** false
11 **a** **i** negative **ii** negative **iii** negative
iv positive **v** negative **vi** negative
b If there is an even number of negative factors the result will be positive, if odd then negative
12 **a** 4 **b** 4 **c** -4 **d** -32
e -32 **f** 32 **g** 2 **h** -2
i -1
13 Kevin should have typed $(-3)^4$ to raise -3 to the power of 4. -3^4 is -1×3^4.

Exercise 7F


1 C **2** B **3** no, 20
4 **a** 17 **b** 23 **c** -8 **d** 8
e 6 **f** 11 **g** -7 **h** 6
i 3 **j** -9 **k** -9 **l** 6
5 **a** -8 **b** -2 **c** 2 **d** -13
e -25 **f** 17 **g** 36 **h** 18
6 **a** 38 **b** 5 **c** 4 **d** -13
e -4 **f** -16
7 **a** 10 **b** -1 **c** -24 **d** -6
8 **a** 6 m^2 **b** 16 m^2
9 **a** 32 metres per second
b 14 metres per second
c 2 metres per second
10 **a** **i** 16 **ii** -2
b A negative width is not possible.
11 Answer may vary.
12 Answers may vary.
13 **a** $a - a = 0$ and $-b + b = 0$
b $\frac{a}{a} = 1$
c $a - a = 0$
d $\frac{ab}{b}$ cancels to simply give a.
14 **a** **i** 5°C **ii** -15°C **iii** -25°C
b $F = \frac{9C}{5} + 32$

Exercise 7G

1 **a** D **b** B **c** A **d** C
e E **f** H **g** F **h** G
2 **a** 9 **b** 18 **c** 15 **d** 6
e 10 **f** 2 **g** 1
3 $A(2,1), B(3,-2), C(-1,-4), D(-2,2), E(4,3), F(2,-3), G(-3,-1), H(-4,4)$


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 **a, b**




5 **a** $A(3, 0), B(0, -2), C(-1, 0), D(0, 4), E(0, 2), F(1, 0), G(0, -4), H(-3, 0)$

6 **a**



b They lie in a straight line.

7 **a**



b They lie in a straight line.

8 **a** triangle **b** rectangle **c** trapezium **d** kite

9 **a** 4 square units **b** 6 square units
c 4 square units **d** 15 square units

10 28 km


11 $y = 2$

12 $y = 3$

13 **a** B **b** C **c** B, A, C


14 **a** **i** 1 and 4 **ii** 4 **iii** 3 and 4 **iv** 3

b



15 **a** $y = \{-7, -5, -3, -1, 1, 3, 5\}$

b, c



d They are in a straight line.

Problems and challenges

1 **a** $-81, 243, -729$ **b** $4, -2, 1$
c $-10, -15, -21$ **d** $-8, -13, -21$

2 **a** 0 **b** -153
c 101

3 **a** $-3 \times (4 + (-2)) = -6$ or $-3 \times 4 \div (-2) = -6$
b $-2 \times 5 \times (-1) + 11 = 21$ or
$-2 \times 5 \div (-1) + 11 = 21$
c $1 \times 30 \div (-6) - (-2) = -3$

4 **a** 11 and -3 **b** 21 and -10

5 9 pairs

6 $a = 1, b = -1, c = -2, d = -3, e = 5$

7 $-\frac{1}{25}$

8 **a** $p + t > q + t$ **b** $t - p < t - q$ **c** $pt < qt$

9 all numbers less than 1 except 0

Multiple-choice questions

1 C	**2** E	**3** B	**4** D	**5** C
6 A	**7** E	**8** C	**9** B	**10** C

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 a $<$ b $<$ c $>$ d $<$

2 a -5 b -2 c -15 d 1
e -2 f -5 g 12 h -18
i -6 j 5 k -11 l 5

3 a -1 b -9 c -1 d 2
e -21 f -2 g -87 h 30

4 a -10 b -21 c 30 d -5
e -3 f 4 g 1 h -8

5 a -2 b -50 c -36 d -1

6 a -37 b 8 c -3 d 1
e 56 f 80

7 a 10 b -41 c -22 d -11

8 $A(3, 0), B(2, 3), C(-1, 2), D(-4, -2), E(0, -3), F(4, -4)$

Extended-response questions

1 a 16°C b -31°C c 8°C d 19°C e 27°C

2 rocket

Chapter 8

Exercise 8A

1 a iii b iv c i
d v e vi f ii

2 a categorical b numerical c numerical
d categorical e numerical f numerical

3 Answers will vary.

4 a discrete numerical
b continuous numerical
c continuous numerical
d categorical
e categorical
f categorical
g discrete numerical
h discrete numerical
i continuous numerical
j continuous numerical
k continuous numerical
l discrete numerical
m continuous numerical
n discrete numerical
o categorical
p discrete numerical
q discrete numerical
r categorical

5 a observation
b sample of days using observation or secondary source records within each day
c census of the class
d sample
e sample
f sample using secondary source data
g census (this question appears on the population census)
h census of the class
i sample
j results from the population census
k observation
l observation
m sample
n sample

6 a secondary – a market research company
b secondary – department of education data
c primary data collection via a sample
d secondary source using results from the census
e secondary source using NAPLAN results or similar

7 a Proximity to the Indian Ocean makes first hand collection of the data difficult.
b Too many people to ask and a sensitive topic means that using the census results as your source would be better.
c Extremely large population makes primary data difficult to collect.
d Sensitive topic might make student less keen to give honest and reliable answers.
e Cultural issues and the different cultural groups that exist in the community makes collection difficult.

8 The data is often collected by a market research company. It is not always possible to know how the data is collected, the areas it is collected from and whether there was a bias introduced in the surveys.

9 a Population is the entire group of people but a sample is a selection from within it.
b If the population is small enough (e.g. a class) or there is enough time/money to survey the entire population (e.g. national census).
c When it is too expensive or difficult to survey the whole population, e.g. television viewing habits of all of NSW.

10 a The answers stand for different categories and are not treated as numbers. They could have been A–E rather than 1–5.
b i 1 = strongly disagree, 2 = somewhat disagree, 3 = somewhat agree, 4 = strongly agree.
ii 1 = poor, 2 = satisfactory, 3 = strong, 4 = excellent.
iii 1 = never, 2 = rarely, 3 = sometimes, 4 = usually, 5 = always.
iv 1 = strongly disagree, 2 = disagree, 3 = neutral, 4 = agree, 5 = strongly agree.

11 a Excludes people who have only mobile numbers or who are out when phone is rung; could bias towards people who have more free time.
b Excludes people who do not respond to these types of mail outs; bias towards people who have more free time.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c Excludes working parents; bias towards shift workers or unemployed.
d Excludes anyone who does not read this magazine; bias towards girls.
e Excludes people who do not use Facebook; bias towards younger people or people with access to technology.

12 a For example, number of babies at a local playground. Other answers possible.
b Count a sample, e.g. just one floor of one car park.

13 It gives ownership and establishes trust where there may not have been any. It also ensures a deeper understanding of the process and need for honesty in the collection and use of any data.

14 a Too expensive and difficult to measure television viewing in millions of households.
b Not enough people – results can be misleading.
c Programs targeted at youth are more likely to be watched by the students.
d Research required.

15 a Too expensive and people might refuse to respond if it came too often.
b English as a second language can impact the collection of data (simple, unambiguous English is required). Some people from particular cultures may not be keen to share information about themselves.
c Some people cannot access digital technologies and they would be excluded from the results.
d Larger populations and a greater proportion of people in poverty can make census data harder to obtain.

16 Different people are chosen in the samples. Larger, randomly selected samples give more accurate guides.

17 a i and
ii Answers will vary.
iii Random processes give different results.
b i Different vowels have different frequencies of occurring.
ii If a high frequency word has an unusual range of vowels, e.g. a webpage on Mississippi.

Exercise 8B

1 a 1, 2, 3, 5, 10 b 10
c 1 d 9

2 a 9 b 12 c 9 d 7

3 a 30 b 6 c 7 d 7

4 a i 6 ii 3 iii 2 iv 1
b i 11 ii 7 iii 8 iv 2
c i 18 ii 12 iii 11 iv 11
d i 17 ii 26 iii 25 iv 25
e i 32 ii 16 iii 15 iv 10
f i 40 ii 34 iii 30 iv 55
g i 102 ii 71 iii 83 iv 84
h i 91 ii 41 iii 31 iv 18

5 a 16.6 b 17.5 c 12

6 a Brent b Brent c Ali d Brent

7 43.5

8 a 2 b 4 c 12
d 25 e 2.1 f 4

9 a 12 b 2 c 0 saves

10 a {9, 11}; other solutions possible.
b {8, 10, 13}; other solutions possible.
c {0, 100}; other solutions possible.
d {0, 5, 5, 7, 8, 8.1, 8.9}; other solutions possible.

11 a 3 values; e.g. {5, 5, 8}
b yes, e.g. {0, 0, 5, 5, 5, 7, 20}

12 the mean distance (the median is basically unaffected)

13 a mean: 7, median: 7.5, mode: 10, range: 12
b i increases by 5 ii increases by 5
iii increases by 5 iv no effect
c i doubles ii doubles iii doubles
iv doubles
d Yes; e.g. if the set were duplicated: 1, 1, 3, 3, 5, 5, 10, 10, 10, 10, 13, 13.

14 a 7 and 13 b 9, 10, 11
c They must be 8, 10 and 12.

15 Numbers are: x, $x + 1$, $x + 2$; mean $= \frac{(3x + 3)}{3} = x + 1 =$ median

16 a range $= 6$, mean $= 7.18$ b range $= 4$, mean $= 7.21$

17 50.5

18 a i 4, 4, 4; other solutions possible.
ii 1, 4, 3, 9, 1; other solutions possible.
iii 2, 3, 8, 10, 10; other solutions possible.
iv 1, 2, 3, 4, 4, 16; other solutions possible.
b It is possible. (Hint: Divide every number by the current range.)

Exercise 8C


1 a true b false c true d true e false

2 a 5 b 3 c sport d 20

3 a 2 b 7 c red d 27

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


e **Favourite colour in 7B**



4 **a** 8 **b** 24 **c** 8 **d** 7 **e** 2

5 **a** 120 cm **b** 20 cm **c** 60 cm
d 11 years old

6 **a**



b




7 **a**

	1990	1995	2000	2005	2010	2015
Using public transport	30	25	40	50	60	55
Driving a car	60	65	50	40	20	20
Walking or cycling	10	20	15	15	25	60

b 2005 and 2010
c 2010 and 2015
d Environmental concerns; others answers possible.
e Public transport usage is increasing; other answers possible.


8 **a**



b 2000 **c** 2004 **d** 2002 **e** boys

9 **a** It has increased steadily. **b** approx. $38 000
c approx. $110 000-$130 000

10 **a** It is unequal.
b The axes have no labels and it does not have a title.
c



d four times as popular
e one and a half times as popular
f Music

11 **a** 7 **b** 7 **c** 3M: 8, 3S: 4
d 3M **e** 3M because best student got 10.

12 **a** 1500 **b** 104 000 **c** increased
d approx. 590 000 passengers


13 Helps to compare different categories quickly by comparing heights.

14 240

Exercise 8D

1 **a** 3 kg **b** 4 kg **c** 5 kg **d** 4.5 kg

2




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3 **a** 45 cm **b** 110 cm **c** 8 years
d 15 cm **e** 140 cm

4 **a** 23°C
b 2:00 pm
c 12:00 am
d **i** 10°C **ii** 18°C **iii** 24°C
iv 24.5°C

5 **a**



b Weight increases from January until July, then goes down suddenly.
c July


6 **a** 200 km **b** 80 km **c** At rest
d In the first hour **e** 40 km

7 **a** 2 hours **b** 5 km **c** Fifth hour


8 **a** July
b Year starts July and ends October.
c 20 megalitres because the level stayed the same
d Southern Hemisphere because winter occurs in middle of year.

9 **a** at 7:00 am and 8:00 pm
b at 8:00 am and 11:00 pm
c **i** around 7:00 am (heater goes on)
ii around 8:00 am (turns heater off)
iii around 8:00 pm (heater put back on)
iv around 11:00 pm (heater turned off)
d Answers will vary.


10 **a**



b



11 **a** City is in Southern Hemisphere because hot in January/December.
b City is quite close to equator because winter temperatures reasonably high.
c



d Maximum occurs in the middle.
e It depends on what Month 1 means. If it means January, then this is the Northern Hemisphere. If it means June, then this is the Southern Hemisphere.

Exercise 8E

1 **a** 5 **b** 2

2 **a** 39 **b** 27 **c** 134

3 57

4 **a** 8, 9, 10, 11, 13, 15, 17, 18, 21, 24
b 10
c **i** false **ii** true **iii** true
iv false

5 **a** range = 20, median = 17 **b** range = 31, median = 26
c range = 19, median = 40.5

6 **a**

Stem	Leaf
1	1 2 3 4 4 5 7
2	0 4 8 9
3	1 2 3 5

b

Stem	Leaf
2	0 2
3	9
4	5 7 9 9
5	1 2 2 3 5 6 8 8

c

Stem	Leaf
1	6 6 8
2	1 4 8 9
3	1 2 3 5
4	1 8 9
5	0

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d

Stem	Leaf
1	1 2 4
2	7 9
3	2 7 8 8
4	
5	
6	0 0
7	3 8
8	1 7

7 a

Stem	Leaf
8	0 4 5 6
9	0 6
10	1 4 5
11	0 3 4 4 5 9

b

Stem	Leaf
8	1 6
9	1 4 5 6 8
10	2 6 8
11	3 5 5 7
12	0

c

Stem	Leaf
15	5 7 8
16	2 5 7
17	3 4 8
18	1 4 4 5 7
19	2 2 3 3 6 9

d

Stem	Leaf
39	1 5 6
40	1 2 4 5 6 6 8 9
41	1 2 3 3 5 6 7 8
42	0

8 a 2 **b** B **c** 1 **d** B
e 1 **f** N **g** 2 **h** 1
i N

9 a 10 **b** 1 **c** 8
d 58 **e** 10 seconds

10 a i 49 years **ii** 36 years
b radio station 1
c i 33 to 53 years **ii** 12 to 32 years

11 a i 30 **ii** 52
b girls
c i 151.5 cm **ii** 144.5 cm
d boys
e perhaps Year 6 or 7
f Both would have a smaller range and a higher median.

12 a 15 **b** 13
c a is 5 or 6, b is 0, c is 8 or 9, d is 0.

13 a Easier to compare sizes of different stems visually.
b Helps in noticing trends and calculating the median.

14 a i 30 **ii** 10
iii between 10 and 19 years old
iv between 31 and 49 years **v** 18
vi between 18 and 28
b i true **ii** false **iii** true
iv true **v** false **vi** false
c Cannot determine how many people are exactly aged 40 years.
d close to 30 years


15 a minimum: −29°C, maximum: 23°C
b i 5 **ii** 10 **iii** 11
c Because −05 and 05 are different numbers
d −5.2°C
e −8°C; it is 2.8°C higher than the mean.

Exercise 8F


1 a playing sport **b** watching television
c more

2 a rugby **b** basketball **c** $\frac{1}{5}$ **d** $\frac{2}{3}$


3 a 20
b i $\frac{3}{10}$ **ii** $\frac{1}{4}$ **iii** $\frac{7}{20}$
iv $\frac{1}{10}$
c i 108° **ii** 90° **iii** 126°
iv 36°
d



4 a



b



Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


c Higher proportion of Year 7s like red; higher proportion of Year 8s likes yellow.

d




■ red □ green ■ yellow ■ blue □ pink

5 a




■ food □ drinks ■ household items ■ other

b




6 a i 20 ii 10 iii 6 iv 4

b



c i chips ii fruits and pies
iii chocolate

7 a i 9 ii 6 iii 15



8 a Krishna b Nikolas

c It means Nikolas also spends more time playing sport.


9 a 6 b 10

c Bird was chosen by $\frac{1}{8}$, which would be 2.5 people.

d Each portion is $\frac{1}{3}$, but $\frac{1}{3}$ of 40 is not a whole number.

e 24, 48, 72 or 96 people participated in survey.

10 a



b 24 c 6

Progress quiz


1 a categorical b continuous numerical
c discrete numerical d continuous numerical

2 a i 10 ii 6 iii 5 iv 3

b i 13 ii 20 iii 19 iv 15

3 a 2 children b 17 children c 7
d 3 children e 8 children

4 a



b around 24°C


5 a 20 km b 10 km c at rest
d 10 km e 5th hour

6 a 14 towns
b maximum 37°C, minimum 14°C
c 23°C
d 26°C


7

Stem	Leaf	1/6 means 16
0	7 9	
1	0 2 6 8 8 9	
2	0 1	

8 a



b



Exercise 8G

1 a D b A c B d C

2 a certain b even chance
c unlikely d impossible

3 a true b false c true d false
e true f false

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

4 **a** D **b** C **c** A **d** B

5 **a** **i** true **ii** false **iii** false
iv true **v** true


b **i** spinner landing on yellow (other answers possible)
ii spinner not landing on red
iii spinner landing on green, blue or red
iv spinner landing on blue or on red

6 **a** spinner 3 **b** spinner 2 **c** spinner 1

7 Answers will vary.


8 **a** Blue, red and green equally likely.
b Red and green both have an even chance.
c Green and blue equally likely, red and blue are not equally likely.
d Blue is certain.
e Blue, red and green all possible, but no two colours are equally likely.
f Red and blue both have an even chance.

9 **a**




b All sectors have the same size; i.e. 60°.

c




d by replacing the 5 with a 6 (so that there are two faces with 6).
e with 52 equal segments

10 **a** spinner 1: $\frac{1}{4}$, spinner 2: $\frac{1}{3}$, spinner 3: $\frac{1}{9}$
b $\frac{1}{2}$
c **i**



ii



Other answers possible

d **i** 50% **ii** 0% **iii** 0%, 50%
iv 50%
e If the two fractions are equal, the two events are equally likely.
f The proportion of the spinner's area cannot exceed 100% (or 1) and must be greater than or equal to 0%.

Exercise 8H

1 **a** C **b** A **c** D **d** B

2 **a** sample space **b** 0 **c** certain
d more **e** even chance

3 **a** {1, 2, 3, 4, 5, 6} **b** {1, 3, 5} **c** $\frac{1}{2}$

4 **a** 3: red, green, blue
b $\frac{1}{3}$ **c** $\frac{2}{3}$ **d** $\frac{2}{3}$ **e** 0


5 **a** {1, 2, 3, 4, 5, 6, 7}
b $\frac{1}{7}$ **c** 0 **d** $\frac{2}{7}$ **e** $\frac{3}{7}$ **f** $\frac{4}{7}$
g Number chosen is less than 10; other solutions possible.

6 **a** {M, A, T, H, S} **b** 0.2 **c** 0.8
d 60%

7 **a** $\frac{1}{11}$ **b** $\frac{2}{11}$ **c** $\frac{5}{11}$
d $\frac{9}{11}$ **e** $\frac{4}{11}$
f Choosing a letter in the word ROPE; other solutions possible.

8 **a** 30% **b** 50% **c** 80%

9 **a** {2, 3, 4, 5, 6, 7, 8, 9}
b 0.5
c **i** 0.375 **ii** 0.375 **iii** 0
d Possible spinner shown:



10 **a** **i** 12 red, 6 blue, 4 yellow, 2 green
ii $\frac{1}{12}$
b **i** 18 red, 9 blue, 6 yellow, 3 green
ii $\frac{1}{12}$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

c 12

d No, because it is always $1 - \frac{1}{2} - \frac{1}{4} - \frac{1}{6}$.


11 **a** $a = 1, b = \frac{1}{2}, c = 1, d = \frac{1}{3}, e = 1, f = \frac{2}{5}, g = \frac{3}{5}, h = 1$

b $\frac{10}{13}$

c $\frac{3}{7}$

12 **a** yes, $\frac{19}{210}$ **b** 210 **c** 840


13 **a** **i**



ii Cannot be done because adds to more than 1.

iii Cannot be done because adds to less than 1.

iv



b $1 - x - y$. Also x, y and $1 - x - y$ must all be between 0 and 1.

Exercise 8I

1 **a** $\frac{1}{10}$ **b** $\frac{2}{5}$ **c** $\frac{3}{10}$

2 **a** $\frac{53}{100}$ **b** $\frac{47}{100}$ **c** $\frac{1}{2}$

3 **a** 50 **b** $\frac{2}{5}$ **c** $\frac{1}{10}$ **d** $\frac{1}{2}$

e No, just that nobody did it within the group surveyed.

4 **a** 500

b 1750

c **i** 7 tails **ii** more

5 **a** 100 **b** 300

c yes (but this is very unlikely)

d from 2 rolls

6 Answers will vary.

7 **a** $\frac{1}{4}$ **b** $\frac{3}{100}$ **c** $\frac{31}{100}$ **d** 60

8 **a** 5 **b** 40 **c** 70

d $\frac{26}{35}$ **e** $\frac{4}{7}$ **f** 126

9 **a** 2 red, 3 green and 5 blue

b **i** yes **ii** yes **iii** yes

iv yes **v** no

10 **a** C **b** D **c** B **d** A

11 **a** Answers will vary.

b Answers will vary.

c No technique for finding theoretical probability has been taught yet.

d less accurate

e more accurate

12 **a** False; there is no guarantee it will occur exactly half of the time.

b False; e.g. in two rolls, a die might land 3 one time. The theoretical probability is not $\frac{1}{2}$, though.

c False; perhaps the event did not happen yet but it could.

d True; if it is theoretically impossible it cannot happen in an experiment.

e False; experiment might have been lucky.

f True; if it is certain, then it must happen in an experiment.

13 **a** red: 25%, green: 42.2%, blue: 32.8%

b Fifth set is furthest from the final estimate.

c have 4 green sectors, 3 blue and 3 red sectors

d red: 90°, green: 150°, blue: 120°

Problems and challenges

1 2, 2, 5, 7, 8, 12

2 **a** 4 **b** 10 **c** 90 **d** 72

3

No. of cars	0	1	2	3
No. of students	4	6	8	2

4 PROBABLE (or PEBBLIER)

5 **a** 60°

b $192 - 3.6 = 188.4°$


c $\frac{1}{4}$ or 25%

d $\frac{99}{100}$ or 99%

e $\frac{1}{20}$ or 5%

6 A spinner with these sector angles has actual probabilities close to the experimental probabilities.

Sector colour	Red	Green	Purple	Yellow
Sector angle	120°	90°	60°	90°
Actual probability	$\frac{40}{120}$	$\frac{30}{120}$	$\frac{20}{120}$	$\frac{30}{120}$
Experimental probability	$\frac{40}{120}$	$\frac{30}{120}$	$\frac{19}{120}$	$\frac{19}{120}$




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Multiple-choice questions

1 B	2 D	3 E	4 D	5 C
6 C	7 A	8 C	9 C	10 B


Short-answer questions

1



2 a 40 b 400 c 10 hours


d



3 a 4 students b 2 students
c 1:00 pm d 6 students

4 a 105° b 25%

c



5 a 11 b 5 c 3.5 d 2

6 a 12 b 5 c 3.5 d 3

7 a 1 b $\frac{1}{8}$ c $\frac{19}{20}$ d $\frac{3}{4}$
e 0

8 a {1, 2, 3, 4, 5, 6} b {heads, tails}
c {D, E, S, I, G, N} d {blue, yellow, green}

9 a 9
b i $\frac{5}{9}$ ii $\frac{1}{3}$ iii 0
iv $\frac{1}{3}$ v $\frac{4}{9}$ vi $\frac{4}{9}$


10 a $\frac{1}{26}$ b $\frac{2}{13}$ c $\frac{1}{52}$ d $\frac{3}{13}$

11 a 42% b 50%

12 a $\frac{1}{2}$ b $\frac{1}{4}$ c 25 d 250

Extended-response questions

1 a



b 66 c $\frac{6}{92} = \frac{3}{46}$
d discrete numerical e categorical

2 a 40
b cheesecake
c $\frac{7}{40}$
d i yes ii no iii yes
iv yes
e 80

Chapter 9


Exercise 9A

1 a pentagon
b i and iii, all interior angles are less than 180°
c ii, there is one interior angle greater than 180°
d regular pentagon


2 a



b



c



3 a 5 b 3 c 10 d 7
e 11 f 4 g 9 h 6
i 8 j 12

4 a i, iv and vi
b i quadrilateral ii pentagon iii hexagon
iv octagon v octagon vi triangle



5 a quadrilateral *ABCD*
b pentagon *ABCDE*
c heptagon *DEFGHIJ*



6 circle, oval, cylinder, cube, line, segment



7 a i 2 ii 7
b i 5 ii 35

8 Answers may vary. Some possibilities are given.


Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

a  **b** 

c  **d** 

e  **f** 

9 **a** true **b** false **c** false **d** true

10 **a** **i**  **ii** 

b Non-convex, as at least one diagonal will cross over space outside the shape.

11 No, a rectangle is equi-angular.



12 No.



13 **a**



No. of sides	3	4	5	6	7
No. of diagonals (not allowed to cross)	0	1	2	3	4
No. of diagonals (allowed to cross)	0	2	5	9	14

b **i** $n-3$ **ii** $\frac{n}{2}(n-3)$

Exercise 9B

1 **a**  **b** 

c  **d** 

e  **f** 


2 **a** A **b** BC **c** AC and AB


d $\angle ACB$ and $\angle ABC$

3 **a** equilateral **b** isosceles **c** scalene


4 **a** right **b** obtuse **c** acute

5 Check measurements with a ruler and protractor.

6 **a** yes 








b yes 

c no

d yes 

7 **a** 2 **b** 4 **c** 6 **d** 12

8

Triangles	Scalene	Isosceles	Equilateral
Acute			
Right			
Obtuse			

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

9 **a** yes **b** isosceles

10 The two shorter sides together must be longer than the longest side.


11 **a** yes **b** No, the three sides will not join.

12 **a** not unique, as triangles can be the same shape but different size

b unique, as only one triangle is possible

c not unique, as *AC* could be of any length

d not unique, as two triangles are possible



Exercise 9C

1 Check your answers by measuring required lengths and angles.

2 **a** yes (SSS) **b** no **c** yes (SAS)
d no **e** yes (RHS) **f** yes (AAS)

3 Check by doing parts **d** and **e**.

4 Check by doing parts **d** and **e**.

5 Check that $\angle CAB = 90°$.

6 **a** Start with one side and the intersection of two arcs to give the other two lengths.

b Start with the base and use two arcs of equal radius.

c Start with the base and use two arcs with the same radius as the base.

d Start with the 4 cm segment, construct a right angle (see **Q5**), then the hypotenuse.

7 **a** Start with the base and use two arcs with the same radius as the base.

b Start with the base, add a perpendicular bisector and place the apex on this line.

c Start with the base, add a perpendicular line for one side, then add the hypotenuse.

8 **a** Triangles with the same angles could be of different size.

b The angle between the two sides could vary.

9 **b** 2 triangles; there are two points on the ray *AE* that could be used to create the third side.

c The information does not give a unique triangle.

10 **a** Check that the dashed lines form an equilateral triangle.

b Use the diagram to assist.

Exercise 9D

1 **b** The three angles should add to 180°.

2 **a** The 160° angle and a are on a straight line, which should add to 180°.

b $a + b + 100 = 180$; so if $a = 20$, b must be 60.

3 60°

4 **a** The two base angles in an isosceles triangle are equal.

b The sum must be 180° (i.e. $70° + 70° + 40° = 180°$).

5 **a** 60 **b** 30 **c** 55
d 65 **e** 25 **f** 145

6 **a** 65 **b** 20 **c** 35
d 75 **e** 55 **f** 32

7 **a** 30 **b** 140 **c** 60
d 60 **e** 10 **f** 142

8 **a** 40 **b** 120 **c** 45
d 132 **e** 16 **f** 30

9 **a** 60 **b** 60 **c** 55
d 55 **e** 145 **f** 50

10 20°

11 **a** 155° **b** 155

c They are the same.

d yes, always true

12 **a** alternate angles in parallel lines

b alternate angles in parallel lines

c They must add to 180°.

13 **a** $\angle DCA = a$ (Alternate to $\angle BAC$ and DE is parallel to AB.)

$\angle ECB = b$ (Alternate to $\angle ABC$ and DE is parallel to AB.)

$\angle DCA + \angle ACB + \angle ECB = 180°$ (Angles on a line add to 180°.)

$\therefore a + b + c = 180$

b $a + b + c = 180$ (Angles in a triangle sum to 180°.)

$a + b = 180 - c$ **(1)**

Also $\angle ACB + \angle BCD = 180°$ (Angles in a straight line sum to 180°.)


$c + \angle BCD = 180°$

$\angle BCD = (180 - c)°$ **(2)**


From **(1)** and **(2)** we have $\angle BAC = a° + b°$.

Exercise 9E


1 **a**




b



c




d




Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

e **f**



2 a



b 1

3 **a** convex **b** non-convex **c** non-convex

4 **a** square **b** trapezium **c** kite
d rhombus **e** rectangle **f** parallelogram

5 **a** rectangles, kite, parallelogram
b rhombus, parallelogram
c square, rectangle, rhombus, parallelogram
d trapezium
e kite

6 **a** $a = 90, b = 10$
b $a = 100, b = 5$
c $a = 50, b = 130$

7 **a** 5 **b** 4 **c** 1 **d** 10

8 Forming a square is possible.

9 **a** square, rectangle
b square, rhombus, kite

10 **a** A square is a type of rectangle because a rectangle can be constrained to form a square.
b Yes, a parallelogram can be constrained to be a rhombus.
c no

11 **a** Use given diagram and check that all sides are the same length.
b Use given diagram and check that the distance between the lines are always equal.

Exercise 9F

1 Answer may vary, but the sum of angles should be very close to 360°.

2 Answer may vary, but the sum of angles should be very close to 360°.

3 **a** $a + 70 = 180$, so $a = 110$.
b $b + 110 + 100 + 60 = 360$, so $b = 90$.

4 **a** 130 **b** 90 **c** 230

5 **a** $a = 80, b = 90$ **b** $a = 20, b = 10$
c $a = 120, b = 155$ **d** $a = 90, b = 35$
e $a = 265, b = 40$ **f** $a = 270, b = 35$

6 **a** $a = 90$ **b** $a = 50, b = 130$
c $a = 131$

7 **a** 100 **b** 70 **c** 77.5

8 **a** 60 **b** 115 **c** 108

9 **a** 130 **b** 110 **c** 150

10 **a** possible **b** impossible
c impossible **d** possible
e impossible

11 $a + b + f = 180$ (sum of angles in a triangle)
$c + d + e = 180$ (sum of angles in a triangle)
Total sum $= a + b + f + c + d + e$
$= 180 + 180$
$= 360$


12 **a** 21 **b** 60 **c** 36
d 24 **e** 22.5 **f** 60

Progress quiz

1 **a** concave irregular pentagon
b convex regular hexagon
c convex irregular rectangle
d non-convex irregular decagon

2 **a** isosceles triangle
b right-angled triangle

3



4 180°

5 **a** 70 **b** 70

6 **a** 60 **b** 60

7 **a** square **b** trapezium
c rhombus **d** parallelogram

8 **a** 102 **b** 85 **c** 90

9 **a** 85 **b** 48 **c** 122

10 **a** 60 **b** 48 **c** 132 **d** 192

Exercise 9G

1 **a** 4 ways **b** 2 ways **c** 3 ways
d 1 way **e** 2 ways **f** 0 ways

2 **a** 4 **b** 2 **c** 3
d 1 **e** 2 **f** 2

3 **a** 4 and 4 **b** 2 and 2 **c** 2 and 2
d 1 and 1 **e** 1 and 1 **f** 0 and 2

4 **a** equilateral **b** isosceles **c** scalene



5 **a** **i** kite **ii** rectangle, rhombus
iii none **iv** square





Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

b **i** trapezium, kite
ii rectangle, rhombus, parallelogram
iii none **iv** square


6 **a** line and rotational symmetry of order 5
b line and rotational symmetry of order 1
c line and rotational symmetry of order 1
d line and rotational symmetry of order 4

7 **a** A, B, C, D, E, K, M, T, U, V, W, Y
b H, I, O, X
c H, I, N, O, S, X, Z

8 **a**  **b**  **c** 

9 **a**  **b** 
c  **d** 
e 





10 **a** 4 and 4 **b** 1 and 1 **c** 1 and 1



11 **a**  **b** 

12 **a** **i** no **ii** no
b isosceles trapezium

13 **a** 9 **b** 3 **c** 4
d 1 **e** infinite **f** infinite

Exercise 9H

1 **a**  **b** 
c  **d** 

e  **f** 

2 **a** $(-2, 0)$ **b** $(-2, 0)$ **c** $(0, -2)$ **d** $(0, 2)$







3 **a** no **b** no

4 **a** $A'(1, 1), B'(1, 4), C'(2, 2), D'(3, 1)$
b $A'(-3, 4), B'(-3, 1), C'(-2, 1), D'(-1, 2)$
c $A'(-1, -2), B'(-2, -4), C'(-4, -4), D'(-4, -3)$
d $A'(2, -1), B'(2, -4), C'(4, -2), D'(4, -1)$
e $A'(-3, 2), B'(-3, 3), C'(-1, 4), D'(-1, 1)$
f $A'(-3, -4), B'(-1, -4), C'(-1, -1), D'(-2, -3)$

5 **a** $(-3, -3)$ **b** $(3, -3)$ **c** $(-3, 3)$
d $(-3, 3)$ **e** $(3, 3)$ **f** $(-3, -3)$

6 **a** $A'(0, -1), B'(2, 0), D'(0, -3)$
b $A'(1, 0), B'(0, 2), D'(3, 0)$
c $A'(0, 1), B'(-2, 0), D'(0, 3)$

7 **a** $A'(-1, 0), B'(-3, 0), D'(-1, 2)$
b $A'(0, -1), B'(0, -3), D'(-2, -1)$
c $A'(1, 0), B'(3, 0), D'(1, -2)$

8 **a**  **b** 
c  **d** 
e  **f** 

9 $(2, -5)$

10 **a** $(0, -1)$ **b** $(3, 0)$ **c** $(-1, 2)$

11 **a** 180° **b** 90° **c** 90°

12 **a** 270° **b** 322° **c** 10°

13 **a** $(2, -5)$ **b** $(2, -5)$
c the same point **d** (4, 1) for both

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press





14 The triangle has been shifted, not rotated.
15 Check with your teacher.
16 Check with your teacher.

Exercise 9I

1 a (4, 2) b (1, 2) c (3, 5) d (3, 1)
e (2, 4) f (0, 1) g (5, 1) h (3, 0)

2 a up b left c down d up
e left f left g right h right

3 a 7 units
b 3 units
ic 7 units ii 3 units

4 a  b 
c  d 

5 a (1, 3) b (−4, 3) c (−2, 1) d (−2, −2)
e (−2, 5) f (8, 3) g (1, 4) h (2, 1)
i (3, −3) j (−3, 1) k (−5, 4) l (−4, −2)

6 a 3 units up b 7 units down
c 4 units down d 2 units up
e 5 units left f 2 units right
g 1 unit left and 4 units up
h 3 units right and 6 units up
i 3 units right and 4 units down
j 3 units left and 11 units up
k 12 units right and 3 units down
l 10 units left and 13 units down

7 a 2 units left and 2 units up
b 4 units left and 4 units up
c 1 unit right and 5 units down
d 6 units right and 2 units down

8 a 4 b 12




9 24 points

10 It is neither rotated nor enlarged.







11 a 3 right and 1 down b 1 right and 2 up
c 2 left and 4 down d 6 right and 7 up

12 a (−4, −1) b (−4, −3) c (−7, 2)
d (−13, −5) e (4, −2)

Exercise 9J

1 a  b 
c 




2 a 2 b 4 c 6

3 a  b 
c  d 
e  f 


4 See given diagrams.

5 See given diagrams in Question 2.


6 a  b 

7 a  (two squares)
b  (square and rectangle with the same top side length)
c  (circle, isosceles triangle)
d  (square, isosceles triangle)
e  (square, diamond)
f  (2 circles)

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.


g  (square, triangle on square)


h  (circle in square, semicircle on rectangle)


i  (circle, triangle on semicircle)

8 6

9 20

10 **a** 
(4-sided pyramid)


b 
(8-sided double pyramid)

c 
(pyramid with 5-sided base)


11 Yes, one can be rotated to match the other.



12 **a** C **b** A **c** B **d** D

13 **a** **i** front left top



ii front left top



b **i**  **ii** 

Exercise 9K



1 **a** equal **b** regular **c** platonic



2 A and C



3 **a** equilateral triangle **b** square
c equilateral triangle **d** regular pentagon
e equilateral triangle

4 **a** cube **b** cylinder
c triangular pyramid

5 Answers may vary.

a  **b** 

c  **d** 

e  **f** 

6 **a** tetrahedron, octahedron, icosahedron
b icosahedron
c octahedron
d tetrahedron
e hexahedron, octahedron
f hexahedron, octahedron

7 **a** octahedron **b** hexahedron
c dodecahedron **d** icosahedron
e tetrahedron

8 **a** 3 **b** 3 **c** 4
d 3 **e** 5

9 **a**  **b** 

10 **a** 2 **b** 11

11 **a** 6 **b** Yes
c There is not the same number of faces meeting at each vertex.

12 **a** **i** 1 **ii** 26

b


n (side length)	1	2	3	4	5
n^3 (number of 1 cm cubes)	1	8	27	64	125
Number of inside cubes	0	0	1	8	27
Number of outside cubes	1	8	26	56	98

c **i** n^3 **ii** $(n-2)^3$ **iii** $n^3-(n-2)^3$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2 © Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Problems and challenges

1 tetrahedron



2 27

3 36

4 a 35 b 1175

5 161

6 18

Multiple-choice questions

1 E	2 B	3 C	4 D	5 C
6 A	7 E	8 C	9 E	10 C

Short-answer questions

1 a 5 b 7 c 11

2 a 2 b 1

3 Check lengths and angles with a ruler and pair of compasses.

4 Check lengths and angles with a ruler and pair of compasses.

5 a yes, AAS b no c yes, RHS

6 a 30 b 48 c 50
d 60 e 80 f 130
g 40 h 80 i 105

7 a trapezium b rhombus c kite

8 a 90 b 255 c 100
d 125 e 100 f 55


9 a 2, 2 b 1, 1 c 0, 2

10 a $A'(-1, -2)$, $B'(-3, -3)$, $C'(-3, -1)$
b $A'(1, 2)$, $B'(3, 3)$, $C'(3, 1)$


11 a $A'(0, -4)$, $B'(-2, 0)$, $D'(-3, -3)$
b $A'(4, 0)$, $B'(0, -2)$, $D'(3, -3)$
c $A'(-4, 0)$, $B'(0, 2)$, $D'(-3, 3)$

12 a $A'(1, -1)$, $B'(4, -1)$, $C'(3, 1)$
b $A'(-4, 1)$, $B'(-1, 1)$, $C'(-2, 3)$

13 a




b



Extended-response questions

1 a 30° b 65° c 35
d It stays the same.

2



Chapter 10

Exercise 10A

1 a E b N c E d E e E
f N g E h E i N

2 a true b false c false

3 true

4 a 19 b 19 c true

5 a true b false c true d true
e false f false g true h false
i true j true k false l true
m false n false o true

6 a false b true c false d true

7 a true b true c false d true

8 a true b false c true d true
e true f false g false h true
i true

9 a $3 + x = 10$ b $5k = 1005$ c $a + b = 22$
d $2d = 78$ e $8x = 56$ f $3p = 21$
g $\frac{t}{4} = 12$ h $q + p = q \times p$

10 a $6c = 546$ b $5x = 37.5$ c $12a + 3b = 28$
d $f + 10 = 27$ e $j + 10 + m + 10 = 80$

11 $m = 3$

12 $k = 2$, $k = 6$

13 $x = 1$ and $y = 5$, $x = 2$ and $y = 4$, $x = 3$ and $y = 3$, $x = 4$ and $y = 2$, $x = 5$ and $y = 1$

14 a S b S c A d A
e N f N g A h S
i A j S k N l N

15 a $6 = 2 \times 3$; other solutions possible.
b $5 - 4 = 1$; other solutions possible.
c $10 \div 2 = 7 - 2$; other solutions possible.
d $4 - 2 = 10 \div 5$; other solutions possible.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

16 **a** 12
b 4
c Yes; if 5 is changed to 1, then $1 + 2 = 3$ is a true equation.
d Yes; if $+$ is changed to $-$, then $5 - 3 = 2$ is a true equation.

Exercise 10B

1 **a** true **b** false **c** true **d** false

2 **a** 12 **b** 17 **c** 13 **d** 6

3 **a** 3 **b** 6 **c** 10 **d** 4
e 6 **f** 70 **g** 20 **h** 19

4 **a** x **b** c **c** b **d** d

5 **a** $y = 8$ **b** $l = 2$ **c** $l = 6$ **d** $d = 2$
e $l = 12$ **f** $a = 6$ **g** $s = 12$ **h** $x = 8$
i $e = 8$ **j** $r = 10$ **k** $s = 8$ **l** $z = 3$

6 **a** $p = 3$ **b** $p = 4$ **c** $q = 3$ **d** $v = 5$
e $b = 1$ **f** $u = 4$ **g** $g = 3$ **h** $e = 3$
i $d = 4$ **j** $d = 6$ **k** $m = 4$ **l** $o = 3$

7 **a** $x = 3$ **b** $x = 7$ **c** $x = 5$
d $x = 4$ **e** $x = 1$ **f** $x = 5$

8 **a** 11 **b** 12 **c** 16
d 33 **e** 30 **f** 2

9 **a** $10x = 180$ **b** $x = 18$

10 **a** $2w = 70$ **b** $w = 35$

11 **a** $4.5x = 13.5$ **b** $x = 3$

12 **a** $y + 12 = 3y$ **b** $y = 6$

13 **a** $x = 9$ **b** $2x + 1 = 181$ so $x = 90$

14 **a** $x = 14$, so 14, 15 and 16 are the numbers.
b LHS is $3x + 3$ or $3(x + 1)$, which will always be a multiple of 3.

15 **a** $x = 2$ and $y = 6$; other solutions possible.
b $x = 12$ and $y = 10$; other solutions possible.
c $x = 1$ and $y = 1$; other solutions possible.
d $x = 12$ and $y = 0.5$; other solutions possible.
e $x = 10$ and $y = 0$; other solutions possible.
f $x = 2$ and $y = 2$; other solutions possible.

Exercise 10C

1 **a** $10d + 15 = 30$ **b** $7e + 10 = 41$
c $2a + 10 = 22$ **d** $x + 10 = 22$

2 **a** C **b** D **c** E **d** B **e** A

3 **a** $6 + x = 11$ **b** $6x = 14$ **c** $3 = 2q$
d $6 + a = 10$ **e** $12 + b = 15$ **f** $0 = 3b + 2$
g $4 = 7 + a$ **h** $12x + 2 = 8$ **i** $7p = 12$

4 **a** subtracting 2 **b** adding 2 **c** dividing by 10
d multiplying by 2 **e** dividing by 3 **f** adding 3
g dividing by 4 **h** adding 4


5 **a** $3(x + 4) = 27$ **b** $18 = 3(a + 5)$
c $3d = 18$ **d** $3(11 + a) = 36$
e $3(3y + 2) = 33$ **f** $3(2x + 4) = 30$

6 **a** E $(+2)$ **b** A $(+4)$ **c** D $(\div 2)$ **d** B (-2)
e C $(\times 2)$


7 **a** $\times 3$ then $+2$ **b** $\times 10$ then -3 **c** $\div 5$ then -2
d -10 then $\div 3$

8 **a** $2q = 2$ **b** $10x = 7$
c $3 + x = 20$ **d** $x = 60$


9 **a**



b




c




10 **a** **i** $0 = 0$ **ii** $0 = 0$ **iii** $0 = 0$
b Regardless of original equation, will always result in $0 = 0$.

11 **a**



b



12 **a** True; you can $+3$ to both sides and then -3 to get the original equation again.
b True; simply perform the opposite operations in the reverse order, so $+4$ becomes -4.
c True; use the operations that take equation 1 to equation 2 and then the operations that take equation 2 to equation 3.
d false; e.g. equation 1: $x = 4$, equation 2: $x = 5$, equation 3: $2x = 8$.

Exercise 10D

1 **a** true **b** false **c** true
d false **e** false

2 **a** 6 **b** $x = 6$

3 $g = 2$

4 **a** -5 **b** $\div 10$ **c** $\times 4$ **d** $+12$

5 **a** $m = 9$ **b** $g = 11$ **c** $s = 9$ **d** $i = 10$
e $t = 2$ **f** $q = 3$ **g** $y = 12$ **h** $s = 12$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

i $j = 4$ **j** $l = 4$ **k** $v = 2$ **l** $y = 12$
m $k = 5$ **n** $y = 9$ **o** $z = 7$ **p** $t = 10$
q $b = 12$ **r** $p = 11$ **s** $a = 8$ **t** $n = 3$

6 a
$7a + 3 = 38$
-3 -3
$7a = 35$
$\div 7$ $\div 7$
$a = 5$

b
$4b - 10 = 14$
$+10$ $+10$
$4b = 24$
$\div 4$ $\div 4$
$b = 6$

c
$2(q + 6) = 20$
$\div 2$ $\div 2$
$q + 6 = 10$
-6 -6
$q = 4$

d
$5 = \frac{x}{10} + 3$
-3 -3
$2 = \frac{x}{10}$
$\times 10$ $\times 10$
$20 = x$

7 a subtract 3 **b** add 7 **c** divide by 5 **d** divide by 2

8 a $f = 11$ **b** $k = 4$ **c** $x = 9$ **d** $a = 9$
e $k = 8$ **f** $a = 6$ **g** $n = 11$ **h** $n = 8$
i $g = 4$ **j** $q = 11$ **k** $z = 10$ **l** $p = 1$
m $d = 4$ **n** $t = 8$ **o** $u = 5$ **p** $c = 1$
q $q = 11$ **r** $y = 12$ **s** $q = 2$ **t** $u = 10$

9 a $x = \frac{3}{4}$ **b** $k = \frac{24}{5}$ **c** $w = \frac{4}{3}$
d $x = \frac{4}{3}$ **e** $x = \frac{5}{8}$ **f** $x = \frac{1}{3}$

10 a $r = -7$ **b** $x = -3$ **c** $t = -16$ **d** $y = -24$
e $x = -5$ **f** $k = -9$ **g** $x = -6$ **h** $x = -4$
i $x = \frac{-3}{2}$

11 a $x + 5 = 12 \rightarrow x = 7$ **b** $2y = 10 \rightarrow y = 5$
c $2b + 6 = 44 \rightarrow b = 19$ **d** $3(k - 7) = 18 \rightarrow k = 13$
e $\frac{b}{4} + 3 = 6 \rightarrow b = 12$ **f** $\frac{k}{2} - 10 = 1 \rightarrow k = 22$

12 a $12n + 50 = 410$ **b** $n = 30$ h

13 a $12 + 5x$ **b** $12 + 5x = 14.5$
c $x = 0.5$, so pens cost 50 cents.

14 a $3w = 15 \rightarrow w = 5$ **b** $4x = 12 \rightarrow x = 3$
c $2(10 + x) = 28 \rightarrow x = 4$
d $4w = 28 \rightarrow w = 7$

15 a $x = 6$ **b** $x = 8$ **c** $x = 5$

16 Examples include: $x + 1 = 3, 7x = 14, 21 - x = 19, \frac{4}{x} = x, \frac{x}{2} = 1$.

17 a
$2x + 5 = 13$
-5 -5
$2x = 8$
$\div 2$ $\div 2$
$x = 4$
$\times 5$ $\times 5$
$5x = 20$

b
$10 + 2x = 20$
-10 -10
$2x = 10$
$\div 2$ $\div 2$
$x = 5$
-3 -3
$x - 3 = 2$
$\times 2$ $\times 2$
$2(x - 3) = 4$

c yes **d** yes

18 a First step, $4x + 2$ is not completely divided by 4.
b Second step, LHS divided by 3, RHS has 3 subtracted.
c First step, RHS has 5 added not subtracted.
d First step, LHS has $11a$ subtracted, not 12.

19 a $x = 4$ **b** $x = 1$ **c** $l = 3$ **d** $t = 1$
e $s = 5$ **f** $b = 19$ **g** $j = 2$ **h** $d = 1$

Exercise 10E

1 a true **b** false **c** true
d false **e** true **f** false

2 a 7 **b** 9 **c** false

3 a $b = 44$ **b** $d = 15$ **c** $h = 28$ **d** $p = 26$

4 a B **b** C **c** A **d** D

5 a $m = 12$ **b** $c = 18$ **c** $s = 16$ **d** $r = 10$
e $u = 20$ **f** $y = 18$ **g** $x = 4$ **h** $a = 16$
i $h = 10$ **j** $j = 15$ **k** $v = 9$ **l** $q = 8$

6 a $h = 9$ **b** $y = 6$ **c** $j = 3$ **d** $b = 4$
e $u = 3$ **f** $t = 9$ **g** $w = 6$ **h** $r = 4$
i $q = 9$ **j** $s = 3$ **k** $l = 8$ **l** $z = 7$
m $v = 11$ **n** $f = 9$ **o** $x = 2$ **p** $d = 5$
q $n = 5$ **r** $m = 11$ **s** $p = 8$ **t** $a = 9$

7 a $y = -1$ **b** $a = -10$ **c** $x = -10$ **d** $x = -48$
e $u = -30$ **f** $y = -10$ **g** $u = -4$ **h** $d = -5$

8 a $\frac{t}{2} = 9 \rightarrow t = 18$ **b** $\frac{q}{3} = 14 \rightarrow q = 42$
c $\frac{2r}{5} = 6 \rightarrow r = 15$ **d** $\frac{q - 4}{2} = 3 \rightarrow q = 10$
e $\frac{x + 3}{4} = 2 \rightarrow x = 5$ **f** $\frac{y}{4} + 3 = 5 \rightarrow y = 8$

9 a $\frac{b}{5} = 31.50$ **b** $b = 157.5$ **c** \$157.50

10 a $\frac{x}{2} + 5$
b $\frac{x}{2} + 5 = 11 \rightarrow x = \$12$
c \$6

11 a The different order in which 3 is added and the result is multiplied by 5.
b multiply by 5
c subtract 3
d No, the difference between them is always 2.4 for any value of x.

12 a $4x = 2$ (other solutions possible)
b $7x = 5$
c yes, e.g. $2x + 1 = 0$

13 a i multiply by 2 **ii** divide by $\frac{1}{2}$
b $x = 26$ for both of them.
c Makes the first step a division (by a fraction) rather than multiplication.

14 a $x = \frac{7}{2}$ **b** $x = \frac{17}{6}$ **c** $x = \frac{19}{6}$ **d** $x = \frac{7}{6}$

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Progress quiz

1 **a** E **b** N **c** E **d** N

2 **a** T **b** F **c** T **d** F

3 **a** $5 + m = 12$ **b** $2d = 24$
c $9x = 72$ **d** $3c + 4b = 190$

4 **a** $a = 9$ **b** $x = 4$ **c** $m = 30$ **d** $a = 2$

5 **a** $20x = 35$ **b** $2a = 16$

6 **a** $+ 8$ **b** $\div 6$ **c** $\times 2$

7 **a** $a = 12$ **b** $w = 31$ **c** $k = 63$ **d** $m = 8$

8 **a** $x = 11$ **b** $a = 7$ **c** $m = 6$ **d** $y = 8$

9 **a** $c = 24$ **b** $a = 8$ **c** $h = 12$ **d** $m = 55$

10 **a** $\frac{m}{2} + 5 = 11; m = 12$ **b** $\frac{7 + x}{2} = 9; x = 11$

Exercise 10F

1 C

2 **a** 6 **b** 4 **c** 2 **d** 12

3 **a** true **b** false **c** true
d true **e** false **f** false

4 **a** $2x + 2$ **b** $10b + 15$ **c** $6a - 8$ **d** $35a + 5$
e $12x + 16$ **f** $24 - 9y$ **g** $48a + 36$ **h** $2u - 8$

5 **a** $4a + 2$ **b** $5 + 3x$ **c** $3b - 4$ **d** $3a + 12$
e $6x + 3$ **f** $k + 6$ **g** $2b + 6$ **h** $5k + 1$

6 **a** $s = 6$ **b** $l = 1$ **c** $p = 9$ **d** $y = 0$
e $q = 1$ **f** $p = 12$ **g** $m = 5$ **h** $b = 6$
i $p = 3$ **j** $p = 7$ **k** $y = 9$ **l** $r = 8$

7 **a** $d = 3$ **b** $x = 2$ **c** $x = 5$ **d** $e = 1$
e $a = 1$ **f** $r = 3$ **g** $u = 1$ **h** $q = 11$

8 **a** $s = 1$ **b** $i = 1$ **c** $c = 5$ **d** $v = 8$
e $k = 1$ **f** $q = 3$ **g** $y = 4$ **h** $f = 3$
i $t = 2$

9 **a** $u = -5$ **b** $k = -3$ **c** $p = -1$ **d** $q = -2$
e $u = -1$ **f** $x = -3$ **g** $p = -4$ **h** $r = -10$
i $x = -5$

10 **a** **i** $2(5 + x) = 14$ **ii** $x = 2$
b **i** $3(q - 3) = 30$ **ii** $q = 13$
c **i** $2(2x + 3) = 46$ **ii** $x = 10$
d **i** $2(y + 4) - y = 17$ **ii** $y = 9$

11 **a** LHS simplifies to 10, but $10 = 7$ is never true.
b LHS simplifies to 15, not 4.
c LHS simplifies to 6, not 12.

12 **a** LHS $= 9$, RHS $= 9$, therefore true.
b LHS $= 9$, RHS $= 9$, therefore true.
c LHS simplifies to 9.
d For example $2(x + 5) - 3 - 2x = 7$. Others possible.

13 **a** $s = 6$ **b** $l = 1$ **c** $p = 9$ **d** $y = 0$
e $q = 1$ **f** $p = 12$ **g** $m = 5$ **h** $b = 6$
i $p = 3$ **j** $p = 7$ **k** $y = 9$ **l** $r = 8$

14 **a** $j = 2$ **b** $a = 1$ **c** $a = 3$ **d** $a = 8$
e $c = 4$ **f** $d = 8$ **g** $x = 1$ **h** $x = 3$
i $x = 0$

Exercise 10G

1 **a** N **b** R **c** R
d N **e** R **f** R

2 **a** 15 **b** 36 **c** 8 **d** 2

3 **a** $h = 7$ **b** $h = 9$ **c** $m = 8$ **d** $m = 10$

4 **a** $y = 23$ **b** $x = 4$ **c** $x = 7$

5 **a** $A = 7$ **b** $q = 4$ **c** $t = 0$

6 **a** $G = 27$ **b** $x = 1$ **c** $y = 5$

7 **a** $20 = w \times 4 \rightarrow w = 5$
b **i** $25 = 5h \rightarrow h = 5$ **ii** square

8 **a** $P = 16$ **b** $h = 3$ **c** 24 units squared

9 **a** $F = 68$ **b** $C = 10$ **c** 12°C **d** 15°C

10 **a** $d = \frac{S - 3b}{5}$ **b** $C = \frac{5(F - 32)}{9}$
c $x = \frac{Q - 36}{4}$

11 **a** Check by substituting values back into equation.
b If $D = 20$, C should equal 60 not 50, as in row 2.
c Check by substituting values back into equation.
d For example, $C = 2t - 10$, $C = \frac{Dt}{20} + 20$; other solutions possible.

12 **a** Abbotsford Apes
b 8 goals
c $S = 9q + 6g + b$
d 0 goals and 0 behinds, 2 goals and 12 behinds, 3 goals and 9 behinds, 7 goals and 7 behinds.

Exercise 10H

1 **a** A **b** C **c** C

2 **a** $x = 6$ **b** $a = 2$ **c** $k = 9$

3 **a** Let $c =$ car's cost **b** $c + 2000 = 40\,000$
c $c = 38\,000$ **d** \$38 000

4 **a** Let $p =$ cost of one pen **b** $12p = 15.6$
c $p = 1.3$ **d** \$1.30

5 **a** Let $h =$ number of hours worked
b $17h + 65 = 643$
c $h = 34$
d 34 hours

6 **a** $24w = 720$ **b** $w = 30$ **c** 30 m
d 108 m

7 $2(2x + 3) = 34 \rightarrow x = 7$

8 $x = 4$

9 1.5 h

10 14 years old

11 $2x + 154 = 180 \rightarrow x = 13$

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

12 $3y = 90 \rightarrow y = 30$

13 Examples include: $h = 3, w = 6$ or $h = 12, w = 2.4$; other solutions possible.

14 $x = 3.5, y = 2$

15 **a** possible ($p = 12$)
b Not possible because solution is not a whole number.
c possible ($p = 8$)

16 $a + 2b = 180$, so $a = 180 - 2b = 2(90 - b)$ is always even.

17 **a** **i** $x = 60$
ii One angle is $-10°$, which is impossible.
b **i** $60 - x + 70 + x + 50$ is always 180, regardless of the value of x.
ii any value less than 60 and greater than -70.
c Answers will vary.

Problems and challenges

1 **a** 26 **b** 29 **c** 368 **d** $31\frac{1}{3}$
e 36

2 27 cm

3 $x = 7, y = 9, P = 72$ cm

4 1458 m^2

5 $a = 5, b = 2, c = 12$

6 **a** $a = 22.5, b = 37.5$ **b** $a = 10, b = 23$
c $a = 36, b = 108$ **d** $a = 60, b = 40$

7 26 sheep, 15 ducks

8 $x = 45$; 132, 133, 134, 135, 136

Multiple-choice questions

1 C **2** A **3** D **4** B **5** E
6 C **7** A **8** A **9** B **10** E

Short-answer questions

1 **a** false **b** true **c** true
d false **e** true **f** false

2 **a** $2 + u = 22$ **b** $5k = 41$
c $3z = 36$ **d** $a + b = 15$

3 **a** $x = 3$ **b** $x = 6$ **c** $y = 1$ **d** $y = 9$
e $a = 2$ **f** $a = 10$

4 **a** $2x = 8$ **b** $7a = 28$ **c** $15 = 3r$ **d** $16 = 8p$

5 **a** $x = 3$ **b** $r = 45$ **c** $p = 9$ **d** $b = 6$
e $x = 9$ **f** $r = 4$ **g** $q = 2$ **h** $u = 8$

6 **a** $u = 8$ **b** $p = 3$ **c** $x = 4$ **d** $y = 8$
e $y = 4$ **f** $x = 15$

7 **a** $6 + 4p$ **b** $12x + 48$ **c** $7a + 35$ **d** $18x + 9$

8 **a** $x = 8$ **b** $x = 8$ **c** $x = 7$ **d** $y = 10$
e $z = 5$ **f** $q = 3$

9 **a** no **b** Solution is $x = \frac{7}{11}$, which is not whole.

10 **a** No; LHS simplifies to 10.
b **i** Is a solution. **ii** Is a solution.

11 **a** $A = 450$ cm^2 **b** $h = 10$ cm

12 **a** 36 **b** 6 **c** 3

13 **a** 5 **b** 6 **c** 20 **d** 6 cm

14 **a** $y = 35$ **b** $y = 30$

Extended-response questions

1 **a** 75 cents **b** $C = 15 + 2t$ **c** \$1.75
d 12 seconds **e** 81 seconds
f 2.5 min in total (50 seconds for the first call, then 100 seconds)

2 **a** \$500
b 30 hours at \$$x$/hour, and 10 hours at \$(x+ 2)/hour.
c \$660
d $x = 15$
e $x = 21$, so Gemma earned \$630 from Monday to Friday.

Chapter 11

Exercise 11A

1 **a** **i** 1 foot = 12 inches = 16 digits = 4 palms
ii 1 mile = 1000 paces
b **i** 1 foot = 12 inches **ii** 3 feet = 1 yard
iii 1 mile = 1760 yards
c **i** 1 m = 100 cm **ii** 1 cm = 10 mm
iii 1 km = 1000 m

2 digit, inch, palm, foot, cubit, pace, mile

3 inch, foot, yard, rod, chain, furlong, mile

4 millimetre, centimetre, metre, kilometre

5 **a** 5 **b** 5000 **c** 4
d 20 **e** 16 **f** 80

6 **a** 12 **b** 3 **c** 36
d 1760 **e** 22 **f** 40

7 **a** 10 **b** 100 **c** 1000
d 1000 **e** 100 000 **f** 1 000 000

8 **a** kilometres **b** millimetres **c** metres
d metres **e** centimetres **f** kilometres

9 **a** metres **b** millimetres **c** kilometres
d kilometres **e** metres **f** centimetres

10 1 pace

11 5000

12 440

13 **a** 2 mm **b** 5 mm **c** 2 cm
d 5 cm **e** 8 cm

14 **a** 6 cm **b** 5 cm **c** 25 cm

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

15 a

	mm	cm	m	km
mm	1	$\frac{1}{10}$	$\frac{1}{1000}$	$\frac{1}{1000\,000}$
cm	10	1	$\frac{1}{100}$	$\frac{1}{100\,000}$
m	1000	100	1	$\frac{1}{1000}$
km	1 000 000	100 000	1000	1

b

	Inch	Feet	Yard	Mile
Inch	1	$\frac{1}{12}$	$\frac{1}{36}$	$\frac{1}{63\,360}$
Feet	12	1	$\frac{1}{3}$	$\frac{1}{5280}$
Yard	36	3	1	$\frac{1}{1760}$
Mile	63 360	5280	1760	1

c

	Digit	Palm	Feet	Pace	Mile
Digit	1	$\frac{1}{4}$	$\frac{1}{16}$	$\frac{1}{80}$	$\frac{1}{80\,000}$
Palm	4	1	$\frac{1}{4}$	$\frac{1}{20}$	$\frac{1}{20\,000}$
Feet	16	4	1	$\frac{1}{5}$	$\frac{1}{5000}$
Pace	80	20	5	1	$\frac{1}{1000}$
Mile	80 000	20 000	5000	1000	1

16 4 rods = 1 chain, but conversion to other units is less simple.

17 All conversions involve a power of 10.

18 Answers may vary.

Exercise 11B

1 a 100 b 1000 c divide
d multiply e multiply f divide

2 a 1000 b 1000 c 100 000 d 1 000 000

3 a right b left

4 a 50 mm b 200 cm c 3500 m d 2610 cm
e 4 cm f 5 m g 4.2 km h 47.2 cm
i 684 cm j 20 m k 926.1 cm l 4.23 km

5 a 2.5 cm b 82 mm c 2.5 m
d 730 cm e 6200 m f 25.732 km

6 a 3000 mm b 600 000 cm c 2400 mm
d 4000 cm e 0.47 km f 913 m
g 0.216 km h 0.0005 m

7 a 2 cm b 5 cm c 1.5 cm d 3.2 cm
e 3 cm f 3 cm g 1.2 cm h 2.8 cm

8 a 2.7 m b 0.4 km

9 a 8.5 km b 310 cm c 19 cm

10 a 38 cm, 0.5 m, 540 mm
b 160 cm, 2100 mm, 0.02 km, 25 m
c 142 mm, 20 cm, 0.003 km, 3.1 m
d 10 mm, 0.1 m, 0.001 km, 1000 cm

11 125 cm

12 Bigan tower

13 a \$8200 b \$6.56 c 41c


14 625 years

15 50 000 years

16 0.08 mm

17 2500 s

18



19 So that only one unit is used and mm deliver a high degree of accuracy.

20 a i 1 million ii 10 000 iii 1000
iv 1 billion (1 000 000 000)
b 0.312 μm
c The distance you travel in 1 year at light speed

Exercise 11C

1 a 10 cm b 12 cm

2 a 6 cm b 12 cm c 5.2 cm d 6.4 cm

3 a 15 cm b 37 m c 30 km
d 2.4 m e 26 cm f 10 cm

4 a 42 cm b 34 m c 36 km

5 a 8.4 cm b 14 m c 46.5 mm

6 \$21 400

7 a 516 ft b 157.38 m

8 a 70 mm b 72 cm

9 a 40.7 cm b 130.2 cm c 294 cm

10 400 m

11 a 5 cm b 5 m c 7 km

12 4, including a square

13 a $P = a + 2b$ b $P = 4a$ c $P = 2a + 2b$
d $P = 4a$ e $P = 2a + 2b$ f $P = 2a + b + c$

14 a $P = 2a + 2b + 2c$ or $2(a + b + c)$
b $P = 2a + 2b + 2c$ or $2(a + b + c)$

15 a $\frac{P}{4}$ b $\frac{(P - 2a)}{2}$

16 a 160 cm b 216 cm c 40 cm
d $4a + 32$ or $4(a + 8)$

Exercise 11D

1 a 8 b 4 cm and 2 cm c 8 cm^2

2 a 9 b 3 cm and 3 cm c 9 cm^2

3 a 5 square units b 8 square units
c 96 square units

4 a cm^2 b m^2 c ha

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

d km^2 **e** ha **f** mm^2

5 **a** 6 cm^2 **b** 3 cm^2 **c** 2 cm^2
d 5 cm^2 **e** 4.5 cm^2 **f** 9 cm^2

6 **a** 200 cm^2 **b** 22 mm^2 **c** 7 cm^2
d 25 m^2 **e** 1.44 mm^2 **f** 6.25 mm^2
g 1.36 m^2 **h** 0.81 cm^2 **i** 179.52 km^2

7 **a** 2 cm **b** 5 m **c** 12 km

8 **a** 2 ha **b** 10 ha **c** 0.5 ha

9 5000 m^2

10 2500 cm^2

11 20 000 cm^2

12 **a** 25 cm^2 **b** 12 cm **c** 4 units

13 $2100

14 5 L

15 8 ha

16 **a** **i** 10 cm **ii** 9 mm
b Divide the area by the given length.

17 half of a rectangle with area 4 cm^2

18 **a** 121 cm^2 **b** $\left(\frac{P}{4}\right)^2$

19 Area is quadrupled $(\times 4)$.

20 **a** **i** 100 **ii** 10 000 **iii** 1 000 000
b $\times 1\,000\,000$ $\times 10\,000$ $\times 100$
km^2 m^2 cm^2 mm^2
$\div 1\,000\,000$ $\div 10\,000$ $\div 100$
c **i** 200 mm^2 **ii** 100 000 cm^2
iii 3 500 000 m^2 **iv** 3 cm^2
v 2.16 m^2 **vi** 4.2 km^2 **vii** 5000 mm^2
viii 100 ha **ix** 0.4 ha

Exercise 11E

1 **a** 20 cm **b** 7 m **c** 2 m **d** 6.3 cm

2 **a** 6 m **b** 11 mm **c** 1.9 m **d** 3.2 mm

3 **a** 10 **b** 56 **c** 12.5

4 **a** 16 m^2 **b** 30 cm^2 **c** 160 m^2 **d** 1.2 m^2
e 3 mm^2 **f** 24.5 km^2 **g** 1.3 cm^2 **h** 20 m^2
i 4.25 m^2

5 **a** 2 cm^2 **b** 6 cm^2 **c** 3 cm^2 **d** 3 cm^2

6 480 m^2

7 4800 m^2

8 6.8 cm^2

9 160 m^2

10 $6300

11 **a** 5 cm **b** 4.4 mm

12 Yes, the base and height for each triangle are equal.

13 No, the base and height are always the same.

14 $b = \frac{2A}{h}$

15 **a** 7 cm^2 **b** 8 cm^2 **c** 11 cm^2 **d** 11 cm^2

Exercise 11F

1 **a** $A = bh$
$= 5 \times 7$
$= 35$
b $A = bh$
$= 20 \times 3$
$= 60$
c $A = bh$
$= 8 \times 2.5$
$= 20$

2 **a** $b = 6$ cm, $h = 2$ cm
b $b = 10$ m, $h = 4$ m
c $b = 5$ m, $h = 7$ m
d $b = 5.8$ cm, $h = 6.1$ cm
e $b = 5$ cm, $h = 1.5$ cm
f $b = 1.8$ m, $h = 0.9$ m

3 **a** 40 m^2 **b** 28 m^2 **c** 36 km^2 **d** 17.5 m^2
e 6.3 cm^2 **f** 30 m^2 **g** 1.8 cm^2 **h** 14 cm^2
i 176 mm^2

4 **a** 6 cm^2 **b** 4 cm^2 **c** 15 cm^2 **d** 8 cm^2

5 54 m^2

6 **a** 2 m **b** 7 cm **c** 0.5 mm

7 **a** 10 cm **b** 5 m **c** 2 km

8 $1200

9 **a** 1800 cm^2 **b** 4200 cm^2



10 Because height must be less than 5 cm.

11 half; area(parallelogram) $= bh$ and area(triangle) $= 1/2\ bh$

12 area = twice triangle area
$= 2 \times \frac{1}{2}bh$
$= bh$

13 $4 500 000

Exercise 11G

1 **a**  **b**  **c** 

2 **a** addition **b** subtraction **c** subtraction

3 **a** $A = l^2 + lw$
$= 1^2 + 3 \times 1$
$= 1 + 3$
$= 4$ cm^2

b $A = lw - \frac{1}{2}bh$
$= 13 \times 8 - \frac{1}{2} \times 5 \times 4$
$= 104 - 10$
$= 94$ m^2

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

4 **a** 33 m^2 **b** 600 mm^2 **c** 25 m^2
d 21 m^2 **e** 171 cm^2 **f** 45 km^2

5 **a** 39 m^2 **b** 95.5 cm^2 **c** 26 m^2
d 78.5 m^2 **e** 260 cm^2 **f** 4 m^2

6 **a** 62 cm^2 **b** 16 m^2 **c** 252 cm^2

7 **a** 80 cm^2 **b** 7 m^2 **c** 14.5 m^2 **d** 11.75 cm^2

8 10.08 m^2

9 yes, with $100 to spare

10 Subtraction may involve only two simple shapes.

11 **a** No; bases could vary depending on the position of the top side.
b Yes, 40 m^2; take out the rectangle and join the triangles to give a base of $10 - 6 = 4$.

12 **a** See given diagram in textbook.
b i $\frac{1}{16}, \frac{1}{32}, \frac{1}{64}, \frac{1}{128}, \frac{1}{256}, \frac{1}{512}, \frac{1}{1024}, \frac{1}{2048}, \frac{1}{4096}, \frac{1}{8192}$ ii no
c 1 square unit
d Total must equal 1.

Progress quiz

1 **a** metres **b** millimetres **c** kilometres

2 **a** 400 cm **b** 2000 mm **c** 35 mm
d 3000 m **e** 1450 m **f** 23 km

3 **a** 14.6 cm **b** 10.4 m **c** 354 cm

4 **a** 0.9 m^2 **b** 49 cm^2

5 **a** 6 m^2 **b** 31.5 m^2 **c** 9.68 m^2 **d** 20 mm^2

6 **a** 55 cm^2 **b** 72.9 m^2 **c** 192 mm^2

7 **a** 105 m^2 **b** 24.5 m^2 **c** 1820 m^2

8 **a** 225 cm^2 **b** 200 cm^2 **c** 7

Exercise 11H

1 **a** 6 **b** 24 **c** 24
d 144 **e** 56 **f** 13

2 **a** $V = lwh$ $= 4 \times 2 \times 3$ $= 24$ cm^3 **b** $V = lwh$ $= 1 \times 3 \times 6$ $= 18$ m^3 **c** $V = l^3$ $= 2 \times 2 \times 2$ $= 8$ km^3

3 **a** 84 m^3 **b** 10 cm^3 **c** 98 cm^3 **d** 27 cm^3
e 1000 km^3 **f** 2.744 mm^3 **g** 100 m^3 **h** 11.25 km^3

4 24 000 cm^3

5 96 m^3

6 12 000 mm^3

7 27 000 000 km^3

8 **a** 28 cm^3 **b** 252 m^3 **c** 104 cm^3

9 600


10 4096 cm^3

11 **a** 125 cm^3 **b** 729 m^3

12 **a** 6 cubic units **b** 4 cubic units **c** 14 cubic units

13 **a** i 2 m ii 5 cm iii 7 cm
iv 3 m
b Use: Volume ÷ area of base
c $h = V \div (l \times w)$

14 **a** i 10 ii 100 iii 10
iv 1000
b i 1 000 000 ii 1 000 000 000
c



Exercise 11I

1 **a** 1 **b** 1000 **c** 1000
d 1000 **e** 1000

2 **a** 1 L, 1000 mL, 1000 cm^3 **b** 1 m^3, 1000 L, 1 kL

3 **a** D **b** B **c** F
d A **e** C **f** E

4 **a** 2000 mL **b** 100 mL **c** 6000 kL **d** 24 000 L
e 2 kL **f** 3.5 L **g** 70 L **h** 2.5 ML
i 257 mL **j** 9.32 L **k** 3847 kL **l** 47 kL
m 500 L **n** 91 ML **o** 420 mL **p** 0.17 kL

5 **a** 12 mL **b** 2.5 m^3 **c** 875 mL

6 **a** 1200 mL **b** 1.2 L

7 **a** 6 000 000 L **b** 0.32 ML
c 4000 mL **d** 0.9927 kL

8 3 300 000 L

9 **a** 1.5 L **b** 0.48 L **c** 0.162 L
d 8.736 L **e** 25 L **f** 32.768 L

10 **a** 2500 m^3 **b** 2 500 000 L

11 **a** 0.2 mL
b i 1 L ii 0.6 L iii 14.4 L
iv 5256 L

12 15 days

13 41 h 40 min

14 1000 days

15 **a** 1000x cm^3 **b** 0.001x m^3
c 0.001x kL **d** 0.000 001x ML

16 **a** i lwh ii lwh iii $\frac{lwh}{1000}$
iv $\frac{lwh}{1000\,000}$
b i lwh m^3 ii 1000 lwh L iii lwh kL
iv $\frac{lwh}{1000}$ ML

17 **a** i 8 cm ii 4 cm iii 3.2 cm
b 0.6 cm
c 13.4 cm

Exercise 11J

1 **a** 1 kg, 1000 g **b** 1000 mg, 1 g

2 **a** C **b** F **c** A
d D **e** B **f** E

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

3 **a** B **b** A **c** D **d** C

4 **a** 2000 kg **b** 70 000 g **c** 2400 mg **d** 2.3 g
e 4.620 g **f** 21.6 t **g** 470 kg **h** 0.312 kg
i 0.027 g **j** 750 kg **k** 125 g **l** 0.0105 kg
m 210 t **n** 470 kg **o** 592 g **p** 80 g

5 **a** 4 kg **b** 12 g **c** 65 t

6 **a** 12°C **b** 37°C **c** 17°C
d 225°C **e** 1.7°C **f** 31.5°C

7 **a** 60 kg **b** 60 000 g **c** 60 000 000 mg

8 **a** 3000 g **b** 3 kg

9 33°C

10 147°C

11 **a** 8 kg **b** 8.16 kg

12 **a** 400 mg, 370 g, 2.5 kg, 0.1 t
b 290 000 mg, 0.000 32 t, 0.41 kg, 710 g

13 **a** 4th day **b** 25°C **c** 26°C

14 50 days

15 yes, by 215 kg

16 **a** 45.3 t **b** yes, by 2.7 t

17 **a** 1 g **b** 1 t **c** 1000 t

18 **a** 12 kg **b** 1000 kg **c** 360 000 kg

19 **a** **i** 10°C **ii** 27°C **iii** 727°C
b **i** 273 K **ii** 313 K **iii** 0 K

20 **a** 180°F **b** $\frac{5}{9}$ **c** $\frac{9}{5}$
d **i** 0°C **ii** 20°C **iii** 60°C **iv** 105°C
e $F = \frac{9C}{5} + 32$

Problems and challenges

1 Both line segments are the same length.

2 Mark a length of 5 m, then use the 3 m stick to reduce this to 2 m. Place the 3 m stick on the 2 m length to show a remainder of 1 m.

3 **a** 3 cm^2 **b** 20 cm^2

4 500 L

5 24 m^3

6 10.5 cm^2

7 **a** 12.5 cm **b** 3.75 cm

8 48 cm^2

Multiple-choice questions

1 D **2** E **3** C **4** A **5** E
6 B **7** A **8** B **9** E **10** B

Short-answer questions

1 **a** **i** 16 **ii** 1000
b **i** 3 **ii** 12
c **i** 10 **ii** 100 000

2 **a** 50 mm **b** 2 m **c** 3700 m **d** 4.21 km
e 7100 g **f** 24.9 g **g** 28.49 t **h** 9000 g
i 4 L **j** 29.903 kL **k** 400 kL **l** 1000 mL
m 1440 min **n** 60 min **o** 3.5 days **p** 9000 s

3 **a** 2.5 cm **b** 2.3 cm **c** 4.25 kg **d** 5 L

4 **a** 16 m **b** 20.6 cm **c** 23 m **d** 34 km
e 3.2 mm **f** 24 m

5 **a** 24.01 cm^2 **b** 14 km^2 **c** 67.5 m^2 **d** 12 cm^2
e 14 m^2 **f** 5 cm^2 **g** 14 m^2 **h** 0.9 km^2

6 **a** 22 m^2 **b** 21 mm^2 **c** 291 cm^2 **d** 52 m^2

7 **a** 18 cm^3 **b** 7.5 cm^3 **c** 64 mm^3

8 **a** 72 000 cm^3 **b** 72 000 mL **c** 72 L

9 **a** 45 mg, 290 000 g, 3 t, 4700 kg
b 50 000 mL, 51 L, 0.5 kL, 1 ML

Extended-response questions

1 **a** **i** 18 m^2 **ii** 180 000 cm^2
b 36 m^3 **c** 36 000 L
d 51.4 t **e** 3 h 52 min 54 s

2 **a** 97.3 m **b** 5 min 30 s
c 270 m^2 **d** $2040
e 50 m^3

Semester review 2

Multiple-choice questions

Negative numbers

1 C **2** B **3** D **4** E **5** A

Short-answer questions

1 **a** $<$ **b** $<$ **c** $=$

2 **a** -13 **b** -84 **c** -108 **d** -21
e 84 **f** 0

3 **a** -24 **b** 72 **c** 144 **d** 21
e 30 **f** -31

4 **a** negative **b** positive **c** negative

5 **a** -15 **b** -8 **c** -4

6 **a** -10 **b** 10 **c** -20 **d** -96
e 52 **f** -1

Extended-response questions

1 **a** D **b** A, B, O and G; all lie on the x-axis.
c F **d** **i** 2 units **ii** 5 units
e trapezium **f** 8 square units
g $X(4, 2)$ **h** DECIDE

Statistics and probability

Multiple-choice questions

1 B **2** A **3** B **4** E **5** D

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Short-answer questions

1 a 1, 2, 3, 5, 5, 5, 8, 8, 9, 10 b 10
c i 5.6 ii 5 iii 5 iv 9
d 11.2

2 a A b B c B, C, D, A

3 a $\frac{1}{2}$ b $\frac{1}{2}$ c $\frac{1}{4}$
d $\frac{1}{13}$ e $\frac{1}{13}$ f $\frac{1}{26}$

4 a 13 b 3, 47 c i 44 ii 22 iii 22

5 a 20 b 22
c mean is 23, median is 22

Extended-response questions

1 a $\frac{1}{4}$ b $\frac{1}{4}$ c $\frac{1}{2}$
d $\frac{1}{52}$ e $\frac{2}{13}$ f $\frac{1}{13}$
g $\frac{4}{13}$ h $\frac{4}{13}$

Polygons and transformations

Multiple-choice questions

1 E 2 B 3 D 4 C 5 A

Short-answer questions

1 a pentagon b octagon
c isosceles right triangle d rhombus
e trapezium f kite

2 a 130 b 45 c 80

3 a $a = 60$
b $a = 65$
c $a = 115$
d $a = 90, b = 90$
e $a = 65$
f $a = 132, b = 48, c = 48, d = 102$

4 a $A'(2, 0), B'(2, -3), C'(4, 0)$
b $A'(-2, 0), B'(-2, 3), C'(-4, 0)$
c $A'(0, -2), B'(3, -2), C'(0, -4)$
d $A'(0, 2), B \ni (-3, 2), C'(0, 4)$
e $A'(-2, 0), B'(-2, -3), C'(-4, 0)$
f $A'(-2, 1), B'(-2, 4), C'(0, 1)$
g $A'(-1, -2), B'(-1, 1), C'(1, -2)$

Extended-response questions

1 a Student's own construction.
b $a + b + c = 180$
c Student's own measurements.
d $x + y + z = 360$
e 360

Equations

Multiple-choice questions

1 B 2 E 3 C 4 B 5 D

Short-answer questions

1 a $x = 3$ b $x = 108$ c $x = 21$ d $x = \frac{4}{3}$

2 a $x = 2$ b $x = 12$ c $m = 7$

3 a $y = 20$ b $b = 4$ c $m = 8$

4 a $P = 103$ b $S = 61$ c $C = 325$

5 a $x = 5$ b $x = 6$ c $x = 18$

6 $4x + 25 = 85; x = 15$

Extended-response questions

1 a \$320 b \$400
c $\$(200 + 40n)$ d $6\frac{1}{2}$ h

Measurement

Multiple-choice questions

1 C 2 A 3 E 4 C 5 A

Short-answer questions

1 a 500 b 6000 c 1.8 d 0.017
e 1.8 f 5500

2 a 272 cm b 11 m c 3m
d 220 cm e 3.4 m f 92 m

3 a 1.69 m^2 b 24 m^2 c 60 m^2
d 75 m^2 e 114 m^2 f 171 m^2

4 a 729 cm^3 b 120 m^3 c 160 m^3

5 a 5000 b 7 c 250
d 3000 e 8 f 25

6 21 h 15 min

7 120

8 5:00 am

Extended-response questions

1 a Many answers possible; e.g. 8 m × 10 m, 4 m × 14 m, 15 m × 3 m
b 9 m by 9 m (area = 81 m^2)
c 36 posts
d 9h

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press

Acknowledgments

The author and publisher wish to thank the following sources for permission to reproduce material:

Cover: Used under license 2015 from Shutterstock.com / Idambies (**boy**) / Be Good (**solar panel**).

Images: ©Alamy / ClassicStock, **p.5**; ©Australian Paralympic Committee. Creative Commons Attribution-Share Alike 3.0 Unported licence, **pp.294-295**; ©Bidgee. Creative Commons Attribution-Share Alike 3.0 Unported licence, **p.397(t)**; ©Kham Tran. Creative Commons Attribution 3.0 Unported licence, **p.334**; ©Marie-Lan Nguyen. Creative Commons Attribution 2.5 Generic licence, **p.519**; ©Mark Strozier. Creative Commons Attribution 2.0 Generic licence, **p.456**; National Archives UK [SP12/193/54], **pp.392-393**; ©Severin.stadler. Creative Commons Attribution-Share Alike 3.0 Unported licence, **pp.582-583**; Used under license 2015 from Shutterstock.com / beths, **p.xvi(t)** / wavebreakmedia, **pp.xvi(b)**, **394** / Arena Photo UK, **p.xvii(t)** / PicturesWild, **p.xvii(b)** / Pakhnyushchy, **pp.2-3** / Uroš Medved, **p.4** / Planner, **p.7** / i3d, **p.8** / ILYA GENKIN, **p.10** / Edward Westmacott, **p.12** / Edyta Pawlowska, **p.13** / AHMAD FAIZAL YAHYA, **p.16(t)** / David Steele, **p.16(b)** / AntonioDiaz, **p.18** / gualtiero boffi, **p.21(t)** / pockygallery, **p.21(b)** / Jozsef Bagota, **p.22** / dwphotos, **p.26** / jcjgphotography, **p.27** / Neale Cousland, **pp.28**, **38**, **84**, **145**, **182**, **282**, **285(b)**, **532-533**, **638(t)** / Asaf Eliason, **p.29** / STILLFX, **p.30** / Vasya Kobelev, **p.31** / Tribalium, **p.40** / GDM, **p.42** / Tang Yan Song, **p.44(t)** / Concept Photo, **p.44(b)** / szefei, **p.46(b)** / Viktor Gladkov, **p.50** / Popova Valeriya, **p.52** / Anton Gvozdikov, **p.53** / Detelina Petkova, **pp.54-55** / Sergey Nivens, **p.56** / Govert Nieuwland, **p.57** / Jaren Jai Wicklund, **p.61** / pryzmat, **p.62** / Taigi, **p.67** / El Nariz, **p.72** / Frontpage, **p.73** / Dmitry Pistrov, **p.75** / microvector, **p.82** / Phillip Minnis, **p.83** / Yuyangc, **p.88(t)** / Nigel Paul Monckton, **p.88(b)** / OzZon, **p.91** / staskin, **p.94(b)** / LuckyImages, **p.95** / vesilvio, **p.102** / MrGarry, **p.103** / Pigprox, **pp.104-105** / Nikola Bilic, **p.106** / Igor.stevanovic, **p.109** / Juriah Mosin, **p.114** / Robyn Mackenzie, **p.118** / Rido, **p.119** / forestpath, **p.120** / Ollyy, **pp.122**, **421(b)** / Standret, **p.123(t)** / leonello calvetti, **p.127** / Di Studio, **p.128** / Tungphoto, **p.131** / Oleksiy Mark, **pp.132**, **385**, **518** / Mapics, **p.134** / Valentyn Volkov, **p.138** / Andrey_Popov, **pp.139(t-l)**, **231(b)**, **367** / A and N photography, **p.139(t-r)** / Jeanette Dietl, **p.139(b-r)** / Monkey Business Images, **pp.139(b-r)**, **274(b)**, **413** / Andresr, **pp.143**, **548** / V.J. Matthew, **p.152** / dedoma, **p.153** / hxdbzxy, **p.158** / robodread, **p.163** / Pressmaster, **p.165(b)** / Evdokimov Maxim, **p.166** / Jennifer Gottschalk, **p.173** / Jose Ignacio Soto, **pp.174-175** / Maxx-Studio, **p.176** / FlashStudio, **p.180** / O.V.D., **pp.181**, **186(b)** / Cre8tive Images, **p.186(t)** / Lasse Kristensen, **p.188** / Kert, **p.190** / Ilolab, **p.193** / Tyler Olson, **p.194** / Dmitrij Skorobogatov, **p.198** / graphit, **p.203** / riekephotos, **p.204** / auremar, **p.205(t)** / JoemanjiArts, **p.205(b)** / Nonwarit, **p.208** / Kelvin Wong, **p.210** / Jaimie Duplass, **p.211** / Dirk Ott, **p.212(l)** / Pincasso, **p.212(r)** / Aleksandar Mijatovic, **p.213(t)** / Dmitry Naumov, **p.213(b)** / Johnny Lye, **p.218** / Vera Petruk, **p.219** / Warren Goldswain, **p.224** / Teddy Leung, **p.225** / XAOC, **p.227** / Aspen Photo, **p.230** / bikeriderlondon, **pp.231(t)**, **415**, **451(b)** / Bikeworldtravel, **p.232** / Dmitry Vinogradov, **p.235** / Mik Lav, **p.236** / Mark Schwettmann, **p.237** / Coprid, **p.241** / Nir Darom, **pp.242(b)**, **243** / Jeep2499, **p.244** / Kevin Hellon, **p.249** / Rainer Plendl, **pp.250-251** / Minerva Studio, **p.252** / Dan Kosmayer, **p.269** / phatisakolpap, **p.274(t)** / Zurijeta, **p.275** / Shi Yali, **p.276** / Areipa.It, **p.280** / monticello, **pp.281**, **397(c)** / Vorobyeva, **p.284(t)** / iurii, **p.284(b)** / lightwavemedia, **p.285(t)** / Syda Productions, **pp.286**, **397(b)** / spiro, **p.287** / Goodluz, **p.288** / Michael William, **p.293(t)** / Suwatchai Pluemruetai, **p.293(b)** / Roman Samokhin, **p.296** / Mitch Gunn, **p.299** / M. Pellinni, **p.300** / Pete Niesen, **p.301** / Siberia – Photo and Video, **p.304** / Chad McDermott, **p.305** / Ministr-84, **p.306** / Heather LaVelle, **p.310** / Eviled, **p.314** / solarseven, **p.315** / goory, **p.316** / bibiphoto, **p.324** / Richard Griffin, **p.326** / james weston, **p.327** / Africa Studio, **pp.329(t)**, **553(b)** / stefanei, **p.329(b)** / Nisakorn Neera, **p.330** / Rafa Irusta, **p.336(l)** / Heliosphile, **p.336(r)** / Lisa S., **p.337** / Willem Tims, **pp.354-355** / Alperium, **p.359** / ppart, **p.360** / Armin Rose, **p.362** / Lorelyn Medina, **p.364** / Ethan Daniels, **p.366** / Deyan Georgiev, **p.368** / Evgeny Aramanenko, **p.373** / Shmeliova Natalia, **p.376** / Anneka, **p.377** / Max Earey, **p.378** / Steven Colling, **p.380** / Diego Cervo, **p.384** / oceanfishing, **p.391** / Ulrich Mueller, **p.396** / milias1987, **p.398** / Daniel Taeger, **p.400** / mooinblack, **p.404** / Adam Gregor, **p.405** / Carbonell, **p.409** / Wallenrock, **p.410** / jcjgphotography, **p.411** / ChameleonsEye, **p.412(l)** / connel, **p.412(r)** / Frank Wasserfuehrer, **p.418** / WilleeCole Photography, **p.419** / Tupungato, **pp.420**, **429**, **571** / karamysh, **p.421(t)** / Ronald Sumners, **p.422** / Sofiaworld, **p.423** / sanneberg, **p.425** / Valentina Razumova, **p.426** / Charlie Edward, **p.427** / DmitriMaruta, **p.428** / Ekaterina Pokrovsky, **p.430** / MJTH, **pp.435(l&r)** / Eric Isselee, **p.436** / Pakhotin Andrey, **p.438** / 3dfoto, **p.439(t)** / jabiru, **p.439(b)** / Bombaert Patrick, **p.441(t)** / Zbigniew Guzowski, **p.441(b)** / Boule, **pp.443**, **451(t)** / digitalreflections, **p.444** / Artens, **p.447(t)** / Felix Furo, **p.447(b)** / bekuinis, **p.448** / onsuda, **p.449** / Alexander Chaikin, **p.453** / Nadezda Cruzova, **p.459** / kazoka, **p.461** / Francesco Abrignani, **p.462** / cappi thompson, **p.463** / yodiyim, **pp.464-465** / Christopher Tan Teck Hean, **p.466** / Photobank, **p.470** / psamtik, **p.471** / Pavel Ignatov, **p.475** / 1stclassphoto, **p.479** / CBCK, **p.480** / mountainpix, **p.484** / Luciano Mortula, **p.486** / jopelko, **p.496(l)** / Ian 2010, **p.496(r)** / Sergey Titov, **p.498(l)** / Carolina K. Smith MD, **p.468(r)** / Nadia Zagainova, **p.499(r)** / HomeArt, **p.501** / Warongdech, **p.507** / Christopher Halloran, **p.509** / pedrosala, **p.513** / Franck Boston, **p.514** / hans engbers, **p.524** / doomu, **p.531** / Hayati Kayhan, **p.534** / terekhov igor, **p.537** / 3Dsculptor, **p.538** / Photocammie, **p.539** / Madlen, **p.541** / Blend Images, **p.542** / BlueSkyImage, **p.553(t)** / Darren Whittingham, **p.555** / Lara65, **p.559** / Kostsov, **p.566** / vblinov, **p.570** / manaemedia, **p.572** / KRISANOV YURY, **p.574** / Kiev.Victor, **p.575** / Jenoche, **p.577** / Kasza, **p.587 (drill bit)** / RCPPHOTO, **p.587(a)** / Evgeniy Ayupov, **p.587(b)** / Ashley Whitworth, **p.587(c)** / Brad Thompson, **p.587(d)** / Nicola Gavin, **p.588(l)** / Péter Gudella, **p.588(r)** / Meunierd, **p.589** / racorn, **p.590** / Miao Liao, **p.594** / Denton Rumsey, **p.599** / Fedorov Oleksiy, **p.604** / Haak78, **p.605** / Hamdan, **p.608** / Bildagentur Zoonar GmbH, **pp.609 641** / Christian Mueller, **p.612** / Ljupco Smokovski, **p.615** / Miks Mihalis Ignats, **p.616** / tororo reaction, **p.623** / Anton_Ivanov, **p.626** / Noramin.s, **p.629** / Irina Schmidt, **p.631** / nubephoto, **p.632** / i-m-a-g-e, **p.633** / Gyuszko-Photo, **p.634(t)** / Sebastian Duda, **p.634(b)** / violetkaipa, **p.637** / Andraž Cerar, **p.638(b)** / darkgreenwolf, **p.639** / Joern, **p.640** / Dirima, **p.647** / Constantine Pankinm **p.656**; ©Tristen Murray. Creative Commons Attribution-Share Alike 2.0 Generic licence, **p.569**.

Every effort has been made to trace and acknowledge copyright. The publisher apologises for any accidental infringement and welcomes information that would redress this situation.

Essential Mathematics for the Australian Curriculum Year 7 2ed ISBN 978-1-107-56882-2 © Greenwood et al. 2015 Cambridge University Press
Photocopying is restricted under law and this material must not be transferred to another party.

Essential Mathematics for the Australian Curriculum Year 7 2ed
ISBN 978-1-107-56882-2
© Greenwood et al. 2015
Photocopying is restricted under law and this material must not be transferred to another party.
Cambridge University Press